

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

REGULATIONS

JULY 2007

PART 1

**Lloyd's**  
**Register**

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

---

<b>PART</b>	<b>1</b>	<b>REGULATIONS</b>
		<b>Chapter 1 General Regulations</b>
		<b>2 Classification Regulations</b>
		<b>3 Periodical Survey Regulations</b>
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
PART	3	SHIP STRUCTURES (GENERAL)
PART	4	SHIP STRUCTURES (SHIP TYPES)
PART	5	MAIN AND AUXILIARY MACHINERY
PART	6	CONTROL, ELECTRICAL, REFRIGERATION AND FIRE
PART	7	OTHER SHIP TYPES AND SYSTEMS

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.



<b>CHAPTER</b>	<b>1</b>	<b>GENERAL REGULATIONS</b>
<b>Sections</b>		<b>1 to 10</b>
<b>CHAPTER</b>	<b>2</b>	<b>CLASSIFICATION REGULATIONS</b>
<b>Section</b>	<b>1</b>	<b>Conditions for classification</b>
	1.1	General
	1.2	Advisory services
<b>Section</b>	<b>2</b>	<b>Character of classification and class notations</b>
	2.1	Definitions
	2.2	Character symbols
	2.3	Class notations (hull)
	2.4	Class notations (machinery)
	2.5	Class notations (refrigerated cargo installations (RMC), controlled atmosphere (CA) systems and carriage of refrigerated containers (CRC))
	2.6	Class notations (Environmental Protection)
	2.7	Descriptive notes
	2.8	Application notes
<b>Section</b>	<b>3</b>	<b>Surveys – General</b>
	3.1	Statutory surveys
	3.2	New construction surveys
	3.3	Existing ships
	3.4	Damages, repairs and alterations
	3.5	Existing ships – Periodical Surveys
	3.6	Certificates
	3.7	Notice of surveys
	3.8	Withdrawal/Suspension of class
	3.9	Appealing against Surveyors' recommendations
	3.10	Force majeure
	3.11	Ownership details
<b>Section</b>	<b>4</b>	<b>IACS QSCS Audits</b>
	4.1	Audit of surveys
<b>Section</b>	<b>5</b>	<b>Approval/Type Testing/Quality Control System</b>
	5.1	LR Type Approval – Marine Applications
	5.2	Type testing
	5.3	Quality Control System
<b>Section</b>	<b>6</b>	<b>Classification of machinery with <del>[X]</del> LMC or MCH notation</b>
	6.1	General
	6.2	Appraisal and records
	6.3	Survey and inspection
<b>CHAPTER</b>	<b>3</b>	<b>PERIODICAL SURVEY REGULATIONS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Frequency of surveys
	1.2	Surveys for damage or alterations
	1.3	Unscheduled surveys
	1.4	Surveys for the issue of Convention certificates
	1.5	Definitions
	1.6	Preparation for survey and means of access
	1.7	Thickness measurement at surveys
	1.8	Repairs
<b>Section</b>	<b>2</b>	<b>Annual Surveys – Hull and machinery requirements</b>
	2.1	General
	2.2	Annual Surveys

# Contents

# Part 1

---

<b>Section</b>	<b>3</b>	<b>Intermediate Surveys – Hull and machinery requirements</b>
	3.1	General
	3.2	Intermediate Surveys
<b>Section</b>	<b>4</b>	<b>Docking Surveys and In-water Surveys – Hull and machinery requirements</b>
	4.1	General
	4.2	Docking Surveys
	4.3	In-water Surveys
<b>Section</b>	<b>5</b>	<b>Special Survey – General – Hull requirements</b>
	5.1	General
	5.2	Preparation
	5.3	Examination and testing
	5.4	Overall Survey
	5.5	Close-up Survey
	5.6	Thickness measurement
<b>Section</b>	<b>6</b>	<b>Special Survey – Bulk carriers – Hull requirements</b>
	6.1	General
	6.2	Documentation
	6.3	Planning for survey
	6.4	Overall Survey
	6.5	Testing
	6.6	Close-up Survey
	6.7	Thickness measurement
<b>Section</b>	<b>7</b>	<b>Special Survey – Oil tankers (including ore/oil ships and ore/bulk/oil ships) – Hull requirements</b>
	7.1	General
	7.2	Documentation
	7.3	Planning for survey
	7.4	Overall Survey
	7.5	Testing
	7.6	Close-up Survey
	7.7	Thickness measurement
<b>Section</b>	<b>8</b>	<b>Special Survey – Chemical tankers – Hull requirements</b>
	8.1	General
	8.2	Documentation
	8.3	Planning for survey
	8.4	Overall Survey
	8.5	Testing
	8.6	Close-up Survey
	8.7	Thickness measurement
<b>Section</b>	<b>9</b>	<b>Ships for liquefied gases</b>
	9.1	General
	9.2	Annual Surveys – Basic requirements
	9.3	Annual Surveys – Reliquefaction/refrigeration equipment
	9.4	Annual Surveys – Methane burning equipment and other equipment components
	9.5	Annual Surveys – Cargo containment systems
	9.6	Intermediate Surveys
	9.7	Special Survey I (ships five years old) – General requirements
	9.8	Special Survey I (ships five years old) – Reliquefaction/refrigeration equipment
	9.9	Special Survey I (ships five years old) – Methane burning equipment
	9.10	Special Survey II and Special Surveys thereafter (ships 10 years old and over)
	9.11	Special Survey III and Special Surveys thereafter (ships 15 years old and over)
	9.12	Close-up Survey
	9.13	Thickness measurement
<b>Section</b>	<b>10</b>	<b>Dredgers, hopper dredgers, sand carriers, hopper barges and reclamation craft</b>
	10.1	General
	10.2	Special Surveys

---

<b>Section</b>	<b>11</b>	<b>Machinery surveys – General requirements</b>
	11.1	Annual, Intermediate and Docking Surveys
	11.2	Complete Surveys
<b>Section</b>	<b>12</b>	<b>Turbines and steam engines – Detailed requirements</b>
	12.1	Complete Surveys
<b>Section</b>	<b>13</b>	<b>Oil engines – Detailed requirements</b>
	13.1	Complete Surveys
<b>Section</b>	<b>14</b>	<b>Electrical equipment</b>
	14.1	Annual and Intermediate Surveys
	14.2	Complete Surveys
	14.3	Docking Surveys
<b>Section</b>	<b>15</b>	<b>Boilers</b>
	15.1	Frequency of surveys
	15.2	Scope of surveys
<b>Section</b>	<b>16</b>	<b>Steam pipes</b>
	16.1	Frequency of surveys
	16.2	Scope of surveys
<b>Section</b>	<b>17</b>	<b>Screwshafts, tube shafts and propellers</b>
	17.1	Frequency of surveys
	17.2	Normal surveys
	17.3	Screwshaft Condition Monitoring (SCM)
	17.4	Modified Survey
	17.5	Partial Survey
<b>Section</b>	<b>18</b>	<b>Inert gas systems</b>
	18.1	Frequency of surveys
	18.2	Scope of surveys
<b>Section</b>	<b>19</b>	<b>Classification of ships not built under survey</b>
	19.1	General
	19.2	Hull and equipment
	19.3	Machinery
	19.4	Refrigerated cargoes
<b>Section</b>	<b>20</b>	<b>Refrigerated cargo installations</b>
	20.1	Annual Surveys
	20.2	Special Surveys
	20.3	Subsequent Special Survey
	20.4	Loading Port Survey
	20.5	Refrigerating plant on ships not classed with LR
<b>Section</b>	<b>21</b>	<b>Controlled atmosphere systems</b>
	21.1	Retention of class
	21.2	Annual Surveys
	21.3	Special Surveys





# General Regulations

## Part 1, Chapter 1

*Sections 1 & 2*

### ■ Section 1

1.1 Lloyd's Register (hereinafter referred to as LR), which is recognized under the laws of the United Kingdom as a Corporation whose business is conducted for the benefit of the community, was founded in 1760. It was established for the purpose of obtaining for the use of Merchants, Shipowners and Underwriters a faithful and accurate Classification of Merchant Shipping and whilst it still continues to fulfil that purpose, it now also:

- (a) approves design, surveys and reports on: hovercraft; ships which embody features of a novel kind; non-mercantile shipping; yachts; amphibious and land and sea and sea bed installations, structures, plant, etc.; machinery, apparatus, materials, components, equipment, production methods and processes of all kinds; for the purpose of testing their compliance with plans, specifications, Rules, Codes of Practice, etc., or their fitness for particular requirements;
- (b) acts with delegated authority on behalf of numerous governments in respect of Statutory Requirements;
- (c) provides other technical inspection and advisory services relating to ships and the maritime industry generally and also in respect of land and sea-based undertakings.

### ■ Section 2

2.1 LR's affairs are under the overall direction of the General Committee, which is composed of persons nominated or elected to represent the world community and industry which LR serves.

The General Committee (hereinafter referred to as the Committee), which may at its discretion vary the constitution of such representation, is currently composed of:

- The Corporation of Lloyd's (five representatives).
- The International Underwriting Association (two representatives).
- The Chamber of Shipping (five representatives).
- The International Maritime Industries Forum (one representative).
- The Greek Shipping Co-operation Committee (one representative).
- Intercargo (one representative).
- Institute of Quality Assurance (one representative).
- Intertanko (one representative).
- The International Group of P&I Clubs (one representative).

Nominated members of the Committee are elected for a term of service of three years and are eligible for re-election, subject to the membership age limit and unbroken membership of the nominating body they represent during their period of membership.

Six members representing P&I Clubs elected by the Committee for a term of service of one year. P&I Club representatives are eligible for re-election, subject to the membership age limit.

Such persons specially elected by the Committee for a term of service of one year. Specially Elected Members are eligible for re-election, subject to the membership age limit. The number of Specially Elected Members shall be limited not to exceed the balance of the maximum Committee membership of 85 persons. A specially elected member will automatically relinquish his/her membership in this category on being elected as a nominated member of the Committee.

2.2 The Committee is further empowered to elect as Honorary Members of the Committee such persons of distinction and eminence as the Committee shall from time to time think fit.

2.3 With the exception of honorary members, any member of the Committee shall automatically retire from the Committee on reaching the age of seventy years, unless special approval for an additional term of service is recommended by the Committee's Nominations Committee and approved by the Committee each year thereafter.

# General Regulations

# Part 1, Chapter 1

Sections 3, 4 & 5

## Section 3

- 3.1 The Committee has power to:
- Appoint a Board and delegate thereto such of its powers as it may determine;
  - Appoint a General Committee Nominations Committee and determine its powers;
  - Appoint a Sub-Committee of Classification and determine its powers and functions;
  - Appoint Committees in any country or area to form a liaison between LR and the local maritime, industrial and commercial communities;
  - Appoint Technical Committees and determine their functions, powers and duties.
- 3.2 The Committee has exercised its powers and has appointed such committees and Board.

## Section 4

- 4.1 National and Area Committees are established in the following:
- |   |   |
|---|---|
| <p>Countries:</p> <ul style="list-style-type: none"> <li>Australia (via Lloyd's Register Asia)</li> <li>Canada (via Lloyd's Register North America, Inc.)</li> <li>China (via Lloyd's Register Asia)</li> <li>Egypt (via Lloyd's Register EMEA)</li> <li>Federal Republic of Germany (via Lloyd's Register EMEA)</li> <li>France (via Lloyd's Register EMEA)</li> <li>Greece (via Lloyd's Register EMEA)</li> <li>Italy (via Lloyd's Register EMEA)</li> <li>Japan (via Lloyd's Register Asia)</li> <li>New Zealand (via Lloyd's Register Asia)</li> <li>Poland (via Lloyd's Register (Polska) Sp zoo)</li> <li>Spain (via Lloyd's Register EMEA)</li> <li>United States of America (via Lloyd's Register North America, Inc.)</li> </ul> | <p>Areas:</p> <ul style="list-style-type: none"> <li>Benelux (via Lloyd's Register EMEA)</li> <li>Central America (via Lloyd's Register Central and South America Ltd)</li> <li>Nordic Countries (via Lloyd's Register EMEA)</li> <li>South Asia (via Lloyd's Register Asia)</li> <li>Asian Shipowners (via Lloyd's Register Asia)</li> </ul> |
|---|---|

## Section 5

5.1 The main Technical Committee is at present composed of:		
<i>Ex officio:</i>		TOTAL
• The Chairman of LR	.....	1
• The Chairman of the Sub-Committee of Classification	.....	1
<i>Nominated by:</i>		
• The Committee	.....	18
• The Royal Institution of Naval Architects	.....	2
• The Institution of Engineers and Shipbuilders in Scotland	.....	2
• The Institute of Marine Engineers	.....	2
• The Institution of Mechanical Engineers	.....	2
• The Shipbuilders' and Shiprepairers' Association	.....	2
• The Short Sea Group of the Chamber of Shipping	.....	1
• The Society of Consulting Marine Engineers and Ship Surveyors	.....	1
• The Institute of Materials	.....	1
• The UK Steel Association	.....	1
• The Honourable Company of Master Mariners	.....	2
• The Institution of Electrical Engineers	.....	1
• Federation of British Electrotechnical and Allied Manufacturers' Associations	.....	1
• The Technical Committee	.....	18
• The Technical Committee (from other countries)	.....	18
• The Institute of Refrigeration	.....	1
• International Oil Companies	.....	2
• Association of European Shipbuilders and Shiprepairers	.....	1
• Greek Shipping Co-operation Committee	.....	1
		<u>79</u>

# General Regulations

## Part 1, Chapter 1

Sections 5 &amp; 6

5.2 All nominations are subject to confirmation by the Committee.

5.3 In addition to the foregoing:

- (a) Each National or Area Committee may appoint a representative to attend meetings of the Technical Committee.
- (b) A maximum of five representatives from National Administrations may, with the consent of the Committee, be co-opted to serve on the Technical Committee. Such representatives may also be elected as members of the Technical Committee under one of the categories identified in 5.1.
- (c) Further persons may, with the consent of the Committee, be co-opted to serve on the Technical Committee.

5.4 The function of the Technical Committee is to consider any technical problems connected with LR's business (see 1.1(a)) and with the exception of changes necessitated by mandatory implementation of International Conventions, Codes or Unified Requirements adopted by the International Association of Classification Societies, any proposed alterations in the existing Rules and to frame new Rules for classification as deemed necessary.

5.5 The term of office of the Chairman and of all members of the Technical Committee is five years. Members may serve one additional term of office with the approval of the Committee.

5.6 In the case of continuous non-attendance of a member, the Committee may withdraw his/her membership.

5.7 Meetings of the Technical Committee are convened as often and at such times and places as is necessary, but there is to be at least one meeting in each year.

5.8 Any proposal of the Technical Committee involving any alteration in, or addition to, Rules for classification is referred to the Committee and may be finally approved at the next meeting of the Board if the General Committee so direct.

5.9 The Technical Committee is empowered to:

- (a) appoint sub-Committees or panels of the Committee; and
- (b) co-opt to the Technical Committee, or to its sub-Committees or panels, representatives of any organization or industry or private individuals for the purpose of considering any particular problem.

## ■ Section 6

6.1 The Naval Ship Technical Committee (hereinafter referred to as NSTC) is at present composed of not more than 50 members to include nominees of:

- The Royal Navy and the UK Ministry of Defence;
- The Defence Evaluation and Research Agency;
- UK Shipbuilders, Ship Repairers and Defence Industry;
- Overseas Governments and Governmental Agencies;
- Overseas Shipbuilders, Ship Repairers and Defence Industries;
- Various maritime bodies and institutions, nominated by the NSTC;
- The Chairman and Chairman of the Sub-Committee of Classification who are *ex officio* members.

6.2 All nominations are subject to confirmation by the Committee.

6.3 All members of the NSTC are to hold security clearance from their National Authority for the equivalent of NATO CONFIDENTIAL. All material is to be handled in accordance with NATO Regulations or, for non-NATO countries, an approved equivalent. No classified material shall be disclosed to any third party without the consent of the originator.

6.4 The term of office of the NSTC Chairman and of all members of the NSTC is five years. Members may serve one additional term of office with the approval of the Committee. The term of the Chairman may be extended with the approval of the General Committee.

6.5 In the case of continuous non-attendance of a member, the Committee may withdraw that person's membership.

6.6 The function of the NSTC is to consider technical issues connected with Naval Ship matters and to approve proposals for new Naval Ship Rules, or amendments to existing Naval Ship Rules.

6.7 Meetings of the NSTC shall be convened as necessary but there shall be at least one meeting per year.

6.8 Following approval by the NSTC, details of new Rules (or amendments) will be submitted to the Committee for adoption.

# General Regulations

# Part 1, Chapter 1

Sections 7, 8, & 9

## Section 7

7.1 The Committee has power to adopt, and publish as deemed necessary, Rules relating to classification and has (in relation thereto) provided the following:

- (a) Except in the case of a special directive by the Committee, no new Regulation or alteration to any existing Regulation relating to character of classification or to class notations is to be applied to existing ships.
- (b) Except in the case of a special directive by the Committee, or where changes necessitated by mandatory implementation of International Conventions, Codes or Unified Requirements adopted by the International Association of Classification Societies are concerned, no new Rule or alteration in any existing Rule is to be applied compulsorily after the date on which the contract between the ship builder and ship owner for construction of the ship has been signed, nor within six months of its adoption. The date of 'contract for construction' of a ship is the date on which the contract to build the ship is signed between the prospective ship owner and the ship builder. This date and the construction number (i.e. hull numbers) of all the vessels included in the contract are to be declared to the Committee by the party applying for the assignment of class to a newbuilding. The date of 'contract for construction' of a series of sister ships, including specified optional ships for which the option is ultimately exercised, is the date on which the contract to build the series is signed between the prospective ship owner and the ship builder. In this section a 'series of sister ships' is a series of ships built to the same approved plans for classification purposes, under a single contract for construction. The optional ships will be considered part of the same series of sister ships if the option is exercised not later than 1 year after the contract to build the series was signed. If a contract for construction is later amended to include additional ships or additional options, the date of 'contract for construction' for such ships is the date on which the amendment to the contract is signed between the prospective ship owner and the ship builder. The amendment to the contract is to be considered as a 'new contract'. Where it is desired to use existing approved ship or machinery plans for a new contract, written application is to be made to the Committee.

### NOTE

Sister ships may have minor design alterations provided that such alterations do not affect matters related to classification.

- (c) All reports of survey are to be made by Surveyors authorised by LR to survey and report (hereinafter referred as the Surveyors) according to the form prescribed, and submitted for the consideration of the Committee, or its Sub-Committee of Classification, but the character assigned by the latter is to be subject to confirmation by the Committee or by the Chairman acting on behalf of the Committee.
- (d) Information contained in the reports of classification and statutory surveys will be made available to the relevant owner, National Administration, Port State Administration, P&I Club, hull underwriter and, if authorized in writing by that owner, to any other person or organization.
- (e) Information relating to the status of classification and statutory surveys and suspensions/withdrawals of class together with any associated conditions of class will be made available as required by applicable legislation or court order.
- (f) Notwithstanding the general duty of confidentiality owed by LR to its clients, LR will participate fully in the IACS Early Warning System which requires each IACS member to provide its fellow IACS members with information on serious hull structural and engineering systems failures, including the name of the ship and its IMO number, to enable such useful information to be shared and utilised to facilitate the proper working of the IACS Early Warning System (which is aimed at enabling (i) 'sister' or similar ships to avoid similar problems and (ii) the shipping industry generally to learn from failures and mistakes).
- (g) A Classification Executive consisting of senior members of LR's Classification Department staff shall carry out whatever duties that may be within the function of the Sub-Committee of Classification that the Sub-Committee of Classification assigns to it.

## Section 8

8.1 No Lloyd's Register Group employee is permitted under any circumstances, to accept, directly or indirectly, from any person, firm or company, with whom the work of the employee brings the employee into contact, any present, bonus, entertainment or honorarium of any sort whatsoever which is of more than nominal value or which might be construed to exceed customary courtesy extended in accordance with accepted ethical business standards.

## Section 9

9.1 The Committee has power to:

- (a) determine the amounts to be charged for the services provided by LR or for any of its publications;
- (b) withhold or, if already granted, to suspend or withdraw any class (or to withhold any certificate or report in any other case), in the event of non-payment of any fee.

## ■ Section 10

10.1 In this section:

- (i) 'Services' means the services provided by LR; and
- (ii) 'Contract' means the contract for supply of the Services; and
- (iii) the 'LR Group' includes LR, its affiliates and subsidiaries, and the officers, directors, employees, representatives and agents of any of them, individually or collectively.

10.2 LR's services do not assess compliance with any standard other than the applicable LR Rules, international conventions, and other standards agreed in writing by LR and the Client.

10.3 In providing Services, information or advice, the LR Group does not warrant the accuracy of any information or advice supplied. Except as set out herein, the LR Group will not be liable for any loss, damage or expense sustained by any person and caused by any act, omission, error, negligence or strict liability of any of the LR Group or caused by any inaccuracy in any information or advice given in any way by or on behalf of the LR Group even if held to amount to a breach of warranty. Nevertheless, if the Client uses LR's Services or relies on any information or advice given by or on behalf of the LR Group and as a result suffers loss, damage or expense that is proved to have been caused by any negligent act, omission or error of the LR Group or any negligent inaccuracy in information or advice given by or on behalf of the LR Group, then LR will pay compensation to the Client for its proved loss up to but not exceeding the amount of the fee (if any) charged for that particular service, information or advice.

10.4 Notwithstanding the previous clause, the LR Group will not be liable for any loss of profit, loss of contract, loss of user or any indirect or consequential loss, damage or expense sustained by any person caused by any act, omission or error or caused by any inaccuracy in any information or advice given in any way by or on behalf of the LR Group even if held to amount to a breach of warranty.

10.5 LR's omission or failure to carry out or observe any stipulation, condition, or obligation to be performed under the Contract will not give rise to any claim against LR or be deemed to be a breach of contract if the failure or omission arises from causes beyond LR's reasonable control.

10.6 Any dispute about the Services or the Contract is subject to the exclusive jurisdiction of the English courts and will be governed by English law.



# Classification Regulations

## Part 1, Chapter 2

Section 1

## Section

- 1 **Conditions for classification**
- 2 **Character of classification and class notations**
- 3 **Surveys – General**
- 4 **IACS QSCS Audits**
- 5 **Approval/Type Testing/Quality Control System**
- 6 **Classification of machinery with [X] LMC or MCH notation**

### ■ Section 1 Conditions for classification

#### 1.1 General

1.1.1 Ships referred to in this Chapter are defined in Parts 3, 4 and 7 of these Rules. Machinery referred to in this Chapter is defined in Parts 5 and 6 of these Rules. Systems referred to in this Chapter are defined in Part 7 of these Rules. Materials are referred to in the *Rules for the Manufacture and Certification of Materials* (hereinafter referred to as the Rules for Materials).

1.1.2 Ships built in accordance with LR's Rules and Regulations, or in accordance with requirements equivalent thereto, will be assigned a class in the *Register Book* and will continue to be classed as long as they are found, upon examination at the prescribed surveys, to be maintained in accordance with the requirements of the Rules. Classification will be conditional upon compliance with LR's requirements for both hull and machinery.

1.1.3 The Committee, in addition to requiring compliance with LR's Rules, may require to be satisfied that ships are suitable for the geographical or other limits or conditions of the service contemplated.

1.1.4 Loading conditions and any other preparations required to permit a ship with a class notation specifying some service limitation to undertake a sea-going voyage, either from port of building to service area or from one service area to another, are to be in accordance with arrangements agreed by LR prior to the voyage.

1.1.5 Any damage, defect, breakdown or grounding, which could invalidate the conditions for which a class has been assigned, is to be reported to LR without delay.

1.1.6 The Rules are framed on the understanding that ships will be properly loaded and handled. They do not, unless stated or implied in the class notation, provide for special distributions or concentrations of loading. The Committee may require additional strengthening to be fitted in any ship which, in their opinion, would otherwise be subjected to severe stresses due to particular features in the design, or where it is desired to make provision for exceptional loaded or ballast conditions. In such cases, particulars are to be submitted for consideration.

1.1.7 When longitudinal strength calculations have been required, loading guidance information is supplied to the Master by means of a Loading Manual and in addition, when required, by means of a loading instrument.

1.1.8 The Rules are framed on the understanding that ships will not be operated in environmental conditions more severe than those agreed for the design basis and approval, without the prior agreement of LR.

1.1.9 For ships, the arrangements and equipment of which are required to comply with the requirements of the:

- Load Line Convention;
- International Convention for the Safety of Life at Sea, 1974 and its Protocol of 1978;
- International Convention for the Prevention of Pollution from Ships, 1973, as modified by the Protocol of 1978 relating thereto;
- International Code for the Construction and Equipment of Ships Carrying Dangerous Chemicals in Bulk (IBC Code);
- International Code for the Construction and Equipment of Ships Carrying Liquefied Gases in Bulk (IGC Code);

and applicable Amendments thereto, the Committee requires the applicable Convention Certificates to be issued by a National Administration, or by LR, or by an IACS Member when so authorized. Safety Management Certificates in accordance with the provisions of the International Safety Management Code (ISM Code) may be issued by an organization complying with IMO Resolution A.739(18) and authorized by the National Authority with which the ship is registered. Cargo Ship Radio Certificates may be issued by an organization authorized by the National Authority with which the ship is registered. In the case of dual-classed ships, Convention Certificates may be issued by the other Society with which the ship is classed provided this is recognized in a formal Dual Class Agreement with LR and provided the other Society is also authorized by the National Authority.

1.1.10 Where an onboard computer system having longitudinal strength computation capability, which is required by the Rules, is provided on a new ship, or newly installed on an existing ship, then the system is to be certified in respect of longitudinal strength in accordance with LR's document entitled *Approval of Longitudinal Strength and Stability Calculation Programs*, see also Pt 3, Ch 4.8.

# Classification Regulations

## Part 1, Chapter 2

Sections 1 & 2

**1.1.11** Where an onboard computer system having stability computation capability is provided on a new ship, then the system is to be certified in respect of stability aspects in accordance with LR's document entitled, *Approval of Longitudinal Strength and Stability Calculation Programs*. When provided, an onboard computer system having stability computation capability is to carry out the calculations and checks necessary to assess compliance with all the stability requirements applicable to the ship on which it is installed.

### 1.2 Advisory services

**1.2.1** The Rules do not cover certain technical characteristics, such as stability, trim, hull vibration, etc., but the Committee is willing to advise on such matters although it cannot assume responsibility for them.

**1.2.2** Where a vessel is so badly damaged that class has to be suspended, LR is prepared to assist the Owner with advice if requested.

## Section 2 Character of classification and class notations

### 2.1 Definitions

#### NOTE

For the purpose of class notations, the definitions given in 2.1.1 to 2.1.11 will apply.

**2.1.1 Clear water.** Water having sufficient depth to permit the normal development of wind generated waves.

**2.1.2 Fetch.** The extent of clear water across which a wind has blown before reaching the ship.

**2.1.3 Sheltered water.** Water where the fetch is six nautical miles or less.

**2.1.4 Reasonable weather.** Wind strengths of force six or less in the Beaufort scale, associated with sea states sufficiently moderate to ensure that green water is taken on board the ship's deck at infrequent intervals only or not at all.

**2.1.5 Type notation.** A notation indicating that the ship has been arranged and constructed in compliance with particular Rules intended to apply to that type of ship, e.g. dredger.

**2.1.6 Cargo notation.** A notation indicating that the ship has been designed, modified or arranged to carry one or more particular cargoes, e.g. sulphuric acid. Ships with one or more particular cargo notations are not thereby prevented from carrying other cargoes for which they are suitable.

**2.1.7 Special duties notation.** A notation indicating that the ship has been designed, modified or arranged for special duties other than those implied by the type and cargo notations, e.g. research. Ships with special duties notations are not thereby prevented from performing any other duties for which they may be suitable.

**2.1.8 ShipRight notation.** A notation indicating that one or more of LR's ShipRight procedures have been satisfactorily followed. Class notations or descriptive notes will be assigned according to whether the ShipRight procedures are applied on a mandatory or voluntary basis, i.e.:

- (a) The procedures relating to the design and construction of the hull are mandatory for the classification of large and structurally complex ships. In such cases, the associated ShipRight notation is assigned as a class notation and will appear in column 4 of the *Register Book*, see 2.3.16. When these procedures are applied on a voluntary basis, then the associated ShipRight notation is assigned as a descriptive note and will appear in column 6 of the *Register Book*, see 2.7.
- (b) The remaining ShipRight procedures are voluntary for the purposes of classification, and are assigned as descriptive notes and will appear in column 6 of the *Register Book*, see 2.7.3.

**2.1.9 Special features notation.** A notation indicating that the ship incorporates special features which significantly affect the design, e.g. movable decks.

**2.1.10 Service restriction notation.** A notation indicating that a ship has been classed on the understanding that it will be operated only in suitable areas or conditions which have been agreed by the Committee, e.g. protected waters service.

**2.1.11 Linked** means connected, while in operation, to an attendant ship (which may be on shore, submerged or afloat) by a restraining line, suspension cable or umbilical cord.

### 2.2 Character symbols

**2.2.1** All ships, when classed, will be assigned one or more character symbols as applicable. For the majority of ships, the character assigned will be **100A1** or **⌘ 100A1**.

**2.2.2** A full list of character symbols for which ships may be eligible is as follows:

**⌘** This distinguishing mark will be assigned, at the time of classing, to new ships constructed under LR's Special Survey, in compliance with the Rules, and to the satisfaction of the Committee.

**—**  
**⌘** This distinguishing mark will be assigned, at the time of classing, to new ships constructed under LR's Special Survey in accordance with plans approved by another recognized classification society.

**100** This character figure will be assigned to all ships considered suitable for sea-going service.



# Classification Regulations

## Part 1, Chapter 2

Section 2

**A** This character letter will be assigned to all ships which have been built or accepted into class in accordance with LR's Rules and Regulations, and which are maintained in good and efficient condition.

**1** This character figure will be assigned to:

- (a) Ships having on board, in good and efficient condition, anchoring and/or mooring equipment in accordance with the Rules.
- (b) Ships classed for a special service, having on board, in good and efficient condition, anchoring and/or mooring equipment approved by the Committee as suitable and sufficient for the particular service.

**N** This character letter will be assigned to ships on which the Committee has agreed that anchoring and mooring equipment need not be fitted in view of their particular service.

**T** This character letter will be assigned to ships which are intended to perform their primary designed service function only while they are anchored, moored, towed or linked, and which have, in good and efficient condition, adequately attached anchoring, mooring, towing or linking equipment which has been approved by the Committee as suitable and sufficient for the intended service.

2.2.3 For classification purposes, the character figure **1**, or either of the character letters **N** or **T**, is to be assigned.

2.2.4 In cases where the anchoring and/or mooring equipment is found to be seriously deficient in quality or quantity, the class of the ship will be liable to be withheld.

### 2.3 Class notations (hull)

2.3.1 When considered necessary by the Committee, or when requested by an Owner and agreed by the Committee, a class notation will be appended to the character of classification assigned to the ship. This class notation will consist of one of, or a combination of: a type notation, a cargo notation, a special duties notation, a special features notation and/or a service restriction notation, e.g. 'A100A1 Oil Tanker F.P. exceeding 60°C in No. 4 tanks ESP Baltic Service Ice Class 1B'.

2.3.2 Details of the ship types and particular cargoes for which special Rules apply are given in those Chapters of Parts 3, 4 and 7 which apply to such ships and cargoes.

2.3.3 Details of the more common special features and the conditions relevant to the assignment of special features notations, together with the form of such notations, are incorporated in Parts 3, 4 and 7 as applicable.

2.3.4 Service restriction notations will generally be assigned in one of the forms shown in 2.3.6 to 2.3.10, but this does not preclude Owners or Shipbuilders requesting special consideration for other forms in unusual cases.

2.3.5 Where a service notation is applicable, certain exemptions may be granted. Where these affect statutory requirements, such as Load Lines, the Owner or shipbuilder is to obtain the authorisation of the flag state. Such exemptions are to be recorded on the Class certificate and any applicable statutory certificate.

2.3.6 **Protected waters service.** Service in sheltered waters adjacent to sand banks, reefs, breakwaters or other coastal features, and in sheltered waters between islands, e.g. 'Protected Waters Service at Storebaelt Bridge'.

2.3.7 **Extended protected waters service.** Service in protected waters and also for short distances (generally less than 15 nautical miles) beyond protected waters in 'reasonable weather', e.g. 'Extended Protected Waters Service from the Port of Lagos'.

2.3.8 **Specified coastal service.** Service along a coast, the geographical limits of which will be indicated in the *Register Book*, and for a distance out to sea generally not exceeding 21 nautical miles, unless some other distance is specified for 'coastal service' by the Administration with which the ship is registered, or by the Administration of the coast off which it is operating, as applicable, e.g. 'Indonesian coastal service'.

2.3.9 **Specified route service.** Service between two or more ports or other geographical features which will be indicated in the *Register Book*, e.g. 'London to Rotterdam service' 'London, Rotterdam and Hamburg service'.

2.3.10 **Specified operating area service.** Service within one or more geographical area(s) which will be indicated in the *Register Book*, e.g. 'Pacific Tropical Zone service' 'Great Lakes and St. Lawrence to Pt. du Monts service' 'Red Sea, Eastern Mediterranean and Black Sea service'.

2.3.11 **\*IWS.** This notation (In-water Survey) may be assigned to a ship where the applicable requirements of LR's Rules and Regulations are complied with, see Ch 3,4.3; Pt 3, Ch 1,5.2 and 5.3; Pt 3, Ch 2,3.5; Pt 3, Ch 13,2.8 and Pt 5, Ch 6,3.12.

2.3.12 **ESP.** This notation (Enhanced Survey Programme) will be assigned to oil tankers, combination carriers, chemical tankers, bulk carriers and ore carriers, as defined in Ch 3,1.5 which are subject to an enhanced survey programme as detailed in Ch 3, Sections 3, 6, 7 and 8.

2.3.13 **CSR.** This notation will be assigned to bulk carriers and double hull oil tankers compliant with the *IACS Common Structural Rules*, see Pt 4, Ch 7,1.2.1 and Ch 9,1.2.1.

2.3.14 **ESN.** This notation (Enhanced Survivability Notation) will be assigned to non-**CSR** bulk carriers which are designed to withstand the individual flooding of all cargo holds, see Pt 4, Ch 7,1.3.2.

2.3.15 **LI.** This notation will be assigned where an approved loading instrument has been installed as a classification requirement.

# Classification Regulations

## Part 1, Chapter 2

Section 2

**2.3.16 ShipRight notations.** The following notations are associated with LR's ShipRight procedures and may be assigned in conjunction with the **ShipRight** notation as considered appropriate by the Committee, on application from the Owners. The requirements pertaining to these notations and the (hull) ShipRight procedures are given in Pt 3, Ch 16.

### ShipRight

**SDA** This notation (Structural Design Assessment) will be assigned when direct calculations in accordance with the ShipRight procedures have been applied.

### ShipRight

**FDA** This notation (Fatigue Design Assessment) will be assigned when an appraisal has been made of the fatigue performance of the structure in accordance with the ShipRight procedures.

### ShipRight

**FDA plus** This notation (Fatigue Design Assessment plus) will be assigned when an appraisal has been made for a higher level of fatigue performance than that made for the assignment of **ShipRight FDA**.

### ShipRight

**CM** This notation (Construction Monitoring), which complements the **ShipRight SDA**, **ShipRight FDA** and **ShipRight FDA plus** notations, will be assigned when the controls in construction tolerances detailed in the ShipRight procedures have been applied and verified.

**2.3.17** When **ShipRight SDA**, **ShipRight FDA** or **ShipRight FDA plus** are assigned, the precise technical conditions of the appraisal will be made available to Owners.

**2.3.18** Where LR's ShipRight SDA procedure has been applied individually or where ShipRight SDA, ShipRight FDA or ShipRight FDA plus and ShipRight CM procedures have all been applied, whether on a voluntary or mandatory basis, these particular class notations will appear in column 4 of the *Register Book*.

## 2.4 Class notations (machinery)

**2.4.1** The following class notations are associated with the machinery construction and arrangement, and may be assigned as considered appropriate by the Committee:

✠ **LMC** This notation will be assigned when the propelling and essential auxiliary machinery have been constructed, installed and tested under LR's Special Survey and in accordance with LR's Rules and Regulations.

### ✠ LMC

This notation will be assigned when the propelling and essential auxiliary machinery have been constructed under the survey of a recognized authority in accordance with the Rules and Regulations equivalent to those of LR. In addition, the whole of the machinery will be required to have been installed and tested under LR's Special Survey in accordance with LR's Rules and Regulations.

### [✠] LMC

This notation will be assigned when the propelling arrangements, steering systems, pressure vessels and the electrical equipment for essential systems have been constructed, installed and tested under LR's Special Survey and are in accordance with LR's Rules and Regulations. Other items of machinery for propulsion and electrical power generation including propulsion gearing arrangements and other auxiliary machinery for essential services that are in compliance with LR Rules and supplied with the manufacturer's certificate will be acceptable under this notation. The system arrangements of propelling and essential auxiliary machinery are required to be appraised by LR, and found to be acceptable to LR. See 2.8.2.

### LMC

This notation (without ✠) will be assigned when the propelling and essential auxiliary machinery have neither been constructed nor installed under LR's Special Survey but the existing machinery, its installation and arrangement, have been tested and found to be acceptable to LR. This notation is assigned to existing ships in service accepted or transferring into LR class.

### MCH

This notation will be assigned when the propelling and essential auxiliary machinery has been installed and tested under LR's survey requirements and found to be acceptable to LR. Items of machinery and equipment for propelling and auxiliary machinery for essential services supplied with the manufacturer's certificate will be acceptable under this class notation. The system arrangements of propelling and essential auxiliary machinery are required to be appraised by LR, and found to be acceptable to LR. See 2.8.3.

### IGS

This notation will be assigned when a ship intended for the carriage of oil in bulk, or for the carriage of liquid chemicals in bulk, is fitted with an approved system for producing gas for inerting the cargo tanks.

### PMR

This notation will be assigned where the main propulsion systems are arranged such that, in the event of a single failure in equipment, the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

# Classification Regulations

## Part 1, Chapter 2

Section 2

**PMR\*** This notation will be assigned where the main propulsion systems are arranged such that, in the event of a single failure in equipment, the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and where the machinery is installed in separate compartments such that, in the event of the loss of one compartment, the ship will retain availability of propulsion power. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

**SMR** This notation will be assigned where the steering systems for manoeuvring are arranged so that steering capability will continue to be available in the event of a single failure in the steering gear equipment or loss of power supply or control system for any steering system. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

**SMR\*** This notation will be assigned where the steering systems for manoeuvring are arranged so that steering capability will continue to be available in the event of a single failure in the steering gear equipment or loss of power supply or control system for any steering system and where the steering systems are installed in separate compartments such that, in the event of the loss of one compartment, steering capability will continue to be available. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

**PSMR** This notation will be assigned where the main propulsion and steering systems are configured such that, in the event of a single failure in equipment, the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and retain steering capability. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

**PSMR\*** This notation will be assigned where the main propulsion and steering systems are configured such that, in the event of a single failure in equipment, the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and retain steering capability. The propulsion and steering arrangements are to be installed in separate compartments such that in the event of the loss of one compartment, the ship will retain availability of propulsion power and manoeuvring capability. It also denotes that the installation has been arranged, installed and tested in accordance with LR Rules.

2.4.2 The following class notations are associated with the machinery control and automation, and may be assigned as considered appropriate by the Committee:

**UMS** This notation may be assigned when the arrangements are such that the ship can be operated with the machinery spaces unattended. It denotes that the control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**CCS** This notation may be assigned when the arrangements are such that the machinery may be operated with continuous supervision from a centralized control station. It denotes that the control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**ICC** This notation may be assigned when the arrangements are such that the control and supervision of ship operational functions are computer based. It denotes that the control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**IP** This notation may be assigned to a ship classed with LR when the arrangements of the machinery are such that the propulsion equipment and all the essential auxiliary machinery is integrated with the power unit for operation under all normal sea-going and manoeuvring conditions. The system is to be bridge controlled and the propulsion equipment is to incorporate an emergency means of propulsion in the event of failure in the prime mover. It also denotes that the machinery and control equipment have been arranged, installed and tested in accordance with LR's Rules.

**IFP** This additional notation may be assigned where an integrated fire protection system is fitted to provide control and monitoring of all active fire protection and fixed fire extinguishing systems from a centralized fire-control station. It denotes that the integrated fire protection system has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

2.4.3 The following class notations are associated with dynamic positioning arrangements, and may be assigned as considered appropriate by the Committee:

**DP(CM)** This notation may be assigned when a ship is fitted with centralized remote manual controls for position keeping and with position reference system(s) and environmental sensor(s). It denotes that the machinery and control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

# Classification Regulations

# Part 1, Chapter 2

Section 2

**DP(AM)** This notation may be assigned when a ship is fitted with automatic main and manual standby controls for position keeping and with position reference system(s) and environmental sensor(s). It denotes that the machinery and control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**DP(AA)** This notation may be assigned when a ship is fitted with automatic main and automatic standby controls for position keeping and with position reference system(s) and environmental sensor(s). It denotes that the machinery and control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**DP(AAA)** This notation may be assigned when a ship is fitted with automatic main and automatic standby controls for position keeping, together with an additional/emergency automatic control unit located in a separate compartment and with position reference systems and environmental sensors. It denotes that the machinery and control engineering equipment has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

The foregoing dynamic positioning notations may be supplemented with a Performance Capability Rating (PCR). This rating indicates the calculated percentage of time that a ship is capable of holding heading and position under a standard set of environmental conditions (North Sea), see Pt 7, Ch 4.

2.4.4 The following class notations are associated with navigation safety, and may be assigned as considered appropriate by the Committee:

**NAV1** This notation will be assigned when the bridge layout and level of equipment are such that the ship is considered suitable for safe periodic operation under the supervision of a single watchkeeper on the bridge. It denotes that the navigational installation has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto.

**IBS** This additional notation will be assigned where an integrated bridge system is fitted to provide electronic chart display, track planning and automatic track following, centralized navigation information display, and bridge alarm management. It denotes that the integrated bridge system has been arranged, installed and tested in accordance with LR's Rules, or is equivalent thereto. For assignment of this notation, the layout of the bridge and the equipment on the bridge are to satisfy the requirements for assignment of the notation **NAV1**. Where the layout of the bridge and the equipment located on the bridge satisfy the requirements of a relevant international or national ergonomic or

human centred design standard or an acceptable equivalent, compliance with the requirements of **NAV1** may be relaxed.

2.4.5 Machinery class notations will not be assigned to ships the hulls of which are not classed or intended to be classed with LR.

2.4.6 The notations **⌘ LMC**, **⌘ LMC**, **[⌘]LMC**, **LMC** (without **⌘**) and **MCH** will in general not be assigned to non-propelled craft, but individual cases will be considered on their merits.

## 2.5 Class notations (refrigerated cargo installations (RMC), controlled atmosphere (CA) systems and carriage of refrigerated containers (CRC))

2.5.1 The following class notations may be assigned as considered appropriate by the Committee, on application from the Owners:

**⌘ Lloyd's RMC** This notation will be assigned when a refrigerated cargo installation has been constructed, installed and tested under LR's Special Survey and in accordance with the relevant requirements of the Rules.

**Lloyd's RMC** This notation will be assigned when the arrangements of the refrigerated cargo installation have been found to be equivalent to Rule requirements, and the installation has been tested in accordance with the relevant requirements of the Rules.

**‡** This symbol will be assigned to installations considered suitable for the carriage of fruit. It indicates that the following parameters have been assessed and found satisfactory:

- The rate of air circulation and the air refreshing arrangements through the refrigerated spaces or chambers, or to containers.
- The temperature controls and monitoring arrangements.
- The installation's capability to cool down a complete cargo of fruit to its carrying temperature within a specified time. The symbol will also be assigned to fishing vessels that have the refrigerating capacity to freeze down their catch.

**⌘ Lloyd's RMC (LG)** This notation will be assigned to a classed liquefied gas carrier or tanker, in which reliquefaction or refrigeration equipment is approved and fitted for cargo temperature and pressure control where the equipment has been constructed, installed and tested in accordance with the relevant requirements of the Rules.

# Classification Regulations

## Part 1, Chapter 2

Section 2

### Lloyd's

**RMC (LG)** This notation will be assigned to a classed liquefied gas carrier or tanker, in which reliquefaction or refrigeration equipment is fitted for cargo temperature and pressure control, where the equipment has been found equivalent to Rule requirements and tested in accordance with the relevant requirements of the Rules.

2.5.2 The following class notations are associated with controlled atmospheres and may be assigned as considered appropriate by the Committee, on application from Owners, see also Pt 7, Ch 1:

**(CA)** This notation may be assigned when a ship is fitted with arrangements for maintaining airtightness in CA zones and for the ready connection to a gas system in accordance with the relevant requirements of the Rules.

**CA (%O<sub>2</sub>, %CO<sub>2</sub>)** This notation may be assigned when a ship is provided with a CA system which will achieve and maintain specified ranges of oxygen and carbon dioxide levels in accordance with the relevant requirements of the Rules.

**RH** This notation may be assigned when a ship can maintain a specified relative humidity in the CA zones.

Before assignment of any of the above notations it is a prerequisite that the refrigeration installation is assigned an **RMC** class notation.

2.5.3 The following class notation is associated with the carriage of refrigerated cargo containers and may be assigned as considered appropriate by the Committee, on application from Owners, see also Pt 7, Ch 10:

✱ **CRC** This notation may be assigned when a ship is provided with a ventilation system which is approved, installed and tested in accordance with the relevant requirements of the Rules.

2.5.4 The class notation assigned will additionally specify the temperature conditions and other relevant characteristics for which the equipment has been approved, see Pt 6, Ch 3.

2.5.5 The class notation assigned will be maintained as long as the installation is found, at the prescribed Periodical Surveys, to be in a fit and efficient condition, and in accordance with the requirements of the Rules.

2.5.6 The Committee will give consideration to ships engaged on voyages of short duration, to installations of small capacity, or to other special circumstances. In such cases the class may include a service limitation or other restriction.

2.5.7 Refrigerating installations designed to supply refrigerated air to insulated containers in ships' holds aboard container ships, are eligible for classification. The installation is to include the refrigerating machinery, supply and return air ducting, and the flexible couplings between containers and the duct system. Where the arrangements are such that cell air conditioning is essential to the carriage of the containers, the air conditioning equipment and/or insulation of the hold, deckheads, sides and tank tops are to be included in the classification.

2.5.8 Other methods of carrying refrigerated cargoes in containers aboard container ships will be considered for classification on application.

### 2.6 Class notations (Environmental Protection)

2.6.1 The following class notations are associated with the design and operation of a ship and may be assigned as considered appropriate by the Committee, on application from the Owners:

**EP** This notation will be assigned when a ship is designed and operated in accordance with the relevant requirements of the Rules.

**EP** This notation will be assigned when the environmental protection arrangements are in accordance with the requirements of another recognized classification society and are essentially equivalent to Rule requirements and the ship is operated in accordance with the relevant requirements of the Rules.

2.6.2 The class notations defined in 2.6.1 will be suspended on change of Owner or Manager until LR can confirm by audit that the necessary operational procedures required by the Rules are established.

### 2.7 Descriptive notes

2.7.1 In addition to any class notations, an appropriate descriptive note may be entered in column 6 of the *Register Book* indicating the type of ship in greater detail than is contained in the class notation, and/or providing additional information about the ship's design and construction. This descriptive note is not an LR class notation and is provided solely for the information of users of the *Register Book*.

2.7.2 Where evidence exists that supporting calculations have been performed in accordance with hull structural finite element and fatigue analysis procedures of a recognized Classification Society, then, on application from Owners, the descriptive note **ShipRight (E)** may be entered in column 6 of the *Register Book*.

# Classification Regulations

# Part 1, Chapter 2

Sections 2 & 3

2.7.3 Where LR's ShipRight procedures for the following have been applied on a voluntary basis, then a descriptive note will, at the Owner's request, be entered in column 6 of the *Register Book*, preceded by the word **ShipRight** (see also Pt 3, Ch 16 and Pt 5, Ch 21):

<b>ES</b>	Enhanced Scantlings
<b>PCWBT(date)</b>	Protection Coatings in Water Ballast Tanks
<b>SEA(Hss-n)</b>	Ship Event Analysis (Hull Surveillance Systems)
<b>SERS</b>	Ship Emergency Response Service
<b>SCM</b>	Screwshaft Condition Monitoring
<b>TCM</b>	Main Steam Turbine Condition Monitoring
<b>MCM</b>	Machinery Condition Monitoring
<b>HPMS</b>	Hull Planned Maintenance Scheme
<b>MPMS</b>	Machinery Planned Maintenance Scheme
<b>RCM</b>	Reliability Centred Maintenance
<b>BWMP</b>	Ballast Water Management Plan

2.7.4 Where an approved loading instrument is provided as an Owner's requirement, a descriptive note **LI** may be entered in column 6 of the *Register Book*.

## 2.8 Application notes

2.8.1 **Propelling and essential auxiliary machinery** includes machinery, equipment and systems installed for the ship to be under seagoing conditions and that are necessary for the following:

- Maintaining the watertight and weathertight integrity of the hull and spaces within the hull.
- The safety of the ship, machinery and personnel on board.
- The functioning and dependability of propulsion, steering and electrical systems.
- The operation and functioning of control engineering systems for the monitoring and safety of propulsion and steering systems.
- The operation and functioning of emergency machinery and equipment.

2.8.2 **Manufacturer's certificate** for assignment of the [X]LMC notation. Acceptance of the manufacturer's certificate for items of machinery for propulsion (including propulsion gearing with single input/output arrangements) and for electrical power generation and for other auxiliary machinery for essential services is subject to the following:

- The ship is a cargo ship of less than 500 gross tonnage or is a ship of 500 gross tonnage or greater and is not required to comply with international conventions applicable to a ship with unrestricted service.
- Propulsion power is provided by oil engines or gas turbines which have been type approved to LR requirements for marine application.
- Electrical power is provided by generators driven by oil engines or gas turbines which have been type approved to LR requirements for marine application.
- The design and manufacture standards for all machinery and associated systems are the applicable LR Rules.
- The machinery and equipment is manufactured under a recognized quality control system.

- Propellers, propulsion shafting and multiple input/output gearboxes are not included within the scope of propulsion arrangements for acceptance of a manufacturer's certificate.

2.8.3 **Manufacturer's certificate** for assignment of the **MCH** notation. Acceptance of the manufacturer's certificate for propelling and essential auxiliary machinery is subject to the following:

- The ship is a cargo ship of less than 500 gross tonnage or is a ship of 500 gross tonnage or greater and is not required to comply with the international conventions applicable to a ship with unrestricted service.
- Propulsion power is provided by oil engines or gas turbines which have been type approved to LR requirements for marine application.
- Electrical power is provided by generators driven by oil engines or gas turbines which have been type approved to LR requirements for marine application.
- The power of any engine or gas turbine is less than 2,250 kW and the cylinder bore or any diesel engine is not greater than 300 mm.
- The design and manufacture standards for machinery and associated systems are the applicable LR Rules or other marine standards acceptable to LR.
- The machinery and equipment is manufactured under a recognized quality control system.

## Section 3 Surveys – General

### 3.1 Statutory surveys

3.1.1 The Committee will act, when authorized on behalf of Governments, in respect of National and International statutory safety and other requirements for passenger and cargo ships.

3.1.2 The Committee will also act, when authorized, in respect of National Safety and other requirements relating to ships used for offshore mineral exploration and exploitation.

### 3.2 New construction surveys

3.2.1 When it is intended to build a ship for classification with LR, constructional plans and all necessary particulars relevant to the hull, equipment and machinery, as detailed in the Rules, are to be submitted for the approval of the Committee before the work is commenced. Any subsequent modifications or additions to the scantlings, arrangements or equipment shown on the approved plans are also to be submitted for approval.

3.2.2 Where the proposed construction of any part of the hull or machinery is of novel design, or involves the use of unusual material, or where experience, in the opinion of the Committee, has not sufficiently justified the principle or mode of application involved, special tests or examinations before and during service may be required. In such cases a suitable notation may be entered in the *Register Book*.

# Classification Regulations

## Part 1, Chapter 2

Section 3

3.2.3 The materials used in the construction of hulls and machinery intended for classification are to be of good quality and free from defects and are to be tested in accordance with the requirements of the Rules for Materials (Part 2). The steel is to be manufactured by an approved process at works recognized by the Committee. Alternatively, tests to the satisfaction of the Committee will be required to demonstrate the suitability of the steel.

3.2.4 New ships intended for classification are to be built under LR's Special Survey. From the commencement of the work until the completion of the ship, the Surveyors are to be satisfied that the materials, workmanship and arrangements are satisfactory and in accordance with the Rules. Any items found not to be in accordance with the Rules or the approved plans, or any material, workmanship or arrangements found to be unsatisfactory, are to be rectified.

3.2.5 For compliance with 3.2.4, LR is prepared to consider methods of survey and inspection for hull construction which formally include procedures involving the shipyard management, organization and quality systems. The minimum requirements for the approval of any such proposed Quality Assurance methods are laid down in Pt 3, Ch 15.

3.2.6 Each offshore supply ship, offshore tug/supply ship, dredger, hopper dredger, sand carrier, hopper barge or reclamation craft, proceeding to sea is to comply with the draught and stability requirements of the National Authority and is to have on board sufficient stability data to enable it to be properly loaded and handled, or, where appropriate, to be properly towed. This data is to take full account of any intended special distribution or concentration of loading. In the case of an unmanned ship under tow, the data is to be made available to the tug master.

3.2.7 Copies of approved plans (showing the ship as built), essential certificates and records, required loading and other instruction manuals are to be readily available for use when required by LR's Surveyors, and may be required to be kept on board.

3.2.8 When the machinery is constructed under LR's Special Survey, this survey is to relate to the period from the commencement of the work until the final test under working conditions. Any items found not to be in accordance with the Rules or the approved plans, or any material, workmanship or arrangements found to be unsatisfactory, are to be rectified.

3.2.9 When arrangements are such that essential machinery can be operated by remote and/or automatic control equipment, the control equipment is to be arranged, installed and tested in accordance with LR's Rules and Regulations.

3.2.10 The date of completion of the Special Survey during construction of ships built under LR's inspection will normally be taken as the date of build to be entered in the *Register Book*. If the period between launching and commissioning is, for any reason, unduly prolonged, the dates of launching and completion or commissioning may be separately indicated in the *Register Book*.

3.2.11 When a ship, upon completion, is not immediately commissioned but is laid-up for a period, the Committee, upon application by the Owner, prior to the ship proceeding to sea, will direct an examination to be made by LR's Surveyors which may include a survey in dry-dock. If, as the result of such a survey, the hull and machinery be reported in all respects free from deterioration, the subsequent Special Survey and Complete Survey of the machinery will date from the time of such examination.

### 3.3 Existing ships

3.3.1 **Classification of ships not built under survey.** The requirements of the Committee for the classification of ships which have not been built under LR's Survey are indicated in Ch 3,19. Special consideration will be given to ships transferring class to LR from another recognized Classification Society.

3.3.2 **Reclassification.** When reclassification or class reinstatement is desired for a ship for which the class previously assigned by LR has been withdrawn or suspended, the Committee will direct that a survey, appropriate to the age of the ship and the circumstances of the case, be carried out by LR's Surveyors. If, at such a survey, the ship be found or placed in a good and efficient condition in accordance with the requirements of the Rules and Regulations, the Committee will be prepared to consider reinstatement of the original class or the assignment of such other class as may be deemed necessary.

3.3.3 A similar arrangement will apply in the case of reclassification of refrigerated cargo installations.

3.3.4 The Committee reserves the right to decline an application for classification or reclassification where the prior history or condition of the ship indicates this to be appropriate.

### 3.4 Damages, repairs and alterations

3.4.1 All repairs to hull, equipment and machinery which may be required in order that a ship may retain her class, (see 1.1.5), are to be carried out to the satisfaction of LR's Surveyors. When repairs are effected at a port, terminal or location where the services of a Surveyor to LR are not available, the repairs are to be surveyed by one of LR's Surveyors at the earliest opportunity thereafter.

3.4.2 When, at any survey, the Surveyors consider repairs to be immediately necessary, either as a result of damage, or wear and tear, they are to communicate their recommendations at once to the Owner, or his representative. When such recommendations are not complied with, immediate notification is to be given to the Committee by the Surveyors.

# Classification Regulations

## Part 1, Chapter 2

### Section 3

3.4.3 When, at any survey, it is found that any damage, defect or breakdown (see 1.1.5) is of a nature that does not require immediate permanent repair, but is sufficiently serious to require rectification by a prescribed date in order to maintain class, a suitable condition of class is to be imposed by the Surveyors and recommended to the Committee for consideration.

3.4.4 If a ship which is classed with LR is to leave harbour limits or protected waters under tow, the Owner is to advise LR of the circumstances prior to her departure.

3.4.5 If a ship which is classed with LR is taken in tow whilst at sea, the Owner is to advise LR of the circumstances at the first practicable opportunity.

3.4.6 Plans and particulars of any proposed alterations to the approved scantlings and arrangements of hull, equipment, or machinery are to be submitted for approval, and such alterations are to be carried out to the satisfaction of LR's Surveyors.

### 3.5 Existing ships – Periodical Surveys

3.5.1 Annual Surveys are to be held on all ships within three months, before or after each anniversary of the completion, commissioning or Special Survey in accordance with the requirements given in Chapter 3. The date of the last Annual Survey will be recorded on the ClassDirect Live website.

3.5.2 Intermediate Surveys are to be held on all ships instead of the second or third Annual Survey after completion, commissioning or Special Survey. The Intermediate Survey may be commenced at the second Annual Survey and progressed with completion at the third Annual Survey. The date of the last Intermediate Survey will be recorded on the ClassDirect Live website.

3.5.3 The Owner should notify LR whenever a ship can be examined in dry-dock or on a slipway. A minimum of two Docking Surveys are to be held in each five-year Special Survey period and the maximum interval between successive Docking Surveys is not to exceed three years. One of the two Docking Surveys required in each five year period is to coincide with the Special Survey. Consideration may be given in exceptional circumstances to an extension of this interval not exceeding three months beyond the due date. The Committee may accept an In-water Survey in lieu of the intermediate docking between Special Surveys, see Ch 3, 4.3.

An In-water Survey shall not be permitted for ships over 15 years of age that are assigned the notation **ESP**. A Docking Survey is considered to coincide with the Special Survey when held within the 15 months prior to the due date of the Special Survey.

Where the Special Survey of the hull is carried out on a Continuous Survey basis, as given in 3.5.14, the survey in dry-dock may be held at any time within the five-year cycle.

In this context 'exceptional circumstances' means unavailability of dry-docking facilities, repair facilities, essential materials, equipment or spare parts or delays incurred by action taken to avoid severe weather conditions.

3.5.4 The interval between dry-dockings for ships operating in fresh water and for certain non-self-propelled craft may be greater than that given in 3.5.3.

3.5.5 Attention is to be given to any relevant statutory requirements of the National Authority of the country in which the ship is registered.

3.5.6 The date of the last examination in dry-dock or on a slipway will be recorded on the ClassDirect Live website.

3.5.7 As an alternative to Annual Surveys and Docking Surveys, according to 3.5.1 and 3.5.3 respectively, ships classed '100A1 shipborne barge' may be subjected to Intermediate Surveys. These surveys become due 30 months after the previous Special Survey. The survey is to be in accordance with the requirements given in Ch 3,2, as applicable. Intermediate Surveys are to be completed within three months of the due date.

3.5.8 Survey requirements for In-water Surveys are given in Ch 3,4.3. The date of the last In-water Survey will be recorded on the ClassDirect Live website.

3.5.9 All ships classed with LR are also to be subjected to Special Surveys in accordance with the requirements given in Chapter 3. These Surveys become due at five-yearly intervals, the first one five years from the date of build or date of Special Survey for Classification as recorded in the *Register Book*, and thereafter five years from the date recorded for the previous Special Survey. Consideration may be given at the discretion of the Committee to any exceptional circumstances justifying an extension of the hull classification to a maximum of three months beyond the fifth year. If an extension is agreed, the next period of hull classification will start from the due date of the Special Survey before the extension was granted. A definition of 'exceptional circumstances' is given in 3.5.3.

3.5.10 Where, on shipborne barges, Intermediate Surveys are permitted as an alternative to Annual and Docking Surveys, Special Surveys become due five years after the previous Special Survey.

3.5.11 Special Surveys may be commenced at the fourth Annual Survey after completion, commissioning, or previous Special Survey, and be progressed during the succeeding year with a view to completion by the due date of the Special Survey.

3.5.12 When Special Surveys are commenced prior to the fourth Annual Survey, the entire survey is to be completed within 15 months if such work is to be credited towards the Special Survey.

3.5.13 Ships which have satisfactorily passed a Special Survey will have a record entered in the *Register Book* indicating the date and the notation **ESP** if this is applicable (see 2.3.12). Where the Special Survey is completed more than three months before the due date, the new record of Special Survey will be the final date of survey. In all other cases the date recorded will be the fifth anniversary.



# Classification Regulations

## Part 1, Chapter 2

### Section 3

3.5.14 At the request of an Owner, the Committee may agree that the Special Survey of the hull, for ships other than general dry cargo ships, bulk carriers, combination carriers, chemical tankers and oil tankers, be carried out on the Continuous Survey basis, all compartments of the hull being opened for survey and testing, in rotation, with an interval of five years between consecutive examinations of each part. In general, approximately one fifth of the Special Survey is to be completed each year and all the requirements of the particular hull Special Survey must be completed at the end of the five year cycle. For examination of items listed in Ch 3,2.2.19 to 2.2.20, 2.2.24 and Ch 3,3.2.6, 3.2.7 and 3.2.9, the intervals for inspection will require to be specially agreed. For ships more than 10 years of age, an examination of the ballast tanks is to be carried out twice in each five year cycle, i.e. once within the scope of the Intermediate Survey and once within the scope of the Continuous Survey. Ships which have satisfactorily completed the cycle will have a record entered in the *Register Book* indicating the date of completion which will not be later than five years from the last assigned date of Complete Survey of the hull. The agreement for surveys to be carried out on Continuous Survey basis may be withdrawn at the discretion of the Committee.

3.5.15 Machinery is to be submitted to the surveys detailed in Ch 3,11 to 17.

3.5.16 Complete Surveys of machinery become due at five-yearly intervals, the first one five years from the date of build or date of first classification as recorded in the *Register Book*, and thereafter five years from the date recorded for the previous Complete Survey. Consideration can be given at the discretion of the Committee to any exceptional circumstances justifying an extension of machinery class to a maximum of three months beyond the fifth year. If an extension is agreed, the next period of machinery class will start from the due date of Complete Survey of machinery before extension was granted. Surveys which are commenced prior to their due date are not to extend over a period greater than 12 months, except with the prior approval of the Committee. Where the complete survey is completed more than three months before the due date, the recorded date of completion will be the final date of survey. In all other cases the date recorded will be the fifth anniversary.

3.5.17 Upon application by an Owner, the Committee may agree to an extension of the survey requirements for main engines, which, by the nature of the ship's normal service, do not attain the number of running hours recommended by the engines' manufacturer for major overhauls within the survey periods given in 3.5.16.

3.5.18 If it is found desirable that any part of the machinery should be examined again before the due date of the next survey, a certificate for a limited period will be granted in accordance with the nature of the case.

3.5.19 When, at the request of an Owner, it has been agreed by the Committee that the Complete Survey of the machinery may be carried out on the Continuous Survey basis, the various items of machinery are to be opened for survey in rotation, as far as practicable, to ensure that the interval between consecutive examinations of each item will not exceed five years. In general, approximately one-fifth of the machinery is to be examined each year.

3.5.20 If any examination during Continuous Survey reveals defects, further parts are to be opened up and examined as considered necessary by the Surveyor, and the defects are to be made good to his satisfaction.

3.5.21 Upon application by an Owner, the Committee may agree to an arrangement whereby, subject to certain conditions, some items of machinery may be examined by the Chief Engineer of the ship at ports where LR is not represented, or, where practicable, at sea, followed by a limited confirmatory survey carried out at the next port of call where an Exclusive Surveyor is available. Particulars of this arrangement may be obtained from LR's Headquarters. Where an approved planned maintenance scheme is in operation the confirmatory surveys may be held at annual intervals, at which time the records will be checked and the operation of the scheme verified. Particulars of this arrangement may be obtained from any of LR's Offices.

3.5.22 Where condition monitoring equipment is fitted, the Committee, upon application by the Owner, will be prepared to amend applicable Periodical Survey requirements where details of the equipment are submitted and found satisfactory. Where machinery installations are accepted for this method of survey, it will be a requirement that an Annual Survey be held, at which time monitored records will be analyzed and the machinery examined under working conditions. An acceptable lubricating oil trend analysis programme may be required as part of the condition monitoring procedures.

3.5.23 Boiler Surveys, examination of steam pipes and Screwshaft Surveys are to be carried out as stated in Ch 3,15 to 17.

3.5.24 Where any inert gas system is fitted for the protection of cargo tanks on board a ship intended for the carriage of oil or liquid chemicals in bulk, the system is to be surveyed annually in accordance with the requirements of Ch 3,2.2.22. In addition, on ships to which an **IGS** notation has been assigned, a Special Survey of the inert gas plant is to be carried out at intervals not exceeding five years, in accordance with the requirements of Ch 3,18.

3.5.25 Where the ship is fitted with classed dynamic positioning equipment, the system is to be examined annually in accordance with the requirements of Ch 3,2.2.16. In addition, a Special Survey is to be carried out at intervals not exceeding five years in accordance with Ch 3,11.2.9.

# Classification Regulations

## Part 1, Chapter 2

Section 3

3.5.26 Where the ship is fitted with a classed refrigerated cargo installation, the installation is to be surveyed annually in accordance with the requirements of Ch 3,20.1. In addition, a Special Survey is to be carried out at intervals not exceeding five years in accordance with the requirements of Ch 3,20.2. At the request of the Owner, consideration will be given to the Survey of the installation being carried out on the Continuous Survey basis.

3.5.27 Where the ship is fitted with a classed refrigerated cargo installation, a Loading Port Survey, as detailed in Ch 3,20.4, may be carried out at the request of the Owner. On completion, a certificate will be issued recording, in addition to other details, the temperatures in the various refrigerated spaces at the time of the survey. The certificate issued by LR is not in respect of the cargo to be loaded or the manner in which it is to be stowed. A Loading Port Survey is not mandatory for classification, but may be carried out concurrently with the Annual, Continuous or Special Surveys if so desired.

### 3.6 Certificates

3.6.1 When the required reports, on completion of the survey of new or existing ships which have been submitted for classification, have been received from the Surveyors and approved by the Committee, a certificate of First Entry of Classification, signed by the Chairman, or the Deputy Chairman and Chairman of the Sub-Committee of Classification, will be issued to Builders or Owners.

3.6.2 A Certificate of Class valid for five years subject to endorsement for Annual and Intermediate Surveys will also be issued to the Owners.

3.6.3 LR's Surveyors are permitted to issue provisional (interim) certificates to enable a ship classed with LR to proceed on her voyage (or to continue her service in the case of a fixed or tethered ship) provided that in their opinion it is in a fit and efficient condition. Such certificates will embody the Surveyors' recommendations for continuance of class, but in all cases are subject to confirmation by the Committee.

3.6.4 The full class notation and abbreviated descriptive notes shall be stated on the Certificate of Class and provisional (interim) certificate.

### 3.7 Notice of surveys

3.7.1 It is the responsibility of the Owners to ensure that all surveys necessary for the maintenance of class are carried out at the proper time and in accordance with the instructions of the Committee. Information is available to Owners on the ClassDirect Live website.

3.7.2 LR will give timely notice to an Owner about forthcoming surveys by means of a letter or a computer printout of a ship's Quarterly Listing of Surveys, Conditions of Class and Memoranda. The omission of such notice, however, does not absolve the Owner from his responsibility to comply with LR's survey requirements for maintenance of class, all of which are available to Owners on the ClassDirect Live website.

### 3.8 Withdrawal/Suspension of class

3.8.1 When the class of a ship, for which the Regulations as regards surveys on hull, equipment and machinery have been complied with, is withdrawn by the Committee in consequence of a request from the Owner the notation 'Class withdrawn at Owner's request' (with date) will be assigned.

3.8.2 When the Regulations as regards surveys on hull, equipment or machinery have not been complied with and the ship is thereby not entitled to retain class, the class will be suspended or withdrawn, at the discretion of the Committee, and a corresponding notation will be assigned.

3.8.3 Class will be automatically suspended and the Certificate of Class will become invalid if the Annual or Intermediate Survey is not completed within three months of the due date of the survey.

3.8.4 Class will be automatically suspended from the expiry date of the Certificate of Class in the event that the Special Survey has not been completed by the due date and an extension has not been agreed (see 3.5.9), or is not under attendance by the Surveyors with a view to completion prior to resuming trading.

3.8.5 When, in accordance with 3.4.3 of the Regulations, a condition of class is imposed, this will be assigned a due date for completion and the ship's class will be subject to a suspension procedure if the condition of class is not dealt with, or postponed by agreement, by the due date.

3.8.6 When it is found, from the reported condition of the hull or equipment or machinery of a ship, that an Owner has failed to comply with Regulations 1.1.5, 1.1.9, 3.4.1 or 3.4.5, the class will be liable to be suspended or withdrawn, at the discretion of the Committee, and a corresponding notation assigned. When it is considered that an Owner's failure to comply with these requirements is sufficiently serious, the suspension or withdrawal of class may be extended to include other ships controlled by the same Owner, at the discretion of the Committee.

3.8.7 When any ship proceeds to sea with less freeboard than that approved by the Committee, or when the freeboard marks are placed higher on the sides of the ship than the position assigned or approved by the Committee, or, in cases of ships where freeboards are not assigned, the draught is greater than that approved by the Committee, the class will be liable to be withdrawn or suspended.

3.8.8 When it is found that a specialized ship is being operated in a manner contrary to that agreed at the time of classification, or is being operated in environmental conditions which are more onerous or in areas other than those agreed by the Committee, the class will be liable to be automatically withdrawn or suspended.

# Classification Regulations

## Part 1, Chapter 2

Sections 3, 4 &amp; 5

3.8.9 Where a ship has been detained following a Port State Control inspection on two or more occasions in a two year period, with serious deficiencies found, then the class will be liable to be suspended or withdrawn, at the discretion of the Committee, and a corresponding notation will be assigned. In these cases, a period of notice, not exceeding 3 months, may be given prior to any suspension or withdrawal of class.

3.8.10 In all instances of class withdrawal or suspension, the assigned notation, with date of application, will appear in the *Register Book*. In cases where class has been suspended by the Committee and it becomes apparent that the Owners are no longer interested in retaining LR's class, the notation will be amended to withdrawn status. After class withdrawn status has been established in the *Register Book* for one year, it will be automatically amended to 'classed LR until' (with date).

3.8.11 For reclassification and reinstatement of class, see 3.3.2.

### 3.9 Appealing against Surveyors' recommendations

3.9.1 If the recommendations of LR's Surveyors are considered in any case to be unnecessary or unreasonable, an appeal may be made to the Committee, who may direct a Special Examination to be held.

### 3.10 Force majeure

3.10.1 If due to circumstances reasonably beyond the Owner's or LR's control, as defined below, the ship is not in a port when surveys become overdue the Committee may allow the ship to sail, in class, directly to an agreed discharge port and then, if necessary, in ballast to an agreed repair facility at which the survey can be completed. In this context 'Force Majeure' means damage to the ship, unforeseen inability of Surveyors to attend the ship due to governmental restrictions on right of access or movement of personnel, unforeseen delays in port or inability to discharge cargo due to unusually lengthy periods of severe weather, strikes, civil strife, acts of war or other force majeure.

### 3.11 Ownership details

3.11.1 It is the responsibility of each Owner to inform LR in writing of any change to its contact details and in the event of a ship sale to supply details of the new Owners. If the new Owner of a ship cannot be properly identified and the contact details established then the class of that ship will be specially considered by the Committee.

## Section 4 IACS QSCS Audits

### 4.1 Audit of surveys

4.1.1 The surveys required by the Regulations may be subject to audit in accordance with the requirements of the International Association of Classification Societies Quality System Certification Scheme.

## Section 5 Approval/Type Testing/Quality Control System

### 5.1 LR Type Approval – Marine Applications

5.1.1 LR Type Approval is an impartial certification system that provides independent third-party Type Approval Certificates attesting to a product's conformity with specific standards or specifications. It is based on design review and type testing or where testing is not appropriate, a design analysis.

5.1.2 The LR Type Approval System is a process whereby a product is assessed in accordance with a specification, standard or code to check that it meets the stated requirements and through selective testing demonstrates compliance with specific performance requirements. The testing is carried out on a prototype or randomly selected product(s) which are representative of the manufactured product under approval. Thereafter, the producer is required to use Quality Control procedures and processes to ensure that each item delivered is in conformity with that which has been Type Approved.

5.1.3 The selective testing required by 5.1.2 is to include environmental testing applicable to the product's installation on board a ship classed or intended to be classed with LR.

5.1.4 LR Type Approval does not remove the requirements for inspection and survey procedures required by the Rules for equipment to be installed in ships classed or intended to be classed with LR. Also, LR Type Approval does not remove the requirement for plan appraisal of a system that incorporates Type Approved equipment where required by the Rules.

5.1.5 LR Type Approval is subject to the understanding that the producer's recommendations and instructions for the product and any relevant requirements of the Rules for the Classification of Ships are fulfilled.

5.1.6 The producer supplying equipment or components under Quality Control procedures and processes is to have a recognized quality management system certified by an IACS member or Notified Body. The Quality Control procedures and processes are to address the production of the product consistent with 5.3.

# Classification Regulations

# Part 1, Chapter 2

Sections 5 & 6

5.1.7 Where equipment or components have been Type Approved in accordance with specifications and procedures other than LR's, details of the product, certification and testing are to be submitted for consideration where appropriate.

## 5.2 Type testing

5.2.1 Type testing is an impartial process that provides independent third-party verification that an item of machinery or equipment has satisfactorily undergone a functional type test.

5.2.2 Type testing is carried out against defined performance and test standards for a defined period of time with test conditions varying between minimum and maximum declared design conditions.

5.2.3 Type testing is carried out on a prototype or randomly selected product(s) which are representative of the manufactured product under assessment.

5.2.4 After type testing, mechanical equipment is to be opened out and inspected for damage or excessive wear.

5.2.5 On application from the manufacturer, type tests may be waived for equipment and machinery that has been proven to be reliable in marine service and where compliance with the current applicable standards can be demonstrated. Equipment and machinery that has been previously type tested with satisfactory testing evidence and certification need not have the type tests repeated where previous testing is in accordance with current testing standards.

5.2.6 The acceptance of type testing certification is subject to the understanding that the manufacturer's recommendations and instructions for the product and any relevant requirements of the applicable Rules are fulfilled.

## 5.3 Quality Control System

5.3.1 A quality control system for the purposes of LR acceptance of materials and machinery refers to a scheme that covers the operational techniques and activities that is used to demonstrate that the quality requirements for a product are in accordance with declared standards.

5.3.2 The quality control system for a particular product extends to all parties involved in the supply chain from manufacture and testing through to delivery of the product.

5.3.3 LR acceptance of machinery and equipment manufactured under a quality control scheme is dependent on the scheme being maintained through a traceable process involving planned audits and spot inspections at the discretion of LR Surveyors. The purpose of the audits and spot inspections is to ensure that the procedures for manufacture and quality control are being maintained in a satisfactory manner.

5.3.4 The use of a quality control system does not remove the requirements for inspection processes that may be required by the Rules applicable to the equipment being supplied with a manufacturer's certificate. Also the use of a quality control system does not remove the requirement for plan appraisal of equipment or systems where required by the Rules.

## Section 6 Classification of machinery with [X] LMC or MCH notation

### 6.1 General

6.1.1 After delivery of machinery and equipment with the manufacturer's certificate to the shipyard, Survey at the Shipyard and Periodical Surveys are to be in accordance with the requirements for ships built or accepted into class with the [X] LMC notation.

### 6.2 Appraisal and records

6.2.1 To facilitate survey and compilation of classification records, plans and information required for a ship being accepted into class with the [X] LMC notation are to be submitted for appraisal and information. Plans are not required where machinery and equipment has previously been type approved; in these cases it is only necessary to submit details of the machinery and equipment together with details of previous approval.

### 6.3 Survey and inspection

6.3.1 The manufacturer's certificate for acceptance of machinery and equipment for assignment of the [X] LMC or MCH notation is to be in the English language and include the following information:

- Design and manufacturing standard(s) used.
- Materials used for construction of key components and their sources.
- Details of the quality control system applied during design, manufacture and testing and of any software maintenance.
- Details of any type approval or type testing.
- Details of installation and testing recommendations for the machinery or equipment.

The manufacturer is to have a recognized quality management system certified by an IACS member or a Notified Body.

6.3.2 The installation and testing of machinery and equipment at the build yard which has been supplied with a manufacturer's certificate is to be in accordance with the requirements applicable to a ship having the [X] LMC notation.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 1

## Section

- 1 **General**
- 2 **Annual Surveys – Hull and machinery requirements**
- 3 **Intermediate Surveys – Hull and machinery requirements**
- 4 **Docking Surveys and In-water Surveys – Hull and machinery requirements**
- 5 **Special Survey – General – Hull requirements**
- 6 **Special Survey – Bulk carriers – Hull requirements**
- 7 **Special Survey – Oil tankers (including ore/oil ships and ore/bulk/oil ships) – Hull requirements**
- 8 **Special Survey – Chemical tankers – Hull requirements**
- 9 **Ships for liquefied gases**
- 10 **Dredgers, hopper dredgers, sand carriers, hopper barges and reclamation craft**
- 11 **Machinery surveys – General requirements**
- 12 **Turbines and steam engines – Detailed requirements**
- 13 **Oil engines – Detailed requirements**
- 14 **Electrical equipment**
- 15 **Boilers**
- 16 **Steam pipes**
- 17 **Screwshafts, tube shafts and propellers**
- 18 **Inert gas systems**
- 19 **Classification of ships not built under survey**
- 20 **Refrigerated cargo installations**
- 21 **Controlled atmosphere systems**

## ■ Section 1 General

### 1.1 Frequency of surveys

1.1.1 The requirements of this Chapter are applicable to the Periodical Surveys set out in Ch 2,3.5. Except as amended at the discretion of the Committee, the periods between such surveys are as follows:

- (a) Annual Surveys, as required by Ch 2,3.5.1.
- (b) Intermediate Surveys, as required by Ch 2,3.5.2.
- (c) Docking Surveys, as required by Ch 2,3.5.3 and 3.5.4.
- (d) When ships classed **100A1 shipborne barge** are subjected to Intermediate Surveys, those surveys become due 30 months after the previous Special Survey, see Ch 2,3.5.7.
- (e) Special Surveys at five-yearly intervals, see Ch 2,3.5.9. For alternative arrangements, see *also* Ch 2,3.5.10, 3.5.11, 3.5.12 and 3.5.14.
- (f) Complete Surveys of machinery at five-yearly intervals, see Ch 2,3.5.16.

1.1.2 When it has been agreed that the complete survey of the hull and machinery may be carried out on the Continuous Survey basis, all compartments of the hull and all items of machinery are to be opened for survey in rotation to ensure that the interval between consecutive examinations of each part will not exceed five years, see Ch 2,3.5.14 and 3.5.19.

1.1.3 For the frequency of surveys of boilers, steam pipes, screwshafts, tube shafts, propellers and inert gas systems, see Sections 15 to 18.

1.1.4 For the requirements for surveys of refrigerated cargo installations, see Pt 6, Ch 3.

### 1.2 Surveys for damage or alterations

1.2.1 At any time when a ship is undergoing alterations or damage repairs, any exposed parts of the structure normally difficult to access are to be specially examined, e.g. if any part of the main or auxiliary machinery, including boilers, insulation or fittings, is removed for any reason, the steel structure in way is to be carefully examined by the Surveyor, or when cement in the bottom or covering on decks is removed, the plating in way is to be examined before the cement or covering is relaid.

### 1.3 Unscheduled surveys

1.3.1 In the event that Lloyd's Register (hereinafter referred to as LR) has cause to believe that its Rules and Regulations are not being complied with, LR reserves the right to perform unscheduled surveys of the hull or machinery.

1.3.2 In the event of significant damage or defect affecting any ship, LR serves the right to perform unscheduled surveys of the hull or machinery of other similar ships classed by LR and deemed to be vulnerable.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 1

## 1.4 Surveys for the issue of Convention certificates

1.4.1 Surveys are to be held by LR when so appointed, or by the Exclusive Surveyors to a National Administration or by an IACS Member when so authorized by the National Authority, or, in the case of Cargo Ship Safety Radio Certificates or Safety Management Certificates, by any organization authorized by the National Authority. In the case of dual classed ships, Convention Certificates may be issued by the other Society with which the ship is classed provided this is recognized in a formal Dual Class Agreement with LR and provided the other Society is also authorized by the National Authority.

## 1.5 Definitions

1.5.1 An **Oil Tanker** is a sea going self-propelled ship which is constructed generally with integral tanks and is intended primarily to carry oil in bulk and includes ship types such as combination carriers (ore/oil and ore/bulk/oil ships, etc.). Where referred to in this Chapter, it shall also include double hull oil tankers as well as tankers with alternative structural arrangements, e.g. mid-deck designs, except where specified.

1.5.2 A **Double Hull Oil Tanker** is a sea going self-propelled ship which is constructed primarily for the carriage of oil in bulk, where the cargo tanks are protected by a double hull extending for the entire length of the cargo area, consisting of double side and double bottom spaces for the carriage of salt-water ballast.

1.5.3 A **Bulk Carrier** is a sea going self-propelled ship which is constructed generally with single deck, double bottom, topside tanks and hopper side tanks and with single side skin construction in the cargo length area, and is intended primarily to carry dry cargo in bulk and includes ship types such as ore carriers. Where referred to in this Chapter, it shall also include double skin bulk carriers except where specified.

1.5.4 A **Double Skin Bulk Carrier** is a sea going self-propelled ship which is constructed generally with single deck, double bottom, topside tanks and hopper side tanks and with double side skin construction in the cargo length area (regardless of the width of the wing space), and is intended primarily to carry dry cargo in bulk and includes such types as ore carriers.

1.5.5 An **Ore Carrier** is a sea going self-propelled ship which is constructed generally with single deck, two longitudinal bulkheads and a double bottom throughout the cargo length area and intended primarily to carry ore cargoes in the centre holds only.

1.5.6 A **Chemical Tanker** is a sea going self-propelled ship constructed generally with integral tanks and being single or double hull construction, or having alternative structural arrangements, used primarily for the carriage in bulk of any liquid product listed in Chapter 17 of the *International Code for the Construction and Equipment of Ships Carrying Dangerous Chemicals in Bulk, IBC Code*.

1.5.7 A **Gas Carrier** is a cargo ship constructed or adapted and used for the carriage in bulk of any liquefied gas or other products of flammable nature listed in Chapter 19 of the *International Code for the Construction and Equipment of Ships Carrying Liquefied Gases in Bulk*.

1.5.8 A **Ballast Tank** is a tank which is used solely for the carriage of salt-water ballast. For bulk carriers, a space which is used for both cargo and salt-water ballast will be treated as a salt-water ballast tank when substantial corrosion has been found in that space. For double skin bulk carriers, the double side tank is to be considered as a separate tank even if it is connected to either the topside or hopper side tank. For oil tankers and chemical tankers, a combined tank which is used for both cargo and salt-water ballast as a routine part of the ship's operation will be treated as a ballast tank. A cargo tank which in exceptional cases may carry salt-water ballast during severe weather conditions and is not designated as a combined cargo/ballast tank will be treated as a cargo tank.

1.5.9 **Spaces** are separate compartments such as holds and tanks.

1.5.10 An **Overall Survey** is a survey intended to report on the overall condition of the hull structure and to determine the extent of additional Close-up Surveys.

1.5.11 A **Close-up Survey** is a survey where the details of structural components are within the close visual inspection range of the Surveyor, i.e. normally within reach of hand.

1.5.12 A **Transverse Section** includes all longitudinal members such as plating, longitudinals and girders at the deck, side, bottom, inner bottom, inner side, hopper side, top wing side and longitudinal bulkhead, where fitted. For transversely framed ships, a transverse section includes adjacent frames and their end connections in way of transverse sections.

1.5.13 **Representative Spaces** are those which are expected to reflect the condition of other spaces of similar type and service and with similar corrosion prevention systems. When selecting representative spaces, account is to be taken of the service and repair history on board and identifiable Critical Structural Areas.

1.5.14 **Critical Structural Areas** are locations which have been identified from calculations to require monitoring or from the service history of the subject ship or from similar ships or sister ships, if applicable, to be sensitive to cracking, buckling or corrosion which would impair the structural integrity of the ship.

1.5.15 **Substantial Corrosion** is wastage of individual plates and stiffeners in excess of 75 per cent of allowable margins, but within acceptable limits. For ships built in accordance with the Common Structural Rules (CSR), substantial corrosion is as an extension of corrosion such that the assessment of the corrosion pattern indicates a gauged (or measured) thickness between  $t_{\text{net}} + 0,5 \text{ mm}$  and  $t_{\text{net}}$ .

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 1

**1.5.16 A Corrosion Prevention System** is normally considered a full hard protective coating. This is usually to be an epoxy coating or equivalent. Other systems (e.g. soft coatings) may be considered acceptable as alternatives provided they are applied and properly maintained in compliance with the manufacturer's specification.

**1.5.17** For the application of requirements outlined in Sections 2, 3, 4 and 5, a general dry cargo ship is a self-propelled ship of 500 gross tonnes or above, constructed generally with a 'tween deck and intended to carry solid cargoes. This excludes bulk carriers, refrigerated cargo ships, roll on-roll off ships, livestock carriers, dock/deck ships and ships dedicated for the carriage of containers, forest products (but not log or timber carriers), wood chips and cement.

**1.5.18 Coating Condition** is defined as follows:

- GOOD** condition with only minor spot rusting affecting not more than 20 per cent of areas under consideration, e.g. on a deck transverse, side transverse, on the total area of platings and stiffeners on the longitudinal structure between these components, etc.
- FAIR** condition with local breakdown at edges of stiffeners and weld connections and/or light rusting affecting 20 per cent or more of areas under consideration.
- POOR** condition with general breakdown of coating affecting 20 per cent or more of areas under consideration or hard scale affecting 10 per cent or more of area under consideration.

**1.5.19 A Prompt and Thorough Repair** is a permanent repair completed at the time of survey to the satisfaction of the Surveyor, therein removing the need for the imposition of any associated condition of class.

**1.5.20** Bulk carriers with hybrid cargo hold arrangements are to have single skin cargo holds surveyed in accordance with the requirements for single skin bulk carriers and the double skin cargo holds surveyed in accordance with the requirements for double skin bulk carriers.

**1.5.21 Special consideration or specially considered** (in connection with close-up surveys and thickness measurements) means sufficient close-up inspection and thickness measurements are to be taken to confirm the actual average condition of the structure under the coating.

**1.5.22 Air pipe heads** installed on the exposed decks are those extending above the freeboard deck or superstructure decks.

**1.5.23** The **Cargo Area** or **Cargo Length Area** is that part of the ship which contains all cargo holds and adjacent areas including fuel tanks, cofferdams, ballast tanks and void spaces. For oil tankers and chemical tankers, the **Cargo Area** is that part of the ship which contains cargo tanks, slop tanks and cargo/ballast pump-rooms, cofferdams, ballast tanks and void spaces adjacent to cargo tanks and also deck areas throughout the entire length and breadth of the part of the ship over the above mentioned spaces.

## 1.6 Preparation for survey and means of access

**1.6.1** Tanks and spaces are to be safe for access, i.e. gas freed, ventilated and illuminated.

**1.6.2** In preparation for survey, thickness measurements and to allow for a thorough examination, all spaces are to be cleaned including removal from surfaces of all loose accumulated corrosion scale. Spaces are to be sufficiently clean and free from water, scale, dirt, oil residues, etc., to reveal corrosion, deformation, fractures, damages or other structural deterioration. However, those areas of structure whose renewal has already been decided by the owner need only be cleaned and descaled to the extent necessary to determine the limits of renewed areas.

**1.6.3** Sufficient illumination is to be provided to reveal corrosion, deformation, fractures, damages or other structural deterioration.

**1.6.4** Means are to be provided to enable the Surveyor to examine the structure in a safe and practical way.

**1.6.5** For surveys, including close-up survey where applicable, in cargo spaces and ballast tanks, one or more of the following means of access, is to be provided: ss is to be provided:

- (a) Permanent staging and passages through structures.
- (b) Temporary staging and passages through structures.
- (c) Lifts and movable platforms.
- (d) Boats or rafts.
- (e) Other equivalent means.

Portable ladders may be used, at the discretion of the Surveyor, for survey of the hull structure of single skin bulk carriers, except for the close-up survey of cargo hold shell frames, see 1.6.6 and 1.6.7.

**1.6.6** For close-up surveys of the cargo hold shell frames of single skin bulk carriers with a deadweight less than 100,000 tonnes, one or more of the following means of access is to be provided:

- (a) Permanent staging and passages through structures.
- (b) Temporary staging and passages through structures.
- (c) Portable ladder restricted to not more than 5 m in length may be accepted for surveys of the lower section of a shell frame including bracket.
- (d) Hydraulic arm vehicles such as conventional cherry pickers, lifts and movable platforms.
- (e) Boats or rafts, provided the structural capacity of the hold is sufficient to withstand static loads at all levels of water.
- (f) Other equivalent means.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 1

1.6.7 For close-up surveys of the cargo hold shell frames of single skin bulk carriers with a deadweight equal to or greater than 100,000 tonnes the use of portable ladders is not accepted and one or more of the following means of access, is to be provided:

- (a) At Annual Surveys, Intermediate Surveys held before the ship is 10 years old and Special Survey I:
  - (i) Permanent staging and passages through structures.
  - (ii) Temporary staging and passages through structures.
  - (iii) Hydraulic arm vehicles such as conventional cherry pickers, lifts and movable platforms.
  - (iv) Boats or rafts, provided the structural capacity of the hold is sufficient to withstand static loads at all levels of water.
  - (v) Other equivalent means.
- (b) At Special Survey II and all subsequent surveys:
  - (i) Either permanent or temporary staging and passage through structures for close-up survey of at least the upper part of hold frames.
  - (ii) Hydraulic arm vehicles such as conventional cherry pickers for surveys of lower and middle part of shell frames as alternative to staging.
  - (iii) Lifts and movable platforms.
  - (iv) Boats or rafts, provided the structural capacity of the hold is sufficient to withstand static loads at all levels of water.
  - (v) Other equivalent means.
- (c) Notwithstanding the above requirements, for single skin bulk carriers greater than 10 years old, at Annual Survey the use of a portable ladder fitted with a mechanical device to secure the upper end of the ladder is acceptable for the close-up survey of cargo hold shell frames.

1.6.8 Survey at sea or anchorage may be undertaken when the Surveyor is fully satisfied with the necessary assistance from the personnel onboard and provided the following conditions and limitations are met:

- (a) Surveys of tanks by means of boats or rafts is at the sole discretion of the attending Surveyor, who is to take into account the safety arrangements provided, including weather forecasting and ship response under foreseeable sea conditions and provided the expected rise of water within the tank does not exceed 0,25 m. Appropriate life jackets are to be available for all participants. The boats or rafts are to have satisfactory residual buoyancy and stability even if one chamber is ruptured. A safety checklist is also to be provided. An oxygen-meter, breathing apparatus, lifeline and whistles are to be at hand during the survey. For oil tankers and chemical tankers, an explosimeter is also to be provided.
- (b) A communication system is to be arranged between the survey party in the tank and the responsible officer on deck. This system must include the personnel in charge of ballast pump handling if boats or rafts are to be used.
- (c) Rafts or boats may be permitted for the survey of the under deck areas of tanks or spaces, if the depth of the under deck web plating is 1,5 m or less. If the depth of the under deck web plating is greater than 1,5 m, then rafts or boats may be permitted only when the coating of the under deck structure is in GOOD condition and there is no evidence of wastage or if a permanent means of access is provided in each bay to allow safe entry and

exit. A permanent means of access is considered to mean:

- (i) Access direct from the deck via a vertical ladder and a small platform fitted approximately 2 m below the deck in each bay or,
- (ii) Access to deck from a longitudinal permanent platform having ladders to the deck at each end of the tank. The platform shall be arranged over the full length of the tank and level with, or above, the maximum water level needed for rafting of the under deck structure. For this purpose, the ullage corresponding to the maximum water level is to be assumed not more than 3 m from the deck plate measured at the midspan of deck transverses and at the mid point of the tank's length.

If neither of the above conditions are met, then staging or another equivalent means is to be provided for the survey of the under deck areas.

1.6.9 Where soft coatings have been applied, safe access is to be provided for the Surveyor to verify the effectiveness of the coating and to carry out an assessment of the conditions of internal structures which may include spot removal of the coating. When safe access cannot be provided, the soft coating is to be removed.

1.6.10 A survey planning meeting is to be held prior to the commencement of Intermediate Survey and Special Survey.

1.6.11 For ships assigned the quotation **ESP**, the owner is to respond to a Survey Planning Questionnaire and to prepare a Survey Programme, see 6.3, 7.3 and 8.3.

- (a) The Survey Planning Questionnaire is to be submitted to LR prior to the preparation of the Survey Programme. This is to include information on access provisions for close-up Surveys and thickness measurements; cargo history; the results of inspections carried out by the Owner; a list of reports of Port State Control Inspection containing hull structural deficiencies; a list of Safety Management System non-conformities related to hull maintenance and details of the thickness measurement company.
- (b) The Survey Programme is to be submitted prior to the commencement of any part of the Intermediate Survey on ships over 10 years of age and Special Survey. This is to be in a written format and submitted to LR at least six months in advance of the survey. The Survey Programme at Intermediate Survey may consist of the Survey Programme agreed for the previous Special Survey supplemented by the Executive Hull Summary of that Special Survey and later relevant survey reports. The survey programme is to be worked out taking into account any amendments to the survey requirements implemented after the previous Special Survey.

## 1.7 Thickness measurement at surveys

1.7.1 This Section is applicable to the thickness measurement of the hull structure where required by Sections 2, 3, 5, 6, 7, 8 and 9.



# Periodical Survey Regulations

## Part 1, Chapter 3

Sections 1 &amp; 2

1.7.2 Further to the requirements of 1.6.8 a survey planning meeting is to be held between the attending Surveyor(s), the Owner's representative and the thickness measurement firm's representative, so as to ensure the safe and efficient execution of the surveys and thickness measurements to be carried out on board.

1.7.3 For non-ESP ships less than 500 gross tons and all fishing vessels, the designated Surveyor, who has received training and been qualified by LR, may carry out thickness measurements. The Owner is to respond to a Survey Planning Questionnaire and to prepare a Survey Programme, see 6.3, 7.3 and 8.3.

1.7.4 Thickness measurements are normally to be taken by means of ultrasonic test equipment and are to be carried out by a firm approved in accordance with Lloyd's Register's *Approval for Thickness Measurement of Hull Structure*.

1.7.5 The Surveyor may require to measure the thickness of the material in any portion of the structure where signs of wastage are evident or wastage is normally found. Any parts of the structure which are found defective or excessively reduced in scantlings are to be made good by materials of the approved scantlings and quality. Attention is to be given to the structure in way of discontinuities. If a corrosion control (cc) notation, as defined in the *Register Book*, is assigned, surfaces are to be re-coated as necessary.

1.7.6 Thickness measurements are to be witnessed by the Surveyor. This requires the Surveyor is to be on board, while the measurements are carried out, to the extent necessary to control the process. This also applies to thickness measurements carried out while the ship is at sea.

1.7.7 The Surveyor may extend the scope of thickness measurement if deemed necessary.

1.7.8 Where it is required as part of the survey to carry out thickness measurements for the structural areas subject to Close-up Survey, then these measurements are to be carried out simultaneously with the Close-up Survey.

1.7.9 Thickness measurements are to be taken in the forward and aft areas of all plates. Where plates cross ballast/cargo tank boundaries separate measurements for the area of plating in way of each type of tank are to be reported. In all cases the measurements are to represent the average of multiple measurements taken on each plate and/or stiffener. Where measured plates are renewed, the thicknesses of adjacent plates in the same strake are to be reported.

1.7.10 A report is to be prepared by the approved firm or surveyor carrying out the thickness measurements. The report is to give the location of measurement, the thickness measured as well as the corresponding original thickness. The report is to give the date when measurement was carried out, the type of measuring equipment, names of personnel and their qualifications and is to be signed by the operator.

1.7.11 The thickness measurement report is to be verified and signed by the Surveyor and countersigned by an authorising Surveyor.

### 1.8 Repairs

1.8.1 Any damage in association with wastage over the allowable limit (including buckling, grooving, detachment or fracture), or extensive areas of wastage over the allowable limits, which affects or, in the opinion of the Surveyor, will affect the ship's structural, watertight or weathertight integrity, is to be promptly and thoroughly repaired. Areas to be considered include, (where fitted):

- side shell frames, their end attachments and adjacent shell plating;
- deck structure and deck plating;
- bottom structure and bottom plating;
- side structure and side plating;
- inner bottom structure and inner bottom plating;
- inner side structure and inner side plating;
- watertight or oiltight bulkheads;
- hatch covers and hatch coamings.

For locations where adequate repair facilities are not available, consideration may be given to allow the ship to proceed directly to a repair facility. This may require discharging the cargo and/or temporary repairs for the intended voyage.

1.8.2 Additionally, when a survey results in the identification of structural defects or corrosion, either of which, in the opinion of the Surveyor, will impair the ship's fitness for continued service, remedial measures are to be implemented before the ship continues in service.

## Section 2 Annual Surveys – Hull and machinery requirements

### 2.1 General

2.1.1 Annual Surveys are to be held concurrently with statutory annual or other relevant statutory surveys, wherever practicable.

2.1.2 At Annual Surveys, the Surveyor is to examine the ship and machinery, so far as necessary and practicable, in order to be satisfied as to their general condition.

2.1.3 For additional requirements for ships for liquefied gases, see Section 9.

2.1.4 For ships which are required by International Convention to comply with the International Safety Management Code (ISM Code), the Surveyor is to review the overall effectiveness of the Code onboard ship. This is to be undertaken regardless of the organisation issuing the Safety Management Certificate (SMC).

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 2

## 2.2 Annual Surveys

2.2.1 The Surveyor is to be satisfied regarding:

- (a) The efficient condition of hatchways on freeboard and superstructure decks, weather deck plating, ship side plating above the waterline, ventilator coamings and air pipes, exposed casings, fiddley openings, skylights, flush deck scuttles, deckhouses and companionways, superstructure bulkheads, side, bow and stern doors, side scuttles and deadlights, chutes and other openings, together with all closing appliances and flame screens. In addition, the Surveyor is to externally examine all air pipe heads installed on exposed decks and examine the weld connection between air pipes and deck plating.
- (b) The efficient operating condition of mechanically-operated hatch covers including stowage and securing in open condition; proper fit and efficiency of sealing in closed condition; operational testing of hydraulic and power components, wires, chains and link drives.
- (c) The efficient condition of scuppers and sanitary discharges (so far as practicable); valves on discharge lines (so far as practicable) and their controls; guard rails and bulwarks; freeing ports, gangways and life-lines; fittings and appliances for timber deck cargoes.
- (d) The efficient condition of bilge level detection and alarm systems on ships assigned a **UMS** notation.

2.2.2 The Surveyor is to obtain confirmation that no unapproved changes have been made to the hatch covers, hatch coamings and their securing and sealing devices since the previous survey:

- (a) Mechanically-operated steel covers are to be tested to confirm the satisfactory condition of:
  - hatch covers;
  - tightness devices of longitudinal, transverse and intermediate cross junctions (gaskets, gasket lips, compression bars, drainage channels);
  - clamping devices, retaining bars, cleating;
  - chain or rope pulleys;
  - guides;
  - guide rails and track wheels;
  - stoppers, etc;
  - wires, chains, gypsies, tensioning devices;
  - hydraulic system essential to closing and securing;
  - safety locks and retaining devices.
- (b) Cargo hatch covers of the portable type (i.e. wood or steel pontoons) are to be examined to confirm the satisfactory condition where applicable, of:
  - wooden covers and portable beams, carriers or sockets for the portable beam, and their securing devices;
  - steel pontoons;
  - tarpaulins;
  - cleats, battens and wedges;
  - hatch securing bars and their securing devices;
  - loading pads/bars and the side plate edge;
  - guide plates and chocks;
  - compression bars, drainage channels and drain pipes (if any).
- (c) The Surveyor is to confirm the satisfactory condition of hatch coaming plating and their stiffeners, where applicable.

- (d) For **general dry cargo ships** and **bulk carriers**, in addition to the above, the steel cargo hatch covers, coamings and stiffeners are to be subjected to a close-up examination.

2.2.3 The Surveyor is to confirm that, where required, an approved loading instrument together with its operation manual is available on board, see Pt 3, Ch 4.8. The operation of the loading instrument is to be verified in accordance with LR's certification procedure.

2.2.4 The anchoring and mooring equipment is to be examined so far as practicable.

2.2.5 The watertight doors in watertight bulkheads, their indicators and alarms, are to be examined and tested (locally and remotely), together with an examination of watertight bulkhead penetrations, so far as practicable.

2.2.6 The Surveyor is to examine and test in operation all main and auxiliary steering arrangements including their associated equipment and control systems, and verify that log book entries have been made in accordance with statutory requirements where applicable.

2.2.7 The Surveyor is to be satisfied regarding the free-board marks on the ship's side.

2.2.8 The Surveyor is to generally inspect the machinery and boiler spaces, with particular attention being given to the propulsion system, auxiliary machinery and to the existence of any fire and explosion hazards. Emergency escape routes are to be checked to ensure that they are free of obstruction.

2.2.9 The means of communication between the navigating bridge and the machinery control positions, as well as the bridge and the alternative steering position, if fitted, are to be tested.

2.2.10 The bilge pumping systems and bilge wells, including operation of extended spindles and level alarms, where fitted, are to be examined so far as practicable. Satisfactory operation of the bilge pumps is to be proven.

2.2.11 Piping systems containing oil fuel, lubricating oil or other flammable liquids are to be generally examined and operated as far as practicable, with particular attention being paid to tightness, fire precaution arrangements, flexible hoses and sounding arrangements.

2.2.12 The Surveyor is to be satisfied regarding the condition of non-metallic joints in piping systems which penetrate the hull, where both the penetration and the non-metallic joint are below the deepest load waterline.

2.2.13 The boilers, other pressure vessels and their appurtenances, including safety devices, foundations, controls, relieving gear, high pressure and waste steam piping, insulation and gauges, are to be generally examined. Surveyors should confirm that Periodical Surveys of boilers and other pressure vessels have been carried out as required by the Rules and that the safety devices have been tested.

# Periodical Survey Regulations

## Part 1, Chapter 3

### Section 2

2.2.14 The electrical equipment and cabling forming the main and emergency electrical installations are to be generally examined under operating conditions so far as practicable. The satisfactory operation of the main and emergency sources of power and electrical services essential for safety in an emergency is to be verified; where the sources of power are automatically controlled they should be tested in the automatic mode. Bonding straps for the control of static electricity and earthing arrangements are to be examined where fitted.

2.2.15 The electrical installation in areas which may contain flammable gas or vapour and/or combustible dust is to be examined in order to verify that it is in good condition and has been properly maintained.

2.2.16 For ships having **UMS** or **CCS** notation, a General Examination of automation equipment is to be carried out. Satisfactory operation of safety devices and control systems is to be verified.

2.2.17 For ships fitted with a classed dynamic positioning system and/or classed thruster assisted positional mooring system, the control system and associated machinery items are to be generally examined and tested under operating conditions to an approved Test Schedule.

2.2.18 For ships fitted with positional mooring equipment in accordance with Pt 7, Ch 8, a schedule or rota of moorings to be examined at Annual Survey should be agreed for component parts of the positional moorings.

2.2.19 For ships to which Pt 6, Ch 4 applies, the arrangements for fire protection, detection and extinction are to be examined and are to include:

- (a) Verification, so far as practicable, that no significant changes have been made to the arrangement of structural fire protection.
- (b) Verification of the operation of manual and/or automatic doors where fitted.
- (c) Verification that fire-control plans are properly posted.
- (d) Examination, so far as possible, and testing as feasible, of the fire and/or smoke detection and alarm system(s).
- (e) Examination of fire main system, and confirmation that each fire pump, including the emergency fire pump can be operated separately so that the two required powerful jets of water can be produced simultaneously from different hydrants.
- (f) Verification that fire-hoses, nozzles, applicators and spanners are in good working condition and situated at their respective locations.
- (g) Examination of fixed fire-fighting systems controls, piping, instructions and marking, checking for evidence of proper maintenance and servicing, including date of last systems tests.
- (h) Verification that all portable and semi-portable fire-extinguishers are in their stowed positions, checking for evidence of proper maintenance and servicing, conducting random checks for evidence of discharged containers.
- (j) Verification, so far as practicable, that the remote control for stopping fans and machinery and shutting-off fuel supplies in machinery spaces and, where fitted, the remote controls for stopping fans in accommodation spaces and the means of cutting off power to the galley are in good working order.

- (k) Examination of the closing arrangements of ventilators, funnel annular spaces, skylights, doorways and tunnels, where applicable.
- (l) Verification that the firemen's outfits are complete and in good condition.

2.2.20 The requirements of 3.2.4, 3.2.5, 5.3.3 and 5.3.4 regarding the survey of water ballast spaces are also to be complied with as applicable.

2.2.21 The Surveyor is to carry out an examination and thickness measurement of structure identified at the previous Special Survey or Intermediate Survey as having substantial corrosion, as defined in 1.5. This requirement does not apply to cargo tanks of oil tankers and chemical tankers. The extent of thickness measurements is to be increased in accordance with the appropriate tables in Sections 5, 6, 7 or 8, as applicable, to determine the full extent of the corrosion pattern. The survey will not be considered complete until these additional thickness measurements have been carried out.

2.2.22 For **oil tankers** (including ore/bulk/oil ships and ore/oil ships), in addition to the applicable requirements of 2.2.1 to 2.2.21, the following are to be dealt with where applicable:

- (a) Examination of cargo tank openings including gaskets, covers, coamings and screens.
- (b) Examination of cargo tank venting arrangements including secondary means of venting, or over/under pressure alarms where fitted, with associated pressure/vacuum valves and flame screens.
- (c) Examination of flame screens on vents to all bunker, oily ballast and oily slop tanks and void spaces, so far as practicable.
- (d) Examination of cargo, crude oil washing, bunker, ballast and vent piping systems together with flame arrestors and pressure/vacuum valves, as applicable above the upper deck within the cargo tank area, including vent masts and headers.
- (e) Verification that no potential sources of ignition such as loose gear, excessive products in the bilges, excessive vapours, combustible materials, etc., are present in or near the cargo pump room and that access ladders are in good condition.
- (f) Examination of cargo pump rooms and pipe tunnels (where fitted) and examination of all pump room bulkheads for signs of leakage or fractures and, in particular, the sealing arrangements of all penetrations in these bulkheads.
- (g) Verification that the pump room ventilation system is operational, ducting intact, dampers operational and screens are clean.
- (h) For ships to which Pt 6, Ch 4 applies, the external examination of the piping and cut-out valves of cargo tank and cargo pump room fixed fire-fighting system.
- (j) For ships to which Pt 6, Ch 4 applies, verification that the deck foam system and deck sprinkler system are in good operating condition.
- (k) Examination of the condition of all piping systems in the cargo pump room so far as practicable.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 2

- (l) Examination, so far as practicable, of cargo, bilge, ballast and stripping pumps for excessive gland seal leakage, verification of proper operation of electrical and mechanical remote operating and shutdown devices and operation of pump room bilge system, and checking that pump foundations are intact.
- (m) Verification that installed pressure gauges on cargo discharge lines and level indicator systems are operational.
- (n) Verification that at least one portable instrument for measuring flammable vapour concentrations is available, together with a sufficient set of spares and a suitable means of calibration.
- (o) Examination of any inert gas system, see 2.2.24.
- (p) For single hull oil tankers, ballast tanks adjacent to (i.e. with a common plane boundary) a cargo tank with any means of heating are to be examined. Thickness measurement is to be carried out where considered necessary by the Surveyor. Special consideration may be given by the Surveyor to those tanks where the coatings was found in GOOD condition, as defined in 1.5, at the previous Intermediate or Special Survey.
- (q) For ballast tanks, in areas where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out in accordance with Tables 3.7.7 to 3.7.15, as applicable. The survey will not be considered complete until these additional thickness measurements have been carried out.
- (r) Verification that any special arrangements made for bow or stern loading and unloading are in good condition.

2.2.23 For **chemical tankers**, in addition to the applicable requirements of 2.2.1 to 2.2.22, the following are to be dealt with, where applicable:

- (a) Examination of gauging devices, high level alarms and valves associated with overflow control.
- (b) Verification that any devices provided for measuring the temperature of the cargo and any associated alarms are satisfactory.
- (c) Examination of the cargo heating/cooling system sampling arrangements where fitted.
- (d) Verification that wheelhouse doors and windows, side scuttles and windows in superstructure and deckhouse ends facing the cargo area are in good condition.
- (e) Verification that pump discharge pressure gauges fitted outside the cargo pump rooms are satisfactory.
- (f) Verification that pumps, valves and pipelines are identified and distinctively marked.
- (g) Verification that the remote operation of the cargo pump room bilge system is satisfactory.
- (h) Verification that cargo pump room rescue arrangements are in order.
- (i) Verification that removable pipe lengths or other approved equipment necessary for cargo separation are available, and satisfactory.
- (k) Verification that the ventilation system including portable equipment, if any, of all spaces in the cargo area is operational.
- (l) Verification that arrangements are made for sufficient inert/padding/drying gas to be carried to compensate for normal losses and that means are provided for monitoring of ullage spaces.

- (m) Verification that arrangements are made for sufficient medium to be carried where drying agents are used on air inlets to cargo tanks.
- (n) Verification that suitable protective clothing is available for crew engaged in loading and discharging operations and that suitable storage is maintained.
- (o) Verification that the requisite safety equipment and associated breathing apparatus with requisite air supplies and emergency escape respiratory and eye protection, if required, are in good condition and are properly stowed.
- (p) Verification that medical first aid equipment including stretchers and oxygen resuscitation is in good condition and that satisfactory arrangements are made for antidotes for cargoes actually carried to be on board.
- (q) Verification that decontamination arrangements are operational.
- (r) Verification that the requisite gas detection instruments are on board and that satisfactory arrangements are made for the supply of any required vapour detection tubes.
- (s) Verification that the cargo sample stowage arrangements are in good condition.
- (t) Verification that, if applicable, the provisions made for chemicals which have special requirements listed in Chapter 17 of the *Rules for Ships for Liquid Chemicals* are in order.
- (u) For ballast tanks, in areas where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out in accordance with Tables 3.8.4, 3.8.5, 3.8.6 and 3.8.7. The survey will not be considered complete until these additional thickness measurements have been carried out.

2.2.24 For **inert gas systems**, where fitted, the following are to be dealt with:

- (a) External examination of the condition of piping including vent piping above the upper deck in the cargo tank area and overboard discharges through the shell so far as practicable, together with components for signs of corrosion or gas leakage/effluent leakage.
- (b) Verification of the proper operation of both inert gas blowers.
- (c) Checking the scrubber room ventilation system.
- (d) Checking, so far as practicable, of the deck water seal for automatic filling and draining and checking for presence of water carry-over. Checking the operation of the non-return valve.
- (e) Testing of all remotely operated or automatically controlled valves including the flue gas isolating valve(s).
- (f) Checking the interlocking features of soot blowers.
- (g) Checking that the gas pressure regulating valve automatically closes when the inert gas blowers are secured.
- (h) Checking, so far as practicable, the following alarms and safety devices of the inert gas system using simulated conditions where necessary:
  - (i) high oxygen content of gas in the inert gas main;
  - (ii) low gas pressure in the inert gas main;
  - (iii) low pressure in the supply to the deck water seal;
  - (iv) high temperature of gas in the inert gas main;
  - (v) low water pressure to the scrubber;
  - (vi) accuracy of portable and fixed oxygen measuring equipment by means of calibration gas.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 2

2.2.25 For **bulk carriers**, in addition to the applicable requirements of 2.2.1 to 2.2.21, the following are to be dealt with, where applicable:

- (a) Examination of cargo holds in accordance with Table 3.2.1 is required.
- (b) Where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out in accordance with Tables 3.6.4, 3.6.5, 3.6.6, 3.6.7, 3.6.8 and 3.6.9. The survey will not be considered complete until these additional thickness measurements have been carried out.
- (c) For ships fitted with water level detectors in cargo holds, ballast tanks forward of the collision bulkhead and any dry or void space which extends forward of the foremost cargo hold, an examination and a test, at random, of the water ingress detection systems and of their alarms is to be carried out.
- (d) For ships fitted with a means for draining and pumping ballast tanks forward of the collision bulkhead and the bilges of dry spaces, any part of which extends forward of the foremost cargo hold, an examination and a test of the draining and pumping systems, including their controls, is to be carried out.

2.2.26 For **general dry cargo ships**, in addition to the applicable requirements of 2.2.1 to 2.2.21, the following are required for ships over 10 years of age:

- (a) Overall survey of one forward and one after cargo hold and their associated 'tween deck spaces.
- (b) Where considered necessary by the Surveyor, thickness measurement is to be carried out. Where the results of thickness measurement indicate substantial corrosion, the extent of thickness measurement should be in accordance with Section 5, Table 3.5.6. The survey will not be considered complete until these additional thickness measurements have been carried out.

2.2.27 For **general dry cargo ships**, in addition to the applicable requirements of 2.2.1 to 2.2.21, the following are required for ships over 15 years of age:

- (a) Overall survey of all cargo holds and 'tween deck spaces.
- (b) Close-up Survey of at least 25 per cent of shell frames, including their end attachments and adjacent shell plating in a forward lower cargo hold and one other selected lower cargo hold. Close-up Survey is to include the lower one third length of the shell frames.
- (c) Where the survey reveals the need for remedial measures, then the survey is to be extended to include the Close-up Survey of all shell frames and adjacent shell plating in those cargo holds and associated 'tween deck spaces, as well as a Close-up Survey of sufficient extent of all remaining cargo holds and 'tween deck spaces.
- (d) Where the protective coatings in cargo holds are found in GOOD condition, as defined in 1.5, the extent of Close-up Survey may be specially considered.
- (e) Where considered necessary by the Surveyor, thickness measurement is to be carried out. Where the results of thickness measurement indicate substantial corrosion, the extent of thickness measurement should be in accordance with Table 3.5.6 in Section 5. The survey will not be considered complete until these additional thickness measurements have been carried out.

2.2.28 For **ship-borne barges** where surveys are permitted in accordance with Pt 1, Ch 2,3.5.7, see Section 3.

**Table 3.2.1 Bulk Carriers – Annual Surveys**

Ships less than 10 years old	Ships between 10 and 15 years old	Ships greater than 15 years old
An Overall Survey of the forward cargo hold and an aft cargo hold on single skin ships  See Note 1	(a) Overall Survey of <ol style="list-style-type: none"> <li>(i) all cargo holds on single skin ships</li> <li>(ii) two selected cargo holds on double skin ships</li> </ol> (b) Close-up Survey of at least 25 per cent of the cargo hold side shell frames, their lower end attachments and adjacent shell plating in the forward cargo hold on single skin ships. See Notes 2, 3, 4 and 5.	(a) Overall Survey of all cargo holds (b) Close-up Survey of at least 25 per cent of the cargo hold side shell frames, their lower end attachments and adjacent shell plating in the forward cargo hold and one other selected cargo hold on single skin ships See Notes 2, 3, 4 and 5.
<b>NOTES</b> The requirements in this Table apply to both single skin and double skin ships, unless stated otherwise. <ol style="list-style-type: none"> <li>1. Where the Survey reveals the need for remedial measures, then the Survey is to be extended to include all cargo holds.</li> <li>2. Close-up Survey is required within the area of the lower one-third of the length of the cargo hold side shell frames.</li> <li>3. Where the Survey reveals the need for remedial measures, the Survey is to be extended to include a Close-up Survey of all of the cargo hold side shell frames and adjacent shell plating of that cargo hold, as well as a Close-up Survey of sufficient extent of all remaining cargo holds.</li> <li>4. When considered necessary by the Surveyor, thickness measurement is to be carried out. Where the results of thickness measurement indicate substantial corrosion, the extent of thickness measurement should be in accordance with Section 6, Tables 3.6.4, 3.6.5, 3.6.6, 3.6.7, 3.6.8 and 3.6.9 as applicable. The survey will not be considered complete until these additional thickness measurements have been carried out.</li> <li>5. Where protective coatings are found in good condition, as defined in 1.5, the extent of the Close-up Survey and thickness measurement may be specially considered. Prior to any coating or recoating of cargo holds, scantlings are to be confirmed by thickness measurement with the Surveyor in attendance.</li> </ol>		

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 2 & 3

2.2.29 For **roll on-roll off ships** and **other ship types** fitted with bow doors, inner doors, side doors and stern doors, in addition to the requirements of 2.2.1, the following are to be satisfactorily dealt with as applicable:

- (a) Verification of the freedom of movement of doors, and operation of their power units.
- (b) Examination of the door structure and surrounding ship structure.
- (c) Examination of the door sealing arrangements including gaskets and retaining bars.
- (d) Examination of the door cleating, locking and securing arrangements.
- (e) Examination of the door hinging arrangements.
- (f) Verification of the local and/or remote control of the securing devices/cleats.
- (g) Examination of all equipment associated with the opening, closing and securing of the door, e.g. wire ropes, chains, sheaves, rollers, guides, shackles, etc.
- (h) Verification of the tightness of the doors.
- (j) Examination and testing of remote control panels and associated indicator lights, closed circuit television systems, water leakage indicator lights and alarm systems.
- (k) Examination of the required notice boards and verification of log entries.
- (l) Verification of the satisfactory testing of the bilge systems for the space between the inner and outer bow doors and of the vehicle deck.
- (m) Verification that the approved Operation and Maintenance Manual is on board and satisfactorily maintained.

2.2.30 For **navigational arrangements for periodic one man watch**, and where applicable **integrated bridge systems**, Annual Surveys are to be carried out in accordance with the approved test schedule as required by Pt 7, Ch 9, 1.2.1 to ascertain that the equipment and arrangements required for the applicable class notation are being maintained in good working order. At the time of the survey, relevant statutory certificates may be accepted as evidence of satisfactory operation.

2.2.31 For **liquefied gas ships**, see also Section 9.

2.2.32 Where a special features notation 'certified container securing arrangements' is assigned, the Surveyor is to examine the securing arrangements so far as necessary and practicable in order to be satisfied as to their general condition.

2.2.33 For single hold general dry cargo ships, other than bulk carriers, fitted with water level detectors in the cargo hold, an examination and a test, at random, of the water ingress detection system and alarms are to be carried out.

## Section 3

## Intermediate Surveys – Hull and machinery requirements

### 3.1 General

3.1.1 Intermediate Surveys are to be held concurrently with statutory annual or other relevant statutory surveys wherever practicable.

### 3.2 Intermediate Surveys

3.2.1 The requirements of Section 2 are to be complied with so far as applicable.

3.2.2 A general examination of salt-water ballast tanks is to be carried out as required by 3.2.6 and 3.2.7. For ships other than oil tankers and chemical tankers, if such examinations reveal no visible structural defects then the examination may be limited to a verification that the protective coating remains in GOOD or FAIR condition as defined in 1.5. When considered necessary by the Surveyor, thickness measurement of the structure is to be carried out.

3.2.3 In application of 3.2.12, 3.2.15 and 3.2.17 respectively for **oil tankers** (including ore/oil and ore/bulk/oil ships), **chemical tankers** and **bulk carriers** over 15 years of age a survey in dry-dock is to be a part of the Intermediate Survey. The overall and close-up surveys and thickness measurements, as applicable, of the lower portions of cargo tanks/holds and water ballast tanks are to be surveyed in accordance with the applicable requirements for Intermediate Surveys, if not already surveyed.

3.2.4 For **oil tankers** (including ore/oil and ore/bulk/oil ships) and **chemical tankers**, salt-water ballast tanks are to be examined and gauged as necessary at Annual Surveys where:

- (a) A hard protective coating has not been applied from the time of construction; or
- (b) A soft coating has been applied; or
- (c) Substantial corrosion is found within the tank, or
- (d) The hard protective coating is found to be in less than GOOD condition, as defined in 1.5, and the hard protective coating is not repaired to the satisfaction of the Surveyor; or
- (e) For **single hull oil tankers**, the tank has a common plane boundary with a cargo tank with any means of heating.

3.2.5 For salt-water ballast tanks on those ships not listed in 3.2.4, where a hard protective coating is found to be in POOR condition, as defined in 1.5, and it has not been repaired, where a soft coating has been applied or where a protective coating was not applied from the time of construction the following requirements are applicable:

- (a) For salt-water ballast tanks, other than independent double bottom tanks, maintenance of class will be subject to the spaces in question being examined and gauged as necessary at Annual Surveys.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 3

- (b) For independent salt-water double bottom tanks, maintenance of class may, at the discretion of the Surveyor, be subject to the spaces in question being examined and gauged as necessary at Annual Surveys.

**NOTE**

Independent double bottom tanks are those double bottom tanks which are separate from topside tank, side tanks or deep tanks.

3.2.6 For ships over 5 years of age and up to 10 years of age, representative salt-water ballast tanks are to be examined. In addition to this, the following requirements are applicable:

- (a) For **general dry cargo ships**, an Overall Survey of representative salt-water ballast tanks, as selected by the Surveyor is to be carried out.
- (b) For **bulk carriers**, an Overall Survey of representative salt-water ballast tanks, as selected by the Surveyor is to be carried out. The selected tanks are to include the fore peak tank, aft peak tank and a number of other tanks, taking into account the total number and type of ballast tanks.
- (c) For **single hull oil tankers** (including ore/oil and ore/bulk/oil ships), an examination of all salt-water ballast tanks is to be carried out. Where considered necessary by the Surveyor, thickness measurement and testing are to be carried out to ensure the structural integrity remains effective.
- (d) For **double hull oil tankers** and **chemical tankers**, an Overall Survey of representative salt-water ballast tanks, as selected by the Surveyor is to be carried out. If the survey reveals no visible defects, the examination may be limited to a verification that the hard protective coating remains in GOOD condition, as defined in 1.5.

3.2.7 For all ships over 10 years of age, the following are required:

- (a) All salt-water ballast tanks are to be examined.
- (b) The anchors are to be partially lowered and raised using the windlass.

3.2.8 The Surveyor is to carry out an examination and thickness measurement of structure identified at the previous Special Survey as having substantial corrosion, see *also* Sections 5, 6, 7 and 8.

3.2.9 For all ships, the electrical generating sets are to be examined under working conditions to verify compliance with Pt 6, Ch 2,2.2.

3.2.10 In addition to the foregoing, in the case of all **oil tankers** (including ore/oil and ore/bulk/oil ships) the following are to be dealt with where applicable:

- (a) An examination of cargo, crude oil washing, bunker, ballast, steam and vent piping on the weather decks, as well as vent masts and headers. If upon examination there is any doubt as to the condition of the piping, the piping may be required to be pressure tested, gauged, or both.

- (b) A General Examination within the areas deemed as dangerous, such as cargo pump rooms and spaces adjacent to and zones above cargo tanks, for defective and non-certified safe-type electrical equipment, improperly installed, defective and dead-end wiring. An electrical insulation resistance test of the circuits terminating in, or passing through, the dangerous areas is to be carried out. If the ship is not in a gas free condition the results of previously recorded test readings may be accepted.

3.2.11 For **oil tankers** (including ore/oil and ore/bulk/oil ships), in addition to 3.2.10, the following are required for ships over 10 years of age:

- (a) A survey to the same extent as the previous Special Survey (applicable only to ESP surveys, see 7.1.2).
- (b) Pressure testing of cargo and ballast tanks and the requirements for the longitudinal strength evaluation (see 7.7.3) are to be carried out if deemed necessary by the attending Surveyor.

3.2.12 For **chemical tankers**, in addition to the applicable requirements of 3.2.1 to 3.2.9 the following are to be dealt with where applicable:

- (a) Examination of vent line drainage arrangements.
- (b) Verification that the cargo heating/cooling system is in good condition.
- (c) Verification that the ship's cargo hoses are approved and in good condition.
- (d) Verification that, where applicable, pipelines and independent cargo tanks are electrically bonded to the hull.
- (e) An examination of cargo, cargo washing, bunker, ballast, steam and vent piping on the weather decks, as well as vent masts and headers. If upon examination there is any doubt as to the condition of the piping, the piping may require to be pressure tested, gauged or both.
- (f) A General Examination within the areas deemed as dangerous, such as cargo pump rooms and spaces adjacent to and zones above cargo tanks, for defective and non-certified safe-type electrical equipment, improperly installed, defective and dead-end wiring. An electrical insulation resistance test of the circuits terminating in, or passing through, the dangerous areas is to be carried out. If the ship is not in a gas free condition the results of previously recorded test readings may be accepted.

3.2.13 For **chemical tankers**, in addition to 3.2.12, the following are required for ships over 10 years of age:

- (a) A survey to the same extent as the previous Special Survey (applicable only to ESP surveys, see 8.1.2).
- (b) Pressure testing of cargo and ballast tanks is to be carried out if deemed necessary by the attending Surveyor.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 3

3.2.14 For **bulk carriers**, in addition to the applicable requirements of 3.2.1 to 3.2.9, the following are to be dealt with on ships over five years of age:

- (a) Examination of holds in accordance with Table 3.3.1.
- (b) The thickness measurement requirements of 3.2.8 are to be complied with. In areas where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out in accordance with Tables 3.6.3, 3.6.4, 3.6.5 and 3.6.6. The survey will not be considered complete until these additional thickness measurements have been carried out.
- (c) Thickness measurement of those areas subject to Close-up Survey, to determine both general and local corrosion levels. The extent of thickness measurement may be specially considered provided the Surveyor is satisfied that there is no structural diminution and the protective coating, where provided, remains in GOOD condition, as defined in 1.5.
- (d) For ore carriers, in addition to the requirements of 3.2.7, the examination of salt-water ballast tanks is to include the following:
  - (i) All web frame rings in one ballast wing tank.
  - (ii) One deck transverse in each remaining ballast wing tank.
  - (iii) Both transverse bulkheads in one ballast wing tank.
  - (iv) One transverse bulkhead in each remaining ballast wing tank.

3.2.15 For **bulk carriers**, in addition to the applicable requirements of 3.2.1 to 3.2.9, the following is required for ships over 10 years of age:

- (a) A survey to the same extent as the previous special Survey (applicable to ESP surveys, see 6.1.2).
- (b) Pressure testing of all tanks and the internal examination of fuel oil tanks are to be carried out if deemed necessary by the Surveyor.

3.2.16 For **dry cargo ships** over 15 years old (other than bulk carriers and general dry cargo ships), in addition to the applicable requirements of 3.2.1 to 3.2.8, an Overall Survey of selected cargo holds is to be carried out.

3.2.17 For **general dry cargo ships**, in addition to the applicable requirements of 3.2.1 to 3.2.9, the following is required for ships over 5 years of age:

- An overall survey of one forward and one after cargo hold and their associated 'tween deck spaces.

3.2.18 For **general dry cargo ships**, in addition to the applicable requirements of 3.2.1 to 3.2.9, the following are required for ships over 10 years of age:

- (a) An overall survey of all cargo holds and 'tween deck spaces.
- (b) Where considered necessary by the Surveyor, thickness measurement is to be carried out. Where the results of thickness measurement indicate substantial corrosion, the extent of thickness measurement should be in accordance with Table 3.5.6 in Section 5. The survey will not be considered complete until these additional thickness measurements have been carried out.

3.2.19 For **general dry cargo ships**, in addition to the applicable requirements of 3.2.1 to 3.2.9, the following are required for ships over 15 years of age:

- (a) A survey to the same extent as the previous special Survey (applicable only to surveys of the hull structure and piping systems in way of the cargo holds, cofferdams, pipe tunnels and void spaces within the cargo area and all salt water ballast tanks).
- (b) Tank testing, survey of automatic air pipe heads and internal examination of fuel oil, lubricating oil and fresh water tanks are to be carried out if deemed necessary by the Surveyor.

**Table 3.3.1 Bulk carriers – Intermediate Surveys**

Ships between 5 and 10 years old	Ships between 10 and 15 years old	Ships greater than 15 years old
<ol style="list-style-type: none"><li>(a) Overall Survey of all cargo holds, see Notes 1, 2, 3 and 4</li><li>(b) Close-up Survey to establish the condition of at least 25 per cent of the cargo hold side shell frames including their upper and lower end attachments, adjacent shell plating and the transverse bulkheads in the forward cargo hold and one other selected cargo hold on single skin ships, see Notes 1, 3 and 4.</li></ol>	A survey to the same extent as the previous Special Survey (applicable only to ESP surveys, see 6.1.2), see Note 3.	A survey to the same extent as the previous Special Survey (applicable only to ESP surveys, see 6.1.2), see Note 3.
<p><b>NOTES</b></p> <p>The requirements in this Table apply to both single skin and double skin ships, unless stated otherwise.</p> <ol style="list-style-type: none"><li>1. For single skin ships, where considered necessary by the Surveyor as a result of the Overall and Close-up Survey, the Survey is to be extended to include a Close-up Survey of all of the side shell frames and adjacent shell plating of that cargo hold, as well as a Close-up Survey of sufficient extent of all remaining cargo holds.</li><li>2. For double skin ships, where considered necessary by the Surveyor as a result of the Overall Survey, the Survey is to be extended to include a Close-up Survey of those areas of structure in cargo holds selected by the Surveyor.</li><li>3. Thickness measurement is to be carried out of sufficient extent to determine the level of corrosion of those areas subject to Close-up Survey. Where the results of thickness measurement indicate substantial corrosion, the extent of thickness measurement should be in accordance with Section 6, Tables 3.6.4, 3.6.5, 3.6.6, 3.6.7, 3.6.8 and 3.6.9 as applicable. The survey will not be considered complete until these additional thickness measurements have been carried out.</li><li>4. For ships between 5 and 10 years old where hard protective coatings in cargo holds are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Survey and thickness measurement may be specially considered. Prior to any coating or recoating of cargo holds, scantlings are to be confirmed by thickness measurement with the Surveyor in attendance.</li></ol>		



# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 3 & 4

3.2.20 For **ship-borne barges**, where Intermediate Surveys are permitted as an alternative to Annual Surveys and Docking Surveys, all the hatch covers are to be hose tested at every survey. The external surfaces of the barges are to be surveyed at these surveys.

3.2.21 For **liquefied gas ships**, see Section 9.

## Section 4 Docking Surveys and In-water Surveys – Hull and machinery requirements

### 4.1 General

4.1.1 At Docking Surveys or In-water Surveys the Surveyor is to examine the ship and machinery, so far as necessary and practicable, in order to be satisfied as to the general condition.

4.1.2 For **oil tankers** (including ore/oil and ore/bulk/oil ships), **chemical tankers** and **bulk carriers** over 15 years of age the intermediate docking between Special Surveys is to be held in dry-dock. Further, this survey is to be held as part of the Intermediate Survey.

### 4.2 Docking Surveys

4.2.1 Where a ship is in dry-dock or on a slipway it is to be placed on blocks of sufficient height, and proper staging is to be erected as may be necessary, for the examination of the shell including bottom and bow plating, keel, stern, stern-frame and rudder. The rudder is to be lifted for examination of the pintles if considered necessary by the Surveyor.

4.2.2 The shell plating is to be examined for excessive corrosion, deterioration due to chafing or contact with the ground and for undue unfairness or buckling. Special attention is to be given to the connection between the bilge strakes and the bilge keels.

4.2.3 The clearances in the rudder bearings are to be measured. Where applicable, pressure testing of the rudder may be required if deemed necessary by the Surveyor.

4.2.4 The sea connections and overboard discharge valves and cocks and their attachments to the hull are to be examined.

4.2.5 The propeller, sternbush and sea connection fastenings and the gratings at the sea inlets are to be examined.

4.2.6 The clearance in the sternbush or the efficiency of the oil glands is to be ascertained.

4.2.7 When chain cables are ranged, the anchors and cables are to be examined by the Surveyor, see *also* 5.3.13, 5.3.14 and Table 3.5.1.

4.2.8 For electrical equipment survey requirements of oil tankers five years old and over, see 14.3.

### 4.3 In-water Surveys

4.3.1 The Committee will accept an In-water Survey in lieu of the intermediate docking between Special Surveys required in a five year period on ships other than those covered in 4.1.2 and where an **\*IWS** notation is assigned, see Ch 2,2.3.11.

4.3.2 The Committee may accept an In-water Survey in lieu of the intermediate docking between Special Surveys required in a five year period on ships where suitable protection is applied to the underwater portion of the hull. If requested, an **\*IWS** notation may be assigned on satisfactory completion of the Survey, provided that the applicable requirements of LR's Rules and Regulations are complied with, see *also* Ch 2,2.3.11.

4.3.3 The In-water Survey is to provide the information normally obtained from the Docking Survey.

4.3.4 Special consideration shall be given to ascertaining rudder bearing clearances and sternbush clearances based on a review of the operating history, on board testing and stern bearing oil analysis. These considerations are to be included in the proposals. In-water Surveys which are to be submitted in advance of the survey being required, so that satisfactory arrangements can be agreed with LR.

4.3.5 The In-water Survey is to be carried out at an agreed geographical location under the surveillance of a Surveyor to LR, with the ship at a suitable draught in sheltered waters and with weak tidal streams and currents. The in-water visibility is to be good and the hull below the waterline is to be clean. The Surveyor is to be satisfied that the method of pictorial presentation is satisfactory. There is to be good two-way communication between the Surveyor and the diver.

4.3.6 Prior to commencing the In-water Survey, the equipment and procedures for both observing and reporting the survey are to be agreed between the Owners, the Surveyor and the diving firm

4.3.7 The In-water Survey is to be carried out by a qualified diver employed by a firm approved by LR.

4.3.8 If the In-water Survey reveals damage or deterioration that requires early attention, the Surveyor may require that the ship be dry-docked in order that a fuller survey can be undertaken and the necessary work carried out.

4.3.9 Where a vessel has an **\*IWS** notation, the conditions of the high resistant paint is to be confirmed at each dry-docking in order that the **\*IWS** notation can be maintained.

4.3.10 Some National Administrations may have requirements additional to those of 4.3.1 to 4.3.9.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 5

## Section 5 Special Survey – General – Hull requirements

### 5.1 General

5.1.1 The survey is to be of sufficient extent to ensure that the hull and related piping are in satisfactory condition and are fit for the intended purpose for the new period of class of five years to be assigned, subject to proper maintenance and operation and to periodical surveys being carried out as required by the Regulations.

5.1.2 The requirements of Section 2 are to be complied with as applicable for all ships.

5.1.3 Additional requirements for **general dry cargo ships** are given in this Section; **dry bulk cargo ships bulk carriers** in Section 6; **oil tankers** (including ore/oil ships and ore/bulk/oil ships) in Section 7; **chemical tankers** in Section 8; **ships for liquefied gases** in Section 9.

5.1.4 A Docking Survey in accordance with the requirements of Section 4 is to be carried out as part of the Special Survey.

5.1.5 During the Docking Survey, for general dry cargo ships, oil tankers (including ore/oil ships and ore/bulk/oil ships), chemical tankers and bulk carriers, the overall and close-up surveys and thickness measurements, as applicable, of the lower portions of the cargo spaces and ballast tanks are to be carried out as required, if not already surveyed.

### 5.2 Preparation

5.2.1 The ship is to be prepared for Overall Survey in accordance with the requirements of Table 3.5.1. The preparation should be of sufficient extent to facilitate an examination to ascertain any significant corrosion, deformation, fractures, damages and other structural deterioration.

### 5.3 Examination and testing

5.3.1 All spaces within the hull and superstructure are to be examined.

5.3.2 The requirements for tank internal examination are given in Table 3.5.2.

5.3.3 For **oil tankers** (including ore/oil and ore/bulk/oil ships) and **chemical tankers**, the condition of the corrosion prevention system, where provided, is to be examined in cargo tanks and salt-water ballast tanks. Thickness measurements are to be carried out as deemed necessary by the Surveyor. Ballast tanks are to be examined and gauged as necessary at Annual Surveys where:

- (a) A hard protective coating has not been applied from the time of construction, or
- (b) A soft coating has been applied, or
- (c) Substantial corrosion is found within the tank, or

- (d) The hard protective coating is found to be in less than GOOD condition, as defined in 1.5, and the hard protective coating is not repaired to the satisfaction of the Surveyor, or
- (e) For **single hull oil tankers**, the tank has a common plane boundary with a cargo tank with any means of heating.

5.3.4 For those ships not listed in 5.3.3, the condition of the corrosion prevention system, where provided, in salt-water ballast tanks is to be examined. Thickness measurements are to be carried out as deemed necessary by the Surveyor. Where a hard protective coating is found to be in POOR condition, as defined in 1.5, and it has not been repaired, where a soft coating has been applied or where a protective coating was not applied from the time of construction the following requirements are applicable:

- (a) For salt-water ballast tanks, other than independent double bottom tanks, maintenance of class will be subject to the spaces in question being examined and gauged as necessary at Annual Surveys.
- (b) For independent salt-water double bottom tanks, maintenance of class may, at the discretion of the Surveyor, be subject to the spaces in question being examined and gauged as necessary at Annual Surveys.

#### NOTE

Independent double bottom tanks are those double bottom tanks which are separate from topside tank, side tanks or deep tanks.

5.3.5 Double bottom, deep, ballast, peak and other tanks, including cargo holds assigned also for the carriage of salt water ballast, are to be tested with a head of liquid to the top of air pipes or to near the top of hatches for ballast/cargo holds. Boundaries of oil fuel, lubricating oil and fresh water tanks are to be tested with a head of liquid to the highest point that liquid will rise under service conditions. Tank testing of oil fuel, lubricating oil and fresh water tanks may be specially considered based upon a satisfactory external examination of the tank boundaries, and a confirmation from the Master stating that the pressure testing has been carried out according to the requirements with satisfactory results. Surveyors may extend the testing as deemed necessary.

5.3.6 Where repairs are effected to the shell plating or bulkheads, any tanks in way are to be tested to the Surveyor's satisfaction on completion of these repairs.

5.3.7 On ship-borne barges, in lieu of water testing, tanks and cofferdams may be air tested.

5.3.8 In cases where the inner surface of the bottom plating is covered with cement, asphalt, or other composition, the removal of this covering may be dispensed with, provided that it is inspected, tested by beating or chipping, and found sound and adhering satisfactorily to the steel.

5.3.9 All decks, casings and superstructures are to be examined.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 5

**Table 3.5.1 Survey preparation**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)
<p>(1) The holds, 'tween decks, peaks, deep tanks, engine and boiler spaces, and other spaces, are to be cleared and cleaned as necessary, and the bilges and limbers all fore and aft are to be cleaned and prepared for examination. Platform plates in engine and boiler spaces are to be lifted as may be necessary for the examination of the structure below. Where necessary, close and spar ceiling, lining and pipe casings are to be removed for examination of the structure</p> <p>(2) In ships having a single bottom, a sufficient amount of close ceiling is to be lifted all fore and aft on each side from the bottom and bilges to permit the structure below to be examined</p> <p>(3) In ships having a double bottom, a sufficient amount of ceiling is to be removed from the bilges and inner bottom to enable the condition of the plating to be ascertained. If it is found that the plating is clean and in good condition, and free from rust, the removal of the remainder of ceiling may be dispensed with. The Surveyor may waive the removal of heavy reinforced compositions if there is no evidence of leakages, cracking or other faults in the composition</p> <p>(4) Where holds are insulated for the purpose of carrying refrigerated cargoes, and the hull in way of the insulation was examined by LR's Surveyors at the time such insulation was fitted, it will be sufficient to remove the limbers and hatches to enable the framing and plating in way to be examined; in other cases, additional insulation is to be removed as necessary to satisfy the Surveyor as to the condition of the structure, see <i>also</i> Pt 6, Ch 3</p> <p>(5) The steelwork is to be exposed and cleaned and rust removed as may be required for its proper examination by the Surveyor</p> <p>(6) All tanks are to be cleaned as necessary to permit examination, where this is required by Table 3.5.2</p> <p>(7) Casings or covers of air, sounding, steam and other pipes, spar ceiling and lining in way of the side scuttles are to be removed, as required by the Surveyor</p>	<p>In addition to the requirements for Special Survey I, the following are to be complied with:</p> <p>(1) A sufficient amount of ceiling in the holds and other spaces is to be removed from the bilges and inner bottom to enable the condition of the structure in the bilges, the inner bottom plating, pillar feet, and the bottom plating of bulkheads and tunnel sides to be examined. If the Surveyor deems it necessary, the whole of the ceiling is to be removed</p> <p>(2) In ships having a single bottom, the limber boards and ceiling equal to not less than three strakes, all fore and aft on each side are to be removed, one such strake being taken from the bilges. Where the ceiling is fitted in hatches, the whole of the hatches and at least one strake of ceiling in the bilges are to be removed. If the Surveyor deems it necessary the whole of the ceiling and limber boards are to be removed</p> <p>(3) The chain locker is to be cleaned internally. The chain cables are to be ranged for inspection. The anchors are to be cleaned and placed in an accessible position for inspection</p>	<p>In addition to the requirements for Special Survey II the following are to be complied with:</p> <p>(1) Ceiling in holds is to be removed in order to ascertain that the steelwork is in good condition, free from rust and coated. If the Surveyor is satisfied, after removal of portions of the ceiling then it need not all be removed</p> <p>(2) Portions of wood sheathing, or other covering, on steel decks are to be removed, as considered necessary by the Surveyor, in order to ascertain the condition of the plating</p> <p>(3) Where the holds are insulated for the purpose of carrying refrigerated cargoes, the limbers and hatches are to be lifted and sufficient insulation is to be removed in each of the chambers to enable the Surveyor to satisfy himself of the condition of the framing and plating, see <i>also</i> Pt 6, Ch 3</p>
		All subsequent Special Surveys
		<p>In addition to the requirements for Special Survey III the following are to be complied with:</p> <p>(1) Where the holds are insulated for the purpose of carrying refrigerated cargoes, the limbers and hatches are to be lifted, and sufficient additional insulation is to be removed in each of the chambers to enable the Surveyor to be satisfied as to the condition of the steel structure, and to enable the thickness of the shell plating to be ascertained as required by 5.4</p>

**5.3.10** Wood decks or sheathing are to be examined. If decay or rot is found or the wood is excessively worn, the wood is to be renewed. When a wood deck, laid on stringers and ties, has worn by 15 mm or more, it is to be renewed. Attention is to be given to the condition of the plating under wood decks, sheathing or other deck covering. If it is found that such coverings are broken, or are not adhering closely to the plating, sections are to be removed as necessary to ascertain the condition of the plating, see *also* 1.2.1.

**5.3.11** Mechanically-operated hatch covers are to be tested to confirm satisfactory operation including stowage; and securing in open condition; proper fit and efficiency of sealing in closed conditions; operational testing of hydraulic and power components, wires, chains and link drives. The effectiveness of sealing arrangements of all hatch covers is to be checked by carrying out hose testing or equivalent.

**5.3.12** The masts and standing rigging are to be examined.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 5

**Table 3.5.2 Tank internal examination requirements**

Tank	Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
(1) Peaks	All tanks	All tanks	All tanks	All tanks
(2) Salt water ballast	All tanks	All tanks	All tanks	All tanks
(3) Lubricating oil	None	None	None	One tank
(4) Fresh water	None	One tank	All tanks	All tanks
(5) Oil fuel - in way of (i) Engine Room (ii) Cargo Area	None None	None One tank	One tank Two tanks (Note 3)	One tank 50% of tanks – Notes 3 and 4
<p><b>NOTES</b></p> <p>1. The above requirements apply to integral tanks only.</p> <p>2. Where a selected number of tanks are examined, then different tanks are to be examined at each Special Survey on a rotational basis.</p> <p>3. To include one deep tank, if any.</p> <p>4. Where 50% of tanks are to be examined, a minimum of two tanks are required to be examined depending upon the overall number of tanks.</p>				

5.3.13 The anchors are to be examined. If the chain cables are ranged they are to be examined. If any length of chain cable is found to be reduced in mean diameter at its most worn part by 12 per cent or more from its nominal diameter, it is to be renewed. The windlass is to be examined. For equipment forming part of a positional mooring system, see 5.3.16.

5.3.14 The chain cables are to be ranged and examined on all ships over five years old.

5.3.15 The Surveyor is to be satisfied that there are suitable mooring ropes when these are a Rule requirement.

5.3.16 On ships fitted with positional mooring equipment in accordance with Pt 7, Ch 8, the anchors are to be cleaned and examined. Wire rope anchor cables are to be examined. If cables are found to contain broken, badly corroded or birdcaging wires they are to be renewed. Chain cables are to be ranged and examined. If any length of chain cable is found to be reduced in mean diameter at its most worn part by 12 per cent or more from its nominal diameter it is to be renewed. The windlass(es) or winches are to be examined.

5.3.17 The hand pumps, suction, watertight doors, air and sounding pipes are to be examined. In addition, the Surveyor is to internally and externally examine air pipe heads in accordance with the requirements of Table 3.5.7.

5.3.18 The Surveyor is to be satisfied as to the efficient condition of the following:

- For ships to which Pt 6, Ch 4 applies, means of escape from crew and passenger spaces, and spaces in which crew are normally employed.
- Helm indicator, protection of aft steering wheel and gear.

5.3.19 Where a special features notation 'certified container securing arrangements' is assigned, the Surveyor is to be satisfied as to the efficient condition of:

- Cell guide structure including the connections between vertical cell guides and cross ties.
- Cell guide entry devices.

- Portable frameworks or other forms of structural restraints.
- Fittings attached to the ship structure, with special attention to any signs of leakage in way of tanks or deck and shell plating.
- End connecting pieces for lashings, twist locks and other loose fittings, which are to be examined and verified with the Register.
- All lashings, rods, wire ropes, and chains, together with turn buckles and other tightening devices, which are to be examined and verified with the Register.
- Lashing wire ropes, which are to be renewed where more than five per cent of the wires are broken, worn or corroded in any length of 10 diameters of the wire rope.
- Chains, which are to be renewed where worn or damaged. Where renewals are required, the new item is to be of approved type and manufacture. Where test certificates are not available, the item is to be tested in accordance with Pt 3, Ch 14.3.

5.3.20 All bilge and ballast piping systems are to be examined and operationally tested to working pressure, to the satisfaction of the Surveyor, to ensure that tightness and condition remain satisfactory.

## 5.4 Overall Survey

5.4.1 The following requirements are applicable to **general dry cargo ships**.

5.4.2 All cargo holds, salt-water ballast tanks including double bottom tanks, pipe tunnels, cofferdams and void spaces bounding cargo holds, decks and outer hull are to be examined, and this is to be supplemented by Close-up Survey, thickness measurement and testing as deemed necessary, to ensure that the structural integrity remains effective.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 5

5.4.3 The examination is to be sufficient to ascertain substantial corrosion, significant deformation, fractures, damages or other structural deterioration and, if deemed necessary by the Surveyor, suitable non-destructive examination may be required.

5.4.4 All piping systems within the tanks and spaces indicated in 5.4.2 are to be examined and operationally tested to working pressure to the satisfaction of the Surveyor, to ensure that conditions remain satisfactory.

5.4.5 Where the salt-water ballast tanks have been converted to void spaces, the survey extent is to be specially considered based upon salt-water ballast tank requirements.

5.4.6 For single hold general dry cargo ships, other than bulk carriers, fitted with water level detectors in the cargo hold, an examination and a test of the water ingress detection system and alarms are to be carried out.

### 5.5 Close-up Survey

5.5.1 The following requirements are applicable to **general dry cargo ships**.

5.5.2 The minimum requirements for Close-up Survey are given in Table 3.5.4. The Close-up Survey may be extended, as deemed necessary by the Surveyor, after taking into account the maintenance of the spaces under survey, the condition of the corrosion prevention system and where spaces have structural arrangements or details which have suffered defects in similar spaces or on similar ships according to available information.

5.5.3 For areas in tanks and cargo holds where coatings are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Surveys may be specially considered.

### 5.6 Thickness measurement

5.6.1 The general minimum requirements for thickness measurement are given in Table 3.5.3. For **general dry cargo ships**, the minimum requirements for thickness measurement are given in Table 3.5.5. The Surveyor may extend the thickness measurements as deemed necessary.

5.6.2 Thickness measurements may be carried out in association with the fourth Annual Survey.

5.6.3 In areas where substantial corrosion, as defined in 1.5, has been noted, then additional measurements are to be carried out, as applicable, in accordance with Table 3.5.6 to determine the full extent of the corrosion pattern. The survey will not be considered complete until these additional thickness measurements have been carried out.

5.6.4 Where substantial corrosion is identified and not rectified, this will be subject to re-examination and gauging as necessary at Annual and Intermediate Surveys.

5.6.5 At each Special Survey, thickness measurements are to be taken in way of critical areas, as considered necessary by the Surveyor. Critical areas are to include locations throughout the ship that show substantial corrosion and/or are considered prone to rapid wastage.

5.6.6 Where required by LR, a check of the buckling capacity of the upper deck is to be carried out for tankers having a length greater than 90 m.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 5

**Table 3.5.3 Thickness measurement – General**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
(1) Critical areas, as required by the Surveyor	(1) Within 0,5L amidships; 2 transverse sections in way of two different cargo spaces, see Notes 2, 3 and 4 (2) All cargo hold hatch covers and coamings (plating and stiffeners) (3) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank (see Notes 3 and 5) (4) Critical areas, as required by the Surveyor	(1) Within 0,5L amidships; a minimum of 3 transverse sections in way of cargo spaces, see Notes 2, 3 and 4 (2) All cargo hold hatch covers and coamings (plating and stiffeners) (3) All exposed main deck plating over full length of ship (4) All wind and water strakes over the full length of the ship, port and starboard. (5) Representative exposed superstructure deck plating (i.e. poop, bridge and forecastle deck) (6) Lowest strake and strakes in way of 'tween deck of all transverse bulkheads in cargo spaces together with internals in way, see Note 3 (7) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 3 and 5 (8) All keel plates over the full length of the ship. Also additional bottom plates in way of cofferdams, machinery space and aft end of tanks (9) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor (10) Critical areas, as required by the Surveyor
Special Survey II (Ships 10 years old)		
(1) Within 0,5L amidships; 1 transverse section of deck plating in way of a cargo space (2) Critical areas, as required by the Surveyor		
<p><b>NOTES</b></p> <p>1. Thickness measurement locations are to be selected to provide the best representative sampling of areas likely to be most exposed to corrosion, considering cargo and ballast history and arrangement, and condition of protective coatings.</p> <p>2. A transverse section is to include all longitudinal members such as plating, longitudinals and girders at the deck, sides, bottom, inner bottom, hopper side and longitudinal bulkheads, where fitted.</p> <p>3. Where the protective coating is in GOOD condition, then the extent of thickness measurements of internals may be specially considered at the discretion of the Surveyor.</p> <p>4. For ships having length <math>L</math> less than 100 m: (a) the number of transverse sections required at Special Survey III may be reduced to one; (b) the number of transverse sections required at Special Survey IV and subsequent surveys may be reduced to two; (c) at Special Survey III, thickness measurements of exposed deck plating within 0,5L amidships may be required.</p> <p>5. Transverse bulkhead complete including stiffening system.</p> <p>6. The requirements for thickness measurement for bulk carriers, oil tankers (including ore/oil and ore/bulk/oil ships), chemical tankers and ships for liquefied gases are given in Sections 6, 7, 8 and 9 respectively.</p>		

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 5

**Table 3.5.4 Close-up Survey – General dry cargo ships**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
(1) Selected shell frames in one forward and one aft cargo hold and associated 'tween deck spaces. (2) One selected cargo hold transverse bulkhead. (3) All cargo hold hatch covers and coamings (plating and stiffeners).	(1) Selected shell frames in all cargo holds and 'tween deck spaces. (2) One transverse bulkhead in each cargo hold, including stiffening system. (3) Forward and aft transverse bulkhead in one side ballast tank, including stiffening system. (4) One transverse web with associated plating and framing in two representative water ballast tanks of each type (i.e. topside, hopper side, side tank or double bottom tank). (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) Selected areas of all deck plating and underdeck structure inside the line of hatch openings between cargo hold hatches. (7) Selected areas of inner bottom plating.	(1) All shell frames in the forward lower cargo hold and 25% of shell frames in each remaining cargo hold and 'tween deck spaces, including their end attachments and adjacent shell plating. (2) All cargo hold transverse bulkheads, including stiffening system. (3) All transverse bulkheads in ballast tanks, including stiffening system. (4) All transverse webs with associated plating and framing in each water ballast tank. (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) All deck plating and underdeck structure inside the line of hatch openings between cargo hold hatches. (7) All areas of inner bottom plating.	(1) All shell frames in all cargo holds and 'tween deck spaces, including their end attachments and adjacent shell plating. (2) All cargo hold transverse bulkheads, including stiffening system. (3) All transverse bulkheads in ballast tanks, including stiffening system. (4) All transverse webs with associated plating and framing in each water ballast tank. (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) All deck plating and underdeck structure inside the line of hatch openings between cargo hold hatches. (7) All areas of inner bottom plating.
<b>NOTES</b> 1. Close-up survey of cargo hold transverse bulkheads to be carried out at the following areas: (i) Immediately above the inner bottom and immediately above the 'tween decks, as applicable. (ii) Mid-height of the bulkhead for holds without 'tween decks. (iii) Immediately below the main deck plating and 'tween deck plating. 2. Ballast tank includes peak tanks.			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 5

**Table 3.5.5 Thickness measurement – General dry cargo ships**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
(1) Critical areas, as required by the Surveyor.	(1) Within 0,5L amidships; 2 transverse sections in way of two different cargo spaces, see Notes 2, 3 and 4.	(1) Within 0,5L amidships; a minimum of 3 transverse sections, see Notes 2, 3 and 4.
Special Survey II (Ships 10 years old)	(2) Measurements for the general assessment and recording of corrosion pattern of those structural members subject to Close-up Survey in accordance with Table 3.5.4, see Note 5.	(2) Measurements for the general assessment and recording of corrosion pattern of those structural members subject to Close-up Survey in accordance with Table 3.5.4, see Note 5.
(1) Within 0,5L amidships; 1 transverse section of deck plating in way of a cargo space.	(3) Within the cargo length area; (i) Each deck plate outside the line of cargo hatch openings. (ii) All wind and water strakes.	(3) Within the cargo length area; (i) Each deck plate outside the line of cargo hatch openings. (ii) Each bottom plate, including turn of bilge. (iii) Duct keel or pipe tunnel plating and internals.
(2) Measurements for the general assessment and recording of corrosion pattern of those structural members subject to Close-up Survey in accordance with Table 3.5.4, see Note 5.	(4) Selected wind and water strakes outside the cargo length area.	(4) All wind and water strakes over the full length of the ship, port and starboard.
(3) Critical areas, as required by the Surveyor.	(5) All cargo hold hatch covers and coamings (plating and stiffeners).	(5) All cargo hold hatch covers and coamings (plating and stiffeners).
	(6) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank, see Notes 3 and 6.	(6) Representative exposed superstructure deck plating (i.e. poop, bridge and forecastle deck).
	(7) Critical areas, as required by the Surveyor	(7) Lowest strake and strakes in way of 'tween decks of all transverse bulkheads in cargo spaces together with internals in way, see Note 3.
		(8) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 3 and 6.
		(9) All keel plates over the full length of the ship. Also additional bottom plates in way of cofferdams, machinery spaces and aft end of tanks.
		(10) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor.
		(11) Critical areas, as required by the Surveyor.
<b>NOTES</b> 1. Thickness measurement locations are to be selected to provide the best representative sampling of areas likely to be most exposed to corrosion, considering cargo and ballast history and arrangement, and condition of protective coatings. 2. A transverse section is to include all longitudinal members such as plating, longitudinals and girders at deck, sides, bottom, inner bottom, hopper side and longitudinal bulkheads, where fitted. 3. Where the protective coating is in GOOD condition, then the extent of thickness measurements of internals may be specially considered at the discretion of the attending Surveyor. 4. For ships having length <i>L</i> less than 100 m: (a) the number of transverse sections required at Special Survey III may be reduced to one. (b) the number of transverse sections required at Special Survey IV and subsequent surveys may be reduced to two. 5. For areas in cargo holds and salt-water ballast tanks subject to Close-up Survey, the thickness measurements may be dispensed with provided the Surveyor is satisfied with the Close-up Survey examination, that there is no structural diminution and the protective coating remains effective. 6. Transverse bulkhead complete including stiffening system.		

**Table 3.5.6 Thickness measurement – Additional requirements in way of structure identified with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
Plating	Suspect areas and adjacent plates	5 point pattern over 1 m <sup>2</sup>
Stiffeners	Suspect areas	3 measurements each in line across web and flange



# Periodical Survey Regulations

## Part 1, Chapter 3

Sections 5 &amp; 6

**Table 3.5.7 Air pipe head internal examination requirements (applicable for automatic air pipe heads installed on exposed decks of all ships except passenger ships)**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old) and subsequent
(1) Two air pipe heads (one port and one starboard) on exposed decks in the forward 0,25L. (See Notes 1 to 5)  (2) Two air pipe heads (one port and one starboard) on the exposed decks, serving spaces aft of 0,25L. (See Notes 1 to 5)	(1) All air pipe heads on exposed decks in the forward 0,25L. (See Notes 1 to 5)  (2) At least 20% of air pipe heads on exposed decks, serving spaces aft of 0,25L. (See Notes 1 to 5)	All air pipe heads on exposed decks. (See Notes 1 to 6)
<b>NOTES</b> 1. Air pipe heads serving ballast tanks are to be selected where available. 2. The Surveyor is to select which air pipe heads are to be examined. 3. Where considered necessary by the Surveyor as a result of the examinations, the extent of examinations may be extended to include other air pipe heads on exposed decks. 4. Where the inner parts of air pipe head cannot be properly examined due to its design, it is to be removed in order to allow an internal examination. 5. Particular attention is to be given to the condition of the zinc coating in heads constructed from galvanised steel. 6. Exemption may be considered for air pipe heads where there is documented evidence of their replacement within the previous five years.		

### Section 6

### Special Survey – Bulk carriers – Hull requirements

#### 6.1 General

6.1.1 The requirements of Sections 2, 4 and 5 are to be complied with as applicable.

6.1.2 In order to maintain and/or assign the **ESP** notation, the following requirements apply to the surveys of the hull structure and piping systems in way of the cargo holds, cofferdam, pipe tunnels, void spaces, topside tanks and double bottom tanks in way of the cargo hold area and all salt-water ballast tanks.

#### 6.2 Documentation

6.2.1 The Owner is to maintain documentation on board as follows:

- (a) A survey file comprising reports of structural surveys, thickness measurement and executive hull summary in accordance with IMO Resolution A.744(18).
- (b) Supporting documentation consisting of:
  - (i) Main structural plans of cargo holds and ballast tanks.
  - (ii) Previous repair history.
  - (iii) Cargo and ballast history.
  - (iv) Reports on structural defects/deterioration in general.
  - (v) Reports on leakage in bulkheads and piping systems.
  - (vi) Condition of corrosion prevention system, if any.
  - (vii) Information that may help to identify critical areas.
  - (viii) Survey Programme as required by 6.3.

The complete documentation in 6.2.1 is to be readily available for examination by the Surveyor and should be used as a basis for survey.

6.2.2 The documentation is to be kept on board for the lifetime of the ship.

#### 6.3 Planning for survey

6.3.1 A Survey Programme is to be submitted by the Owner and is to include the proposals for survey, including the means of providing access for Close-up Survey, thickness measurement and tank testing and should take account of the information detailed in 6.2.1.

6.3.2 Prior to the development of the Survey Programme, a Survey Planning Questionnaire is to be completed and submitted by the Owner, see 1.6.9.

#### 6.4 Overall Survey

6.4.1 All cargo holds, salt-water ballast tanks including double bottom tanks, pipe tunnels, cofferdams and void spaces bounding cargo holds, decks and outer hull are to be examined, and this examination is to be supplemented by Close-up Survey, thickness measurement and testing as deemed necessary, to ensure that the structural integrity remains effective.

6.4.2 The examination is to be sufficient to ascertain substantial corrosion, significant deformation, fractures, damages or other structural deterioration and, if deemed necessary by the Surveyor, suitable non-destructive examination may be required.

6.4.3 Where substantial corrosion, as defined in 1.5, is identified and is not rectified, this will be subject to re-examination at Annual and Intermediate Surveys.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 6

6.4.4 All piping systems within the tanks and spaces indicated in 6.4.1 are to be examined and tested under working conditions to ensure that the conditions remain satisfactory.

6.4.5 The extent of survey of combined salt-water ballast cargo holds is to be evaluated based on the records of ballast history, the extent and condition of the corrosion protection system provided, and the extent of structural diminution (corrosion).

6.4.6 Where salt-water ballast tanks have been converted to void spaces the survey extent is to be based upon salt-water ballast tank requirements.

6.4.7 Where provided, in association with a corrosion control (c.c.) notation as defined in the *Register Book*, the condition of the protective coating or corrosion prevention system is to be examined.

6.4.8 For ships fitted with water level detectors in cargo holds, ballast tanks forward of the collision bulkhead and any dry or void space which extends forward of the foremost cargo hold, an examination and a test of the water ingress detection systems and of their alarms is to be carried out.

6.4.9 For ships fitted with a means for draining and pumping ballast tanks forward of the collision bulkhead and the bilges of dry spaces, any part of which extends forward of the foremost cargo hold, an examination and a test of the draining and pumping systems including their controls is to be carried out.

## 6.5 Testing

6.5.1 The minimum requirements for tank testing, as applicable, are given in 5.3.5. Where required, the Surveyor may extend the tank testing if deemed necessary.

## 6.6 Close-up Survey

6.6.1 The minimum requirements for Close-up Survey are given in Table 3.6.1.

6.6.2 The Close-up Survey may be extended, as deemed necessary by the Surveyor, after taking into account the maintenance of the spaces under survey, the condition of the corrosion prevention system and where spaces have structural arrangements or details which have suffered defects in similar spaces or on similar ships according to available information.

6.6.3 For areas in tanks and cargo holds where coatings are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Surveys may be specially considered.

## 6.7 Thickness measurement

6.7.1 The minimum requirements for thickness measurements are given in Table 3.6.2, see also 5.4.

6.7.2 In areas where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out, as applicable, in accordance with Tables 3.6.4, 3.6.5, 3.6.6, 3.6.7, 3.6.8 and 3.6.9 to determine the full extent of the corrosion pattern. The survey will not be considered complete until these additional thickness measurements have been carried out.

6.7.3 Thickness measurement is required to determine both general and local levels of corrosion in salt-water ballast tanks and in the shell frames and their end attachments in all cargo holds. Thickness measurements are also to be carried out to determine the corrosion levels on the transverse bulkhead plating.

6.7.4 Single skin bulk carriers contracted for construction prior to 1 July 1998 are to undergo a re-assessment and evaluation of their cargo hold shell frames in accordance with the Provisional Rules for Existing Ships. The number of shell frames to be measured is equivalent to number of shell frames subject to close-up survey (see Table 3.6.1), with representative measurements to be taken at specific areas for each frame. The extent of thickness measurement may be specially considered by the Surveyor, provided the structural members indicate no thickness diminution with respect to the Rule thickness and the coating is found in 'as-new' condition (i.e. without breakdown or rusting). Repairs to shell frames are to be based upon the minimum thickness values shown in the evaluation records.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 6

**Table 3.6.1 Close-up Survey – Single skin bulk carriers**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
(1) 25% of shell frames and their end attachments in the forward cargo hold at representative positions. (2) Selected shell frames and their end attachments in remaining cargo holds. (3) 1 transverse web with associated plating and longitudinals in 2 representative water ballast tanks of each type (i.e. topside or hopper side tank). (4) 2 selected cargo hold transverse bulkheads, including internal structure of upper and lower stools, where fitted. This is to include the aft bulkhead of the forward hold. (5) All cargo hold hatch covers and coamings (plating and stiffeners).	(1a) For bulk carriers with a deadweight less than 100,000 tonnes, all shell frames in the forward cargo hold and 25% of frames in each of the remaining cargo holds, including their end attachments and adjacent shell plating. (1b) For bulk carriers with a deadweight equal to or greater than 100,000 tonnes, all shell frames in the forward cargo hold and 50% of frames in each of the remaining cargo holds, including their end attachments and adjacent shell plating. (2) 1 transverse web with associated plating and longitudinals in each water ballast tank. (3) Forward and aft transverse bulkhead in 1 side ballast tank, including stiffening system. (4) All cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted. (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) All deck plating and underdeck structure inside line of hatch openings between all cargo hold hatches.	(1) All shell frames in the forward and one other selected cargo hold and 50% of frames in each of the remaining cargo holds, including their end attachments and adjacent shell plating. (2) All transverse webs with associated plating and longitudinals in each water ballast tank. (3) All transverse bulkheads in ballast tanks, including stiffening system. (4) All cargo hold transverse bulkheads, including internal structure of upper and lower stools, where fitted. (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) All deck plating and underdeck structure inside line of hatch openings between all cargo hold hatches.	(1) All shell frames in all cargo holds, including their end attachments and adjacent shell plating. (2) All transverse webs with associated plating and longitudinals in each water ballast tank (i.e. topside, hopper side or side tank). (3) All transverse bulkheads in ballast tanks, including stiffening system. (4) All transverse webs with associated plating and longitudinals in each water ballast tank. (5) All cargo hold hatch covers and coamings (plating and stiffeners). (6) All deck plating and underdeck structure inside line of hatch openings between all cargo hold hatches.
<b>NOTES</b> The requirements in this Table apply to all single skin bulk carriers unless stated otherwise. 1. Ballast tank includes peak tanks. 2. Close-up Survey of transverse bulkheads to be carried out at four levels: Level (a) Immediately above the inner bottom and immediately above the line of gussets (if fitted) and shedders for ships without lower stool. Level (b) Immediately above and below the lower stool shelf plate (for those ships fitted with lower stools), and immediately above the line of the shedder plates. Level (c) About mid-height of the bulkhead. Level (d) Immediately below the upper deck plating and immediately adjacent to the upper wing tank and immediately below the upper stool shelf plate for those ships fitted with upper stools, or immediately below the topside tanks.			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 6

**Table 3.6.2 Close-up Survey – Double skin bulk carriers**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
<p>(1) 1 transverse web with associated plating and longitudinals in 2 representative water ballast tanks of each type. This is to include the foremost topside and double side ballast tanks on either side</p> <p>(2) 2 selected cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted</p> <p>(3) All cargo hold hatch covers and coamings (plating and stiffeners)</p>	<p>(1) 1 transverse web with associated plating and longitudinals in each water ballast tank</p> <p>(2) Forward and aft transverse bulkheads, including stiffening system, in a complete ballast tank, see Note 1</p> <p>(3) 25% of ordinary transverse web frames in the foremost double side tanks</p> <p>(4) One transverse bulkhead in each cargo hold including internal structure of upper and lower stools, where fitted</p> <p>(5) All cargo hold hatch covers and coamings (plating and stiffeners)</p> <p>(6) All deck plating and under-deck structure inside line of hatch openings between all cargo hold hatches</p>	<p>(1) All transverse webs with associated plating and longitudinals in each water ballast tank</p> <p>(2) All transverse bulkheads in ballast tanks, including stiffening system</p> <p>(3) 25% of ordinary transverse web frames in all double side tanks</p> <p>(4) All cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted</p> <p>(5) All cargo hold hatch covers and coamings (plating and stiffeners)</p> <p>(6) All deck plating and under-deck structure inside line of hatch openings between all cargo hold hatches</p>	<p>(1) All transverse webs with associated plating and longitudinals in each water ballast tank</p> <p>(2) All transverse bulkheads in ballast tanks, including stiffening system</p> <p>(3) All ordinary transverse web frames in all double side tanks</p> <p>(4) All cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted</p> <p>(5) All cargo hold hatch covers and coamings (plating and stiffeners)</p> <p>(6) All deck plating and under-deck structure inside line of hatch openings between all cargo hold hatches</p>
<p>NOTES</p> <p>1. Complete ballast tank means topside tank, hopper tank, double bottom tank and double side tank, even if these are separate.</p> <p>2. Ballast Tank includes peak tanks.</p> <p>3. Close-up survey of transverse bulkheads to be carried out at four levels:</p> <p>Level (a) Immediately above the inner bottom and immediately above the line of gussets (if fitted) and shedders for ships with out lower stool.</p> <p>Level (b) Immediately above and below the lower stool shelf plate (for those ships fitted with lower stools), and immediately above the line of the shedder plates.</p> <p>Level (c) About mid-height of the bulkhead.</p> <p>Level (d) Immediately below the upper deck plating and immediately adjacent to the upper wing tank and immediately below the upper stool shelf plate for those ships fitted with upper stools, or immediately below the topside tanks.</p>			

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 6

**Table 3.6.3 Thickness measurement – Single skin and double skin bulk carriers**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
<p>(1) Measurement, for general assessment and recording of corrosion pattern, of those structural members subject to Close-up Survey in accordance with Table 3.6.1 or Table 3.6.2.</p> <p>(2) Critical areas, as required by the Surveyor.</p>	<p>(1) Within the cargo length area:</p> <p>(a) Each deck plate outside line of cargo hatch openings.</p> <p>(b) 2 transverse sections, outside line of cargo hatch openings. (A minimum of 1 of the above transverse sections is to be within 0,5L amidships).</p> <p>(2) Measurement, for general assessment and recording of corrosion pattern, of those structural members subject to Close-up Survey in accordance with Table 3.6.1 or Table 3.6.2.</p> <p>(3) All wind and water strakes within the cargo length area.</p> <p>(4) Selected wind and water strakes outside the cargo length area.</p> <p>(5) All cargo hatch covers and coamings (plating and stiffeners).</p> <p>(6) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank see Notes 1 and 3.</p> <p>(7) The aft bulkhead of the forward cargo hold on single skin ships (see Note 4).</p> <p>(8) Cargo hold shell frames on single skin ships, see Note 5.</p> <p>(9) Critical areas, as required by the Surveyor.</p>	<p>(1) Within the cargo length area:</p> <p>(a) Each deck plate outside line of cargo hatch openings.</p> <p>(b) 3 transverse sections, outside line of cargo hatch openings. (A minimum of 2 of the above transverse sections is to be within 0,5L amidships).</p> <p>(c) Each bottom plate.</p> <p>(2) Measurement, for general assessment and recording of corrosion pattern, of those structural members subject to Close-up Survey in accordance with Table 3.6.1 or Table 3.6.2.</p> <p>(3) All wind and water strakes over the full length of the ship, port and starboard.</p> <p>(4) All cargo hatch covers and coamings (plating and stiffeners).</p> <p>(5) Remaining exposed main deck plates not considered in item (1) and representative exposed superstructure deck plating (i.e. poop, bridge and forecastle deck).</p> <p>(6) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 1 and 3.</p> <p>(7) All keel plates outside the cargo length area. Also additional bottom plates in way of cofferdams. Machinery space and aft end of tanks.</p> <p>(8) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor.</p> <p>(9) The aft bulkhead of the forward cargo hold on single skin ships (see Note 4).</p> <p>(10) Cargo hold shell frames on single skin ships, see Note 5.</p> <p>(11) Critical areas, as required by the Surveyor.</p>
Special Survey II (Ships 10 years old)		
<p>(1) Within the cargo length area:</p> <p>(a) 2 sections of deck plating outside line of cargo hatch openings.</p> <p>(2) Measurement, for general assessment and recording of corrosion pattern, of those structural members subject to Close-up Survey in accordance with Table 3.6.1 or Table 3.6.2.</p> <p>(3) Wind and water strakes in way of the transverse sections considered in item (1).</p> <p>(4) Cargo hold shell frames on single skin ships, see Note 5.</p> <p>(5) Critical areas, as required by the Surveyor.</p>		

## NOTES

The requirements in this table apply to both single skin and double skin ships unless stated otherwise.

- For areas in spaces where coatings are found to be in GOOD condition, as defined in 1.5, the extent of thickness measurement may be specially considered. Prior to any coating or re-coating of cargo holds, scantlings are to be confirmed by thickness measurement with the Surveyor in attendance.
- Transverse sections should be chosen where the largest reductions are likely to occur, or as revealed by deck plating measurement.
- Transverse bulkhead complete including stiffening system.
- For ships assigned the notation ESN, the corrugated part of the aft transverse bulkhead of the forward cargo hold is to be subject to thickness measurement. This is to include each vertical corrugation at its lower and middle level including shedder plates and gusset plates, where applicable.
- Single skin bulk carriers contracted for construction prior to 1 July 1998 are to undergo a re-assessment of their cargo hold shell frames in accordance with the Provisional Rules for Existing Ships. The number of shell frames to be measured is equivalent to the number of shell frames subject to Close-up survey (see Table 3.6.1), with representative measurements to be taken at specific areas for each frame.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 6

**Table 3.6.4 Thickness measurement – Single skin bulk carriers – Shell plating and stiffening, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Bottom and side shell plating	Suspect plate, plus four adjacent plates	5 point pattern for each panel between longitudinals
(2) Bottom/side shell longitudinals	Minimum of three longitudinals in way of suspect areas	3 measurements in line across web and 3 measurements on flange
(3) Side shell frames	Suspect frame and each adjacent	(a) At each end and mid-span: 5 point pattern on both web and flange (b) 5 point pattern within 25 mm of welded attachment to both shell and hopper sloping plate

**Table 3.6.5 Thickness measurement – Single skin bulk carriers – Double bottom and hopper structure, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Inner bottom plating	Suspect plate plus all immediately adjacent plates	5 point pattern for each panel between longitudinals over 1 m length
(2) Inner bottom longitudinals	Three longitudinals in way of plates measured	3 measurements in line across web and 3 measurements on flange
(3) Transverse floors and longitudinal girders	Suspect plates	5 point pattern over approximately 1 m <sup>2</sup> of plating
(4) Watertight floors and girders	(a) lower 1/3 of tank (b) upper 2/3 of tank	(a) 5 point pattern over 1 m <sup>2</sup> of plating (b) 5 point pattern alternate plates over 1 m <sup>2</sup> of plating
(5) Transverse web frames	Suspect plate	5 point pattern over 1 m <sup>2</sup> of plating

**Table 3.6.6 Thickness measurement – Single skin and double skin bulk carriers – Transverse bulkheads in cargo holds, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Lower stool	(a) Transverse band within 25 mm of welded connection to inner-bottom (b) Transverse band within 25 mm of welded connection to shelf plate	(a) 5 point pattern between stiffeners over 1 m length (b) as above
(2) Transverse bulkhead	(a) Transverse band immediately above lower stool shelf plate (b) Transverse band at approximately mid-height (c) Transverse band at part of bulkhead adjacent to upper deck or below upper stool shelf plate (for those ships fitted with upper stools)	(a) 5 point pattern over 1 m length (b) 5 point pattern over 1 m <sup>2</sup> of plating (c) 5 point pattern over 1 m <sup>2</sup> of plating

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 6

**Table 3.6.7 Thickness measurement – Single skin and double skin bulk carriers – Deck structure including cross strips, main cargo hatchways, hatch covers, coamings and topside tanks, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Cross deck strip plating	Suspect cross deck strip plating	5 point pattern between underdeck stiffeners over 1 m length
(2) Underdeck stiffeners	(a) Transverse members (b) Longitudinal member	(a) 5 point pattern at each end and mid-span (b) 5 point pattern on both web and flange
(3) Hatch covers	(a) Each side and end plate 3 locations (b) Top plate, 3 longitudinal bands – 2 on outboard strakes and 1 on centreline strake	(a) 5 point pattern at each location (b) 5 point measurement at each band
(4) Hatch coamings	Each side and end of coaming, one upper and one lower band	5 point measurement at each band
(5) Topside salt water ballast tanks	(a) Watertight transverse bulkheads (i) lower 1/3 of bulkhead (ii) upper 2/3 of bulkhead (iii) stiffeners (b) Swash transverse bulkheads (i) lower 1/3 of bulkhead (ii) upper 2/3 of bulkhead (iii) stiffeners (c) 3 representative bays of the topside sloping plate (i) lower 1/3 of tank (ii) upper 2/3 of tank (d) suspect longitudinals and adjacent longitudinals	(i) 5 point pattern over 1 m <sup>2</sup> of plating (ii) 5 point pattern over 1 m <sup>2</sup> of plating (iii) 5 point pattern over 1 m length  (i) 5 point pattern over 1 m <sup>2</sup> of plating (ii) 5 point pattern over 1 m <sup>2</sup> of plating (iii) 5 point pattern over 1 m length  (i) 5 point pattern over 1 m <sup>2</sup> of plating (ii) 5 point pattern over 1 m <sup>2</sup> of plating  5 point pattern both web and flange over 1 m length
(6) Main deck plating	Suspect plates and 4 immediately adjacent plates	5 point pattern over 1 m <sup>2</sup> of plating
(7) Main deck longitudinals	Minimum of 3 longitudinals where plating measured	5 point pattern on both web and flange over 1 m length
(8) Web frames/transverses	Suspect plates	5 point pattern over 1 m <sup>2</sup> of plating

**Table 3.6.8 Thickness measurement – Double skin bulk carriers – Bottom, inner bottom and hopper structure, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Bottom, inner bottom and hopper structure plating	(a) Minimum of 3 bays across double bottom tank, including aft bay (b) Measurements around and under all suction bell mouths	5 point pattern for each panel between longitudinals and floors
(2) Bottom, inner bottom and hopper structure longitudinals	Minimum of 3 longitudinals in each bay where bottom plating measured	3 measurements in line across flange and 3 measurements on the vertical web
(3) Bottom girders, including watertight girders	At fore and aft watertight floors and in centre of tanks	Vertical line of single measurements on girder plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements
(4) Bottom floors, including watertight floors	3 floors in the bays where bottom plating measured, with measurements at both ends and middle	5 point pattern over 2 m <sup>2</sup> area
(5) Hopper structure web frame ring	3 floors in bays where bottom plating measured	5 point pattern over 1 m <sup>2</sup> of plating and single measurements on flange
(6) Hopper structure transverse watertight bulkhead or swash bulkhead	(a) lower 1/3 of bulkhead (b) upper 2/3 of bulkhead (c) stiffeners (minimum of 3)	(a) 5 point pattern over 1 m <sup>2</sup> of plating (b) 5 point pattern over 2 m <sup>2</sup> of plating (c) For web, 5 point pattern over span (2 measurements across web at each end and 1 at centre of span). For flange, single measurements at each end and centre of span
(7) Panel stiffening	Where applicable	Single measurements

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 6 & 7

**Table 3.6.9 Thickness measurement – Double skin bulk carriers – Double side ballast tank structure, with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Side shell and inner plating: (i) Upper strake and strakes in way of horizontal girders (ii) All other strakes	(i) Plating between each pair of transverse frames/longitudinals in a minimum of 3 bays along the tank (ii) Plating between every third pair of longitudinals in same 3 bays	(i) Single measurement (ii) Single measurement
(2) Side shell and inner side transverse frames/longitudinals on: (i) Upper strake (ii) All other strakes	(i) Each transverse frame/longitudinal in same 3 bays (ii) Every third transverse frame/longitudinal in same 3 bays	(i) 3 measurements across web and 1 measurement on flange (ii) 3 measurements across web and 1 measurement on flange
(3) Transverse frames/longitudinals – brackets	Minimum of 3 at top, middle and bottom of tank in same 3 bays	5 point pattern over area of bracket
(4) Vertical web and transverse bulkheads: (i) Strakes in way of horizontal girders (ii) Other strakes	(i) Minimum of 2 webs and both transverse bulkheads (ii) Minimum of 2 webs and both transverse bulkheads	(i) 5 point pattern over approx. 2 m <sup>2</sup> area (ii) 2 measurements between each pair of vertical stiffeners
(5) Horizontal girders	Plating on each girder in a minimum of 3 bays	2 measurements between each pair of longitudinal girder stiffeners
(6) Panel stiffening	Where applicable	Single measurements

## Section 7

### Special Survey – Oil tankers (including ore/oil ships and ore/bulk/oil ships) – Hull requirements

#### 7.1 General

7.1.1 The requirements of Sections 2, 4 and 5 are to be complied with as applicable.

7.1.2 In order to maintain and/or assign the **ESP** notation, the following requirements apply to the surveys of the hull structure and piping systems in way of the cargo tanks/cargo holds, pump rooms, cofferdam, pipe tunnels, void spaces, double bottom tanks, etc., in way of the cargo tank area and all salt-water ballast tanks.

#### 7.2 Documentation

7.2.1 The Owner is to maintain documentation on board as follows:

- A survey file comprising reports of structural surveys, thickness measurement and executive hull summary in accordance with IMO Resolution A.744(18).
- Supporting documentation consisting of:
  - Main structural plans of cargo tanks/cargo holds and ballast tanks.
  - Previous repair history.
  - Cargo and ballast history.
  - Reports on structural defects/deterioration in general.

- Reports on leakage in bulkheads and piping systems.
- Condition of corrosion prevention system, if any.
- Extent of use of inert gas plant and tank cleaning procedures when forming part of approved corrosion control system.
- Information that may help to identify critical areas.
- Survey Programme as required by 7.3.

The complete documentation in 7.2.1 is to be readily available for examination by the Surveyor and should be used as a basis for survey.

7.2.2 The documentation is to be kept on board for the lifetime of the ship.

#### 7.3 Planning for survey

7.3.1 A Survey Programme is to be submitted by the Owner and is to include the proposals for survey, including the means of providing access for Close-up Survey, thickness measurement and tank testing and should take account of the information detailed in 7.2.1.

7.3.2 Prior to the development of the Survey Programme a Survey Planning Questionnaire is to be completed and submitted by the Owner, see 1.6.9.



# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

### 7.4 Overall Survey

7.4.1 All cargo tanks/cargo holds, and salt-water ballast tanks including double bottom tanks, pump rooms, pipe tunnels, cofferdams and void spaces bounding cargo tanks/cargo holds, deck and outer hull are to be examined, and this examination is to be supplemented by Close-up Survey, thickness measurement and testing as deemed necessary, to ensure that the structural integrity remains effective.

7.4.2 The examination is to be sufficient to ascertain substantial corrosion, significant deformation, fractures, damages or other structural deterioration and, if deemed necessary by the Surveyor, suitable non-destructive examination may be required.

7.4.3 Where substantial corrosion, as defined in 1.5, is identified and is not rectified, this will be subject to re-examination at Annual and/or Intermediate Surveys. In the case of salt-water ballast tanks and combined tanks for the carriage of salt-water ballast and cargo oil, the examination will be required at Annual Survey and Intermediate Survey. In the case of cargo oil tanks the examination will be required at Intermediate Surveys.

7.4.4 All cargo piping on deck, including Crude Oil Washing (COW) piping, and cargo and ballast piping within those spaces indicated in 7.4.1 are to be examined and tested under working conditions to ensure that tightness and condition remain satisfactory. Special attention is to be given to ballast piping in cargo tanks and any cargo piping in ballast tanks and void spaces.

7.4.5 Where salt-water ballast tanks have been converted to void spaces the survey extent is to be based upon salt-water ballast tank requirements.

7.4.6 Where provided, in association with a corrosion control (c.c.) notation as defined in the *Register Book*, the condition of the protective coating or corrosion prevention system of cargo tanks is to be examined.

7.4.7 The attachment to the structure and condition of anodes in tanks are to be examined.

7.4.8 Where fitted, the strums of the cargo suction pipes are to be removed or lifted to facilitate examination of the shell plating and bulkheads in the vicinity, unless other means for visual inspection of these parts are provided.

### 7.5 Testing

7.5.1 The minimum tank testing requirements are given in Table 3.7.1 and, where required, the Surveyor may extend the tank testing if deemed necessary. The remaining requirements for tank testing, as applicable, are given in 5.3.5.

### 7.6 Close-up Survey

7.6.1 The minimum requirements for Close-up Survey are given in Table 3.7.2 (Single hull oil tankers), Table 3.7.3 (Double hull oil tankers), Table 3.7.4 (Ore/oil ships) and Table 3.7.5 (Ore/bulk/oil ships).

7.6.2 The Surveyor may extend the Close-up Survey, if deemed necessary, taking into account the maintenance of the tanks under survey, the condition of the corrosion prevention system, and the following:

- Structural arrangements or details which have suffered defects in similar spaces or on similar ships.
- Spaces which have structures approved with reduced scantlings in association with an approved corrosion control system (c.c.).

7.6.3 For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Surveys may be specially considered.

### 7.7 Thickness measurement

7.7.1 The minimum requirements for thickness measurements are given in Table 3.7.6 (Single and double hull oil tankers, including ore/oil ships and ore/bulk/oil ships), see also 5.4.

7.7.2 In areas where substantial corrosion, as defined in 1.5, has been noted then additional measurements are to be carried out, as applicable, in accordance with Tables 3.7.7, 3.7.8, 3.7.9, 3.7.10, 3.7.11, 3.7.12, 3.7.13, 3.7.14 and 3.7.15 to determine the full extent of the corrosion pattern. The survey will not be considered complete until these additional thickness measurements have been carried out.

7.7.3 For **oil tankers** (including ore/oil and ore/bulk/oil ships) of 130 m in length and upwards (as defined by the International Convention on Load Lines in force), the ship's longitudinal strength is to be evaluated by using the thickness of structural members measured, renewed and reinforced as appropriate, during the Special Surveys carried out after the ship reaches 10 years of age.

**Table 3.7.1 Tank testing requirements – Single hull and double hull oil tankers, ore/oil ships and ore/bulk/oil ships**

Special Survey I (Ships 5 years old)	Special Survey II and subsequent (Ships 10 years old and over)
All ballast tank boundaries	All ballast tank boundaries
Cargo tank boundaries facing ballast tanks, void spaces, pipe tunnels, pump rooms or cofferdams	All cargo tank bulkheads

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 7

**Table 3.7.2 Close-up Survey – Single hull oil tankers**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
<p>(1) One web frame ring – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 1</p> <p>(2) One deck transverse – in a cargo tank, see Note 2</p> <p>(3) One transverse bulkhead, see Note 4: (a) in a ballast tank (b) in a cargo wing tank (c) in a cargo centre tank</p>	<p>(1) All web frame rings – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 1</p> <p>(2) One deck transverse, see Notes 2 and 8: (a) in each of the remaining ballast tanks, if any (b) in a cargo wing tank (c) in 2 cargo centre tanks</p> <p>(3) Both transverse bulkheads – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 3</p> <p>(4) One transverse bulkhead, see Note 4: (a) in each remaining ballast tank (b) in a cargo wing tank (c) in 2 cargo centre tanks</p>	<p>(1) All web frame rings, see Note 1: (a) in all ballast tanks (b) in a cargo wing tank</p> <p>(2) A minimum of 30% of all web frame rings in each remaining cargo wing tank, see Notes 1 and 8</p> <p>(3) All transverse bulkheads – in all cargo and ballast tanks, see Note 3</p> <p>(4) A minimum of 30% of deck and bottom transverses in each cargo centre tank, see Notes 5 and 8.</p> <p>(5) As considered necessary by the Surveyor, see Note 6</p>	<p>(1) As Special Survey III</p> <p>(2) Additional transverse areas if deemed necessary by the Surveyor</p>
<p><b>NOTES</b></p> <p>1. Complete transverse web frame ring including adjacent structural members.</p> <p>2. Deck transverse including adjacent deck structural members.</p> <p>3. Transverse bulkhead complete, including girder system and adjacent members, and adjacent longitudinal bulkhead structure.</p> <p>4. Transverse bulkhead lower part including girder system and adjacent structural members.</p> <p>5. Deck and bottom transverse including adjacent structural members.</p> <p>6. Additional complete transverse web frame ring.</p> <p>7. Ballast tank includes peak tanks.</p> <p>8. Within the mid 0,5 length of the tank. The 30% is to be rounded up to the next whole number of structural items.</p>			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.3 Close-up Survey – Double hull oil tankers**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
<p>(1) One web frame ring in a complete ballast tank, see Notes 1 and 3</p> <p>(2) One deck transverse in a cargo tank, see Notes 4 and 12</p> <p>(3) One transverse bulkhead in a complete ballast tank, see Notes 1 and 6</p> <p>(4) One transverse bulkhead in a cargo centre tank, see Notes 2 and 7</p> <p>(5) One transverse bulkhead in a cargo wing tank, see Note 7</p>	<p>(1) All web frame rings in a complete ballast tank, see Notes 1 and 3</p> <p>(2) The knuckle area and the upper part (approx. 5 m) of one web frame ring in each remaining ballast tank, see Note 8</p> <p>(3) One deck transverse in two cargo tanks, see Note 4</p> <p>(4) One transverse bulkhead in each complete ballast tank, see Notes 1 and 6</p> <p>(5) One transverse bulkhead in two cargo centre tanks, see Notes 2 and 7</p> <p>(6) One transverse bulkhead in a cargo wing tank, see Note 7</p>	<p>(1) All web frame rings in all ballast tanks, see Note 3</p> <p>(2) All web frame rings in a cargo tank, see Note 9</p> <p>(3) One web frame ring in each remaining cargo tank, see Note 9</p> <p>(4) All transverse bulkheads – in all cargo and ballast tanks, see Notes 5 and 6</p> <p>(5) As considered necessary by the Surveyor, see Note 10</p>	<p>(1) As Special Survey III</p> <p>(2) Additional transverse areas if deemed necessary by the Surveyor, see Note 10</p>
<p><b>NOTES</b></p> <p>1. Complete ballast tank means double bottom tank plus the double side tank and the double deck tank, as applicable, even if these are separate.</p> <p>2. Where there are no centre tanks, the transverse bulkheads in wing tanks are to be subject to Close-up Survey.</p> <p>3. Web frame ring in a ballast tank includes the vertical web in side tank, hopper web in hopper tank, floor in double bottom tank and deck transverse in a double deck tank and adjacent structural members. In peak tanks a web frame means a complete transverse web frame, including adjacent structural members.</p> <p>4. Deck transverse including adjacent deck structural members (or external structure on deck in way of the tank, where applicable).</p> <p>5. Transverse bulkhead complete in cargo tanks, including girder system, adjacent structural members (including longitudinal bulkheads) and internal structure of lower and upper stools, where fitted.</p> <p>6. Transverse bulkhead complete in ballast tanks, including girder system and adjacent structural members including longitudinal bulkheads, girders in double bottom tanks, inner bottom plating, hopper side, connecting brackets.</p> <p>7. Transverse bulkhead lower part in cargo tanks, including girder system, adjacent structural members (including longitudinal bulkheads) and internal structure of lower stool, where fitted.</p> <p>8. The knuckle area and the upper part (approximately 5 m), including adjacent structural members. Knuckle area is the area of the web frame around the connections of the sloping hopper plating to the inner hull bulkhead and the inner bottom plating, up to 2 m from the corners both on the bulkhead and the double bottom.</p> <p>9. Web frame ring in cargo tank includes deck transverse, longitudinal bulkhead vertical girder and cross ties, where fitted, and adjacent structural members.</p> <p>10. Additional complete transverse web frame ring.</p> <p>11. Ballast tanks include peak tanks.</p> <p>12. Within the mid 0,5 length of the tank.</p>			

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 7

**Table 3.7.4 Close-up Survey – Ore/oil ships**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
<p>(1) One web frame ring – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 1</p> <p>(2) One deck transverse – in a cargo tank, see Note 2</p> <p>(3) One transverse bulkhead, see Note 4: (a) in a ballast tank (b) in a cargo wing tank (c) in a cargo centre tank</p>	<p>(1) All web frame rings – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 1</p> <p>(2) One deck transverse, see Notes 2 and 6: (a) in each of the remaining ballast tanks, if any (b) in a cargo wing tank (c) in 2 cargo centre tanks</p> <p>(3) Both transverse bulkheads – in a wing ballast tank, if any, or a cargo wing tank used primarily for water ballast, see Note 3</p> <p>(4) One transverse bulkhead, see Note 4: (a) in each remaining ballast tank (b) in a cargo wing tank (c) in 2 cargo centre tanks</p> <p>(5) Selected cargo hold hatch covers and coamings (plating and stiffeners)</p> <p>(6) Selected areas of deck plating inside line of hatch openings between cargo hold hatches</p>	<p>(1) All web frame rings, see Note 1: (a) in all ballast tanks (b) in a cargo wing tank</p> <p>(2) One web frame ring – in each remaining cargo wing tank, see Notes 1 and 6</p> <p>(3) One deck transverse – in each cargo centre tank, see Notes 2 and 6</p> <p>(4) All transverse bulkheads– in all cargo and ballast tanks, see Note 3</p> <p>(5) All cargo hold hatch covers and coamings (plating and stiffeners)</p> <p>(6) All deck plating inside line of hatch coamings between cargo hold hatches</p> <p>(7) As considered necessary by the Surveyor, see Note 5</p>	<p>(1) As Special Survey III</p> <p>(2) Additional transverse areas if deemed necessary by the Surveyor</p>
<p>NOTES</p> <p>1. Complete transverse web frame ring including adjacent structural members.</p> <p>2. Deck transverse including adjacent deck structural members.</p> <p>3. Transverse bulkhead complete, including girder system and adjacent members, and adjacent longitudinal bulkhead structure.</p> <p>4. Transverse bulkhead lower part including girder system and adjacent structural members.</p> <p>5. Additional complete transverse web frame ring.</p> <p>6. Within the mid 0,5 length of the tank.</p>			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.5 Close-up Survey – Ore/bulk/oil ships**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
(1) 25% of shell frames and their end attachments in the forward cargo hold at representative positions (2) Selected frames and their end attachments in remaining cargo holds (3) 1 transverse web with associated plating and longitudinals in 2 representative water ballast tanks of each (i.e. topside, hopper side or side tank) (4) 2 selected cargo hold transverse bulkheads including internal structure of upper and lower stools where fitted. This is to include the aft bulkhead in the forward cargo hold	(1) 25% of shell frames including their end attachments and adjacent shell plating in all cargo holds (2) 1 transverse web with associated plating and longitudinals in each water ballast tank (i.e. topside, hopper side or side tank) (3) Forward and aft transverse bulkhead in 1 side ballast tank, including stiffening system (4) 1 transverse bulkhead in each cargo hold including internal structure of upper and lower stools where fitted. This is to include the aft bulkhead in the forward cargo hold (5) Selected cargo hold hatch covers and coamings (plating and stiffeners) (6) Selected areas of deck plating inside line of hatch openings between cargo hold hatches	(1) All shell frames in the forward cargo hold and 25% of frames in remaining cargo holds, including their end attachments and adjacent shell plating (2) All transverse webs with associated plating and longitudinals in each water ballast tank (i.e. topside, hopper side or side tank) (3) All transverse bulkheads in ballast tanks, including stiffening system (4) All cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted (5) All cargo hold hatch covers and coamings (plating and stiffeners) (6) All deck plating inside line of hatch openings between cargo hold hatches	(1) All shell frames including their end attachments and adjacent shell plating in all cargo holds (2) All transverse webs with associated plating and longitudinals in each water ballast tank (i.e. topside, hopper side or side tank) (3) All transverse bulkheads in ballast tanks, including stiffening system (4) All cargo hold transverse bulkheads including internal structure of upper and lower stools, where fitted (5) All cargo hold hatch covers and coamings (plating and stiffeners) (6) All deck plating inside line of hatch openings between cargo hold hatches
<b>NOTES</b> 1. Ballast tank includes peak tanks. 2. Close-up Survey of transverse bulkheads to be carried out at four levels: Level (a) Immediately above the inner bottom and immediately above the line of gussets (if fitted) and shedders for ships without lower stool. Level (b) Immediately above and below the lower stool shelf plate (for those ships fitted with lower stools), and immediately above the line of the shedder plates. Level (c) About mid-height of the bulkhead. Level (d) Immediately below the upper deck plating and immediately adjacent to the upper wing tank and immediately below the upper stool shelf plate for those ships fitted with upper stools, or immediately below the topside tanks.			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.6 Thickness measurement – Single hull and double hull oil tankers, ore/oil ships and ore/bulk/oil ships**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
(1) 1 section of deck plating for the full beam of the ship within 0,5L amidships in way of a ballast tank, if any, or a cargo tank used primarily for water ballast. (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.7.2, Table 3.7.3, Table 3.7.4 or Table 3.7.5. (3) Critical areas, as required by the Surveyor.	(1) Within the cargo area: (a) Each deck plate. (b) 2 transverse sections, see Note 6. (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.7.2, Table 3.7.3, Table 3.7.4 or Table 3.7.5. (3) Selected wind and water strakes outside the cargo area. (4) All wind and water strakes within the cargo area. (5) All cargo hold hatch covers and coamings (plating and stiffeners), see Note 5. (6) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank, see Notes 1 and 4. (7) Critical areas, as required by the Surveyor.	(1) Within the cargo area: (a) Each deck plate. (b) 3 transverse sections, see Note 6. (c) Each bottom plate. (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.7.2, Table 3.7.3, Table 3.7.4 or Table 3.7.5. (3) All wind and water strakes over the full length of the ship, port and starboard. (4) All cargo hold hatch covers and coamings (plating and stiffeners), see Note 5. (5) Remaining exposed main deck plating not considered in item (1) and representative exposed superstructure deck plating (i.e. poop, bridge and forecastle deck). (6) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 1 and 4. (7) All keel plates outside the cargo tank length. Also additional bottom plates in way of cofferdams, machinery space and aft end of tanks. (8) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor. (9) Critical areas, as required by the Surveyor.
Special Survey II (Ships 10 years old)		
(1) Within the cargo area: (a) Each deck plate. (b) 1 transverse section, see Note 6. (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.7.2, Table 3.7.3, Table 3.7.4 or Table 3.7.5. (3) Selected wind and water strakes outside the cargo area. (4) Critical areas, as required by the Surveyor.		
<b>NOTES</b> 1. For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of thickness measurements may be specially considered. 2. Transverse sections should be chosen where the largest reductions are likely to occur, or as revealed by deck plating measurements. 3. Where two or three transverse sections are required to be measured, at least one is to include a ballast tank within 0,5L amidships. 4. Transverse bulkhead complete including stiffening system. 5. All cargo hold hatch covers and coamings, where fitted, are to be measured on ore/oil and ore/bulk/oil ships. 6. For oil tankers (including ore/oil and ore/bulk/oil ships), with length $\geq 130$ m and over 10 years of age, the longitudinal strength is to be evaluated. In such cases, a minimum of three transverse sections are to be measured within 0,5L amidships.		

**Table 3.7.7 Thickness measurement – Single hull oil tankers, ore/oil ships and ore/bulk/oil ships – Bottom structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Bottom plating	Minimum of 3 bays across tank, including aft bay Measurement around and under all suction strums	5 point pattern for each panel between longitudinals and webs
(2) Bottom longitudinals	Minimum of 3 longitudinals in each bay where bottom plating measured	3 measurements in line across flange and 3 measurements on vertical web
(3) Bottom girders and brackets	At fore and aft transverse bulkhead, bracket toes and in centre of tanks	Vertical line of single measurements on web plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements. 2 measurements across face flat. 5 point pattern on girder/bulkhead brackets
(4) Bottom transverse webs	3 webs in bays where bottom plating measured, with measurements at middle and both ends	5 point pattern over 2 m <sup>2</sup> area. Single measurements on face flat
(5) Panel stiffening	Where applicable	Single measurements

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.8 Thickness measurement – Single hull oil tankers, ore/oil ships and ore/bulk/oil ships – Deck structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deck plating	2 bands across tank	Minimum of 3 measurements per plate per band
(2) Deck longitudinals	Minimum of 3 longitudinals in each of 2 bays	3 measurements in line vertically on webs and 2 measurements on flange (if fitted)
(3) Deck girders and brackets	At fore and aft transverse bulkhead, bracket toes and in centre of tanks	Vertical line of single measurements on web plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements. 2 measurements across face flat. 5 point pattern on girder/bulkhead brackets
(4) Deck transverse webs	Minimum of 2 webs with measurement at both ends and middle of span	5 point pattern over 2 m <sup>2</sup> area. Single measurements on face flat
(5) Panel stiffening	Where applicable	Single measurements

**Table 3.7.9 Thickness measurement – Single hull oil tankers, ore/oil ships and ore/bulk/oil ships – Shell and longitudinal bulkheads with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deckhead and bottom strakes and strakes in way of stringer platforms	Plating between each pair of longitudinals in a minimum of 3 bays	Single measurement
(2) All other strakes	Plating between every 3rd pair of longitudinals in same 3 bays	Single measurement
(3) Longitudinals – deckhead and bottom strakes	Each longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(4) Longitudinals – all others	Every third longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(5) Longitudinals – bracket	Minimum of 3 at top, middle and bottom of tank in same 3 bays	5 point pattern over area of bracket
(6) Web frames and cross ties	3 webs with minimum of 3 locations on each web, including in way of cross tie connections	5 point pattern over 2 m <sup>2</sup> area, plus single measurements on web frame and cross tie face flats

**Table 3.7.10 Thickness measurement – Single hull oil tankers, ore/oil ships and ore/bulk/oil ships – Transverse bulkheads and swash bulkheads with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deckhead and bottom strakes in way of stringer platforms	Plating between pair of stiffeners at 3 locations: approx. 1/4, 1/2 and 3/4 width of tank	5 point pattern between stiffeners over 1 m length
(2) All other strakes	Plating between pair of stiffeners at middle location	Single measurement
(3) Strakes in corrugated bulkheads	Plating for each change of scantling at centre of panel and at flange or fabricated connection	5 point pattern over 1 m <sup>2</sup> of plating
(4) Stiffeners	Minimum of 3 typical stiffeners	For web, 5 point pattern over span between bracket connections (2 measurements across web at each bracket connection and one at centre of span). For flange, single measurements at each bracket toe and at centre of span
(5) Brackets	Minimum of 3 at top, middle and bottom of tank	5 point pattern over area of bracket
(6) Deep webs and girders	Measurements at toe of bracket and at centre of span	For web, 5 point pattern over 1 m <sup>2</sup> area. 3 measurements across face flat
(7) Stringer platforms	All stringers with measurements at middle and both ends	5 point pattern over 1 m <sup>2</sup> area plus single measurements near bracket toes and on face flats

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.11 Thickness measurement – Double hull oil tankers – Bottom, inner bottom and hopper structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Bottom, inner bottom and hopper plating	Minimum of 3 bays across double bottom tank, including aft bay. Measurement around and under all suction strums	5 point pattern for each panel between longitudinals and floors
(2) Bottom, inner bottom and hopper longitudinals	Minimum of 3 longitudinals in each bay where bottom plating measured	3 measurements in line across flange and 3 measurements on vertical web
(3) Bottom girders, including watertight girders	At the fore and aft watertight floors and in centre of tanks	Vertical line of single measurements on girder plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements
(4) Bottom floors, including watertight floors	3 floors in bays where bottom plating measured, with measurements at both ends and middle	5 point pattern over 2 m <sup>2</sup> area
(5) Hopper web frame ring	3 floors in bays where bottom plating measured	5 point pattern over 1 m <sup>2</sup> of plating. Single measurements on flange
(6) Hopper transverse watertight bulkhead or swash bulkhead	(i) Lower 1/3 of bulkhead (ii) Upper 2/3 of bulkhead (iii) Stiffeners (minimum of 3)	(i) 5 point pattern over 1 m <sup>2</sup> of plating. (ii) 5 point pattern over 2 m <sup>2</sup> of plating. (iii) For web, 5 point pattern over span (2 measurements across web at each end and 1 at centre of span). For flange, single measurement at each end and centre of span.
(7) Panel stiffening	Where applicable	Single measurements

**Table 3.7.12 Thickness measurement – Double hull oil tankers – Deck structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deck plating	2 transverse bands across tank	Minimum of 3 measurements per plate per band
(2) Deck longitudinals	Every 3rd longitudinal in each of 2 bands with a minimum of 1 longitudinal	3 measurements in line vertically on webs and 2 measurements on flange (if fitted)
(3) Deck girders and brackets (usually in cargo tanks only)	At the fore and aft transverse bulkhead, bracket toes and in centre of tanks	Vertical line of single measurements on web plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements. 2 measurements across flange. 5 point pattern on girder / bulkhead brackets
(4) Deck transverse webs	Minimum of 2 webs, with measurements at both ends and middle of span	5 point pattern over 1 m <sup>2</sup> area. Single measurements on the flange
(5) Vertical web and transverse bulkhead in wing ballast tank (two metres from deck)	Minimum of 2 webs, and both transverse bulkheads	5 point pattern over 1 m <sup>2</sup> area
(6) Panel stiffening	Where applicable	Single measurements



# Periodical Survey Regulations

## Part 1, Chapter 3

Section 7

**Table 3.7.13 Thickness measurement – Double hull oil tankers – Wing ballast tank structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Side shell and longitudinal bulkhead plating: (i) Upper strake and strakes in way of horizontal girders (ii) All other strakes	(i) Plating between each pair of longitudinals in a minimum of 3 bays (along the tank) (ii) Plating between every 3rd pair of longitudinals on same 3 bays	(i) Single measurements (ii) Single measurements
(2) Side shell and longitudinal bulkhead longitudinals on: (i) Upper strake (ii) All other strakes	(i) Each longitudinal in same 3 bays (ii) Every 3rd longitudinal in same 3 bays	(i) 3 measurements across web and 1 measurement on flange (ii) 3 measurements across web and 1 measurement on flange
(3) Longitudinals – brackets	Minimum of 3 at top, middle and bottom of tank in same 3 bays	5 point pattern over area of bracket
(4) Vertical web and transverse bulkheads (excluding deckhead area): (i) Strakes in way of horizontal girders (ii) Other strakes	(i) Minimum of 2 webs and both transverse bulkheads (ii) Minimum of 2 webs and both transverse bulkheads	(i) 5 point pattern over approximately 2 m <sup>2</sup> area (ii) 2 measurements between each pair of vertical stiffeners
(5) Horizontal girders	Plating on each girder in a minimum of 3 bays	2 measurements between each pair of longitudinal girder stiffeners
(6) Panel stiffening	Where applicable	Single measurements

**Table 3.7.14 Thickness measurement – Double hull oil tankers – Longitudinal bulkhead structure in cargo tanks with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deckhead and bottom strakes, and strakes in way of horizontal stringers on transverse bulkheads	Plating between each pair of longitudinals in a minimum of 3 bays	Single measurement
(2) All other strakes	Plating between every 3rd pair of longitudinals in same 3 bays	Single measurement
(3) Longitudinals on deckhead and bottom strakes	Each longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(4) All other longitudinals	Every 3rd longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(5) Longitudinals – brackets	Minimum of 3 at top, middle and bottom of tank in same 3 bays	5 point pattern over area of bracket
(6) Web frames and cross ties	3 webs with minimum of 3 locations on each web, including in way of cross tie connections	5 point pattern over approximately 2 m <sup>2</sup> area of webs, plus single measurements on flanges of web frames and cross ties
(7) Lower end brackets (opposite side of web frame)	Minimum of 3 brackets	5 point pattern over approximately 2 m <sup>2</sup> area of brackets, plus single measurements on bracket flanges

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 7 & 8

**Table 3.7.15 Thickness measurement – Double hull oil tankers – Transverse watertight and swash bulkhead structure in cargo tanks with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Upper and lower stool, where fitted	Transverse band within 25 mm of welded connection to inner bottom/deck plating Transverse band within 25 mm of welded connection to shelf plate	5 point pattern between stiffeners over 1 m length
(2) Deckhead and bottom strakes, and strakes in way of horizontal stringers	Plating between pair of stiffeners at 3 locations; approximately $\frac{1}{4}$ , $\frac{1}{2}$ and $\frac{3}{4}$ width of tank	5 point pattern between stiffeners over 1 m length
(3) All other strakes	Plating between pair of stiffeners at middle location	Single measurement
(4) Strakes in corrugated bulkheads	Plating for each change of scantling at centre of panel and at flange of fabricated connection	5 point pattern over approximately 1 m <sup>2</sup> of plating
(5) Stiffeners	Minimum of 3 typical stiffeners	For web, 5 point pattern over span between bracket connections (2 measurements across web at each bracket connection and 1 at centre of span). For flange, single measurement at bracket toe and at centre of span
(6) Brackets	Minimum of 3 at top, middle and bottom of tank	5 point pattern over area of bracket
(7) Horizontal stringers	All stringers with measurements at both ends and middle	5 point pattern over 1 m <sup>2</sup> area, plus single measurements near bracket toes and on flanges

## Section 8

### Special Survey – Chemical tankers – Hull requirements

#### 8.1 General

8.1.1 The requirements of Sections 2, 4 and 5 are to be complied with as applicable.

8.1.2 In order to maintain and/or assign the **ESP** notation, the following requirements apply to the surveys of the hull structure and piping systems in way of the cargo tanks, pump rooms, cofferdam, pipe tunnels, void spaces, double bottom tanks, etc., in way of the cargo tank area and all salt-water ballast tanks.

#### 8.2 Documentation

8.2.1 The Owner is to maintain documentation on board as follows:

- A survey file comprising reports of structural surveys, thickness measurement and executive hull summary in accordance with IMO Resolution A.744(18).
- Supporting documentation consisting of:
  - Main structural plans of cargo tanks and ballast tanks.
  - Previous repair history.
  - Cargo and ballast history.
  - Reports on structural defects/deterioration in general.

- Reports on leakage in bulkheads and piping systems.
- Condition of corrosion prevention system, if any.
- Extent of use of inert gas plant and tank cleaning procedures when forming part of approved corrosion control system.
- Information that may help to identify critical areas.
- Survey Programme as required by 8.3.

The complete documentation in 8.2.1 is to be readily available for examination by the Surveyor and should be used as a basis for survey.

8.2.2 The documentation is to be kept on board for the lifetime of the ship.

#### 8.3 Planning for survey

8.3.1 A Survey Programme is to be submitted by the Owner and is to include the proposals for survey, including the means of providing access for Close-up Survey, thickness measurement and tank testing and should take account of the information detailed in 8.2.1.

8.3.2 Prior to the development of the Survey Programme a Survey Planning Questionnaire is to be completed and submitted by the Owner, see 1.6.9.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 8

### 8.4 Overall Survey

8.4.1 All cargo tanks and salt-water ballast tanks including double bottom tanks, pump rooms, pipe tunnels, cofferdams and void spaces bounding cargo tanks, deck and outer hull are to be examined, and this examination is to be supplemented by Close-up Survey, thickness measurement and testing as deemed necessary, to ensure that the structural integrity remains effective.

8.4.2 The examination is to be sufficient to ascertain substantial corrosion, significant deformation, fractures, damages or other structural deterioration and, if deemed necessary by the Surveyor, suitable non-destructive examination may be required.

8.4.3 Where substantial corrosion, as defined in 1.5, is identified and is not rectified, this will be subject to re-examination at Annual and/or Intermediate Surveys. In the case of salt-water ballast tanks the examination will be required at Annual Survey and Intermediate Survey. In the case of cargo tanks the examination will be required at Intermediate Surveys.

8.4.4 All cargo piping on deck, and cargo and ballast piping, within those spaces indicated in 8.4.1 are to be examined and tested under working conditions to ensure that tightness and condition remain satisfactory. Special attention is to be given to ballast piping in cargo tanks and any cargo piping in ballast tanks and void spaces.

8.4.5 The survey of stainless steel tanks may be carried out as an Overall Survey supplemented by Close-up Survey as deemed necessary by the Surveyor.

8.4.6 Where salt-water ballast tanks have been converted to void spaces the survey extent is to be based upon salt-water ballast tank requirements.

8.4.7 Where provided, in association with a corrosion control (c.c.) notation as defined in the *Register Book*, the condition of the protective coating or corrosion prevention system of cargo tanks is to be examined.

8.4.8 The attachment to the structure and condition of anodes in tanks are to be examined.

8.4.9 Where fitted, the strums of the cargo suction pipes are to be removed or lifted to facilitate examination of the shell plating and bulkheads in the vicinity, unless other means for visual inspection of these parts are provided.

### 8.5 Testing

8.5.1 The minimum tank testing requirements are given in Table 3.8.1 and, where required, the Surveyor may extend the tank testing if deemed necessary. Other arrangements for cargo tank testing will be considered on application. The remaining requirements for tank testing, as applicable, are given in 5.3.5.

### 8.6 Close-up Survey

8.6.1 The minimum requirements for Close-up Survey are given in Table 3.8.2.

8.6.2 The Surveyor may extend the Close-up Survey, if deemed necessary, taking into account the maintenance of the tanks under survey, the condition of the corrosion prevention system, and the following:

- Structural arrangements or details which have suffered defects in similar spaces or on similar ships.
- Spaces which have structures approved with reduced scantlings in association with an approved corrosion control system (c.c.).

8.6.3 For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Surveys may be specially considered.

### 8.7 Thickness measurement

8.7.1 The minimum requirements for thickness measurements are given in Table 3.8.3.

8.7.2 In areas where substantial corrosion, as defined in 1.5, has been noted, then additional measurements are to be carried out, as applicable, in accordance with Tables 3.8.4, 3.8.5, 3.8.6 and 3.8.7 to determine the full extent of the corrosion pattern. The survey will not be considered complete until these additional thickness measurements have been carried out.

**Table 3.8.1 Tank testing requirements – Chemical ships**

Special Survey I (Ships 5 years old)	Special Survey II and subsequent (Ships 10 years old and over)
All ballast tank boundaries	All ballast tank boundaries
Cargo tank boundaries facing ballast tanks, void spaces, pipe tunnels, pump rooms or cofferdams	All cargo tank bulkheads

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 8

**Table 3.8.2 Close-up Survey – Chemical tankers**

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
<p>(1) One web frame ring – in a wing ballast tank, if any, or a ballast double hull side tank, see Notes 1 and 8</p> <p>(2) One deck transverse – in a cargo tank or on deck, see Note 2</p> <p>(3) One transverse bulkhead, see Note 4: (a) in a ballast tank (b) in a cargo wing tank (c) in a cargo centre tank</p>	<p>(1) All plating and internal structure in a wing ballast tank, if any, or a ballast double hull side tank, see Notes 7 and 8</p> <p>(2) One deck transverse, see Note 2: (a) in each of the remaining ballast tanks, or on deck (b) in a cargo wing tank or on deck (c) in 2 cargo centre tanks or on deck</p> <p>(3) Both transverse bulkheads – in a wing ballast tank, if any, or a double hull side tank, see Note 3</p> <p>(4) One transverse bulkhead, see Note 4: (a) in each remaining ballast tank (b) in a cargo wing tank (c) in 2 cargo centre tanks</p>	<p>(1) All plating and internal structure, see Note 7: (a) in all ballast tanks (b) in a cargo wing tank</p> <p>(2) One web frame ring – in each remaining cargo tank, see Note 1</p> <p>(3) All transverse bulkheads – in all cargo tanks, see Note 3</p> <p>(4) As considered necessary by the Surveyor, see Note 5</p>	<p>(1) As Special Survey III</p> <p>(2) Additional transverse areas if deemed necessary by the Surveyor</p>
<p><b>NOTES</b></p> <div> <div> <p>1. Complete transverse web frame ring including adjacent structural members.</p> <p>2. Deck transverse including adjacent deck structural members.</p> <p>3. Transverse bulkhead complete, including girder system and adjacent members, and adjacent longitudinal bulkhead structure.</p> <p>4. Transverse bulkhead lower part including girder system and adjacent structural members.</p> </div> <div> <p>5. Additional complete transverse web frame ring.</p> <p>6. Ballast tank includes peak tanks.</p> <p>7. Complete tank – including all tank boundaries and internal structure, and external structure on deck in way of the tank where applicable.</p> <p>8. Double hull side tank includes double bottom and side tank even though these tanks may be separated.</p> </div> </div>			

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 8

**Table 3.8.3 Thickness measurement – Chemical tankers**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
(1) 1 section of deck plating for the full beam of the ship within 0,5L amidships (in way of a ballast tank, if any) (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.8.2 (3) Critical areas, as required by the Surveyor	(1) Within the cargo area: (a) Each deck plate (b) 2 transverse sections (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.8.2 (3) Selected wind and water strakes outside the cargo area (4) All wind and water strakes within the cargo area (5) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank, see Notes 1 and 4 (6) Critical areas, as required by the Surveyor	(1) Within the cargo area: (a) Each deck plate (b) 3 transverse sections (c) Each bottom plate (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.8.2 (3) All wind and water strakes over the full length of the ship, port and starboard (4) Remaining exposed main deck plating not considered in item (1) and representative exposed superstructure deck plating (i.e. poop, bridge and fore-castle deck) (5) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 1 and 4 (6) All keel plates outside the cargo tank length. Also additional bottom plates in way of cofferdams, machinery space and aft end of tanks (7) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor (8) Critical areas, as required by the Surveyor
Special Survey II (Ships 10 years old)		
(1) Within the cargo area: (a) Each deck plate (b) 1 transverse section (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.8.2 (3) Selected wind and water strakes outside the cargo area (4) Critical areas, as required by the Surveyor		
<b>NOTES</b> 1. For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of thickness measurements may be specially considered. 2. Transverse sections should be chosen where the largest reductions are likely to occur, or as revealed by deck plating measurements. 3. Where two or three transverse sections are required to be measured, at least one is to include a ballast tank within 0,5L amidships. 4. Transverse bulkhead complete including stiffening system.		

**Table 3.8.4 Thickness measurement – Chemical tankers – Bottom structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Bottom plating and inner bottom plating	Minimum of 3 bays across tank, including aft bay Measurement around and under all suction strums	5 point pattern for each panel between longitudinals over 1 m length
(2) Bottom longitudinals and inner bottom longitudinals	Minimum of 3 longitudinals in each bay where plating measured	3 measurements in line across flange and 3 measurements on vertical web
(3) Bottom longitudinal girder, transverse floors and web frames	Suspect plates	5 point pattern over about 1 m <sup>2</sup> area
(4) Watertight floors	(a) Lower 1/3 of tank (b) Upper 2/3 of tank	5 point pattern over about 1 m <sup>2</sup> area
(5) Panel stiffening	Where applicable	Single measurements

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 8

**Table 3.8.5 Thickness measurement – Chemical tankers – Deck structure with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deck plating	2 bands across tank	Minimum of 3 measurements per plate per band
(2) Deck longitudinals	Minimum of 3 longitudinals in each 2 bays	3 measurements in line vertically on webs and 2 measurements on flange (if fitted)
(3) Deck girders and brackets	At fore and aft transverse bulkhead, bracket toes and in centre of tanks	Vertical line of single measurements on web plating with 1 measurement between each panel stiffener, or a minimum of 3 measurements. 2 measurements across face flat. 5 point pattern on girder/bulkhead brackets
(4) Deck transverse webs	Minimum of 2 webs with measurement at both ends and middle of span	5 point pattern over 2 m <sup>2</sup> area. Single measurements on face flat
(5) Panel stiffening	Where applicable	Single measurements

**Table 3.8.6 Thickness measurement – Chemical tankers – Shell and longitudinal bulkheads with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deckhead and bottom strakes and strakes in way of stringer platforms	Plating between each pair of longitudinals in a minimum of 3 bays	Single measurement
(2) All other strakes	Plating between every 3rd pair of longitudinals in same 3 bays	Single measurement
(3) Longitudinals – deckhead and bottom strakes	Each longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(4) Longitudinals – all others	Every third longitudinal in same 3 bays	3 measurements across web and 1 measurement on flange
(5) Longitudinals – bracket	Minimum of 3 at top, middle and bottom of tank in same 3 bays	5 point pattern over area of bracket
(6) Web frames and cross ties	3 webs with minimum of 3 locations on each web, including in way of cross tie connections	5 point pattern over 2 m <sup>2</sup> area, plus single measurements on web frame and cross tie face flats

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 8 & 9

**Table 3.8.7 Thickness measurement – Chemical tankers – Transverse bulkheads and swash bulkheads with substantial corrosion**

Structural member	Extent of measurement	Pattern of measurement
(1) Deckhead and bottom strakes in way of stringer platforms	Plating between pair of stiffeners at 3 locations: approx. 1/4, 1/2 and 3/4 width of tank	5 point pattern between stiffeners over 1 m length
(2) All other strakes	Plating between pair of stiffeners at middle location	Single measurement
(3) Strakes in corrugated bulkheads	Plating for each change of scantling at centre of panel and at flange or fabricated connection	5 point pattern over 1 m <sup>2</sup> of plating
(4) Stiffeners	Minimum of 3 typical stiffeners	For web, 5 point pattern over span between bracket connections (2 measurements across web at each bracket connection and one at centre of span). For flange, single measurements at each bracket toe and at centre of span
(5) Brackets	Minimum of 3 at top, middle and bottom of tank	5 point pattern over area of bracket
(6) Deep webs and girders	Measurements at toe of bracket and at centre of span	For web, 5 point pattern over 1 m <sup>2</sup> area. 3 measurements across face flat
(7) Stringer platforms	All stringers with measurements at middle and both ends	5 point pattern over 1 m <sup>2</sup> area, plus single measurements near bracket toes and on face flats

## Section 9 Ships for liquefied gases

### 9.1 General

9.1.1 The requirements of Sections 2 to 7 are to be complied with, as applicable.

9.1.2 Prior to the inspection of cargo tanks, surrounding spaces, associated piping, fittings and equipment, etc., the respective items are to be cleaned and thoroughly cleared of gas. Every precaution is to be taken to ensure safety during inspection.

9.1.3 The following documentation, as applicable, is to be available on board the ship:

- Relevant instruction and information material such as cargo handling plans, filling limit information, cooling down procedures, etc.
- A copy of the IGC Code.
- Test records of secondary barrier.
- Loading and stability information, including damage stability.

9.1.4 For requirements of Special Survey for electrical equipment, see Section 14.

### 9.2 Annual Surveys – Basic requirements

9.2.1 The Annual Survey is preferably to be carried out during a loading or discharging operation. Access to cargo tanks or inerted hold spaces, necessitating gas freeing/aerating will normally not be necessary unless required by the Regulations.

9.2.2 The ship's log and operational records for the cargo containment system covering the period from the previous survey are to be examined. Any malfunction of the system entered in the log is to be investigated, the cause ascertained, and that part of the system at fault is to be found or placed in good order.

9.2.3 Instrumentation and safety systems are to be surveyed as follows:

- The instrumentation of the cargo installations with regard to pressure, temperature and liquid level is to be verified in good working order by one or more of the following methods:
  - Visual external examination.
  - Comparing of read outs from different indicators.
  - Consideration of read outs with regard to the actual cargo and/or actual conditions.
  - Examination of maintenance records with reference to cargo plant instrumentation maintenance manual.
  - Verification of calibration status of the measuring instruments.
- The low level, high level, and overfill alarms are to be examined and tested to ascertain that they are in working order.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 9

- (c) The alarms associated with the following are to be tested as applicable:
  - (i) Cargo tank high and low pressure.
  - (ii) Cargo tank temperature.
  - (iii) Cargo hold pressure.
  - (iv) Interbarrier space pressure.
  - (v) Inner hull temperature.
  - (vi) Secondary barrier temperature.
  - (vii) Cargo Hold or Interbarrier bilge level detection.
- (d) Control devices for the cargo containment systems and cargo handling equipment, together with any associated shutdown and/or interlock, are to be checked under simulated working conditions and, if necessary, recalibrated. Such safety systems include but are not limited to:
  - (i) Cargo tank overfill protection including cargo pump, compressor and other cargo machinery automatic shutdown.
  - (ii) Cargo pump, compressor and other cargo machinery shutdown on low cargo tank pressure or cargo tank and interbarrier/hold space differential pressure.
  - (iii) Cargo pump automatic shutdown on low level or current;
- (e) The emergency shutdown system is to be tested, without flow in the pipe lines, to verify that the system will cause the cargo pumps, compressors and other cargo machinery, as applicable, to stop.
- (f) Consideration will be given to the acceptance of simulated tests, provided that they are carried out at the cargo temperature, or comprehensive maintenance records, including details of tests held, in accordance with the cargo plant instrumentation maintenance manual.

9.2.4 Cargo gas leakage detection systems are to be examined and tested to ascertain that they are in working order and calibrated using sample gas.

9.2.5 Inert gas/dry air installations including the means for prevention of backflow of cargo vapour to gas-safe spaces are to be verified as being in satisfactory operating condition.

9.2.6 Ventilation systems and air locks in working spaces are to be checked for satisfactory operation.

9.2.7 Cargo pipeline, valves and fittings are to be generally examined, with special reference to expansion bellows, supports and vapour seals on insulated pipes. It is to be verified that all accessible cargo piping systems are electrically bonded to the hull.

9.2.8 Portable and/or fixed drip trays, or insulation for deck protection in the event of cargo leakage, are to be examined for condition.

9.2.9 The means for accomplishing gas tightness of the wheelhouse doors and windows is to be examined. All windows and side-scuttles within the area required to be of the fixed type (non-opening) are to be examined for gas tightness. The closing devices for all air intakes and openings into accommodation spaces, service spaces, machinery spaces, control stations and approved openings in superstructures and deckhouses facing the cargo area or bow and stern loading/unloading arrangements are to be examined. For ships carrying toxic gases such devices should be capable of being operated from inside the space.

9.2.10 Venting systems, including protection screens if provided, for the cargo tanks, inter-barrier spaces and hold spaces are to be visually examined externally. It is to be verified that the cargo tank relief valves are sealed and that the certificate for the relief valves opening/closing pressures is on board the ship.

9.2.11 Mechanical ventilation fans in gas dangerous spaces and zones are to be visually examined. Adequate spare parts should be carried for each type of fan installed.

9.2.12 Electrical equipment, cables and supports in gas dangerous zones shall be examined as far as practicable. Alarms and safety systems associated with pressurised lighting systems and any safety device associated with non-safe type electrical equipment that is protected by air-locks are to be verified.

9.2.13 Heating arrangements, if fitted, for cofferdams and other spaces shall be verified in good working order.

9.2.14 All accessible gas-tight bulkhead penetrations including gas-tight shaft sealings are to be visually examined.

9.2.15 The sealing arrangements for tanks or tank domes penetrating decks or tank covers are to be externally examined.

## 9.3 Annual Surveys – Reliquefaction/refrigeration equipment

9.3.1 Where reliquefaction or refrigeration equipment for cargo temperature and pressure control is fitted, the following are to be examined, so far as practicable:

- (a) The machinery under working conditions.
- (b) The shells of all pressure vessels in the system, externally. Insulation need not be removed for this examination, but any deterioration of insulation or evidence of dampness which could lead to external corrosion of the vessels or their connections, is to be investigated.
- (c) Primary refrigerant gas and liquid pipes, cargo vapour and liquid condensate pipes and condenser cooling water pipes. Insulation need not be removed, but any deterioration or evidence of dampness is to be investigated.
- (d) The reliquefaction/refrigeration plant spare gear.

9.3.2 Reference should be made to the Special Survey requirements for guidance on Continuous Survey arrangements.



# Periodical Survey Regulations

# Part 1, Chapter 3

Section 9

## 9.4 Annual Surveys – Methane burning equipment and other equipment components

9.4.1 The following components are to be generally examined externally. If insulation is fitted, this need not be removed, but any deterioration of insulation, or evidence of dampness which could lead to external corrosion of the vessels or their connections, is to be investigated:

- (a) Heat exchangers and pressure vessels for use with methane burning in boilers or machinery.
- (b) Cargo heaters, vaporizers, masthead heaters and other miscellaneous pressure vessels.

9.4.2 Controls and interlocks are to be checked.

9.4.3 Alarm systems are to be checked to ascertain that they are in working order.

9.4.4 Exhaust fans and/or pressurizing system for gas trunking are to be tested.

## 9.5 Annual Surveys – Cargo containment systems

9.5.1 Where the insulation arrangement is such that the insulation cannot be examined, the surrounding structures of wing tanks, double bottom tanks and cofferdams are to be examined for cold spots, prior to the survey. This examination is to be held at a convenient cargo discharge operation with the cargo tanks loaded at approximately the minimum notation temperature.

9.5.2 On application by the Owner, consideration will be given to the cold spot examination, where applicable, being carried out by the ship's staff.

9.5.3 When tests are required after repairs, independent cargo tanks, other than independent tanks Type C, are to be tested by hydraulic or hydropneumatic means as appropriate. Test heads and pressures should be as defined in Ch 4, 10 of the Rules for Liquefied Gases. Cargo tanks of the membrane or semi-membrane type are to be tested by means of a detectable gas in the inter-barrier spaces and discolouring paint on the weld seams of the cargo tanks wall, or other suitable means. Independent cargo tanks of Type C are to be tested hydraulically at 1,25 times the approved maximum vapour pressure.

## 9.6 Intermediate Surveys

9.6.1 The Intermediate Survey intends to supplement the Annual Survey by testing cargo handling installations with related automatic control, alarm and safety systems for correct functioning. The Intermediate Survey is preferably to be carried out with the ship in a gas-free condition. The extent of the testing required for the Intermediate Survey will normally be such that the survey cannot be carried out during a loading or discharging operation.

9.6.2 In addition to the requirements for Annual Survey and the requirements of 3.2.1 to 3.2.8, the following are to be dealt with as applicable:

- (a) Examination of means for draining the vent piping system.
- (b) Verification that pipelines and cargo tanks are electrically bonded to the hull.
- (c) Verification that the heating arrangements, if any, for steel structures are satisfactory.
- (d) Where required by the manufacturer's maintenance instructions, cargo tank and inter-barrier space pressure and vacuum relief valve settings are to be checked and adjusted as required. Cargo tank pressure relief valve harbour settings are also to be checked, if applicable. Cargo tank pressure relief valves are to lift at a pressure not more than the percentage given below, above the maximum vapour pressure for which the tanks have been approved.
  - For 0 to 1,5 bar (0 to 1,5 kgf/cm<sup>2</sup>), 10 per cent.
  - For 1,5 to 3,0 bar (1,5 to 3,0 kgf/cm<sup>2</sup>), 6 per cent.
  - For pressures exceeding 3,0 bar (3,0 kgf/cm<sup>2</sup>), 3 per cent.
  - Valves may be removed from the tanks for the purpose of checking.
- (e) A General Examination within the areas deemed as dangerous such as cargo compressor rooms and spaces adjacent to and zones above cargo areas, for defective and non-certified safe-type electrical equipment, improperly installed, defective and dead wiring. An electrical insulation resistance test of the circuits terminating in, or passing through the dangerous areas, is to be carried out. If the ship is not in a gas free condition the results of previously recorded test readings may be accepted.

9.6.3 At the first Intermediate Survey after initial commissioning of the ship, the following examinations are to be carried out:

- (a) Cargo tanks, other than independent tanks Types A and C, are to be examined internally. Insulation, where fitted externally, is to be generally examined.
- (b) Particular attention is to be given to tower structures and other attachments within the tanks, tank supports and securing arrangements.

## 9.7 Special Survey I (ships five years old) – General requirements

9.7.1 The requirements of 9.1 to 9.6 are to be complied with.

9.7.2 The requirements for Close-up Survey and thickness measurement are given in 9.12 and 9.13.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 9

9.7.3 All cargo tanks are to be examined internally, also externally so far as practicable, particular attention being paid to the plating in way of supports of securing arrangements, tower structures, seatings and pipe connections, also to sealing arrangements in way of the deck penetrations. Provided that the structural examination is satisfactory, that the gas leakage monitoring systems have been found to be operating satisfactorily and that the voyage records have not shown any abnormal operation, cargo tanks do not require to be hydraulically tested. The primary membranes of 'Gas Transport' design should be examined with the primary insulation space under a vacuum of at least -500 mbar gauge. For 'Moss Type' LNG cargo tanks, the Structural Transition Joints (STJ) are to be examined at the port, starboard, forward and aft locations. Insulation is to be removed as required. Non-destructive testing may be required where considered necessary.

9.7.4 The non-destructive testing of cargo tanks is to be carried out as follows:

- (a) Non-destructive testing is to supplement cargo tank inspection with special attention to be given to the integrity of the main structural members, tank shell and highly stressed parts, including welded connections as deemed necessary by the Surveyor. The following items are, inter alia, considered as highly stressed parts:
  - (i) Cargo tanks supports and anti-rolling/anti-pitching devices;
  - (ii) Web frames or stiffening rings;
  - (iii) Swash bulkhead boundaries;
  - (iv) Dome and stump connections to tank shell;
  - (v) Foundations for pumps, towers, ladders, etc.;
  - (vi) Pipe connections.
- (b) For independent tanks of Type B, the extent of non-destructive testing shall be as given in the programme specially prepared for the cargo tank design.
- (c) Independent cargo tanks of Type C are to be subjected to non-destructive testing of the plating in way of supports and also at selected lengths of welds. Where such testing raises doubt as to the structural integrity, a hydraulic test should be carried out at 1.25 times the approved maximum vapour pressure. Alternatively, consideration will be given to pneumatic testing under special circumstances, provided full details are submitted for approval.
- (d) At each alternate Special Survey (i.e. SSII, SSIV and so on), all independent cargo tanks of Type C are to be either:
  - (i) Hydraulically or hydro-pneumatically tested to 1.25 times MARVS, followed by non-destructive testing in accordance with paragraph (a) above, or,
  - (ii) Subjected to a thorough, planned, non-destructive testing. This testing is to be carried out in accordance with a programme specially prepared for the tank design. If a special programme does not exist, the following applies:
    - cargo tank supports and anti-rolling/anti-pitching devices;
    - stiffening rings;

- Y-connections between tank shell and a longitudinal bulkhead of bi-lobe tanks;
- swash bulkhead boundaries;
- dome and sump connections to the tank shell;
- foundations for pumps, towers, ladders etc.;
- pipe connections.

At least 10 per cent of the length of the welded connections in each of the above mentioned areas is to be tested. This testing is to be carried out internally and externally as applicable. Insulation is to be removed as necessary for the required non-destructive testing.

9.7.5 Deck mounted cargo storage tanks are to be examined in the same manner as main cargo tanks.

9.7.6 Secondary barriers are to be examined for their effectiveness, visually whenever possible, or by means of pressure/vacuum tests on the inter-barrier spaces. Testing is to be carried out in accordance with the system designer's requirements as approved by LR. Alternative means of checking the secondary barriers will be considered.

9.7.7 Where cargo containment systems have secondary barriers which cannot be examined or tested and have been approved on the basis of extensive prototype testing, the barriers will be considered to remain efficient provided a cold spot examination of the adjacent steelwork is satisfactory and records of the steelwork temperature readings are verified as acceptable.

9.7.8 Where a cargo tank or the hull structure is insulated and the insulation is accessible, the insulation should be examined externally, together with any vapour or protective barrier, and sections removed for examination, if considered necessary by the Surveyor. Special attention should be given to insulation in way of chocks, supports and keys. Portions of the insulation are also to be removed, if required by the Surveyor, to enable the condition of the plating to be ascertained. Where the insulation is not accessible, see 9.5.1.

9.7.9 Cargo tank internal pipes and fittings are to be examined, and all valves and cocks in direct communication with the interiors of the tanks are to be opened out for inspection and the connection pipes are to be examined internally, so far as practicable.

9.7.10 Relief valves are to be surveyed as follows:

- (a) The pressure relief valves for the cargo tanks are to be opened for examination, adjusted, function tested, and sealed. If the cargo tanks are equipped with relief valves with non-metallic membranes in the main or pilot valves, such non-metallic membranes are to be replaced.
- (b) Pressure relief valves are subsequently to be adjusted to lift at a pressure in accordance with 9.6.1(d). Relief valve harbour settings are to be checked, if applicable. Valves may be removed from the shell for the purpose of making this adjustment under pressure of air or other suitable gas.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 9

- (c) Where a proper record of continuous overhaul and retesting of individually identifiable relief valves is maintained, consideration will be given to acceptance on the basis of opening, internal examination, and testing of a representative sampling of valves, including each size and type of liquefied gas or vapour relief valve in use, provided there is logbook evidence that the remaining valves have been overhauled and tested since crediting of the previous Special Survey.
- (d) Relief valves on cargo gas and liquid pipelines are to have their pressure settings checked. The valves may be removed from the pipelines for this purpose. At the Surveyor's discretion a sample of each size and type of valve may be opened for examination and testing.

9.7.11 All cargo pumps, cargo booster pumps and cargo vapour pumps are to be opened out for examination. If requested by the Owner, these items may be examined on a Continuous Survey basis, provided the interval between examination of each item does not exceed five years. Pumping systems for inter-barrier spaces are to be checked and verified to be in good working order.

9.7.12 Where considered necessary, insulated cargo gas and liquid pipelines are to have sections of insulation removed to ascertain the condition of the pipes. Care is to be taken that in the replacement of insulation, the outer vapour seal is made good.

9.7.13 Equipment for the production of inert gas is to be examined and shown to be operating satisfactorily within the gas specification limits. Pipelines, valves, etc., for the distribution of the inert gas are to be generally examined. Pressure vessels for the storage of inert gas are to be examined internally and externally and the securing arrangements are to be specially examined. Pressure relief valves are to be demonstrated to be in good working order. Liquid nitrogen storage vessels are to be examined, so far as practicable, and all control equipment, alarms and safety devices are to be verified as operational.

9.7.14 Gastight bulkhead shaft seals are to be opened out so that the sealing arrangements may be checked.

9.7.15 Sea connections associated with the cargo handling equipment are to be opened out when the ship is in dry-dock.

9.7.16 The arrangements for discharging the cargo overboard in an emergency are to be checked.

## 9.8 Special Survey I (ships five years old) – Reliquefaction/refrigeration equipment

9.8.1 Each reciprocating compressor is to be opened out. Cylinder bores, pistons, piston rods, connecting rods, valves and seats, glands, relief devices, suction filters and lubricating arrangements are to be examined. Crankshafts are to be examined, but crankcase glands and the lower half of main bearings need not be exposed if the Surveyor is satisfied with the alignment and wear.

9.8.2 Where other than reciprocating-type compressors are fitted, or where there is a program of replacement instead of surveys on board, alternative survey arrangements will be considered. Each case will be given individual consideration.

9.8.3 The water end covers of condensers are to be removed for examination of the tubes, tubeplates and covers.

9.8.4 Refrigerant condenser cooling water pumps, including standby pump(s) which may be used on other services, are to be opened out for examination.

9.8.5 Where a pressure vessel is insulated, sufficient insulation is to be removed, especially in way of connections and supports, to enable the vessel's condition to be ascertained.

9.8.6 Insulated pipes are to have sufficient insulation removed to enable their condition to be ascertained. Vapour seals are to be specially examined for their condition.

9.8.7 The Surveyor is to satisfy himself that all pressure relief valves and/or safety discs throughout the system are in good order. No attempt, however, is to be made to test primary refrigerant pressure relief valves on board ship.

9.8.8 The items covered by 9.8.1 to 9.8.4 may, at the request of the Owner, be examined on a Continuous Survey basis provided the interval between examination of each item does not exceed five years.

## 9.9 Special Survey I (ships five years old) – Methane burning equipment

9.9.1 Where methane is used as fuel for main propulsion purposes, the associated compressors and heat exchangers are to be opened out and examined as for reliquefaction/refrigeration equipment. The steam side of steam heaters is to be hydraulically tested to 1,5 times the design pressure.

9.9.2 Methane gas pipe trunks or casings are to be generally examined and the exhaust or inerting arrangements for these trunks are to be verified.

9.9.3 All alarms associated with the methane burning systems are to be verified.

## 9.10 Special Survey II and Special Surveys thereafter (ships 10 years old and over)

9.10.1 The requirements of 9.1 to 9.9 are to be complied with.

9.10.2 Water cooled condensers in which the primary refrigerant is in contact with the shell are to have the end covers removed and the shell pneumatically tested to a pressure equal to the designed working pressure.

9.10.3 All other pressure vessels in the reliquefaction/refrigeration system, methane burning system and other handling systems are to be pneumatically tested to a pressure equal to the designed working pressure.

9.10.4 Liquid cargo pipes are to be tested, by approved means, to a pressure equal to 1,25 times the working pressure. Alternatively, selected representative lengths may be removed for internal examination and hydraulic testing.

9.10.5 The requirements for Close-up Survey and thickness measurement are given in 9.12 and 9.13.

9.11 Special Survey III and Special Surveys thereafter (ships 15 years old and over)

9.11.1 The requirements of 9.1 to 9.10 are to be complied with.

9.11.2 For independent tanks of Type B, the Owner is to submit proposals for the extent of non-destructive testing of the cargo tanks well in advance of the Special Survey.

9.12 Close-up Survey

9.12.1 The minimum requirements for Close-up Survey are given in Table 3.9.1.

9.12.2 The Surveyor may extend the Close-up Survey, if deemed necessary, taking into account the maintenance of the tanks under survey, the condition of the corrosion prevention system and the structural arrangements or details which have suffered defects in similar spaces or on similar ships.

9.12.3 For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of Close-up Survey may be specially considered.

9.13 Thickness measurement

9.13.1 The minimum requirements for thickness measurement are given in Table 3.9.2.

Table 3.9.1 Close-up Survey – Ships for liquefied gases

Special Survey I (Ships 5 years old)	Special Survey II (Ships 10 years old)	Special Survey III (Ships 15 years old)	Special Survey IV (Ships 20 years old and over)
(1) One transverse web frame in 2 representative water ballast tanks of each type, see Notes 1 and 2 (2) One transverse bulkhead in a ballast tank, see Note 4	(1) One transverse web frame in each water ballast tank, see Notes 1 and 2 (2) Forward and aft transverse bulkhead in one side ballast tank, see Note 3	(1) All web frame rings in all ballast tanks, see Notes 1 and 2 (2) All transverse bulkheads – in all ballast tanks, see Note 3 (3) As considered necessary by the Surveyor, see Note 5	(1) All web frame rings in all ballast tanks, see Notes 1 and 2 (2) All transverse bulkheads – in all ballast tanks, see Note 3 (3) As considered necessary by the Surveyor, see Note 5
NOTES 1. Ballast tanks includes topside, double hull side, double bottom, hopper side, or any combined arrangement of the aforementioned, and peak tanks where fitted. 2. Complete transverse web frame ring including adjacent structural members. 3. Transverse bulkhead complete, including girder system and adjacent members, and adjacent longitudinal bulkhead structure. 4. Transverse bulkhead lower part including girder system and adjacent structural members. 5. Additional complete transverse web frame ring.			

# Periodical Survey Regulations

## Part 1, Chapter 3

Sections 9 &amp; 10

**Table 3.9.2 Thickness measurement – Ships for liquefied gases**

Special Survey I (Ships 5 years old)	Special Survey III (Ships 15 years old)	Special Survey IV and subsequent (Ships 20 years old and over)
(1) 1 section of deck plating for the full beam of the ship within 0,5L amidships in way of a ballast tank, if any (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to close-up survey in accordance with Table 3.9.1 (3) Critical areas, as required by the Surveyor	(1) Within the cargo area: (a) Each deck plate (b) 2 transverse sections (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.9.1 (3) Selected wind and water strakes outside the cargo area (4) All wind and water strakes within the cargo area (5) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank, see Notes 1 and 4 (6) Critical areas, as required by the Surveyor	(1) Within the cargo area: (a) Each deck plate (b) 3 transverse sections (c) Each bottom plate (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.9.1 (3) All wind and water strakes over the full length of the ship, port and starboard (4) Remaining exposed main deck plating not considered in item (1) and representative exposed superstructure deck plating (i.e. poop, bridge and forecastle deck) (5) All transverse webs with associated plating and longitudinals, and the transverse bulkhead complete in the fore peak tank and aft peak tank, see Notes 1 and 4 (6) All keel plates outside the cargo tank length. Also additional bottom plates in way of cofferdams, machinery space and aft end of tanks (7) Plating of seachests. Also side shell plating in way of overboard discharges, as considered necessary by the Surveyor (8) Critical areas, as required by the Surveyor
Special Survey II (Ships 10 years old)		
(1) Within the cargo area: (a) Each deck plate (b) 1 transverse section (2) Measurements for general assessment and recording of corrosion pattern of the structural members subject to Close-up Survey in accordance with Table 3.9.1 (3) Selected wind and water strakes outside the cargo area (4) Critical areas, as required by the Surveyor		
<b>NOTES</b> 1. For areas in tanks where coatings are found to be in GOOD condition, as defined in 1.5, the extent of thickness measurements may be specially considered. 2. Transverse sections should be chosen where the largest reductions are likely to occur, or as revealed by deck plating measurements. 3. Where two or three transverse sections are required to be measured, at least one is to include a ballast tank within 0,5L amidships. 4. Transverse bulkhead complete including stiffening system. 5. Where considered necessary by the Surveyor, the inner bottom plating and adjacent tank supports are to be subject to thickness measurement for general assessment and recording of the corrosion pattern. 6. For those ships designated to carry light oils in the independent cargo tanks, thickness measurement of the independent cargo tank structure is to be carried out as considered necessary by the Surveyor.		

### Section 10 Dredgers, hopper dredgers, sand carriers, hopper barges and reclamation craft

#### 10.1 General

10.1.1 The requirements of this Section are to be complied with, as applicable, in addition to the survey requirements of Sections 2, 3, 4 and 5. Where surveys are required on dredging or hopper equipment such as gantries, bottom doors and their operating gear, positioning spuds and suction pipe attachments or split hull devices such as actuating and locking devices, these will be limited to the extent considered necessary by the Surveyor to satisfy himself that their condition or malfunction will not adversely affect the ship's structure.

10.1.2 Where applicable, the Docking Survey is to include the examination of hopper doors and their fittings, and of hopper valves.

#### 10.2 Special Surveys

10.2.1 On ships up to 10 years old (Special Survey I and II):

- Hoppers are to be cleared and cleaned as necessary and examined.
- Where applicable, hopper doors or valves are to be opened and closed, so far as practicable, but keel blocks need not normally be moved specially to permit this to be done.
- The integrity of hopper overflows and diluting water inlet and distribution structures is to be confirmed. Weir valves and sluices are to be tested to ensure proper operation, particular attention being paid to the lower weir when weirs are fitted at more than one level.
- Attention is to be given to shell plating in way of hopper overflows.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 10 & 11

- (e) The attachment to the ship's structure of all main items of dredging equipment, including gantries, 'A' frames, spud control gear supports and items provided to facilitate separation of split hulls including hinge pin gudgeons, anchorages for rams and locking devices, is to be carefully examined to ensure that no fracture is present.

10.2.2 On ships 15 years old and over (Special Survey III and subsequent Special Surveys):

- (a) Attention is to be given by the Surveyor to the structure in way of dredging pumps.
- (b) Hopper doors, valves and items provided to facilitate separation of split hulls are to be checked for proper operation, and their hinges, control gear and other fittings are to be examined for wear or distortion. All seals and wear-down strips are to be replaced if necessary, but a watertight seal is not normally required. Attention is to be paid to areas likely to be suffering from excessive erosion.
- (c) Those items of dredging gear and equipment whose efficiency is not part of classification but whose failure or malfunctioning is, nevertheless, likely to adversely affect the ship's structure, are to be examined to ensure that the structural integrity of the ship is maintained.

## Section 11 Machinery surveys – General requirements

### 11.1 Annual, Intermediate and Docking Surveys

11.1.1 For Annual, Intermediate and Docking Surveys, see Sections 2, 3 and 4.

### 11.2 Complete Surveys

11.2.1 While the ship is in dry-dock, all openings to the sea in the machinery spaces and pump-rooms, together with the valves, cocks and the fastenings with which these are connected to the hull, are to be examined.

11.2.2 All shafts (except screwshafts and tube shafts, for which special arrangements are detailed in Section 17), thrust block and all bearings are to be examined. The lower halves of bearings need not be exposed if alignment and wear are found to be acceptable.

11.2.3 An examination is to be made of all reduction gears complete with all wheels, pinions, shafts, bearings and gear teeth, thrust bearings and incorporated clutch arrangements.

11.2.4 The following auxiliaries and components are also to be examined:

- (a) Auxiliary engines, auxiliary air compressors with their intercoolers, filters and/or oil separators and safety devices, and all pumps and components used for essential services.
- (b) Steering machinery.

- (c) Windlass and associated driving equipment, where fitted.
- (d) Evaporators (other than those of vacuum type) and their safety valves, which should be seen in operation under steam.
- (e) The holding down bolts and chocks of main and auxiliary engines, gearcases, thrust blocks and intermediate shaft bearings.

11.2.5 All air receivers for essential services, together with their mountings, valves and safety devices, are to be cleaned internally and examined internally and externally. If internal examination of the air receivers is not practicable, they are to be tested hydraulically to 1,3 times the working pressure.

11.2.6 The valves, cocks and strainers of the bilge system, including bilge injection, are to be opened up as considered necessary by the Surveyor and, together with pipes, are to be examined and tested under working conditions. The oil fuel, feed, lubricating oil and cooling water systems, as well as the ballast connections and blanking arrangements to deep tanks which may carry liquid or dry cargoes, together with all pressure filters, heaters and coolers used for essential services, are to be opened up and examined or tested, as considered necessary by the Surveyor. All safety devices for the foregoing items are to be examined.

11.2.7 Fuel tanks which do not form part of the ship's structure are to be examined and, if considered necessary by the Surveyor, they are to be tested to the pressure specified for new tanks. The tanks need not be examined internally at the first survey if they are found satisfactory on external inspection. The mountings, fittings and remote controls of all oil fuel tanks are to be examined, so far as practicable.

11.2.8 Where remote and/or automatic controls are fitted for essential machinery, they are to be tested to demonstrate that they are in good working order.

11.2.9 On vessels fitted with a classed dynamic positioning system, the control system and associated machinery items are to be examined and tested to demonstrate that they are in good working order.

11.2.10 In addition to the above, detailed requirements for steam and gas turbines and steam engines, oil engines, electrical installations and boilers are given in Sections 12, 13, 14 and 15 respectively. In certain instances, upon application by the Owner or where indicated by the maker's servicing recommendations, the Committee will give consideration to the circumstances where deviation from these detailed requirements is warranted, taking account of design, appropriate indicating equipment (e.g. vibration indicators) and operational records.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 12 & 13

## ■ Section 12 Turbines and steam engines – Detailed requirements

### 12.1 Complete Surveys

12.1.1 The requirements of Section 11 are to be complied with.

12.1.2 The working parts of the main engine and attached pumps, and of auxiliary machinery used for essential services, are to be opened out and examined, including:

- (a) For reciprocating engines:
  - Bulkhead stop valves and manoeuvring valves.
  - Cylinders.
  - Pistons, piston rods, connecting rods, crossheads and guides.
  - Valves and valve gear.
  - Crankshaft.
- (b) For turbine machinery:
  - Blading and rotors.
  - Flexible couplings.
  - Casings.

12.1.3 In gas turbines and free piston gas generators, the following parts are also to be opened out and examined:

- Impellers or blading.
- Rotors and casings of the air compressors.
- Combustion chambers and burners.
- Intercoolers and heat exchangers.
- Gas and air piping, and fittings.
- Starting and reversing arrangements.

12.1.4 Where gas turbines operate in conjunction with free piston gas generators, the following parts of the latter are to be opened out and examined:

- Gas and air compressor cylinders and pistons.
- Compressor end covers.
- Valves and valve gear.
- Fuel pumps and fittings.
- Synchronizing and control gear.
- Cooling system.
- Explosion relief devices.
- Gas and air piping.
- Receivers and valves, including by-pass arrangements.

12.1.5 Condensers, steam reheaters, desuperheaters which are not incorporated in the boilers, and any other appliances used for essential services, are to be examined to the satisfaction of the Surveyor and, if it is considered necessary, they are to be tested.

12.1.6 The manoeuvring of the engines is to be tested under working conditions.

12.1.7 Exhaust steam turbines supplying power for main propulsion purposes in conjunction with reciprocating engines together with their gearing and appliances, steam compressors or electrical machinery, are to be examined, so far as practicable. Where cone connections to internal gear shafts are fitted, the coned ends are to be examined, so far as practicable.

12.1.8 In ships having essential auxiliary machinery driven by oil engines, the prime movers of these auxiliaries are to be examined as detailed in Section 13.

## ■ Section 13 Oil engines – Detailed requirements

### 13.1 Complete Surveys

13.1.1 The requirements of Section 11 are to be complied with.

13.1.2 The following parts are to be opened out and examined:

- Cylinders and covers.
- Pistons, piston rods, connecting rods, crossheads and guides.
- Valves and valve gear.
- Crankshafts and all bearings.
- Crankcases, bedplates and entablatures.
- Crankcase door fastenings, explosion relief devices and scavenge relief devices.
- Scavenge pumps, scavenge blowers, superchargers and their associated coolers.
- Air compressors and their intercoolers.
- Filters and/or separators and safety devices.
- Fuel pumps and fittings.
- Camshaft drives and balancer units.
- Vibration dampers or detuners.
- Flexible couplings and clutches.
- Reverse gears.
- Attached pumps and cooling arrangements.

13.1.3 Selected pipes in the starting air system are to be removed for internal examination and are to be hammer tested. If any appreciable amount of lubricating oil is found in the pipes, the starting air system is to be thoroughly cleaned internally by steaming out, or other suitable means. Some of the pipes selected are to be those adjacent to the starting air valves at the cylinders and to the discharges from the air compressors.

13.1.4 The electric ignition system, if fitted, is to be examined and tested.

13.1.5 The manoeuvring of engines is to be tested under working conditions. Initial starting arrangements are to be tested.

13.1.6 Where steam is used for essential purposes, the condensing plant, feed pumps and oil fuel burning plant are to be examined and the steam pipes examined and tested as detailed in Section 16.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 14 & 15

## ■ Section 14 Electrical equipment

### 14.1 Annual and Intermediate Surveys

14.1.1 The requirements of 2.2 and 3.2 are to be complied with as far as applicable.

### 14.2 Complete Surveys

14.2.1 An electrical insulation resistance test is to be made on the electrical equipment and cables. The installation may be sub-divided, or equipment which may be damaged disconnected, for the purpose of this test.

14.2.2 The fittings on the main and emergency switch-board, section boards and distribution boards are to be examined and over-current protective devices and fuses inspected to verify that they provide suitable protection for their respective circuits.

14.2.3 Generator circuit-breakers are to be tested, so far as practicable, to verify that protective devices including preference tripping relays, if fitted, operate satisfactorily.

14.2.4 The electric cables are to be examined, so far as practicable, without undue disturbance of fixtures or casings, unless opening up is considered necessary as a result of observation or of the tests required by 14.2.1.

14.2.5 The generator prime movers are to be surveyed as required by Sections 12 and 13 and the governing of the engines tested. The motors concerned with essential services together with associated control and switch gear are to be examined and, if considered necessary, are to be operated, so far as practicable, under working conditions. All generators and steering gear motors are to be examined and are to be operated under working conditions, though not necessarily under full load or simultaneously.

14.2.6 Where transformers associated with supplies to essential services are liquid-immersed, the Owner is to arrange for samples of the liquid to be taken and tested for breakdown voltage, acidity and moisture by a competent testing authority, and a certificate giving the test results is to be furnished to the Surveyor.

14.2.7 Navigation light indicators are to be tried under working conditions, and correct operation on the failure of supply or failure of navigation lights is to be verified.

14.2.8 The emergency sources of electrical power, their automatic arrangements and associated circuits are to be tested.

14.2.9 Emergency lighting, transitional emergency lighting, supplementary emergency lighting, general emergency alarm and public address systems are to be tested as far as practicable.

14.2.10 Where the ship is electrically propelled, the propulsion motors, generators, cables and all ancillary electrical gear, exciters and ventilating plant (including coolers) associated therewith are to be examined, and the insulation resistance to earth is to be tested. Special attention is to be given to windings, commutators and slip-rings. The operation of protective gear and alarm devices is to be checked, so far as practicable. Insulating oil, if used, is to be tested in accordance with 14.2.6. Interlocks intended to prevent unsafe operations or unauthorized access are to be checked to verify that they are functioning correctly. Emergency overspeed governors are to be tested.

14.2.11 A General Examination of the electrical equipment in areas which may contain flammable gas or vapour and/or combustible dust is to be made to ensure that the integrity of the safe-type electrical equipment has not been impaired owing to corrosion, missing bolts, etc., and that there is not an excessive build-up of dust on or in dust protected electrical equipment. Cable runs are to be examined for sheath and armouring defects, where practicable, and to ensure that the means of supporting the cables are in good order. Tests are to be carried out to demonstrate the effectiveness of bonding straps for the control of static electricity. Alarms and interlocks associated with pressurized equipment or spaces are to be tested for correct operation.

### 14.3 Docking Surveys

14.3.1 For tankers five years old and over, 14.2.11 is to be complied with. In addition, an electrical insulation resistance test of the circuits terminating in, or passing through, the dangerous areas is to be carried out.

## ■ Section 15 Boilers

### 15.1 Frequency of surveys

15.1.1 All boilers, economizers, steam receivers, steam heated steam generators, thermal oil and hot water units intended for essential services, together with boilers used exclusively for non-essential services having a working pressure exceeding 3,5 bar and a heating surface exceeding 4,5 m<sup>2</sup> are to be surveyed internally. There is to be a minimum of two internal examinations during each five-year Special Survey cycle. The interval between any two such examinations is not to exceed 36 months. A general external examination is to be carried out at the time of the Annual Survey.

15.1.2 Consideration may be given in exceptional circumstances to an extension of the internal examination of the boiler not exceeding three months beyond the due date. The extension may be granted after the following is satisfactorily carried out:

- (a) External examination of the boiler
- (b) Examination and operational test of the boiler safety valve relieving gear (easing gear)



# Periodical Survey Regulations

## Part 1, Chapter 3

Sections 15 &amp; 16

- (c) Operational tests of the boiler protective devices
- (d) Review of the following records since the previous Boiler Survey:
  - Operation
  - Maintenance
  - Repair history
  - Feedwater chemistry

In this context 'exceptional circumstances' means unavailability of repair facilities, essential materials, equipment or spare parts, or delays incurred by action taken to avoid severe weather conditions.

**15.1.3** An external survey of boilers including tests of safety and protective devices, and tests of safety valves using their relieving gear, is to be carried out annually within the range dates of the Annual Survey of the ship. For exhaust gas heated economizers, the safety valves are to be tested by the Chief Engineer at sea within the range dates of the Annual Survey. This test is to be recorded in the log book and reviewed by the attending Surveyor prior to crediting the Annual Survey.

### 15.2 Scope of surveys

**15.2.1** At the surveys described in 15.1, the boilers, superheaters, economizers and air heaters are to be examined internally on the water-steam side and the fire side. Where considered necessary, the pressure parts are to be tested by hydraulic pressure and the thicknesses of plates and tubes and sizes of stays are to be ascertained to determine a safe working pressure. The safety valves and principal mountings on boilers, superheaters and economizers are to be examined and opened up as necessary by the Surveyor. The adjustment of safety valves is to be verified during each boiler internal survey. Boiler safety valves and their relieving gear are to be examined and tested to verify their satisfactory operation. Safety valves are to be set under steam to a pressure not greater than the approved design pressures of the respective parts. As a working tolerance, the setting is acceptable, provided that the valves lift at not more than 103 per cent of the approved design pressure. However, for exhaust gas heated economizers, if steam cannot be raised in port, the safety valves may be set by the Chief Engineer at sea, and the results recorded in the log book and reviewed by the attending Surveyor. The following records since the previous Boiler Survey are to be reviewed as part of the survey:

- Operation
- Maintenance
- Repair history
- Feedwater chemistry.

The remaining mountings are to be examined externally and, if considered necessary by the Surveyor, are to be opened up for internal examination. Collision chocks, rolling stays and boiler stools are to be examined and maintained in an efficient condition.

**15.2.2** In addition to the foregoing, in exhaust gas heated economizers of the shell type, all accessible welded joints are to be subjected to a visual examination in order to identify any evidence of cracking. Non-destructive testing may be required for this purpose and may be requested by the Surveyor.

**15.2.3** In fired boilers employing forced circulation, the pumps used for this service are to be opened and examined at each Boiler Survey.

**15.2.4** The oil fuel burning system is to be examined under working conditions and a General Examination made of fuel tank valves, pipes, deck control gear and oil discharge pipes between pumps and burners.

**15.2.5** At each survey of a cylindrical boiler which is fitted with smoke tube superheaters, the saturated steam pipes are to be examined as detailed in Section 16.

**15.2.6** At the annual General Examination referred to in 15.1.1 the requirements of 2.2.11 are to be complied with.

## Section 16 Steam pipes

### 16.1 Frequency of surveys

**16.1.1** Saturated steam pipes, as well as superheated steam pipes where the temperature of the steam at the superheater outlet is not over 450°C, are to be surveyed 10 years from the date of build (or installation) and thereafter at five-yearly intervals.

**16.1.2** Superheated steam pipes where the temperature of the steam at the superheater outlet is over 450°C are to be surveyed five years from the date of build (or installation) and thereafter at five-yearly intervals.

**16.1.3** At 10 years from the date of build (or installation) and thereafter at five-yearly intervals, all copper or copper alloy steam pipes over 76 mm external diameter supplying steam for essential services at sea, are to be hydraulically tested to twice the working pressure.

### 16.2 Scope of surveys

**16.2.1** At each survey, a selected number of main steam pipes, also of auxiliary steam pipes, which:

- (a) are over 76 mm external diameter,
- (b) supply steam for essential services at sea, and
- (c) have bolted joints,

are to be removed for internal examination and are to be hydraulically tested to 1,5 times the working pressure. If these selected pipes are found satisfactory in all respects, the remainder need not be tested. So far as practicable, the pipes are to be selected for examination and hydraulic test in rotation, so that in the course of surveys all sections of the pipeline will be tested.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 16 & 17

**16.2.2** Where main and/or auxiliary steam pipes of the category described in 16.2.1(a) and (b) have welded joints between the lengths of pipe and/or between pipes and valves, the lagging in way of the welds is to be removed, and the welds examined and, if considered necessary by the Surveyor, crack detected. Pipe ranges having welded joints are to be hydraulically tested to 1,5 times the working pressure. Where lengths having ordinary bolted joints are fitted in such pipe ranges and can be readily disconnected, they are to be removed for internal examination and hydraulically tested to 1,5 times the working pressure.

**16.2.3** Where, on cylindrical boilers having smoke tube superheaters, the saturated steam pipes adjoining the saturated steam headers are situated partly in the boiler smoke boxes, all such pipes adjoining and cross-connecting these headers in the smoke boxes are, at the surveys required by 16.1, to be included in the pipes selected for examination and testing, as defined in 16.2.1. Where the saturated steam pipes inside the smoke boxes consist of steel castings of substantial construction, these requirements need only be applied to a sample casting. Where steel castings are not fitted, the Surveyor is to satisfy himself of the condition of the ends of the saturated steam pipes in the smoke boxes at each Boiler Survey and, if he considers it necessary, a sample pipe is to be removed for examination.

**16.2.4** At the surveys specified in 16.1.3, any of the copper or copper alloy pipes, such as those having expansion or other bends, which may be subject to bending and/or vibration, as well as closing lengths adjacent to steam-driven machinery, are to be annealed before being tested.

**16.2.5** Where it is inconvenient for the Owner to fulfil all the requirements of a Steam Pipe Survey at its due date, the Committee will be prepared to consider postponement of the survey, either wholly or in part.

## Section 17 Screwshafts, tube shafts and propellers

### 17.1 Frequency of surveys

**17.1.1** Shafts with keyed propeller attachments and fitted with continuous liners or approved oil glands, or made of approved corrosion resistant materials, are to be surveyed at intervals of five years when the keyway complies fully with the present Rules.

**17.1.2** Shafts having keyless-type propeller attachments are to be surveyed at intervals of five years, provided that they are fitted with approved oil glands or are made of approved corrosion resistant materials.

**17.1.3** Shafts having solid coupling flanges at the after end are to be surveyed at intervals of five years, provided that they are fitted with approved oil glands or are made of approved corrosion resistant materials.

**17.1.4** All other shafts not covered by 17.1.1 to 17.1.3 are to be surveyed at intervals of 2½ years.

**17.1.5** Controllable pitch propellers for main propulsion purposes are to be surveyed at the same intervals as the screwshaft.

**17.1.6** Directional propeller and podded propulsion units for main propulsion purposes are to be surveyed at intervals not exceeding five years.

**17.1.7** Water jet units for main propulsion purposes are to be surveyed at intervals not exceeding five years, provided that the impeller shafts are made of approved corrosion resistant material or have approved equivalent arrangements.

**17.1.8** Dynamic positioning and/or thruster-assisted mooring and athwartship thrust propellers and shaftings are to be surveyed at intervals not exceeding five years.

### 17.2 Normal surveys

**17.2.1** All screwshafts are to be withdrawn for examination by LR's Surveyors at the intervals prescribed in 17.1.1 to 17.1.4. The after end of the cylindrical part of the shaft and forward one-third of the shaft cone, or fillet of the flange, are to be examined by a magnetic particle crack detection method. In the case of a keyed propeller attachment, at least the forward one-third of the shaft cone is to be examined with the key removed. Wear down is to be measured and the stern tube bearings, oil glands, propellers and fastenings are to be examined. Controllable pitch propellers, where fitted, are to be opened up and the working parts examined, together with the control gear.

**17.2.2** Directional propeller and podded propulsion units are to be dismantled for examination of the propellers, shafts, gearing, control and electrical gear.

**17.2.3** Water jet units are to be dismantled for examination of the impeller, casing, shaft, shaft seal, shaft bearing, inlet and outlet channels, steering nozzle, reversing arrangements, and control gear.

**17.2.4** Dynamic positioning and/or thruster-assisted mooring and athwartship thrust propellers are to be generally examined so far as possible in dry-dock and tested under working conditions afloat for satisfactory operation.

**17.2.5** Podded propulsion unit screwshaft roller bearings are to be renewed when the calculated life at the maximum continuous rating no longer exceeds the survey interval. See Pt 5, Ch 23,6.3.7.

# Periodical Survey Regulations

## Part 1, Chapter 3

Sections 17 &amp; 18

### 17.3 Screwshaft Condition Monitoring (SCM)

17.3.1 Where oil lubricated shafts with approved oil glands are fitted, and the Owner has complied with the following requirements, the ShipRight descriptive note **SCM** (Screwshaft Condition Monitoring) may be entered in column 6 of the *Register Book*:

- (a) Lubricating oil analysis to be carried out regularly at intervals not exceeding six months. The lubricating oil analysis documentation is to be available on board. Each analysis is to include the following minimum parameters:
  - water content
  - chloride content
  - bearing material and metal particles content
  - oil ageing (resistance to oxidation).
- (b) Oil samples are to be taken under service conditions and are to be representative of the oil within the sterntube.
- (c) Oil consumption is to be recorded.
- (d) Bearing temperatures are to be recorded, (two temperature sensors or other approved arrangements are to be provided).
- (e) Facilities are to be provided for measurement of bearing wear down.
- (f) Oil glands are to be capable of being replaced without withdrawal of the screwshaft.

17.3.2 For maintenance of the descriptive note **SCM**, the records of analyses, consumption and temperatures, together with wear down readings, are to be retained on board and audited annually.

17.3.3 Where the requirements for the descriptive note **SCM** have been complied with, the screwshaft need not be withdrawn at surveys as required by 17.2.1, provided all condition monitoring data are found to be within permissible limits and all exposed areas of the shaft are examined by a magnetic particle crack detection method. The remaining requirements of 17.2.1 are to be complied with. Where the Surveyor considers that the data presented are not entirely to his satisfaction, the shaft will be required to be withdrawn in accordance with 17.2.1.

### 17.4 Modified Survey

17.4.1 A Modified Survey may be accepted at alternate five-yearly surveys for shafts described in 17.1.1, provided that they are fitted with oil lubricated bearings and approved oil glands, and also for those in 17.1.2 and 17.1.3.

17.4.2 The Modified Survey is to consist of the partial withdrawal of the shaft, sufficient to ascertain the condition of the stern bearing and shaft in way. For keyless propellers or shafts with a solid flange connection to the propeller, a visual examination to confirm the good condition of the sealing arrangements is to be made. The oil glands are to be capable of being replaced without removal of the propeller. The forward bearing and all accessible parts, including the propeller connection to the shaft, are to be examined as far as possible. Wear down is to be measured and found satisfactory. Where a controllable pitch propeller is fitted, at least one of the blades is to be dismantled complete for examination of the working parts and the control gear.

17.4.3 For keyed propellers, the after end of the cylindrical part of the shaft and forward one-third of the shaft cone is to be examined by a magnetic particle crack detection method, for which dismantling of the propeller and removal of the key will be required.

17.4.4 Where the requirements for the descriptive note **SCM** have been complied with as described in 17.3.1 and all data are found to be within permissible limits, partial withdrawal of the shaft will not be required. Where doubt exists regarding any of the above findings, the shaft is to be withdrawn to permit an entire examination.

### 17.5 Partial Survey

17.5.1 For shafts where the Modified Survey is applicable, upon application by the Owner, the Committee will be prepared to give consideration to postponement of the survey for a maximum period of half the specified cycle provided a Partial Survey is held.

17.5.2 The Partial Survey is to consist of the propeller being backed off in any keyed shaft and the top half of the cone examined by an efficient crack detection method for which removal of the key will be required. Oil gland and seals are to be examined and dealt with as necessary. Wear down is to be measured and found satisfactory. Propeller and fastenings are to be examined.

17.5.3 The Committee will be prepared to give consideration to the circumstances of any special case upon application by the Owner.

## Section 18 Inert gas systems

### 18.1 Frequency of surveys

18.1.1 Inert gas systems installed on board ships intended for the carriage of oil or liquid chemicals in bulk are to be surveyed annually in accordance with the requirements of 2.2.22. A Special Survey of the inert gas system, in accordance with the requirements of 18.2, is to be held at intervals not exceeding five years.

### 18.2 Scope of surveys

18.2.1 At each Special Survey of the inert gas system, the inert gas generator, scrubber and blower are to be opened out as considered necessary and examined. Gas distribution lines and shut-off valves, including soot blower interlocking devices are to be examined as considered necessary. The deck seal and non-return valve are to be examined. Cooling water systems including the effluent piping and overboard discharge from the scrubbers are to be examined. All automatic shutdown devices and alarms are to be tested. The complete installation is to be tested under working conditions on completion of survey.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 18 & 19

**18.2.2** When, at the request of an Owner, it has been agreed by the Committee that the Complete Survey of the inert gas systems may be carried out on the Continuous Survey basis, the various items of machinery are to be opened for survey in rotation, so far as practicable, to ensure that the interval between consecutive examinations of each item will not exceed five years. In general, approximately one-fifth of the machinery is to be examined each year.

**18.2.3** If any examination during Continuous Survey reveals defects, further parts are to be opened up and examined as considered necessary by the Surveyors, and the defects are to be made good to their satisfaction.

**18.2.4** See 9.7.12 for inert gas systems on ships for liquefied gases.

## ■ Section 19 Classification of ships not built under survey

### 19.1 General

**19.1.1** When classification is desired for a ship not built under the supervision of LR's Surveyors, application should be made to the Committee in writing.

**19.1.2** Periodical Surveys of such ships, when classed, are subsequently to be held as in the case of ships built under survey.

**19.1.3** Where classification is desired for a ship which is classed by another recognized Society, special consideration will be given to the scope of the survey.

### 19.2 Hull and equipment

**19.2.1** Plans showing the main scantlings and arrangements of the actual ship, together with any proposed alterations, are to be submitted for approval. These should comprise plans of the midship section, longitudinal section and decks, and such other plans as may be requested. If plans cannot be obtained or prepared by the Owner, facilities are to be given for LR's Surveyor to obtain the necessary information from the ship.

**19.2.2** Particulars of the process of manufacture and the testing of the material of construction are to be supplied.

**19.2.3** In all cases, the full requirements of Sections 5, 6, 7, 8, 9 and 10 are to be carried out as applicable. Ships of recent construction will receive special consideration.

**19.2.4** During the survey, the Surveyors are to satisfy themselves regarding the workmanship and verify the approved scantlings and arrangements. For this purpose, and in order to ascertain the amount of any deterioration, parts of the structure will require to be gauged as necessary. Full particulars of the anchors, chain cables and equipment are to be submitted. For ships to which Pt 6, Ch 4 applies, fire protection, detection and extinction are to be in accordance with that Chapter. Loading instruments, where required, are to be in accordance with the Rules, see Pt 3, Ch 4,8 as applicable.

**19.2.5** When the full survey requirements indicated in 19.2.3 and 19.2.4 cannot be completed at one time, the Committee may consider granting an interim record for a limited period. The conditions regarding the completion of the survey will depend on the merits of each particular case, which should be submitted for consideration.

### 19.3 Machinery

**19.3.1** To facilitate the survey, plans of the following items (plans of piping are to be diagrammatic), together with the particulars of the materials used in the construction of the boilers, air receivers and important forgings, are to be furnished:

- General pumping arrangements, including air and sounding pipes (Shipbuilder's plan).
- Pumping arrangements at the forward and after ends of oil tankers and drainage of cofferdams and pump rooms.
- General arrangement of cargo piping in tanks and on deck of oil tankers.
- Piping arrangements for cargo oil (F.P. 60°C or above, closed cup test).
- Bilge, ballast and oil fuel pumping arrangements in the machinery space, including the capacities of the pumps on bilge service.
- Arrangement and dimensions of main steam pipes.
- Arrangement of oil fuel pipes and fittings at settling and service tanks.
- Arrangement of oil fuel piping in connection with oil burning installations.
- Oil fuel and cargo oil overflow systems, where these are fitted.
- Arrangement of boiler feed systems.
- Oil fuel settling, service and other oil fuel tanks not forming part of the ship's structure.
- Boilers, superheaters and economizers.
- Air receivers.
- Crank, thrust, intermediate and screw shafting.
- Clutch and reversing gear with methods of control.
- Reduction gearing.
- Propeller (including spare propeller if supplied).
- Electrical circuits.
- Arrangement of compressed air systems for main and auxiliary services.
- Arrangement of lubricating oil systems.
- Arrangement of flammable liquids used for power transmission, control and heating systems.
- Arrangement of cooling water systems for main and auxiliary services.

# Periodical Survey Regulations

# Part 1, Chapter 3

Sections 19 & 20

- General arrangement of cargo tank vents. The plan is to indicate the type and position of the vent outlets from any superstructure, erection, air intake, etc. Ventilation arrangements of cargo and/or ballast pump rooms and other enclosed spaces which contain cargo handling equipment.

19.3.2 Plans additional to those detailed in 19.3.1 are not to be submitted unless the machinery is of a novel or special character affecting classification.

19.3.3 Where remote and/or automatic controls are fitted to propulsion machinery and essential auxiliaries, a description of the scheme is to be submitted.

19.3.4 For new ships and ships which have been in service less than two years, calculations of the torsional vibration characteristics of the propelling machinery are to be submitted for consideration, as required for ships constructed under Special Survey. For older ships, the circumstances will be specially considered in relation to their service record and type of machinery installed. Where calculations are not submitted, the Committee may require that the machinery certificate be endorsed to this effect. When desired by the Owner, the calculations and investigation of the torsional vibration characteristics of the machinery may be carried out by LR upon special request.

19.3.5 The main and auxiliary machinery, feed pipes, compressed air pipes and boilers are to be examined as required at Complete Surveys. Working pressures are to be determined from the actual scantlings in accordance with the Rules.

19.3.6 The screwshaft is to be drawn and examined.

19.3.7 The steam pipes are to be examined and tested as required by Section 16.

19.3.8 The bilge, ballast and oil fuel pumping arrangements are to be examined and amended, as necessary, to comply with the Rules.

19.3.9 Oil burning installations are to be examined as required at Complete Surveys and found, or modified, to comply with the requirements of the Rules; they are also to be tested under working conditions.

19.3.10 The electrical equipment is to be examined as required at Complete Surveys.

19.3.11 Where an inert gas system is fitted on ships intended for the carriage of oil in bulk having a flashpoint not exceeding 60°C, the requirements of Pt 5, Ch 15,7, apply.

19.3.12 The whole of the machinery, including essential controls, is to be tried under working conditions to the Surveyor's satisfaction.

19.3.13 First entry reports are to be prepared by the Surveyors.

## 19.4 Refrigerated cargoes

19.4.1 When classification is desired for an installation not constructed under the supervision of LR's Surveyors, application is to be made to the Committee in writing.

19.4.2 Full particulars and plans are to be forwarded for consideration, together with the particulars of the materials of the crankshafts, pressure vessels and pressure piping. The requirements of Pt 6, Ch 3,1 and Ch 3,4 are to be used for guidance in regard to the information required.

19.4.3 A special examination is to be made at least to the extent required for subsequent Special Surveys, see 20.3.

19.4.4 The thickness and material of the insulation, the particulars of the frames, beams, stiffeners and other steelwork within the insulation, the air coolers and/or chamber grid piping, the compressors, evaporators and condensers are to be verified so far as practicable.

19.4.5 The installation is to conform to the requirements of the relevant Sections of Pt 6, Ch 3.

19.4.6 Acceptance tests are to be carried out in accordance with the requirements of Pt 6, Ch 3,5.

## Section 20 Refrigerated cargo installations

### 20.1 Annual Surveys

20.1.1 The Surveyors are to examine the machinery under working conditions as soon as practicable after a ship's arrival at a port of discharge before the cargo is unloaded. An examination of the refrigerated cargo installation log book (or other records) is to be made and any breakdowns or malfunctions of the plant during the previous twelve months are to be noted and reported to the Committee.

20.1.2 A General Examination of the refrigerating plant is to be carried out, and satisfactory operation of safety devices, controls and thermometry is to be verified. Insulated cargo spaces are to be inspected, and the condition of insulation, lining, scuppers, hatches, coolers, air ducting and air refreshing arrangements are to be checked. The Surveyors may request opening out of suspected items, or recommend repair or renewal of defective items, as a result of inspection.

20.1.3 A General Examination is to be made of electrical motors driving refrigerant compressors, pumps and fans, together with their control gear and cables. Random tests for insulation resistance are to be made on the cables, switchgear, motors, etc., and this resistance is to be not less than 1 MΩ between individual conductors and between those conductors and earth. The installation may be subdivided for the purpose of this test, and the Surveyor may at his discretion accept the results of tests carried out by a competent member of staff or contractor.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 20

20.1.4 A survey book or other permanent record is to be kept on board the ship to show the date of examination of the various parts. This is to be available to the Surveyor at all times, and is to be signed by the Surveyor on the occasion of each survey.

## 20.2 Special Surveys

20.2.1 At the first Special Survey, the examinations outlined below are to be carried out. Where there is a programme of replacement instead of maintenance on board, alternative survey arrangements will be considered. Each case will be given individual consideration.

20.2.2 Detailed internal examination of each reciprocating compressor, opened up for inspection of cylinders, pistons, connection rods, valves, seats, glands, relief devices, filters, lubrication and crankshaft.

20.2.3 For screw-type compressors, the period before opening up may be extended to six years or 25 000 running hours, whichever is the earlier. Examination should be made of rotors, clearances, gearing, etc.

20.2.4 Refrigerant condenser cooling water pumps, including standby pump(s) which may be used on other services, are to be opened up and their working parts exposed.

20.2.5 Primary and secondary refrigerant pumps are to be opened up and their working parts exposed.

20.2.6 The water end covers of condensers are to be removed for examination of the tubes, tubeplates and covers.

20.2.7 In the case of pressure vessels covered by insulation, any evidence of dampness or deterioration of the insulation which could lead to external corrosion of the vessels or their connections is to be investigated.

20.2.8 Sufficient insulation is to be stripped from insulated pressure vessels to allow the condition of the vessels and their connections to be ascertained. Care is to be taken that in replacement of the insulation, the vapour sealing of the outer covering is made good.

20.2.9 Sufficient insulation is to be stripped from pipes carrying the refrigerant at various points of the system both outside and inside the insulated chambers to permit the condition of the pipes to be ascertained. Sections of piping exposed are to include locations where lengths of piping have been connected by screwed couplings or butt welding. Care is to be taken that when ungalvanized portions of the piping in way of joints have been exposed, they are to be suitably coated and taped, after pressure testing, to prevent corrosion. On replacement of the insulation, the vapour sealing of the outer covering is to be made good.

20.2.10 A General Examination is to be made of all pressure relief valves and/or safety discs throughout the refrigerating plant to ensure that they are in good order and covered by current certification. However, no attempt is to be made to test primary refrigerant pressure relief on board ship. Relief valves are to be removed, overhauled and recalibrated every five years or in accordance with the manufacturer's recommendations, whichever is sooner.

20.2.11 Sea connections to refrigerant condenser cooling water pumps are to be opened up on the occasion of the hull and/or main machinery Special Survey.

20.2.12 The electric motors driving refrigerant compressors, pumps and fans, together with their control gear and cables, are to have their insulation resistance tested and this is to be not less than 1 MΩ between individual conductors and between those conductors and earth. The installation may be subdivided to any desired extent by opening switches, removing fuses or disconnecting appliances for the purpose of this test.

20.2.13 All automatic controls, alarms and safety systems are to be tested and correct operation confirmed.

20.2.14 Sufficient air ducting and insulation lining is to be stripped from the cargo spaces or chamber's overhead and vertical surfaces to allow the condition of the insulation, insulation linings, grounds, supports, hangers and fixtures which support the insulation, grids, meat rails, etc., to be ascertained. Care is to be taken that on replacement, the ducts and linings are sealed against air blowing into the insulation, or against moisture ingress from refrigerated cell or space atmosphere.

20.2.15 Sufficient tank top insulation is to be stripped to allow the condition of the grounds and inner insulation lining to be ascertained.

20.2.16 Due consideration is to be given to the type of insulation used in the cargo spaces and chambers when determining the amount of insulation lining to be removed. Where organic foam insulants have been used, including panel systems or foamed *in situ*, or other insulants in slab form, the removal of panels or linings is to be at the Surveyor's discretion.

20.2.17 Under normal circumstances, the condition of the cargo space and chamber insulation, grounds, etc., can be ascertained when the Special Survey of the ship's steel structure is being held.

20.2.18 Arrangements made for defrosting air coolers, and for draining condensate from trays below coolers, are to be examined to ascertain that they are in working order. Trace heating elements around drain pipes should be specially examined.

20.2.19 Any air refreshing arrangements are to be examined.

# Periodical Survey Regulations

## Part 1, Chapter 3

Section 20

### 20.3 Subsequent Special Survey

20.3.1 A subsequent Special Survey is to be held approximately five years from the date of the previous Special Survey. Where a Continuous Survey procedure has been agreed, the interval between consecutive examinations of each item should not exceed five years.

20.3.2 In addition to the requirements for the first Special Survey as detailed in 20.2, paragraphs 20.3.3 to 20.3.5 are to be complied with.

20.3.3 'Shell-and-tube' condensers and evaporators (secondary refrigerant coolers) in which the primary refrigerant is in the shell, are to have the shell pneumatically tested with the refrigerant, or air, or a mixture of inert gas and refrigerant (with the end covers removed) at pressures as stated in Pt 6, Ch 3,2.5.5.

20.3.4 Shell-and-tube evaporators (secondary refrigerant coolers) in which the secondary refrigerant is in the shell are to have the shell hydraulically tested (with the end covers removed) to 1,5 times the design pressure, but in no case less than 2,9 bar g. After refitting the end covers, the primary refrigerant side is to be pneumatically tested as stated in 20.3.3, and an examination made as far as practicable for gas leakage in the shell with the secondary refrigerant connection removed.

20.3.5 Heat exchangers used for cooling refrigerant liquid by the suction return gas to a compressor are not subject to internal corrosion, and would normally require to be specially examined internally only if leakage is suspected between high and low pressure sides. This type of heat exchanger, together with others using brine or water, are to be examined and tested at the discretion of the Surveyor according to the design of such equipment.

### 20.4 Loading Port Survey

20.4.1 When a Loading Port Certificate is required by the Owner or his representative, a survey as detailed in 20.4.2 to 20.4.7 is to be carried out at the loading port. The certificate is not in respect of the cargo to be loaded or the manner in which it is to be stowed.

20.4.2 The refrigerating installation is to be examined under working conditions, and the temperatures in the cargo chambers are to be noted.

20.4.3 A General Examination of the generating plant supplying electric power to the refrigerated cargo installation is to be carried out to confirm that it complies with Pt 6, Ch 3,6.1.

20.4.4 The refrigerated cargo spaces and chambers are to be examined in an empty state to ascertain that they are clean and free from odour which may adversely affect the cargo to be loaded, that the air cooler coils and cooling grids and their connections are free from leakage, that cargo battens, where fixed to the vertical surfaces, are in good order, that cargo gratings or dunnage battens (see Pt 6, Ch 3) are available as necessary for the floors or decks, and that no damage has been sustained to the insulation or its lining prior to the loading of the refrigerated cargo. Any indications of defective insulation not considered to warrant immediate attention are to be noted and specially reported.

20.4.5 All scuppers and bilge suctions draining insulated spaces are to be examined to ensure that they are in good working order, and that any liquid seals are primed.

20.4.6 If the ship loads at more than one port, one survey only at the first loading port will be required, provided that it includes the examination of all spaces or chambers which are to be used for refrigerated cargo during the voyage, and that general cargo is not subsequently carried in any of the spaces or chambers prior to loading the refrigerated cargo.

20.4.7 In the case of ships engaged on voyages of less than two months' duration, a Loading Port Certificate will be considered as valid for two months, provided that the cargoes carried are of such a nature as not to damage the insulation or appliances in the insulated chambers, nor to affect, by taint or mould, the refrigerated cargoes loaded during that period. For longer voyages, the certificate is valid for only one cargo from the loading port(s) to the discharge port(s).

20.4.8 If there is no LR Surveyor available at the loading port(s), or if none is obtainable from a port within a reasonable distance, the Committee will accept the report of a survey held at the loading port by two competent engineers of the ship.

### 20.5 Refrigerating plant on ships not classed with LR

20.5.1 In the case of refrigerating installations being constructed under Special Survey on ships not intended to be classed with LR, the installation is to comply with the applicable requirements of Pt 6, Ch 3.

20.5.2 The generator engines and electrical equipment, which supply power to the refrigerating installations are to be constructed in accordance with the requirements of the Classification Society concerned and the installation is also to comply with the requirements of Pt 6, Ch 3,6.1.2. Such a plant is to be examined generally and under working conditions by the Surveyors.

# Periodical Survey Regulations

# Part 1, Chapter 3

Section 21

## ■ Section 21 Controlled atmosphere systems

### 21.1 Retention of class

21.1.1 It is a prerequisite of the **CA** notation that the refrigeration installation on board already conforms to a **⌘Lloyd's RMC** notation, see Pt 1, Ch 2,2.5.1.

21.1.2 For the retention of Class, the CA systems are to be submitted for Periodical Surveys by LR's Surveyors as specified in 21.2 and 21.3.

### 21.2 Annual Surveys

21.2.1 Annual Surveys are to be carried out from the date of the Initial Classification Survey to verify that the CA system remains satisfactory.

21.2.2 The complete CA installation is to be visually examined and tested for the following main aspects:

- (a) CA zone sealing arrangements including cleats and hinges, pressure/vacuum (P/V) valves, door locks, ventilation of adjacent spaces, warning notices.
- (b) CA zones to be individually tested for airtightness to the design pressure. Testing by ship's staff, within one month prior to the survey may be accepted, based on a written report by the Master subject to visual inspection confirming the airtightness.
- (c) Operation and performance testing of the gas supply equipment, including controls, alarms, interlocks, safety devices.
- (d) Ventilation arrangements including fans.
- (e) Electrical supply arrangements.
- (f) Gas analyzers and analyzing equipment and calibration.
- (g) RH sensors and calibrations.
- (h) Permanent and portable gas monitoring, calibration and personnel safety equipment.
- (j) Witnessing of the air leakage.
- (k) Voyage logs, records of CA zone airtightness and calibration of instruments.
- (l) Verification that an Operating and Safety Manual is on board, is complete and that the responsible officers have countersigned to confirm that they are familiar with its contents.

21.2.3 On satisfactory completion of this survey, a new Annual Survey 'AS', with date, will be assigned.

### 21.3 Special Surveys

21.3.1 Special Surveys are to be carried out at intervals of five years from the date of the Initial Classification Survey to verify that all machinery, CA zones and safety arrangements remain satisfactory. On request from Owners, all surveyable items may be examined on a continuous basis. With this option, 20 per cent of all items are to be presented for survey annually.

21.3.2 Each CA zone is to be subjected to an airtightness test.

21.3.3 The extent of dismantling is to be at the LR Surveyor's discretion, but is to be sufficient for the Surveyor to be satisfied as to the condition of the installation.

21.3.4 On satisfactory completion of this survey, a new Special Survey 'SS', or 'RMC CS' with date, will be assigned.





© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

SHIP STRUCTURES (GENERAL)

JULY 2007

PART 3

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

---

PART	1	REGULATIONS
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
<b>PART</b>	<b>3</b>	<b>SHIP STRUCTURES (GENERAL)</b>
	<b>Chapter 1</b>	<b>General</b>
	<b>2</b>	<b>Materials</b>
	<b>3</b>	<b>Structural Design</b>
	<b>4</b>	<b>Longitudinal Strength</b>
	<b>5</b>	<b>Fore End Structure</b>
	<b>6</b>	<b>Aft End Structure</b>
	<b>7</b>	<b>Machinery Spaces</b>
	<b>8</b>	<b>Superstructures, Deckhouses and Bulwarks</b>
	<b>9</b>	<b>Special Features</b>
	<b>10</b>	<b>Welding and Structural Details</b>
	<b>11</b>	<b>Closing Arrangements for Shell, Deck and Bulkheads</b>
	<b>12</b>	<b>Ventilators, Air Pipes and Discharges</b>
	<b>13</b>	<b>Ship Control Systems</b>
	<b>14</b>	<b>Cargo Securing Arrangements</b>
	<b>15</b>	<b>Quality Assurance Scheme for the Hull Construction of Ships</b>
	<b>16</b>	<b>ShipRight Procedures for the Design, Construction and Lifetime Care of Ships</b>
PART	4	SHIP STRUCTURES (SHIP TYPES)
PART	5	MAIN AND AUXILIARY MACHINERY
PART	6	CONTROL, ELECTRICAL, REFRIGERATION AND FIRE
PART	7	OTHER SHIP TYPES AND SYSTEMS

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.



---

<b>CHAPTER</b>	<b>1</b>	<b>GENERAL</b>
<b>Section</b>	<b>1</b>	<b>Rule application</b>
	1.1	General
	1.2	Exceptions
	1.3	Loading
	1.4	Advisory services
	1.5	Intact stability
<b>Section</b>	<b>2</b>	<b>Direct calculations</b>
	2.1	General
	2.2	ShipRight – Design, construction and lifetime ship care procedures
	2.3	Submission of direct calculations
<b>Section</b>	<b>3</b>	<b>Equivalents</b>
	3.1	Alternative arrangements and scantlings
<b>Section</b>	<b>4</b>	<b>National and International Regulations</b>
	4.1	International Conventions
	4.2	International Association of Classification Societies (IACS)
	4.3	International Maritime Organization (IMO)
<b>Section</b>	<b>5</b>	<b>Information required</b>
	5.1	General
	5.2	Plans and supporting calculations
	5.3	Plans to be supplied to the ship
	5.4	Fire protection, detection and extinction
<b>Section</b>	<b>6</b>	<b>Definitions</b>
	6.1	Principal particulars
	6.2	Freeboard deck
	6.3	Weathertight
	6.4	Watertight
	6.5	Position 1 and Position 2
	6.6	Passenger ship
	6.7	Reference system
	6.8	Co-ordinate system
<b>Section</b>	<b>7</b>	<b>Equipment Number</b>
	7.1	Calculation of Equipment Number
<b>Section</b>	<b>8</b>	<b>Inspection, workmanship and testing procedures</b>
	8.1	Inspection
	8.2	Workmanship
	8.3	Testing procedures
<b>CHAPTER</b>	<b>2</b>	<b>MATERIALS</b>
<b>Section</b>	<b>1</b>	<b>Materials of construction</b>
	1.1	General
	1.2	Steel
	1.3	Aluminium
<b>Section</b>	<b>2</b>	<b>Fracture control</b>
	2.1	Grades of steel
	2.2	Refrigerated spaces
	2.3	Grades of steel for ice-breaking ships designed to operate in low ambient temperatures

# Contents

# Part 3

---

<b>Section</b>	<b>3</b>	<b>Corrosion protection</b>
	3.1	General
	3.2	Prefabrication primers
	3.3	Internal cathodic protection
	3.4	Aluminium and magnesium anodes
	3.5	External hull protection
	3.6	Corrosion protection coatings for salt-water ballast spaces
<b>Section</b>	<b>4</b>	<b>Deck covering</b>
	4.1	General
<b>CHAPTER</b>	<b>3</b>	<b>STRUCTURAL DESIGN</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
<b>Section</b>	<b>2</b>	<b>Rule structural concepts</b>
	2.1	Definition of requirements
	2.2	Definition of fore end region
	2.3	Definition of aft end region
	2.4	Symbols
	2.5	Taper requirements for hull envelope
	2.6	Vertical extent of higher tensile steel
	2.7	Grouped stiffeners
<b>Section</b>	<b>3</b>	<b>Structural idealization</b>
	3.1	General
	3.2	Geometric properties of section
	3.3	Determination of span point
	3.4	Calculation of hull section modulus
<b>Section</b>	<b>4</b>	<b>Bulkhead requirements</b>
	4.1	Number and disposition of bulkheads
	4.2	Collision bulkhead
	4.3	After peak bulkhead
	4.4	Height of bulkheads
	4.5	Watertight recesses, flats and loading ramps
	4.6	Longitudinal subdivision
	4.7	Protection of tanks carrying oil fuel, lubricating oil, vegetable or similar oils
	4.8	Watertight tunnels and passageways
	4.9	Means of escape
	4.10	Oil tankers
<b>Section</b>	<b>5</b>	<b>Design loading</b>
	5.1	General
	5.2	Symbols
	5.3	Stowage rate and design loads
	5.4	Design pressure for partially filled tanks
<b>Section</b>	<b>6</b>	<b>Minimum bow heights, reserve buoyancy and extent of forecastle</b>
	6.1	Minimum bow heights
	6.2	Extent of forecastle
<b>CHAPTER</b>	<b>4</b>	<b>LONGITUDINAL STRENGTH</b>
<b>Section</b>	<b>1</b>	<b>Definitions</b>
	1.1	List of symbols



---

<b>Section</b>	<b>2</b>	<b>General</b>
	2.1	Longitudinal strength calculations
	2.2	Erections contributing to hull strength
	2.3	Open type ships
	2.4	Ships with large flare
	2.5	Direct calculation procedures
	2.6	Approved calculation systems
<b>Section</b>	<b>3</b>	<b>Application</b>
	3.1	Symbols
	3.2	General
	3.3	Exceptions
<b>Section</b>	<b>4</b>	<b>Information required</b>
	4.1	List of requirements
<b>Section</b>	<b>5</b>	<b>Hull bending strength</b>
	5.1	Symbols
	5.2	Design vertical wave bending moments
	5.3	Design still water bending moments
	5.4	Minimum hull section modulus
	5.5	Permissible still water bending moments
	5.6	Permissible hull vertical bending stresses
	5.7	Local reduction factors
	5.8	Hull moment of inertia
	5.9	Continuous strength members above strength deck
<b>Section</b>	<b>6</b>	<b>Hull shear strength</b>
	6.1	Symbols
	6.2	General
	6.3	Design wave shear force
	6.4	Design still water shear force
	6.5	Permissible still water shear force
	6.6	Permissible shear stress
	6.7	Design shear stress
<b>Section</b>	<b>7</b>	<b>Hull buckling strength</b>
	7.1	Application
	7.2	Symbols
	7.3	Elastic critical buckling stress
	7.4	Design stress
	7.5	Scantling criteria
<b>Section</b>	<b>8</b>	<b>Loading guidance information</b>
	8.1	General
	8.2	Loading Manual
	8.3	Loading instrument
<b>CHAPTER</b>	<b>5</b>	<b>FORE END STRUCTURE</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration
	1.3	Structural continuity
	1.4	Symbols and definitions
	1.5	Strengthening of bottom forward
	1.6	Strengthening against bow flare slamming

# Contents

# Part 3

---

<b>Section</b>	<b>2</b>	<b>Deck structure</b>
	2.1	General
	2.2	Deck plating
	2.3	Deck stiffening
	2.4	Deck supporting structure
	2.5	Deck openings
<b>Section</b>	<b>3</b>	<b>Shell envelope plating</b>
	3.1	General
	3.2	Keel
	3.3	Stem
	3.4	Bottom shell and bilge
	3.5	Side shell and sheerstrake
	3.6	Shell openings
<b>Section</b>	<b>4</b>	<b>Shell envelope framing</b>
	4.1	General
	4.2	Shell longitudinals
	4.3	Shell framing
	4.4	Panting stringers in way of transverse framing
	4.5	Primary structure at sides
<b>Section</b>	<b>5</b>	<b>Single and double bottom structure</b>
	5.1	General
	5.2	Single bottoms – Transverse framing
	5.3	Single bottoms – Longitudinal framing
	5.4	Double bottoms
<b>Section</b>	<b>6</b>	<b>Fore peak structure</b>
	6.1	General
	6.2	Bottom structure
	6.3	Side structure – Transverse framing
	6.4	Side structure – Longitudinal framing
	6.5	Bulbous bow
	6.6	Wash bulkhead
	6.7	Collision bulkhead
<b>Section</b>	<b>7</b>	<b>Forward deep tank structure</b>
	7.1	General
	7.2	Bottom structure
	7.3	Side structure – Transverse framing
	7.4	Side structure – Longitudinal framing
	7.5	Wash bulkheads
	7.6	Transverse boundary bulkheads
<b>CHAPTER</b>	<b>6</b>	<b>AFT END STRUCTURE</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration
	1.3	Structural continuity
	1.4	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Deck structure</b>
	2.1	General
	2.2	Deck plating
	2.3	Deck stiffening
	2.4	Deck supporting structure
	2.5	Deck openings

---

<b>Section</b>	<b>3</b>	<b>Shell envelope plating</b>
	3.1	General
	3.2	Keel
	3.3	Bottom shell and bilge
	3.4	Side shell and sheerstrake
	3.5	Shell openings
<b>Section</b>	<b>4</b>	<b>Shell envelope framing</b>
	4.1	General
	4.2	Shell longitudinals
	4.3	Shell framing
	4.4	Panting stringers in way of transverse framing
	4.5	Primary structure at sides
<b>Section</b>	<b>5</b>	<b>Single and double bottom structure</b>
	5.1	General
	5.2	Single bottoms – Transverse framing
	5.3	Single bottoms – Longitudinal framing
	5.4	Double bottoms
<b>Section</b>	<b>6</b>	<b>After peak structure</b>
	6.1	Bottom structure
	6.2	Side structure – Transverse framing
	6.3	Side structure – Longitudinal framing
	6.4	Wash bulkheads
	6.5	After peak bulkhead
<b>Section</b>	<b>7</b>	<b>Sternframes and appendages</b>
	7.1	General
	7.2	Sternframes
	7.3	Rudder horns
	7.4	Shaft bossing
	7.5	Shaft brackets
	7.6	Propeller hull clearances
<b>CHAPTER</b>	<b>7</b>	<b>MACHINERY SPACES</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration
	1.3	Structural continuity
	1.4	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Deck structure</b>
	2.1	Strength deck – Plating
	2.2	Strength deck – Primary structure
	2.3	Lower decks
<b>Section</b>	<b>3</b>	<b>Side shell structure</b>
	3.1	Secondary stiffening
	3.2	Primary structure – Transverse framing
	3.3	Primary structure – Longitudinal framing
<b>Section</b>	<b>4</b>	<b>Double and single bottom structure</b>
	4.1	Double bottom structure
	4.2	Single bottom structure
<b>Section</b>	<b>5</b>	<b>Machinery casings and oil fuel bunkers</b>
	5.1	Machinery casings
	5.2	Oil fuel bunkers

---

<b>Section</b>	<b>6</b>	<b>Engine seatings</b>
	6.1	General
	6.2	Seats for oil engines
	6.3	Seats for turbines
	6.4	Seats for boilers
	6.5	Seats for auxiliary machinery
 <b>CHAPTER</b>	 <b>8</b>	 <b>SUPERSTRUCTURES, DECKHOUSES AND BULWARKS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Symbols
	1.3	Definition of tiers
	1.4	Design pressure head
 <b>Section</b>	 <b>2</b>	 <b>Scantlings of erections other than forecastles</b>
	2.1	Thickness of bulkhead and side plating
	2.2	Stiffeners and their connections
	2.3	Deck plating
	2.4	Deck longitudinals and beams
	2.5	Deck girders and transverses
	2.6	Strengthening at ends and sides of erections
	2.7	Erections contributing to hull strength
	2.8	Unusual designs
 <b>Section</b>	 <b>3</b>	 <b>Aluminium erections</b>
	3.1	Scantlings
	3.2	Bimetallic joints
 <b>Section</b>	 <b>4</b>	 <b>Forecastles</b>
	4.1	Construction
 <b>Section</b>	 <b>5</b>	 <b>Bulwarks, guard rails and other means for the protection of crew</b>
	5.1	General requirements
	5.2	Bulwark construction
	5.3	Freeing arrangements
	5.4	Free flow area
	5.5	Special requirements for tugs and offshore supply ships
 <b>CHAPTER</b>	 <b>9</b>	 <b>SPECIAL FEATURES</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Symbols
 <b>Section</b>	 <b>2</b>	 <b>Timber deck cargoes</b>
	2.1	Application
	2.2	Symbols and definitions
	2.3	Statutory Requirements
	2.4	Arrangements
	2.5	Longitudinal strength
	2.6	Deck loading and scantlings
	2.7	Scantlings of hatch covers
	2.8	Direct calculations
 <b>Section</b>	 <b>3</b>	 <b>Decks loaded by wheeled vehicles</b>
	3.1	General
	3.2	Symbols
	3.3	Loading
	3.4	Deck plating
	3.5	Deck longitudinals and beams
	3.6	Deck girders and transverses

	3.7	Direct calculations
	3.8	Hatch covers
	3.9	Train decks
	3.10	Heavy and special loads
	3.11	Securing arrangements
<b>Section</b>	<b>4</b>	<b>Movable decks</b>
	4.1	Classification
	4.2	Symbols
	4.3	Arrangements and design
	4.4	Loading
	4.5	Pontoon deck plating
	4.6	Pontoon webs and stiffeners
	4.7	Deflection
	4.8	Direct calculations
<b>Section</b>	<b>5</b>	<b>Helicopter landing areas</b>
	5.1	General
	5.2	Symbols
	5.3	Arrangements
	5.4	Landing area plating
	5.5	Deck stiffening and supporting structure
	5.6	Bimetallic connections
<b>Section</b>	<b>6</b>	<b>Strengthening requirements for navigation in ice – Application of requirements</b>
	6.1	Additional strengthening
	6.2	Geographical zones
	6.3	Icebreakers
<b>Section</b>	<b>7</b>	<b>Strengthening requirements for navigation in first-year ice conditions</b>
	7.1	General
	7.2	Definitions
	7.3	Framing – General requirements
	7.4	Primary longitudinal members supporting transverse ice framing
	7.5	Stem
	7.6	Stern
	7.7	Rudder and steering arrangements
<b>Section</b>	<b>8</b>	<b>Strengthening requirements for navigation in multi-year ice conditions</b>
	8.1	Ice Class notations
	8.2	Application
	8.3	Definitions
	8.4	Arrangement
	8.5	Longitudinal strength
	8.6	Bulkheads
	8.7	Bottom structure
	8.8	Powering of ships intended to operate in multi-year ice conditions
	8.9	Shell plating
	8.10	Transverse framing
	8.11	Longitudinal framing
	8.12	Framing – General requirements
	8.13	Primary longitudinal members supporting transverse ice framing
	8.14	Web frames
	8.15	Stem
	8.16	Stern
	8.17	Bossings and shaft struts
	8.18	Rudder, steering arrangements and nozzles
	8.19	Direct calculations

<b>Section</b>	<b>9</b>	<b>Strengthening requirements for navigation in very light first-year ice conditions</b>
	9.1	General
	9.2	Shell plating
	9.3	Transverse framing
	9.4	Primary longitudinal members supporting ice frames
	9.5	Sternframe and rudder
	9.6	Weld connections
<b>Section</b>	<b>10</b>	<b>Lifting appliances and support arrangements</b>
	10.1	General
	10.2	Masts, derrick posts and crane pedestals
	10.3	Support structure for masts, derrick posts and crane pedestals
	10.4	Lifting appliances
<b>Section</b>	<b>11</b>	<b>Freight container securing arrangements</b>
	11.1	Classification
<b>Section</b>	<b>12</b>	<b>Bottom strengthening for loading and unloading aground</b>
	12.1	Application
<b>Section</b>	<b>13</b>	<b>Strengthening for regular discharge by heavy grabs</b>
	13.1	Application
	13.2	Inner bottom plating
	13.3	Hopper side tank sloped bulkhead plating
	13.4	Transverse bulkhead plating
<b>CHAPTER</b>	<b>10</b>	<b>WELDING AND STRUCTURAL DETAILS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Symbols
<b>Section</b>	<b>2</b>	<b>Welding</b>
	2.1	General
	2.2	Butt welds
	2.3	Lap connections
	2.4	Closing plates
	2.5	Stud welding
	2.6	Fillet welds
	2.7	Welding of primary structure
	2.8	Welding of primary and secondary member end connections
	2.9	Welding equipment
	2.10	Welding consumables and equipment
	2.11	Welding procedures and welder qualifications
	2.12	Workmanship and shipyard practice
	2.13	Inspection of welds
<b>Section</b>	<b>3</b>	<b>Secondary member end connections</b>
	3.1	General
	3.2	Symbols
	3.3	Basis for calculation
	3.4	Scantlings of end brackets
	3.5	Arrangements and details
<b>Section</b>	<b>4</b>	<b>Construction details for primary members</b>
	4.1	General
	4.2	Symbols
	4.3	Arrangements
	4.4	Geometric properties and proportions
	4.5	Web stability
	4.6	Openings in the web
	4.7	End connections

<b>Section</b>	<b>5</b>	<b>Structural details</b>
	5.1	Continuity and alignment
	5.2	Arrangements at intersections of continuous secondary and primary members
	5.3	Openings
	5.4	Sheerstrake and bulwarks
	5.5	Fittings and attachments, general
	5.6	Bilge keels and ground bars
	5.7	Other fittings and attachments
<b>Section</b>	<b>6</b>	<b>Access arrangements for oil tankers and bulk carriers</b>
	6.1	Application
	6.2	Information for approval
<b>CHAPTER</b>	<b>11</b>	<b>CLOSING ARRANGEMENTS FOR SHELL, DECK AND BULKHEADS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Symbols
<b>Section</b>	<b>2</b>	<b>Steel hatch covers</b>
	2.1	Plating
	2.2	Webs and stiffeners
<b>Section</b>	<b>3</b>	<b>Hatch beams and wood covers</b>
	3.1	Portable hatch beams
	3.2	Wood covers
<b>Section</b>	<b>4</b>	<b>Hatch cover securing arrangements and tarpaulins</b>
	4.1	Cargo oil tank and adjacent spaces
	4.2	Steel covers – Clamped and gasketed
	4.3	Portable covers – Tarpaulins and battening devices
<b>Section</b>	<b>5</b>	<b>Hatch coamings</b>
	5.1	General
	5.2	Construction
	5.3	Rest bars in hatchways
	5.4	Loading in excess of Rule requirements
<b>Section</b>	<b>6</b>	<b>Miscellaneous openings</b>
	6.1	Small hatchways on exposed decks
	6.2	Manholes and flush scuttles
	6.3	Hatchways within enclosed superstructures or 'tween decks
	6.4	Companionways, doors and accesses on weather decks
	6.5	Side scuttles, windows and skylights
	6.6	Small hatchways on exposed fore decks
<b>Section</b>	<b>7</b>	<b>Tanker access arrangements and closing appliances</b>
	7.1	Materials
	7.2	Cargo tank access hatchways
	7.3	Enlarged cargo tank access openings
	7.4	Miscellaneous openings
	7.5	Access to spaces other than cargo tanks
	7.6	Equivalents
	7.7	Other openings

---

<b>Section</b>	<b>8</b>	<b>Side and stern doors and other shell openings</b>
	8.1	Symbols
	8.2	General
	8.3	Scantlings
	8.4	Doors serving as ramps
	8.5	Arrangements for the closing, securing and supporting of doors
	8.6	Design loads
	8.7	Design of securing and supporting devices
	8.8	Operating and Maintenance Manual
<b>Section</b>	<b>9</b>	<b>Watertight doors in bulkheads below the freeboard deck</b>
	9.1	Openings in bulkheads
	9.2	Watertight doors
<b>Section</b>	<b>10</b>	<b>External openings and openings in watertight bulkheads and internal decks in cargo ships</b>
	10.1	Shell and watertight subdivision openings
<b>CHAPTER</b>	<b>12</b>	<b>VENTILATORS, AIR PIPES AND DISCHARGES</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Protection
<b>Section</b>	<b>2</b>	<b>Ventilators</b>
	2.1	General
	2.2	Coamings
	2.3	Closing appliances
	2.4	Machinery spaces
<b>Section</b>	<b>3</b>	<b>Air and sounding pipes</b>
	3.1	General
	3.2	Height of air pipes
	3.3	Closing appliances
<b>Section</b>	<b>4</b>	<b>Scuppers and sanitary discharges</b>
	4.1	General
	4.2	Closing appliances
	4.3	Rubbish chutes, offal and similar discharges
	4.4	Materials for valves, fittings and pipes
<b>Section</b>	<b>5</b>	<b>Air pipes, ventilator pipes and their securing devices located on the exposed fore deck</b>
	5.1	General
	5.2	Loading
	5.3	Strength requirements
	5.4	Ventilator coamings
	5.5	Height of air pipes
	5.6	Closing appliances for ventilators
	5.7	Closing appliances for air pipes
<b>CHAPTER</b>	<b>13</b>	<b>SHIP CONTROL SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	General symbols
	1.3	Navigation in ice
	1.4	Materials



<b>Section</b>	<b>2</b>	<b>Rudders</b>
	2.1	Lateral force on rudder blade
	2.2	Rudder torque calculation for rudders without cut-outs
	2.3	Rudder torque calculation for rudders with cut-outs
	2.4	Rudder stock and main bearing
	2.5	Rudder construction – Double plated
	2.6	Rudder construction – Single plated
	2.7	Rudder couplings
	2.8	Pintles
	2.9	Ancillary items
<b>Section</b>	<b>3</b>	<b>Fixed and steering nozzles</b>
	3.1	General
	3.2	Nozzle structure
	3.3	Nozzle stock and solepiece
	3.4	Ancillary items
<b>Section</b>	<b>4</b>	<b>Steering gear and allied systems</b>
	4.1	General
<b>Section</b>	<b>5</b>	<b>Bow and stern thrust unit structure</b>
	5.1	Unit wall thickness
	5.2	Framing
<b>Section</b>	<b>6</b>	<b>Stabilizer structure</b>
	6.1	Fin stabilizers
	6.2	Stabilizer tanks
<b>Section</b>	<b>7</b>	<b>Equipment</b>
	7.1	General
	7.2	Anchors
	7.3	High holding power anchors
	7.4	Chain cables
	7.5	Towlines and mooring lines
	7.6	Windlass design and testing
	7.7	Testing of equipment
	7.8	Structural requirements associated with anchoring
	7.9	Structural requirements for windlasses on exposed fore decks
	7.10	Structural requirements associated with towing and mooring
<b>Section</b>	<b>8</b>	<b>Mooring of ships at single point moorings</b>
	8.1	General
	8.2	Arrangements
<b>Section</b>	<b>9</b>	<b>Emergency towing arrangements</b>
	9.1	Structural requirements
	9.2	Chafing chain and wire or fibre rope for Emergency Towing Arrangements
<b>CHAPTER</b>	<b>14</b>	<b>CARGO SECURING ARRANGEMENTS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Plans and information required
	1.3	Securing systems
	1.4	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Fixed cargo securing fittings, materials and testing</b>
	2.1	General
	2.2	Materials and design
	2.3	Prototype testing
	2.4	Production testing

---

<b>Section</b>	<b>3</b>	<b>Loose container securing fittings, materials and testing</b>
	3.1	General
	3.2	Materials and design
	3.3	Prototype testing
	3.4	Production testing
<b>Section</b>	<b>4</b>	<b>Ship structure</b>
	4.1	General
	4.2	Strength
<b>Section</b>	<b>5</b>	<b>Container securing arrangements for stowage on exposed decks without cell guides</b>
	5.1	General
	5.2	Containers in one tier
	5.3	Containers in two tiers
	5.4	Containers in more than two tiers
	5.5	Line Load stowage
	5.6	Systems incorporating structural restraint
<b>Section</b>	<b>6</b>	<b>Container securing arrangements for underdeck stowage without cell guides</b>
	6.1	General
<b>Section</b>	<b>7</b>	<b>Container securing arrangements for stowage using cell guides</b>
	7.1	General
	7.2	Arrangement and construction
	7.3	Mixed stacks of 20 ft and 40 ft containers
	7.4	Cell guide systems on exposed decks
	7.5	Entry guide devices
<b>Section</b>	<b>8</b>	<b>Determination of forces for container securing arrangements</b>
	8.1	General
	8.2	Resultant forces
<b>Section</b>	<b>9</b>	<b>Strength of container securing arrangements</b>
	9.1	Resultant applied forces
	9.2	Forces in an unlashed stack
	9.3	Arrangements incorporating lashings or buttresses
	9.4	Tensions in the lashing rods
	9.5	Residual forces
	9.6	Structural restraint systems
	9.7	Allowable forces on containers
<b>Section</b>	<b>10</b>	<b>Surveys</b>
	10.1	Initial Survey
	10.2	Periodical Surveys
<b>CHAPTER</b>	<b>15</b>	<b>QUALITY ASSURANCE SCHEME FOR THE HULL CONSTRUCTION OF SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Definitions
	1.2	Scope of the Quality Assurance Scheme
<b>Section</b>	<b>2</b>	<b>Application</b>
	2.1	Certification of the shipyard
<b>Section</b>	<b>3</b>	<b>Particulars to be submitted</b>
	3.1	Documentation and procedures
	3.2	Amendments

<b>Section</b>	<b>4</b>	<b>Requirements of Parts 1 and 2 of the Scheme</b>
	4.1	General
	4.2	Policy statement
	4.3	Responsibility
	4.4	Management Representative
	4.5	Quality control and testing personnel
	4.6	Resources
	4.7	The Quality Management System
	4.8	Regulatory requirements
	4.9	Control of hull drawings
	4.10	Documentation and change control
	4.11	Purchasing data and receipt
	4.12	Owner supplied material
	4.13	Identification and traceability
	4.14	Fabrication control
	4.15	Control of inspection and testing
	4.16	Indication of inspection status
	4.17	Inspection, measuring and test equipment
	4.18	Non-conforming materials and corrective action
	4.19	Protection and preservation of quality
	4.20	Records
	4.21	Internal audit and management review
	4.22	Training
	4.23	Sampling
	4.24	Sub-contracted personnel, services and components
<b>Section</b>	<b>5</b>	<b>Additional requirements for Part 2 of the Scheme</b>
	5.1	Quality System procedures
	5.2	Quality Plans
	5.3	Material supplier approval
	5.4	Identification and traceability
	5.5	Fabrication control
	5.6	Control of inspection and testing
	5.7	Control of non-conforming materials and corrective action
	5.8	Records
	5.9	Training
	5.10	Sub-contracted personnel, services and components
<b>Section</b>	<b>6</b>	<b>Initial assessment of the shipyard</b>
	6.1	General
<b>Section</b>	<b>7</b>	<b>Approval of the shipyard</b>
	7.1	General
<b>Section</b>	<b>8</b>	<b>Maintenance of approval</b>
	8.1	General
<b>Section</b>	<b>9</b>	<b>Suspension or withdrawal of approval</b>
	9.1	General
<b>CHAPTER</b>	<b>16</b>	<b>SHIPRIGHT PROCEDURES FOR THE DESIGN, CONSTRUCTION AND LIFETIME CARE OF SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Classification notations and descriptive notes
	1.3	Information and plans required to be submitted
<b>Section</b>	<b>2</b>	<b>Structural design assessment</b>
	2.1	Structural Design Assessment notation – SDA
<b>Section</b>	<b>3</b>	<b>Fatigue design assessment</b>
	3.1	Fatigue Design Assessment notation – FDA

---

<b>Section</b>	<b>4</b>	<b>Construction monitoring</b>
	4.1	Construction Monitoring notation – <b>CM</b>
<b>Section</b>	<b>5</b>	<b>Ship Event Analysis</b>
	5.1	Ship Event Analysis – Descriptive notes <b>SEA(HSS-n)</b>
<b>Section</b>	<b>6</b>	<b>Enhanced scantlings</b>
	6.1	Enhanced Scantlings – Descriptive note <b>ES</b>
<b>Section</b>	<b>7</b>	<b>Protective coating in water ballast tanks</b>
	7.1	Protective Coating in Water Ballast Tanks – Descriptive note <b>PCWBT</b>
<b>Section</b>	<b>8</b>	<b>Hull planned maintenance</b>
	8.1	Descriptive note <b>HPMS</b>
<b>Section</b>	<b>9</b>	<b>Ship Emergency Response Service</b>
	9.1	Ship Emergency Response Service – Descriptive note <b>SERS</b>
<b>Section</b>	<b>10</b>	<b>Assessment of Ballast Water Management Plans</b>
	10.1	Ballast Water Management Plan – Descriptive note <b>BWMP</b>

## Section

- 1 **Rule application**
- 2 **Direct calculations**
- 3 **Equivalents**
- 4 **National and International Regulations**
- 5 **Information required**
- 6 **Definitions**
- 7 **Equipment Number**
- 8 **Inspection, workmanship and testing procedures**

## ■ Section 1 Rule application

### 1.1 General

1.1.1 The Rules apply in general to single hull ships of normal form, proportions and speed. Relevant parameters to define what is regarded as normal are given by limitations specified at the beginning of individual ship type Chapters. Although the Rules are, in general, for steel ships of all welded construction, other materials for use in hull construction will be considered.

### 1.2 Exceptions

1.2.1 Ships of unusual form, proportions or speed, intended for the carriage of special cargoes, or for special or restricted service, not covered by Parts 3 and 4, will receive individual consideration based on the general standards of the Rules.

1.2.2 The requirements of 7.1 and 8.3 are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2,2.3).

### 1.3 Loading

1.3.1 The Rules are framed on the understanding that ships will be properly loaded and handled; they do not, unless it is stated or implied in the class notation, provide for special distributions or concentrations of loading other than those included in the approved Loading Manual. The Committee may require additional strengthening to be fitted in any ship which, in their opinion, would otherwise be subjected to severe stresses due to particular features of the design, or where it is desired to make provision for exceptional load or ballast conditions.

### 1.4 Advisory services

1.4.1 The Rules do not cover certain technical characteristics, such as stability, trim, vibration, docking arrangements, etc. The Committee cannot assume responsibility for these matters but is willing to advise upon them on request.

### 1.5 Intact stability

1.5.1 New ships to which the Load Lines Conventions are applicable will be assigned Class only after it has been demonstrated that the level of intact stability is adequate, see Pt 1, Ch 2,1.1.9.

## ■ Section 2 Direct calculations

### 2.1 General

2.1.1 Direct calculations may be specifically required by the Rules or may be required for ships having novel design features, as defined in 1.2 or may be submitted in support of alternative arrangements and scantlings. Lloyd's Register (hereinafter referred to as 'LR') may, when requested, undertake calculations on behalf of designers and make recommendations in regard to suitability of any required model tests.

2.1.2 Where model testing is undertaken to complement direct calculations the following details would normally be required to be submitted:

- Schedule of tests;
- details of test equipment;
- input data;
- analysis; and
- calibration procedure together with tabulated and plotted output.

### 2.2 ShipRight – Design, construction and lifetime ship care procedures

2.2.1 LR's direct calculation procedures and facilities are summarized in two documents entitled *ShipRight Procedures Manual* and *Marine Software Guide*.

### **2.3 Submission of direct calculations**

2.3.1 In cases where direct calculations have been carried out using ShipRight procedures, the following supporting information should be submitted as applicable:

- (a) Reference to the ShipRight direct calculation procedure and technical program used.
- (b) A description of the structural modelling.
- (c) A summary of analysis parameters including properties and boundary conditions.
- (d) Details of the loading conditions and the means of applying loads.
- (e) A comprehensive summary of calculation results. Sample calculations should be submitted where appropriate.

2.3.2 In general, submission of large volumes of input and output data associated with such programs as finite element analysis will not be necessary.

2.3.3 The responsibility for error free specification and input of program data and the subsequent correct transposal of output rests with the Builder.

## ■ **Section 3 Equivalents**

### **3.1 Alternative arrangements and scantlings**

3.1.1 In addition to cases where direct calculations are specifically required by the Rules, LR will consider alternative arrangements and scantlings which have been derived by direct calculations in lieu of specific Rule requirements. All direct calculations are to be submitted for examination.

3.1.2 Where calculation procedures other than those available within ShipRight are employed, supporting documentation is to be submitted for appraisal and this is to include details of the following:

- calculation methods, assumptions and references;
- loading;
- structural modelling;
- design criteria and their derivation, e.g. permissible stresses, factors of safety against plate panel instability, etc.

3.1.3 LR will be ready to consider the use of Builders' programs for direct calculations in the following cases:

- (a) Where it can be established that the program has previously been satisfactorily used to perform a direct calculation similar to that now submitted.
- (b) Where sufficient information and evidence of satisfactory performance is submitted to substantiate the validity of the computation performed by the program.

## ■ **Section 4**

### **National and International Regulations**

#### **4.1 International Conventions**

4.1.1 The Committee, when authorized, will act on behalf of Governments and, if requested, LR will certify compliance in respect of National and International statutory safety and other requirements for passenger and cargo ships.

4.1.2 In satisfying the Load Line Conventions, the general structural strength of the ship is required to be sufficient for the draught corresponding to the freeboards to be assigned. Ships built and maintained in accordance with LR's Rules and Regulations possess adequate strength to satisfy the Load Line Conventions. However, some National Authorities may, in addition, require to be supplied with calculations of bending moments and shear forces for certain conditions of loading.

#### **4.2 International Association of Classification Societies (IACS)**

4.2.1 Where applicable, the Rules take into account unified requirements and interpretations established by IACS.

#### **4.3 International Maritime Organization (IMO)**

4.3.1 Attention is drawn to the fact that Codes of Practice issued by IMO contain requirements which are outside classification as defined in these Rules and Regulations.

## ■ **Section 5 Information required**

### **5.1 General**

5.1.1 The categories and lists of information required are given in 5.2.

5.1.2 Plans are generally to be submitted in triplicate, but one copy only is necessary for supporting documents and calculations.

5.1.3 Plans are to contain all necessary information to fully define the structure, including construction details, equipment and systems as appropriate.

5.1.4 Additional requirements for individual ship types are given in subsequent Chapters.

## 5.2 Plans and supporting calculations

5.2.1 Plans covering the following items are to be submitted:

- Midship sections showing longitudinal and transverse material.
- Profile and decks.
- Shell expansion.
- Oiltight and watertight bulkheads.
- Propeller brackets.
- Double bottom construction.
- Pillars and girders.
- Aft end construction.
- Engine room construction.
- Engine and thrust seatings.
- Fore end construction.
- Hatch coamings.
- Hatch cover construction.
- Deckhouses and superstructures.
- Sternframe.
- Rudder, stock and tiller.
- Equipment.
- Loading Manuals, preliminary and final.
- Ice strengthening.
- Welding.
- Hull penetration plans.
- Support structure for masts, derrick posts or cranes.
- Bilge keels showing material grades, welded connections and detail design.
- Supporting structure of deck fittings used for towing and mooring.

5.2.2 The following supporting documents are to be submitted:

- General arrangement.
- Capacity plan.
- Lines plan or equivalent.
- Dry-docking plan.
- Freeboard plan or equivalent showing freeboards and items relative to the conditions of assignment.
- Towing and mooring arrangements plan as defined in 5.3.8.
- When the ship is required to comply with statutory damage stability criteria:  
Watertight Integrity plan or equivalent showing watertight boundaries and associated design head necessary to satisfy damage stability criteria.

5.2.3 The following supporting calculations are to be submitted:

- Calculation of Equipment Number.
- Calculation of hull girder still water bending moment and shear force as applicable.
- Calculation of midship section modulus.
- Calculations for structural items in the aft end, midship and fore end regions of the ship.
- Preliminary freeboard calculation.

5.2.4 Where an **\*IWS** (In-water Survey) notation is to be assigned (see Pt 1, Ch 2,2.3.11), plans and information covering the following items are to be submitted:

- Details showing how rudder pintle and bush clearances are to be measured and how the security of the pintles in their sockets are to be verified with the vessel afloat.
- Details showing how stern bush clearances are to be measured with the vessel afloat.
- Details of high resistant paint, for information only.

5.2.5 Where it is intended to exchange ballast water at sea resulting in the partial filling of the ballast spaces, the scantlings and structural arrangements of the tank boundaries are to be capable of withstanding the loads imposed by the movement of the ballast water in those spaces. The magnitude of the predicted loadings, together with the scantling calculations, may require to be submitted.

5.2.6 Ships that are required to comply with SOLAS Regulation 3-6 in chapter II-1 for 'Access to and within spaces in the cargo area of oil tankers and bulk carriers' are to supply information showing attachment of the access arrangements to the ship structure. This is to include necessary strength calculations, local detail and any reinforcements.

## 5.3 Plans to be supplied to the ship

5.3.1 To facilitate the ordering of materials for repairs, plans are to be carried in the ship indicating the disposition and grades (other than Grade A) of hull structural steel, the extent and location of higher tensile steel together with details of specification and mechanical properties, and any recommendations for welding, working and treatment of these steels.

5.3.2 Similar information is to be provided when aluminium alloy or other materials are used in the hull construction.

5.3.3 A copy of the final Loading Manual, when approved, and details of the loadings applicable to approved decks, hatch covers and inner bottom are to be placed on board the ship.

5.3.4 Details of any corrosion control system fitted are to be placed on board the ship.

5.3.5 Copies of main scantling plans are to be placed on board.

5.3.6 Where an **\*IWS** (In-water Survey) notation is to be assigned, approved plans and information covering the items detailed in 5.2.4 are to be placed on board.

5.3.7 Where a ShipRight **CM** (Construction Monitoring) notation or descriptive note is to be assigned, the approved Construction Monitoring Plan (CMP), as detailed in the ShipRight Construction Monitoring Procedures, is to be maintained on board the ship.

5.3.8 The towing and mooring arrangements plan is to be provided on board for the guidance of the Master. The information provided on the plan is to include the following in respect of each shipboard fitting:

- Location on the ship.
- Fitting type.
- Safe working load (SWL).
- Purpose of fitting (mooring/harbour towing/escort towing).
- Manner of applying towing or mooring line load, including limiting fleet angles.

This information is to be incorporated into the pilot card in order to provide the pilot with the necessary information on harbour/escorting operations.

## 5.4 Fire protection, detection and extinction

5.4.1 For information and plans required, see Pt 6, Ch 4.

## Section 6 Definitions

### 6.1 Principal particulars

6.1.1 Rule length,  $L$ , is the distance, in metres, on the summer load waterline from the forward side of the stem to the after side of the rudder post or to the centre of the rudder stock if there is no rudder post.  $L$  is to be not less than 96 per cent, and need not be greater than 97 per cent, of the extreme length on the summer load waterline. In ships with unusual stem or stern arrangements the Rule length,  $L$ , will be specially considered.

6.1.2 Amidships is to be taken as the middle of the Rule length,  $L$ , measuring from the forward side of the stem.

6.1.3 Breadth,  $B$ , is the greatest moulded breadth, in metres.

6.1.4 Depth,  $D$ , is measured, in metres, at the middle of the length,  $L$ , from top of keel to top of the deck beam at side on the uppermost continuous deck, or as defined in appropriate Chapters. When a rounded gunwale is arranged, the depth,  $D$ , is to be measured to the continuation of the moulded deck line.

6.1.5 Draught,  $T$ , is the summer draught, in metres, measured from top of keel.

6.1.6 The block coefficient,  $C_b$ , is the moulded block coefficient at draught,  $T$ , corresponding to summer load waterline, based on Rule length,  $L$ , and moulded breadth,  $B$ , as follows:

$$C_b = \frac{\text{moulded displacement (m}^3\text{) at draught } T}{LBT}$$

6.1.7 Length between perpendiculars,  $L_{pp}$ , is the distance, in metres, on the summer load waterline from the fore side of the stem to the after side of the rudder post, or to the centre of the rudder stock if there is no rudder post. In ships with unusual stern arrangements the length,  $L_{pp}$ , will be specially considered. The forward perpendicular, F.P., is the perpendicular at the intersection of the summer load waterline with the fore side of the stem. The after perpendicular, A.P., is the perpendicular at the intersection of the summer load waterline with the after side of the rudder post. For ships without a rudder post, the A.P. is the perpendicular at the intersection of the waterline with the centreline of the rudder stock.

6.1.8 Load line length,  $L_L$ , is to be taken as 96 per cent of the total length on a waterline at 85 per cent of the least moulded depth measured from the top of the keel, or as the length from the fore side of the stem to the axis of the rudder stock on that waterline, if that is greater. In ships designed with a rake of keel, the waterline on which this length is measured is to be parallel to the designed waterline. The length  $L_L$  is to be measured in metres.

6.1.9 Load line block coefficient,  $C_{bL}$ , is defined as:

$$C_{bL} = \frac{\nabla}{L_L B T_L}$$

where

$\nabla$  = volume of the moulded displacement, in m<sup>3</sup>, excluding appendages, taken at draught  $T_L$

$T_L$  = moulded draught, in metres, measured to the waterline at 85 per cent of the least moulded depth.

6.1.10 Maximum service speed,  $V$ , means the maximum ahead service speed, in knots, which the ship is designed to maintain, at the summer load waterline at maximum propeller RPM and corresponding MCR.

6.1.11 Bow reference height,  $H_b$ , is defined as:  
For ships less than 250 m in length:

$$H_b = 0,056L_L \left(1 - \frac{L_L}{500}\right) \left(\frac{1,36}{C_{bL} + 0,68}\right) \text{ m}$$

For ships 250 m or greater in length:

$$H_b = 7 \left(\frac{1,36}{C_{bL} + 0,68}\right) \text{ m}$$

where

$L_L$  is defined in 6.1.8

$C_{bL}$  is defined in 6.1.9.

### 6.2 Freeboard deck

6.2.1 The freeboard deck is normally the uppermost complete deck exposed to weather and sea, which has permanent means of closing all openings in the weather part, and below which all openings in the sides of the ship are fitted with permanent means of watertight closing.



## General

## Part 3, Chapter 1

Sections 6 &amp; 7

6.2.2 For the purposes of the Load Lines Conventions, as applicable, where the assigned summer freeboard is increased such that the resulting draught is not more than that corresponding to a minimum summer freeboard for the same ship, but with an assumed freeboard deck located a distance below the actual freeboard deck at least equal to the standard superstructure height, the related items for the conditions of assignment to the actual freeboard deck may be as required for a superstructure deck.

### 6.3 Weathertight

6.3.1 A closing appliance is considered weathertight if it is designed to prevent the passage of water into the ship in any sea conditions.

6.3.2 Generally, all openings in the freeboard deck and in enclosed superstructures are to be provided with weathertight closing appliances.

### 6.4 Watertight

6.4.1 A closing appliance is considered watertight if it is designed to prevent the passage of water in either direction under a head of water for which the surrounding structure is designed.

6.4.2 Generally, all openings below the freeboard deck in the outer shell/envelope (and in main bulkheads) are to be fitted with permanent means of watertight closing.

### 6.5 Position 1 and Position 2

6.5.1 For the purpose of Load Line conditions of assignment, there are two basic positions of hatchways, doorways and ventilators defined as follows:

- Position 1 – Upon exposed freeboard and raised quarterdecks, and exposed superstructure decks within the forward 0,25 of the load line length.
- Position 2 – Upon exposed superstructure decks abaft the forward 0,25 of the load line length and located at least one standard height of superstructure above the freeboard deck. Upon exposed superstructure decks situated within the forward 0,25 of the Load Line length and located at least two standard heights of superstructure above the freeboard deck.

### 6.6 Passenger ship

6.6.1 A passenger ship is a ship which carries more than 12 passengers.

### 6.7 Reference system

6.7.1 For hull reference purposes, the ship is divided into 21 equally spaced stations where Station 0 is the after perpendicular, Station 20 is the forward perpendicular, and Station 10 is mid- $L_{pp}$ .

### 6.8 Co-ordinate system

6.8.1 Unless otherwise stated, the co-ordinate system is as shown in Fig. 1.6.1, that is, a right-hand co-ordinate system with the X axis positive forward, the Y axis positive to port and the Z axis positive upwards. Angular motions are considered positive in a clockwise direction about the X, Y or Z axes.




Fig. 1.6.1 Co-ordinate system

## Section 7

### Equipment Number

#### 7.1 Calculation of Equipment Number

7.1.1 The equipment of anchors and chain cables specified in Ch 13,7 is based on an 'Equipment Number' which is to be calculated as follows:

$$\text{Equipment Number} = \Delta^{2/3} + 2BH + \frac{A}{10}$$

where

$A$  = area, in  $m^2$ , in profile view of the hull, within the Rule length of the vessel, and of superstructures and houses above the summer load waterline, which are within the Rule length of the vessel, and also having a breadth greater than  $\frac{B}{4}$

See also 7.1.3 and 7.1.4

$B$  = greatest moulded breadth, in metres

# General

# Part 3, Chapter 1

Sections 7 & 8

$H$  = freeboard amidships, in metres, from the summer load waterline to the upper deck, plus the sum of the heights at the centreline, in metres, of each tier of houses having a breadth greater than  $\frac{B}{4}$

See also 7.1.2, 7.1.3 and 7.1.4

$\Delta$  = moulded displacement, in tonnes, to the summer load waterline.

7.1.2 In the calculation of  $H$  and  $A$ , sheer and trim are to be ignored. Where there is a local discontinuity in the upper deck,  $H$  is to be measured from a notional deckline.

7.1.3 If a house having a breadth greater than  $\frac{B}{4}$  is above a house with a breadth of  $\frac{B}{4}$  or less, then the wide house is to be included, but the narrow house ignored.

7.1.4 Screens and bulwarks more than 1,5 m in height are to be regarded as parts of houses when determining  $H$  and  $A$ . Where a screen or bulwark is of varying height, the portion to be included is to be that length, the height of which exceeds 1,5 m.

7.1.5 The Equipment Number for tugs is to be calculated as follows:

$$\text{Equipment Number} = \Delta^{2/3} + 2(Bf + \Sigma bh) + \frac{A}{10}$$

where

$\Delta$ ,  $B$  and  $A$  are defined in 7.1.1

$b$  = breadth, in metres, of the widest superstructure or deckhouse on each tier

$f$  = freeboard amidships, in metres, from the summer load waterline

$h$  = the height, in metres, of each tier of superstructure or deckhouse at side having a breadth of  $\frac{B}{4}$  or greater. In the calculation of  $h$ , sheer and trim are to be ignored.

## Section 8 Inspection, workmanship and testing procedures

### 8.1 Inspection

8.1.1 Adequate facilities are to be provided to enable the Surveyor to carry out a satisfactory inspection of all components during each stage of prefabrication and construction.

### 8.2 Workmanship

8.2.1 All workmanship is to be of good quality and in accordance with good shipbuilding practice. Any defect is to be rectified to the satisfaction of the Surveyor before the material is covered with paint, cement or other composition. The materials and welding are to be in accordance with the requirements of the Rules for Materials (Part 2). The assembly sequence and welding sequence are to be agreed prior to construction and are to be to the satisfaction of the Surveyor. Plates which have been subjected to excessive heating while being worked are to be satisfactorily heat treated before being erected in the hull.

8.2.2 **Wood sheathing on decks.** Where plated decks are sheathed with wood, the sheathing is to be efficiently attached to the deck, caulked and sealed, to the satisfaction of the Surveyor.

8.2.3 **Rudder and sternframe.** The final boring out of the propeller boss and sternframe skeg or solepiece, and the fit-up and alignment of the rudder, pintles and axles, are to be carried out after completing the major part of the welding of the after part of the ship. The contacts between the conical surfaces of pintles, rudder stocks and rudder axles are to be checked before the final mounting.

### 8.3 Testing procedures

8.3.1 **Definitions.** For the purpose of these procedures the following definitions apply:

- (a) **Protective coating** is the coating system applied to protect the structure from corrosion. This excludes the prefabrication primer.
- (b) **Structural testing** is a hydrostatic test carried out to demonstrate the tightness of the tanks and the structural adequacy of the design. Where practical limitations prevail and hydrostatic testing is not feasible, hydropneumatic testing (see 8.3.1(e)), may be carried out instead.
- (c) **Leak testing** is an air or other medium test carried out to demonstrate the tightness of the structure.
- (d) **Hose testing** is carried out to demonstrate the tightness of structural items not subjected to hydrostatic or leak testing, and other components which contribute to the watertight or weathertight integrity of the hull.
- (e) **Hydropneumatic testing** is a combination of hydrostatic and air testing, consisting of filling the tank with water and applying an additional air pressure. The conditions are to simulate, as far as practicable, the actual loading of the tank and in no case is the air pressure to be less than given in 8.3.4.

8.3.2 **Application.** The testing requirements for gravity tanks including independent tanks of 5 m<sup>3</sup> or more in capacity, watertight and weathertight compartments, are listed in Table 1.8.1. Tests are to be carried out in the presence of the Surveyor at a stage sufficiently close to completion such that the strength and tightness are not subsequently impaired.

## General

## Part 3, Chapter 1

## Section 8

**Table 1.8.1** Testing requirements (to be continued)

Item to be tested	Testing procedure	Testing requirement
Double bottom tanks	Structural <sup>(1)</sup>	The greater of: <ul style="list-style-type: none"> <li>• head of water up to the top of the overflow</li> <li>• head of water up to the margin line</li> <li>• head of water representing the maximum pressure experienced in service</li> </ul>
Combined double bottom and lower hopper side tanks	Structural <sup>(1)</sup>	The greater of: <ul style="list-style-type: none"> <li>• head of water representing the maximum pressure experienced in service</li> <li>• head of water up to the top of the overflow</li> </ul>
Combined double bottom, lower hopper and topside tanks	Structural <sup>(1)</sup>	The greater of: <ul style="list-style-type: none"> <li>• head of water up to the top of the overflow</li> <li>• 2,4 m head of water above highest point of tank <sup>(4)</sup></li> </ul>
Double side tanks	Structural <sup>(1)</sup>	
Topside tanks	Structural <sup>(1)</sup>	
Cofferdams	Structural <sup>(1)</sup>	
Forepeak and aft peak used as tank <sup>(3)</sup>	Structural	
Tank bulkheads	Structural <sup>(1)</sup>	The greater of: <ul style="list-style-type: none"> <li>• head of water up to the top of the overflow</li> <li>• 2,4 m head of water above the highest point of tank <sup>(4)</sup></li> <li>• setting pressure of the safety valves, where relevant <sup>(10)</sup></li> <li>• 2,0p m above the top of the tank, where p is the relative density of any intended cargo</li> </ul>
Deep tanks	Structural <sup>(1)</sup>	
Fuel oil bunkers	Structural	
Scupper and discharge pipes in way of tanks	Structural <sup>(1)</sup>	
Cargo holds with trunks fitted	Structural <sup>(1)</sup>	The greater of test heads given in Table 1.8.2
Water ballast holds in bulk carriers (see 1.2.2)	Structural <sup>(1)</sup>	The tank testing requirement is not to be less than the head up to the top of the hatch coaming <sup>(11)</sup> & <sup>(12)</sup>
Double plate rudders	Structural <sup>(1)</sup> , <sup>(5)</sup>	2,4 m head of water, and rudder should normally be tested while laid on its side
Steel hatch covers fitted to the cargo oil tanks and cargo holds of ships used for the alternate carriage of oil cargo and dry bulk cargo <sup>(6)</sup>	Structural <sup>(1)</sup>	The greater of: <ul style="list-style-type: none"> <li>• 2,4 m head of water above the top of hatch cover</li> <li>• setting pressure of the safety valves <sup>(10)</sup></li> </ul>
Watertight bulkheads, shaft tunnels, flats and recesses, etc.	Hose <sup>(2)</sup>	See 8.3.5
Watertight doors (below freeboard or bulkhead deck) when fitted in place	Hose <sup>(9)</sup>	
Weathertight hatch covers and closing appliances	Hose	
Fore peak not used as tank	Hose <sup>(2)</sup>	
Shell doors	Hose	
Chain locker, if aft of collision bulkhead	Structural	Head of water up to the top
Independent tanks	Structural	Head of water up to the top of overflow, but not less than 0,9 m
Ballast ducts	Structural	Ballast pump maximum pressure
Pump-rooms, shell plating in way	Visual examination	<sup>(7)</sup>
Pump-room bulkheads not forming tank boundaries	Leak	See 8.3.4 <sup>(8)</sup>
After peak not used as tank	Leak	See 8.3.4

## General

## Part 3, Chapter 1

Section 8

**Table 1.8.1** Testing requirements (continuation)

## NOTES

1. Leak or hydropneumatic testing may be accepted, provided that at least one tank of each of structural configuration is structurally tested, to be selected in connection with the approval of the design. For chemical tankers, all cargo tank boundaries are to be structurally tested from at least one side, see also 8.3.8.
2. When hose testing cannot be performed without damaging possible outfittings already installed, it may be replaced by a careful visual inspection of all the crossings and welded joints. Where necessary, dye penetrant test or ultrasonic leak test may be required.
3. Testing of the aft peak is to be carried out after the stern tube has been fitted.
4. The highest point of the tank is generally to exclude hatchways. In holds for liquid cargo or ballast with large hatch openings, the highest point of the tank is to be taken to the top of the hatch.
5. If leak or hydropneumatic testing is carried out, arrangements are to be made to ensure that no pressure in excess of 0,30 bar (0,30 kgf/cm<sup>2</sup>) can be applied.
6. A minimum of every second hatch cover is to be tested.
7. To be carefully examined with the vessel afloat.
8. Alternative methods of testing will be considered.
9. See also SOLAS Reg. II-1/18. Where the door has had the full hydrostatic test before installation, the hose test may be replaced by careful visual examination after full operational tests.
10. Pressure/vacuum relief valve head to be taken as 12,0  $p_v$  m above the top of the tanks, where  $p_v$  is the maximum positive pressure/vacuum relief valve setting, in bar (kgf/cm<sup>2</sup>).
11. Prior to performing the test, small access hatches having a smaller coaming height than the main hatch are to be fully closed.
12. For those designs unable to apply the tank test requirements up to the top of the hatch coaming, the applied head is to be as close to the hatch coaming top level as is reasonably practical.

**Table 1.8.2** Required test heads where a trunk is fitted

Depth of midship tank to top of trunk centre where fitted metres	Test heads	
	Above trunk metres	Above deck metres
> 5,0	1,50	2,45
> 4,25 ≤ 5,0	1,20	2,15
> 3,75 ≤ 4,25	0,90	1,85
> 3,0 ≤ 3,75	0,60	1,50
≤ 3,0	0,60	1,20

**8.3.3 Structural testing:**

- (a) Structural testing may be carried out afloat where testing using water is undesirable in dry-dock or on the building berth. The testing afloat is to be carried out by separately filling each tank and cofferdam to the test head. For tankers and ore or oil ships (see 1.2.2), the testing afloat is to be carried out by separately filling each tank and cofferdam to the test head given in Table 1.8.1. With about half the number of tanks full, the bottom and lower side shell in the empty tanks is to be examined and the remainder of the bottom and lower side shell examined when the water is transferred to the remaining tanks.
- (b) The attachment of fittings to oiltight surfaces is to be completed before tanks are structurally tested. Where it is intended to carry out structural tests after the protective coating has been applied, welds are generally to be leak tested prior to the coating application.
- (c) For welds other than manual and automatic erection welds, manual fillet welds on tank boundaries and manual penetration welds, the leak test may be waived provided that careful visual inspection is carried out, to the satisfaction of the Surveyor, before the coating is applied. The cause of any discolouration or disturbance of the coating is to be ascertained, and any deficiencies repaired.

**8.3.4 Leak testing.**

- (a) This is carried out by applying an efficient indicating liquid (e.g. soapy water solution), to the weld or outfitting penetration being tested, while the tank or compartment is subject to an air pressure of at least 0,15 bar (0,15 kgf/cm<sup>2</sup>).
- (b) It is recommended that the air pressure be raised to 0,2 bar (0,2 kgf/cm<sup>2</sup>) and kept at this level for about one hour to reach a stabilized state, with a minimum number of personnel in the vicinity, and then lowered to the test pressure prior to inspection. A U-tube filled with water to a height corresponding to the test pressure is to be fitted for verification and to avoid overpressure. The U-tube is to have a cross-section larger than that of the air supply pipe. In addition, the test pressure is to be verified by means of a pressure gauge, or alternative equivalent system.
- (c) Leak testing is to be carried out, prior to the application of a protective coating, on all fillet welds and erection welds on tank boundaries, and on all outfitting penetrations. Automatic and Flux Core Arc Welding (FCAW) semi-automatic butt welds of the erection joints need not be tested, provided that careful visual inspections show continuous uniform weld profile shape, free from repairs, and the results of selected NDE testing show no significant defects.
- (d) Selected locations of automatic erection welds and pre-erection manual or automatic welds may also be required to be tested before coating, at the discretion of the Surveyor, taking account of the quality control procedures of the shipyard. Where exempt from this requirement, leak testing may be carried out after the protective coating has been applied, provided that the welds have been carefully inspected to the satisfaction of the Surveyor.

**8.3.5 Hose testing.** This is to be carried out at a maximum distance of 1,5 m with a hose pressure not less than 2,0 bar (2,0 kgf/cm<sup>2</sup>). The nozzle diameter is not to be less than 12 mm. The jet is to be targeted directly onto the weld or seal being tested.

8.3.6 **Hydropneumatic testing.** When this is performed, the safety precautions identified in 8.3.4 are to be followed.

8.3.7 Equivalent proposals for testing will be considered.

8.3.8 **Trial trip and operational tests.** The items listed in Table 1.8.3 are to be tested on completion of the installation or at sea trials.

**Table 1.8.3 Trial trip and operational tests**

Item	Requirement
Sliding watertight doors	To be operated under working conditions.
Windlass	An anchoring test is to be carried out in the presence of the Surveyor. The test should demonstrate that the windlass with brakes, etc., functions satisfactorily, and that the power to raise anchor can be developed and satisfies the Rule requirements. For Rule requirements, see Ch 13,7.
Steering gear, main and auxiliary	To be tested under working conditions, to the satisfaction of the Surveyors, to demonstrate that the Rule requirements are met. For Rule requirements, see Pt 5, Ch 19.
Bilge suctions in holds, and hand pumps in peak spaces	To be tested under working conditions to the satisfaction of the Surveyors.



## Section

- 1 **Materials of construction**
- 2 **Fracture control**
- 3 **Corrosion protection**
- 4 **Deck covering**

## Section 1 Materials of construction

### 1.1 General

1.1.1 The Rules relate in general to the construction of steel ships, although consideration will be given to the use of other materials.

1.1.2 The materials used in the construction of the ship are to be manufactured and tested in accordance with the requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials (Part 2)). Materials for which provision is not made therein may be accepted, provided that they comply with an approved specification and such tests as may be considered necessary.

1.1.3 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2.2.3) with the exception of 1.2.5, 2.3 and 3.2 which are to be complied with.

### 1.2 Steel

1.2.1 Steel having a specified minimum yield stress of 235 N/mm<sup>2</sup> (24 kgf/mm<sup>2</sup>) is regarded as mild steel. Steel having a higher specified minimum yield stress is regarded as higher tensile steel.

1.2.2 For the determination of the hull girder section modulus, where higher tensile steel is used, a higher tensile steel factor,  $k_L$ , is given in Table 2.1.1.

**Table 2.1.1 Values of  $k_L$**

Specified minimum yield stress in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	$k_L$
235 (24)	1,0
265 (27)	0,92
315 (32)	0,78
355 (36)	0,72
390 (40)	0,68
<b>NOTES</b> 1. Intermediate values by linear interpolation. 2. For the purpose of calculating hull moment of inertia as specified in Ch 4.5.7.1, $k_L = 1,0$ .	

1.2.3 The local scantling requirements of higher tensile steel plating, longitudinals, stiffeners and girders may be based on a  $k$  factor determined as follows:

$$k = \frac{235}{\sigma_o} \left( k = \frac{24}{\sigma_o} \right)$$

or 0,66, whichever is the greater,  
where

$\sigma_o$  = specified minimum yield stress in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

1.2.4 For the application of the requirements of 1.2.2 and 1.2.3, special consideration will be given to steel where  $\sigma_o \geq 355$  N/mm<sup>2</sup> (36 kgf/mm<sup>2</sup>). Where such steel grades are used in areas which are subject to fatigue loading, the structural details are to be verified using fatigue design assessment methods.

1.2.5 Where steel castings or forgings are used for stern-frames, rudder frames, rudder stocks, propeller shaft brackets and other major structural items, they are to comply with Chapter 4 or Chapter 5 of the Rules for Materials (Part 2), as appropriate.

### 1.3 Aluminium

1.3.1 The use of aluminium alloy is permitted for special purpose craft, and for superstructures, deckhouses, hatch covers, helicopter platforms, or other local components on board ships.

1.3.2 Aluminium is not to be used for the crowns or casings of Category A machinery spaces, see Pt 5, Ch 1.4.8.1.

1.3.3 Except where otherwise stated, equivalent scantlings are to be derived as follows:

Plating thickness;

$$t_a = t_s \sqrt{k_a c}$$

Section modulus of stiffeners;

$$Z_a = Z_s k_a c$$

where

$c$  = 0,95 for high corrosion resistant alloy  
= 1,00 for other alloys

$$k_a = \frac{245}{\sigma_a}$$

$t_a$  = thickness of aluminium plating

$t_s$  = thickness of mild steel plating

$Z_a$  = section modulus of aluminium stiffener

$Z_s$  = section modulus of mild steel stiffener

$\sigma_a$  = 0,2 per cent proof stress or 70 per cent of the ultimate strength of the material, whichever is the lesser.

1.3.4 In general, for welded structure, the maximum value of  $\sigma_a$  to be used in the scantlings derivation is that of the aluminium in the welded condition. However, consideration will be given to using unwelded values depending upon the weld line location, other heat affected zones, in relation to the maximum applied stress on the member (e.g. extruded sections).

Table 2.1.2 Minimum mechanical properties for aluminium alloys

Alloy	Condition	0,2% proof stress, N/mm <sup>2</sup>		Ultimate tensile strength, N/mm <sup>2</sup>	
		Unwelded	Welded (see Note 4)	Unwelded	Welded (see Note 4)
5083	O/H111	125	125	275	275
5083	H112	125	125	275	275
5083	H116/H321	215	125	305	275
5383	O/H111	145	145	290	290
5383	H116/H321	220	145	305	290
5086	O/H111	100	95	240	240
5086	H112	125 (see Note 2)	95	250 (see Note 2)	240
5086	H116/H321	195	95	275	240
5059	O/H111	160	160	330	330
5059	H116/H321	260	160	360	300
5456	O	125	125	285	285
5456	H116	200 (see Note 5)	125	290 (see Note 5)	285
5456	H321	215 (see Note 5)	125	305 (see Note 5)	285
5754	O/H111	80	80	190	190
6005A (see Note 1)	T5/T6 Extruded: Open Profile Extruded: Closed Profile	215	100	260	160
		215	100	250	160
6061 (see Note 1)	T5/T6 Rolled Extruded: Open Profile Extruded: Closed Profile	240	125	290	160
		240	125	260	160
		205	125	245	160
6082	T5/T6 Rolled Extruded: Open Profile Extruded: Closed Profile	240	125	280	190
		260	125	310	190
		240	125	290	190

NOTES
 

- These alloys are not normally acceptable for application in direct contact with sea-water.
- See also Table 8.1.4 in Pt 2, Ch 8.
- The mechanical properties to be used to determine scantlings in other types and grades of aluminium alloy manufactured to National or proprietary standards and specifications are to be individually agreed with LR, see also Pt 2, Ch 8,1.1.5.
- Where detail structural analysis is carried out, 'Unwelded' stress values may be used away from heat affected zones and weld lines, see also 1.3.3.
- For thickness less than 12,5 mm the minimum unwelded 0,2% proof stress is to be taken as 230 N/mm<sup>2</sup> and the minimum tensile strength is to be taken as 315 N/mm<sup>2</sup>.

1.3.5 A comparison of the mechanical properties for selected welded and unwelded alloys is given in Table 2.1.2.

1.3.6 Where strain hardened grades (designated Hxxx) are used, adequate protection by coating is to be provided to avoid the risk of stress corrosion cracking.

■ Section 2  
Fracture control

2.1 Grades of steel

2.1.1 The resistance to fracture is controlled, in part, by the notch toughness of the steel used in the structure. Steels with different levels of notch toughness are specified in the Rules for Materials (Part 2). The grade of steel to be used is, in general, related to the thickness of the material and the stress pattern associated with its location.



# Materials

## Part 3, Chapter 2

Section 2

2.1.2 In order to distinguish between the material grade requirements for different hull members, material classes are assigned as given in Table 2.2.1. Steel grades are to be not lower than those corresponding to the material classes as given in Table 2.2.2.

2.1.3 Where tee or cruciform connections employ full penetration welds, and the plate material is subject to significant strains in a direction perpendicular to the rolled surfaces, it is recommended that consideration be given to the use of special plate material with specified through thickness properties, as detailed in Ch 3,8 of the Rules for Materials (Part 2).

2.1.4 The material grade of exposed structure of ships intended to operate in temperatures below minus 20°C will be specially considered. The design air temperature is to be taken as the lowest mean daily average air temperature in the area of operation:

where

Mean = statistical mean over a minimum of 20 years (MDHT)

Average = average during one day and one night (MDAT)

Lowest = lowest during the year (MDLT)


Fig. 2.1.1 shows the definition graphically.

**Table 2.2.1 Material classes and grades**

Structural member category	Within 0,4L amidships	Outside 0,4L amidships
<b>SECONDARY:</b> <ul style="list-style-type: none"> <li>Lower strake in longitudinal bulkhead</li> <li>Deck plating exposed to weather, in general</li> <li>Side plating</li> </ul>	I	A/AH
<b>PRIMARY:</b> <ul style="list-style-type: none"> <li>Bottom plating, including keel plate</li> <li>Strength deck plating, excluding those belonging to the special category</li> <li>Continuous longitudinal members above strength deck, excluding longitudinal hatch coamings</li> <li>Upper strake in longitudinal bulkhead</li> <li>Vertical strake (hatch side girder) and upper sloped strake in top wing tank</li> </ul>	II	A/AH
<b>SPECIAL:</b> <ul style="list-style-type: none"> <li>Sheerstrake or rounded gunwale, see Note 1</li> <li>Stringer plate at strength deck, see Note 1</li> <li>Strength deck plating at outboard corners of cargo hatch openings in container carriers and other ships with similar hatch opening configurations, see Note 2</li> <li>Strength deck plating at corners of cargo hatch openings in bulk carriers (see 1.1.3), or carriers, combination carriers and other ships with similar hatch opening configuration, see Note 3</li> <li>Deck strake at longitudinal bulkhead, see Note 4</li> <li>Bilge strake, see Notes 5 and 6</li> <li>Longitudinal hatch coaming of length greater than 0,15L, see Note 7</li> <li>End brackets and deckhouse transition of longitudinal cargo hatch coamings, see Note 7</li> </ul>	III	II, in general  I, outside 0,6L
<b>NOTES</b> <ol style="list-style-type: none"> <li>In ships with length exceeding 250 m, sheerstrake or rounded gunwale and stringer plate at strength deck are not to be less than Grade E/EH within 0,4L amidships.</li> <li>Plating at outboard corners of cargo hatch opening and plating intersections of the longitudinal underdeck girders and the cross-deck strips are not to be less than Class III within the length of the cargo region.</li> <li>Not to be less than Class III within 0,6L amidships and Class II within the remaining length of the cargo region.</li> <li>Excluding deck plating in way of inner-skin bulkhead of double hull ships.</li> <li>In ships with a double bottom over the full breadth and with length less than 150 m, bilge strake may be of Class II within 0,4L amidships.</li> <li>In ships with length exceeding 250 m, bilge strake is not to be less than Grade D/DH within 0,6L amidships.</li> <li>Grade is not to be less than D/DH.</li> <li>Corner inserts in way of any complex openings such as for lifts and side doors which may impinge on the deck plating or stringer plate are to be of Grade D/DH for <math>t \leq 20</math> mm and Grade E/EH for <math>t &gt; 20</math> mm.</li> <li>For strength members not mentioned, Grade A/AH may generally be used.</li> <li>Within 0,4L amidships, single strakes required to be of Class III or of Grade E/EH are to have breadths not less than <math>800 + 5L</math> mm, but need not be greater than 1800 mm.</li> <li>The material class used for reinforcement and the quality of material (i.e. whether mild or higher tensile steel) used for welded attachments, such as waterway bars and bilge keels, is to be similar to that of the hull envelope plating in way. Where attachments are made to rounded gunwale plates, special consideration will be given to the required grade of steel, taking account of the intended structural arrangements and attachment details.</li> <li>The material class for deck plating, sheerstrake and upper strake of longitudinal bulkhead within 0,4L amidships is also to be applied at structural breaks of the superstructure, irrespective of position.</li> <li>Engine seat top plates outside 0,6L amidships may be Grade A/AH. Steel grade requirement for top plates within 0,6L amidships will be specially considered.</li> <li>Steel grade is to correspond to the as-fitted thickness.</li> <li>Plating materials for sternframes, rudders, rudder horns and shaft brackets are, in general, not to be of lower Grades than corresponding to Class II. For rudder and rudder body plates subjected to stress concentrations (e.g. in way of lower support of semi-spade rudders or at upper part of spade rudders) Class III is to be applied.</li> </ol>		

Table 2.2.2 Steel grades

Thickness, <i>t</i> , in mm	Material class					
	I		II		III	
	Mild steel	H.T. steel	Mild steel	H.T. steel	Mild steel	H.T. steel
$t \leq 15$	A	AH	A	AH	A	AH
$15 < t \leq 20$	A	AH	A	AH	B	AH
$20 < t \leq 25$	A	AH	B	AH	D	DH
$25 < t \leq 30$	A	AH	D	DH	D	DH
$30 < t \leq 35$	B	AH	D	DH	E	EH
$35 < t \leq 40$	B	AH	D	DH	E	EH
$t > 40$	D	DH	E	EH	E	EH
NOTE See Notes under Table 2.2.1						



2.2.2 Unless a temperature gradient calculation is carried out to assess the design temperature in the items defined in 2.2.1, the temperature to which the steel deck may be subjected is to be assessed as shown in Table 2.2.4.

Table 2.2.4 Assessment of deck temperature

Arrangement	Deck temperature
(1) Deck not covered with insulation in the refrigerated space	Temperature of the refrigerated space
(2) Deck covered with insulation in the refrigerated space and not insulated on the other side	Temperature of the space on the uninsulated side
(3) Deck covered with insulation on both sides	
(a) Temperature difference not greater than 11°C	Mean of the temperatures of the spaces above and below the deck
(b) Temperature difference greater than 11°C but not greater than 33°C	Mean of the temperatures of the spaces above and below the deck less 3°C
(c) Temperature difference greater than 33°C	Deck temperature will be specially assessed
NOTE Where one of the internal spaces concerned is not refrigerated, the temperature of the space is to be taken as 5°C.	

2.2 Refrigerated spaces

2.2.1 Where the minimum design temperature of the steel falls below 0°C in refrigerated spaces, in addition to the requirements of 2.1.2, the grade of steel for the following items is to comply, in general, with the requirements of Table 2.2.3:

- Deck plating.
- Webs of deck girders.
- Longitudinal bulkhead strakes attached to deck.
- Shelf plates and their face bars supporting hatch covers.

Table 2.2.3 Grades of steel for minimum design temperatures below 0°C

Minimum design temperature, in °C	Thickness, in mm	Grades of steel
0 to -10	$t \leq 12,5$ $12,5 < t \leq 25,5$ $t > 25,5$	B/AH D/DH E/EH
-10 to -25	$t \leq 12,5$ $t > 12,5$	D/DH E/EH
-25 to -40	$t \leq 12,5$ $t > 12,5$	E/EH FH/LT-FH, see also Pt 2, Ch 3,6

2.3 Grades of steel for ice-breaking ships designed to operate in low ambient temperatures

2.3.1 These requirements are intended for ships strengthened in accordance with the requirements stated in Ch 9,8 and designed to operate for long periods in low air temperatures.

2.3.2 The grade of steel to be used is related to the anticipated operating temperature,  $T_0$ , degree of ice induced dynamic loading and the thickness of material. In no case should the grade of steel be less than that required by 2.1 or 2.2.

2.3.3 In order to establish the anticipated operating temperature,  $T_0$ , for a given structural member, it is assumed that the minimum design air temperature,  $T$ , for ships designed to operate in Arctic or Antarctic conditions, is not lower than  $-45^{\circ}\text{C}$  and should not be taken as higher than  $-35^{\circ}\text{C}$ . It is the responsibility of the Owner to specify the design air temperature  $T$ . Where reliable environment records for contemplated operational areas exist, the minimum design air temperature can be obtained after the exclusion of all recorded values having a probability of occurrence of less than 3 per cent. If  $T$  is lower than  $-45^{\circ}\text{C}$  then the steel grades to be used will be specially considered.

2.3.4 The operating temperature  $T_0$  relevant for the selection of steel grades is given in Table 2.2.5.

2.3.5 Steel grades for plating forming the outer shell and deck boundaries are obtained from the figures specified in Table 2.2.5. The strakes of shell plating to which the bilge keels or ground bars are attached are to be made of Grade D steel over the forward 0,5L but may be of Grade B steel elsewhere.

2.3.6 In general, longitudinal frames and longitudinal bulkhead strakes attached to deck and shell and outboard strakes of horizontal stringers are to be of the same steel grade as the hull envelope plating to which they are connected, but the grade may be adjusted to take account of difference in thickness.

2.3.7 The outer strake of web plating of web frames is to be constructed of material of the same steel grade as the shell plating to which they are attached, but the grade may be adjusted to take account of difference in thickness.

2.3.8 The steel grade of transverse side frames and the strakes of transverse bulkhead plating directly attached to the shell in Region A, see Table 2.2.5, are to be determined from Fig. 2.2.2 in conjunction with an operating temperature of  $(T + 10)^{\circ}\text{C}$ .

2.3.9 Steel grades for rudder horn, stern frame and stem (including the adjacent strake of shell plating), are given in Table 2.2.6. The steel grades of internal members attached to these items are to be of the same grade (or equivalent) with due account taken of difference in thickness.

**Table 2.2.5 Steel grades and operating temperatures for ships intended to navigate in Arctic and Antarctic conditions**

Region	Position	Operating temp. $T_0^{\circ}\text{C}$	Steel grade Fig. No.
A	Region between a line set at a distance 0,1D or 2 m (whichever is less) below the Ice Light Waterline and a line set the same distance above the Ice Load Waterline:		
	Forward of 0,3L from the F.P. Aft of 0,3L from the F.P.	$T + 10$ $T + 10$	2.2.1 2.2.2
B	Region between the keel and a line set at the lesser of 0,1D or 2 m below the Ice Light Waterline		
	Forward of 0,3L from the F.P. Permanently immersed parts of the welded stern frame	$T + 20$ $T + 20$	2.2.1 2.2.2
C	Exposed portions of side shell, main deck, stem and stern, excluding coamings, protected positions and forecastle sides:		
	Forward of 0,3L from the F.P. Aft of 0,3L from the F.P.	$T$ , see Note $T$ , see Note	2.2.1 2.2.2
D	Main deck protected from open environment, i.e. within accommodation block or forecastle, etc., but excluding a 1 m wide strip adjacent to boundaries which are to be treated as exposed:		
	Permanently heated spaces Permanently unheated spaces	0 -15	2.2.2 2.2.2
E	Deck coamings, hatch covers, crane pedestals	$T + 5$	2.2.2
F	External bulkheads of accommodation block (the lowest strake is not to be less than Grade D), and forecastle sides	$T + 20$ but not greater than $-10^{\circ}\text{C}$	2.2.2
G	Forecastle deck	$T + 10$ , see Note	2.2.2
H	All other permanently immersed structure	—	Normal Rule Requirement
<p><b>NOTE</b> For ships intended to operate only during the summer period and to be laid up in winter the operating temperature <math>T_0</math> may be taken as <math>T + 20</math> but need not be taken lower than <math>-18^{\circ}\text{C}</math>.</p>			





Table 2.2.6 Steel grades for rudder horn, stern frame and stern for ships intended to navigate in Arctic or Antarctic conditions

Item	Condition	Construction	Steel grade <sup>(2)/(3)</sup>	
			$f < 25(1)$	$f \geq 25(1)$
Rudder horn	Fully immersed	Cast steel	Carbon manganese steel Grade 400	Carbon manganese steel Grade 400
		Fabricated	Grade EH	Grade EH
	Periodically immersed or exposed	Cast steel	Carbon manganese steel Grade 460	2 1/4 Ni steel or equivalent
		Fabricated	Grade FH	1 1/2 Ni steel or equivalent
Stern frame	Fully immersed	Cast steel	Normal Rule requirement	Normal Rule requirement
		Fabricated	Table 2.2.5 Region B	Table 2.2.5 Region B
	Periodically immersed or exposed	Cast steel	Carbon manganese steel Grade 400	Carbon manganese steel Grade 460
		Fabricated	Table 2.2.5 Region C	Grade FH
Stern including adjacent strake of shell plating	Fully immersed	Fabricated	Table 2.2.5 Region B	Table 2.2.5 Region B
		Cast steel	Carbon manganese steel Grade 400	Carbon manganese steel Grade 400
	Periodically immersed or exposed	Fabricated	Table 2.2.5 Region C	Table 2.2.5 Region C
		Cast steel	2 1/4 Ni steel	2 1/4 Ni steel

NOTES

- $f = \sqrt{P_o \Delta} \times 10^{-3} (= 0,858 \sqrt{H_o \Delta} \times 10^{-3})$   
 where  $P_o$  ( $H_o$ ) is the maximum propulsion shaft power for which the machinery is classed  
 $\Delta$  is displacement, in tonnes, at Ice Load Waterline or Deepest Ice Operation Waterline when floating in water of relative density of 1,0.
- For cast steel, see Pt 2, Ch 4,7.
- For C-Mn LT60 and Ni plates, see Pt 2, Ch 3,6.

Section 3

**Corrosion protection**

3.1 General

3.1.1 Where bimetallic connections are made, measures are to be incorporated to preclude galvanic corrosion.

# Materials

# Part 3, Chapter 2

Section 3

## 3.2 Prefabrication primers

3.2.1 Where a primer is used to coat steel after surface preparation and prior to fabrication, the composition of the coating is to be such that it will have no significant deleterious effect on subsequent welding work and that it is compatible with the paints or other coatings subsequently applied in association with an approved system of corrosion control.

3.2.2 To determine the influence of the primer coating on the characteristics of welds, tests are to be made as detailed in 3.2.3 and 3.2.5.

3.2.3 Three butt weld assemblies are to be tested using plate material 20 to 25 mm thick. A 'V' preparation is to be used and, prior to welding, the surfaces and edges are to be treated as follows:

- (a) Assembly 1 – Coated in accordance with the manufacturer's instructions.
- (b) Assembly 2 – Coated to a thickness approximately twice the manufacturer's instructions.
- (c) Assembly 3 – Uncoated.

3.2.4 Tests as follows are to be taken from each test assembly:

- (a) Radiographs. These are to have a sensitivity of better than two per cent of the plate thickness under examination, as shown by an image quality indicator.
- (b) Photo-macrographs. These may be of actual size and are to be taken from near each end and from the centre of the weld.
- (c) Face and reverse bend test. The test specimens are to be bent by pressure or hammer blows round a former of diameter equal to three times the plate thickness.
- (d) Impact tests. These are to be carried out at ambient temperature on three Charpy V-notch test specimens prepared in accordance with Ch 2,3 of the Rules for Materials (Part 2). The specimens are to be notched at the centreline of the weld, perpendicular to the plate surface.

3.2.5 The tests are to be carried out in the presence of a Surveyor to Lloyd's Register (hereinafter referred to as 'LR') or by an independent laboratory specializing in such work. A copy of the test report is to be submitted, together with radiographs and macrographs.

3.2.6 In ships intended for the carriage of oil cargoes having a flash point not exceeding 60°C (closed cup test), paint containing aluminium should not, in general, be used in positions where cargo vapours may accumulate, unless it has been shown by appropriate tests that the paint to be used does not increase the incensive sparking hazard.

## 3.3 Internal cathodic protection

3.3.1 When a cathodic protection system is to be fitted in tanks for the carriage of liquid cargo with flash point not exceeding 60°C, a plan showing details of the locations and attachment of anodes is to be submitted. The arrangements will be considered for safety against fire and explosion aspects only. Impressed current cathodic protection systems are not permitted in any tank.

3.3.2 Particular attention is to be given to the locations of anodes in relation to the structural arrangements and openings of the tank.

3.3.3 Anodes are to be of approved design and sufficiently rigid to avoid resonance in the anode support. Steel cores are to be fitted, and these are to be so designed as to retain the anode even when the latter is wasted.

3.3.4 Anodes are to be attached to the structure in such a way that they remain secure both initially and during service. The following methods of attachment would be acceptable:

- (a) Steel core connected to the structure by continuous welding of adequate section.
- (b) Steel core bolted to separate supports, provided that a minimum of two bolts with lock nuts is used at each support. The separate supports are to be connected to the structure by continuous welding of adequate section.
- (c) Approved means of mechanical clamping.

3.3.5 Anodes are to be attached to stiffeners, or may be aligned in way of stiffeners on plane bulkhead plating, but they are not to be attached to the shell. The two ends are not to be attached to separate members which are capable of relative movement.

3.3.6 Where cores or supports are welded to the main structure, they are to be kept clear of the toes of brackets and similar stress raisers. Where they are welded to asymmetrical stiffeners, they are to be connected to the web with the welding kept at least 25 mm away from the edge of the web. In the case of stiffeners or girders with symmetrical face plates, the connection may be made to the web or to the centreline of the face plate but well clear of the free edges. However, it is recommended that anodes are not fitted to face plates of higher tensile steel longitudinals.

## 3.4 Aluminium and magnesium anodes

3.4.1 Aluminium and aluminium alloy anodes are permitted in tanks used for the carriage of oil, but only at locations where the potential energy does not exceed 275 J (28 kgf m). The weight of the anode is to be taken as the weight at the time of fitting, including any inserts and fitting devices.

3.4.2 The height of the anode is, in general, to be measured from the bottom of the tank to the centre of the anode. Where the anode is located on, or closely above, a horizontal surface (such as a bulkhead girder) not less than 1 m wide, provided with an upstanding flange or face plate projecting not less than 75 mm above the horizontal surface, the height of the anode may be measured above that surface.

3.4.3 Aluminium anodes are not to be located under tank hatches or Butterworth openings unless protected by adjacent structure.

3.4.4 Magnesium or magnesium alloy anodes are permitted only in tanks intended solely for water ballast.

## 3.5 External hull protection

3.5.1 Suitable protection of the underwater portion of the hull is to be provided.

3.5.2 Where an impressed current cathodic protection system is fitted, plans showing the proposed layout of anodes and hull penetrations are to be submitted.

3.5.3 The arrangements for glands, where cables pass through the shell, are to include a small cofferdam. Cables to anodes are not to be led through tanks intended for the carriage of low flash point oils. Where cables are led through cofferdams or clean ballast tanks of tankers, they are to be enclosed in a substantial steel tube of about 10 mm thickness, see also Pt 6, Ch 2, 13.9.

3.5.4 Where an **\*IWS** (In-water Survey) notation is to be assigned, see Pt 1, Ch 2, 2.3.11, protection of the underwater portion of the hull is to be provided by means of a suitable high resistant paint applied in accordance with the manufacturer's requirements. Details of the high resistant paint are to be submitted for information.

## 3.6 Corrosion protection coatings for salt-water ballast spaces

3.6.1 At the time of new construction, all salt-water ballast spaces having boundaries formed by the hull envelope shall have an efficient protective coating, epoxy or equivalent, applied in accordance with the manufacturer's recommendations. The durability of the coatings could affect the frequency of survey of the spaces and light coloured coatings would assist in improving the effectiveness of subsequent surveys. It is therefore recommended that these aspects be taken into account by those agreeing the specification for the coatings and their application.

3.6.2 For further information and recommendations regarding the coating of salt-water ballast spaces see the *List of Paints, Resins, Reinforcements and Associated Materials*, published by LR.

4.1.3 Primary deck coverings within accommodation spaces, control stations or service spaces are to be of a type which will not readily ignite or give rise to smoke or toxic or explosive hazards at elevated temperatures in accordance with the requirements of the *International Code for the Application of Fire Test Procedures*.

## ■ Section 4 Deck covering

### 4.1 General

4.1.1 Where plated decks are sheathed with wood or an approved composition, reductions in plate thickness may be allowed.

4.1.2 The steel deck is to be coated with a suitable material in order to prevent corrosive action, and the sheathing or composition is to be effectively secured to the deck.

# Structural Design

# Part 3, Chapter 3

Sections 1 & 2

## Section

- 1 **General**
- 2 **Rule structural concepts**
- 3 **Structural idealization**
- 4 **Bulkhead requirements**
- 5 **Design loading**
- 6 **Minimum bow heights, reserve buoyancy and extent of forecastle**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter illustrates the general principles to be adopted in applying the Rule structural requirements given in Parts 3 and 4. In particular, consideration has been given to the layout of the Rules as regards the different regions of the ship, principles for taper of hull scantlings, definition of span point, derivation of section moduli and basic design loading for deck structures. Principles for subdivision are also covered.

1.1.2 Where additional requirements relating to particular ship types apply, these are, in general, dealt with under the relevant ship type Chapter in Part 4.

1.1.3 The requirements in this chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2,2.3) with the exception of 4.7 which is to be complied with.

## ■ Section 2 Rule structural concepts

### 2.1 Definition of requirements

2.1.1 In Fig. 3.2.1 the breakdown of the ship into regions is shown. Within each region, the applicable Parts and Chapters of the Rules are indicated.

### 2.2 Definition of fore end region

2.2.1 The fore end region structure is considered to include structure forward of the midship  $0,4L$  region.

### 2.3 Definition of aft end region

2.3.1 The aft end region structure is considered to include all structure aft of the midship  $0,4L$  region.

## 2.4 Symbols

2.4.1 The symbols used in this Section are defined as follows:

$F_D, F_B$  = local scantling reduction factor as defined in Ch 4,5.6

$k_L, k$  = higher tensile steel factor, see Ch 2,1.2

$z_D, z_B$  = vertical distance, in metres, from the hull transverse neutral axis to the moulded deck line at side and to the top of keel respectively

$Z_{ht}$  = vertical extent of higher tensile steel.

## 2.5 Taper requirements for hull envelope

2.5.1 The thickness of the shell envelope and strength deck plating, and the modulus and sectional area of strength deck longitudinals are to taper gradually from the midship region to the fore and aft ends. For the requirements, see Table 3.2.1.

2.5.2 Outside the line of openings where higher tensile steel is used amidships and mild steel at the ends, the equivalent mild steel midship thickness for plating, equivalent mild steel midship deck longitudinal area and equivalent mild steel midship total deck area, for taper purposes are to be determined as follows:

(a) Equivalent mild steel value

$$= \frac{\text{H.T. steel value}}{k_L}$$

(b) If the higher tensile steel plating is based on minimum thickness requirements, then:

Equivalent mild steel midship plating thickness determined from Pt 4, Ch 1 and Ch 9.

2.5.3 The transition from higher tensile steel to mild steel is to be as shown in Fig. 3.2.2 for the forward region. The transition in the aft region is to be similar to the forward region.

2.5.4 Where the higher tensile steel longitudinals extend beyond the point of transition from higher tensile to mild steel plating, the modulus of the composite section is not to be taken less than the required mild steel value at the deck plate flange, and  $k$  times the mild steel value at the higher tensile flange.

## 2.6 Vertical extent of higher tensile steel

2.6.1 Higher tensile steel may be used for both deck and bottom structures or deck structure only. Where fitted, it is to be used for the whole of the longitudinal continuous material for the following vertical distances:

(a) from the line of deck at side

$$z_{ht} = \left(1 - \frac{k_L}{F_D}\right) z_D$$

(b) from the top of keel

$$z_{ht} = \left(1 - \frac{k_L}{F_B}\right) z_B$$

In the above formulae  $F_D$  and  $F_B$  are to be taken not less than  $k_L$ .

## Structural Design

## Part 3, Chapter 3

Section 2




Fig. 3.2.1 Rule scantlings – Schematic layout of requirements



## Structural Design

## Part 3, Chapter 3

Section 2


Table 3.2.1 Taper requirements for hull envelope

Item	Location	Requirement
Plating		
(1) Shell envelope plating, see Notes 1 and 2	Fore and aft ends	The thickness, in mm, is to be the greater of the following: (a) $t_t = \left[ (t_c - t_{e1}) \left( 1 - \frac{d}{0,225L} \right) + t_{e1} \right]$ (see Note 3) (b) $t_t = (6,5 + 0,033L) \sqrt{\frac{k s_1}{s_b}}$
(2) Strength deck plating, see Notes 1 and 2	Fore and aft ends	The thickness, in mm, is to be the greater of the following: (a) $t_t = \left[ (t_c - t_{e2}) \left( 1 - \frac{d}{0,225L} \right) + t_{e2} \right]$ (see Note 3) (b) $t_t = (5,5 + 0,02L) \sqrt{\frac{k s_1}{s_b}}$
Longitudinals outside 0,4L amidships		
(3) Strength deck, see Notes 1 and 2	Fore and aft ends	<b>MODULUS</b> The section modulus in association with deck plating, in cm <sup>3</sup> , is to be the greater of the following: (a) $Z_t = \left[ (Z_c - Z_e) \left( 1 - \frac{d}{0,225L} \right) + Z_e \right]$ (see Note 3) (b) As determined by Table 5.2.3 in Chapter 5, Table 6.2.3 in Chapter 6, and Pt 4, Ch 9, as appropriate
		<b>SECTIONAL AREA</b> The deck longitudinals may be gradually tapered outside the 0,4L midships region in association with the deck plating on the basis of area. The sectional area of one longitudinal without plating, in cm <sup>2</sup> , is to be not less than the following: $A_t = \left[ (A_c - A_e) \left( 1 - \frac{d}{0,225L} \right) + A_e \right]$ (see Note 3)
Strength deck area		
(4) Deck area taper, see Notes 1 and 2	Fore and aft ends	The total area of longitudinals and deck plating outside line of openings at midship region should have a linear taper from 0,2L from midships to 0,075L from F.P. or A.P. such that the area at 0,075L and 0,15L from F.P. or A.P. is not less than 30 and 50 per cent respectively of the total midships area, see Note 3.
Symbols		
<i>L, k, s</i> as defined in Ch 5,1.4.1 <i>d</i> = distance, in m, from 0,2L forward or aft of amidships to the mid-length of the building block, strake, or longitudinal under consideration <i>s<sub>b</sub></i> = standard frame spacing, in mm, as given in Tables 5.2.1 and 5.3.1 in Chapter 5, and Tables 6.2.1 and 6.3.1 in Chapter 6, as appropriate <i>s<sub>1</sub></i> = <i>s</i> , but is to be taken not less than <i>s<sub>b</sub></i> <i>t<sub>c</sub></i> = actual thickness of deck or shell plating within the 0,4L midships region <i>t<sub>e1</sub></i> = basic shell end thickness for taper and is (6,5 + 0,033L) $\sqrt{k}$ at 0,075L from the A.P. or F.P. <i>t<sub>e2</sub></i> = basic strength deck end thickness for taper and is (5,5 + 0,02L) $\sqrt{k}$ at 0,075L from the A.P. or F.P. <i>t<sub>t</sub></i> = taper thickness for strength deck and shell plating <i>Z<sub>c</sub></i> = section modulus of deck longitudinal in association with deck plating, in cm <sup>3</sup> , within the 0,4L midships region <i>Z<sub>e</sub></i> = section modulus of deck longitudinal in association with deck plating, in cm <sup>3</sup> , at 0,075L from the ends <i>Z<sub>t</sub></i> = taper section modulus of deck longitudinal in association with deck plating, in cm <sup>3</sup> <i>A<sub>c</sub></i> = cross sectional area of one longitudinal without attached plating, in cm <sup>2</sup> , within the 0,4L midships region <i>A<sub>e</sub></i> = cross sectional area of one longitudinal without attached plating, in cm <sup>2</sup> , at 0,075L from the ends <i>A<sub>t</sub></i> = taper cross-sectional area of one longitudinal without attached plating, in cm <sup>2</sup>		
NOTES		
1. For thickness of strength deck and shell plating in way of cargo tanks of double hull oil tankers, single hull oil tankers or ore carriers, see also Pt 4, Ch 9, Ch 10, or Ch 11 as appropriate. 2. The taper requirement does not apply to container ships or open type ships, see Ch 4,2.3, where the requirements of Pt 4, Ch 8,3.2 are applicable, nor to fast cargo ships where the requirements of Pt 4, Ch 1,3 are applicable. See also Ch 4,5 for hull section modulus requirement away from the midship area. 3. The formulae for the taper values are based on the assumption that the quality of steel is the same at amidships and ends. Where higher tensile steel is used in the midship region and mild steel at the ends, the taper values should be calculated for both qualities of steel in way of the transition from higher tensile to mild steel, and applied as determined by 2.5.2 and 2.5.3.		

# Structural Design

# Part 3, Chapter 3

Sections 2 & 3



## 2.7 Grouped stiffeners

2.7.1 Where stiffeners are arranged in groups of the same scantling, the section modulus requirement of each group is to be based on the greater of the following:

- the mean value of the section modulus required for individual stiffeners within the group;
- 90 per cent of the maximum section modulus required for individual stiffeners within the group.

## Section 3 Structural idealization

### 3.1 General

3.1.1 For derivation of scantlings of stiffeners, beams, girders, etc., the formulae in the Rules are normally based on elastic or plastic theory using simple beam models supported at one or more points and with varying degrees of fixity at the ends, associated with an appropriate concentrated or distributed load.

3.1.2 Apart from local requirement for web thickness or flange thicknesses, the stiffener, beam or girder strength is defined by a section modulus and moment of inertia requirement.

### 3.2 Geometric properties of section

3.2.1 The symbols used in this sub-Section are defined as follows:

$b$  = the actual width, in metres, of the load-bearing plating, i.e. one-half of the sum of spacings between parallel adjacent members or equivalent supports

$f$  =  $0,3 \left( \frac{l}{b} \right)^{2/3}$ , but is not to exceed 1,0. Values of this factor are given in Table 3.3.1

$l$  = the overall length, in metres, of the primary support member, see Fig. 3.3.3

$t_p$  = the thickness, in mm, of the attached plating. Where this varies, the mean thickness over the appropriate span is to be used.

**Table 3.3.1 Load bearing plating factor**

$\frac{l}{b}$	$f$	$\frac{l}{b}$	$f$
0,5	0,19	3,5	0,69
1,0	0,30	4,0	0,76
1,5	0,39	4,5	0,82
2,0	0,48	5,0	0,88
2,5	0,55	5,5	0,94
3,0	0,62	6 and above	1,00

NOTE  
Intermediate values to be obtained by linear interpolation.

3.2.2 The effective geometric properties of rolled or built sections may be calculated directly from the dimensions of the section and associated effective area of attached plating. Where the web of the section is not normal to the attached plating, and the angle exceeds 20°, the properties of the section are to be determined about an axis parallel to the attached plating.

3.2.3 The geometric properties of rolled or built stiffener sections and of swedges are to be calculated in association with effective area of attached load bearing plating of thickness  $t_p$  mm and of width 600 mm or  $40t_p$  mm, whichever is the greater. In no case, however, is the width of plating to be taken as greater than either the spacing of the stiffeners or the width of the flat plating between swedges, whichever is appropriate. The thickness,  $t_p$ , is the actual thickness of the attached plating. Where this varies, the mean thickness over the appropriate span is to be used.

3.2.4 The effective section modulus of a corrugation over a spacing  $p$  is to be calculated from the dimensions and, for symmetrical corrugations, may be taken as:

$$Z = \frac{d_w}{6000} (3bt_p + ct_w) \text{ cm}^3$$

where  $d_w$ ,  $b$ ,  $t_p$ ,  $c$  and  $t_w$  are measured, in mm, and are as shown in Fig. 3.3.1. The value of  $b$  is to be taken not greater than:

$$50t_p \sqrt{k} \text{ for welded corrugations}$$

$$60t_p \sqrt{k} \text{ for cold formed corrugations}$$


The value of  $\theta$  is to be not less than 40°. The moment of inertia is to be calculated from:

$$I = \frac{Z}{10} \left( \frac{d_w}{2} \right) \text{ cm}^4$$


3.2.5 The section modulus of a double plate bulkhead over a spacing  $b$  may be calculated as:

$$Z = \frac{d_w}{6000} (6fb t_p + d_w t_w) \text{ cm}^3$$

where  $d_w$ ,  $b$ ,  $t_p$  and  $t_w$  are measured, in mm, and are as shown in Fig. 3.3.2.



**Fig. 3.3.1 Corrugation dimensions**



**Fig. 3.3.2 Double plate bulkhead dimensions**

3.2.6 The effective section modulus of a built section may be taken as:

$$Z = \frac{ad_w}{10} + \frac{t_w d_w^2}{6000} \left( 1 + \frac{200(A-a)}{200A + t_w d_w} \right) \text{ cm}^3$$

where

- $a$  = the area of the face plate of the member, in  $\text{cm}^2$
- $d_w$  = the depth, in mm, of the web between the inside of the face plate and the attached plating. Where the member is at right angles to a line of corrugations, the minimum depth is to be taken
- $t_w$  = the thickness of the web of the section, in mm
- $A$  = the area, in  $\text{cm}^2$ , of the attached plating, see 3.2.7. If the calculated value of  $A$  is less than the face area  $a$ , then  $A$  is to be taken as equal to  $a$ .

3.2.7 The geometric properties of primary support members (i.e. girders, transverses, webs, stringers, etc.) are to be calculated in association with an effective area of attached load bearing plating,  $A$ , determined as follows:

- (a) For a member attached to plane plating:  
 $A = 10fb t_p \text{ cm}^2$
- (b) For a member attached to corrugated plating and parallel to the corrugations:  
 $A = 10b t_p \text{ cm}^2$   
See Fig. 3.3.1
- (c) For a member attached to corrugated plating and at right angles to the corrugations:  
 $A$  is to be taken as equivalent to the area of the face plate of the member.

## 3.3 Determination of span point

3.3.1 The effective length,  $l_e$ , of a stiffening member is generally less than the overall length,  $l$ , by an amount which depends on the design of the end connections. The span points, between which the value of  $l_e$  is measured, are to be determined as follows:

- (a) For rolled or built secondary stiffening members:  
The span point is to be taken at the point where the depth of the end bracket, measured from the face of the secondary stiffening member is equal to the depth of the member. Where there is no end bracket, the span point is to be measured between primary member webs. For double skin construction, the span may be reduced by the depth of primary member web stiffener, see Fig. 3.3.3.
- (b) For primary support members:  
The span point is to be taken at a point distant from the end of the member,

$$\text{where } b_e = b_b \left( 1 - \frac{d_w}{d_b} \right)$$

See also Fig. 3.3.3.

3.3.2 Where the end connections of longitudinals are designed with brackets to achieve compliance with the ShipRight FDA Procedure, no reduction in span is permitted for such brackets unless the fatigue life is subsequently reassessed and shown to be adequate for the resulting reduced scantlings.

3.3.3 Where the stiffener member is inclined to a vertical or horizontal axis and the inclination exceeds  $10^\circ$ , the span is to be measured along the member.

3.3.4 It is assumed that the ends of stiffening members are substantially fixed against rotation and displacement. If the arrangement of supporting structure is such that this condition is not achieved, consideration will be given to the effective span to be used for the stiffener.

## 3.4 Calculation of hull section modulus

3.4.1 All continuous longitudinal structural material is to be included in the calculation of the inertia of the hull midship section, and the lever  $z$  is, except where otherwise specified for particular ship types, to be measured vertically from the neutral axis to the top of keel and to the moulded strength deck line at the side. The strength deck is to be taken as follows:

- (a) Where there is a complete upper deck and no effective superstructure, the strength deck is the upper deck.
- (b) Where the upper deck is stepped, as in the case of raised quarter deck ships, or there is an effective superstructure on the upper deck, the strength deck is stepped as shown in Fig. 3.3.4.

3.4.2 An effective superstructure is one which exceeds  $0,15L$  in length and extends inside the midship  $0,5L$  region. Superstructure decks less than 12 m in length are not to be considered as strength deck.





Fig. 3.3.3 Span points

3.4.3 Openings having a length in the fore and aft direction exceeding 2,5 m or  $0,1B$  m or a breadth exceeding 1,2 m or  $0,04B$  m, whichever is the lesser, are always to be deducted from the sectional areas used in the section modulus calculation.

3.4.4 Smaller openings (including manholes, lightening holes, single scallops in way of seams, etc.) need not be deducted provided they are isolated and the sum of their breadths or shadow area breadths (see 3.4.7), in one transverse section does not reduce the section modulus at deck or bottom by more than 3 per cent.


3.4.5 Where  $B_1$  equals the breadth of the ship at the section considered and  $\Sigma b_1$  equals the sum of breadths of deductible openings, the expression  $0,06 (B_1 - \Sigma b)$  may be used for deck openings in lieu of the 3 per cent limitation of reduction of section modulus in 3.4.4.

3.4.6 Where a large number of openings are proposed in any transverse space, special consideration will be required.



**Fig. 3.3.4 Strength deck stepping**

3.4.7 When calculating deduction-free openings, the openings are assumed to have longitudinal extensions as shown by the shaded areas in Fig. 3.3.5. The shadow area is obtained by drawing two tangent lines to an opening angle of 30°. The section to be considered should be perpendicular to the centreline of the ship and should result in the maximum deduction in each transverse space.



**Fig. 3.3.5 Deduction free openings shadow areas**

3.4.8 Isolated openings in longitudinals or longitudinal girders need not be deducted if their depth does not exceed 25 per cent of the web depth with a maximum depth for scallops of 75 mm.

3.4.9 Openings are considered isolated if they are spaced not less than 1 m apart.

3.4.10 For compensation that may be required for openings, see individual ship Chapters.

3.4.11 Where trunk decks or continuous hatch coamings are effectively supported by longitudinal bulkheads or deep girders, they are to be included in the longitudinal sectional area when calculating the hull section modulus. The lever  $z_t$  is to be taken as:

$$z_t = z_c \left( 0,9 + 0,2 \frac{y}{B} \right) \text{ m but not less than } z$$

$y$  = horizontal distance from top of continuous strength member to the centreline of the ship, in metres

$z$  = vertical distance from the neutral axis to the moulded deck line at side, in metres

$z_c$  = vertical distance from the neutral axis to the top of the continuous strength member, in metres

$z_c$  and  $y$  are to be measured to the point giving the largest value of  $z_t$ .

3.4.12 Where continuous hatch coamings are effectively supported (except inboard coamings of multi-hatch arrangements, see 3.4.14), 100 per cent of their sectional area may be included in the calculation of the hull section modulus.

3.4.13 Where a continuous longitudinal underdeck girder, or girders, are arranged to support the inboard hatch coamings, 50 per cent of their sectional area may be included. If the girder is fitted in conjunction with a longitudinal centreline bulkhead, 100 per cent of the sectional area may be included. In cases where the girders are enclosed box sections, or where the girders are effectively tied to the bottom structure, the area to be included will be specially considered.

3.4.14 The percentage of the sectional area to be included for inboard continuous hatch side coamings should be the same percentage as that of the longitudinal girder under.

3.4.15 Where continuous deck longitudinals or deck girders are arranged above the strength deck, the sectional area may be included in the calculation of the hull section modulus. The lever is to be taken to a position corresponding to the depth of the longitudinal member above the moulded deckline at side amidships.

## Section 4 Bulkhead requirements

### 4.1 Number and disposition of bulkheads

4.1.1 All ships are to have a collision bulkhead, an after peak bulkhead, generally enclosing the sterntubes in a watertight compartment, and a watertight bulkhead at each end of the machinery space. Additional watertight bulkheads are to be fitted so that the total number of bulkheads is at least in accordance with Table 3.4.1.

# Structural Design

# Part 3, Chapter 3

Section 4

**Table 3.4.1 Total number of bulkheads**

Length, $L$ , in metres	Total number of bulkheads	
	Machinery amidships	Machinery aft, see Note
$\leq 65$	4	3
$> 65 \leq 85$	4	4
$> 85 \leq 90$	5	5
$> 90 \leq 105$	5	5
$> 105 \leq 115$	6	5
$> 115 \leq 125$	6	6
$> 125 \leq 145$	7	6
$> 145 \leq 165$	8	7
$> 165 \leq 190$	9	8
$> 190$	To be considered individually	

NOTE  
With after peak bulkhead forming after boundary of machinery space.

4.1.2 The bulkheads in the holds should be spaced at reasonably uniform intervals. Where non-uniform spacing is unavoidable and the length of a hold is unusually great, the transverse strength of the ship is to be maintained by fitting web frames, increased framing, etc., and details are to be submitted.

4.1.3 Proposals to dispense with one or more of these bulkheads will be considered, subject to suitable structural compensation, if they interfere with the requirements of a special trade.

4.1.4 Where applicable, the number and disposition of bulkheads are to be arranged to suit the requirements for subdivision, floodability and damage stability, and are to be in accordance with the requirements of the National Authority in the country in which the ship is registered.

## 4.2 Collision bulkhead

4.2.1 The collision bulkhead in all ships other than passenger ships is to be positioned as detailed in Table 3.4.2. Consideration will, however, be given to proposals for the collision bulkhead to be positioned slightly further aft on arrangement (b) ships, but not more than  $0,08L_L$  from the fore end of  $L_L$ , provided that the application is accompanied by calculations showing that flooding of the space forward of the collision bulkhead will not result in any part of the freeboard deck becoming submerged, nor any unacceptable loss of stability.

4.2.2 The collision bulkhead in passenger ships is to be in accordance with the following:

- (a) A ship shall have a forepeak or collision bulkhead, which shall be watertight up to the bulkhead deck. (The bulkhead deck is the uppermost deck up to which the transverse watertight bulkheads are carried, see 4.1.4). This bulkhead is to be positioned as detailed in Table 3.4.3.

**Table 3.4.2 Collision bulkhead position (other than passenger ships)**

Arrangement	Length $L_L$ , in metres	Distance of collision bulkhead aft of fore end of $L_L$ , in metres	
		Minimum	Maximum
(a)	$\leq 200$	$0,05L_L$	$0,08L_L$
	$> 200$	10	$0,08L_L$
(b)	$\leq 200$	$0,05L_L - f_1$	$0,08L_L - f_1$
	$> 200$	$10 - f_2$	$0,08L_L - f_2$
Symbols and definitions			
$f_1 = \frac{G}{2}$ or $0,015L_L$ , whichever is the lesser			
$f_2 = \frac{G}{2}$ or 3 m, whichever is the lesser			
$G$ = projection of bulbous bow forward of fore end of $L_L$ , in metres			
$L_L$ is as defined in Ch 1,6.1			
Arrangement (a) A ship that has no part of its underwater body extending forward of the fore end of $L_L$			
Arrangement (b) A ship with part of its underwater body extending forward of the fore end of $L_L$ (e.g. bulbous bow)			

- (b) If a ship has a long forward superstructure, the forepeak or collision bulkhead shall be extended weathertight to the deck next above the bulkhead deck. The extension need not be fitted directly over the bulkhead below, provided it is located within the limits specified in Table 3.4.3 with the exemption permitted by 4.5.3 and the part of the bulkhead deck which forms the step is made effectively weathertight.

**Table 3.4.3 Collision bulkhead position for passenger ships**

Arrangement	Distance of collision bulkhead aft of fore perpendicular, in metres	
	Minimum	Maximum
(a)	$0,05L_{pp}$	$3 + 0,05L_{pp}$
(b)	$0,05L_{pp} - f$	$3 + 0,05L_{pp} - f$
Symbols and definitions		
$f = \frac{G}{2}$ or $0,015L_{pp}$ or 3 m, whichever is the lesser		
$G$ = projection of bulbous bow forward of fore perpendicular, in metres		
$L_{pp}$ is to be taken as the length measured between the extremities of the deepest subdivision waterline		
Arrangement (a) A ship that has no part of its underwater body extending forward of the fore perpendicular		
Arrangement (b) A ship with part of its underwater body extending forward of the fore perpendicular, (e.g. bulbous bow)		

# Structural Design

# Part 3, Chapter 3

Section 4

## 4.3 After peak bulkhead

4.3.1 All ships are to have an after peak bulkhead generally enclosing the sterntube and rudder trunk in a watertight compartment. In twin screw ships where the bossing ends forward of the after peak bulkhead, the sterntubes are to be enclosed in suitable watertight spaces inside or aft of the shaft tunnels. In passenger ships, the sterntubes are to be enclosed in watertight spaces of moderate volume. The stern gland is to be situated in a watertight shaft tunnel or other watertight space separate from the stern tube compartment and of such volume that, if flooded by leakage through the stern gland, the margin line will not be submerged. (The margin line is a line drawn at least 76 mm below the upper surface of the bulkhead deck at side).

## 4.4 Height of bulkheads

4.4.1 The collision bulkhead is normally to extend to the uppermost continuous deck or, in the case of ships with combined bridge and forecastle or a long superstructure which includes a forecastle, to the superstructure deck. However, if a ship is fitted with more than one complete superstructure deck, the collision bulkhead may be terminated at the deck next above the freeboard deck. Where the collision bulkhead extends above the freeboard deck, the extension need only be to weathertight standards.

4.4.2 The after peak bulkhead may terminate at the first deck above the load waterline, provided that this deck is made watertight to the stern or to a watertight transom floor. In passenger ships, the after peak bulkhead is to extend watertight to the bulkhead deck. However, it may be stepped below the bulkhead deck provided the degree of safety of the ship as regards watertight subdivision is not thereby diminished.

4.4.3 The remaining watertight bulkheads are to extend to the freeboard deck. In passenger ships of restricted draught and all ships of unusual design, the height of the bulkheads will be specially considered.

## 4.5 Watertight recesses, flats and loading ramps

4.5.1 Watertight recesses in bulkheads are generally to be so framed and stiffened as to provide strength and stiffness equivalent to the requirements for watertight bulkheads.

4.5.2 In collision bulkheads, any recesses or steps in the bulkhead are to fall within the limits of bulkhead positions given in 4.2.1. Where the bulkhead is extended above the freeboard deck or bulkhead deck in passenger ships, the extension need only be to weathertight standards. If a step occurs at that deck, the deck need also only be to weathertight standards in way of the step, unless the step forms the crown of a tank, see Pt 4, Ch 1,4.

4.5.3 In ships fitted with bow doors, in which a sloping loading ramp forms part of the collision bulkhead above the freeboard or bulkhead deck, that part of the ramp which is more than 2,30 m above the freeboard or bulkhead deck may extend forward of the minimum limit specified in Table 3.4.2 or Table 3.4.3 as appropriate. Such a ramp is to comply with Pt 4, Ch 2,8.2.5.

## 4.6 Longitudinal subdivision

4.6.1 When timber load lines are to be assigned, double bottom tanks within the midship half-length are to have adequate longitudinal subdivision.

## 4.7 Protection of tanks carrying oil fuel, lubricating oil, vegetable or similar oils

4.7.1 Tanks carrying oil fuel or lubricating oil are to be separated by cofferdams from those carrying feed water, fresh water, edible oil or similar oils. Similarly, tanks carrying vegetable or similar oils are to be separated from those carrying fresh or feed water.

4.7.2 Lubricating oil compartments are also to be separated by cofferdams from those carrying oil fuel. However these cofferdams need not be fitted provided that:

- (a) Common boundaries of lubricating oil and oil fuel tanks have full penetration welds.

- (b) The tanks are arranged such that the oil fuel tanks are not generally subjected to a head of oil in excess of that in the adjacent lubricating oil tanks.

4.7.3 Cofferdams are not required between oil fuel double bottom tanks and deep tanks above, provided that the inner bottom plating is not subjected to a head of oil fuel.

4.7.4 Where fitted, cofferdams are to be suitably ventilated.

4.7.5 If oil fuel tanks are necessarily located within or adjacent to the machinery spaces, their arrangement is to be such as to avoid direct exposure of the bottom from rising heat resulting from an engine room fire, see SOLAS 1974 as amended Reg. II-2/B4.2.2.3.2.

4.7.6 In passenger ships, water ballast is, in general, not to be carried in tanks intended for oil fuel. Attention is drawn to the Statutory Regulations issued by National Authorities in connection with the *International Convention for the Prevention of Pollution of the Sea by Oil*, 1973/78.

## 4.8 Watertight tunnels and passageways

4.8.1 Where a machinery space is situated with a compartment or compartments between it and the after peak bulkhead, the shafting is to be enclosed in a watertight tunnel large enough to permit proper examination and repair of shafting. A sliding watertight door, capable of being operated locally from both sides, is to be provided at the forward end of the tunnel. Consideration may, however, be given to the omission of the watertight door, subject to satisfactory compliance with any relevant statutory requirements.

# Structural Design

# Part 3, Chapter 3

Sections 4 & 5

4.8.2 Pipe tunnels are to have dimensions adequate for reasonable access.

4.8.3 Where fore and aft underdeck passageways are arranged at the ship's side, the after access thereto is to be by a watertight trunk led to the upper deck. Alternative arrangements to prevent the engine room being flooded, in the event of a collision or if the passageway doors are left open, will be considered.

## 4.9 Means of escape

4.9.1 For the requirements for means of escape, see SOLAS 1974 as amended Reg. II-2/D, 13.

## 4.10 Oil tankers

4.10.1 For subdivision requirements within the cargo tank region for oil tankers, see Pt 4, Ch 9, 1.

## Section 5 Design loading

### 5.1 General

5.1.1 This Section contains the design heads/pressures to be used in the derivation of scantlings for decks, tank tops and transverse bulkheads. These are given in Table 3.5.1.

### 5.2 Symbols

5.2.1 The symbols used in this Section are defined as follows:

$L, L_{pp}, C_b, B, D$  and  $T$  as defined in Ch 1, 6.1

$h_i$  = appropriate design head, in metres

$l_e$  = span of stiffener

$p$  = design loading, in kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>)

$p_a$  = applied loading, in kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>)

$C$  = stowage rate, in m<sup>3</sup>/tonne

$$= \frac{h_i}{p} \text{ generally}$$

= volume of the hold, in m<sup>3</sup> excluding the volume contained within the depth of the cargo hatchway, divided by the weight of cargo, in tonnes, stowed in the hold, for inner bottom

$E$  = correction factor for height of platform

$$\frac{0,0914 + 0,003L}{D - T} - 0,15, \text{ but not less than zero}$$

nor more than 0,147

$H$  = height from tank top to deck at side, in metres

$H_c$  = 'tween deck height measured vertically on the centreline of the ship from 'tween deck to underside of hatch cover stiffeners on deck above, in metres

$H_{td}$  = cargo head in 'tween deck, in metres, as defined in Fig. 3.5.1.

5.2.2 The following symbols and definitions apply in particular to the design pressures for partially filled tanks:

$L_{pp}$  and  $C_b$  as defined in Ch 1, 6.1

$b$  = height of internal primary bottom members, in metres

$F$  = fill height, in metres

$F_r$  = effective filling ratio

$$= \frac{\pi}{L_s} \left( F - b \sqrt{\frac{n}{n+1}} \right)$$

$GM$  = transverse metacentric height, in metres, including free surface correction, for the loading condition under consideration

$H_t$  = tank depth, in metres, measured from the bottom of the tank to the underside of the deck at side. In the case of holds, the depth is measured from the inner bottom to the underside of the deck at hatch side, except in double skin ships with hatch coaming in line with the inner skin, in which case, the depth is measured to the top of the hatch coaming

$n$  = number of internal primary bottom members

$L_s$  = the effective horizontal free surface length, in metres, in the direction of angular motion (i.e. tank breadth for roll, tank length for pitch)

$S_{nr}$  = ship's natural rolling period

$$= \frac{2,35r}{\sqrt{GM}} \text{ seconds}$$

for ships for which either  $r$  or  $GM$  varies significantly between loading conditions (for example, bulk carriers and tankers, see 1.1.3),  $S_{nr}$  should be evaluated for each representative loading condition considered

$r$  = radius of gyration of roll, in metres, and may be taken as 0,34 $B$

$S_{np}$  = ship's natural pitching period

$$= 3,5 \sqrt{TC_b} \text{ seconds}$$

for ships for which either  $T$  or  $C_b$  varies significantly between loading conditions (for example, bulk carriers and tankers, see 1.1.3),  $S_{np}$  should be evaluated for each representative loading condition considered

$T_{np}$  = fluid natural period of pitch

$$= \sqrt{\frac{4\pi L_s}{g \cdot \tanh(F_r)}} \text{ seconds}$$

$T_{nr}$  = fluid natural period of roll

$$= \sqrt{\frac{4\pi L_s}{g \cdot \tanh(F_r)}} \text{ seconds}$$

$\theta_{max}$  = maximum 'lifetime' pitch angle, in degrees:  
(32,7 - 8,2 $C_b$ )  $e^{-0,001L_{pp}(4,9 + 0,5C_b)}$

$\phi_{max}$  = maximum 'lifetime' roll angle, in degrees:

$$\left( 14,8 + 3,7 \frac{L_{pp}}{B} \right) e^{-0,0023L_{pp}}$$



## Structural Design

## Part 3, Chapter 3

Section 5

Table 3.5.1 Design heads and permissible cargo loadings (SI units) (see continuation)

Structural item and position	Component	Standard stowage rate $C$ , in $\text{m}^3/\text{tonne}$	Design loading $p$ , in $\text{kN/m}^2$	Equivalent design head $h_1$ in metres	Permissible cargo loading in $\text{kN/m}^2$	Equivalent permissible head, in metres
Weather deck (general cargo)				$h_1$		
(a) Loading for minimum scantlings						
Forward of 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	12,73 29,64 + 14,41E	1,8 4,2 + 2,04E	8,5	1,2
Between 0,12L and 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	10,61 22,59 + 14,41E	1,5 3,2 + 2,04E	8,5	1,2
Aft of 0,12L from F.P.	Beams and longitudinals Primary structure	1,39	8,5 + 14,41E	1,2 + 2,04E	8,5	1,2
(b) Specified cargo loading						
Forward of 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	2,47 $p_a$ + 14,41E or as (a), whichever is larger (Note 1) 3,5 $p_a$ + 14,41E or as (a), whichever is larger (Note 1)	0,35 $p_a$ + 2,04E (Note 1) 0,5 $p_a$ + 2,04E (Note 1)	$p_a$	0,14 $p_a$
Between 0,12L and 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	1,98 $p_a$ + 14,41E or as (a), whichever is larger (Note 1) 2,67 $p_a$ + 14,41E or as (a), whichever is larger (Note 1)	0,28 $p_a$ + 2,04E (Note 1) 0,38 $p_a$ + 2,04E (Note 1)	$p_a$	0,14 $p_a$
Aft of 0,12L from F.P.	Beams and longitudinals Primary structure	1,39	$p_a$ + 14,41E (Note 1)	0,14 $p_a$ + 2,04E (Note 1)	$p_a$	0,14 $p_a$
Cargo decks				$h_2$		
General cargo (standard loads)	All structure	1,39	7,07 $H_{td}$	$H_{td}$	7,07 $H_{td}$	$H_{td}$
Special cargo (specified loads)		$C$	$p_a$	$\frac{Cp_a}{9,82}$	$p_a$	$\frac{Cp_a}{9,82}$
Machinery space, workshop and stores		1,39	18,37	2,6	—	—
Ship stores		1,39	14,14	2,0	—	—
Accommodation decks (clear of tanks)	All structure	1,39	8,5	$h_3$ 1,2	—	—

# Structural Design

## Part 3, Chapter 3

Section 5

**Table 3.5.1 Design heads and permissible cargo loadings (SI units) (see continuation)**

Structural item and position	Component	Standard stowage rate C, in m <sup>3</sup> /tonne	Design loading <i>p</i> , in kN/m <sup>2</sup>	Equivalent design head <i>h<sub>i</sub></i> in metres	Permissible cargo loading in kN/m <sup>2</sup>	Equivalent permissible head, in metres
Superstructure decks (Note 3)				<i>h</i> <sub>3</sub>		
1st tier	Beams and longitudinals	—	—	0,9	—	—
2nd tier				0,6		
3rd tier and above				0,45		
Decks forming crown of tunnels and deep tanks	Plating and stiffeners	C	$\frac{9,82h}{C}$ where <i>h</i> = 1/2 height of stand pipe above crown	<i>h</i> <sub>4</sub>  <i>h</i>	—	—
(c) Bulk carrier (see 1.1.3) with topside tanks						
Weather deck outside line of hatch- ways in way of cargo hold region, when topside tanks empty	Beams and longitudinals	1,39	—	—	7,06 <i>h</i>	h = the lesser of (i) 0,22 <i>B</i> (ii) $1,2 + 0,14 \frac{W_b}{A}$ where <i>W<sub>b</sub></i> = weight of water ballast in the topside tank per frame space, in kN  <i>A</i> = Corresponding area, (m <sup>2</sup> ), of deck in way over one hold frame space
	Primary structure	1,39	—	—		
Weather deck hatch covers (non-liquid cargo)	see also Pt 3, Ch 11, for weather loading			<i>h<sub>H</sub></i>		
Steel covers – Position 1 (Note 4)	Webs, stiffeners and plating	1,39	$\left(7,56 + \frac{L_L}{10,26}\right)$ Min. 10,59 Max. 17,17	$\left(1,07 + \frac{L_L}{72,5}\right)$ Min. 1,5 Max. 2,45	10,59 (Note 2)	1,5 (Note 2)
Steel covers – Position 2 (Note 4)			$\left(5,65 + \frac{L_L}{14,15}\right)$ Min. 8,47 Max. 12,77	$\left(0,8 + \frac{L_L}{100}\right)$ Min. 1,2 Max. 1,8	8,5 (Note 2)	1,2 (Note 2)
Wood covers	As for steel covers					

# Structural Design

## Part 3, Chapter 3

Section 5

**Table 3.5.1** Design heads and permissible cargo loadings (SI units) (conclusion)

Structural item and position	Component	Standard stowage rate $C$ , in $\text{m}^3/\text{tonne}$	Design loading $p$ , in $\text{kN/m}^2$	Equivalent design head $h_1$ in metres	Permissible cargo loading in $\text{kN/m}^2$	Equivalent permissible head, in metres
Cargo hatch covers (standard loading)				$h_H$		
Steel cover	Webs, stiffeners and plating	1,39	$7,07H_{td}$	$H_{td}$	$7,07H_{td}$	$H_{td}$
Wood cover	—	1,39	—	—	$7,07H_{td}$	$H_{td}$
Inner bottom				$H$		
Ship without heavy cargo notation		1,39	—	—	$9,82T$	$1,39T$
Ship with heavy cargo notation	Plating and stiffeners	$C$ but $\leq 0,865$	$\frac{H}{C}$	$H$	$\frac{H}{C}$	$H$
Watertight bulkheads	Plating and stiffeners	0,975	$10,07h_4$	$h_4$ from Fig. 3.5.2	—	—
Deep tank bulkhead	Plating and stiffeners	$C$ but $\leq 0,975$	$\frac{9,82h_4}{C}$	$h_4$ from Fig. 3.5.2	—	—
<b>NOTES</b> 1. In the case of beams and longitudinals, the equivalent design head is to be used in conjunction with the appropriate formulae. 2. Where the scantlings of weather deck covers have been approved for the loading equal to or in excess of the minimum design loading and cargo is to be carried at this loading, the scantlings of the deck supporting structure are also to be suitable for this loading. 3. For forecastle decks forward of 0,12L from F.P., see Weather decks. 4. For definitions of Positions 1 and 2, and specified cargo loading, see Ch 11,1.1.						

# Structural Design

# Part 3, Chapter 3

Section 5

**Table 3.5.1 Design heads and permissible cargo loadings (metric units) (see continuation)**

Structural item and position	Component	Standard stowage rate $C$ , in $\text{m}^3/\text{tonne}$	Design loading $p$ , in $\text{tonne-f/m}^2$	Equivalent design head $h_1$ in metres	Permissible cargo loading in $\text{tonne-f/m}^2$	Equivalent permissible head, in metres
Weather deck (general cargo)				$h_1$		
(a) Loading for minimum scantlings						
Forward of 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	1,296 3,02 + 1,467E	1,8 4,2 + 2,04E	0,865	1,2
Between 0,12L and 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	1,08 2,30 + 1,467E	1,5 3,2 + 2,04E	0,865	1,2
Aft of 0,12L from F.P.	Beams and longitudinals Primary structure	1,39	0,865 + 1,467E	1,2 + 2,04E	0,865	1,2
(b) Specified cargo loading						
Forward of 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	2,50 $p_a$ + 1,467E or as (a), whichever is larger (Note 1) 3,50 $p_a$ + 1,467E or as (a), whichever is larger (Note 1)	3,50 $p_a$ + 2,04E (Note 1) 4,87 $p_a$ + 2,04E (Note 1)	$p_a$	1,39 $p_a$
Between 0,12L and 0,075L from F.P.	Beams and longitudinals Primary structure	1,39	2,00 $p_a$ + 1,467E or as (a), whichever is larger (Note 1) 2,67 $p_a$ + 1,467E or as (a), whichever is larger (Note 1)	2,78 $p_a$ + 2,04E (Note 1) 3,71 $p_a$ + 2,04E (Note 1)	$p_a$	1,39 $p_a$
Aft of 0,12L from F.P.	Beams and longitudinals Primary structure	1,39	$p_a$ + 1,467E (Note 1) $p_a$ + 1,467E (Note 1)	1,39 $p_a$ + 2,04E (Note 1) 1,39 $p_a$ + 2,04E (Note 1)	$p_a$	1,39 $p_a$
Cargo decks				$h_2$		
General cargo (standard loads)	All structure	1,39	$\frac{H_{td}}{1,39}$	$H_{td}$	$\frac{H_{td}}{1,39}$	$H_{td}$
Special cargo (specified loads)		C	$p_a$	$C p_a$	$p_a$	$C p_a$
Machinery space, workshop and stores		1,39	1,87	2,6	—	—
Ship stores		1,39	1,44	2,0	—	—
Accommodation decks (clear of tanks)		1,39	0,865	$h_3$ 1,2	—	—

## Structural Design

## Part 3, Chapter 3

Section 5

Table 3.5.1 Design heads and permissible cargo loadings (metric units) (see continuation)

Structural item and position	Component	Standard stowage rate C, in m <sup>3</sup> /tonne	Design loading ρ, in tonne-f/m <sup>2</sup>	Equivalent design head <i>h<sub>i</sub></i> in metres			Permissible cargo loading in tonne-f/m <sup>2</sup>	Equivalent permissible head, in metres
Superstructure decks (Note 3)				<i>h<sub>3</sub></i>				
1st tier	Beams and longitudinals	—	—	0,9	Where the deck is exposed to the weather, add 2,04 <i>E</i>		—	—
2nd tier				0,6				
3rd tier and above				0,45				
Decks forming crown of tunnels and deep tanks	Plating and stiffeners	C	$\frac{h}{C}$ where <i>h</i> = 1/2 height of stand pipe above crown	<i>h<sub>4</sub></i> <i>h</i>			—	—
(c) Bulk carrier (see 1.1.3) with topside tanks								
Weather deck outside line of hatch- ways in way of cargo hold region, when topside tanks empty	Beams and longitudinals	1,39	—	—			$\frac{h}{1,39}$	<i>h</i> = the lesser of (i) 0,22 <i>B</i> (ii) 1,2 + 0,39 $\frac{W_b}{A}$ where <i>W<sub>b</sub></i> =weight of water ballast in the topside tank per frame space, tonne-f <i>A</i> =Correspond- ing area, (m <sup>2</sup> ), of deck in way over one hold frame space
	Primary structure	1,39	—	—				
Weather deck hatch covers (non-liquid cargo)				<i>h<sub>H</sub></i>				
Steel covers – Position 1 (Note 4)	Webs, stiffeners and plating	1,39	$\left(0,77 + \frac{L_L}{100,8}\right)$ Min. 1,08 Max. 1,75	$\left(1,07 + \frac{L_L}{72,5}\right)$ Min. 1,5 Max. 2,45			1,08 (Note 2)	1,5 (Note 2)
Steel covers – Position 2 (Note 4)			$\left(0,575 + \frac{L_L}{139}\right)$ Min. 0,865 Max. 1,3	$\left(0,8 + \frac{L_L}{100}\right)$ Min. 1,2 Max. 1,8			0,865 (Note 2)	1,2 (Note 2)
Wood covers	As for steel covers							


# Structural Design

## Part 3, Chapter 3

Section 5

**Table 3.5.1** Design heads and permissible cargo loadings (metric units) (conclusion)

Structural item and position	Component	Standard stowage rate $C$ , in $\text{m}^3/\text{tonne}$	Design loading $p_i$ in $\text{tonne-f/m}^2$	Equivalent design head $h_i$ in metres	Permissible cargo loading in $\text{tonne-f/m}^2$	Equivalent permissible head, in metres
Cargo hatch covers (standard loading)				$h_H$		
Steel cover	Webs, stiffeners and plating	1,39	$\frac{H_{td}}{1,39}$	$H_{td}$	$\frac{H_{td}}{1,39}$	$H_{td}$
Wood cover	—	1,39	—	—	$\frac{H_{td}}{1,39}$	$H_{td}$
Inner bottom				$H$		
Ship without heavy cargo notation		1,39	—	—	$T$	1,39 $T$
Ship with heavy cargo notation	Plating and stiffeners	$C$ but $\leq 0,865$	$\frac{H}{C}$	$H$	$\frac{H}{C}$	$H$
Watertight bulkheads	Plating and stiffeners	0,975	$\frac{h_4}{0,975}$	$h_4$ from Fig. 3.5.2	—	—
Deep tank bulkhead	Plating and stiffeners	$C$ but $\leq 0,975$	$\frac{h_4}{C}$	$h_4$ from Fig. 3.5.2	—	—
<b>NOTES</b> 1. In the case of beams and longitudinals, the equivalent design head is to be used in conjunction with the appropriate formulae. 2. Where the scantlings of weather deck covers have been approved for the loading equal to or in excess of the minimum design loading and cargo is to be carried at this loading, the scantlings of the deck supporting structure are also to be suitable for this loading. 3. For forecastle decks forward of 0,12L from F.P., see Weather decks. 4. For definitions of Positions 1 and 2, and specified cargo loading, see Ch 11,1,1.						



**Fig. 3.5.1 Heads for 'tween decks**

## 5.3 Stowage rate and design loads

5.3.1 Unless it is specifically requested otherwise, the following standard stowage rates are to be used:

- 1,39 m<sup>3</sup>/tonne for weather or general cargo loading on deck and inner bottom.
- 0,975 m<sup>3</sup>/tonne for liquid cargo of density 1,025 tonne/m<sup>3</sup> or less on watertight and tank divisions. For liquid of density greater than 1,025 tonne/m<sup>3</sup> the corresponding stowage rates are to be adopted.

5.3.2 Proposals to use a stowage rate greater than 1,39 m<sup>3</sup>/tonne for permanent structure will require special consideration, and will normally be accepted only in the case of special purpose designs such as fruit carriers, etc.

5.3.3 The design head and permissible cargo loading are shown in Table 3.5.1.

## 5.4 Design pressure for partially filled tanks

5.4.1 When partial filling of tanks or holds is contemplated for sea-going conditions, the risk of significant loads due to sloshing induced by any of the ship motions is to be considered. An initial assessment is to be made to determine whether or not a higher level of sloshing investigation is required, using the following procedure which corresponds to the Level 1 Investigation outlined in the *SDA Procedure for Sloshing loads and scantling assessment*, on tanks partially filled with liquids.

5.4.2 In general, significant dynamic magnifications of the sloshing pressures are considered unlikely for the following cases:

- For internally stiffened tanks:
  - where two (or more) deck girders (in the case of rolling) or deck transverses (in the case of pitching) are located not more than 25 per cent of the tank breadth or length respectively from the adjacent tank boundary, and the fill level is greater than the tank depth minus the height of the deck girders or transverses;
  - where the deck girders or transverses, at any location, are less than 10 per cent of the tank depth, and the fill level is greater than the tank depth minus the height of the deck girders or transverses;
  - where the fill level is less than the height of any bottom girders or transverses.
- For smooth tanks: where the fill level is less than 10 per cent or more than 97 per cent of the tank depth.

5.4.3 Significant dynamic magnification of the fluid motions, and hence the sloshing pressure, can occur if either of the following conditions exist:

- The natural rolling period,  $T_{nr}$ , of the fluid and the ship's natural rolling period,  $S_{nr}$ , are within five seconds of each other.
- The natural pitching period,  $T_{np}$ , of the fluid is greater than a value of three seconds below the ship natural pitching period,  $S_{np}$ .

These values define the limits of the critical fill range for each tank.

5.4.4 The critical fill range,  $F_{crit}$ , is to be determined using the following formula:

$$F_{crit} = \left( \frac{100}{H_t} \right) \left[ \left( \frac{L_s}{2\pi} \right) \ln \left( \frac{(1+\eta)}{(1-\eta)} \right) + b \sqrt{\frac{n}{n+1}} \right] \%$$

where

$\ln$  = natural logarithm to base e

$$\eta = \frac{4\pi L_s}{[(S_{nr} - 5)^2 g]} \text{ for fill level at } S_{nr} - 5 \text{ seconds}$$

upper bound roll critical fill level

$$\text{or } \eta = \frac{4\pi L_s}{[(S_{nr} + 5)^2 g]} \text{ for fill level at } S_{nr} + 5 \text{ seconds}$$

lower bound roll critical fill level

$$\text{or } \eta = \frac{4\pi L_s}{[(S_{np} - 3)^2 g]} \text{ for fill level at } S_{np} - 3 \text{ seconds}$$


upper bound pitch critical fill level

$$\text{or } \eta = \frac{4\pi L_s}{[(S_{np})^2 g]} \text{ for fill level at } S_{np} \text{ seconds}$$


The lower bound pitch critical fill level is 0,1 per cent fill.

The value of  $F_{crit}$  is limited to the range 0 to 100 per cent, see also 5.4.6.

5.4.5 The natural periods of the ship for a given motion type are to be determined for the service loading conditions agreed between the Shipbuilder and Lloyd's Register (hereinafter referred to as 'LR'). From this aspect, the storm-ballast and the segregated ballast conditions and the condition with all tanks partially filled could be the most critical.



(a) Heads for watertight and deep tank bulkheads in intact condition



(b) Heads for watertight bulkheads in damaged condition

**Fig. 3.5.2 Heads for watertight and deep tank bulkheads**



# Structural Design

## Part 3, Chapter 3

Sections 5 &amp; 6

5.4.6 When a ship is to be approved for Unrestricted Filling Levels – Unspecified Loading Conditions, many arbitrary ship loading conditions are possible. In order to cover the complete range of loading conditions, the fully loaded and ballast conditions are to be considered. These two conditions give an upper and lower limit for the possible range of natural periods of the ship as shown in Fig. 3.5.3. Both the roll and pitch motion modes are to be examined.

Because of the unrestricted filling level requirement, the critical sloshing ranges extend from  $[S_{nrBallast} - 5]$  to  $[S_{nrLoaded} + 5]$  seconds in roll and from  $[S_{npBallast} - 3]$  to  $[S_{npLoaded}]$  in pitch. Also, because of unrestricted filling levels, the ship natural period range extends from  $[S_{nBallast}]$  to  $[S_{nLoaded}]$  for both pitch and roll.

For sloshing in the roll motion mode shown in Fig. 3.5.3(a), the critical fill range extends from  $F_1$  to  $F_4$ . All fill levels between  $F_1$  and  $F_4$  are to be investigated:


- For fill levels between  $F_1$  and  $F_2$ ,  $S_{nrBallast}$  is to be used.
  - For fill levels between  $F_3$  and  $F_4$ ,  $S_{nrLoaded}$  is to be used.
  - For fill levels between  $F_2$  and  $F_3$ ,  $S_{nr}$  is to be equal to  $T_{nr}$ .
- Similarly, for sloshing in the pitch motion mode shown in Fig. 3.5.3(b), the critical fill range extends from  $F_1$  to  $F_4$ . All fill levels between  $F_1$  and  $F_4$  are to be investigated:
- For fill levels between  $F_1$  and  $F_2$ ,  $S_{npBallast}$  is to be used.
  - For fill levels between  $F_2$  and  $F_3$ ,  $S_{np}$  is to be equal to  $T_{np}$ .
  - For fill levels between  $F_3$  and  $F_4$ ,  $S_{npLoaded}$  is to be used.

5.4.7 When a ship is to be approved for Restricted Filling Levels – Unspecified Loading Conditions, many arbitrary ship loading conditions are possible within the restrictions imposed. In order to cover the complete range of loading conditions, the fully loaded and ballast conditions are to be considered. These two conditions give an upper and lower limit for the possible range of ship natural period. It is recognized that there might be ship natural period bands which will not be applicable as a result of the limitations on the fill levels. However, it is recommended that the Unrestricted Filling Levels – Unspecified Loading Conditions procedure outlined in 5.4.6 be applied.

5.4.8 When a ship is to be approved for Unrestricted Filling Levels – Specified Loading Conditions, each specified loading condition is to be examined for the complete fill ranges to determine the critical sloshing fill range for each tank in both roll and pitch motion modes.

5.4.9 When a ship is to be approved for Restricted Filling Levels – Specified Loading Conditions, each specified loading condition is to be examined for the restricted fill ranges to determine the critical sloshing fill range for each tank in both roll and pitch motion modes.

5.4.10 Where the assessment indicates that all the intended fill levels are outside the critical fill ranges and, therefore, significant sloshing will not occur, no further evaluation is required with regard to sloshing pressure. In such cases, the scantlings of the tank boundaries are to be determined in accordance with the relevant Rule requirements.



**Fig. 3.5.3 Natural periods diagrams**

5.4.11 Where the separation of periods defined in 5.4.3 is not met, other levels of assessment will be required as given in the *SDA Procedure for Sloshing loads and scantling assessment*, on tanks partially filled with liquids.

5.4.12 The structural capability of the tank boundaries to withstand the dynamic sloshing pressures is to be examined. The magnitude of the predicted loads, together with the scantling calculations may be required to be submitted.

## Section 6 Minimum bow heights, reserve buoyancy and extent of forecastle

### 6.1 Minimum bow heights

6.1.1 Ships are to comply with the Load Lines conventions, so far as these are applicable.

6.1.2 Bulk carriers, ore carriers and combination carriers are also to comply with the requirements of Pt 4, Ch 7,14.

## 6.2 Extent of forecastle

6.2.1 Forecastles are to extend from the stem to a point at least  $0,07L_L$  abaft the forward end of  $L_L$  (as defined in Ch 1,6.1). If the minimum bow height is obtained by increasing the sheer of the upper deck, the sheer is to extend for at least  $0,15L_L$  abaft the forward end of  $L_L$ .

6.2.2 Bulk carriers, ore carriers and combination carriers are also to comply with the requirements of Pt 4, Ch 7,14.

6.2.3 Forecastles are to be enclosed; that is with enclosing bulkheads of efficient construction and access openings complying with Pt 3, Ch 11 and all other openings in sides or ends fitted with efficient weathertight means of closing.

# Longitudinal Strength

## Part 3, Chapter 4

Sections 1, 2 & 3

### Section

- 1 **Definitions**
- 2 **General**
- 3 **Application**
- 4 **Information required**
- 5 **Hull bending strength**
- 6 **Hull shear strength**
- 7 **Hull buckling strength**
- 8 **Loading guidance information**

### ■ Section 1 Definitions

#### 1.1 List of symbols

1.1.1 The following symbols and definitions are applicable to this Chapter, unless otherwise stated:

$L$ ,  $B$ ,  $D$ ,  $C_b$  and  $V$  are as defined in Ch 1,6.1  
 $k_L$ ,  $k$  = higher tensile steel factor, see Ch 2,1.2.

### ■ Section 2 General

#### 2.1 Longitudinal strength calculations

2.1.1 Longitudinal strength calculations are to be carried out for all ships where  $L$  is greater than 65 m, covering the range of load and ballast conditions proposed, in order to determine the required hull girder strength. The calculations of still water shear forces and bending moments are to cover both departure and arrival conditions and any special mid-voyage conditions caused by changes in ballast distribution.

2.1.2 For ships where  $L$  is equal to or less than 65 m, longitudinal strength calculations may be required, dependent upon proposed loading.

2.1.3 Specific information regarding required loading conditions is given in the individual ship type Chapters.

#### 2.2 Erections contributing to hull strength

2.2.1 In general, where a long superstructure or deckhouse of length greater than  $0,15L$  is fitted, extending within the  $0,5L$  amidships, the requirements for longitudinal strength in the hull and erection will be considered in each case.

#### 2.3 Open type ships

2.3.1 For ships other than container ships which have large deck openings and where the structural configuration is such that warping stresses in excess of  $14,7 \text{ N/mm}^2$  are likely to occur, local increases in section modulus, based normally on the combined stress diagram undertaken for container ships, may be required. For calculations for container ships, see Pt 4, Ch 8,3.

#### 2.4 Ships with large flare

2.4.1 In ships of length between 120 and 170 m and maximum service speed greater than 17,5 knots, in association with a bow shape factor of more than 0,15, the Rule hull midship section modulus and the distribution of longitudinal material in the forward half-length will be specially considered, see Pt 4, Ch 1,3.

#### 2.5 Direct calculation procedures

2.5.1 In direct calculation procedures capable of deriving the wave induced loads on the ship, and hence the required modulus, account is to be taken of the ship's actual form and weight distribution.

2.5.2 Lloyd's Register's (hereinafter referred to as 'LR') direct calculation method involves derivation of response to regular waves by strip theory, short-term response to irregular waves using the sea spectrum concept, and long-term response predictions using statistical distributions of sea states. Other direct calculation methods submitted for approval should normally contain these three elements and produce similar and consistent results when compared with LR's methods.

#### 2.6 Approved calculation systems

2.6.1 Where the assumptions, method and procedures of a longitudinal strength calculation system have received general approval from LR, calculations using the system for a particular ship may be submitted.

### ■ Section 3 Application

#### 3.1 Symbols

3.1.1 The symbols used in this Section are defined as follows:

$b$  = breadth, in metres, of the hatch opening. Where there are multiple openings abreast, these are regarded as a single opening, and  $b$  is to be the sum of the individual breadths of these openings  
 $l_H$  = length of the hatch opening, in metres


# Longitudinal Strength

## Part 3, Chapter 4

Sections 3 &amp; 4

$l_{BH}$  = distance, in metres, between centres of the deck strip at each end of the hatch opening. Where there is no further opening beyond the one under consideration, the point to which  $l_{BH}$  is measured will be considered, see also Fig. 4.3.1

$B_1$  = extreme breadth of deck including hatch opening, measured at the mid-length of the opening, in metres.



**Fig. 4.3.1 Deck opening size**

### 3.2 General

3.2.1 The requirements of this Chapter apply to sea-going steel ships, of normal form, proportions and speed, unless direct calculation procedures are adopted, in which case the assumptions made and the calculations performed are to be submitted for approval.

3.2.2 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation. See Pt 1, Ch 2,2.3.

### 3.3 Exceptions

3.3.1 Individual consideration based on direct calculation procedures will generally be required for ships having one or more of the following characteristics:

- Length  $L$  greater than 400 m.
- Speed  $V$  greater than that defined in Table 4.3.1 for the associated block coefficient.
- Unusual type or design.

- Unusual hull weight distribution.
- $\frac{L}{B} \leq 5$ , or  $\frac{B}{D} \geq 2,5$
- Large deck openings, or where warping stresses in excess of 14,7 N/mm<sup>2</sup> (1,5 kgf/mm<sup>2</sup>) are likely to occur.
- Openings for side loading in way of both sheerstrake and stringer.
- $C_b < 0,6$
- Carriage of heated cargo, see Pt 4, Ch 9,12.

**Table 4.3.1 Ship speed criteria**

Ship length $L$ , m	$C_b$	Speed, knots
$\leq 200$	$> 0,80$ $= 0,70$ $< 0,60$	17 19,5 22
$> 200$	$> 0,80$ $= 0,70$ $< 0,60$	18 21,5 25
NOTE Intermediate values of speed to be obtained by linear interpolation for $C_b$ .		

3.3.2 A ship is regarded as having large deck openings if both the following conditions apply to any one opening:

$$\frac{b}{B_1} > 0,6$$

$$\frac{l_H}{l_{BH}} > 0,7$$

See also Fig. 4.3.1.

## Section 4 Information required

### 4.1 List of requirements

4.1.1 In order that an assessment of the longitudinal strength requirements can be made, the following information is to be submitted, in LR's standard format where appropriate.

- General arrangement and capacity plan or list, showing details of the volume and position of centre of gravity of all tanks and compartments.
- Bonjean data, in the form of tables or curves, for at least 21 equally spaced stations along the hull. A lines plan and/or tables of offsets may also be required.
- Details of the calculated lightweight and its distribution.
- Loading Manual.
- Details of the weights and centres of gravity of all deadweight items for each of the main loading conditions for individual ship types specified in Part 4. It is recommended that this information be submitted in the form of a preliminary Loading Manual, and that it includes the calculated still water bending moments and shear forces.

# Longitudinal Strength

## Part 3, Chapter 4

Sections 4 &amp; 5

4.1.2 For final Loading Manual, see Section 8.

### Section 5

#### Hull bending strength

##### 5.1 Symbols

5.1.1 The symbols used in this Section are defined as follows:

- $f_1$  = ship service factor
- $f_2$  = wave bending moment factor
- $F_B$  = local scantling reduction factor for hull members below the neutral axis, see 5.6
- $F_D$  = local scantling reduction factor for hull members above the neutral axis, see 5.6
- $I_{min}$  = minimum moment of inertia, of the hull midship section about the transverse neutral axis, in  $m^4$
- $M_s$  = design still water bending moment, sagging (negative) and hogging (positive), in kN m (tonne-f m), to be taken negative or positive according to the convention given in 5.3.2
- $\overline{M}_s$  = maximum permissible still water bending moment, sagging (negative) and hogging (positive), in kN m (tonne-f m), see 5.4
- $M_w$  = design hull vertical wave bending moment amidships, sagging (negative) and hogging (positive), in kN m (tonne-f m), to be taken negative or positive according to the convention given in 5.3.2
- $Z_c$  = actual hull section modulus, in  $m^3$ , at continuous strength member above strength deck, calculated with the lever specified in Ch 3,3.4
- $Z_D, Z_B$  = actual hull section moduli, in  $m^3$ , at strength deck and keel respectively, see Ch 3,3.4
- $Z_{min}$  = minimum hull midship section modulus about the transverse neutral axis, in  $m^3$
- $\sigma$  = permissible combined stress (still water plus wave), in  $N/mm^2$  (kgf/mm<sup>2</sup>), see 5.5
- $\sigma_D, \sigma_B$  = maximum hull vertical bending stress at strength deck and keel respectively, in  $N/mm^2$  (kgf/mm<sup>2</sup>)
- $z$  = vertical distance from the hull transverse neutral axis to the position considered, in metres
- $z_M$  = vertical distance, in metres, from the hull transverse neutral axis to the minimum limit of higher tensile steel, as defined in Ch 3,2.6, above or below the neutral axis as appropriate.

##### 5.2 Design vertical wave bending moments

5.2.1 The appropriate hogging or sagging design hull vertical wave bending moment at amidships is given by the following:

$$M_w = f_1 f_2 M_{wo}$$

where

$C_b$  is to be taken not less than 0,60

$C_1$  is given in Table 4.5.1

$C_2 = 1$ , (also defined in 5.2.2 at other positions along the length  $L$ )

$f_1$  = ship service factor. To be specially considered depending upon the service restriction and in any event should be not less than 0,5. For unrestricted sea-going service  $f_1 = 1,0$

$f_2 = -1,1$  for sagging (negative) moment

$f_2 = \frac{1,9C_b}{(C_b + 0,7)}$  for hogging (positive) moment

$$M_{wo} = 0,1C_1 C_2 L^2 B (C_b + 0,7) \text{ kN m} \\ (0,0102C_1 C_2 L^2 B (C_b + 0,7) \text{ tonne-f m})$$

Consideration will be given to direct calculations of long-term vertical wave bending moments, see 2.6.

**Table 4.5.1 Wave bending moment factor**

Length $L$ , in metres	Factor $C_1$
<90	$0,0412L + 4,0$
90 to 300	$10,75 - \left( \frac{300 - L}{100} \right)^{1,5}$
>300 ≤ 350	10,75
>350 ≤ 500	$10,75 - \left( \frac{L - 350}{150} \right)^{1,5}$

5.2.2 The longitudinal distribution factor,  $C_2$ , of wave bending moment is to be taken as follows:

- 0 at the aft end of  $L$
- 1,0 between 0,4 $L$  and 0,65 $L$  from aft
- 0 at the forward end of  $L$

Intermediate values are to be determined by linear interpolation.

5.2.3 For operation in sheltered water or short voyages, a higher permissible still water bending moment can be assigned based on a reduced vertical wave bending moment given by:

(a) For operating in sheltered water:

$$M_w = 0,5f_2 M_{wo}$$

(b) For short voyages:

$$M_w = 0,8f_2 M_{wo}$$

These expressions can only be used in the expression for permissible still water bending moment, see 5.4, and the relevant loading conditions are to be included in the Loading Manual, see 8.1.

5.2.4 'Short voyages' are defined as voyages of limited duration in reasonable weather. 'Reasonable weather' and 'sheltered water' are defined in Pt 1, Ch 2,2.

##### 5.3 Design still water bending moments

5.3.1 The design still water bending moment,  $M_s$ , hogging and sagging is the maximum moment calculated from the loading conditions, given in 5.3.3, and is to satisfy the following relationship:

$$|M_s| \leq |\overline{M}_s|$$

# Longitudinal Strength

# Part 3, Chapter 4

Section 5

5.3.2 Still water bending moments are to be calculated along the ship length. For these calculations, downward loads are to be taken as positive values and are to be integrated in the forward direction from the aft end of  $L$ . Hogging bending moments are positive.

5.3.3 In general, the following loading conditions, based on amount of bunkers, fresh water and stores at departure and arrival, are to be considered.

- (a) General cargo ships, container ships, passenger ships, roll on-roll off ships and refrigerated cargo carriers:
  - (i) Homogeneous loading conditions, at maximum draught.
  - (ii) Ballast conditions.
  - (iii) Special loading conditions, e.g. container or light load conditions at less than the maximum draught, heavy cargo, empty holds or non-homogeneous cargo conditions, deck cargo conditions, etc., where applicable.
- (b) Bulk carriers (see 3.2.2), ore carriers and combination carriers
  - (i) For ships of length,  $L$ , less than 150 m:
    - Alternate hold loading conditions at maximum draught, where applicable.
    - Homogeneous loading conditions at maximum draught.
    - Ballast conditions, including intermediate conditions associated with ballast exchange at sea.
    - Special conditions, e.g. deck cargo conditions.
  - For combination carriers, the conditions as specified in (c) for oil tankers are also to be considered.
  - (ii) For ships of length,  $L$ , 150 m or above:
    - Alternate light and heavy cargo loading conditions at maximum draught, where applicable.
    - Homogeneous light and heavy cargo loading conditions at maximum draught.
    - Ballast conditions. Where vessels are designed with a ballast hold adjacent to topside wing, hopper and double bottom tanks, the structure design is to be such that the ballast hold can be filled with all adjacent tanks empty.
    - Short voyage conditions where the ship is loaded to maximum draught with reduced bunkers, where applicable.
    - Multiple port loading/unloading conditions, where applicable.
    - Deck cargo conditions, where applicable.
    - Typical loading and discharging sequences from commencement to end of cargo operation, for homogeneous, alternate and part load conditions, where applicable.
    - Typical sequences for exchange of ballast at sea, where applicable.
    - For combination carriers, the conditions as specified in (c) for oil tankers are also to be considered.
    - For bulk carriers, the conditions as specified in 5.4 for the relevant notation are also to be considered.

- (c) Oil tankers (see 3.2.2):
  - (i) Homogeneous loading conditions (excluding dry and clean ballast tanks) and ballast or part loaded conditions.
  - (ii) Any specified non-uniform distribution of loading.
  - (iii) Mid-voyage conditions relating to tank cleaning or other operations where these differ significantly from the ballast conditions.
- (d) Chemical tankers:
  - (i) Conditions as specified for oil tankers.
  - (ii) Conditions for high density or segregated cargo.
- (e) Liquefied gas carriers:
  - (i) Homogeneous loading conditions for all approved cargoes.
  - (ii) Ballast conditions.
  - (iii) Cargo conditions where one or more tanks are empty or partially filled or where more than one type of cargo having significantly different densities is carried.
- (f) All ships:
  - (i) Any other loading condition likely to result in high bending moments and/or shear forces (including docking conditions, as appropriate).

5.3.4 Where the amount and disposition of consumables at any intermediate stage of the voyage are considered more severe, calculations for such intermediate conditions are to be submitted in addition to those for departure and arrival conditions. Also, where any ballasting and/or de-ballasting is intended during voyage, calculations of the intermediate condition just before and just after ballasting and/or de-ballasting any tank are to be submitted and, where approved, included in the loading manual for guidance.

5.3.5 Ballast loading conditions involving partially filled peak and/or other ballast tanks at departure, arrival or during intermediate conditions are not permitted as design conditions unless the design stress limits are satisfied for all filling levels between empty and full, and for bulk carriers the requirements of Pt 4, Ch 7,3, as applicable, are to be complied with for all filling levels between empty and full. To demonstrate compliance with all filling levels between empty and full, it will be acceptable if, in each condition at departure, arrival and where required by 5.3.3, any intermediate condition, the tanks intended to be partially filled are assumed to be:

- empty
- full
- partially filled at intended level.

Where multiple tanks are intended to be partially filled, all combinations of empty, full or partially filled at intended level for those tanks are to be investigated. However, for conventional ore carriers with large wing water ballast tanks in cargo area, where empty or full ballast water filling levels of one or maximum two pairs of these tanks lead to the ship's trim exceeding one of the following conditions, it is sufficient to demonstrate compliance with maximum, minimum and intended partial filling levels of these one or maximum two pairs of ballast tanks such that the ship's condition does not exceed any of these trim limits. Filling levels of all other wing ballast tanks are to be considered between empty and full.

# Longitudinal Strength

# Part 3, Chapter 4

Section 5


The trim conditions mentioned above are:

- trim by stern of 3% of the ship's length, or
- trim by bow of 1,5% of ship's length, or
- any trim that cannot maintain propeller immersion ( $I/D$ ) not less than 25%, where;

$I$  = the distance from propeller centreline to the waterline, see Fig. 4.5.1

$D$  = propeller diameter, see Fig. 4.5.1

The maximum and minimum filling levels of the above mentioned pairs of side ballast tanks are to be indicated in the loading manual.



**Fig 4.5.1 Propeller immersion**

5.3.6 When considering cargo loading conditions, the requirements of 5.3.5 apply to peak tanks only.

5.3.7 When considering ballast water exchange using the sequential method, the requirements of 5.3.5 and 5.3.6 do not apply.

## 5.4 Minimum hull section modulus

5.4.1 The hull midship section modulus about the transverse neutral axis, at the deck or the keel, is to be not less than:

$$Z_{\min} = f_1 k_L C_1 L^2 B (C_b + 0,7) \times 10^{-6} \text{ m}^3$$

and

$f_1$  is to be taken not less than 0,5.

5.4.2 For materials to be included in the calculation of actual hull section properties, see Ch 3,3.

5.4.3 The midship section modulus for ships with a service restriction notation is to be not less than half the minimum value required for unrestricted service.

5.4.4 Scantlings of all continuous longitudinal members of the hull girder based on the minimum section modulus requirements given in 5.4.1 are to be maintained within 0,4L amidships. However, in special cases, based on consideration of type of ship, hull form and loading conditions, the scantlings may be gradually reduced towards the ends of the 0,4L part, bearing in mind the desire not to inhibit the vessel's loading flexibility.

## 5.5 Permissible still water bending moments

5.5.1 The permissible still water bending moments sagging and hogging are to be taken as the lesser of the following:

$$(a) |\bar{M}_s| = F_D \sigma Z_D \times 10^3 - |M_w| \text{ kN m (tonne-f m)}$$

$$(b) |\bar{M}_s| = F_B \sigma Z_B \times 10^3 - |M_w| \text{ kN m (tonne-f m)}$$

where

$\sigma$  = the permissible combined stress in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) is given in 5.6 and  $F_D$  and  $F_B$  are defined in 5.7.2.  $M_w$  is the design wave bending moment, sagging or hogging as appropriate, in accordance with 5.2.

## 5.6 Permissible hull vertical bending stresses

5.6.1 The permissible combined (still water plus wave) stress for hull vertical bending,  $\sigma$ , is given by:

(a) Within 0,4L amidships

$$\sigma = \frac{175}{k_L} \text{ N/mm}^2 \left( \frac{17,84}{k_L} \text{ kgf/mm}^2 \right)$$

(b) for continuous longitudinal structural members outside 0,4L amidships

$$\sigma = \left( 75 + 543 \frac{d}{L} - 699 \left( \frac{d}{L} \right)^2 \right) \frac{1}{k_L} \text{ N/mm}^2$$

$$\left( \sigma = \left( 75 + 543 \frac{d}{L} - 699 \left( \frac{d}{L} \right)^2 \right) \frac{0,102}{k_L} \text{ kgf/mm}^2 \right)$$

where  $d$  is the distance, in metres, from the F.P. (for the fore end region) or from the A.P. (for the aft end region), as appropriate, to the location under consideration.

Special consideration will be given to increasing the permissible stress outside 0,4L amidships to

$$\frac{175}{k_L} \text{ N/mm}^2 \left( \frac{17,84}{k_L} \text{ kgf/mm}^2 \right)$$

provided that sufficient buckling checks are carried out.

5.6.2 The requirements for ships of special or unusual design and for the carriage of special cargoes will be individually considered.

# Longitudinal Strength

# Part 3, Chapter 4

Sections 5 & 6

## 5.7 Local reduction factors

5.7.1 The maximum hull vertical bending stresses at deck,  $\sigma_D$ , and keel,  $\sigma_B$ , are given by the following, using the appropriate combination of bending moments to give sagging and hogging stresses:

$$\sigma_D = \frac{|\overline{M}_s + M_w|}{Z_D} \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$\sigma_B = \frac{|\overline{M}_s + M_w|}{Z_B} \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

Where the ship is always in the hogging condition, the sagging bending moment is to be specially considered.

5.7.2 Where the maximum hull vertical bending stress at deck or keel is less than the permissible combined stress,  $\sigma$ , reductions in local scantlings within 0,4L amidships may be permitted. The reduction factors applicable in Part 4 are defined as follows:

For hull members above the neutral axis

$$F_D = \frac{\sigma_D}{\sigma}$$

For hull members below the neutral axis

$$F_B = \frac{\sigma_B}{\sigma}$$

In general, the values of  $\sigma_D$  and  $\sigma_B$  to be used are the greater of the sagging or hogging stresses, and  $F_D$  and  $F_B$  are not to be taken less than 0,67 for plating and 0,75 for longitudinal stiffeners.

5.7.3 Where higher tensile steel is used in the hull structure, the values of  $F_D$  and  $F_B$  for the mild steel part are to be taken as not less than  $\frac{Z}{Z_M}$ .

## 5.8 Hull moment of inertia

5.8.1 The hull midship section moment of inertia about the transverse neutral axis is to be not less than the following using the maximum total bending moment, sagging or hogging:

$$I_{\min} = \frac{3L (|\overline{M}_s + M_w|)}{k_L \sigma} \times 10^{-5} \text{ m}^4$$

where values of  $\sigma$  are given in 5.6.1.

## 5.9 Continuous strength members above strength deck

5.9.1 Where trunk decks or continuous hatch coamings are effectively supported or deck longitudinals or girders are fitted above the strength deck, the modulus  $Z_C$  is to be not less than  $Z_{\min}$ . The scantling reduction factor,  $F_D$ , referred to strength deck at side, is applicable and, in addition to the requirement given in 5.5.1, the permissible still water bending moments, sagging and hogging, are not to exceed:

$$|\overline{M}_s| = \sigma Z_C \times 10^3 - |M_w| \text{ kN m (tonne-f m)}$$

where

$M_w$  is the design wave bending moment sagging or hogging, as appropriate, in accordance with 5.2.

## Section 6

## Hull shear strength

### 6.1 Symbols

- 6.1.1 The symbols used in this Section are defined as follows:
- $I$  = the inertia of the hull about the horizontal neutral axis at the section concerned, in  $\text{cm}^4$
  - $Az$  = the first moment, in  $\text{cm}^3$ , about the neutral axis, of the area of the effective longitudinal members between the vertical level under consideration, and the vertical extremity of the effective longitudinal members, taken at the section under consideration
  - $Q_s$  = design hull still water shear force, in kN (tonne-f), to be taken as negative or positive according to the convention given in 6.4.2
  - $\overline{Q}_s$  = permissible hull still water shear force, in kN (tonne-f), see 6.5
  - $Q_w$  = design hull wave shear force, in kN (tonne-f), to be taken as negative or positive according to the convention given in 6.4.2
  - $\tau$  = permissible combined shear stress (still water plus wave), in  $\text{N/mm}^2$  (kgf/mm $^2$ ), see 6.6
  - $\tau_A$  = design shear stress, in  $\text{N/mm}^2$  (kgf/mm $^2$ ), as given in 6.7.1 for use in 7.4.

### 6.2 General

6.2.1 For ships with length  $L$  greater than 65 m, the shear forces on the hull structure are to be investigated.

6.2.2 For  $L$  greater than 200 m, where double skin construction of the side shell in association with topside and hopper tanks is proposed, shear flow calculations may be required to be submitted.

6.2.3 Where shear flow calculation procedures other than those available within ShipRight are employed, the requirements of Ch 1,3 are to be complied with.

6.2.4 For passenger ships, the assessment of permissible still water shear forces is to take into consideration the effectiveness of the continuous superstructures and the sizes and arrangements of window and door openings.

6.2.5 Where longitudinal bulkheads are perforated by cut-outs, the assessment of permissible still water shear forces is to take into consideration the loss of material.

### 6.3 Design wave shear force

6.3.1 The design hull wave shear force,  $Q_w$ , at any position along the ship is given by:

$$Q_w = K_1 K_2 Q_{w0} \text{ kN (tonne-f)}$$

where



# Longitudinal Strength

# Part 3, Chapter 4

Section 6

$$Q_{w0} = 0,3C_1 LB (C_b + 0,7) \text{ kN}$$

$$(0,0306C_1 LB (C_b + 0,7) \text{ tonne-f})$$

and  $C_b$  is to be taken not less than 0,6

$K_1$  is to be taken as follows, see also Fig. 4.6.1:

(a) Positive shear force

$$K_1 = 0 \text{ at aft end of } L$$

$$= \frac{1,589C_b}{(C_b + 0,7)} \text{ between } 0,2L \text{ and } 0,3L \text{ from aft}$$

$$= 0,7 \text{ between } 0,4L \text{ and } 0,6L \text{ from aft}$$

$$= 1,0 \text{ between } 0,7L \text{ and } 0,85L \text{ from aft}$$

$$= 0 \text{ at forward end of } L$$

(b) Negative shear force

$$K_1 = 0 \text{ at aft end of } L$$

$$= -0,92 \text{ between } 0,2L \text{ and } 0,3L \text{ from aft}$$

$$= -0,7 \text{ between } 0,4L \text{ and } 0,6L \text{ from aft}$$

$$= \frac{-1,727C_b}{(C_b + 0,7)} \text{ between } 0,7L \text{ and } 0,85L \text{ from aft}$$

$$= 0 \text{ at forward end of } L$$

Intermediate values to be determined by linear interpolation

$$K_2 = 1,0 \text{ for unrestricted sea-going service conditions}$$

$$= 0,8 \text{ for short voyages}$$

$$= 0,5 \text{ for operating in sheltered water.}$$




Fig. 4.6.1 Shear force factor  $K_1$

## 6.4 Design still water shear force

6.4.1 The design still water shear force,  $Q_s$ , at each transverse section along the hull is to be taken as the maximum positive and negative value found from the longitudinal strength calculations for each of the loading conditions given in 5.3.3 and is to satisfy the following relationship:

$$|Q_s| \leq |\overline{Q}_s|$$

6.4.2 Still water shear forces are to be calculated at each section along the ship length. For these calculations, downward loads are to be taken as positive values and are to be integrated in a forward direction from the aft end of  $L$ . The shear force is positive when the algebraic sum of all vertical forces aft of the section is positive.

6.4.3 For hull configuration Types A, D, G, H and I, as indicated in Table 4.6.1, where loading conditions are featuring either:

- cargo loading with specified or alternate cargo holds (or cargo tanks) empty; or
- ballasting of cargo hold(s);

the actual shear forces obtained from the longitudinal strength calculations may be corrected for the effect of local forces at the transverse bulkheads. The calculation of these local forces is to be submitted for approval or, alternatively, the proportion of the double bottom load carried by the transverse bulkhead may be arrived at by using the following bulkhead factor  $F$ :

$$F = \frac{1}{1 + 1,5\alpha^{1,65}}$$

where

$l_F$  = span of floors measured to intersection of hopper side or ship's side, and inner bottom, in metres

$S_H$  = length of hold measured between bulkhead stools, where fitted, at the level of the inner bottom on the centreline, in metres

$$\alpha = \frac{S_H}{l_F}$$

6.4.4 If the hull shear forces in kN (tonne-f) at transverse bulkheads A and B are calculated to be  $Q_A$  and  $Q_B$  respectively (with appropriate algebraic signs), the excess load or buoyancy over hold AB is given by  $Q_B - Q_A$  and the load transmitted to each bulkhead is:

$$0,5F (Q_B - Q_A) \text{ kN (tonne-f)}$$

where  $F$  is the bulkhead factor as given in 6.4.3. See Fig. 4.6.2.




Fig. 4.6.2 Shear force correction

# Longitudinal Strength

# Part 3, Chapter 4

Section 6

6.4.5 The corrected shear forces,  $Q_A'$  and  $Q_B'$ , at bulkheads A and B with respect to hold AB are then obtained from:

$$\begin{aligned} Q_A' &= Q_A + 0,5F(Q_B - Q_A) \text{ kN (tonne-f)} \\ Q_B' &= Q_B - 0,5F(Q_B - Q_A) \text{ kN (tonne-f)} \end{aligned}$$

## 6.5 Permissible still water shear force

6.5.1 The permissible hull still water shear force is given by the minimum value obtained from:

$$|Q_s| = \tau \frac{I \delta_i}{100Az} - |Q_w| \text{ kN (tonne-f)}$$

when

$$\delta_i = \frac{t_i}{f_i + m_i}$$

$i$  = structural member index for the hull configuration under consideration, see Table 4.6.1

$t_i$  = the plate thickness of the structural member at the vertical level and section under consideration, in mm

$f_i, m_i$  = factors determined from Tables 4.6.1 and 4.6.2 respectively, for the hull configuration under consideration.

6.5.2 The permissible shear forces assigned for approved loading instruments will normally be based on 6.5.1. However, where use is made of an approved loading instrument incorporating a facility to calculate the transverse distribution of shear forces, separate permissible still water shear forces,  $Q_{si}$  may be assigned for the structural members indicated in Table 4.6.1 for the hull configuration under consideration.

$$|Q_{si}| = (f_i + m_i) |Q_s| \text{ kN (tonne-f)}$$

6.5.3 Individual loading conditions in the ship's loading manual may be specially considered on a similar basis to that in 6.5.2 with the factors being determined by direct calculation.

6.5.4 For hull configuration types B and E (see Table 4.6.1), where loading conditions are such that hull girder torsion may be induced, direct calculations may be required.

6.5.5 The calculation of shear forces immediately beyond the ends of the longitudinal bulkheads will be considered in relation to the arrangement of structure in these regions.

## 6.6 Permissible shear stress

6.6.1 The permissible combined shear stress (still water plus wave) is to be taken as:

$$\tau = \frac{110}{k_L} \text{ N/mm}^2 \quad \left( \frac{11,2}{k_L} \text{ kgf/mm}^2 \right)$$

6.6.2 Where a plate is tapered, the permissible combined shear stress is not to be exceeded at any point in way of the taper, see Fig. 4.6.3.

## 6.7 Design shear stress

6.7.1 The design shear stress for use in 7.4 is to be taken as:







$$\begin{aligned} \tau_A &= 100Az \frac{|Q_s| + |Q_w|}{I \delta_i} \text{ N/mm}^2 \\ &= \left( 10,2Az \frac{|Q_s| + |Q_w|}{I \delta_i} \text{ kgf/mm}^2 \right) \end{aligned}$$

# Longitudinal Strength

## Part 3, Chapter 4

Section 6

**Table 4.6.1**  $f_i$  factors (see continuation)





Hull configuration	$f_i$ factors
<p>Type A</p> 	<p>Member 1  <math>f_1 = 0,5</math></p>
<p>Type B</p> 	<p>Member 1  <math>f_1 = 0,231 + 0,076 A_1/A_2</math>            Member 2  <math>f_2 = 0,538 - 0,152 A_1/A_2</math></p>
<p>Type C</p> 	<p>Member 1  <math>f_1 = 0,135 + 0,088 A_1/A_2</math>            Member 2  <math>f_2 = 0,365 - 0,088 A_1/A_2</math></p>
<p>Type D</p> 	<p>Member 1  <math>f_1 = 0,128 + 0,105 A_1/A_2</math>            Member 2  <math>f_2 = 0,372 - 0,105 A_1/A_2</math></p>
<p>Type E</p> 	<p>Member 1  <math>f_1 = 0,055 + 0,097 A_1/A_2 + 0,020 A_2/A_3</math>            Member 2  <math>f_2 = 0,193 - 0,059 A_1/A_2 + 0,058 A_2/A_3</math>            Member 3  <math>f_3 = 0,504 - 0,076 A_1/A_2 - 0,156 A_2/A_3</math></p>
<p>Type F</p> 	<p>Member 1  <math>f_1 = 0,028 + 0,087 A_1/A_2 + 0,023 A_2/A_3</math>            Member 2  <math>f_2 = 0,119 - 0,038 A_1/A_2 + 0,072 A_2/A_3</math>            Member 3  <math>f_3 = 0,353 - 0,049 A_1/A_2 - 0,095 A_2/A_3</math></p>

# Longitudinal Strength

## Part 3, Chapter 4

Section 6

**Table 4.6.1**  $f_i$  factors (continued)

Hull configuration	$f_i$ factors
<p>Type G</p> 	<p>Member 1  <math>f_1 = 0,139 + 0,099 A_1/A_2</math>                      Member 2  <math>f_2 = 0,361 - 0,099 A_1/A_2</math></p>
<p>Type H</p>  <p>3688/06</p>	<p>Member 1  <math>f_1 = 0,216 + 0,087 A_1/(A_7 + A_2 \sin \theta_t)</math>                      Member 2  <math>f_2 = 0,284 - 0,087 A_1/(A_7 + A_2 \sin \theta_t)</math>                      Member 3  <math>f_3 = 0,5</math>                      Member 5  <math>f_5 = 0,155 + 0,087 A_5/(A_8 + A_6 \sin \theta_h)</math>                      Member 6  <math>f_6 = 0,345 - 0,087 A_5/(A_8 + A_6 \sin \theta_h)</math>  <math>f_7 = f_2, f_8 = f_6</math></p>
<p>Type I</p>  <p>3688/07</p>	<p>Member 1  <math>f_1 = 0,216 + 0,087 A_1/(A_7 + A_2 \sin \theta_t)</math>                      Member 2  <math>f_2 = 0,284 - 0,087 A_1/(A_7 + A_2 \sin \theta_t)</math>                      Member 3  <math>f_3 = 0,143 + 0,104 A_3/A_4</math>                      Member 4  <math>f_4 = 0,357 - 0,104 A_3/A_4</math>                      Member 5  <math>f_5 = 0,155 + 0,087 A_5/(A_8 + A_6 \sin \theta_h)</math>                      Member 6  <math>f_6 = 0,345 - 0,087 A_5/(A_8 + A_6 \sin \theta_h)</math>  <math>f_7 = f_2, f_8 = f_6</math></p>
<p>Type J</p> 	<p>Member 1  <math>f_1 = 0,153 + 0,105 A_1/A_2</math>                      Member 2  <math>f_2 = 0,347 - 0,105 A_1/A_2</math></p>

# Longitudinal Strength

## Part 3, Chapter 4

Section 6

**Table 4.6.1**  $f_i$  factors (conclusion)

Hull configuration	$f_i$ factors
<p>Type K</p> <p>Member 1  <math>f_1 = 0,128 + 0,105 A_1/A_2</math></p> <p>Member 2  <math>f_2 = 0,372 - 0,105 A_1/A_2</math></p>	
<p>Type L</p> <p>Member 1  <math>f_1 = 0,093 + 0,162 A_1/A_2</math></p> <p>Member 2  <math>f_2 = 0,407 - 0,162 A_1/A_2</math></p>	
Symbols	
<p><math>i</math> = structural member index for different hull configurations  for types A, B, C, D, E, F and G, <math>i</math> may take the value of 1, 2 or 3.  for <math>i = 1</math>, the side shell at the section is under consideration  for <math>i = 2</math> and 3, the longitudinal bulkheads at the section are under consideration  for types H and I, <math>i</math> may take the value of 1, 2, 3, 4, 5, 6, 7 or 8  for <math>i = 1</math>, the part of side shell in way of topside tank is under consideration  for <math>i = 2</math>, the topside slope is under consideration  for <math>i = 3</math>, the part of side shell between topside tank and hopper tank is under consideration  for <math>i = 4</math>, the inner hull is under consideration  for <math>i = 5</math>, the part of side shell in way of hopper tank is under consideration  for <math>i = 6</math>, the hopper slope is under consideration  for <math>i = 7</math>, the vertical strake at topside tank is under consideration  for <math>i = 8</math>, the double bottom girder at hopper tank is under consideration  for types J, K and L, <math>i</math> may take the value of 1 or 2:  for <math>i = 1</math>, the side shell at the section is under consideration  for <math>i = 2</math>, the longitudinal bulkheads at the section are under consideration</p> <p><math>A_i</math> = the area of structural member <math>i</math> at the section under consideration, in cm<sup>2</sup>  In the event of part of the structural member being non-vertical, <math>A_i</math> is to be calculated using the projected area in the vertical direction, see Fig. 4.6.4, except for members 2 and 6 for types H and I, where the inclined area is to be applied.</p>	
<p>NOTES</p> <ol style="list-style-type: none"> <li>For hull configurations not included above, <math>f_i</math> factors are to be specially considered.</li> <li>Where it is necessary to increase the thickness of the side shell or longitudinal bulkhead(s) to meet these requirements, the original thicknesses are to be used in the calculation of the cross-sectional areas <math>A_i</math>.</li> </ol>	

Table 4.6.2  $m_i$  factors

Hull configuration, see Table 4.6.1	$m_i$ factors
Type A	$m_1 = 0$
Type B	$m_1 = \frac{m_2}{2}, \quad m_2 = (0,1 + r) 0,5$
Type C	$m_1 = m_2, \quad m_2 = (0,1 + r) \frac{b_2}{B}$
Type D	$m_i = 0$
Type E	$m_1 = \frac{m_3}{4}, \quad m_2 = \frac{m_3}{4}, \quad m_3 = (0,1 + r) 0,5 \left(1 - \frac{b_2}{B}\right)$
Type F	$m_1 = \frac{m_3}{2}, \quad m_2 = \frac{m_3}{2}, \quad m_3 = (0,1 + r) \left(\frac{b_3 - 0,5b_2}{B}\right)$
Type G	$m_i = 0$
Type H	$m_i = 0$
Type I	$m_i = 0$
Type J	$m_i = 0$
Type K	$m_i = 0$
Type L	$m_i = 0$
Symbols	
$i$ = structural member index for different hull configurations, see Table 4.6.1 $b_i$ = the horizontal distance of the structural member $i$ from the side shell, at the section under consideration, in metres $r$ = 0,15 within 0,20 $L_T$ from the transverse bulkhead position for loading conditions where the cargo region between two consecutive bulkheads is unevenly loaded in the transverse direction = 0 within 0,20 $L_T$ from the transverse bulkhead position for loading conditions where the cargo region between two consecutive bulkheads is evenly loaded in the transverse direction = 0 elsewhere $L_T$ = cargo hold length, in metres	
NOTE For hull configurations not included above, $m_i$ factors are to be specially considered.	





Fig. 4.6.3 Tapered plates



## 7.2 Symbols

7.2.1 The symbols used in this Section are defined as follows:

$d_t$  = standard deduction for corrosion, see Table 4.7.1  
 $s$  = spacing of secondary stiffeners, in mm. In the case of symmetrical corrugations,  $s$  is to be taken as  $b$  or  $c$  in Fig. 3.3.1 in Chapter 3, whichever is the greater

$t$  = as built thickness of plating, stiffener flange and web used in Table 4.7.1 in calculating standard deduction  $d_t$ , in mm

$t_p$  = as built thickness of plating less standard deduction  $d_t$ , in mm, (i.e.  $t_p = t - d_t$ )

$E$  = modulus of elasticity, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)  
 = 206000 N/mm<sup>2</sup> (21000 kgf/mm<sup>2</sup>) for steel

$S$  = spacing of primary members, in metres

$\sigma_o$  = specified minimum yield stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$\sigma_A$  = design longitudinal compressive stress in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$\sigma_{CRB}$  = critical buckling stress in compression, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) corrected for yielding effects

$\sigma_E$  = elastic critical buckling stress in compression, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$\tau_A$  = design shear stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$\tau_{CRB}$  = critical buckling stress in shear, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) corrected for yielding effects

$\tau_E$  = elastic critical buckling stress in shear, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$$\tau_o = \frac{\sigma_o}{\sqrt{3}}$$

## 7.3 Elastic critical buckling stress

7.3.1 The elastic critical buckling stress of plating is to be determined from Table 4.7.2.

7.3.2 The elastic critical buckling stress of longitudinals is to be determined from Table 4.7.3.

## Section 7

### Hull buckling strength

#### 7.1 Application

7.1.1 These requirements apply to plate panels and longitudinals subjected to hull girder compression and shear stresses based on design values for still water and wave bending moments and shear forces.

7.1.2 The hull buckling strength requirements are applicable within 0,4L amidships to ships of 90 m or greater in length.

7.1.3 Hull buckling strength outside 0,4L amidships and hull buckling strength for ships less than 90 m in length will be specially considered.

# Longitudinal Strength

## Part 3, Chapter 4

Section 7

**Table 4.7.1 Standard deduction for corrosion,  $d_t$**

Structure		$d_t$ mm	$d_t$ range mm min. – max.
(a) Compartments carrying dry bulk cargoes		0,05t	0,5 – 1
(b) One side exposure to water ballast and/or liquid cargo.	Vertical surfaces and surfaces sloped at an angle greater than 25° to the horizontal line.		
(c) One side exposure to water ballast and/or liquid cargo.	Horizontal surfaces and surfaces sloped at an angle less than 25° to the horizontal line.	0,10t	2 – 3
(d) Two side exposure to water ballast and/or liquid cargo.	Vertical surfaces and surfaces sloped at an angle greater than 25° to the horizontal line.		
(e) Two side exposure to water ballast and/or liquid cargo.	Horizontal surfaces and surfaces sloped at an angle less than 25° to the horizontal line.	0,15t	2 – 4
<b>NOTES</b> 1. The standard deduction $d_t$ is to be taken as appropriate and within the range given above. 2. For direct calculation purposes, standard deductions will be specially considered.			

**Table 4.7.2 Elastic critical buckling stress of plating**

Mode	Elastic critical buckling stress, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
(a) Compression of plating with longitudinal stiffeners (parallel to compressive stress), see Note	$\sigma_E = 3,6E \left( \frac{t_p}{s} \right)^2$
(b) Compression of plating with transverse stiffeners (perpendicular to compressive stress), see Note	$\sigma_E = 0,9c \left[ 1 + \left( \frac{s}{1000S} \right)^2 \right]^2 E \left( \frac{t_p}{s} \right)^2$ where $c = 1,3$ when plating stiffened by floors or deep girders $= 1,21$ when stiffeners are built up profiles or rolled angles $= 1,10$ when stiffeners are bulb plates $= 1,05$ when stiffeners are flat bars
(c) Shear, see Note	$\tau_E = 3,6 \left[ 1,335 + \left( \frac{s}{1000S} \right)^2 \right] E \left( \frac{t_p}{s} \right)^2$
<b>NOTE</b> Where the elastic critical buckling stress, as evaluated from (a), (b) or (c), exceeds 50 per cent of specified minimum yield stress of the material, the corrected critical buckling stresses in compression ( $\sigma_{CRB}$ ) and shear ( $\tau_{CRB}$ ) are given by:	
$\sigma_{CRB} = \sigma_E$ when $\sigma_E \leq \frac{\sigma_o}{2}$ $= \sigma_o \left( 1 - \frac{\sigma_o}{4\sigma_E} \right)$ when $\sigma_E > \frac{\sigma_o}{2}$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	
$\tau_{CRB} = \tau_E$ when $\tau_E \leq \frac{\tau_o}{2}$ $= \tau_o \left( 1 - \frac{\tau_o}{4\tau_E} \right)$ when $\tau_E > \frac{\tau_o}{2}$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	



# Longitudinal Strength

## Part 3, Chapter 4

Section 7

**Table 4.7.3 Elastic critical buckling stress of longitudinals** (see continuation)

Mode	Elastic critical buckling stress, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
(a) Column buckling (perpendicular to plane of plating) without rotation of cross section, see Note 1	$\sigma_E = 0,001E \frac{I_a}{A_t S^2}$
(b) Torsional buckling, see Note 1	$\sigma_E = \frac{0,001 E I_w}{I_p S^2} \left( m^2 + \frac{K}{m^2} \right) + 0,385E \frac{I_t}{I_p}$
(c) Web buckling, see Notes 1 and 3 (flat bars are excluded)	$\sigma_E = 3,8E \left( \frac{t_w}{d_w} \right)^2$
Symbols and Parameters	
<p><math>d_w</math> = web depth, in mm</p> <p><math>t_w</math> = as built web thickness less standard deduction <math>d_t</math> as specified in Table 4.7.1, in mm, (i.e. <math>t_w = t - d_t</math>). For webs in which the thickness varies, a mean thickness is to be used</p> <p><math>b_f</math> = flange width, in mm</p> <p><math>t_f</math> = as built flange thickness less standard deduction <math>d_t</math> as specified in Table 4.7.1, in mm, (i.e. <math>t_f = t - d_t</math>). For bulb plates, the mean thickness of the bulb may be used, see Fig. 4.7.1</p> <p><math>A_t</math> = cross-sectional area, in cm<sup>2</sup>, of longitudinal, including attached plating, taking account of standard deductions, see Note 4</p> <p><math>I_a</math> = moment of inertia, in cm<sup>4</sup>, of longitudinal, including attached plating, taking account of standard deductions, see Note 4</p> <p><math>I_t</math> = St.Venant's moment of inertia, in cm<sup>4</sup>, of longitudinal (without attached plating)</p> <p><math>= \frac{d_w t_w^3}{3} 10^{-4}</math> for flat bars</p> <p><math>= \frac{1}{3} \left[ d_w t_w^3 + b_f t_f^3 \left( 1 - 0,63 \frac{t_f}{b_f} \right) \right] 10^{-4}</math> for built up profiles, rolled angles and bulb plates</p> <p><math>I_p</math> = polar moment of inertia, in cm<sup>4</sup>, of profile about connection of stiffener to plating</p> <p><math>= \frac{d_w^3 t_w}{3} 10^{-4}</math> for flat bars</p> <p><math>= \left( \frac{d_w^3 t_w}{3} + d_w^2 b_f t_f \right) 10^{-4}</math> for built up profiles, rolled angles and bulb plates</p> <p><math>I_w</math> = sectorial moment of inertia, in cm<sup>6</sup>, of profile about connection of stiffener to plating</p> <p><math>= \frac{d_w^3 t_w^3}{36} 10^{-6}</math> for flat bars</p> <p><math>= \frac{t_f b_f^3 d_w^2}{12} 10^{-6}</math> for 'Tee' profiles</p> <p><math>= \frac{b_f^3 d_w^2}{12 (b_f + d_w)^2} \left[ t_f \left( b_f^2 + 2b_f d_w + 4d_w^2 \right) + 3t_w b_f d_w \right] 10^{-6}</math> for 'L' profiles, rolled angles and bulb plates</p> <p><math>K = \frac{1,03C S^4}{E I_w} 10^4</math></p>	

### 7.4 Design stress

7.4.1 Design longitudinal compressive stress,  $\sigma_A$ , is to be determined in accordance with Section 5:

$$\text{minimum } \sigma_A = \frac{30}{k_L} \text{ N/mm}^2 \left( \frac{3,06}{k_L} \text{ kgf/mm}^2 \right)$$

for structural members above the neutral axis,

$$\sigma_A = \sigma_D \frac{Z}{Z_D}$$

for structural members below the neutral axis,

$$\sigma_A = \sigma_B \frac{Z}{Z_B}$$

$\sigma_D$  based on sagging moment and  $\sigma_B$  based on hogging moment are determined in 5.6.1.

where

$Z$  = vertical distance from the hull transverse neutral axis to the position considered, excluding deck camber, in metres

$Z_D, Z_B$  = vertical distances from the hull transverse neutral axis to the deck and keel respectively, in metres

# Longitudinal Strength

## Part 3, Chapter 4

Section 7

**Table 4.7.3 Elastic critical buckling stress of longitudinals (conclusion)**

$m$  is determined as follows:

$m$	$K$ range
1	$0 < K \leq 4$
2	$4 < K \leq 36$
3	$36 < K \leq 144$
4	$144 < K \leq 400$
5	$400 < K \leq 900$
6	$900 < K \leq 1764$
$m$	$(m-1)^2 m^2 < K \leq m^2 (m+1)^2$

$C$  = spring stiffness exerted by supporting plate panel

$$C = \frac{k_p E t_p^3}{3s \left( 1 + \frac{1,33 k_p d_w t_p^3}{s t_w^3} \right)}$$

$k_p$  =  $1 - \eta_p$ , and is not to be taken less than zero. For built up profiles, rolled angles and bulb plates,  $k_p$  need not be taken less than 0,1

$\eta_p = \frac{\sigma_A}{\sigma_{Ep}}$  where  $\sigma_{Ep}$  = elastic critical buckling stress ( $\sigma_E$ ) of supporting plate derived from Table 4.7.2

All other symbols as defined in 7.2.1.

### NOTES

- Where the elastic critical buckling stress, as evaluated from (a), (b) or (c), exceeds 50 per cent of specified minimum yield stress of the material, the corrected critical buckling stress in compression ( $\sigma_{CRB}$ ) is given by:

$$\sigma_{CRB} = \sigma_o \left( 1 - \frac{\sigma_o}{4\sigma_E} \right) \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

- Fig. 4.7.1 shows the dimensions of longitudinals.
- For flanges on angles and T-sections of longitudinals, the following requirement is to be satisfied:

$$\frac{b_f}{t} \leq 15 \text{ for angles,} \quad \frac{b_f}{t} \leq 30 \text{ for 'Tee' profiles,}$$

where

$t$  = as built flange thickness, in mm

- The area of attached plating is to be calculated using actual spacing of secondary stiffeners.

For initial design purposes, the hull transverse neutral axis may be taken at a distance  $\frac{D}{2}$  above keel, where  $D$  is the depth of the ship, in metres, as defined in Ch 1,6.

7.4.2 Design shear stress,  $\tau_A$ , is to be determined in accordance with Section 6.

For initial design purposes,  $\tau_A$  may be taken as:

$$\tau_A = \frac{110}{k_L} \text{ N/mm}^2 \left( \frac{11,2}{k_L} \text{ kgf/mm}^2 \right)$$

### 7.5 Scantling criteria

7.5.1 The corrected critical buckling stress in compression,  $\sigma_{CRB}$ , of plate panels and longitudinals, as derived from Tables 4.7.2 and 4.7.3, is to satisfy the following:

$$\sigma_{CRB} \geq \beta \sigma_A$$


where

$\beta$  = 1 for plating and for web plating of longitudinals (local buckling)

$\beta$  = 1,1 for longitudinals

7.5.2 The corrected critical buckling stress in shear,  $\tau_{CRB}$ , of plate panels, as derived from Table 4.7.2(c), is to satisfy the following:

$$\tau_{CRB} \geq \tau_A$$



## Section 8

### Loading guidance information

#### 8.1 General

8.1.1 Sufficient information is to be supplied to the Master of every ship to enable him to arrange loading and ballasting in such a way as to avoid the creation of unacceptable stresses in the ship's structure.

8.1.2 This information is to be provided by means of a Loading Manual and in addition, where required, by means of an approved loading instrument.

#### 8.2 Loading Manual

8.2.1 A Loading Manual is to be supplied to all ships where longitudinal strength calculations have been required, see Section 2. The Manual is to be submitted for approval in respect of strength aspects. Where both Loading Manual and loading instrument are supplied, the Loading Manual must nevertheless be approved from the strength aspect. In this case, the Manual is to be endorsed to the effect that any departures from these conditions in service are to be arranged on the basis of the loading instrument and the allowable local loadings shown in the Manual, see 8.2.4.

8.2.2 The Manual is to be based on the final data of the ship and is to include well-defined lightweight distribution and buoyancy data.

8.2.3 Details of the loading conditions given in 5.3.3 are to be included in the Manual as applicable.

# Longitudinal Strength

# Part 3, Chapter 4

Section 8

8.2.4 The Manual is also to contain the following:

- (a) Values of actual and permissible still water bending moments and shear forces and, where applicable, limitations due to torsional loads.
- (b) The allowable local loadings for the structure such as the hatch covers, decks and double bottoms. If the ship is not approved to carry load on the deck or hatch covers, this is to be clearly stated.
- (c) Details of cargo carriage constraints imposed by the use of an accepted coating in association with a system of corrosion control, see Ch 2,3.6.
- (d) A note saying:  
'Scantlings approved for minimum draught forward of ...m with ballast tanks No... filled. In heavy weather conditions the forward draught should not be less than this value. If, in the opinion of the Master, sea conditions are likely to cause regular slamming, then other appropriate measures such as change in speed, heading or an increase in draught forward may also need to be taken.'
- (e) The maximum unladen weight, in tonnes, of grab that is considered suitable for the approved thickness of the hold inner bottom for bulk carriers and ore or oil carriers that are regularly discharged by grabs. This maximum unladen weight may differ for adjacent holds, see Ch 9,13.2 and Pt 4, Ch 7,8.1. This weight does not preclude the use of heavier grabs, but is intended as an indication to the Builders, Owners and operators of the increased risk of local damage and the possibility of accelerated diminution of the plating thickness if grabs heavier than this are used regularly to discharge cargo.

8.2.5 In addition to the requirements of 8.2.4, the Manual is to contain the following information for bulk carriers (see 3.2.2), ore carriers and combination carriers of length,  $L$ , 150 m or above:

- (a) The cargo hold(s) or combination of cargo holds that may be empty at maximum draught. If no cargo hold is permitted to be empty at maximum draught, this is to be clearly stated in the Manual.
- (b) Maximum allowable and minimum required mass of cargo and double bottom ballast for each hold as a function of the draught at mid-hold position.
- (c) Maximum allowable and minimum required mass of cargo and double bottom ballast for any two adjacent holds as a function of the mean draught in way of these holds. The mean draught may be calculated by averaging the draught at the two mid-hold positions.
- (d) Maximum allowable inner bottom loading together with specification of the nature of the cargo, for cargoes other than bulk cargoes.
- (e) The maximum rate of ballast exchange, together with advice that a load plan is to be agreed with the terminal on the basis of achievable rates of exchange.

For bulk carriers for which it is required to undertake longitudinal strength calculations in the flooded condition, see Pt 4, Ch 7,1.2.2, the Manual is also to contain envelope results and permissible limits of still water bending moments and shear forces for hold flooded conditions, see Pt 4, Ch 7,3.4.

8.2.6 Where applicable, the Manual is also to contain the procedure for ballast exchange and sediment removal at sea.

8.2.7 Where alteration to structure, lightweight, cargo distribution or draught is proposed, revised information is to be submitted for approval.

## 8.3 Loading instrument

8.3.1 In addition to a Loading Manual, an approved type loading instrument is to be provided for all ships where  $L$  is greater than 65 m and which are approved for non-uniform distribution of loading. The following ships are exempt from this requirement:

- (a) Ships with very limited possibilities for variations in the distribution of cargo and ballast.
- (b) Ships with a regular or fixed trading pattern.
- (c) Ships exempt by individual Chapters in Part 4.

8.3.2 The loading instrument is to be capable of calculating shear forces and bending moments, in any load or ballast condition at specified readout points and is to indicate the permissible values. On container ships and other ships with large deck openings (see 3.3.2), cargo torque is also to be calculated.

8.3.3 For bulk carriers, ore carriers and combination carriers of length,  $L$ , 150 m or above, the loading instrument is to be additionally capable of verifying that the following are within permissible limits:

- (a) the mass of cargo and double bottom ballast in way of each hold as a function of the draught at the mid-hold position.
- (b) the mass of cargo and double bottom ballast for any two adjacent holds as a function of the mean draught in way of these holds. The mean draught may be calculated by averaging the draught at the two mid-hold positions.

For bulk carriers for which it is required to undertake longitudinal strength calculations in the flooded condition, see Pt 4, Ch 7,1.2.2, the loading instrument is also to be capable of verifying that the still water bending moments and shear forces in hold flooded conditions (see Pt 4, Ch 7,3.4), are within permissible limits.

8.3.4 If the approved loading manual utilises bulkhead correction factors for shear force distribution, then the loading instrument must also have the capability to account for the bulkhead correction factors.

8.3.5 The instrument is to be certified in accordance with LR's document entitled *Approval of Longitudinal Strength and Stability Calculations Programs*.

8.3.6 The instrument readout points are usually selected at the position of the transverse bulkheads or other obvious boundaries. As many readout points as considered necessary by LR are to be included, e.g., between bulkheads.

8.3.7 A notice is to be displayed on the loading instrument stating:

‘Scantlings approved for minimum draught forward of ...m with ballast tanks No... filled. In heavy weather conditions, the forward draught should not be less than this value. If, in the opinion of the Master, sea conditions are likely to cause regular slamming, then other appropriate measures such as change in speed, heading or an increase in draught forward may also need to be taken.’

8.3.8 Where alteration to structure, lightweight or cargo distribution is proposed, the loading instrument is to be modified accordingly and details submitted for approval.

8.3.9 The operation of the loading instrument is to be verified by the Surveyors upon installation and at Annual and Periodical Surveys as required in Pt 1, Ch 3. An Operation Manual for the instrument is to be verified as being available on board.

8.3.10 Where an onboard computer system having a strength computation capability is provided as an Owner’s option, it is recommended that the system be certified in accordance with LR’s document entitled *Approval of Longitudinal Strength and Stability Calculations Programs*. For systems having a stability computation capability and installed on a new ship, see also Pt 1, Ch 2,1.1.11. For systems having a stability computation capability and installed on an existing ship, it is recommended that the system be certified in accordance with LR’s document entitled *Approval of Longitudinal Strength and Stability Calculation Programs*.

---



# Fore End Structure

## Part 3, Chapter 5

Section 1

### Section

- 1 **General**
- 2 **Deck structure**
- 3 **Shell envelope plating**
- 4 **Shell envelope framing**
- 5 **Single and double bottom structure**
- 6 **Fore peak structure**
- 7 **Forward deep tank structure**

### ■ Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies to all types of ship covered by Part 4 except where specifically stated otherwise.

1.1.2 The requirements given are those specific to fore ends and relate to structure situated in the region forward of 0,3L from the forward perpendicular.

1.1.3 Requirements for cargo space structure within this region not dealt with in this Chapter are to be as detailed in the relevant Chapter of Part 4 for the particular ship type.

1.1.4 The requirements in this chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation. See Pt 1, Ch 2,2.3.

#### 1.2 Structural configuration

1.2.1 The Rules provide for both longitudinal and transverse framing systems.

1.2.2 In the case of container ships and open type ships, additional requirements may apply as detailed in Pt 4, Ch 8.

1.2.3 In the case of fast cargo ships, the additional requirements given in Pt 4, Ch 1,3 are to be complied with where applicable.

1.2.4 The requirements regarding minimum bow height given in Ch 3,6 are to be complied with where applicable.

#### 1.3 Structural continuity

1.3.1 Suitable scarfing arrangements are to be made to ensure continuity of strength and the avoidance of abrupt structural changes.

1.3.2 Where longitudinal framing terminates and is replaced by a transverse system, adequate arrangements are to be made to avoid an abrupt changeover. Where a fore-castle is fitted extending aft of 0,15L from the F.P., longitudinal framing at the upper deck and topsides is generally to be continued forward of the end bulkhead of this superstructure. In bulk carriers and oil tankers (see 1.1.4) the longitudinal framing at the upper deck is to be maintained over the cargo space region and continued over the fore peak region.

1.3.3 In container or similar ships having continuous side tanks or double skin construction in way of the cargo spaces, the longitudinal bulkheads are to be continued as far forward as is practicable and are to be suitably tapered at their ends. Where, due to the ship's form, such bulkheads are stepped, suitable scarfing is to be arranged.

1.3.4 In bulk carriers (see 1.1.4) the topside tank and double bottom hopper tank structures are to be maintained over the cargo space region, and suitable taper brackets are to be arranged in line with the end of these tank structures in the fore peak region. In addition, in way of the cargo space forward bulkhead, a girder or intercostal bulb plate stiffeners (fitted between and connected to the bulkhead vertical stiffeners), are to be arranged on the forward side in line with the sloped bulkheads of the topside and hopper tanks clear of the taper brackets.

#### 1.4 Symbols and definitions

1.4.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L, B, D, T, C_b$  and  $V$  as defined in Ch 1,6.1

$k_L, k$  = higher tensile steel factor, see Ch 2,1.2

$l$  = overall length of stiffening member, in metres, see Ch 3,3.3

$l_e$  = effective length of stiffening member, in metres, see Ch 3,3.3

$s$  = spacing of secondary stiffeners, in mm

$t$  = thickness of plating, in mm

$I$  = inertia of stiffening member, in cm<sup>4</sup>, see Ch 3,3.2

$S$  = spacing, or mean spacing, of primary members, in metres

$Z$  = section modulus of stiffening member, in cm<sup>3</sup>, see Ch 3,3.2

$\rho$  = relative density (specific gravity) of liquid carried in a tank and is to be taken not less than 1,025.

1.4.2 For the purpose of this Chapter the forward perpendicular, F.P., is defined as the forward limit of the Rule length  $L$ .

#### 1.5 Strengthening of bottom forward

1.5.1 The bottom forward of a sea-going ship is to be additionally strengthened, except where the ship is so designed that a minimum draught forward,  $T_{FB}$ , of 0,045L can be achieved for any ballast or part loaded condition. This draught is to be indicated on the shell expansion plan, the plan showing the internal strengthening, the Loading Manual and loading instrument, where fitted, see Ch 4,8.

# Fore End Structure

# Part 3, Chapter 5

Section 1

1.5.2 The requirements for the additional strengthening apply to ships where  $L$  is greater than 65 m. Where a ship is classed for service in protected waters or extended protected waters, compliance with the requirements of this Section may be modified or waived altogether.

1.5.3 The additional strengthening is to extend forward of  $0,3L$  from the F.P. over the flat of bottom and adjacent plating with attached stiffeners up to a height of  $0,002L$  above the base line or 300 mm whichever is the lesser.

1.5.4 The scantling requirements outside the areas defined in 1.5.3 are to be suitably tapered to maintain adequate continuity of strength in both longitudinal and transverse directions.

1.5.5 The requirements for the additional strengthening within the region defined in 1.5.3 are given in Table 5.1.1, or may be obtained by direct calculation. Where  $T_{FB}$  is less than  $0,01L$ , the additional strengthening is to be specially considered.

1.5.6 Bottom longitudinals are to pass through and be supported by the webs of primary members. The vertical web stiffeners are to be connected to the bottom longitudinals. The cross-sectional area of the connections is to comply with the requirements given in Table 5.1.1.

1.5.7 The scantlings required by this Section must in no case be less than those required by the remaining Sections in Chapter 5.

1.5.8 For minimum draught forward,  $T_{FB}$  between  $0,01L$  and  $0,045L$ , the equivalent slamming pressure expressed as a head of water,  $h_s$ , is to be obtained from Fig. 5.1.1, where  $h_{max}$  is calculated from the following expressions:

$$65 < L \leq 169 \text{ m}, h_{max} = 10\sqrt{L} F \text{ m}$$

$$169 < L \leq 180 \text{ m}, h_{max} = 130 F \text{ m}$$

$$L > 180 \text{ m}, h_{max} = 130 F e^{-0,0125(L-180)^{0,705}} \text{ m}$$

where

$$F = 5,95 - 10,5 \left( \frac{T_{FB}}{L} \right)^{0,2}$$

and

$e$  = base of natural logarithm, 2,7183

- The application of the maximum pressure for forward of  $0,3L$  from the F.P. is as indicated in Fig. 5.1.1. For  $C_b$  between 0,70 and 0,80 its position may be obtained by linear interpolation.
- Where the bottom plating forms the boundary of a double bottom tank, deep tank or double skin tank which is full in all ballast conditions, then for such conditions the head,  $h_s$ , may be reduced by 1,25 times the head, in metres, of ballast water to top of tank.
- For bulk carriers (see 1.1.4) the reduction to the head,  $h_s$ , is not to exceed the head, in metres, of ballast water to the top of the hopper tank or 1,25 times the depth, in metres, of the double bottom tank, whichever is the greater.
- For ballast and part loaded conditions where the draught forward is less than  $0,045L$  and the reduction to the head,  $h_s$ , has been applied, the ballast tanks are to be filled and a note added to the loading booklet to this effect, see Ch 4,8.2.4(d).




Fig. 5.1.1 Pressure heads

## 1.6 Strengthening against bow flare slamming

1.6.1 The requirements of this Section apply to all ships except those defined in Pt 4, Ch 2 and Pt 4, Ch 8.

1.6.2 The side structure in the area forward of  $0,075L$  from the F.P. and above the summer load waterline is to be strengthened against bow flare impact pressure. The strengthening is to extend vertically to the uppermost deck level, including the forecabin deck, if fitted, but need not exceed the level of  $T + 1,65H_b$  above the base line, where  $H_b$  is the minimum bow height, in metres, as derived in Ch 3,6.1.

1.6.3 The flare angle,  $\alpha$ , is the angle between the vertical axis and the tangent of the outer shell measured normal to the shell in a vertical plane, at the point under consideration. The entry angle,  $\beta$ , is the angle between the longitudinal axis and the waterplane tangent measured on the outer shell, at the point under consideration. The flare angle may normally be derived in accordance with Fig. 5.1.2.

1.6.4 The equivalent bow flare slamming head,  $h_s$ , is to be taken as:

$$h_s = 0,8 (0,2 + 1,5 \tan \alpha) \left( 0,51V \sin \beta \cos \alpha + \frac{\pi}{\sqrt{L}} \delta \right)^2 \text{ m}$$

where

$V$  = as defined in 1.4.1

$\alpha$  = flare angle, in degrees, at the point under consideration

$\beta$  = entry angle, in degrees, at the point under consideration

$\delta = \left( \frac{\pi}{30} L e^{-0,0033L} - 0,5d \right)$  and is not to be taken less than zero

$e$  = base of natural logarithms 2,7183

$d$  = vertical distance, in metres, between the waterline at draught  $T$  and the point under consideration.



## Fore End Structure

## Part 3, Chapter 5

Section 1

**Table 5.1.1 Additional strengthening of bottom forward** (see continuation)

Item	Requirements	
(1) Longitudinally framed bottom shell plating (including keel), see Notes 1 and 2	$t = 0,003s f \sqrt{h_s k}$	
(2) Bottom longitudinals – other than flat bars	$\frac{d_w}{t_w} \leq 55 \sqrt{k}$ $\frac{d_w t_w}{100} \geq 0,00033 k h_s s c \left( S - \frac{s}{2000} \right) \text{ cm}^2$ $Z \geq 6,8 \times 10^{-6} h_s s k \left[ (17,5 l_s)^2 - (0,01s)^2 + d_w c \left( S - \frac{s}{2000} \right) \right] \text{ cm}^3$ $\frac{(A_1 \bar{\tau} + \alpha)}{\bar{\rho}} \times 10^{-1} \geq 1$ $A_w \geq 0,84 A_1$	
(3) Bottom longitudinals – flat bars	Will be specially considered	
(4) Primary structure in way of single bottoms	Transverse framing	Longitudinal framing
	<p>(a) Centre girder: Scantlings as required by item (1) in Table 5.5.1, except that in determining <math>Z</math> in way of a deep tank forward of <math>0,2L</math> from the F.P. the value of <math>h_s</math> is to be increased by the following percentages: where <math>T_{FB} \leq 0,03L_2</math>, 30 per cent where <math>T_{FB} \geq 0,04L_2</math>, 0 per cent The increase in <math>h_s</math> for intermediate values of <math>T_{FB}</math> is to be obtained by interpolation</p> <p>(b) Floors: Scantlings as required by item (2) in Table 5.5.1, except that in way of dry cargo spaces the minimum face area is to be increased by the following percentages: where <math>T_{FB} \leq 0,03L_2</math>, 50 per cent where <math>T_{FB} \geq 0,04L_2</math>, 0 per cent The increase of minimum face area for intermediate values of <math>T_{FB}</math> is to be obtained by interpolation</p> <p>(c) Side girders: Arrangement and scantlings as required by 5.2.2 and 5.2.3, with the addition of intermediate half-height girders or equivalent fore and aft stiffening</p>	<p>(a) Ships having one or more longitudinal bulkheads:</p> <p>(i) Centre girder Scantlings as required by item (4) in Table 5.5.1 and (iii)</p> <p>(ii) Bottom transverses Maximum spacing As for midships region Scantlings as required by Pt 4, Ch 9,9 or Pt 4, Ch 10,2</p> <p>(iii) For horizontally stiffened longitudinal bulkheads and girders the depth to thickness ratio of the panel attached to the bottom shell plate is not to exceed <math>55 \sqrt{k}</math></p> <p>(iv) Where <math>T_{FB} &lt; 0,025L_2</math> the scantlings and arrangements will receive individual consideration</p> <p>(b) Other ship arrangements will receive individual consideration</p>
(5) Primary structure in way of double bottoms, see Note 3	<p>(a) Plate floors: Maximum spacing, every frame Scantlings as required by Pt 4, Ch 1,8</p> <p>(b) Centre and side girders: Maximum spacing, <math>0,003s_F</math> m Scantlings as required by Pt 4, Ch 1,8</p> <p>(c) Intermediate half-height girders to be arranged midway between side girders: Scantlings as required for non watertight side girders by Pt 4, Ch 1,8</p>	<p>(a) Plate floors: Maximum spacing: <math>0,002s_F</math> m for <math>T_{FB} &lt; 0,04L_2</math> <math>0,003s_F</math> m for <math>T_{FB} \geq 0,04L_2</math> but not to exceed that required by item (2) in Table 5.5.2 Scantlings as required by Pt 4, Ch 1,8</p> <p>(b) Centre and side girders: Maximum spacing: <math>0,003s_L</math> m for <math>T_{FB} &lt; 0,04L_2</math> <math>0,004s_L</math> m for <math>T_{FB} &gt; 0,04L_2</math> but not to exceed that required by item (4) in Table 5.5.2 Scantlings as required by Pt 4, Ch 1,8</p>
(6) Primary structure in way of double bottoms supported by longitudinal bulkheads	—	The scantlings and arrangements will receive individual consideration on the basis of direct calculations using, if necessary, a suitably defined two-dimensional grillage model, see Ch 1,3

## Fore End Structure

## Part 3, Chapter 5

Section 1

**Table 5.1.1 Additional strengthening of bottom forward (conclusion)**

Symbols	
$L, T, s, k$ as defined in 1.4.1 $c = 1,0$ for $S \leq 2,5$ m $= (0,87 + 0,16S)$ $c_1$ for $S > 2,5$ m $c_1 = 1,0$ for $S \leq 1,0$ m $= (1,14 - 0,14S)$ for $1,0 \text{ m} < S \leq 4,0 \text{ m}$ $= \frac{2,32}{S}$ for $S > 4,0$ m $d_w$ = web depth, in mm, which for bulb flats may be taken as 0,9 times the section height $f = \left( 1,1 - \frac{s}{2500S} \right)$ but not greater than 1,0 $h_s$ = equivalent slamming pressure, in metres obtained from 1.5.8 $l_s = l_e$ , in metres, as defined in 1.4.1 where in way of a double bottom $= S$ , in metres, where in way of a single bottom $S$ = spacing of primary members, in metres $p = 9,81 h_s s c_1 \left[ S - \frac{s}{2000} \right] \times 10^{-3} \text{ kN}$ $= \left( h_s s c_1 \left[ S - \frac{s}{2000} \right] \times 10^{-3} \text{ tonne-f} \right)$	$s_F$ = spacing of transverse frames, in mm, for longitudinally framed side and bottom construction $s_F$ may be taken as $s_L$ $s_L$ = spacing of bottom longitudinals, in mm $t_w$ = web thickness, in mm $A_f$ = cross-sectional area of primary member web stiffener, in $\text{cm}^2$ $A_{fc}$ = effective area of primary member web stiffener in way of butted end connection to the longitudinal, in $\text{cm}^2$ $A_L$ = area of weld of lapped connection, in $\text{cm}^2$ , calculated as total length of weld, in cm x throat thickness, in cm $A_w$ = area of weld of lug and web connection to the longitudinal, in $\text{cm}^2$ , calculated as total length of weld in cm x throat thickness, in cm $A_1$ = effective total cross-sectional area of the lug and web connection to the longitudinal, in $\text{cm}^2$ $L_2 = L$ but need not be taken greater than 215 m $T_{FB}$ = draught, in metres, at the F.P., as defined in 1.5.1 $\alpha = A_f \bar{\sigma}$ for the web stiffeners $= A_{fc} \bar{\sigma}$ for a butted connection to the longitudinals $= A_L \bar{\tau}$ for a lapped connection $\bar{\sigma}$ = permissible direct stress, in $\text{N/mm}^2$ ( $\text{kgf/mm}^2$ ), given in Table 5.1.2 $\bar{\tau}$ = permissible shear stress, in $\text{N/mm}^2$ ( $\text{kgf/mm}^2$ ), given in Table 5.1.2
<b>NOTES</b> 1. If intermediate stiffening is fitted the thickness of the bottom shell plating may be 80 per cent of that required by (1) but is to be not less than the normal taper thickness. 2. For transverse framing the bottom shell plating is to be specially considered. 3. Particular care is to be taken to limit the size and number of openings in way of the ends of floors or girders or to fit suitable reinforcement where such openings are essential. 4. The welding requirements of Ch 10, and in cargo oil tanks of tankers, the requirements of Pt 4, Ch 9, 10.14 or Pt 4, Ch 10, 7.14, are also to be complied with.	

1.6.5 The thickness of the side shell is to be not less than:

$$t = 3,2s_C \sqrt{k h_s} C_R \times 10^{-2} \text{ mm}$$

where

$s_C$  = spacing of secondary stiffeners, in mm, measured along a chord between parallel adjacent members or equivalent supports, as shown in Fig. 5.1.3

$h_s$  = bow flare slamming head, in metres, as defined in 1.6.4

$C_R$  = panel ratio factor

$= \left( \frac{l}{s_C} \right)^{0,41}$  but is not to be taken less than 0,06 or greater than 0,1

$l$  = overall panel length, in metres, measured along a chord between the primary members.

1.6.6 The scantlings of secondary stiffeners are not to be less than:

(a) Section modulus of secondary stiffeners

$$Z = 3,6s_{CM} k h_s l_e^2 \times 10^{-3} \text{ cm}^3$$

(b) Web area of secondary stiffeners

$$A = 3,7s_{CM} k h_s (l_e - s_{CM}/2000) \times 10^{-4} \text{ cm}^2$$

where

$s_{CM}$  = mean spacing of secondary stiffeners, in mm, measured along a chord between parallel adjacent members or equivalent supports, as shown in Fig. 5.1.3

$h_s$  = bow flare slamming head, in metres, as defined in 1.6.4

Other symbols are as defined in 1.4.1.

1.6.7 The scantlings of primary members are not to be less than:

(a) Section modulus of primary members

$$Z = 2s_{CM} k h_s l_e^2 \text{ cm}^3$$

(b) Web area of primary members

$$A = 0,2s_{CM} k h_s l_e \text{ cm}^2$$

where

$s_{CM}$  = mean spacing of primary members, in metres, measured along a chord between parallel adjacent members or equivalent supports, as shown in Fig. 5.1.4

$h_s$  = bow flare slamming head, in metres, as defined in 1.6.4

Other symbols are as defined in 1.4.1.

## Fore End Structure

## Part 3, Chapter 5

Section 1

Table 5.1.2 Permissible stresses

Item		Direct stress, $\bar{\sigma}$ in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) see Note	Shear stress, $\bar{\tau}$ in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Primary member web stiffener on area $A_f$	(a) Flat bars, see Note	$\frac{10,3}{k} \left[ 33 - \frac{d}{t \sqrt{k}} \right]$  $\left( \frac{1,05}{k} \left[ 33 - \frac{d}{t \sqrt{k}} \right] \right)$	—  —
	(b) Bulb plates, see Note	$\frac{8,6}{k} \left[ 40 - \frac{d}{\left( \frac{100A_f}{d} - \frac{t}{6} \right) \sqrt{k}} \right]$  $\left( \frac{0,88}{k} \left[ 40 - \frac{d}{\left( \frac{100A_f}{d} - \frac{t}{6} \right) \sqrt{k}} \right] \right)$	—  —
	(c) Inverted angles	$\frac{220}{k} \left( \frac{22,4}{k} \right)$	—
Primary member web stiffener on area $A_{fc}$		$\frac{245}{k} \left( \frac{25}{k} \right)$	—
Primary member web stiffener lapped to secondary member on area $A_L$		—	$\frac{167}{k} \left( \frac{17}{k} \right)$
Lug or web connection on area $A_1$	Single	—	$\frac{124}{k} \left( \frac{12,6}{k} \right)$
	Double	—	$\frac{141}{k} \left( \frac{14,4}{k} \right)$
Symbols			
$A_f, A_L, A_1$ as defined in Table 5.1.1 $d$ = stiffener depth, in mm $k$ = as defined in 1.4.1 $t$ = stiffener web thickness, in mm			
NOTE $\bar{\sigma}$ to be taken not greater than $\frac{220}{k} \left( \frac{22,4}{k} \right)$			

1.6.8 For primary members with cut-outs for the passage of secondary stiffeners, and which may have web stiffeners connected to the secondary stiffener, buckling checks are to be carried out to ensure that the primary member web plating and web stiffener will not buckle under the design load. The buckling procedure to be followed is given in Table 5.1.3. Where the web stiffener is fitted with a bracket, the buckling capability of the web stiffener in way of the cut-out is to take account of the bracket. Where no web stiffener is fitted, the buckling capability of the primary member web plating is to be checked for the total load transmitted to the connection.

1.6.9 The structural scantlings required in areas strengthened against bow flare slamming are to be tapered from 0,075L aft of fore perpendicular to meet the normal requirements at 0,15L aft of the fore perpendicular.

1.6.10 Where the stiffener web is not perpendicular to the plating, tripping brackets may need to be fitted in order to obtain adequate lateral stability.





1.6.11 For stiffeners and primary structure, where the angle between the stiffener web and the plating is less than 70°, the effective section modulus and shear area are to take account of the non-perpendicularity.

1.6.12 The side structure scantlings required by this Section must in no case be taken less than those required by the remaining Sections of Chapter 5.

# Fore End Structure

## Part 3, Chapter 5

Section 1



## Fore End Structure

## Part 3, Chapter 5

Sections 1 &amp; 2

**Table 5.1.3 Buckling procedure for primary member web plating and web stiffener**

Steps	Members	
	Primary member web plating	Primary member web stiffener
Determination of the design compressive stress, $\sigma_A$ , N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	$\sigma_A = \frac{1000P_W}{A_W}$	$\sigma_A = \frac{1000P_S}{A_S}$
Determination of the elastic critical buckling stress, $\sigma_E$ , in compression, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	$\sigma_E = \frac{9,87E I_W}{l_W^2 A_W}$	$\sigma_E = \frac{9,87E I_S}{l_S^2 A_S}$
Determination of the corrected critical buckling stress, $\sigma_{CR}$ , in compression, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	$\sigma_{CR} = \sigma_o \left( 1 - \frac{\sigma_o}{4 \sigma_E} \right) \quad \text{where } \sigma_E > \frac{\sigma_o}{2}$ $\sigma_{CR} = \sigma_E \quad \text{where } \sigma_E \leq \frac{\sigma_o}{2}$	
Requirement	$\sigma_{CR} \geq \sigma_A$	
Symbols		
<p><math>b_W, b_S, l_W</math>, and <math>l_S</math> are dimensions, in mm, as shown in Fig. 5.1.5</p> <p><math>h_S</math> = equivalent bow flare slamming head, in metres, as defined in 1.6.4</p> <p><math>s_{CM}</math> = mean spacing of secondary stiffeners, in mm, as defined in 1.6.6</p> <p><math>t_W</math> = thickness of primary member web plating, in mm</p> <p><math>t_S</math> = thickness of primary member web stiffener, in mm</p> <p><math>A_W = b_W t_W</math> mm<sup>2</sup></p> <p><math>A_S = b_S t_S</math> mm<sup>2</sup></p> <p><math>E</math> = modulus of elasticity, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)</p> <p>= 206000 N/mm<sup>2</sup> (21000 kgf/mm<sup>2</sup>) for steel</p> <p><math>I_W = \frac{b_W t_W^3}{12}</math> mm<sup>4</sup></p> <p><math>I_S = \frac{b_S t_S^3}{12}</math> mm<sup>4</sup></p> <p><math>P</math> = total load transmitted to the connection</p> <p>= 10,06 <math>s_{CM} s_{CM} h_S \times 10^{-3}</math> kN</p> <p>(<math>P</math> = 1,025 <math>s_{CM} s_{CM} h_S \times 10^{-3}</math> tonne-f)</p> <p><math>P_W</math> = load transmitted through the primary member web plating, in kN (tonne-f)</p> <p>= <math>P - P_S</math>, or by direct calculations</p> <p><math>P_S</math> = load transmitted through the primary member web stiffener, in kN (tonne-f), to be determined from Ch 10,5.2.7(b), or by direct calculations</p> <p><math>s_{CM}</math> = mean spacing of primary members, in metres, as defined in 1.6.7</p> <p><math>\sigma_o</math> = specified minimum yield stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)</p>		

## Section 2

### Deck structure

#### 2.1 General

2.1.1 Where the upper deck is longitudinally framed outside the line of openings in the midship region, this system of framing is to be carried as far forward as possible. In the case of oil tankers (see 1.1.4), longitudinal framing is to extend to at least the forward end of the cargo tank section.

#### 2.2 Deck plating

2.2.1 The thickness of strength/weather deck plating is to comply with the requirements of Table 5.2.1.

2.2.2 The thickness of lower deck plating is to comply with the requirements of Table 5.2.2.

2.2.3 The taper thickness of the strength deck stringer plate is to be increased by 20 per cent at the end of a forecastle or bridge where the end bulkhead is situated aft of 0,25L from the F.P. No increase is required where the end bulkhead lies forward of 0,2L from the F.P. The increase at intermediate positions is to be determined by interpolation.

2.2.4 The deck plating thickness and supporting structure are to be suitably reinforced in way of the anchor windlass and other deck machinery, and in way of cranes, masts or derrick posts.

2.2.5 Where long, wide hatchways are arranged at lower decks, it may be necessary to increase the deck plating thickness to ensure effective support for side framing.

## Fore End Structure

## Part 3, Chapter 5

Section 2

**Table 5.2.1 Strength/weather deck plating forward (excluding forecastle deck)**

Symbols	Location	Thickness, in mm
$L, D, T, s, S, k, p$ as defined in 1.4.1 $C = \left( \frac{D + 2,3 - T}{\text{height of deck above load waterline at F.P.}} \right)$ but is to be taken not greater than 1,0 nor less than 0,9 $s_1 = s$ , but to be taken not less than $s_b$ $s_b$ = standard frame spacing as follows: (a) forward of 0,05L from the F.P.: $s_b = \left( 470 + \frac{L}{0,6} \right)$ mm or 600 mm, whichever is the lesser (b) between 0,05L and 0,2L from the F.P.: $s_b = \left( 470 + \frac{L}{0,6} \right)$ mm or 700 mm, whichever is the lesser $f = 1,1 - \frac{s}{2500S}$ but to be taken not greater than 1,0 $h_4$ = tank head, in metres, as defined in Ch 3,5	(1) Forward of 0,075L from the F.P.	$t = (6,5 + 0,02L) C \sqrt{\frac{ks_1}{s_b}}$
	(2) Between 0,075L and 0,2L from the F.P.	The greater of the following: (a) $t = (5,5 + 0,02L) C \sqrt{\frac{ks_1}{s_b}}$ (b) the taper thickness (see Notes 1, 2 and 3) (c) for oil tankers, the thickness is also to be in accordance with Pt 4, Ch 9,4.3.3
	(3) Aft of 0,2L from the F.P.	The taper thickness (see Notes 1, 2 and 3) or as (2) (c) whichever is the greater
	(4) Inside forecastle extending aft of 0,15L from the F.P.	As for a lower deck (see Note 4)
	(5) In way of crown of a tank	$t = 0,004s f \sqrt{\frac{p k h_4}{1,025}} + 3,5$ or as in (1) to (4) as applicable, whichever is the greater but not less than: 7,5 mm where $L \geq 90$ m, or 6,5 mm where $L < 90$ m
<b>NOTES</b> 1. The taper thickness is to be determined from Table 3.2.1 in Chapter 3. 2. For taper area requirements, see Table 3.2.1 in Chapter 3. 3. For thickness of upper deck plating in way of the cargo and fore peak tanks of oil tankers or ore carriers, see also Pt 4, Ch 9, Ch 10 or Ch 11, as applicable. 4. The exposed deck taper thickness is to extend into a forecastle or bridge for at least one-third of the breadth of the ship from the superstructure end bulkhead.		

**Table 5.2.2 Lower deck plating forward**

Symbols	Location	Thickness, in mm
$L, s, S, k, p$ as defined in 1.4.1 $b$ = breadth of increased plating, in mm $f = 1,1 - \frac{s}{2500S}$ but is to be taken not greater than 1,0 $h_4$ = tank head, in metres, as defined in Ch 3,5 $K_2$ = 2,5 mm at bottom of tank, or = 3,5 mm at crown of tank $s_1 = s$ , but is to be taken not less than $\left( 470 + \frac{L_1}{0,6} \right)$ mm $A_f$ = girder face area, in cm <sup>2</sup> $L_1 = L$ but need not be taken greater than 190 m	(1) Forward of 0,075L from the F.P.	$t = 0,01 s_1 \sqrt{k}$ but not less than 6,5 mm
	(2) Aft of 0,075L from the F.P., inside line of openings	$t = 0,01 s_1 \sqrt{k}$ but not less than 6,5 mm
	(3) Aft of 0,075L from the F.P., outside line of openings	As determined by a taper line from the midship thickness to the end thickness given by (1)
	(4) In way of crown or bottom of tank	$t = 0,004 f s \sqrt{\frac{p k h_4}{1,025}} + K_2$ or as in (1), (2) or (3) as applicable, whichever is the greater but not less than: 7,5 mm where $L \geq 90$ m, or 6,5 mm where $L < 90$ m
	(5) Plating forming the upper flange of underdeck girders	Clear of cargo hatches $t = \sqrt{\frac{A_f}{1,8k}}$ In way of hatch side girders $t = 1,1 \sqrt{\frac{A_f}{1,8k}}$ Minimum breadth $b = 760$ mm
<b>NOTES</b> 1. Where the deck loading exceeds 43,2 kN/m <sup>2</sup> (4,4 tonne-f/m <sup>2</sup> ), the thickness of plating will be specially considered. This is equivalent to a 'tween deck height of 6,1 m in association with the standard stowage rate of 1,39 m <sup>3</sup> /tonne. 2. For minimum thickness of deck plating in oil tankers, see Pt 4, Ch 9,10.2.		

# Fore End Structure

# Part 3, Chapter 5

Section 2

## 2.3 Deck stiffening

2.3.1 The scantlings of strength/weather deck longitudinals are to comply with the requirements of Table 5.2.3.

2.3.2 The scantlings of cargo and accommodation deck longitudinals are to comply with the requirements given in Table 1.4.4 in Pt 4, Ch 1.

2.3.3 End connections of longitudinals to bulkheads are to provide adequate fixity, lateral support and, so far as practicable, direct continuity of longitudinal strength.

2.3.4 The scantlings of weather deck beams are to comply with the requirements of Table 5.2.4.

2.3.5 The scantlings of lower deck beams are to comply with the requirements of Table 1.4.5 in Pt 4, Ch 1.

2.3.6 End connections of beams are to be in accordance with the requirements of Ch 10,3.

**Table 5.2.3 Strength/weather deck longitudinals forward**

Location	Modulus, cm <sup>3</sup>	Inertia, cm <sup>4</sup>
(1) Forward of 0,075L from the F.P.	The greater of the following: (a) $Z = s k (635h_1 + 0,0078 (l_e L_1)^2) \times 10^{-4}$ (b) $Z = 0,0127s k h_1 l_e^2$	—
(2) At 0,075L from the F.P., for end modulus for taper	The greater of the following: (a) $Z_e = s k (485h_o + 0,0062 (l_{e1} L_1)^2) \times 10^{-4}$ (b) $Z_e = 0,009s k h_o l_{e1}^2$	—
(3) Aft of 0,075L from the F.P., outside line of openings	As given by (4) or as determined from Table 3.2.1 in Chapter 3 whichever is the greater, see Note 1	—
(4) At 0,075L and between 0,075L and 0,12L from the F.P.	The greater of the following: (a) $Z = s k (570h_1 + 0,0072 (l_e L_1)^2) \times 10^{-4}$ (b) $Z = 0,0127s k h_1 l_e^2$	—
(5) Aft of 0,12L from the F.P., inside line of main cargo hatchways openings	The greater of the following: (a) $Z = s k (400h_1 + 0,005 (l_e L_1)^2) \times 10^{-4}$ (b) $Z = 0,007s k h_1 l_e^2$	—
(6) In way of the crown of a tank	As (1) to (5), as applicable, or $Z = \frac{0,0113p s k h_4 l_e^2}{b}$ whichever is the greater	$I = \frac{2,3}{k} l_e Z$
Symbols		
<div> <div> <math>L, s, k_L, k, p</math> as defined in 1.4.1  <math>b = 1,4</math> for rolled or built sections  <math>= 1,6</math> for flat bars  <math>d_w</math> = web depth of longitudinal, in mm  <math>h_o = 1,2</math> m for dry cargo ships  <math>= \frac{L_1}{56}</math> m for oil tankers (see 1.1.4)  <math>h_1</math> = weather head, in metres, as defined in Ch 3,5 for dry cargo ships  <math>= \frac{L_1}{70}</math> m for oil tankers (see 1.1.4) </div> <div> <math>h_4</math> = tank head, in metres, as defined in Ch 3,5  <math>l_e</math> as defined in 1.4.1, but is to be taken not less than 1,5 m  <math>l_{e1}</math> is to be taken as the maximum span in metres in the midship cargo tank region for oil tankers (see 1.1.4) and equal to <math>l_e</math> for dry cargo ships  <math>L_1 = L</math> but need not be taken greater than 190 m </div> </div>		
<p>NOTES</p> <div> <div> 1. For area taper requirements, see also Table 3.2.1 in Chapter 3.  2. Where weather decks are intended to carry deck cargo and the loading is in excess of 8,5 kN/m<sup>2</sup> (0,865 tonne-f/m<sup>2</sup>), the scantlings of longitudinals may be required to be increased to comply with the requirements for location (1) in Table 1.4.4 in Pt 4, Ch 1 using the equivalent design head, for specified cargo loadings, for weather decks given in Table 3.5.1 in Chapter 3.  3. For the scantlings of deck longitudinals forward in way of the cargo tanks of oil tankers (see 1.1.4) or ore carriers, see also Pt 4,Ch9,Ch 10 or Ch 11, as applicable. </div> <div> 4. The thickness of flat bar longitudinals situated outside the line of openings is to be not less than the following:  (a) <math>t = \frac{d_w}{18\sqrt{k_L}}</math> mm  where longitudinal continuous through bulkhead  (b) <math>t = \frac{d_w}{15\sqrt{k_L}}</math> mm  where longitudinal cut at bulkhead  5. The web depth of longitudinal, <math>d_w</math>, is to be not less than 60 mm. </div> </div>		

## Fore End Structure

## Part 3, Chapter 5

Section 2

**Table 5.2.4 Weather deck beams forward**

Location	Modulus, cm <sup>3</sup>	Inertia, cm <sup>4</sup>
(1) Forward of 0,075L from the F.P.	The lesser of the following: (a) $Z = k (800K_1 T D + 5,4B_1 s h_1 l_e^2) \times 10^{-4}$ (b) $Z = 10,8B_1 s k h_1 l_e^2 \times 10^{-4}$	—
(2) Between 0,075L and 0,12L from the F.P.	The lesser of the following: (a) $Z = k (800K_1 T D + K_3 B_1 s h_1 l_e^2) \times 10^{-4}$ (b) $Z = 2K_3 B_1 s k h_1 l_e^2 \times 10^{-4}$	—
(3) Aft of 0,12L from the F.P.	As required for location (1) of Table 1.4.5 in Pt 4, Ch 1	—
(4) In way of the crown of a tank	As (1), (2) or (3), as applicable, or $Z = \frac{0,0113p s k h_4 l_e^2}{b}$ whichever is the greater	$I = \frac{2,3}{k} l_e Z$
Symbols		
<p><math>B, D, T, s, p, k</math> as defined in 1.4.1  <math>b = 1,4</math> for rolled or built sections  <math>= 1,6</math> for flat bars  <math>h_1 =</math> weather head, in metres, as defined in Ch 3,5  <math>h_4 =</math> tank head, in metres, as defined in Ch 3,5  <math>l_e</math> as defined in 1.4.1, but is to be taken not less than 1,83 m</p> <p><math>K_1 =</math> a factor dependent on the number of decks (including a bridge superstructure) at the position of the beam under consideration as follows:  1 deck 20,0  2 decks 13,3  3 decks 10,5  4 decks or more 9,3  For a forecastle deck, <math>K_1</math> is to be taken as 13,3  <math>K_3 =</math> a factor dependent on the location of the beam as follows:  Span adjacent to ship's side 3,6  Elsewhere 3,3  <math>B_1 = B</math>, but need not be taken greater than 21,5 m</p>		
<p>NOTES</p> <p>1. Beams at the upper deck inside superstructures are to have scantlings determined as for a lower deck, see Table 1.4.5 in Pt 4, Ch 1.</p> <p>2. Where weather decks are intended to carry deck cargo and the loading is in excess of 8,5 kN/m<sup>2</sup> (0,865 tonne-f/m<sup>2</sup>), the scantlings of beams are also to comply with the requirements for location (2) in Table 1.4.5 of Pt 4, Ch 1 using the equivalent design head, for specified cargo loadings, for weather decks given in Table 3.5.1 in Chapter 3.</p> <p>3. The web depth of beams, <math>d_w</math>, is to be not less than 60 mm.</p> <p>4. The scantlings of deck beams forward in way of the cargo tanks of oil tankers or ore carriers will be specially considered, see Pt 4, Ch 9, 1.3.10.</p>		

**2.4 Deck supporting structure**

2.4.1 The arrangements and scantlings of supporting structure are generally to be in accordance with the requirements given in Pt 4, Ch 1,4 using the heads given in Ch 3,5 for the particular region concerned, except as required by 2.4.2 to 2.4.4.

2.4.2 The spacings of girders and transverses are generally not to exceed the values given in Table 5.2.5.

2.4.3 Primary structure in the topside tanks of bulk carriers is to comply with the requirements of Pt 4, Ch 7,7.

2.4.4 Primary structure in the cargo tanks of oil tankers and ore carriers is to be determined from Pt 4, Ch 9, Ch 10 or Ch 11, as applicable.

**2.5 Deck openings**

2.5.1 In dry cargo ships the requirements for deck openings given in Pt 4, Ch 1,4 are generally applicable throughout the forward region, except that forward of 0,25L from the F.P.:

- The radii or dimensions of the corners of main cargo hatchway openings on the strength deck are to be in accordance with the requirements of Pt 4, Ch 1,4.5. The thickness of the insert plates, where required, is not to be less than 20 per cent greater than the adjacent deck thickness outside the line of openings, with a minimum increase of 3 mm.
- Insert plates will be required at lower decks in way of any rapid change in hull form to compensate for loss of deck cross-sectional area. Otherwise, insert plates will not normally be required.
- Compensation and edge reinforcement for openings outside the line of main hatchways will be considered, bearing in mind their position, the deck arrangements and the type of ship concerned.



# Fore End Structure

## Part 3, Chapter 5

Sections 2 &amp; 3

**Table 5.2.5 Spacing of girders and transverses under strength/weather decks forward**

Location	Maximum spacing	
	Girders in association with transverse framing system	Transverses in association with longitudinal framing system
(1) Forward of the collision bulkhead	3,7 m	2,5 m where $L \leq 100$ m 3,5 m where $L \geq 300$ m Intermediate values by interpolation
(2) Between the collision bulkhead and 0,075L from the F.P.	3,7 m	
(3) In way of a deep tank, forward of 0,2L from the F.P.	—	3,0 m where $L \leq 100$ m 4,2 m where $L \geq 300$ m Intermediate values by interpolation
(4) Elsewhere in way of dry cargo spaces or deep tanks, see Note 1	—	3,8 m where $L \leq 100$ m (3,2 + 0,006L) m where $L > 100$ m
NOTES 1. For the maximum spacing of transverses in the cargo tanks of oil tankers or ore carriers, see Pt 4, Ch 9,9. 2. For the maximum spacing of transverses in dredgers, see Pt 4, Ch 12,5.		

2.5.2 For deck openings in way of the cargo tanks in oil tankers and ore carriers, see *also* Pt 4, Ch 9, Ch 10 or Ch 11, as applicable. For main cargo hatchway openings on bulk carriers and container ships, see *also* Pt 4, Ch 7 and Ch 8, as applicable.

3.3.2 The scantlings of plate stems are to be determined from Table 5.3.1. Plate stems are to be supported by horizontal diaphragms positioned in line with the side stringers or perforated flats with intermediate breasthook diaphragms. Diaphragms are to be spaced not more than 1,5 m apart, measured along the stem. Where the stem plate radius is large, a centreline stiffener or web will be required.

### Section 3

## Shell envelope plating

### 3.1 General

3.1.1 Where the shell is longitudinally framed in the midship region, this system of framing is to be carried as far forward as practicable. In the case of oil tankers (see 1.1.4), longitudinal framing is to extend at least to the forward end of the cargo tanks.

### 3.2 Keel

3.2.1 The scantlings of bar keels at the fore end are to be the same as in the midship region as required by Pt 4, Ch 1,5.

3.2.2 The thickness and width of plate keels in the forward region are to be the same as required in the midship region for the particular type of ship concerned, see Part 4.

### 3.3 Stem

3.3.1 Bar stems may be either steel castings or steel forgings complying with the requirements of Chapter 3 of the Rules for Materials (Part 2) for rolled steel flat bars or Chapter 5 of the Rules for Materials (Part 2) for solid round bars. The scantlings of bar stems are to comply with Table 5.3.1.

### 3.4 Bottom shell and bilge

3.4.1 The thickness of bottom shell and bilge plating in the forward region for ships not requiring additional strengthening of bottom is to comply with Table 5.3.1.

3.4.2 For thickness of bottom shell and keel when additional bottom strengthening is required, see 1.5.

3.4.3 Where longitudinals are omitted in way of radiused bilge plating amidships, the plating thickness forward will be considered in relation to the support derived from the hull form and internal stiffening arrangements.

### 3.5 Side shell and sheerstrake

3.5.1 The thickness of side shell and sheerstrake plating in the forward region is to be not less than the values given in Table 5.3.1, but may be required to be increased locally on account of high shear forces, in accordance with Ch 4,6.5.

3.5.2 For transversely framed side shells where panting stringers are omitted, see 4.4, the side shell plating in the region concerned is to be increased in thickness by the percentages given below:

(a) 15 per cent, where  $L \leq 150$  m

(b) 5 per cent, where  $L \geq 215$  m

For intermediate values of  $L$ , the percentage increase is to be obtained by interpolation.

## Fore End Structure

## Part 3, Chapter 5

Section 3

Table 5.3.1 Shell plating forward

Location	Thickness, in mm	NOTES
(1) Bottom shell and bilge, <i>see also</i> 1.5 and Note 5: (a) Forward of 0,075 <i>L</i> from the F.P.  (b) Between 0,075 <i>L</i> and 0,25 <i>L</i> from the F.P., <i>see</i> Note 7 (c) Aft of 0,25 <i>L</i> from the F.P., <i>see</i> Note 7	$t = (6,5 + 0,033L)\sqrt{\frac{k s_1}{s_b}} \quad (\text{see Note 1})$ As (1)(a) or the taper thickness, whichever is the greater The taper thickness ( <i>see</i> Note 2)	1. For ships where $L \leq 70$ m this thickness may be reduced by 1 mm, but it is to be not less than 6 mm. 2. The taper thickness is to be determined from Table 3.2.1 in Chapter 3. 3. For thickness of shell plating in way of the cargo and fore peak tanks of oil tankers or ore carriers, <i>see also</i> Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate. 4. In offshore supply ships the thickness of side shell is to be not less than 9 mm. 5. For trawlers and fishing vessels, <i>see</i> Pt 4, Ch 6,5. 6. For fast cargo ships, <i>see</i> Pt 4, Ch 1,3. 7. For oil tankers the thickness is also to be in accordance with Pt 4, Ch 9,4.3.3.
(2) Side shell, <i>see</i> Notes 4 and 5: (a) Forward of 0,075 <i>L</i> from the F.P.  (b) Between 0,075 <i>L</i> and 0,2 <i>L</i> from the F.P., <i>see also</i> 3.5.2 (c) Aft of 0,2 <i>L</i> from the F.P.	$t = (6,5 + 0,033L)\sqrt{\frac{k s_1}{s_b}} \quad (\text{see Note 1})$ As (2)(a) or the taper thickness, whichever is the greater The taper thickness ( <i>see</i> Note 2)	
(3) Sheerstrake, <i>see</i> Notes 4 and 5: (a) Forward of 0,075 <i>L</i> from the F.P.: where $\frac{T}{D} > 0,7$  where $\frac{T}{D} \leq 0,7$  (b) Between 0,075 <i>L</i> and 0,2 <i>L</i> from the F.P., <i>see</i> Note 7 (c) Aft of 0,2 <i>L</i> from the F.P., <i>see</i> Note 7	As (2)(a) for side shell  As (4) for a forecastle  As (3)(a) or as determined from Table 3.2.1 in Chapter 3 The taper thickness ( <i>see</i> Note 2)	
(4) Forecastle, <i>see</i> Notes 4 and 5	$t = (7,0 + 0,02L)\sqrt{\frac{k s_1}{s_b}}$	
(5) Stem, <i>see</i> Notes 4 and 5: (a) Bar stem: below load waterline  at stem head  (b) Plate stem: below load waterline  at stem head	$A_1 = (1,6L - 32) \text{ cm}^2 \text{ or } L \text{ cm}^2 \text{ whichever is the greater}$ $A_2 = 0,75 A_1 \text{ cm}^2$ $t = (5,0 + 0,083L_2)\sqrt{k} \text{ mm}$ $t = \text{as (2)(a) for side shell}$	
Symbols		
<i>L, B, D, T, s, k</i> as defined in 1.4.1 <i>s</i> <sub>1</sub> = <i>s</i> , but to be taken as not less than <i>s</i> <sub>b</sub> <i>s</i> <sub>b</sub> = standard frame spacing, in mm, as follows:		
Region	Bottom shell <i>s</i> <sub>b</sub>	Side shell <i>s</i> <sub>b</sub>
Forward of 0,05 <i>L</i> from the F.P.	$\left(470 + \frac{L}{0,6}\right) \text{ or } 600^*$	$\left(470 + \frac{L}{0,6}\right) \text{ or } 600^*$
Between 0,05 <i>L</i> and 0,2 <i>L</i> from the F.P.	$\left(470 + \frac{L}{0,6}\right) \text{ or } 700^*$	$\left(470 + \frac{L}{0,6}\right) \text{ or } 700^*$
Between 0,2 <i>L</i> and 0,25 <i>L</i> from the F.P.	$\left(510 + \frac{L_2}{0,6}\right)$	*whichever is the lesser
<i>A</i> <sub>1</sub> = cross-sectional area of bar stem below load waterline, in cm <sup>2</sup> <i>A</i> <sub>2</sub> = cross-sectional area of bar stem at stem head, in cm <sup>2</sup> <i>L</i> <sub>2</sub> = <i>L</i> , but need not be taken greater than 215 m		

# Fore End Structure

# Part 3, Chapter 5

Sections 3 &amp; 4

3.5.3 The side shell plating of increased thickness required by 3.5.2 is to be continued forward past the fore peak or collision bulkhead. In addition, horizontal brackets in line with the fore peak stringers are to be fitted at the aft side of the bulkhead where practicable. The brackets are to be the same thickness as the side shell and are to extend from the bulkhead to the adjacent shell frame and be connected thereto. Transversely the toes of the brackets are to extend past the outboard stiffener of the bulkhead to clear any cut out in the bulkhead stringer.

3.5.4 The sheerstrake taper thickness is to be increased by 20 per cent at the ends of a bridge superstructure extending out to the ship's side irrespective of position. Similar strengthening is to be fitted in way of the end of a forecastle if this occurs at a position aft of  $0,25L$  from the F.P. No increase is required if the forecastle end bulkhead lies forward of  $0,2L$  from the F.P. The increase at intermediate positions of end bulkhead is to be obtained by interpolation.

3.5.5 The shell plating may be required to be increased in thickness locally in way of hawse pipes, see Ch 13,7.8.

3.5.6 The shell plating is to be increased in thickness locally in way of a bulbous bow, see 6.5.6.

## 3.6 Shell openings

3.6.1 In general, compensation will not be required for holes in the sheerstrake which are clear of the gunwale, or for any deck openings situated outside the line of main hatchways and whose depth does not exceed 20 per cent of the depth of the sheerstrake or 380 mm, whichever is the lesser. Openings are not to be cut in a rounded gunwale. Cargo door openings are to have well rounded corners, and the proposed compensation for the door openings will be individually considered.

3.6.2 Sea inlet and other openings are to have well rounded corners. The thickness of sea inlet box plating is generally to be the same as the adjacent shell. It is however, to be not less than 12,5 mm, and need not exceed 25 mm.

## ■ Section 4 Shell envelope framing

### 4.1 General

4.1.1 Requirements are given in this Section for both longitudinal and transverse framing systems. Where longitudinal framing is adopted in the midship region it is to be carried as far forward as practicable. In the case of oil tankers (see 1.1.4), longitudinal framing is to be continued at least to the fore end of the cargo tanks.

4.1.2 End connections of longitudinals to bulkheads are to provide adequate fixity, lateral support and, so far as practicable, direct continuity of longitudinal strength, see also Ch 10,3. Where  $L$  exceeds 215 m, the bottom longitudinals are to be continuous in way of both watertight and non-watertight floors, but alternative arrangements will be considered. Higher tensile steel longitudinals within 10 per cent of the ship's depth at the bottom and deck are to be continuous irrespective of the ship length.

4.1.3 Stiffeners and brackets on side transverses, where fitted on one side and connected to higher tensile steel longitudinals between the base line and  $0,8D$  above the base line, are to have their heels well radiused to reduce stress concentrations. Where a symmetrical arrangement is fitted, i.e. bracket or stiffening on both sides, and it is connected to higher tensile steel longitudinals, the toes of the stiffeners or brackets are to be well radiused. Alternative arrangements will be considered if supported by appropriate direct calculations.

4.1.4 Where higher tensile steel side longitudinals pass through transverse bulkheads in the cargo area, well radiused brackets of the same material are to be fitted on both the fore and aft side of the connection between the upper turn of bilge and  $0,8D$  above the base line. Particular attention is to be given to ensuring the alignment of these brackets. Alternative arrangements will be considered if supported by appropriate direct calculations.

4.1.5 For ships intended to load or unload while aground, see Ch 9,12.

## 4.2 Shell longitudinals

4.2.1 The scantlings of bottom and side shell longitudinals in the forward region are to comply with the requirements given in Table 5.4.1. For the scantlings of bottom shell longitudinals where additional bottom strengthening is required, see 1.5.

4.2.2 End connections of longitudinals to bulkheads are to provide adequate fixity, lateral support and so far as practicable, direct continuity of longitudinal strength, see also Ch 10,3.

## 4.3 Shell framing

4.3.1 The scantlings of side frames in the forward region are to comply with the requirements given in Table 5.4.2.

4.3.2 The scantlings of main frames are normally to be based on Rule standard brackets at top and bottom, whilst the scantlings of 'tween deck frames are normally to be based on a Rule standard bracket at the top only.

## Fore End Structure

## Part 3, Chapter 5

Section 4

Table 5.4.1 Shell framing (longitudinal) forward

Location	Modulus, in cm <sup>3</sup>
(1) Side longitudinals in forecastle	$Z = 0,0075s k I_e^2 (0,6 + 0,167D_1)$
(2) Side longitudinals in way of dry spaces including double skin construction: (a) Forward of the collision bulkhead (b) Between the collision bulkhead and 0,2L from the F.P. (c) Aft of 0,2L from the FP	$Z = 0,007s k h_{T1} I_e^2 F_s$ but not to be less than as required by (1)  As (a) above or as required in the midship region for the particular type of ship concerned, whichever is the greater. However, not to be taken less than as required by (1).  As required in the midship region for the particular type of ship concerned.
(3) Side longitudinals in way of double skin tanks or deep tanks	The greater of the following: (a) Z as from (2) (b) As required by Pt 4, Ch 1,9 for deep tanks.
(4) Bottom and bilge longitudinals	The greater of the following: (a) As required in the midship region for the particular type of ship concerned. (b) As required by 1.5, strengthening of bottom forward, where applicable.
Symbols	
<p><math>L, D, T, s, k</math>, as defined in 1.4.1  <math>I_e</math> = as defined in 1.4.1, but is to be taken not less than 1,5 m  <math>L_1</math> = <math>L</math> but need not be taken greater than 190 m  <math>F_s</math> is a fatigue factor to be taken as follows:  (a) For built sections and rolled angle bars:  <math display="block">F_s = \frac{1,1}{k} \left[ 1 - \frac{2b_{f1}}{b_f} (1 - k) \right]</math> at 0,6<math>D_1</math> above the base line  = 1,0 at <math>D_1</math> and above, and <math>F_{sb}</math> at the base line  intermediate values by linear interpolation  <math>F_{sb}</math> is a fatigue factor for bottom longitudinals  = 0,5 (1 + <math>F_s</math> at 0,6<math>D_1</math>)  (b) For flat bars and bulb plates <math>\frac{b_{f1}}{b_f}</math> may be taken as 0,5  where  <math>b_{f1}</math> = the minimum distance, in mm, from the edge of the face plate of the side longitudinal under consideration to the centre of the web plate, see Fig. 9.5.1 in Pt 4, Ch 9  <math>b_f</math> = the width of the face plate, in mm, of the side longitudinal under consideration, see Fig. 9.5.1 in Pt 4, Ch 9  <math>T_1</math> = <math>T</math> but not to be taken less than 0,65<math>D_1</math></p>	<p><math>D_1</math> = <math>T + H_b</math> metres, where <math>H_b</math> is the minimum bow height, in metres, obtained from Ch 3,6.1  <math display="block">h_{T1} = f_w C_w \left( 1 - \frac{h_6}{D_1 - T_1} \right) F_\lambda</math>, in metres, for longitudinals above the waterline at draught <math>T_1</math> where  <math>f_w \left( 1 - \frac{h_6}{D_1 - T_1} \right)</math> is not to be taken less than 0,7  <math display="block">= \left[ h_6 + f_w C_w \left( 1 - \frac{h_6}{2T_1} \right) \right] F_\lambda</math>, in metres, for longitudinals below the waterline at draught <math>T_1</math>  where  <math>f_w</math> = 1,0 at 0,2L from F.P. and 1,71 at, and forward of, 0,15L from F.P.  Intermediate positions by interpolation  <math>h_6</math> = vertical distance, in metres, from the waterline at draught <math>T_1</math>, to the longitudinal under consideration  <math>F_\lambda</math> = 1,0 for <math>L \leq 200</math> m  = <math>[1,0 + 0,0023 (L - 200)]</math> for <math>L &gt; 200</math> m  <math>C_w</math> = a wave head, in metres = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math>  where  e = base of natural logarithms 2,7183</p>
<p>NOTE  Where struts are fitted midway between transverses in double skin construction, the modulus of the side longitudinals may be reduced by 50k per cent from that obtained for locations (2) and (3) as applicable.</p>	

4.3.3 End connections of transverse main and 'tween deck frames are to be in accordance with Ch 10,3. For bulk carriers the end connections of main frames in cargo holds are to be in accordance with Pt 4, Ch 7,6.2.5 to 6.2.12. Where brackets are omitted at the foot of main frames in cargo spaces, small easing brackets are to be fitted forward of 0,15L from the F.P.

#### 4.4 Panting stringers in way of transverse framing

4.4.1 In lower hold or deep tank spaces panting stringers are generally to be fitted in line with each stringer or flat in the fore peak space and extending back to 0,15L from the F.P. These stringers may be omitted if the shell plating is increased in thickness as required by 3.5.2. Where the span of the main frames exceeds 9 m, panting stringers are to be fitted irrespective of whether the shell plating is increased in thickness or not. These stringers are to be arranged in line with alternate stringers or flats in the fore peak and are to extend back to 0,2L from the F.P.

## Fore End Structure

## Part 3, Chapter 5

Section 4

Table 5.4.2 Shell framing (transverse) forward

Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
(1) Frames in fore peak spaces and lower 'tween decks over, see Note 1	$Z = K_1 s k T D_2 S_1 \times 10^{-3}$	$I = \frac{3,5}{k} S_1 Z$
(2) Frames in upper 'tween decks and forecastles forward of the collision bulkhead, see Notes 1, 2 and 8	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1 s k D_1 \times 10^{-3}$	$I = \frac{3,5}{k} H Z$
(3) Main and 'tween deck frames (including forecastle) between the collision bulkhead and 0,15L from the F.P., see Notes 1 to 4 and 8	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1 s k D_1 \times 10^{-3}$	$I = \frac{3,5}{k} H Z$
(4) Main and 'tween deck frames between 0,15L and 0,2L from the F.P. in dry cargo spaces, see Notes 1 to 4 and 8	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1 s k D_1 \times 10^{-3}$	$I = \frac{3,2}{k} H Z$
(5) Panting stringers, see Note 5	Web depth, $d_w$ , same depth as frames Web thickness, $t = 6 + 0,025L_2$ mm Face area, $A = kS_2 (H + 1)$ cm <sup>2</sup>	
(6) Main and 'tween deck frames elsewhere, see Notes 1 to 4	As required in the midship region for the particular type of ship concerned	
Symbols		
<div><div><div><div><math>L, D, T, s, k</math> as defined in 1.4.1</div><div><math>L_2 = L</math> but need not be taken greater than 215 m</div><div><math>D_1 = T + H_b</math>, in metres, where <math>H_b</math> is defined in Ch 1,6.1.11</div><div><math>D_2 = D_1</math>, but is to be taken not greater than 16 m, nor less than 6,0 m</div><div><math>H = H_{MF}</math> or <math>H_{TF}</math> as applicable, see Note 7</div><div><math>H_{MF}</math> = vertical framing depth, in metres, of main frames as shown in Fig. 5.4.1 but is to be taken not less than 3,5 m, see Note 6</div><div><math>H_{TF}</math> = vertical framing depth, in metres, of 'tween deck frames as shown in Fig. 5.4.1 but is to be taken not less than 2,5 m</div><div><math>K_1 = 2,3</math> for peak tanks = 1,87 for 'tween decks over peak tanks</div><div><math>S_1</math> = vertical spacing of peak stringers or height of lower 'tween deck above the peak, in metres, as applicable</div><div><math>S_2</math> = vertical spacing of panting stringers, in metres</div><div><math>C</math> = end connection factor = 3,4 where two Rule standard brackets fitted = 3,4 (1,8 – 0,8(<math>l_a/l</math>)) where one Rule standard bracket and one reduced bracket is fitted = 3,4 (2,15 – 1,15 (<math>l_{amean}/l</math>)) where two reduced brackets are fitted = 6,1 where one Rule standard bracket is fitted = 6,1 (1,2 – 0,2 (<math>l_a/l</math>)) where one reduced bracket is fitted = 7,3 where no brackets are fitted. The requirements for frames where brackets larger than Rule standard are fitted will be specially considered</div><div><math>l</math> = length, in mm, as derived from Pt 3, Ch 10,3.4.1</div></div><div><div><math>l_a</math> = equivalent arm length, in mm, as derived from Pt 3, Ch 10,3.4.1</div><div><math>l_{amean}</math> = mean equivalent arm length, in mm, for both brackets</div><div><math>T_1</math> = <math>T</math> but not to be taken less than 0,65<math>D_1</math></div><div><math>h_{T1}</math> = head, in metres, at mid-length of <math>H</math></div><div><math>= f_w C_w \left(1 - \frac{h_6}{D_1 - T_1}\right) F_\lambda</math>, in metres for frames where the mid-length of frame is above the waterline at draught <math>T_1</math></div><div>where <math>f_w \left(1 - \frac{h_6}{D_1 - T_1}\right)</math> is not to be taken less than 0,7</div><div><math>= \left[h_6 + f_w C_w \left(1 - \frac{h_6}{2T_1}\right)\right] F_\lambda</math>, in metres for frames where the mid-length of frame is below the waterline at draught <math>T_1</math></div><div>where</div><div><math>f_w = 1,0</math> at 0,2L from F.P. and 1,71 at, and forward of, 0,15L from F.P. Intermediate positions by interpolation</div><div><math>h_6</math> = vertical distance, in metres, from the waterline at draught <math>T_1</math> to the mid-length of <math>H</math></div><div><math>F_\lambda = 1,0</math> for <math>L \leq 200</math> m = [1,0 + 0,0023 (<math>L - 200</math>)] for <math>L &gt; 200</math> m</div><div><math>C_w</math> = a wave head, in metres = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math> where <math>e</math> = base of natural logarithms 2,7183</div></div></div></div>		
NOTES		
<div><div>1. For framing in the fore end of fishing vessels, see Pt 4, Ch 6,6.</div><div>2. In offshore supply ships the moduli of main and 'tween deck frames are to be 25 per cent greater than given in (2), (3) and (4).</div><div>3. In way of the cargo tanks of oil tankers or ore carriers, the scantlings of frames are also to comply with the requirements for frames in the midship region of such ships, see Pt 4, Ch 9, Ch 10 or Ch 11, as applicable.</div><div>4. In bulk carriers the scantlings of frames are also to comply with the requirements of Pt 4, Ch 7,6 in which the requirements of Table 7.6.1 location (1) are to be multiplied by the following factor: Between 0,15L and 0,2L from the F.P., <math>C_1 = (0,018D_2 + 0,82)</math>, but not to be taken less than 1,0. Between collision bulkhead and 0,15L from the F.P., <math>C_1 = (0,021D_2 + 0,96)</math>.</div><div>5. Panting stringers are not required in tugs less than 46 m in length, see Pt 4, Ch 3,4.</div><div>6. Where the frames are supported by fully effective horizontal stringers, these may be considered as decks for the purpose of determining <math>H_{MF}</math>.</div><div>7. Where frames are inclined at more than 15° to the vertical, <math>H_{MF}</math> or <math>H_{TF}</math> is to be measured along a chord between span points of the frame.</div><div>8. Except for main frames the modulus for these members need not exceed that derived from (1) using <math>H_{TF}</math> in place of <math>S_1</math>.</div></div>		




Fig. 5.4.1 Framing depths for transverse frames

4.4.2 In 'tween deck spaces in the region forward of 0,15L from the F.P., where the unsupported length of frame exceeds 2,6 m in a lower 'tween deck or 3,0 m in an upper 'tween deck, intermediate panting stringers are generally to be fitted. These stringers may be omitted if the shell plating is increased in thickness as required by 3.5.2.

4.4.3 The scantlings of panting stringers are to be determined from Table 5.4.2.

4.5 Primary structure at sides

4.5.1 For the arrangement of primary structure in peak tanks and deep tanks forward, see also Sections 6 and 7.

4.5.2 The spacing of side transverses and web frames is generally not to exceed the values given in Table 5.4.3.

4.5.3 The scantlings of side transverses supporting longitudinal framing and stringers and webs supporting transverse framing in the forward region are to be determined from Table 5.4.4.

4.5.4 The web thickness, stiffening arrangements and end connections of primary supporting members are to be in accordance with the requirements of Ch 10,4.

Table 5.4.3 Spacing of side transverses and web frames forward

Location	Maximum spacing	
	Web frames in association with transverse framing system	Side transverses in association with longitudinal framing system
(1) Forward of the collision bulkhead	5 frame spaces	2,5 m where $L \leq 100$ m 3,5 m where $L \geq 300$ m Intermediate values by interpolation
(2) In way of a forward deep tank adjacent to the collision bulkhead	5 frame spaces	3,0 m where $L \leq 100$ m 4,2 m where $L \geq 300$ m Intermediate values by interpolation
(3) Elsewhere in way of dry cargo spaces or deep tanks	See Note 1	3,8 m where $L \leq 100$ m (0,006L + 3,2) m where $L > 100$ m
(4) In way of the cargo tanks of oil tankers, chemical tankers or ore or oil carriers	—	3,6 m where $L \leq 180$ m 0,02L where $L > 180$ m

NOTES

- 1. In 'tween decks above deep tanks situated adjacent to the collision bulkhead, web frames are to be fitted in line with those in the tanks.
- 2. For the maximum spacing of transverses in dredgers, see Pt 4, Ch 12,5.



## Fore End Structure

## Part 3, Chapter 5

Section 4

Table 5.4.4 Primary structure forward

Item and location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
Longitudinal framing system		
(1) Side transverses in dry spaces forward of 0,2L from the F.P., see Note 5: (a) Holds (b) 'tween decks	$Z = 10 k S h_{T1} l_e^2$ $Z = C_2 k S T H_{TF} \sqrt{D}$	—
(2) Side transverses in peak and deep tanks forward of 0,2L from the F.P., see Notes 1 and 4: (a) where no struts fitted (b) where struts fitted	$Z = 14,1 p k S h_4 l_e^2 \gamma$ or as (1) above, whichever is the greater As in Pt 4, Ch 9,9	$I = \frac{2,5}{k} l_e Z$
(3) Side transverses in dry spaces and deep tanks aft of 0,2L from the F.P.	As in Pt 4, Ch 1,6, see Notes 1 and 2	
Transverse framing system		
(4) Side stringers supported by webs in dry spaces forward of 0,2L from the F.P., see Note 3	$Z = 7,75 k S h_{T1} l_e^2$	—
(5) Side stringers supported by webs in peak or deep tanks forward of 0,2L from the F.P., see Notes 1 and 3	$Z = 11,7 p k S h_4 l_e^2$ or as (4) above, whichever is the greater	$I = \frac{2,5}{k} l_e Z$
(6) Web frames supporting side stringers forward of 0,2L from the F.P., see Notes 1, 2 and 3	Z to be determined from the calculations based on the following assumptions: (a) Fixed ends (b) Point loadings from stringers (c) Head $\gamma h_4$ or $\gamma h_{T1}$ as applicable (d) Bending stress $\frac{93,2}{k}$ N/mm <sup>2</sup> $\left( \frac{9,5}{k}$ kgf/mm <sup>2</sup> $\right)$ (e) Shear stress $\frac{83,4}{k}$ N/mm <sup>2</sup> $\left( \frac{8,5}{k}$ kgf/mm <sup>2</sup> $\right)$	In deep tanks $I = \frac{2,5}{k} l_e Z$
(7) Web frames in 'tween decks, not supporting side stringers, forward of 0,2L from the F.P.	$Z = C_3 k S T H_{TF} \sqrt{D}$	—
(8) Side stringers and web frames in dry spaces and deep tanks aft of 0,2L from the F.P.	As in Pt 4, Ch 1,6, see Notes 1 and 2	
Symbols		
$D, T, S, l_e, k, p$ as defined in 1.4.1 $B_f$ = bow fullness factor determined from Fig. 5.4.3 to be taken as 1,0 for framing members located at and abaft 0,2L from the forward perpendicular $h_4$ = tank head, in metres, as defined in Ch 3,5 $h_{T1}$ = head, in metres, at mid-length of span $= f_w C_w \left( 1 - \frac{h_6}{D_1 - T_1} \right) F_\lambda$ , in metres, where the mid-length of span is above the waterline at draught $T_1$ where $f_w \left( 1 - \frac{h_6}{D_1 - T_1} \right)$ is not to be taken less than 0,7 $= \left[ h_6 + f_w C_w \left( 1 - \frac{h_6}{2T_1} \right) \right] F_\lambda$ , in metres, where the mid-length of span is below the waterline at draught $T_1$ where $f_w = 1,0$ at 0,2L from F.P. and 1,71 at, and forward of, 0,15L from F.P. Intermediate positions by interpolation	$h_6$ = vertical distance, in metres, from the waterline at draught $T_1$ to the mid-length of span $F_\lambda = 1,0$ for $L \leq 200$ m $= [1,0 + 0,0023 (L - 200)]$ for $L > 200$ m $C_w$ = a wave head, in metres $= 7,71 \times 10^{-2} L e^{-0,0044L}$ where e = base of natural logarithms 2,7183 $D_1 = T + H_b$ , in metres, where $H_b$ is defined in Ch 1,6.1.11 $T_1 = T$ but not to be taken less than 0,65 $D_1$ $C_2, C_3$ = factors obtained from Fig. 5.4.2 $H_{TF}$ = vertical height of 'tween decks, in metres, as shown in Fig. 5.4.1 $\gamma$ is to be measured at the mid-span of the member as follows: $\gamma_1 = 1,0$ at base line $\gamma_2$ = bow fullness factor ( $B_f$ ) at 0,6D above base $\gamma_3 = \left( \frac{B_f - 1}{2} \right) + 1,0$ at depth D above base Intermediate values are to be determined by interpolation. Minimum value = 1,0	
NOTES		
1. In way of the cargo tanks, fore peak tanks and dry spaces of oil tankers or ore carriers the scantlings of primary structure are to comply with the requirements of Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate. 2. For bulk carriers see Pt 4, Ch 7,6.2. 3. For stringers and webs in fore peaks or deep tanks, see also 6.3 and 7.3. 4. In the fore peak, the breadth S should be measured along the line of shell. The effective length $l_e$ of the vertical webs should be measured along the line of shell from horizontal flat to horizontal flat, except that it may be taken to the underside of a transverse or strut where fitted. 5. The web depth of side transverses forward of 0,2L from the F.P. is to be not less than 2,5 times the depth of the longitudinals supported. The web depth of stringers forward of 0,2L is to be not less than 2,2 times the depth of the frames supported. 6. For the primary structure at sides in dredgers with restricted service notations, see Table 12.5.2 in Pt 4, Ch 12.		



## Section 5

### Single and double bottom structure

#### 5.1 General

5.1.1 For dry cargo ships exceeding 120 m in length and for all ships which have the notation 'strengthened for heavy cargoes', longitudinal framing is, in general, to be adopted, see also Pt 4, Ch 9,1.3 and Pt 4, Ch 10.

5.1.2 For ships requiring additional strengthening of bottom forward the requirements given in 1.5 are also to be complied with, as applicable.

5.1.3 For ships having the notation 'strengthened for heavy cargoes' the requirements of Pt 4, Ch 7,8 are also to be complied with, as applicable.

5.1.4 For ships intended to load or unload while aground, see Ch 9,13.

5.1.5 Provision is to be made for the free passage of water and/or air from all parts of single or double bottoms to bilge or tank suctions, account being taken of the pumping rates required.

5.1.6 For passenger ships, see Pt 4, Ch 2,6.

#### 5.2 Single bottoms – Transverse framing

5.2.1 In fore peak spaces, for ships of full form the floors are to be supported by a centreline girder or a centreline wash bulkhead. In other cases the centreline girder is to be carried as far forward as practicable. The arrangement and scantlings of the floors and centreline girder are to be sufficient to give adequate stiffness to the structure, but are to be not less than required by Table 5.5.1. The floor panels and the upper edges of the floors and centreline girder are to be suitably stiffened.

5.2.2 In deep tanks forward of 0,2L from the F.P. floors are to be supported by a primary centreline girder or centreline bulkhead together with intercostal side girders. In the case of an oil tanker (see 1.1.4) or similar ship having longitudinal bulkheads port and starboard, these may be extended to the fore end of the deep tank in lieu of a centreline bulkhead. The arrangement and scantlings of centreline girder, floors and side girders are to be determined from Table 5.5.1, but in way of web frames the depth of the floor and size of the face bar are to be not less than those of the web frame. In general, floors are not to be flanged.

5.2.3 In way of dry cargo spaces forward, the arrangement and scantlings of transversely framed single bottoms are to be generally as required in the midship region as given in Pt 4, Ch 1,7, except as required by Table 5.1.1. The girders forward are to scarf into the normal girder arrangement in the midship region. In ships having considerable rise of floor towards the fore end, the depth of the floors may be required to be increased or the top edge sloped upwards towards the outboard end. In general, floors are not to be flanged.



## Fore End Structure

## Part 3, Chapter 5

Section 5

Table 5.5.1 Single bottom construction forward

Item	Parameter	Requirement
Transverse framing system		
(1) Centre girder: (a) In fore peak tank, or deep tank, forward of 0,2L from the F.P.  (b) In dry spaces	Modulus  Inertia Web thickness  Web thickness  Web depth and face area	<p>The greater of the following:</p> $\begin{cases} Z = 8,5 k S h_5 l_e^2 \text{ cm}^3, \text{ or} \\ Z = 9,75 p k S h_4 l_e^2 \text{ cm}^3 \end{cases}$ $I = \frac{2,5}{k} l_e Z \text{ cm}^4$ $t = t_w \text{ as in Ch 10,4.4}$ <p>Forward of 0,075L from the F.P.,</p> $t = (\sqrt{Lk} + 0,5) \text{ mm or } 6 \text{ mm, whichever is the greater.}$ <p>Between 0,075L and 0,3L from the F.P. the thickness may taper from the midship thickness to the end thickness above</p> <p>As in Pt 4, Ch 1,7</p>
(2) Floors: (a) In fore peak tank, or deep tank, forward of 0,2L from the F.P.  (b) In dry cargo spaces	Maximum spacing Web depth (at centreline)  Web thickness  Minimum face plate area in deep tank Maximum spacing Scantlings	<p>Every frame</p> $d_f = (83D + 150) \text{ mm or } 1400 \text{ mm, whichever is the lesser}$ $t = (6,0 + 0,025L_2) \sqrt{\frac{s_2}{800}} \text{ mm}$ $A_f = 0,85k B \text{ cm}^2$ <p>Every frame</p> <p>As in Pt 4, Ch 1,7.2</p>
(3) Intercoastal side girders: (a) In deep tank, forward of 0,2L from the F.P.  (b) In dry cargo spaces	Maximum spacing Web depth Web thickness Minimum face plate area  Maximum spacing Scantlings	<p>0,003s<sub>F</sub> m</p> <p>As floors</p> $t = t_w \text{ as in Ch 10,4.4}$ <p>Suitable stiffener</p> <p>0,003s<sub>F</sub> m</p> <p>As in Pt 4, Ch 1,7</p>
Longitudinal framing system		
(4) Centre girder: (a) In deep tanks forward of 0,2L from the F.P. (b) In dry spaces	Scantlings  Scantlings	<p>As in Pt 4, Ch 9,9</p> <p>To be specially considered</p>
(5) Bottom transverses: (a) In deep tanks forward of 0,2L from the F.P., see Note 4  (b) In dry spaces	Maximum spacing  Scantlings Scantlings	<p>3,0 m for <math>L \leq 100</math> m</p> <p>4,2 m for <math>L \geq 300</math> m</p> <p>Spacing at intermediate lengths by interpolation</p> <p>As in Pt 4, Ch 9,9</p> <p>To be specially considered</p>
(6) Intercoastal side girders	Scantlings	To be specially considered
Symbols		
<p><math>L, B, D, S, s, l_e, k, p</math> as defined in 1.4.1</p> <p><math>h_4</math> = tank head, in metres, as defined in Ch 3,5</p> <p><math>h_5</math> = distance, in metres, from mid-point of span to the following positions:</p> <p>(a) forward of 0,15L from the F.P., 3 m above the deck height obtained from Ch 3,6.1</p> <p>(b) at 0,2L from the F.P., the upper deck at side</p> <p>(c) between 0,15L and 0,2L from the F.P., by interpolation between (a) and (b)</p> <p><math>s_F</math> = transverse frame spacing, in mm</p> <p><math>s_2</math> = spacing of stiffener, in mm, but to be taken not less than 800 mm</p> <p><math>L_2 = L</math> but need not be taken greater than 215 m</p>		
NOTES		
<p>1. For single bottom construction in way of the cargo tanks of oil tankers, see Pt 4, Ch 9,1.3 and Pt 4, Ch 10.</p> <p>2. For minimum thickness of structure within cargo tanks and fore peak tanks in oil tankers, see Pt 4, Ch 9,10.2 and Pt 4, Ch 10,7.2</p> <p>3. For single bottom construction in dredgers, see Pt 4, Ch 12,6.</p> <p>4. For ships having one or more longitudinal bulkheads the maximum spacing may be increased but is not to exceed that for the midship region.</p>		

**5.3 Single bottoms – Longitudinal framing**

5.3.1 In deep tanks forward of  $0,2L$  from the F.P., bottom transverses are to be supported by a primary centreline girder or a centreline bulkhead. In addition, an intercostal side girder is generally to be fitted port and starboard. In the case of an oil tanker (see 1.1.4) or similar ship having longitudinal bulkheads port and starboard, these may be extended to the fore end of the deep tank in lieu of a primary centreline support and intercostal girders. The spacing of bottom transverses and scantlings of the centreline girder, bottom transverses and side girders are to be as required by Table 5.5.1.

5.3.2 The requirements for longitudinally framed single bottoms in way of dry cargo spaces will be specially considered.

**5.4 Double bottoms**

5.4.1 The minimum depth of centre girder forward is generally to be the same as that required in the midship region by Part 4 for the particular type of ship concerned, but in ships with considerable rise of floor, a greater depth may be required at the fore end to provide adequate access throughout the double bottom tank.

5.4.2 Where the height of the double bottom varies, this variation is generally to be made gradual by sloping the inner bottom over an adequate longitudinal extent. Knuckles in the plating are to be arranged close to plate floors. Otherwise, suitable scarfing arrangements are to be made.

5.4.3 The arrangement and scantlings of girders, floors and inner bottom plating and the section modulus of inner bottom stiffening are to be determined from Table 5.5.2. In other respects the structural arrangements are to be as detailed in Part 4 for the particular type of ship concerned.

5.4.4 For double bottom construction in way of the cargo tanks of oil tankers or ore carriers, see *also* Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate.

# Fore End Structure

## Part 3, Chapter 5

Sections 5 &amp; 6

**Table 5.5.2 Double bottom construction forward**

Item and parameter	Requirements	
	Transverse framing	Longitudinal framing
(1) Centre girder: (a) Thickness forward of 0,075L from the F.P. (b) Thickness between 0,075L and 0,3L from the F.P.	$t = (0,008 d_{DB} + 2) \sqrt{k}$ mm  As determined by a taper line from the midship thickness given in Pt 4, Ch 1,8 to the end thickness as for (1) (a)	
(2) Plate floors: (a) Maximum spacing forward of 0,2L from the F.P. (b) Maximum spacing aft of 0,2L from the F.P. (c) Scantlings	0,002s <sub>F</sub> m  As for midship region  As in Pt 4, Ch 1,8	2,5 m  As for midship region, see Note 5  As in Pt 4, Ch 1,8
(3) Watertight floors and bracket floors	As in Pt 4, Ch 1,8	As in Pt 4, Ch 1,8
(4) Side girders, see Note 1: (a) Maximum spacing forward of 0,2L from the F.P. (b) Maximum spacing aft of 0,2L from the F.P. (c) Scantlings	0,003s <sub>F</sub> m  As for midship region  As in Pt 4, Ch 1,8	0,004s <sub>L</sub> or 3,7 m whichever is the lesser  As for midship region, see Note 5  As in Pt 4, Ch 1,8
(5) Inner bottom plating, see Note 2: (a) Thickness at or forward of 0,075L from the F.P. (b) Thickness between 0,075L and 0,3L from the F.P. (c) In way of deep tanks or holds used for the carriage of water ballast or where the double bottom tank is common with a wing ballast tank	$t = (0,00127(s + 660) \sqrt[4]{k^2 LT})$ mm or 6,5 mm, whichever is the greater, see Notes 3, 4 and 5  As determined by a taper line from the midship thickness given in Pt 4, Ch 1,8 to the end thickness as for (5) (a), but not less than 6,5 mm, see Notes 3, 4 and 5  $t = \left( 0,004 s f \sqrt{\frac{\rho k h_4}{1,025}} + 2,5 \right)$ mm or 6,5 mm, whichever is the greater	
(6) Inner bottom longitudinals	As in Pt 4, Ch 1,8, see Notes 2 and 5	
Symbols		
$L, T, S, s, k, \rho$ as defined in 1.4.1 $d_{DB}$ = minimum depth of centre girder as required by Pt 4, Ch 1,8 $f = 1,1 - \frac{s}{2500S}$ but to be taken not greater than 1,0		$h_4$ = tank head, in metres, as defined in Ch 3,5 $s_F$ = transverse frame spacing, in mm $s_L$ = spacing of bottom longitudinals, in mm
NOTES 1. The girders forward of 0,2L are to be suitably scarfed into the midship girder arrangement. 2. For double bottom construction in way of the cargo tanks of oil tankers or ore carriers, see also Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate. 3. In way of hatches the tank top taper thickness is to be increased by 2 mm if no ceiling is fitted, but is to be taken not less than 7,5 mm. 4. Where cargo is to be regularly discharged by grabs the tank top taper thickness is to be increased by 5,0 mm if no ceiling is fitted, or by 3,0 mm where ceiling is fitted. 5. For ships having the notation ‘strengthened for heavy cargoes’, the requirements of Pt 4, Ch 7,8 are also to be complied with.		

## Section 6 Fore peak structure

### 6.1 General

6.1.1 The requirements given in this Section apply to the arrangement of primary structure supporting the peak side framing and bulbous bow, the arrangement and scantlings of wash bulkheads and perforated flats, and the scantlings of collision bulkheads.

6.1.2 In ships of very full form it is recommended that transverse framing and side transverses supporting longitudinal framing, together with attached floors and beams, be inclined at an angle to the centreline of ship so that the frames or transverses lie as near normal to the shell plating as possible.

# Fore End Structure

# Part 3, Chapter 5

Section 6

## 6.2 Bottom structure

6.2.1 The bottom of the peak space is generally to be transversely framed with arrangements and scantlings as detailed in 5.2.1. Longitudinally framed bottom structure will be specially considered.

## 6.3 Side structure – Transverse framing

6.3.1 Above the floors, transverse side framing is to be supported by one of the following arrangements:

- (a) Side stringers spaced about 2,0 m apart and supported by struts fitted at alternate frames. The struts are to be bracketed to the frames and where the span is long, supported at the centreline by a complete or partial wash bulkhead or equally effective structure. Intermediate frames are to be bracketed to the stringer plates.
- (b) Side stringers spaced about 2,0 m apart and supported by web frames. The upper ends of the web frames are to be supported under the tank top by suitable deep beams or buttresses which should generally form a ring structure.
- (c) Perforated flats spaced not more than 2,5 m apart. The area of perforations in each flat is to be not less than 10 per cent of the total area of the flat. The plating is to be suitably framed in way of openings.
- (d) A combination of the above arrangements.

6.3.2 Where the depth of the peak space exceeds 10 m, a perforated flat is to be arranged at about mid-depth.

6.3.3 Where the length of the space exceeds 10 m and the side framing is supported as required by 6.3.1(a) or (c), additional transverse strengthening in the form of transverse wash bulkheads or web frames is to be provided.

6.3.4 The scantlings of side stringers supported by struts, and also of the struts and their brackets, are to be determined from Table 5.6.1.

6.3.5 The scantlings of side stringers supported by web frames, and also of the web frames, are to be determined from 4.5.

6.3.6 The scantlings of perforated flats are to be determined from Table 5.6.1.

## 6.4 Side structure – Longitudinal framing

6.4.1 The spacing and scantlings of side transverses supporting longitudinal framing are to be as required by 4.5.

6.4.2 Where the depth of a tank exceeds 10 m, side transverses are generally to be supported by one or more perforated flats or an arrangement of struts.

6.4.3 Suitable transverses or deep beams are to be arranged at the top of the tank and at perforated flats to provide end rigidity to the side transverses.

## 6.5 Bulbous bow

6.5.1 Where a bulbous bow is fitted, the structural arrangements are to be such that the bulb is adequately supported and integrated into the fore peak structure.

6.5.2 At the fore end of the bulb the structure is generally to be supported by horizontal diaphragm plates spaced about 1,0 m apart in conjunction with a deep centreline web.

6.5.3 In general, vertical transverse diaphragm plates are to be arranged in way of the transition from the peak framing to the bulb framing.

6.5.4 In way of a wide bulb, additional strengthening in the form of a centreline wash bulkhead is generally to be fitted.

6.5.5 In way of a long bulb, additional strengthening in the form of transverse wash bulkheads or substantial web frames spaced about five frame spaces apart are generally to be fitted.

6.5.6 The shell plating is to be increased in thickness at the fore end of the bulb and in other areas likely to be damaged by the anchors and chain cables. The increased plate thickness is to be the same as that required for plated stems by 3.3.2.

## 6.6 Wash bulkhead

6.6.1 Where a fore peak space is used as a tank and the breadth of the tank at its widest point exceeds  $0,5B$ , a complete or partial centreline wash bulkhead is to be fitted.

6.6.2 Wash bulkheads are to have an area of perforations not less than five per cent nor more than 10 per cent of the area of the bulkhead. The plating is to be suitably stiffened in way of openings.

6.6.3 The scantlings of wash bulkheads are to be determined from Table 5.6.1. Stiffeners are to be bracketed at top and bottom.

## 6.7 Collision bulkhead

6.7.1 The position and height of the collision bulkhead are to be in accordance with the requirements of Ch 3,4.

6.7.2 The scantlings are to comply with the requirements of Pt 4, Ch 1,9 except that the thickness of plating and modulus of stiffeners are to be not less than 12 per cent greater and 25 per cent greater, respectively, than would be required for a dry space. If the collision bulkhead forms the boundary of a cargo tank or cofferdam in an oil tanker or ore carrier the minimum thickness requirements of Pt 4, Ch 9,10 are also to be complied with.

## Fore End Structure

## Part 3, Chapter 5

Sections 6 &amp; 7

Table 5.6.1 Fore peak structure

Item	Parameter	Requirement
(1) Unflanged stringers supported by panting beams at alternate frames	Web thickness	$t = (6,0 + 0,025L_2) \sqrt{\frac{s_1}{600}} \text{ mm}$
	Web depth	$d_w = (400 + 3,3L) \frac{S_1}{2,0} \text{ mm}$
(2) Struts	Cross-sectional area	$A = (2,5B_1 - 0,04L_2) k \text{ cm}^2$
	Least inertia	$I = S_1 S_2 h_5 l_e^2 \text{ cm}^4$
(3) Brackets supporting stringers and beams	Thickness	$t = (6,0 + 0,025L_2) \sqrt{\frac{s_1}{600}} \text{ mm}$
	Arm length	$l_e = \frac{150A}{t} \text{ mm in way of struts}$ $l_e = 0,5d_w \text{ mm at intermediate frames}$
(4) Perforated flats and wash bulkheads (excluding lowest strake of plating), see Notes 1, 2 and 3	Plating thickness	$t = (6,0 + 0,015L) \sqrt{\frac{s_2}{800}} \text{ mm}$
	Stiffener modulus	$Z = \frac{0,0057 s k h_6 l_e^2}{b} \text{ cm}^3$
(5) Diaphragms in bulbous bows and lowest strake of wash bulkhead	Plating thickness	$t = (6,0 + 0,025L_2) \sqrt{\frac{s_2}{800}} \text{ mm}$
Symbols		
<p><math>L, B, S, s, k</math> as defined in 1.4.1  <math>b = 1,4</math> for rolled or built sections  <math>= 1,6</math> for flat bars  <math>h_5</math> = vertical distance, in metres, from the stringer to a position 3 m above the deck height obtained from Ch 3,6.1  <math>h_6</math> = vertical distance, in metres, from mid-depth of tank to top of tank  <math>l_e</math> = effective length of stiffening member, in metres, see Tables 1.9.1 and 1.9.3 in Pt 4, Ch 1</p>		
<p><math>s_1</math> = spacing of peak frames, in mm, but to be taken not less than 600 mm  <math>s_2</math> = spacing of stiffeners, in mm, but to be taken not less than 800 mm  <math>B_1 = B</math> but need not be taken greater than 32 m  <math>L_2 = L</math> but need not be taken greater than 215 m  <math>S_1</math> = vertical spacing or mean spacing of stringers, in metres  <math>S_2</math> = horizontal spacing of struts, in metres</p>		
<p>NOTES</p> <p>1. For oil tankers, see also Pt 4, Ch 9,10.7.</p> <p>2. For horizontal flats supporting vertical webs in the fore peak tank, the thickness of the flat in way of the web is to comply with Table 9.7.1(b)(ii) in Pt 4, Ch 9.</p> <p>3. For minimum thickness within fore peak tanks of oil tankers, see also Pt 4, Ch 9,10.2.</p>		

6.7.3 Doors, manholes, permanent access openings or ventilation ducts are not to be cut in the collision bulkhead below the freeboard deck, see also Pt 5, Ch 13,3. The number of openings in collision bulkheads above the freeboard deck is to be kept to a minimum compatible with the design and proper working of the ship. All such openings are to be fitted with means of closing to weathertight standards.

## Section 7

## Forward deep tank structure

## 7.1 General

7.1.1 The requirements given in this Section apply to the arrangement of primary structure supporting the side framing, the arrangement and scantlings of wash bulkheads and perforated flats, and the scantlings of boundary bulkheads in way of deep tanks situated forward of 0,2L from the F.P.

7.1.2 For deep tanks situated aft of this position, see Pt 4, Ch 1,9.

## 7.2 Bottom structure

7.2.1 The bottom structure is to comply with the requirements given in 5.2.2, 5.3.1 and 5.4, as applicable.

# Fore End Structure

# Part 3, Chapter 5

Section 7

## 7.3 Side structure – Transverse framing

7.3.1 Above the floors, transverse framing is to be supported by one of the following arrangements:

- (a) Side stringers spaced not more than 5 m apart and supported by web frames. The upper ends of the web frames are to be supported under the tank top by suitable deep beams or buttresses which should generally form a ring system.
- (b) Side stringers spaced not more than 5 m apart and spanning from bulkhead to bulkhead. The ends of these stringers are to be connected to horizontal stringers on the transverse bulkheads to form a ring system.
- (c) In the case of narrow tanks, perforated flats spaced not more than 5 m apart. The area of perforations is to be not less than 10 per cent of the area of the flat, and the plating is to be suitably stiffened in way of openings.

7.3.2 Where the side framing is supported as required by 7.3.1(a) and the depth of the tank exceeds 16 m, the web frames are to be supported by one of the following:

- (a) One or more side stringers spanning from bulkhead to bulkhead.
- (b) One or more perforated flats having deep beams or transverses in way of the web frames.
- (c) One or more cross ties.

7.3.3 Where the side framing is supported as required by 7.3.1(c) and the length of the tank exceeds 14 m, additional transverse strengthening in the form of transverse wash bulkheads or web frames is to be provided.

7.3.4 The scantlings of stringers and web frames as required by 7.3.1(a) are to be determined from 4.5.

7.3.5 The scantlings of side stringers supporting framing as required by 7.3.1(b) are to be determined from Item (5) in Table 5.4.4.

7.3.6 The scantlings of side stringers supporting web frames as required by 7.3.2(a) are to be determined from Item (6) in Table 5.4.4.

7.3.7 The scantlings of perforated flats as required by 7.3.1(c) or 7.3.2(b) are to be determined from Table 5.6.1.

7.3.8 The scantlings of cross ties are to be determined as for cross ties in the cargo tanks of oil tankers, see Pt 4, Ch 9.9. Where the span between the side shell and longitudinal bulkhead exceeds  $0,3B$ , additional fore and aft or vertical support for the struts may be required.

## 7.4 Side structure – Longitudinal framing

7.4.1 The spacing and scantlings of side transverses supporting longitudinal framing are to be as required by 4.5.

7.4.2 Where the depth of the tank exceeds 16 m, the side transverses are to be supported as required by 7.3.2.

## 7.5 Wash bulkheads

7.5.1 Where the breadth of the tank at its widest point exceeds  $0,5B$ , a centreline wash bulkhead is generally to be fitted. If the maximum breadth of tank exceeds  $0,7B$ , it is recommended that the centreline bulkhead be made intact. In the case of an oil tanker or similar ship having longitudinal bulkheads port and starboard, these may be extended to the fore end of the deep tank in lieu of a centreline bulkhead.

7.5.2 Wash bulkheads are to have an area of perforations not less than 5 per cent nor more than 10 per cent of the area of the bulkhead. The plating is to be suitably stiffened in way of openings.

7.5.3 The scantlings of wash bulkheads are generally to be as required by Table 5.6.1, but see also 7.5.4 to 7.5.6. Stiffeners are to be bracketed at top and bottom.

7.5.4 The thickness of longitudinal bulkheads may be required to be increased to ensure compliance with the shear strength requirements of Ch 4,6. In the case of a centreline or perforated wing bulkhead, the proportion of the total shear force absorbed by the bulkhead will be specially considered.

7.5.5 The thickness of plating of wash bulkheads may also be required to be increased to take account of shear buckling.

7.5.6 Where longitudinal wash bulkheads support bottom transverses, the lower section of the bulkhead is to be kept free of non-essential openings for a depth equal to 1,75 times the depth of the transverses, and the plating thickness may be required to be increased to meet local buckling requirements.

## 7.6 Transverse boundary bulkheads

7.6.1 The transverse bulkheads forming the forward and after boundaries of the tank are generally to comply with the requirements of Pt 4, Ch 1,9, except that when the after bulkhead forms the boundary of a cargo tank or cofferdam in an oil tanker or ore carrier, the minimum thickness requirements of Pt 4, Ch 9,10 are also to be complied with.

# Aft End Structure

# Part 3, Chapter 6

Section 1

## Section

- 1 **General**
- 2 **Deck structure**
- 3 **Shell envelope plating**
- 4 **Shell envelope framing**
- 5 **Single and double bottom structure**
- 6 **After peak structure**
- 7 **Sternframes and appendages**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to all types of ship covered by Part 4, except where specifically stated otherwise.

1.1.2 The requirements given are those specific to aft ends and relate to structure situated in the region aft of  $0,3L$  from the after perpendicular.

1.1.3 Requirements for cargo space structure within this region not dealt with in this Chapter are to be as detailed in the relevant Chapter of Part 4 for the particular ship type.

1.1.4 The requirements in this chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation. See Pt 1, Ch 2,2.3.

### 1.2 Structural configuration

1.2.1 The Rules provide for both longitudinal and transverse framing systems.

1.2.2 In the case of container ships and open type ships additional requirements may apply as detailed in Pt 4, Ch 8.

### 1.3 Structural continuity

1.3.1 Suitable scarfing arrangements are to be made to ensure continuity of strength and the avoidance of abrupt structural changes.

1.3.2 Where longitudinal framing terminates and is replaced by a transverse system, adequate arrangements are to be made to avoid an abrupt changeover. Where a poop is fitted extending forward of  $0,15L$  from the A.P., longitudinal framing at the upper deck and topsides is generally to be continued aft of the forward bulkhead of this superstructure. In bulk carriers and oil tankers (see 1.1.4) the longitudinal framing at the upper deck is to be maintained over the cargo space region and continued over the aft end region.

1.3.3 In oil tankers (see 1.1.4) with machinery aft, continuity of the longitudinal bulkheads is to be maintained as far as is practicable into the machinery space, and suitable taper brackets are to be fitted at their ends.

1.3.4 In bulk carriers (see 1.1.4) with machinery aft, continuity of the topside tank and double bottom hopper tank structure is to be maintained over the cargo space region and as far as is practicable continued into the machinery space, and suitable taper brackets are to be arranged at their ends. Also a vertical taper bracket in line with the vertical strake of the topside tank is to be fitted at the forward side of the aft bulkhead of the cargo space region. Where the topside tank and double bottom hopper tank structures terminate at the cargo space aft bulkhead, the vertical strake of the topside tank is to be arranged with an integral taper bracket and continued through the bulkhead into the machinery space for a distance of  $0,2B$ , and the ends of the hopper and topside structures are to be arranged with suitable taper brackets. In addition, in way of the cargo space aft bulkhead, a girder or intercostal bulb plate stiffeners (fitted between and connected to the bulkhead vertical stiffeners), are to be arranged on the aft side in line with the sloped bulkheads of the topside and hopper tanks clear of the taper brackets.

1.3.5 In container or similar ships having continuous side tanks or double skin construction in way of the cargo spaces, the longitudinal bulkheads are to be continued as far aft as is practicable and are to be suitably tapered at their ends. Where, due to the ship's form, such bulkheads are stepped, suitable scarfing is to be arranged.

### 1.4 Symbols and definitions

1.4.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L, B, D, T$  as defined in Ch 1,6.1

$k_L, k$  = higher tensile steel factor as defined in Ch 2,1.2

$l$  = overall length of stiffening member, in metres, see Ch 3,3.3

$l_e$  = effective length of stiffening member, in metres, see Ch 3,3.3

$s$  = spacing of secondary stiffeners, in mm

$t$  = thickness of plating, in mm

$S$  = spacing, or mean spacing, of primary members, in metres

$Z$  = section modulus of stiffening member, in  $\text{cm}^3$ , see Ch 3,3.2

$\rho$  = relative density (specific gravity) of liquid carried in a tank and is to be taken not less than 1,025

$I$  = inertia of stiffening member, in  $\text{cm}^4$ , see Ch 3,3.2.

1.4.2 For the purpose of this Chapter, the after perpendicular, A.P., is defined as the after limit of the Rule length  $L$ .

# Aft End Structure

# Part 3, Chapter 6

Section 2

## Section 2 Deck structure

### 2.1 General

2.1.1 Where the upper deck is longitudinally framed outside the line of openings in the midship region, this system of framing is to be carried as far aft as possible, see *a/so* Pt 4, Ch 9,1.3.

### 2.2 Deck plating

2.2.1 The thickness of strength/weather deck plating is to comply with the requirements of Table 6.2.1.

2.2.2 The thickness of lower deck plating is to comply with the requirements of Table 6.2.2.

2.2.3 The taper thickness of the strength deck stringer plate is to be increased by 20 per cent at the ends of a poop or bridge where the end bulkhead is situated forward of 0,25L from the A.P. No increase is required where the end bulkhead lies aft of 0,2L from the A.P. The increase at intermediate positions is to be determined by interpolation.

2.2.4 The deck plating thickness and supporting structure are to be suitably reinforced in way of deck machinery, and in way of cranes, masts or derrick posts.

2.2.5 Where long, wide hatchways are arranged at lower decks it may be necessary to increase the deck plating thickness to ensure effective support for side framing.

### 2.3 Deck stiffening

2.3.1 The scantlings of strength/weather deck longitudinals are to comply with the requirements of Table 6.2.3.

2.3.2 The scantlings of cargo and accommodation deck longitudinals are to comply with the requirements given in Table 1.4.4 in Pt 4, Ch 1.

2.3.3 End connections of longitudinals to bulkheads are to provide adequate fixity, lateral support and so far as practicable, direct continuity of longitudinal strength.

2.3.4 The scantlings of weather deck beams are to comply with the midship requirements for the particular ship type.

2.3.5 The scantlings of lower deck beams are to comply with the requirements of Table 1.4.5 in Pt 4, Ch 1.

2.3.6 End connections of beams are to be in accordance with the requirements of Ch 10,3.

**Table 6.2.1 Strength/weather deck plating aft (excluding poop deck)**

Symbols	Location	Thickness, in mm
<p><math>L, s, S, k, p</math> as defined in 1.4.1</p> <p><math>f = 1,1 - \frac{s}{2500S}</math> but is to be taken not greater than 1,0</p> <p><math>h_4</math> = tank head, in metres, as defined in Ch 3,5</p> <p><math>s_b</math> = standard frame spacing as follows: Aft of 0,15L from the A.P.:</p> $s_b = \left( 510 + \frac{L}{0,6} \right) \text{ mm or } 850 \text{ mm,}$ <p>whichever is the lesser</p> <p><math>s_1 = s</math>, but is to be taken not less than <math>s_b</math></p>	(1) Aft of 0,075L from the A.P.	$t = (5,5 + 0,02L) \sqrt{\frac{ks_1}{s_b}}$
	(2) Between 0,075L and 0,15L from the A.P.	The greater of the following: (a) $t = (5,5 + 0,02L) \sqrt{\frac{ks_1}{s_b}}$ (b) the taper thickness, see Notes 1, 2 and 3 (c) for oil tankers, the thickness is also to be in accordance with Pt 4, Ch 9,4.3.3
	(3) Forward of 0,15L from the A.P.	The taper thickness, see Notes 1, 2 and 3, or as 2(c) whichever is the greater
	(4) Inside poop extending forward of 0,15L	As for a lower deck, see Note 4
	(5) In way of the crown of a tank	$t = 0,004sf \sqrt{\frac{p k h_4}{1,025}} + 3,5$ or (1) to (4) as applicable, whichever is the greater but not less than 7,5 mm where $L \geq 90$ m, or 6,5 mm where $L < 90$ m
<p><b>NOTES</b></p> <p>1. The taper thickness is to be determined from Table 3.2.1 in Chapter 3.</p> <p>2. For taper area requirements, see Table 3.2.1 in Chapter 3.</p> <p>3. For thickness of upper deck plating in way of the cargo tanks of oil tankers or ore carriers, see <i>a/so</i> Pt 4, Ch 9, Ch 10 or Ch 11.</p> <p>4. The exposed weather deck taper thickness is to extend into a poop or bridge for at least one-third of the breadth of the ship from the superstructure end bulkhead.</p>		



## Aft End Structure

## Part 3, Chapter 6

Section 2

Table 6.2.2 Lower deck plating aft

Symbols	Location	Thickness, in mm
$L, s, S, k, p$ as defined in 1.4.1 $b$ = breadth of increased plating, in mm $f = 1,1 - \frac{S}{2500S}$ but is to be taken not greater than 1,0 $h_4$ = tank head, in metres, as defined in Ch 3,5 $K_2 = 2,5$ mm at bottom of tank or 3,5 mm at crown of tank $s_1 = s$ , but is to be taken not less than $\left(470 + \frac{L_1}{0,6}\right)$ mm $A_f$ = girder face area, in cm <sup>2</sup> $L_1 = L$ , but need not be taken greater than 190 mm	(1) Aft of 0,075L from the A.P.	$t = 0,01s_1 \sqrt{k}$ but not less than 6,5 mm
	(2) Forward of 0,075L from the A.P., inside line of openings	$t = 0,01s_1 \sqrt{k}$ but not less than 6,5 mm
	(3) Forward of 0,075L from the A.P., outside line of openings	As determined by a taper line from the midship thickness to the end thickness given by (1)
	(4) In way of the crown or bottom of a tank	$t = 0,004sf \sqrt{\frac{pkh_4}{1,025}} + K_2$ or (1), (2) or (3) as applicable, whichever is the greater but not less than 7,5 mm where $L \geq 90$ m, or 6,5 mm where $L < 90$ m
<b>NOTE</b> Where the deck loading exceeds 43,2 kN/m <sup>2</sup> , (4,4 tonne-f/m <sup>2</sup> ), the thickness of plating will be specially considered. This is equivalent to a 'tween deck height of 6,1 m in association with the standard stowage rate of 1,39 m <sup>3</sup> /tonne.	(5) Plating forming upper flange of underdeck girders	Clear of cargo hatches $t = \sqrt{\frac{A_f}{1,8k}}$
		In way of hatch side girders $t = 1,1 \sqrt{\frac{A_f}{1,8k}}$ Minimum breadth $b = 760$ mm

Table 6.2.3 Strength/weather deck longitudinals aft

Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
(1) Aft of 0,075L from the A.P.	The greater of the following: (a) $Z = s k (400h_1 + 0,005 (l_e L_1)^2) \times 10^{-4}$ (b) $Z = 0,0074s k h_1 l_e^2$	—
(2) Forward of 0,075L from the A.P., inside line of openings	As (1)	—
(3) Forward of 0,075L from the A.P., outside line of openings	As determined from Table 3.2.1 in Chapter 3, see Note 1 For oil tankers (see 1.1.4) and dry cargo ships the end modulus for taper at 0,075L from the A.P. is to be derived from Table 5.2.3 item (2)	—
(4) In way of the crown of a tank	$Z = \frac{0,0113p s k h_4 l_e^2}{b}$ or as (1) to (3) as applicable, whichever is the greater	$I = \frac{2,3}{k} l_e Z$
Symbols		
$L, s, k_L, k, p$ as defined in 1.4.1 $b = 1,4$ for rolled or built sections $= 1,6$ for flat bars $d_w$ = web depth of longitudinal, in mm $h_1$ = weather head, in metres, as defined in Ch 3,5 $h_4$ = tank head, in metres, as defined in Ch 3,5 $l_e$ = as defined in 1.4.1 but is to be taken not less than 1,5 m $L_1 = L$ but need not be taken greater than 190 mm		
<b>NOTES</b> 1. For taper area requirements, see Table 3.2.1 in Chapter 3. 2. Where weather decks are intended to carry deck cargo and the loading is in excess of 8,5 kN/m <sup>2</sup> (0,865 tonne-f/m <sup>2</sup> ) the scantlings of longitudinals are also to comply with the requirements for location (1) in Table 1.4.4 in Pt 4, Ch 1 using the equivalent design head, for specified cargo loadings, for weather decks given in Table 3.5.1 in Chapter 3. 3. For the scantlings of deck longitudinals aft in way of the cargo tanks of oil tankers (see 1.1.4) or ore carriers, see also Pt 4, Ch 9, Ch 10 or Ch 11, as applicable. 4. The thickness of flat bar longitudinals, situated outside the line of openings is to be not less than the following: (a) $t = \frac{d_w}{18 \sqrt{k_L}}$ mm where longitudinal continuous through bulkhead (b) $t = \frac{d_w}{15 \sqrt{k_L}}$ mm where longitudinal cut at bulkhead 5. The web depth of longitudinal, $d_w$ , to be not less than 60 mm.		

# Aft End Structure

# Part 3, Chapter 6

Sections 2 & 3

## 2.4 Deck supporting structure

2.4.1 The arrangements and scantlings of supporting structure are generally to be in accordance with the requirements given in Pt 4, Ch 1,4 except as required by 2.4.2 to 2.4.4.

2.4.2 At upper and lower decks above the after peak, deep beams are generally to be fitted in way of web frames. Deck girders are generally to be spaced not more than 3,0 m apart.

2.4.3 Primary structure in the topside tanks of bulk carriers is to comply with the requirements of Pt 4, Ch 7,7.

2.4.4 Primary structure in the cargo tanks of oil tankers, or ore carriers, is to be determined from Pt 4, Ch 9, Ch 10 or Ch 11, as applicable.

## 2.5 Deck openings

2.5.1 In dry cargo ships, the requirements for deck openings given in Pt 4, Ch 1,4 are generally applicable throughout the aft region except that aft of 0,25L from the A.P.:

- (a) The radii or dimensions of the corners of main cargo hatchway openings of the strength deck are to be in accordance with the requirements of Pt 4, Ch 1,4.5. The thickness of the insert plates, where required, is not to be less than 20 per cent greater than the adjacent deck thickness outside the line of openings, with a minimum increase of 3 mm.
- (b) Insert plates will be required at lower decks in way of any rapid change in hull form to compensate for loss of deck cross-sectional area. Otherwise, insert plates will not normally be required.
- (c) Compensation and edge reinforcement for openings outside the line of main hatchways will be considered, bearing in mind their position, the deck arrangements and the type of ship concerned.

2.5.2 For deck openings in way of cargo tanks in oil tankers and ore carriers, see also Pt 4, Ch 9, Ch 10 or Ch 11, as applicable. For main cargo hatchway openings on bulk carriers and container ships, see also Pt 4, Ch 7 and Ch 8, as applicable.

3.2.2 The thickness and width of plate keels in the aft region are to be the same as required in the midship region for the particular type of ship concerned, see Part 4.

## 3.3 Bottom shell and bilge

3.3.1 The thickness of bottom shell and bilge plating in the aft region is to comply with the requirements of Table 6.3.1.

3.3.2 Where the bottom is transversely framed and there are large flat areas of shell plating, the buckling stability of the plating will be specially considered, and increased plate thickness or additional stiffening may be required, see also 5.2.3.

3.3.3 Where longitudinals are omitted in way of radiused bilge plating amidships, the plating thickness aft will be considered in relation to the support derived from the hull form and internal stiffening arrangements.

## 3.4 Side shell and sheerstrake

3.4.1 The thickness of side shell and sheerstrake plating in the aft region is to be not less than the values given in Table 6.3.1, but may be required to be increased locally on account of high shear forces, in accordance with Ch 4,6.5.

3.4.2 Increased shell plate thickness may be required where the panting stringers required by 4.4.1 are omitted. The extent and amount of the increase will be specially considered.

3.4.3 The thickness of shell plating is to be increased locally in way of the sternframe, propeller brackets or rudder horn. The increased plate thickness is to be not less than 50 per cent greater than the basic shell end thickness.

3.4.4 The sheerstrake thickness is to be increased by 20 per cent at the ends of a bridge superstructure extending out to the ship's side, irrespective of position. Similar strengthening is to be fitted in way of the end of a poop if this occurs at a position forward of 0,25L from the A.P. No increase is required if the poop end bulkhead lies aft of 0,2L from the A.P. The increase at intermediate positions of end bulkhead is to be obtained by interpolation.

## ■ Section 3 Shell envelope plating

### 3.1 General

3.1.1 Where the shell is longitudinally framed in the midship region, this system of framing is to be carried as far aft as practicable.

### 3.2 Keel

3.2.1 The scantlings of bar keels at the aft end are to be the same as in the midship region as required by Pt 4, Ch 1,5.

### 3.5 Shell openings

3.5.1 In general, compensation will not be required for holes in the sheerstrake which are clear of the gunwale, or for any deck openings situated outside the line of main hatchways and whose depth does not exceed 20 per cent of the depth of the sheerstrake or 380 mm, whichever is the lesser. Openings are not to be cut in a rounded gunwale. Cargo door openings are to have well rounded corners, and the proposed compensation for the door openings will be individually considered.

## Aft End Structure

## Part 3, Chapter 6

Sections 3 &amp; 4

Table 6.3.1 Shell plating aft

Location	Thickness, in mm	NOTES									
(1) Bottom shell and bilge, see Notes 4 and 5: (a) Aft of 0,075L from the A.P. (b) Between 0,075L and 0,15L from the A.P., see Note 6 (c) Forward of 0,15L from the A.P., see Note 6	$t = (6,5 + 0,033L) \sqrt{\frac{k s_1}{s_b}}$ (see Note 1) As (1) (a) or the taper thickness, whichever is the greater, see Note 2 The taper thickness, see Note 2	1. For ships where $L \leq 70$ m this thickness may be reduced by 1 mm, but it is to be not less than 6 mm. 2. The taper thickness is to be determined from Table 3.2.1 in Chapter 3.									
(2) Side shell, see Notes 4 and 5: (a) Aft of 0,075L from the A.P. (b) Between 0,075L and 0,15L from the A.P., see also 3.4.2 (c) Forward of 0,15L from the A.P.	$t = (6,5 + 0,033L) \sqrt{\frac{k s_1}{s_b}}$ (see Note 1) As (2) (a) or the taper thickness, whichever is the greater, see Note 2 The taper thickness, see Note 2	3. For thickness of shell plating in way of the cargo tanks of oil tankers or ore carriers, see also Pt 4, Ch 9, Ch 10 or Ch 11, as applicable.									
(3) Sheerstrake, see Notes 4 and 5 (a) Aft of 0,075L from the A.P.: where $\frac{T}{D} > 0,7$  where $\frac{T}{D} \leq 0,7$ (b) Between 0,075L and 0,15L from the A.P., see Note 6 (c) Forward of 0,15L from the A.P., see Note 6	As (2) (a) for side shell  As (4) for a poop  As (3) (a) or as determined from Table 3.2.1 in Chapter 3 The taper thickness, see Note 2	4. In offshore supply ships the thickness of side shell is to be not less than 9 mm. 5. For trawlers and fishing vessels see Pt 4, Ch 6.5. 6. For oil tankers the thickness is also to be in accordance with Pt 4, Ch 9.4.3.3.									
(4) Poop, see Notes 4 and 5	$t = (6,5 + 0,017L) \sqrt{\frac{k s_1}{s_b}}$										
Symbols											
<p><math>L, B, D, T, s, k</math> as defined in 1.4.1  <math>s_1 = s</math> but to be taken as not less than <math>s_b</math>  <math>s_b</math> = standard frame spacing, in mm, as follows:</p> <table> <tr> <th>Region</th><th>Bottom shell <math>s_b</math></th><th>Side shell <math>s_b</math></th></tr> <tr> <td>Aft of 0,05L from the A.P.</td><td><math>\left(470 + \frac{L}{0,6}\right)</math> or 600*</td><td><math>\left(470 + \frac{L}{0,6}\right)</math> or 600* below the deck next above the load waterline or <math>\left(470 + \frac{L}{0,6}\right)</math> or 700* above the deck next above the load waterline</td></tr> <tr> <td>Between 0,05L and 0,15L from the A.P.</td><td><math>\left(510 + \frac{L}{0,6}\right)</math> or 850*</td><td><math>\left(510 + \frac{L}{0,6}\right)</math> or 850*</td></tr> </table> <p>*whichever is the lesser</p>			Region	Bottom shell $s_b$	Side shell $s_b$	Aft of 0,05L from the A.P.	$\left(470 + \frac{L}{0,6}\right)$ or 600*	$\left(470 + \frac{L}{0,6}\right)$ or 600* below the deck next above the load waterline or $\left(470 + \frac{L}{0,6}\right)$ or 700* above the deck next above the load waterline	Between 0,05L and 0,15L from the A.P.	$\left(510 + \frac{L}{0,6}\right)$ or 850*	$\left(510 + \frac{L}{0,6}\right)$ or 850*
Region	Bottom shell $s_b$	Side shell $s_b$									
Aft of 0,05L from the A.P.	$\left(470 + \frac{L}{0,6}\right)$ or 600*	$\left(470 + \frac{L}{0,6}\right)$ or 600* below the deck next above the load waterline or $\left(470 + \frac{L}{0,6}\right)$ or 700* above the deck next above the load waterline									
Between 0,05L and 0,15L from the A.P.	$\left(510 + \frac{L}{0,6}\right)$ or 850*	$\left(510 + \frac{L}{0,6}\right)$ or 850*									

3.5.2 Sea inlet and other openings are to have well rounded corners and so far as possible, should be kept clear of the bilge radius. The thickness of sea inlet box plating is generally to be the same as the adjacent shell. It is not, however, to be less than 12,5 mm, and need not exceed 25 mm.

4.1.2 End connections of longitudinals to bulkheads are to provide adequate fixity, lateral support and, so far as practicable, direct continuity of longitudinal strength, see also Ch 10.3. Where  $L$  exceeds 215 m, the bottom longitudinals are to be continuous in way of both watertight and non-watertight floors, but alternative arrangements will be considered. Higher tensile steel longitudinals within 10 per cent of the ship's depth at the bottom and deck are to be continuous irrespective of the ship length.

## Section 4

### Shell envelope framing

#### 4.1 General

4.1.1 Requirements are given in this Section for both longitudinal and transverse framing systems. Where longitudinal framing is adopted in the midship region, it is to be carried as far aft as practicable.

4.1.3 Stiffeners and brackets on side transverses, where fitted on one side and connected to higher tensile steel longitudinals between the base line and 0,8D above the base line, are to have their heels well radiused to reduce stress concentrations. Where a symmetrical arrangement is fitted, i.e. bracket or stiffening on both sides, and it is connected to higher tensile steel longitudinals, the toes of the stiffeners or brackets are to be well radiused. Alternative arrangements will be considered if supported by appropriate direct calculations.

## Aft End Structure

## Part 3, Chapter 6

Section 4

4.1.4 Where higher tensile steel side longitudinals pass through transverse bulkheads in the cargo area, well radiused brackets of the same material are to be fitted on both the fore and aft side of the connection between the upper turn of bilge and  $0,8D$  above the base line. Particular attention is to be given to ensuring the alignment of these brackets. Alternative arrangements will be considered if supported by appropriate direct calculations.

4.1.5 For ships intended to load or unload while aground, see Ch 9,13.

## 4.2 Shell longitudinals

4.2.1 The scantlings of bottom and side shell longitudinals in the aft region are to comply with the requirements given in Table 6.4.1.

## 4.3 Shell framing

4.3.1 The scantlings of side frames in the aft region are to comply with the requirements given in Table 6.4.2.

Table 6.4.1 Shell framing (longitudinal) aft

Location	Modulus, in $\text{cm}^3$
(1) Side longitudinals in poop	$Z = 0,0065 s k l_e^2 (0,6 + 0,167D_2)$
(2) Side longitudinals in way of dry spaces including double skin construction: (a) Aft of the after peak bulkhead (b) Between the after peak bulkhead and $0,2L$ from the A.P. (c) Forward of $0,2L$ from the A.P.	$Z = 0,0085 s k h_{T1} l_e^2 F_s$ but not to be less than as required by (1) $Z = 0,007 s k h_{T1} l_e^2 F_s$ or as required in the midship region for the particular type of ship concerned, whichever is the greater As required in the midship region for the particular type of ship concerned
(3) Side longitudinals in way of double skin tanks or deep tanks	The greater of the following: (a) $Z$ as from (2) (b) As required by Pt 4, Ch 1,9 for deep tanks
(4) Bottom and bilge longitudinals	As required in the midship region for the particular type of ship concerned
Symbols	
$L, D, T, s, k$ , as defined in 1.4.1 $l_e$ = as defined in 1.4.1, but is to be taken not less than 1,5 m $D_2$ = $D_1$ but need not be taken greater than 20 m $L_1$ = $L$ but need not be taken greater than 190 m $F_s$ is a fatigue factor to be taken as follows: (a) For built sections and rolled angle bars $F_s = \frac{1,1}{k} \left[ 1 - \frac{2b_{f1}}{b_f} (1 - k) \right]$ at $0,6D_1$ above the base line = 1,0 at $D_1$ and above, and $F_{sb}$ at the base line intermediate values by linear interpolation $F_{sb}$ is a fatigue factor for bottom longitudinals = $0,5 (1 + F_s \text{ at } 0,6D_1)$ (b) For flat bars and bulb plates $\frac{b_{f1}}{b_f}$ may be taken as 0,5 where $b_{f1}$ = the minimum distance, in mm, from the edge of the face plate of the side longitudinal under consideration to the centre of the web plate, see Fig. 9.5.1 in Pt 4, Ch 9 $b_f$ = the width of the face plate, in mm, of the side longitudinal under consideration, see Fig. 9.5.1 in Pt 4, Ch 9 $D_1$ = $D$ but need not exceed $T + H_b$ , in metres, where $H_b$ is the minimum bow height, in metres, obtained from Ch 3,6.1	
$T_1$ = $T$ but not to be taken less than $0,65D_1$ $h_{T1} = f_w C_w \left( 1 - \frac{h_6}{D_1 - T_1} \right) F_\lambda$ , in metres, for longitudinals above the waterline at draught $T_1$ where $f_w \left( 1 - \frac{h_6}{D_1 - T_1} \right)$ is not to be taken less than 0,7 = $\left[ h_6 + f_w C_w \left( 1 - \frac{h_6}{2T_1} \right) \right] F_\lambda$ , in metres, for longitudinals below the waterline at draught $T_1$ where $f_w$ = 1,0 at $0,2L$ from A.P. and 1,32 at and aft of aft peak bulkhead. Intermediate positions by interpolation. $h_6$ = vertical distance, in metres, from the waterline at draught $T_1$ , to the longitudinal under consideration $C_w$ = a wave head, in metres = $7,71 \times 10^{-2} L e^{-0,0044L}$ where $e$ = base of natural logarithms 2,7183 $F_\lambda$ = 1,0 for $L \leq 200$ m = $[1,0 + 0,0023 (L - 200)]$ for $L > 200$ m	
NOTES	
1. Where struts are fitted midway between transverses in double skin construction, the modulus of the side longitudinals may be reduced by 50k per cent from that obtained for locations (2) and (3) as applicable.	
2. For modulus and area of side longitudinals in way of a machinery space, see Ch 7,3.1.	

## Aft End Structure

## Part 3, Chapter 6

Section 4

Table 6.4.2 Shell framing (transverse) aft



Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
(1) Frames in after peak spaces and lower 'tween decks over	$Z = 1,85s k T D_2 S_1 \times 10^{-3}$	$I = \frac{3,2}{k} S_1 Z$
(2) Frames in upper 'tween decks and poops aft of the after peak bulkhead, see Notes 1, 2 and 6	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1s k D_1 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(3) Main and 'tween deck frames (including poop) between the after peak bulkhead and 0,2L from the A.P., see Notes 1, 2 and 3	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1s k D_1 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(4) Main and 'tween deck frames elsewhere, see Notes 1, 2 and 3	As required in the midship region for the particular type of ship concerned	
(5) Panting stringers, see Note 4	Web depth, $d_w$ , same depth as frames Web thickness, $t = t_w$ as in Ch 10,4.4 Face area, $A = k S_2 (H + 1) \text{ cm}^2$	
Symbols		
<div><div><div><div><div><math>L, D, T, s, k</math></div><div>as defined in 1.4.1</div></div><div><div><math>D_1</math></div><div><math>= D</math> but need not exceed <math>T + H_b</math>, in metres, where <math>H_b</math> is the minimum bow height, in metres, obtained from Ch 3,6.1</div></div><div><div><math>D_2</math></div><div><math>= D_1</math> but is to be taken not greater than 16 m nor less than 6 m</div></div><div><div><math>H</math></div><div><math>= H_{MF}</math> or <math>H_{TF}</math> as applicable, see Note 3</div></div><div><div><math>H_{MF}</math></div><div><math>=</math> vertical framing depth, in metres, of main frames as shown in Fig. 6.4.1 but is not to be taken less than 3,5 m, see Note 5</div></div><div><div><math>H_{TF}</math></div><div><math>=</math> vertical framing depth, in metres, of 'tween deck frames as shown in Fig. 6.4.1, but is not to be taken less than 2,5 m</div></div><div><div><math>S_1</math></div><div><math>=</math> vertical spacing of peak stringers or height of lower 'tween deck above the peak, in metres, as applicable</div></div><div><div><math>S_2</math></div><div><math>=</math> vertical spacing of panting stringers, in metres</div></div><div><div><math>C</math></div><div><math>=</math> end connection factor</div></div><div><div></div><div><math>= 3,4</math> where two Rule standard brackets fitted</div></div><div><div></div><div><math>= 3,4 (1,8 - 0,8(l_a/l))</math> where one Rule standard bracket and one reduced bracket fitted</div></div><div><div></div><div><math>= 3,4 (2,15 - 1,15 (l_{amean}/l))</math> where two reduced brackets fitted</div></div><div><div></div><div><math>= 6,1</math> where one Rule standard bracket fitted</div></div><div><div></div><div><math>= 6,1 (1,2 - 0,2 (l_a/l))</math> where one reduced bracket fitted</div></div><div><div></div><div><math>= 7,3</math> where no brackets fitted</div></div><div><div></div><div>The requirements for frames where brackets larger than Rule standard are fitted will be specially considered</div></div><div><div><math>l</math></div><div><math>=</math> length, in mm, as derived from Pt 3, Ch 10,3.4.1</div></div></div><div><div><div><math>l_a</math></div><div><math>=</math> equivalent arm length, in mm, as derived from Pt 3, Ch 10,3.4.1</div></div><div><div><math>l_{amean}</math></div><div><math>=</math> mean equivalent arm length, in mm, for both brackets</div></div><div><div><math>T_1</math></div><div><math>= T</math> but not to be taken less than 0,65<math>D_1</math></div></div><div><div><math>h_{T1}</math></div><div><math>=</math> head, in metres, at mid length of <math>H</math></div></div><div><div></div><div><math>= f_w C_w \left(1 - \frac{h_6}{D_1 - T_1}\right) F_\lambda</math>, in metres for frames where the mid-length of frame is above the waterline, at draught <math>T_1</math></div></div><div><div></div><div><math>f_w \left(1 - \frac{h_6}{D_1 - T_1}\right)</math> is not to be taken less than 0,7</div></div><div><div></div><div><math>= \left[h_6 + f_w C_w \left(1 - \frac{h_6}{2T_1}\right)\right] F_\lambda</math>, in metres for frames where the mid-length of frame is below the waterline at draught <math>T_1</math></div></div><div><div>where</div><div></div></div><div><div><math>f_w</math></div><div><math>= 1,0</math> at 0,2L from A.P. and 1,32 at and aft of aft peak bulkhead Intermediate positions by interpolation.</div></div><div><div><math>h_6</math></div><div><math>=</math> vertical distance in metres from the waterline at draught <math>T_1</math> to the mid-length of <math>H</math></div></div><div><div><math>F_\lambda</math></div><div><math>= 1,0</math> for <math>L \leq 200</math> m</div></div><div><div></div><div><math>= [1,0 + 0,0023 (L - 200)]</math> for <math>L &gt; 200</math> m</div></div><div><div><math>C_w</math></div><div><math>=</math> a wave head in metres</div></div><div><div></div><div><math>= 7,71 \times 10^{-2} L e^{-0,0044L}</math></div></div><div><div></div><div>where <math>e =</math> base of natural logarithms 2,7183</div></div></div></div></div>		
NOTES		
1. In fishing vessels the modulus of main and 'tween deck frames need not be greater than 80 per cent of that given in (2).		
2. In offshore supply ships the moduli of main and 'tween deck frames are to be 25 per cent greater than those given in (2), (3) and (4).		
3. Where frames are inclined at more than 15° to the vertical, $H_{MF}$ or $H_{TF}$ is to be measured along a chord between span points of the frame.		
4. Panting stringers are not required in tugs less than 46 m in length, see Pt 4, Ch 3,4.		
5. Where the frames are supported by fully effective horizontal stringers, these may be considered as decks for the purpose of determining $H_{MF}$ .		
6. Except for main frames the modulus for these members need not exceed that derived from (1) using $H_{TF}$ in place of $S_1$ .		

4.3.2 The scantlings of main frames are normally to be based on Rule standard brackets at top and bottom, whilst the scantlings of 'tween deck frames are normally to be based on a Rule standard bracket at the top only.

4.3.3 End connections of transverse main and 'tween deck frames are to be in accordance with Ch 10,3. For bulk carriers (see 1.1.4), the end connections of main frames in cargo holds are to be in accordance with Pt 4, Ch 7,6.2.5 to 6.2.12.

#### 4.4 Panting stringers in way of transverse framing

4.4.1 In deep 'tween decks above the after peak space, panting stringers having scantlings as given in Table 6.4.2 or increased shell plate thickness may be required, see also 3.4.2.



4.5 Primary structure at sides

4.5.1 Where the 'tween decks above an after peak space are transversely framed, web frames are to be fitted. Their spacing is generally not to exceed the values given in Table 6.4.3, and their scantlings are to be determined from Table 6.4.4.

4.5.2 Where longitudinal framing is arranged, the spacing of transverses is generally not to exceed the values given in Table 6.4.3, and their scantlings are to be determined from Table 6.4.4.

4.5.3 Where the shape of the after sections is such that there are large sloped flat areas, particularly in the vicinity of the propellers, additional primary supports for the secondary stiffening may be required. Their extent and scantlings will be specially considered.

4.5.4 The web thickness, stiffening arrangements and connections of primary supporting members are to be in accordance with the requirements of Ch 10,4.

Table 6.4.3 Spacing of side transverses and web frames aft

Location	Maximum spacing	
	Web frames in association with transverse framing system	Side transverses in association with longitudinal framing system
(1) Aft of the after peak bulkhead	4 frame spaces	2,5 m where $L \leq 100$ m 3,5 m where $L \geq 300$ m Intermediate values by interpolation
(2) Elsewhere in way of dry cargo spaces or deep tanks, see Note	—	3,8 m where $L \leq 100$ m (0,006L + 3,2) m where $L > 100$ m
(3) In way of cargo tanks of oil tankers, chemical tankers or ore or oil carriers	—	3,6 m where $L \leq 180$ m 0,02L where $L > 180$ m
NOTE For the maximum spacing of transverses in dredgers, see Pt 4, Ch 12,5.		

## Aft End Structure

## Part 3, Chapter 6

Section 4

Table 6.4.4 Primary structure aft

Item and location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
Longitudinal framing system		
(1) Side transverses in dry spaces aft of the after peak bulkhead, see Note 4: (a) Lower space (b) 'Tween deck	$Z = 10 k S h_{T1} l_e^2$ $Z = C_2 k S T H_{TF} \sqrt{D}$	—
(2) Side transverses in tanks aft of the after peak bulkhead, see Note 4: (a) Lower space (b) 'Tween decks	$Z = 11,7 p k S h_4 l_e^2$ $Z = 14,1 p k S h_4 l_e^2$ or as (1) above, whichever is the greater	$I = \frac{2,5}{k} l_e Z$
(3) Side transverses in dry spaces and deep tanks forward of the after peak bulkhead	As in Pt 4, Ch 1,6, see Notes 1 and 2	
Transverse framing system		
(4) Side stringers supported by webs in after peak dry space, see Note 3	$Z = 7,75 k S h_{T1} l_e^2$	—
(5) Side stringers supported by webs in after peak tank, see Note 3	$Z = 11,7 p k S h_4 l_e^2$ or as (4) above, whichever is the greater	$I = \frac{2,5}{k} l_e Z$
(6) Web frames supporting side stringers in after peak, see Note 3	Z to be determined from the calculations based on following assumptions: (a) Fixed ends (b) Point loadings from stringers (c) Head $h_4$ or $h_{T1}$ as applicable  (d) Bending stress $\frac{93,2}{k}$ N/mm <sup>2</sup> $\left(\frac{9,5}{k}$ kgf/mm <sup>2</sup> )  (e) Shear stress $\frac{83,4}{k}$ N/mm <sup>2</sup> $\left(\frac{8,5}{k}$ kgf/mm <sup>2</sup> )	In deep tanks  $I = \frac{2,5}{k} l_e Z$
(7) Web frames in 'tween decks aft of the after peak bulkhead not supporting side stringers	$Z = C_3 k S T H_{TF} \sqrt{D}$	—
(8) Side stringers and web frames in dry spaces and deep tanks forward of the after peak bulkhead	As in Pt 4, Ch 1,6, see Notes 1 and 2	
Symbols		
$D, T, S, l_e, k, p$ as defined in 1.4.1 $C_2, C_3$ = factors obtained from Fig. 6.4.2 $h_4$ = tank head, in metres, as defined in Ch 3,5 $h_{T1}$ = head, in metres, at mid-length of span  $= f_w C_w \left(1 - \frac{h_6}{D_1 - T_1}\right) F_\lambda$ , in metres where the mid-length of span is above the waterline at draught $T_1$  where $f_w \left(1 - \frac{h_6}{D_1 - T_1}\right)$ is not to be taken less than 0,7  $= \left[h_6 + f_w C_w \left(1 - \frac{h_6}{2T_1}\right)\right] F_\lambda$ , in metres where the mid-length of span is below the waterline at draught $T_1$	where $f_w$ = 1,0 at 0,2L from A.P. and 1,32 at and aft of aft peak bulkhead. Intermediate positions by interpolation $h_6$ = vertical distance, in metres, from the waterline at draught $T_1$ to the mid-length of span $F_\lambda$ = 1,0 for $L \leq 200$ m = $[1,0 + 0,0023 (L - 200)]$ for $L > 200$ m $C_w$ = a wave head, in metres = $7,71 \times 10^{-2} L e^{-0,0044L}$ where e = base of natural logarithms 2,7183 $D_1$ = $D$ but need not be taken greater than $T + H_b$ , in metres, where $H_b$ is the minimum bow height, in metres, obtained from Ch 3,6.1 $T_1$ = $T$ but not to be taken less than $0,65D_1$ $H_{TF}$ = vertical height of 'tween decks, in metres, as shown in Fig. 6.4.1	
NOTES		
1. In way of the cargo tanks or oil fuel tanks of oil tankers or ore carriers, the scantlings of primary structure are to comply with the requirements of Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate. 2. For bulk carriers, see Pt 4, Ch 7,6. 3. For stringers and webs in after peaks, see also 6.2. 4. The web depth of side transverses aft of the after peak bulkhead is to be not less than 2,5 times the depth of the longitudinals supported. The web depth of stringers is to be not less than 2,2 times the depth of frames supported.		

# Aft End Structure

# Part 3, Chapter 6

Sections 5 & 6

## Section 5 Single and double bottom structure

### 5.1 General

5.1.1 For dry cargo ships exceeding 120 m in length, and for all ships which are strengthened for heavy cargoes, longitudinal framing is, in general, to be adopted, see *also* Pt 4, Ch 9,1.3.

5.1.2 For ships having the notation 'strengthened for heavy cargoes', the requirements of Pt 4, Ch 7,8 are also to be complied with, as applicable.

5.1.3 For ships intended to load or unload while aground, see Pt 3, Ch 9,13.

5.1.4 Provision is to be made for the free passage of water and/or air from all parts of single or double bottoms to the bilge or tank suction, account being taken of the pumping rates required.

5.1.5 For passenger ships, see Pt 4, Ch 2,6.

### 5.2 Single bottoms – Transverse framing

5.2.1 In after peak spaces, floors are to be arranged at every frame. For details and scantlings, see 6.1.

5.2.2 In way of dry cargo spaces aft, the arrangement and scantlings of transversely framed single bottoms are to be generally as required in the midship region, as given in Pt 4, Ch 1,7, except that the thickness of the centreline girder may be tapered from the midship thickness at 0,3L from the A.P. to  $t = (\sqrt{Lk} + 0,5)$  mm or 6 mm, whichever is the greater, at 0,075L from the A.P. In ships having considerable rise of floor towards the aft end, the depth of the floors may be required to be increased.

5.2.3 Where the shape of the after sections is such that there are large flat areas of shell plating, additional stiffening and/or increased shell plate thickness may be required, see 3.3. The extent of this stiffening will be specially considered.

### 5.3 Single bottoms – Longitudinal framing

5.3.1 The scantlings and arrangement of longitudinally framed single bottoms in way of dry cargo spaces will be specially considered.

### 5.4 Double bottoms

5.4.1 The minimum depth of centre girder aft is generally to be the same as that required in the midship region by Part 4 for the particular type of ship concerned, but in ships with considerable rise of floor a greater depth may be required at the aft end to provide adequate access throughout the double bottom tank.

5.4.2 Where the height of the double bottom varies, this variation is generally to be made gradual by sloping the inner bottom over an adequate longitudinal extent. Knuckles in the plating are to be arranged close to plate floors. Otherwise, suitable scarfing arrangements are to be made.

5.4.3 For dry cargo ships, the arrangement and scantlings of girders, floors, inner bottom plating and inner bottom stiffening in the aft end region are to be determined from Pt 4, Ch 1,8.

5.4.4 For double bottom construction in way of the cargo tanks of oil tankers or ore carriers, see *also* Pt 4, Ch 9, Ch 10 or Ch 11, as appropriate.

## Section 6 After peak structure

### 6.1 Bottom structure

6.1.1 Floors are to be arranged at every frame space and are to be carried to a suitable height, and at least to above the sterntube, where fitted. They are to have a thickness as determined from Table 6.6.1 and are to be adequately stiffened. In way of a propeller post, rudder post or rudder horn, the floors are generally to be carried to the top of the space and are to be increased in thickness. The extent and amount of the increase will be specially considered, account being taken of the arrangements proposed.

### 6.2 Side structure – Transverse framing

6.2.1 Above the floors, transverse side framing is to be supported by one of the following arrangements:

- (a) Side stringers spaced not more than 2,5 m apart and supported by web frames. The upper ends of the web frames are to be supported under the tank top by suitable deep beams to form a ring structure.
- (b) Perforated flats spaced not more than 2,5 m apart. The area of perforations in each flat is to be not less than 10 per cent of the total area of the flat.
- (c) A combination of the above arrangements.

6.2.2 The scantlings of side stringers supported by web frames, and also of the web frames are to be determined from 4.5.

6.2.3 The scantlings of perforated flats are to be determined from Table 6.6.1. Stiffeners are to be fitted at every frame.

### 6.3 Side structure – Longitudinal framing

6.3.1 The spacing and scantlings of side transverses supporting longitudinal framing are to be as required by 4.5.

6.3.2 Suitable transverses or deep beams are to be arranged at the top of the tank to provide end rigidity to the side transverses.



## Aft End Structure

## Part 3, Chapter 6

Sections 6 &amp; 7

Table 6.6.1 After peak structure

Item	Parameter	Requirement
(1) Floors	Thickness	$t = (7,5 + 0,025L_2) \sqrt{\frac{s_2}{800}} \text{ mm}$
(2) Perforated flats and wash bulkheads	Thickness, see Note	$t = (7,5 + 0,015L) \sqrt{\frac{s_2}{800}} \text{ mm}$
	Stiffener modulus	$z = \frac{0,0057 s k h_6 l_e^2}{b} \text{ cm}^3$
Symbols		
$L, s, l_e, k$ as defined in 1.4.1 $b = 1,4$ for rolled or built sections $= 1,6$ for flat bars $h_6 =$ vertical distance from middle of effective length of stiffener to top of tank, in metres		
$s_2 =$ spacing of stiffeners, in mm, but is to be taken not less than 800 mm $L_2 = L$ but need not be taken greater than 215 m		
<b>NOTE</b> The thickness for perforated flats and wash bulkheads may be reduced by 1 mm for ships of 40 m and under with no reduction for ships of 90 m and above. Reduction for intermediate lengths to be by linear interpolation.		

## 6.4 Wash bulkheads

6.4.1 A centreline wash bulkhead is to be arranged in the upper part of the after peak space and counter or cruiser stern. Where the overhang is very large, or the breadth of the space at the widest point exceeds 20 m, additional wash bulkheads may be required port and starboard.

6.4.2 Wash bulkheads are to have an area of perforations not less than 5 per cent nor more than 10 per cent of the area of the bulkhead. The plating is to be suitably stiffened in way of openings, and the arrangement of openings is to be such as to maintain adequate shear rigidity.

6.4.3 The scantlings of wash bulkheads are to be determined from Table 6.6.1, and stiffeners are to be fitted at every frame and bracketed top and bottom. The plating thickness may be required to be increased locally in way of the upper part of the sternframe or the rudder horn.

## 6.5 After peak bulkhead

6.5.1 The position and height of the after peak bulkhead are to be in accordance with the requirements of Ch 3,4.

6.5.2 The scantlings of the after peak bulkhead and of the flat forming the top of the peak space are to be determined from Pt 4, Ch 1,9, but the plating thickness is to be increased locally in way of the sterntube gland.

7.1.2 In castings, sudden changes of section or possible constrictions to the flow of metal during casting are to be avoided. All fillets are to have adequate radii, which should, in general, be not less than 50 to 75 mm, depending on the size of the casting.

7.1.3 Castings and forgings are to comply with the requirements of Chapter 4 and Chapter 5 of the Rules for Materials (Part 2) respectively.

7.1.4 Cast sternframes, rudder horns and solepieces are to be manufactured from special grade material. Cast bossings can be manufactured from normal grade material, see Ch 4,2 of the Rules for Materials (Part 2).

7.1.5 Sternframes, rudder horns, shaft brackets, etc., are to be effectively integrated into the ship's structure, and their design is to be such as to facilitate this.

## 7.2 Sternframes

7.2.1 The scantlings of sternframes are to be determined from Table 6.7.1. In the case of very large ships, the scantlings and arrangements may be required to be verified by direct calculations.

7.2.2 Fabricated and cast propeller posts and rudder posts of twin screw ships are to be strengthened at intervals by webs. In way of the upper part of the sternframe arch, these webs are to line up with the floors.

7.2.3 Rudder posts and propeller posts are to be connected to floors of increased thickness, see 6.1.

7.2.4 The sole piece is to be dimensioned such that the stresses do not exceed the permissible stresses given in Table 6.7.2.

## Section 7

### Sternframes and appendages

## 7.1 General

7.1.1 Sternframes, rudder horns, boss end brackets and shaft brackets may be constructed of cast or forged steel, or may be fabricated from plate.

# Aft End Structure

# Part 3, Chapter 6

Section 7

**Table 6.7.1 Sternframes** (see continuation)

Item	Parameter	Requirement		
(1) Propeller posts see Notes 1 and 2		Cast steel, see Fig. 6.7.1(a)	Forged steel, see Fig. 6.7.1(b)	Fabricated mild steel, see Fig. 6.7.1(c)
	$l$	$165\sqrt{T}$ mm	—	$200\sqrt{T}$ mm
	$r$	$20\sqrt{T}$ mm	—	$18\sqrt{T}$ mm
	$t_w$	$8\sqrt{T}$ mm (need not exceed 38)	—	$6\sqrt{T}$ mm (need not exceed 30)
	$t_1$	$12\sqrt{T}$ mm (min. 19)	—	$12\sqrt{T}$ mm
	$t_2$	$16\sqrt{T}$ mm (min. 25)	—	—
	$w$	$115\sqrt{T}$ mm	$40\sqrt{T}$ mm	$140\sqrt{T}$ mm
	$A$	—	$\left\{ \begin{array}{l} (10 + 0,5L)T \text{ cm}^2 \text{ where } L \leq 60 \text{ m} \\ 40T \text{ cm}^2 \text{ where } L > 60 \text{ m} \end{array} \right\}$	—
(2) Propeller boss, see Note 3 and Fig. 6.7.2	$t_b$	$(0,1\delta_{TS} + 56)$ mm, but need not exceed $0,3 \delta_{TS}$		
(3) Rudder posts or axles		Single screw with integral solepiece, see Fig. 6.7.5(a)	Single screw with bolted rudder axle, see Fig. 6.7.3	Twin screw, integral with hull, see Fig. 6.7.4
	$n$	—	6 (see Note 4)	—
	$r$	—	—	$20\sqrt{T}$ mm
	$r_b$	—	$\delta_A$ mm	—
	$t_F$	—	$\delta_b$ mm	—
	$t_1$	—	—	$12\sqrt{T}$ mm
	$t_2$	—	—	$15\sqrt{T}$ mm
	$t_3$	—	—	$18\sqrt{T}$ mm
	$w$	—	—	$120\sqrt{T}$ mm
	$Z_{PB1}, Z_{PB2}$	—	$1,2\delta_{PL2}$ mm	—
	$Z_T$	$0,147 \left( \frac{k_R}{0,248} \right)^3 A_R c_2 b (V_0 + 3)^2 \text{ cm}^3$	—	—
	$\delta_A$	—	$(25T + 76)$ mm but need not exceed $0,9\delta_{PL2}$ mm	—
	$\delta_b$	—	$6,25T + 19$ mm or $0,225\delta_{PL2}$ mm whichever is the greater	—
	$\delta_{PL1}, \delta_{PL2}$ bearing pressure and pintle clearance	—	$\left\{ \begin{array}{l} \text{As for rudder pintles} \\ \text{(see Table 13.2.11 in Chapter 13)} \end{array} \right\}$	—
(4) Solepieces, see Notes 5, 6 and 7	$Z_T$	$0,0125M_b K_O$		
	$Z_V$	$0,5Z_T$		
	$A_S$	$0,02B_1 K_O$		

## Aft End Structure

## Part 3, Chapter 6

Section 7

**Table 6.7.1 Sternframes (conclusion)**

Symbols	
$L, T$ as defined in 1.4.1 $a, b, c$ = distances, in metres, as shown in Fig. 6.7.5 $B_1$ = see Table 6.7.2 $c_2$ = rudder profile coefficient, as given by Table 13.2.1 in Chapter 13 $n$ = number of bolts in palm coupling $r_b$ = mean distance of bolt centres from centre of palm, in mm $t_b$ = finished thickness of boss, in mm $M_B$ = see Table 6.7.2 $A$ = cross-sectional area of forged steel propeller post, in cm <sup>2</sup> $A_R$ = rudder area, in m <sup>2</sup>	$k_R$ = rudder coefficient, as given by Table 6.7.4 $V$ = maximum service speed, in knots, with the ship in the loaded condition $Z_T$ = section modulus against transverse bending, in cm <sup>3</sup> $Z_V$ = section modulus against vertical bending, in cm <sup>3</sup> $\delta_b$ = diameter of coupling bolts, in mm $\delta_{TS}$ = diameter of tail shaft, in mm $K_O$ = as defined in 7.3.3 $A_s$ = sectional area, in mm <sup>2</sup>
<b>NOTES</b> 1. Where scantlings and proportions of the propeller post differ from those shown in Item (1), the section modulus about the longitudinal axis of the proposed section normal to the post is to be equivalent to that with Rule scantlings. $t$ is to be not less than $8\sqrt{T}$ (minimum of 19 mm for cast steel sternframes) or as required by Ch 6,3.4.2, whichever is the greater. 2. On sternframes without solepieces, the modulus of the post below the propeller boss, about the longitudinal axis may be gradually reduced to not less than 85% of that required by Note 1, subject to the same thickness limitations. 3. In fabricated sternframes the connection of the propeller post to the boss is to be by full penetration welds. 4. If more than six bolts are fitted, the arrangements are to provide equivalent strength. 5. In fabricated solepieces, transverse webs are to be fitted spaced not more than 760 mm apart. Where the breadth of the solepiece exceeds 900 mm, a centreline vertical web is also to be fitted. 6. Solepieces supporting fixed or movable nozzles will be specially considered, see Ch 13,3.2. 7. For dredging and reclamation craft classed 'A1 protected waters service', the scantlings of an 'open' type solepiece are to be such that: (a) $Z_T = 0,625Z_T$ (b) The cross-sectional area is not less than 18 cm <sup>2</sup> (c) The depth is not less than two-thirds of the width at any point.	

**Table 6.7.2 Permissible stresses for sole pieces**

Mode	Permissible stress
(1) Equivalent stress	$115/K_O$ N/mm <sup>2</sup> $(11,7/K_O)$ kgf/mm <sup>2</sup>
Symbols	
$\sigma_e$ = equivalent stress $= \sqrt{\sigma_b^2 + 3\tau_T^2}$ N/mm <sup>2</sup> $\sigma_b$ = bending stress $= \frac{M_B}{Z_T}$ N/mm <sup>2</sup> $\tau_T$ = shear stress $= \frac{B_1}{A_s}$ N/mm <sup>2</sup> $K_O$ = as defined in 7.3.3 $M_B$ = bending moment, in Nm, at the section considered $= B_1 x$ $B_1$ = supporting force, in N, in pintle bearing $= 0,5P_L$ $P_L$ = rudder force, in N, as calculated in Ch 13,2 $x$ = distance, in metres, from centre of rudder stock to section under consideration $Z_T$ = see Table 6.7.1(4) $A_s$ = sectional area, in mm <sup>2</sup> , of solepiece	

7.3.2 The shell plating is to be increased in thickness in way of the horn. Where the horn plating is radiused into the shell plating, the radius at the shell connection is to be not less than:

$$r = (150 + 0,8L) \text{ mm}$$

7.3.3 The scantlings of the rudder horn are to be such that the section modulus against transverse bending at any section is not less than:

$$Z_T = 0,015M_B K_O \text{ cm}^3$$

where

$$M_B = \text{bending moment} \\ = B_{1L} z \text{ Nm}$$

$$B_{1L} = \text{as calculated in Table 13.2.11 in Ch 13,2}$$

$$z = \text{see Fig. 6.7.6}$$

$$K_O = k_O \text{ see Table 13.2.4 in Ch 13,2 for cast steel}$$

$$K_O = k = 1,0 \text{ for fabricated mild steels}$$

$$= k = 0,78 \text{ for high tensile steels with yield stress}$$

$$\sigma_o = 315 \text{ N/mm}^2$$

$$= k = 0,72 \text{ for high tensile steels with yield stress}$$

$$\sigma_o = 355 \text{ N/mm}^2.$$

7.3.4 The rudder horn is to be dimensioned such that the stresses do not exceed the permissible stresses given in Table 6.7.3.

**7.3 Rudder horns**

7.3.1 Rudder horns supporting semi-spade type rudders are to be efficiently integrated into the main hull structure, and additional web frames or side transverses may be required in the 'tween deck over.

## Aft End Structure

## Part 3, Chapter 6

Section 7

Table 6.7.3 Permissible stresses for rudder horns

Mode	Permissible stress
(1) Shear stress	$48/K_o$ N/mm <sup>2</sup> (4,9/ $K_o$ kgf/mm <sup>2</sup> )
(2) Equivalent stress	$120/K_o$ N/mm <sup>2</sup> (12/ $K_o$ kgf/mm <sup>2</sup> )
Symbols	
$\sigma_e$ = equivalent stress $= \sqrt{\sigma_b^2 + 3(\tau^2 + \tau_T^2)}$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	
$\sigma_b$ = bending stress $= \frac{M_B}{Z_T}$ N/mm <sup>2</sup>	
$\tau$ = shear stress $= \frac{B_{1L}}{A_h}$ N/mm <sup>2</sup>	
$\tau_T$ = torsional stress $= \frac{10^3 M_T}{2A_T t_h}$ N/mm <sup>2</sup>	
$A_h$ = effective shear area, in mm <sup>2</sup> , of rudder horn in y-direction $A_T$ = area in the horizontal section enclosed by the rudder horn, in mm <sup>2</sup> $B_{1L}$ = as calculated in Table 13.2.11 in Ch 13,2 $K_o$ = as defined in 7.3.3 $M_B$ = bending moment at the section considered, in Nm $= B_{1L} z$ $M_T$ = torsional moment at the section considered, in Nm $= B_{1L} e$ $t_h$ = plate thickness of rudder horn, in mm $e$ = see Fig. 6.7.6 $z$ = see Fig. 6.7.6 $Z_T$ = see 7.3.3	

Table 6.7.4 Rudder coefficient  $k_R$ 

Design criteria		$k_R$
Ahead condition	Rudder in propeller slipstream	0,248
	Rudder out of propeller slipstream	0,235
Astern condition		0,185
Bow rudder		0,226
Barge – non self-propelled		

## 7.4 Shaft bossing



7.4.1 Where the propeller shafting is enclosed in bossings extending back to the bearings supporting the propellers, the aft end of the bossings and the bearings are to be supported by substantially constructed boss end castings or fabrications. These are to be designed to transmit the loading from the shafting efficiently into the ship's internal structure.

7.4.2 For shaft bossings attached to shaft brackets, the length of the boss is to be adequate to accommodate the aftermost bearing and to allow for proper connection of the shaft brackets.

7.4.3 Cast steel supports are to be suitably radiused where they enter the main hull to line up with the boss plating radius. Where the hull sections are narrow, the two arms are generally to be connected to each other within the ship. The arms are to be strengthened at intervals by webs.

Table 6.7.5 Recommended propeller/hull clearances

Number of blades	Hull clearances for single screw, in metres, see Fig. 6.7.7(a)				Hull clearances for twin screw, in metres, see Fig. 6.7.7(b)	
	<i>a</i>	<i>b</i>	<i>c</i>	<i>d</i>	<i>e</i>	<i>f</i>
3	1,20 <i>Kδ</i>	1,80 <i>Kδ</i>	0,12 <i>δ</i>	0,03 <i>δ</i>	1,20 <i>Kδ</i>	1,20 <i>Kδ</i>
4	1,00 <i>Kδ</i>	1,50 <i>Kδ</i>	0,12 <i>δ</i>	0,03 <i>δ</i>	1,00 <i>Kδ</i>	1,20 <i>Kδ</i>
5	0,85 <i>Kδ</i>	1,275 <i>Kδ</i>	0,12 <i>δ</i>	0,03 <i>δ</i>	0,85 <i>Kδ</i>	0,85 <i>Kδ</i>
6	0,75 <i>Kδ</i>	1,125 <i>Kδ</i>	0,12 <i>δ</i>	0,03 <i>δ</i>	0,75 <i>Kδ</i>	0,75 <i>Kδ</i>
Minimum value	0,10 <i>δ</i>	0,15 <i>δ</i>	<i>t<sub>R</sub></i>	—	3 and 4 blades, 0,20 <i>δ</i> 5 and 6 blades, 0,16 <i>δ</i>	0,15 <i>δ</i>
Symbols						
<i>L</i> as defined in 1.4.1 <i>C<sub>b</sub></i> = moulded block coefficient at load draught $K = \left(0,1 + \frac{L}{3050}\right) \left(\frac{3,48C_b P}{L^2} + 0,3\right)$ $\left(K = \left(0,1 + \frac{L}{3050}\right) \left(\frac{2,56C_b P}{L^2} + 0,3\right)\right)$				<i>t<sub>R</sub></i> = thickness of rudder, in metres, measured at 0,7 <i>R<sub>p</sub></i> above the shaft centreline <i>P</i> = designed power on one shaft, in kW (shp) <i>R<sub>p</sub></i> = propeller radius, in metres <i>δ</i> = propeller diameter, in metres		
NOTE The above recommended minimum clearances also apply to semi-spade type rudders.						



7.4.4 Fabricated supports are to be carefully designed to avoid or reduce the effect of hard spots. Continuity of the arms into the ship is to be maintained, and they are to be attached to substantial floor plates or other structure. The connection of the arms to the bearing boss is to be by full penetration welding.

7.4.5 The scantlings of supports will be specially considered. In the case of certain high powered ships, direct calculations may be required.

7.4.6 The boss plating is generally to be radiused into the shell plating and supported at the aft end by diaphragms at every frame. These diaphragms are to be suitably stiffened and connected to floors or a suitable arrangement of main and deep web frames. At the forward end, the main frames may be shaped to fit the bossing, but deep webs are generally to be fitted not more than four frame spaces apart.

## 7.5 Shaft brackets

7.5.1 Where the propeller shafting is exposed to the sea for some distance clear of the main hull, it is generally to be supported adjacent to the propeller by independent brackets having two arms. In very small ships, the use of single arm brackets will be considered.

7.5.2 Fabricated brackets are to be designed to avoid or reduce the effect of hard spots and ensure a satisfactory connection to the hull structure. The connection of the arms to the bearing boss is to be by full penetration welding.




Fig. 6.7.3 Rudder axle




Fig. 6.7.4 Rudder post for twin screw ships

7.5.3 Where bracket arms are carried through the shell plating, they are to be attached to floors or girders of increased thickness. The shell plating is to be increased in thickness and connected to the arms by full penetration welding.




Fig. 6.7.5 Solepieces





Fig. 6.7.6 Rudder horn

7.5.4 The scantlings of shaft brackets will be specially considered and, in the case of certain high powered ships, direct calculations may be required.

7.5.5 The region where the shafting enters the ship, and the bearing in way, is to be adequately supported by floors or deep webs.



## 7.6 Propeller hull clearances

7.6.1 Recommended minimum clearances between the propeller and the sternframe, rudder or hull are given in Table 6.7.3. These are the minimum distances considered desirable in order to expect reasonable levels of propeller excited vibration. Attention is drawn to the importance of the local hull form characteristics, shaft power, water flow characteristics into the propeller disc and cavitation when considering the recommended clearances.





# Machinery Spaces

# Part 3, Chapter 7

Sections 1 & 2

## Section

- 1 **General**
- 2 **Deck structure**
- 3 **Side shell structure**
- 4 **Double and single bottom structure**
- 5 **Machinery casings and oil fuel bunkers**
- 6 **Engine seatings**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to all ship types detailed in Part 4. Only requirements particular to machinery spaces, including protected machinery casings and engine seatings, are given. For other scantlings and arrangement requirements, see the relevant Chapter in Part 4 for the particular ship type concerned.

1.1.2 Requirements are given for machinery spaces situated as follows:

- (a) In the midship region.
- (b) In the aft end region but with a cargo compartment between it and the after peak bulkhead.
- (c) In the aft end region where the after peak bulkhead forms the aft end of the machinery space.

1.1.3 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation. See Pt 1, Ch 2,2.3.

### 1.2 Structural configuration

1.2.1 Requirements are given for ships constructed using either a transverse framing system or a longitudinal framing system, or a combination of the two.

1.2.2 For midship machinery spaces, where the shell and decks (outside line of openings) are longitudinally framed in way of adjacent cargo spaces, this system of framing is also to be adopted in the machinery space.

1.2.3 For machinery spaces situated aft, where the longitudinal framing terminates and is replaced by transverse framing, a suitable scarfing arrangement of the longitudinal framing is to be arranged, see also Ch 6,1.

1.2.4 The maximum spacing,  $S_{\max}$ , of transverses in longitudinally framed machinery spaces is not to exceed the following:

- (a) where  $L \leq 100$  m,  $S_{\max} = 3,8$  m
- (b) where  $L > 100$  m,  $S_{\max} = (0,006L + 3,2)$  m

In addition, the spacing in way of a machinery space situated adjacent to the after peak is not to exceed five transverse frame spaces.

### 1.3 Structural continuity

1.3.1 Suitable scarfing arrangements are to be made to ensure continuity of strength and the avoidance of abrupt discontinuities where structure which contributes to the main longitudinal strength of the ship is omitted in way of a machinery space.

1.3.2 In cargo ships, suitable taper brackets are, in general, to be arranged in way of deck ends.

1.3.3 In oil tankers and bulk carriers with machinery aft (see 1.1.3), continuity of the longitudinal bulkheads and topside tank structure is to be maintained as far as possible into the machinery space with suitable taper brackets at the end.

1.3.4 In container or similar ships having side tanks or double skin construction in way of the cargo spaces, the longitudinal bulkheads are generally to be carried through the machinery space where this is situated amidships or separated from the after peak by a cargo compartment. Where the machinery space is situated adjacent to the after peak, the longitudinal bulkheads are to be continued as far aft as possible and suitably tapered at their ends.

### 1.4 Symbols and definitions

1.4.1 For symbols not defined in this Chapter, see Pt 4, Ch 1.  $L$ ,  $B$ ,  $D$  and  $T$  are defined in Ch 1,6.1. Other symbols are defined in the appropriate Sections.

## ■ Section 2 Deck structure

### 2.1 Strength deck – Plating

2.1.1 The corners of machinery space openings are to be of suitable shape and design to minimize stress concentrations.

2.1.2 In the case of oil tankers (see 1.1.3), or other ships having small deck openings amidships and machinery aft, where the width of machinery openings exceeds  $\frac{B}{2}$  and the opening extends forward beyond a point  $\frac{B}{3}$  aft of the poop front, the thickness of deck plating may be required to be increased locally.

# Machinery Spaces

# Part 3, Chapter 7

Sections 2 & 3

## 2.2 Strength deck – Primary structure

2.2.1 Where a transverse framing system is adopted, deck beams are to be supported by a suitable arrangement of longitudinal girders in association with pillars or pillar bulkheads. Deep beams are to be arranged in way of the ends of engine casings and also in line with web frames where fitted.

2.2.2 Where a longitudinal framing system is adopted, deck longitudinals are to be supported by transverses in association with pillars or pillar bulkheads. For the maximum spacing of transverses, see 1.2.4. Deck transverses are to be in line with side transverses or web frames.

2.2.3 Machinery casings are to be supported by a suitable arrangement of deep beams or transverses and longitudinal girders in association with pillars or pillar bulkheads. In way of particularly large machinery casing openings, cross ties may be required, and these are to be arranged in line with deep beams or transverses.

## 2.3 Lower decks

2.3.1 The scantlings of lower decks or flats are generally to be as detailed in Ch 5,2, Ch 6,2 or Pt 4, Ch 1,4 as appropriate. However, in way of concentrated loads such as those from boiler bearers or heavy auxiliary machinery, etc., the scantlings of deck structure will be specially considered, taking account of the actual loading.

2.3.2 In way of machinery openings, etc., particularly towards the aft end, decks or flats are to have sufficient strength where they are intended as effective supports for side framing, webs or transverses. Web frames and side transverses are to be supported by deep beams or deck transverses.

## Section 3 Side shell structure

### 3.1 Secondary stiffening

3.1.1 Transverse frames are generally to have scantlings determined as required by Pt 4, Ch 1,6 for cargo spaces, except that where, in a machinery space situated in the midship region, it is desired to omit web frames as permitted by 3.2.3, the section modulus of the ordinary main or 'tween deck frames is to be increased by 50 per cent, up to the level of the lowest deck above the load waterline. Where fully effective stringers supported by web frames are fitted, the stringers may be considered as decks for the purpose of calculating the modulus of the frames.

3.1.2 Longitudinal framing is generally to have scantlings determined as required by Pt 4, Ch 1,6 for machinery spaces in the midship region, and by Table 6.4.1 Location 2(b) in Chapter 6 for machinery spaces clear of and aft of the midship region.

## 3.2 Primary structure – Transverse framing

3.2.1 Where the space is situated in the aft end region, web frames are to be fitted, spaced in general not more than five frame spaces apart, extending from the tank top to the upper deck and having scantlings as required by Table 7.3.1. However, consideration will be given to a spacing of web frames at not more than seven transverse frame spaces apart, in association with substantially increased ordinary frames to satisfy the overall modulus and inertia requirements. The web frames are to be connected at top and bottom to members of adequate stiffness and supported at lower decks by deep beams. If the span of ordinary frames below the lowest deck or flat exceeds 6,5 m, one or more fully effective side stringers are to be fitted to support the frames. These are to have scantlings as required by Table 7.3.1. Stringers are to be efficiently bracketed to bulkheads, and their connection to the web frames is to be such as to provide adequate continuity of face material.

3.2.2 As an alternative to the fully effective stringers required by 3.2.1, an arrangement of light stringers spaced about 2,5 m apart may be accepted. These stringers are to have scantlings not less than those required in the panting region forward, see Ch 5,4.4.

3.2.3 Where the machinery space is situated in the midship region, it is recommended that web frames be fitted in the engine-room, spaced not more than five frame spaces apart and extending from the tank top to the level of the lowest deck above the load waterline. The scantlings of these webs are to be such that the combined section modulus of the web frame and the main or 'tween deck frames is 50 per cent greater than that required for normal transverse framing. These webs may be omitted if the section modulus of the transverse frames is increased as required by 3.1.1.

3.2.4 If an effective side stringer supporting the side frames is fitted, then its scantlings and those of the supporting web frames are to be determined from Table 7.3.1.

## 3.3 Primary structure – Longitudinal framing

3.3.1 Where the machinery space is longitudinally framed, side transverses are to be fitted having scantlings as required by Table 7.3.1. For the maximum spacing of transverses, see 1.2.4. Transverses are to be connected at top and bottom to members of adequate stiffness and supported at lower decks by transverses or deep beams.

# Machinery Spaces

## Part 3, Chapter 7

Sections 3 &amp; 4

**Table 7.3.1 Primary structure in machinery spaces**

Symbols	Item and position	Scantlings	
		Section modulus, in cm <sup>3</sup>	Min. web depth $d_w$ , in mm
$L$ , $D$ and $T$ are as defined in Ch 1,6.1 $h$ = load head, in metres, measured from mid-point of span to upper deck at side amidships $k$ = higher tensile and steel factor, see Ch 2, 1.2 $l_e$ = effective length of stiffening member, in metres, see Ch 3,3.3 $s$ = spacing of floors and longitudinals, in mm $C$ = 2,2 for a lower 'tween deck or 2,0 for an upper 'tween deck $S$ = spacing or mean spacing of primary supporting members, in metres	<b>TRANSVERSE FRAMING SYSTEM</b>  Aft end region: Web frames below lowest deck and not supporting effective stringers  Web frames above lowest deck  Any region: Fully effective stringers  Web frames below lowest deck supporting effective stringers	$Z = 5kShl_e^2$  $Z = 1,68CkTSl_e \sqrt{D}$  $Z = 7,75kShl_e^2$  Determined from calculation based on following assumptions: (a) Fixed ends (b) Point loadings (c) Head to upper deck at side (d) Bending stress 93,2 N/mm <sup>2</sup> (9,5 kgf/mm <sup>2</sup> ) (e) Shear stress 83,4 N/mm <sup>2</sup> (8,5 kgf/mm <sup>2</sup> )	} 2,5 x depth of adjacent main frames          } 2,5 x depth of adjacent main frames
	<b>LONGITUDINAL FRAMING SYSTEM</b> Side transverses below lowest deck Side transverses above lowest deck	$Z = 10kShl_e^2$  $Z = 2,1CkTSl_e \sqrt{D}$	} 2,5 x depth of longitudinals

### Section 4

## Double and single bottom structure


### 4.1 Double bottom structure

**4.1.1** The minimum depth of the centre girder and its thickness are to be at least the same as required in way of cargo space amidships, see Pt 4, Ch 1,8. A greater depth is recommended in way of large engine-rooms when the variation in draught between light and load conditions is considerable. For passenger ships, see Pt 4, Ch 2,6.

**4.1.2** In machinery spaces situated adjacent to the after peak, the double bottom is to be transversely framed. Elsewhere transverse or longitudinal framing may be adopted, but see also Pt 4, Ch 1,8.

**4.1.3** Where the double bottom is transversely framed, plate floors are to be fitted at every frame in the engine-room. In way of boilers, plate floors are to be fitted under the boiler bearers, and elsewhere as required by Pt 4, Ch 1,8.

**4.1.4** Where the double bottom is longitudinally framed, plate floors are to be fitted at every frame under the main engines and thrust bearing. Outboard of the engine seating, floors may be fitted at alternate frames, see Fig. 7.4.1.



**4.1.5** The scantlings of floors clear of the main engine seatings, are generally to be as required in way of cargo spaces, see Pt 4, Ch 1,8. In way of engine seatings, the floors are to be increased in thickness, see 6.2.1.

# Machinery Spaces

# Part 3, Chapter 7

Sections 4 & 5

4.1.6 Sufficient fore and aft girders are to be arranged in way of the main machinery to effectively distribute its weight and to ensure adequate rigidity of the structure. In midship machinery spaces these girders are to extend for the full length of the space and are to be carried aft to support the foremost shaft tunnel bearing. This extension beyond the after bulkhead of the engine-room is to be for at least three transverse frame spaces, aft of which the girders are to scarf into the structure. Forward of the engine-room bulkhead, the girders are to be tapered off over three frame spaces and effectively scarfed into the structure. In machinery spaces situated at the aft end the girders are to be carried as far aft as practicable and the ends effectively supported by web frames or transverses. For recommended scantlings of engine girders, see 6.2.1.

4.1.7 Outboard of the engines, side girders are to be arranged, where practicable, to line up with the side girders in adjacent cargo spaces. These are to have scantlings as required by Pt 4, Ch 1,8.

4.1.8 Where the double bottom is longitudinally framed and transverse floors are fitted in way of the engine seatings as required by 4.1.4, no additional longitudinal stiffening is required in way of the engines other than the main engine girders, provided that the spacing of girders does not exceed 1,5 times the normal spacing of longitudinals. Where this spacing of girders is exceeded, shell longitudinals are to be fitted. These are to scarf into the longitudinal framing clear of the machinery spaces. The scantlings of the longitudinals are to be determined as required by Pt 4, Ch 1,6 using a minimum span of 1,3 m, see Fig. 7.4.1.

4.1.9 The thickness,  $t$ , of inner bottom plating in engine-rooms, clear of the engine seatings, is to be not less than:

$$t = 0,0015 \sqrt{L T k^2} (s + 660) \text{ mm}$$

and not less than 7,0 mm (symbols as defined in Table 7.3.1). This thickness will be required to be increased in way of engine seatings integral with the tank top, see 6.2.1.

4.1.10 Where the height of inner bottom in the machinery spaces differs from that in adjacent spaces, continuity of longitudinal material is to be maintained by sloping the inner bottom over an adequate longitudinal extent. The knuckles in the plating are to be arranged close to plate floors.

## 4.2 Single bottom structure

4.2.1 In way of machinery spaces situated amidships the minimum depth of floors is to be at least 10 per cent greater than that required elsewhere in general cargo ships, see Pt 4, Ch 1,7. If the top of the floors is recessed in way of the engines, the depth of the floors in way of the recess should generally be not less than that required by Pt 4, Ch 1,7, but this will be specially considered in each case in relation to the arrangements proposed.

4.2.2 In way of machinery spaces situated aft, or where there is considerable rise of floor, the depth of the floors will be specially considered.

4.2.3 Clear of the engine seatings the thickness and face plate area of the floor webs are to be 1,0 mm and 10 per cent greater, respectively, than the requirements for general cargo ships as given in Pt 4, Ch 1,7. The floors are not to be flanged.

4.2.4 Sufficient fore and aft girders are to be arranged in way of machinery to effectively distribute its weight and ensure adequate rigidity of the structure. In midship machinery spaces these girders are to extend for the full length of the space and are to be carried aft to support the foremost shaft tunnel bearing and forward to scarf into the structure. In machinery spaces situated at the aft end, the girders are to be carried as far aft as practicable and the ends effectively supported by web frames or transverses. For scantlings of engine girders, see 6.2.1.

4.2.5 Outboard of the engines, side girders are to be arranged having scantlings as required by Pt 4, Ch 1,7 and these are to be scarfed into the side girders in adjacent spaces.

## Section 5 Machinery casings and oil fuel bunkers

### 5.1 Machinery casings

5.1.1 The scantlings and arrangements of exposed casings protecting machinery openings are to be in accordance with Ch 8,2.

5.1.2 The minimum scantlings of protected casings are to be in accordance with Table 7.5.1.

**Table 7.5.1 Protected machinery casings**

Item	Minimum scantlings
Plating: In way of cargo hold spaces	$t = 6,5 \sqrt{k}$ mm
In way of accommodation spaces	$t = 5,0 \sqrt{k}$ mm
Stiffeners	$Z = 0,008 l_e s k$ cm <sup>3</sup>
Symbols	
$k$ = higher tensile steel factor, see Ch 2,1.2 $l_e$ = effective length of stiffening member, in metres, see Ch 3,3.3 $s$ = spacing of stiffeners, in mm $t$ = thickness, in mm $Z$ = section modulus of stiffening member, in cm <sup>3</sup> , see Ch 3,3.2	
NOTE In no case is the depth of the stiffener to be less than 60 mm.	

# Machinery Spaces

## Part 3, Chapter 7

Sections 5 &amp; 6

5.1.3 Where casing stiffeners carry loads from deck transverses, girders, etc., or where they are in line with pillars below, they are to be suitably increased, see also Pt 4, Ch 1.4.

5.1.4 Where casing sides act as girders supporting decks over, care is to be taken that access openings do not seriously weaken the structure. Openings are to be effectively framed and reinforced if found necessary. Particular attention is to be paid to stiffening where the casing supports the funnel or exhaust uptakes.

### 5.2 Oil fuel bunkers

5.2.1 Oil fuel bunkers situated within the machinery space are generally to comply with the requirements given in Pt 4, Ch 1 or Ch 9, as appropriate.

## Section 6

### Engine seatings

#### 6.1 General

6.1.1 Main engines and thrust bearings are to be effectively secured to the hull structure by seatings of adequate scantlings to resist the various gravitational, thrust, torque, dynamic and vibratory forces which may be imposed on them.

6.1.2 For initial guidance, recommended scantlings for oil engine seatings are given in 6.2.1.

6.1.3 In the case of higher power oil engines or turbine installations the seatings should generally be integral with the double bottom structure. The tank top plating in way of the engine foundation plate or the turbine gear case and the thrust bearing should be substantially increased in thickness, see Fig. 7.6.1, Type 1.

6.1.4 If the main machinery is supported on seatings of Type 2 as shown in Fig. 7.6.1, these are to be so designed that they distribute the forces from the engine as uniformly as possible into the supporting structure. Longitudinal members supporting the seating are to be arranged in line with girders in the double bottom, and adequate transverse stiffening is to be arranged in line with floors, see Fig. 7.6.1, Type 2.

6.1.5 In ships having open floors in the machinery space the seatings are generally to be arranged above the level of the top of floors and securely bracketed to them, see Fig. 7.6.1, Type 3.

#### 6.2 Seats for oil engines

6.2.1 In determining the scantlings of seats for oil engines, consideration is to be given to the general rigidity of the engine itself and to its design characteristics in regard to out of balance forces. As a general guide to designers, recommended scantlings are given in Table 7.6.1.




Fig. 7.6.1 Engine seatings

# Machinery Spaces

# Part 3, Chapter 7

Section 6

**Table 7.6.1 Seats for oil engines – Recommended scantlings**

Symbols	Item	Scantlings of one seat
<p><math>L</math> as defined in Ch 1,6.1</p> <p><math>f</math> = engine factor = <math>\frac{P}{Rl}</math></p> <p><math>t</math> = minimum thickness of top plate, in mm</p> <p><math>t_1, t_2</math> = main engine girder thicknesses, in mm</p> <p><math>t_3</math> = floor plate thickness under seating, in mm, see also Fig. 7.6.1</p> <p><math>A</math> = area of top plate for one side of seat, in <math>\text{cm}^2</math></p> <p>where</p> <p><math>l</math> = effective length of engine foundation plate, in metres, required for bolting the engine to the seating. The thrust and gearcase seating is to be considered as a separate item</p> <p><math>P</math> = power of one engine at maximum service speed, in kW (bhp)</p> <p><math>R</math> = rev/min of engine at maximum service speed</p>	Top plate	<p><math>A = (120 + 44,2f + 4,07f^2) \text{ cm}^2</math>  <math>(A = (120 + 32,5f + 2,2f^2) \text{ cm}^2)</math></p> <p>Minimum thickness:</p> <p>(a) Where two girders fitted  <math>t = (19 + 3,4f) \text{ mm}</math>  <math>(t = (19 + 2,5f) \text{ mm})</math></p> <p>(b) Where one girder fitted  <math>t = (25 + 3,4f) \text{ mm}</math>  <math>(t = (25 + 2,5f) \text{ mm})</math></p>
	Girders (both inside and above double bottom where fitted)	<p>Number:</p> <p>Generally two but a single girder can be accepted where all the following apply:</p> <p>(a) <math>f &lt; 1,84</math> (2,5)  (b) <math>P &lt; 5900 \text{ kW}</math> (8000 bhp)  (c) <math>L &lt; 100 \text{ m}</math></p> <p>Total thickness:</p> <p>(a) Where two girders are fitted  <math>t_1 + t_2 = (28 + 4,08f) \text{ mm}</math>  <math>(t_1 + t_2 = (28 + 3,0f) \text{ mm})</math></p> <p>(b) Where one girder is fitted  <math>t_1 = (15 + 4,08f) \text{ mm}</math>  <math>(t_1 = (15 + 3,0f) \text{ mm})</math></p>
	Floors (between girders or under seat where a single girder is fitted)	<p>Thickness:</p> <p><math>t_3 = (10 + 1,5f) \text{ mm}</math>  <math>(t_3 = (10 + 1,1f) \text{ mm})</math></p>

## 6.3 Seats for turbines

6.3.1 Seats are to be so designed as to provide effective support for the turbines and ensure their proper alignment with the gearing, and (where applicable) allow for thermal expansion of the casings. In general, the seats are not to be arranged in way of breaks or recesses in the double bottom.

## 6.4 Seats for boilers

6.4.1 Boiler bearers are to be of substantial construction and efficiently supported by transverse and horizontal brackets. These should generally be arranged in line with plate floors and girders in a double bottom or with suitable deep beams or transverses and girders at boiler flats. Suitable allowance is to be made in the design of the supporting structure for the variation in loading due to thermal expansion effects, see also Pt 5, Ch 14,2.

## 6.5 Seats for auxiliary machinery

6.5.1 Auxiliary machinery is to be secured on seatings, of adequate scantlings, so arranged as to distribute the loadings evenly into the supporting structure.

## Section

- 1 **General**
- 2 **Scantlings of erections other than forecastles**
- 3 **Aluminium erections**
- 4 **Forecastles**
- 5 **Bulwarks, guard rails and other means for the protection of crew**

## Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to all types of ships detailed in Part 4, except for deckhouses situated on forecastles of offshore supply ships, which are dealt with separately in Pt 4, Ch 4.

1.1.2 The scantlings of exposed bulkheads and decks of superstructures and deckhouses are generally to comply with the following requirements, but increased scantlings may be required where the structure is subjected to loading additional to Rule. Where there is no access from inside the house to below the free-board deck, or where a bulkhead is in a particularly sheltered location, the scantlings may be specially considered.

1.1.3 The term 'erection' is used in this Section to include both superstructures and deckhouses.

1.1.4 For requirements relating to companionways, doors, accesses and skylights, see Chapter 11.

1.1.5 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation with the exception of Section 5 which is to be complied with. See Pt 1, Ch 2,2.3.

### 1.2 Symbols

1.2.1 The following symbols and definitions are applicable to this Chapter, unless otherwise stated:

$L$ ,  $B$ ,  $T$  and  $C_b$  as defined in Ch 1,6.1

- $b$  = breadth of deckhouse, at the positions under consideration, in metres
- $k$  = higher tensile steel factor, see Ch 2,1.2
- $l_e$  = effective length, in metres, of the stiffening member, deck beam or longitudinal measured between span points, see Ch 3,3.3
- $l_s$  = span, in metres, of stiffeners, and is to be taken as the 'tween deck or house height but in no case as less than 2,0 m
- $s$  = spacing of stiffeners, beams or longitudinals, in mm

$s_b$  = standard spacing, in mm, of stiffeners, beams or longitudinals, and is to be taken as:

- (a) for  $0,05L$  from the ends:  
 $s_b = 610$  mm or that required by (b), whichever is the lesser
- (b) elsewhere:  
 $s_b = 470 + 1,67L_2$  mm  
but forward of  $0,2L$  from the forward perpendicular  $s_b$  is not to exceed 700 mm

$B_1$  = actual breadth of ship, at the section under consideration, measured at the weather deck, in metres

$D$  = moulded depth of ship, in metres, to the uppermost continuous deck or the deck next above a height of 1,67 from the base line amidships, whichever is the lesser

$L_2$  = length of ship, in metres, but need not be taken greater than 250 m

$L_3$  = length of ship, in metres, but need not be taken greater than 300 m

$X$  = distance, in metres, between the after perpendicular and the bulkhead under consideration. When determining the scantlings of deckhouse sides, the deckhouse is to be subdivided into parts of approximately equal length not exceeding  $0,15L$  each, and  $X$  is to be measured to the mid-length of each part

$\alpha$  = a coefficient given in Table 8.1.1

$$\beta = 1,0 + \left( \frac{\left( \frac{X}{L} - 0,45 \right)}{(C_b + 0,2)} \right)^2 \text{ for } \frac{X}{L} \leq 0,45$$

$$= 1,0 + 1,5 \left( \frac{\left( \frac{X}{L} - 0,45 \right)}{(C_b + 0,2)} \right)^2 \text{ for } \frac{X}{L} > 0,45$$

$C_b$  is to be taken as not less than 0,6 nor greater than 0,8. Where the aft end of an erection is forward of amidships, the value of  $C_b$  used in determining  $\beta$  for the aft end bulkhead need be taken as not less than 0,8

$\gamma$  = vertical distance, in metres, from the summer load waterline to the mid-point of span of the bulkhead stiffener, or the mid-point of the plate panel, as appropriate

$\delta$  = 1,0 for exposed machinery casings and houses protecting openings to pump-rooms

$\left( 0,3 + 0,7 \frac{b}{B_1} \right)$  elsewhere, but in no case to be taken less than 0,475

$\lambda$  = a coefficient given in Table 8.1.2.

## Superstructures, Deckhouses and Bulwarks

## Part 3, Chapter 8

Sections 1 &amp; 2

Table 8.1.1 Values of  $\alpha$ 

Position	$\alpha$
Lowest tier – unprotected front	$2,0 + 0,0083L_3$
Second tier – unprotected front	$1,0 + 0,0083L_3$
Third tier and above – unprotected front All tiers – protected fronts All tiers – sides	$0,5 + 0,0067L_3$
All tiers – aft end where aft of amidships	$0,7 + 0,001L_3 - 0,8 \frac{X}{L}$
All tiers – aft end where forward of amidships	$0,5 + 0,001L_3 - 0,4 \frac{X}{L}$

Table 8.1.2 Values of  $\lambda$ 

Length $L$ metres	$\lambda$	Expression for $\lambda$
20 30 40 50 60 70 80 90 110 130 150	0,89 1,76 2,57 3,34 4,07 4,76 5,41 6,03 7,16 8,18 9,10	$L \leq 150 \text{ m}$ $\lambda = \left( \frac{L}{10} e^{-\frac{L}{300}} \right) - \left( 1 - \left( \frac{L}{150} \right)^2 \right)$
150 170 190 210 230 250 270 290 300	9,10 9,65 10,08 10,43 10,69 10,86 10,98 11,03 11,03	$150 \text{ m} \leq L \leq 300 \text{ m}$ $\lambda = \frac{L}{10} e^{-\frac{L}{300}}$
300 and above	11,03	$L \geq 300 \text{ m}$ $\lambda = 11,03$

## 1.3 Definition of tiers

1.3.1 The lowest, or first tier, is normally that which is directly situated on the deck to which  $D$  is measured. The second tier is the next tier above the lowest tier and so on.

1.3.2 Where the freeboard corresponding to the required summer moulded draught for the ship can be obtained by considering the ship to have a virtual moulded depth at least one standard superstructure height less than the Rule depth,  $D$ , measured to the uppermost continuous deck, proposals to treat the first tier erection as a second tier, and so on, will be specially considered. The standard height of superstructure is the height defined in the *International Convention on Load Lines, 1966*.

## 1.4 Design pressure head

1.4.1 The design pressure head,  $h$ , to be used in the determination of erection scantlings is to be taken as:

$$h = \alpha \delta (\beta \lambda - \gamma) \text{ m}$$

1.4.2 In no case is the design pressure head to be taken as less than the following:

- (a) Lowest tier of unprotected fronts:  
minimum  $h = 2,5 + 0,01L_2 \text{ m}$
- (b) All other locations:  
minimum  $h = 1,25 + 0,005L_2 \text{ m}$ .

## Section 2 Scantlings of erections other than forecastles

## 2.1 Thickness of bulkhead and side plating

2.1.1 The thickness,  $t$ , of plating of the fronts, sides and aft ends of all erections, other than the sides of superstructures where these are an extension of the side shell, is to be not less than:

$$t = 0,003s \sqrt{kh} \text{ mm}$$

but in no case is the thickness to be less than:

- (a) for the lowest tier:

$$t = (5,0 + 0,01L_3) \sqrt{k} \text{ mm}$$

- (b) for the upper tiers:

$$t = 4,0 + 0,01L_3 \sqrt{k} \text{ mm but not less than } 5,0 \text{ mm.}$$

2.1.2 The thickness of sides of poops and bridges is to be as required by Ch 6,3 or Pt 4, Ch 1,5, as appropriate.

## 2.2 Stiffeners and their connections

2.2.1 The modulus of stiffeners,  $Z$ , on front, side and end bulkheads of all erections, other than sides of superstructures, is to be not less than:

$$Z = 0,0035h s I_s^2 k \text{ cm}^3$$

2.2.2 The section modulus of side frames of poops and bridges is to comply with the requirements of Ch 6,4 or Pt 4, Ch 1,6, as appropriate.

2.2.3 The end connections of stiffeners are to be as given in Table 8.2.1.

## 2.3 Deck plating

2.3.1 The thickness of erection deck plating is to be not less than that required by Table 8.2.2.



**Table 8.2.1 Stiffener end connections**

Position	Attachment at top and bottom
1. Front stiffeners of lower tiers and of upper tiers when $L$ is 160 m or greater	See Chapter 10
2. Front stiffeners of upper tiers when $L$ is less than 160 m	May be unattached
3. Side stiffeners of lower tiers where two or more tiers are fitted	Bracketed, unless stiffener modulus is increased by 20 per cent and ends are welded to the deck all round
4. Side stiffeners if only one tier is fitted, and aft end stiffeners of after deckhouses on deck to which $D$ is measured	See Chapter 10
5. Side stiffeners of upper tiers when $L$ is 160 m or greater	See Chapter 10
6. Side stiffeners of upper tiers when $L$ is less than 160 m	May be unattached
7. Aft end stiffeners except as covered by item 4	May be unattached
8. Exposed machinery and pump-room casings – Front stiffeners on amidship casings and all stiffeners on aft end casings which are situated on the deck to which $D$ is measured	Bracketed
9. All other stiffeners on exposed machinery and pump-room casings	6,5 cm <sup>2</sup> of weld

**Table 8.2.2 Thickness of deck plating**

Position	Thickness of deck plating, in mm	
	$L \leq 100$ m	$L > 100$ m
Top of first tier erection	$(5,5 + 0,02L) \sqrt{\frac{ks}{s_b}}$	$7,5 \sqrt{\frac{ks}{s_b}}$
Top of second tier erection	$(5,0 + 0,02L) \sqrt{\frac{ks}{s_b}}$	$7,0 \sqrt{\frac{ks}{s_b}}$
Top of third tier and above	$(4,5 + 0,02L) \sqrt{\frac{ks}{s_b}}$	$6,5 \sqrt{\frac{ks}{s_b}}$

2.3.2 When decks are fitted with approved sheathing, the thicknesses derived from Table 8.2.2 may be reduced by 10 per cent for a 50 mm sheathing thickness, or 5 per cent for 25,5 mm, with intermediate values in proportion. The steel deck is to be coated with a suitable material in order to prevent corrosive action, and the sheathing or composition is to be effectively secured to the deck, see also Pt 6, Ch 4. Inside deckhouses the thickness may be reduced by a further 10 per cent.

## 2.4 Deck longitudinals and beams

2.4.1 The section modulus of superstructure deck longitudinals and beams is to be in accordance with the requirements for location (2) in Table 1.4.4 and location (3) in Table 1.4.5 in Pt 4, Ch 1, using design heads not less than those specified in Table 3.5.1 in Chapter 3 for superstructure decks.

2.4.2 Transverse deck beams in deckhouses and deck longitudinals other than as in 2.7 are to have a section modulus,  $Z$ , not less than:

$$Z = 0,0048h_2 s l_e^2 k \text{ cm}^3, \text{ but in no case less than:}$$

$$Z = 0,025s \text{ cm}^3$$

and the value of  $h_2$ , the load head, is to be taken as not less than:

on first tier decks	0,9 m
on second tier decks	0,6 m
on third tier decks and above	0,45 m.

## 2.5 Deck girders and transverses

2.5.1 The section modulus of deck girders and transverses is to be in accordance with the requirements for location (1) in Table 1.4.6 in Pt 4, Ch 1, using design heads not less than those specified in Table 3.5.1 in Chapter 3 for superstructure decks.

## 2.6 Strengthening at ends and sides of erections

2.6.1 Web frames or partial bulkheads are to be fitted within poops and bridges that have large deckhouses or other erections above.

2.6.2 Web frames or equivalent strengthening are also to be arranged to support the sides and ends of large deckhouses.

2.6.3 These web frames should be spaced about 9 m apart and are to be arranged, where practicable, in line with watertight bulkheads below. Webs are also to be arranged in way of large openings, boats, davits and other points of high loading.

2.6.4 Arrangements are to be made to minimize the effect of discontinuities in erections. All openings cut in the sides are to be substantially framed and have well rounded corners. Continuous coamings or girders are to be fitted below and above doors and similar openings. House tops are to be strengthened in way of davits. Special care is to be taken to minimize the size and number of openings in the side bulkheads in the region of the ends of erections within  $0,5L$  amidships. Account is to be taken of the high vertical shear loading which can occur in these areas.

2.6.5 Adequate support under the ends of erections is to be provided in the form of webs, pillars, diaphragms or bulkheads in conjunction with reinforced deck beams. At the corners of houses and in way of supporting structures, attention is to be given to the connection to the deck, and inserts or equivalent arrangements are generally to be fitted especially for erections that are effective in resisting vertical hull girder bending as defined in Pt 3, Ch 3,3.4.2.

2.6.6 The side plating of bridges having a length of  $0,15L$  or greater is to be increased in thickness by 25 per cent at the ends of the structure, and is to be tapered into the upper deck sheerstrake. This plating is to be efficiently stiffened at the upper edge and supported by web plates not more than 1,5 m from the end bulkhead. Proposals for alternative arrangements, including the use of higher tensile steel, will be individually considered.

## 2.7 Erections contributing to hull strength

2.7.1 Where a long superstructure or deckhouse is fitted, extending within  $0,5L$  amidships, the scantlings of the first tier deck plating and longitudinals may be required to be increased, see also Ch 3,3.4 and Ch 4,2.3.

## 2.8 Unusual designs

2.8.1 Where superstructures or deckhouses are of unusual design, the strength is to be not less than that required by this Chapter for a conventional design.

## Section 3 Aluminium erections

### 3.1 Scantlings

3.1.1 Where an aluminium alloy complying with Chapter 8 of the Rules for Materials (Part 2) is used in the construction of erections, the scantlings of these erections are to be increased (relative to those required for steel construction) by the percentages given in Table 8.3.1.

3.1.2 The thickness,  $t$ , of aluminium alloy members is to be not less than:

$$t = 2,5 + 0,022d_w \text{ mm but need not exceed 10 mm}$$

where

$$d_w = \text{depth of the section, in mm.}$$

3.1.3 The minimum moment of inertia,  $I$ , of aluminium alloy stiffening members is to be not less than:

$$I = 5,25Z l_e \text{ cm}^4$$

Where  $l_e$  is the effective length of the member in metres, as defined in 1.2.1, and  $Z$  is the section modulus of the stiffener and attached plating calculated using the formulae in 2.2.1 and 2.4.2 as applicable taking  $k$  as 1.

**Table 8.3.1 Percentage increase of scantlings**

Item	Percentage increase
Fronts, sides, aft ends, unsheathed deck plating	20
Decks sheathed in accordance with 2.3.2	10
Deck sheathed with wood, and on which the plating is fixed to the wood sheathing at the centre of each beam space	Nil
Stiffeners and beams	70
Scantlings of small isolated houses	Nil

## 3.2 Bimetallic joints

3.2.1 Where aluminium erections are arranged above a steel hull, details of the arrangements in way of the bimetallic connections are to be submitted.

## Section 4 Forecastles

### 4.1 Construction

4.1.1 Side plating and framing of forecastles are to comply with the requirements of Ch 5,3 and Ch 5,4 respectively. The end plating and its stiffening are to comply with the requirements of 2.1.1 and 2.2.1 respectively.

4.1.2 The bow height and the extent of the forecastle are to comply with the requirements of Ch 3,6.

4.1.3 The thickness,  $t$ , of forecastle deck plating is to be not less than:

$$t = (6 + 0,017L) \sqrt{\frac{ks}{s_b}} \text{ mm}$$

4.1.4 Deck longitudinals and beams are to comply with Ch 5,2.3, using a head of 1,8 m forward of  $0,075L$  and 1,5 m between  $0,12L$  and  $0,075L$ .

4.1.5 Girders, transverses and pillars are to be in accordance with Ch 5,2.4, and the depth of the girder or transverse is to be not less than twice that of the beam or longitudinal supported.



## Section 5

### Bulwarks, guard rails and other means for the protection of crew

#### 5.1 General requirements

5.1.1 Bulwarks or guard rails are to be provided around all exposed decks. Bulwarks or guard rails are to be not less than 1,0 m in height measured above sheathing, and are to be constructed as required by this Section. Consideration will be given to cases where this height would interfere with the normal operation of the ship.

5.1.2 The freeing arrangements in bulwarks are to be in accordance with 5.3.

5.1.3 Guard rails fitted on superstructure and freeboards decks are to have at least three courses. The opening below the lowest course of guard rails is not to exceed 230 mm. The other courses are to be spaced not more than 380 mm apart. In the case of ships with rounded gunwales, the guard rail supports are to be placed on the flat of the deck. In other locations, guard rails with at least two courses are to be fitted.

5.1.4 Guard rails are to be fitted with fixed, removable or hinged stanchions fitted no more than 1,5 m apart. Removable or hinged stanchions shall be capable of being locked in the upright position.

5.1.5 At least every third stanchion is to be supported by a stay.

5.1.6 Where necessary for the normal operation of the ship, steel wire ropes may be accepted in lieu of guard rails. Wires are to be made taut by means of turnbuckles. Chains are only permitted in short lengths in way of access openings.

5.1.7 Satisfactory means, in the form of guard rails, life-lines, handrails, gangways, underdeck passageways or other equivalent arrangements, are to be provided for the protection of the crew in getting to and from their quarters, the machinery space and all other parts used in the necessary work of the ship in accordance with Table 8.5.1.

5.1.8 Where gangways on a trunk are provided by means of a stringer plate fitted outboard of the trunk side bulkheads (port and starboard), each gangway is to be a solid plate, effectively stayed and supported, with a clear walkway at least 450 mm wide, at or near the top of the coaming, with guard rails complying with 5.1.3 and hatch cover securing appliances accessible from the gangway.

5.1.9 Where permitted by the National Authority, gangways or walkways may be omitted on ships engaged on protected or extended protected water service. However, life-lines are to be provided on tankers and flush deck ships, or where the cargo hatch coamings are less than 600 mm high.

5.1.10 For a Type 'A' ship with freeboards assigned greater than, or equal to, Type 'B', a life-line may be provided in lieu of a walkway.

#### 5.2 Bulwark construction

5.2.1 Plate bulwarks are to be stiffened by a strong rail section and supported by stays from the deck. The spacing of these stays forward of 0,07L from the forward perpendicular is to be not more than 1,2 m on Type 'A', Type 'B-60' and Type 'B-100' ships (as defined in Ch 11,1.1), and not more than 1,83 m on other Types. Elsewhere, bulwark stays are to be not more than 1,83 m apart. Where bulwarks are cut to form a gangway or other opening, stays of increased strength are to be fitted at the ends of the openings. Bulwarks are to be adequately strengthened in way of eyeplates for cargo gear, and in way of mooring pipes the plating is to be doubled or increased in thickness and adequately stiffened.

5.2.2 Bulwarks should not be cut for gangway or other openings near the breaks of superstructures, and are also to be arranged to ensure their freedom from main structural stresses. See shell plating in appropriate Chapters.

5.2.3 The section modulus,  $Z$ , at the bottom of the bulwark stay is to be not less than:

$$Z = (33,0 + 0,44L) h^2 s \text{ cm}^3$$

where

$h$  = height of bulwark from the top of the deck plating to the top of the rail, in metres

$s$  = spacing of the stays, in metres, in accordance with 5.2.1

$L$  = length of ship, in metres (as defined in Ch 1,6.1), but to be not greater than 100 m.

5.2.4 In the calculation of the section modulus, only the material connected to the deck is to be included. The bulb or flange of the stay may be taken into account where connected to the deck, and where, at the ends of the ship, the bulwark plating is connected to the sheerstrake, a width of plating not exceeding 600 mm may also be included. The free edge of the stay is to be stiffened.

5.2.5 Bulwark stays are to be supported by, or to be in line with, suitable underdeck stiffening, which is to be connected by double continuous fillet welds in way of the bulwark stay connection.

5.2.6 It should be noted that the above requirements do not allow for any loading from deck cargoes.

#### 5.3 Freeing arrangements

5.3.1 The requirements of 5.3.2 to 5.3.11 apply to ships of Type 'B'. Additional requirements applicable to ships of Type 'A', Type 'B-100' and Type 'B-60' are indicated in 5.3.18 and 5.3.20. The ship Types are as defined in Ch 11,1.1.

5.3.2 Where bulwarks on the weather portions of freeboard or superstructure decks form wells, ample provision is to be made for rapidly freeing the decks of large quantities of water by means of freeing ports, and also for draining them.

## Superstructures, Deckhouses and Bulwarks

## Part 3, Chapter 8

Section 5

**Table 8.5.1 Protection of crew** (see continuation)

Ship type	Location in ship	Assigned Summer Freeboard, in mm	Acceptable arrangements according to type of freeboard assigned			
			Type A	Type (B-100)	Type (B-60)	Type (B & B+)
Oil tankers, chemical tankers and gas carriers (see 1.1.5)	1.1 Access to bow	$\leq (A_f + H_s)$	a	a	a	a
	1.1.1 Between poop and bow or		e	e	e	e
	1.1.2 Between a deckhouse containing living accommodation or navigation equipment, or both, and bow, or		f(1)	f(1)	f(1)	f(1)
	1.1.3 In the case of a flush deck vessel, between crew accommodation and the forward ends of ship	$>(A_f + H_s)$	a e f(1) f(2)			
	1.2 Access to after end In the case of a flush deck vessel, between crew accommodation and the after end of ship	As required in item 2.2.4 in Table 8.5.1 for other types of ships				
Symbols						
$A_f$ = the minimum summer freeboard calculated as Type A ship regardless of type freeboard actually assigned $H_s$ = the standard height of superstructure as defined in International Convention on Load Lines, Regulation 33						
<b>Acceptable arrangements:</b> Acceptable arrangements referred to in the Table are defined as follows: a A well lighted and ventilated under-deck passageway (clear opening 0,8 m wide, 2 m high) as close as practicable to the freeboard deck, connecting and providing access to the locations in question. b A permanent and efficiently constructed gangway fitted at or above the level of the superstructure deck on or as near as practicable to the centreline of the ship, providing a continuous platform at least 0,6 m in width and a non-slip surface, with guard rails extending on each side throughout its length. Guard rails shall be at least 1 m high with courses as required in 5.1, and supported by stanchions spaced not more than 1,5 m; a foot-stop shall be provided. c A permanent walkway at least 0,6 m in width fitted at freeboard deck level consisting of two rows of guard rails with stanchions spaced not more than 3 m. The number of courses of rails and their spacing are to be as required by 5.1. On Type B ships, hatchway coamings not less than 0,6 m in height may be regarded as forming one side of the walkway, provided that between the hatchways two rows of guard rails are fitted. d A 10 mm minimum thickness diameter wire rope life-line supported by stanchions about 10 m apart, or a single hand rail or wire rope attached to hatch coamings, continued and adequately supported between hatchways. e A permanent and efficiently constructed gangway fitted at or above the level of the superstructure deck on or as near as practicable to the centreline of the ship: <ul style="list-style-type: none"><li>located so as not to hinder easy access across the working areas of the deck;</li><li>providing a continuous platform at least 1,0 m in width;</li><li>constructed of fire resistant and non-slip material;</li><li>fitted with guard rails extending on each side throughout its length; guard rails should be at least 1,0 m high with courses as required by Regulation 25(3) and supported by stanchions spaced not more than 1,5 m;</li><li>provided with a foot stop on each side;</li><li>having openings, with ladders where appropriate, to and from the deck. Openings should not be more than 40 m apart;</li><li>having shelters of substantial construction set in way of the gangway at intervals not exceeding 45 m if the length of the exposed deck to be traversed exceeds 70 m. Every such shelter should be capable of accommodating at least one person and be so constructed as to afford weather protection on the forward port and starboard sides.</li></ul> f A permanent and efficiently constructed walkway fitted at freeboard deck level on or as near as practicable to the centre line of the ship having the same specifications as those for a permanent gangway listed in (e) except for foot-stops. On Type B ships (certified for the carriage of liquids in bulk), with a combined height of hatch coaming and fitted hatch cover of together not less than 1 m in height the hatchway coamings may be regarded as forming one side of the walkway, provided that between the hatchways two rows of guard rails are fitted.						
Alternative transverse locations for (c), (d) and (f): (1) At or near centreline of ship; or fitted on hatchways at or near centreline of ship. (2) Fitted on each side of the ship. (3) Fitted on one side of the ship, provision being made for fitting on either side. (4) Fitted on one side of the ship only. (5) Fitted on each side of hatchways as near to the centreline as practicable.						

## Superstructures, Deckhouses and Bulwarks

## Part 3, Chapter 8

Section 5

Table 8.5.1 Protection of crew (conclusion)

Ship type	Location in ship	Assigned Summer Freeboard, in mm	Acceptable arrangements according to type of freeboard assigned			
			Type A	Type (B-100)	Type (B-60)	Type (B & B+)
Other ship type	2.1 Access to midship quarters					
	2.1.1 Between poop and bridge, or	≤ 3000 mm	a b e	a b e	a b c(1) e f(1)	
	2.1.2 Between poop and deckhouse containing living accommodation or navigation equipment, or both	> 3000 mm	a b e	a b e	a b c(1) c(2) e f(1) f(2)	
	2.2 Access to ends					
	2.2.1 Between poop and bow (if there is no bridge),	≤ 3000 mm	a b c(1) e f(1)	a b c(1) c(2) e f(1) f(2)	a b c(1) c(2) e f(1) f(2)	
	2.2.2 Between bridge and bow, or					
	2.2.3 Between a deckhouse containing living accommodation or navigation equipment, or both, and bow, or	> 3000 mm	a b c(1) d(1) e f(1)	a b c(1) c(2) d(1) d(2) e f(1) f(2)	a b c(1) c(2) d(1) d(2) d(3) e f(1) f(2) f(4)	
	2.2.4 In the case of a flush deck vessel, between crew accommodation and the forward and after ends of ship					

## NOTES

1. In all cases where wire ropes are fitted, adequate devices are to be provided to ensure their tautness.
2. Wire ropes may only be accepted in lieu of guard rails in special circumstances and then only in limited lengths.
3. Lengths of chain may only be accepted in lieu of guard rails if fitted between two fixed stanchions.
4. Where stanchions are fitted, every third stanchion is to be supported by a bracket or stay.
5. Removable or hinged stanchions shall be capable of being locked in the upright position.
6. A means of passage over obstructions, if any, such as pipes or other fittings of a permanent nature, should be provided.
7. Generally, the width of the gangway or deck-level walkway should not exceed 1,5 m.

5.3.3 The minimum freeing area on each side of the ship, for each well on the freeboard deck or raised quarterdeck, where the sheer in the well is not less than the standard sheer required by the *International Convention on Load Lines, 1966*, is to be derived from the following formulae:

(a) where the length,  $l$ , of the bulwark in the well is 20 m or less:

$$\text{area required} = 0,7 + 0,035l \quad \text{m}^2$$

(b) where the length,  $l$ , exceeds 20 m:

$$\text{area required} = 0,07l \quad \text{m}^2$$

$l$  need not be taken greater than  $0,7L_L$ , where  $L_L$  is the length of the ship as defined in Ch 1,6.1.

5.3.4 If the average height of the bulwark exceeds 1,2 m or is less than 0,9 m, the freeing area is to be increased or decreased, respectively, by 0,004 m<sup>2</sup> per metre of length of well for each 0,1 m increase or decrease in height respectively.

5.3.5 The minimum freeing area for each well on a first tier superstructure is to be half the area calculated from 5.3.3.

5.3.6 Two-thirds of the freeing port area required is to be provided in the half of the well nearest to the lowest point of the sheer curve.

5.3.7 When the deck has little or no sheer, the freeing area is to be spread along the length of the well.

5.3.8 In ships with no sheer the freeing area as calculated from 5.3.3 is to be increased by 50 per cent. Where the sheer is less than the standard, the percentage is to be obtained by linear interpolation.

5.3.9 Where the length of the well is less than 10 m, or where a deckhouse occupies most of the length, the freeing port area will be specially considered but in general need not exceed 10 per cent of the bulwark area.

**5.3.10** Where it is not practical to provide sufficient freeing port area in the bulwark, particularly in small ships, credit can be given for bollard and fairlead openings where these extend to the deck.

**5.3.11** Where a ship fitted with bulwarks has a continuous trunk, or hatch side coamings that are continuous, or substantially continuous, the minimum freeing area is to be not less than 20 per cent of the total bulwark area where the width of trunk or hatchway is  $0,4B$  or less, and not less than 10 per cent of the total bulwark area when the width of the trunk or hatch is  $0,75B$  or greater. The freeing area required for an intermediate width of trunk or hatch is to be obtained by linear interpolation.

**5.3.12** Where the trunk referred to in 5.3.11 or its equivalent is included in the calculation of freeboard, open rails are to be fitted for at least 50 per cent of the length of the exposed part of the weather deck. Alternatively, if a continuous bulwark is fitted, the minimum freeing area is to be at least 33 per cent of the bulwark area. The freeing area is to be placed in the lower part of the bulwark.

**5.3.13** Where a deckhouse has a breadth less than 80 per cent of the beam of the ship, or the width of the side passageways exceeds 1,5 m, the arrangement is considered as one well. Where a deckhouse has a breadth equal to or more than 80 per cent of the beam of the ship, or the width of the side passageways does not exceed 1,5 m, or when a screen bulkhead is fitted across the full breadth of the ship, this arrangement is considered as two wells, before and abaft the deckhouse.

**5.3.14** Suitable provision is also to be made for the rapid freeing of water from recesses formed by superstructures, deckhouses and deck cargo arrangements, etc., in which water may be shipped and trapped. Deck gear, particularly on fishing vessels, is not to be stowed in such a manner as to obstruct unduly the flow of water to freeing ports.

**5.3.15** The lower edges of freeing ports are to be as near to the deck as practicable, and should not be more than 100 mm above the deck.

**5.3.16** Where freeing ports are more than 230 mm high, vertical bars spaced 230 mm apart may be accepted as an alternative to a horizontal rail to limit the height of the freeing port.

**5.3.17** Where shutters are fitted, the pins or bearings are to be of a non-corrodible material, with ample clearance to prevent jamming. The hinges are to be within the upper third of the port. Shutters are not to be fitted with securing appliances.

**5.3.18** Ships of Type 'A' and Type 'B-100' are to have open rails for at least half the length of the exposed part of the weather deck. Alternatively, if a continuous bulwark is fitted, the minimum freeing area is to be at least 33 per cent of the total area of the bulwark. The freeing area is to be placed in the lower part of the bulwark.

**5.3.19** Where superstructures are connected by trunks, open rails are to be fitted for the whole length of the exposed part of the freeboard deck.

**5.3.20** Ships of Type 'B-60' are to have a minimum freeing area of at least 25 per cent of the total area of the bulwark. The freeing area is to be placed in the lower part of the bulwark.

**5.3.21** Gutter bars greater than 300 mm in height fitted on the weather decks of tankers are to be treated as bulwarks and freeing ports arranged as required by this Section. Closures for use during loading and discharge operations are to be arranged in such a way that jamming cannot occur while at sea.

**5.3.22** In ships having superstructures which are open at either or both ends to wells formed by bulwarks on the open deck, adequate provision for freeing the open spaces are to be provided as follows:

The freeing port area,  $A_w$  for the open well:

$$A_w = (0,07l_w + A_c) (S_c) \left( \frac{0,5h_s}{h_w} \right)$$

The freeing port area,  $A_s$  for the open superstructure:

$$A_s = (0,07l_t) (S_c) \left( \frac{b_o}{l_t} \left( 1 - \left( \frac{l_w}{l_t} \right)^2 \right) \left( \frac{0,5h_s}{h_w} \right) \right)$$

where

$l_w$  = the length of the open deck enclosed by bulwarks, in metres

$l_s$  = the length of the common space within the open superstructure, in metres

$l_t$  =  $l_w + l_s$  but if 20 m or less then the freeing area is to be calculated in accordance with 5.3.3(a)

$S_c$  = sheer correction factor, maximum 1,5 as defined in 5.3.8

$b_o$  = breadth of openings in the end bulkhead of the enclosed superstructure, in metres

$h_w$  = distance of the well deck above the freeboard deck, in metres

$h_s$  = one standard superstructure height

$h_b$  = actual height of the bulwark, in metres.

$A_c$  = bulwark height correction factor taken as;

= 0 for bulwarks between 0,9 and 1,2 m in height

=  $l_w \left( \frac{(h_b - 1,2)}{1,0} \right) (0,004) \text{ m}^2$  for bulwarks of height

greater than 1,2 m, and

=  $l_w \left( \frac{(h_b - 0,9)}{1,0} \right) (0,004) \text{ m}^2$  for bulwarks of height

less than 0,9 m

## 5.4 Free flow area

**5.4.1** The effectiveness of the freeing port area in bulwarks of vessels not fitted with a continuous deck obstruction, depends on the free flow across the deck.

**5.4.2** The free flow area is the net total longitudinal area of the transverse passageways or gaps between hatchways and superstructures or deckhouses, due account being made for any obstructions such as equipment or other fittings. The height of passageways or gaps used in the calculation of the area is the height of the bulwark.

5.4.3 The provision of freeing area in bulwarks should be related to the net free flow area as follows:

- (a) If the free flow area is equal to, or greater than the freeing port area calculated from 5.3.11 when the hatchway coamings are continuous, then the minimum freeing area calculated from 5.3.3 is sufficient.
- (b) If the free flow area is less than the freeing port area calculated from 5.3.3, then the minimum freeing area is to be that calculated from 5.3.11.
- (c) If the free flow area is less than the freeing port area derived from (a) but greater than that derived from (b), the minimum freeing area,  $F$ , in the bulwark is to be obtained from the following formula:

$$F = F_1 + F_2 - f_p \quad \text{m}^2$$

where

$f_p$  = total net area of passages and gaps between hatchways, superstructures and deckhouses (the free flow area)

$F_1$  = minimum area from 5.3.3

$F_2$  = minimum area from 5.3.11.

## 5.5 Special requirements for tugs and offshore supply ships

5.5.1 In tugs and offshore supply ships where there is a recess at the after end of the forecastle for the towing winch, the freeing port area in way of the recess is to be calculated as follows:

$B$  = breadth of ship

$b$  = breadth of recess

$L$  = length of well

$l$  = mean length of recess

$a$  = freeing area for well length  $L$

Freeing port area in way of recess:

$$A = a \frac{l}{L}$$

Reduction due to breadth of recess:

$$A_1 = A \frac{b}{B}$$

Reduce  $A_1$  by 25 per cent for winch area:

$$A_2 = 0,75 A_1$$

= required freeing port area each side in way of the recess

Where the winch is enclosed in a non-weather-tight compartment freeing ports are not required but adequate drainage by means of scuppers is to be provided.





# Special Features

# Part 3, Chapter 9

Sections 1 &amp; 2

## Section

- 1 **General**
- 2 **Timber deck cargoes**
- 3 **Decks loaded by wheeled vehicles**
- 4 **Movable decks**
- 5 **Helicopter landing areas**
- 6 **Strengthening requirements for navigation in ice – Application of requirements**
- 7 **Strengthening requirements for navigation in first-year ice conditions**
- 8 **Strengthening requirements for navigation in multi-year ice conditions**
- 9 **Strengthening requirements for navigation in very light first-year ice conditions**
- 10 **Lifting appliances and support arrangements**
- 11 **Freight container securing arrangements**
- 12 **Bottom strengthening for loading and unloading aground**
- 13 **Strengthening for regular discharge by heavy grabs**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter are to be taken in conjunction with the Chapters of Parts 3 and 4 applicable to the particular ship type.

### 1.2 Symbols

1.2.1 The following symbols and definitions are applicable to this Chapter:

- $k$  = higher tensile steel factor, see Ch 2,1.2
- $l$  = overall length, of the stiffening member, in metres
- $l_e$  = effective length, in metres, of the stiffening member, measured between span points, see Ch 3,3.3
- $s$  = spacing, of stiffeners, in mm
- $B$  = moulded breadth of ship, in metres, see Ch 1,6.1
- $L$  = length of ship, in metres, see Ch 1,6.1
- $Z$  = section modulus of the stiffening member, in  $\text{cm}^3$ , see Ch 3,3.2.

1.2.2 Other symbols are defined in the appropriate Section.

## ■ Section 2 Timber deck cargoes

### 2.1 Application

2.1.1 Where timber load lines are to be assigned, the full requirements of this Section are to be complied with, and the ship will be eligible to be assigned the notation 'timber deck cargoes'.

2.1.2 In other cases, proposals to carry timber deck cargoes which will impose on the weather deck a mean cargo loading in excess of  $8,5 \text{ kN/m}^2$  ( $0,865 \text{ tonne-f/m}^2$ ) will be considered on the basis of these requirements. In particular, the requirements of 2.5 to 2.8 are to be complied with.

### 2.2 Symbols and definitions

2.2.1 The term 'timber deck cargo' means a cargo of timber carried on an uncovered part of the freeboard or super-structure deck. The term does not include wood pulp or similar cargo.

2.2.2 The symbols used in this Section are defined as follows:

- $C$  = mean stowage rate, in  $\text{m}^3/\text{tonne}$ , of the timber deck cargo, making allowance for normal battens, etc.
- $h$  = the height, in metres, to which the timber deck cargo is to be stowed, measured vertically from the deck or hatch cover as applicable.

2.2.3 Other symbols are defined in 1.2.

### 2.3 Statutory Requirements

2.3.1 Attention is drawn to the requirements of the *International Load Line Convention, 1966*, concerning timber deck cargoes, and also to National Regulations.

2.3.2 A timber deck cargo loading and lashing plan, showing the stowage and securing of the timber cargo and the walkway/life-line arrangements, is to be submitted for approval, and a copy placed on board the ship for the information of the Master.

2.3.3 Timber freeboards cannot be used where wood pulp is being carried as the deck cargo. Packaged timber (timber which has been prelashed) may be carried on deck with the ship at its timber freeboards.

2.3.4 Type 'B-60' ships may have timber freeboards assigned based on ordinary Type 'B' freeboards.

2.3.5 Timber freeboards are not appropriate for ships which are assigned freeboards from a second deck. However, where the maximum geometric upper deck draught is restricted, a restricted timber draught may be assigned.

# Special Features

# Part 3, Chapter 9

Section 2

2.3.6 It is the Owner's/Master's responsibility to supply loose gear (e.g. uprights, wire lashings and life-lines) in accordance with the approved timber deck cargo loading and lashing plan when the ship is carrying timber deck cargoes at timber freeboards. However, it is not a requirement that loose gear remains permanently on board a ship assigned timber freeboards.

## 2.4 Arrangements

2.4.1 Double bottom tanks within the midship half-length are to have adequate longitudinal subdivision.

2.4.2 A forecastle of at least standard height and of length at least 0,07L is to be fitted. In addition, in ships of less than 100 m in length, a poop of at least standard height, or a raised quarterdeck with a deckhouse or strong steel hood of at least the same total height, is to be fitted.

2.4.3 Uprights are to be of adequate strength. Where timber uprights are used, it is the responsibility of the Master to use timber which is of a type and grade which has proved satisfactory for the purpose.

2.4.4 Where only packaged timber is to be carried, uprights may be omitted.

2.4.5 The spacing of the uprights is to be suitable for the length and character of the timber to be carried but should not exceed 3 m.

2.4.6 Each upright is to extend above the top of the cargo and be fitted with a strap or bracket support at the top of the bulwark to hold it upright whilst loading.

2.4.7 Strong permanent bulwarks, or efficient rails of specially strong construction, are to be fitted. Steel bulwarks, along with guard rails and stanchions, are acceptable as supports for uprights, provided substantial sockets are built for each upright.

2.4.8 Deck sockets are to be of a size to suit the dimensions of the uprights and are to be not less than 100 mm in depth with drainage provided. They are to be efficiently connected to the hull structure. A locking pin or wedge is to be provided to prevent the upright lifting out of the socket.

2.4.9 The timber deck cargo is to be secured along its length by independent overall lashings.

2.4.10 The spacing of lashings is to be determined by the height of the cargo above the deck:

- (a) For a height not exceeding 4 m, the spacing should not be more than 3 m.
- (b) For a height of 6 m and above, the spacing should not be more than 1,5 m where the timber uprights are used.
- (c) At intermediate heights, the average spacing is to be obtained by linear interpolation.

2.4.11 Lashings are to be provided 0,6 m and 1,5 m from the ends of timber deck cargoes where there is no end bulkhead.

2.4.12 Where only packaged timber is to be carried, and uprights are omitted, lashings are to be spaced 1,5 m apart.

2.4.13 Lashings are to be not less than 19 mm close link chain, or flexible wire rope of equivalent strength, fitted with slip hooks and turnbuckles which are accessible at all times. Wire rope lashings are to have a short length of long link chain to permit the length of the lashings to be regulated.

2.4.14 Lashings and fittings are to have a minimum SWL of 2700 kg and 2800 kg respectively. Each component is to be proof loaded to twice the SWL, and should not show any sign of damage or deformation afterwards.

2.4.15 Where timber is in lengths less than 3,6 m, the spacing of lashings is to be reduced, or other suitable provisions made to suit the length of the timber.

2.4.16 Eye plates are to be of substantial construction, effectively connected to the hull structure, and placed at intervals determined from 2.4.10, 2.4.11 or 2.4.12. The distance from a superstructure end bulkhead to the first eye plate is to be not more than 2 m.

2.4.17 A walkway is to be provided over the timber deck cargo. This walkway is either to be:

- (a) At, or near, the centreline of the ship, consisting of two sets of guard wires, spaced 1 m apart, each with three courses of wires, the lower spaced at 230 mm and the remainder at 380 mm. Stanchions are to be not more than 3 m apart, and these are to be secured to the timber cargo by spikes, or other equivalent means. A polypropylene net, with a mesh not greater than 230 mm x 230 mm, in conjunction with stanchions and top and bottom wires, may also be accepted, or
- (b) where the timber uprights are taken up 1 m above the top of the timber cargo, three courses of guard wires spaced not more than 350 mm apart, secured to the uprights from forward to aft, port and starboard, with a single wire life-line fitted at the centreline of the ship adequately supported by stanchions spaced not more than 10 m apart.

2.4.18 Safe access is to be provided from the top of the timber deck cargo to poop and forecastle decks.

2.4.19 All openings in the weather deck are to be capable of being properly closed and secured tight. Ventilators, air pipes and other fittings enclosing openings are to be efficiently protected against damage.

2.4.20 Access hatches, vents, air pipes, fire hydrants, hoses, valve operating positions, sounding pipes and other essential equipment are to be clearly marked and left accessible.

2.4.21 The timber deck cargo is to extend athwartships as close as possible to the ship's side, due allowance being made for obstructions provided any gap thus created at the side of the ship does not exceed a mean of four per cent of the breadth.

2.4.22 The timber is to be stowed as solidly as possible to at least the standard height of a superstructure other than a raised quarter deck.

# Special Features

# Part 3, Chapter 9

Sections 2 & 3

## 2.5 Longitudinal strength

2.5.1 The proposed timber deck loading conditions are to be taken into account in the longitudinal strength calculations, see Chapter 4, and details are to be included in the ship's Loading Manual.

## 2.6 Deck loading and scantlings

2.6.1 In general, the stowage rate,  $C$ , of timber deck cargoes is to be taken as:

- (a) for round timber and logs:  
 $C = 2,1 \text{ m}^3/\text{tonne}$
- (b) for packaged sawn timber:  
 $C = 1,45 \text{ m}^3/\text{tonne}$ .

These values are based on the total volume occupied by the cargo, including normal battens, etc., measured from bulwark to bulwark, and deck, or hatch cover, to top of cargo.

2.6.2 Where it is proposed to store timber more densely than that corresponding to the above values, the appropriate value of  $C$  is to be used.

2.6.3 The load height,  $h$ , of the cargo at any position is to be determined from the overall heights of cargo stowage as supplied by the Shipbuilder. Where the height of cargo varies, a mean effective load height is to be adopted. Attention is drawn to the limitation on height of cargo contained in the Load Lines Conventions where these apply.

2.6.4 A scantling correction factor,  $K$ , is to be determined from  $K = \frac{h}{1,08C}$ , and the hull scantlings are to

be increased as follows:

- (a) **Deck longitudinals.** The section modulus is to be multiplied by the factor  $0,5 (1 + K)$ .
- (b) **Deck beams.** The load head contained in the expression for section modulus is to be multiplied by  $K$ , and the section modulus determined using the increased value.
- (c) **Deck girders and transverses.** The section modulus is to be multiplied by the factor  $K$ .
- (d) **Pillars and deck supporting structure.** The design load is to be multiplied by the factor  $K$ , and scantlings determined using the increased value.
- (e) **Side structure.** The arrangement and scantlings of side structure are to be considered, and increased scantlings of framing may be required.

## 2.7 Scantlings of hatch covers

2.7.1 The section modulus and moment of inertia of hatch cover webs and stiffeners determined from Pt 3, Ch 11 are to be multiplied by the factor  $\frac{1,39h}{h_H C}$  where  $h_H$  is defined in Ch 3,5.1.

2.7.2 The hatch cover securing and support arrangements, stoppers, etc., and coamings are to be suitably reinforced to take account of increased loading from timber deck cargoes, see Ch 11,4.2.

## 2.8 Direct calculations

2.8.1 As an alternative to the above, the scantlings of the deck and side structure, and of hatch covers, may be assessed using direct calculations based on the proposed loading of the ship.

2.8.2 In the case of hatch covers, the stress and deflection criteria given in Table 11.2.3 in Chapter 11 corresponding to a uniformly distributed weather load are not to be exceeded.

## Section 3 Decks loaded by wheeled vehicles

### 3.1 General

3.1.1 Where it is proposed either to stow wheeled vehicles on the deck or to use wheeled vehicles for cargo handling, the deck and supporting structure are to be designed on the basis of the maximum loading to which they may be subjected in service. Where applicable, the hatch covers are to be similarly designed. In no case, however, are the scantlings to be less than would be required as a weather or cargo deck or hatch cover, as applicable.

3.1.2 The vehicles, types and axle loads, for which the vehicle carrying decks including, where applicable, hatch covers have been approved, are to be stated in the Loading Manual and be contained in a notice displayed on each deck.

### 3.2 Symbols

3.2.1 The symbols used in this Section are defined in 1.2 and in the appropriate sub-Section.


### 3.3 Loading

3.3.1 Details of the deck loading resulting from the proposed stowage or operation of vehicles are to be supplied by the Shipbuilder. These details are to include the wheel load, axle and wheel spacing, tyre print dimensions and type of tyre for the vehicles.

3.3.2 For design purposes, where wheeled vehicles are to be used for cargo handling, the deck is to be taken as loaded with a normal head cargo, except in way of the vehicle.

Table 9.3.1 Deck plate thickness calculation

Symbols	Expression	
$a, s, u,$ and $v$ as defined in Fig. 9.3.1 $n$ = tyre correction factor, see Table 9.3.3 $P_w$ = load, in tonnes, on the tyre print. For closely spaced wheels the shaded area shown in Fig. 9.3.1 may be taken as the combined print $P_1$ = corrected patch load, in tonnes $\lambda$ = dynamic magnification factor $\phi_1$ = patch aspect ratio correction factor $\phi_2$ = panel aspect ratio correction factor $\phi_3$ = wide patch load factor	$P_1 = \phi_1 \phi_2 \phi_3 \lambda P_w$	
	$\phi_1 = \frac{2v_1 + 1,1s}{u_1 + 1,1s}$	$v_1 = v,$ but $\triangleright s$ $u_1 = u,$ but $\triangleright a$
	$\phi_2 = 1,0$ $= \frac{1}{1,3 - \frac{0,3}{s}(a - u)}$ $= 0,77 \frac{a}{u}$	for $u \leq (a - s)$ for $a \geq u > (a - s)$ for $u > a$
	$\phi_3 = 1,0$ $= 0,6 \frac{s}{v} + 0,4$ $= 1,2 \frac{s}{v}$	for $v < s$ for $1,5 > \frac{v}{s} \geq 1,0$ for $\frac{v}{s} \geq 1,5$
	$\lambda = 1,25$ for harbour conditions $= (1 + 0,7n)$ for sea-going conditions	



# Special Features

# Part 3, Chapter 9

Section 3

## 3.4 Deck plating

3.4.1 The deck plate thickness,  $t$ , is to be not less than:

$$t = t_1 + t_c \quad \text{mm}$$

where

$t_c$  = wear and wastage allowance determined from Table 9.3.2

$$t_1 = \frac{\alpha s}{1000\sqrt{k}} \quad \text{mm}$$

$P_1$  = corrected patch load obtained from Table 9.3.1

$\alpha$  = thickness coefficient obtained from Fig. 9.3.1

$\beta$  = tyre print coefficient used in Fig. 9.3.1

$$= \log_{10} \left( \frac{P_1 k^2}{s^2} \times 10^7 \right)$$

**Table 9.3.2 Wear and wastage allowance**

Location	$t_c$ , in mm
Strength deck, weather decks, decks forming crown of tank, inner bottom	1,5
Internal decks elsewhere	0,75

**Table 9.3.3 Tyre correction factor,  $n$**

Number of wheels in idealized patch	Pneumatic tyres	Solid rubber tyres	Steel or solid tyres
1	0,6	0,8	1,0
2 or more	0,75	0,9	1,0

3.4.2 Where transversely framed decks contribute to the hull girder strength, or where secondary stiffening is fitted perpendicular to the direction of vehicle lanes, the thickness,  $t$ , derived from 3.4.1 is to be increased by 1,0 mm.

3.4.3 Where decks are designed for the exclusive carriage of unladen wheeled vehicles, the deck plate thickness,  $t$ , may be reduced as follows:

$$t = (t_1 - 0,75) + t_c \quad \text{mm}$$

3.4.4 Where it is proposed to carry tracked vehicles, the patch dimensions may be taken as the track print dimensions and  $P_w$  is to be taken as half the total weight of the vehicle. The wear and wastage allowance from Table 9.3.2 is to be increased by 0,5 mm. Deck fittings in way of vehicle lanes are to be recessed.

3.4.5 If wheeled vehicles are to be used on insulated decks or tank tops, consideration will be given to the permissible loading in association with the insulation arrangements and the plating thickness.

## 3.5 Deck longitudinals and beams

3.5.1 The section modulus,  $Z$ , of deck longitudinals or beams is to be not less than that required for a weather or cargo deck as appropriate, nor less than the following:

(a) For general purpose cargo decks where fork lift trucks are to be used:

$$Z = (0,375K_1 P l_e + 0,00125 K_2 h s l_e^2) k \quad \text{cm}^3$$

(b) For permanent vehicle decks in association with a value of  $h$  which need not exceed 2,5 m:

$h$  = normal load height on the deck, in metres

$P$  = total weight, in tonnes, of the vehicle divided by the number of axles. Where distribution of weight is not uniform,  $P$  is to be taken as the maximum axle load. For fork lift trucks the total weight is to be applied to one axle

$$Z = (0,536K_1 P l_e + 0,00125 K_2 h s l_e^2) k \quad \text{cm}^3$$

where the values of  $K_1$  and  $K_2$  are given in Table 9.3.4

(c) For decks designed for the carriage of wheeled vehicles only that required to satisfy the most severe arrangement of print wheel loads on the stiffener in association with a bending stress of  $\frac{100}{k}$  N/mm<sup>2</sup>  $\left( \frac{10,2}{k} \text{ kgf/mm}^2 \right)$

assuming 100 per cent end fixity.

**Table 9.3.4 Values of  $K_1$  and  $K_2$**

Wheel spacing* Beam span	$K_1$	$K_2$
0,1	15,4	1,89
0,2	14,6	1,845
0,3	13,35	1,730
0,4	11,8	1,55
0,5 and greater	10,1	1,30
* Outer wheel to outer wheel on axles with multiple wheel arrangements		

## 3.6 Deck girders and transverses

3.6.1 Where the load on deck girders and transverses is uniformly distributed, the section modulus is to be not less than:

$$Z = 4,75b h l_e^2 k \quad \text{cm}^3$$

where

$h$  is defined in 3.5.1

$b$  = mean width of plating supported by a deck girder or transverse, in metres.

3.6.2 Where the member supports point loads, with or without the addition of uniformly distributed load, the section modulus is to be based on a stress of  $\frac{123,6}{k}$  N/mm<sup>2</sup>

$\left( \frac{12,6}{k} \text{ kgf/mm}^2 \right)$ , assuming 100 per cent end fixity.

3.6.3 Where it is proposed to carry tracked vehicles, the total weight of the vehicle is to be taken when determining the section modulus of the transverse at the top of a ramp or at other changes of gradient.

3.7 Direct calculations

3.7.1 As an alternative to the above, permissible deck loads may be determined by direct calculation. The assumed loadings in these calculations are to include suitable allowance for weather, generally 2,16 kN/m<sup>2</sup> (0,22 tonne-f/m<sup>2</sup>), where applicable.

3.8 Hatch covers

3.8.1 Where wheeled vehicles are to be used, the hatch cover plating is to be not less in thickness than that required by 3.4, and the modulus of the stiffeners is to be not less than:

$$Z = (K_3 P I_e + 0,00167 K_4 h s I_e^2) k$$

where the values of  $K_3$  and  $K_4$  are given in Table 9.3.5 and  $P$  and  $h$  are defined in 3.5.1.

In no case, however, are the scantlings of plating and stiffeners to be less than would be required as a weather or cargo deck hatch cover, as applicable.

Table 9.3.5 Values of  $K_3$  and  $K_4$

Wheel spacing* Stiffener span	$K_3$	$K_4$
0,1	11,96	2,32
0,2	10,69	1,89
0,3	9,58	1,55
0,4	8,46	1,28
0,5	7,46	1,07
0,6	6,51	0,91
0,7	5,55	0,73
0,8	4,23	0,36
0,9	2,38	0,11
* Outer wheel to outer wheel on axles with multiple wheel arrangements		

3.8.2 Where unusual arrangements of hatch cover stiffening are proposed, the scantlings may be determined by direct calculations using a two-dimensional grillage idealization, and the parameters given in Table 11.2.3 in Chapter 11.

3.9 Train decks

3.9.1 Decks for the transport of railway rolling stock on fixed rails will be specially considered.

3.10 Heavy and special loads

3.10.1 Where heavy or special loads, such as machinery transporters, are proposed to be carried, the scantlings and arrangements of the deck structure will be individually considered.

3.11 Securing arrangements

3.11.1 Details of the connections to the hull of vehicle securing arrangements are to be submitted for approval.

Section 4  
Movable decks

4.1 Classification

4.1.1 Movable decks other than those described in 4.1.2 are not a classification item, although consideration must be given to associated supporting structure. Where movable decks are fitted, it is recommended that they be based on the requirements of this Section.

4.1.2 At the Owner's or Builder's request, however, movable decks will be included as a classification item, and the class notation 'movable decks' will be entered in the *Register Book*. In such cases, all movable decks on board the ship are to comply with the requirements of this Section.

4.2 Symbols

4.2.1 The symbols used in this Section are defined in 1.2 and in the appropriate sub-Section.

4.3 Arrangements and design

4.3.1 Movable decks are generally to be constructed as pontoons comprising a web structure with top decking. Other forms of construction will be individually considered.

4.3.2 These requirements assume that the pontoons are to be constructed of steel. Other materials will be considered on the basis of equivalent strength.

4.3.3 Positive means of control are to be provided to secure decks in the lowered position.

4.3.4 The decks are to be efficiently supported, and hinges, pillars, chains or other means (or a combination of these) are to be designed on the basis of the imposed loads. Where supporting chains and fittings are required, they are to have a factor of safety of at least two on the proof load.

4.3.5 Plans showing the proposed scantlings and arrangements of the system are to be submitted.

4.3.6 Where it is proposed to stow the pontoons on deck, when not in use, details of the proposals for racks, fittings, etc., are to be submitted for consideration.

## Special Features

## Part 3, Chapter 9

Sections 4 &amp; 5

### 4.4 Loading

4.4.1 Details of the deck loading resulting from the proposed stowage arrangements of vehicles are to be supplied by the Shipbuilder. These details are to include the axle and wheel spacing, the wheel load, type of tyre and tyre print dimensions for the vehicles. For design purposes the axle loading is to be taken as not less than 5,9 kN (0,6 tonne-f).

4.4.2 Where it is proposed also to use the decks for general cargo, the design loadings are to be submitted for consideration.

### 4.5 Pontoon deck plating

4.5.1 Where the pontoon is constructed of steel decking with stiffening webs, the deck plate thickness,  $t$ , is to be not less than that required by 3.4.

4.5.2 The plate thickness,  $t$ , for aluminium pontoons is to be not less than:

$$t = (1,4t_1 + 0,75) \text{ mm}$$

where

$t_1$  is the mild steel thickness as determined from 3.4. For aluminium pontoons designed for the exclusive carriage of unladen wheeled vehicles:

$$t = 1,4t_1 \text{ mm}$$

4.5.3 Where it is proposed to use plywood decking, the arrangement and thickness will be considered. Plywood alone, is not, generally, to be used for axle loads in excess of 7,8 kN (0,8 tonne-f).

4.5.4 Attention is drawn to National fire regulations which in certain cases may ban the use of plywood and certain other materials in 'special category spaces' on passenger ships.

### 4.6 Pontoon webs and stiffeners

4.6.1 The section modulus of webs and stiffening of steel pontoons is to be not less than:

(a) For general purpose cargo decks where fork lift trucks may be used:

$$Z = (0,375K_1 P I_e + 0,00125K_2 h s I_e^2) k \text{ cm}^3$$

(b) For decks designed for the carriage of vehicles only:

$$Z = 1,39K_1 P I_e k \text{ cm}^3$$

where the values of  $K_1$  and  $K_2$  are given in Table 9.4.1, and

$h$  = load height of cargo on the deck, where this is proposed to be carried, in metres

$P$  = total weight, in tonnes, of the vehicle divided by the number of axles. Where the distribution of weight is not uniform,  $P$  is to be taken as the greatest axle load. For fork lift trucks the total weight is to be applied to one axle.

4.6.2 The section modulus of webs and stiffening of aluminium pontoons is to be not less than that defined in 4.6.1 replacing  $k$  by  $k_a$  where  $k_a$  is defined in Ch 2,1.

**Table 9.4.1 Values of  $K_1$  and  $K_2$**

Wheel spacing* Beam span	$K_1$	$K_2$
0,1	15,4	1,89
0,2	14,6	1,845
0,3	13,35	1,730
0,4	11,8	1,55
0,5 and greater	10,1	1,30
* Outer wheel to outer wheel on axles with multiple wheel arrangements		

4.6.3 Where plywood decking is proposed, or in other arrangements where the decking is not integral with the stiffening webs, the arrangement of the grillage of webs is to be such as to provide the required strength.

### 4.7 Deflection

4.7.1 Where wheeled vehicles are to be used, the supporting arrangements are to be such that the movement at the edge of one pontoon relative to the next does not exceed 50 mm during loading or unloading operations.

### 4.8 Direct calculations

4.8.1 As an alternative to 4.3 to 4.7, the structure may be designed on the basis of a direct calculation using a grillage idealization. The method adopted and the stress levels proposed for the material of construction are to be submitted for consideration.

## Section 5 Helicopter landing areas

### 5.1 General

5.1.1 Where it is proposed to provide a helicopter landing area on the ship, the structure is to be designed to suit the largest helicopter type which it is intended to use.

5.1.2 Attention is drawn to the requirements of National and other Authorities concerning the construction of helicopter landing platforms and the operation of helicopters as they affect the ship.

5.1.3 Plans are to be submitted showing the proposed scantlings and arrangements of the structure. The type, size and weight of helicopters to be used are also to be indicated. Details of the helicopter types to be used are to be included in the Loading Manual (see Ch 4,8.2) and be contained in a notice displayed on the helicopter landing deck.

5.1.4 Where the landing area forms part of a weather or erection deck, the scantlings are to be not less than those required for decks in the same position.

# Special Features

# Part 3, Chapter 9

Section 5

## 5.2 Symbols

5.2.1 The symbols in this Section are defined in 1.2 and in the appropriate sub-Section.

## 5.3 Arrangements

5.3.1 The landing area is to be sufficiently large to allow for the landing and manoeuvring of the helicopter, and is to be approached by a clear landing and take-off sector complying in extent with the applicable Regulations.

5.3.2 The landing area is to be free of any projections above the level of the deck. Projections in the zone surrounding the landing area are to be kept below the heights permitted by the Regulations.

5.3.3 Suitable arrangements are to be made to minimize the risk of personnel or machinery sliding off the landing area. A non-slip surface and anchoring devices are to be provided.

5.3.4 Arrangements are to be made for drainage of the platform, including drainage of spilt fuel. These arrangements are to be constructed of steel and lead directly overboard, independent of any other system, and shall be designed so that drainage does not fall onto any other part of the ship.

5.3.5 If the helideck is constructed from aluminium alloy, the following provisions apply:

- (a) the deckhouse top and bulkheads under the platform shall have no openings;
- (b) windows under the platform are to be provided with steel shutters.

5.3.6 Engine uptake arrangements are to be sited such that exhaust gases cannot be drawn into helicopter engine intakes during helicopter take off or landing operations.

## 5.4 Landing area plating

5.4.1 The deck plate thickness,  $t$ , within the landing area is to be not less than:

$$t = t_1 + 1,5 \text{ mm}$$

where

$$t_1 = \frac{\alpha s}{1000\sqrt{k}} \text{ mm}$$

$\alpha$  = thickness coefficient obtained from Fig. 9.3.1

$\beta$  = tyre print coefficient used in Fig. 9.3.1

$$= \log_{10} \left( \frac{P_1 k^2}{s^2} \times 10^7 \right)$$

The plating is to be designed for the emergency landing case taking:

$$P_1 = 2,5 \phi_1 \phi_2 \phi_3 f \gamma P_w \text{ tonnes}$$

in which  $\phi_1, \phi_2, \phi_3$  are to be determined from Table 9.3.1

$f = 1,15$  for landing decks over manned spaces, e.g., deckhouses, bridges, control rooms, etc.

$= 1,0$  elsewhere

$P$  = the maximum all-up weight of the helicopter, in tonnes

$P_w$  = landing load, on the tyre print in tonnes;  
for helicopters with a single main rotor,  $P_w$  is to be taken as  $P$  divided equally between the two main undercarriages,

for helicopters with tandem main rotors,  $P_w$  is to be taken as  $P$  distributed between all main undercarriages in proportion to the static loads they carry

$\gamma$  = a location factor given in Table 9.5.1.

The tyre print dimensions specified by the manufacturer are to be used for the calculation. Where these are unknown, it may be assumed that the print area is 300 x 300 mm and this assumption is to be indicated on the submitted plan.

**Table 9.5.1 Location factor**

Location	$\gamma$
On decks forming part of the hull girder	0,71
(a) within 0,4L amidships	
(b) at the F.P. or A.P.	0,6
Elsewhere	0,6

Values for intermediate locations are to be determined by interpolation

5.4.2 The plate thickness for aluminium decks is to be not less than:

$$t = 1,4t_1 + 1,5 \text{ mm}$$

where  $t_1$  is the mild steel thickness as determined from 5.4.1.

5.4.3 For helicopters fitted with landing gear consisting of skids, the print dimensions specified by the manufacturer are to be used. Where these are unknown, it may be assumed that the print consists of a 300 mm line load at each end of each skid, when applying Fig. 9.3.1.

## 5.5 Deck stiffening and supporting structure

5.5.1 The helicopter deck stiffening and the supporting structure for helicopter platforms is to be designed for the load cases given in Table 9.5.2 in association with the permissible stresses given in Table 9.5.3.

5.5.2 The minimum moment of inertia,  $I$ , of aluminium secondary structure stiffening is to be not less than:

$$I = \frac{5,25}{k_a} Z l_e \text{ cm}^4$$

where  $Z$  is the required section modulus of the aluminium stiffener and attached plating and  $k_a$  as defined in 4.6.2.

5.5.3 Where a grillage arrangement is adopted for the platform stiffening, it is recommended that direct calculation procedures be used.



# Special Features

# Part 3, Chapter 9

Section 5

**Table 9.5.2 Design load cases for deck stiffening and supporting structure**

Loadcase	Loads			
	Landing area		Supporting structure (See Note 1)	
	UDL	Helicopter (See Note 2)	Self weight	Horizontal load (See Note 2)
(1) Overall distributed loading	$\frac{2}{(0,2)}$	—	—	—
(2) Helicopter emergency landing	$\frac{0,2}{(0,02)}$	$2,5Pf$	$W$	$0,5P$
(3) Normal usage	$\frac{0,5}{(0,05)}$	$1,5P$	$W$	$0,5P + 0,5W$
Symbols				
<p><math>P</math> and <math>f</math> as defined in 5.4.1  <math>UDL</math> = Uniformly distributed vertical load over entire landing area, kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>)  <math>W</math> = structural weight of helicopter platform</p>				
<p>NOTES</p> <p>1. For the design of the supporting structure for helicopter platforms, applicable self weight and horizontal loads are to be added to the landing area loads.</p> <p>2. The helicopter is to be so positioned as to produce the most severe loading condition for each structural member under consideration.</p>				

**Table 9.5.3 Permissible stresses for deck stiffening and supporting structure**

Loadcase (See Table 9.5.2)	Permissible stresses, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )			
	Deck secondary structure (beams, longitudinals) (See Notes 1 and 2)	Primary structure (transverses, girders, pillars, trusses)	All structure	
	Bending		Combined bending and axial	Shear
(1) Overall distributed loading	$\frac{147}{k} \left( \frac{15}{k} \right)$	$\frac{147}{k} \left( \frac{15}{k} \right)$	0,6σ <sub>c</sub>	$\frac{\text{Bending}}{\sqrt{3}}$
(2) Helicopter emergency landing	$\frac{245}{k} \left( \frac{25}{k} \right)$	$\frac{220,5}{k} \left( \frac{22,5}{k} \right)$	0,9σ <sub>c</sub>	
(3) Normal usage	$\frac{176}{k} \left( \frac{18}{k} \right)$	$\frac{147}{k} \left( \frac{15}{k} \right)$	0,6σ <sub>c</sub>	
Symbols				
<p><i>k</i> = a material factor : = as defined in 1.2 for steel members = <i>k<sub>a</sub></i> as defined in 4.6.2 for aluminium alloy members σ<sub>c</sub> = yield stress, 0,2% proof stress or compressive buckling stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>), whichever is the lesser</p>				
NOTES				
<p>1. For strength deck longitudinals and girders, the permissible bending stresses are to be reduced as follows: (a) within 0,4L of amidships – by 30% (b) at the F.P. or A.P. – by 0% Values at intermediate locations are to be determined by interpolation between (a) and (b).</p> <p>2. When determining bending stresses in secondary structure, for compliance with the above permissible stresses, 100% end fixity may be assumed.</p>				

## 5.6 Bimetallic connections

5.6.1 Where aluminium alloy platforms are connected to steel structures, details of the arrangements in way of the bimetallic connections are to be submitted.

■

Section 6

Strengthening requirements for navigation in ice – Application of requirements

6.1 Additional strengthening

6.1.1 Where additional strengthening is fitted in accordance with the requirements given in Sections 7 and 8, an appropriate special features notation will be assigned. It is the responsibility of the Owner to determine which notation is most suitable for his requirements. For material requirements, see Ch 2,2. For machinery requirements, see Pt 5, Ch 9.

6.1.2 Where a special features notation is desired, the ship is to comply with the requirements of the applicable Sections, in addition to those for sea-going service, so far as they are applicable.

6.1.3 Ships that comply with the requirements of the Finnish Swedish Ice Class Rules in force at the time of contract and Section 7, for Ice Class **IA Super**, **IA**, **IB** and **IC** may be assigned the corresponding notations Ice Class **1AS FS**, Ice Class **1A FS**, Ice Class **1B FS** or Ice Class **1C FS**. The Finnish Swedish Ice Class Rules may be obtained from the following website:  
[www.fma.fi](http://www.fma.fi)

6.1.4 The requirements for **Ice Class 1D** are for ships intended to navigate in light first year ice conditions. The requirements for strengthening the forward region, the rudder and steering arrangements for **Ice Class 1C FS** are applicable.

6.1.5 The requirements for Ice Class **IE** are for offshore supply ships, as defined in Pt 4, Ch 4, and are intended to navigate in very light first-year ice conditions, such as in brash ice and small ice pieces. The requirements of Section 9 are to be complied with.

6.1.6 For ships where the ice class notation Ice Class **1AS FS(+)**, Ice Class **1A FS(+)**, Ice Class **1B FS(+)** or Ice Class **1C FS(+)** is requested, the requirements of the Finnish Swedish Ice Class Rules in force at the time of contract, and Section 7, and Pt 5, Ch 9,4 are to be complied with.

6.1.7 The requirements for strengthening for navigation in ice, as given in Section 8, are intended for ships operating in multi-year ice in Arctic or Antarctic ice conditions under their own power.

6.2 Geographical zones

6.2.1 Ships intending to navigate in the Canadian Arctic must comply with the *Canadian Arctic Shipping Pollution Prevention Regulations* established by the Consolidated Regulations of Canada, 1978, Chapter 353, in respect of which Lloyd’s Register (hereinafter referred to as ‘LR’) is authorized to issue Arctic Pollution Prevention Certificates.

6.2.2 The Canadian Arctic areas have been divided into zones relative to the severity of the ice conditions experienced and, in addition to geographic boundaries, each zone has seasonal limits affecting the necessary ice class notation required to permit operations at a particular time of year. It is the responsibility of the Owner to determine which notation is most suitable for his requirements.

6.2.3 The Canadian Authorities recognize that in the period November 6 to July 31 and any extension to that period declared by the Canadian Coast Guard, oil and bulk chemical tankers which qualify for Canadian Type A, B, C and D as indicated in Table 9.6.1 are suitable for operating in designated ice control zones within Canadian waters, off the east coast of Canada south of 60° north latitude. For all Type E tankers operating in this zone during the specified period, the Canadian Authorities will require either additional hull strength in way of the forward wing cargo tanks port and starboard, or the level of oil or chemical in these tanks to be not higher than one metre below the waterline of the ship in her condition of transit. Where the latter arrangement is adopted, the effect on longitudinal strength is to be considered.

Table 9.6.1 Canadian Types

Canadian Type	Lloyd’s Register Ice Class Notation	
Type A	100A1	Ice Class 1AS FS
Type B	100A1	Ice Class 1A FS
Type C	100A1	Ice Class 1B FS
Type D	100A1	Ice Class 1C FS and 1D
Type E	100A1	

6.3 Icebreakers

6.3.1 Sea-going ships specially designed for icebreaking duties will be assigned the ship type notation ‘Icebreaker’ in addition to the special features notation appropriate to the degree of ice strengthening provided.

■

Section 7

Strengthening requirements for navigation in first-year ice conditions

7.1 General

7.1.1 In addition to the requirements of the Finnish Swedish Ice Class Rules,the following sections are to be complied with for **Ice Class 1AS FS**, **Ice Class 1A FS**, **Ice Class 1B FS**, **Ice Class 1C FS** and **Ice Class 1D** where applicable. Alternative arrangements to attain similar performance will be specially considered.

# Special Features

# Part 3, Chapter 9

Section 7

**7.1.2** The ballast capacity of the ship is to be sufficient to give adequate propeller immersion in all ice navigating conditions without trimming the ship in such a manner that the actual waterline at the bow is below the ice light waterline. Ballast tanks situated above the ice light waterline and adjacent to the shell, which are intended to be used in ice navigating conditions, are to be provided with heating pipes.

**7.1.3** These Rules are formulated for both transverse and longitudinal framing systems but it is recommended that, whenever practicable, transverse framing is selected.

**7.1.4** These Rules assume that when approaching ice infested waters, the ship's speed will be reduced appropriately. The vertical extent of ice strengthening for ships intended to operate at speeds exceeding 15 knots in areas containing isolated ice floes will be specially considered.

**7.1.5** An icebreaking ship is to have a hull form at the fore end adapted to break ice effectively. It is recommended that bulbous bows are not fitted to Ice Class 1AS ships.

**7.1.6** The stern of an icebreaking ship is to have a form such that broken ice is effectively displaced.

**7.1.7** Where it is desired to make provision for short tow operations, the bow area is to be suitably reinforced. Similarly, icebreakers may require local reinforcement in way of the stern fork.

**7.1.8** The vertical extent of the ice strengthening is related to the ice light and ice load waterlines, which are defined in 7.3. The maximum and minimum Ice Class draughts at both the fore and aft ends will be stated on the Class Certificate. In addition, the minimum engine output, see Pt 5, Ch 9, will be stated on the Class Certificate.

## 7.2 Definitions

**7.2.1** The Ice Load Waterline corresponds to the Fresh Water Summer Loadline. Where specially requested and where permitted by the appropriate National Administration, an Ice Load Waterline may be specified which differs from the foregoing, but corresponds to the deepest condition in which the ship is expected to navigate in ice.

**7.2.2** The Ice Light Waterline is that corresponding to the lightest condition in which the ship is expected to navigate ice.

**7.2.3** The Ice Load Waterline and the Ice Light Waterline are to be indicated on the plans. For navigation in certain geographical areas, the relevant National Authority may require the maximum Ice Class draught to be marked on the ship in a specified manner.

**7.2.4** **Displacement**  $\Delta$  is the displacement, in tonnes, at the Ice Load Waterline when floating in water having a relative density of 1,0.

**7.2.5** **Shaft power**,  $P_0$  ( $H_0$ ), is the maximum propulsion shaft power, in kW (shp), for which the machinery is to be classed.

## 7.3 Framing – General requirements

**7.3.1** Where a frame intersects a boundary between two of the hull regions the scantling requirements applicable will be those for the forward region if the forward midship boundary is intersected or for the midship region if the aft midship boundary is intersected.

**7.3.2** The effective weld area attaching ice frames to primary members is not to be less than the shear area for the frames.

## 7.4 Primary longitudinal members supporting transverse ice framing

**7.4.1** The webs of primary longitudinal members supporting transverse ice frames are to be stiffened and connected to the main or intermediate frames so that the distance,  $r$ , between such stiffening is not to be greater than given according to the following formula:

$$r = \sqrt{\frac{291t^3}{\alpha_o \gamma^2}} \text{ mm}$$

where

$t$  = thickness, in mm, of the primary longitudinal member adjacent to the shell plating

$\alpha_o$  = longitudinal distribution factor as given in Table 9.7.1

(a) Forward region

$$\gamma = 0,653 + 3,217 \sqrt{P_0 \Delta} \times 10^{-5}$$

$$(\gamma = 0,653 + 2,76 \sqrt{H_0 \Delta} \times 10^{-5}), \text{ or}$$

$$\gamma = 0,876 + 9,908 \sqrt{P_0 \Delta} \times 10^{-6}$$

$$(\gamma = 0,876 + 8,5 \sqrt{H_0 \Delta} \times 10^{-6})$$

or  $\gamma = 1,0$  whichever is the least

where  $P_0$  ( $H_0$ ) and  $\Delta$  are as defined in 7.2.

(b) Midship and aft regions

$$\gamma = 0,653 + 9,908 \sqrt{P_0 \Delta} \times 10^{-6}$$

$$(\gamma = 0,653 + 8,5 \sqrt{H_0 \Delta} \times 10^{-6})$$

or  $\gamma = 0,79$ , whichever is the lesser.

**Table 9.7.1 Longitudinal distribution factor  $\alpha_o$**

Ice Class	$\alpha_o$		
	Forward	Midship	Aft
1AS FS	1,00	0,98	0,89
1A FS	0,87	0,75	0,64
1B FS	0,78	0,64	0,51
1C FS	0,68	0,53	0,37
1D	0,68	—	—

**7.4.2** The minimum thickness of the web plating of longitudinal primary members is to comply with the requirements of Ch 10,4.


## Special Features

## Part 3, Chapter 9

Section 7

### 7.5 Stem

7.5.1 The stem is to be made of rolled, cast or forged steel or of shaped steel plates. A sharp edged stem, as shown in Fig. 9.7.1 improves the manoeuvrability of the ship in ice.



7.5.2 The section modulus of the stem in the fore and aft direction is not to be less than determined in accordance with the following formula:

$$Z = 1500 (\alpha_o \gamma^2)^{3/2} \text{ cm}^3$$

where

$\alpha_o$  = longitudinal distribution factor for the forward region as given in Table 9.7.1

$\gamma$  is defined in 7.5.2.

7.5.3 The dimensions of a welded stem constructed as shown in Fig. 9.7.1 are to be determined in accordance with the following formula:

$$t = 31 \sqrt{\alpha_o \gamma^2} \text{ mm}$$

where

$t$  = thickness of the side plates, in mm.

7.5.4 In bulbous bow constructions, the extent of plating below the Ice Light Waterline should be such as to cover that part of the bulb forward of the vertical line originating at the intersection of the Ice Light Waterline and the stem contour at the centreline. A suitably tapered transition piece should be arranged between the reinforced stem plating and keel. However, in no case should the reinforced stem plating extend vertically below the Ice Light Waterline for less than 750 mm. The adjacent strake to the reinforced shaped stem plating of the bulb should be in accordance with the requirements for shell plating.

7.5.5 Where in the ice belt region the radius of the stem or bulb front plating is large, one or more vertical stiffeners are to be fitted in order to meet the section modulus requirement of 7.7.2. In addition, vertical ring stiffening will be required for the bulb.

7.5.6 The dimensions of the stem may be tapered to the requirements of Ch 5,3.3 at the upper deck. The connections of the shell plating to the stem are to be flush.

### 7.6 Stern

7.6.1 Where the screwshaft diameter exceeds the Rule diameter, the propeller post is to be correspondingly strengthened, see Ch 6,7.

### 7.7 Rudder and steering arrangements

7.7.1 Rudder scantlings, posts, rudder horns, solepieces, rudder stocks, steering engine and pintles are to be dimensioned in accordance with Chapters 6 and 13 as appropriate. The speed used in the calculations is to be the maximum service speed or that given in Table 9.7.3, whichever is the greater. When used in association with the speed given in Table 9.7.3, the hull form factor and the rudder profile coefficients are to be taken as 1,0.

**Table 9.7.2 Longitudinal distribution factor  $\alpha_p$**

Ice Class	$\alpha_p$		
	Forward	Midship	Aft
1AS FS	1,00	0,95	0,85
1A FS	0,98	0,86	0,73
1B FS	0,93	0,71	0,57
1C FS	0,86	0,53	0,38
1D	0,86	—	—

**Table 9.7.3 Minimum speed**

Ice Class	Minimum speed, in knots
1AS FS	20
1A FS	18
1B FS	16
1C FS	14
1D	14

7.7.2 For double plate rudders, the minimum thickness of plating and horizontal and vertical webs in the main ice belt zone is to be determined as for shell plating in the aft region. For the horizontal and vertical webs the corrosion-abrasion increment,  $c$ , need not be added. For Ice Class 1D, the minimum thickness of plating and webs, of double plate rudders and the extent of application are to be determined as for those in Ice Class 1C FS.

7.7.3 Where an ice class notation is included in the class of a ship, the nozzle construction requirements, as defined in Table 13.3.1 in Chapter 13, are to be upgraded to include abrasion allowance as follows:

Ice Class	Thickness increment
1AS FS	5 mm
1A FS	4 mm
1B FS	3 mm
1C FS	2 mm
1D	2 mm

However, the thickness of the shroud plating is not to be less than the shell plating for the aft region taking frame spacing  $s$  in the formula as 500 mm.

# Special Features

# Part 3, Chapter 9

Sections 7 & 8

7.7.4 The scantlings of the stock, pintles, gudgeon and solepiece associated with the nozzle are to be increased on the basis given in 7.7.1. However, the diameter of the nozzle stock is to be not less than that calculated in the astern condition taking the astern speed as half the speed given in Table 9.7.3 or the actual astern speed, whichever is the greater.

7.7.5 Nozzles with articulated flaps will be subject to special consideration.

7.7.6 For the ice classes **1AS FS** and **1A FS** the rudder stock and the upper edge of the rudder shall be protected against ice pressure by an ice knife or equivalent means. The ice knife is to extend down to the ice light waterline; this requirement may be waived where this would lead to impracticable ice knives, e.g. for ships with large draught variations.

7.7.7 For the ice classes **1AS FS** and **1A FS** due regard is to be paid to the excessive load caused by the rudder being forced out of the midship position when backing into an ice ridge. When vessels are intended to operate with significant time in astern operation, then the hull strength is to be based on the method used in the forward region, however due consideration may be given to the anticipated power in this mode of operation.

7.7.8 Relief valves for hydraulic pressure are to be effective, see Pt 5, Ch 19,3.3. The components of the rudder steering gear are to be able to withstand the yield torque of the rudder stock, see Pt 5, Ch 19,3.2.2. Rudder stoppers working on the rudder blade or rudder head are to be fitted.

(d) **Ice Class AC3:** The requirements for the assignment of this class are intended for ships designed to navigate in Arctic or Antarctic ice conditions equivalent to unbroken ice with a thickness of 3,0 m.

## 8.2 Application

8.2.1 The requirements of this Section are formulated on the assumption that ships having Ice Class AC notations will be longitudinally framed at the uppermost continuous deck and at the bottom. Alternative proposals will be specially considered.

8.2.2 The vertical extent of ice strengthening is related to the Ice Load Waterline or Deepest Ice Operating Waterline and the Ice Light Waterline as defined in 8.3. The maximum and minimum ice class draughts at both the fore and aft ends will be stated on the Class Certificate.

## 8.3 Definitions, see Fig. 9.8.1

8.3.1 The Ice Load Waterline corresponds to the Freshwater Load Line in summer as defined by the *1966 International Load Line Convention*.

8.3.2 A Deepest Ice Operating Waterline which differs from the Ice Load Waterline may be specified, where specially requested, and would correspond to the deepest condition in which the ship is expected to navigate in ice.

8.3.3 The Ice Light Waterline is that corresponding to the lightest condition in which the ship is expected to navigate in ice.

8.3.4 The Ice Load Waterline, the Deepest Ice Operating Waterline and the Ice Light Waterline should be indicated on the plans. For navigation in certain geographic areas, the relevant National Authority may require the maximum Ice Class draught to be marked on the ship in a specified manner.

8.3.5 For the purpose of defining the standard of ice strengthening required, which is dependent upon longitudinal and vertical position, the hull is divided longitudinally into three regions designated bow section, mid-body section and stern section. Each section is further subdivided in its depth so that the bow section contains the lower bow area, main bow area and that part of the upper transition area in way, the mid-body section contains the lower transition area, main mid-body area and that part of the upper transition area in way and the stern section contains the stern area and that part of the upper transition area in way. These divisions are shown in Fig. 9.8.1 and further defined in 8.3.6 and 8.3.21.

8.3.6 The bow section is that region between the forward boundary of the mid-body section and the stem, see also 8.3.9.


8.3.7 The mid-body section has its aft boundary a distance *S* forward of the A.P. and its forward boundary, except as provided by 8.3.9, a distance *F* aft of the F.P. The distances *F* and *S* are given in Fig. 9.8.1.

## Section 8 Strengthening requirements for navigation in multi-year ice conditions

### 8.1 Ice Class notations

8.1.1 Where the requirements of this Section are complied with, the ship will be eligible for the addition of the term 'Icebreaking' to the ship type notation, e.g. 'Icebreaking Bulk Carrier', 'Icebreaking Tanker', etc. In addition, one of the following special features notations will be assigned:

- (a) **Ice Class AC1:** The requirements for the assignment of this class are intended for ships designed to navigate in Arctic or Antarctic ice conditions equivalent to unbroken ice with a thickness of 1,0 m.
- (b) **Ice Class AC1,5:** The requirements for the assignment of this class are intended for ships designed to navigate in Arctic or Antarctic ice conditions equivalent to unbroken ice with a thickness of 1,5 m.
- (c) **Ice Class AC2:** The requirements for the assignment of this class are intended for ships designed to navigate in Arctic or Antarctic ice conditions equivalent to unbroken ice with a thickness of 2,0 m.



8.3.8 The stern section is that region between the stern and the aft boundary of the mid-body section.

8.3.9 Where the shoulder of the ship consists of a pronounced hard chine, this may be taken as the basis of the boundary between the bow and mid-body sections of the hull. This chine may be in the form of a reamer or of a knuckle line. In the latter case, an overlap of the bow section beyond this line by the lesser of 0,04L or 5 m may be necessary.

8.3.10 The main bow area is part of the bow section and extends vertically above the keel to a line a distance, H, above the Ice Load Waterline or Deepest Ice Operating Waterline, if applicable, at the F.P., and a distance AW above these waterlines at the main mid-body area, but need not include the area defined as lower bow area.

8.3.11 The main mid-body area is part of the mid-body section and extends vertically from a line a distance BW below the Ice Light Waterline to a line a distance AW above the Ice Load Waterline or Deepest Ice Operating Waterline, if applicable. The distances BW and AW are given in Fig. 9.8.1.

8.3.12 The stern area is part of the stern section. It has its upper edge a distance AW above the Ice Load Waterline or Deepest Ice Operating Waterline at its fore end and a distance C above these waterlines at the A.P. The lower edge of the stern region is a distance (BW + LT), below the Ice Light Waterline. The distances AW, C and LT are given in Fig. 9.8.1.

8.3.13 The main ice belt zone comprises the main bow area, main mid-body area and stern area.

8.3.14 The upper transition area extends a distance, UT, above the main ice belt zone.

8.3.15 The lower transition area is part of the mid-body section. Aft of amidships, it extends below the main mid-body area by a distance LT. Forward of amidships, its lower edge is a line drawn from a point a distance LT below the main mid-body area at amidships to the junction of the bilge boundary line with the aft end of the main bow area.

8.3.16 The lower bow area is that part of the bow section below the main bow area. Its upper edge is a line drawn from a point at the aft end of the bow section set a distance BW below the Ice Light Waterline to a point on the keel line set a distance E aft of the bow line's departure from the level keel line.

8.3.17 The lower transition area need not extend below the bilge boundary line by more than the value of LT (see Fig. 9.8.1) measured around the circumference of the bilge.

8.3.18 The Ice Belt comprises the main Ice Belt Zone together with the lower bow area and the upper and lower transition areas.

8.3.19 Displacement, Δ, is the displacement in tonnes at the Ice Load Waterline, or Deepest Ice Operating Waterline, if applicable, when floating in water having a relative density of 1,0.

# Special Features

# Part 3, Chapter 9

Section 8

8.3.20 Shaft power,  $P_0 (H_0)$  is the maximum propulsion shaft power in kW (horsepower) for which the machinery is classed, see Pt 5, Ch 1,3 and Pt 5, Ch 9,1.3.

8.3.21 Bilge boundary line is that line which in elevation is parallel to the keel and at amidships is coincident with the upper turn of bilge.

## 8.4 Arrangement

8.4.1 The ballast capacity of the ship should be sufficient to give adequate propeller immersion in all ice navigating conditions. It is anticipated that the propeller tips at their highest point will not be closer to the Ice Light Waterline than the distance given in Table 9.8.1.

**Table 9.8.1 Propeller tip minimum distance**

Class	Ice Light Waterline Propeller tip minimum distance, in metres
Ice Class AC1	3,0
Ice Class AC1,5	3,75
Ice Class AC2	4,5
Ice Class AC3	6,0

8.4.2 It is recommended that the minimum draught at the fore-end should be not less than:

$$T_f = (1,5 + 0,1 \sqrt[3]{\Delta}) h \text{ m}$$

where

$h$  = the nominal ice thickness, in metres, associated with the desired Ice Class notation, see 8.1.

$\Delta$  = displacement as defined in 8.3.

8.4.3 All wing ballast tanks adjacent to the shell are to be supplied with heating pipes. All deck machinery such as mooring winches, windlass and essential parts of ice management systems, etc., should be equipped with an efficient de-icing system.

8.4.4 The bow should be such as to break ice effectively. The rake of stem should, in general, be less than 30° relative to the horizontal for Ice Classes AC1,5, AC2 and AC3. Apart from spoon shaped bow forms, the entry angle of the portion of the fore-body below the deepest ice waterline should not exceed 30°. Bulbous bows are not to be fitted to ships having Ice Class AC notations.

8.4.5 Where flare of the side shell amidships is proposed, it is recommended the slope of the side should be at least 8°.

8.4.6 For ships provided with a heel inducing system, it is recommended that the depth of the ship is such that immersion of the deck edge does not occur when the ship, whilst floating at the Ice Load Waterline or Deepest Ice Operating Waterline as applicable, is heeled to an angle of 5° greater than the nominal capacity of the system or 15° whichever is the greater.

8.4.7 It is recommended that the upper deck bulwark is sloped inboard and efficiently supported by transverse stays spaced at no more than 1,5 m, see also Ch 8,5.

8.4.8 The aft body of icebreaking ships should have a form such that broken ice is effectively displaced.

8.4.9 Where it is desired to make provision for close tow-push operations, the bow area should be suitably reinforced. Similarly, it is recommended that suitable reinforcements are arranged in way of the stern fork.

## 8.5 Longitudinal strength

8.5.1 The section modulus at deck and keel of vessels having Ice Class AC notations is to be increased above that required in Pt 3, Ch 4,5 to take account of beaching and dynamic impact loads during ice-breaking operations. Relevant calculations are to be submitted. For initial structural design guidance, the minimum required section modulus of ice-breaking ships would normally be expected to be greater than:

$$Z_{act} = K Z_{min}$$

where  $K$  is a modulus amplification factor depending on  $L$  as follows:

$L$ (m)	$K$
50	1,80
75	1,58
100	1,45
150	1,30
200 and over	1,20

The midship scantlings of the main longitudinal members are to be maintained between 0,2L aft of amidships and 0,3L forward of amidships. However, these scantlings are to extend to at least B/3 forward of the position of the maximum bending moment obtained from the simulated beaching calculations carried out in the structural design of these ships. The position of this maximum bending moment is to be indicated on the submitted plan. The corrosion-abrasion increment required for the shell plating given in Table 9.8.5 is not to be included in the calculation of the actual modulus.

8.5.2 The maximum permissible still water bending moment  $|\overline{M}_s|$  which can be assigned to ships having Ice Class AC notations is as follows:

- (a) Non-Ice-transiting voyages:  
 $|\overline{M}_s|$  is to be calculated from Ch 4,5.4.
- (b) Ice-transiting or partially Ice-transiting voyages:  
 $|\overline{M}_s|$  is to be taken as 95 per cent of the value calculated from Ch 4,5.4, taking  $F_B = 1,0$  and  $F_D$  as calculated from Ch 4,5.6.

## 8.6 Bulkheads

8.6.1 Bulkheads are to be arranged in accordance with the requirements given in Table 9.8.2, see also Ch 3,4.

8.6.2 It is recommended that vertically stiffened transverse bulkheads are fitted with additional horizontal stiffening to resist buckling.

# Special Features

# Part 3, Chapter 9

Section 8

**Table 9.8.2 Bulkhead arrangements**

Class	Longitudinal bulkheads minimum requirements	Transverse bulkheads <sup>(1) (2)</sup> maximum spacing
Ice Class AC1	1 – fwd. 0,4L <sup>(1) (4)</sup>	Lesser of 0,14L or 40 m
Ice Class AC1,5	Double skin for full length of ship <sup>(3)</sup>	
Ice Class AC2	Double skin for full length of ship <sup>(3)</sup> plus 1 – fwd. 0,4L <sup>(1)</sup>	
Ice Class AC3	Double skin for full length of ship <sup>(3)</sup> plus 3 – fwd. 0,4L <sup>(1)</sup> 1 – aft 0,6L <sup>(1)</sup>	
NOTES		
1. May be watertight or non-watertight.		
2. In the case of ships intended to navigate in Canadian Arctic waters attention is drawn to the requirements of the Arctic Shipping Pollution Prevention Regulation C353 in respect to sub-division standards.		
3. The minimum width of the side tanks formed by the double skin should not be less than 1,2 m and the vertical extent of these tanks should be at least up to the bulkhead deck.		
4. It is recommended that double skin is also adopted for this Class.		

## 8.7 Bottom structure

8.7.1 The maximum spacing of floors should not exceed 2(550 + 1,667L) or 1700 mm whichever is the lesser. The maximum spacing of side girders in the double bottom should not exceed 1,6 m. Special consideration will be given to ships having deep draughts.

8.7.2 Ships designed to operate in ice conditions at shallow draught, i.e. at a draught less than indicated by 8.4.2, will require additional strengthening of bottom shell structure forward. Spacing of floors forward for such ships should not exceed 1,0 m. Bottom shell and bottom shell longitudinals will be specially considered. The spacing of side girders forward should not exceed 1,4 m.

## 8.8 Powering of ships intended to operate in multi-year ice conditions

8.8.1 The total shaft power installed in icebreaking ships intended to operate in Canadian Arctic regions should be not less than that required by the Canadian Arctic Shipping Pollution Prevention Regulations. For other regions, the minimum power is to be not less than that obtained by 8.8.3 taking the ship's speed as 1 knot.

8.8.2 Ships intended to operate in multi-year ice conditions should, in general, be able to develop sufficient thrust to permit continuous mode ice-breaking at a speed of five knots assuming the ice thickness related to the required Ice Class AC notation as given in 8.1. Snow cover should be assumed to be at least 0,3 m.

8.8.3 The requirements of 8.8 to 8.18 are formulated on the basis that the power necessary to provide the independent icebreaking capability described in 8.7.2 can be determined by the equation:

$$P_1(H_1) = C_0 C_1 C_2 C_3 (240B h (1 + h + 0,035v^2) + 70S_c \sqrt{L}) \text{ kW (shp)}$$

where

$h$  = ice thickness for desired Ice Class AC notation, see 8.1

$v$  = ship speed (knots) when breaking ice of thickness  $h$

$C_0$  = 0,736 (1,0)

$$C_1 = \frac{1,2B}{\sqrt[3]{\Delta}}$$

but to be taken as not less than 1,0

$C_2$  = 0,9 if ship fitted with controllable pitch propeller, otherwise 1,0

$C_3$  = 0,9 if the rake of stem is 45° or less, otherwise 1,0. The product  $C_2 C_3$  is not to be taken as less than 0,85

$S_c$  = depth of snow cover, in metres

$\Delta$  = displacement as defined in 8.3.19.

8.8.4 The ice strengthening requirements set out in 8.9 to 8.15 include a power-displacement correction factor which is to be determined as follows:

(a) Bow section

$$\gamma = (0,88 + 0,0103f - 2,232f^2 \times 10^{-4}) (1 + A (F - 1))$$

(b) Stern and mid-body sections

$$\gamma = 0,7 + 0,00924f - 2,134f^2 \times 10^{-4}$$

where

$$f = \sqrt{P_0 \Delta} \times 10^{-3} (= 0,858 \sqrt{H_0 \Delta} \times 10^{-3})$$

but is not to be taken greater than 22

$A$  = 0,1 for shell plating

= 0 for frames, stringers and web-frames

$F$  = ratio of installed power  $P_0$  ( $H_0$ ) to the power  $P_1(H_1)$  calculated in accordance with 8.8.2 and 8.8.3 but is not to be taken as less than 1,0

and  $P_0$ ,  $H_0$ ,  $\Delta$  are defined in 8.3.19 and 8.3.20.

## 8.9 Shell plating

8.9.1 In way of the Ice Belt, the thickness of the shell plating is not to be less than:

$$t = 0,5s \alpha_p \beta \gamma \sqrt{\frac{\rho}{\sigma_o}} + c \text{ mm}$$

in association with transverse or longitudinal framing,

where

$c$  = corrosion-abrasion increment as given in Table 9.8.5

$\rho$  = design ice pressure for each Ice Class as given in Table 9.8.4

$s$  = frame spacing between adjacent frames, in mm

$\alpha_p$  = longitudinal distribution factor dependent upon Ice Class AC notation and longitudinal position as given in Table 9.8.3

$\beta$  = vertical distribution factor dependent on vertical position as given in Table 9.8.6

$\gamma$  = power-displacement factor as defined in 8.8.4

$\sigma_o$  = specified minimum yield stress of steel in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>). For mild steel, the value of 235 N/mm<sup>2</sup> (24 kgf/mm<sup>2</sup>) is to be used.



# Special Features

# Part 3, Chapter 9

Section 8

**Table 9.8.3 Longitudinal distribution factor  $\alpha_p$** 

Class	$\alpha_p$		
	Bow	Mid-body	Stern
Ice Class AC1	1,0	0,8	0,9
Ice Class AC1,5	1,31	1,05	1,16
Ice Class AC2	1,6	1,28	1,45
Ice Class AC3	2,1	1,7	1,9

**Table 9.8.4 Design ice pressure  $p$** 

Class	Design ice pressure, $p$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Ice Class AC1	5,89 (0,60)
Ice Class AC1,5	5,40 (0,55)
Ice Class AC2	4,91 (0,50)
Ice Class AC3	3,92 (0,40)

**Table 9.8.5 Corrosion-abrasion increment  $c$** 

Class	Corrosion-abrasion increment, $c$ (mm)
Ice Class AC1	5
Ice Class AC1,5	6
Ice Class AC2	7
Ice Class AC3	9

**Table 9.8.6 Vertical distribution factor  $\beta$** 

Vertical position	$\beta$
Main ice belt zone	1,0
Upper transition area:	
Above main bow area	0,8
Above main mid-body area	0,5
Above main stern area	0,5
Lower transition area	0,5
Lower bow area	0,5

## 8.10 Transverse framing

8.10.1 The section modulus of main and intermediate transverse frames in way of the ice belt (including a width of attached plating equal to  $s$ ) is to be not less than that determined in accordance with the following:

$$Z = 40 \alpha_t \beta \gamma \frac{p s h_o}{l \sigma_o} (3l^2 - h_o^2) \text{ cm}^3$$

where

$h$  = as defined in 8.7.3

$h_o$  = ice bearing height, dependent upon the span  $l$ , as given in Table 9.8.7 but is to be taken as not greater than the design ice thickness  $h$  or the span  $l$ , whichever is the least

$l$  = span, in metres, measured along a chord at the side between the span points. For definition of span points, see Ch 3.3.3. Where adjacent main and intermediate frames have different end connections, resulting in different spans, a mean value is to be used

$p$  = the ice pressure dependent upon ice bearing height,  $h_o$ , as given in Table 9.8.10

$s, \sigma_o$  = as defined in 8.9.1

$\alpha_t$  = longitudinal distribution factor dependent on ice bearing height,  $h_o$ , and longitudinal position as given in Table 9.8.8

$\beta$  = vertical distribution factor on vertical position and given in Table 9.8.9

$\gamma$  = as defined in 8.8.4.

**Table 9.8.7 Ice bearing height  $h_o$** 

Span $l$ m	Ice bearing height, $h_o$ m
Less than 1,5	1,0
$1,5 \leq l < 2,2$	1,5
$2,2 \leq l < 4$	2
4 or greater	3
NOTE $h_o$ is not to be taken greater than the value of ice thickness, $h$ , implied by the Ice Class AC notation.	

**Table 9.8.8 Longitudinal distribution factor  $\alpha_t$** 

Ice bearing height, $h_o$ m	$\alpha_t$		
	Bow	Mid-body	Stern
1 or less	1,0	0,8	0,9
1,5	0,95	0,76	0,86
2	0,91	0,73	0,82
3 or greater	0,86	0,69	0,78

**Table 9.8.9 Vertical distribution factor  $\beta$** 

Vertical position	$\beta$
Main ice belt zone	1,0
Upper transition area	0,5
Lower transition area	0,7
Lower bow area	0,5

**Table 9.8.10 Ice bearing height  $h_o$** 

Ice bearing height, $h_o$ m	$p$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
1,0 or less	5,89 (0,6)
1,5	5,40 (0,55)
2,0	4,91 (0,50)
3 or greater	3,92 (0,40)

## Special Features

## Part 3, Chapter 9

Section 8

8.10.2 The cross-sectional shear area of transverse main and intermediate frames is to be not less than determined in accordance with the following formula:

$$A = 13\alpha_l \beta \gamma h_o \frac{\rho s}{\sigma_o} \text{ cm}^2$$

where

$h_o$  = ice bearing height to be taken as equal to the span,  $l$ , but is not to be taken as greater than the design ice thickness for the desired Ice Class as given in 8.1

$\rho$  = design ice pressure dependent upon ice bearing height,  $h_o$ , as given in Table 9.8.10. Linear interpolation is to be used for intermediate values of  $h_o$

$\alpha_l$  = longitudinal distribution factor dependent on ice bearing height,  $h_o$ , and longitudinal position as given in Table 9.8.8. Linear interpolation is to be used for intermediate values of  $h_o$ ,  $l$ ,  $\beta$  as defined in 8.10.1  
 $s$ ,  $\sigma_o$  as defined in 8.9.1  
 $\gamma$  as defined in 8.8.4.

8.10.3 The main and intermediate frames of the main ice belt zone, having scantlings as required by 8.10.1 and 8.10.2, should be extended to the first primary longitudinal member above or below this zone. The end connections of these frames to the primary longitudinal members are to be bracketed. Where the side frames are flat bar sections, they may be extended through the primary longitudinal member, suitably tapered and butt welded to the flat bar side frames required for the upper and lower transition areas.

8.10.4 The main and intermediate frames of the upper transition and lower transition areas, having scantlings as required by 8.10.1 and 8.10.2, should be extended, in the case of the upper transition area, to the first primary member above this area and for the lower transition area continued to the double bottom and/or margin plate as applicable. These frames should be effectively bracketed to the primary longitudinal member.

8.10.5 In the context of 8.10.3 and 8.10.4, a primary longitudinal member is defined as either a deck, deep tank top, or ice stringer complying with 8.13.

8.10.6 The intermediate frames need not extend beyond the limits defined in 8.10.4 provided that, in the case where the primary longitudinal member is an ice stringer, a suitable extension bracket is fitted.

### 8.11 Longitudinal framing

8.11.1 The section modulus of longitudinal frames (including a width of attached plating  $s$ ) is to be not less than that determined in accordance with the following:

$$Z = 56\alpha_l \beta \gamma s l^2 \frac{\rho}{\sigma_o} \text{ cm}^3$$

$l$  = span of longitudinal, in metres, determined in accordance with Ch 3,3.3

$\rho$  = 5,89 (0,60)

$s$  = longitudinal frame spacing, in mm

$\alpha_l$  = longitudinal distribution factor as given in Table 9.8.11

**Table 9.8.11 Longitudinal distribution factor  $\alpha_l$**

Class	$\alpha_l$		
	Bow	Mid-body	Stern
All ice classes	1,0	0,8	0,9

**Table 9.8.12 Vertical distribution factor  $\beta$**

Vertical position	$\beta$
Main ice belt zone	1,0
Upper transition area:	
Above main bow area	1,0
Above main mid-body area	0,7
Above main stern area	1,0
Lower transition area	0,7
Lower bow area	0,8

$\beta$  = vertical distribution factor as given in Table 9.8.12  
 $\gamma$ ,  $\sigma_o$  = is as defined in 8.8.4 and 8.9.1.

8.11.2 The cross-section shear resisting area of longitudinal frames is to be not less than that determined in accordance with the following:

$$A = 13\alpha_l \beta \gamma s l \frac{\rho}{\sigma_o} \text{ cm}^2$$

where

$\alpha_l$ ,  $\beta$ ,  $l$ ,  $\rho$ ,  $s$  are defined in 8.11.1

$\sigma_o$  is defined in 8.9.1

$\gamma$  is defined in 8.8.4.

### 8.12 Framing – General requirements

8.12.1 In general, the web thickness of frames within the ice belt is to be not less than half that of the attached shell plating and the depth to thickness ratio for flat bar frames and longitudinals not greater than 15.

8.12.2 Where a frame intersects a boundary between two hull sections, the scantling requirements applicable will be those for the bow section, if the boundary between the bow and mid-body sections is intersected, or those for the stern section, if the boundary between the stern and mid-body sections is intersected.

8.12.3 Main and intermediate frames within the ice belt are to be efficiently supported to prevent tripping as shown in Fig. 9.7.6. The distance between anti-tripping supports is not to exceed 1,0 m.

8.12.4 Frames within the ice belt are to be attached to the shell plating by double continuous welding and are not to be scalloped except in way of shell butts.

8.12.5 The effective weld area attaching frames to primary members is to be not less than the shear area for the frames as required by 8.10.2 or 8.11.2 as appropriate.

## Special Features

## Part 3, Chapter 9

Section 8

8.12.6 For bulkheads or decks within the ice belt, the thickness of the plating adjacent to the shell is to be not less than that of the web of the adjacent frame. This increased thickness should extend for a width sufficient to give an area equal to that required for such frames.

### 8.13 Primary longitudinal members supporting transverse ice framing

8.13.1 The section modulus of ice stringers or of decks adjacent to hatchways, including a width of attached plating determined in accordance with Ch 3,3.2, and taken about an axis perpendicular to the web, is to be not less than that given by:

$$Z = 16\,700 \alpha_o \beta \gamma^2 S l^2 \frac{p}{\sigma_o} \text{ cm}^3$$

where

$l$  = span of member, in metres, measured between span points but is to be taken as not less than 1,6 m

$p$  = design ice pressure for desired Ice class as given in Table 9.8.4

$S$  = spacing of primary longitudinal members, in metres, but need not be taken as greater than  $h$ , the nominal ice thickness for desired Ice Class as given in 8.1

$\alpha_o$  = longitudinal distribution factor as given in Table 9.8.13

$\beta$  = vertical distribution factor as given in Table 9.8.14. and  $\gamma$ ,  $\sigma_o$  as given in 8.8.4 and 8.9.1.

**Table 9.8.13 Longitudinal distribution factor  $\alpha_o$**

Class	$\alpha_o$		
	Bow	Mid-body	Stern
Ice Class AC1	1	0,9	0,95
Ice Class AC1,5	1,13	1,02	1,07
Ice Class AC2	1,8	1,6	1,7
Ice Class AC3	2,5	2,25	2,4

**Table 9.8.14 Vertical distribution factor  $\beta$**

Vertical position	$\beta$
Main ice belt zone	1,0
Upper transition area:	
In way of bow section	0,9
In way of mid-body section	0,7
In way of stern section	0,8
Lower transition area	0,7
Lower bow area	0,9

8.13.2 The cross-sectional shear resisting area of ice stringers or of decks adjacent to hatchways is to be not less than that determined in accordance with the following:

$$A = 3000 \alpha_o \beta \gamma^2 S l^2 \frac{p}{\sigma_o} \text{ cm}^3$$

where

$\alpha_o$ ,  $\beta$ ,  $l$ ,  $p$  and  $S$  are defined in 8.13.1

$\gamma$ ,  $\sigma_o$  are defined in 8.8.4 and 8.9.1.

8.13.3 Primary longitudinal members supporting transverse frames should normally be arranged so that the maximum deviation of their webs from the perpendicular to the shell plating does not exceed  $\pm 20$  degrees. Arrangements based on horizontal side stringers will be acceptable only if the section modulus is related to the axis parallel to the shell plating and brackets extending the full depth of the web are arranged at every transverse frame.

8.13.4 In all cases, the transverse frames are to be attached to the ice stringers by flat bars extending the full depth of the web of the primary longitudinal member. These flat bars should be fitted to both sides of the primary longitudinal member in vessels having designations Ice Class AC2 and AC3.

8.13.5 The minimum thickness of the web plating of longitudinal primary members is to comply with the requirements of Ch 10,4.

### 8.14 Web frames

8.14.1 The section modulus of web frames supporting ice stringers or longitudinal ice frames, including a width of attached plating determined in accordance with Ch 3,3.2 and taken about an axis perpendicular to the web, is to be not less than that given by:

$$Z = 8300 \alpha_o \beta \gamma^2 \frac{Sp}{l \sigma_o} h_o (3l^2 - h_o^2) \text{ cm}^3$$

where

$h$  = nominal ice thickness for desired Ice Class as given in 8.1

$h_o$  = ice bearing height, in metres, to be taken as equal to the ice thickness  $h$  but is not to exceed the span  $l$

$l$  = web frame span, in metres, measured along a chord at side between span points but is to be taken as not less than 2 m. For definition of span points, see Ch 3,3.3

$p$  = design ice pressure as given in Table 9.8.10

$S$  = web frame spacing, in metres

$\alpha_o$  = longitudinal distribution factor as given by Table 9.8.13

$\beta$  = vertical distribution factor as given by Table 9.8.14

$\gamma$ ,  $\sigma_o$  are defined in 8.8.4 and 8.9.1.

# Special Features

# Part 3, Chapter 9

Section 8

8.14.2 The cross-sectional shear resisting area of web frames supporting ice stringers or longitudinal ice frames is to be not less than that determined in accordance with the following:

$$A = 3000 \alpha_o \beta \gamma^2 S h_o \frac{\rho}{\sigma_o} \text{ cm}^2$$

where

$\alpha_o$ ,  $\beta$ ,  $S$ ,  $\rho$  and  $h_o$  are defined in 8.14.1

$\gamma$ ,  $\sigma_o$  are defined in 8.8.4 and 8.9.1.

8.14.3 The thickness of the web plating of web frames below the upper deck level is to be not less than one per cent of the web depth or the thickness given in Table 9.8.15 whichever is the greater, see also 8.14.6.

**Table 9.8.15 Web frame thickness**

Class	Minimum web thickness of web frames mm
Ice Class AC1	12
Ice Class AC1,5	15
Ice Class AC2	18
Ice Class AC3	20

8.14.4 The minimum thickness of the face flat attached to the web frame is to be not less than 10 mm greater than the minimum web thickness as given by 8.14.3 and the minimum width of the face plate should be not less than 15 per cent of the web depth.

8.14.5 The spacing of tripping brackets supporting web frames should not exceed 2 m in the main ice-belt zone and 2,5 m elsewhere.

8.14.6 Where longitudinal frames pass through web frames, watertight or non-watertight bulkheads, the thickness of these members, adjacent to the shell plating, is to be not less than 60 per cent of the thickness of the longitudinals.

8.14.7 The longitudinal frames should be connected to the web frames by a flat bar extending the full depth of the web frame. In the case of Ice Class AC1,5, Ice Class AC2 and Ice Class AC3, this connection should be effected by double brackets.

## 8.15 Stem

8.15.1 The stem is to be made from rolled, cast or forged steel or of shaped steel plates.

8.15.2 The plate thickness of a plate stem is to be not less than:

$$t = 0,5s \alpha_p \beta \gamma \sqrt{\frac{\rho}{\sigma_o}} + c \text{ mm}$$

where

$\alpha_p$ ,  $\beta$ ,  $\gamma$ ,  $\sigma_o$ ,  $\rho$ ,  $c$  are defined in 8.9.1

and

$s$  = distance, in mm, between horizontal webs and diaphragm plates having a thickness of at least  $0,5t$ .

8.15.3 The thickness of the stem plate is to be not less than 1,1 times the thickness of the adjacent plating in the bow section as determined by 8.9.1.

8.15.4 Where a forged or cast steel stem profile is incorporated, the extent of the ice reinforced profile is to extend to at least the upper edge of the upper transition zone. The connection of the shell plating to the stem is to be flush. Similar requirements apply to welded stem constructions.

8.15.5 The stem should extend to the forefoot ice arrester structure. Ice arresters are recommended for all ships having Arctic Ice Class AC notations to prevent riding up of the bow and submergence of the aftermost deck edge.

## 8.16 Stern

8.16.1 Where the screwshaft diameter exceeds the Rule diameter, the propeller post is to be correspondingly strengthened, see Ch 6,7.

8.16.2 A transom stern should not normally extend below the Ice Load Waterline. Where this cannot be avoided, the transom should be kept as narrow as possible and the scantlings of plating and stiffeners are to be as required for the stern section.

8.16.3 Where special provision is made in the stern area of the vessel for close tow-push operations, the fork structure should be of sufficient strength to transmit the applied forces.

## 8.17 Bossings and shaft struts

8.17.1 Shaftings and stern tubes of ships with two or more propellers are to be enclosed within plated bossings.

## 8.18 Rudder, steering arrangements and nozzles

8.18.1 In general, spade rudders are not to be fitted on ships employed in Arctic or Antarctic operations.

8.18.2 Rudder posts, rudder horns, solepieces, rudder stocks and pintles are to be dimensioned in accordance with Chapter 6 or Chapter 13 as appropriate. The speed used in the calculations is to be the maximum service speed or that given in Table 9.8.16, whichever is the greater. However, the section modulus of the solepiece calculated in accordance with the above need not be greater than three times the section modulus of solepiece calculated in accordance with Ch 6,7 using the maximum service speed.

8.18.3 For double plate rudders, the minimum thickness of plates and horizontal and vertical webs in the main ice-belt zones is to be determined as for the shell plating in the stern area, as required by 8.9.1. Horizontal and vertical webs, however, need not include the corrosion abrasion increment of Table 9.8.5.

## Special Features

## Part 3, Chapter 9

Section 8

**Table 9.8.16 Minimum speed**

Class	Minimum speed knots
Ice Class AC1	22
Ice Class AC1,5	23
Ice Class AC2	24
Ice Class AC3	26

8.18.4 The rudder head and upper edge of the rudder are to be efficiently protected against ice impact, when the ship is backing into ice, by a robust ice knife. The thickness of the boundaries of this ice knife structure is to be not less than that of the rudder side plating. The width of the ice knife should exceed the maximum width of the rudder by five per cent.

8.18.5 Fixed nozzles are to be effectively integrated into the aft end structure. Where a twin screw nozzle arrangement is fitted, a heavy skeg is to be arranged in front of each nozzle. For such an arrangement it is considered advisable to keep the distance between the nozzles to a minimum in order to restrict ice flow between the nozzles. The head box structure should contain a dense grillage of longitudinal and transverse plate girders. Particular attention is to be paid to all structural details and especially the connections between the nozzle and the solepiece. Freely suspended nozzles are not considered suitable for icebreaking duties.

8.18.6 The nozzle construction requirements of Table 13.3.1 in Ch 13,3 should be upgraded for ships having Ice Class AC notations to include the abrasion allowance given in Table 9.8.17. However, the thickness of the shroud plating is to be not less than the shell plating in the stern area as determined by 8.9.1 taking the frame spacing,  $s$ , as 350 mm, but need not exceed 45 mm.

**Table 9.8.17 Abrasion allowance**

Class	Abrasion increment
Ice Class AC1	8
Ice Class AC1,5	10
Ice Class AC2	12
Ice Class AC3	15

8.18.7 The scantling, of nozzle stock, gudgeon, pintles, solepiece, etc., determined in accordance with Ch 13,3, should be increased on the basis of 8.17.2. However the diameter of the nozzle stock is to be not less than that calculated in the astern condition taking the astern speed as half the speed given in Table 9.8.16 or the actual stern speed, whichever is the greater. The allowable stresses to be used in the calculation of nozzle stock diameter are to be taken as:

combined stress at lower bearings  $\leq 85 \text{ N/mm}^2$   
(8,7 kgf/mm<sup>2</sup>)

torsional stress in upper stock  $\leq 55 \text{ N/mm}^2$   
(5,6 kgf/mm<sup>2</sup>)

8.18.8 The section modulus of the solepiece obtained from 8.18.7 is to be not less than that determined in accordance with the following:

$$Z = C Z_s \text{ cm}^3$$

where

$Z_s$  = modulus of the solepiece calculated using the Rule stress given in Ch 13,3

$C$  = see Table 9.8.18

For the ahead condition, the maximum service speed is to be used and for the astern condition, the greater of half the maximum service speed or the astern speed.

**Table 9.8.18 Values of C**

Class	C
Ice Class AC1	1,5
Ice Class AC1,5	2
Ice Class AC2	2,5
Ice Class AC3	3,0

8.18.9 Nozzles with articulated flaps will be subject to special consideration.

8.18.10 Where the nozzle numeral as per Table 13.3.1, in Chapter 13, exceeds 400 an analysis of the nozzle structure should be carried out including appropriate simulation of ice impact loading.

8.18.11 It is advisable to verify that the natural frequency of the nozzle arrangement immersed in water is well removed from the excitation frequencies.

8.18.12 Due regard is to be paid to the method of securing the rudder in the centreline position when backing into ice. Where possible, rudder stoppers working on the blade or rudder head should be fitted.

8.18.13 Ships having Ice Class AC notations are, in addition to the main steering gear, to be fitted with auxiliary steering gear capable of being readily connected to the tiller, *see also* Pt 5, Ch 19. In the case of twin rudders operated by a single steering gear, there is to be provision for each rudder to be readily disconnected and secured.

8.18.14 The main steering gear of ships having Ice Class AC notations shall be fitted with a shock absorbing device and be capable of moving the rudder from 35° on one side to 30° on the other side in  $\sqrt{6,56L}$  seconds or 28 seconds, whichever, is the lesser when the ship is fully loaded and travelling at her maximum service speed.

## 8.19 Direct calculations

8.19.1 If, as an alternative to the requirements of 8.12 and 8.13, the scantlings of primary longitudinal members and web frames are determined by direct calculation as permitted by Ch 1,2.1, the following procedure is to be adopted:

- The extent of the structural model should be at least equal to the largest cargo hold length between two transverse bulkheads. The upper boundary should be the upper deck and the lower boundary the inner bottom.
- The structural members represented should include stringers, web frames, side frames and all relevant decks.
- The rate of applied ice loading  $q$ , for the mid-body section, should be taken as:  
 $q = p h 10^3 \text{ kN/m (tonne-f/m)}$   
 where  $p$  is given in Table 9.8.4  
 $h$  is defined in 8.4
- The scantlings should be suitable for the centre of load depth to be located at any height between the Ice Load Waterline and Ice Light Waterline.
- The maximum von Mises-Hencky combined stress is not to exceed 80 per cent of the yield stress of the steel.

## Section 9 Strengthening requirements for navigation in very light first-year ice conditions

### 9.1 General

9.1.1 These requirements apply to offshore supply ships, as defined in Pt 4, Ch 4, and which are intended to operate in very light first-year ice conditions. Where additional strengthening is fitted in accordance with the requirements of this sub-Section, the notation Ice Class **1E** will be assigned.

9.1.2 For longitudinally framed ships, the scantlings of shell plating and framing are to comply with the requirements of Ice Class **1C FS** using 0,9 times the ice pressure. The requirements for shell plating need only be applied in the region shown in Fig. 9.1.1. The requirements for framing need only be applied forward of the flat of side.

9.1.3 For transversely framed ships, the requirements of 9.3 to 9.8 are to be applied.

9.1.4 Where the structural requirements of Ice Class **1C FS** give lesser scantlings than the requirements of this sub-Section, the lesser scantlings may be applied.

### 9.2 Shell plating

9.2.1 The shell plating thickness within the region shown in Fig. 9.1.1 is not to be less than:

$$t = 21,75s \sqrt{k \left( \frac{BL^2}{110000} + 1 \right) \left( 1,3 - \frac{4,2}{(0,26/s + 1,8)^2} \right)} + 2 \text{ mm}$$

where

$s$  = spacing of main frames, in metres  
 $L$  and  $B$  are defined in Ch 1,6.1  
 $k$  is defined in Ch 2,1.2.

### 9.3 Transverse framing

9.3.1 The section modulus of main frames forward of the flat of side is not to be less than:

$$z = 6,08s l k \left( \frac{BL^2}{140000} + 1,23 \right) \left( 7 - \frac{1}{21} \right) \text{ cm}^3$$

but need not be taken as greater than:

$$z = sLT$$

where

$s$  = spacing of main frames, in metres  
 $l$  = span, in metres




Fig. 9.1.1 Extent of application of plating requirements

# Special Features

# Part 3, Chapter 9

Sections 9 & 10

$L$  and  $B$  are defined in Ch 1,6.1  
 $k$  is defined in Ch 2,1.2.

9.3.2 Intermediate ice frames are to be fitted in the region forward of the flat of side and are to extend from 0,62 m above the Ice Load Waterline to 1 m below the Ice Light Waterline.

9.3.3 Intermediate ice frames aft of the collision bulkhead are to have a section modulus not less than 65 per cent of that given in 9.3.1.

9.3.4 Intermediate ice frames forward of the collision bulkhead are to have a section modulus not less than 40 per cent of that given in 9.3.1.

## 9.4 Primary longitudinal members supporting ice frames

9.4.1 Forward of the collision bulkhead, in single deck ships, an ice stringer is to be fitted approximately 0,25 m below the Ice Load Waterline and is to have scantlings in accordance with Table 5.4.4 in Chapter 5.

9.4.2 Aft of the collision bulkhead a series of tripping brackets are to be fitted at each main and intermediate frame at the same level as the ice stringer to a distance 0,1 $L$  aft of the flat of side.

## 9.5 Sternframe and rudder

9.6.1 The rudder and sternframe scantlings are to be in accordance with 7.7. However, the ship's speed need not be taken as greater than 14 knots. The hull form factor and the rudder profile coefficients are to be taken as 1,0.

## 9.6 Weld connections

9.6.1 Weld connections to the shell plating forward of the collision bulkhead are to be double continuous.

10.1.3 Elsewhere, classification of lifting appliances is optional and may be assigned at the request of the Owner on compliance with the appropriate requirements.

10.1.4 Certain movable support structures and lifting appliances on special purpose vessels which are considered an essential feature of the vessel are to be included in the classification of the vessel.

10.1.5 Proposals to class lifting appliances on unclassified ships will be specially considered.

## 10.2 Masts, derrick posts and crane pedestals

10.2.1 The scantlings of masts and derrick posts, intended to support derrick booms, conveyor arms and similar loads, and of crane pedestals, are to comply with the requirements of LR's Code for *Lifting Appliances in a Marine Environment* (hereinafter referred to as LAME).

10.2.2 In addition to the information and plans requested in LR's LAME the following details are to be submitted:

- Details of masthouses or other supports for the masts, derrick posts or crane pedestals, together with details of the attachments to the hull structure.
- Details of any reinforcement or additional supporting material fitted to the hull structure in way of the mast, derrick post or crane pedestal.

## 10.3 Support structure for masts, derrick posts and crane pedestals

10.3.1 The requirements of 10.2.3 and 10.2.4 are not applicable to Double Hull Oil Tankers or Bulk Carriers with a CSR notation (see Pt 1, Ch 2,2.3)

10.3.2 Masts, derrick posts and crane pedestals are to be efficiently supported and, in general, are to be carried through the deck and satisfactorily scarfed into a transverse hold or 'tween deck bulkhead. Alternatively, the masts, derrick posts or crane pedestals may be carried into a mast house, in which case the mast house is to be of substantial construction. Proposals for other support arrangements will be specially considered.

10.3.3 Deck plating and underdeck structure are to be reinforced under masts, derrick posts or crane pedestals and, where the deck is penetrated, the deck plating is to be suitably increased locally.

## 10.4 Lifting appliances

10.4.1 Ships or offshore units fitted with lifting appliances built in accordance with LR's LAME in respect of structural and machinery requirements will be eligible to be assigned Special Features class notations as listed in Table 9.10.1. This notation will be retained so long as the appliances are found upon examination at the prescribed surveys to be maintained in accordance with LR's requirements.

## Section 10 Lifting appliances and support arrangements

### 10.1 General

10.1.1 Masts, derrick posts, crane pedestals and similar supporting structures are classification items, and the scantlings and arrangements are to comply with LR's requirements whether or not LR is also requested to issue the Register of Ships' Cargo Gear and Lifting Appliances.

10.1.2 Where the lifting appliance is considered to be an essential feature of a classed ship, the special feature class notation **LA** will, in general, be mandatory.

# Special Features

## Part 3, Chapter 9

Sections 10, 11 &amp; 12

**Table 9.10.1 Special features class notations associated with lifting appliances**

Lifting appliance	Special features class notation	Remarks
Derricks, derrick cranes or cranes on ships	CG	Optional notation. Indicates that the ship's cargo gear is included in class.
Cranes on offshore installations	PC	Optional notation. Indicates that the installation's platform cranes are included in class.
Lifts and ramps on ships	CL PL CR	Optional notations. Indicate that the ship's cargo lifts (CL), passenger lifts (PL) or cargo ramps (CR) are included in class.
Lifting appliances forming an essential feature of the vessel, e.g. cranes on crane barges or pontoons, lifting arrangements for diving on diving support ships, etc.	LA	Mandatory notation. Indicates that the lifting appliance is included in class.

### ■ Section 11 Freight container securing arrangements

#### 11.1 Classification

11.1.1 Where freight container securing arrangements are fitted and the design and construction of the system are in accordance with the requirements of Chapter 14, the ship will be eligible to be assigned the special features notation **Certified Container Securing Arrangements**.

### ■ Section 12 Bottom strengthening for loading and unloading aground

#### 12.1 Application

12.1.1 Where a ship of length,  $L$ , less than 90 m has the bottom structure additionally strengthened for loading and unloading aground in accordance with Table 9.12.1, it will be eligible for the special features notation 'bottom strengthened for loading and unloading aground'. Ships of length,  $L$ , 90 m or more intended for this service will receive individual consideration.

12.1.2 For dredgers intended to operate aground, the requirements of Pt 4, Ch 12 are to be applied.



# Special Features

## Part 3, Chapter 9

Sections 12 &amp; 13

**Table 9.12.1 Bottom strengthening for loading and unloading aground**

Item	Requirement	
The following requirements are to be applied to the bottom structure upon which the ship is likely to be supported whilst aground		
(1) Bottom shell and keel plating	Thickness to be increased by 20% over the minimum requirements given in Part 4 for the particular type of ship with a minimum of 8 mm	
(2) Bottom longitudinals in way of single bottoms	For dry cargo ships, as required in way of double bottoms, see item (3)  For oil tankers, scantlings as required by Table 9.5.1 in Pt 4, Ch 9 in taking $c_1 = 1,0$	
(3) Bottom longitudinals in way of double bottoms, see Note 1	For dry cargo ships, scantlings as required by Table 1.6.1 in Pt 4, Ch 1 in taking $c_1 = 1,0$	
(4) Bilge longitudinals (where fitted)	Scantlings to be the same as bottom longitudinals	
(5) Primary stiffening in way of single bottoms, see Notes 2 and 3	Transverse framing	Longitudinal framing
	(a) Floors to be fitted at every frame with vertical stiffeners spaced, in general, not more than 1,25 m apart  (b) One side girder is to be fitted on each side of the centreline in addition to the requirements of Pt 4, Ch 1,7 and intermediate 150 x 10 bulb plate longitudinals or equivalent fitted	(a) The arrangements and scantlings will receive individual consideration depending on the structural arrangements of the particular ship type  (b) The spacing of transverse or floors is, in general, not to exceed 1,85 m
(6) Primary stiffening in way of double bottoms, see Notes 1, 2 and 3	(a) Plate floors are to be fitted at every frame and vertical stiffening arranged to give panel widths, in general, not exceeding 1,25 m  (b) One side girder is to be fitted on each side of the centreline in addition to the requirements of Pt 4, Ch 1,8 and intermediate 150 x 10 bulb plate longitudinals or equivalent fitted	(a) The spacing of floors is, in general, not to exceed 1,85 m  (b) One side girder is to be fitted on each side of the centreline in addition to the requirements of Pt 4, Ch 1,8
NOTES 1. For oil tankers, to be specially considered. 2. The scantlings of floors, girders and transverses are to be determined from Part 4, for the particular ship type. 3. The number and sizes of holes in floors, girders and transverses are to be kept to a minimum; see Pt 4, Ch 1,8 and Pt 4, Ch 9,6.		

### Section 13

#### Strengthening for regular discharge by heavy grabs

##### 13.1 Application

13.1.1 For bulk carriers where cargoes are regularly discharged by heavy grabs and the thickness of the plating of the hold inner bottom, hopper and transverse bulkhead bottom stool is increased in accordance with the requirements of this Section, the ship will, at the Owner's option, be assigned the notation 'strengthened for regular discharge by heavy grabs'.

13.1.2 It should be noted that damage to the plating cannot be excluded even when complying with these requirements and can result from the mishandling of the grabs during the discharge of cargo.

13.1.3 The grab weight given in 13.2.1 does not preclude the use of heavier grabs. It is intended as an indication to the Builders, Owners and operators of the increased risk of local damage and the possibility of accelerated diminution of the plating thickness if grabs heavier than this are used regularly to discharge cargo.

13.1.4 The maximum unladen weight of the grab is to be recorded in the Loading Manual, see also Ch 4,8.2.4(e).

13.1.5 The requirements in this Section are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation. See Pt 1, Ch 2,2.3.

## 13.2 Inner bottom plating

13.2.1 The thickness of the inner bottom plating in the holds is to be not less than required by the greater of the following:

$$(a) \quad t = \frac{\left( \log_{10} \left( 1,775P \left( \frac{k}{s} \right)^2 \right) + 5,7633 \right) s - 344,5}{40,875 \sqrt{k}} + 1,5 \text{ mm}$$

(b)  $t$  = the Rule required thickness, in mm in accordance with Pt 4, Ch 7,8 for the intended class notation.

where

- $P$  = specified unladen grab weight for the hold, in tonnes, and is not to be taken as less than 25 tonnes
- $s$  = spacing of inner bottom longitudinals, in mm
- $k$  = higher tensile steel factor as defined in Ch 2,1.2.

## 13.3 Hopper side tank sloped bulkhead plating

13.3.1 The thickness of the sloped bulkhead plating adjacent to the inner bottom knuckle is to be as required by 13.2.1 but based on the actual spacing of stiffeners. The plating of increased thickness is to extend for a minimum distance corresponding to a vertical height of 1,5 m above the line of the inner bottom. Outboard of the plating of increased thickness, the thickness of the adjacent strakes is to be tapered to the Rule thickness for plating, as required by Pt 4, Ch 1,8.4.1, at the top corner of the tank, *see also* Pt 4, Ch 7,9.2.3 where, in addition, the 'strengthened for heavy cargo' notation is desired.

## 13.4 Transverse bulkhead plating

13.4.1 The thickness of the bulkhead or stool plating adjacent to the inner bottom is to be as required by 13.2.1 but based on the actual spacing of the bulkhead or stool stiffeners. The plating of increased thickness is to extend for a minimum distance corresponding to a vertical height of 1,5 m above the line of the inner bottom.

# Welding and Structural Details

# Part 3, Chapter 10

Sections 1 & 2

## Section

- 1 **General**
- 2 **Welding**
- 3 **Secondary member end connections**
- 4 **Construction details for primary members**
- 5 **Structural details**
- 6 **Access arrangements for oil tankers and bulk carriers**

- (b) Grades and thicknesses of materials to be welded.
- (c) Location, types of joints and angles of abutting members.
- (d) Reference to welding procedures to be used.
- (e) Sequence of welding of assemblies and joining up of assemblies.

## 2.2 Butt welds

2.2.1 Abrupt change of section is to be avoided where plates of different thicknesses are to be butt welded. Where the difference in thickness exceeds 3 mm, the thicker plate to be welded is to be prepared with a taper not exceeding 1 in 3 or with a bevelled edge to form a welded joint proportioned correspondingly. Where the difference in thickness is less than 3 mm the transition may be achieved within the width of the weld. Difference in thickness greater than 3 mm may be accepted provided it can be proven by the Builder, through procedure tests, that the Rule transition shape can be achieved and that the weld profile is such that structural continuity is maintained to the Surveyor's satisfaction.

2.2.2 Where stiffening members are attached by continuous fillet welds and cross completely finished butt or seam welds, these welds are to be made flush in way of the faying surface. Similarly, for butt welds in webs of stiffening members, the butt weld is to be completed and generally made flush with the stiffening member before the fillet weld is made. The ends of the flush portion are to run out smoothly without notches or sudden change of section. Where these conditions cannot be complied with, a scallop is to be arranged in the web of the stiffening member. Scallops are to be of such size, and in such a position, that a satisfactory weld can be made.

## 2.3 Lap connections

2.3.1 Overlaps are generally not to be used to connect plates which may be subjected to high tensile or compressive loading and alternative arrangements are to be considered. Where, however, plate overlaps are adopted, the width of the overlap is not to exceed four times nor be less than three times the thickness of the thinner plate and the joints are to be positioned as to allow adequate access for completion of sound welds. The faying surfaces of lap joints are to be in close contact and both edges of the overlap are to have continuous fillet welds.

## 2.4 Closing plates

2.4.1 For the connection of plating to internal webs, where access for welding is not practicable, the closing plating is to be attached by continuous full penetration welds or by slot fillet welds to face plates fitted to the webs. Slots are to have a minimum length of 90 mm and a minimum width of twice the plating thickness, with well rounded ends. Slots cut in plating are to have smooth, clean and square edges and should be spaced not more than 230 mm apart centre to centre. Slots are not to be filled with welding. For rudder closing plates, see Ch 13,2.5.6.

## Section 1 General

### 1.1 Application

1.1.1 This Chapter is applicable to all ship types and components.

1.1.2 Requirements are given in this Chapter for the following:

- (a) Welding-connection details, defined practices and sequence, consumables and equipment, procedures, workmanship and inspection.
- (b) End connection scantlings and constructional details for longitudinals, beams, frames and bulkhead stiffeners.
- (c) Primary member proportions, stiffening and construction details.

Additional requirements for primary structure of tankers and similar ships are given in Pt 4, Ch 9,6.

1.1.3 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2,2.3) with the exception of 2.9 to 2.13 which are to be complied with

### 1.2 Symbols

1.2.1 Symbols are defined as necessary in each Section.

## Section 2 Welding

### 2.1 General

2.1.1 The plans to be submitted for approval are to indicate clearly details of the welded connections of main structural members, including the type and size of welds. This requirement includes welded connections to steel castings.

The information to be submitted should include the following:

- (a) Whether weld sizes given are throat thicknesses or leg lengths.

# Welding and Structural Details

# Part 3, Chapter 10

Section 2

## 2.5 Stud welding

2.5.1 Where permanent or temporary studs are to be attached by welding to main structural parts in areas subject to high stress, the proposed location of the studs and the welding procedures adopted are to be to the satisfaction of the Surveyors.

## 2.6 Fillet welds

2.6.1 T-connections are generally to be made by fillet welds on both sides of the abutting plate, the dimensions and spacing of which are shown in Fig. 10.2.1. Where the connection is highly stressed, deep penetration or full penetration welding may be required. Where full penetration welding is required, the abutting plate may be required to be bevelled.

2.6.2 The throat thickness of fillet welds is to be determined from:

$$\text{Throat thickness} = t_p \times \text{weld factor} \times \frac{d}{s}$$

where

$d$  = the distance between start positions of successive weld fillet, in mm

$s$  = the length, in mm, of correctly proportioned weld fillet, clear of end craters, and is to be not less than 75 mm

$t_p$  = plate thickness, on which weld fillet size is based, in mm

see also Fig. 10.2.1

Weld factors are given in Tables 10.2.1, 10.2.3 and 10.2.4.

2.6.3 Where an approved deep penetration procedure is used, the fillet leg length calculated from the weld factors given in the Tables may be reduced by 15 per cent provided that the Shipyard is able to meet the following requirements:

- Use of a welding consumable approved for deep penetration welding in accordance with Pt 2, Ch 11 for either the 'p' or 'T' techniques.
- Demonstrations by way of production weld testing that the minimum required penetration depths (i.e. throat thicknesses) are maintained. This is to be documented on a monthly basis by the Shipyard, and made available to the Surveyor on request.

A reduction of 20 per cent may be given provided that in addition to the requirements of (a) and (b) the Shipyard is able to consistently meet the following additional requirements:

- The documentation required in (b) is to be completed and made available to the Surveyor upon request on a weekly basis.
- Suitable process selection confirmed by satisfactory welding procedure tests covering both minimum and maximum root gaps.

2.6.4 Where double continuous fillet welding is proposed, the throat thickness is to be determined taking  $\frac{d}{s}$  equal to 1,0.

2.6.5 The leg length of the weld is to be not less than  $\sqrt{2} \times$  the specified throat thickness.

2.6.6 The plate thickness,  $t_p$ , to be used in the above calculation is generally to be that of the thinner of the two parts being joined. Where the difference in thickness is considerable, the size of fillet will be considered.

2.6.7 Where the thickness of the abutting member of the connection (e.g. the web of a stiffener) is greater than 15 mm and exceeds the thickness of the table member (e.g. plating), the welding is to be double continuous and the throat thickness of the weld is to be not less than the greatest of the following:

- $0,21 \times$  thickness of the table member. The table member thickness used need not exceed 25 mm.
- $0,21$  (0,27 in tanks)  $\times$  half the thickness of the abutting member.
- As required by Table 10.2.2.

2.6.8 Except as permitted by 2.6.7, the throat thickness of the weld is not to be outside the limits specified in Table 10.2.2.




Fig. 10.2.1 Weld types

# Welding and Structural Details

# Part 3, Chapter 10

Section 2

**Table 10.2.1** Weld factors (see continuation)

Item	Weld factor	Remarks
(1) General application: Watertight plate boundaries Non-tight plate boundaries Longitudinals, frames, beams, and other secondary members to shell, deck or bulkhead plating Panel stiffeners, etc. Overlap welds generally Longitudinals of the flat-bar type to plating	0,34 0,13 0,10 0,13 0,21 0,10 0,27	except as required below  in tanks in way of end connections  see Note 5
(2) Bottom construction in way of holds or tanks: Non-tight centre girder: to keel to inner bottom Non-tight boundaries of floors, girders and brackets Inner bottom longitudinals or reverse frames Connection of floors to inner bottom in way of plane bulkheads, bulkhead stools, or corrugated and double plate bulkheads supported on inner bottom. The supporting floors are to be continuously welded to the inner bottom	0,27 0,21 0,21 0,27 0,13 0,44	no scallops in way of 0,2 x span at ends in way of brackets at lower end of main frame under holds strengthened for heavy cargoes Weld size based on floor thickness Weld material compatible with floor material See Note 4
(3) Hull framing: Webs of web frames and stringers: to shell to face plate Tank side brackets to shell and inner bottom	0,16 0,13 0,34	
(4) Decks and supporting structure: Strength deck plating to shell  Other decks to shell and bulkheads (except where forming tank boundaries) Webs of cantilevers to deck and to shell in way of root bracket Webs of cantilevers to face plate Pillars: fabricated end connections end connections (tubular) Girder web connections and brackets in way of pillar heads and heels	  0,21 0,44 0,21 0,10 0,34 full penetration 0,21	as shown in Table 10.2.5 but alternative proposals will be considered  generally continuous   see Note 1 continuous

2.6.9 Continuous welding is to be adopted in the following locations, and may be used elsewhere if desired:

- (a) Boundaries of weathertight decks and erections, including hatch coamings, companionways and other openings.
- (b) Boundaries of tanks and watertight compartments.
- (c) All structure in the after peak and the after peak bulkhead stiffeners.
- (d) All welding inside tanks intended for chemicals or edible liquid cargoes.
- (e) All lap welds in tanks.
- (f) Primary and secondary members to bottom shell in the 0,3L forward.
- (g) Primary and secondary members to plating in way of end connections, and end brackets to plating in the case of lap connections.
- (h) Where 2.6.7 applies.
- (j) Other connections or attachments, where considered necessary, and in particular the attachment of minor fittings to higher tensile steel plating.
- (k) Fillet welds where higher tensile steel is used.

2.6.10 Where intermittent welding is used, the welding is to be made continuous in way of brackets, lugs and scallops and at the orthogonal connections with other members.

4

# Welding and Structural Details

## Part 3, Chapter 10

Section 2

**Table 10.2.1** Weld factors (continued)

Item	Weld factor	Remarks
(9) Structure in machinery space:		
Centre girder to keel and inner bottom	0,27	
Floors to centre girder in way of engine, thrust and boiler bearers	0,27	
Floors and girders to shell and inner bottom	0,21	
Main engine foundation girders:		
to top plate	deep penetration to	edge to be prepared with maximum root 0,33t <sub>p</sub> deep
to hull structure	depend on design	penetration generally
Floors to main engine foundation girders	0,27	
Brackets, etc., to main engine foundation girders	0,21	
Transverse and longitudinal framing to shell	0,13	
(10) Construction in 0,25L forward:		
Floors and girders to shell and inner bottom	0,21	
Bottom longitudinals to shell	0,13	
Transverse and longitudinal side framing to shell	0,13	
Tank side brackets to frame and inner bottom	0,34	
Panting stringers to shell and frames	0,34	
Fore peak construction:		
all internal structure	0,13	unless a greater weld factor is required
(11) After peak construction:		
All internal structure and stiffeners on after peak bulkhead	0,21	unless a greater weld factor is required
(12) Superstructure and deckhouses:		
Connection of external bulkheads to deck	0,34 0,21	1st and 2nd tier erections elsewhere
Internal bulkheads	0,13	
(13) Hatchways and closing arrangements:		
Hatchways coamings to deck	0,34	0,44 at corners
Hatch cover rest bar	0,16	
Hatch coaming stays to coaming	0,13	
Hatch coaming stays to deck	0,21	
Cleats and fittings	0,44	full penetration welding may be required
Primary and secondary stiffening of hatch covers	0,10	0,13 for tank covers and where covers strengthened for loads over
(14) Steering control systems:		
Rudder:		
Fabricated mainpiece and mainpiece to side plates and webs	0,44	
Slot welds inside plates	0,44	
Remaining construction	0,21	
Fixed and steering nozzles:		
Main structure	0,44	
Elsewhere	0,21	
Fabricated housing and structure of thruster units, stabilizers, etc.:		
Main structure	0,44	
Elsewhere	0,21	

# Welding and Structural Details

## Part 3, Chapter 10

Section 2

**Table 10.2.1** Weld factors (conclusion)

Item	Weld factor	Remarks
(15) Miscellaneous fittings and equipment:		
Rings for manhole type covers, to deck or bulkhead	0,34	
Frames of shell and weathertight bulkhead doors	0,34	
Stiffening of doors	0,21	
Ventilator, air pipe, etc., coamings to deck	0,34 0,21	Load Line Positions 1 and 2 elsewhere
Ventilator, etc., fittings	0,21	
Scuppers and discharges, to deck	0,44	
Masts, derrick posts, crane pedestals, etc., to deck	0,44	full penetration welding may be required
Deck machinery seats to deck	0,21	generally
Mooring equipment seats	0,21	generally, but increased or full penetration welding may be required
Bulwark stays to deck	0,21	
Bulwark attachment to deck	0,34	
Guard rails, stanchions, etc., to deck	0,34	
Bilge keel ground bars to shell	0,34	Continuous fillet weld, minimum throat thickness 4 mm
Bilge keels to ground bars	0,21	Light continuous fillet weld, minimum throat thickness 3 mm
Fabricated anchors	full penetration	
<b>NOTES</b> 1. Where pillars are fitted inside tanks or under watertight flats, the end connection is to be such that the tensile stress in the weld does not exceed 108 N/mm <sup>2</sup> (11 kgf/mm <sup>2</sup> ). 2. $t_p$ need not be taken greater than the thickness determined from item 1(a) or 1(b) and Notes, as appropriate, of Table 9.6.1 in Pt 4, Ch 9, but in no case is the weld throat thickness to be less than 0,34 x actual plate thickness. 3. $t_p$ need not be taken greater than the Rule thickness determined from Table 9.7.1 of Pt 4, Ch 9 for stiffener spacing of 760 mm, but in no case is the weld throat thickness to be less than 0,34 x actual plate thickness. 4. In way of bulkhead stools in ballast holds of bulk carriers or in tanks at longitudinal girder/transverse floor intersection, cut-outs are to be omitted and full penetration welding is to be applied to both floor and girder for a distance of 150 mm on either side of intersection. 5. The throat thickness of the weld is to be determined by 2.6.7. For longitudinals within $D/4$ of the strength deck and with a thickness less than 100 mm, the throat thickness need not exceed 5,5 mm.		

2.6.11 Where structural members pass through the boundary of a tank, and leakage into the adjacent space could be hazardous or undesirable, full penetration welding is to be adopted for the members for at least 150 mm on each side of the boundary. Alternatively a small scallop of suitable shape may be cut in the member close to the boundary outside the compartment, and carefully welded all round.

2.7.3 Where direct calculation procedures have been adopted, the weld factors for the 0,2 x overall length at the ends of the members will be considered in relation to the calculated loads.

2.7.4 The throat thickness limits given in Table 10.2.2 are to be complied with.

### 2.7 Welding of primary structure

2.7.1 Weld factors for the connections of primary structure are given in Table 10.2.3.

2.7.2 The weld connection to shell, deck or bulkhead is to take account of the material lost in the notch where longitudinals or stiffeners pass through the member. Where the width of notch exceeds 15 per cent of the stiffener spacing, the weld factor is to be multiplied by:

$$\frac{0,85 \times \text{stiffener spacing}}{\text{length of web plating between notches}}$$

### 2.8 Welding of primary and secondary member end connections

2.8.1 Welding of end connections of primary members is to be such that the area of welding is not less than the cross-sectional area of the member, and the weld factor is to be not less than 0,34 in tanks or 0,27 elsewhere.

2.8.2 The welding of secondary member end connections is to be not less than as required by Table 10.2.4. Where two requirements are given the greater is to be complied with.



# Welding and Structural Details

## Part 3, Chapter 10

Section 2

**Table 10.2.2 Throat thickness limits**

Item	Throat thickness, in mm	
	Minimum	Maximum
(1) Double continuous welding	$0,21t_p$	$0,44t_p$
(2) Intermittent welding	$0,27t_p$	$0,44t_p$ or 4,5
(3) All welds, overriding minimum:		
(a) Plate thickness $t_p \leq 7,5$ mm		
Hand or automatic welding	3,0	—
Automatic deep penetration welding	3,0	—
(b) Plate thickness $t_p > 7,5$ mm		
Hand or automatic welding	3,25	—
Automatic deep penetration welding	3,0	—
<b>NOTES</b> 1. In all cases, the limiting value is to be taken as the greatest of the applicable values given above. 2. Where $t_p$ exceeds 25 mm, the limiting values may be calculated using a notional thickness equal to $0,4(t_p + 25)$ mm. 3. The maximum throat thicknesses shown are intended only as a design limit for the approval of fillet welded joints. Any welding in excess of these limits is to be to the Surveyor's satisfaction.		

2.8.3 The area of weld,  $A_w$ , is to be applied to each arm of the bracket or lapped connection.

2.8.4 Where a longitudinal strength member is cut at a primary support and the continuity of strength is provided by brackets, the area of weld is to be not less than the cross-sectional area of the member.

2.8.5 Where the secondary member passes through, and is supported by, the web of a primary member, the weld connection is to be in accordance with the following:

- In strengthening of bottom forward region:  
Comply with the requirements of Ch 5, 1.5.
- Elsewhere:  
Comply with the requirements of 5.2.

2.8.6 The throat thickness limits given in Table 10.2.2 are to be complied with.

### 2.9 Welding equipment

2.9.1 Welding plant and appliances are to be suitable for the purpose intended and properly maintained taking due cognizance of relevant safety precautions.

2.9.2 Satisfactory storage and handling equipment for consumables are to be provided close to working areas.

2.9.3 The fabricator is to provide suitable means at the welding area to enable accurate measurement of current and voltage.

**Table 10.2.3 Connections of primary structure**

Primary member face area, in cm <sup>2</sup>		Position <sup>(1)</sup>	Weld factor			
Exceeding	Not exceeding		In tanks		In dry spaces	
			To face plate	To plating	To face plate	To plating
	30,0	At ends	0,21	0,27	0,21	0,21
		Remainder	0,10	0,16	0,10	0,13
30,0	65,0	At ends	0,21	0,34	0,21	0,21
		Remainder	0,13	0,27	0,13	0,16
65,0	95,0	At ends	0,34	0,44 <sup>(3)</sup>	0,21	0,27
		Remainder	0,27 <sup>(2)</sup>	0,34	0,16	0,21
95,0	130,0	At ends	0,34	0,44 <sup>(3)</sup>	0,27	0,34
		Remainder	0,27 <sup>(2)</sup>	0,34	0,21	0,27
130,0		At ends	0,44	0,44 <sup>(3)</sup>	0,34	0,44 <sup>(3)</sup>
		Remainder	0,34	0,34	0,27	0,34

NOTES

1. The weld factors 'at ends' are to be applied for 0,2 x the overall length of the member from each end, but at least beyond the toes of the member end brackets. On vertical webs the increased welding may be omitted at the top, but is to extend at least 0,3 x overall length from the bottom.

2. Weld factor 0,34 in cargo oil tanks.

3. Where the web plate thickness is increased locally, the weld size may be based on the thickness clear of the increase, but is to be not less than 0,34 x the increased thickness.

4. In tankers over 122 m in length, the weld factor of the connection of bottom transverses to shell, and of side transverses to shell and vertical webs to longitudinal and transverse bulkheads all in the lower half depth, is to be not less than 0,34.

5. The final throat thickness of the weld fillet to be not less than 0,34t<sub>p</sub> in cargo oil tanks.

## Welding and Structural Details


## Part 3, Chapter 10

Section 2

Table 10.2.4 Secondary member end connection welds

Connection	Weld area, $A_w$ , in $\text{cm}^2$	Weld factor
(1) Stiffener welded direct to plating	$0,25A_s$ or $6,5 \text{ cm}^2$ whichever is the greater	0,34
(2) Bracketless connection of stiffeners or stiffener lapped to bracket or bracket lapped to stiffener:		
(a) in dry space	$1,2 \sqrt{Z}$	0,27
(b) in tank	$1,4 \sqrt{Z}$	0,34
(c) main frame to tank side bracket in 0,15L forward	as (a) or (b)	0,34
(3) Bracket welded to face of stiffener and bracket connection to plating	—	0,34
(4) Stiffener to plating for 0,1 x span at ends, or in way of end bracket if that be greater	—	0,34
Symbols		
$A_s$ = cross sectional area of the stiffener, in $\text{cm}^2$ $A_w$ = the area of the weld, in $\text{cm}^2$ , and is calculated as total length of weld, in cm, x throat thickness, in cm $Z$ = the section modulus, in $\text{cm}^2$ , of the stiffener on which the scantlings of the bracket are based, see Section 3		
NOTE For maximum and minimum weld fillet sizes, see Table 10.2.2.		

Table 10.2.5 Weld connection of strength deck plating to sheerstrake

Item	Stringer plate thickness, mm	Weld type
1	$t \leq 15$	Double continuous fillet weld with a weld factor of 0,44
2	$15 < t \leq 20$	Single vee preparation to provide included angle of $50^\circ$ with root $R \leq \frac{1}{3}t$ in conjunction with a continuous fillet weld having a weld factor of 0,39 or Double vee preparation to provide included angles of $50^\circ$ with root $R \leq \frac{1}{3}t$
3	$t > 20$	Double vee preparation to provide included angles of $50^\circ$ with root $R \leq \frac{1}{3}t$ but not to exceed 10 mm
<p>Where <math>t</math> = thickness of stringer plate, in mm</p>  <p>Single vee preparation      Double vee preparation</p>		
NOTES 1. Welding procedure, including joint preparation, is to be specified. Procedure is to be qualified and approved for individual Builders. 2. See also 2.6.11. 3. For thickness $t$ in excess of 20 mm the stringer plate may be bevelled to achieve a reduced thickness at the weld connection. The length of the bevel is in general to be based on a taper not exceeding 1 in 3 and the reduced thickness is in general to be not less than 0,65 times the thickness of stringer plate or 20 mm, whichever is the greater. 4. Alternative connections will be considered.		

## 2.10 Welding consumables and equipment

2.10.1 All welding consumables are to be approved by Lloyd's Register (hereinafter referred to as 'LR') and are to be suitable for the type of joint and grade of material, see Chapter 11 of the Rules for Materials (Part 2).

2.10.2 Special care is to be taken in the distribution, storage and handling of all welding consumables. Prior to use they are to be kept in a heated dry storage area with a relatively uniform temperature. Condensation on the metal surface during storage and use is to be avoided. Flux-coated electrodes and submerged arc fluxes are to be stored under controlled conditions. Other welding consumables, such as bare wire and welding studs, are to be stored under dry conditions to prevent rusting. Prior to use, the welding consumables are to be baked as per the manufacturers' recommendations.

2.10.3 Steel welding consumables approved by LR, up to and including Grade Y40, are considered acceptable for marine construction in line with the following:

- Consumables are acceptable for welding steels up to three strength levels below that for which the approval applies (e.g. 3Y is acceptable for welding 36, 32 and 27S higher tensile ship steels and normal strength ship steel).
- Consumables with an approved impact toughness grading are acceptable for welding steels with lower specified impact properties subject to (a) (e.g. 3Y is acceptable for EH, DH and AH materials).
- For joints between steels of different grades or different strength levels, the welding consumables may be of a type suitable for the lesser grade or strength being connected, provided that due consideration is given to the total load carrying requirement of the joint. The use of a higher grade of welding consumable may be required where attachments are made to main structural members of a higher grade or strength.

# Welding and Structural Details

## Part 3, Chapter 10

### Section 2

2.10.4 Where the carbon equivalent, calculated from the ladle analysis and using the formula given below, is in excess of 0,45 per cent, approved low hydrogen welding consumables and preheating are to be used. Where the carbon equivalent is above 0,41 per cent but is not more than 0,45 per cent, approved low hydrogen welding consumables are to be used, but preheating will not generally be required except under conditions of high restraint or low ambient temperature. Where the carbon equivalent is not more than 0,41 per cent, welding consumables that have no hydrogen grading may be used and preheating will not generally be required except as above.

$$\text{Carbon equivalent} = C + \frac{\text{Mn}}{6} + \frac{\text{Cr} + \text{Mo} + \text{V}}{5} + \frac{\text{Ni} + \text{Cu}}{15}$$

The type of consumable and preheat proposed for low alloy steels will be subject to special consideration.

2.10.5 All aluminium alloy welding consumables are to be approved by LR. The following consumables and material grades apply:

Consumable alloy grade	Base material alloy grade
RA/WA	5754
RB/WB	5086, 5754
RC/WC	5083, 5086, 5754
RD/WD	6005A, 6061, 6082

### 2.11 Welding procedures and welder qualifications

2.11.1 Welding procedures, giving details of the welding process, type of consumables, joint preparation and welding position, are to be established for the welding of all joints.

2.11.2 Welding procedures are to be tested and qualified in accordance with a recognized National or International Standard. For this purpose, the sample joints are to be prepared under conditions similar to those that will occur during construction of the ship.

2.11.3 The proposed welding procedures are to be approved by the Surveyor prior to construction.

2.11.4 Weld repairs, when required, are to be carried out in accordance with the approved procedures.

2.11.5 Welders and welding operators are to be proficient in the type of work on which they are engaged.

2.11.6 The responsibility for selection, training and testing of welding operators rests with the Builders. The Builders are to test welding operators to a suitable National or International Standard. Records of tests and qualifications are to be kept by the Builders and made available to the Surveyors so that they can be satisfied that the personnel employed during the construction of the ship can achieve the required standard of workmanship.

### 2.12 Workmanship and shipyard practice

2.12.1 A sufficient number of skilled supervisors is to be provided to ensure an effective and systematic control at all stages of welding operations.

2.12.2 Where structural components are to be assembled and welded in works sub-contracted by Builders, the Surveyors are to inspect the sub-contractor's works to ensure that compliance with the requirements of this Chapter can be achieved.

2.12.3 Structural arrangements are to be such as will allow adequate ventilation and access for preheating, where required, and for the satisfactory completion of all welding operations.

2.12.4 The location of welding connections and sequences of welding are to be arranged to minimize restraint. Welded joints are to be so arranged as to facilitate the use of downhand welding wherever possible.

2.12.5 All welding is to be carried out in accordance with the approved welding procedure, see 2.11. The welding arrangements and sequence are to be in accordance with the approved plans and agreed with the Surveyor prior to construction.

2.12.6 Careful consideration is to be given to assembly sequence and overall shrinkage of plate panels, assemblies, etc., resulting from welding processes employed. Welding is to proceed systematically with each welded joint being completed in correct sequence without undue interruption. Where practicable, welding is to commence at the centre of a joint and proceed outwards or at the centre of an assembly and progress outwards towards the perimeter so that each part has freedom to move in one or more directions. Generally, the welding of stiffener members, including transverses, frames, girders, etc., to welded plate panels by automatic processes is to be carried out in such a way as to minimize angular distortion of the stiffener.

2.12.7 The surfaces of all parts to be welded are to be clean, dry and free from rust, scale and grease. Where manual metal arc welding is used, each run of deposit is to be clean and free from slag before the next run is applied. Before a sealing run, or the first run, is applied to the second side of a full penetration butt weld or T-joint, the root is to be back-chipped, ground or air-arc gouged to sound metal. With other multi-run welding processes, back-gouging may not be necessary, before the first run is applied to the second side. When air-arc gouging is used for this operation, special care is to be taken to ensure that the ensuing groove is slag free and has a profile suitable for the completion of welding.

2.12.8 Where prefabrication primers are applied over areas which will be subsequently welded, they are to be of a quality acceptable to LR as having no significant deleterious effect on the finished weld, see Ch 2,3.

# Welding and Structural Details

# Part 3, Chapter 10

## Section 2

**2.12.9** All joints are to be properly aligned and closed or adjusted before welding. Excessive force is not to be used in fairing and closing the work. Where excessive gaps exist between surfaces or edges to be joined, the corrective measures adopted are to be to the satisfaction of the Surveyor. Provision is to be made for retaining correct adjustment during welding operations. Clamps with wedges or strong-backs used for this purpose are to be suitably arranged to allow freedom of lateral movement between adjacent elements. All such temporary fitting aids are to be made from the same type of material as that of the weld joint, e.g. stainless steel with stainless steel.

**2.12.10** Tack welds are to be kept to the minimum and are to be made in accordance with the approved welding procedure. Tack welds that are to be retained as part of the finished weld are to be clean and free from defects. Care is to be taken when removing tack welds used for assembly to ensure that the material of the structure is not damaged.

**2.12.11** Generally, tack welds are not to be applied in lengths of less than 30 mm for mild steel grades and aluminium alloys, and 50 mm for higher tensile steel grades.

**2.12.12** Special attention is to be given to the examination of plating in way of all lifting eye plate positions to ensure freedom from cracks. This examination is not restricted to the positions where eye plates have been removed but includes the positions where lifting eye plates are permanent fixtures.

**2.12.13** Welded temporary attachments used to aid construction are to be removed carefully by grinding, cutting or chipping. The surface of the material is to be finished smooth by grinding followed by crack detection.

**2.12.14** Where complete removal of lifting lug attachments is required, it is recommended they be burned off at the top of the fillet weld connections and the remainder chipped and ground smooth. However, alternative methods of removing these attachments will be considered.

**2.12.15** Any defects in the structure resulting from the removal of temporary attachments are to be repaired.

**2.12.16** When modifications or repairs have been made which result in openings having to be closed by welded inserts, particular care is to be given to the fit of the insert and the welding sequence. The welding is also to be subject to non-destructive examination.

**2.12.17** Fairing, by linear or spot heating, to correct distortions due to welding, is to be carried out using approved procedures in order to ensure that the properties of the material are not adversely affected. Visual examination of all heat affected areas and welds in the vicinity is to be carried out to ensure freedom from cracking. The use of spot or line heating to correct distortion is not permitted for aluminium alloys.

**2.12.18** All major welding operations that would adversely affect finished machined tolerances are to be complete before the final machining operations on, for example, rudders, stern-tubes, propeller brackets and jet units.

**2.12.19** Preheating is to be applied in accordance with the approved procedure. When the ambient temperature is below 0°C or where moisture resides on the surfaces to be welded, due care is to be taken to prewarm and dry the joint preparation.

**2.12.20** Adequate protection is to be provided where welding is required to be carried out in exposed positions in wet, windy or cold weather.

**2.12.21** Special attention is to be paid to preheating when low hydrogen electrodes are used for higher tensile steels on thick materials under high restraint or when applying small weld beads.

**2.12.22** Repairs to defective welding are to be carried out using approved welding consumables and procedures. The repair is to be re-examined, see also 2.13.19.

**2.12.23** Major repairs are not to be carried out without prior approval of the Surveyor.

**2.12.24** Repairs to defects found in the base materials during construction are not to be carried out without prior approval of the Surveyor. If repairs are agreed, these are to be carried out in accordance with the requirements of the relevant Section of Part 2, using qualified welding procedures.

**2.12.25** When misalignment of structural members either side of bulkheads, decks etc., exceeds the agreed tolerance, the misaligned item is to be released, realigned and rewelded in accordance with an approved weld procedure.

**2.12.26** Where welding of aluminium alloy is employed, the following additional requirements are to be complied with, if applicable:

- (a) The aluminium alloys are to be welded by the metal inert gas or tungsten inert gas processes. Where it is proposed to use other welding processes, details are to be submitted for approval.
- (b) The edges of the material to be welded are to be clean and free from grease by chemical or solvent cleaning. The joint edges are to be scratch-brushed, preferably immediately before welding, in order to remove oxide or adhering films of dirt, fillings, etc.

## 2.13 Inspection of welds

**2.13.1** Effective arrangements are to be provided by the Shipbuilder for the visual inspection of finished welds to ensure that all welding has been satisfactorily completed.

**2.13.2** All finished welds are to be sound and free from cracks and lack of fusion and substantially free from incomplete penetration, porosity and slag. The surfaces of welds are to be reasonably smooth and substantially free from undercut and overlap. Care is to be taken to ensure that the specified dimensions of welds have been achieved and that both excessive reinforcement and under-fill of welds are avoided.

**2.13.3** Welds are to be clean and free from paint at the time of visual inspection.

# Welding and Structural Details

# Part 3, Chapter 10

## Section 2

2.13.4 Welds may be coated with a thin layer of protective primer prior to inspection provided it does not interfere with inspection and is removed, if required by the Surveyor, for closer interpretation of possible defective areas.

2.13.5 Visual inspection of all welds may be supplemented by other non-destructive examination techniques in cases of unclear interpretation, as considered necessary by the Surveyor.

2.13.6 In addition to visual inspection, welded joints are to be examined using any one or a combination of ultrasonic, radiographic, magnetic particle, eddy current, dye penetrant or other acceptable methods appropriate to the configuration of the weld.

2.13.7 The method to be used for the volumetric examinations of welds is the responsibility of the Shipbuilder. Radiography using x-rays is generally preferred for the examination of butt welds of 10 mm thickness or less. Ultrasonic examination is acceptable for welds of 10 mm thickness or greater and is to be used for the examination of full penetration, tee butt or cruciform welds or joints of similar configuration. Where ultrasonic inspection of welds below 10 mm in thickness is proposed, this will be specially considered by LR NDE.

2.13.8 Non-destructive examinations are to be made in accordance with definitive written procedures prepared in accordance with a nationally or internationally recognised standard and authorised by Level III qualified personnel. As a minimum, procedures are to identify personnel qualification levels required, NDE datum and identification system, the extent of testing, NDE methods to be applied with technique sheets, acceptance criteria to be applied and the reporting requirements. All NDE procedures are to be approved by a surveyor prior to beginning examination.

2.13.9 Non-destructive examinations are to be undertaken by personnel qualified to an appropriate level of a certification scheme recognized by LR, such as those based on the requirements of ISO 9712, EN 473 or SNT-TC-1A. Generally, inspection personnel subject to direct supervision are to be qualified to Level I; where personnel are unsupervised, they are required to be qualified to Level II or Level III as appropriate. Qualification schemes for Level I and II personnel are to include assessment of practical ability where examinations are to be made on representative test pieces containing relevant defects. The results of qualification tests are to be made available upon request.

2.13.10 Checkpoints examined at the pre-fabrication stage are to include ultrasonic testing on examples of the stop/start points of automatic welding and magnetic particle inspections of weld ends.

2.13.11 Checkpoints examined at the construction stage are generally to be selected from those welds intended to be examined as part of the agreed quality control programme to be applied by the Shipbuilder. The locations and numbers of checkpoints are to be agreed between the Shipbuilder and the Surveyor.

2.13.12 Where components of the structure are sub-contracted for fabrication, the same inspection regime is to be applied as if the item had been constructed within the shipyard. In these cases, particular attention is to be given to highly loaded fabrications (such as stabilizer fin boxes) forming an integral part of the hull envelope.

2.13.13 Particular attention is to be paid to highly stressed items. Magnetic particle inspection is to be used at ends of fillet welds, T-joints, joints or crossings in main structural members and at sternframe connections.

2.13.14 Checkpoints for volumetric examination are to be selected so that a representative sample of welding is examined.

2.13.15 Typical locations for volumetric examination and number of checkpoints to be taken are shown in Table 10.2.6. Critical locations as identified by ShipRight FDA Procedure (see Chapter 16) will also be considered. A list of the proposed items to be examined is to be submitted for approval.

2.13.16 In addition, the following non-destructive examination is to be carried out on ships to be assigned the class notation 'Chemical tanker':

- (a) All crossings of butts and seams of cargo tank bulkhead plating joint welded in assembly areas or on the berth.
- (b) Where cargo tank boundary welding is completed in assembly areas or on the berth, a minimum of 10 per cent of the total weld length is to be crack detected.
- (c) Where side and bottom longitudinal framing and longitudinal stiffeners terminate at transverse bulkheads, a minimum of 10 per cent of the bulkhead boundary connections is to be crack detected in addition to the requirement given in (b).
- (d) Where longitudinal framing and longitudinal bulkhead stiffeners are continuous through transverse bulkheads, 30 per cent each of the bottom and shipside boundaries and 20 per cent of the longitudinal bulkhead boundaries are to be crack detected in addition to the requirement given in (b).
- (e) Where transverse framing members are continuous through the cargo tank boundary, a minimum of 10 per cent of boundary connections is to be crack detected.

2.13.17 For the hull structure of refrigerated spaces, and of ships designed to operate in low air temperatures, the extent of non-destructive examination will be specially considered. For non-destructive examination of gas ships see the *Rules for Liquefied Gases*.

2.13.18 For all ship types, the Shipbuilder is to carry out random non-destructive examination at the request of the Surveyor.

2.13.19 The full extent of any weld defect is to be ascertained by applying additional non-destructive examinations where required. Unacceptable defects are to be completely removed and where necessary, re-welded. The repair is to be examined after re-welding.

# Welding and Structural Details

## Part 3, Chapter 10

Sections 2 &amp; 3

**Table 10.2.6 Non-destructive examination of welds**

Volumetric non-destructive examinations – Recommended extent of testing, see 2.13.15		
Item	Location	Checkpoints, see Note 1
Intersections of butts and seams of fabrication and section welds	Throughout: (a) hull envelope, shell envelope and deck structure plating: • at highly stressed areas, see Note 3 • remainder (b) longitudinal and transverse bulkheads (c) inner bottom and hopper plating	all 1 in 2 (see Note 4) 1 in 2 1 in 2
SDA/FDA	At critical locations identified by SDA or FDA, see Note 2	all
Butt welds in plating	Throughout	1 m in 25 m (see Notes 5 and 6)
Seam welds in plating	Throughout	1 m in 100 m
Butts in longitudinals	Hull envelope within 0,4L amidships Hull envelope outside 0,4L amidships	1 in 10 welds (see Note 7) 1 in 20 welds
Bilge keel butts	Within 0,4L amidships Remainder	all 1 in 3
Structural items when made with full penetration welding as follows: • connection of stool and bulkhead to lower stool shelf plating • vertical corrugations to an inner bottom • hopper knuckles • sheerstrake to deck stringer • hatchways coaming to deck	Throughout  Hatchway ends within 0,4L amidships Hatchway ends outside 0,4L amidships Remainder	1 m in 20 m 1 m in 20 m 1 m in 20 m 1 m in 40 m All 1 in 2 1 in 40 m
<b>NOTES</b> 1. The length of each checkpoint is to be between 0,3 m and 0,5 m. 2. SDA signifies the ShipRight Structural Design Assessment Procedure, FDA signifies the ShipRight Fatigue Design Assessment Procedure. 3. Typically those at sheerstrake, deck stringer, keel strake and turn of bilge. 4. The extent of testing in those areas shown by SDA to be lightly stressed in service may be reduced to 1 in 4 with the agreement of the Surveyor. 5. Checkpoints in butt welds and seam welds are in addition to those at intersections. 6. Welds at inserts used to close openings in hull envelope plating are to be checked by non-destructive examination. 7. Particular attention is to be given to repair rates in longitudinal butts. Additional welds are to be tested if defects such as lack of fusion or incomplete penetration are observed in more than 10 per cent of the welds examined. 8. Agreed locations are not to be indicated on the blocks prior to the welding taking place, nor is special treatment to be given at these locations.		

2.13.20 Results of non-destructive examinations made during construction are to be recorded and evaluated by the Shipbuilder on a continual basis in order that the quality of welding can be monitored. These records are to be made available to the Surveyors.

2.13.21 The extent of applied non-destructive examinations is to be increased when warranted by the analysis of previous results.



### Section 3

## Secondary member end connections

### 3.1 General

3.1.1 Secondary members, that is longitudinals, beams, frames and bulkhead stiffeners forming part of the hull structure, are generally to be connected at their ends in accordance with the requirements of this Section. Where it is desired to adopt bracketless connections, the proposed arrangements will be individually considered.

3.1.2 Where end connections are fitted in accordance with these requirements, they may be taken into account in determining the effective span of the member.

3.1.3 Where the section modulus of the secondary member on which the bracket is based (see 3.3.2) exceeds 2000 cm<sup>3</sup>, the scantlings of the connection will be considered.

## 3.2 Symbols

3.2.1 The symbols used in this Section are defined as follows:

- $a, b$  = the actual lengths of the two arms of the bracket, in mm, measured from the plating to the toe of the bracket
- $b_f$  = the breadth of the flange, in mm
- $t$  = the thickness of the bracket, in mm
- $Z$  = the section modulus of the secondary member, in cm<sup>3</sup>.


3.3.2 In other cases the scantlings of the bracket are to be based on the modulus as follows:

- (a) Bracket connecting stiffener to primary member: modulus of the stiffener.
- (b) Bracket at the head of a main transverse frame where frame terminates: modulus of the frame.
- (c) Brackets connecting lower deck beams or longitudinals to the main frame in the forward 0,15L: modulus of the frame.
- (d) Elsewhere: the lesser modulus of the members being connected by the bracket.

3.3.3 Typical arrangements of stiffener end brackets are shown diagrammatically in Fig. 10.3.1.

## 3.3 Basis for calculation

3.3.1 Where a longitudinal strength member is cut at a primary support and the continuity of strength is provided by brackets, the scantlings of the brackets are to be such that their section modulus and effective cross-sectional area are not less than those of the member. Care is to be taken to ensure correct alignment of the brackets on each side of the primary member.



# Welding and Structural Details

# Part 3, Chapter 10

Section 3

## 3.4 Scantlings of end brackets

3.4.1 The lengths,  $a$  and  $b$ , of the arms are to be measured from the plating to the toe of the bracket and are to be such that:

- (a)  $a + b \geq 2,0l$
- (b)  $a \geq 0,8l$
- (c)  $b \geq 0,8l$

where

$$l = 90 \left( 2 \sqrt{\frac{Z}{14 + \sqrt{Z}}} - 1 \right) \text{ mm}$$

but in no case is  $l$  to be taken as less than twice the web depth of the stiffener on which the bracket scantlings are to be based.

The scantlings of main frames are normally to be based on these standard brackets at top and bottom, while the scantlings of 'tween deck frames are normally to be based on a standard bracket at the top only. Where the actual arm lengths fitted,  $a_1$  and  $b_1$  (in mm) are smaller than Rule size, or bracket is omitted, an equivalent arm length,  $l_a$ , for the calculation of end connection factor, see Table 1.6.2 in Pt 4, Ch 1, is to be derived from:

- (d)  $l_a = \frac{(a_1 + b_1)}{2}$
- (e)  $a_1 \geq 0,8l_a$
- (f)  $b_1 \geq 0,8l_a$
- (g)  $l_a = 0$ , where:
  - (i) bracket is omitted from the upper or lower ends of the frame, or
  - (ii) lower frame bracket at bilge is at same level as the inner bottom, or
  - (iii) lower frame is welded directly to the inner bottom.

3.4.2 The length of arm of tank side and hopper side brackets is to be not less than 20 per cent greater than that required above.

3.4.3 The thickness of the bracket is to be not less than as required by Table 10.3.1.

3.4.4 The free edge of the bracket is to be stiffened where any of the following apply:

- (a) The section modulus,  $Z$ , exceeds 2000 cm<sup>3</sup>.
- (b) The length of free edge exceeds 50t mm.
- (c) The bracket is fitted at the lower end of main transverse side framing.

3.4.5 Where a flange is fitted, its breadth is to be not less than:

$$b_f = 40 \left( 1 + \frac{Z}{1000} \right) \text{ mm}$$

but not less than 50 mm

3.4.6 Where the edge is stiffened by a welded face flat, the cross-sectional area of the face flat is to be not less than:

- (a) 0,009 $b_f t$  cm<sup>2</sup> for offset edge stiffening.
- (b) 0,014 $b_f t$  cm<sup>2</sup> for symmetrically placed stiffening.

3.4.7 Where the stiffening member is lapped on to the bracket, the length of overlap is to be adequate to provide for the required area of welding. In general, the length of overlap should be not less than  $10\sqrt{Z}$  mm, or the depth of stiffener, whichever is the greater.

3.4.8 Where the free edge of the bracket is hollowed out, it is to be stiffened or increased in size to ensure that the modulus of the bracket through the throat is not less than that of the required straight edged bracket.

## 3.5 Arrangements and details

3.5.1 The arrangement of the connection between the stiffener and the bracket is to be such that at no point in the connection is the modulus reduced to less than that of the stiffener with associated plating.

3.5.2 The design of end connections and their supporting structure is to be such as to provide adequate resistance to rotation and displacement of the joint.

**Table 10.3.1 Thickness of brackets**

Bracket	Thickness, in mm	Limits	
		Minimum	Maximum
With edge stiffened:			
(a) in dry spaces	$3,5 + 0,25 \sqrt{Z}$	6,5	12,5
(b) in tanks	$4,5 + 0,25 \sqrt{Z}$	7,5 (see Note)	13,5
Unstiffened brackets:			
(a) in dry spaces	$5,5 + \frac{Z}{55} - \left( \frac{Z}{168} \right)^{1,3}$	7,5	—
(b) in tanks	$6,5 + \frac{Z}{55} - \left( \frac{Z}{168} \right)^{1,3}$	8,5 (see Note)	—
NOTE In the cargo tank region of tankers, the minimum thickness is to be not less than the compartment minimum thickness, see Pt 4, Ch 9,10.			



# Welding and Structural Details

# Part 3, Chapter 10

Sections 3 & 4

3.5.3 For arrangements where end brackets are not perpendicular to the adjacent plating the strength of the brackets, in term of lateral stability, may need to be specially considered.

## Section 4 Construction details for primary members

### 4.1 General

4.1.1 The requirements for section modulus and inertia (if applicable) of primary members are given in the appropriate Chapter. This Section includes the requirements for proportions, stiffening and construction details for primary members in dry spaces and in tanks of all ship types other than tankers.

4.1.2 The requirements for construction details for the primary structure of tankers are given in Pt 4, Ch 9,10.

4.1.3 The requirements of this Section may be modified where direct calculation procedures are adopted to analyse the stress distribution in the primary structure.

### 4.2 Symbols

4.2.1 The symbols used in this Section are defined as follows:

- $d_w$  = depth of member web, in mm
- $k_L, k$  = higher tensile steel factor, see Ch 2,1.2
- $t_w$  = thickness of member web, in mm
- $A_f$  = area of member face plate or flange, in cm<sup>2</sup>
- $F_D$  = local scantlings reduction factor as defined in Pt 3, Ch 4,5.6
- $S_w$  = spacing of stiffeners on member web, or depth of unstiffened web, in mm.

### 4.3 Arrangements

4.3.1 Primary members are to be so arranged as to ensure effective continuity of strength, and abrupt changes of depth or section are to be avoided. Where members abut on both sides of a bulkhead, or on other members, arrangements are to be made to ensure that they are in alignment. Primary members in tanks are to form a continuous line of support and wherever possible, a complete ring system.

4.3.2 The members are to have adequate lateral stability and web stiffening and the structure is to be arranged to minimize hard spots and other sources of stress concentration. Openings are to have well rounded corners and smooth edges and are to be located having regard to the stress distribution and buckling strength of the panel.

4.3.3 Primary members are to be provided with adequate end fixity by end brackets or equivalent structure. The design of end connections and their supporting structure is to be such as to provide adequate resistance to rotation and displacement of the joint and effective distribution of the load from the member.

4.3.4 Where the primary member is supported by structure which provides only a low degree of restraint against rotation, the member is generally to be extended for at least two frame spaces, or equivalent, beyond the point of support before being tapered.

4.3.5 Where primary members are subject to concentrated loads, particularly if these are out of line with the member web, additional strengthening may be required.

### 4.4 Geometric properties and proportions

4.4.1 The geometric properties of the members are to be calculated in association with an effective width of attached plating determined in accordance with Ch 3,3.2.

4.4.2 The minimum thickness or area of material in each component part of the primary member is given in Table 10.4.1.

**Table 10.4.1 Minimum thickness of primary members**

Item	Requirement
(1) Member web plate (see Note)	$t_w = 0,01S_w$ but not less than 7 mm in dry spaces and not less than 8 mm in tanks
(2) Member face plate	$A_f$ not to exceed $\frac{d_w t_w}{150}$ cm <sup>2</sup>
(3) Deck plating forming the upper flange of underdeck girders	Plate thickness not less than $\sqrt{\frac{A_f}{1,8k}}$ mm, and 10 per cent greater for hatch side girders Width of plate not less than 700 mm
(4) Primary members in cargo oil tanks in tankers	As required by Pt 4, Ch 9,10
<b>NOTE</b> For primary members having a web depth exceeding 1500 mm, the arrangement of stiffeners will be individually considered, and stiffening parallel to the member face plate may be required.	

4.4.3 Primary members constructed of higher tensile steel are to comply with Table 10.4.1.

### 4.5 Web stability

4.5.1 Primary members of asymmetrical section are to be supported by tripping brackets at alternate secondary members. If the section is symmetrical, the tripping brackets may be four spaces apart.

# Welding and Structural Details

# Part 3, Chapter 10

Sections 4 & 5

4.5.2 Tripping brackets are also to be fitted at the toes of end brackets and in way of heavy or concentrated loads such as the heels of pillars.

4.5.3 Where the ratio of unsupported width of face plate (or flange) to its thickness exceeds 16:1, the tripping brackets are to be connected to the face plate and on members of symmetrical section, the brackets are to be fitted on both sides of the web.

4.5.4 Intermediate secondary members may be welded directly to the web or connected by lugs.

4.5.5 Where the depth of web of a longitudinal girder at the strength deck within 0,4L amidships exceeds:

(a)  $55t_w$  for mild steel members

(b)  $55t_w \sqrt{\frac{k_L}{F_D}}$  for higher tensile steel members

additional longitudinal web stiffeners are to be fitted at a spacing not exceeding the value given in (a) or (b) as appropriate, with a maximum of  $65t_w \sqrt{k_L}$  for higher tensile steel members. In cases where this spacing is exceeded, the web thickness is, in general, to be suitably increased.

4.5.6 The arm length of unstiffened end brackets is not to exceed  $100t_w$ . Stiffeners parallel to the bracket face plate are to be fitted where necessary to ensure that this limit is not exceeded.

4.5.7 Web stiffeners may be flat bars of thickness  $t_w$  and depth  $0,1d_w$ , or 50 mm, whichever is the greater. Alternative sections of equivalent moment of inertia may be adopted.

## 4.6 Openings in the web

4.6.1 Where openings are cut in the web, the depth of opening is not to exceed 25 per cent of the web depth, and the opening is to be so located that the edges are not less than 40 per cent of the web depth from the face plate. The length of opening is not to exceed the web depth or 60 per cent of the secondary member spacing, whichever is the greater, and the ends of the openings are to be equidistant from the corners of cut-outs for secondary members. Where larger openings are proposed, the arrangements and compensation required will be considered.

4.6.2 Openings are to have smooth edges and well rounded corners.

4.6.3 Cut-outs for the passage of secondary members are to be designed to minimize the creation of stress concentrations. The breadth of cut-out is to be kept as small as practicable and the top edge is to be rounded, or the corner radii made as large as practicable. The extent of direct connection of the web plating, or the scantlings of lugs or collars, is to be sufficient for the load to be transmitted from the secondary member.

## 4.7 End connections

4.7.1 End connections of primary members are generally to comply with the requirements of Section 3, taking  $Z$  as the section modulus of the primary member.

4.7.2 The thickness of the bracket is to be not less than that of the primary member web. The free edge of the bracket is to be stiffened.

4.7.3 Where a deck girder or transverse is connected to a vertical member on the shell or bulkhead, the scantlings of the latter may be required to be increased to provide adequate stiffness to resist rotation of the joint.

4.7.4 Where a member is continued over a point of support, such as a pillar or pillar bulkhead stiffener, the design of the end connection is to be such as to ensure the effective distribution of the load into the support. Proposals to fit brackets of reduced scantlings, or alternative arrangements, will be considered.

4.7.5 Connections between primary members forming a ring system are to minimize stress concentrations at the junctions. Integral brackets are generally to be radiused or well rounded at their toes. The arm length of the bracket, measured from the face of the member, is to be not less than the depth of the smaller member forming the connection.

## Section 5 Structural details

### 5.1 Continuity and alignment

5.1.1 The arrangement of material is to be such as will ensure structural continuity. Abrupt changes of shape or section, sharp corners and points of stress concentration are to be avoided.

5.1.2 Where members abut on both sides of a bulkhead or similar structure, care is to be taken to ensure good alignment.

5.1.3 Pillars and pillar bulkheads are to be fitted in the same vertical line wherever possible, and elsewhere arrangements are to be made to transmit the out of line forces satisfactorily. The load at head and heel of pillars is to be effectively distributed and arrangements are to be made to ensure the adequacy and lateral stability of the supporting members.

5.1.4 Continuity is to be maintained where primary members intersect and where the members are of the same depth, a suitable gusset plate is to be fitted.

5.1.5 End connections of structural members are to provide adequate end fixity and effective distribution of the load into the supporting structure.

5.1.6 The toes of brackets, etc., should not land on unstiffened panels of plating. Special care should be taken to avoid notch effects at the toes of brackets, by making the toe concave or otherwise tapering it off.

5.1.7 Where primary and/or secondary members are constructed of higher tensile steel, particular attention is to be paid to the design of the end bracket toes in order to minimize stress concentrations. Sniped face plates which are welded onto the edge of primary member brackets are to be carried well around the radiused bracket toe and are to incorporate a taper not exceeding 1 in 3. Where sniped face plates are welded adjacent to the edge of primary member brackets, adequate cross sectional area is to be provided through the bracket toe at the end of the snipe. In general, this area measured perpendicular to the face plate, is to be not less than 60 per cent of the full cross-sectional area of the face plate, see Fig. 10.5.1. See also Pt 4, Ch 1,4.3, Pt 4, Ch 1,6.1, Pt 4, Ch 9,5.7 and Pt 4, Ch 9,10.13.




Fig. 10.5.1 Bracket toe construction

## 5.2 Arrangements at intersections of continuous secondary and primary members

5.2.1 Cut-outs for the passage of secondary members through the web of primary members, and the related collaring arrangements, are to be designed to minimize stress concentrations around the perimeter of the opening and in the attached hull envelope or bulkhead plating. The critical shear buckling stress of the panel in which the cut-out is made is to be investigated. Cut-outs for longitudinals will be required to have double lugs in areas of high stress, e.g. in way of cross tie ends and floors under bulkhead stools in ore and ballast holds.

5.2.2 Cut-outs are to have smooth edges, and the corner radii are to be as large as practicable, with a minimum of 20 per cent of the breadth of the cut-out or 25 mm, whichever is the greater. It is recommended that the web plate connection to the hull envelope or bulkhead should end in a smooth tapered 'soft toe'. Recommended shapes of cut-out are shown in Fig. 10.5.3, but consideration will be given to other shapes on the basis of maintaining equivalent strength and minimizing stress concentration. Consideration is to be given to the provision of adequate drainage and unimpeded flow of air and water when designing the cut-outs and connection details.

5.2.3 Asymmetrical secondary members are to be connected on the heel side to the primary member web plate. Additional connection by lugs on the opposite side may be required.

5.2.4 Symmetrical secondary members are to be connected by lugs on one or both sides, as necessary.

5.2.5 The cross-sectional areas of the connections are to be determined from the proportion of load transmitted through each component in association with its appropriate permissible stress.

5.2.6 The total load,  $P$ , transmitted to the primary member is to be derived in accordance with Table 10.5.1.

5.2.7 This load is to be apportioned between the connections as follows:

(a) Transmitted through the collar arrangement:

$$P_1 = P \left( \frac{s_1}{S_w} + \frac{A_1}{4C_f A_f + A_1} \right)$$

where  $A_1$  is derived in accordance with 5.2.8 and  $\frac{s_1}{S_w}$  is

not to be taken as greater than 0,25

The collar load factor,  $C_f$ , is to be derived as follows:

Symmetrical secondary members

$$\begin{aligned} C_f &= 1,85 & \text{for } A_f \leq 18 \\ C_f &= 1,85 - 0,0341 (A_f - 18) & \text{for } 18 < A_f \leq 40 \\ C_f &= 1,1 - 0,01 (A_f - 40) & \text{for } A_f > 40 \end{aligned}$$

Asymmetrical secondary members

$$C_f = 0,68 + 0,0224 \frac{b_l}{A_f}$$

where

$A_f$  = the area, in cm<sup>2</sup>, of the primary member web stiffener in way of the connection including backing bracket, where fitted, see 5.2.10

$b_l$  = the length of lug or direct connection, in mm, as shown in Fig. 10.5.3. Where the lug or direct connections differ in length, a mean value of  $b_l$  is to be used.

(b) Transmitted through the primary member web stiffener:

$$P_2 = P - P_1 \text{ kN (tonne-f)}$$

(c) Where the web stiffener is not connected to the secondary member,  $P_1$  is to be taken equal to  $P$ .

# Welding and Structural Details

# Part 3, Chapter 10

Section 5

**Table 10.5.1** Total load transmitted to connection of secondary members (see continuation)

Ship type	Head, $h_1$ , in metres	Total load, $P$ , transmitted to connection
(1) Oil tankers, bulk chemical tankers and combination carriers (see 1.1.3)	<p><math>h_1</math> = load height, in metres, derived in accordance with the following provisions, but to be taken as not less than <math>\frac{L_1}{56}</math> or <math>(0,01L_1 + 0,7)</math> m whichever is the greater</p> <p>For shell framing members:</p> <p>(a) With mid-point of span at base line, <math>h_1 = 0,8D_2</math></p> <p>(b) With mid-point of span at a distance <math>0,6D_2</math> above base line, <math>h_1 = f D_2 B_f</math></p> <p>(c) With mid-point of span intermediate between (a) and (b). The value of <math>h_1</math> is to be obtained by linear interpolation between values from (a) and (b).</p> <p>(d) With mid-point of span higher than <math>0,6D_2</math> above base line. The value of <math>h_1</math> is to be obtained by linear interpolation between the values from (b) and the values at the following points:</p> <p>(i) For framing members located at and abaft <math>0,2L</math> from the forward perpendicular (see Fig. 10.5.2(a)) Zero value at the level of the deck edge amidships</p> <p>(ii) For framing members forward of cargo tank region (see Fig. 10.5.2(b)) Value of <math>f D_2 (B_f - 1)</math> at the level 3 m above the minimum bow height determined from the Load Lines Conventions</p> <p>(iii) Intermediate values between locations (i) and (ii) are to be determined by linear interpolation</p> <p>For secondary stiffening members of transverse and longitudinal bulkheads, and inner hull and inner bottom of double hull tankers (see 1.1.3): <math>h_1</math> = distance from mid-point of span to top of tank but need not exceed <math>0,8D_2</math></p>	<p>(a) In general <math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN (<math>P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p> <p>(b) For wash bulkheads <math>P = 11,77 (S_w - s_1/2) s_1 h_1</math> kN (<math>P = 1,2 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p>
(2) Other ship types for which oil tanker (see 1.1.3) requirements are not applicable	<p>Side and bottom shell longitudinals</p> <p>As for (1) except as follows:</p> <p>(a) <math>h_1</math> to be derived in accordance with (1) above but to be taken as not less than <math>\frac{L_1}{56}</math> m for type 'B - 60' and the greater of <math>\frac{L_1}{70}</math>, or 1,20 m for Type 'B' ships</p> <p>(b) <math>h_1</math> for item (1)(d)(ii) above to extend forward of <math>0,15L</math> from the forward perpendicular</p>	<p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN (<math>P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p>

## Welding and Structural Details

## Part 3, Chapter 10

## Section 5

**Table 10.5.1** Total load transmitted to connection of secondary members (conclusion)

Ship type	Head, $h_1$ , in metres	Total load, $P$ , transmitted to connection
(3) Other ship types for which oil tanker (see 1.1.3) requirements are not applicable (continued)	<p>Internal tank boundaries</p> <p>(a) Topside tank longitudinals</p> <p><math>h_1</math> = distance from the longitudinal under consideration to the highest point of the tank with the ship inclined 30° either way, or</p> <p>= the greater of the distance from the longitudinal under consideration to the top of the tank, or half the distance to the top of the overflow, or</p> <p>= 1,5 m</p> <p>whichever is the greatest</p> <p>(b) Inner bottom and hopper longitudinals</p> <p>(i) For cargo ships and bulk carriers (see 1.1.3) without the notation 'strengthened for heavy cargoes'</p> <p><math>h_1 = 1,39T</math></p> <p>(ii) For cargo ships and bulk carriers (see 1.1.3) with the notation 'strengthened for heavy cargoes' <math>h_1 = H</math></p> <p>(iii) For bulk carriers (see 1.1.3) where the topside wing tank is interconnected with hopper side and double bottom tanks</p> <p><math>h_1</math> = the distance from the longitudinal under consideration to the top of the topside tank with the ship inclined 25° either way</p> <p>(iv) For bulk carriers (see 1.1.3) in way of ballast hold</p> <p><math>h_1</math> = the distance from the longitudinal under consideration to the top of the hatchway coaming</p> <p>(v) For cargo ships and bulk carriers (see 1.1.3) with double hull where tank at side interconnected with double bottom</p> <p><math>h_1 = H</math></p> <p>(c) Longitudinals of inner hull of double hull cargo ships and bulk carriers (see 1.1.3)</p> <p><math>h_1</math> = the distance from the longitudinal under consideration to the top of the tank, or half the distance to the top of the overflow, whichever is the greater</p>	<p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN  <math>(P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p> <p><math>P = 9,81 (S_w - s_1/2) s_1 h_1 / C</math> kN  <math>P = (S_w - s_1/2) s_1 h_1 / C</math> tonne-f  but not to be taken less than the load derived from (b)(iii), (b)(iv), (b)(v) or (c) where applicable</p> <p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN  <math>(P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p> <p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN  <math>(P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p> <p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN  <math>(P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p> <p><math>P = 10,06 (S_w - s_1/2) s_1 h_1</math> kN  <math>(P = 1,025 (S_w - s_1/2) s_1 h_1</math> tonne-f)</p>
<p><math>B_f</math> = bow fullness factor determined from Ch 5, Fig. 5.4.3 to be considered. To be taken as 1 for framing members located at and abaft 0,2L from the forward perpendicular</p> <p><math>f</math> = load height factor at level 0,6D above base line, see Table 10.5.2</p> <p><math>h_1</math> = load height, in metres, see also Fig. 10.5.2</p> <p><math>C</math> = stowage rate, in m<sup>3</sup>/tonne, as defined in Ch 3.5.2. For cargo ships without the notation 'strengthened for heavy cargoes', the value to be used is 1,39 m<sup>3</sup>/tonne. For cargo ships and bulk carriers (see 1.1.3) with the notation 'strengthened for heavy cargoes', the actual stowage rate is to be used, but the value is not to be taken greater than 0,865 m<sup>3</sup>/tonne</p> <p><math>H</math> = height from inner bottom at position under consideration, to deck at side amidships, in metres, for inner bottom longitudinals</p> <p>= height from the longitudinal under consideration to the underside of the topside tank sloped bulkhead, in metres, for hopper longitudinals</p> <p><math>S_w</math> = spacing of primary members, in metres</p> <p><math>s_1</math> = spacing of secondary members, in metres</p> <p><math>T</math> = the summer draught, in metres, measured from top of keel</p> <p><math>D_2 = D</math> in metres, but need not be taken greater than 1,67</p> <p><math>L_1 = L</math> but need not be taken as greater than 190 m</p>		


## Welding and Structural Details

## Part 3, Chapter 10

Section 5

**Table 10.5.2** Load height factor,  $f$ 

	Ship depth, $D$ metres					
	$\leq 17,5$	20	22,5	25	27,5	30
(1) (a) For oil tankers, bulk chemical tankers and combination carriers (see 1.1.3), tank boundaries wholly within parallel mid-body	0,6	0,6	0,582	0,556	0,535	0,517
(b) For other ship types, at and abaft 0,2L from the forward perpendicular						
(2) (a) For oil tankers, bulk chemical tankers and combination carriers (see 1.1.3), tank boundaries wholly or partially outside parallel mid-body	0,7	0,685	0,685	0,628	0,6	0,577
(b) For other ship types, forward of 0,15L from the forward perpendicular						
NOTE Intermediate values to be obtained by linear interpolation.						



5.2.8 The effective cross-sectional area  $A_1$  of the collar arrangements is to be taken as the sum of cross-sectional areas of the components of the connection as follows:

(a) Direct connection:

$$A_1 = 0,01 b_1 t_w \text{ cm}^2$$

(b) Lug connection:

$$A_1 = 0,01 f_1 b_1 t_1 \text{ cm}^2$$

where

$f_1 = 1,0$  for symmetrical secondary member connections

$\frac{140}{W_1}$  but not greater than 1,0, for asymmetrical

secondary member connections

$t_w$  = thickness of primary member web, in mm

$t_2$  = thickness, in mm, of lug connection, and is to be taken not greater than the thickness of the adjacent primary member web plate

$W$  = overall width of the cut-out, in mm


$W_2$  = width for cut-out asymmetrical to secondary member web, in mm

(see Fig. 10.5.3)


5.2.9 The values of  $A_f$  and  $A_1$  are to be such that the stresses given in Table 10.5.3 are not exceeded.

5.2.10 Where a bracket is fitted to the primary member web plate in addition to a connected stiffener it is to be arranged on the opposite side to, and in alignment with the stiffener. The arm length of the bracket is to be not less than the depth of the stiffener, and its cross-sectional area through the throat of the bracket is to be included in the calculation of  $A_f$ .

5.2.11 In general where the primary member stiffener is connected to the secondary member it is to be aligned with the web of the secondary member, except where the face plate of the latter is offset and abutted to the web, in which case the stiffener connection is to be lapped. Lapped connections of primary member stiffeners to mild steel bulb plate or rolled angle secondary members may also be permitted. Where such lapped connections are fitted, particular care is to be taken to ensure that the primary member stiffener wrap around weld connection is free from undercut and notches, see also 2.13.



**Fig. 10.5.3 Cut-outs and connections**



**Fig. 10.5.4 Arrangement with offset stiffener**

5.2.12 Fabricated longitudinals having the face plate welded to the underside of the web, leaving the edge of the web exposed, are not recommended for side shell and longitudinal bulkhead longitudinals. Where it is proposed to fit such sections, a symmetrical arrangement of connection to transverse members is to be incorporated. This can be achieved by fitting backing brackets on the opposite side of the transverse web or bulkhead. The primary member stiffener and backing brackets are to be lapped to the longitudinal web, see 5.2.11.

# Welding and Structural Details

# Part 3, Chapter 10

Section 5

**Table 10.5.3 Permissible stresses**

Item		Direct stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) (see Notes 1 and 2)		Shear stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) (see Note 1)	
		Oil tankers	Other ship types for which oil tanker requirements are not applicable	Oil tankers and ship types where primary member stiffener unconnected	Other ship types for which oil tanker requirements are not applicable
Primary member web plate stiffener within distance <i>a</i> of end, see Fig. 10.5.3		147,2 (15,0)	157 (16,0)	—	—
Welding of primary member web plate stiffener to secondary member	Butted	98,1 (10,0) (double continuous fillet)	117,7 (12,0) (double continuous fillet)	—	—
		147,2 (15,0) (automatic deep penetration)	157 (16,0) (automatic deep penetration)	—	—
	Lapped	—	—	83,4 (8,5) (See Note 2)	98,1 (10,0) (See Note 2)
Lug or collar plate and weld	Single	—	—	68,6 (7,0)	98,1 (10,0)
	Double	—	—	83,4 (8,5)	
NOTES					
1. The welding requirements of Section 2 and, where applicable 5.2.13 are also to be complied with (see 1.1.3).					
2. Where longitudinals are of higher tensile steel having a yield stress of 32 kg/mm <sup>2</sup> or more, these stresses are to be divided by the factor 1,2 for application to side longitudinals above 0,3 <i>D</i> <sub>2</sub> from the base-line. For definition of <i>D</i> <sub>2</sub> see Table 10.5.1.					

5.2.13 For ship types for which oil tanker (see 1.1.3) requirements are not applicable, the collar arrangement is to satisfy the requirements of 5.2.1 to 5.2.12 inclusive. In addition the weld area of the connections is to be not less than the following:

(a) Connection of primary member stiffener to the secondary member:

$A_w = 0,25A_f$  or 6,5 cm<sup>2</sup>, whichever is the greater, corresponding to a weld factor of 0,34 for the throat thickness

(b) Connection of secondary member to the web of the primary member:

$A_w = 0,5 \sqrt{Z}$  corresponding to a weld factor of 0,34 in tanks or 0,27 in dry spaces for the throat thickness where

$A_w$  = weld area, in cm<sup>2</sup>, and is calculated as total length of weld, in cm, multiplied by throat thickness, in cm

$A_f$  = cross-sectional area of the primary member web stiffener, in cm<sup>2</sup>, in way of connection

$Z$  = the section modulus, in cm<sup>3</sup>, of the secondary member.

5.2.14 Where the stiffeners of the double bottom floors, and the hopper primary members are unconnected to the secondary members and offset from them (see Fig. 10.5.4) the collar arrangement is to satisfy the requirements of 5.2.1 to 5.2.13 inclusive. In addition, the fillet welds attaching the lugs to the secondary members are to be based on a weld factor of 0,44 for the throat thickness. To facilitate access for welding the offset, stiffeners are to be located 50 mm from the slot edge furthest from the web of the secondary member. The ends of the offset stiffeners are to be suitably tapered and softened.

5.2.15 Alternative arrangements will be considered on the basis of their ability to transmit load with equivalent effectiveness. Details of the calculations made and testing procedures are to be submitted.

## 5.3 Openings

5.3.1 Manholes, lightening holes and other cut-outs are to be avoided in way of concentrated loads and areas of high shear. In particular, manholes and similar openings are not to be cut in vertical or horizontal diaphragm plates in narrow cofferdams or double plate bulkheads within one-third of their length from either end, nor in floors or double bottom girders close to their span ends, or below the heels of pillars, unless the stresses in the plating and the panel buckling characteristics have been calculated and found satisfactory.

5.3.2 Manholes, lightening holes and other openings are to be suitably framed and stiffened where necessary.

5.3.3 Air and drain holes, notches and scallops are to be kept at least 200 mm clear of the toes of end brackets and other areas of high stress. Openings are to be well rounded with smooth edges. Details of scalloped construction are shown in Fig. 10.2.1. Closely spaced scallops are not permitted in higher tensile steel members. Widely spaced air or drain holes may be accepted, provided that they are of elliptical shape, or equivalent, to minimize stress concentration and are, in general, cut clear of the weld connection.



# Welding and Structural Details

## Part 3, Chapter 10

Section 5

### 5.4 Sheerstrake and bulwarks

5.4.1 Where an angled gunwale is fitted, the top edge of the sheerstrake is to be kept free of all notches and isolated welded fittings. Bulwarks are not to be welded to the top of the sheerstrake within the 0,5L amidships.

5.4.2 Where a rounded gunwale is adopted, the welding of fairlead stools and other fittings to this plate is to be kept to the minimum, and the design of the fittings is to be such as to minimize stress concentration.

5.4.3 Arrangements are to ensure a smooth transition from rounded gunwale to angled gunwale towards the ends of the ship.

5.4.4 At the ends of superstructures where the side plating is extended and tapered to align with the bulwark plating, the transition plating is to be suitably stiffened and supported. Where freeing ports or other openings are essential in this plate, they are to be suitably framed and kept well clear of the free edge.

### 5.5 Fittings and attachments, general

5.5.1 The quality of welding and general workmanship of fittings and attachments as given in 5.6 and 5.7 are to be equivalent to that of the main hull structure. Visual examination of all welds is to be supplemented by non-destructive testing as considered necessary by the Surveyor.

### 5.6 Bilge keels and ground bars

5.6.1 It is recommended that bilge keels should not be fitted in the forward 0,3L region on ships intended to navigate in severe ice conditions.

5.6.2 Bilge keels are to be attached to a continuous ground bar as shown in Fig. 10.5.5. Butt welds in shell plating, ground bar and bilge keels are to be staggered.


5.6.3 The minimum thickness of the ground bar is to be equal to the thickness of the bilge strake or 14 mm, whichever is the lesser.

5.6.4 The material class, grade and quality of the ground bar are to be in accordance with Table 2.2.1, Note 11 in Chapter 2.

5.6.5 The ground bar is to be connected to the shell with a continuous fillet weld and the bilge keel to the ground bar with a light continuous fillet weld.

5.6.6 Direct connection between ground bar butt welds and shell plating, and between bilge keel butt welds and ground bar is to be avoided.

5.6.7 The design of single web bilge keels is to ensure that failure to the web occurs before failure of the ground bar. In general, this may be achieved by ensuring the web thickness of bilge keels does not exceed that of the ground bar.



**Fig. 10.5.5 Bilge keel construction**

5.6.8 The end details of bilge keels and intermittent bilge keels, where adopted, are to be as shown in Fig. 10.5.6.

5.6.9 The ground bar and bilge keel ends are to be tapered or rounded. Where the ends are tapered, the tapers are to be gradual with ratios of at least 3:1, see Figs. 10.5.6(a) and (b). Where the ends are rounded, details are to be as shown in Fig. 10.5.6(c). Cut-outs on the bilge keel web within zone 'A' (see Fig. 10.5.6(b)) are not permitted.

5.6.10 The end of the bilge keel web is to be between 50 mm and 100 mm from the end of the ground bar, see Fig. 10.5.6(a).

5.6.11 An internal transverse support is to be positioned as close as possible to halfway between the end of the bilge keel web and the end of the ground bar, see Fig. 10.5.6(b).

5.6.12 Where an internal longitudinal stiffener is fitted in line with the bilge keel web, the longitudinal stiffener is to extend to at least the nearest transverse member outside zone 'A', see Fig. 10.5.6(b). In this case, the requirement of 5.6.10 does not apply.

5.6.13 For ships over 65 m in length, holes are to be drilled in the bilge keel butt welds. The size and position of these holes are to be as illustrated in Fig. 10.5.5. Where the butt weld has been subject to non-destructive examination the stop hole may be omitted.

5.6.14 Bilge keels of a different design from that shown in Fig. 10.5.5 and Fig. 10.5.6 will be specially considered.

5.6.15 Within zone 'B' (see Fig. 10.5.6(a)) welds at the end of the ground bar and bilge plating, and at the end of the bilge keel web and ground bar, are to have weld factors of 0,44 and 0,34 respectively. These welds are to be ground and to blend smoothly with the base materials.




Fig. 10.5.6 Bilge keel end design

5.6.16 A plan of the bilge keels is to be submitted for approval of material grades, welded connections and detail design.

## **5.7 Other fittings and attachments**

5.7.1 Gutterway bars at the upper deck are to be so arranged that the effect of main hull stresses on them is minimized.

5.7.2 Minor attachments, such as pipe clips, staging lugs and supports, are generally to be kept clear of toes of end brackets, corners of openings and similar areas of high stress. Where connected to asymmetrical stiffeners, the attachments may be in line with the web providing the fillet weld leg length is clear of the offset face plate or flange edge. Where this cannot be achieved the attachments are to be connected to the web, and in the case of flanged stiffeners they are to be kept at least 25 mm clear of the flange edge. On symmetrical stiffeners, they may be connected to the web or to the centreline of the face plate in line with the web.

5.7.3 Where necessary in the construction of the ship, lifting lugs may be welded to the hull plating but they are not to be slotted through. Where they are subsequently removed, this is to be done by flame or mechanical cutting close to the plate surface, and the remaining material and welding ground off. After removal the area is to be carefully examined to ensure freedom from cracks or other defects in the plate surface.

---

## **■ Section 6 Access arrangements for oil tankers and bulk carriers**

### **6.1 Application**

6.1.1 Access arrangements are to be provided as required by SOLAS.

### **6.2 Information for approval**

6.2.1 Details of the attachment of the access arrangements to the ship's structure are to be submitted for approval and suitable designs are to take into account proper location, strength, detail and reinforcement of all attachments to hull structural members.

---



# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

### Section 1

#### Section

- 1 **General**
- 2 **Steel hatch covers**
- 3 **Hatch beams and wood covers**
- 4 **Hatch cover securing arrangements and tarpaulins**
- 5 **Hatch coamings**
- 6 **Miscellaneous openings**
- 7 **Tanker access arrangements and closing appliances**
- 8 **Side and stern doors and other shell openings**
- 9 **Watertight doors in bulkheads below the freeboard deck**
- 10 **External openings and openings in watertight bulkheads and internal decks in cargo ships**

Type 'B-100' } Cargo ships of type 'B' with reduced free-boards on account of their ability to survive a stipulated damage.  
 Type 'B-60' }  
 Type 'B +' } Cargo ships with increased freeboard on account of hatch cover arrangements.

1.1.5 The type of hatch covers on the weather decks of the basic ship types defined in 1.1.4 are detailed below and may be used in the types of ships as indicated in Table 11.1.1:

- (a) Steel plated cargo hatch covers stiffened by webs or stiffeners and secured by clamping devices. Weathertightness to be achieved by means of gaskets. Hatch covers used for holds containing liquid cargoes are included in this category.
- (b) Steel plated cargo hatch pontoon covers having interior webs and stiffeners extending for the full width of the hatchway. Weathertightness to be obtained by tarpaulins.
- (c) Hatch covers of wood or steel used in conjunction with portable beams. Weathertightness to be obtained by tarpaulins.
- (d) Access hatch covers for cargo oil tanks and adjacent spaces. The hatch covers are to be of steel and gasketed.
- (e) Access hatch covers other than (d). For Type 'A', Type 'B-100' and Type 'B-60' ships, the covers are to be of steel, and weathertightness is to be achieved by means of gaskets.

### Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies to all ship types detailed in Part 4 with the exception of Sections 1 to 5 which are not applicable to Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2,2.3). Additional provisions regarding access arrangements for oil tankers and chemical carriers are contained in Pt 4, Ch 9, Ch 10 and the *Rules for Liquid Chemicals in Bulk*, respectively.

1.1.2 Requirements are given for steel and wooden hatch covers, securing arrangements, tarpaulins, coamings and side shell doors for main openings, also closing arrangements for other miscellaneous openings.

1.1.3 Where relevant, the contents of this Chapter conform with the requirements of the *International Convention on Load Lines, 1966*. Attention should, however, be given to any additional Statutory Requirements of the National Authority of the country in which the ship is to be registered and to the relevant regulations of the *International Convention for the Safety of Life at Sea, 1974* and applicable amendments.

1.1.4 For the purpose of this Chapter the basic types of ships are those defined in the *International Convention on Load Lines, 1966*, namely:

- Type 'A' Ships designed solely for the carriage of liquid cargoes.  
 Type 'B' Cargo ships, other than Type 'A', with steel weathertight hatch covers.

**Table 11.1.1 Covers associated with ship types**

Type of cover	Type of ship				
	'A'	'B-100'	'B-60'	'B'	'B +'
(a)	–	X	X	X	X
(b)	–	–	–	X	X
(c)	–	–	–	–	X
(d)	X	X	X	Not applicable	
(e)	X	X	X	X	X

1.1.6 The positions of hatches on weather decks are defined in Ch 1,6.5.

1.1.7 'Tween deck hatch covers may be any of the types defined in 1.1.5, but need not be weathertight unless fitted to deep tanks or water ballast holds or compartments, in which case the covers are to be of type (a) and oiltight or watertight as appropriate.

1.1.8 The scantlings specified in the following Sections are applicable to covers of mild steel or higher tensile steel. Where other materials are used, equivalent scantlings are to be provided. The scantlings apply basically to rectangular covers, with the stiffening members arranged primarily in one direction and carrying a uniformly distributed load. The covers are assumed to be simply supported. Where covers are stiffened by a grillage formation, and also where point loads are applied to any type of cover, the scantlings are to be determined from direct calculations, see 2.2.4.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 1

1.1.9 In the case of flush hatch covers or of covers on coamings of lesser height than required by 5.1.1, their scantlings, the securing and sealing arrangements and the drainage of gutterways will be specially considered.

1.1.10 The scantlings of hatch covers need to be increased only if the maximum loading exceeds 17,17 kN/m<sup>2</sup>. The scantlings of the surrounding deck structure are to be sufficient to support this loading. Heavier loading may be permitted only if the scantlings of the cover are increased in direct proportion to the load. The deck structure is to be capable of withstanding this increased loading.

1.1.11 Where timber cargo is to be carried on the hatch covers the requirements of Ch 9,2.7 are to be satisfied.

1.1.12 Where hatchways are trunked through one or more 'tween decks, and hatchway beams and covers are dispensed with at the intermediate decks, the hatchway beams, coamings and covers immediately below the trunk are to be adequately strengthened. Plans are to be submitted for approval.

1.1.13 The net plate thickness,  $t_{net}$ , is the calculated minimum thickness of the plating and stiffeners. The required thickness is the net thickness plus a corrosion addition,  $t_c$ , given in Table 11.1.2.

**Table 11.1.2 Corrosion addition  $t_c$**

Hatch cover type	$t_c$ , in mm
(a) Single skin	2,0
(b) Pontoon (double skin)	
(i) for the top and bottom plating	2,0
(ii) for the internal structures	1,5
For coaming and coaming stays	1,5

1.1.14 For ships with cargo environments giving permanently reduced corrosion characteristics and with increased protection of hatch covers from excessive freeboard height above the freeboard, or virtual freeboard deck, the corrosion margin may be specially considered.

### 1.2 Symbols

1.2.1 The minimum design pressure,  $p$ , in kN/m<sup>2</sup>, acting on the hatch covers is given by:

(a) For ships of length 100 m or greater, for hatchways located at the freeboard deck,  $p$  is to be the greater of 34,3 or the following:

$$p = 34,3 + \frac{p_{FP} - 34,3}{0,25} \left( 0,25 - \frac{x}{L_L} \right) \text{ kN/m}^2$$

Where a hatchway is located in the forward quarter of the Load Line length and at least one standard superstructure height higher than the freeboard deck, the pressure  $p$  may be 34,3 kN/m<sup>2</sup>. Position 2 hatch covers are to be designed with  $p$  taken as 25,5 kN/m<sup>2</sup>.

(b) For ships less than 100 m in length, for hatchways located at the freeboard deck,  $p$  is to be the greater of  $0,195L_L + 14,9$  or the following:

$$p = 15,8 + \frac{L_L}{3} \left( 1 - \frac{5}{3} \frac{x}{L} \right) - 3,6 \frac{x}{L_L} \text{ kN/m}^2$$

Where two or more panels are connected by hinges, each individual panel is to be considered separately. Position 2 hatch covers are to be designed with  $p$  taken as 14,7 kN/m<sup>2</sup> where  $L_L$  is 24 m and  $p$  taken as 25,5 kN/m<sup>2</sup> where  $L_L$  is 100 m; intermediate values are to be obtained by linear interpolation.

Where

$p_{FP}$  = pressure at the forward perpendicular.

$$= 49,1 + (L_L - 100) a$$

$a$  = 0,0726 for type B freeboard ships

= 0,356 for ships with reduced freeboard

$L_L$  = freeboard length, in metres, as defined in the Load Lines Conventions, to be taken not greater than 340 m

$x$  = distance, in metres, of the mid length of the hatch cover under examination from the forward end of  $L_L$ .

(c) For weather deck covers for holds which may be flooded and used as ballast tanks and holds in OBO, ore or oil and similar types of ship, the pressure for the internal load is to be taken as that corresponding to the ship heeled to 25° with the liquid level in the hold intersecting the hatch cover top line at the centreline of the ship.

The pressure  $p$ , in kN/m<sup>2</sup> for the member and position under consideration is not to be less than  $4,14Y_s$  where  $Y_s$  = is to be taken as the distance from ship centreline to the edge, stiffener, or primary member under consideration, in metres.

In way of holds for oil cargo, a load equivalent to the inert gas pressure is to be applied over the full breadth of the cover and added to the load corresponding to the liquid pressure.

The above pressures are to be applied in conjunction with a stowage rate of 0,975 m<sup>3</sup>/tonne.

However, where the rolling angle has been determined by direct calculations, the load may be derived accordingly, but is not to be less than that required in (a).

(d) In 'tween decks:

$p$  = is to be taken as the 'tween deck height, in metres, measured vertically on the centreline of the ship from 'tween deck to underside of hatch cover stiffeners on deck above, multiplied by a factor of 7,06

For specified rates of loading in excess of 1,39 m<sup>3</sup>/tonne, an equivalent  $p$  is to be used. In accommodation spaces,  $p$  is to be taken as 12,7 kN/m<sup>2</sup>.



# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 1 & 2

1.2.2 The following symbols and definitions, in addition to those given in 1.2.1, are applicable to this Chapter, unless otherwise stated:

- (a)  $L, L_L$  as defined in Ch 1,6.1.
- (b) The following definitions apply to webs or stiffeners with attached plating, or portable beams:
  - $b$  = length of panel (longer panel dimension), in mm, in transverse direction, see Fig. 11.1.1
  - $d_w$  = overall depth at the supports, measured as shown in Fig. 11.1.2, but is to be not less than 150 mm, see also definition of  $l_1$
  - $k$  = higher tensile steel factor, see Ch 2,1.2
  - $l_0$  = unsupported span, in metres, measured as shown in Fig. 11.1.2
  - $l_1$  = proportion of the span, in metres, measured as shown in Fig. 11.1.2. The depth and face area over the remainder of the span is assumed to be constant
  - $s$  = spacing of webs and stiffeners (shorter panel dimension), in mm
  - $t$  = thickness of plating, in mm
  - $H_c$  = height of hatch coaming, in mm
  - $\sigma_{ac}$  = corrected critical buckling stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $\sigma_b$  = the compressive bending stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>), in the steel cover plating, calculated by taking the cover as a loaded beam simply supported at its ends
  - $\sigma_c$  = critical buckling stress of panel, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $\sigma_o$  = yield stress of cover plating material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $\sigma_u$  = minimum ultimate tensile strength, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).
  - $h_H$  = head, as defined in Ch 3,5.1.



## Section 2 Steel hatch covers

### 2.1 Plating

2.1.1 The thickness of the plating of steel hatch covers is to be not less than required by Table 11.2.1.

### 2.2 Webs and stiffeners

2.2.1 The scantlings of steel cover primary and secondary webs or stiffeners are to be not less than would be required to satisfy the requirements of Table 11.2.2.

2.2.2 As an alternative to 2.2.1, scantlings may be determined by direct calculations, which are to be submitted for approval. In no case are the stresses and deflections given in Table 11.2.3 to be exceeded.

2.2.3 Where hatch covers are subjected to point loads, such as from containers, the requirements of Pt 4, Ch 8,11 are also to be complied with.

2.2.4 Covers having primary stiffeners in two directions will be considered using direct calculations in conjunction with the requirements of Table 11.2.3. For weather deck covers for holds which may be flooded and used as ballast tanks, and holds in OBO, ore or oil and similar types of ship the loading is to be as required by 1.2.1(b) but is not to be less than 1.2.1(a).

2.2.5 On ships of length  $L_L$  greater than 100 m, hatch covers fitted on top of a second, or virtual second, tier superstructure (as defined in Ch 8,1.3) or above, may be permitted a reduction in design pressure. The following minimum scantlings are to be complied with:

- (a) Abaft  $0,25L_L$  the cover plate thickness may be  $0,0091s$  but not less than 6 mm.
- (b) The value of  $h_H$  used in 1.2.1 may be  $25,5 \text{ kN/m}^2$  forward of  $0,25L_L$ , and  $20,6 \text{ kN/m}^2$  abaft of  $0,25L_L$ .

2.2.6 For the omission of gaskets or hatch covers in ships carrying container cargoes, see Pt 4, Ch 8,11.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 2

**Table 11.2.1 Steel hatch cover plating**

Symbols	Position of cover	Thickness of cover
$k, s, b$ and $t$ as defined in 1.2 For $h_H \leq 3,5$ m, $K_C = 1$ $p \leq 34,3$ kN/m <sup>2</sup> , $K_C = 1,116$ For $h_H > 3,5$ m, $K_C = \sqrt[3]{0,286h_H}$ $p > 34,3$ kN/m <sup>2</sup> , $K_C = \sqrt[3]{0,0405p}$ $Y$ = distance from ship centreline to the outboard edge of the plate under consideration, in metres	Steel covers to dry cargo holds	The greater of: (a) $t = 0,01sK_C \sqrt{k}$ mm (b) $t = 6,0$ mm
	OBO, ore or oil or similar types of ships and weather deck openings to holds which may be flooded and used as ballast tanks	The greatest of: (a) $t = (0,01s + 0,5) \sqrt{k}$ mm (b) $t = (0,0025s \sqrt{Y} + 2,5) \sqrt{k}$ mm (c) $t = 7,5$ mm
	*Tween deck covers to deep tanks	Pt 4, Ch 1,9 for plating forming boundaries of tanks
	Covers on decks where wheeled vehicles are used	Ch 9,3 for deck plating where wheeled vehicles are used
	Portable covers	The greater of: (a) $t = 0,01s$ mm (b) $t = 3,5$ mm
	Reduced thicknesses for covers in certain positions	See 2.2.5
Buckling requirements for hatch cover plating		
$\sigma_b, \sigma_c, \sigma_{ac}$ and $\sigma_o$ are defined in 1.2 $\sigma_c = 18,6R_C \left(\frac{t}{b}\right)^2 \times 10^4$ N/mm <sup>2</sup> $\left(\sigma_c = 1,9R_C \left(\frac{t}{b}\right)^2 \times 10^4$ kgf/mm <sup>2</sup> ) $\sigma_{ac} = \sigma_o \left(1 - \frac{\sigma_o}{4\sigma_c}\right)$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) (a) Where primary bending stress acts on longer panel edge $b$ , see Fig. 11.1.1: $\frac{\sigma_c}{\sigma_b} \left(\text{or } \frac{\sigma_{ac}}{\sigma_b}\right) \geq 1,3$ where $R_C = \left(\frac{s}{b} + \frac{b}{s}\right)^2$ Where primary bending stress acts on shorter panel edge $s$ : $\frac{\sigma_c}{\sigma_b} \left(\text{or } \frac{\sigma_{ac}}{\sigma_b}\right) \geq 1,2$ where $R_C = 4 \left(\frac{b^2}{s^2}\right)$ If $\sigma_c > 0,5 \sigma_o$ then corrected value $\sigma_{ac}$ is used It is recommended that $\left(\frac{b}{s}\right) < 5,0$ (b) Where covers are stiffened in two directions by a grillage formation, buckling checks are to be carried out as per (a) above for bending stresses acting on both the longer and shorter edges of the panel. For the derivation of the section modulus for primary members an effective width of plating to achieve a balanced section is to be adopted. However a greater width of plating in accordance with Ch 3,3.2 may be adopted where this is suitably stiffened in the directions being considered from the buckling aspect.		



# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 2

**Table 11.2.2 Steel hatch cover webs and stiffeners**

Symbols	Position of cover	Type of cover	Requirement (primary stiffening)				
<p><math>I_0</math> and <math>I_1</math> are moments of inertia, in <math>\text{cm}^4</math>, at mid-span and supports, where <math>I_1 &gt; 0,05I_0</math></p> <p><math>l_0</math>, <math>l_1</math> and <math>h_H</math> are defined in 1.2, except that for covers to deep tanks in 'tween decks <math>h_H = 1,67H</math>, where <math>H</math> is half the vertical height from top of the overflow</p> $C_H = 1 + \frac{8\alpha_H^3 (1 - \beta_H)}{0,2 + 3 \sqrt{\beta_H}}$ $K_H = 1 + \frac{3,2\alpha_H - \gamma_H - 0,8}{7,0\gamma_H + 0,4}$ <p>but not less than 1,0. To be specially considered when discontinuities in area of face material occur</p> <p><math>K_1</math> and <math>C_1</math> are given opposite</p> <p><math>Z_0</math> and <math>Z_1</math> are section moduli, in <math>\text{cm}^3</math>, at mid-span and supports</p> $\alpha_H = \frac{l_1}{l_0} \quad \beta_H = \frac{I_1}{I_0} \quad \gamma_H = \frac{Z_1}{Z_0}$ <p>For weather decks:</p> $F = \frac{400 \text{ N/mm}^2 (41 \text{ kgf/mm}^2)}{\text{Minimum ultimate tensile strength for higher tensile steel used in manufacture}}$ <p>For 'tween decks</p> $F = k$ <p><math>k</math> as defined in 1.2.2</p>	Weather decks – Positions 1 and 2	(1) (a) Covers secured by clamping devices (b) Portable covers	$Z_0 = \frac{p s l_0^2 K_H F}{K_1} \text{ cm}^3$ $I_0 = \frac{p s l_0^3 C_H}{C_1} \text{ cm}^4$				
		(2) Covers for holds in OBO, ore or oil or similar types of ships and covers to holds which may be flooded and used as ballast tanks	As for (1) Thickness of webs or stiffeners $>7,5 \text{ mm}$				
		(3) Pontoon covers	As for (1)				
		Cargo 'tween decks	(4) Covers including pontoon covers	As for (1) Covers carrying wheeled vehicles are also to comply with Ch 9,3			
	Secondary panel stiffening						
	The section modulus and moment of inertia are to be derived as for longitudinal primary stiffening, using appropriate span and spacing. Where the ends of the panel stiffeners are effectively bracketed or continuous, these values of modulus and inertia may be reduced respectively by 33 per cent and 80 per cent						
Type of cover		1	2	3	4		
$K_1$		1507	1507	1281	1865		
$C_1$		886	633	696	1108		

**Table 11.2.3 Parameters for direct calculations**

Location	Item	Loading	Permissible bending stress $\text{N/mm}^2$ ( $\text{kgf/mm}^2$ )	Permissible shear stress $\text{N/mm}^2$ ( $\text{kgf/mm}^2$ )	Permissible deflection, metres
Weather deck – Positions 1 and 2, see Note	Steel weather-tight covers	Uniformly distributed (weather load)	$0,8\sigma_0$	$0,46\sigma_0$	$0,0056l_0$
	Steel weather deck covers for holds which may be flooded and used as ballast tanks, and holds in OBO, ore or oil or similar types of ships	Internal loading See 1.2.1(b)	$\frac{117,7}{k} \left( \frac{12,0}{k} \right)$	$\frac{68,7}{k} \left( \frac{7,0}{k} \right)$	$0,0020l_0$
	Pontoon covers	Uniformly distributed (weather load) See Ch 3,5	$0,68\sigma_0$		$0,0044l_0$
Cargo 'tween deck, see Note	Steel covers	Uniformly distributed container or other specified loading	$\frac{117,7}{k} \left( \frac{12,0}{k} \right)$		$0,0035l_0$
NOTE For buckling requirements for hatch cover plating, see Table 11.2.1. Alternatively, the criteria in Pt 4, Ch 7,12 may be applied.					

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 3 & 4

### Section 3 Hatch beams and wood covers

#### 3.1 Portable hatch beams

3.1.1 The section modulus and moment of inertia of portable web plate beams stiffened at their upper and lower edges by continuous flat bars are to satisfy the requirements of 2.2.1 for pontoon covers. Alternatively, direct calculations may be used, provided the requirements of 2.2.2 for pontoon covers are complied with.

3.1.2 The ends of web plates are to be doubled, or inserts fitted for at least 180 mm along length of web.

3.1.3 At beams which carry the ends of wood or steel hatch covers, a vertical 50 mm flat is to be arranged on the upper face plate. The width of bearing surface for hatch covers is to be not less than 65 mm.

3.1.4 Carriers or sockets, or other suitable arrangements, of suitable construction are to provide means for the efficient fitting and securing of portable hatch beams. The width of bearing surface is to be not less than 75 mm.

3.1.5 Sliding hatch beams are to be provided with an efficient device for locking them in their correct fore and aft positions when the hatchway is closed.

#### 3.2 Wood covers

3.2.1 Wood covers are to have a finished thickness of not less than 60 mm in association with an unsupported span of not more than 1,5 m. Where the 'tween deck height as specified in 1.2.1, exceeds 2,6 m, the thickness of the wood covers is to be increased at the rate of 16,5 per cent per metre excess in 'tween deck height.

3.2.2 The ends of all wood hatch covers are to be protected by encircling galvanized steel bands, about 65 mm wide and 33 mm thick, efficiently secured.

### Section 4 Hatch cover securing arrangements and tarpaulins

#### 4.1 Cargo oil tank and adjacent spaces

4.1.1 For access hatchways to cargo oil tanks and adjacent spaces, see Section 7.

#### 4.2 Steel covers – Clamped and gasketed

4.2.1 These requirements, unless stated otherwise, apply to steel hatch covers in Positions 1 and 2 fitted with gaskets and securing devices and situated above dry cargo holds.

4.2.2 Where steel hatch covers are fitted to hatch openings on weather decks, the arrangements are to be such that weathertightness can be maintained.

4.2.3 The weight of the covers and weather loading may be transmitted to the ship's structure by means of continuous steel to steel contact of the cover skirt plate with the ship's structure in association with a maximum bearing pressure of 200 kgf/cm<sup>2</sup>. Alternatively the weight may be transmitted by means of defined bearing pads. For covers loaded by containers or other cargo, the total load together with inertial forces generated by the ship's motion, are to be transmitted by means of defined bearing pads only. The maximum pressure on steel to steel bearing areas is not to exceed 600 kgf/cm<sup>2</sup>. In cases where the pads are constructed of materials other than steel, the maximum bearing pressure should be based on the manufacturer's recommendation.

For hatch cover roll/pitching stoppers intended to prevent horizontal movement of the cover panels, the force components parallel to the cover are to be taken as given in Table 14.8.2 of Ch 14,8:

and the permissible stresses are as follows:

Shear stress	$0,4\sigma_o$
Bending stress plus axial stress	$0,67\sigma_o$
Combined stress	$0,86\sigma_o$

where  $\sigma_o$  is the yield stress of the material.

In addition, the hatch side coamings and stays are to be of sufficient strength to accommodate the transverse inertial forces, see 5.2.12.

4.2.4 The sealing is to be obtained by a continuous gasket of relatively soft elastic material compressed to achieve the necessary weathertightness. Similar sealing is to be arranged between cross-joint elements. Where fitted, compression flat bars or angles are to be well rounded where in contact with the gasket and are to be made of a corrosion-restraint material or suitably protected against corrosion.

4.2.5 Special consideration is to be given to the gasket and securing arrangements in ships with large relative movements between cover and ship structure or between cover elements. The relative horizontal and vertical deflections are to be calculated and submitted with the hatch cover plans. Where applicable, deflections due to thermal effects and internal pressure loads are also to be included.

4.2.6 The suitability of the gasket material and the securing adhesive is the responsibility of the Builder and Owner. When selecting such material, consideration is to be given to its suitability for the environmental conditions likely to be experienced by the ship and its compatibility with the cargo carried. The material and form of gasket selected are to be considered in conjunction with the type of cover, the securing arrangement and the expected relative movement between cover and ship structure. The gasket is to be effectively secured to the cover.

4.2.7 Drainage is to be arranged inside the line of gasket by means of a gutter bar or vertical extension of the hatch side and end coaming. This requirement need not be complied with for special ships carrying container cargoes when the requirements of 2.2.6 are satisfied.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

### Section 4

4.2.8 Where the arrangement includes continuous steel to steel contact between hatch cover and coaming or at cross-joints, drainage on both sides of the gasket is to be provided.

4.2.9 Drain openings are to be arranged at the ends of drain channels and are to be provided with effective means for preventing ingress of water from outside.

The following requirements are to be complied with:

- If manufactured from steel, the minimum drain pipe wall thickness is to be not less than 5,5 mm.
- If not manufactured from steel, details of the drain, including the material specification, method of manufacture and details of any tests carried out, are to be submitted for consideration.
- Where the drains are not provided with an approved automatic means of preventing water entering the hold, the drains are to be capable of being closed by a screw plug or cap which is to be attached by a strong keep chain to the drain.
- The drains are to be securely attached to the hatch coaming and adequately protected if in an exposed position.
- When the drain is fitted to a hold also designed to carry liquids, a shut-off valve is to be incorporated into the assembly.

4.2.10 Panel hatch covers are to be secured by appropriate devices (bolts, wedges or similar) suitably spaced alongside the coamings. The securing devices are not to have a vertical clearance but are to be pre-tensioned when the cover is in the closed position. The devices are also to be arranged in close proximity horizontally to the gasket. Arrangement and spacing are to be determined with due attention to the effectiveness for weathertightness, depending upon the type and the size of the hatch cover, as well as on the stiffness of the cover edges between the securing devices. A minimum of two securing devices for each side of a panel are to be fitted. The securing devices should be arranged as close to the panel corners as is practicable.

4.2.11 Between cover and coaming and at cross-joints, a gasket pressure sufficient to obtain weathertightness is to be maintained by the securing devices. This pressure is to be specified. Securing devices of a design other than rod or bolts will be specially considered, see 4.2.26.

4.2.12 The net sectional area of each securing device is to be not less than:

$$A = \frac{1,4S_1 W_1}{50f} \text{ cm}^2 \left( \frac{1,4S_1 W_1}{5,1f} \text{ cm}^2 \right)$$

where

$$f = \left( \frac{\sigma_c}{235} \right)^e$$

$S_1$  = spacing or securing devices, in metres, not to exceed 6 m

$W_1$  = the gasket loading per unit length, in N/cm (kgf/cm), but not less than 50 N/cm (5,1 kgf/cm)

$\sigma_c$  = specified minimum upper yield stress in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) of the steel used for cleats or securing devices, to be taken not greater than 70 per cent of the ultimate tensile strength

$e$  = 0,75 for  $\sigma_c \geq 235$  (24)

= 1,0 for  $\sigma_c < 235$  (24)

4.2.13 Rods or bolts are to have a net diameter not less than 19 mm for hatchways exceeding 5 m<sup>2</sup> in area.

4.2.14 In order to ensure compression between gasket and compression bar along the full length, the cover edge stiffness is to be examined. The inertia of the cover edge is to be not less than:

$$I_E = 0,6W_1 S_1^4 \text{ cm}^4$$

$$(I_E = 5,89W_1 S_1^4 \text{ cm}^4)$$

where  $W_1$  and  $S_1$  are as defined in 4.2.12.

4.2.15 Securing devices are to be constructed of reliable design and securely attached to the hatchway coamings, decks or covers. Individual securing devices on each cover are to have approximately the same stiffness characteristics.

4.2.16 Where rod cleats are fitted, resilient washers or cushions are to be incorporated.

4.2.17 Where hydraulic cleating is adopted, a positive means is to be provided to ensure that it remains mechanically locked in the closed position in the event of failure of the hydraulic system.

4.2.18 The cross-joints of multi-panel covers are to be arranged with wedges, or locators (male and female) to retain the hatch covers in the correct sealing position, the number and spacing are to be arranged to suit the size and type of cover, gasket arrangements and stiffness of cover edges at cross-joints. Means are also to be provided to prevent excessive relative vertical deflections between loaded and unloaded panels. The arrangement of the gasket retaining angle and the compression bar at the cross-joints is to be such that the gasket compression is maintained between loaded and unloaded panels.

4.2.19 In addition to the requirements given above, all hatch covers, especially those carrying deck cargo are to be effectively secured against horizontal shifting due to the horizontal forces arising from the ship motions.

4.2.20 To prevent damage to hatch covers and ship structure, the location of stoppers is to be compatible with the relative movements between hatch covers and ship structure. The number should be as small as practically possible.

4.2.21 Towards the ends of the ship, vertical acceleration forces may exceed gravity forces. The resulting lifting forces must therefore be also considered when dimensioning the securing devices. Also lifting forces from cargo secured on the hatch cover during rolling are to be taken into account.

4.2.22 Hatch coamings and supporting structure are to be adequately stiffened to accommodate the loading from hatch covers and cargo carried thereon.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 4 & 5

4.2.23 Upon completion of installation of hatch covers, a hose test with a pressure of water as specified in Table 1.8.1 in Chapter 1 is to be carried out. Alternative methods of tightness testing will be considered. This does not apply to covers with reduced securing arrangements as specified in 2.2.6.

4.2.24 All hatch covers are to be tested to prove satisfactory operation.

4.2.25 It is recommended that ships with steel hatch covers are supplied with an operation and maintenance manual including:

- (a) opening and closing instructions;
- (b) maintenance requirements and specifications for packings, securing devices and operating items;
- (c) cleaning instructions for the drainage system;
- (d) corrosion prevention instructions;
- (e) list of spare parts.

4.2.26 The spacing and size of securing devices in hatch covers for holds which may be flooded and used for ballast tanks and holds in OBO, ore or oil and similar types of ship are to correspond to the reaction forces at the cover edges found by calculation, see 2.2.4.

The permissible stresses are not to exceed the following values:

- (a) For rod and bolt type; a tensile stress of  $120f$  N/mm<sup>2</sup> ( $12,2f$  kgf/mm<sup>2</sup>) in way of the thread or in way of the minimum section clear of the thread whichever is the smaller section.
- (b) For devices other than rod and bolt type:
  - $\sigma = 120f$  N/mm<sup>2</sup> ( $12,2f$  kgf/mm<sup>2</sup>)
  - $\sigma_e = 150f$  N/mm<sup>2</sup> ( $15,3f$  kgf/mm<sup>2</sup>)
  - $\tau = 80f$  N/mm<sup>2</sup> ( $8,2f$  kgf/mm<sup>2</sup>)
 where
  - $f$  = material factor as defined in 4.2.12
  - $\sigma$  = bending stress in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $\sigma_e$  = equivalent stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $= \sqrt{(\sigma^2 + 3\tau^2)}$
  - $\tau$  = shear stress in N/mm<sup>2</sup>.

4.2.27 On tank hatch covers in 'tween decks the maximum spacing of cleats is to be 600 mm, but cleats are to be arranged as close to the corners as practicable.

4.2.28 Steel hatch covers with special sealing arrangements, insulated covers, flush hatch covers, and covers having coamings less than required by 5.1, will be specially considered.

4.2.29 For reduced securing arrangements, see 2.2.6.

### 4.3 Portable covers – Tarpaulins and battening devices

4.3.1 At least two layers of tarpaulin in good condition are to be provided for each hatchway in Positions 1 and 2.

4.3.2 Tarpaulins are to be free from jute, waterproof and of ample strength. The minimum mass of the material before treatment is to be 0,65 kg/m<sup>2</sup> if the material is to be tarred, 0,60 kg/m<sup>2</sup> if to be chemically dressed, or 0,55 kg/m<sup>2</sup> if to be dressed with black oil. A certificate to this effect is to be supplied by the makers of the tarpaulins. Special consideration will be given to the use of synthetic materials for tarpaulins.

4.3.3 Cleats are to be of an approved pattern, at least 65 mm wide, with edges so rounded as to minimize damage to the wedges, and are to be spaced not more than 600 mm from centre to centre: the first and last cleats along each side or end are to be not more than 150 mm from the hatch corners. Cleats should be so set as to fit the taper of the wedges.

4.3.4 Battens and wedges shall be efficient and in good condition. Wedges are to be of tough wood, generally not more than 200 mm in length and 50 mm in width. They should have a taper of not more than 1 in 6 and should not be less than 13 mm at the point.

4.3.5 For all hatchways in Positions 1 and 2, steel bars or other equivalent means are to be provided in order to secure each section of hatch covers efficiently and independently after the tarpaulins are battened down. Hatch covers of more than 1,5 m in length are to be secured by at least two such securing appliances. Where hatchway covers extend over intermediate supports, steel bars or their equivalent are to be fitted at each end of each section of covers. At all other hatchways in exposed positions on weather decks, ring bolts or other fittings suitable for lashings are to be provided.

## Section 5 Hatch coamings

### 5.1 General

5.1.1 The height of coamings above the upper surface of the deck, measured above sheathing if fitted, for hatchways closed by portable covers secured weathertight by tarpaulins and battening devices, is to be not less than:

- 600 mm at Position 1,
- 450 mm at Position 2.

5.1.2 The height of coamings of hatchways situated in Positions 1 and 2 closed by steel covers fitted with gaskets and clamping devices is to be as specified in 5.1.1, but may be reduced, or the coamings may be omitted entirely, if the safety of the ship is not thereby impaired in any sea condition. Special attention will be given in such cases to the scantlings of the covers, to their gasketing and securing arrangements and to the drainage of recesses in the deck. The agreement of the National Authority concerned will also be required.

5.1.3 The height of coamings may be required to be increased on ships of Type 'B-100' or Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 5

### 5.2 Construction

5.2.1 Vertical coamings are to have a thickness,  $t$ , in mm not less than the greater of the following:

- (a)  $t = 0,008H_C\sqrt{k} + 1,0$  mm
- (b)  $t = 12,0$  mm where  $L \geq 60$  m, and not less than 9 mm where  $L \leq 30$  m

Intermediate values are to be obtained by interpolation.

In addition, for ships without a forecastle or breakwater the scantlings of the coamings for No. 1 cargo hatchway are not to be less than that required by Ch 8,2 for front bulkhead of deckhouse at that position.

5.2.2 Vertical cargo hatch coamings 600 mm or more in height are to be stiffened on their upper edges by a horizontal bulb flat or equivalent which is to be not less than 180 mm in width for ships where  $L$  is greater than 75 m. Additional support is to be afforded by fitting brackets or stays from the bulb flat to the deck at intervals of not more than 3 m. Each bracket or stay is to be aligned with suitable underdeck stiffeners and is to have a softened nose.

5.2.3 Vertical coamings less than 600 mm in height are to be stiffened at their upper edge by a substantial rolled or fabricated section. Additional support is to be arranged as required by 5.2.2.


5.2.4 Cargo hatchways on other decks, in positions not specified in Ch 1,6.5, are to be suitably framed.

5.2.5 The scantlings and arrangements of vertical cargo hatch coamings more than 900 mm in height and of cargo hatch coamings acting as girders will be specially considered. The coamings are to be arranged with intermediate continuous horizontal stiffeners supported by the bracket stays. In such cases the coamings are to have a thickness as required by 5.2.1 taking  $H_C$ , in mm, as the vertical distance between the continuous longitudinal stiffeners.

5.2.6 Sloped cargo hatch coamings will be specially considered. In general, the sloped coaming arrangement is to be restricted to the hatch side coamings with vertical coamings at the ends. The sloped coaming is not to have a knuckle and the angle to the vertical is not to exceed  $30^\circ$ . The scantlings are to be in accordance with 5.2.1 to 5.2.3 inclusive except that the end coamings are to be increased by 20 per cent for a distance of  $0,15b$  from the side coamings where  $b$  is the width of the hatchway at the deck. Particular care is to be taken where the proposed loadings exceed the loadings given in 1.2.1(a) and Ch 3,5, and where the coamings are not in alignment with the topside tank vertical strake in bulk carriers.

5.2.7 A radiused coaming plate at the corner junction of the longitudinal and transverse cargo hatch coamings is acceptable for ships where  $L \leq 90$  m and the heights of coamings are not in excess of that specified in 5.1.1. Where  $L > 90$  m the corner junctions are to be rectangular and arranged with continuation brackets as required by 5.2.8.

5.2.8 The deck plating is to extend inside the coamings and the side coamings are to be extended in the form of tapered brackets. A recommended arrangement is shown in Fig. 11.5.1. Continuation brackets are also to be arranged athwartships in line with the hatch end coamings and the under deck transverse. In bulk carriers the athwartship brackets, in conjunction with the hatch end beams should be arranged to achieve a satisfactory overlap with the top side tank transverses. In cases where the hatch end beam is formed by the transverse bulkhead top stool the horizontal knuckle of the stool should be arranged well clear of the topside tank knuckle line.



5.2.9 In bulk carriers where the hatch side coaming does not align with the topside tank vertical strake the arrangement and scantlings will be specially considered. In general, suitable underdeck girders and cantilever brackets are to be arranged taking into consideration the hatch cover loading. The under-deck girders are to continue beyond the hatch end for a distance of  $2H_C$  mm. Alternative arrangements incorporating bulkhead top stool structure or cross-deck structure will be considered.

5.2.10 Extension brackets or rails arranged approximately in line with the cargo hatch side coamings and intended for the stowage of steel covers are not to be welded to a deckhouse, masthouse or to each other unless they form part of the longitudinal strength members.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 5 & 6

**5.2.11** The arrangement and scantlings of continuous hatchway coamings on the strength deck will be specially considered. The material of the coamings is to comply with Tables 2.2.1 and 2.2.2 in Chapter 2 and is to be of the same strength level as the deck plating. Discontinuous coamings of length greater than 0,09L are also to satisfy this requirement.

**5.2.12** Where containers are carried on multi-panel hatch covers, the hatch coaming in way of the loaded panel will be required to be reinforced to resist the lateral loads imposed on the coaming due to rolling of the ship. Thrust blocks are to be fitted on the coaming rest bar to prevent the covers from moving. Where one-piece hatch covers are fitted with locating devices, the coamings are to be reinforced in way of the locators.

**5.2.13** Cut outs in the top of hatch coamings are to be avoided. Where these are necessary for the securing devices they are to be circular or elliptical in shape. Also any local reinforcements should be given a tapered transition in the longitudinal direction with a taper the rate of which should not exceed 1 in 3. Cut-outs and drain holes are to be avoided in the hatch side coaming continuation brackets. Where these are necessary the size, shape and position will be specially considered.

### 5.3 Rest bars in hatchways

**5.3.1** Rest bars are to provide at least 65 mm bearing surface and are to be aligned if required to suit the slope of the hatches.

### 5.4 Loading in excess of Rule requirements

**5.4.1** For weather deck hatch side coamings forming part of a hatch side girder subjected to loading exceeding that defined in 1.2.1, see Pt 4, Ch 1,4.

## Section 6 Miscellaneous openings

### 6.1 Small hatchways on exposed decks

**6.1.1** Hatches which:

- are designed for access to spaces below the deck;
- are capable of being closed weathertight or watertight, as applicable;
- have an opening 2,5 m<sup>2</sup> or less;
- are located on the exposed deck over the forward 0,25L of the ship's rule length;
- are on a ship of sea-going service of length 80 m or more, where the height of the exposed deck in way of the hatch is less than 0,1L or 22 m above the summer load waterline, whichever is the lesser;

are to comply with the requirements of 6.6. All other small hatchways or access openings in the positions defined in 1.1.6 are to comply with the following requirements.

**6.1.2** The number and size of hatchways and other access openings are to be kept to the minimum consistent with the satisfactory operation of the ship.

**6.1.3** The height of coamings is to be in accordance with 5.1.1. Lower heights may be considered in relation to operational requirements and the nature of the spaces to which access is given.

**6.1.4** Rope hatches may be accepted with reduced coamings, but generally not less than 380 mm, provided they are well secured and closed before the ship leaves port. A suitable notice is to be displayed at the hatch stating that it is to be closed whilst the ship is at sea.

**6.1.5** The thickness of the coamings is to be not less than the Rule minimum thickness for the deck inside line of openings for that position, or 11 mm, whichever is the lesser. Stiffening of the coaming is to be appropriate to its length and height.

**6.1.6** Hatch covers are to be of steel, weathertight and generally hinged. The means of securing are to be such that weathertightness can be maintained in any sea condition. Where toggles are fitted, their diameter and spacing are to be in accordance with ISO standard or equivalent.

**6.1.7** Hinges are not to be used as securing devices unless specially considered.

**6.1.8** The thickness of covers is to be not less than the Rule minimum thickness inside the line of openings for the deck at that point, or 8 mm, whichever is the lesser.

**6.1.9** The covers are to be adequately stiffened.

**6.1.10** Escape hatches are to be capable of being opened from either side.

**6.1.11** Small hatches, including escape hatches, are to be situated clear of cargo containment areas, particularly in the case of offshore supply ships.

**6.1.12** Where portable plates are required in decks for unshipping machinery, or for other similar reasons, they may be accepted provided they are of equivalent strength to the unpierced deck and are secured by gaskets and closely spaced bolts at a pitch not exceeding five diameters.

**6.1.13** Satisfactory means are to be provided to prevent inadvertent flooding of chain lockers. See Ch 13,7.8.5 and 7.8.7.

**6.1.14** Where permitted by the National Authority, access hatch coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable with a minimum height of 230 mm.

### 6.2 Manholes and flush scuttles

**6.2.1** Manholes and flush scuttles fitted in Positions 1 and 2, or within superstructures other than enclosed superstructures, are to be closed by substantial covers capable of being made watertight. Unless secured by closely spaced bolts, the covers are to be permanently attached.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

### Section 6

#### 6.3 Hatchways within enclosed superstructures or 'tween decks

6.3.1 The requirements of 6.1 are to be complied with where applicable.

6.3.2 Access hatches within a superstructure or deckhouse in Positions 1 or 2 need not be provided with means for closing if all openings in the surrounding bulkheads have weathertight closing appliances.

#### 6.4 Companionways, doors and accesses on weather decks

6.4.1 Companionways on exposed decks are to be of equivalent construction, weathertightness and strength to a deckhouse in the same position and effectively secured to the deck.

6.4.2 Access openings in:

- (a) bulkheads at ends of enclosed superstructures;
- (b) deckhouses or companionways protecting openings leading into enclosed superstructures or to spaces below the freeboard deck; and
- (c) deckhouse on a deckhouse protecting an opening leading to a space below the freeboard deck;

are to be fitted with doors of steel or other equivalent material, permanently and strongly attached to the bulkhead and framed, stiffened and fitted so that the whole structure is of equivalent strength to the unpierced bulkhead, and weathertight when closed. The doors are to be gasketed and secured weathertight by means of clamping devices or equivalent arrangements, permanently attached to the bulkhead or to the door. Doors are generally to open outwards and are to be capable of being operated and secured from both sides. The sill heights are to be as required by 6.4.5. See also Section 7 and Pt 4, Ch 9,13 and Ch 11,1 and the *Rules for Liquid Chemicals in Bulk*, Chapter 3 concerning access openings in tankers, chemical tankers and ore or oil ships. Double doors are to be equivalent in strength to the unpierced bulkhead, and in Position 1, a centre pillar is to be provided which may be portable.

6.4.3 Elsewhere doors may be of hardwood not less than 50 mm in thickness or of equivalent material and strength.

6.4.4 Fixed lights in doors in Positions 1 and 2 are to comply with the requirements for side scuttles as given in 6.5.1 and 6.5.2. Hinged steel deadlights may be external.

6.4.5 The height of doorway sills above deck sheathing, if fitted, is to be not less than 600 mm in Position 1, and not less than 380 mm in Position 2.

6.4.6 Where access is provided from the deck above as an alternative to access from the freeboard deck, the height of sill into a bridge or a poop is to be not less than 380 mm. The same requirement applies to deckhouses on the freeboard deck. The sill height for doorways in a forecastle, if protecting a companionway, is to be 600 mm regardless of whether or not access is provided from above. If not protecting a companionway, the sill height may be 380 mm.

6.4.7 When the closing appliances of openings in superstructures and deckhouses do not comply with 6.4.2, interior deck openings are to be treated as if exposed on the weather deck.

6.4.8 Where an access opening, in the top of a deckhouse situated on a raised quarterdeck, gives access below the freeboard deck or to an enclosed superstructure, the closing appliances in the surrounding bulkheads are not required to be gasketed, provided the raised quarterdeck is at least standard height, and the deckhouse is at least standard superstructure height.

6.4.9 The height of door sills may be required to be increased on ships of Type 'A', Type 'B-100' or Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*.

6.4.10 Direct access from the freeboard deck to the machinery space through exposed casings is not permitted on ships of Type 'A', Type 'B-100' or Type 'B-60'. A door complying with 6.4.2 may, however, be fitted in an exposed machinery casing on these ships, provided that it leads to a space or passageway which is of equivalent strength to the casing and is separated from the machinery space by a second weathertight door complying with 6.4.2. The outer and inner weathertight doors are to have sill heights of not less than 600 mm and 230 mm, respectively and the space between is to be adequately drained by means of a screw plug or equivalent.

6.4.11 For a Type 'A' ship with freeboards assigned greater than, or equal to, Type 'B', inner doors are not required for direct access to the engine-room.

6.4.12 If internal access is provided from a wheelhouse in Position 2, or below, to spaces below the weather deck either directly or through other spaces, the opening should be protected by a hinged weathertight cover adequately secured, fitted on a coaming appropriate to its position, or by an equivalent arrangement, and the space adequately drained.

6.4.13 In way of a moonpool, where a working or platform deck is provided below the weather deck, openings in the surrounding bulkheads are to be kept to a minimum. Access or companionway openings are to be provided with weathertight closing appliances as for an exposed superstructure bulkhead, with 600 mm high coamings.

6.4.14 Where portable plates are required in casings for unshipping machinery, or for other similar reasons, they may be accepted provided they are of equivalent strength to the unpierced bulkhead and are secured by gaskets and close spaced bolts at a pitch not exceeding five diameters.

6.4.15 The sill heights of accesses closed by covers which are secured by closely spaced bolts or otherwise kept permanently closed at sea will be specially considered.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 6

6.4.16 Where permitted by the National Authority, companionway coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable with a minimum height of 230 mm. Where the wheelhouse is on the freeboard deck, or located in the forward quarter of the ship's length, with internal access below, a weathertight cover, fitted to a coaming not less than 230 mm high, is to be provided for the access. Alternatively, storm covers are to be provided for windows in exposed positions. The wheelhouse is to be adequately drained.

### 6.5 Side scuttles, windows and skylights

6.5.1 Side scuttles are defined as being round or oval openings with an area not exceeding 0,16 m<sup>2</sup>.

6.5.2 Windows are defined as being rectangular openings generally, and round or oval openings with an area exceeding 0,16 m<sup>2</sup>.

6.5.3 A plan showing the location of side scuttles and windows is to be submitted. Attention is to be given to any relevant Statutory Requirements of the National Authority of the country in which the ship is to be registered.

6.5.4 Side scuttles and windows together with their glasses and deadlights if fitted, are to be of an approved design or in accordance with a recognized National or International Standard, see also Pt 4, Ch 4,6.3 for offshore supply ships.

6.5.5 Side scuttles to spaces below the freeboard deck, or to spaces within the first tier of enclosed superstructures, or to first tier deckhouses on the freeboard deck protecting openings leading below or considered buoyant in stability calculations, are to be fitted with efficient, hinged, inside deadlights and capable of being effectively closed and secured watertight.

6.5.6 Deadlights are to be capable of being closed and secured watertight if fitted below the freeboard deck or weathertight if fitted above.

6.5.7 No side scuttle is to be fitted in such a position that its sill is below a line drawn parallel to the freeboard deck at side and having its lowest point 2,5 per cent of the breadth  $B$  above the load waterline corresponding to the summer freeboard (or timber summer freeboard if assigned), or 500 mm, whichever is the greater distance, see Fig. 11.6.1.

6.5.8 If the required damage stability or floatability calculations indicate that the side scuttles would become immersed at any intermediate stages of flooding or the final equilibrium waterline, these are to be of the non-opening type. Windows are not to be fitted in such locations.

6.5.9 Windows are not to be fitted in machinery space boundaries. However this does not preclude the use of glass in control rooms within the machinery space.

6.5.10 If fitted in a deckhouse in Position 1, windows are to be provided with strong, hinged, steel, weathertight storm covers. However, if there is an opening leading below deck in this deckhouse, this opening is to be treated as being on an exposed deck and is to be protected as required by 6.5.5.

6.5.11 Windows are not to be fitted below the freeboard deck, in first tier end bulkheads or sides of enclosed superstructures, or in first tier deckhouses that are considered buoyant in stability calculations.

6.5.12 Side scuttles and windows at the shell in Position 2, protecting direct access below, are to be provided with strong permanently attached deadlights.

6.5.13 Side scuttles and windows at the shell in Position 2, not protecting direct access below, are to be provided with strong portable steel covers for 50 per cent of each size, with means for securing at each side scuttle and window.

6.5.14 Side scuttles and windows set inboard from the shell in Position 2, protecting direct access below, are either to be provided with strong permanently attached deadlights or, where they are accessible, strong permanently attached external steel storm covers instead of internal deadlights.




Fig. 11.6.1 Side scuttle positioning



# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 6

6.5.15 Side scuttles and windows set inboard from the shell in Position 2, not protecting direct access below, do not require deadlights or storm covers.

6.5.16 In Position 2, cabin bulkheads and doors are considered effective between side scuttles or windows and access below.

6.5.17 Windows in the shell above Position 2 are to be provided with strong portable internal storm covers for 25 per cent of each size of window, with means of securing being provided at each window.

6.5.18 Where windows are permitted in an exposed bulkhead on the weather deck in the forward 0,25 $L_L$ , strong external storm covers which may be portable and stored adjacent are to be provided.

6.5.19 Where the wheelhouse is in Position 2, in lieu of storm covers being provided for the wheelhouse windows, a weathertight cover, fitted to a coaming of not less than 230 mm in height around the internal stairway opening within the wheelhouse, may be accepted. If this arrangement is accepted, adequate means of draining the wheelhouse are to be provided.

6.5.20 If necessary, for practical considerations, the storm covers may be in two parts.

6.5.21 Deckhouses situated on a raised quarter deck may be treated as being in Position 2 as far as the provision of deadlights is concerned, provided the height of the raised quarter deck is equal to, or greater than, the standard height.

6.5.22 Skylights, where fitted, are to be of substantial construction and securely attached to their coamings. The height of the lower edge of opening is to be as required by 5.1.1. The scantlings of the coaming are to be as required by this Section or Section 5, as appropriate. The thickness of glasses in fixed or opening skylights is to be appropriate to their size and position as required for side scuttles or windows. Glasses in any position are to be protected from mechanical damage, and where fitted in Positions 1 or 2 are to be provided with robust deadlights or storm covers permanently attached. Cargo pump room and machinery space skylights are not to contain glass.

6.5.23 Skylights to cargo pump rooms are to be capable of being closed from outside the pump room.

6.5.24 Laminated toughened safety glass may also be used for windows but the total thickness will need to be greater than that required for the equivalent sized window using toughened safety glass. The equivalent thickness of laminated toughened safety glass is to be determined from the following formula:

$$T_{L1}^2 + T_{L2}^2 + \dots T_{Ln}^2 = T_S^2$$

where:

$n$  = number of laminates

$T_L$  = thickness of glass laminate

$T_S$  = thickness of toughened safety glass

6.5.25 Rubber frames are not acceptable for windows in Positions 1 and 2, and are not generally acceptable in any other position in external casings. Any proposals to fit rubber frames are to be submitted for consideration, and are to be acceptable to the administration. The proposed locations, frame dimensions, glass thicknesses and the results of any tests carried out, are to be forwarded.

### 6.6 Small hatchways on exposed fore decks

6.6.1 For the application of the following requirements, see 6.1.1.

6.6.2 The number and size of hatchways and other access openings are to be kept to the minimum consistent with the satisfactory operation of the ship.

6.6.3 The height of coamings is to be in accordance with 5.1.1. Lower heights may be considered in relation to operational requirements and the nature of the spaces to which access is given.

6.6.4 Rope hatches may be accepted with reduced coamings, but generally not less than 380 mm, provided they are well secured and closed before the ship leaves port. A suitable notice is to be displayed at the hatch stating that it is to be closed whilst the ship is at sea.

6.6.5 Where permitted by the National Authority, access hatch coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable with a minimum height of 230 mm.

6.6.6 The thickness of the coamings is to be not less than the Rule minimum thickness for the deck inside line of openings for that position, or 11 mm, whichever is the lesser.

6.6.7 The upper edge of the hatchway coamings is to be suitably reinforced by a horizontal section, normally not more than 170 to 190 mm from the upper edge of the coamings.

6.6.8 Hatches are to be fitted with primary securing devices such that their hatch covers can be secured in place and weather-tight by means of a mechanism employing any one of the following methods:

- (a) Butterfly nuts tightening onto forks (clamps),
- (b) Quick acting cleats, or
- (c) Central locking device.

Emergency escape hatches are excluded from options (a) and (b).

6.6.9 Dogs (twist tightening handles) with wedges are not acceptable as primary securing devices.

6.6.10 Escape hatches are to be capable of being opened from either side.


# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 6

6.6.11 For a primary securing method using butterfly nuts, the forks (clamps) are to be of robust design. They are to be designed to minimize the risk of butterfly nuts being dislodged while in use; by means of curving the forks upward, a raised surface on the free end, or a similar method. The plate thickness of unstiffened steel forks is not to be less than 16 mm. An example arrangement is shown in Fig. 11.6.3.


6.6.12 The hatch cover is to be fitted with a gasket of elastic material. This is to be designed to allow a metal to metal contact at a designed compression and to prevent over compression of the gasket by green sea forces that may cause the securing devices to be loosened or dislodged. The metal-to-metal contacts are to be arranged close to each securing device in accordance with Fig. 11.6.2, and of sufficient capacity to withstand the bearing force.



# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 6



- (Note: Dimensions in millimeters)
1. butterfly nut
  2. bolt
  3. pin
  4. centre of pin
  5. fork (clamp) plate
  6. hatch cover
  7. gasket
  8. hatch coaming
  9. bearing pad welded on the bracket of a toggle bolt for metal to metal contact
  10. stiffener
  11. inner edge stiffener

**Fig. 11.6.3 Example of a primary securing method**

6.6.13 The primary securing method is to be designed and manufactured such that the designed compression pressure can be achieved by one person without the need of any tools.

6.6.14 For small rectangular steel hatch covers, the plate thickness, stiffener arrangement and scantlings are to be in accordance with Table 11.6.1 and Fig. 11.6.2. Stiffeners, where fitted, are to be aligned with the metal-to-metal contact points required in 6.6.11, see Fig. 11.6.2. Primary stiffeners are to be continuous. All stiffeners are to be welded to the inner edge stiffener, see Fig. 11.6.3.

6.6.15 For hatch covers constructed of materials other than steel, the required scantlings are to provide equivalent strength.

**Table 11.6.1 Scantlings for small steel hatch covers on exposed deck**

Nominal size (mm x mm)	Cover plate thickness (mm)	Primary stiffeners	Secondary stiffeners
		Flat bar (mm x mm); number	
630 x 630	8	—	—
630 x 830	8	100 x 8;1	—
830 x 630	8	100 x 8;1	—
830 x 830	8	100 x 10;1	—
1030 x 1030	8	120 x 12;1	80 x 8;2
1330 x 1330	8	150 x 12;2	100 x 10;2

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 6 & 7

6.6.16 For small hatch covers of circular or similar shape, the cover plate thickness and reinforcement are to be of equivalent strength to that of the small rectangular steel hatch covers described in 2.2.1.

6.6.17 For hatch covers located on the deck forward of the fore-most cargo hatch, the hinges are to be fitted such that the predominant direction of green sea will cause the cover to close. The hinges are normally to be located on the fore edge.

6.6.18 On small hatches located between the main hatches, for example between Nos. 1 and 2, the hinges are to be placed on the fore edge or outboard edge, whichever is practicable for protection from green water in beam sea and bow quartering conditions.

6.6.19 Hatches, excluding emergency escape hatches, are to be fitted with an independent secondary securing device, e.g. by means of a sliding bolt, a hasp or a backing bar of slack fit, which is capable of keeping the hatch cover in place, even in the event that the primary securing device became loosened or dislodged. It is to be fitted on the side opposite to the hatch cover hinges.

6.6.20 Small hatches, including escape hatches, are to be situated clear of cargo containment areas, particularly in the case of offshore supply ships.

6.6.21 Where portable plates are required in decks for unshipping machinery, or for other similar reasons, they may be accepted provided they are of equivalent strength to the unpierced deck and are secured by gaskets and closely spaced bolts at a pitch not exceeding five diameters.

6.6.22 Satisfactory means are to be provided to prevent inadvertent flooding of chain lockers, see Ch 13, 7.8.5 and 7.8.7.

## Section 7 Tanker access arrangements and closing appliances

### 7.1 Materials

7.1.1 Covers for access hatches, tank cleaning and other openings to cargo tanks and adjacent spaces are to be manufactured from mild steel complying with the Rules for Materials (Part 2).

7.1.2 Consideration will be given to the use of bronze, brass or other materials; however, aluminium alloy is not to be used for the covers of any openings to tanks.

7.1.3 Synthetic materials will be considered, taking into account their fire resistance and physical and chemical properties in relation to the intended operating conditions. Details of the properties of the material, the design of the cover and the method of manufacture are to be submitted for approval.

7.1.4 The hatch cover packing material is to be compatible with the cargoes to be carried and is to be efficiently held in place.

### 7.2 Cargo tank access hatchways

7.2.1 Attention is drawn to IMO Resolutions concerning safe access to, and working in, large tanks.

7.2.2 Oiltight hatchways are to be kept to the minimum size required to provide reasonable access and ventilation. Where tanks are large or subdivided by wash bulkheads, additional hatchways may be required. In determining the size and location of hatchways, consideration should be given to the handling of materials and staging for maintenance in the tank.

7.2.3 The size and location of hatchways should also take into account access for personnel wearing breathing apparatus, and removal of injured personnel (possibly on a stretcher) from the bottom of the tank.

7.2.4 The height of hatch coaming is to be not less than 600 mm, measured above the upper surface of the freeboard deck, unless a lower height is permitted by the Administration of the country in which the ship is to be registered.

7.2.5 Taking account of sheer and camber, the height of any cargo tank hatch coaming is to be such as to ensure that the top of the hatch coaming is above the highest point of the tank over which it is fitted.

7.2.6 The height of the coaming may be required to be increased if this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*.

7.2.7 The thickness of the coaming plate is to be not less than 10 mm, but may be required to be increased, and edge stiffening fitted, where the coaming height exceeds 600 mm.

7.2.8 Unstiffened plate covers are to be not less than 12,5 mm in thickness, but if the area of the cover exceeds 1,2 m<sup>2</sup> this thickness may be required to be increased or stiffening fitted.

7.2.9 Unstiffened covers are to be secured by fastenings spaced not more than 600 mm apart on circular hatchways. On rectangular hatchways the spacing of fastenings is generally not to exceed 450 mm, and the distance between hatch corners and adjacent fastenings is to be not more than 230 mm.

7.2.10 The arrangement of fastenings on stiffened hatchway covers and covers of special design will be specially considered.

7.2.11 Where the cover is hinged, adequate stiffening of the coaming and cover in way of the hinge is to be provided. In general, hinges are not to be used as securing devices for the cover.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 7 & 8

### 7.3 Enlarged cargo tank access openings

7.3.1 Proposals to fit enlarged cargo tank accesses closed by bolted plate covers will be considered. Such openings may be of extended dimensions for ease of access and evacuation of personnel, see 7.2.3, and may incorporate a smaller access hatch for normal use constructed as required by 7.2.

7.3.2 The plate cover is to be not less than 15 mm in thickness and is to be secured by closely spaced studs to a ring of suitable dimensions, welded to the deck. The studs are not to penetrate the deck plating.

### 7.4 Miscellaneous openings

7.4.1 Small openings for tank cleaning, ullage and similar purposes may be closed by flush covers which are to be not less than 12,5 mm in thickness and secured by studs not more than 100 mm apart. Studs are to be arranged in a ring of suitable width and thickness attached to the deck, and are not to penetrate the deck plating.

7.4.2 Small diameter holes provided for staging wires are to be closed by plugs of an approved pattern. The plugs are to be provided with a thick washer of suitable material which is also compatible with the intended cargoes. Spare plugs equal to at least 10 per cent of the number of holes are to be provided and maintained on board, see *also* Pt 4, Ch 9,4. If these openings are threaded they are to be protected while in use with a protective sleeve of suitable material.

### 7.5 Access to spaces other than cargo tanks

7.5.1 Access to clean ballast or dry tanks and to cofferdams may be either by access hatch or by manhole generally complying with the preceding requirements.

### 7.6 Equivalentents

7.6.1 Alternative access cover designs and securing arrangements will be considered on the basis of equivalence to the above requirements and taking into account any relevant National Requirements.

### 7.7 Other openings

7.7.1 For access to structure within cargo tanks, see Pt 4, Ch 9,13.

## Section 8 Side and stern doors and other shell openings

### 8.1 Symbols

- 8.1.1 The symbols used in this Section are defined as follows:
- $d$  = distance between closing devices, in metres
  - $k$  = material factor, see Ch 2,1.2, but is not to be taken less than 0,72 unless demonstrated otherwise by a direct strength analysis with regard to relevant modes of failure
  - $I$  = moment of inertia, in  $\text{cm}^4$ , of the stiffener or girder, in association with an effective width of attached plating determined in accordance with Ch 3,3
  - $\sigma$  = bending stress, in  $\text{N/mm}^2$  ( $\text{kgf/mm}^2$ )
  - $\sigma_e$  = equivalent stress, in  $\text{N/mm}^2$  ( $\text{kgf/mm}^2$ )  

$$= \sqrt{(\sigma^2 + 3\tau^2)}$$
  - $\sigma_0$  = minimum yield stress of the bearing material, in  $\text{N/mm}^2$  ( $\text{kgf/mm}^2$ )
  - $\tau$  = shear stress, in  $\text{N/mm}^2$  ( $\text{kgf/mm}^2$ ).

### 8.2 General

8.2.1 These requirements cover cargo and service doors in the ship side (abaft the collision bulkhead) and stern area, below the freeboard deck and in enclosed superstructures.

8.2.2 For the requirements of bow doors, see Pt 4, Ch 2,8.

8.2.3 Side and stern doors are to be so fitted as to ensure tightness and structural integrity commensurate with their location and the surrounding structure, see *also* Ch 1,6.3.2 and 6.4.2.

8.2.4 In general, and for passenger ships in particular, the lower edge of door openings is not to be below a line drawn parallel to the freeboard deck at side, which has at its lowest point at least 230 mm above the upper edge of the uppermost Load Line.

8.2.5 When the lower edge is below the line specified in 8.2.4, the arrangement will be specially considered. Special consideration is to be given to preventing the spread of leakage water over the deck. The reference to the uppermost Load Line is to be taken as the tropical fresh waterline or, if timber freeboards are assigned, the timber tropical fresh waterline.

8.2.6 Doors are generally to be arranged to open outwards, however inward opening doors will be considered provided these satisfy the requirements of 8.2.7.

8.2.7 Inward opening doors situated in the first two 'tween decks above the summer load waterline are to be fitted with a second independent securing device, such as a strongback or equivalent arrangement, capable of providing weathertight integrity. Where the consequences of water ingress due to failure of the door are minimal, such as a small pilot door giving access to a watertight trunk leading to the bulkhead deck, the required enhancements will be specially considered.

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 8

8.2.8 For passenger ships the following are also applicable:

- (a) Gangway, cargo and service ports fitted below the margin line, see Ch 3,4.3, are to satisfy the strength requirements given for side doors in this Section. They are to be effectively closed and secured watertight before the ship leaves port, and are to be kept closed during navigation. Such ports are not to have their lowest point below the deepest subdivision Load Line.
- (b) Where the inboard end of a rubbish chute is below the margin line in a passenger ship, the inboard end cover is to be watertight and, in addition to the discharge flap interlock, a screwdown automatic non-return valve is to be fitted in an easily accessible position above the deepest subdivision. The valve is to be controlled from a position above the bulkhead deck and provided with an open/shut indicator, and kept closed when not in use. A suitable notice is to be displayed at the valve position.

8.2.9 For ships complying with the requirements of this Section, the securing, supporting and locking devices are defined as follows:

- (a) A securing device is used to keep the door closed by preventing it from rotating about its hinges or other pivoted attachments to the ship.
- (b) A supporting device is used to transmit external and internal loads from the door to a securing device and from the securing device to the ship's structure, or a device other than a securing device, such as a hinge, stopper or other fixed device, that transmits loads from the door to the ship's structure.
- (c) A locking device locks a securing device in the closed position.

8.2.10 Ro-ro cargo spaces are spaces not normally subdivided in any way and extending to either a substantial length or the entire length of the ship, in which motor vehicles with fuel in their tanks for their own propulsion and/or goods (packaged or in bulk, in or on rail or road cars, vehicles (including road or rail tankers), trailers, containers, pallets, demountable tanks in or on similar stowage units or other receptacles) can be loaded and unloaded normally in a horizontal direction.

8.2.11 Special category spaces are those enclosed spaces above and below the bulkhead deck, into and from which vehicles can be driven and to which passengers have access, and which may be accommodated on more than one deck where total overall clear height for vehicles does not exceed 10 m.

### 8.3 Scantlings

8.3.1 In general the strength of side and stern doors is to be equivalent to the strength of the surrounding structure.

8.3.2 Door openings in the side shell are to have well rounded corners and adequate compensation is to be arranged with web frames at sides and stringers or equivalent above and below, see Pt 4, Ch 1,5.

8.3.3 Doors are to be adequately stiffened, and means are to be provided to prevent movement of the doors when closed. Adequate strength is to be provided in the connections of the lifting/manoeuvring arms and hinges to the door structure and to the ship structure.

8.3.4 The thickness of the door plating is to be not less than the shell plating calculated with the door stiffener spacing, and in no case to be less than the minimum adjacent shell thickness.

8.3.5 Where stern doors are protected against direct wave impact by a permanent external ramp, the thickness of the stern door plating may be reduced by 20 per cent relative to the requirements of 8.3.4. Those parts of the stern door which are not protected by the ramp are to have the thickness of plating in full compliance with 8.3.4.

8.3.6 Where higher tensile steel is proposed, the plating thickness required in 8.3.4 and 8.3.5 may be reduced by  $\sqrt{k}$ .

8.3.7 The section modulus of horizontal or vertical stiffeners is to be not less than required for the adjacent shell framing using the actual stiffener spacing. Consideration is to be given, where necessary, to differences in fixity between ship's frames and door stiffeners.

8.3.8 Where necessary, door secondary stiffeners are to be supported by primary members constituting the main stiffening elements of the door.

8.3.9 The scantlings of such primary members are to be based on direct strength calculations. Normally, formulae for simple beam theory may be applied to determine the bending stress. Members are to be considered to have simply supported end connections. The design load is the uniformly distributed external sea pressure,  $p_e$ , as defined in 8.8.1. For minimum scantlings,  $p_e$  is to be taken as 25 kN/m<sup>2</sup> (2,55 tonne-f/m<sup>2</sup>) and the permissible stresses as follows:

$$\tau = \frac{80}{k} \text{ N/mm}^2 \left( \frac{8,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma = \frac{120}{k} \text{ N/mm}^2 \left( \frac{12,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma_e = \frac{150}{k} \text{ N/mm}^2 \left( \frac{15,3}{k} \text{ kgf/mm}^2 \right)$$

8.3.10 The webs of primary members are to be adequately stiffened, preferably in a direction perpendicular to the shell plating.

8.3.11 The stiffness of the edges of the doors and the hull structure in way are to be sufficient to ensure weathertight integrity. Edge stiffeners/girders are to be adequately stiffened against rotation and are to have a moment of inertia not less than:

$$I = 0,8 p_I d^4 \text{ cm}^4$$

$$(I = 8 p_I d^4 \text{ cm}^4)$$

where

$p_I$  = packing line pressure along edges, not to be taken less than 50 N/cm (5,1 kgf/cm).

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Section 8

For edge girders supporting main door girders between securing devices, the moment of inertia is to be increased in relation to the additional force.

8.3.12 The buckling strength of primary members is to be specially considered.

8.3.13 All load transmitting elements in the design load path from door through securing and supporting devices into the ship structure, including welded connections, are to be to the same strength standard as required for the securing and supporting devices. These elements include pins, supporting brackets and back-up brackets. Where cut-outs are made in the supporting structure, the strength and stiffness will be specially considered.

### 8.4 Doors serving as ramps

8.4.1 Where doors also serve as vehicle ramps, the plating and stiffeners are to be not less than required for vehicle decks, see Ch 9,3.

8.4.2 The design of the hinges for these doors should take into account the ship angle of trim or heel which may result in uneven loading of the hinges.

### 8.5 Arrangements for the closing, securing and supporting of doors

8.5.1 Doors are to be fitted with adequate means of closing, securing and support so as to be commensurate with the strength and stiffness of the surrounding structure. The hull supporting structure in way of the doors is to be suitable for the same design loads and design stresses as the securing and supporting devices. Where packing is required, the packing material is to be of comparatively soft type, and the supporting forces are to be carried by the steel structure only. Other types of packing may be considered. Maximum design clearance between securing and supporting devices is generally not to exceed 3 mm.

8.5.2 Devices are to be simple to operate and easily accessible. They are to be of a design approved by Lloyd's Register (hereinafter referred to as 'LR') for the intended purpose.

8.5.3 Securing devices are to be equipped with positive locking arrangements. Arrangements are to be such that the securing devices are retained in the closed position within design limits of inclination, vibration and other motion-induced loads and in the event of loss of any actuating power supply.

8.5.4 Systems for door opening/closing and securing/locking are to be interlocked in such a way that they can only operate in a proper sequence. Hydraulic systems are to comply with Pt 5, Ch 14,9.

8.5.5 Means are to be provided to enable the doors to be mechanically fixed in the open position taking into account the self weight of the door and a minimum wind pressure of 1,5 kN/m<sup>2</sup> (0,153 tonne-f/m<sup>2</sup>) acting on the maximum projected area in the open position.

8.5.6 The spacing for cleats or closing devices should not exceed 2,5 m and there should be cleats or closing devices positioned as close to the corners as practicable. Alternative arrangements for ensuring weathertight sealing will be specially considered.

8.5.7 Control and monitoring arrangements are to comply with the applicable requirements of Pt 6, Ch 2,18.

### 8.6 Design loads

8.6.1 The design force considered for the scantlings of primary members, securing and supporting devices of side shell doors and stern doors are to be taken not less than:

(a) Design forces for securing or supporting devices of doors opening inwards:

External force:

$$P_e = A p_e + P_p \text{ kN (tonne-f)}$$

Internal force:

$$P_i = P_o + 10W \text{ kN}$$

$$(P_i = P_o + 1,02W \text{ tonne-f})$$

(b) Design forces for securing or supporting devices of doors opening outwards:

External force:

$$P_e = A p_e \text{ kN (tonne-f)}$$

Internal force:

$$P_i = P_o + 10W + P_p \text{ kN}$$

$$(P_i = P_o + 1,02W + P_p \text{ tonne-f})$$

(c) Design forces for primary members:

External force:

$$P_e = A p_e \text{ kN (tonne-f)}$$

Internal force:

$$P_i = P_o + 10W \text{ kN}$$

$$(P_i = P_o + 1,02W \text{ tonne-f})$$

whichever is the greater.

The symbols used are defined as follows:

$p_e$  = external sea pressure, in kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>), determined at the centre of gravity of the door opening and is not to be taken less than:

$$\text{for } Z_G < T \quad 10 (T - Z_G) + 25 \text{ kN/m}^2$$

$$(1,02 (T - Z_G) + 2,55 \text{ tonne-f/m}^2)$$

$$\text{for } Z_G \geq T \quad 25 \text{ kN/m}^2$$

$$(2,55 \text{ tonne-f/m}^2)$$

For stern doors of ships fitted with bow doors,  $p_e$  is not to be taken less than:

$$p_{emin} = 0,6\lambda C_H (0,8 + 0,6L^{0,5})^2 \text{ kN/m}^2$$

$$(p_{emin} = 0,061\lambda C_H (0,8 + 0,6L^{0,5})^2 \text{ tonne-f/m}^2)$$

$T$  = summer draught, in metres

$Z_G$  = height of the centre of area of the door, in m, above the base line

$L$  = length of ship, but need not be taken greater than 200 m

$\lambda$  = coefficient depending on the area where the ship is intended to be operated:

= 1 for sea-going ships

= 0,8 for ships operated in coastal waters

= 0,5 for ships operated in sheltered waters

$$C_H = 0,0125L \text{ for } L < 80 \text{ m}$$

$$= 1 \text{ for } L \geq 80 \text{ m}$$

$A$  = area, in m<sup>2</sup>, of the door opening

$W$  = weight of the door, in tonnes

$P_p$  = total packing force, kN (tonne-f). When packing is fitted, the packing line force per unit length is to be specified, normally not to be taken less than:

$$5 \text{ kN/m (0,51 tonne-f/m)}$$

# Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 8 & 9

$P_o$  = the greater of  $P_c$  and 5A kN (0,5A tonne-f)  
 $P_c$  = accidental force, in kN (tonne-f), due to loose cargo, etc., to be uniformly distributed over the area  $A$  and not to be taken less than 300 kN (30,6 tonne-f). For small doors such as bunker doors and pilot doors, the value of  $P_c$  may be taken as zero, provided an additional structure such as an inner ramp is fitted, which is capable of protecting the door from accidental force due to loose cargoes.

### 8.7 Design of securing and supporting devices

8.7.1 Securing devices and supporting devices are to be designed to withstand the forces given above using the following permissible stresses:

$$\tau = \frac{80}{k} \text{ N/mm}^2 \left( \frac{8,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma = \frac{120}{k} \text{ N/mm}^2 \left( \frac{12,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma_e = \frac{150}{k} \text{ N/mm}^2 \left( \frac{15,3}{k} \text{ kgf/mm}^2 \right)$$

The terms 'securing device' and 'supporting device' are defined in Pt 4, Ch 2,8.2.8.

8.7.2 The arrangement of securing and supporting devices is to be such that threaded bolts are not to carry support forces. The maximum tensile stress in way of threads of bolts, not carrying support forces, is not to exceed:

$$\frac{125}{k} \text{ N/mm}^2 \left( \frac{12,7}{k} \text{ kgf/mm}^2 \right)$$

8.7.3 For steel to steel bearings in securing and supporting devices, the normal bearing pressure is not to exceed  $0,8\sigma_o$ , see 8.1.1. For other bearing materials, the permissible bearing pressure is to be determined according to the manufacturer's specification. The normal bearing pressure is to be calculated by dividing the design force by the projected bearing area.

8.7.4 The distribution of the reaction forces acting on the securing and supporting devices may require to be supported by direct calculations taking into account the flexibility of the hull structure and the actual position and stiffness of the supports. Small and/or flexible devices, such as cleats, intended to provide load compression of the packing material are not generally to be included in these calculations.

8.7.5 Only the active supporting and securing devices having an effective stiffness in the relevant direction are to be considered in the calculation of the reaction forces acting on the devices.

8.7.6 The number of securing and supporting devices is generally to be the minimum practicable whilst complying with 8.5.3 and taking account of the available space in the hull for adequate support.

8.7.7 The arrangement of securing devices and supporting devices in way of these securing devices is to be designed with redundancy so that in the event of failure of any single securing or supporting device the remaining devices are capable of withstanding the reaction forces, without exceeding, by more than 20 per cent, the permissible stresses as defined in 8.7.1.

### 8.8 Operating and Maintenance Manual

8.8.1 An Operating and Maintenance Manual for the doors is to be provided on board and is to contain necessary information on:

- (a) main particulars and design drawings,
- (b) service conditions, e.g. service area restrictions, acceptable clearances for supports,
- (c) maintenance and function testing,
- (d) register of inspections, repairs and renewals.

8.8.2 For passenger/vehicle ferries and roll on-roll off cargo ships, see Pt 4, Ch 2,1.1.1, an Operating and Maintenance Manual for the doors, as defined in Pt 4, Ch 2,8.7.1, is to be provided on board instead of that required by 8.8.1.

8.8.3 The Manual is to be submitted for approval, and is to contain a note recommending that recorded inspections of the door supporting and securing devices be carried out by the ship's staff at monthly intervals or following incidents that could result in damage, including heavy weather or contact in the region of the doors. Any damages recorded during such inspections are to be reported to LR.

8.8.4 Documented operating procedures for closing and securing the doors are to be kept on board and posted at an appropriate place.

## Section 9 Watertight doors in bulkheads below the freeboard deck

### 9.1 Openings in bulkheads

9.1.1 Certain openings below the freeboard deck are permitted, but these must be kept to a minimum and provided with means of closing to watertight standards. All such openings are to be to the satisfaction of the Surveyor.

### 9.2 Watertight doors

9.2.1 Watertight doors are to be of equivalent strength to the unpierced bulkhead, efficiently constructed and fitted, and are to be capable of being closed watertight when the ship is listed up to 15° either way. They are to be operated under working conditions and hose tested in place, see Ch 1,8.3.



## Closing Arrangements for Shell, Deck and Bulkheads

## Part 3, Chapter 11

Sections 9 & 10

9.2.2 The scantlings of the watertight doors are to comply with Pt 4, Ch 1,9 using the actual stiffener spacing of the door.

9.2.3 The scantlings of the frames of the watertight doors are to satisfy the requirements of watertight bulkheads given in Table 1.9.1(5) in Pt 4, Ch 1,9 taking into account the arrangement of door stiffeners and securing arrangements.

9.2.4 Watertight doors of the sliding type are to be capable of being operated by efficient hand operated gear, both at the door itself and from an accessible position above the bulkhead deck. Means are to be provided at the remote operating position to indicate whether the door is open or closed. The lead of shafting is to be as direct as possible and the screw is to work in a gunmetal nut, see also Ch 3,4.8.

9.2.5 Hinged watertight doors of approved pattern may be fitted in 'tween decks in approved positions. The hinges of these doors are to be fitted with gunmetal pins or gunmetal bushes.

9.2.6 Means are to be provided on the navigating bridge to indicate whether the watertight doors are open or closed.

9.2.7 In passenger ships the number and construction of the watertight doors in bulkheads will be specially considered. Each watertight door is to be tested, see Table 1.8.1 in Chapter 1. The test may be carried out either before or after the door is fitted. The relevant regulations regarding openings in watertight bulkheads in passenger ships, contained in the *International Convention for the Safety of Life at Sea, 1974* and applicable amendments, are also to be complied with.

---

### ■ Section 10

#### **External openings and openings in watertight bulkheads and internal decks in cargo ships**

##### **10.1 Shell and watertight subdivision openings**

10.1.1 In addition to the requirements of Sections 8 and 9, for cargo ships of 80 m in length and above, the relevant regulations concerning shell and watertight subdivision openings contained in the *International Convention for the Safety of Life at Sea, 1974*, and amendments thereto are also to be complied with.

---



# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

Sections 1 & 2

## Section

- 1 **General**
- 2 **Ventilators**
- 3 **Air and sounding pipes**
- 4 **Scuppers and sanitary discharges**
- 5 **Air pipes, ventilator pipes and their securing devices located on the exposed fore deck**

## Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to all ship types detailed in Part 4, and provides requirements for ventilators, air and sounding pipes and overboard discharges.

1.1.2 The requirements conform, where relevant, with those of the *International Convention on Load Lines, 1966*. Reference should also be made to any additional requirements of the National Authority of the country in which the ship is to be registered and to the relevant regulations of the *International Convention for the Safety of Life at Sea, 1974* and applicable amendments.

### 1.2 Protection

1.2.1 In all cargo spaces and other areas where mechanical damage is likely, all air and sounding pipes, scuppers and discharges, including their valves, controls and indicators, are to be well protected. This protection is to be of steel or other equivalent material.

## Section 2 Ventilators

### 2.1 General

2.1.1 Ventilators located on the exposed deck over the forward 0,25L of the rule length, of ships of sea-going service of length 80 m or more, where the height of the exposed deck in way of the item is less than 0,1L or 22 m above the summer load waterline, whichever is the lesser, are to comply with the requirements of Section 5. All other ventilators are to comply with the following requirements.

2.1.2 Special care is to be taken in the design and positioning of ventilator openings and coamings, particularly in the region of the forward end of superstructures and other points of high stress. The deck plating in way of the coamings is to be efficiently stiffened.

2.1.3 Ventilators from deep tanks and tunnels passing through 'tween decks are to have scantlings suitable for withstanding the pressures to which they may be subjected, and are to be made watertight.

2.1.4 For height and location of cargo tank vent outlets, see Pt 5, Ch 15,4 and see also Ch 8,8.2.9 and 8.2.10 of the *Rules for Ships for Liquefied Gases*, or Ch 8,8.2.2, of the *Rules for Ships for Liquid Chemicals*, where applicable.

### 2.2 Coamings

2.2.1 The scantlings and height of ventilator coamings exposed to the weather are to be not less than required by Table 12.2.1 but the thickness need not exceed that of the adjacent deck or bulkhead plating. In particularly exposed positions, the height of coamings and scantlings may be required to be increased.

**Table 12.2.1 Ventilator coaming requirements**

Feature	Requirements
Height (measured above sheathing if fitted)	(1) $z_c = 900$ mm at Position 1 (see Ch 1,6.5)  $z_c = 760$ mm at Position 2 (see Ch 1,6.5)
Thickness	(2) $t_c = 5,5 + 0,01\delta_v$ mm where $7,5$ mm $\leq t_c \leq 10,0$ mm
Support	(3) If $z_c > 900$ mm the coaming is to be specially supported
Symbols	
$t_c$ = thickness of coaming, in mm $z_c$ = height of coaming, in mm $\delta_v$ = internal diameter of coaming, in mm	
NOTE Where the height of the ventilator exceeds that given in Item (1), the thickness given by (2) may be gradually reduced, above that height, to a minimum of 6,5 mm. The ventilator is to be adequately stayed.	

2.2.2 The height of ventilator coamings may be required to be increased on ships of Type 'A', Type 'B-100' and Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*.

2.2.3 For gooseneck ventilators, the coaming height is to be measured to the underside of the bend, this being the lowest point through which water on deck could pass freely to spaces below.

# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

Sections 2 & 3

2.2.4 Where wall vents are fitted with an internal baffle which rises above the lower edge of the exterior opening, the coaming height is measured to the top of the baffle.

2.2.5 Where permitted by the National Authority, ventilator coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable, with a minimum height of 450 mm in Position 1 and 300 mm in Position 2.

## 2.3 Closing appliances

2.3.1 All ventilator openings are to be provided with efficient weathertight closing appliances of steel or other equivalent material unless:

- (a) the height of the coaming is greater than 4,5 m where Table 12.2.1 requires a minimum height of 900 mm; or
- (b) the height of the coaming is greater than 2,3 m where Table 12.2.1 requires a minimum height of 760 mm.

2.3.2 In ships where the load line length,  $L_L$  (see Ch 1,6.1), is not more than 100 m, the closing appliances are to be permanently attached to the ventilator coaming. Where not so provided in other ships, they are to be conveniently stowed near the ventilator to which they are to be fitted.

2.3.3 Where, in ferries, ventilators are proposed to be led overboard in an enclosed 'tween deck, the closing arrangements are to be submitted for approval. If such ventilators are led overboard more than 4,5 m above the main vehicle deck, closing appliances may be omitted, provided that satisfactory baffles and drainage arrangements are provided, as in the case of air intakes or exhaust openings for machinery spaces, which may be arranged in the sides of the ship.

2.3.4 On offshore supply ships, to ensure satisfactory operation in all weather conditions, machinery space ventilation inlets and outlets are to be located in such positions that closing appliances will not be necessary.

2.3.5 Mushroom ventilators closed by a head revolving on a centre spindle (screw down head) are acceptable in Position 2, and also in sheltered positions in Position 1, excluding those described in 2.1.1, but the diameter is not to exceed 300 mm if situated within the forward 0,25 $L_L$ .

2.3.6 Mushroom ventilators with a fixed head and closed by a screw down plate (screw down cover) may be accepted in exposed positions within the forward 0,25 $L_L$ , excluding those described in 2.1.1, up to a diameter of 750 mm.

2.3.7 Wall ventilators (jalousies) may be accepted provided they are capable of being closed weathertight by hinged steel gasketed covers secured by bolts or toggles.

2.3.8 A ventilator head not forming part of the closing arrangements is to be not less than 6,5 mm thick.

## 2.4 Machinery spaces

2.4.1 In general, ventilators necessary to continuously supply the machinery space are to have coamings of sufficient height to comply with 2.3.1 without having to fit weathertight closing appliances. Ventilators to emergency generator rooms are to be so positioned that closing appliances are not required.

2.4.2 Where due to ship size and arrangement this is not practicable, lesser heights for machinery space ventilator coamings fitted with weathertight closing appliances may be permitted by the administration in combination with other suitable arrangements to ensure uninterrupted, adequate supply of ventilation to these spaces.

## Section 3 Air and sounding pipes

### 3.1 General

3.1.1 Air pipes located on the exposed deck over the forward 0,25 $L$  of the rule length, of ships of sea-going service of length 80 m or more, where the height of the exposed deck in way of the item is less than 0,1 $L$  or 22 m above the summer load waterline, whichever is the lesser, are to comply with the requirements of Section 5. All other air and sounding pipes are to comply with the following requirements in addition to the applicable requirements of Pt 5, Ch 13,10 and Ch 13,15.2.

3.1.2 Striking plates of suitable thickness, or their equivalent, are to be fitted under all sounding pipes.

3.1.3 On offshore supply ships, air pipes are to be situated clear of the cargo containment areas.

### 3.2 Height of air pipes

3.2.1 The height of air pipes from the upper surface of decks exposed to the weather, to the point where water may have access below, is normally to be not less than:

- 760 mm on the freeboard deck;
  - 450 mm on the superstructure deck;
- these heights being measured above deck sheathing, where fitted.

3.2.2 Lower heights may be approved in cases where these are essential for the working of the ship, provided that the design and arrangements are otherwise satisfactory. In such cases, efficient, permanently attached closing appliances of an approved automatic type will generally be required.

# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

Sections 3 & 4

3.2.3 The height of air pipes may be required to be increased on ships of Type 'A', Type 'B-100' and Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*. An increase in height may also be required or recommended by individual Administrations when air pipes to oil fuel and settling tanks are situated in positions where sea-water could be temporarily entrapped, e.g. in recesses in the sides and ends of superstructures or deckhouses, between hatch ends, behind high sections of bulwark, etc. This may entail an increase in tank scantlings, see also Chapter 3.

3.2.4 Air pipes are generally to be led to an exposed deck. For alternative arrangements in an enclosed space on a main vehicle deck, see Pt 4, Ch 2,9.

3.2.5 Where air pipes are led through the side of superstructures, the opening is to be at least 2,3 m above the summer load waterline.

3.2.6 The minimum wall thickness of air pipes in positions indicated in 3.2.1 is to be:

- 6,0 mm for pipes of 80 mm external diameter or smaller;
- 8,5 mm for pipes of 165 mm external diameter or greater.

Intermediate minimum thicknesses are to be determined by linear interpolation.

3.2.7 Where permitted by the National Authority, air pipe coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable, with a minimum height of 450 mm on the freeboard deck and 300 mm on a superstructure deck.

## 3.3 Closing appliances

3.3.1 All openings of air and sounding pipes are to be provided with permanently attached, satisfactory means of closing to prevent the free entry of water, see also 3.2.2.

3.3.2 Closing appliances are to be of an approved automatic type.

3.3.3 Pressure/vacuum valves as required by Pt 5, Ch 15,4 may be accepted as closing appliances for cargo tanks.

4.1.3 Scuppers and discharges which drain spaces below the freeboard deck, or spaces within intact superstructures or deckhouses on the freeboard deck fitted with efficient weathertight doors, may be led to the bilges in the case of scuppers, or to suitable sanitary tanks in the case of sanitary discharges. Alternatively, they may be led overboard provided that:

- (a) The freeboard is such that the deck edge is not immersed when the ship heels to 5°, and
- (b) the scuppers are fitted with means of preventing water from passing inboard in accordance with 4.2.

4.1.4 In ships where an approved fixed pressure water spray fire-extinguishing system is fitted in vehicle or cargo spaces, deck scuppers of not less than 150 mm diameter are to be provided port and starboard, spaced about 9,0 m apart. The scupper area will require to be increased if the design capacity of the drencher system exceeds the Rule required capacity by 10 per cent or more. After installation, the two adjacent sections with the greatest aggregate drencher capacity are to be tested in operation to ensure that there is no build up of water on the deck, see also Pt 4, Ch 2,10.2.2. The mouth of the scupper is to be protected by bars.

4.1.5 Where a sewage system is fitted, the shipside valves on the discharge pipe from the effluent tank(s) and the by-pass system are to comply with 4.2.

4.1.6 The minimum wall thickness of pipes not indicated in 4.2.6 is to be:

- 4,5 mm for pipes of 155 mm external diameter or smaller;
- 6,0 mm for pipes of 230 mm external diameter or greater.

Intermediate minimum thicknesses are to be determined by linear interpolation.

4.1.7 For the use of non-metallic pipe, see Pt 5, Ch 12,5.

4.1.8 Scuppers and discharge pipes should not normally pass through oil fuel or cargo oil tanks. Where scuppers and discharge pipes pass, unavoidably, through oil fuel or cargo oil tanks, and are led through the shell within the tanks, the thickness of the piping should be at least the same thickness as Rule shell plating in way, derived from the appropriate Chapters, but need not exceed 19 mm.

4.1.9 Piping within tanks is to be tested in accordance with Ch 1,8.

4.1.10 All piping is to be adequately supported.

4.1.11 See also the *Rules for Ships for Liquefied Gases* or the *Rules for Ships for Liquid Chemicals*, where applicable.

4.1.12 For additional requirements for scuppers and sanitary discharges on dredging and reclamation craft, see Pt 4, Ch 12,15.

## Section 4 Scuppers and sanitary discharges

### 4.1 General

4.1.1 Scuppers sufficient in number and size to provide effective drainage are to be fitted in all decks.

4.1.2 Scuppers draining weather decks and spaces within superstructures or deckhouses not fitted with efficient weathertight doors are to be led overboard.

# Ventilators, Air Pipes and Discharges

## Part 3, Chapter 12

Section 4

### 4.2 Closing appliances


4.2.1 In general, each separate overboard discharge is to be fitted with a screw-down non-return valve capable of being operated from a position always accessible and above the freeboard deck. An indicator is to be fitted at the control position showing whether the valve is open or closed. A machinery space, whether manned or unmanned (i.e. with **UMS** notation), is considered accessible. Cargo holds or spaces with access only by hatches or bolted manholes are not considered accessible.

4.2.2 Where a drencher fire-extinguishing system is provided in an enclosed vehicle space of a ferry, the scupper controls are to be operated from a position above the bulkhead deck, and outside the vehicle space protected by the drencher system, and are to be protected from mechanical damage.

4.2.3 Where the vertical distance from the summer load waterline to the inboard end of the discharge pipe exceeds  $0,01L_L$  the discharge may be fitted with two automatic non-return valves without positive means of closing, instead of the screw-down non-return valve, provided that the inboard valve is always accessible for examination under service conditions.

4.2.4 Where the vertical distance from the summer load waterline to the inboard end of the discharge pipe exceeds  $0,02L_L$ , a single automatic non-return valve without positive means of closing may be fitted, see Fig. 12.4.1.

4.2.5 The requirements for non-return valves are applicable only to those discharges which remain open during the normal operation of the ship. For discharges which are closed at sea, such as gravity drains from topside ballast tanks, a single screw down valve operated from the freeboard deck is considered to provide sufficient protection.



# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

Sections 4 & 5

4.2.6 Scuppers and discharge pipes originating at any level which penetrate the shell either more than 450 mm below the freeboard deck or less than 600 mm above the summer load waterline, are to be fitted with an automatic non-return valve at the shell. This valve, unless required by 4.1.3, may be omitted provided the piping has a minimum wall thickness of:

- 7,0 mm for pipes of 80 mm external diameter or smaller;
- 10,0 mm for pipes of 180 mm external diameter;
- 12,5 mm for pipes of 220 mm external diameter or greater.

Intermediate minimum thicknesses are to be determined by linear interpolation. Unless required by 4.1.8, the maximum thickness need not exceed 12,5 mm.

4.2.7 The outboard valve is to be mounted directly on the shell and secured in accordance with Pt 5, Ch 13,2.5.1. If this is impracticable, a short distance piece of rigid construction may be introduced between the valve and the shell. Valves should not be fitted in cargo tanks.

4.2.8 If a valve is required by 4.1.3, this valve should preferably be fitted as close as possible to the point of entry of the pipe into the tank. If fitted below the freeboard deck, the valve is to be capable of being controlled from an easily accessible position above the freeboard deck. Local control is also to be arranged, unless the valve is inaccessible. An indicator is to be fitted at the control position showing whether the valve is open or closed.

4.2.9 In a ship to which timber freeboards are assigned, the summer load waterline is to be regarded as that corresponding to the timber summer freeboard.

4.2.10 For ship side valves and fittings (other than those on scuppers and sanitary discharges), see Pt 5, Ch 13,2 and Pt 6, Ch 1,2.

## 4.3 Rubbish chutes, offal and similar discharges

4.3.1 Rubbish chutes, offal and similar discharges should be constructed of mild steel piping or plating of shell thickness. Other materials will be specially considered. Openings are to be kept clear of the sheerstrake and areas of high stress concentration.

4.3.2 Rubbish chute hoppers are to be provided with a hinged weathertight cover at the inboard end with an interlock so that the discharge flap and hopper cover cannot be open at the same time. The hopper cover is to be secured closed when not in use, and a suitable notice displayed at the control position.

4.3.3 Where the inboard end of the hopper is less than 0,01L<sub>L</sub> above the summer load waterline, a suitable valve with positive means for closing is to be provided in addition to the cover and flap in an easily accessible position above the deepest seasonal waterline. The valve is to be controlled from a position adjacent to the hopper and provided with an open/shut indicator. The valve is to be kept closed when not in use, and a suitable notice displayed at the valve operating position.

4.3.4 Where damage stability requirements apply and the inboard end of the chute is below the equilibrium waterlines, or in passenger ships, where the inboard end of a rubbish chute is below the margin line; see Ch 11,8.2.8(b).

4.3.5 In trawlers or fish factory ships, offal discharges in the fish working spaces are to be provided with either a non-return flap, preferably fitted at the shell which can be positively secured weathertight, or a separate positively controlled valve kept closed when not in use. A suitable notice is to be displayed at the flap or valve operating position.

## 4.4 Materials for valves, fittings and pipes

4.4.1 All shell fittings and valves required by 4.2 are to be of steel, bronze or other approved ductile material; ordinary cast iron or similar material is not acceptable. Materials are to satisfy the requirements of the Rules for Materials (Part 2).

4.4.2 All these items, if made of steel or other approved material with low corrosion resistance, are to be suitably protected against wastage.

4.4.3 The lengths of pipe attached to the shell fittings, elbow pieces or valves are to be of galvanized steel or other equivalent approved material.

## Section 5 Air pipes, ventilator pipes and their securing devices located on the exposed fore deck

### 5.1 General

5.1.1 For the application of the following requirements relating to ventilators, see 2.1.1. For the application of the following requirements relating to air pipes, see 3.1.1. Air pipes complying with the following requirements are also to comply with the applicable requirements of Pt 5, Ch 13,10 and Pt 5, Ch 15,2.5.

5.1.2 Special care is to be taken in the design and positioning of ventilator openings and coamings, particularly in the region of the forward end of superstructures and other points of high stress. The deck plating in way of the coamings is to be efficiently stiffened.

5.1.3 Ventilators from deep tanks and tunnels passing through 'tween decks are to have scantlings suitable for withstanding the pressures to which they may be subjected, and are to be made watertight.

5.1.4 For height and location of cargo tank vent outlets, see Pt 5, Ch 15,4 and see also Ch 8,8.2.9 and 8.2.10 of the *Rules for Ships for Liquefied Gases*, or Ch 8,8.2.2, of the *Rules for Ships for Liquid Chemicals*, where applicable.

5.1.5 On offshore supply ships, air pipes are to be situated clear of the cargo containment areas.

# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

Section 5

## 5.2 Loading

5.2.1 The pressures,  $p$ , in  $\text{kN/m}^2$  acting on air pipes, ventilator pipes and their closing devices may be calculated from:

$$p = 0,5\rho V^2 C_d C_s C_p$$

where

- $\rho$  = density of sea-water ( $1,025 \text{ t/m}^3$ )
- $V$  = velocity of water over the fore deck ( $13,5 \text{ m/sec}$ )
- $C_d$  = shape coefficient (0,5 for pipes, 1,3 for air pipe or ventilator heads in general and 0,8 for an air pipe or ventilator head of cylindrical form with its axis in the vertical direction)
- $C_s$  = slamming coefficient (3,2)
- $C_p$  = protection coefficient (0,7 for pipes and ventilator heads located immediately behind a breakwater or forecastle and 1,0 elsewhere and immediately behind a bulwark).

5.2.2 Forces acting in the horizontal direction on the pipe and its closing device may be calculated from 5.2.1 using the largest projected area of each component.

## 5.3 Strength requirements

5.3.1 Bending moments and stresses in air and ventilator pipes are to be calculated at critical positions:

- at penetration pieces;
- at weld or flange connections; and
- at toes of supporting brackets.

5.3.2 Bending stresses in the net section are not to exceed  $0,8\sigma_y$ , where  $\sigma_y$  is the specified minimum yield stress or 0,2 per cent proof stress of the steel at room temperature. Irrespective of corrosion protection, a corrosion addition to the net section of 2,0 mm is then to be applied.

5.3.3 For standard air pipes of 760 mm coaming height closed by heads of not more than the tabulated projected area, pipe thicknesses and bracket heights are specified in Table 12.5.1. Where brackets are required, three or more radial brackets are to be fitted. Brackets are to be of gross thickness 8 mm or more, of minimum length 100 mm, and height according to Table 12.5.1 but need not extend over the joint flange for the head. Bracket toes at the deck are to be suitably supported.

5.3.4 For other configurations, loads according to 5.2 are to be applied, and means of support determined in order to comply with the requirements of 5.3.1 and 5.3.2. Brackets, where fitted, are to be of suitable thickness and length according to their height. Pipe thickness is not to be taken less than as indicated in Pt 5, Ch 12.

5.3.5 For standard ventilators of 900 mm coaming height closed by heads of not more than the tabulated projected area, pipe thicknesses and bracket heights are specified in Table 12.5.2. Brackets, where required, are to be as specified in 5.3.3.

**Table 12.5.1 Air pipe thickness and bracket standards**

Nominal pipe diameter, in mm	Minimum fitted gross thickness, in mm	Maximum projected area of head, in $\text{cm}^2$	Height <sup>(1)</sup> of brackets, in mm
65A	6,0	—	480
80A	6,3	—	460
100A	7,0	—	380
125A	7,8	—	300
150A	8,5	—	300
175A	8,5	—	300
200A	8,5 <sup>(2)</sup>	1900	300 <sup>(2)</sup>
250A	8,5 <sup>(2)</sup>	2500	300 <sup>(2)</sup>
300A	8,5 <sup>(2)</sup>	3200	300 <sup>(2)</sup>
350A	8,5 <sup>(2)</sup>	3800	300 <sup>(2)</sup>
400A	8,5 <sup>(2)</sup>	4500	300 <sup>(2)</sup>
(1) Brackets (see 5.3.3) need not extend over the joint flange for the head.			
(2) Brackets are required where the as fitted (gross) thickness is less than 10,5 mm, or where the tabulated projected head area is exceeded.			
NOTE For other pipe heights, the relevant requirements of 5.3 are to be applied.			

**Table 12.5.2 900 mm Ventilator pipe thickness and bracket standards**

Nominal pipe diameter, in mm	Minimum fitted gross thickness, in mm	Maximum projected area of head, in $\text{cm}^2$	Height of brackets, in mm
80A	6,3	—	460
100A	7,0	—	380
150A	8,5	—	300
200A	8,5	550	—
250A	8,5	880	—
300A	8,5	1200	—
350A	8,5	2000	—
400A	8,5	2700	—
450A	8,5	3300	—
500A	8,5	4000	—
NOTE For ventilator heights other than 900 mm, the relevant requirements of 5.3 are to be applied.			

5.3.6 For ventilators of coaming height greater than 900 mm, the coaming support will be specially considered. Pipe thickness is not to be taken less than as indicated in Pt 5, Ch 12.

5.3.7 All component parts and connections of the air pipe or ventilator are to be capable of withstanding the loads defined in 5.2.



# Ventilators, Air Pipes and Discharges

# Part 3, Chapter 12

## Section 5

### 5.4 Ventilator coamings

5.4.1 The heights of ventilator coamings is to be not less than 900 mm, this height being measured above deck sheathing, where fitted. In particularly exposed positions, the heights of coamings and scantlings may be required to be increased.

5.4.2 The height of ventilator coamings may be required to be increased on ships of Type 'A', Type 'B-100' and Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*.

5.4.3 For gooseneck ventilators, the coaming height is to be measured to the underside of the bend, this being the lowest point through which water on deck could pass freely to spaces below.

5.4.4 Where wall vents are fitted with an internal baffle which rises above the lower edge of the exterior opening, the coaming height is measured to the top of the baffle.

5.4.5 Where permitted by the National Authority, ventilator coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable, with a minimum height of 450 mm.

### 5.5 Height of air pipes

5.5.1 The height of air pipes from the upper surface of decks exposed to the weather, to the point where water may have access below is normally to be not less than 760 mm, this height being measured above deck sheathing, where fitted.

5.5.2 Lower heights may be approved in cases where these are essential for the working of the ship, provided that the design and arrangements are otherwise satisfactory. In such cases, efficient, permanently attached closing appliances of an approved automatic type will generally be required.

5.5.3 The height of air pipes may be required to be increased on ships of Type 'A', Type 'B-100' and Type 'B-60' where this is shown to be necessary by the floatability calculations required by the *International Convention on Load Lines, 1966*. An increase in height may also be required or recommended by individual Administrations when air pipes to oil fuel and settling tanks are situated in positions where sea-water could be temporarily entrapped, e.g. in recesses in the sides and ends of superstructures or deckhouses, between hatch ends, behind high sections of bulwark, etc. This may entail an increase in tank scantlings, see also Chapter 3.

5.5.4 Air pipes are generally to be led to an exposed deck. For alternative arrangements in an enclosed space on a main vehicle deck, see Pt 4, Ch 2,9.

5.5.5 Where air pipes are led through the side of superstructures, the opening is to be at least 2,3 m above the summer load waterline.

5.5.6 Where permitted by the National Authority, air pipe coaming heights may be reduced on ships engaged on protected or extended protected water service. Coaming heights are to be as high as practicable, with a minimum height of 450 mm.

### 5.6 Closing appliances for ventilators

5.6.1 All ventilator openings are to be provided with efficient weathertight closing appliances unless the height of the coaming is greater than 4,5 m.

5.6.2 In ships where the load line length,  $L_L$  (see Ch 1,6.1), is not more than 100 m, the closing appliances are to be permanently attached to the ventilator coaming. Where not so provided in other ships, they are to be conveniently stowed near the ventilator to which they are to be fitted.

5.6.3 Where, in ferries, ventilators are proposed to be led overboard in an enclosed 'tween deck, the closing arrangements are to be submitted for approval. If such ventilators are led overboard more than 4,5 m above the main vehicle deck, closing appliances may be omitted, provided that satisfactory baffles and drainage arrangements are provided, as in the case of air intakes or exhaust openings for machinery spaces, which may be arranged in the sides of the ship.

5.6.4 On offshore supply ships, to ensure satisfactory operation in all weather conditions, machinery space ventilation inlets and outlets are to be located in such positions that closing appliances will not be necessary.

5.6.5 Rotating type mushroom ventilator heads are unsuitable for application on the exposed fore deck.

5.6.6 Wall ventilators (jalousies) may be accepted provided they are capable of being closed weathertight by hinged steel gasketed covers secured by bolts or toggles.

5.6.7 A ventilator head not forming part of the closing arrangements is to be not less than 6,5 mm thick.

### 5.7 Closing appliances for air pipes

5.7.1 All openings of air pipes are to be provided with permanently attached, satisfactory means of closing to prevent the free entry of water, see also 5.5.2.

5.7.2 Closing appliances are to be of an approved automatic type where, with the ship at its summer load waterline, the openings are immersed at an angle of heel of 40° or, the angle of down flooding if this is less than 40°, see also Ch 3,7.

5.7.3 Where the closing appliances are not of an automatic type, provision is to be made for relieving vacuum when the tanks are being pumped out.

5.7.4 In a ship to which timber freeboards are assigned, air pipes which will be inaccessible when the deck cargo is carried are to be provided with approved automatic closing appliances.

## Ventilators, Air Pipes and Discharges

## Part 3, Chapter 12

### *Section 5*

---

5.7.5 Pressure/vacuum valves as required by Pt 5, Ch 15,4 may be accepted as closing appliances for cargo tanks.

---

# Ship Control Systems

# Part 3, Chapter 13

Sections 1 & 2

## Section

- 1 **General**
- 2 **Rudders**
- 3 **Fixed and steering nozzles**
- 4 **Steering gear and allied systems**
- 5 **Bow and stern thrust unit structure**
- 6 **Stabilizer structure**
- 7 **Equipment**
- 8 **Mooring of ships at single point moorings**
- 9 **Emergency towing arrangements**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to all the ship types detailed in Part 4, and requirements are given for rudders, nozzles, steering gear, bow and stern thrust unit structure, stabilizer structure, anchoring and mooring equipment, and emergency towing arrangements.

1.1.2 The requirements in this Chapter are not applicable to Double Hull Oil Tankers or Bulk Carriers with a **CSR** notation (see Pt 1, Ch 2,2.3) with the exception of the following:

- For Double Hull Oil Tankers; Sections 2 to 6 and Section 8 are to be complied with as applicable.
- For Bulk Carriers; Sections 3-6, 8 and 9 are to be complied with as applicable.

### 1.2 General symbols

1.2.1 The following symbols and definitions are applicable to this Chapter, unless otherwise stated:

$L$ ,  $B$  and  $C_b$  as defined in Ch 1,6.1

$\sigma_o$  = minimum yield stress or 0,5 per cent proof stress of the material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$k$  = higher tensile steel factor, see Ch 2,1.2.

### 1.3 Navigation in ice

1.3.1 Where an ice class notation is included in the class of a ship, additional requirements are applicable as detailed in Chapter 9.

## 1.4 Materials

1.4.1 The requirements for materials are contained in the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

## ■ Section 2 Rudders

### 2.1 Lateral force on rudder blade

2.1.1 The lateral rudder force at the centre of pressure is to be determined for both ahead and stern conditions from the following formula:

$$P_L = 132c_1 c_2 c_3 C_{TH} A_R V^2 \quad \text{N}$$

where

$A_R$  = rudder blade area, in m<sup>2</sup>

$A_T$  = sum of rudder blade area  $A_R$  and area of rudder post or rudder horn, if any, within the rudder mean height  $h_R$ , in m<sup>2</sup>

$c_1$  = factor depending on the aspect ratio  $\lambda$  of the rudder area

$$= \frac{\lambda + 2}{3}$$

$c_2$  = rudder profile coefficient, see Table 13.2.1

$c_3$  = 1,0 in general

= 0,8 for rudders outside the propeller jet

= 1,15 for rudders behind a fixed propeller nozzle

$C_{TH}$  = thrust coefficient, is generally to be taken as 1

$P_L$  = lateral force acting on the rudder, in N, is to be calculated for both ahead and astern conditions. The greater of these two values is to be used throughout Section 2

$V$  = maximum service speed, in knots, which the ship is designed to maintain, at the summer load waterline. Maximum ahead service speed means the maximum service speed which the ship is designed to maintain, at the summer load waterline at maximum propeller RPM and corresponding engine MCR. When the speed is less than 10 knots,  $V$  is to be replaced by the expression  $V_{\min} = \frac{V + 20}{3}$ . For the


astern condition the actual astern speed, in knots, or 0,5V, whichever is the greater is to be used (for bow rudders  $V = V_A$ )

$$\lambda = \frac{h_R^2}{A_T}, \text{ but not to be taken greater than 2}$$

$h_R$  = mean height, in metres, of the rudder area, see Fig. 13.2.2.

**Table 13.2.1 Rudder profile coefficient,  $c_2$**

Profile type (see Fig. 13.2.1)	Ahead	Astern
NACA-00	1,1	0,8
Hollow profiles	1,35	0,9
Flat side profiles	1,1	0,9
High lift profile	1,7	to be specially considered
<b>NOTE</b> For rudder profiles not defined above, the value of $c_2$ may be determined on the basis of experimental results. These results are to be submitted for consideration.		



**Fig. 13.2.1 Rudder profiles**

## 2.2 Rudder torque calculation for rudders without cut-outs


2.2.1 The rudder torque,  $M_T$ , is to be determined for both the ahead and astern conditions according to the following formula:

$$M_T = P_L x_P \text{ Nm}$$

where

- $P_L$  = lateral force acting on rudder, as calculated in 2.1
- $x_P$  =  $b_R (\alpha - k)$ , in metres, but not less than  $0,1b_R$
- $b_R$  = mean breadth of rudder, in metres, see Fig. 13.2.2
- $\alpha$  = as given in Table 13.2.2
- $k = \frac{A_f}{A_R}$

$A_f$  = portion of the rudder blade area, situated in front of the centreline of the rudder stock, in  $m^2$ , see Fig. 13.2.2.



**Fig. 13.2.2 Rudder co-ordinate system**

**Table 13.2.2 Coefficient,  $\alpha$**

Condition	Behind fixed structure (see Note)	Not behind a fixed structure
Ahead	0,25	0,33
Astern	0,55	0,66
<b>NOTE</b> For rudder parts behind a fixed structure such as a rudder horn.		

## 2.3 Rudder torque calculation for rudders with cut-outs

2.3.1 The rudder torque,  $M_T$ , is to be determined for both the ahead and astern conditions as follows. The rudder area,  $A_R$ , used in the derivation of the rudder torque may be divided into two rectangular or trapezoidal parts with areas  $A_1$  and  $A_2$ , so that  $A_R = A_1 + A_2$ , see Fig. 13.2.3.

$$M_T = M_1 + M_2 \text{ Nm}$$

where

$$M_1 = P_{L1} x_{P1} \text{ Nm}$$

$$M_2 = P_{L2} x_{P2} \text{ Nm}$$

$M_T$  = the rudder torque, in Nm, to be calculated for both ahead and astern conditions. The greater of these two values are to be used throughout Section 2

$P_L$  = lateral force acting on the rudder, in N, as calculated in 2.1.1

$$P_{L1} = \frac{A_1}{A_R} P_L \text{ N}$$

## Ship Control Systems

## Part 3, Chapter 13

## Section 2




Fig. 13.2.3 Rudder areas

$$P_{L2} = \frac{A_2}{A_R} P_L \text{ N}$$

$$x_{P1} = b_{R1} (\alpha - k_1), \text{ in metres}$$

$$x_{P2} = b_{R2} (\alpha - k_2), \text{ in metres}$$

$$A_1 = A_{1a} + A_{1f}, \text{ in m}^2, \text{ see Fig. 13.2.3}$$

$$A_2 = A_{2a} + A_{2f}, \text{ in m}^2, \text{ see Fig. 13.2.3}$$

$$b_{R1} = \text{mean breadth, in metres, of partial area } A_1$$

$$b_{R2} = \text{mean breadth, in metres, of partial area } A_2$$

$$\alpha = \text{as given in Table 13.2.2}$$

$$k_1 = \frac{A_{1f}}{A_1}$$

$$k_2 = \frac{A_{2f}}{A_2}$$

For ahead condition  $M_T$  is not to be taken less than

$$M_{T,\min} = 0,1 P_L \frac{A_1 b_{R1} + A_2 b_{R2}}{A_R} \text{ Nm}$$

## 2.4 Rudder stock and main bearing

2.4.1 The scantlings of the stock are to be not less than required by Table 13.2.3.

2.4.2 For the purpose of this Section, the material factor,  $k_o$ , applicable to rudder stocks, pintles, coupling flanges, bolts, keys, etc., is defined in Table 13.2.4. For higher tensile steel rudder stocks, welding, including cladding, is not generally permitted.

2.4.3 The rudder stock diameter is to be dimensioned such that the stresses do not exceed the permissible stresses given in Table 13.2.5.

Table 13.2.3 Rudder stock diameter

Item	Requirement
(1) Basic stock diameter, $\delta_S$ , at and below lowest bearing	$\delta_S = \delta_t \sqrt[6]{1 + \frac{4}{3} \left( \frac{M_B}{M_T} \right)^2} \text{ mm}$
(2) Diameter, $\delta_t$ , in way of tiller	$\delta_t = 4,2 \sqrt[3]{M_T k_o} \text{ mm}$
Symbols	
$M_T$ = Total rudder torque, in Nm, as calculated in 2.2 or 2.3 $M_B$ = bending moment, in Nm, at section considered. If direct calculations of bending moment distribution are not carried out, then $M_B$ at the lowest main bearing or rudder coupling may be taken as:	
$M_B = \frac{h_R}{10 C_r} P_L$ , for rudders with heel support $M_B = b P_L$ , for spade rudders $M_B = \frac{h_R}{10 (1 + C_r)} P_L$ , for semi-spade rudders	
$C_r = \frac{b_R^2}{A_R}$ $b$ = distance, in metres, from centroid of rudder area to the centre of lowest bearing, see Fig. 13.2.4 $b_R$ = mean breadth of rudder, in metres, see Fig. 13.2.2 $h_R$ = mean depth of rudder, in metres, see Fig. 13.2.2 $P_L$ = rudder force, as defined in 2.1.1 $k_o$ = as defined in Table 13.2.4	


Table 13.2.4 Material factor  $k_o$ 

$\sigma_o$	$k_o$
For $\sigma_o > 235$ (24)	$\left( \frac{235}{\sigma_o} \right)^{0,75} \left( \frac{24}{\sigma_o} \right)^{0,75}$
For $\sigma_o \leq 235$ (24)	$\left( \frac{235}{\sigma_o} \right) \left( \frac{24}{\sigma_o} \right)$
Symbols	
$\sigma_o$ = minimum yield stress in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) $k_o$ = higher tensile steel correction factor	
NOTE $\sigma_o$ is to be taken not greater than 70 per cent of the ultimate tensile strength or 450 N/mm <sup>2</sup> (45,9 kgf/mm <sup>2</sup> ), whichever is the lesser. $\sigma_o$ is not to be less than 200 N/mm <sup>2</sup> , see Ch 5,2.4.6 of the Rules for Materials.	


2.4.4 Where reductions in rudder stock diameter due to the application of steels with yield stresses exceeding 235 N/mm<sup>2</sup> are requested, evaluation of the rudder stock deformations may be required. Large deformations are to be avoided in order to avoid excessive edge pressures in way of bearings.

**Table 13.2.5 Permissible stresses**

Mode	Permissible stress, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	
(1) Torsional shear stress, $\tau_T$	$68/k_0$	$(6,9/k_0)$
(2) Equivalent stress, $\sigma_e$	$118/k_0$	$(12/k_0)$
Symbols and parameters		
$\sigma_T$ = equivalent stress $= \sqrt{\sigma_b^2 + 3\tau^2}$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) $\sigma_b$ = bending stress $= 10,2 \frac{M_B}{\delta_s^3} 10^3$ N/mm <sup>2</sup> $\left( 1,04 \frac{M_B}{\delta_s^3} 10^3 \text{ kgf/mm}^2 \right)$ $\tau_T$ = torsional shear stress $= 5,1 \frac{M_T}{\delta_s^3} 10^3$ N/mm <sup>2</sup> $\left( 0,52 \frac{M_T}{\delta_s^3} 10^3 \text{ kgf/mm}^2 \right)$ $\delta_s$ = actual stock diameter, as calculated in Table 13.2.3 $M_B$ = bending moment, in Nm, at the section considered. If direct calculations of bending moment distribution are not carried out, then $M_B$ at the lowest main bearing or rudder coupling may be taken as given in Table 13.2.3 $M_T$ = total rudder torque, in Nm, as calculated in 2.2 or 2.3 $k_0$ = as defined in Table 13.2.4		



2.4.5 For spade rudders the stock diameter corrected for higher tensile steel is to be greater than 90 per cent of the uncorrected stock diameter unless direct calculations are submitted showing that the slope of the stock at the lowest main bearing does not exceed 0,0035 when the rudder blade is loaded by a lateral force of  $P_L$ , acting at the centre of pressure.



## Ship Control Systems

## Part 3, Chapter 13

## Section 2

**Table 13.2.6 Bearing requirements for rudder stock and pintles**

Item	Requirement	
(1) Bearing surface area	$A_B = \frac{B}{q_a} \text{ mm}^2$	
(2) Bearing length	The length/diameter ratio of the actual bearing surface is not to be greater than 1,2	
(3) Clearance	Bearing material	Minimum clearance (on diameter)
	Metal	$0,001\delta + 1,0$
	Synthetic	See Notes 1, 3, 4 and 5
(4) Rudder stock main bearing wall thickness	Lesser of $0,2\delta$ or 100	See Note 2
(5) Gudgeon thickness in way of pintle (measured outside bush if fitted)	$b_G \geq 0,25\delta$ but need not normally exceed 125 mm	
Symbols		
$A_B$ = bearing surface area, in $\text{mm}^2$ , defined as the projected area (length x diameter) of liner $b$ = distance, in metres, from centre of rudder area to the centre of lowest bearing $b_G$ = thickness of gudgeon material in way of pintle, in mm $c$ = distance, in metres, from centre of lower pintle to the centre of lowest bearing $d$ = distance, in metres, from centre of lowest bearing to the centre of upper bearing. In the case of semi spade rudder with two pintles, $d$ , is to be measured between the centre of upper pintle and centre of upper bearing $\delta$ = diameter of stock, $\delta_S$ , given in Table 13.2.3, or pintle, $\delta_{PL}$ , given in Table 13.2.11, in mm $l_B$ = length of bearing, in mm $q_a$ = maximum surface pressure, see Table 13.2.7 $B$ = bearing force, in N. If direct calculations are not carried out, the bearing force at various positions can be taken as: $B_2 = \left(1 - \frac{b}{c}\right)P_L$ , at lowest main bearing for single pintle rudders and semi-spade rudders, see Fig. 13.2.4(a), (c) and (d). $B_2$ is not to be less than $0,35P_L$ $B_2 = P_L + B_3$ , at lowest main bearing for spade rudders, see Fig. 13.2.4(b). $B_3 = \frac{M_B}{d}$ , at upper bearing for spade rudders, see Fig. 13.2.4(b). For bearing force at pintles, see Table 13.2.11.		
NOTES		
1. If non-metallic bearing material is applied, the bearing clearance is to be specially determined considering the material's swelling and thermal expansion properties. This clearance is normally not to be less than 1,5 mm on bearing diameter.		
2. Where web stiffening is fitted on the bearing, a reduction in wall thickness will be considered.		
3. For bearings which are pressure lubricated the clearance must be restricted to enable the pressure to be maintained.		
4. The value of the proposed minimum clearance is to be indicated on plans submitted for approval.		
5. Proposals for higher pressures or other materials will be specially considered on the basis of satisfactory test results.		

**2.4.6** For rudders having an increased diameter of the rudder stock in way of the rudder, the increased diameter is to be maintained to a point as far as practicable above the top of the lowest bearing. The diameter may then be tapered to the diameter required in way of the tiller. The length of the taper is to be at least three times the reduction in diameter. Particular care is to be taken to avoid the formation of a notch at the upper end of the taper, see Fig. 13.2.5.

**2.4.7** Sudden changes of section or sharp corners in way of the rudder coupling, jumping collars and shoulders for rudder carriers, are to be avoided. Jumping collars are not to be welded to the rudder stock. Keyways in the rudder stock are to have rounded ends and the corners at the base of the keyway are to be radiused. For stainless steel liners formed by weld deposit, see 2.8.3.

**2.4.8** The design of the lowest bearing is to comply with the requirements of Table 13.2.6. Fitting of bearings is to be carried out in accordance with the bearing manufacturer's recommendations to ensure that they remain secure under all foreseen operating conditions.

**Table 13.2.7 Maximum surface pressure**

Bearing material	$q_a$ (N/mm <sup>2</sup> ) (see Note 1)
Lignum vitae	2,5
White metal, oil lubricated	4,5
Synthetic material with hardness between 60 and 70 Shore D (see Note 2)	5,5
Steel (see Note 3) and bronze and hotpressed bronze-graphite materials	7,0
NOTES	
1. Proposals for higher pressures will be specially considered on the basis of satisfactory test results. 2. Indentation hardness test at 23°C and with 50% moisture, according to a recognized standard. Synthetic bearing materials are to be of an approved type. 3. Stainless and wear-resistant steel in an approved combination with stock liner.	

# Ship Control Systems

# Part 3, Chapter 13

Section 2

2.4.9 On dredging and reclamation craft classed **A1 protected water service**, the rudder stock diameter may be 84 per cent of that required for ships classed **100A1**.

## 2.5 Rudder construction – Double plated

2.5.1 The scantlings of a double plated rudder are to be not less than required by Table 13.2.8.

**Table 13.2.8 Single and double plated rudder construction**

Type	Item	Requirement
Double plated rudder construction	(1) Rudder side, top and bottom plating	$t = 5,5s_{\min} s_e \sqrt{\left(T + \frac{P_L 10^{-4}}{A_R}\right) k} + 2,5 \text{ mm}$
	(2) Webs vertical and horizontal	$t_W = 0,7t$ from (1) but is not to be less than 8 mm
	(3) Nose plate	$t_N = 1,25t$ from (1) but need not exceed 22 mm
	(4) Mainpiece fabricated rectangular, see Note 1	Breadth and width $\geq \delta_S$ $t_M = 8,5 + 0,56\sqrt{\delta_S} \sqrt[3]{k} \text{ mm}$ Minimum fore and aft extent of side plate = $0,2b_R$ Stress due to bending, see Table 13.2.9
	(5) Mainpiece tubular, see Note 1	Inside diameter $\geq \delta_S$ $t_M$ as for (4) Side plating as for (1) Bending stress as for (4)
	(6) Mainpiece semi-spade (Mariner) type rudders in way of lower pintle regions, see Note 2	Bending moment applied at section 'AA' (see Fig. 13.2.6) by the underhung position to result in stresses not greater than those given in Table 13.2.9
Single plated rudder construction	(7) Blade thickness	$t_B = 0,0015V y_W + 2,5 \text{ mm}$ with a minimum of 10 mm
	(8) Arms	Spacing $\leq 1000 \text{ mm}$ $Z_A = 0,0005 V^2 x_a^2 y_W \text{ cm}^3$ thickness = $t_B$ in mm with a minimum of 10 mm
	(9) Mainpiece	Diameter $\geq \delta_S$ for spade rudders, the lower third may be tapered down to $0,75\delta_S$ mm at the bottom end

### Symbols

$b_R$	= mean breadth of rudder at centreline of stock, in mm
$k$	= see Note 3
$s_e$	= $\sqrt{1,1 - 0,5 \left(\frac{s_{\min}}{s_{\max}}\right)^2}$ but not more than 1,00 if $s_{\max}/s_{\min} \geq 2,5$
$s_{\max}$	= greatest unsupported width of plating, in metres
$s_{\min}$	= smallest unsupported width of plating, in metres
$t$	= thickness, in mm
$t_W$	= thickness of webs, in mm
$t_M$	= thickness of side plating and vertical webs forming mainpiece, in mm
$t_N$	= thickness of nose plate, in mm
$x_a$	= horizontal distance from the aft edge of the rudder to the centre of the rudder stock, in metres
$y_W$	= vertical spacing of rudder arms, in mm. Not to exceed 1000 mm
$A_R$	= rudder area, in m <sup>2</sup>
$P_L$	= rudder force, as defined in 2.1.1
$T$	= as given in Pt 3, Ch 1,6.1
$V$	= as defined in 2.1.1
$Z_A$	= section modulus of arm, in cm <sup>3</sup>
$\delta_S$	= basic stock diameter, given by Table 13.2.3, in mm

### NOTES

1. The value of the basic stock diameter  $\delta_S$ , used in (4) and (5), is that for mild steel, as given in Table 13.2.3.
2. The effective breadth of the side plate may be taken as  $0,16b_R$ .
3. For higher tensile steels, the material factor  $k = 0,78$  for steels with  $\delta_y = 315 \text{ N/mm}^2$  and  $k = 0,72$  for steels with  $\delta_y = 355 \text{ N/mm}^2$ .



2.5.2 The rudder is to be dimensioned such that the stresses do not exceed the permissible stresses given in Table 13.2.9.

2.5.3 In way of rudder couplings and heel pintles, the plating thickness is to be suitably increased.

2.5.4 On semi-spade/mariner type rudders the following items are to be complied with:


- (a) The main vertical web forming the mainpiece is to be continuous over the full depth of the rudder.
- (b) The thickness of the main vertical web is to be not less than two times the thickness required by Table 13.2.8(4) from the top of the rudder to the lower pintle. The thickness is to be not less than required by Table 13.2.8(4) from the lower pintle to approximately a point midway between the lower pintle and bottom of the rudder. Below this the thickness,  $t_2$ , is to be not less than the thickness required by Table 13.2.8(2). See Fig. 13.2.6.

- (c) Where an additional continuous main vertical web is arranged to form an efficient box mainpiece structure, the thickness of each web is to be not less than that required by Table 13.2.8(4) from the top of the rudder to approximately a point midway between the lower pintle and bottom of the rudder. Below this the thickness,  $t_2$ , is not to be less than that required by Table 13.2.8(2).
- (d) The internal radius,  $r$ , of the cut-out for the rudder pintle is to be as large as practicable. See Fig. 13.2.6.
- (e) To reduce the notch effect at the corners of the cut-out for the lower pintle, an insert plate 1,6 times the Rule thickness of the side plating is to be fitted. The insert plate is to extend aft of the main vertical web and to have well rounded corners.

2.5.5 Adequate hand or access holes are to be arranged in the rudder plating in way of pintles as required, and the rudder plating is to be reinforced locally in way of these openings. Continuity of the modulus of the rudder mainpiece is to be maintained in way of the openings.

Table 13.2.9 Permissible stresses for rudder blade scantlings

Item	Permissible stresses, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )		
	Bending stress	Shear stress	Equivalent stress
Rudder blades clear of cut-outs, see Fig. 13.2.2	$\frac{110}{k} \left( \frac{11,2}{k} \right)$	$\frac{50}{k} \left( \frac{5,1}{k} \right)$	$\frac{120}{k} \left( \frac{12,2}{k} \right)$
Rudder blades in way of cut-outs, see Fig. 13.2.2 and Note	$\frac{75}{k} \left( \frac{7,6}{k} \right)$	$\frac{50}{k} \left( \frac{5,1}{k} \right)$	$\frac{100}{k} \left( \frac{10,2}{k} \right)$
Symbols			
$k$ is as defined in 1.2.1			
NOTE Requirements in way of cut-outs apply to semi-spade/mariner type rudders.			



# Ship Control Systems

## Part 3, Chapter 13

Section 2

2.5.6 Connection of rudder side plating to vertical and horizontal webs, where internal access for welding is not practicable, is to be by means of slot welds on to flat bars on the webs. The slots are to have a minimum length of 75 mm and, in general, a minimum width of twice the side plating thickness. The ends of the slots are to be rounded. The space between the slots is not to exceed 150 mm and welding is to be based on a weld factor of 0,44.

2.5.7 For testing of rudders, see Table 1.8.1 in Chapter 1.

2.5.8 Where the fabricated mainpiece of a spade rudder is connected to the horizontal coupling flange by welding, a full penetration weld is required.

### 2.6 Rudder construction – Single plated

2.6.1 The scantlings of a single plated rudder are to be not less than required by Table 13.2.8.

2.6.2 Rudder arms are to be efficiently attached to the mainpiece.

### 2.7 Rudder couplings

2.7.1 Rudder coupling design is to be in accordance with Table 13.2.10.

2.7.2 Where coupling bolts are required they are to be fitted bolts. Suitable arrangements are to be made to lock the nuts.

2.7.3 For rudders with horizontal coupling arrangements the rudder stock should be forged when the stock diameter exceeds 350 mm. Where the stock diameter does not exceed 350 mm the rudder stock may be either forged or fabricated. Where the upper flange is welded to the rudder stock, a full penetration weld is required and its integrity is to be confirmed by non-destructive examination. The flange material is to be from the same welding materials group as the stock. Such rudder stocks are to be subjected to a furnace post-weld heat treatment (PWHT) after completion of all welding operations. For carbon or carbon manganese steels, the PWHT temperature is not to be less than 600°C.

2.7.4 For a spade rudder, the fillet radius between the rudder stock and the flange is to conform to the requirements of Fig. 13.2.7. Where space permits between the upper face of the flange and the lowest main bearing, it is preferable to use a compound fillet design of the parabolic or Morgenbrod form having similar dimensions to those of Fig. 13.2.7. Alternative arrangements will be specially considered.

2.7.5 The connecting bolts for coupling the rudder to the rudder stock are to be positioned with sufficient clearance to allow the fitting and removal of the bolts and nuts without contacting the palm radius,  $R$ , see Fig. 13.2.8(a). The surface forming the palm radius is to be free of hard and sharp corners and is to be machined smooth to the Surveyor's satisfaction. The surface in way of bolts and nuts is to be machined smooth to the Surveyor's satisfaction.

2.7.6 For spade rudders fitted with a fabricated rectangular mainpiece, the mainpiece is to be designed with its forward and aft transverse sections at equal distances forward and aft of the rudder stock transverse axis, see Fig. 13.2.8(b).

2.7.7 Where a rudder stock is connected to a rudder by a keyless fitting, the rudder is to be a good fit on the rudder stock cone. During the fit-up, and before the push-up load is applied, an area of contact of at least 90 per cent of the theoretical area of contact is to be achieved, and this is to be evenly distributed. The relationship of the rudder to stock at which this occurs is to be marked, and the push-up then measured from that point. The upper edge of the upper mainpiece bore is to have a slight radius. After final fitting of the stock to the rudder, positive means are to be used for locking the securing nut to the stock.

2.7.8 Where a keyed conical fitting of a rudder stock to a rudder is proposed, a securing nut is to be provided. Minimum dimensions for the securing nut are given in Table 13.2.10. After final fitting of the stock to the rudder, positive means are to be used for locking this nut.

2.7.9 Guidelines for keys and keyways are given in Table 13.2.10.

### 2.8 Pintles

2.8.1 Rudder pintles and their bearings are to comply with the requirements of Table 13.2.11.

2.8.2 The distance between the lowest rudder stock bearing and the upper pintle should be as short as possible.

2.8.3 Where liners are fitted to pintles, they are to be shrunk on or otherwise efficiently secured. If liners are to be shrunk on, the shrinkage allowance is to be indicated on the plans. Where liners are formed by stainless steel weld deposit, the pintles are to be of weldable quality steel and details of the procedure are to be submitted, see also 2.9.7.

2.8.4 The bottom pintle on semi-spade (Mariner) type rudders and all pintles over 500 mm in diameter are:

- (a) if inserted into their sockets from below, to be keyed to the rudder or sternframe as appropriate or to be hydraulically assembled, with the nut adequately locked, or
- (b) if inserted into their sockets from above, to be provided with an appropriate locking device, the nut being adequately secured.

2.8.5 Fitting of pintle bearings is to be carried out in accordance with the bearing manufacturer's recommendations to ensure that they remain secure under all foreseen operating conditions.

2.8.6 Where an **\*IWS** (In-water Survey) notation is to be assigned (see Pt 1, Ch 2, 2.3.11), means are to be provided for ascertaining the rudder pintle and bush clearances and for verifying the security of the pintles in their sockets with the vessel afloat.

## Ship Control Systems

## Part 3, Chapter 13

## Section 2

Table 13.2.10(a) Rudder couplings to stock – Bolted couplings

Item	Requirement	
	Horizontal coupling	Vertical coupling
Number of bolts in coupling	$n \geq 6$	$n \geq 8$
Diameter of coupling bolts	$\delta_b = 0,62 \sqrt{\frac{\delta_S^3 k_b}{l_a n k_S}}$	$\delta_b = 0,81 \delta_S \sqrt{\frac{k_b}{n k_S}}$
First moment of area of bolts about centre of coupling	$m = 0,00071 n \delta_S \delta_b^2 \sqrt{\frac{k_b}{k_S}}$	$m = 0,00043 \delta_S^3 \sqrt{\frac{k_b}{k_S}}$
Thickness of coupling flange	$t_f = \delta_b \sqrt{\frac{k_b}{k_S}}$ (see Notes 1 & 2)	$t_f = \delta_b$
Stress concentration factor for as built scantlings	$\alpha_{as\ built} \leq \alpha_{max}$ (see Note 3)	—
Maximum allowable stress concentration factor	$\alpha_{max} = (53,82 - 35,29 k_{max}) \frac{\delta_S^3}{h P_L 10^3} - \left(1,8 - 6,3 \frac{R}{\delta_S}\right) \frac{t_f - t_{fa}}{t_{fa}}$ (see Note 3)	—
Width of flange material outside the bolt holes	$w_f = 0,67 \delta_b$	$w_f = 0,67 \delta_b$
Symbols		
<p><math>\alpha_{as\ built}</math> = stress concentration factor for as built scantlings</p> <p><math>= \frac{0,73}{\sqrt{\frac{R}{\delta_S}}}</math></p> <p><math>\alpha_{max}</math> = maximum allowable stress concentration factor</p> <p><math>\delta_b</math> = diameter of coupling bolts, in mm</p> <p><math>\delta_S</math> = basic stock diameter as defined in Table 13.2.3, in mm</p> <p><math>b_f</math> = breadth of the flange, in mm</p> <p><math>h</math> = vertical distance, in metres, between the centre of pressure and the centre point of the palm radius, see Fig. 13.2.8</p> <p><math>k_b</math> = coupling bolt material factor, see 2.4.2</p> <p><math>k_{max}</math> = the greater of <math>k_S</math> and <math>k_f</math></p> <p><math>k_f</math> = upper coupling flange material factor, see 2.4.2</p> <p><math>k_S</math> = rudder stock material factor, see 2.4.2</p> <p><math>l_a</math> = the mean of the horizontal distances between the centres of the bolts and the centre of the coupling, in mm</p> <p><math>m</math> = first moment of area of bolts about a longitudinal axis through centre of coupling, in cm<sup>3</sup></p> <p><math>n</math> = number of bolts in coupling</p> <p><math>P_L</math> = lateral force on rudder as defined in 2.1.1, in N (tonne-f)</p> <p><math>R</math> = palm radius, in mm, between the rudder stock and connection flange, see 2.7.4 and 2.7.5.</p> <p><math>t_f</math> = minimum thickness of coupling flange, in mm</p> <p><math>t_{fa}</math> = as built flange thickness, in mm</p> <p><math>w_f</math> = width of flange material outside the bolt holes, in mm</p>		
<p>NOTES</p> <p>1. For spade rudders with horizontal couplings, <math>t_f</math> is not to be less than <math>0,33 \delta_S \sqrt[3]{k_S}</math>. The mating plate on the rudder is to have the same thickness as the flange on the stock</p> <p>2. For a twin spade rudder arrangement with single screw where the rudders are within the slipstream of the propeller:</p> <p>(a) the thickness of the palm is not to be less than <math>0,35 \delta_S \sqrt[3]{k_S}</math></p> <p>(b) where the stock is welded to the palm plate, the stock diameter, <math>\delta_S</math> is to be increased by 14 per cent.</p> <p>3. This requirement is applicable only for spade rudders with horizontal couplings, see Fig. 13.2.6.</p>		

2.8.7 For axle type rudder support used with Simplex rudders, see Ch 6,7.

## 2.9 Ancillary items

2.9.1 Internal surfaces of double plate rudders are to be efficiently coated, and means for draining the rudder are to be provided.

# Ship Control Systems

# Part 3, Chapter 13

Section 2

**Table 13.2.10(b) Rudder couplings to stock – Conical couplings** (see continuation)

Item	Requirement
Taper of conical coupling on the diameter	$\theta_t \leq \frac{1}{K_1}$
Length of taper	$l_t \geq 1,5\delta_S$
Required mean grip stress – keyless connection	$p_M = \frac{P_R \theta_t \delta_{CTM} + 4M_T 10^3 \sqrt{K_2 \left( \left[ \frac{P_R \delta_{CTM}}{2000M_T} \right]^2 + 1 \right) - \left( \frac{\theta_t}{2} \right)^2}}{5,66\delta_{CTM}^2 l_t \left( K_2 - \left( \frac{\theta_t}{2} \right)^2 \right)}$
Required mean grip stress – keyed connection	$p_M = 20$
Corresponding push-up of rudder stock	$w = \frac{9,6 \cdot 10^{-6} p_M \delta_{CTM}}{\theta_t (1 - f_M^2)} \left( \frac{0,95 \cdot 10^{-4} p_M \delta_{CTM}}{\theta_t (1 - f_M^2)} \right)$
Corresponding push-up load	Approximately equal to $P_U = 2,83p_M l_t \delta_{CTM} \left( K_3 + \frac{\theta_t}{2} \right)$
Corresponding pull-off load	Approximately equal to $P_O = 2,83p_M l_t \delta_{CTM} \left( K_3 - \frac{\theta_t}{2} \right)$
Minimum yield stress of stock and gudgeon	$\sigma_o = \frac{123 \cdot 500 w \theta_t \sqrt{3 + f^4}}{\delta_{CT}} \left( \frac{12600 w \theta_t \sqrt{3 + f^4}}{\delta_{CT}} \right)$
Recommended minimum effective sectional area of the key in shear	$A_{key} = \frac{M_T k_{min}}{3,3\delta_{CTM}} \text{ (see Note)}$
Minimum thickness of key	$\delta_{key} = \frac{67A_{key}}{H}$
Minimum dimensions of securing nut	$\delta_n = 1,2\delta_{SU} \text{ or } \begin{matrix} \delta_g = 0,65\delta_S \\ 1,5\delta_g \text{ whichever is the greater} \\ h_n = 0,6\delta_g \end{matrix}$

2.9.2 Where it is intended to fill the rudder with plastic foam, details of the foam are to be submitted.

2.9.3 Suitable arrangements are to be provided to prevent the rudder from lifting.

2.9.4 Where a bow rudder is fitted for use when navigating astern, a locking device is to be arranged to ensure that the rudder is kept in the central position when the ship is navigating ahead.

2.9.5 Where the weight of the rudder is supported by a carrier bearing attached to the rudder head, the structure in way is to be adequately strengthened. The plating under all rudder head bearings or rudder carriers is to be increased in thickness.

2.9.6 In rudder trunks which are open to the sea, a seal or stuffing box is to be fitted above the deepest load waterline, to prevent water from entering the steering gear compartment and the lubricant from being washed away from the rudder carrier. If the top of the rudder trunk is below the deepest waterline, two separate stuffing boxes are to be provided. Rudder trunk boundaries where exposed to the sea are to have a corrosion protection coating applied in accordance with the manufacturer's instructions.

2.9.7 Where it is proposed to use stainless steel for liners or bearings for rudder stocks and/or pintles, the chemical composition is to be submitted for approval. Synthetic rudder bearing materials are to be of a type approved by Lloyd's Register (hereinafter referred to as 'LR'). When this type of lining material is used, arrangements to ensure an adequate supply of sea-water to the bearing are to be provided.

**Table 13.2.10(b) Rudder couplings to stock – Conical couplings** (conclusion)

Symbols				
$h_n$ = minimum required length of securing nut, in mm, see Fig. 13.2.9 $f = \frac{\delta_{CT}}{\delta_{GH}}$ $f_M = \frac{\delta_{CTM}}{\delta_{GHM}}$ $k_{min}$ = taken as $k_0$ , where $\sigma_0$ is the minimum nominal upper yield point of the key, stock or coupling material, in N/mm <sup>2</sup> , whichever is less $k_0$ = material factor as defined in Table 13.2.3, for the appropriate item $l_t$ = length of taper, in mm $\rho_M$ = required mean grip stress, in N/mm <sup>2</sup> $w$ = corresponding push-up of rudder stock, in mm $A_{key}$ = recommended minimum effective sectional area of the key in shear, in cm <sup>2</sup> $H$ = length of the key, in mm $M_T$ = rudder torque, in Nm, as given in Table 13.2.5 $P_R$ = effective weight of rudder, in N (kgf) $P_u, P_o$ = corresponding push-up, pull-off loads respectively, in N (kgf) $\delta_g$ = minimum external thread diameter, in mm, see Fig. 13.2.9 $\delta_n$ = minimum outer diameter of nut, in mm, see Fig. 13.2.9 $\delta_{CT}$ = diameter of coupling taper in any position, in mm $\delta_{CTM} = \frac{\delta_S + \delta_{SU}}{2}$ $\delta_{GH}$ = external diameter of gudgeon housing at any position, in mm $\delta_{GHM}$ = mean external diameter of gudgeon housing, in mm $\delta_{key}$ = minimum thickness of key. See Fig. 13.2.9 $\delta_S$ = basic stock diameter as defined in Table 13.2.3, in mm $\delta_{SU}$ = see Fig. 13.2.9, in mm $\sigma_0$ = minimum yield stress of stock and gudgeon material, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) $\sigma_0$ is not to be taken greater than 70 per cent of the ultimate tensile strength or 450 N/mm <sup>2</sup> (45,9 kgf/mm <sup>2</sup> ) whichever is the lesser $\theta_t$ = taper of conical coupling, on the diameter, e.g. $\frac{1}{15} = 0,067$				
$K_1, K_2, K_3$ = constants depending on the type of assembly adopted as follows:				
Type of assembly		$K_1$	$K_2$	$K_3$
Oil injection	With key	12	—	0,025
	Without key	15	0,0036	0,025
Dry fit method	With key	8	—	0,170
	Without key	12	0,0072	0,170
<b>NOTE</b> The keyway is to have a smooth fillet at the bottom of the keyway. The radius of the fillet is to be at least 0,0125 of the diameter of the rudder stock at the top of the cone.				





Fig. 13.2.7 Rudder stock horizontal flange fillet radius for spade rudders

**Table 13.2.11 Pintle requirements**

Item	Requirement	
(1) Pintle diameter (measured outside liner if fitted)	$\delta_{PL} = 0,35 \sqrt{B k_o}$ mm	
(2) Pintle taper	Method of assembly	Taper (on diameter)
	Keyed and other manually assembled pintles	1:8 – 1:12
	Pintles mounted with oil injection and hydraulic nut	1:12 – 1:20
Symbols		
<p> <math>b</math> = distance in metres, from centroid of rudder area to the centre of lowest main bearing, see Fig. 13.2.4  <math>c</math> = distance, in metres, from centre of bearing of lower pintle to the centre of lowest main bearing, see Fig. 13.2.4  <math>k_o</math> = as defined in Table 13.2.3 or 13.2.4  <math>B</math> = bearing force, in N. If direct calculations are not carried out, the bearing force at various positions can be taken as:  <math>B_{1L} = \frac{b}{c} P_L</math> for single pintle rudders and lower pintle of semi-spade rudders  <math>B_{1U} = \left(1 - \frac{b}{c}\right) P_L</math> at upper pintle on semi-spade rudder. <math>B_{1U}</math> is not to be less than <math>0,35P_L</math>  <math>B = \frac{1}{N_{PL}} P_L</math> for rudders with two or more pintles (except semi-spade rudders)  <math>N_{PL}</math> = number of pintles on the rudder  <math>P_L</math> = rudder force, as defined in 2.1.1 </p>		




Fig. 13.2.9 Conical coupling

### Section 3 Fixed and steering nozzles

#### 3.1 General

3.1.1 The requirements for scantlings for fixed and steering nozzles are given, for guidance only, in 3.2 to 3.4 and Table 13.3.1.

3.1.2 The requirements, in general, apply to nozzles with a numeral not greater than 200, see Table 13.3.1. Nozzles exceeding this value will be specially considered.

#### 3.2 Nozzle structure

3.2.1 For basic scantlings of the structure, see Table 13.3.1, in association with Fig. 13.3.1.

3.2.2 The shroud plating in way of the propeller tips is to be carried well forward and aft of this position, due allowance being made on steering nozzles for the rotation of the nozzle in relation to the propeller.

3.2.3 Fore and aft webs are to be fitted between the inner and outer skins of the nozzle. Both sides of the headbox and pintle support structure are to be connected to fore and aft webs of increased thickness. For thicknesses, see Table 13.3.1.

Table 13.3.1 Nozzle construction requirements

Item	Requirement
(1) Nozzle numeral	$N_N = 0,01P\delta_p$ ( $N_N = 0,00736H\delta_p$ )
(2) Shroud plating in way of propeller blade tips	For $N_N \leq 63t_s =$ ( $11 + 0,1N_N$ ) mm For $N_N > 63t_s =$ ( $14 + 0,052N_N$ ) mm
(3) Shroud plating clear of blade tips, flare and cone plating, wall thickness of leading and trailing edge members	$t_p = (t_s - 7)$ mm but not less than 8 mm
(4) Webs and ring webs	As item (3) except in way of headbox and pintle support where $t_w = (t_s + 4)$ mm
(5) Nozzle stock	Combined stresses in stock at lower bearing $\leq 92,7$ N/mm <sup>2</sup> (9,45 kgf/mm <sup>2</sup> ) Torsional stress in upper stock $\leq 62,0$ N/mm <sup>2</sup> (6,3 kgf/mm <sup>2</sup> )
(6) Solepiece and strut	Bending stresses not to exceed 70,0 N/mm <sup>2</sup> (7,1 kgf/mm <sup>2</sup> )
Symbols	
$N_N$ = a numeral dependent on the nozzle requirements $P$ = power transmitted to the propellers, in kW $(H$ = power transmitted to the propellers, in shp) $\delta_p$ = diameter of the propeller, in metres $t_s$ = thickness of shroud plating in way of propeller tips, in mm $t_p$ = thickness of plating, in mm $t_w$ = thickness of webs and ring webs in way of headbox and pintle support, in mm	
NOTE Thicknesses given are for mild steel. Reductions in thickness will be considered for certain stainless steels.	




Fig. 13.3.1 Nozzle construction



# Ship Control Systems

## Part 3, Chapter 13

Sections 3 to 7

3.2.4 The transverse strength of the nozzle is to be maintained by the fitting of ring webs. Two ring webs are to be fitted in nozzles not exceeding 2,5 m diameter. Nozzles between 2,5 and 3,0 m in diameter are generally to have two full ring webs and a half-depth web supporting the flare plating. The number of ring webs is to be increased as necessary on nozzles exceeding 3,0 m in diameter. Where ring webs are increased in thickness in way of the headbox and pintle support structure in accordance with Table 13.3.1, the increased thickness is to be maintained to the adjacent fore and aft web.

3.2.5 Local stiffening is to be fitted in way of the top and bottom supports which are to be integrated with the webs and ring webs. Continuity of bending strength is to be maintained in these regions.

3.2.6 Fin plating thickness should be not less than the cone plating, and the fin should be adequately reinforced. Solid fins should be not less than 25 mm thick.

3.2.7 Care is to be taken in the manufacture of the nozzle to ensure its internal preservation and watertightness. The preservation and testing are to be as required for rudders, see 2.6 and Table 1.8.1 in Chapter 1.

### 3.3 Nozzle stock and solepiece

3.3.1 Stresses, derived using the maximum side load on the nozzle and fin acting at the assumed centre of pressure, are not to exceed the values given in Table 13.3.1, in both the ahead and astern conditions.

### 3.4 Ancillary items

3.4.1 The diameter and first moment of area about the stock axis of coupling bolts and the diameter of pintles, are to be derived from 2.4 and 2.5.

3.4.2 Suitable arrangements are to be provided to prevent the steering nozzle from lifting.

## Section 4 Steering gear and allied systems

### 4.1 General

4.1.1 For the requirements of steering gear, see Pt 5, Ch 19.

## Section 5 Bow and stern thrust unit structure

### 5.1 Unit wall thickness

5.1.1 The wall thickness of the unit is, in general, to be in accordance with the manufacturer's practice, but is to be not less than either the thickness of the surrounding shell plating plus 10 per cent or 15 mm, whichever is greater.

### 5.2 Framing

5.2.1 The unit is to be framed to the same standard as the surrounding shell plating.

5.2.2 The unit is to be adequately supported and stiffened.

## Section 6 Stabilizer structure

### 6.1 Fin stabilizers

6.1.1 The box into which the stabilizers retract is to have perimeter plating of the same thickness as the surrounding Rule shell plating plus 2 mm, but is to be not less than 12,5 mm, and is to be stiffened to the same standard as the shell.

6.1.2 The stabilizer machinery and surrounding structure are to be adequately supported and stiffened. Where bending stresses are induced in the structure under fatigue conditions the maximum stress is not to exceed 39,0 N/mm<sup>2</sup> (4 kgf/mm<sup>2</sup>).

### 6.2 Stabilizer tanks

6.2.1 The general structure of the tank is to comply with the Rule requirements for deep tanks. Sloshing forces in the tank structure are to be taken into account. Where such forces are likely to be significant, the scantlings will be required to be verified by additional calculation.

## Section 7 Equipment

### 7.1 General

7.1.1 To entitle a ship to the figure **1** in its character of classification, equipment in accordance with the requirements of Table 13.7.1 is to be provided. The regulations governing the assignment of the character figure **1** for equipment are given in Pt 1, Ch 2,2.



# Ship Control Systems

# Part 3, Chapter 13

Section 7

**Table 13.7.1** Equipment requirements (conclusion)

Ship type	Service	Required equipment
Tugs	Unrestricted and restricted service	(6) See Table 13.7.2 using $N_C$ except as stated below Stream anchor – not required Towlines – adequate for tug's maximum bollard pull with factor of safety $\geq 2,0$
	Service restricted, see Pt 1, Ch 2,2.3.7 to 2.3.10	(7) See Table 13.7.2 using $N_C$ Mass of bower anchor } reduced to correspond to two Equipment Letters below that required for $N_C$ Chain cable diameter }
	Protected waters service, see Pt 1, Ch 2,2.3.6	(8) See Table 13.7.2 using $N_A$ Mass of bower anchor } $N_A = 0,5N_C$ Chain cable diameter } Chain cable length = 0,5 times length required by $N_A$ Where $N_C < 90$ , the requirements for anchors and chain cable will be specially considered
Offshore supply ships	Unrestricted service	(9) See Tables 13.7.2 and 13.7.3, using $N_C$ Chain cable length and diameter – increased to correspond to two Equipment Letters above that required for $N_C$
Manned barges and pontoons	Service restricted, see Pt 1, Ch 2,2.3.7 to 2.3.10	(10) As item (3) in this Table
Unmanned barges and pontoons	Unrestricted service, or service restricted, see Pt 1, Ch 2,2.3.7 to 2.3.10	(11) See Tables 13.7.2 and 13.7.3, using $N_C$ and $N_A$ as appropriate Anchors $\left\{ \begin{array}{l} L < 30 \text{ m, no anchor need be carried} \\ L \geq 30 \text{ m, one anchor to be fitted} \end{array} \right.$ Anchor cable length – greater of 40 m or $2L$ m (a) Unrestricted service: mass of anchors and chain cable diameters as for $N_C$ (b) Protected water service, see Pt 1, Ch 2,2.3.6: mass of anchors and chain cable diameters, $N_A = 0,5N_C$ (c) Service restriction, see Pt 1, Ch 2,2.3.7 to 2.3.10: mass of anchor and chain cable diameter, $N_A$ reduced to correspond to two Equipment Letters below $N_C$ Mooring lines $\left\{ \begin{array}{l} L < 65 \text{ m, two mooring lines to be fitted} \\ L \geq 65 \text{ m, three mooring lines to be fitted} \end{array} \right.$ length of mooring lines to be the greater of $2L$ or 80 m, but need not exceed that for manned ships Strength of each line to be that required by $N_C$ Consideration will be given to proposals to omit anchoring equipment in association with the assignment of the character figure <b>1</b> , see Pt 1, Ch 2,2.2. Where $L < 65$ m consideration will be given to the omission of anchoring and mooring equipment, in which case the character letter <b>N</b> will be assigned in the character of classification, see Pt 1, Ch 2,2.2
Symbols		
$L$ = length of ship as defined in Ch 1,6.1 $N_A$ = actual equipment number to be used, if different from $N_C$ $N_C$ = calculated equipment number for ship as required by Ch 1,7 $T_D$ = maximum depth at which ship is designed to dredge, in metres		

## 7.2 Anchors

**7.2.1** Anchors are to be of an approved design. The design of all anchor heads is to be such as to minimize stress concentrations, and in particular, the radii on all parts of cast anchor heads are to be as large as possible, especially where there is considerable change of section.

**7.2.2** Anchors which must be specially laid the right way up, or which require the fluke angle or profile to be adjusted for varying types of sea bed, will not generally be approved for normal ship use, but may be accepted for offshore units, floating cranes, etc. In such cases suitable tests may be required.

7.2.3 The mass of each bower anchor given in Table 13.7.2 is for anchors of equal mass. The masses of individual anchors may vary by  $\pm 7$  per cent of the masses given in the Table, provided that the total mass of the anchors is not less than would have been required for anchors of equal mass.

7.2.4 The mass of the head, including pins and fittings, of an ordinary stockless anchor is to be not less than 60 per cent of the total mass of the anchor.

7.2.5 When stocked bower or stream anchors are to be used, the mass 'ex-stock' is to be not less than 80 per cent of the mass given in Table 13.7.2 for ordinary stockless bower anchors. The mass of the stock is to be 25 per cent of the total mass of the anchor, including the shackle, etc., but excluding the stock.

## 7.3 High holding power anchors

7.3.1 When high holding power anchors are used as bower anchors, the mass of each such anchor may be 75 per cent of the mass given in the Table for ordinary stockless bower anchors.

## 7.4 Chain cables

7.4.1 Chain cables may be of mild steel, special quality steel or extra quality steel in accordance with the requirements of Chapter 10 of the Rules for Materials and are to be graded in accordance with Table 13.7.5.

7.4.2 Grade U1 material having a tensile stress of less than 400 N/mm<sup>2</sup> (41 kgf/cm<sup>2</sup>) is not to be used in association with high holding power anchors. Grade U3 material is to be used only for chain 20,5 mm or more in diameter.

7.4.3 Where stream anchors are used in association with chain cable, this cable may be either stud link or short link.

7.4.4 The form and proportion of links and shackles are to be in accordance with Chapter 10 of the Rules for Materials.

7.4.5 Where Owners require equipment for anchoring at depths greater than 82,5 m, it is their responsibility to specify the appropriate total length of the chain cable required for this purpose. In such cases, consideration can be given to dividing the chain cable into two unequal lengths.

## 7.5 Towlines and mooring lines

7.5.1 **Ships under 90 m** require mooring lines as specified in Table 13.7.3. Towlines are not required for classification and the details given in the Table are for guidance purposes only. Mooring lines may be of wire, natural fibre or synthetic fibre. The diameter, construction and specification of wire or natural fibre mooring lines are to comply with the requirements of Chapter 10 of the Rules for Materials. Where it is proposed to use synthetic fibre ropes, the size and construction will be specially considered.

7.5.2 The lengths of individual mooring lines in Table 13.7.3 may be reduced by up to seven per cent of the Table length, provided that the total length of mooring lines is not less than would have resulted had all lines been of equal length.

7.5.3 **Ships 90 m and over** in length do not require towlines and mooring lines as a classification item. It is recommended, however, that the sum of the strengths of all the mooring lines supplied to such ships should be not less than the Rule breaking load of one anchor cable as required by Table 13.7.2, based on Grade U2 chain for ships with equipment numbers up to 12400 and on Grade U3 chain for ships with higher equipment numbers. On ships regularly using exposed berths, twice the above total strength of mooring ropes is desirable. Where a separate towline is supplied, it is recommended that its strength be not less than 40 per cent of the strength of the anchor cable.

7.5.4 It is recommended that not less than four mooring lines be carried on ships exceeding 90 m in length, and not less than six mooring lines on ships exceeding 180 m in length. The length of mooring lines should be not less than 200 m, or the length of the ship, whichever is the lesser.

7.5.5 For ease of handling, fibre ropes should be not less than 20 mm diameter. All ropes having breaking strengths in excess of 736,0 kN (75,0 tonne-f) and used in normal mooring operations are to be handled by, and stored on, suitably designed winches. Alternative methods of storing should give due consideration to the difficulties experienced in manually handling ropes having breaking strengths in excess of 490,0 kN (50,0 tonne-f).

7.5.6 Mooring winches should be fitted with drum brakes, the strength of which is sufficient to prevent unreeling of the mooring line when the rope tension is equal to 80 per cent of the breaking strength of the rope as fitted on the first layer on the winch drum.

## 7.6 Windlass design and testing

7.6.1 A windlass of sufficient power and suitable for the size of chain is to be fitted to the ship. Where Owners require equipment significantly in excess of Rule requirements, it is their responsibility to specify increased windlass power.

## Ship Control Systems

## Part 3, Chapter 13

Section 7

Table 13.7.2 Equipment – Bower anchors and chain cables

Equipment number		Equipment Letter	Stockless bower anchors		Stud link chain cables for bower anchors			
Exceeding	Not exceeding		Number	Mass of anchor, in kg	Total length, in metres	Diameter, in mm		
						Mild steel (Grade 1 or U1)	Special quality steel (Grade U2)	Extra special quality steel (Grade U3)
50	70	A	2	180	220	14	12,5	—
70	90	B	2	240	220	16	14	—
90	110	C	2	300	247,5	17,5	16	—
110	130	D	2	360	247,5	19	17,5	—
130	150	E	2	420	275	20,5	17,5	—
150	175	F	2	480	275	22	19	—
175	205	G	2	570	302,5	24	20,5	—
205	240	H	2	660	302,5	26	22	20,5
240	280	I	2	780	330	28	24	22
280	320	J	2	900	357,5	30	26	24
320	360	K	2	1020	357,5	32	28	24
360	400	L	2	1140	385	34	30	26
400	450	M	2	1290	385	36	32	28
450	500	N	2	1440	412,5	38	34	30
500	550	O	2	1590	412,5	40	34	30
550	600	P	2	1740	440	42	36	32
600	660	Q	2	1920	440	44	38	34
660	720	R	2	2100	440	46	40	36
720	780	S	2	2280	467,5	48	42	36
780	840	T	2	2460	467,5	50	44	38
840	910	U	2	2640	467,5	52	46	40
910	980	V	2	2850	495	54	48	42
980	1060	W	2	3060	495	56	50	44
1060	1140	X	2	3300	495	58	50	46
1140	1220	Y	2	3540	522,5	60	52	46
1220	1300	Z	2	3780	522,5	62	54	48
1300	1390	A†	2	4050	522,5	64	56	50
1390	1480	B†	2	4320	550	66	58	50
1480	1570	C†	2	4590	550	68	60	52
1570	1670	D†	2	4890	550	70	62	54
1670	1790	E†	2	5250	577,5	73	64	56
1790	1930	F†	2	5610	577,5	76	66	58
1930	2080	G†	2	6000	577,5	78	68	60
2080	2230	H†	2	6450	605	81	70	62
2230	2380	I†	2	6900	605	84	73	64
2380	2530	J†	2	7350	605	87	76	66
2530	2700	K†	2	7800	632,5	90	78	68
2700	2870	L†	2	8300	632,5	92	81	70
2870	3040	M†	2	8700	632,5	95	84	73
3040	3210	N†	2	9300	660	97	84	76
3210	3400	O†	2	9900	660	100	87	78
3400	3600	P†	2	10 500	660	102	90	78
3600	3800	Q†	2	11 100	687,5	105	92	81
3800	4000	R†	2	11 700	687,5	107	95	84
4000	4200	S†	2	12 300	687,5	111	97	87
4200	4400	T†	2	12 900	715	114	100	87
4400	4600	U†	2	13 500	715	117	102	90
4600	4800	V†	2	14 100	715	120	105	92
4800	5000	W†	2	14 700	742,5	122	107	95
5000	5200	X†	2	15 400	742,5	124	111	97
5200	5500	Y†	2	16 100	742,5	127	111	97
5500	5800	Z†	2	16 900	742,5	130	114	100
5800	6100	A*	2	17 800	742,5	132	117	102
6100	6500	B*	2	18 800	742,5	—	120	107
6500	6900	C*	2	20 000	770	—	124	111
6900	7400	D*	2	21 500	770	—	127	114
7400	7900	E*	2	23 000	770	—	132	117
7900	8400	F*	2	24 500	770	—	137	122
8400	8900	G*	2	26 000	770	—	142	127
8900	9400	H*	2	27 500	770	—	147	132
9400	10 000	I*	2	29 000	770	—	152	132
10 000	10 700	J*	2	31 000	770	—	157	137
10 700	11 500	K*	2	33 000	770	—	157	142
11 500	12 400	L*	2	35 500	770	—	162	147
12 400	13 400	M*	2	38 500	770	—	—	152
13 400	14 600	N*	2	42 000	770	—	—	157
14 600	16 000	O*	2	46 000	770	—	—	162

## Ship Control Systems

## Part 3, Chapter 13

Section 7

**Table 13.7.3 Equipment – Stream anchors, stream wires, towlines and mooring lines** (continued)

Equipment number		Equipment Letter	Mass of stock-less stream anchor, in kg	Stream wire or chain		Towline <sup>(1)</sup>		Mooring lines		
Exceeding	Not exceeding			Minimum length in metres	Minimum breaking strength, in kN (tonne-f)	Minimum length in metres	Minimum breaking strength, in kN	Number	Minimum length of each line, in metres	Minimum breaking strength, in kN (tonne-f)
50	70	A	60	80	64,7 (6,60)	180	98	3	80	34
70	90	B	80	85	73,5 (7,50)	180	98	3	100	37
90	110	C	100	85	81,4 (8,30)	180	98	3	110	39
110	130	D	120	90	89,2 (9,10)	180	98	3	110	44
130	150	E	140	90	98,1 (10,00)	180	98	3	120	49
150	175	F	165	90	107,9 (11,00)	180	98	3	120	54
175	205	G	190	90	117,7 (12,00)	180	112	3	120	59
205	240	H	—	—	—	180	129	4	120	64
240	280	I	—	—	—	180	150	4	120	69
280	320	J	—	—	—	180	174	4	140	74
320	360	K	—	—	—	180	207	4	140	78
360	400	L	—	—	—	180	224	4	140	88
400	450	M	—	—	—	180	250	4	140	98
450	500	N	—	—	—	180	277	4	140	108
500	550	O	—	—	—	190	306	4	160	123
550	600	P	—	—	—	190	338	4	160	132
600	660	Q	—	—	—	190	370	4	160	147
660	720	R	—	—	—	190	406	4	160	157
720	780	S	—	—	—	190	441	4	170	172
780	840	T	—	—	—	190	479	4	170	186
840	910	U	—	—	—	190	518	4	170	201
910	980	V	—	—	—	190	559	4	170	216
980	1060	W	—	—	—	200	603	4	180	230
1060	1140	X	—	—	—	200	647	4	180	250
1140	1220	Y	—	—	—	200	691	4	180	270
1220	1300	Z	—	—	—	200	738	4	180	284
1300	1390	A†	—	—	—	200	786	4	180	309
1390	1480	B†	—	—	—	200	836	4	180	324
1480	1570	C†	—	—	—	220	888	5	190	324
1570	1670	D†	—	—	—	220	941	5	190	333
1670	1790	E†	—	—	—	220	1024	5	190	353
1790	1930	F†	—	—	—	220	1109	5	190	378
1930	2080	G†	—	—	—	220	1168	5	190	402
2080	2230	H†	—	—	—	240	1259	5	200	422
2230	2380	I†	—	—	—	240	1356	5	200	451
2380	2530	J†	—	—	—	240	1453	5	200	480
2530	2700	K†	—	—	—	260	1471	6	200	480
2700	2870	L†	—	—	—	260	1471	6	200	490
2870	3040	M†	—	—	—	260	1471	6	200	500
3040	3210	N†	—	—	—	280	1471	6	200	520
3210	3400	O†	—	—	—	280	1471	6	200	554
3400	3600	P†	—	—	—	280	1471	6	200	588
3600	3800	Q†	—	—	—	300	1471	6	200	618
3800	4000	R†	—	—	—	300	1471	6	200	647
4000	4200	S†	—	—	—	300	1471	7	200	647
4200	4400	T†	—	—	—	300	1471	7	200	657
4400	4600	U†	—	—	—	300	1471	7	200	667
4600	4800	V†	—	—	—	300	1471	7	200	677
4800	5000	W†	—	—	—	300	1471	7	200	686
5000	5200	X†	—	—	—	300	1471	8	200	686
5200	5500	Y†	—	—	—	300	1471	8	200	696
5500	5800	Z†	—	—	—	300	1471	8	200	706
5800	6100	A*	—	—	—	300	1471	9	200	706
6100	6500	B*	—	—	—	—	—	9	200	716
6500	6900	C*	—	—	—	—	—	9	200	726
6900	7400	D*	—	—	—	—	—	10	200	726
7400	7900	E*	—	—	—	—	—	11	200	726
7900	8400	F*	—	—	—	—	—	11	200	736
8400	8900	G*	—	—	—	—	—	12	200	736
8900	9400	H*	—	—	—	—	—	13	200	736
9400	10000	I*	—	—	—	—	—	14	200	736
10000	10700	J*	—	—	—	—	—	15	200	736
10700	11500	K*	—	—	—	—	—	16	200	736
11500	12400	L*	—	—	—	—	—	17	200	736
12400	13400	M*	—	—	—	—	—	18	200	736
13400	14600	N*	—	—	—	—	—	19	200	736
14600	16000	O*	—	—	—	—	—	21	200	736

## Ship Control Systems

## Part 3, Chapter 13

Section 7

**Table 13.7.3 Equipment – Stream anchors, stream wires, towlines and mooring lines** (conclusion)

NOTES	
1. Towline specified for guidance only, see 7.5.1. For tugs see Table 13.7.1 item (6).	4. Wire ropes for towlines and mooring lines used in association with mooring winches (on which the rope is stored on the winch drum) are to be of suitable construction.
2. The rope used for stream wire is to be constructed of not less than 72 wires, made up into six strands.	5. Irrespective of strength requirements, no fibre rope is to be less than 20 mm diameter.
3. Wire ropes used for towlines and mooring lines are generally to be of a flexible construction with not less than: 144 wires in six strands with seven fibre cores for strengths up to 490 kN (50 tonne-f). 222 wires in six strands with one fibre core for strengths exceeding 490 kN (50 tonne-f). The wires laid round the fibre centre of each strand are to be made up in not less than two layers.	6. Tests. See Pt 2, Ch 10 for wire ropes and fibre ropes respectively.

**Table 13.7.4 Trawlers, stern trawlers and fishing vessels**

Equipment number		Stockless bower anchors		Stud link chain cables for bower anchors		
Exceeding	Not exceeding	Number	Mass of anchor in kg	Total length in metres	Diameter, in mm	
					Mild steel (Grade 1 or U1)	Special quality steel (Grade U2)
50	60	2	120	192,5	12,5	–
60	70	2	140	192,5	12,5	–
70	80	2	160	220,0	14,0	12,5
80	90	2	180	220,0	14,0	12,5
90	100	2	210	220,0	16,0	14,0
100	110	2	240	220,0	16,0	14,0
110	120	2	270	247,5	17,5	16,0
120	130	2	300	247,5	17,5	16,0
130	140	2	340	275,0	19,0	17,5
140	150	2	390	275,0	19,0	17,5
150	175	2	480	275,0	22,0	19,0
175	205	2	570	302,5	24,0	20,5
205	240	2	660	302,5	26,0	22,0
240	280	2	780	330,0	28,0	24,0
280	320	2	900	357,5	30,0	26,0
320	360	2	1020	357,5	32,0	28,0
360	400	2	1140	385,0	34,0	30,0
400	450	2	1290	385,0	36,0	32,0
450	500	2	1440	412,5	38,0	34,0
500	550	2	1590	412,5	40,0	34,0
550	600	2	1740	440,0	42,0	36,0
600	660	2	1920	440,0	44,0	38,0
660	720	2	2100	440,0	46,0	40,0

7.6.2 The following performance criteria are to be used as a design basis for the windlass:

(a) The windlass is to have sufficient power to exert a continuous duty pull over a period of 30 minutes of:

- for specified design anchorage depths up to 82,5 m:  
Chain cable grade      Duty pull,  $P$ , in N (kgf)  
U1                               $36,79d_c^2$  ( $3,75d_c^2$ )  
U2                               $41,68d_c^2$  ( $4,25d_c^2$ )  
U3                               $46,60d_c^2$  ( $4,75d_c^2$ )

- for specified design anchorage depths greater than 82,5 m:

$$P_1 = P + (D_a - 82,5) 0,214d_c^2 \text{ N}$$

$$[P_1 = P + (D_a - 82,5) 0,0218d_c^2 \text{ kgf}]$$

where

**Table 13.7.5 Chain cable steel grades**

Grade	Material	Tensile strength	
		N/mm <sup>2</sup>	(kgf/mm <sup>2</sup> )
U1	Mild steel	300 – 490	(31 – 50)
U2 (a)	Special quality steel (wrought)	490 – 690	(50 – 70)
U2 (b)	Special quality steel (cast)	490 – 690	(50 – 70)
U3	Extra special quality steel	690 min.	(70 min.)

$d_c$  is the chain diameter, in mm

$D_a$  is the specified design anchorage depth, in metres

$P$  is the duty pull for anchorage depth up to 82,5 m

$P_1$  is the duty pull for anchorage depths greater than 82,5 m.

(b) The windlass is to have sufficient power to exert, over a period of at least two minutes, a pull equal to the greater of:

- (i) short term pull:  
1,5 times the continuous duty pull as defined in 7.6.2(a).

- (ii) anchor breakout pull:

$$12,18W_a + \frac{7,0L_c d_c^2}{100} \text{ N}$$

$$\left( 1,24W_a + \frac{7,1L_c d_c^2}{1000} \text{ kgf} \right)$$

where:

$L_c$  is the total length of chain cable on board, in metres, as given by Table 13.7.2

$W_a$  is the mass, in kilograms, of bower anchor as given in Table 13.7.2.

(c) The windlass, with its braking system in action and in conditions simulating those likely to occur in service, is to be able to withstand, without permanent deformation or brake slip, a load, applied to the cable, given by:

$$K_b d_c^2 (44 - 0,08d_c) \text{ N}$$

$$(K_b d_c^2 (44 - 0,08d_c) \text{ kgf})$$

where  $K_b$  is given in Table 13.7.6.

# Ship Control Systems

## Part 3, Chapter 13

Section 7

The performance criteria are to be verified by means of shop tests in the case of windlasses manufactured on an individual basis. Windlasses manufactured under LR's *Type Approval Scheme for Marine Engineering Equipment* will not require shop testing on an individual basis.

**Table 13.7.6 Values of  $K_b$**

Cable grade	$K_b$	
	Windlass used in conjunction with chain stopper	Chain stopper not fitted
	N (kgf)	N (kgf)
U1	4,41 (0,45)	7,85 (0,8)
U2	6,18 (0,63)	11,0 (1,12)
U3	8,83 (0,9)	15,7 (1,6)

7.6.3 Where shop testing is not possible and Type Approval has not been obtained, calculations demonstrating compliance with 7.6.2 are to be submitted together with detailed plans and an arrangement plan showing the following components:

- Shafting
- Gearing
- Brakes
- Clutches.

7.6.4 During trials on board ship, the windlass is to be shown to be capable of:

- for all specified design anchorage depths: raising the anchor from a depth of 82,5 m to a depth of 27,5 m at a mean speed of 9 m/min; and
- for specified design anchorage depths greater than 82,5 m: in addition to (a), raising the anchor from the specified design anchorage depth to a depth of 82,5 m at a mean speed of 3 m/min.

Where the depth of the water in the trial area is inadequate, suitable equivalent simulating conditions will be considered as an alternative. Following trials, the ship will be eligible to be assigned a descriptive note **specified design anchorage depth ... metres**, which will be entered in column 6 of the *Register Book*.

7.6.5 Windlass performance characteristics specified in 7.6.2 and 7.6.4 are based on the following assumptions:

- one cable lifter only is connected to the drive shaft;
- continuous duty and short term pulls are measured at the cable lifter;
- brake tests are carried out with the brakes fully applied and the cable lifter declutched;
- the probability of declutching a cable lifter from the motor with its brake in the off position is minimized;
- hawse pipe efficiency assumed to be 70 per cent.

7.6.6 The design of the windlass is to be such that the following requirements or equivalent arrangements will minimize the probability of the chain locker or forecabin being flooded in bad weather:

- a weathertight connection can be made between the windlass bedplate, or its equivalent, and the upper end of the chain pipe, and
- access to the chain pipe is adequate to permit the fitting of a cover or seal, of sufficient strength and proper design, over the chain pipe while the ship is at sea.

### 7.7 Testing of equipment

7.7.1 All anchors and chain cables are to be tested at establishments and on machines recognized by the Committee and under the supervision of LR's Surveyors or other Officers recognized by the Committee, and in accordance with Chapter 10 of the Rules for Materials.

7.7.2 Test certificates showing particulars of weights of anchors, or size and weight of cable and of the test loads applied are to be furnished. These certificates are to be examined by the Surveyors when the anchors and cables are placed on board the ship.

7.7.3 Steel wire and fibre ropes are to be tested as required by Chapter 10 of the Rules for Materials.

7.7.4 For holding power testing requirements relating to high holding power anchors, see Ch 10,1.7 of the Rules for Materials

### 7.8 Structural requirements associated with anchoring

7.8.1 The windlass is to be efficiently bedded and secured to the deck. The thickness of the deck in way of the windlass is to be increased, and adequate stiffening is to be provided, to the Surveyor's satisfaction. The structural design integrity of the bedplate is the responsibility of the Shipbuilder and windlass manufacturer.

7.8.2 An easy lead of the cables from the windlass to the anchors and chain lockers is to be arranged. Where cables pass over or through stoppers, these stoppers are to be manufactured from ductile material and be designed to minimize the probability of damage to, or snagging of, the cable. They are to be capable of withstanding without permanent deformation a load equal to 80 per cent of the Rule breaking load of the cable passing over them.

7.8.3 Hawse pipes and anchor pockets are to be of ample thickness and of a suitable size and form to house the anchors efficiently, preventing, as much as practicable, slackening of the cable or movements of the anchor being caused by wave action. The shell plating and framing in way of the hawse pipes are to be reinforced as necessary. Reinforcing is also to be arranged in way of those parts of bulbous bows liable to be damaged by anchors or cables. Substantial chafing lips are to be provided at shell and deck. These are to have sufficiently large, radiused faces to minimize the probability of cable links being subjected to high bending stresses. Alternatively, roller fairleads of suitable design may be



fitted. Where unpocketed rollers are used, it is recommended that the roller diameter be not less than eleven times the chain diameter. Where hawse pipes are not fitted, alternative arrangements will be specially considered.

**7.8.4** The chain locker is to be of a capacity and depth adequate to provide an easy direct lead for the cable into the chain pipes, when the cable is fully stowed. Chain or spurling pipes are to be of suitable size and provided with chafing lips. The port and starboard cables are to be separated by a division in the locker.

**7.8.5** Where means of access is provided to the chain locker it is to be closed by a substantial cover and secured by closely spaced bolts.

**7.8.6** Chain lockers and spurling pipes are to be watertight up to the exposed weather deck and the space is to be efficiently drained. However, bulkheads between separate chain lockers, or which form a common boundary of chain lockers, need not be watertight.

**7.8.7** Spurling pipes are to be provided with permanently attached closing appliances to minimise water ingress. It is recommended that steel plates in halves, hooked over the spurling pipe tops, be provided on top of which cement may be laid before lashing a canvas cover. Suitable alternatives will be considered.

**7.8.8** Provision is to be made for securing the inboard ends of the cables to the structure. This attachment should have a working strength of not less than 63,7 kN (6,5 tonne-f) or 10 per cent of the breaking strength of the chain cable, whichever is the greater, and the structure to which it is attached is to be adequate for this load. Attention is drawn to the advantages of arranging that the cable may be slipped from an accessible position outside the chain cable locker. The proposed arrangement for slipping the chain cable, if constructed outside the chain locker, must be made watertight.

**7.8.9** Satisfactory arrangements are to be made for the stowage and working of the stream anchor, if provided.

**7.8.10** On dredging and reclamation craft the following are to be complied with:

- On unpowered ships, the windlass may be hand operated.
- When wire rope instead of chain is used for the anchor cable, it is to be stored on a properly designed drum or reel.
- Fairleads intended for use with wire rope cable are to be designed to minimize wear and to avoid kinking or other damage occurring to the rope. Fairleads should, in general, be fitted with rollers having a diameter not less than eleven times the diameter of the anchor cable, but a ratio of not less than 15,7 to 1 is recommended.
- On split type vessels, the arrangements are to be such that jamming of the anchor cable during opening and closing operations of the hull will not occur.

## 7.9 Structural requirements for windlasses on exposed fore decks

**7.9.1** Windlasses located on the exposed deck over the forward 0,25L of the rule length, of ships of sea-going service of length 80 m or more, where the height of the exposed deck in way of the item is less than 0,1L or 22 m above the summer load waterline, whichever is the lesser, are to comply with the following requirements. Where mooring winches are integral with the anchor windlass, they are to be considered as part of the windlass.

**7.9.2** The following pressures and associated areas are to be applied, see Fig. 13.7.1:

- 200 kN/m<sup>2</sup> normal to the shaft axis and away from the forward perpendicular, over the projected area in this direction;
- 150 kN/m<sup>2</sup> parallel to the shaft axis and acting both inboard and outboard separately, over the multiple of  $f$  times the projected area in this direction;

where

$f = 1 + B/H$ , but not greater than 2,5

$B$  = width of windlass measured parallel to the shaft axis, in metres

$H$  = overall height of windlass, in metres.

**7.9.3** Forces in the bolts, chocks and stoppers securing the windlass to the deck are to be calculated. The windlass is supported by  $N$  bolt groups, each containing one or more bolts, see Fig. 13.7.2.

**7.9.4** The axial force  $R_i$  in bolt group (or bolt)  $i$ , positive in tension, may be calculated from:

$$R_{xi} = P_x h x_i A_i / I_x \text{ in kN}$$

$$R_{yi} = P_y h y_i A_i / I_y \text{ in kN}$$

and

$$R_i = R_{xi} + R_{yi} - R_{si} \text{ in kN}$$

where

$P_x$  = force acting normal to the shaft axis, in kN

$P_y$  = force acting parallel to the shaft axis, either inboard or outboard whichever gives the greater force in bolt group  $i$ , in kN

$h$  = shaft height above the windlass mounting, in cm


$x_i, y_i$  =  $x$  and  $y$  coordinates of bolt group  $i$  from the centroid of all  $N$  bolt groups, positive in the direction opposite to that of the applied force, in cm

$A_i$  = cross sectional area of all bolts in group  $i$ , in cm<sup>2</sup>


$I_x = \Sigma A_i x_i^2$  for  $N$  bolt groups, in cm<sup>4</sup>

$I_y = \Sigma A_i y_i^2$  for  $N$  bolt groups, in cm<sup>4</sup>

$R_{si}$  = static reaction at bolt group  $i$ , due to weight of windlass, in kN.



**Fig. 13.7.1 Windlass loading**



**Fig. 13.7.2 Direction of forces and weight**

7.9.5 Shear forces  $F_{xi}$ ,  $F_{yi}$  applied to the bolt group  $i$ , and the resultant combined force  $F_i$  may be calculated from:

$$F_{xi} = (P_x - \alpha g M)/N \text{ in kN}$$

$$F_{yi} = (P_y - \alpha g M)/N \text{ in kN}$$

and

$$F_i = \sqrt{(F_{xi}^2 + F_{yi}^2)} \text{ kN}$$

where

$\alpha$  = coefficient of friction (0,5)

$M$  = mass of windlass, in tonnes

$g$  = gravity acceleration (9,81 m/sec<sup>2</sup>)

$N$  = number of bolt groups.

# Ship Control Systems

## Part 3, Chapter 13

Section 7

7.9.6 Tensile axial stresses in the individual bolts in each bolt group  $i$  are to be calculated. The horizontal forces  $F_{xi}$  and  $F_{yi}$  are normally to be reacted by shear chocks. Where 'fitted' bolts are designed to support these shear forces in one or both directions, the von Mises equivalent stresses in the individual bolts are to be calculated, and compared to the stress under proof load. Where pourable resins are incorporated in the holding down arrangements, due account is to be taken in the calculations.

7.9.7 The safety factor against bolt proof strength is to be not less than 2.0.

7.9.8 The windlass is to be efficiently bedded and secured to the deck. The thickness of the deck in way of the windlass is to be increased. Adequate stiffening of the deck in way of the windlass is to be provided. The scantlings of the supporting structure and deck are to be determined by additional calculations applying the weight of the windlass combined with the resultant force on the seat due to the application of the following design loads:

- $P_x$  (as defined in 7.9.4);
- $P_y$ ;
- $P_x$  and  $P_y$  combined;
- a load no less than the maximum pull developed by the windlass under normal operating conditions;
- a load no less than the ultimate breaking strength of the chain stopper, but need not be taken greater than the maximum brake holding capacity of the windlass. Requirements for chain stoppers are described in Section 8.

The allowable stresses given in Table 13.7.7 are not to be exceeded.

**Table 13.7.7 Allowable stress in windlass supporting structure**

	Bending stress, in N/mm <sup>2</sup>	Shear stress, in N/mm <sup>2</sup>	Combined stress, in N/mm <sup>2</sup>
Allowable stress	$\frac{150}{k}$	$\frac{87}{k}$	$\frac{213}{k}$
$k$ = material factor, see Pt 3, Ch 2, 1.2			

7.9.9 The axial tensile and compressive forces in 7.9.4 and the lateral forces in 7.9.5 are also to be considered in the design of the supporting structure.

### 7.10 Structural requirements associated with towing and mooring

7.10.1 The following requirements are applicable to bollards and bitts, fairleads, stand rollers and chocks used for the normal mooring and towing of the vessel, the supporting structure and their attachment to it. They are also applicable to the supporting structure of capstans, winches and similar items used for the normal mooring and towing of the vessel. Any weld, bolt or equivalent device connecting the shipboard fitting to the supporting structure is part of the shipboard fitting and is subject to the National or International standard applicable to that shipboard fitting.

7.10.2 The design criteria in this sub-Section are to be used to derive the net scantlings of the supporting structure. A corrosion addition of 2 mm is to be added to the net thickness derived.

7.10.3 Shipboard fittings for towing or mooring are to be located on longitudinals, beams and/or girders, which are part of the deck construction so as to facilitate efficient distribution of the load. Other arrangements will be specially considered provided that the strength is confirmed as adequate for the service.

7.10.4 The design load applied to shipboard fittings and supporting hull structure is not to be less than that given in Table 13.7.8.

**Table 13.7.8 Minimum design load for deck fittings and supporting structure**


Use/Item	Minimum design load <sup>(1)</sup>
Normal towing (harbour/manoeuvring)	1,25 times the intended maximum towing load as indicated on the towing and mooring arrangements plan
Escort towing	minimum breaking strength of the towline given in Table 13.7.3 for the ship's corresponding equipment number <sup>(2)</sup>
Mooring	1,25 times the breaking strength of the mooring line given in Table 13.7.3 for the ship's corresponding equipment number <sup>(2)</sup>
Winches, etc.	1,25 times the intended maximum brake holding power
Capstans	1,25 times the maximum hauling in force
NOTES 1. If a greater design load is specified by the designer this load is to be used. 2. The equipment number calculation is to include the maximum projected area of all deck cargo.	

# Ship Control Systems

# Part 3, Chapter 13

Section 7

7.10.5 The design load is to be applied according to the arrangement shown on the towing and mooring arrangement plan. The point of action of the force on the fitting is to be taken as the point of attachment of the mooring line or towline or at a change in its direction. The total design load applied to a fitting need not be more than twice the design load, see Fig. 13.7.3.



**Fig. 13.7.3 Design load applied to fittings**

7.10.6 The selection of shipboard fittings is to be made by the shipyard in accordance with an acceptable National or International standard (e.g. ISO3913 Shipbuilding Welded Steel Bollards). If the shipboard fitting is not selected from an acceptable National or International standard then the design load used to assess its strength and its attachment to the ship is to be in accordance with the design load given in Table 13.7.8 and the design is to be submitted for approval.

7.10.7 The reinforced members beneath shipboard fittings are to be effectively arranged for any variation of the direction, in both the lateral and vertical plane, of the forces acting through the arrangement.

7.10.8 The stress within the supporting structure of fittings is not to exceed that given in Table 13.7.9.

**Table 13.7.9 Allowable stress within the supporting structure of shipboard fittings**

	Normal stress, in N/mm <sup>2</sup>	Shear stress, in N/mm <sup>2</sup>
Allowable stress	$\frac{235}{k}$	$\frac{141}{k}$
where $k = \frac{235}{\sigma_0}$ $\sigma_0$ = specified minimum yield strength of the material in N/mm <sup>2</sup>		

7.10.9 The Safe Working Load (SWL) of a shipboard fitting used for normal towing and mooring is not to be greater than 80 per cent of the design load. The SWL of a shipboard fitting used for escort towing is not to be greater than the design load. For fittings used for both operations, the greater design load is to be used.

7.10.10 The SWL of each shipboard fitting is to be marked, by weld bead or equivalent, on the fitting and relates to a single post basis.

7.10.11 When determining the minimum design load for deck fitting and supporting structure the 'Mooring Equipment Number' is to be calculated as follows:

$$\text{Mooring Equipment Number} = \Delta^{2/3} + 2BH + \frac{A}{10}$$

where

$A$  = area, in m<sup>2</sup>, in profile view of the hull including the projected area of all deck cargo, within the Rule length of the vessel, and of superstructures and houses above the summer load waterline, which are within the Rule length of the vessel, and also having a breadth greater than  $\frac{B}{4}$

See also 7.10.12 and 7.10.13

$B$  = greatest moulded breadth, in metres

$H$  = freeboard amidships, in metres, from the summer load waterline to the upper deck, plus the sum of the heights at the centreline, in metres, of each tier of houses having a breadth greater than  $\frac{B}{4}$

See also 7.10.12, 7.10.13 and 7.10.14

$\Delta$  = moulded displacement, in tonnes, to the summer load waterline.

7.10.12 In the calculation of  $H$  and  $A$ , sheer and trim are to be ignored. Where there is a local discontinuity in the upper deck,  $H$  is to be measured from a notional deckline.

7.10.13 If a house having a breadth greater than  $\frac{B}{4}$  is above a house with a breadth of  $\frac{B}{4}$  or less, then the wide house is to be included, but the narrow house ignored.

7.10.14 Screens and bulwarks more than 1,5 m in height are to be regarded as parts of houses when determining  $H$  and  $A$ . Where a screen or bulwark is of varying height, the portion to be included is to be that length, the height of which exceeds 1,5 m.

# Ship Control Systems

## Part 3, Chapter 13

Section 8

### Section 8

### Mooring of ships at single point moorings

#### 8.1 General

8.1.1 These requirements are applicable to ships intended to utilize the fittings standardized for single point moorings and include the type, strength and location of the required fittings.

8.1.2 A ship provided with mooring arrangements in accordance with the requirements of this Section will be eligible to be assigned the Class notation **SPM**.

#### 8.2 Arrangements

8.2.1 The ship is to be fitted with bow chain stoppers and/or Smit-Type Brackets, and bow fairleads. In addition, pedestal roller fairleads may be required for alignment purposes.

8.2.2 In order to ensure matching with terminal mooring equipment, the requirements for shipboard fittings are specified in association with ranges of ship deadweight as shown in Table 13.8.1.

**Table 13.8.1 Deadweight group for shipboard fittings requirements**

Group	Deadweight in tonnes
I	< 150 000
II	≥ 150 000 < 350 000
III	≥ 350 000

#### 8.2.3 Bow chain stoppers:

- The number, chain cable size and minimum safe working load of bow chain stoppers should be as given in Table 13.8.2.
- Bow chain stoppers should be located between 2,7 m and 3,7 m aft of the bow fairlead and should be positioned so as to give correct alignment with the bow fairlead and the pedestal fairlead or the drum end of the winch or capstan, see Fig. 13.8.1.
- The leading edge of the stopper base plate is to be suitably faired to allow unimpeded entry of the combination chafe chain into the stopper. The chain referred to, forms part of the standardized SPM equipment.
- Details of bow chain stoppers should be submitted for approval.

**Table 13.8.2 Fittings requirements for deadweight group**

Group	Chain size, in mm	No. of chain stoppers	SWL, in kN (tonnes)
I	76	1	1960 (200)
II	76	2	1960 (200)
III	76	2	2450 (250)


#### 8.2.4 Smit-Type Brackets:

- Smit-Type Brackets may be fitted in lieu of bow chain stoppers. The required number and safe working load are as given in Table 13.8.2 for bow chain stoppers.
- The scantlings of the pin, connecting brackets and welded attachments to the baseplate are to be determined in association with a horizontal load of 1,5 x SWL and a permissible shear stress of 78 N/mm<sup>2</sup> (8 kg/mm<sup>2</sup>).
- Where fitted, Smit-Type Brackets should be located between 2,7 m and 3,7 m aft of the bow fairlead and should be positioned so as to give correct alignment with the bow fairlead and pedestal fairlead or drum end of the winch or capstan, see Fig. 13.8.1.
- To facilitate connection to the terminal equipment it is recommended that each Smit-Type Bracket be provided with a length of chain cable comprising a pear link, an open link, and a special shackle, see Fig. 13.8.2. The safe working load should be as given in Table 13.8.2 for bow stoppers.
- Adjacent to each Smit-Type Bracket a lug with a recommended safe working load of 490 kN (50 tonnes) should be attached to the doubler plate. The lug should be provided with a hole of sufficient size to accept the pin of a 490 kN (50 tonnes) SWL shackle and should be used as a securing point for the chafe chain holding stopper.
- Details of Smit-Type Brackets should be submitted for approval.

8.2.5 The forecastle deck in way of bow chain stoppers or Smit-Type Brackets is to have a minimum thickness of 15 mm and is to be suitably reinforced to resist horizontal loads equal to 1,5 x SWL as given in Table 13.8.2.

#### 8.2.6 Bow fairleads:

- One centrally located bow fairlead should be provided for ships up to 150,000 tonnes deadweight (Group I). Two bow fairleads should be provided for ships larger than 150,000 tonnes deadweight (Groups II and III).
- Bow fairlead openings should be at least 600 x 450 mm for 76 mm chafe chain size. Where more than one bow fairlead is installed, the spacing of centres should be between 2 m and 3 m.
- The height of the centre of the bow fairlead opening above the forecastle deck should be determined by the extension, parallel to the deck, of the lead line of the chain cable to the bow chain stopper or Smit-Type Bracket, see Fig. 13.8.1. The fairlead should have a minimum radius equal to seven times the chain radius.
- Details of bow fairleads and their attachment to the bulwark should be submitted for approval.




**Fig. 13.8.1 Positioning of fairleads, chainstoppers and pedestal roller leads**

**8.2.7 Pedestal roller fairleads:**

- Pedestal roller fairleads should have a minimum radius equal to 10 times the radius of wire mooring ropes with a fibre core, seven times the radius of wire mooring ropes with a steel core or three times the radius of synthetic mooring ropes.
- The number of pedestal roller fairleads should correspond to the number of bow chain stoppers or Smit-Type Brackets.
- The minimum distance of pedestal roller fairleads from the bow chain stopper or Smit-Type Bracket should be 4,5 m. Any variation in the minimum distance will be specially considered.
- Details of local strengthening of the forecastle deck in way of pedestal roller fairleads should be submitted for approval.

**8.2.8** The winch drum or capstan used for handling the mooring gear should be capable of exerting a continuous duty pull of not less than 147 kN (15 tonnes).



## Section 9 Emergency towing arrangements

### 9.1 Structural requirements

9.1.1 For ships equipped with emergency towing arrangements in accordance with IMO Resolution MSC 35(63), the deck and its supporting structure in way of strongpoints and fairleads are to be suitably reinforced to resist design loads of at least 1,3 x specified breaking strength of the weakest component of the emergency towing arrangement, for angles of tow as specified in IMO Resolution MSC 35(63). The deck in way of strongpoints and fairleads is to have a minimum thickness of 15 mm.

9.1.2 Where a ship is provided with an emergency towing arrangement and the supporting structure complies with the requirements of this Section, the ship will be eligible to be assigned the descriptive note **ETA** which will be entered in column 6 of the *Register Book*.

9.1.3 Stresses induced in the supporting structure and welds in way of strongpoints and fairleads, determined using the design loads from 9.1.1, are not to exceed the permissible values given in Table 13.9.1. The capability of the structure to withstand buckling is also to be assessed.

**Table 13.9.1 Permissible stress values**


	Permissible stress N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Direct stress	$\sigma_0$
Shear stress	$\frac{\sigma_0}{\sqrt{3}}$
Combined stress	$\sigma_0$
Symbols	
$\sigma_0$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

9.1.4 The structural arrangement is to be such that continuity will be ensured. Abrupt changes of shape or section, sharp corners and other points of stress concentration are to be avoided.

### 9.2 Chafing chain and wire or fibre rope for Emergency Towing Arrangements

9.2.1 Chafing chains are to be manufactured, tested and certified in accordance with Ch 10,2 of the Rules for Materials Grades U2 and U3.

9.2.2 The outboard end of the chafing chain is to include a pear-shaped link allowing connection to a shackle corresponding to the type of ETA and chain grade. A typical arrangement is shown in Fig. 13.9.1.



9.2.3 The chafing chain is to be able to withstand a breaking load not less than twice the safe working load (SWL). The nominal diameter of common link for chafing chains is to comply with the value indicated in Table 13.9.2.

**Table 13.9.2 Nominal diameter of common link for chafing chains for ETA**

Type of ETA	Nominal diameter of common link, $d$ , min	
	Grade U2	Grade U3
ETA 1000	62 mm	52 mm
ETA 2000	90 mm	76 mm

9.2.4 Steel wire ropes are to be manufactured, tested and certified in accordance with Ch 10,6 of the Rules for Materials.

9.2.5 Fibre ropes are to be manufactured, tested and certified in accordance with Ch 10,7 of the Rules for Materials.

---



# Cargo Securing Arrangements

# Part 3, Chapter 14

Section 1

## Section

1	<b>General</b>
2	<b>Fixed cargo securing fittings, materials and testing</b>
3	<b>Loose container securing fittings, materials and testing</b>
4	<b>Ship structure</b>
5	<b>Container securing arrangements for stowage on exposed decks without cell guides</b>
6	<b>Container securing arrangements for underdeck stowage without cell guides</b>
7	<b>Container securing arrangements for stowage using cell guides</b>
8	<b>Determination of forces for container securing arrangements</b>
9	<b>Strength of container securing arrangements</b>
10	<b>Surveys</b>

## ■ Section 1 General

### 1.1 Application

**1.1.1** All cargo ships, regardless of tonnage, except those engaged solely in the carriage of either liquid or solid bulk cargoes are to be provided with a Cargo Securing Manual approved by the Flag Administration, as required by SOLAS 1974 (as amended). Sections 2, 4 and 10 apply to all ships for which a Cargo Securing Manual is required.

**1.1.2** Where the design and construction of the system comply with Sections 2, 4 and 10, and all the proposed fixed cargo securing fittings have been certified by an organisation acceptable to Lloyd's Register (hereinafter referred to as 'LR'), the ship will be eligible to be assigned the descriptive note **fsa** (fixed securing arrangements) and for an entry to be made in column 6 of the *Register Book*.

**1.1.3** Where container securing arrangements are fitted, and the design and construction of the system are in accordance with this Chapter, the ship will be eligible to be assigned the special features notation **CCSA** (certified container securing arrangements). Where loose container securing fittings are supplied for part container stowage only, the special features notation will be suitably modified.

**1.1.4** Where container securing arrangements are fitted and the design and construction of the system are in accordance with this Chapter, but an Initial Survey in accordance with 10.1.1 has not been requested, the descriptive note **fcsa (plans)** will be entered in column 6 of the *Register Book*.

**1.1.5** The requirements for container securing arrangements have been framed in relation to ISO Standard Series 1 Freight Containers. Proposals for the securing of other types of containers will be specially considered.

**1.1.6** In general, the containers are to be assumed loaded to their maximum operating gross weight. Where, however, specified loading patterns are proposed, the securing arrangements may be considered on the basis of these loading patterns which are to be clearly indicated on the approved arrangement plan carried on board the ship.

**1.1.7** Containers may be approved and certified using LR's *Container Certification Scheme*.

### 1.2 Plans and information required

**1.2.1** For all fixed cargo securing arrangements, except container securing arrangements, the following information and plans are to be submitted:

- Details of certification including safe working load (SWL), of fixed cargo securing fittings.
- Plans of structure in way of fixed cargo securing fittings.
- Direction of loads imposed on the ship's fixed cargo securing fittings.
- A general arrangement of fixed cargo securing fittings.

**1.2.2** For container securing arrangements, the following plans and information are to be submitted:

- General arrangement plan showing the disposition and design weights of the containers.
- Details of materials, design, scantlings of cell guides structure, lashing bridges, pedestals, and other container securing arrangements, where fitted.
- Details of certification, including safe working loads, of fixed and loose container securing fittings.
- Plans of structure in way of fixed container securing fittings and arrangements.
- Design values of the following ship parameters for the container load departure and arrival conditions:
  - Moulded draught ( $T_d$ )
  - Longitudinal centre of flotation (LCF)
  - Transverse metacentric height (GM)
- Design wind speed.
- Where available, details of the long term distribution of ship motions, particularly roll, pitch and heave, in irregular seas which the ship will encounter during its operating life. Where simplified dynamic response data, or other means of assessing the maximum motions of the ship, are proposed they are to be submitted for consideration. In other cases the motions defined in Section 8 will be used.

# Cargo Securing Arrangements

# Part 3, Chapter 14

Sections 1 & 2

1.2.3 Where containers of types other than ISO containers are to be incorporated in the stowage arrangement, the container stowage plan is to indicate clearly the locations where these containers are stowed. The plan is also to indicate the container weights and required securing arrangements for stacks composed entirely of ISO standard containers.

## 1.3 Securing systems

1.3.1 Containers are to be secured by one, or a combination, of the following systems:

- Corner locking devices.
- Rod, wire or chain lashings.
- Buttresses, shores or equivalent structural restraint.
- Cell guides.

Alternative systems will be considered on the basis of their suitability for the intended purpose.

1.3.2 Dunnage is not to be used in association with approved container securing systems except where forming part of an approved line load stowage, see 5.5.

## 1.4 Symbols and definitions

1.4.1 The following definitions are applicable to this Chapter, except where otherwise stated:

- $a$  = breadth of the container, in metres
- $b$  = length of the container, in metres
- $e$  = base of natural logarithms, 2,7183
- $GM$  = transverse metacentric height of the ship in the container load condition, in metres. It is recommended that for the purpose of design of the container securing system,  $GM$  should be taken as not less than  $0,05B$  m.
- $x$  = longitudinal horizontal distance from  $O_m$  to the centre of the container, in metres
- $y$  = transverse horizontal distance from the centreline of the ship to the centre of the container, in metres
- $z_m$  = vertical distance from  $O_m$  to the centre of gravity of the container, in metres
- $A$  = projected side area of the container, in  $m^2$
- $B$  = moulded breadth of the ship, in metres
- $D$  = moulded depth of the ship, in metres
- $L_{pp}$  = length between perpendiculars of the ship, in metres
- $O_m$  = centre of motion, to be taken on the centreline at the longitudinal centre of flotation of the ship and at a distance  $T_c$  or  $D/2$ , whichever is the greater, above the keel
- $R$  = the rating, or maximum operating gross weight for which the container is certified, and is equal to the tare weight plus payload of the container, in tonnes
- $T_c$  = moulded draught in the container load condition, in metres
- $T_h$  = full period of heave of the ship, in seconds
- $T_p$  = full period of pitch of the ship, in seconds
- $T_r$  = full period of roll of the ship, in seconds
- $V$  = wind speed, in m/s
- $W$  = design weight of the container and contents. In general  $W$  is to be taken as  $R$  unless reduced maximum weights are specified

- $\phi$  = maximum single amplitude of roll, in degrees
- $\psi$  = maximum single amplitude of pitch, in degrees.

## Section 2 Fixed cargo securing fittings, materials and testing

### 2.1 General

2.1.1 Randomly selected samples of fixed cargo securing fittings are to be subjected to prototype testing and, upon satisfactory completion, will be granted General Approval.

2.1.2 Randomly selected samples drawn from production runs are to be subjected to production testing prior to delivery to the ship.

2.1.3 Cargo securing fittings, certified by an organization other than LR, will be accepted where the certification scheme is to the satisfaction of LR.

### 2.2 Materials and design

2.2.1 Steel used for the construction of the fixed cargo securing fittings is to comply with the requirements of the Rules for Materials or with an equivalent specification acceptable to LR. Due account is to be taken of the grade and tensile strength of the hull material in way of the attachment. The chemical composition of the steel is to be such as to ensure acceptable qualities of weldability. Where necessary, tests are to be carried out to establish specific welding procedures.

2.2.2 Where securing arrangements are intended to operate at low ambient temperatures, special consideration is to be given to the specification of the steel.

2.2.3 Proposals for the use of materials other than steel will be specially considered.

2.2.4 Attention is drawn to the need for measures to be taken to prevent water accumulation in pockets or recesses that could lead to excessive corrosion.

### 2.3 Prototype testing

2.3.1 Prototype tests to determine the breaking or failure loads are to be carried out on at least two randomly selected samples of each item used in the securing system. The relationship between design breaking load and safe working load (SWL) is to be as indicated in Table 14.2.1.

2.3.2 The Surveyor is to be satisfied that the design and materials of the fittings are in accordance with the approved plans.

# Cargo Securing Arrangements

# Part 3, Chapter 14

## Section 2

**Table 14.2.1 Design breaking loads and proof loads for fixed cargo securing fittings**

Minimum design breaking load		Minimum proof load	
SWL ≤ 40 tonnes	SWL > 40 tonnes	SWL ≤ 40 tonnes	SWL > 40 tonnes
2 x SWL	SWL + 40 tonnes	1,5 x SWL	SWL + 20 tonnes
<b>NOTE</b> Breaking and proof loads for fixed cargo securing fittings of a material other than steel will be specially considered.			

2.3.3 For acceptance, no permanent deformation (other than due to initial embedding of component parts) is to be induced by test loads up to the proof load given in Table 14.2.1.

2.3.4 When considering the test modes, all expected directions of operation are to be taken into account. Jigs are to be employed, where necessary, in order that satisfactory simulation is obtained.

2.3.5 In the interests of standardization of the strength of container securing fittings, safe working loads in accordance with Table 14.2.2 are recommended.

2.3.6 Where one of the required two randomly selected test samples required fails before the design breaking load is reached, this can be accepted provided that:

- the failure is not less than 95 per cent of the design breaking load;
- an additional randomly selected sample is tested satisfactorily; and
- the average failure load of the three randomly selected samples is equal to or greater than the design breaking load.

## 2.4 Production testing






2.4.1 The nature and extent of proposed production testing will be considered by LR, but the arrangements are to be at least equivalent to one of the following testing procedures:

- One randomly selected sample from every 50 pieces, or from each batch if less than 50 pieces, is to be proof loaded in accordance with Table 14.2.1.
- All fittings are to be proof loaded to the SWL of the item.

2.4.2 Consideration will be given to a reduced frequency of the mechanical production testing proposed in 2.4.1, provided that:

- the prototype test results indicate a breaking load at least 50 per cent greater than that required by Table 14.2.1; and
- a suitable non-destructive inspection procedure is agreed.

**Table 14.2.2 Test loads and test modes for fixed container securing fittings**

Item No.	Description	Required test modes	Recommended minimum, in tonnes		
			SWL	Proof load	Breaking load
1	Flush socket	 Pull-out load	20	30	40
2	Pedestal socket	 Pull-out load	20	30	40
		 Tangential load	15	22,5	30
3	'D' ring	 45° Tensile load	18	27	36
4	Lashing plate	 45° Tensile load	18	27	36

### NOTES

- For items 3 and 4, where specially designed for use with chain or steel wire rope (SWR) lashings, a lesser SWL may be considered. A greater SWL will be required for use with item 2 in Table 14.3.2.
- For items 1 and 2, where multiple flush sockets or pedestal sockets are involved, test loads are to be applied simultaneously to each socket opening which can be loaded simultaneously in service.
- For item 4, where multiple lashing points are fitted in one deck plate fitting, testing is to be similarly arranged as for Note 2.
- Where containers with strength higher than required for ISO containers are used, consideration will be given to the required minimum loads.
- The test modes illustrated above are diagrammatic only.

# Cargo Securing Arrangements

# Part 3, Chapter 14

Sections 2 & 3

2.4.3 Permanent deformation (other than that due to initial embedding of component parts) will not be accepted unless tests are conducted in accordance with 2.4.1(a) and the SWL of the sample is 25 tonnes or greater. In this case, consideration may be given to acceptance of permanent deformation in the load range between SWL + 12,5 tonnes and the proof load, provided that satisfactory manual operation can be achieved after completion of tests.

2.4.4 In the event of premature failure or serious plastic deformation occurring in a test sample, a further randomly selected sample is to be selected for testing. In the event that this sample is found to be unsatisfactory, the associated batch will be rejected.

## Section 3 Loose container securing fittings, materials and testing

### 3.1 General

3.1.1 Randomly selected samples of loose container securing fittings are to be subjected to prototype testing and, upon satisfactory completion, will be granted General Approval.

3.1.2 Randomly selected samples drawn from production runs are to be subjected to production testing prior to delivery to the ship in accordance with 3.4.

3.1.3 Loose container securing fittings, certified by an organization other than LR, will be accepted where the certification scheme is to the satisfaction of LR.

### 3.2 Materials and design

3.2.1 Steel used for loose container securing fittings is to comply with the requirements of the Rules for Materials (Part 2) or with an equivalent specification acceptable to LR.

3.2.2 Where loose container securing fittings are intended to operate at low ambient temperatures, special consideration is to be given to the specification of the steel.

3.2.3 Proposals for the use of materials other than steel will be specially considered.

3.2.4 Locking devices are to be such as to minimize the risk of working loose under the effects of vibration.

### 3.3 Prototype testing

3.3.1 Prototype tests are to be in accordance with 2.3.1 to 2.3.6, except that Tables 14.3.1 and 14.3.2 are to be applied in lieu of Tables 14.2.1 and 14.2.2 respectively.

### 3.4 Production testing

3.4.1 The nature and extent of proposed production testing will be considered by LR, but the arrangements are to be at least equivalent to one of the following testing procedures:

- (a) For:
  - (i) **Loose container securing fittings except chain or wire rope lashings.** One randomly selected sample from every 50 pieces, or from each batch if less than 50 pieces, is to be proof loaded in accordance with Table 14.3.1.
  - (ii) **Chain or wire rope lashings.** One randomly selected sample from every 50 pieces or from each batch if less than 50 pieces, is to be tested to breaking.
- (b) All fittings, securing devices and lashings are to be proof loaded to the SWL of the item and in addition, one randomly selected sample from every batch of chain or wire rope lashings is to be tested to breaking.

3.4.2 Permanent deformation (other than that due to initial embedding of component parts) will not be accepted unless tests are conducted in accordance with 3.4.1(a)(i) and the SWL of the sample is 25 tonnes or greater. In this case, consideration may be given to acceptance of permanent deformation in the load range between SWL + 12,5 tonnes and the proof load, provided that satisfactory manual operation can be achieved after completion of tests.

3.4.3 In the event of premature failure or serious plastic deformation occurring in a test sample a further randomly selected sample is to be selected for testing. In the event that this sample is found to be unsatisfactory, the associated batch will be rejected.

**Table 14.3.1 Design breaking loads and proof loads for loose container securing fittings**











Item	Min. design breaking load		Min. proof load	
	SWL ≤ 40 tonnes	SWL > 40 tonnes	SWL ≤ 40 tonnes	SWL > 40 tonnes
Lashings				
Wire rope	3 x SWL			
Rod: higher tensile steel	2 x SWL		1,5 SWL	
Chain: mild steel	3 x SWL			
higher tensile steel	2,5 x SWL			
Other loose container securing fittings	2 x SWL	SWL + 40 t	1,5 x SWL	SWL + 20 t
NOTES				
1. Higher tensile steel is defined for this purpose as steel having a yield stress not less than 315 N/mm <sup>2</sup> (32 kgf/mm <sup>2</sup> ).				
2. Breaking and proof loads for lashings of material other than steel will be considered.				

# Cargo Securing Arrangements

## Part 3, Chapter 14

Sections 3 &amp; 4

**Table 14.3.2 Test loads and test modes for loose container securing fittings**

Item No.	Description	Required test modes	Recommended minimum, in tonnes		
			SWL	Proof load	Breaking load
1	Lashing rod (HTS)	 Tensile load	18	27	36
2	Lashing rod (high strength)		25	37,5	50
3	Lashing chain (HTS)		8	—	20
4	Lashing chain (M.S.)		10	—	30
5	Lashing steel wire rope		12	—	36
6	Turnbuckle	 Tensile load	18	27	36
7	Twistlock (single)	 Shear load	15	22,5	30
		 Tensile load	20	30	40
8	Twistlock (double)	 As for item 7 + Tensile load	5	7,5	10
9	Stacker (single)	 Shear load	15	22,5	30
10	Stacker (double)	 As for item 9 + Tensile load	5	7,5	10
11	Penguin hook	 Tangential load	18	27	36
12	Bridge fitting	 Tensile load	5	7,5	10
13	Buttress	 Tensile load	See Note 3		

**NOTES**

- For items 6 and 11, where specially designed for use with chain or SWR lashings, a lesser SWL may be considered.
- For items 8, 10 and 12, the recommended minimum loads quoted in the Table refer to the fittings when employed in a location in container stacks which do not transfer load to an adjacent stack. Where items 8, 10 and 12 are fitted in line with a buttress/shore support at stowage sides, then test loads are to be determined in association with Note 3.
- For item 13, test loads for buttress fittings are to be determined by detailed consideration of the individual stowage arrangement proposed in association with Table 14.3.1.
- Where containers with strength higher than required for ISO containers are used, consideration will be given to the required minimum loads.
- The test modes illustrated above are diagrammatic only.
- HTS denotes high tensile steel.

## Section 4 Ship structure

### 4.1 General

4.1.1 The ship structure and hatch covers in way of fixed cargo securing fittings are to be strengthened as necessary.

### 4.2 Strength

4.2.1 The SWL of the fixed cargo securing fitting is to be used as the design load when approving the weld attachments and the support structure of the fixed cargo securing fitting.

4.2.2 For container securing arrangements, the design load when approving the weld attachment and supporting structure is to be calculated in accordance with Section 9.

4.2.3 When considering the loads, all expected directions of operation are to be taken into account.

# Cargo Securing Arrangements

## Part 3, Chapter 14

Sections 4 &amp; 5

4.2.4 Stresses induced in the weld attachments, supporting structure, cell guides, lashing bridges and other structures serving as fixed cargo securing points, determined using the design loads from 4.2.1 to 4.2.3, are not to exceed the permissible values given in Table 14.4.1.

**Table 14.4.1 Permissible stress values**

	Permissible stress, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Normal stress (bending, tension, compression)	$0,67\sigma_0$
Shear stress	$0,4\sigma_0$
Combined stress	$0,86\sigma_0$
Symbols	
$\sigma_0$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

### Section 5 Container securing arrangements for stowage on exposed decks without cell guides

#### 5.1 General

5.1.1 Containers stowed on deck or on hatch covers are generally to be aligned in the fore and aft direction, but alternative arrangements will be considered.

5.1.2 Containers are to be stowed so that they do not extend beyond the ship's side. Adequate support is to be provided where they overhang hatch coamings or other deck structures. The stowage arrangements are to be such as to permit safe access for personnel in the necessary working of the ship, and to provide sufficient access for operation and inspection of the securing devices.

5.1.3 Where containers are stowed on hatch covers, the covers are to be effectively restrained against sliding by approved type stoppers or equivalent. Details of the locations of stoppers relative to the supporting structure are to be submitted at as early a stage as possible.

5.1.4 Stanchions and similar structure supporting containers and securing devices such as D-rings for lashings, are to be of adequate strength for the imposed loads and of sufficient stiffness to minimize any deflection which could lead to a reduction in the effectiveness of the securing device.

5.1.5 In the region forward of  $0,25L_{pp}$  abaft the fore perpendicular additional securing devices may be required, see 8.1.8.

#### 5.2 Containers in one tier

5.2.1 Containers are to be secured at their lower corners by approved locking devices.

5.2.2 Alternatively, containers may be secured by lashings fitted diagonally or vertically at both ends of each container, in association with cone fittings at each container corner.

#### 5.3 Containers in two tiers

5.3.1 Containers are to be secured at their lower corners at each tier by approved locking devices.

5.3.2 Where the calculations indicate that separation forces will not occur at any point in the stack, double stacking cones may be fitted at all internal corners of the stack and bridge fittings used to connect the tops of the rows in the transverse direction. Locking devices are to be fitted at all external corners.

5.3.3 Alternatively, containers may be secured by lashings in association with stacking cones or, where the calculations indicate that separation forces may occur, with locking devices.

#### 5.4 Containers in more than two tiers

5.4.1 Containers are to be secured at their lower corners at each tier by approved locking devices.

5.4.2 Alternatively, containers may be secured by lashings. One or two tiers of lashings may be fitted in association with stacking cones or, where the calculations indicate that separation forces may occur, with locking devices.

5.4.3 Proposals to use lashings in pairs will be considered. Lashings in pairs are generally to be attached one to the bottom corner fitting of the upper tier and the other to the top corner fitting of the lower tier container. Suitable connections are to be provided at the lower ends. The effectiveness of paired lashings is to be taken as equal to 1,5 times that of a single lashing, unless a suitable load-equalizing device is fitted.

5.4.4 Where a fourth tier of containers is fitted, it is generally to be secured to the third tier by locking devices at each corner.

5.4.5 Proposals to stow more than four tiers will be specially considered.

#### 5.5 Line Load stowage

5.5.1 Where the containers are supported on bearers placed to distribute the stackweight as uniform Line Loads, the following requirements are to be complied with:

- The stack is, in general, to comprise a maximum of two tiers of loaded containers.

# Cargo Securing Arrangements

# Part 3, Chapter 14

Sections 5, 6 & 7

- (b) The load from the upper tier is to be transferred through the container corners. Line Loading is not to be used between tiers.
- (c) The load on each vertical corner post of the bottom tier, calculated in accordance with Section 9, is not to exceed one half the Rated Load of the container.
- (d) Where the calculations indicate that lifting forces may occur, locking devices are to be fitted at the container corners.
- (e) The clearance below the bottom container corner casting is to be such that the stacking cone or equivalent cannot be dislodged under shear loading.

5.5.2 Where an approved Line Load stowage system is installed the special features notation will be suitably modified.

## 5.6 Systems incorporating structural restraint

5.6.1 Containers may be secured by the use of a fixed structure providing permanent buttresses in association with portable frameworks. Proposals to adopt such systems will be considered on the basis of the loads developed in the structure and the corresponding stresses.

5.6.2 The framework or other devices securing the containers are to be aligned with the container corner fittings and any clearance gap is to be kept to the minimum to reduce shifting.

6.1.5 Where the calculations indicate that separation forces will not occur between containers at any level, consideration will be given to the use of stacking cones in lieu of locking devices throughout.

6.1.6 Buttresses are generally to be of the tension and compression type and are to be provided with means of adjustment to ensure tightness when fitted in place. Where applicable, the attachment to the ship's structure is also to include means for vertical adjustment of the buttress to match container stacks of different heights.

6.1.7 Shores of the compression only type may be permanently attached to the ship structure or they may be hinged or portable. When in place they are to abut the container corner fittings with minimal clearance. Means are to be provided to prevent slackening of the device.

6.1.8 Adjacent stacks of containers are to be linked in line with buttresses or shores in order to transmit lateral loads. The fittings used for these linkages are to be of adequate strength to transmit the loads imposed.

6.1.9 The ship's structure supporting shores and buttresses is to be reinforced as necessary.

6.1.10 Proposals for alternative securing systems, including systems relying on minimal clearance between containers and hull structure, will be specially considered.

## Section 6 Container securing arrangements for underdeck stowage without cell guides

### 6.1 General

6.1.1 Containers are generally to be stowed in holds and 'tween decks in the fore and aft direction, but alternative arrangements will be considered. The securing arrangements are to be designed on the basis of the most severe distribution of loads which may arise in the container stack.

6.1.2 Containers may be secured by locking devices only or by a combination of locking devices, buttresses, shores or lashings. Containers are, in general, to be restrained at every corner at the base of the stack and at all intermediate levels.

6.1.3 Where stacks consist of one or two tiers only, consideration will be given to the omission of corner locking devices. Containers must, however, be secured by a minimum of two corner locking devices.

6.1.4 Where the calculations indicate that separation forces could occur at any particular level, twistlocks or equivalent means of securing are to be fitted at that level. Elsewhere, consideration will be given to the use of double stacking cones.

## Section 7 Container securing arrangements for stowage using cell guides

### 7.1 General

7.1.1 Cell guide systems may be fitted to support containers stowed in holds or on exposed decks.

7.1.2 The cell guides are not to form an integral part of the ship's structure. The guide system is generally to be so designed as to keep it free of the main hull stresses.

7.1.3 Cell guides are to be designed to resist loads caused by loading and unloading of the containers, to prevent shifting of the containers and to transmit the loads caused by motions of the ship into the main hull structure.

### 7.2 Arrangement and construction

7.2.1 Cell guides are to be of robust construction and generally fabricated from steel plate and rolled sections. They are to have sufficient vertical extent and continuity to provide efficient support to containers. Guide bars are to be effectively attached to the supporting structure to prevent tripping or distortion resulting from container loading.


7.2.2 The intersection between cell guide and cross-ties is to provide adequate torsional stability.

# Cargo Securing Arrangements

# Part 3, Chapter 14

Section 7

7.2.3 Intermediate brackets are to be fitted to vertical cell guides at suitable intervals, see Fig. 14.7.1.



**Fig. 14.7.1 Typical arrangement of cell guides**

7.2.4 The cell guides are to give a total clearance between the container and guide bars not exceeding 25 mm in the transverse direction and 40 mm in the longitudinal direction. The deviation of the cell guide bar from its intended line is not generally to exceed 4 mm in the transverse direction and 5 mm in the longitudinal direction.

7.2.5 Athwartship cross-ties are to be fitted between cell guides at a spacing determined from the loading on the guides but, generally, not more than 5 m apart. Wherever possible, cross-ties are to be arranged in line with the corners of the containers as stowed and are to be supported against fore and aft movement at a minimum of two points across the breadth of the hold. Where, however, the maximum fore and aft deflection in the cross-tie can be shown not to exceed 20 mm, then one support point may be accepted.

7.2.6 Longitudinal tie bars may be required to be fitted where shown necessary by the force calculations for the structure. Where fitted they are to comply with the requirements of 7.2.5.

7.2.7 Where, at the sides or ends of holds, the guide rails are fitted to transverse or longitudinal bulkheads, the bulkhead is to be locally reinforced to resist the additional loads.

## 7.3 Mixed stacks of 20 ft and 40 ft containers

7.3.1 Where the cell guides are arranged for the carriage of 40 ft containers, provision may be made for the installation of temporary intermediate cell guides for 20 ft containers. The permanent structure is to be designed such that it is suitable for either loading pattern.

7.3.2 Alternatively, permanent means for the support of 20 ft containers at the mid-length of a cell arranged for 40 ft containers will be considered. Such means may include the following:

- A pillar (inboard) and vertical rest bar (on the longitudinal bulkhead) against which the container stack may rest. The pillar is to be supported laterally by the deck structure over and is to be sufficiently stiff to control lateral deflection of the container stacks.
- Guide bars supported transversely by slim structure within the gap between containers and with longitudinal ties as necessary.

Details of proposals will be individually considered, taking into account the loads on the support structure and the resulting deflections.

7.3.3 Where it is desired to stow 20 ft containers in the lower tiers without external support at the mid-bay location, arrangements meeting the following requirements will be considered:

- Maximum container weights for 20 ft containers stowed in cell guides with no 40 ft container overstowed, can be derived from Tables 14.7.1 and 14.7.3 depending on the transverse acceleration and the number of tiers in the stack.
- Maximum container weights for 20 ft containers stowed in cell guides with at least one 40 ft container overstowed, can be derived from Tables 14.7.2 and 14.7.4 depending on the transverse acceleration and the number of tiers in the stack.
- Where a mixed stack not covered by Tables 14.7.1 to 14.7.4 is proposed, two-thirds of the transverse components of forces acting on 20 ft containers are to be assumed to be transmitted to the cell guides and one-third transmitted as a racking force through the unsupported end wall. The container weights are to be such that the racking force on the container end walls does not exceed 15 tonnes at the mid-hold end of the stack of 20 ft containers. The allowable compressive forces in the container corner posts are not to be exceeded, taking due account of 40 ft containers above as per 7.3.3(e), if applicable. The container weights are to be defined to ensure separation is minimized.
- Means are to be provided to prevent transverse sliding of the bottom of the stacks of 20 ft containers at the mid-hold end. This is to be in the form of permanently attached chocks at the inner bottom or equivalent.
- Stacking cones are to be fitted between each tier of the 20 ft containers to prevent transverse sliding. In addition, where a 40 ft container is required to be stowed above 20 ft containers, stacking cones are to be fitted at the ends of the 40 ft container between the 40 ft container and the 20 ft containers below.
- The 20 ft containers are to have steel walls and top (no open frame containers) and are to be of specially strengthened design, where necessary, to correspond to the vertical compressive load at the cell guide end of the 40 ft containers above.



# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 7

**Table 14.7.1 Maximum container weights of ISO 1496-1:1984 20 ft containers stowed in 40 ft cell guides with no overstay**

Lowest tier Transverse acceleration (g)	Maximum container weights, in tonnes					
	3 Tiers	4 Tiers	5 Tiers	6 Tiers	7 Tiers	8 Tiers
0,4	24,0	23,5	18,9	14,3	11,0	8,9
0,405	24,0	23,4	18,7	14,2	11,0	8,8
0,41	24,0	23,2	18,5	14,1	10,9	8,8
0,415	24,0	23,0	18,3	14,0	10,8	8,7
0,42	24,0	22,8	18,2	13,9	10,7	8,7
0,425	24,0	22,6	18,0	13,8	10,7	8,6
0,43	24,0	22,4	17,8	13,7	10,6	8,5
0,435	24,0	22,2	17,6	13,6	10,5	8,5
0,44	24,0	22,0	17,5	13,6	10,5	8,4
0,445	24,0	21,8	17,3	13,5	10,4	8,3
0,45	24,0	21,6	17,1	13,4	10,3	8,3
0,455	24,0	21,4	16,9	13,3	10,3	8,2
0,46	24,0	21,2	16,8	13,2	10,2	8,2
0,465	24,0	21,0	16,6	13,1	10,1	8,1
0,47	24,0	20,8	16,4	13,0	10,1	8,0
0,475	24,0	20,6	16,2	12,9	10,0	8,0
0,48	24,0	20,4	16,1	12,8	9,9	7,9
0,485	24,0	20,2	15,9	12,7	9,9	7,8
0,49	24,0	20,0	15,7	12,6	9,8	7,8
0,495	24,0	19,8	15,5	12,5	9,7	7,7
0,5	24,0	19,6	15,4	12,4	9,7	7,7
0,505	24,0	19,4	15,2	12,3	9,6	7,6
0,51	24,0	19,2	15,0	12,3	9,5	7,5
0,515	24,0	19,0	14,9	12,1	9,4	7,5
0,52	24,0	18,8	14,7	12,0	9,4	7,4
0,525	24,0	18,6	14,5	11,8	9,3	7,4
0,53	24,0	18,4	14,3	11,7	9,2	7,3
0,535	24,0	18,2	14,2	11,5	9,2	7,2
0,54	24,0	18,0	14,0	11,4	9,1	7,2
0,545	24,0	17,8	13,8	11,2	9,0	7,1
0,55	24,0	17,6	13,6	11,1	9,0	7,0

(g) Where fore and aft tension/pressure approved adapter cones are used to link two 20 ft containers to equate to a 40 ft container, the storage of 40 ft containers above is not required. Special consideration is to be given to the maximum stack weight which is stowed in association with this method of securing. In general, each stack of 20 ft containers is not to exceed 120 tonnes.

Proposals for stowage arrangements other than the above will be individually considered and are to be accompanied by supporting calculations.

### 7.4 Cell guide systems on exposed decks

7.4.1 Analysis methods for the strength of the cell guide structure are to take due account of the interactive effects between guide structure and supporting deck structure and also of the deformation of the hull girder.

7.4.2 At its lower end the guide structure is to be efficiently connected to the deck structure. Cross-ties are to be arranged between guides in a transverse direction at a spacing determined by the loading on the guides but in general not more than 3 m apart. Cross-bracing members of adequate strength and sufficient number are to be fitted in the transverse and longitudinal directions to prevent excessive deflection of the guide structure.

7.4.3 The height of guide bars above the deck is to be sufficient to ensure adequate restraint to the uppermost container tiers.

7.4.4 Where the cell guide structure is attached to highly stressed hull or deck elements, such as sheerstrake, special attention is to be given to the design of the connection and the grade and quality of steel utilized.

# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 7

**Table 14.7.2 Maximum container weights of ISO 1496-1:1984 20 ft containers stowed in 40 ft cell guides with overstow**

Lowest tier Transverse acceleration (g)	Maximum container weights, in tonnes, see Note					
	3 Tiers	4 Tiers	5 Tiers	6 Tiers	7 Tiers	8 Tiers
0,4	24,0	24,0	24,0	19,4	16,5	13,7
0,405	24,0	24,0	23,6	19,3	16,4	13,7
0,41	24,0	24,0	23,3	19,1	16,3	13,6
0,415	24,0	24,0	22,9	19,0	16,2	13,5
0,42	24,0	24,0	22,5	18,8	16,1	13,5
0,425	24,0	24,0	22,1	18,7	15,9	13,4
0,43	24,0	24,0	21,8	18,5	15,8	13,3
0,435	24,0	24,0	21,5	18,4	15,7	13,2
0,44	24,0	24,0	21,2	18,2	15,6	13,2
0,445	24,0	24,0	21,0	18,0	15,5	13,1
0,45	24,0	24,0	20,8	17,9	15,4	13,0
0,455	24,0	24,0	20,6	17,7	15,2	13,0
0,46	24,0	24,0	20,5	17,6	15,1	12,9
0,465	24,0	24,0	20,3	17,4	15,0	12,8
0,47	24,0	24,0	20,2	17,3	14,9	12,8
0,475	24,0	24,0	20,1	17,1	14,8	12,7
0,48	24,0	23,9	19,9	17,0	14,7	12,6
0,485	24,0	23,8	19,8	16,8	14,5	12,6
0,49	24,0	23,6	19,6	16,7	14,4	12,5
0,495	24,0	23,4	19,4	16,5	14,3	12,4
0,5	24,0	23,2	19,3	16,4	14,2	12,4
0,505	24,0	23,1	19,1	16,2	14,1	12,3
0,51	24,0	22,9	18,9	16,1	13,9	12,2
0,515	24,0	22,7	18,8	15,9	13,8	12,1
0,52	24,0	22,5	18,6	15,7	13,6	12,0
0,525	24,0	22,4	18,5	15,6	13,5	11,8
0,53	24,0	22,3	18,3	15,4	13,3	11,7
0,535	24,0	22,2	18,2	15,3	13,2	11,6
0,54	24,0	22,1	18,1	15,1	13,0	11,4
0,545	24,0	22,0	18,0	15,0	12,9	11,3
0,55	24,0	21,8	17,9	14,8	12,8	11,2

NOTE  
40 ft overstow containers not included in the number of tiers.

### 7.5 Entry guide devices

7.5.1 A device to pre-centre the container and direct it into the cell guides is normally to be fitted at the top of the guide bars. Such devices include:

- fixed even peaks;
- fixed high and low peaks;
- 'flip-flop' systems;

but other devices will be considered. The device is to be of robust construction.

**Cargo Securing Arrangements****Part 3, Chapter 14**

Section 7

**Table 14.7.3 Maximum container weights of ISO 1496-1:1990 20 ft containers stowed in 40 ft cell guides with no overstow**

Lowest tier Transverse acceleration (g)	Maximum container weights, in tonnes					
	3 Tiers	4 Tiers	5 Tiers	6 Tiers	7 Tiers	8 Tiers
0,4	24,0	23,5	18,9	15,6	13,4	11,6
0,405	24,0	23,4	18,7	15,5	13,2	11,5
0,41	24,0	23,2	18,5	15,3	13,1	11,4
0,415	24,0	23,0	18,3	15,2	12,9	11,3
0,42	24,0	22,8	18,2	15,0	12,8	11,1
0,425	24,0	22,6	18,0	14,9	12,7	11,0
0,43	24,0	22,4	17,8	14,7	12,5	10,9
0,435	24,0	22,2	17,6	14,6	12,4	10,8
0,44	24,0	22,0	17,5	14,4	12,3	10,6
0,445	24,0	21,8	17,3	14,3	12,1	10,5
0,45	24,0	21,6	17,1	14,1	12,0	10,4
0,455	24,0	21,4	16,9	14,0	11,8	10,2
0,46	24,0	21,2	16,8	13,8	11,7	10,1
0,465	24,0	21,0	16,6	13,7	11,6	10,0
0,47	24,0	20,8	16,4	13,5	11,4	9,9
0,475	24,0	20,6	16,2	13,4	11,3	9,7
0,48	24,0	20,4	16,1	13,2	11,2	9,6
0,485	24,0	20,2	15,9	13,1	11,0	9,5
0,49	24,0	20,0	15,7	12,9	10,9	9,4
0,495	24,0	19,8	15,5	12,7	10,8	9,2
0,5	24,0	19,6	15,4	12,6	10,6	9,1
0,505	24,0	19,4	15,2	12,4	10,5	9,0
0,51	24,0	19,2	15,0	12,3	10,3	8,8
0,515	24,0	19,0	14,9	12,1	10,2	8,7
0,52	24,0	18,8	14,7	12,0	10,1	8,6
0,525	24,0	18,6	14,5	11,8	9,9	8,5
0,53	24,0	18,4	14,3	11,7	9,8	8,3
0,535	24,0	18,2	14,2	11,5	9,7	8,2
0,54	24,0	18,0	14,0	11,4	9,5	8,1
0,545	24,0	17,8	13,8	11,2	9,4	8,0
0,55	24,0	17,6	13,6	11,1	9,2	7,8

# Cargo Securing Arrangements

## Part 3, Chapter 14

Sections 7 &amp; 8

**Table 14.7.4 Maximum container weights of ISO 1496-1:1990 20 ft containers stowed in 40 ft cell guides with overstay**

Lowest tier Transverse acceleration (g)	Maximum container weights, in tonnes, see Note					
	3 Tiers	4 Tiers	5 Tiers	6 Tiers	7 Tiers	8 Tiers
0,4	24,0	24,0	24,0	19,6	17,1	15,2
0,405	24,0	24,0	23,6	19,4	17,0	15,1
0,41	24,0	24,0	23,3	19,2	16,8	14,9
0,415	24,0	24,0	22,9	19,1	16,7	14,8
0,42	24,0	24,0	22,5	18,9	16,5	14,7
0,425	24,0	24,0	22,1	18,8	16,4	14,5
0,43	24,0	24,0	21,8	18,6	16,2	14,4
0,435	24,0	24,0	21,5	18,4	16,1	14,3
0,44	24,0	24,0	21,2	18,3	15,9	14,1
0,445	24,0	24,0	21,0	18,1	15,8	14,0
0,45	24,0	24,0	20,8	18,0	15,7	13,9
0,455	24,0	24,0	20,6	17,8	15,5	13,7
0,46	24,0	24,0	20,5	17,7	15,4	13,6
0,465	24,0	24,0	20,3	17,5	15,2	13,5
0,47	24,0	24,0	20,2	17,3	15,1	13,3
0,475	24,0	24,0	20,1	17,2	14,9	13,2
0,48	24,0	23,9	19,9	17,0	14,8	13,1
0,485	24,0	23,8	19,8	16,9	14,6	12,9
0,49	24,0	23,6	19,6	16,7	14,5	12,8
0,495	24,0	23,4	19,4	16,5	14,3	12,7
0,5	24,0	23,2	19,3	16,4	14,2	12,5
0,505	24,0	23,1	19,1	16,2	14,1	12,4
0,51	24,0	22,9	18,9	16,1	13,9	12,2
0,515	24,0	22,7	18,8	15,9	13,8	12,1
0,52	24,0	22,5	18,6	15,7	13,6	12,0
0,525	24,0	22,4	18,5	15,6	13,5	11,8
0,53	24,0	22,3	18,3	15,4	13,3	11,7
0,535	24,0	22,2	18,2	15,3	13,2	11,6
0,54	24,0	22,1	18,1	15,1	13,0	11,4
0,545	24,0	22,0	18,0	15,0	12,9	11,3
0,55	24,0	21,8	17,9	14,8	12,8	11,2

NOTE  
40 ft overstay containers not included in the number of tiers.

### Section 8

#### Determination of forces for container securing arrangements

#### 8.1 General

8.1.1 The forces acting in the securing system are to be determined for each loading condition and associated set of motions of the ship.

8.1.2 The following forces are to be taken into account:

- Static gravity forces.
- Inertial forces generated by accelerations due to roll, pitch and heave motions of the ship.
- Wind forces.
- Forces imposed by the securing arrangements.
- Wave impact forces.

8.1.3 Where ship response data is not available the values for roll, pitch and heave as given in Table 14.8.1 will be used for the calculation.

**Table 14.8.1 Ship motions**

Motion	Maximum single amplitude	Periods, in seconds
Roll	$\phi = \sin^{-1} \theta$ degrees but need not exceed $30^\circ$ and is not to be taken less than $22^\circ$ where $\theta = \sin \phi$ $= \left(0,45 + 0,1 \frac{L}{B}\right) \left(0,54 - \frac{L}{1270}\right)$	$T_r = \frac{0,7B}{\sqrt{GM}}$
Pitch	$\psi = 12e^{-0,0033L_{pp}}$ but need not exceed $8^\circ$	$T_p = 0,5\sqrt{L_{pp}}$
Heave	$\frac{L_{pp}}{80}$ m	$T_h = 0,5\sqrt{L_{pp}}$

# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 8

8.1.4 Wind forces are generally to be based on a maximum wind speed of 40 m/s.

8.1.5 Wind forces are to be taken as acting athwartships on the exposed faces of the container stack so as to increase the transverse force. Where the air gap between adjacent rows of containers does not exceed one metre, wind forces on the adjacent inner stack may be taken as zero. Where the air gap is five metres or more, the adjacent inner stack is to be treated as fully exposed. Wind forces on the inner stack for intermediate air gaps may be obtained by linear interpolation.


8.1.6 The individual components of force due to gravity, wind and ship motions acting on a particular container are to be determined in accordance with Table 14.8.2.

8.1.7 Forces due to pretensioning the securing devices need not, in general, be included in the calculation provided they do not exceed 500 kg in any one item. Special consideration will be given to cases where forces obtained from pre-stressing are an integral part of the design of the system.


8.1.8 Consideration is to be given to the forces from wave impact and shipping green seas where the form and proportions of the ship are such that these may occur. In general the strength of containers and the strength of the securing arrangements in the forward  $0,25L_{pp}$  are to be suitable for forces increased by 20 per cent above the values calculated from these requirements, except where it can be shown that the containers are adequately protected by breakwaters or similar structure.

**Table 14.8.2 Components of forces**

Source	Component of force, in tonnes		
	Pressure (normal to deck)	Sliding (parallel to deck)	
		transverse	longitudinal
STATIC			
Roll	$W \cos \phi$	$W \sin \phi$	
Pitch	$W \cos \psi$		$W \sin \psi$
Combined	$W \cos (0,71\phi ) \cos (0,71\psi )$	$W \sin (0,71\phi )$	$W \sin (0,71\psi )$
DYNAMIC			
Roll	$0,07024W \frac{\phi}{T_r^2} y$	$0,07024W \frac{\phi}{T_r^2} z_m$	
Pitch	$0,07024W \frac{\psi}{T_p^2} x$		$0,07024W \frac{\psi}{T_p^2} z_m$
Heave:			
Roll	$0,05W \frac{L_{pp}}{T_h^2} \cos \phi$	$0,05W \frac{L_{pp}}{T_h^2} \sin \phi$	
Pitch	$0,05W \frac{L_{pp}}{T_h^2} \cos \psi$		$0,05W \frac{L_{pp}}{T_h^2} \sin \psi$
WIND		$8,25AV^2 \cos \phi \times 10^{-5}$	
NOTES			
1. For definition of terms, see 1.4.1 and Fig. 14.8.1.			
2. The appropriate signs are to be used in calculating vector components of forces.			



**Fig. 14.8.1 Diagrammatic representation of symbols used in Table 14.8.2**



## 8.2 Resultant forces

8.2.1 The resultant force acting on the container is the vectorial summation of the individual directional components of all forces acting at a given instant, see Fig. 14.8.2. The securing system is to be designed on the basis of the most severe combination of these forces in such a manner that the forces on the containers and securing devices are within allowable limits. Where different arrangements of securing devices are proposed for different locations on the ship, the forces are to be calculated for the most severe condition applicable to each arrangement.

8.2.2 The instantaneous maximum value of the resultants of the forces depends upon the phase relationship between the ship motions. This relationship may be derived from model testing where carried out for the specific ship, from strip theory or from full scale measurements if carried out for a ship of similar geometry.

8.2.3 Alternatively, the resultants in each of the three co-ordinate axes may be derived from the individual components of force determined from Table 14.8.2 for the instantaneous positions in the motion cycle as follows:

- (a) Rolling condition:
- Maximum roll (descending) with maximum heave (descending).
  - Maximum roll (ascending) with maximum heave (ascending).

- (b) Pitching condition:
- Maximum pitch (descending) with maximum heave (descending).
  - Maximum pitch (ascending) with maximum heave (ascending).
- (c) Combined condition:
- 0,71 [Maximum roll (descending) with maximum pitch (descending)].
  - 0,71 [Maximum roll (ascending) with maximum pitch (ascending)].

8.2.4 The summation of the individual components of force for one container above or below the centre of motion is shown for the Rolling condition in Fig. 14.8.2, and the resultants are obtained from the following expressions:

- (a) Bottom of motions, see 8.2.3 (a)(i):

Pressure

$$P_{\max} = W \left[ \left( 1 + \frac{0,05L_{pp}}{T_h^2} \right) \cos\phi + \frac{0,07024\phi}{T_r^2} y \right]$$

Sliding (transverse)

$$H_{\max} = W \left[ \left( 1 + \frac{0,05L_{pp}}{T_h^2} \right) \sin\phi + \frac{0,07024\phi}{T_r^2} z_m \right]$$

- (b) Top of motions, see 8.2.3(a)(ii):

Pressure

$$P_{\min} = W \left[ \left( 1 - \frac{0,05L_{pp}}{T_h^2} \right) \cos\phi - \frac{0,07024\phi}{T_r^2} y \right]$$

# Cargo Securing Arrangements

# Part 3, Chapter 14

Sections 8 & 9

Sliding (transverse)

$$H_{\min} = W \left[ \left( 1 - \frac{0,05L_{pp}}{T_h^2} \right) \sin \phi + \frac{0,07024\phi}{T_r^2} z_m \right]$$

The corresponding summations for the Pitching and Combined conditions may be written similarly.

## Section 9

## Strength of container securing arrangements

### 9.1 Resultant applied forces

9.1.1 The resultant forces derived for each container in the stack in accordance with Section 8 are assumed to be divided equally between the walls of the container as follows:

$$H_i = \text{sliding force in one transverse end} = \frac{H}{2} \text{ tonnes}$$

$$J_i = \text{sliding force in one longitudinal side} = \frac{J}{2} \text{ tonnes}$$

$$P_i = \text{vertical force in each corner post} = \frac{P}{4} \text{ tonnes}$$

$$Q_i = \text{wind force in one transverse end} = \frac{Q}{2} \text{ tonnes}$$

The subscript *i* refers to any particular container.

9.1.2 The sliding forces  $H_i$  and  $J_i$  are taken to act at a mean height of one third the height of the container above its base. That is, the force may be distributed as to  $\frac{H_i}{3}$  (or  $\frac{J_i}{3}$ )

acting at the top of the container and  $\frac{2H_i}{3}$  (or  $\frac{2J_i}{3}$ ) acting

at the bottom, see Fig. 14.9.1.

9.1.3 Wind force is taken as uniformly distributed over the side of the container and is therefore divided equally between the top and bottom of the container, see Fig. 14.9.1.

### 9.2 Forces in an unlashd stack

9.2.1 Where the stack is supported only by approved devices between the tiers of containers and at the base of the stack, the forces in the stack are determined from Table 14.9.1.


9.2.2 To illustrate this calculation, the equations for the three tier stack shown in Fig. 14.9.1 are listed below for the Rolling condition. In these equations the values of  $P$  and  $H$  are the maxima or minima derived from 8.2.4 as appropriate. Similar equations may be written for the Pitching and for the Combined conditions.

(a) Racking force, per end wall:

Tier 3:  $F_3$

Tier 2:  $F_3 + F_2$

Tier 1:  $F_3 + F_2 + F_1$



**Fig. 14.9.1**  
**Forces in a three tier stack (Rolling condition)**

(b) Shear force, per corner:

Tier 3:  $0,55 (H_3 + Q_3)$

Tier 2:  $0,55 (H_3 + H_2 + Q_3 + Q_2)$

Tier 1:  $0,55 (H_3 + H_2 + H_1 + Q_3 + Q_2 + Q_1)$

(c) Maximum compressive force per bottom corner (i.e. force on the container below):

$$\text{Tier 3: } P_3 + \frac{F_3}{a} h_3$$

$$\text{Tier 2: } P_3 + P_2 + \frac{F_3}{a} (h_3 + h_2) + \frac{F_2}{a} h_2$$

Tier 1:

$$P_3 + P_2 + P_1 + \frac{F_3}{a} (h_3 + h_2 + h_1) + \frac{F_2}{a} (h_2 + h_1) + \frac{F_1}{a} h_1$$

(d) Minimum compressive force per bottom corner:  
Case (i) (maximum amplitude descending):

$$\text{Tier 3: } P_3 - \frac{F_3}{a} h_3$$

$$\text{Tier 2: } P_3 + P_2 - \frac{F_3}{a} (h_3 + h_2) - \frac{F_2}{a} h_2$$

Tier 1:

$$P_3 + P_2 + P_1 - \frac{F_3}{a} (h_3 + h_2 + h_1) - \frac{F_2}{a} (h_2 + h_1) - \frac{F_1}{a} h_1$$

Case (ii) (maximum amplitude ascending):

$$\text{Tier 3: } P_3 - \frac{F_3}{a} h_3$$

$$\text{Tier 2: } P_3 + P_2 - \frac{F_3}{a} (h_3 + h_2) - \frac{F_2}{a} h_2$$

Tier 1:

$$P_3 + P_2 + P_1 - \frac{F_3}{a} (h_3 + h_2 + h_1) - \frac{F_2}{a} (h_2 + h_1) - \frac{F_1}{a} h_1$$

A negative value in these equations indicates a separation force at that level. The minimum is the lesser value from the two cases.

9.2.3 The resultant forces calculated from 9.2.1 are not to exceed the allowable loads for which the container is suitable, see 9.7.

# Cargo Securing Arrangements

# Part 3, Chapter 14

Section 9

**Table 14.9.1 Forces in an unlashed stack**

Force	Symbol	Expression	Unit
Racking force per container wall:			
transverse	$F$	$\sum_{i=1}^i F_i$	t
longitudinal	$G$	$\sum_{i=1}^i G_i$	t
Shear force per corner:			
transverse	$S_{yz}$	$0,55 \sum_{i=1}^i H_i + Q_i$	t
longitudinal	$S_{xz}$	$0,55 \sum_{i=1}^i J_i$	t
Vertical reaction to tipping per corner:			
transverse	$R_{yz}$	$\frac{1}{a} \sum_{i=1}^i F_i z_i$ See Notes 1 and 2	t
longitudinal	$R_{xz}$	$\frac{1}{b} \sum_{i=1}^i G_i z_i$ See Notes 1 and 2	t
Vertical pressure per corner	$P_i$	$\sum_{i=1}^i P_i$ See Note 2	t
Resultant compressive force per corner:			
Maximum transverse		$P_i \text{ max.} + R_{yz} \text{ max.}$	t
Minimum transverse		$P_i \text{ max.} - R_{yz} \text{ max.}$ or $P_i \text{ min.} - R_{yz} \text{ min.}$ See Note 3	t
Maximum longitudinal		$P_i \text{ max.} + R_{xz} \text{ max.}$	t
Minimum longitudinal		$P_i \text{ max.} - R_{xz} \text{ max.}$ or $P_i \text{ min.} - R_{xz} \text{ min.}$ See Note 3	t
<b>NOTES</b> 1. $z_i$ is the distance from the level under consideration to the top of each container above that level, in metres. 2. Both the maximum and the minimum values are to be calculated. 3. Whichever is the lesser. A negative value indicates separation.			

9.2.4 The resultant forces in the securing devices and supports are not to exceed the allowable working loads for which the device has been approved, see Section 3.

9.2.5 For exposed stacks in the forward  $0,25L_{pp}$ , see 8.1.7.

## 9.3 Arrangements incorporating lashings or buttresses

9.3.1 Where the securing arrangements incorporate lashings, proper allowance is to be made for flexibility of the system. For this purpose, the following values may be adopted:

(a) **Racking deformation of the container.** Full scale testing of containers indicates that values of the spring constant (see Fig. 14.9.3) may be taken as in Table 14.9.2.

(b) **Horizontal movement of the containers.** Initial displacement of containers due to tolerances in container fittings will be considered in conjunction with the stowage arrangement proposed. Generally, initial displacement may be neglected in calculation procedures for conventional stowages.

(c) **Elongation of lashings.** Elongation is to be determined by reference to the effective modulus of elasticity of the lashing (allowance for straightening and stretching) which, in the absence of actual test values, may be taken as:

steel rod lashings	9,8 t/mm <sup>2</sup>
steel wire rope lashings	9,0 t/mm <sup>2</sup>
steel chain lashings	8,0 t/mm <sup>2</sup>
(based on the nominal diameter of the chain)	



# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 9

Adjustable tension/ compression buttress	12,0 t/mm <sup>2</sup>
Aluminium or other materials	To be considered.

**Table 14.9.2 Spring constants for containers**

Height (m)	Door end (t/mm)	Closed end (t/mm)	Side wall (t/mm)
2,438	0,37	1,67	0,61
2,591	0,35	1,54	0,57
2,743	0,33	1,43	0,54
2,896	0,32	1,33	0,51

9.3.2 Any other element introducing flexibility into the structure between the lashing point and the base of the container stack is to be evaluated and taken into account, if necessary. Examples of this could be flexibility of a lashing bridge, sliding of a hatch cover, or torsional deformations of the hull.

9.3.3 When paired lashings are used, a cross-sectional area equal to 150 per cent of the cross-sectional area of one lashing is to be used unless an equalizing system is fitted. If an equalizing system is fitted, the sum of the cross-sectional areas is to be used.


9.3.4 The resultant applied forces are determined in accordance with 9.1. The distribution of forces in the stack is obtained by equating the total movement of the containers with the corresponding component of elongation of the associated support element under the influence of the imposed forces.

9.3.5 The calculations are to be made for each end of the container stack, that is with all door ends together and with all closed ends together.


9.3.6 The load system for a four tier stack of containers with upper and lower lashings is illustrated in Fig. 14.9.2. The containers and lashings are modeled as a system of springs whose stiffness may be calculated and hence the equilibrium condition for the system may be found, see Fig. 14.9.3.

9.3.7 Having established the tension in the lashings, the residual forces in the containers are transmitted through the stack in accordance with the method given in 9.5. The model assumes that the securing devices between tiers of containers are capable of resisting negative (separation) forces. That is, where separation forces are found, suitable locking devices are assumed to be fitted and transmitting load.

9.3.8 A buttress or shore may be modeled in a similar way to a lashing. Where, however, more than one stack is supported by the use of linkages between adjacent containers in line with the buttress or shore, the model is to take this into account.



**Fig. 14.9.2 Container stack load system**



**Fig. 14.9.3 Container stack load system**

### 9.4 Tensions in the lashing rods

9.4.1 For conventional arrangements, the spring constant for the lashing rod may be determined using the expression:

$$k_L = \frac{E \cdot A \cdot \cos^2 \theta_L}{l_L}$$

However, some stowage arrangements may result in considerable longitudinal displacement between the base of the lashing and the fitting in the container corner, i.e. 40' container in a 45' bay. In such cases the spring constant of the lashing rod should be determined using the following expression:

$$k_L = \frac{E \cdot A \cdot l_y^2}{l_L^3}$$

# Cargo Securing Arrangements

# Part 3, Chapter 14

Section 9

where

- $y$  = transverse span of lashing, in mm
- $E$  = Effective Modulus of Elasticity (t/mm<sup>2</sup>)
- $A$  = cross-section area of lashing rod, in mm<sup>2</sup>
- $l_L$  = length of lashing (mm) given by
- $l_L = \sqrt{l_x^2 + l_y^2 + l_z^2}$
- $l_x$  = longitudinal separation of lashing ends measured parallel to ship's X axis, in mm
- $l_y$  = transverse separation of lashing ends measured parallel to ship's Y axis, in mm
- $l_z$  = vertical separation of lashing ends measured parallel to ship's Z axis, in mm
- $\theta_L$  = lashing angle, in degrees.

9.4.2 The expressions for the tensions in the lashing rods will vary with the lashing arrangement used, however, for the three cases below the expressions for the lashing rod tensions are summarised in Table 14.9.4:

- (a) Single cross lashed stack.
- (b) Double cross lashed stack.
- (c) Double cross lashed stack to lashing bridge.

## 9.5 Residual forces

9.5.1 The residual transverse force in the containers at the level of the lashing is:

$$\text{Lower } F_{1,RES} = F_1 - T_{L1} \cos \alpha \text{ (tonnes)}$$

$$\text{Upper } F_{2,RES} = F_2 - T_{L2} \cos \beta \text{ (tonnes)}$$

The racking and shearing forces in the container stack may then be determined in accordance with 9.2.2 using the residual transverse forces. The maximum and minimum vertical forces in the corner posts may be determined similarly taking due account of the vertical component of lashing tension where applicable.

9.5.2 The resultant forces in the containers are not to exceed the allowable values given in 9.7.

9.5.3 The lashing tensions are not to exceed the allowable working loads of the lashings as determined from Pt 3, Ch 14,3 of the Rules for Ships.

9.5.4 Where external support is provided by a buttress or shore the load is to be transmitted between adjacent stacks by linkages in line with the support. The force in the transverse end frame members of the containers adjacent to the support is given by:

$$F_b \left( \frac{2N-1}{2N} \right) \text{ tonnes and the force in the linkage to the}$$

$$\text{adjacent container is } F_b \left( \frac{N-1}{N} \right) \text{ tonnes}$$

where

- $F_b$  = calculated force in the buttress or shore, in tonnes
- $N$  = number of rows of containers supported by the buttress or shore.

## 9.6 Structural restraint systems

9.6.1 Where open framework systems are fitted on deck to provide structural restraint, they are to be designed to absorb the full horizontal component of force at that level and to prevent movement of the container stack. For the purpose of these calculations the deformation of the ship's structure in way of supports may be neglected.

## 9.7 Allowable forces on containers

9.7.1 For ISO containers, the securing arrangements are to be designed so that the forces on the containers do not exceed the values shown in Table 14.9.4. The maximum forces for ISO 1496-1: 1984 containers are illustrated in Fig. 14.9.4.




9.7.2 The allowable forces for containers of other dimensions will be determined on the basis of the values in Table 14.9.3 and of the forces for which the container has been certified.

# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 9

**Table 14.9.3 Summary of container securing methods**

Arrangement	$F'_x$	Tension in lashing	Residual transverse Forces at lashing level
	$F'_1 = \sum_{i=1}^n F_i$	$T_{L1} = \frac{k_{L1} \cdot F'_1}{(k_{C1} + k_{L1}) \cos \alpha}$	$F_{1,RES} = F_1 - T_{L1} \cdot \cos \alpha$
	$F'_2 = \sum_{i=1}^n F_i$	$T_{L1} = \frac{k_{L1}}{\cos \alpha} \cdot \frac{(k_{C2} + k_{L2}) F'_1 + k_{C2} F'_2}{(k_{C1} + k_{C2} + k_{L1}) (k_{C2} + k_{L2}) - k^2_{C2}}$ $T_{L2} = \frac{k_{L2}}{\cos \beta} \cdot \frac{k_{C2} \cdot F'_1 + (k_{C1} + k_{C2} + k_{L1}) F'_2}{(k_{C1} + k_{C2} + k_{L1}) (k_{C2} + k_{L2}) - k^2_{C2}}$	$F_{1,RES} = F_1 - T_{L1} \cdot \cos \alpha$ $F_{2,RES} = F_2 - T_{L2} \cdot \cos \beta$
	$F'_3 = \sum_{i=1}^n F_i$	$T_{L1} = \frac{k_{L1}}{\cos \beta} \cdot \frac{F_1 [(k_{C3} + k_{L2, \gamma}) k_{C2}] + F_2 [(k_{C1} + k_{C2}) (k_{C3} + k_{L2, \gamma})] + F_3 [(k_{C1} + k_{C2}) k_{C3}]}{(k_{C1} + k_{C2}) [(k_{C2} + k_{C3} + k_{L1, \gamma}) (k_{C3} + k_{L2, \gamma}) - k^2_{C3}] - k^2_{C2} (k_{C3} + k_{L2, \gamma})}$ $T_{L2} = \frac{k_{L2}}{\cos \beta} \cdot \frac{F_1 (k_{C2} \cdot k_{C3}) + F_2 [(k_{C1} + k_{C2}) k_{C3}] + F_3 [(k_{C1} + k_{C2}) (k_{C2} + k_{C3} + k_{L1, \gamma}) - k^2_{C2}]}{(k_{C1} + k_{C2}) [(k_{C2} + k_{C3} + k_{L1, \gamma}) (k_{C3} + k_{L2, \gamma}) - k^2_{C3}] - k^2_{C2} (k_{C3} + k_{L2, \gamma})}$	$F_{2,RES} = F_2 - T_{L1} \cdot \cos \alpha$ $F_{3,RES} = F_3 - T_{L2} \cdot \cos \beta$

# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 9


**Table 14.9.4 Allowable forces on ISO containers**

	ISO 1496-1:1984		ISO 1496-1:1990	
	20 ft	40 ft	20 ft	40 ft
	in tonnes			
Horizontal force from lashing on container fitting acting parallel to the side face, see Note 1	15,0	15,0	15,0	15,0
Horizontal force from lashing on container fitting acting parallel to the end face, see Note 1	22,5	22,5	22,5	22,5
Vertical force from lashing on container fitting acting parallel to the end or side face, see Note 1	30,0	30,0	30,0	30,0
Racking force on container end	15,0	15,0	15,0	15,0
Racking force on container side	10,0	10,0	10,0	10,0
Vertical forces at each top corner, tension	15,0	15,0	25,0	25,0
Vertical forces at each bottom corner, tension	20,0	20,0	25,0	25,0
Vertical forces at each corner post, compression	2,25R	2,25R	86,4	86,4
Transverse forces acting at the level of and parallel to the top face, tension or compression, see Note 2	22,5	34,0	34,0	34,0
Transverse forces acting at the level of and parallel to the bottom face, tension or compression, see Note 2	35,0	50,0	50,0	50,0
NOTES 1. In no case is the resultant of the horizontal and the vertical forces to exceed the limiting value derived from Fig. 14.9.3(a). 2. Where a buttress supports the stack at an intermediate level, the total transverse force in the containers at the level is not to exceed the sum of the appropriate top and bottom forces.				

# Cargo Securing Arrangements

## Part 3, Chapter 14

Section 9



**Fig. 14.9.4 Allowable forces for 20 ft or 40 ft ISO 1496-1: 1984 containers**

**■ Section 10**  
**Surveys****10.1 Initial Survey**

*10.1.1* The Surveyor is to be satisfied that the materials, workmanship and arrangements are satisfactory and in accordance with the requirements and the approved plans. Any items found not to be in accordance with the requirements or the approved plans, or any material, workmanship or arrangements found to be unsatisfactory are to be rectified.

*10.1.2* A Register of fixed and loose cargo securing fittings, when approved, is to be kept on board and up to date, and is to be made available to the Surveyor upon request. The Register is to contain sufficient details to enable all the fixed and loose cargo securing fittings to be identified, including:

- a simple sketch;
- the name of the item;
- the number supplied;
- the manufacturer's mark or code; and
- the safe working load with the corresponding breaking load.

*10.1.3* For container securing arrangements, a suitable container stowage arrangement plan is to accompany the Register. Where containers of types other than ISO containers are proposed to be carried, their stowage locations are to be clearly indicated on the plan.

*10.1.4* The Register and stowage plans, if applicable, may be included in the Cargo Securing Manual.

**10.2 Periodical Surveys**

*10.2.1* For the requirements for Periodical Surveys see Pt 1, Ch 3,2.2.28 and Pt 1, Ch 3,5.3.19.

---

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

Sections 1 & 2

### Section

- 1 **General**
- 2 **Application**
- 3 **Particulars to be submitted**
- 4 **Requirements of Parts 1 and 2 of the Scheme**
- 5 **Additional requirements for Part 2 of the Scheme**
- 6 **Initial assessment of the shipyard**
- 7 **Approval of the shipyard**
- 8 **Maintenance of approval**
- 9 **Suspension or withdrawal of approval**

- **Audit.** A documented activity aimed at verifying by examination and evaluation that the applicable elements of the quality programme continue to be effectively implemented.
- **Hold point.** A defined stage of manufacture beyond which the work must not proceed until the inspection has been carried out by all the relevant personnel.
- **System monitoring.** The act of checking, on a regular basis, the applicable processes, activities and associated documentation that the Shipbuilder's quality system continues to operate as defined in the quality programme.
- **Special process.** A process where some aspects of the required quality cannot be assured by subsequent inspection of the processed material alone. Manufacturing special processes include welding, forming and the application of protective treatments. Inspection and testing processes classified as special processes include non-destructive examination and pressure and leak testing.

## ■ Section 1 General

### 1.1 Definitions

**1.1.1 Quality Assurance Scheme.** Lloyd's Register's (hereinafter referred to as 'LR') Quality Assurance requirements for the hull construction of ships are defined as follows:

- **Quality Assurance.** All activities and functions concerned with the attainment of quality including documentary evidence to confirm that such attainment is met.
- **Quality system.** The organization structure, responsibilities, activities, resources and events laid down by Management that together provide organized procedures (from which data and other records are generated) and methods of implementation to ensure the capability of the shipyard to meet quality requirements.
- **Quality programme.** A documented set of activities, resources and events serving to implement the quality system of an organization.
- **Quality plan.** A document derived from the quality programme setting out the specific quality practices, special processes, resources and activities relevant to a particular ship or series of sister ships. This document will also indicate the stages at which, as a minimum, direct survey and/or system monitoring will be carried out by the Classification Surveyor.
- **Quality control.** The operational techniques and activities used to measure and regulate the quality of hull construction to the required level.
- **Inspection.** The process of measuring, examining, testing, gauging or otherwise comparing the item with the approved drawings and the shipyard's written standards including those which have been agreed by LR for the purposes of classification of the specific ship type concerned.
- **Assessment.** The initial comprehensive review of the shipyard's quality systems, prior to the granting of approval, to establish that all the requirements of these Rules have been met.

### 1.2 Scope of the Quality Assurance Scheme

**1.2.1** This Chapter specifies the minimum Quality System requirements for a shipyard to construct ships under LR's Quality Assurance Scheme.

**1.2.2** For the purposes of this Chapter of the Rules, hull construction comprises the hull structure; containment systems, including those which are independent of the main hull structure; appendages; superstructures; deckhouses; and closing appliances all as required by the Rules.

**1.2.3** Although the requirements of this Scheme are, in general, for steel ships of all welded construction, other materials for use in hull construction will be considered.

## ■ Section 2 Application

### 2.1 Certification of the shipyard

**2.1.1** LR will give consideration to a shipyard's Quality Assurance System provided, at all times, there is full commitment by all the shipyard personnel to the implementation and maintenance of this system. On satisfactory completion of assessments and audits LR will issue certificates of approval to the shipyard as indicated in 2.1.2.

**2.1.2** LR's Quality Assurance Scheme comprises:  
Part 1 The requirements of the Quality System for hull construction which are applicable to shipyards operating a quality programme but not necessarily constructing to LR's Class. Certificates of approval valid for three years will be issued, with intermediate audits at intervals of 6 months.

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

Sections 2, 3 & 4

**Part 2** The Quality System requirements for hull construction for application to ships under construction to LR's Class as part of the Special Survey. LR's particular requirements for construction of ships to its Class, and the continuous involvement in the hull construction process by a combination of direct survey and systems monitoring by LR's Surveyors, are provided for by Part 2. Where LR considers that there is a stage in construction at which a high degree of direct inspection by the Surveyors is desirable, this stage will be described on the Part 2 Approval Certificate.

Certificates of approval for Part 2 will be valid for one year, and will be issued after satisfactory assessment/audit carried out at a suitable stage during construction to LR's Class. Part 1 certification will automatically be issued, or re-issued as applicable, on attainment of Part 2 approval.

**2.1.3** Chemical carriers with cargo tank structure of material other than carbon manganese steel and the cargo containment system on ships for liquefied gases will be specially considered. The procedure relating to the construction of such structure on chemical carriers and liquefied gas containment systems is to be separately prescribed in the Quality Plan which will be subject to approval by LR.

**2.1.4** The Quality System at a shipyard will be examined for compliance with these Rules by the assessments and audits as laid down in Sections 4, 5 and 6. Initial and periodical approval of the system will be considered by the Committee on receipt of satisfactory assessment and audit reports.

**2.1.5** All information and data submitted by a Shipbuilder for approval under this Scheme and for maintenance of approval will be treated by LR in strict confidence and will not be disclosed to any third party without the prior written consent of the Shipbuilder.

**2.1.6** A list of shipyards approved under the Scheme will be held in the *List of Shipyards Approved to the Requirements of the Quality Assurance Scheme*.

### ■ Section 3 Particulars to be submitted

#### **3.1 Documentation and procedures**

**3.1.1** Under either Part of the Scheme, the documentation to meet the requirements of Section 4 is to be submitted. This documentation includes the Quality Manual, Quality Plans, documented procedures and work instructions.

**3.1.2** Additionally, under Part 2 of the Scheme the documentation to meet the requirements of Section 5 is to be submitted for approval. Construction plans and all necessary particulars are also to be submitted for approval in accordance with the relevant requirements of the Rules, see Pt 1, Ch 2,3.2.1.

#### **3.2 Amendments**

**3.2.1** Any major changes to the documentation or procedures required by Sections 4 or 5 are to be re-submitted.

### ■ Section 4 Requirements of Parts 1 and 2 of the Scheme

#### **4.1 General**

**4.1.1** The requirements of this Section are applicable to shipyards seeking approval under Parts 1 and 2 of the Scheme.

#### **4.2 Policy statement**

**4.2.1** A policy statement, signed by the Chief Executive of the shipyard concerned, confirming the full commitment of all levels of personnel in the shipyard to the implementation and sustained operation of quality assurance methods is to be included in the Quality Manual.

#### **4.3 Responsibility**

**4.3.1** Personnel responsible for functions affecting quality are to have defined responsibility and authority to identify, control and evaluate quality.

#### **4.4 Management Representative**

**4.4.1** The Shipbuilder is to appoint a Management Representative, who is to be independent of other functions unless specifically agreed otherwise by LR, and who is to have the necessary authority and responsibility for ensuring that the requirements of the Scheme are complied with.

**4.4.2** The Management Representative is to have the authority to stop production if serious quality problems arise.

#### **4.5 Quality control and testing personnel**

**4.5.1** The Shipbuilder is to utilise quality control and testing personnel whose performance and continued freedom of influence from production pressures is to be systematically confirmed by the Management Representative.

#### **4.6 Resources**

**4.6.1** Sufficient resources shall be provided by the shipyard to enable the requirements identified by the Quality Management System to be effectively implemented.



# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

### Section 4

#### 4.7 The Quality Management System

4.7.1 The Shipbuilder is to establish, document and maintain an effective Quality Management System that will ensure and demonstrate that materials and consumables used, and working processes employed, conform to the requirements for hull construction.

4.7.2 **Quality Manual.** The basic documentation is to be in the form of a Quality Manual which sets out the general quality policies and which references the detailed procedures, standards, etc., and includes the requirements of 4.2 to 4.24 and, where appropriate, 5.1 to 5.10.

4.7.3 **Procedures.** The Shipbuilder is to establish, document and maintain an adequate and defined control of the hull construction process comprising:

- (a) defined and documented controls, processes, procedures, tolerances, acceptance/rejection criteria and workmanship standards; and
- (b) the provision of Quality Plans for each ship or series of sister ships for the processes and procedures for manufacture, inspection and testing involved from receipt of material through to completion of the hull construction process.

4.7.4 **Work instructions.** The Shipbuilder is to develop and maintain clear and complete documented work instructions for the processes and standards involved in the construction of the hull. Such instructions are to provide directions to various levels of personnel.

#### 4.8 Regulatory requirements

4.8.1 The Shipbuilder is to establish that the requirements of all applicable Regulations are clearly specified and agreed with the Owner/Classification Society/Regulatory Authority. These Regulations are to be made available for all functions that require them and their suitability is to be reviewed.

4.8.2 The Shipbuilder is to establish a design verification procedure to ensure that the regulatory requirements have been incorporated into the design output.

#### 4.9 Control of hull drawings

4.9.1 The Shipbuilder is to establish, document and maintain a procedure for the submission to the Classification Society and other regulatory bodies of all the necessary drawings required for approval sufficiently early and in such a manner that the requirements of the Classification Society and other regulatory bodies can be included in the design before construction commences. This procedure is to include a provision which ensures that all amendments to approved drawings are incorporated in the working drawings and that design revisions are re-submitted for approval.

#### 4.10 Documentation and change control

4.10.1 The Shipbuilder is to establish a procedure to ensure that:

- (a) valid drawings, specifications, procedures, work instructions and other documentation necessary for each phase of the fabrication process are prepared;
- (b) all necessary documents and data are made readily available at all appropriate work, testing and inspection locations;
- (c) all amended drawings and changes to documentation are processed in a timely manner to ensure inclusion in the production process;
- (d) records are maintained of amendments and changes to documentation; and
- (e) provision is made for the prompt removal or immediate identification of all superseded drawings and documentation throughout the shipyard.

#### 4.11 Purchasing data and receipt

4.11.1 The Shipbuilder is to maintain purchasing documents containing a clear description of the materials ordered for use in hull construction and the standards to which material must conform, and the identification and certification requirements.

4.11.2 For the requirements for receiving inspection of purchased items, see 4.15.

#### 4.12 Owner supplied material

4.12.1 The Shipbuilder is to have procedures for the inspection, storage and maintenance of Owner supplied materials and equipment.

#### 4.13 Identification and traceability

4.13.1 The Shipbuilder is to establish and maintain a procedure to ensure that materials and consumables used in the hull construction process are identified (by colour-coding and/or marking as appropriate) from arrival at the shipyard through to erection in such a way as to enable the type and grade to be readily recognized. The procedure is to ensure that the Shipbuilder has the ability to identify material in the completed vessel and ensure traceability to the mill sheets.

#### 4.14 Fabrication control

4.14.1 The Shipbuilder is to establish, document and maintain suitable procedures to ensure that fabrication and construction operations are carried out under controlled conditions. Controlled conditions are to include:

- (a) clearly documented work instructions defining material treatment, marking, cutting, forming, sub-assembly, assembly, erection, fitting of closing appliances, use of fabrication aids and associated fit-up, weld preparation, welding and dimensional control procedures;

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

### Section 4

- (b) criteria for workmanship and manufacturing tolerances. These are to be documented in a clear manner and made available to the appropriate workforce, and are to include acceptance/rejection criteria; and
- (c) documented instructions for the control of equipment and machines used in fabrication. These are to be made available to the appropriate workforce and supplied to individuals where necessary.

4.14.2 The Shipbuilder is to establish and control welding, non-destructive examination and painting which are part of the fabrication system, the equipment used in such processes and the environment in which they are employed. Operators of these special processes are to be properly qualified. Details of these processes are to be included in the relevant Quality Plans.

4.14.3 A list of approved welding procedures is to be maintained and made available to relevant personnel. Records of the results of testing for approval are also to be maintained. Lists of appropriately qualified welders are to be maintained. Procedures for distribution and recycling of welding consumables are to be implemented.

4.14.4 The Shipbuilder is to establish, document and maintain adequate maintenance schedules and standards for all equipment associated with the hull construction process.

#### 4.15 Control of inspection and testing

4.15.1 The Shipbuilder is to be responsible for ensuring that all incoming plates, sections, castings, components, fabrications and consumables and other materials used in the hull construction process are inspected or otherwise verified as conforming to purchase order requirements.

4.15.2 The Shipbuilder is to provide an inspection system at suitable stages of the fabrication process from the material delivery to the completion of hull construction. The inspection system is to confirm and record the inspections carried out.

#### 4.16 Indication of inspection status

4.16.1 The Shipbuilder is to establish and maintain a system for identifying the inspection status of structural components at appropriate stages of the fabrication process. This may include the direct marking of components. Records of inspection and measurements are to be identifiable to components to which they refer and be readily accessible to production and inspection personnel and to Classification Surveyors.

#### 4.17 Inspection, measuring and test equipment

4.17.1 The Shipbuilder is to be responsible for the control, calibration, and maintenance of the inspection, measuring and test equipment used in the fabrication and non-destructive examination of the hull structure.

4.17.2 The calibration system is to allow traceability back to appropriate National Standards. Where these do not exist the basis of calibration is to be defined.

#### 4.18 Non-conforming materials and corrective action

4.18.1 The Shipbuilder is to establish and define procedures to provide for:

- (a) the clear identification and segregation from production areas of all plates, sections, castings, components, fabrications, consumables and other materials which do not conform to the agreed specification; and
- (b) the initiation of authorized corrective or alternative action.

#### 4.19 Protection and preservation of quality

4.19.1 The Shipbuilder is to establish and maintain a procedure to control handling and preservation processes for both the material used in fabrication and the structural components at all stages of the fabrication process. This procedure is to ensure conformance to specified requirements and established standards.

4.19.2 Welding consumables are to be stored, handled and recycled according to maker's recommendations.

#### 4.20 Records

4.20.1 The Shipbuilder is to develop and maintain records that demonstrate achievement of the required quality and the effective operation of the Quality System. Records demonstrating sub-contractor achievement of these requirements are to be maintained. These records are to be retained and available for a defined period. These records are to include identification of materials and consumables used in fabrication, the number and class of defects found during fabrication and information regarding corrective action taken. Records of particular processes, e.g. plate surface preparation and priming, marking, cutting, forming, accuracy control, non-destructive examination, audits and all other records pertaining to the operation of the Quality System are also to be maintained.

#### 4.21 Internal audit and management review

4.21.1 Internal audits of the performance of all aspects of the systems relating to design, production and testing are to be carried out systematically by appointed staff and recorded under the authority of the Management Representative. These staff members will not normally audit functions for which they are directly responsible.

4.21.2 Using data obtained from the audits and any other available relevant information, management reviews are to take place at specified intervals or more frequently as deemed necessary in order to review the performance of the Quality System.

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

Sections 4 & 5

4.21.3 The Shipbuilder is to establish, document and maintain a procedure for corrective application of data feedback from previous construction, including previous ships during the guarantee period.

4.21.4 The Shipbuilder is to establish, document and maintain a procedure to provide for the analysis of departures from manufacturing standards, steel material scrapped, reworked or repaired during the fabrication and construction process in order to detect trends, investigate the cause to determine the action needed to correct the processes and work procedures, or to identify the further training of operators as appropriate.

4.21.5 Agreed improvements to the Quality System are to be implemented within a time scale appropriate to the nature of the improvement.

### 4.22 Training

4.22.1 The Shipbuilder is to establish and maintain a system to identify training needs and ensure that all personnel involved in the fabrication, erection and quality-involved functions have adequate experience, training and qualifications. This requirement extends to sub-contractor personnel working within the shipyard. Records are to be available to the Classification Surveyor.

### 4.23 Sampling

4.23.1 Any sampling processes used by the Shipbuilder are to be in accordance with specified or Statutory Requirements or to the satisfaction of the Classification Surveyor as applicable.

### 4.24 Sub-contracted personnel, services and components

4.24.1 The requirements of the Scheme are applicable, as appropriate, to all sub-contractor personnel and sub-contracted services operating within the shipyard.

4.24.2 The requirements of the Scheme are not applicable to sub-contractor personnel or sub-contracted services operating at locations outside the shipyard. In these circumstances it will be necessary for inspections to be carried out by the LR Surveyor using conventional survey methods.

## Section 5 Additional requirements for Part 2 of the Scheme

### 5.1 Quality System procedures

5.1.1 The procedures detailed in 4.7 are to be submitted for approval.

### 5.2 Quality Plans

5.2.1 Quality Plans for ships which are to be classed by LR are to be submitted for approval well in advance of commencement of work, irrespective of any submissions that may have been made for sister ships under Part 1 of the Scheme. Such Quality Plans are to outline all of the manufacturing, testing and inspection operations to be performed by the Shipbuilder and by which personnel they will be carried out. The Quality Plans are then to be submitted to the LR Surveyors who will indicate all the stages at which they will perform system monitoring, carry out direct inspection and participate in hold point inspections. These hold points will include, but not be limited to, the following:

- (a) Radiographs and other test records of non-destructive examinations as required for Classification purposes, see Ch 10,2.13.
- (b) The items described in Ch 1,8 relevant to the scope of this Chapter.

5.2.2 Notwithstanding what may have been agreed in the Quality Plans, the LR Surveyors have the discretion to increase their involvement, see also 8.1.5.

### 5.3 Material supplier approval

5.3.1 The Shipbuilder is to ensure that hull construction materials and consumables used are selected from manufacturers who are approved by LR.

### 5.4 Identification and traceability

5.4.1 The procedure required by 4.13.1 is to be submitted for approval.

### 5.5 Fabrication control

5.5.1 The information required by 4.14.1(b) will be examined for acceptability.

5.5.2 Procedures for material treatment, forming, weld preparation and welding are to be submitted for approval.

5.5.3 Procedures required by 4.14.3 are to be submitted to the LR Surveyors for approval.

### 5.6 Control of inspection and testing

5.6.1 The inspection stages incorporated into the Scheme are to include specific checks for fit-up and welding which are to be carried out at each sub-assembly, assembly, pre-erection and erection stage as well as self-checking by the operator. The number of recorded checks at each stage will be agreed with the LR Surveyor, after consideration of documentary evidence of quality being achieved. Repairs, where required, are to be effected after each check. Collated Quality Control data to demonstrate the efficiency of the above self-check system are to be made available to the LR Surveyor by the Shipbuilder. The Quality Plans referred to in 4.7.3(b) provide the opportunity for the Shipbuilder and the LR

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

Sections 5, 6, 7 & 8

Surveyor to consider the structural design and ship type fully in order to determine the most efficient and effective inspection stages.

### 5.7 Control of non-conforming materials and corrective action

5.7.1 All predetermined repair procedures are to be consistent with the requirements of 4.7.3(a) and are to be to the satisfaction of the LR Surveyor. Where a defect is found, whether by the LR Surveyor or through shipyard inspection, for which no agreed repair procedure exists, approval is to be obtained from the LR Surveyor before any corrective action is effected.

### 5.8 Records

5.8.1 The shipyard is to make data available to the LR Surveyor, to demonstrate the efficiency of the inspection system, see 5.6.1.

### 5.9 Training

5.9.1 The competence of the welding operators, non-destructive examination and other personnel involved in special processes and inspection are to be to the satisfaction of the LR Surveyor.

### 5.10 Sub-contracted personnel, services and components

5.10.1 The requirements of the Scheme are not applicable to those services operating at locations outside the shipyard. It will be necessary for inspections to be carried out by the LR Surveyor using conventional survey methods.

5.10.2 The methods of control for the requirements of 4.24.1 are to be submitted to the LR Surveyor.

## Section 6 Initial assessment of the shipyard

### 6.1 General

6.1.1 In the first instance applications for approval under this Scheme will be considered on the recommendation of the local Surveyors.

6.1.2 After receipt and appraisal of the main quality documentation, an assessment of the shipyard is to be carried out by the Surveyors to examine all aspects of the Quality System applicable to hull construction.

6.1.3 The Surveyors will review the quality arrangements proposed by the Shipbuilder at the shipyard. They may advise as to how the proposed Quality System might be improved and where it is considered inadequate, advise how it might be revised to be acceptable to LR.

6.1.4 For assessment to Part 1 of the Scheme, the Surveyors will review the Quality System in association with the quality documentation and will check that all aspects of the System are established and in accordance with the requirements of Section 3.

6.1.5 For assessment of Part 2 of the Scheme, the Surveyors will confirm that the requirements given in Section 3 have been fully implemented and are complied with by a detailed examination of work in progress and by confirming that workmanship and the quality level being consistently achieved are to their satisfaction.

## Section 7 Approval of the shipyard

### 7.1 General

7.1.1 If the initial assessment confirms that the shipyard's quality arrangements are satisfactory, the Committee will issue Part 1 or Part 2 and Part 1 of LR's Quality Assurance Approval Certificates as appropriate. Maintenance of approval will be subject to the provisions of Section 8.

7.1.2 Approval by another organization will not be accepted as sufficient evidence that the arrangements for hull construction comply with these requirements.

## Section 8 Maintenance of approval

### 8.1 General

8.1.1 For Part 2 of the Scheme, the arrangements approved at the shipyard are to be kept under review by the Surveyors to ensure that the approved Quality System is being maintained in a satisfactory manner. This is to be carried out by:

- Regular and systematic audits by the LR Surveyor.
- Comprehensive Annual Audits. The audit team leader will be formally nominated by LR.

8.1.2 Where a comprehensive audit cannot be carried out due to lack of a current building programme to Class, demonstration that the requirements of Part 1 of the Scheme are being maintained may be confirmed by audit review at intervals of six months, normally by the local Surveyors. Where necessary a comprehensive triennial audit would be carried out by a Surveyor formally nominated by LR. The degree of re-assessment for re-approval at the recommencement of building to LR's Class would be at the discretion of the Committee.

# Quality Assurance Scheme for the Hull Construction of Ships

## Part 3, Chapter 15

Sections 8 & 9

8.1.3 All documentation, including reports, is to be available to the Surveyors.

8.1.4 Minor alterations in the approved procedures may be permitted provided that the Surveyors are advised and their prior concurrence obtained. Major alterations would need to be submitted for approval and may require an additional audit.

8.1.5 In a shipyard constructing ships to LR's Class, the following are applicable:

- (a) The LR Surveyor is to be allowed access at all reasonable times to all records pertaining to quality and to all parts of the shipyard involved in the implementation and maintenance of the Quality Assurance Programme.
- (b) The LR Surveyor is immediately to advise the Management Representative of any matter pertaining to the Quality System with which he is not satisfied.
- (c) When minor deficiencies in the approved procedures are discovered during audits, or if workmanship is considered unsatisfactory, the LR Surveyor will apply more intensive auditing and inspection.
- (d) Notwithstanding any of the provisions of the Quality System, all work related to Classification of ships with LR is to be to the satisfaction of the LR Surveyor.

## ■ Section 9 Suspension or withdrawal of approval

### 9.1 General

9.1.1 When the Surveyors have drawn attention to significant faults or deficiencies in the Quality System or its operation and these have not been rectified within a period of time acceptable to LR, the approval of the system, together with the associated certification, will be withdrawn and the shipyard's name deleted from the *List of Shipyards Approved to the Requirements of the Quality Assurance Scheme*.

9.1.2 If a significant period of time elapses between such withdrawal and any application for reinstatement, the reapproval procedures, if agreed to by the Committee, may require a restructuring of the Quality Management System and will always require a complete re-examination as for an initial assessment.



# ShipRight Procedures for the Design, Construction and Lifetime Care of Ships

## Part 3, Chapter 16

Sections 1, 2 & 3

### Section

1	<b>General</b>
2	<b>Structural design assessment</b>
3	<b>Fatigue design assessment</b>
4	<b>Construction monitoring</b>
5	<b>Ship Event Analysis</b>
6	<b>Enhanced scantlings</b>
7	<b>Protective coating in water ballast tanks</b>
8	<b>Hull planned maintenance</b>
9	<b>Ship Emergency Response Service</b>
10	<b>Assessment of Ballast Water Management Plans</b>

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter is applicable to all ship types and components with the exception of Sections 2 and 3 which are not applicable to Bulk Carriers or Double Hull Oil Tankers with a **CSR** notation (see Pt 1, Ch 2,2.3). The requirements are to be applied in conjunction with the relevant Chapters of Parts 3 and 4 applicable to the particular ship type, and the ShipRight procedures.

1.1.2 Details of Lloyd's Register's (hereinafter referred to as 'LR') ShipRight procedures are given in the *ShipRight Procedures Manual* and in this Chapter where related to particular items and notations.

1.1.3 Details of machinery ShipRight procedures are to be found in Pt 5, Ch 21.

### 1.2 Classification notations and descriptive notes

1.2.1 In addition to the hull class notations defined in Pt 1, Ch 2, ships complying with the requirements of this Chapter will be eligible to be assigned the additional class notations defined in Pt 1, Ch 2,2.1 and Ch 2,2.3 or descriptive notes as defined in Pt 1, Ch 2,2.7 and associated with the ShipRight procedures.

### 1.3 Information and plans required to be submitted

1.3.1 The information and plans required to be submitted are as specified in the relevant Chapters of Parts 3 and 4 applicable to the particular ship type and in this Chapter where related to particular items and notations.

## ■ Section 2 Structural design assessment

### 2.1 Structural Design Assessment notation – SDA

2.1.1 The ship structure is to be examined using finite plate element methods to assess both the overall and detailed structural capability to withstand static and dynamic loadings. See:

- the applicable *ShipRight SDA Procedures Manual* for the procedure for each ship type; and
- the Section dealing with direct calculations in the relevant Chapter of Part 4 applicable to the particular ship type.

2.1.2 This procedure is mandatory, and additional to normal Rule structural design approval, for:

- bulk carriers and oil tankers without a **CSR** notation (see 1.1.1) greater than 190 m in length;
- container ships with a beam of Panamax size or greater;
- The primary structure of LNG ships;
- The primary structure of Type A LPG ships;
- Other ships of Type B and C where the type, size and structural configuration demand;
- passenger ships where it is considered that the superstructure will be subjected to a significant load from flexure of the hull girder; or, where it is required to utilise the load carrying capability of the superstructure for longitudinal strength; and
- other ships where type, size and structural configuration demand, see *also* Pt 1, Ch 2,2.3 and Ch 2,2.7.

2.1.3 In addition, and where applicable, the ship structure is to be examined for the structural capability to withstand dynamic loadings from partially filled tanks or the influence of thermal loadings.

## ■ Section 3 Fatigue design assessment

### 3.1 Fatigue Design Assessment notation – FDA

3.1.1 The ShipRight FDA procedure is to be applied in conjunction with the construction control tolerances and limits, in addition to the normal Rule structural detail design appraisal. These procedures are mandatory for bulk carriers and oil tankers (see 1.1.1) greater than 190 m in length and for other ships where the type, size, and structural configuration demand, see *also* Pt 1, Ch 2,2.3 and Ch 2,2.7.

# ShipRight Procedures for the Design, Construction and Lifetime Care of Ships

## Part 3, Chapter 16

Sections 4 to 8

### ■ Section 4 Construction monitoring

#### 4.1 Construction Monitoring notation – CM

4.1.1 Extended controls on structural alignment, fit up and workmanship standards will be applied to areas, shown by the structural design assessment and fatigue design assessment procedures specified in Sections 2 and 3, to be in need of particular attention. This procedure is mandatory for all ship types where either the SDA and/or FDA procedures have been applied on a mandatory basis. The procedure may also be applied on a voluntary basis in conjunction with the voluntary application of SDA and FDA procedures to ensure that the ship is designed and constructed to an enhanced structural standard. The requirements of Chapter 10, and the relevant procedures contained in the *Construction Monitoring Procedure* are to be complied with, see also Pt 1, Ch 2,2.3 and Ch 2,2.7.

4.1.2 The procedure is mandatory for all Bulk Carriers or Double Hull Oil Tankers greater than 190 m in length with a CSR notation (see Pt 1, Ch 2,2.3).

### ■ Section 5 Ship Event Analysis

#### 5.1 Ship Event Analysis – Descriptive notes SEA(HSS-n)

5.1.1 At the Owner's request, and in order to enhance safety and awareness on board during ship operation, provisions can be made for a hull surveillance system that monitors the hull girder stresses and motions of the ship and warns the ship's personnel that these levels or the frequency and magnitude of slamming motions are approaching a level where corrective action is advisable.

5.1.2 Where a hull surveillance system is fitted, the descriptive note **SEA(HSS-n)** will be assigned. The extension **-n** signifies the number of fitted strain gauges connected to the system. The following option extensions will be added to the descriptive note:

- L** The display of the relevant information in the cargo control area.
- M** The display and recording of the ship's motion.
- N** The facility to display and record navigational information.

**VDR** An interface with the ship's voyage data recorder system to enable the recording of hull stress, ship motion and hull pressure information.

The appropriate descriptive note will be entered in column 6 of the *Register Book*, see also Pt 1, Ch 2,2.7.

5.1.3 For the requirements, see the ShipRight Procedures and the *Provisional Rules for the Classification of Ship Event Analysis Systems*.

### ■ Section 6 Enhanced scantlings

#### 6.1 Enhanced Scantlings – Descriptive note ES

6.1.1 Where scantlings in excess of the approved Rule minimum are fitted at defined locations, a descriptive note **ES**, Enhanced Scantlings, will be entered in column 6 of the *Register Book*. For example, the note **ES+1** will indicate that an extra 1 mm has been fitted to the hull envelope plating (i.e. deck, side and bottom).

### ■ Section 7 Protective coating in water ballast tanks

#### 7.1 Protective Coating in Water Ballast Tanks – Descriptive note PCWBT

7.1.1 It is mandatory for all ship types that all salt water spaces having boundaries formed by the hull envelope are to have a corrosion protection coating applied, see Ch 2,3.

7.1.2 If the Owner so wishes, a descriptive note **PCWBT**, 'Protective Coating in Water Ballast Tanks', will be entered in column 6 of the *Register Book* to indicate that the ship's water ballast tanks are coated with a recognized corrosion control coating and that the coating remains efficient and is maintained in good condition. If the coatings have broken down, particularly at more critical areas, and no effort is being made to maintain the coatings, then this note will be placed in parentheses, i.e. (**PCWBT**). In either case the date of the last survey will be placed in parentheses after the note.

7.1.3 Recognized corrosion control coatings are listed in the *List of Paints, Resins, Reinforcements and Associated Materials*, which is published on LR's website, <http://www.lr.org>, and on the CD-Rom version of the *Rules and Regulations for the Classification of Ships* by LR. Guidance on coating condition is given in Chapter 1 of this List.

### ■ Section 8 Hull planned maintenance

#### 8.1 Descriptive note HPMS

8.1.1 Where an Owner operates an approved Planned Maintenance Scheme as part of the Continuous Survey Hull (CSH) Cycle, the descriptive note **HPMS** will, at the Owner's request, be entered in column 6 of the *Register Book*.



# ShipRight Procedures for the Design, Construction and Lifetime Care of Ships

## Part 3, Chapter 16

Sections 8, 9 & 10

8.1.2 The descriptive note will indicate that procedures and documentation are in place to control and record the inspection of selected hull survey items by suitably qualified and trained personnel.

8.1.3 For the requirements and approval procedures, see the appropriate procedures in the *ShipRight Procedures Overview*.

---

### ■ Section 9 Ship Emergency Response Service

#### 9.1 Ship Emergency Response Service – Descriptive note SERS

9.1.1 This service, offered by LR, provides a rapid computer assisted analysis of a damaged ship's stability and damaged longitudinal strength in the event of a casualty to the ship.

9.1.2 Where an Owner adopts this service, the descriptive note **SERS**, 'Ship is registered with LR's Ship Emergency Response Service', will be entered in column 6 of the *Register Book*.

---

### ■ Section 10 Assessment of Ballast Water Management Plans

#### 10.1 Ballast Water Management Plan – Descriptive note BWMP

10.1.1 Compliance with this procedure is optional. A ship meeting the requirements of this procedure will be eligible for an appropriate **ShipRight BWMP** descriptive note, which will be recorded in column 6 of the *Register Book*.





© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

SHIP STRUCTURES (SHIP TYPES)

JULY 2007

PART 4

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

---

PART	1	REGULATIONS
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
PART	3	SHIP STRUCTURES (GENERAL)
<b>PART</b>	<b>4</b>	<b>SHIP STRUCTURES (SHIP TYPES)</b>
	<b>Chapter 1</b>	<b>General Cargo Ships</b>
	<b>2</b>	<b>Ferries, Roll on-Roll off Ships and Passenger Ships</b>
	<b>3</b>	<b>Tugs</b>
	<b>4</b>	<b>Offshore Supply Ships</b>
	<b>5</b>	<b>Barges and Pontoons</b>
	<b>6</b>	<b>Trawlers and Fishing Vessels</b>
	<b>7</b>	<b>Bulk Carriers</b>
	<b>8</b>	<b>Container Ships</b>
	<b>9</b>	<b>Double Hull Oil Tankers</b>
	<b>10</b>	<b>Single Hull Oil Tankers</b>
	<b>11</b>	<b>Ore Carriers</b>
	<b>12</b>	<b>Dredging and Reclamation Craft</b>
PART	5	MAIN AND AUXILIARY MACHINERY
PART	6	CONTROL, ELECTRICAL, REFRIGERATION AND FIRE
PART	7	OTHER SHIP TYPES AND SYSTEMS

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.





---

<b>CHAPTER</b>	<b>1</b>	<b>GENERAL CARGO SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration
	1.3	Class notations
	1.4	Information required
	1.5	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Materials and protection</b>
	2.1	Materials and grades of steel
	2.2	Protection of steelwork
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
	3.2	Fast cargo ships
<b>Section</b>	<b>4</b>	<b>Deck structure</b>
	4.1	General
	4.2	Deck plating
	4.3	Deck stiffening
	4.4	Deck supporting structure
	4.5	Deck openings
<b>Section</b>	<b>5</b>	<b>Shell envelope plating</b>
	5.1	General
	5.2	Keel
	5.3	Bottom shell and bilge
	5.4	Side shell
<b>Section</b>	<b>6</b>	<b>Shell envelope framing</b>
	6.1	General
	6.2	Longitudinal stiffening
	6.3	Transverse stiffening
	6.4	Primary supporting structure
<b>Section</b>	<b>7</b>	<b>Single bottom structure</b>
	7.1	General
	7.2	Girders and floors
<b>Section</b>	<b>8</b>	<b>Double bottom structure</b>
	8.1	Symbols and definitions
	8.2	General
	8.3	Girders
	8.4	Inner bottom plating and stiffening
	8.5	Floors
<b>Section</b>	<b>9</b>	<b>Bulkheads</b>
	9.1	General
	9.2	Watertight and deep tank bulkheads
	9.3	Shaft tunnels
	9.4	Non-watertight bulkheads
<b>CHAPTER</b>	<b>2</b>	<b>FERRIES, ROLL ON-ROLL OFF SHIPS AND PASSENGER SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration
	1.3	Class notations
	1.4	Information required
	1.5	Symbols

---

<b>Section</b>	<b>2</b>	<b>Longitudinal strength</b>
	2.1	General
	2.2	Calculation of hull section modulus
	2.3	Still water bending moments and shear forces
	2.4	Design vertical wave bending moments
	2.5	Design wave shear force
	2.6	Buckling strength
<b>Section</b>	<b>3</b>	<b>Deck structure</b>
	3.1	Loading
	3.2	Deck plating
	3.3	Deck stiffening
	3.4	Deck supporting primary structure
<b>Section</b>	<b>4</b>	<b>Shell envelope plating</b>
	4.1	Bottom and side shell
	4.2	Bow flare and wave impact pressures
	4.3	Strengthening for wave impact loads
<b>Section</b>	<b>5</b>	<b>Shell envelope framing</b>
	5.1	Side structure
	5.2	Strengthening for wave impact loads
<b>Section</b>	<b>6</b>	<b>Double bottom</b>
	6.1	General
	6.2	Transmission of pillar loads
	6.3	Ferries and passenger ships with a specified operating area service
<b>Section</b>	<b>7</b>	<b>Peak, watertight and deep tank bulkheads</b>
	7.1	General
	7.2	Ferries and passenger ships with a specified operating area service
<b>Section</b>	<b>8</b>	<b>Bow doors and inner doors</b>
	8.1	Symbols
	8.2	General
	8.3	Scantlings
	8.4	Vehicle ramps
	8.5	Arrangements for the closing, securing and supporting of doors
	8.6	Design of securing and supporting devices
	8.7	Operating and Maintenance Manual
<b>Section</b>	<b>9</b>	<b>Subdivision structure on vehicle deck</b>
	9.1	General
	9.2	Design loads
	9.3	Height of subdivision structure
	9.4	Material
	9.5	Scantlings of subdivision structure other than doors
	9.6	Scantlings of subdivision doors
	9.7	Closing, securing and supporting of subdivision doors
	9.8	Access doors
	9.9	Watertightness and drainage
	9.10	Ventilation of vehicle deck spaces
	9.11	Operating and Maintenance Manual
<b>Section</b>	<b>10</b>	<b>Masts and standing rigging</b>
	10.1	General
	10.2	Design loadings and allowable stresses
	10.3	Materials of mast construction
	10.4	Standing rigging
	10.5	Design loadings
	10.6	Shroud and stay attachment points
	10.7	Materials for rigging
	10.8	Testing and certification

<b>Section</b>	<b>11</b>	<b>Miscellaneous openings</b>
	11.1	General
	11.2	Openings in main vehicle deck
	11.3	Strength assessment of windows in large passenger ships
	11.4	Frame design and testing

<b>Section</b>	<b>12</b>	<b>Glass structures</b>
	12.1	General
	12.2	Strength of mullions
	12.3	Top rail of balcony balustrades
	12.4	Glass balustrades

<b>Section</b>	<b>13</b>	<b>Direct calculation</b>
	13.1	Application
	13.2	Procedures

## CHAPTER 3 TUGS

<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Class notations
	1.3	Information required

<b>Section</b>	<b>2</b>	<b>Longitudinal strength</b>
	2.1	General

<b>Section</b>	<b>3</b>	<b>Floors in single bottoms</b>
	3.1	Floors

<b>Section</b>	<b>4</b>	<b>Panting and strengthening of bottom forward</b>
	4.1	Panting region reinforcement
	4.2	Strengthening of bottom forward

<b>Section</b>	<b>5</b>	<b>Machinery casings</b>
	5.1	Escape hatches

<b>Section</b>	<b>6</b>	<b>Freeing arrangements</b>
	6.1	General

<b>Section</b>	<b>7</b>	<b>Towing arrangements</b>
	7.1	Towing equipment
	7.2	Towing equipment foundations

<b>Section</b>	<b>8</b>	<b>Fenders</b>
	8.1	Ship's side fenders

<b>Section</b>	<b>9</b>	<b>Escort operation, performance numeral and trials</b>
	9.1	General
	9.2	Towing arrangements
	9.3	Performance trials

## CHAPTER 4 OFFSHORE SUPPLY SHIPS

<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Class notations
	1.3	Information required
	1.4	Symbols

<b>Section</b>	<b>2</b>	<b>Longitudinal strength</b>
	2.1	General

---

<b>Section</b>	<b>3</b>	<b>Hull envelope plating</b>
	3.1	Side shell
	3.2	Weather decks
	3.3	Cargo containment
<b>Section</b>	<b>4</b>	<b>Hull envelope framing</b>
	4.1	Transverse framing
<b>Section</b>	<b>5</b>	<b>Superstructures and deckhouses</b>
	5.1	Scantlings
<b>Section</b>	<b>6</b>	<b>Miscellaneous openings</b>
	6.1	General
	6.2	Access from freeboard deck
	6.3	Windows and side scuttles
<b>Section</b>	<b>7</b>	<b>Watertight bulkhead doors</b>
	7.1	Watertight doors
<b>Section</b>	<b>8</b>	<b>Engine exhaust outlets</b>
	8.1	Location
<b>Section</b>	<b>9</b>	<b>Transport and handling of limited amounts of hazardous and noxious liquid substances in bulk</b>
	9.1	General
<b>CHAPTER</b>	<b>5</b>	<b>BARGES AND PONTOONS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Class notations
	1.3	Information required
	1.4	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Longitudinal strength</b>
	2.1	General
<b>Section</b>	<b>3</b>	<b>Hull envelope plating</b>
	3.1	Shell and deck plating
<b>Section</b>	<b>4</b>	<b>Hull envelope framing</b>
	4.1	Symbols
	4.2	General
	4.3	Longitudinal framing
	4.4	Transverse framing
	4.5	Primary supporting structure
<b>Section</b>	<b>5</b>	<b>Strengthening of bottom forward</b>
	5.1	Application
<b>Section</b>	<b>6</b>	<b>Bottom strengthening for loading and unloading aground</b>
	6.1	Application
<b>Section</b>	<b>7</b>	<b>Watertight bulkheads</b>
	7.1	Collision bulkheads

<b>CHAPTER</b>	<b>6</b>	<b>TRAWLERS AND FISHING VESSELS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Assignment of load lines
	1.3	Class notations
	1.4	Information required
	1.5	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Protection</b>
	2.1	Protection of steelwork
	2.2	Protection of cargo
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
<b>Section</b>	<b>4</b>	<b>Deck structure</b>
	4.1	Deck plating
	4.2	Factory deck beams
<b>Section</b>	<b>5</b>	<b>Shell envelope plating</b>
	5.1	Shell plating
<b>Section</b>	<b>6</b>	<b>Shell envelope framing</b>
	6.1	Transverse side framing
<b>Section</b>	<b>7</b>	<b>Watertight bulkheads</b>
	7.1	Collision bulkheads
<b>Section</b>	<b>8</b>	<b>Stern ramp, and cruiser and transom sterns</b>
	8.1	Stern ramp
	8.2	Cruiser and transom sterns
<b>Section</b>	<b>9</b>	<b>Strengthening of bottom forward</b>
	9.1	General
<b>CHAPTER</b>	<b>7</b>	<b>BULK CARRIERS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	General
	1.2	Application
	1.3	General class notations
	1.4	Class notation for CSR bulk carriers
	1.5	Class notation for non-CSR bulk carriers
	1.6	Information required for CSR bulk carriers
	1.7	Information required for non-CSR bulk carriers
	1.8	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Materials and protection</b>
	2.1	Materials and grades of steel
	2.2	Protection of steelwork
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
	3.2	Hull vertical bending stresses for flooded conditions
	3.3	Shear stresses for flooded conditions
	3.4	Flooded conditions
<b>Section</b>	<b>4</b>	<b>Deck structure</b>
	4.1	General
	4.2	Deck plating
	4.3	Main cargo hatchway openings
	4.4	Deck supporting structure

<b>Section</b>	<b>5</b>	<b>Shell envelope plating</b>
	5.1	General
	5.2	Bottom shell
	5.3	Side shell
<b>Section</b>	<b>6</b>	<b>Shell envelope framing</b>
	6.1	Longitudinal stiffening
	6.2	Transverse stiffening
	6.3	Primary supporting structure
<b>Section</b>	<b>7</b>	<b>Topside tank structure</b>
	7.1	General
	7.2	Bulkhead plating
	7.3	Bulkhead stiffeners
	7.4	Shell and deck structure
	7.5	Primary supporting structure
	7.6	Structural details
<b>Section</b>	<b>8</b>	<b>Double bottom structure</b>
	8.1	General
	8.2	Carriage of heavy cargoes
	8.3	Carriage of heavy cargoes with specified or alternate holds empty
	8.4	Ships to be classed '100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP'
	8.5	Ballast ducts
	8.6	Structural details in way of double bottom tank and hopper tank knuckle
	8.7	Combined double bottom/hopper tank and topside tank
	8.8	Allowable hold loading in the flooded condition
<b>Section</b>	<b>9</b>	<b>Hopper side tank structure</b>
	9.1	General
	9.2	Sloped bulkhead plating
	9.3	Sloped bulkhead stiffeners
	9.4	Shell and bilge stiffeners
	9.5	Tank end bulkheads
	9.6	Primary supporting structure
	9.7	Structural details
<b>Section</b>	<b>10</b>	<b>Bulkheads</b>
	10.1	General
	10.2	Bulkheads supported by stools
	10.3	Structural details in way of holds confined to dry cargoes
	10.4	Vertically corrugated transverse watertight bulkheads – application and definitions
	10.5	Vertically corrugated transverse watertight bulkheads – scantling assessment
	10.6	Vertically corrugated transverse bulkheads – support structure at ends
<b>Section</b>	<b>11</b>	<b>Direct calculation</b>
	11.1	Application
	11.2	Procedures
<b>Section</b>	<b>12</b>	<b>Steel hatch covers</b>
	12.1	General
	12.2	Stiffener arrangement
	12.3	Closing arrangements
	12.4	Load model
	12.5	Allowable stress
	12.6	Effective cross-sectional area of panel flanges for primary supporting members
	12.7	Local net plate thickness
	12.8	Net scantlings of secondary stiffeners
	12.9	Net scantlings of primary supporting members
	12.10	Hatch cover plating
	12.11	Hatch cover secondary stiffeners
	12.12	Web panels of hatch cover primary supporting members
	12.13	Deflection limit and connections between hatch cover panels

<b>Section</b>	<b>13</b>	<b>Hatch coamings</b>
	13.1	General
	13.2	Load model
	13.3	Local net plate thickness
	13.4	Net scantlings of longitudinal and transverse secondary stiffeners
	13.5	Net scantlings of coaming stays
	13.6	Local details
<b>Section</b>	<b>14</b>	<b>Forecastles</b>
	14.1	Arrangement
	14.2	Construction
<b>CHAPTER</b>	<b>8</b>	<b>CONTAINER SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application and definitions
	1.2	Structural configuration
	1.3	Class notations
	1.4	Information required
	1.5	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	Materials
	2.2	Protection of steelwork
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
	3.2	Longitudinal strength
	3.2	Combined longitudinal and torsional strength
<b>Section</b>	<b>4</b>	<b>Deck structure</b>
	4.1	General
	4.2	Primary supporting structure
	4.3	Deck plating and stiffeners
	4.4	Cross decks
	4.5	Deck openings
	4.6	Local reinforcement
	4.7	Support for container corner seats
<b>Section</b>	<b>5</b>	<b>Shell envelope plating</b>
	5.1	General
	5.2	Bottom shell and bilge
	5.3	Side shell and sheerstrake
<b>Section</b>	<b>6</b>	<b>Shell envelope framing</b>
	6.1	General
	6.2	Side shell primary supporting structure
	6.3	Side stringers in double skin construction
	6.4	Transverse webs in double skin construction
	6.5	Minimum thickness of transverse web/side stringers in double skin construction
<b>Section</b>	<b>7</b>	<b>Double bottom structure</b>
	7.1	General
	7.2	Double bottom primary supporting structure
	7.3	Inner bottom plating and stiffening
	7.4	Girders
	7.5	Floors
	7.6	Support for containers

---

<b>Section</b>	<b>8</b>	<b>Longitudinal bulkheads</b>
	8.1	General
	8.2	Side shell primary supporting structure
	8.3	Plating and stiffeners
	8.4	Support for container corner seats
<b>Section</b>	<b>9</b>	<b>Transverse bulkheads</b>
	9.1	General
	9.2	Transverse watertight/non-watertight bulkhead primary supporting structure
	9.3	Transverse watertight bulkheads
	9.4	Transverse non-watertight mid-hold bulkheads
<b>Section</b>	<b>10</b>	<b>Hatch coamings and support for hatch covers</b>
	10.1	Hatch coamings
	10.2	Support for inboard edges of hatch covers by girders
	10.3	Support for hatch cover fillings
<b>Section</b>	<b>11</b>	<b>Hatch covers</b>
	11.1	General
	11.2	Direct calculations
	11.3	Omission of hatch cover gaskets
	11.4	Omission of hatch covers
<b>Section</b>	<b>12</b>	<b>Strengthening for wave impact loads</b>
	12.1	General
<b>Section</b>	<b>13</b>	<b>Container stowage systems</b>
	13.1	Cell guide systems
	13.2	Stowage on decks/hatch covers
<b>Section</b>	<b>14</b>	<b>Direct calculation</b>
	14.1	Procedures for calculation of combined longitudinal and torsional strength
	14.2	Procedures for verification of primary structure scantlings
<b>Section</b>	<b>15</b>	<b>Requirements for ships with large deck openings</b>
	15.1	Application
	15.2	Definitions and information required
	15.3	Symbols and definitions
	15.4	Design loadings
	15.5	Combined stress
	15.6	Permissible stress
<b>CHAPTER</b>	<b>9</b>	<b>DOUBLE HULL OIL TANKERS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	General
	1.2	Application and ship arrangement
	1.3	Class notation and applicable Rules for CSR Double Hull Oil Tankers
	1.4	Class notation and applicable Rules for non-CSR Double Hull Oil Tankers
	1.5	General definitions and symbols
	1.6	Information required for CSR Double Hull Oil Tankers
	1.7	Information required for non-CSR Double Hull Oil Tankers
<b>Section</b>	<b>2</b>	<b>Materials and protection</b>
	2.1	General
	2.2	Corrosion protection coatings for salt water ballast spaces
	2.3	Aluminium structure, fittings and paint
	2.4	Other materials
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
	3.2	Symbols
	3.3	Loading conditions



---

<b>Section</b>	<b>4</b>	<b>Hull envelope plating</b>
	4.1	General
	4.2	Symbols
	4.3	Deck plating
	4.4	Sheerstrake
	4.5	Shell plating
	4.6	Bilge plating
	4.7	Keel
	4.8	Taper of higher tensile steel
	4.9	Thicknesses at ends of erections
	4.10	Deck openings
	4.11	Shell openings
	4.12	Superstructures
<b>Section</b>	<b>5</b>	<b>Hull framing</b>
	5.1	General
	5.2	Symbols
	5.3	Deck, side and bottom longitudinals
	5.4	Bilge longitudinals and brackets
	5.5	Deck longitudinals outside 0,4L amidships
	5.6	Stability of longitudinals
	5.7	Connections of longitudinals
	5.8	Openings in longitudinals
	5.9	Transverse side frames
<b>Section</b>	<b>6</b>	<b>Inner hull, inner bottom and longitudinal oiltight bulkheads</b>
	6.1	General
	6.2	Symbols
	6.3	Inner hull and longitudinal bulkheads
	6.4	Longitudinal corrugated bulkheads
	6.5	Inner bottom
	6.6	Hopper side tank
	6.7	Connections
<b>Section</b>	<b>7</b>	<b>Transverse oiltight bulkheads</b>
	7.1	General
	7.2	Symbols
	7.3	Corrugated bulkheads
	7.4	Bulkheads supported by stools
	7.5	Connections
<b>Section</b>	<b>8</b>	<b>Non-oiltight bulkheads</b>
	8.1	General
	8.2	Symbols
	8.3	Scantlings
	8.4	Connections
<b>Section</b>	<b>9</b>	<b>Primary members supporting longitudinal framing</b>
	9.1	General
	9.2	Symbols
	9.3	Girders and floors in double bottom
	9.4	Vertical webs and horizontal girders in wing ballast tanks and hopper spaces
	9.5	Deck transverses and girders
	9.6	Cross-ties
	9.7	Primary members supporting oiltight bulkheads
	9.8	Primary members supporting non-oiltight bulkheads

<b>Section</b>	<b>10</b>	<b>Construction details and minimum thickness</b>
	10.1	Symbols
	10.2	Compartment minimum thickness
	10.3	Geometric properties and proportions of members
	10.4	Continuity of primary members
	10.5	Primary member web plate stiffening
	10.6	Inertia and dimensions of stiffeners
	10.7	Application of stiffening requirements
	10.8	Stiffening of continuous longitudinal girders
	10.9	Stiffening of vertical webs on transverse bulkheads
	10.10	Double bottom girders in way of docking supports
	10.11	Lateral stability of primary members
	10.12	Openings in web plating
	10.13	Brackets connecting primary members
	10.14	Arrangements at intersections of continuous secondary and primary members
<b>Section</b>	<b>11</b>	<b>Ships for alternate carriage of oil cargo and dry bulk cargo</b>
	11.1	Application
	11.2	Class notations
	11.3	Structural configuration and ship arrangement
	11.4	Bulkheads in way of dry/oil cargo holds
	11.5	Bulkheads in wing tanks of ore or oil carriers
	11.6	Cofferdam bulkheads
	11.7	Hatchways
	11.8	Hatch coamings
<b>Section</b>	<b>12</b>	<b>Heated cargoes</b>
	12.1	General
	12.2	Carriage of heated cargoes
	12.3	Loading of hot oil cargoes
<b>Section</b>	<b>13</b>	<b>Access arrangements and closing appliances</b>
	13.1	General
	13.2	Access to spaces in the cargo area
<b>Section</b>	<b>14</b>	<b>Direct calculations</b>
	14.1	Application
	14.2	Procedures
<b>CHAPTER</b>	<b>10</b>	<b>SINGLE HULL OIL TANKERS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Class notations
<b>Section</b>	<b>2</b>	<b>Primary members supporting longitudinal framing</b>
	2.1	General
	2.2	Symbols
	2.3	Structural arrangements
	2.4	Bottom structure coefficients
	2.5	Bottom transverses
	2.6	Bottom girders
	2.7	Side transverses
	2.8	Deck transverses
	2.9	Deck girders
	2.10	Cross-ties
	2.11	Double bottom girders and floors
<b>Section</b>	<b>3</b>	<b>Primary members supporting transverse side framing</b>
	3.1	General
	3.2	Symbols
	3.3	Structural arrangements
	3.4	Scantlings

<b>Section</b>	<b>4</b>	<b>Primary members supporting oiltight bulkheads</b>
	4.1	General
	4.2	Symbols
	4.3	Structural arrangements
	4.4	Scantlings
<b>Section</b>	<b>5</b>	<b>Primary members supporting non-oiltight bulkheads</b>
	5.1	General
	5.2	Symbols
	5.3	Direct calculations
	5.4	Scantlings and arrangements
<b>Section</b>	<b>6</b>	<b>Trunked construction</b>
	6.1	General
	6.2	Symbols
	6.3	Structural arrangements
	6.4	Trunk scantlings
	6.5	Modification to hull scantlings
<b>Section</b>	<b>7</b>	<b>Construction details and minimum thickness</b>
	7.1	Symbols
	7.2	Compartment minimum thickness
	7.3	Geometric properties and proportions of members
	7.4	Continuity of primary members
	7.5	Primary member web plate stiffening
	7.6	Inertia and dimensions of stiffeners
	7.7	Application of stiffening requirements
	7.8	Stiffening of continuous longitudinal girders
	7.9	Stiffening of vertical webs on transverse bulkheads
	7.10	Docking brackets on bottom centreline girder
	7.11	Lateral stability of primary members
	7.12	Openings in web plating
	7.13	Brackets connecting primary members
	7.14	Arrangements at intersections of continuous secondary and primary members
<b>CHAPTER</b>	<b>11</b>	<b>ORE CARRIERS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Structural configuration and ship arrangement
	1.3	Class notation
	1.4	Symbols and definitions
<b>Section</b>	<b>2</b>	<b>Materials and protection</b>
	2.1	Materials and grades of steel
	2.2	Corrosion protection coating for salt water ballast spaces
<b>Section</b>	<b>3</b>	<b>Longitudinal strength</b>
	3.1	General
<b>Section</b>	<b>4</b>	<b>Hull envelope plating</b>
	4.1	General
	4.2	Deck plating in way of ore hatchways
	4.3	Hatchways
	4.4	Hatch coamings
<b>Section</b>	<b>5</b>	<b>Hull framing</b>
	5.1	General
	5.2	Symbols
	5.3	Bottom longitudinals in double bottom tanks
	5.4	Deck structure in way of centre hold
	5.5	Primary and secondary members inside line of ore hatchways

---

<b>Section</b>	<b>6</b>	<b>Double bottom construction</b>
	6.1	General
	6.2	Arrangement
<b>Section</b>	<b>7</b>	<b>Longitudinal bulkheads</b>
	7.1	General
<b>Section</b>	<b>8</b>	<b>Transverse bulkheads</b>
	8.1	General
	8.2	Transverse watertight bulkheads in wing tanks
	8.3	Transverse watertight bulkheads in centre holds
	8.4	Non-watertight bulkheads
<b>Section</b>	<b>9</b>	<b>Primary structure in wing tanks</b>
	9.1	General
	9.2	Scarfig of double bottom
<b>Section</b>	<b>10</b>	<b>Direct calculations</b>
	10.1	Application
	10.2	Procedures
<b>Section</b>	<b>11</b>	<b>Forecastles</b>
	11.1	General
<b>CHAPTER</b>	<b>12</b>	<b>DREDGING AND RECLAMATION CRAFT</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Stability
	1.3	Class notations
	1.4	Information required
	1.5	Symbols
<b>Section</b>	<b>2</b>	<b>Longitudinal strength</b>
	2.1	General
	2.2	Loading conditions
	2.3	Hull bending strength
	2.4	Design vertical wave bending moments
	2.5	Permissible still water bending moment for dredging conditions
	2.6	Calculation of hull section modulus
	2.7	Hull shear strength
<b>Section</b>	<b>3</b>	<b>Deck structure</b>
	3.1	Deck plating
	3.2	Deck stiffening
	3.3	Deck supporting structure
<b>Section</b>	<b>4</b>	<b>Shell envelope plating</b>
	4.1	Keel
	4.2	Bottom shell
	4.3	Operating aground
	4.4	Bottom openings
	4.5	Ships with chines
	4.6	Side shell
	4.7	Swim ends
<b>Section</b>	<b>5</b>	<b>Shell envelope framing</b>
	5.1	Longitudinal stiffening
	5.2	Transverse stiffening
	5.3	Primary supporting structure at sides

---

<b>Section</b>	<b>6</b>	<b>Bottom structure</b>
	6.1	General
	6.2	Single bottoms transversely framed
	6.3	Single bottoms longitudinally framed
	6.4	Double bottom – General
	6.5	Double bottom with transverse framing
	6.6	Double bottom with longitudinal framing
<b>Section</b>	<b>7</b>	<b>Bottom strengthening for operating aground</b>
	7.1	Application
<b>Section</b>	<b>8</b>	<b>Spoil space and well structure</b>
	8.1	Symbols and definitions
	8.2	General
	8.3	Spoil space and well boundaries
	8.4	Cross-members
	8.5	Pillars within hoppers
	8.6	Continuous coamings
<b>Section</b>	<b>9</b>	<b>Watertight bulkheads</b>
	9.1	Arrangements of bulkheads
<b>Section</b>	<b>10</b>	<b>Exposed casings</b>
	10.1	Scantlings and access
<b>Section</b>	<b>11</b>	<b>Dredging machinery seats and dredging gear</b>
	11.1	Dredging machinery seats
	11.2	Dredging gear
<b>Section</b>	<b>12</b>	<b>Ladder wells</b>
	12.1	Transverse strength at deck
<b>Section</b>	<b>13</b>	<b>Fenders</b>
	13.1	Fenders and reinforcement in way
<b>Section</b>	<b>14</b>	<b>Rudders</b>
	14.1	Rudders on bucket dredgers
<b>Section</b>	<b>15</b>	<b>Spoil space weirs and overflows</b>
	15.1	General
<b>Section</b>	<b>16</b>	<b>Scuppers and sanitary discharges and side scuttles</b>
	16.1	General
<b>Section</b>	<b>17</b>	<b>Split hopper dredgers and barges</b>
	17.1	Symbols and definitions
	17.2	Hull bending strength
	17.3	Separation arrangements
	17.4	Hinge pins
<b>Section</b>	<b>18</b>	<b>Direct calculations</b>
	18.1	Application
	18.2	Procedures



# General Cargo Ships

# Part 4, Chapter 1

Section 1

## Section

- 1 **General**
- 2 **Materials and protection**
- 3 **Longitudinal strength**
- 4 **Deck structure**
- 5 **Shell envelope plating**
- 6 **Shell envelope framing**
- 7 **Single bottom structure**
- 8 **Double bottom structure**
- 9 **Bulkheads**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to sea-going ships designed primarily for the carriage of general cargo. The requirements are intended to cover the midship region, but may also apply with suitable modification to the taper regions forward and aft in way of cargo spaces.

### 1.2 Structural configuration

1.2.1 The Rules provide for a basic structural configuration of a multi-deck or a single deck hull which includes a double bottom, or a single bottom arrangement. The structural configuration may also include a single or multiple arrangement of cargo hatch openings, and side tanks.

1.2.2 Individual consideration may be required where the ship incorporates double hull construction, large deck openings or other special design features.

1.2.3 Longitudinal framing is, in general, to be adopted at the strength deck outside line of openings and at the bottom, but special consideration will be given to proposals for transverse framing in these regions.

### 1.3 Class notations

1.3.1 In general, ships complying with the requirements of this Chapter will be eligible to be classed **100A1**.

1.3.2 Where a ship has been specially strengthened for heavy cargoes in accordance with the requirements listed in Ch 7,8.2, it will be eligible to be classed **100A1 strengthened for heavy cargoes**.

1.3.3 Ships intended to be operated only in suitable areas or conditions which have been agreed by the Committee, as defined in Pt 1, Ch 2,2.3.6 to 2.3.10, will receive individual consideration on the basis of the Rules with respect to the environmental conditions agreed for the design basis and approval.

1.3.4 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2, to which reference should be made.

### 1.4 Information required

1.4.1 For the information required, see Pt 3, Ch 1,5. In addition the following are to be supplied:

- (a) Cargo loadings on decks, hatchways and inner bottom if these are to be in excess of Rule. Where concentrated or point loads occur, their magnitude and points of application are to be defined.
- (b) The maximum pressure head in service on tanks, also details of any double bottom tanks interconnected with side tanks.
- (c) Details of the proposed depths of any partial fillings where water ballast or liquid cargo is intended to be carried in the holds, or large deep tanks.

### 1.5 Symbols and definitions

1.5.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L, B, D, T$  and  $V$  as defined in Pt 3, Ch 1,6

$k_L, k_e$  = higher tensile steel factor, see Pt 3, Ch 2,1

$e$  = base of natural logarithms, 2,7183

$l$  = overall length of stiffening member, or pillar, in metres, see Pt 3, Ch 3,3

$l_e$  = effective length of stiffening member, or pillar, in metres, see Pt 3, Ch 3,3

$t$  = thickness of plating, in mm

$s$  = spacing of secondary stiffeners, in mm

$A$  = cross-sectional area of stiffening member, in cm<sup>2</sup>

$C$  = stowage rate, in m<sup>3</sup>/tonne, see Pt 3, Ch 3,5

$C_w$  = a wave head in metres

=  $7,71 \times 10^{-2} L e^{-0,0044L}$

$I$  = inertia of stiffening member, in cm<sup>4</sup>, see Pt 3, Ch 3,3

$S$  = spacing or mean spacing of primary members, in metres

$Z$  = section modulus of stiffening member, in cm<sup>3</sup>, see Pt 3, Ch 3,3

$\rho$  = relative density (specific gravity) of liquid carried in a tank but is not to be taken less than 1,025.

## ■ Section 2 Materials and protection

### 2.1 Materials and grades of steel

2.1.1 Materials and grades of steel are to comply with the requirements of Pt 3, Ch 2.

### 2.2 Protection of steelwork

2.2.1 For the protection of steelwork, in addition to the requirements specified in Pt 3, Ch 2,3 the requirements of 2.2.2 to 2.2.4 are to be complied with.

2.2.2 Ceiling is to be laid on the inner bottom under cargo hatchways, but may be omitted provided that the inner bottom plating is increased by 2 mm. In any ship which is regularly to be discharged by grabs, ceiling is to be laid on the inner bottom, and the inner bottom plating increased by 3 mm. Alternatively, the ceiling may be omitted provided that the inner bottom plating is increased in thickness by a minimum of 5 mm. The ceiling is to be 76 mm thick in softwood or 65 mm thick in hardwood, and is to be laid at right angles to the inner bottom stiffening. Where it is intended to use plywood or other forms of ceiling of an approved type instead of planking, the thickness will be considered for each case. Ceiling is also to be laid over bilges, and fitted with portable sections which are to be readily removable. The spaces between the frames at the top of the bilge ceiling are to be closed by steel plates, wood chocks, cement or other suitable means. Inner bottom manhole covers or fittings, where projecting above the inner bottom plating, are to be provided with a steel protection coaming around each manhole, and a wood or steel cover is to be fitted.

2.2.3 Where plated decks are sheathed with wood or approved compositions, the minimum thicknesses given in 4.2, Pt 3, Ch 5,2 and Pt 3, Ch 6,2 may be reduced by 10 per cent for a 50 mm sheathing thickness or five per cent for 25 mm, with intermediate values in proportion. The steel deck is to be coated with a suitable material in order to prevent corrosive action, and the sheathing or composition is to be effectively secured to the deck. See also the fire protection requirements relating to deck coverings in the relevant SOLAS Regulations or Pt 6, Ch 4,3 as applicable.

2.2.4 Where cargo battens or equivalent are fitted in the holds of dry cargo ships, the descriptive note 'SF' will be entered in the *Register Book*. The battens, when fitted, are to extend from above the upper part of the bilge to the underside of beam knees in the holds, and in all cargo spaces in the 'tween decks and superstructures, up to the underside of beam knees. Wood cargo battens are to be not less than 50 mm in thickness, and the clear space between adjacent rows is, in general, not to exceed 230 mm. The dimensions and spacing of battens made of other materials will be considered. Nets may be adopted in lieu of battens, and other alternative proposals will be specially considered. For arrangements in way of a refrigerated hold, see Pt 6, Ch 3,4.

## ■ Section 3 Longitudinal strength

### 3.1 General

3.1.1 Longitudinal strength calculations are to be made in accordance with the requirements given in Pt 3, Ch 4.

3.1.2 The requirements of Pt 3, Ch 4,8.3 regarding loading instruments are not applicable to general cargo ships under 120 m.

### 3.2 Fast cargo ships

3.2.1 The hull section modulus for ships of length,  $L$ , between 120 m, and 170 m, and maximum service speed greater than 17,5 knots in association with a bow shape factor,  $\psi$ , of more than 0,15, is to comply with the requirements of this sub-Section.

3.2.2 The bow shape factor is defined as:

$$\Psi = \frac{100 \Sigma A_b}{L^{1,5} B}$$

where

- $a_0$  = projection of upper deck at waterline (F.P.), in metres
- $a_1$  = projection of upper deck at waterline (0,1L from F.P.), in metres
- $a_2$  = projection of upper deck at waterline (0,2L from F.P.), in metres
- $b$  = projection of upper deck at waterline (F.P. to bow line), in metres

$$\Sigma A_b = \frac{ba_0}{2} + 0,1L (a_1 + a_2) \text{ m}^2$$

See also Fig. 1.3.1.

3.2.3 For longitudinal strength requirements, the Rule minimum hull midship section modulus and the distribution of longitudinal material in the forward half-length will be considered. In general, the following requirements are to be complied with:


- (a) The vertical hull midship section modulus, about the horizontal neutral axis, at deck is to be not less than  $331Lk\Sigma A_b \text{ cm}^3$ , or that required by Pt 3, Ch 4,5, whichever is the greater.  $\Sigma A_b$  is defined in 3.2.2.
- (b) The horizontal hull midship section modulus, about a vertical axis through the ship centreline, is to be not less than  $32,5L^2D \text{ cm}^3$ .
- (c) In the forward half-length, the hull section modulus is not to be a lesser percentage of the midship value than that shown in Table 1.3.1.
- (d) Any load or ballast condition resulting in a sagging still water bending moment, or a hogging moment less than 80 per cent of the Rule value of still water bending moment, will be specially considered with a view to minimizing the compressive stresses in the deck in waves.



# General Cargo Ships

# Part 4, Chapter 1

Section 3



**Fig. 1.3.1 Derivation of bow shape factor**

**Table 1.3.1 Fast cargo ships**

Position	Percentage of midship vertical modulus (modulus about horizontal axis)	Percentage of midship horizontal modulus (modulus about vertical axis)
Station 10 (mid- $L_{pp}$ )	100	100
12	98	87
14	95	62
16	81	38
18	44	17
20 (F.P.)	0	0

NOTES  
 1. Intermediate values to be obtained by interpolation.  
 2.  $L_{pp}$  as defined in Pt 3, Ch 1,6.

3.2.4 For local strength, in general the following requirements are to be complied with:

- Longitudinal deck stiffening is to be carried forward to the fore peak bulkhead or as far forward as practical. Where a long forecastle is fitted, the buckling strength of the proposed structure will be specially considered.
- Substantial web frames in way of deck transverses are to be fitted in the forward half-length. Scantlings of webs and frames are to be based on actual lengths, not 'tween deck heights, and collars are to be fitted at ends of members in way of high shear.
- Scantlings of bottom structure in forward part are to be specially considered.

- Deck and side shell panels forward of 0,5L from F.P. are to be examined to establish the critical buckling stress from the following formula:

$$\sigma_c = \frac{\pi^2 E}{12 (1 - \nu^2)} \left( \frac{t}{s} \right)^2 K_c \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

- $s$  = length of shorter edge, in mm
  - $t$  = thickness of plating, in mm
  - $E$  = Young's modulus, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
  - $K_c$  = a factor depending on aspect ratio and boundary restraint  
 = 4 for longitudinally stiffened plating or as shown in Fig. 1.3.2 for transversely stiffened plating
  - $\nu$  = Poisson's ratio (0,3 for steel and aluminium alloy).
- Where the buckling stresses, as evaluated, exceed 50 per cent of yield stress, the actual critical buckling stress is given by:


$$\sigma_{ac} = \sigma_o \left( 1 - \frac{\sigma_o}{4\sigma_c} \right) \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

- $\sigma_{ac}$  = corrected critical buckling stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)
- $\sigma_o$  = yield stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

The critical buckling stress from the above formulae must be not less than 176,6 N/mm<sup>2</sup> (18,0 kgf/mm<sup>2</sup>) within 0,4L amidships, nor less than 147,2 N/mm<sup>2</sup> (15,0 kgf/mm<sup>2</sup>) for the deck forward of this, nor less than 117,7 N/mm<sup>2</sup> (12,0 kgf/mm<sup>2</sup>) for the side shell between the first and second deck forward of 0,5L from F.P. For higher tensile steel plating, the above permissible stresses are to be divided by  $k$ .

- In order to obtain the necessary critical buckling strength, either of the following is to be applied:
  - plate thickness to be increased, or
  - panel aspect ratio to be altered by the fitting of additional panel stiffening.



**Fig. 1.3.2 Plate factor,  $K_c$**

# General Cargo Ships

# Part 4, Chapter 1

Section 4

## Section 4 Deck structure

### 4.1 General

4.1.1 Longitudinal framing is, in general, to be adopted at the strength deck outside line of openings, but special consideration will be given to proposals for transverse framing. Requirements are given in this Section for longitudinal and transverse framing systems of all deck structure, except decks in way of erections. For erection decks, see Pt 3, Ch 8.

### 4.2 Deck plating

4.2.1 The thickness of strength/weather deck plating in the midship region is to comply with the requirements of Table 1.4.1. Outside the line of openings the thickness is also to be that necessary to give the hull section modulus required by Pt 3, Ch 4,5.

4.2.2 The thickness of lower deck plating in the midship region is to comply with the requirements of Table 1.4.2.

4.2.3 The thickness of the strength deck stringer plate is to be increased by 20 per cent at the ends of bridges, poop and forecastle.

4.2.4 The deck plating thickness and supporting structure are to be suitably reinforced in way of cranes, masts, derrick posts and deck machinery.

4.2.5 Where long, wide hatchways are arranged on lower decks, it may be necessary to increase the deck plating thickness to ensure effective support for side framing.

### 4.3 Deck stiffening

4.3.1 The scantlings of strength/weather deck longitudinals in the midship region are to comply with the requirements of Table 1.4.3.

4.3.2 The lateral and torsional stability of longitudinals together with web and flange buckling criteria are to be verified in accordance with Pt 3, Ch 4,7.

4.3.3 The scantlings of cargo and accommodation deck longitudinals are to comply with the requirements of Table 1.4.4.

4.3.4 End connections of longitudinals to bulkheads are to provide adequate fixity and, so far as is practicable, direct continuity of longitudinal strength. Where  $L$  exceeds 215 m, the deck longitudinals are to be continuous through transverse structure, including bulkheads, but alternative arrangements will be considered. Higher tensile steel deck longitudinals are to be continuous irrespective of the ship length.

4.3.5 The scantlings of strength/weather, cargo and accommodation deck transverse beams are to comply with the requirements of Table 1.4.5.

**Table 1.4.1 Strength/weather deck plating**

Location	Minimum thickness, in mm <i>see also</i> 4.2.1	
	Longitudinal framing	Transverse framing
(1) Outside line of openings (see Notes 1 and 2)	The greater of the following: (a) $t = 0,001s_1 (0,059L_1 + 7) \sqrt{\frac{F_D}{k_L}}$ (b) $t = 0,00083s_1 \sqrt{Lk} + 2,5$	The greater of the following: (a) $t = 0,001s_1 f_1 (0,083L_1 + 10) \sqrt{\frac{F_D}{k_L}}$ (b) $t = 0,001s_1 \sqrt{Lk} + 2,5$
(2) Inside line of openings (see Note 2)	$t = 0,00083s_1 \sqrt{Lk} + 2,5$ but not less than 6,5	$t = 0,00083s_1 \sqrt{Lk} + 1,5$ but not less than 6,5
(3) In way of the crown of a tank	$t = 0,004sf \sqrt{\frac{\rho k h_4}{1,025}} + 3,5$ or as (1) or (2), whichever is the greater, but not less than 7,5 mm where $L \geq 90$ m, or 6,5 mm where $L < 90$ m	
Symbols		
$L, k_L, k, p, s, S$ as defined in 1.5.1 $f = 1,1 - \frac{s}{2500S}$ but not to be taken greater than 1,0 $f_1 = \frac{1}{1 + \left(\frac{s}{1000S}\right)^2}$		
$h_4 =$ tank head, in metres, as defined in Pt 3, Ch 3,5 $s_1 = s$ but is not to be taken less than the smaller of $470 + \frac{L}{0,6}$ mm or 700 mm $F_D =$ as defined in Pt 3, Ch 4,5.6 $L_1 = L$ but need not be taken greater than 190 m		
NOTES 1. The thickness derived in accordance with (1) is also to satisfy the buckling requirements of Pt 3, Ch 4,7. 2. The deck thickness is to be not less than the basic end deck thickness as given in Pt 3, Ch 5 and Ch 6.		

## General Cargo Ships

## Part 4, Chapter 1

Section 4

Table 1.4.2 Lower deck plating

Symbols	Location	Minimum thickness, in mm	
		Second deck	Third or platform decks
$s, S, k, p$ as defined in 1.5.1 $b$ = breadth of increased plating, in mm $f = 1,1 - \frac{s}{2500S}$ but not to be taken greater than 1,0 $h_4$ = tank head, in metres, as defined in Pt 3, Ch 3,5 $s_1 = s$ but is not to be taken less than the smaller of $470 + \frac{L}{0,6}$ mm or 700 mm $A_f$ = girder face area, in cm <sup>2</sup> $K_1$ = 2,5 mm at bottom of tank = 3,5 mm at crown of tank	(1) Outside line of openings	$t = 0,012s_1 \sqrt{k}$ but not less than 6,5	$t = 0,01s_1 \sqrt{k}$ but not less than 6,5
	(2) Inside line of openings	$t = 0,01s_1 \sqrt{k}$ but not less than 6,5	
	(3) In way of the crown or bottom of a tank	$t = 0,004sf \sqrt{\frac{pkh_4}{1,025}} + K_1$  but not less than 7,5 where $L \geq 90$ m, or 6,5 where $L < 90$ m	
	(4) Plating forming the upper flange of underdeck girders	Clear of deck openings, $t = \sqrt{\frac{A_f}{1,8k}}$  In way of deck openings, $t = 1,1 \sqrt{\frac{A_f}{1,8k}}$  Minimum breadth, $b = 760$ mm	
NOTE Where a deck loading exceeds 43,2 kN/m <sup>2</sup> (4,4 tonne-f/m <sup>2</sup> ), the thickness of plating will be specially considered.			

Table 1.4.3 Strength/weather deck longitudinals

Symbols	Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
$L, s, k_L, k, p$ as defined in 1.5.1 $b = 1,4$ for rolled or built sections = 1,6 for flat bars $c_1 = \frac{60}{225 - 165 F_D}$ $d_w$ = depth of longitudinal, in mm $F_1 = 0,25c_1$ $h_1$ = weather head, in metres, as defined in Pt 3, Ch 3,5 $h_4$ = tank head, in metres, as defined in Pt 3, Ch 3,5 $l_e$ = as defined in 1.5.1, but not to be taken less than 1,5 m $F_D$ = as defined in Pt 3, Ch 4,5,6 $h_{T1} = \frac{L_1}{56}$ for Type 'B-60' ships = the greater of $\frac{L_1}{70}$ or 1,20 m for Type 'B' ships $L_1 = L$ but need not be taken greater than 190 m $L_2 = L$ but need not be taken greater than 215 m	(1) In way of dry cargo spaces, see Note 1		
	(a) Outside line of openings	$Z = 0,043 s k h_{T1} l_e^2 F_1$	—
	(b) Inside line of openings	$Z = s k (400h_1 + 0,005 (l_e L_2)^2) \times 10^{-4}$	—
	(2) In way of the crown or bottom of a tank	$Z = \frac{0,0113 p s k h_4 l_e^2}{b}$ or as (1)(a) or (1)(b) above, whichever is the greater	$I = \frac{2,3}{k} l_e Z$
	(3) In way of superstructure	To be specially considered	—
NOTES 1. Where weather decks are intended to carry deck cargo and the load is in excess of 8,5 kN/m <sup>2</sup> (0,865 tonne-f/m <sup>2</sup> ), the scantlings of longitudinals may be required to be increased to comply with the requirements for location (1) Table 1.4.4 using the equivalent design head, for specified cargo loading, for weather decks given in Table 3.5.1 in Pt 3, Ch 3. 2. The buckling requirements of Pt 3, Ch 4,7 are to be complied with. The ratio of the web depth $d_w$ to web thickness $t$ is to comply with the following requirements: (a) Built up profiles and rolled angles: $\frac{d_w}{t} \leq 60 \sqrt{k_L}$ (b) Flat bars: $\frac{d_w}{t} \leq 18 \sqrt{k_L}$ when continuous at bulkheads $\frac{d_w}{t} \leq 15 \sqrt{k_L}$ when non-continuous at bulkheads 3. The web depth of longitudinals, $d_w$ is to be not less than 60 mm.			

## General Cargo Ships

## Part 4, Chapter 1

Section 4

Table 1.4.4 Cargo and accommodation deck longitudinals

Symbols	Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
$L, s, k, p$ as defined in 1.5.1 $d_w$ = web depth of longitudinal, in mm, see Note 2 $h_2$ = cargo head, in metres, as defined in Pt 3, Ch 3,5 $h_3$ = accommodation head, in metres, as defined in Pt 3, Ch 3,5 $h_4$ = tank head, in metres, as defined in Pt 3, Ch 3,5 $l_e$ = as defined in 1.5.1, but not to be taken less than 1,5 m $L_1$ = $L$ but need not be taken greater than 190 m $\gamma$ = 1,4 for rolled or built sections = 1,6 for flat bars	(1) Cargo decks		
	(a) $L \geq 90$ m	$Z = sk(5,9L_1 + 25h_2 l_e^2) \times 10^{-4}$	—
	(b) $L < 90$ m	$Z = 0,005s k h_2 l_e^2$	—
	(2) Accommodation decks		
	(a) $L \geq 90$ m	$Z = sk(5,1L_1 + 25h_3 l_e^2) \times 10^{-4}$	—
	(b) $L < 90$ m	$Z = 0,00425s k h_3 l_e^2$ See Note 1	—
	(3) In way of the crown or bottom of a tank	As in (1) or (2) as applicable, or $Z = \frac{0,0113p s k h_4 l_e^2}{\gamma}$ whichever is the greater	$I = \frac{2,3}{k} l_e Z$
NOTES 1. The section modulus of accommodation deck longitudinals need not be taken greater than the value required by location (1)(a), in Table 1.4.3 . 2. The web depth of longitudinals, $d_w$ , to be not less than 60 mm.			

Table 1.4.5 Strength/weather, cargo and accommodation deck beams

Symbols	Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
$B, D, T, s, k, p$ as defined in 1.5.1 $d_w$ = depth of beam, in mm $h_1$ = weather deck head $h_2$ = cargo head $h_3$ = accommodation head $h_4$ = tank head $l_e$ as defined in 1.5.1, but to be taken as not less than 1,83 m $B_1 = B$ , but need not be taken greater than 21,5 m $K_1$ = a factor dependent on the number of decks (including poop and bridge superstructures) at the position of the beam under consideration: 1 deck 20,0    3 decks 10,5 2 decks 13,3    4 or more 9,3 $K_2$ = a factor dependent on the location of the beam: at short bridge and poops 133 elsewhere 530 $K_3$ = a factor dependent on the location of the beam: span adjacent to the ship side 3,6 elsewhere 3,3 $\gamma$ = 1,4 for rolled or built sections = 1,6 for flat bars	(1) Strength/weather decks	The lesser of the following: (a) $Z = (K_1 K_2 T D + K_3 B_1 s h_1 l_e^2) k \times 10^{-4}$ (b) $Z = 2K_3 B_1 s k h_1 l_e^2 \times 10^{-4}$	—
	(2) Cargo decks	$Z = (400K_1 T D + 38,8s h_2 l_e^2) k \times 10^{-4}$	—
	(3) Accommodation decks	$Z = (530K_1 T D + 38,8s h_3 l_e^2) k \times 10^{-4}$	—
	(4) In way of the crown or bottom of a tank	As (1), (2) or (3) as applicable, or $Z = \frac{0,0113p s k h_4 l_e^2}{\gamma}$ whichever is the greater	$I = \frac{2,3}{k} l_e Z$
	NOTES 1. Where weather decks are intended to carry deck cargo and the load is in excess of 8,5 kN/m <sup>2</sup> (0,865 tonne-f/m <sup>2</sup> ), the scantlings of beams may be required to be increased to comply with the requirements for location (2) using the equivalent design head, for specified cargo loading, for weather decks given in Table 3.5.1 in Pt 3, Ch 3. 2. The web depth of beams, $d_w$ , is to be not less than 60 mm.		

# General Cargo Ships

# Part 4, Chapter 1

## Section 4

4.3.6 The end connections of beams are to be in accordance with the requirements of Pt 3, Ch 10,3.

### 4.4 Deck supporting structure

4.4.1 **Girders and transverses** supporting deck longitudinals and beams, also hatch side girders and hatch end beams, are to comply with the requirements of Table 1.4.6. In general, transverses, webs or frames of increased scantlings, see Table 1.6.2, are to be arranged in way of hatch end beams and deck transverses, and these are to be in line with the double bottom floors where practicable. Equivalent transverse ring scantling arrangements will be considered.

4.4.2 **Transverses** supporting deck longitudinals are, in general, to be spaced not more than 3,8 m apart where the length,  $L$ , is 100 m or less, and  $(0,006L + 3,2)$  m apart where  $L$  is greater than 100 m.

4.4.3 The web thickness, stiffening arrangements and end connection of primary supporting members are to be in accordance with Pt 3, Ch 10,4.

4.4.4 Where a girder is subject to concentrated loads, such as pillars out of line, the scantlings are to be suitably increased. Also, where concentrations of loading on one side of the girder may occur, the girder is to be adequately stiffened against torsion. Reinforcements may be required in way of localized areas of high stress.

4.4.5 **Pillars** are to comply with the requirements of Table 1.4.7.

4.4.6 Pillars are to be fitted in the same vertical line wherever possible, and effective arrangements are to be made to distribute the load at the heads and heels of all pillars. Where pillars support eccentric loads, they are to be strengthened for the additional bending moment imposed upon them.

4.4.7 Tubular and hollow square pillars are to be attached at their heads to plates supported by efficient brackets, in order to transmit the load effectively. Doubling or insert plates are to be fitted to the inner bottom under the heels of tubular or hollow square pillars, and to decks under large pillars. The pillars are to have a bearing fit and are to be attached to the head and heel plates by continuous welding. At the heads and heels of pillars built of rolled sections, the load is to be well distributed by means of longitudinal and transverse brackets.

4.4.8 In double bottoms under widely spaced pillars, the connections of the floors to the girders, and of the floors and girders to the inner bottom, are to be suitably increased. Where pillars are not directly above the intersection of plate floors and girders, partial floors and intercostals are to be fitted as necessary to support the pillars. Manholes are not to be cut in the floors and girders below the heels of pillars. Where longitudinal framing is adopted in the double bottom, equivalent stiffening under the heels of pillars is to be provided, and where the heels of pillars are carried on a tunnel, suitable arrangements are to be made to support the load.

4.4.9 Where pillars are fitted inside tanks or under watertight flats, the tensile stress in the pillar and its end connections is not to exceed  $108 \text{ N/mm}^2$  ( $11,0 \text{ kgf/mm}^2$ ) at the test heads. In general, such pillars should be of built sections, and end brackets may be required.

4.4.10 Pillars are to be fitted below deckhouses, windlasses, winches, capstans and elsewhere where considered necessary.

4.4.11 **Non-watertight pillar bulkheads** are to comply with the requirements of Table 1.4.8.

4.4.12 **Cantilevers** and their supporting frames are to comply with the requirements of Table 1.4.9.

### 4.5 Deck openings

4.5.1 The corners of main cargo hatchways in the strength deck within  $0,5L$  amidships are to be elliptical, parabolic or rounded, with a radius generally not less than  $1/24$  of the breadth of the opening. Rounded corners are to have a minimum radius of 300 mm if the deck plating extends inside the coaming, or 150 mm if the coamings are welded to the inner edge of the plating in the form of a spigot. Where elliptical corners are arranged, the major axis is to be fore and aft, the ratio of the major to minor axis is to be not less than 2 to 1 nor greater than 2,5 to 1, and the minimum half-length of the major axis is to be defined by  $I_1$  in Fig. 1.4.5. Where parabolic corners are arranged, the dimensions are also to be as shown in Fig. 1.4.5.

4.5.2 Where the corners of large openings in the strength deck are parabolic or elliptical, insert plates are not required. For other shapes of corner, insert plates of the size and extent shown in Fig. 1.4.6 will, in general, be required. The required thickness of the insert plate is to be not less than 25 per cent greater than the adjacent deck thickness, outside line of openings with a minimum increase of 4 mm. The increase need not exceed 7 mm.

4.5.3 Welded attachments close to or on the free edge of the hatch corner plating are to be avoided (e.g. welded protection strips or shedder plates) and the butt welds of corner insert plates to the adjacent deck plating are to be located well clear of butts in the hatch coaming.

4.5.4 Openings in the strength deck outside the line of hatch openings are to be kept to the minimum number consistent with operational requirements. Openings are to be arranged clear of hatch corners and, so far as possible, clear of one another. Where, within  $0,4L$  amidships, deck openings have a total breadth or shadow area breadth, in one transverse section that exceeds the limitation given in Pt 3, Ch 3,3.4.4 and 3.4.5, compensation will be required to restore the excess. This is generally to be arranged by increasing the deck plate thickness, but other proposals will be considered. Plate panels in which openings are cut are to be adequately stiffened, where necessary, against compression and shear buckling. The corners of all openings are to be well rounded and the edges smooth.



# General Cargo Ships

# Part 4, Chapter 1

Section 4

**Table 1.4.7 Pillars**

Symbols	Parameter	Requirement
<p> <math>b</math> = breadth of side of a hollow rectangular pillar or breadth of flange or web of a built or rolled section, in mm  <math>d_p</math> = mean diameter of tubular pillars, in mm  <math>k</math> = local scantling higher tensile steel factor, see Pt 3, Ch 2, 1.2.3, but not less than 0,72  <math>l</math> = overall length of pillar, in metres  <math>l_e</math> = effective length of pillar, in metres, and is taken as:  for hold pillars 0,65<i>l</i>  for 'tween deck pillars 0,80<i>l</i>  <math>l_p</math> = distance, in metres, between centres of the two adjacent spans of girder, or transverse, supported by the pillar  <math>r</math> = least radius of gyration of pillar cross-section, in mm, and may be taken as:  <math display="block">r = 10 \sqrt{\frac{I}{A_p}} \text{ mm}</math> <math>A_p</math> = cross-sectional area of pillar, in cm<sup>2</sup>  <math>C, S</math> as defined in 1.5.1  <math>H_g</math> as defined in Table 1.4.6  <math>I</math> = least moment of inertia of cross-section, in cm<sup>4</sup>  <math>P</math> = load, in kN (tonne-f), supported by the pillar and is to be taken as  <math display="block">\frac{9,81 SH_g l_p}{C} + P_a \left( \frac{SH_g l_p}{C} + P_a \right)</math> but not less than 19,62 kN (2 tonne-f)  <math>P_a</math> = load, in kN (tonne-f), from pillar or pillars above (zero if no pillars over) </p>	(1) Cross-sectional area of all types of pillar	$A_p = \frac{k P}{12,36 - 51,5 \frac{l_e}{r \sqrt{k}}} \text{ cm}^2$ $\left( A_p = \frac{k P}{1,26 - 5,25 \frac{l_e}{r \sqrt{k}}} \text{ cm}^2 \right)$ <p>See Note</p>
	(2) Minimum wall thickness of tubular pillars	<p>The greater of the following:</p> <p>(a) <math>t = \frac{P}{d_p \left( 0,392 - 1,53 \frac{l_e}{r} \right)} \text{ mm}</math></p> <p>(a) <math>\left( t = \frac{P}{d_p \left( 0,04 - 0,156 \frac{l_e}{r} \right)} \right) \text{ mm}</math></p> <p>(b) <math>t = \frac{d_p}{40} \text{ mm}</math></p> <p>but not to be less than  <math>t = 5,5 \text{ mm}</math> where <math>L &lt; 90 \text{ m}</math>, or  <math>t = 7,5 \text{ mm}</math> where <math>L \geq 90 \text{ m}</math></p>
	(3) Minimum wall thickness of hollow rectangular pillars or web plate thickness of I or channel sections	<p>The lesser of (b) and (c), but not to be less than (a):</p> <p>(a) <math>t = \frac{P}{b \left( 0,5 - 1,95 \frac{l_e}{r} \right)} \text{ mm}</math></p> <p>(a) <math>\left( t = \frac{P}{b \left( 0,05 - 0,2 \frac{l_e}{r} \right)} \right) \text{ mm}</math></p> <p>(b) <math>t = \frac{br}{600 l_e} \text{ mm}</math></p> <p>(c) <math>t = \frac{b}{55} \text{ mm}</math></p> <p>but to be not less than  <math>t = 5,5 \text{ mm}</math> where <math>L &lt; 90 \text{ m}</math>, or  <math>t = 7,5 \text{ mm}</math> where <math>L \geq 90 \text{ m}</math></p>
	(4) Minimum thickness of flanges of angle or channel sections	<p>The lesser of the following:</p> <p>(a) <math>t_f = \frac{br}{200 l_e} \text{ mm}</math></p> <p>(b) <math>t_f = \frac{b}{18} \text{ mm}</math></p>
	(5) Minimum thickness of flanges of built or rolled I sections	<p>The lesser of the following:</p> <p>(a) <math>t_f = \frac{br}{400 l_e} \text{ mm}</math></p> <p>(b) <math>t_f = \frac{b}{36} \text{ mm}</math></p>
<p><b>NOTE</b></p> <p>As a first approximation <math>A_p</math> may be taken as <math>\frac{k P}{9,32} \left( \frac{k P}{0,95} \right)</math> and the radius of gyration estimated for a suitable section having this area.</p> <p>If the area calculated using this radius of gyration differs by more than 10 per cent from the first approximation, a further calculation using the radius of gyration corresponding to the mean area of the first and second approximation is to be made.</p>		

# General Cargo Ships

# Part 4, Chapter 1

Section 4

**Table 1.4.8 Non-watertight pillar bulkheads**

Symbols	Parameter	Requirement	
		Ships with $L < 90$ m	Ships with $L \geq 90$ m
$d_w, t_p, b, c$ as defined in Pt 3, Ch 3,3 $r$ = radius of gyration, in mm, of stiffener and attached plating $= 10 \sqrt{\frac{I}{A}}$ mm for rolled, built or swedged stiffeners $= d_w \sqrt{\frac{3b+c}{12(b+c)}}$ mm for symmetrical corrugation $I$ = moment of inertia, in $\text{cm}^4$ , of stiffener and attached plating $s$ = spacing of stiffeners, in mm $A$ = cross-sectional area, in $\text{cm}^2$ , of stiffener and attached plating $A_1 = \frac{P}{12,36 - 51,5 \frac{l_e}{r}} \text{ cm}^2$ $\left( A_1 = \frac{P}{1,26 - 5,25 \frac{l_e}{r}} \text{ cm}^2 \right)$ As a first approximation $A_1$ may be taken as $\frac{P}{9,32} \left( \frac{P}{0,95} \right)$ $A_2 = \frac{P}{4,9 - 14,7 \frac{l_e}{r}} \text{ cm}^2$ $\left( A_2 = \frac{P}{0,5 - 1,5 \frac{l_e}{r}} \text{ cm}^2 \right)$ As a first approximation $A_2$ may be taken as $\frac{P}{3,92} \left( \frac{P}{0,4} \right)$ $P, l_e$ as defined in Table 1.4.7 $\lambda = \frac{b}{c}$	(1) Minimum thickness of bulkhead plating	5,5 mm in holds and 'tween decks	7,5 mm in holds 6,5 mm in 'tween decks
	(2) Maximum stiffener spacing	1500 mm	1500 mm
	(3) Minimum depth of stiffeners or corrugations	100 mm in holds	150 mm in holds
		75 mm in 'tween decks	100 mm in 'tween decks
	(4) Cross-sectional area (including plating) for rolled, built or swedged stiffeners supporting beams, longitudinals, girders or transverses	(a) Where $\frac{s}{t} \leq 80$	$A = A_1$
		(b) Where $\frac{s}{t} \geq 120$	$A = A_2$
		(c) Where $80 < \frac{s}{t} < 120$	$A$ is obtained by interpolation between $A_1$ and $A_2$
	(5) Cross-sectional area (including plating) for symmetrical corrugation	(a) Where $\frac{b}{t_p} \leq \frac{750 \lambda l_e}{(\lambda + 0,25) r}$	$A = A_1$
		(b) Where $\frac{b}{t_p} > \frac{750 \lambda l_e}{(\lambda + 0,25) r}$	$A = A_2$

4.5.5 Openings in the strength deck outside the line of hatch openings having a stress concentration factor in excess of 2,4 will require edge reinforcements in the form of a spigot of adequate dimensions, but alternative arrangements will be considered. The area of any edge reinforcement which may be required is not to be taken into account in determining the required sectional area of compensation for the opening. Alternatively, the shape of the opening is to be such that a stress concentration factor of 2,4 is not exceeded. In this respect, reinforcement will not in general, be required in way of:

- (a) elliptical openings having their major axis fore and aft and a ratio of length to breadth not less than 2 to 1, or
- (b) openings of other shapes provided that it has been shown by suitable tests that the stress concentration factor does not exceed 2,4.



## General Cargo Ships

## Part 4, Chapter 1

## Section 4

Table 1.4.9 Cantilever beams (see continuation)

Location and supporting arrangements	Required modulus, in cm <sup>3</sup> , see Notes	
	Cantilever beam	Supporting frame
(1) Any position – no support from end girders	$Z_0 = 8,67kM_0$ ( $Z_0 = 85kM_0$ )	$Z_v = \frac{v}{H_1} \left( \frac{fZ_0}{u} - kZ_t \right)$
(2) At hatch side – uniform loading, partial support received from hatch side girder, see Fig. 1.4.3: (a) Hatch side girder supported by Rule hatch end beams or pillars at hatch corners (b) Hatch side girder supported by end bulkheads of hold – no Rule hatch end beams or pillars (c) No transverse bulkheads between hatchways, no Rule hatch end beams or pillars, see Notes (d) At hatch side – concentrated loading	$Z_u = 0,9Z_0 - kG$ $Z_u$ as in (a) or the following formula, whichever is the greater: $\left( \frac{n+1}{n} \right) \left( 0,45 \left( 1 + \frac{1}{\beta} \right) Z_0 - k\beta G - (1 - \beta) kE \right)$ $Z_u$ as in (a) or the following formula, whichever is the greater: $\left( \frac{n+1}{n} \right) \left( \frac{Z_0}{\beta} - 0,5kE \right)$ $Z_u$ as in (a), (b) or (c), whichever is applicable, or as the following formula, whichever is the greater: $Z_0 - kG_1$	$Z_v = \frac{v}{H_1} \left( \frac{fZ_u}{u} - kZ_t \right)$
Case (1) or (2)	Required inertia, in cm <sup>4</sup>	
	$I_u = \frac{9u}{k} Z_u$	—
<p>NOTES</p> <ol style="list-style-type: none"> <li>Where a transverse bulkhead is fitted at only one end of a hatchway the section modulus of cantilever beams is to be a mean of the values obtained from (2)(b) and (2)(c).</li> <li>Where only cantilevers in the length of a hatchway consist of two or three close together at the mid-length of hatchway, their modulus is to be determined by calculating the modulus of a single cantilever at mid-length and dividing this by the actual number of cantilevers.</li> <li>If a negative value is obtained for the required section modulus, cantilevers are not necessary for the arrangement considered.</li> <li>In calculating the actual section modulus of a cantilever or supporting frame, the effective area of attached plating is to be as given in Pt 3, Ch 3.3. Intermediate beams or frames within the effective breadth may be included in the calculation.</li> <li>Rule hatch end beams are those with scantlings determined from Table 1.4.6, assuming that the hatch side girder has a span between hatch end beams.</li> <li>The section modulus of cantilever beams is to be not less than that determined from Table 1.4.5 for beams in the same position.</li> <li>The section modulus of side frames, pillars or pillar bulkhead stiffeners supporting cantilevers is to be not less than that required for ordinary side frames. pillars or pillar bulkhead stiffeners, as determined from the appropriate Sections of the Rules.</li> <li>The scantlings of the cantilever bracket within the shaded area shown in Fig. 1.4.2 are to be as follows:  (a) Where tripping brackets are not fitted:  <math display="block">t = (0,0075d_c + 5) \sqrt{k} \text{ mm}</math> <math display="block">A_f = \left( \frac{27Z_d}{e} \left( 1 - \frac{e}{1420f} \right) - \frac{et}{300} \right) k \text{ cm}^2</math> (b) Where tripping brackets are fitted at the positions indicated in Fig. 1.4.2:  <math display="block">t = (0,0075d_c + 5) \sqrt{k} \text{ mm}</math> <math display="block">A_f = \left( \frac{20Z_d}{e} \left( 1 - \frac{e}{1420f} \right) - \frac{et}{200} \right) k \text{ cm}^2</math> In general the radius at the throat of the cantilever bracket is to be not less than <math>d_c</math>. </li> <li>The cantilever beam and supporting frame face plates may be gradually tapered from the limits of the shaded area shown in Fig. 1.4.2. The web depth of the supporting frame may be tapered to a minimum of <math>0,5d_f</math> at the base.</li> <li>Where the web thickness of cantilevers or supporting frames is less than <math>\frac{d_w}{60\sqrt{k}}</math> transverse web stiffeners are to be fitted spaced approximately <math>1,5d_w</math> apart. In no case is the web thickness outside the limits of the cantilever brackets to be less than <math>\frac{d_w}{85\sqrt{k}}</math>  Where stiffeners are fitted parallel to the face plates, the stiffening arrangements will be specially considered. </li> </ol>		


# General Cargo Ships

# Part 4, Chapter 1

Section 4

**Table 1.4.9 Cantilever beams (conclusion)**



Symbols	
<p> <math>f</math> = overall length of cantilever, in metres  <math>k</math> = higher tensile steel factor as defined in 1.5.1  <math>l_b</math> = distance, in metres, between transverse bulkheads, see Fig. 1.4.4. Where there is no bulkhead midway between hatchways, <math>l_b</math> is to be measured to a point midway between hatchways  <math>l_h</math> = length of hatchway, in metres, see Fig. 1.4.4  <math>C</math> = cargo stowage rate in m<sup>3</sup>/tonne as defined in Pt 3, Ch 3.5, and is to be taken as 1,39 m<sup>3</sup>/tonne unless specified otherwise  <math>Z_a</math> = section modulus, in cm<sup>3</sup>, of hatch side girder which is to be not less than that calculated from Table 1.4.6, taking the span between cantilevers  <math>Z_b</math> = mean of section moduli, in cm<sup>3</sup>, of longitudinal girders in line with hatch side girder (<math>Z_b</math> is to be taken not greater than <math>Z_a</math>)  <math>Z_d = \frac{fZ_u}{u}</math>  <math>Z_o</math> = section modulus, in cm<sup>3</sup>, of cantilever beam, not supported by end girder, at distance <math>u</math> from outer end  <math>Z_t</math> = section modulus, in cm<sup>3</sup>, of frame or stiffener above cantilever, see Fig. 1.4.2. (Where there is no frame or stiffener above cantilever <math>Z_t = 0</math>)  <math>Z_u</math> = section modulus, in cm<sup>3</sup>, of cantilever beam, partially supported by hatch side girder at end, at distance <math>u</math> from outer end  <math>Z_v</math> = section modulus, in cm<sup>3</sup>, of supporting frame, at distance <math>v</math> from lower end  <math>Z_1, Z_2, Z_3</math> = mean of section moduli, in cm<sup>3</sup>, of hatch end beams calculated for the positions shown in Fig. 1.4.3. <math>Z_2</math> is to be taken as the smaller modulus of the two sections adjacent to the hatch side  <math>\beta = \frac{l_h}{l_b}</math>  <math>E</math> is determined as follows:  When centreline bulkheads or pillars are fitted:  <math display="block">E = \frac{4}{n+1} \left( (Z_1 + Z_2) + \frac{2u}{B_h} (Z_2 + Z_3) \right)</math> </p>	<p> Where there is no centreline support:  <math>d_c</math> = web depth of cantilever, at root of bracket, in mm, see Fig. 1.4.2  <math>d_f</math> = web depth of frame at root of bracket, in mm, see Fig. 1.4.2  <math>d_w</math> = web depth of cantilever or frame, in mm  <math>e</math> = web depth, in mm, as shown in Fig. 1.4.2  <math>n</math> = number of cantilevers between the hatch end beams  <math>t</math> = thickness of cantilever bracket, in mm  <math>u, v</math> = lever arms, in metres, as shown in Fig. 1.4.2  <math>A_f</math> = sectional area, in cm<sup>2</sup>, of cantilever bracket face plate  <math>B_h</math> = breadth of hatch, in metres, see Fig. 1.4.4  <math display="block">E = \frac{4}{n+1} (Z_1 + Z_2)</math>  <math display="block">G = \frac{7u}{(n+1)l_h} (Z_a + Z_b)</math>  <math display="block">G_1 = \frac{3,5uZ_a}{S_c}</math>  <math>H_1, H_2, H_3</math> = mean height of hold or 'tween deck, in metres, as shown in Fig. 1.4.2. At weather decks, <math>H_2</math> and <math>H_3</math> are to be taken equivalent to the weather head <math>h_1</math> as defined in Pt 3, Ch 3.5  <math>M_o</math> = bending moment, in kN m (tonne-f m), on the cantilever beam due to the load supported by a single cantilever. This bending moment is to be calculated about an axis at a distance <math>u</math> from the end. For hatch side cantilevers with uniformly distributed loading this will equal  <math display="block">\frac{4,9S_c u}{C} (H_2 B_h + H_3 u)</math>  <math display="block">\left( \frac{0,5S_c u}{C} (H_2 B_h + H_3 u) \right)</math>  <math>S_c</math> = spacing of cantilevers, in metres, see Fig. 1.4.4 </p>



# General Cargo Ships

# Part 4, Chapter 1

## Section 4



4.5.6 Lower deck openings should be kept clear of main hatch corners and the areas of high stress, so far as possible. Compensation will not, in general, be required unless the total width of openings in any frame space, or between any two transverses, exceeds 15k per cent of the original effective plating width. The requirements of 4.5.4 also apply to lower deck openings except that:

- the thickness of inserts, if required, for the second deck hatch corners is to be 2,5 mm greater than the deck thickness,
- inserts will not generally be required for hatch corners on third decks, platform decks and below, and
- reinforcement will not generally be required for circular openings, provided that the plate panels in which they are situated are otherwise adequately stiffened against compression and shear buckling.

4.5.7 All openings are to be adequately framed; attention is to be paid to structural continuity, and abrupt changes of shape, section or plate thickness are to be avoided. Arrangements in way of corners and openings are to be such as to minimize the creation of stress concentrations. Where a deck longitudinal is cut, compensation is to be arranged to ensure full continuity of strength.




Fig. 1.4.4 Deck supporting structure




Fig. 1.4.5 Elliptical and parabolic corners




Fig. 1.4.6 Insert plates for large openings

## Section 5 Shell envelope plating

### 5.1 General

5.1.1 Requirements are given in this Section for longitudinal or transversely framed shell plating, and attention is drawn to the requirements of 6.1.1. In ships with a transversely framed bottom construction, the bottom shell plating is, in general, to be reinforced with additional continuous, or intercostal, longitudinal stiffeners, see also 7.1.2. Alternative arrangements will be considered.

5.1.2 For ships intended to load or unload while aground, see Pt 3, Ch 9, 13.

### 5.2 Keel

5.2.1 The cross-sectional area and thickness of bar keels, and the width and thickness of plate keels, are to comply with the requirements of Table 1.5.1. Forged or rolled bar keels are also to comply with the material requirements of Chapter 3 of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

**Table 1.5.1 Bar and plate keels**

Item and parameter	Requirement
(1) Bar keels: Cross-sectional area Thickness	$A = (1,8L - 16) \text{ cm}^2$ $t = (0,6L + 8) \text{ mm}$
(2) Plate keels: Breadth Thickness	$b = 70B \text{ mm}$ but need not exceed 1800 mm and is not to be less than 750 mm $t = (t_1 + 2) \text{ mm}$ where $t_1$ is as in location (1) in Table 1.5.2, using the spacing in way of the keel plate $t$ is to be taken not less than the adjacent bottom shell thickness
Symbols	
$L, B$ as defined in 1.5.1 $b$ = breadth of keel, in mm $t$ = thickness of keel, in mm $A$ = cross-sectional area, in $\text{cm}^2$	

### 5.3 Bottom shell and bilge

5.3.1 In the midship region the thickness of bottom shell plating to the upper turn of bilge is to be that necessary to give the hull section modulus required by Pt 3, Ch 4,5, and is to be not less than the minimum values given by Table 1.5.2.

### 5.4 Side shell

5.4.1 In the midship region, the thickness of side shell and sheerstrake plating including the sides of bridge superstructures is to be not less than the values given by Table 1.5.3, but may be required to be increased locally on account of high shear forces in accordance with Pt 3, Ch 4,6.

5.4.2 Sea inlets, or other openings, are to have well rounded corners and so far as possible, are to be kept clear of the bilge radius. Openings on, or near to, the bilge radius are to be elliptical. The thickness of sea inlet box plating is to be the same as the adjacent shell, but not less than 12,5 mm and need not exceed 25 mm.

5.4.3 Where a rounded sheerstrake is adopted the radius should, in general, be not less than 15 times the thickness.

5.4.4 The sheerstrake thickness is to be increased by 20 per cent at the ends of a bridge superstructure extending out to the ship's side. In the case of a bridge superstructure exceeding  $0,15L$ , the side plating at the ends of the superstructure is also to be increased by 25 per cent and tapered gradually into the upper deck sheerstrake.

5.4.5 In general, compensation will not be required for holes in the sheerstrake which are clear of the gunwale or any deck openings situated outside the line of the main hatchways and whose depth does not exceed 20 per cent of the depth of the sheerstrake or 380 mm, whichever is the lesser. Openings are not to be cut in a rounded gunwale. Cargo door openings are to have well rounded corners, and the proposed compensation for the door openings will be individually considered.

## General Cargo Ships

## Part 4, Chapter 1

Section 5

Table 1.5.2 Bottom shell and bilge plating

Location	Minimum thickness, in mm, <i>see also</i> 5.3.1	
	Longitudinal framing	Transverse framing
(1) Bottom plating, see Notes 1 and 2	The greater of the following:  (a) $t = 0,001s_1 (0,043L_1 + 10) \sqrt{\frac{F_B}{k_L}}$ (see Note 4)  (b) $t = 0,0052s_1 \sqrt{\frac{h_{T2}k}{1,8 - F_B}}$	The greater of the following:  (a) $t = 0,001s_1 f_1 (0,056L_1 + 16,7) \sqrt{\frac{F_B}{k_L}}$ (see Note 4)  (b) $t = 0,0063s_1 \sqrt{\frac{h_{T2}k}{1,8 - F_B}}$
(2) Bilge plating – where framed, see Notes 1 and 2	$t$ as for (1)	$t$ as for (1)
(3) Bilge plating – where unframed, see Note 3	Provided that transverses or adequate bilge brackets are spaced not more than $\frac{8t^2}{DR_B} \sqrt{\frac{t}{R_B}} \times 10^6 \text{ mm apart}$ $t = \frac{R_B F_B}{165k_L}$ but is to be not less than the adjacent bottom plating	
Symbols		
<div><div><math>L, D, T, s, S, k_L, k</math> as defined in 1.5.1 <math>C_w</math> is as defined in 1.5.1. Where <math>L &gt; 227</math> m, <math>C_w</math> is not to be taken less than 6,446 m <math>f_1 = \frac{1}{1 + \left(\frac{s}{1000S}\right)^2}</math> <math>h_{T2} = (T + 0,5 C_w)</math>, in metres but need not be taken greater than 1,27 m</div><div><math>s_1 = s</math>, but is not to be taken less than the smaller of <math>470 + \frac{L}{0,6}</math> mm or 700 mm <math>F_B =</math> as defined in Pt 3, Ch 4,5.6 <math>L_1 = L</math> but need not be taken greater than 190 m <math>R_B =</math> bilge radius, in mm, see Note 3</div></div>		
NOTES		
<div>1. The thickness derived in accordance with (1) is also to satisfy the buckling requirements of Pt 3, Ch 4,7.</div> <div>2. The thickness of bottom shell or bilge plating is to be not less than the basic shell end thickness for taper as given in Pt 3, Ch 5,3 and Ch 6,3.</div> <div>3. Where longitudinally framed and the lowest side longitudinal lies a distance <math>a</math> mm above the uppermost turn of bilge and/or the outermost bottom longitudinal lies a distance <math>b</math> inboard of the lower turn of bilge, the bilge radius is to be taken as <math>R_B + \frac{(a + b)}{2}</math> mm. In no case is <math>a</math> or <math>b</math> to be greater than <math>s</math>.</div> <div>4. Where separate maximum sagging and hogging still water bending moments are assigned, <math>F_B</math> may be based on the hogging moment.</div>		

## General Cargo Ships

## Part 4, Chapter 1

## Section 5

Table 1.5.3 Side shell plating

Location	Thickness, in mm, see also 5.4.1	
	Longitudinal framing	Transverse framing
(1) Side shell clear of sheerstrake, see Notes 1, 2, 4 and 5	(a) Above $\frac{D}{2}$ from base: The greater of the following: (i) $t = 0,001s_1 (0,059L_1 + 7) \sqrt{\frac{F_D}{k_L}}$ (ii) $t = 0,0042s_1 \sqrt{h_{T1} k}$	(a) Within $\frac{D}{4}$ from the gunwale: The greater of the following: (i) $t = 0,00085s_1 f_1 (0,083L_1 + 10) \sqrt{\frac{F_D}{k_L}}$ (ii) $t = 0,0042s_1 \sqrt{h_{T1} k}$
	(b) At upper turn of bilge, see Note 3: The greater of the following: (i) $t = 0,001s_1 (0,059L_1 + 7) \sqrt{\frac{F_B}{k_L}}$ (ii) $t = 0,0054s_1 \sqrt{\frac{h_{T2} k}{2 - F_B}}$	(b) Within $\frac{D}{4}$ from mid-depth: The greater of the following: (i) $t = 0,001s_1 (0,059L_1 + 7) \sqrt{\frac{F_M}{k_L}}$ (ii) $t = 0,0051s_1 \sqrt{h_{T1} k}$
	(c) Between upper turn of bilge and $\frac{D}{2}$ from base: The greater of the following: (i) $t$ from (b)(i) (ii) $t$ from interpolation between (a)(ii) and (b)(ii)	(c) Within $\frac{D}{4}$ from base (excluding bilge plating), see Note 3: The greater of the following: (i) $t = 0,00085s_1 f_1 (0,083L_1 + 10) \sqrt{\frac{F_B}{k_L}}$ (ii) $t = 0,0056s_1 \sqrt{\frac{h_{T2} k}{1,8 - F_B}}$
(2) Sheerstrake, see Notes 1, 2 and 5	The greater of the following: (i) $t = 0,001s_1 (0,059L_1 + 7) \sqrt{\frac{F_D}{k_L}}$ (ii) $t = 0,00083s_1 \sqrt{Lk} + 2,5$ but $t$ is to be not less than the thickness of the adjacent side plating	The greater of the following: (i) $t = 0,001s_1 f_1 (0,083L_1 + 10) \sqrt{\frac{F_D}{k_L}}$ (ii) $t = 0,001s_1 \sqrt{Lk} + 2,5$ but $t$ is to be not less than the thickness of the adjacent side plating
Symbols		NOTES
$L, D, T, S, s, k_L, k$ , as defined in 1.5.1 $C_w$ is as defined in 1.5.1. Where $L > 227$ m, $C_w$ is not to be taken less than 6,446 m $f_1 = \frac{1}{1 + \left(\frac{s}{1000S}\right)^2}$ $h_{T1} = T + C_w \text{ m but need not be taken greater than } 1,36T$ $h_{T2} = T + 0,5C_w \text{ m but need not be taken greater than } 1,2T$ $s_1 = s, \text{ but is not to be taken less than the smaller of } 470 + \frac{L}{0,6} \text{ mm or } 700 \text{ mm}$ $F_D, F_B = \text{as defined in Pt 3, Ch 4.5.6}$ $F_M = \text{the greater of } F_D \text{ or } F_B$ $L_1 = L, \text{ but need not be taken greater than } 190 \text{ m}$		1. The thickness is also to satisfy the buckling requirements of Pt 3, Ch 4.5.6. 2. The thickness of side shell or sheerstrake is to be not less than the basic shell end thickness for taper, as given in Pt 3, Ch 5.3 and Ch 6.3. The width of the sheerstrake (where of different thickness from the side shell) is to be not less than that required by Table 2.2.1 in Pt 3, Ch 2. 3. The thickness of side shell need not exceed that determined from Table 1.5.2 for bottom shell, but using the spacing of side frames or longitudinals. 4. Outside the Rule minimum region of higher tensile steel as defined in Pt 3, Ch 3.2.6.1 the value of $k_L$ may be taken as 1,0. 5. For the expressions contained in (i), where separate maximum sagging and hogging still water bending moments are assigned, $F_D$ may be based on the sagging moment and $F_B$ on the hogging moment.

## ■ Section 6 Shell envelope framing

### 6.1 General

6.1.1 Longitudinal framing is, in general, to be adopted at the bottom, but special consideration will be given to proposals for transverse framing in this region. Transverse or longitudinal framing can be adopted for the side shell. Requirements are given in this Section for longitudinal and transverse framing systems.

6.1.2 End connections of longitudinals to bulkheads are to provide adequate fixity and, so far as practicable, direct continuity of longitudinal strength. Where  $L$  exceeds 215 m, the bottom longitudinals are to be continuous in way of both watertight and non-watertight floors, but alternative arrangements will be considered. Higher tensile steel longitudinals within 10 per cent of the ship's depth at the bottom and deck are to be continuous irrespective of the ship length, *see also* Pt 3, Ch 10,5.2.

6.1.3 Stiffeners and brackets on side transverses, where fitted on one side and connected to higher tensile steel longitudinals between the base line and  $0,8D_2$  above the base line, are to have their heels well radiused to reduce stress concentrations. Where a symmetrical arrangement is fitted, i.e. bracket or stiffening on both sides, and it is connected to higher tensile steel longitudinals, the toes of the stiffeners or brackets are to be well radiused. Alternative arrangements will be considered if supported by appropriate direct calculations, *see also* Pt 3, Ch 10,5.2.

6.1.4 Where higher tensile steel side longitudinals pass through transverse bulkheads in the cargo area, well radiused brackets of the same material are to be fitted on both the fore and aft side of the connection between the upper turn of bilge and  $0,8D_2$  above the base line. Particular attention should be given to ensuring the alignment of these brackets. Alternative arrangements will be considered if supported by appropriate direct calculations, *see also* 6.2.3.

6.1.5 For ships intended to load or unload while aground, *see* Pt 3, Ch 9,13.

### 6.2 Longitudinal stiffening

6.2.1 For non-CSR tankers and bulk carriers (*see* Pt 1, Ch 2,2.3) the scantlings of bottom and side longitudinals in the midship region are to comply with the requirements given in Table 1.6.1(b). In general other ships are to comply with Table 1.6.1(a).

6.2.2 The lateral and torsional stability of longitudinals together with web and flange buckling criteria are to be verified in accordance with Pt 3, Ch 4,7.

6.2.3 Where higher tensile steel asymmetrical sections are adopted in double bottom tanks which are interconnected with double skin side tanks or combined hopper and topside tanks the requirements of 6.1.3 and 6.1.4 are to be complied with regarding arrangements to reduce stress concentrations. Alternatively, it is recommended that bulb plate or symmetrical sections are adopted.

### 6.3 Transverse stiffening

6.3.1 The scantlings of main and 'tween deck frames, and bottom frames in way of bracket floors, in the midship region are to comply with the requirements given in Table 1.6.2.

6.3.2 The scantlings of main frames are normally to be based on Rule standard brackets at top and bottom, whilst the scantlings of 'tween deck frames are normally to be based on a Rule standard bracket at the top only.

6.3.3 End connections of transverse main and 'tween deck frames are to be in accordance with Pt 3, Ch 10,3.

### 6.4 Primary supporting structure

6.4.1 Side transverses supporting longitudinal stiffening, and webs and stringers supporting transverse side stiffening, are to comply with the requirements of Table 1.6.3.

6.4.2 Side transverses are to be spaced not more than 3,8 m apart when the length,  $L$ , is less than 100 m and  $(0,006L + 3,2)$  m apart where  $L$  is greater than 100 m.



## General Cargo Ships

## Part 4, Chapter 1

Section 6

Table 1.6.1(a) Shell framing (longitudinal)

Location	Modulus, in cm <sup>3</sup>
(1) Side longitudinals in way of dry spaces, including double skin construction, see Note 2	The lesser of the following: (a) $Z = 0,056 sk h_{T1} l_e^2 F_1 F_s$ (b) $Z$ from (3)(a) evaluated using $s$ , $k$ and $l_e$ for the longitudinal under consideration and the remaining parameters evaluated at the base line
(2) Side longitudinals in way of double skin tanks or deep tanks, see Note 2	The greater of the following: (a) $Z$ as from (1) (b) As required by Ch 1,9 for deep tanks
(3) Bottom and bilge longitudinals, see Notes 1, 2, 3 and 4	The greater of the following: (a) $Z = \gamma s k h_{T2} l_e^2 F_1$ (b) $Z = \gamma s k h_{T3} l_e^2 F_1 F_{sb}$
Symbols	
<p><math>L, D, T, s, k, k_L, \rho</math> as defined in 1.5.1</p> <p><math>l_e</math> = as defined in 1.5.1, but is not to be taken less than 1,5 m except in way of the centre girder brackets required by 8.5.3 where a minimum span of 1,25 m may be used</p> <p><math>l_{e1}</math> = <math>l_e</math> in metres, but is not to be taken less than 2,5 m and need not be taken greater than 5,0 m</p> <p> <math>c_1 = \frac{60}{225 - 165F_D}</math> at deck  <math>= 1,0</math> at <math>\frac{D_2}{2}</math>  <math>= \frac{75}{225 - 150F_B}</math> at base line         <span style="font-size: 2em; vertical-align: middle;">}</span> intermediate values by interpolation       </p> <p><math>D_1 = D_2</math>, in metres, but is not to be taken less than 10 and need not be taken greater than 16</p> <p><math>D_2 = D</math>, in metres, but need not be taken greater than <math>1,6T</math></p> <p><math>F_B, F_D</math> as defined in Pt 3, Ch 4,5.6</p> <p> <math>F_1 = \frac{D_2 c_1}{4D_2 + 20h_5}</math> for side longitudinals above <math>\frac{D_2}{2}</math>  <math>= \frac{D_2 c_1}{25D_2 - 20h_5}</math> for side longitudinals below <math>\frac{D_2}{2}</math> and bottom longitudinals         <span style="font-size: 2em; vertical-align: middle;">}</span> minimum <math>F_1 = 0,14</math> </p> <p><math>L_1 = L</math> but need not be taken greater than 190 m</p> <p><math>F_s</math> is a fatigue factor for side longitudinals to be taken as follows:</p> <p>(a) For built sections and rolled angle bars</p> <p> <math>F_s = \frac{1,1}{k} \left[ 1 - \frac{2b_{f1}}{b_f} (1 - k) \right]</math> at <math>0,6D_2</math> above the base line  <math>= 1,0</math> at <math>D_2</math> and above, and <math>F_{sb}</math> at the base line          intermediate values by linear interpolation       </p> <p>(b) For flat bars and bulb plates <math>\frac{b_{f1}}{b_f}</math> may be taken as 0,5</p> <p><math>F_{sb}</math> is a fatigue factor for bottom longitudinals = <math>0,5 (1 + F_s \text{ at } 0,6D_2)</math> where</p>	
<p><math>b_{f1}</math> = the minimum distance, in mm, from the edge of the face plate of the side longitudinal under consideration to the centre of the web plate, see Fig. 9.5.1 in Chapter 9</p> <p><math>h_{T1} = C_W \left( 1 - \frac{h_6}{D_2 - T} \right) F_\lambda</math>, in metres, for longitudinals above the waterline, at draught <math>T</math>, where <math>C_W \left( 1 - \frac{h_6}{D_2 - T} \right)</math> is not to be taken less than <math>\frac{L_1}{56}</math> m for Type 'B-60' ships and the greater of <math>\frac{L_1}{70}</math>, or 1,20 m for Type 'B' ships</p> <p><math>= \left[ h_6 + C_W \left( 1 - \frac{h_6}{2T} \right) \right] F_\lambda</math>, in metres, for longitudinals below the waterline at draught <math>T</math></p> <p><math>h_{T1}</math> need not exceed <math>0,86 \left( h_5 + \frac{D_1}{8} \right)</math> for <math>F_1 \leq 0,14</math> and <math>\left( h_5 + \frac{D_1}{8} \right)</math> for <math>F_1 &gt; 0,14</math></p> <p><math>h_{T2} = (T + 0,5C_W)</math>, in metres for bottom longitudinals need not be taken greater than 1,2T m</p> <p><math>h_{T3} = h_4 - 0,25T</math>, in metres</p> <p><math>h_4</math> = load head required by Ch 1,9 for deep tanks</p> <p><math>h_5</math> = vertical distance, in metres, from longitudinal to deck at depth, <math>D_2</math></p> <p><math>h_6</math> = vertical distance, in metres, from the waterline at draught <math>T</math> to the longitudinal under consideration</p> <p><math>b_f</math> = the width of the face plate, in mm, of the side longitudinal under consideration, see Fig. 9.5.1 in Chapter 9</p> <p><math>C_W</math> = a wave head, in metres = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math> where <math>e</math> = base of natural logarithms 2,7183</p> <p><math>F_\lambda = 1,0</math> for <math>L \leq 200</math> m  <math>= [1,0 + 0,0023(L - 200)]</math> for <math>L &gt; 200</math> m</p> <p><math>\gamma = 0,002 l_{e1} + 0,046</math></p>	
NOTES	
1. The buckling requirements of Pt 3, Ch 4,7 are to be complied with. The ratio of the web depth, $d_w$ , to web thickness, $t$ , is to comply with the following requirements:	
(a) Built up profiles and rolled angles:	
$\frac{d_w}{t} \leq 60 \sqrt{k_L}$	
(b) Flat bars:	
$\frac{d_w}{t} \leq 18 \sqrt{k_L}$ when continuous at bulkheads	
$\frac{d_w}{t} \leq 15 \sqrt{k_L}$ when non-continuous at bulkheads	
2. Where struts are fitted midway between transverses in way of double bottom tanks, or double skin construction, the modulus of the bottom or side longitudinals may be reduced by 50% per cent from that obtained from the locations (1), (2), or (3) as applicable.	
3. Where the bilge radius exceeds the Rule height of a double bottom the modulus of the longitudinal above this nominal height is to be derived from the location (1) or (2) as applicable.	
4. Where no bilge longitudinals are fitted and bilge brackets are required by location (3) in Table 1.5.2, at least two brackets are to be fitted.	

## General Cargo Ships

## Part 4, Chapter 1

Section 6

Table 1.6.1(b) Shell framing (longitudinal)

Location	Modulus, in cm <sup>3</sup>
(1) Side longitudinals in way of dry spaces, including double skin construction, see Note 2	The lesser of the following: (a) $Z = 0,056 s k h_{T1} l_e^2 F_1 F_s$ (b) $Z$ from (3)(a) evaluated using $s$ and $l_e$ for the longitudinal under consideration and the remaining parameters evaluated at the base line
(2) Side longitudinals in way of double skin tanks or deep tanks, see Note 2	The greater of the following: (a) $Z$ as from (1) (b) As required by Ch 1,9 for deep tanks, using $h_{T3}$ instead of $h_4$ , but need not exceed $Z$ from (3)(b) evaluated using $\gamma$ , $s$ and $l_e$ for the longitudinal under consideration and the remaining parameters evaluated at the base line
(3) Bottom and bilge longitudinals, see Notes 1, 2, 3 and 4	The greater of the following: (a) $Z = \gamma s k h_{T2} l_e^2 F_1 F_{sb}$ (b) $Z = \gamma s k h_{T3} l_e^2 F_1 F_{sb}$
Symbols	
<p><math>L, D, T, s, k, \rho</math> as defined in 1.5.1</p> <p><math>l_e</math> = as defined in 1.5.1, but is not to be taken less than 1,5 m except in way of the centre girder brackets required by 8.5.3 where a minimum span of 1,25 m may be used</p> <p><math>l_{e1}</math> = <math>l_e</math> in metres, but is not to be taken less than 2,5 m and need not be taken greater than 5,0 m</p> <p> <math>c_1 = \frac{60}{225 - 165F_D}</math> at deck  <math>= 1,0</math> at <math>\frac{D_2}{2}</math>  <math>= \frac{75}{225 - 150F_B}</math> at base line </p> <p>intermediate values by interpolation</p> <p><math>D_1 = D_2</math>, in metres, but is not to be taken less than 10 and need not be taken greater than 16</p> <p><math>D_2 = D</math>, in metres, but need not be taken greater than 1,6T</p> <p><math>F_B, F_D</math> as defined in Pt 3, Ch 4,5.6</p> <p> <math>F_1 = \frac{D_2 c_1}{4D_2 + 20h_5}</math> for side longitudinals above <math>\frac{D_2}{2}</math>  <math>= \frac{D_2 c_1}{25D_2 - 20h_5}</math> for side longitudinals below <math>\frac{D_2}{2}</math> </p> <p>and bottom longitudinals</p> <p><math>L_1 = L</math> but need not be taken greater than 190 m</p> <p><math>F_s</math> is a fatigue factor for side longitudinals to be taken as follows:</p> <p>(a) For built sections and rolled angle bars</p> <p> <math>F_s = \frac{1,1}{k} \left[ 1 - \frac{2b_{f1}}{b_f} (1 - k) \right]</math> at <math>0,6D_2</math> above the base line  <math>= 1,0</math> at <math>D_2</math> and above, and <math>F_{sb}</math> at the base line          intermediate values by linear interpolation </p> <p>(b) For flat bars and bulb plates <math>\frac{b_{f1}}{b_f}</math> may be taken as 0,5</p> <p> <math>F_{sb}</math> is a fatigue factor for bottom longitudinals = 0,5 (1 + <math>F_s</math> at <math>0,6D_2</math>) where  <math>b_{f1}</math> = the minimum distance, in mm, from the edge of the face plate of the side longitudinal under consideration to the centre of the web plate, see Fig. 9.5.1 in Chapter 9  <math>h_{T1} = C_W \left( 1 - \frac{h_6}{D_2 - T} \right) F_\lambda</math>, in metres, for longitudinals above the waterline, at draught <math>T</math>, where <math>\left( 1 - \frac{h_6}{D_2 - T} \right)</math> is not to be taken less than 0,7  <math>= \left[ h_6 + C_W \left( 1 - \frac{h_6}{2T} \right) \right] F_\lambda</math>, in metres, for longitudinals below the waterline at draught <math>T</math>  <math>h_{T1}</math> and <math>h_{T2}</math> need not exceed <math>0,86 \left( h_5 + \frac{D_1}{8} \right)</math> for <math>F_1 \leq 0,14</math> and <math>\left( h_5 + \frac{D_1}{8} \right)</math> for <math>F_1 &gt; 0,14</math>  <math>h_{T2} = (T + 0,5C_W) F_\lambda</math>, in metres for bottom longitudinals  <math>h_{T3} = h_4 - 0,25T</math>, in metres, at the base line  <math>= h_4</math>, in metres, at and above <math>T/4</math> from the base line, intermediate values by linear interpolation  <math>h_4</math> = load head required by Ch 1,9 for deep tanks  <math>h_5</math> = vertical distance, in metres, from longitudinal to deck at depth, <math>D_2</math>  <math>h_6</math> = vertical distance, in metres, from the waterline at draught <math>T</math> to the longitudinal under consideration  <math>b_f</math> = the width of the face plate, in mm, of the side longitudinal under consideration, see Fig. 9.5.1 in Chapter 9  <math>C_W</math> = a wave head, in metres = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math> where <math>e</math> = base of natural logarithms 2,7183  <math>F_\lambda = 1,0</math> for <math>L \leq 200</math> m  <math>= [1,0 + 0,0023(L - 200)]</math> for <math>L &gt; 200</math> m  <math>\gamma = 0,002l_{e1} + 0,046</math> </p>	
<p>NOTES</p> <p>1. The buckling requirements of Pt 3, Ch 4,7 are to be complied with. The ratio of the web depth, <math>d_w</math>, to web thickness, <math>t</math>, is to comply with the following requirements:</p> <p>(a) Built up profiles and rolled angles:</p> <p><math>\frac{d_w}{t} \leq 60 \sqrt{k_L}</math></p> <p>(b) Flat bars:</p> <p><math>\frac{d_w}{t} \leq 18 \sqrt{k_L}</math> when continuous at bulkheads</p> <p><math>\frac{d_w}{t} \leq 15 \sqrt{k_L}</math> when non-continuous at bulkheads</p> <p>2. Where struts are fitted midway between transverses in way of double bottom tanks, or double skin construction, the modulus of the bottom or side longitudinals may be reduced by 50k per cent from that obtained from the locations (1), (2), or (3) as applicable.</p> <p>3. Where the bilge radius exceeds the Rule height of a double bottom the modulus of the longitudinal above this nominal height is to be derived from the location (1) or (2) as applicable.</p> <p>4. Where no bilge longitudinals are fitted and bilge brackets are required by location (3) in Table 1.5.2, at least two brackets are to be fitted.</p>	


# General Cargo Ships

# Part 4, Chapter 1

Section 6

**Table 1.6.2 Shell framing (transverse)**

Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
(1) Main, 'tween deck and superstructure frames in dry spaces, see Note 3	The greater of the following: (a) $Z = C s k h_{T1} H^2 \times 10^{-3}$ (b) $Z = 9,1 s k D_1 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(2) Main and 'tween deck frames in way of fuel or water ballast tanks or cargo holds used for water ballast	The greater of the following: (a) $1,15 \times Z$ from (1) (b) $Z = 6,7 s k h H_2^2 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(3) Frames supporting hatch end beams or deck transverses, see Note 2	The greater of the following: (a) $Z$ from (1) (b) $Z = 2,5 (0,2 I_s^2 + H_1^2) k S_1 H_g$	$I = \frac{3,2}{k} HZ$
(4) Bottom frames of double bottom bracket floors	$Z = 2,15 s k T I_e \times 10^{-2}$	—
Symbols		
<p><math>D, T, s, k</math> as defined in 1.5.1</p> <p><math>C</math> = end connection factor  = 3,4 where two Rule standard brackets are fitted  = 3,4 (1,8 – 0,8 (<math>l_a/l</math>)) where one Rule standard bracket and one reduced bracket are fitted  = 3,4 (2,15 – 1,15 (<math>l_{a\text{mean}}/l</math>)) where two reduced brackets are fitted  = 6,1 where one Rule standard bracket is fitted  = 6,1 (1,2 – 0,2 (<math>l_a/l</math>)) where one reduced bracket is fitted  = 7,3 where no bracket is fitted  The requirements for frames where brackets larger than Rule standard are fitted will be specially considered</p> <p><math>l_a</math> = equivalent arm length, in mm, as derived from Pt 3, Ch 10,3.4.1</p> <p><math>l_{a\text{mean}}</math> = mean equivalent arm length, in mm, for both brackets</p> <p><math>h_{T1}</math> = head, in metres, at middle of <math>H</math></p> <p>= <math>C_w \left(1 - \frac{h_6}{D_1 - T}\right) F_\lambda</math>, in metres for frames where the mid-length of frame is above the waterline, at draught <math>T</math>  where <math>\left(1 - \frac{h_6}{D_1 - T}\right)</math> is not to be taken less than 0,7</p> <p>= <math>\left[h_6 + C_w \left(1 - \frac{h_6}{2T}\right)\right] F_\lambda</math>, in metres for frames where the mid-length of frame is below the waterline at draught <math>T</math></p> <p><math>h</math> = <math>h_4</math> or <math>h_5</math>, whichever is the greater</p> <p><math>h_4</math> = tank head, in metres, as defined in Pt 3, Ch 3,5</p> <p><math>h_5</math> = head, in metres, measured from the mid-length of <math>H</math>, to the deck at side</p> <p><math>h_6</math> = vertical distance in metres, from waterline at draught <math>T</math> to the mid-length of <math>H</math></p> <p><math>l_s</math> = distance, in metres, from side shell to inboard support of beam or transverse</p> <p><math>l_e</math> = effective length, in metres, of bottom frames for double bottom bracket floors</p> <p><math>l_h</math> = length, in metres, of hatch side girder</p> <p><math>C_w</math> = a wave head, in metres,  = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math>  where <math>e</math> = base of natural logarithms 2,7183</p> <p><math>F_\lambda</math> = 1,0 for <math>L \leq 200</math> m  = <math>(1,0 + 0,0023 (L - 200))</math> for <math>L &gt; 200</math> m</p> <p><math>D_1</math> = <math>D</math>, but need not be taken greater than 1,6T</p> <p><math>H</math> = <math>H_{MF}</math> or <math>H_{TF}</math> as applicable, see Note 1</p> <p><math>H_{MF}</math> = vertical framing depth, in metres, of main frames, as shown in Fig. 1.6.1, but is to be taken not less than 3,5 m</p> <p><math>H_{TF}</math> = vertical framing depth, in metres, of 'tween deck frames, as shown in Fig. 1.6.1, but is to be taken not less than 2,5 m</p> <p><math>H_1</math> = <math>H</math>, but need not be taken greater than 3,5 m</p> <p><math>H_2</math> = <math>H</math>, where <math>H_{MF}</math> is to be taken not less than 2,5 m</p> <p><math>H_g</math> = weather head, <math>h_1</math>, or cargo head, <math>h_2</math>, in metres, as defined in Pt 3, Ch 3,5, whichever is applicable</p> <p><math>S</math> = spacing, in metres, of deck transverses</p> <p><math>S_1</math> = <math>\frac{l_h}{4}</math> for hatch end beams  = <math>S</math> for transverses</p>		
<p>NOTES</p> <p>1. Where frames are inclined at more than 15° to the vertical, <math>H_{MF}</math> or <math>H_{TF}</math> is to be measured along a chord between span points of the frame.</p> <p>2. If the modulus obtained from (3) for frames under deck transverses exceeds that obtained from (1) and (2), the intermediate frames may be reduced provided that the combined modulus is maintained and the reduction in any intermediate frame is not greater than 35 per cent. The reduced modulus is to be not less than that given by (1)(b).</p> <p>3. The scantlings of main frames are not to be less than those of the 'tween deck frames above.</p>		



## General Cargo Ships

## Part 4, Chapter 1

Sections 6 &amp; 7

Table 1.6.3 Primary structure

Item and location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
Longitudinal framing system:		
(1) Side transverses in dry cargo spaces	$Z = 10k S h_{T1} l_e^2$	—
(2) Side transverses in deep tanks	$Z = 11,7p k S h_4 l_e^2$ or as (1) above, whichever is the greater	$I = \frac{2,5}{k} l_e Z$
Transverse framing system:		
(3) Side stringers in dry cargo spaces	$Z = 7,75k S h_{T1} l_e^2$	—
(4) Side stringers in deep tanks	$Z = 11,7p k S h_4 l_e^2$ or as (3) above, whichever is the greater	$I = \frac{2,5}{k} l_e Z$
(5) Web frames supporting side stringers	$Z$ determined from calculation based on following assumptions: (a) fixed ends (b) point loadings (c) head $h_4$ or $h_{T1}$ as applicable (d) bending stress $\frac{93,2}{k}$ N/mm <sup>2</sup> $\left( \frac{9,5}{k} \text{ kgf/mm}^2 \right)$ (e) shear stress $\frac{83,4}{k}$ N/mm <sup>2</sup> $\left( \frac{8,5}{k} \text{ kgf/mm}^2 \right)$	$I = \frac{2,5}{k} l_e Z$
Symbols		
<p><math>T, S, l_e, k, p</math> as defined in 1.5.1</p> <p><math>h_4</math> = tank head, in metres, as defined in Pt 3, Ch 3,5</p> <p><math>h_{T1}</math> = head, in metres, at mid-length of span</p> <p>= <math>C_w \left( 1 - \frac{h_6}{D_1 - T} \right) F_{\lambda}</math>, in metres where the mid-length of span is above the waterline at draught <math>T</math>, where <math>\left( 1 - \frac{h_6}{D_1 - T} \right)</math> is not to be taken less than 0,7</p> <p>= <math>\left[ h_6 + C_w \left( 1 - \frac{h_6}{2T} \right) \right] F_{\lambda}</math>, in metres where the mid-length of span is below the waterline at draught <math>T</math></p> <p>where</p> <p><math>h_6</math> = vertical distance, in metres, from the waterline at draught <math>T</math>, to the mid-length of span</p> <p><math>F_{\lambda} = 1,0</math> for <math>L \leq 200</math> m = <math>[1,0 + 0,0023 (L - 200)]</math> for <math>L &gt; 200</math> m</p> <p><math>C_w</math> = a wave head, in metres = <math>7,71 \times 10^{-2} L e^{-0,0044L}</math> where <math>e</math> = base of natural logarithms 2,7183</p> <p><math>D_1</math> = <math>D</math> but need not be taken greater than 1,6<math>T</math></p>		

## Section 7

## Single bottom structure

## 7.1 General

7.1.1 Requirements are given in this Section for single bottom construction in association with transverse framing, and are generally applicable to the following ships:

- (a) Cargo ships of less than 500 tons gross tonnage.
- (b) Ships not propelled by mechanical means.
- (c) Trawlers and fishing vessels.

Cases where a single bottom structure is adopted in association with longitudinal framing will be considered.

7.1.2 Ships with single bottoms are to have a centre girder fitted. In addition, one side girder is to be fitted on each side of the centreline where  $B$  does not exceed 10 m, and two side girders on each side where  $B$  is greater than 10 m and does not exceed 17 m. In addition, continuous or intercostal longitudinal stiffeners are to be fitted where the panel size exceeds the ratio 4 to 1. Centre and side girders are to extend as far forward and aft as practicable, and where they are cut at bulkheads the longitudinal strength is to be maintained.

7.1.3 Plate floors are to be fitted at every frame, and the tops of floors, in general, may be level from side to side, but in ships having considerable rise of floor, and towards the ends, the depth of the floor plates is to be increased. Floor plates forming part of a watertight or deep tank bulkhead are to be not less than 900 mm in depth measured at the centreline, and the thickness is to be not less than that required for the bottom strake of a bulkhead.

7.1.4 For ships intended to load or unload while aground, see Pt 3, Ch 9, 13.

# General Cargo Ships

# Part 4, Chapter 1

Sections 7 & 8

**Table 1.7.1 Single bottom girders and floors**

Item	Depth, in mm	Thickness, in mm	Face plate area, in cm <sup>2</sup>
(1) Centre girder	As for floors	$t = \sqrt{Lk} + 2$ but not less than 6,0	$A_f = 0,67Lk$ but not less than 12,5 See Notes 2 and 3
(2) Side girders	As for floors	$t = \sqrt{Lk}$ but not less than 6,0	$A_f = (0,25L + 5) k$ but not less than 10,0 See Note 3
(3) Floors	Where $B \leq 10$ m $d_f = 40 (B + T)$  Where $B > 10$ m $d_f = 40 (1,5B + T) - 200$ (see Note 1)	$t = \frac{s\sqrt{k}}{s_1} \left( \frac{d_f}{100} + 3 \right)$  but not less than 6,0	$A_f = \frac{5Tsk}{s_1} \left( 1 - \frac{2,5}{B} \right)$  See Notes 2 and 3
Symbols			
$L, B, T, s, k$ as defined in 1.5.1 $b_f =$ breadth of face plate, in mm $d_f =$ overall depth of floor at the centreline, in mm		$s_1 =$ a standard frame spacing, in mm, and is to be taken as $2(L + 240)$ $A_f =$ cross-sectional area of face plate, in cm <sup>2</sup>	
NOTES			
1. If the side frames are attached to the floors by brackets, the Rule depth of floor may be reduced by 15 per cent and the floor thickness determined using the reduced depth. The brackets are to be flanged and have the same thickness as the floors, and their arm lengths clear of the frame and are to be the same as the reduced floor depth given above.			
2. The face plate thickness of floors and centre girder is to be not less than the floor plate thickness.			
3. The thickness of face plates is to be:			
not less than $\frac{b_f}{16\sqrt{k}}$ nor more than $\frac{b_f}{8}$			

7.1.5 Provision is made for the free passage of water from all parts of the bottom to the suctions, taking into account the pumping rates required.

## 7.2 Girders and floors

7.2.1 The scantlings of girders and floors are to comply with the requirements of Table 1.7.1.

## Section 8 Double bottom structure

### 8.1 Symbols and definitions

8.1.1 The symbols used in this Section are defined as follows:

$L, B, T$  as defined in 1.5.1

$d_{DB}$  = Rule depth of centre girder, in mm

$d_{DBA}$  = actual depth of centre girder, in mm

$h_{DB}$  = head from top of inner bottom to top of over-flow pipe, in metres

$s$  = spacing of stiffeners, in mm

$H_{DB}$  = height from tank top, at position under consideration, to deck at side amidships, in metres

$Z_{BF}$  = section modulus of bottom frame at bracket floor, in cm<sup>3</sup>.

## 8.2 General

8.2.1 Except as specified in 8.2.4, cargo ships other than tankers are to be fitted with a double bottom extending from the collision bulkhead to the after peak bulkhead, as far as this is practicable and compatible with the design and proper working of the ship.

8.2.2 Where a double bottom is required to be fitted, its depth at the centreline,  $d_{DB}$ , is to be in accordance with 8.3.1 and the inner bottom is to be continued out to the ship's side in such a manner as to protect the bottom to the turn of the bilge.

8.2.3 Small wells constructed in the double bottom, in connection with the drainage arrangements of holds, are not to extend in depth more than necessary. A well extending to the outer bottom, may however, be permitted at the after end of the shaft tunnel of the ship. Other well arrangements (e.g. for lubricating oil under main engines) may be considered provided they give protection equivalent to that afforded by the double bottom.

8.2.4 A double bottom need not be fitted in way of watertight compartments used exclusively for the carriage of liquids, provided the safety of the ship in the event of bottom damage is not thereby impaired. In addition, a double bottom need not be fitted on the following ships:

- Cargo ships of less than 500 tons gross tonnage.
- Ships not propelled by mechanical means.
- Trawlers and fishing vessels.

# General Cargo Ships

# Part 4, Chapter 1

Section 8

8.2.5 This Section provides for longitudinal or transverse framing in the double bottom, but for ships exceeding 120 m in length and for ships strengthened for heavy cargoes, longitudinal framing is, in general, to be adopted. For the additional requirements for ships specially strengthened for heavy cargoes, see Ch 7, 1.3.

8.2.6 For ships intended to load or unload while aground, see Pt 3, Ch 9, 13.

8.2.7 Girders and the side walls of duct keels are to be continuous, and the structure in way is to be sufficient to withstand the forces imposed by dry-docking the ship.

8.2.8 Adequate access is to be provided to all parts of the double bottom. The edges of all holes are to be smooth. The size of opening should not, in general, exceed 50 per cent of the double bottom depth, unless edge reinforcement is provided. In way of ends of floors and fore and aft girders at transverse bulkheads, the number and size of holes are to be kept to a minimum, and the openings are to be circular or elliptical. Edge stiffening may be required in these positions.

8.2.9 Provision is to be made for the free passage of air and water from all parts of the tank to the air pipes and suction, account being taken of the pumping rates required. To ensure this, sufficient air holes and drain holes are to be provided in all longitudinal and transverse non-watertight primary and secondary members. The drain holes are to be located as close to the bottom as is practicable, and air holes are to be located as close to the inner bottom as is practicable, see also Pt 3, Ch 10, 5.3 and Pt 4, Ch 9, 5.8.

## 8.3 Girders

8.3.1 The centre girder is to have a depth of not less than that given by:

$$d_{DB} = 28B + 205\sqrt{T} \text{ mm}$$

nor less than 650 mm. The centre girder thickness is to be not less than:

$$t = (0,008d_{DB} + 4)\sqrt{k} \text{ mm}$$

nor less than 6,0 mm. The thickness may be determined using the value for  $d_{DB}$  without applying the minimum depth of 650 mm.

8.3.2 In transversely framed ships where the breadth,  $B$ , does not exceed 10 m, no side girders are required, and one vertical stiffener is to be fitted to the floors on each side, about midway between the centreline and the margin plate. One side girder is to be fitted where the breadth,  $B$ , exceeds 10 m but does not exceed 20 m, and for greater breadths two girders are to be fitted on each side of the centreline. The non-watertight side girders are to extend as far forward and aft as practicable and are to have a thickness not less than:

$$t = (0,008d_{DB} + 1)\sqrt{k} \text{ mm}$$

nor less than 6,0 mm.

8.3.3 Vertical stiffeners are to be fitted at every bracket floor (see 8.5.7), and are to have a depth not less than the depth of the tank top frame or 150 mm, whichever is the greater. For ships with a length,  $L$ , less than 90 m, stiffeners are to have a depth of not less than  $1,65L$  mm with a minimum of 50 mm. The thickness is to be as required for the girder. Watertight side girders are to have a thickness 1 mm greater than required by 8.3.2 for non-watertight side girders. Where the double bottom tanks are interconnected with side tanks or cofferdams, the thickness is to be as for deep tanks (see 9.2.1) with  $h$ , in metres, measured to the highest point at the side tank or cofferdam.

8.3.4 In longitudinally framed ships one side girder is to be fitted where the breadth,  $B$ , exceeds 14 m, and two girders are to be fitted on each side of the centreline where  $B$  exceeds 21 m. The girders are to extend as far forward and aft as practicable and are to have a thickness not less than:

$$t = (0,0075d_{DB} + 1)\sqrt{k} \text{ mm}$$

nor less than 6,0 mm.

In general, a vertical stiffener, having a depth not less than 100 mm and a thickness equal to the girder thickness, is to be arranged midway between floors.

8.3.5 Watertight side girders are to have a plating thickness corresponding to the greater of the following:

- $t = (0,0075d_{DB} + 2)\sqrt{k} \text{ mm}$ , or
- thickness  $t$  as for deep tanks (see 9.2.1) with  $h$ , in metres, measured to the highest point of the side tank, or cofferdam if the double bottom is interconnected with these tanks.

8.3.6 Watertight side girder stiffeners are to be in accordance with the requirements for watertight floors, see 8.5.4 and 8.5.5.

8.3.7 Duct keels, where arranged, are to have a thickness of side plates corresponding to the greater of the following:

- $t = (0,008d_{DB} + 2)\sqrt{k} \text{ mm}$ , or
- thickness  $t$ , as for deep tanks (see 9.2.1) with  $h$ , in metres, measured to the highest point of the side tank, or cofferdam if the double bottom tank is interconnected with these tanks.

8.3.8 The sides of duct keels are, in general, to be spaced not more than 2,0 m apart. Where the sides of the duct keels are arranged on either side of a centreline or side girder, each side is, in general, to be spaced not more than 2,0 m from the centreline or side girder. The inner bottom and bottom shell within the duct keel are to be suitably stiffened. The primary stiffening in the transverse direction is to be suitably aligned with the floors in the adjacent double bottom tanks. Where the duct keels are adjacent to double bottom tanks which are interconnected with side tanks or cofferdams, the stiffening is to be in accordance with the requirements for deep tanks, see 9.2.1. Access to the duct keel is to be by watertight manholes or trunks.

8.3.9 The buckling requirements of Pt 3, Ch 4, 7 are also to be satisfied.

# General Cargo Ships

# Part 4, Chapter 1

Section 8

## 8.4 Inner bottom plating and stiffening

8.4.1 The thickness of the inner bottom plating in the holds is to be not less than:

$$t = 0,00136 (s + 660) \sqrt[4]{k^2 LT} \text{ mm}$$

nor less than 6,5 mm in holds and 7,5 mm under hatchways if no ceiling is fitted.

8.4.2 The thickness of the inner bottom plating as determined in 8.4.1 is to be increased by 2 mm under the hatchways if no ceiling is fitted. If cargo is to be regularly discharged by grabs, see 2.2.2.

8.4.3 A margin plate, if fitted, is to have a thickness throughout 20 per cent greater than that required for inner bottom plating.

8.4.4 Where the double bottom tanks are common with side tanks or cofferdams, the thickness of the inner bottom plating is to be not less than that required for deep tanks (see 9.2.1), with  $h$ , in metres, taken to the highest point of the side tank or cofferdam.

8.4.5 Inner bottom longitudinals, or tank top frames at bracket floors within the range of cargo holds, are to have a section modulus not less than 85 per cent of the Rule value for bottom longitudinals (see 6.2.1) or bottom frames in way of bracket floors (see 6.3.1), whichever is applicable. The unsupported span of tank top frames is generally not to exceed 2,5 m. Where the double bottom tanks are interconnected with side tanks, hopper and topside tanks or cofferdams, the scantlings are to be not less than those required for deep tanks (see 9.2.1). For higher tensile steel inner bottom longitudinals the requirements of 6.2.2 are to be complied with where applicable.

8.4.6 The buckling requirements of Pt 3, Ch 4,7 are also to be satisfied.

## 8.5 Floors

8.5.1 In longitudinally framed ships, plate floors are to be fitted under bulkheads and elsewhere at a spacing not exceeding 3,8 m. The thickness of non-watertight plate floors is to be not less than:

$$t = (0,009d_{DB} + 1)\sqrt{k} \text{ mm}$$

nor less than 6,0 mm. The thickness need not be greater than 15 mm, but the ratio between the depth of the double bottom and the thickness of the floor is not to exceed  $130\sqrt{k}$ . This ratio may, however, be exceeded if suitable additional stiffening is fitted. Vertical stiffeners are to be fitted at each longitudinal, having a depth not less than 150 mm and a thickness equal to the thickness of the floors. For ships of length,  $L$ , less than 90 m, the depth is to be not less than  $1,65L$  mm, with a minimum of 50 mm.

8.5.2 The thickness of watertight floors for longitudinally framed ships is to be not less than:

$$(a) \quad t = (0,008d_{DB} + 3)\sqrt{k} \text{ mm, or}$$

$$(b) \quad t = (0,009d_{DB} + 1)\sqrt{k} \text{ mm}$$

whichever is the greater,

but need not exceed 15 mm on floors of normal depth. The thickness is also to satisfy the requirements for deep tanks (see 9.2.1) with  $h$ , in metres, taken to the highest point of the side tank, or cofferdam if the double bottom tank is interconnected with these tanks. The scantlings of stiffeners are to be in accordance with the requirements of 9.2.1 for deep tanks, or as required by 8.5.4 whichever is the greater. The stiffeners are to be connected to the inner bottom and shell longitudinals.

8.5.3 Between plate floors, transverse brackets having a thickness not less than  $0,009d_{DB}$  mm are to be fitted, extending from the centre girder and margin plate to the adjacent longitudinal. The brackets, which are to be suitably stiffened at the edge, are to be fitted at every frame at the margin plate, and those at the centre girder are to be spaced not more than 1,25 m.

8.5.4 In transversely framed ships, plate floors are to be fitted under bulkheads, in way of change in depth of double bottom and elsewhere at a spacing not exceeding 3,0 m. The shell inner bottom plating between these floors is to be supported by bracket floors. The thickness of non-watertight plate floors is to be not less than:

$$t = (0,008d_{DB} + 1)\sqrt{k} \text{ mm}$$

but need not exceed 15 mm and is to be not less than 6 mm. Watertight or strengthened floors are to be fitted below, or in the vicinity of, watertight bulkheads, and their thickness is to be 2 mm greater than that derived above for non-watertight floors, but need not exceed 15 mm on floors of normal depth. If the depth of such floors exceeds 915 mm but does not exceed 2000 mm, the floors are to be fitted with vertical stiffeners spaced not more than 915 mm apart and having a section modulus not less than:

$$Z = 5,41d_{DBA}^2 h_{DB} s k \times 10^{-9} \text{ cm}^3$$

The ends of the stiffeners are to be sniped.

8.5.5 Where the double bottom tanks are interconnected with side tanks or cofferdams, or where the depth of floor exceeds 2000 mm, the scantlings of watertight floors are to be not less than those required for deep tanks (see 9.2.1), and the ends of the stiffeners are to be bracketed top and bottom.

8.5.6 Where floors form the boundary of a sea inlet box, the thickness of the plating is to be the same as the adjacent shell, but not less than 12,5 mm and need not exceed 25 mm. The scantlings of stiffeners, where required are, in general, to comply with 9.2.1 for deep tanks. Sniped ends for stiffeners on the boundaries of these spaces are to be avoided wherever practicable. The stiffeners should be bracketed or the free end suitably supported to provide alignment with backing structure.



# General Cargo Ships

# Part 4, Chapter 1

Sections 8 & 9

8.5.7 **Where bracket floors** are fitted, the bottom frames are to be derived from 6.3.1. The unsupported span of the frames is not to exceed 2,5 m. The breadth of the brackets attaching the frames and the reverse frames to the centre girder and margin plate is to be three-quarters of the depth of the centre girder. The brackets are to be flanged on the unsupported edge and are to have the same thickness as the plate floors.

8.5.8 **Where struts** are fitted to reduce the unsupported span of the frames, reverse frames and longitudinals, they are to have a cross-sectional area of not less than:

$$(a) A = 0,32Z_{BF} \text{ cm}^2 \quad \text{for } Z_{BF} \leq 83,5, \text{ or}$$

$$(b) A = 23,2 + \frac{Z_{BF}}{25} \text{ cm}^2 \quad \text{for } Z_{BF} > 83,5$$

where  $Z_{BF}$  is the modulus, in  $\text{cm}^3$ , of the frame or longitudinal based on the effective length between floors as defined in Pt 3, Ch 3,3.

## Section 9 Bulkheads

### 9.1 General

9.1.1 The requirements of this Section cover watertight and deep tank transverse and longitudinal bulkheads. Requirements are also given for shaft tunnel boundaries and non-watertight bulkheads. For transverse bulkheads in way of ballast holds, stools may be required, see Ch 7,10.2.

9.1.2 The requirements of this Section apply to a vertical system of stiffening on bulkheads. They may also be applied to a horizontal system of stiffening provided that equivalent end support and alignment are provided.

9.1.3 For number and disposition of transverse watertight bulkheads, see Pt 3, Ch 3,4.

9.1.4 The buckling requirements of Pt 3, Ch 4,7 are also to be satisfied.

### 9.2 Watertight and deep tank bulkheads

9.2.1 The scantlings of watertight and deep tank bulkheads are to comply with the requirements of Tables 1.9.1 to 1.9.3. Where bulkhead stiffeners support deck girders, transverses or pillars over, the requirements of 4.4.11 are also to be satisfied.

9.2.2 In way of partially filled holds or tanks, the scantlings and structural arrangements of the boundary bulkheads are to be capable of withstanding the loads imposed by the movement of the liquid in those spaces. The magnitude of the predicted loadings, together with the scantling calculations may require to be submitted, see Pt 3, Ch 3,5.4.

9.2.3 In deep tanks, oil fuel or oil carried as cargo is to have a flash point of 60°C or above (closed cup test). Where tanks are intended for other liquid cargoes of a special nature the scantlings and arrangements will be considered in relation to the nature of the cargo.

9.2.4 Where watertight bulkhead stiffeners are cut in way of watertight doors in the lower part of a bulkhead, the opening is to be suitably framed and reinforced. Where stiffeners are not cut but the spacing between the stiffeners is increased on account of watertight doors, the stiffeners at the sides of the doorways are to be increased in depth and strength so that the efficiency is at least equal to that of the unpierced bulkhead, without taking the stiffness of the door frame into consideration. Watertight recesses in bulkheads are generally to be so framed and stiffened as to provide strength and stiffness equivalent to the requirements for watertight bulkheads.

9.2.5 A centreline bulkhead is, generally, to be fitted in deep tanks which extend from side to side of the ship and are intended for the carriage of oil fuel for the ship's use. The bulkhead may be intact or perforated as desired. If intact, the scantlings are to be as required for boundary bulkheads. If perforated, the modulus of the stiffeners may be 50 per cent of that required for boundary bulkheads, using  $h_4$  measured to the crown of the tank. The stiffeners are to be bracketed at top and bottom. The area of perforation is to be not less than five per cent nor more than 10 per cent of the total area of the bulkhead. Where brackets from horizontal girders on the boundary bulkheads terminate at the centreline bulkhead, adequate support and continuity are to be maintained.

### 9.3 Shaft tunnels

9.3.1 Where shaft tunnels are required as specified in Pt 3, Ch 3,4 the thickness of the tunnel plating is to comply with Table 1.9.1 for holds or deep tanks as appropriate. If the top plating is well curved, the thickness may be reduced by 10 per cent in dry cargo holds. If the top plating is flat, it is to be not less than 1,1 times the thickness required for watertight bulkheads in dry cargo holds. Under hatchways the top plating is to be increased by 2 mm, unless covered with wood not less than the thickness specified in 2.2.2, which is to be secured by fastenings which do not penetrate the plating. Where it is intended to use plywood or other forms of ceiling of an approved type instead of planking, the thickness will be considered in each case. The tunnel stiffeners are to comply with Table 1.9.1 for holds or deep tanks, as appropriate. When the section modulus of curved stiffeners is determined, the values of  $\omega_1$  and  $\omega_2$  are to be taken as 1,0. The span of the stiffener,  $l_{\sigma}$ , is to be taken as the overall height of the tunnel, measured vertically at the centreline of the tunnel. If the tunnel top is flat, scantlings of the stiffeners are also to comply with 4.3. The lower end connection to the tank top is to be welded. Additional strengthening is to be fitted under the heels of pillars or masts stepped on the tunnel.

### 9.4 Non-watertight bulkheads

9.4.1 The scantlings are to be in accordance with Table 1.4.8.

# General Cargo Ships

# Part 4, Chapter 1

Section 9

**Table 1.9.1 Watertight and deep tank bulkhead scantlings**

Item and requirement	Watertight bulkheads	Deep tank bulkheads
(1) Plating thickness for plane, symmetrically corrugated and double plate bulkheads	$t = 0,004sf \sqrt{h_4 k} \text{ mm}$ but not less than 5,5 mm	$t = 0,004sf \sqrt{\frac{\rho h_4 k}{1,025}} + 2,5 \text{ mm}$ but not less than 6,5 mm, where $L < 90 \text{ m}$ nor less than 7,5 mm, where $L \geq 90 \text{ m}$
	In the case of symmetrical corrugations, $s$ is to be taken as $b$ or $c$ in Fig. 3.3.1 in Pt 3, Ch 3, whichever is the greater	
(2) Modulus of rolled and built stiffeners, swedges, double plate bulkheads and symmetrical corrugations	$Z = \frac{skh_4 l_e^2}{71\gamma(\omega_1 + \omega_2 + 2)} \text{ cm}^3$	$Z = \frac{\rho skh_4 l_e^2}{22\gamma(\omega_1 + \omega_2 + 2)} \text{ cm}^3$
	In the case of symmetrical corrugations, $s$ is to be taken as $p$ , see also Note 2	
(3) Inertia of rolled and built stiffeners and swedges	—	$I = \frac{2,3}{k} l_e Z \text{ cm}^4$
(4) Symmetrical corrugations and double plate bulkheads	Additional requirements to be complied with as detailed in Table 1.9.2	
(5) Stringers or webs supporting vertical or horizontal stiffening		
(a) Modulus	$Z = 5,5kh_4 S l_e^2 \text{ cm}^3$	$Z = 11,7\rho kh_4 S l_e^2 \text{ cm}^3$
(b) Inertia	—	$I = \frac{2,5}{k} l_e Z \text{ cm}^4$
Symbols		
<p><math>s, S, I, k, \rho</math> as defined in 1.5.1</p> <p><math>d_w</math> = web depth of stiffening member, in mm</p> <p><math>f = 1,1 - \frac{s}{2500S}</math> but not to be taken greater than 1,0</p> <p><math>h_4</math> = load head, in metres measured as follows:</p> <p>(a) For watertight bulkhead plating, the distance vertically from a point one-third of the height of the plate above its lower edge to a point 0,91 m above the bulkhead deck at side or perpendicular to the deepest equilibrium waterline in damaged condition obtained from applicable damage stability calculations, whichever is the greater, see also Fig. 3.5.2 in Pt 3, Ch 3</p> <p>(b) For deep tank bulkhead plating, the distance from a point one-third of the height of the plate above its lower edge to the top of the tank, or half the distance to the top of the overflow, whichever is the greater, see also Fig. 3.5.2 in Pt 3, Ch 3</p> <p>(c) For watertight bulkhead stiffeners or girders, the distance vertically from the middle of the effective length to a point 0,91 m above the bulkhead deck at side, or perpendicular to the deepest equilibrium waterline in damaged condition obtained from applicable damage stability calculations, whichever is the greater, see also Fig. 3.5.2 in Pt 3, Ch 3</p> <p>(d) For deep tank bulkhead stiffeners or girders, the distance from the middle of the effective length to the top of the tank, or half the distance to the top of the overflow, whichever is the greater, see also Fig. 3.5.2 in Pt 3, Ch 3</p> <p><math>l_e</math> = effective length of stiffening member, in metres, and for bulkhead stiffeners, to be taken as <math>l - e_1 - e_2</math>, see also Fig. 1.9.1</p> <p><math>\rho</math> = spacing of corrugations as shown in Fig. 3.3.1 of Pt 3, Ch 3</p> <p><math>\gamma</math> = 1,4 for rolled or built sections and double plate bulkheads                      = 1,6 for flat bars                      = 1,1 for symmetrical corrugations of deep tank bulkheads                      = 1,0 for symmetrical corrugations of watertight bulkheads</p> <p><math>\omega, e</math> = as defined in Table 1.9.3, see also Fig. 1.9.1</p>		
<p>NOTES</p> <p>1. In no case are the scantlings of deep tank bulkheads to be less than the requirements for watertight bulkheads where watertight bulkheads are required by Pt 3, Ch 3.5.</p> <p>2. In calculating the actual modulus of symmetrical corrugations, the panel width <math>b</math> is not to be taken greater than that given by Pt 3, Ch 3.3.2.</p> <p>3. For rolled or built stiffeners with flanges or face plates, the web thickness is to be not less than <math>\frac{d_w}{60 \sqrt{k}}</math> whilst for flat bar stiffeners the web thickness is to be not less than <math>\frac{d_w}{18 \sqrt{k}}</math></p>		




Fig. 1.9.1 End connections

## General Cargo Ships

## Part 4, Chapter 1

Section 9

Table 1.9.2 Symmetrical corrugations and double plate bulkheads (additional requirements)

Symbols	Type of bulkhead	Parameter	Watertight bulkheads	Deep tank bulkheads
$s, k$ as defined in 1.5.1 $b$ = panel width as shown in Fig. 3.3.1 in Pt 3, Ch 3 $d$ = depth, in mm, of symmetrical corrugation or double plate bulkhead $l_e$ as defined in Table 1.9.1 $A_w$ = shear area, in cm <sup>2</sup> , of webs of double plate bulkhead $\theta$ = angle of web corrugation to plane of bulkhead	Symmetrically corrugated, see also Notes 1 and 2	$\frac{b}{t}$	Not to exceed: 85 $\sqrt{k}$ at top, and 70 $\sqrt{k}$ at bottom	Not to exceed: 70 $\sqrt{k}$ at top, and at bottom
		$d$	—	To be not less than: 39 $l_e$ mm
		$\theta$	To be not less than 40°	
NOTES 1. The plating thickness at the middle of span $l_e$ of corrugated or double plate bulkheads is to extend not less than 0,2 $l_e$ m above mid-span. 2. Where the span of corrugations exceeds 15 m, a diaphragm plate is to be arranged at about mid-span. 3. See also Pt 3, Ch 10,5.2.1.	Double plate, see also Notes 1 and 3	$\frac{s}{t}$	Not to exceed: 75 $\sqrt{k}$ at top, and 65 $\sqrt{k}$ at bottom	
		$\frac{d}{t_w}$	Not to exceed: 85 $\sqrt{k}$ at top, and 75 $\sqrt{k}$ at bottom	
		$d$	—	To be not less than: 39 $l_e$ mm
		$A_w$	To be not less than: $\frac{0,12Z}{l_e}$ cm <sup>2</sup> at top, and $\frac{0,18Z}{l_e}$ cm <sup>2</sup> at bottom	To be not less than: $\frac{0,07Z}{l_e}$ cm <sup>2</sup> at top, and $\frac{0,10Z}{l_e}$ cm <sup>2</sup> at bottom

## General Cargo Ships

## Part 4, Chapter 1

Section 9

Table 1.9.3 Bulkhead end constraint factors (see continuation)

Type	End connection (see Fig. 1.9.1)		$\omega$	$e$	$\mu$
Rolled or built stiffeners and swedges					
1	End of stiffeners unattached or attached to plating only		0	0	—
2	Members with webs and flanges (or bulbs) in line and attached at deck or horizontal girder, see also Note 1	Adjacent member of B of smaller modulus	The lesser of $\frac{4,5Z_B}{M_1}$ or 1,0	0	—
3		Adjacent member of B of same or larger modulus	1,0	0	—
4	Bracketless connection to longitudinal member	Member A within length $l$	1,0	$\frac{d_A}{1000}$	—
5		Member A outside length $l$	1,0	0	—
6	Bracketed connection	To transverse member	Bracket extends to floor	1,0	The lesser of $\beta a$ or 0,1 $l$
7			Otherwise	1,0	0
8		To longitudinal member		1,0	The lesser of $\beta a$ or 0,1 $l$
Symmetrical corrugations or double plate bulkheads					
9	Welded directly to deck – no bulkhead in line	No longitudinal brackets	0	0	—
10		With longitudinal brackets and transverse stiffeners supporting corrugated bulkhead	The lesser of $\frac{\delta t_e}{t_m}$ or 1,0	0	—
11	Welded directly to deck or girder	Bulkhead B, having same section, in line	The least of $\frac{\delta t_B}{t_m}$ or $\frac{\delta t_e}{t_m}$ or 1,0	0	—
12	Welded directly to tank top and effectively supported by floors in line with each bulkhead flange, see also Note 2	Thickness at bottom same as that at mid-span	The least of $\frac{\delta t_f}{t_m}$ or $\frac{\delta t_e}{t_m}$ or 1,0	0	—
13		Thickness at bottom greater than that at mid-span	The least of $\frac{\delta t_f}{t_m}$ or $\frac{\delta t_e}{t_m}$ or 1,0	The lesser of $\alpha l$ or $a$	The lesser of $\frac{t_f}{t_m}$ or $\frac{t_e}{t_m}$
14	Welded to stool efficiently supported by ship's structure		For deep tank bulkheads 1,0 For watertight bulkheads the least of $\frac{\delta t_s}{t_m}$ or $\frac{\delta t_e}{t_m}$ or 1,0	The lesser of $\alpha l$ or $a$	$\frac{10Z_s}{M_2}$

# General Cargo Ships

# Part 4, Chapter 1

Section 9

**Table 1.9.3 Bulkhead end constraint factors (conclusion)**

Symbols	
<p><math>s, l, p, k</math>, as defined in 1.5.1</p> <p><math>a</math> = height, in metres, of bracket or end stool or lowest strake of plating of symmetrically corrugated or double plate bulkheads, see Fig. 1.9.1</p> <p><math>d_A</math> = overall depth, in mm, of adjacent member A</p> <p><math>e</math> = effective length, in metres, of bracket or end stool, see Fig. 1.9.1</p> <p><math>h_0</math> = <math>h_4</math> but measured from the middle of the overall length <math>l</math></p> <p><math>l_e, p, h_4</math> as defined in Table 1.9.1</p> <p><math>t_B</math> = thickness, in mm, of flange plating of member B</p> <p><math>t_f</math> = thickness, in mm, of supporting floor</p> <p><math>t_m, t_e</math> = thickness, in mm, of flange plating of corrugation or double plate bulkhead at mid-span or end, respectively</p> <p>Subscripts 1 and 2 when applied to <math>\omega, e</math>, and <math>a</math> refer to the top and bottom ends of stiffener</p> <p><math>M_1 = \frac{h_4 s l_e^2}{71}</math> for watertight bulkheads</p> <p><math>= \frac{\rho h_4 s l_e^2}{22}</math> for deep tank bulkheads</p> <p><math>M_2 = \frac{h_0 s l^2}{71}</math> for watertight bulkheads</p> <p><math>= \frac{\rho h_0 s l^2}{22}</math> for deep tank bulkheads</p> <p>In the case of symmetrical corrugations <math>s = p</math></p> <p><math>Z_B</math> = section modulus, in <math>\text{cm}^3</math>, of adjacent member B</p> <p><math>Z_s</math> = section modulus, in <math>\text{cm}^3</math>, of horizontal section of stool adjacent to deck or tank top over breadth <math>s</math> or <math>p</math> (as applicable)</p> <p>All material which is continuous from top to bottom of stool may be included in the calculation</p>	<p><math>\alpha</math> = a factor depending on <math>\mu</math> and determined as follows:</p> <p>where <math>\mu \leq 1,0</math> <math>\alpha = 0</math></p> <p>where <math>\mu &gt; 1,0</math> <math>\alpha = 0,5 - \frac{1}{\sqrt{2\mu + 2}}</math></p> <p><math>\beta</math> = a factor depending on the end bracket stiffening and to be taken as:</p> <p>1,0 for brackets with face bars directly connected to stiffener face bars</p> <p>0,7 for flanged brackets</p> <p>0,5 for unflanged brackets</p> <p><math>\mu</math> = a factor representing end constraint for symmetrical corrugation and double plate bulkheads</p> <p><math>\omega</math> = an end constraint factor relating to the different types of end connection, see Fig. 1.9.1</p> <p><math>t_s</math> = thickness, in mm, of stool adjacent to bulkhead</p> <p><math>\delta</math> = 1,0 generally</p> <p><math>= \frac{0,932\sqrt{k}}{\xi}</math> for corrugated watertight bulkheads</p> <p><math>\xi</math> = 1,0 where full continuity of corrugation webs is provided at the ends</p> <p>= greater of 1,0 and <math>(\eta + 0,333)</math> where full continuity is not provided</p> <p><math>\eta</math> = lesser of 1,0 and <math>\frac{50 t_m \sqrt{k}}{b}</math> for welded sections</p> <p>= lesser of 1,0 and <math>\frac{60 t_m \sqrt{k}}{b}</math> for cold formed sections</p>
<p>NOTES</p> <p>1. Where the end connection is similar to type 2 or 3, but member flanges (or bulbs) are not aligned and brackets are not fitted, <math>\omega = 0</math>.</p> <p>2. Where the end connection is similar to type 12 or 13, but a transverse girder is arranged in place of one of the supporting floors, special consideration will be required.</p>	

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 1

### Section

- 1 **General**
- 2 **Longitudinal strength**
- 3 **Deck structure**
- 4 **Shell envelope plating**
- 5 **Shell envelope framing**
- 6 **Double bottom**
- 7 **Peak, watertight and deep tank bulkheads**
- 8 **Bow doors and inner doors**
- 9 **Subdivision structure on vehicle deck**
- 10 **Masts and standing rigging**
- 11 **Miscellaneous openings**
- 12 **Glass structures**
- 13 **Direct calculation**

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies to sea-going roll on-roll off cargo ships, passenger ships and sailing passenger ships defined as follows:

- (a) A passenger ferry is defined as a ship specially designed and constructed for the carriage of passengers on a regular scheduled service between specified ports operating in reasonable weather conditions.
- (b) A passenger/vehicle ferry is defined as a ship specially designed and constructed for the carriage of passengers and vehicles on a regular scheduled service between specified ports operating in reasonable weather conditions.
- (c) A roll on-roll off cargo ship is defined as a ship specially designed and constructed for the carriage of vehicles, and cargo in pallet form or in containers, and loaded/unloaded by wheeled vehicles.
- (d) A passenger ship is defined as a ship specially designed and constructed for the carriage of more than 12 passengers.
- (e) A sailing passenger ship is defined as a ship specially designed and constructed for the carriage of more than 12 passengers and incorporating sail devices which are intended to be the primary means of propulsion.

1.1.2 Ships intended only to operate in certain areas or conditions which have been agreed by the Committee, as defined in Pt 1, Ch 2, will receive individual consideration on the basis of the rules with respect to the environmental conditions agreed for the design basis and approval.

1.1.3 The scantlings and arrangements are to be as required by Chapter 1 except as otherwise specified in this Chapter.

1.1.4 The scantlings of structural items may be determined by direct calculation. For passenger ships where it is considered that the superstructure will be subjected to a significant load from flexure of the hull girder; or, where it is required to utilise the load carrying capability of the superstructure for longitudinal strength, the scantlings of the primary supporting structure are to be assessed by direct calculations and the ShipRight notations **SDA** and **CM** are mandatory, see 1.3 and Section 11.

### 1.2 Structural configuration

1.2.1 The requirements provide for a basic structural configuration of a multi-deck hull which includes a double bottom, and in some cases wing tanks up to the lowest deck.

1.2.2 For passenger ships, the structural arrangements detailed in Chapter II-1, Part B, of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments as they apply to passenger ships are to be complied with in their entirety.

1.2.3 Where bulkheads are omitted in accordance with Pt 3, Ch 3,4, a system of partial bulkheads, web frames and deck transverse should be fitted to provide equivalent transverse strength.

1.2.4 Longitudinal framing is, in general, to be adopted at the strength deck and at the bottom, but special consideration will be given to proposals for transverse framing in these regions.

1.2.5 Reference should be made to the Regulations of the *International Convention for the Safety of Life at Sea, 1974* and applicable amendments and to the relevant Statutory Requirements of the National Authority of the country in which the ship is to be registered.

1.2.6 Attention is also drawn to the requirements for passenger ships given in:

- Bulkhead requirements, see Pt 3, Ch 3,4
- Closing arrangements for shell, deck and bulkheads, see Pt 3, Ch 11,6, Ch 11,8 and Ch 11,9
- Electrical Installations, see Pt 6, Ch 2
- Fire protection, detection and extinction, see SOLAS Reg. II-2/B and C.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 1

1.2.7 Attention is drawn to National Authority requirements relating to the stowage and securing of vehicles and cargo units on board roll on-roll off ships. Steel used for the construction of fixed securing fittings attached to the ship's structure is to comply with the requirements of *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials (Part 2), or with an equivalent acceptable specification. Due account is to be taken of the grade and tensile strength of the hull material in way of the attachment and the chemical composition of the steel is to be such as to ensure acceptable qualities of weldability.

1.2.8 Sailing passenger ships are to be fitted with auxiliary propulsive power to ensure adequate speed and manoeuvrability of the vessel in conditions when the sail systems are not available for use. The auxiliary propulsion and other essential machinery is to comply with the requirements of Part 5 of the Rules, as applicable.

1.2.9 Sail systems may be made up in the form of soft sails, semi-rigid and rigid sail configurations including wind turbines or systems incorporating rotating cylinders.

1.2.10 For sailing vessels, a continuous visual read out of the apparent wind speed and direction is to be available to the ship's master when the vessel is under way. Sail control and service systems are to provide adequate speed of response to neutralise the sail system in the event of high wind conditions. Sufficient information and evidence is to be submitted to substantiate that the foregoing arrangements are in place.

1.2.11 For sailing passenger ships, the Rules for classification will, in principle, apply to the mast arrangements and standing gear, but will exclude running gear, yards, booms and sail arrangements.

1.2.12 For sailing passenger ships, the equipment requirements will be in accordance with the letter and numeral two grades higher than that corresponding to the calculated Equipment Numeral.

### 1.3 Class notations

1.3.1 In general, ships complying with the requirements of this Chapter will be eligible to be classed:

'100A1 passenger ferry', or  
'100A1 passenger/vehicle ferry', or  
'100A1 roll on-roll off cargo ship', or  
'100A1 passenger ship', or  
'100A1 sailing passenger ship'.

1.3.2 A ship assigned a class notation incorporating the word 'passenger' which is also designed to fulfil other functions not associated with passenger carrying, is to comply with the requirements of this Chapter for passenger ships together with the requirements of the relevant Chapter of this Part for the particular ship type.

1.3.3 Where ferries are specially reinforced for the carriage of trains on fixed rails, the class notation will also include the word 'train'.

1.3.4 The Regulations for the classification and assignment of class notations are given in Pt 1, Ch 2, to which reference should be made.

1.3.5 The 'ShipRight Procedures' for hull construction of ships are detailed in Pt 3, Ch 16 and the classification notations and descriptive notes associated with these procedures are given in Pt 1, Ch 2,2.

1.3.6 The 'Structural Design Assessment' (**SDA**) and 'Construction Monitoring' (**CM**) procedures detailed in the *ShipRight Procedures Manual*, published by Lloyd's Register (hereinafter referred to as 'LR'), are mandatory for passenger ships where it is considered that the superstructure will be subjected to a significant load from flexure of the hull girder; or, where it is required to utilise the load carrying capability of the superstructure for longitudinal strength, and for other passenger ships of abnormal hull form, or of unusual structural configuration or complexity.

### 1.4 Information required

1.4.1 In addition to the information and plans required by Pt 3, Ch 1,5, the following details are to be submitted:

- The intended service areas required for ships designed to operate within specified geographical limits.
- Stern or bow ramps.
- Bow, stern and side doors.
- Movable decks, if fitted, including stowing arrangements for portable components.
- Sail plans and associated operational and design conditions, including apparent wind speeds (sailing ships).
- Masts and all structural components of the standing rigging (sailing ships).
- The standing rigging and all standing rigging attachments (sailing ships).
- The design deck loadings including details of wheeled vehicles, see Pt 3, Ch 9,3, and trains, where applicable.
- Locations of fixed securing points for wheeled vehicles, with indication of the magnitude and direction of the imposed lashing force.

### 1.5 Symbols

1.5.1 For the definition of symbols not defined in this Chapter, see Ch 1,1.5.

1.5.2 The following definitions apply to ships employing sails:

Standing rigging	– Rigging of fixed length used to support masts/bowsprit.
Running rigging	– Rigging used to control yards, booms and sails and which may pass over revolving sheaves.
Apparent wind speed	– The vector resultant of the combination of real wind speed and ship velocity.



# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

### Section 2

#### ■ Section 2 Longitudinal strength

##### 2.1 General

2.1.1 Longitudinal strength calculations are to be made in accordance with the requirements given in Pt 3, Ch 4 and the additional notes contained in this Section.

2.1.2 The design vertical wave bending moments and design wave shear forces to be used in Pt 3, Ch 4 are to be determined in accordance with Sections 2.3 and 2.4 below. For ships of unusual hullform or where their design parameters are outwith the applicability of the Rules, see Pt 3, Ch 4, special consideration will be given to the values and distributions of the wave induced global loads.

2.1.3 The still water bending moment and shear force envelopes are to take into account the requirements of Section 2.3.

2.1.4 For ships where the side shell or side casings contain large openings or where the effectiveness of the superstructures in resisting hull girder bending loads is expected to be reduced by the presence of large numbers of windows or openings, the combined hull and superstructure response may require to be verified using direct calculation techniques.

##### 2.2 Calculation of hull section modulus

2.2.1 The calculation of section modulus is to be in accordance with Pt 3, Ch 3, 3.4 and the additional notes in this Section. In general, the effective sectional area of continuous longitudinal strength members, after deduction of openings, is to be used for the calculation of midship section modulus. For ships where the effectiveness of the superstructure is only partial due to the presence of large or numerous shell openings or discontinuities in the shell envelope, then an equivalent section modulus for the purposes of this section may be derived using direct calculations.

2.2.2 Structural members which contribute to the overall hull girder strength are to be carefully aligned so as to avoid discontinuities resulting in abrupt variations of stresses and are to be kept clear of any form of openings which may affect their structural performances.

2.2.3 In general, short superstructures, see also Pt 3, Ch 3, 3.4.2, or deckhouses will not be accepted as contributing to the global longitudinal or transverse strength of the ship. However, where it is proposed to include substantial, continuous stiffening members, special consideration will be given to their inclusion on submission of the designer's/builder's calculations, see also 2.6.

2.2.4 Adequate transition arrangements are to be fitted at the ends of effective continuous longitudinal strength members in the deck and bottom structures.

2.2.5 Scantlings of all continuous longitudinal members of the hull girder based on the minimum section stiffness requirements determined from Pt 4, Ch 4,5 are to be maintained within 0,4L amidships. However, in special cases, based on consideration of type of ship, hull form and loading conditions, the scantlings may be gradually reduced towards the ends of the 0,4L part, bearing in mind the desire not to inhibit the ship's loading and operational flexibility.

2.2.6 Structural material which is longitudinally continuous but which is not considered to be fully effective for longitudinal strength purposes may be specially considered. The global longitudinal strength assessment must take into account the presence of such material when it can be considered effective. The consequences of failure of such structural material and subsequent redistribution of stresses into or additional loads imposed on the remaining structure is to be considered.

2.2.7 In particular, all longitudinally continuous material will be fully effective in tension whereas this may not be so in compression due to a low buckling capability. In this case, it may be necessary to derive and apply different hull girder section moduli to the hogging and sagging bending moment cases.

##### 2.3 Still water bending moments and shear forces

2.3.1 The design still water hogging and sagging bending moment distribution envelope,  $M_S$ , is to be taken as the maximum sagging (negative) and maximum hogging (positive) still water bending moments, calculated at each position along the ship. The maximum moments from all loading conditions are to be used to define the still water bending moment distribution envelope.

2.3.2 It is normal for ships which have a low deadweight requirement or a uniform loading rate in association with a low block coefficient to have a hogging still water bending moment in all conditions of loading. For these ships, the maximum design sagging still water bending moment may be taken as the minimum actual hogging bending moment.

2.3.3 The design still water shear force distribution envelope,  $Q_S$ , is to be taken as the maximum positive and negative shear force values, calculated at each position along the ship. The maximum shear forces from all loading conditions are to be used to define the still water shear force distribution envelope.

# Ferries, Roll on-Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 2

### 2.4 Design vertical wave bending moments

2.4.1 The minimum value of vertical wave bending moment,  $M_w$  at any position along the ship may be taken as follows:

$$M_w = f_1 f_2 C_2 M_{w0} \quad \text{kNm (tonne-f m)}$$

where

$$M_{w0} = 0,1 C_1 L^2 B_{WL} (C_b + 0,7) \quad \text{kNm}$$

$$(M_{w0} = 0,0102 C_1 L^2 B_{WL} (C_b + 0,7) \quad \text{tonne-f m})$$

$B_{WL}$  = maximum waterline breadth, in metres

$C_1$ ,  $C_2$ ,  $L$  and  $C_b$  are given in Pt 3, Ch 4,5

and

$f_1$  is given in Pt 3, Ch 4,5

$f_2$  is the hogging,  $f_{fH}$ , or sagging,  $f_{fS}$ , correction factor based on the amount of bow flare, stern flare, length and effective buoyancy of the aft end of the ship above the waterline

$f_{fS}$  is the sagging (negative) moment correction factor and is to be taken as

$$f_{fS} = -1,10 R_A^{0,3} \quad \text{for values of } R_A > 1,0$$

$$f_{fS} = -1,10 \quad \text{for values of } R_A \leq 1,0$$

$f_{fH}$  is the hogging (positive) moment correction factor and is to be taken as

$$f_{fH} = \frac{1,9 C_b}{(C_b + 0,7)}$$

$R_A$  is an area ratio factor, see 2.4.2.

2.4.2 The area ratio factor,  $R_A$ , for the combined stern and bow shape is to be derived as follows:

$$R_A = \frac{30 (A_{BF} + 0,5 A_{SF})}{L B_{WL}}$$

where

$A_{BF}$  is the bow flare area, in  $m^2$

$A_{SF}$  is the stern flare area, in  $m^2$

2.4.3 The bow flare area,  $A_{BF}$ , is illustrated in Fig. 2.2.1 and may be derived as follows:

$$A_{BF} = A_{UB} - A_{LB} \quad m^2$$

where

$A_{UB}$  is half the water plane area at a waterline of  $T_{C,U}$  of the bow region of the hull forward of  $0,8L$  from the AP

$A_{LB}$  is half the water plane area at the design draught of the bow region of the hull forward of  $0,8L$  from the AP

NOTE


The AP is to be taken at the aft end of  $L$

The design draught is to be taken as  $T$ , see Pt 3, Ch 1,6.1.

Alternatively the following formula may be used

$$A_{BF} = 0,05L (b_0 + 2b_1 + b_2) + b_0 a/2 \quad m^2$$

where



**Fig. 2.2.1**  
**Derivation of bow and stern flare areas**

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

### Section 2

$b_0$  = projection of  $T_{C,U}$  waterline outboard of the design draught waterline at the FP, in metres, see Fig. 2.2.1

$b_1$  = projection of  $T_{C,U}$  waterline outboard of the design draught waterline at 0,9L from the AP, in metres

$b_2$  = projection of  $T_{C,U}$  waterline outboard of the design draught waterline at 0,8L from the AP, in metres

$a$  = projection of  $T_{C,U}$  waterline forward of the FP, in metres

$T_{C,U}$  is a waterline taken  $C_1/2$  m above the design draught

$$T_{C,U} = T + \frac{C_1}{2} \text{ m}$$

$C_1$  is given in Pt 3, Ch 4, Table 4.5.1

For ships with large bow flare angles above the  $T_{C,U}$  waterline the bow flare area may need to be specially considered.

2.4.4 The stern flare area,  $A_{SF}$ , is illustrated in Fig. 2.2.1 and is to be derived as follows:

$$A_{SF} = A_{US} - A_{LS} \text{ m}^2$$

where

$A_{US}$  is half the water plane area at a waterline of  $T_{C,U}$  of the stern region of the hull aft of 0,2L from the AP

$A_{LS}$  is half the water plane area at a waterline of  $T_{C,L}$  of the stern region of the hull aft of 0,2L from the AP

$T_{C,L}$  is a waterline taken  $C_1/2$  m below the design draught

$$T_{C,L} = T - \frac{C_1}{2} \text{ m}$$

For ships with tumblehome in the stern region, the maximum breadth at any waterline less than  $T_{C,U}$  is to be used in the calculation of  $A_{US}$ . The effects of appendages including bossings are to be ignored in the calculation of  $A_{LS}$ .

2.4.5 Direct calculation methods may be used to derive the vertical wave bending moments, see Pt 3, Ch 4,2.5.

2.4.6 The sagging correction factor,  $f_{IS}$ , in the vertical wave bending moment formulation in 2.3.1 may be derived by direct calculation methods. Appropriate direct calculation methods include a combination of long term ship motion analysis, non linear ship motion analysis and static balance on a wave crest or trough.

## 2.5 Design wave shear force

2.5.1 The design vertical wave shear force,  $Q_w$ , at any position along the ship is given by:

$$Q_w = 3f_1 K_f M_{wo}/L \text{ kN (tonne-f)}$$

where

$K_f$  is to be taken as follows, see also Fig. 2.2.2:

(a) Positive shear force:

$K_f = 0$  at aft end of  $L$

= +0,836 $f_{IH}$  between 0,2L and 0,3L from aft

= +0,65 $f_{IH}$  between 0,4L and 0,5L from aft

= -0,65 $f_{IS}$  between 0,5L and 0,6L from aft

= -0,91 $f_{IS}$  between 0,7L and 0,85L from aft

= 0 at forward end of  $L$

(b) Negative shear force:

$K_f = 0$  at aft end of  $L$

= +0,836 $f_{IS}$  between 0,15L and 0,3L from aft

= +0,65 $f_{IS}$  between 0,4L and 0,5L from aft

= -0,65 $f_{IH}$  between 0,5L and 0,6L from aft

= -0,91 $f_{IH}$  between 0,7L and 0,85L from aft

= 0 at forward end of  $L$

Intermediate values to be determined by linear interpolation.

$f_1$ ,  $M_{wo}$ ,  $f_{IS}$  and  $f_{IH}$  are defined in 2.4.1.




Fig. 2.2.2 Shear force factor  $K_f$

## 2.6 Buckling strength

2.6.1 The buckling requirements in Pt 3, Ch 4,7 are to be applied to plate panels and longitudinals subject to hull girder compression and shear stresses. The design stresses are to be based on the design values of still water and wave bending moments and shear forces and are given in 2.4.1 and 2.5.1.

2.6.2 The standard deduction for corrosion,  $d_t$ , to be applied to plating and longitudinals is to be taken in accordance with Table 4.7.1 in Pt 3, Ch 4.

2.6.3 The buckling factors of safety,  $\lambda$ , to be applied to the corrected critical buckling stress,  $\sigma_{CRB}$ , of plate panels and longitudinals subjected to hull girder compression are given in Table 2.2.1, where the corrected critical buckling stress is to be determined in accordance with Pt 3, Ch 4,7.3

2.6.4 The shear buckling requirements of Pt 3, Ch 4,7.3 are to be applied.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 2 & 3

**Table 2.2.1 Buckling factors of safety,  $\lambda$**

Structural item	Buckling factor of safety, $\lambda$
Longitudinally effective plating	1,0
Longitudinal stiffeners when the buckling failure mode of the attached plating is elasto-plastic, see Note	1,1
Longitudinal stiffeners when the buckling failure mode of the attached plating is elastic, see Note	1,25
<b>NOTE</b> The buckling mode of failure of the attached plating is defined as follows: elastic $\sigma_E \leq 0,5 \sigma_0$ elasto-plastic $\sigma_E > 0,5 \sigma_0$ where $\sigma_E$ = the elastic critical buckling stress, see Pt 3, Ch 4,7.3 $\sigma_0$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

**Table 2.3.1 Design deck loadings (ferries and passenger ships only)**

Deck	Design pressures $P_s$ , in kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> )	
	Secondary structures	Primary structures
Decks in way of accommodation and public spaces, see Note	6,38 (0,65)	3,12 (0,32)
Deck supporting baggage spaces	$3,53H_t$ (0,36 $H_t$ )	$3,53H_t$ (0,36 $H_t$ )
Decks in way of stores and refrigerated spaces	14,13 (1,44)	14,13 (1,44)
Decks in way of workshop and machinery spaces (excludes A/C machinery spaces)	18,34 (1,87)	18,34 (1,87)
Magradomes	2,45 (0,25)	2,45 (0,25)
Balconies	3,92 (0,40)	1,96 (0,20)
Weather exposed superstructure decks	2,26 (0,23)	2,26 (0,23)
Weather exposed lifeboat deck	8,44 (0,86)	8,44 (0,86)
Symbols		
$H_t$ = tween deck height, in metres		
<b>NOTE</b> The design pressure, $P_s$ , may be reduced by 12 per cent for ferries and passenger ships with a specified operating area service notation.		

## Section 3 Deck structure

### 3.1 Loading

3.1.1 In general, loadings for decks should comply with the requirements of Pt 4, Ch 1 except where specified in this Section.

3.1.2 Vehicle decks for the carriage of cars, trucks, etc., are to have a loading for wheeled vehicles as specified in Pt 3, Ch 9,3. Where vehicle decks are also used for the carriage of cargo, the loadings derived from Pt 3, Ch 9,3 are to be not less than would be required by Chapter 1.

3.1.3 For ferries and passenger ships classed **100A1**, the minimum design loadings for decks are not to be taken as less than those in Table 2.3.1.

3.1.4 For ferries and passenger ships classed **100A1** with a specified operating area service notation, the loadings for decks in way of baggage and accommodation spaces are to be in accordance with Table 2.3.1.

3.1.5 Mooring decks, afterward and forward, other than when part of the strength deck, are to comply with the requirements for forecastles, see Pt 3, Ch 8. Canopy decks or aprons protecting mooring decks are to be designed using the weather head for forecastle decks reduced by 0,3 m.

3.1.6 For movable decks, see Pt 3, Ch 9,4.

3.1.7 For train decks, the minimum design loading will be specially considered.

**Table 2.3.2 Thickness of deck plating**

Deck location	Plating thickness (mm)
Accommodation and public spaces	$t = 0,008s\sqrt{k}$
Baggage handling and storage	$t = 0,009s\sqrt{k}$
Storerooms	$t = 0,01s\sqrt{k}$
Workshops and machinery spaces	$t = 0,01s\sqrt{k}$
Weather exposed lifeboat deck	$t = 0,00083s_1\sqrt{Lk} + 2,5$
The thickness of deck plating is in no case to be less than 5,0 mm.	

### 3.2 Deck plating

3.2.1 For ferries and passenger ships classed **100A1** the minimum thicknesses of decks are to be in accordance with Table 2.3.2.

3.2.2 For roll on-roll off cargo ships, the thickness of deck plating (other than for vehicle decks) will generally be in accordance with Pt 4, Ch 1.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 3 &amp; 4

3.2.3 Where decks are required to resist hull girder bending, the thickness is to satisfy the requirements of Pt 3, Ch 4,7.

3.2.4 Where deck plating is required to form the effective flange of deck primary members, the thickness may need to be increased locally taking account of the compressive forces acting, see also Pt 3, Ch 10, Table 10.4.1.

3.2.5 Vehicle deck plating is to satisfy the requirements for plating loaded by wheeled vehicles as specified in Pt 3, Ch 9,3. Where vehicle decks are also to be used for the carriage of cargo, the thickness of plating derived from Pt 3, Ch 9,3 is to be not less than would be required by Ch 1,4.2.

3.2.6 The thickness of all other decks will generally be in accordance with Pt 4, Ch 1.

### 3.3 Deck stiffening

3.3.1 For ferries, roll on-roll off cargo ships and passenger ships, the deck stiffening (other than for vehicle decks) will generally be in accordance with Chapter 1. However, in view of the complexity of some multi-deck arrangements in association with large freeboards, deck stiffening may require special consideration.

3.3.2 Vehicle deck beams and longitudinals are to have scantlings in accordance with the requirements for wheeled vehicles as specified in Pt 3, Ch 9,3. Where vehicle decks are also to be used for the carriage of cargo, the scantlings derived from Pt 3, Ch 9,3 are to be not less than would be required by Ch 1,4.3.

3.3.3 In multi-decked ships with high freeboards, the section modulus of deck beams and longitudinals is to be not less than the value given by Table 2.3.3.

**Table 2.3.3 Modulus of deck beams and longitudinals for multi-decked ships with high freeboards**

Position of beam/longitudinal	Modulus, in cm <sup>3</sup>
Decks, excluding those for the stowage of cargo or vehicles	$Z = 0,00083 f_R P_s l_e^2 s k$ $(Z = 0,0081 f_R P_s l_e^2 s k)$ but not less than: $Z = 0,025 s$
Symbols	
$l_e$ , $s$ , $Z$ , and $k$ as defined in Ch 1,1.5 $P_s$ = deck loading in kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> ), see Table 2.3.1 $f_R$ = 1, for ships with unrestricted service $f_R$ = 0,81 for ships with a specified operating area service notation	

### 3.4 Deck supporting primary structure

3.4.1 The section modulus of primary members supporting four or more point loads or a uniformly distributed load is not to be taken as less than:

$$Z = 0,673 S P_s k l_e^2 \text{ (cm}^3\text{)}$$

$$(Z = 6,60 S P_s k l_e^2) \text{ (cm}^3\text{)}$$

where

$l_e$ ,  $S$ ,  $Z$  and  $k$  are as defined in Ch 1,1.5

$P_s$  = deck design loading, in kN/m<sup>2</sup> (tonnes/m<sup>2</sup>), see Table 2.3.1.

3.4.2 The moment of inertia of primary members supporting more than four point loads is not to be taken as less than:

$$I = \frac{1,85}{k} l_e Z \text{ (cm}^4\text{)}$$

$Z$  and  $l_e$  as defined in 3.4.1.

3.4.3 Scantlings of primary structure are to be verified for the following cases using direct calculation methods.

- The structural support arrangement is complex either due to arrangement or loading pattern.
- Large openings are incorporated in the webs of primary members.
- The structure is of novel or unusual design.

The stress criteria in Pt 4, Ch 1, Table 1.4.6 are to be complied with.

3.4.4 For passenger ships direct calculations should be carried out generally in accordance with the SDA procedure.

3.4.5 For roll on-roll off cargo ships and passenger ships and passenger/vehicle ferries with large vehicle stowage spaces, see 5.1.5.

3.4.6 Vehicle deck structure is to be of adequate strength for the upward forces imposed at fixed securing points. Local reinforcement is to be fitted as necessary.

## Section 4 Shell envelope plating

### 4.1 Bottom and side shell

4.1.1 For ferries and passenger ships classed **100A1** with a specified operating area service notation the keel thickness for 0,4L amidships is to be as required by Ch 1,5. At ends, the keel thickness may be reduced by 25 per cent from the above value, but is to be not less than that of the adjacent shell plating.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 4

4.1.2 The thickness of side shell plating above 1,6T including superstructures may require special consideration depending on the particular structural arrangement, hull vertical bending and shear stresses and position of the shell above the waterline. In no case are the shell scantlings above 1,6T be less than the following:

$$(a) \quad t_{zm} = t_{shell} - (Z_m - 1,6T) (0,24 + 0,0012L) \sqrt{\frac{k s_1}{s_b}}$$

$$(b) \quad t_{zm} = (4 + 0,02L) \sqrt{\frac{k s_1}{s_b}}$$

(c) as required by Pt 3, Ch 8

where

$t_{shell}$  = minimum required shell thickness above D/2 for the specific location, as calculated in Pt 4, Ch 1,5

$t_{zm}$  = minimum shell thickness at  $Z_m$

$Z_m$  = vertical height in metres above base

$L$  and  $T$  as defined in Pt 3, Ch1,1.5.

$s_1$ ,  $s_b$  as defined in Table 5.3.1 in Pt 3, Ch 5 for fore end or Table 6.3.1 in Chapter 6 for aft end.

4.1.3 Openings in the side shell and superstructure plating for windows and doors are to be suitably stiffened and the thickness and grade of plating in way will be specially considered.

4.1.4 For ships with broad flat counter stern sections which are liable to be subjected to large wave impact loading, the effect of wave impact loading on the plating and framing of the local shell structure is to be additionally considered, see 4.3 and 5.2.

4.1.5 The plating and framing of the forward shell structure for ships with significant bow flare is to be additionally considered with regard to wave impact loading, see 4.3 and 5.2.

4.1.6 The minimum thickness of the shell plating at ends and for taper is to be not less than the values given in Table 2.4.1, and is in no case to be less than 6 mm.

4.1.7 For ferries and passenger ships classed **100A1** with a specified operating area service notation, the bottom and side shell minimum thickness at ends may be taken 20 per cent less than that required by Table 2.4.1 and Pt 3, Ch 5 and Ch 6, but is in no case to be less than 6 mm.

**Table 2.4.1 End shell thickness**

Scantling length	Thickness, in mm
70 m and below	$(6,5 + 0,033L) \sqrt{\frac{k s_1}{s_b}} - 1,0$
Between 70 m and 110 m	$(6,5 + 0,033L) \sqrt{\frac{k s_1}{s_b}} - 0,5$
Over 110 m	Pt 3, Ch 5 and Ch 6
Symbols	
$L$ as defined in Pt 3, Ch 1,1.5	
$s_1$ , $s_b$ as defined in Table 5.3.1 in Pt 3, Ch 5 for fore end or Table 6.3.1 in Chapter 6 for aft end.	

### 4.2 Bow flare and wave impact pressures

4.2.1 The bow flare wave impact pressure and wave impact pressure on other parts of the side shell plating close to and above the design waterline,  $P_{bf}$ , in kN/m<sup>2</sup> due to relative motion is to be taken as:

$$P_{bf} = 0,5 (K_{bf} V_{bf}^2 + K_{rv} H_{rv} V_{rv}^2) \text{ kN/m}^2$$

where

$K_{bf}$  = hull form shape coefficient for wave impacts

$$= \frac{\pi}{\tan \beta_p} \quad \text{for } \beta_p \geq 10$$

$$= 28 (1 - \tan (2\beta_p)) \quad \text{for } \beta_p < 10$$

$V_{bf}$  = wave impact velocity, in m/s, and is given by

$$= \sqrt{V_{thbf}^2 + 2m_1 \ln (N_{bf})} \quad \text{for } N_{bf} \geq 1$$

$$= 0 \quad \text{for } N_{bf} < 1$$

$V_{thbf}$  = threshold velocity for wave impact, in m/s, to be taken as:

$$= \frac{\sqrt{10}}{\cos \alpha_p}$$

$\ln ( )$  is the natural logarithm

$N_{bf}$  = No. of wave impacts in a three hour period and is given by

$$= 1720 PR_{bf} \sqrt{\frac{m_1}{m_0}}$$

$PR_{bf}$  = probability of a wave impact and is given by

$$= e^{-u}$$

$$u = \left( \frac{Z_{wl}^2}{2m_0} + \frac{V_{thbf}^2}{2m_1} \right)$$

$Z_{wl}$  = distance of the centroid of the area of plating or stiffener above the local design waterline

$m_1$  = variance of the relative vertical velocity

$$= 0,25(\omega_e f_{sl} H_{rm})^2$$

$m_0$  = variance of the relative vertical motion

$$= 0,25 (f_{sl} H_{rm})^2$$

$\omega_e$  = effective encounter wave frequency

$$= \omega \left( 1 + \frac{0,4\omega V_{sl}}{g} \right)$$

$\omega$  = effective wave frequency based on 80 per cent ship length

$$= \sqrt{\frac{2\pi g}{0,8L_{WL}}}$$

$f_{sl}$  = probability level correction factor for relative vertical motion

$$= 1,2$$

$V_{sl}$  = 0,515V, in m/s

$K_{rv}$  = hull form shape coefficient for impact due to forward speed

$$= \frac{\pi}{\tan (90 - \alpha_p)} \quad \text{for } \alpha_p \leq 80$$

$$= 28 (1 - \tan (2 (90 - \alpha_p))) \quad \text{for } \alpha_p > 80$$

$H_{rv}$  = relative wave heading coefficient

$$= 1 \quad \text{for } \gamma_p > 45$$

$$= \cos(45 - \gamma_p) \quad \text{for } \gamma_p \leq 45$$

$V_{rv}$  = relative forward speed, in m/s

$$= 0,515V \sin \gamma_p$$

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 4

- $\alpha_p$  = buttock angle measured in the longitudinal plane, in degrees, see Fig. 2.4.1  
 $\beta_p$  = flare angle measured in the transverse plane, in degrees, see Fig. 2.4.1. For bow flare regions where the bow is non prismatic, i.e. changing rapidly, then  $\beta$  may be taken as the maximum of  $\alpha$  or  $\beta$   
 $\gamma_p$  = waterline angle measured in the horizontal plane, in degrees, see Fig. 2.4.1.

### NOTE

Where only two angles are known and are measured in orthogonal planes, then the third angle may be obtained by the following expression:

$$\alpha_p = \tan^{-1} (\tan \beta_p \tan \gamma_p)$$

The relative vertical motion,  $H_{rm}$ , is to be taken as

$$H_{rm} = C_{w,min} \left( 1 + \frac{4,5}{(C_b + 0,2)} \left( \frac{x_{WL}}{L_{WL}} - x_m \right)^2 \right)$$

where

$$C_{w,min} = \frac{C_w}{\sqrt{2} k_m}$$

$$C_w = \text{a wave head in metres} \\ = 0,0771 L_{WL} (C_b + 0,2)^{0,3} e^{(-0,0044 L_{WL})}$$

$$k_m = 1 + \frac{4,5 (0,5 - x_m)^2}{(C_b + 0,2)}$$

$$x_m = 0,45 - 0,6 F_n \text{ but is not to be less than } 0,2$$

$$F_n = \frac{0,515 V}{\sqrt{g L_{WL}}}$$

$L_{WL}$  = waterline length at summer load draught

$x$  = longitudinal distance, in metres, measured forwards from the aft end of the  $L_{WL}$  to the location being considered

$V$  = speed, in knots, as defined in 1.5.1 for bow locations

$V$  = 0 for stern locations

$C_b$  = Rule block coefficient

If the area of plating under consideration has a waterline angle which is re-entrant or decreasing, e.g. in the stern region, then the relative wave heading coefficient,  $H_{rv}$ , and the speed  $V$  used in the derivation of  $H_{rm}$ , are to be taken as zero.

4.2.2 Alternatively,  $P_{bf}$  may be derived by the direct calculations carried out in accordance with a procedure agreed by LR.

### 4.3 Strengthening for wave impact loads

4.3.1 The shell envelope in the forward and after portions of the hull are to be strengthened against bow flare or wave impact pressure. Typically, strengthening is to be considered over the following areas:

- over the after body in way of a flat counter stern which is close to the waterline;
- over the fore end side and bow structure above the waterline and up to the deck at side;
- other areas where the hull exhibits significant flare.

4.3.2 The thickness of the side shell plating is to be not less than:

$$t = 3,2 s_c \sqrt{k h_s} C_R \times 10^{-2} \text{ mm}$$

where

$s_c$  = is the length of the shorter edge of a plating panel framed by primary and secondary members, see Fig. 2.4.2

$h_s$  = equivalent wave impact head, in metres

$h_s = 0,1 P_{bf} \text{ m}$

$P_{bf}$  = is defined in 4.2.1

$C_R$  = panel ratio factor

$C_R = \left( \frac{l}{s_c} \right)^{0,41}$  but is not to be taken less than 0,06 or greater than 0,1

$l$  = overall panel length, in metres, measured along a chord between the primary members.





Fig. 2.4.1 Bow flare and bottom slamming angles

# Ferries, Roll on-Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 4 & 5



4.3.3 The structural scantlings required in areas strengthened against bow flare slamming are to be tapered to meet the normal shell envelope requirements.

4.3.4 The side structure scantlings required by this Section must in no case be taken less than those required by the remaining Sections of Chapter 2.

### Section 5 Shell envelope framing

#### 5.1 Side structure

5.1.1 The scantlings of frames, or side longitudinals, web frames or transverse, and stringers below 1,6T above base are to satisfy the requirement of Pt 4, Ch 1 and this Section, but may be required to be confirmed by direct calculation. The scantlings of these members above 1,6T from base may require special consideration on the basis of the particular structural arrangements, design deck loading, hull vertical bending stresses, and position of the member above the waterline.

5.1.2 The scantlings of side transverses supporting shell longitudinals above 1,6T are to satisfy the requirements of:

- Pt 4, Ch 1,6, Pt 3, Ch 5,4 and Pt 3, Ch 6,4.
- The minimum geometric properties required in order to provide rotational constraint to the end of the deck transverse in way:

$$Z_s = \frac{0,677S k P_s L_d^3}{\left(\left(\frac{I_d}{I_s}\right) L_s + L_d\right)} \text{ cm}^3$$

but is not to be less than  $0,339S k P_s L_d^2 \text{ cm}^3$

$$I_s \text{ is not to be less than } I_d \left(\frac{L_s}{L_d}\right) \left(\frac{Z_{dR}}{Z_d}\right) \text{ cm}^4$$

where

- $P_s$  = deck design loading, in kN/m<sup>2</sup>, see Table 2.3.1  
 $L_d$  = span of adjacent deck transverse, in metres  
 $Z_d$  = actual modulus of adjacent deck transverse, in cm<sup>3</sup>  
 $Z_{dR}$  = Rule modulus of adjacent deck transverse, in cm<sup>3</sup>  
 $I_d$  = moment of inertia of adjacent deck transverse, in cm<sup>4</sup>  
 $L_s$  = span of side shell transverse, in metres  
 $I_s$  = moment of inertia of side shell transverse, in cm<sup>4</sup>  
 $S, k$  = as defined in 1.5.1


Due account should be taken of the shell window dimensions when determining the effective width of attached plating.

5.1.3 The required modulus of transverse main and 'tween deck frames, which may have reasonably constant convex curvature over their entire length, may be corrected for curvature as follows:

$$Z_{min} = Z_{rule} \left( \frac{1}{\cosh \left( \frac{2\pi Y_c}{l_e} \right)} \right)^3 \text{ cm}^3$$

where

- $Z_{rule}$  = modulus requirement, in cm<sup>3</sup>, from Pt 4, Ch 1 using  $l_e$   
 $l_e$  = distance between span support points, in metres, as shown in Fig. 2.5.1  
 $Y_c$  = curvature measured from a line intersecting the end support points to the frame at mid-span, in metres, as shown in Fig. 2.5.1  
 $Z_{min}$  = is not to be less than  $0,5Z_{rule}$ .



5.1.4 Where ramp openings are fitted adjacent to the ship's side, adequate support for the side framing is to be provided.

5.1.5 Where bulkheads are omitted as indicated by 1.2.3, the strength of the structure is to be verified by direct calculation. The direct calculation procedure is to be agreed with LR.



# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 5

### 5.2 Strengthening for wave impact loads

5.2.1 The side structure in the forward and after portions of the hull is to be strengthened against bow flare or wave impact pressure. Typically, strengthening is to be considered over the following areas:

- over the after body in way of a flat counter stern which is close to the waterline.
- over the fore end side and bow structure above the waterline and up to the deck at side.
- other areas where the hull exhibits significant flare.

5.2.2 The scantlings of secondary stiffeners are not to be less than:

(a) Effective plastic section modulus of stiffeners:

$$Z_p = 3,75 h_s s_{cm} k l_e^2 \times 10^{-3} \text{ cm}^3$$

where

$h_s$  = wave impact head, in metres, as defined in 4.3.2

$s_{cm}$  = mean spacing of secondary stiffeners, in mm, measured along a chord between parallel adjacent members or equivalent supports, as shown in Fig. 2.4.2

Other symbols are as defined in 1.5.2.

(b) Web area of secondary stiffeners

$$A = 3,7 s_{cm} k h_s \left( l_e - \frac{s_{cm}}{2000} \right) \times 10^{-4} \text{ cm}^2$$

where

$s_{cm}$  = mean spacing of secondary stiffeners, in mm, measured along a chord between parallel adjacent members or equivalent supports, as shown in Fig. 2.4.2

$h_s$  = wave impact head, in metres, as defined in 4.3.2

Other symbols are as defined in 1.5.2.

5.2.3 The effective section properties of secondary stiffeners are to be taken as:

(a) Plastic section modulus of secondary stiffeners,  $Z_p$ , is to be taken as:

$$Z_p = 2,8 \times 10^{-4} s_{cm} t_p^2 - 10^{-3} b_f b_{fc} t_f \sin \theta_e + 5 \times 10^{-4} (h_w^2 t_w + 2 b_f t_f h_w) \cos \theta_e \text{ cm}^3$$

where

$\theta_e = C_0 (90 - \varphi)$

$C_0 = 1,1$

$\varphi$  = the angle between the stiffener and the side shell, in degrees

$b_{fc} = 0,5 (b_f - t_w)$  for L profiles

= 0 for flat bar and T profiles

= see Fig. 4.7.1 in Pt 3, Ch 4, for bulb profiles

$h_w$  = height of stiffener, in mm

$t_w$  = web thickness, in mm

$b_f$  = breadth of flange, in mm

$t_f$  = flange thickness, in mm

$t_p$  = thickness of attached plating, in mm

(b) Web area of secondary stiffeners,  $A_s$ , is to be taken as:

$$A_s = 0,01 (h_w + t_p) t_w \sin \varphi \text{ cm}^2$$

5.2.4 Where the stiffener web is not perpendicular to the plating, tripping brackets have to be fitted in order to obtain adequate lateral stability.

5.2.5 The scantlings of primary members are not to be less than:

(a) Section modulus of primary members

$$Z = 2 \gamma_z k h_s q v l_e^2 \text{ cm}^3$$

(b) Web area of primary members

$$A = 0,2 \gamma_A k h_s q v l_e \text{ cm}^2$$

where

$h_s$  = wave impact head, in metres, as defined in 4.3.2 and

$\gamma_A$  and  $\gamma_z$  are strength factors dependent on the load position for  $q < 1$   $\gamma_A = q^3 - 2q^2 + 2$  and  $\gamma_z = 3q^3 - 8q^2 + 6q$

for  $q = 1$   $\gamma_A = 1$  and  $\gamma_z = 1$

$$q = \frac{u}{l_e} \text{ but } \leq 1$$

for web frames:

$u$  is the minimum of  $g_{bfv}$  or  $l_e$

$v$  is the minimum of  $g_{bth}$  or  $s_{cm}$

for primary stringers:

$u$  is the minimum of  $g_{bth}$  or  $l_e$

$v$  is the minimum of  $g_{bfv}$  or  $s_{cm}$

where


$l_e$  is the effective length of the primary member, in metres

$s_{cm}$  is the mean spacing between primary members along the plating, in metres, see Fig. 2.5.2

$g_{bfv}$  and  $g_{bth}$  are defined in 5.2.6

Other symbols are as defined in 1.5.2.

(c) The web of the primary member is to be adequately stiffened



**Fig. 2.5.2**  
Mean spacing between primary members,  $S_{cm}$ , and the extents of wave impact pressure  $g_{bth}$  and  $g_{bfv}$

# Ferries, Roll on-Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 5 & 6

5.2.6 The extents of the wave impact pressure are to be derived as follows:

(a) the vertical extent,  $g_{bfv}$ , is to be taken as:

$$g_{bfv} = \frac{4}{\sin \beta_p \sqrt{8K_{bf}}} \text{ m}$$

(b) the horizontal extent,  $g_{bfh}$ , is to be taken as:

$$g_{bfh} = 4 \text{ m}$$

where

$K_{bf}$  and  $\beta_p$  are given in 4.2.1.

5.2.7 For primary members with cut-outs for the passage of secondary stiffeners, and which may have web stiffeners connected to the secondary stiffener, buckling checks are to be carried out to ensure that the primary member web plating and web stiffener will not buckle under the design load. The buckling procedure to be followed is given in Table 5.1.3 in Pt 3, Ch 5. Where the web stiffener is fitted with a bracket, the buckling capability of the web stiffener in way of the cut-out is to take account of the bracket. Where no web stiffener is fitted, the buckling capability of the primary member web plating is to be checked for the total load transmitted to the connection.

5.2.8 Where the angle between the primary structure web and the plating is less than 70°, the effective section modulus and shear area are to take account of the non-perpendicularity.

5.2.9 The structural scantlings required in areas strengthened against bow flare slamming are to be tapered to meet the normal shell envelope requirements.

5.2.10 The side structure scantlings required by this Section must in no case be taken less than those required by the remaining Sections of Chapter 2.

(e) Subject to the provisions stipulated in the relevant Regulations of the *International Convention for the Safety of Life at Sea, 1974* including the 1981 amendments, any deviations from the above requirements will be specially considered.

6.1.2 Where a double bottom as required by 6.1.1 is fitted, its depth is to be compatible with the requirements of Ch 1,8 and the inner bottom is to be continued out to the ship's sides in such a manner as to protect the bottom to the turn of bilge. Such protection will be deemed satisfactory if the line of intersection of the outer edge of the margin plate with the bilge plating is not lower at any part than a horizontal plane passing through the point of intersection with the frame line amidships of a transverse diagonal line inclined at 25° to the base line and cutting it at a point one-half the ship's moulded breadth from the middle line, see Fig. 2.6.1.




Fig. 2.6.1 Inner bottom and well position

## Section 6 Double bottom

### 6.1 General

6.1.1 In passenger ships (see 1.1) a double bottom is to be fitted extending from the forepeak bulkhead to the afterpeak bulkhead as far as this is practicable and compatible with the design and proper working of the ship, however:

- (a) In ships of 50 m and upwards but less than 61 m in length a double bottom is to be fitted at least from the machinery space to the forepeak bulkhead, or as near thereto as practicable.
- (b) In ships of 61 m and upwards but less than 76 m in length a double bottom is to be fitted at least outside the machinery space, and is to extend to the fore and after peak bulkheads, or as near thereto as practicable.
- (c) In ships of 76 m in length and upwards, a double bottom is to be fitted amidships, and is to extend to the fore and after peak bulkheads, or as near thereto as practicable.
- (d) A double bottom need not be fitted in way of watertight compartments of moderate size used exclusively for the carriage of liquids, provided the safety of the ship, in the event of bottom or side damage, is not impaired.

6.1.3 Small wells constructed in the double bottom in conjunction with drainage arrangements of holds, etc., are not to extend downwards more than necessary. The depth of the wells is to be at least 460 mm less than the depth of the double bottom at the centreline, and the well is not to extend below the horizontal plane referred to in 6.1.2. A well extending to the outer bottom is, however, permitted at the after end of the shaft tunnel. Other well arrangements (e.g. for lubricating oil under main engines) will be considered provided they give protection equivalent to that afforded by the double bottom.

6.1.4 Where podded drive systems are to be employed, adequate floors and girders are to be arranged in order to efficiently integrate the unit into the aft structure. The adequacy of the hull structure supporting the unit is to be verified using the maximum external forces and moments stated by the manufacturer. Due account is to be taken of additional forces induced by ship motion accelerations.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 6, 7 & 8

### 6.2 Transmission of pillar loads

6.2.1 In ships where the deck centreline supports are widely spaced, transmission of the pillar loads to the double bottom structure will be specially considered, and additional reinforcement may be required if high shear and bending stresses are induced by the concentrated loads. The reinforcement should take the form of additional floors, and fore and aft girders. The final reinforcement is to be confirmed by direct calculation.

6.2.2 Where, in multi-decked passenger ships, the rule deck loadings from Table 2.3.1 have been used to determine the primary deck supporting structure, the cumulative pillar load  $P_p$  may be taken as:

$$P_p = \Sigma (b_p S_p) P_s \quad \text{kN}$$

where

- $b_p$  = breadth of deck supported by pillar
- $S_p$  = mean spacing between pillars
- $P_s$  see Table 2.3.1.

6.2.3 Pillars are to be provided with suitable pads at their heels. Long pillars, and those terminating at the inner bottom are to be bracketed. At pillar heads, the free edges of deck primary structure face plates are to be at least 20 mm clear of the pillar head attachment weld. Where necessary, gusset plates are to be fitted at primary member intersections in way of pillars. These gussets may be applied as doublers onto the primary member face plates and should be at least equal in thickness to the pillar or the face plate, whichever is greater. Where pillars act in tension, the gussets are to be integral with the primary member face plates. The axial stress in tensile pillars is not to exceed 110/k N/mm<sup>2</sup> and full penetration welds are to be arranged in way of the end connections.

### 6.3 Ferries and passenger ships with a specified operating area service

6.3.1 The thickness of double bottom centre girders may be reduced by 10 per cent, and the thickness of double bottom side girders and floors may be reduced by five per cent, from the values required by Ch 1,8, but is in no case to be less than 6 mm.

## Section 7 Peak, watertight and deep tank bulkheads

### 7.1 General

7.1.1 The scantlings of watertight and deep tank bulkheads are to comply with the requirements of Pt 4, Ch 1.

7.1.2 The load head,  $h_4$  to be used in watertight bulkhead scantlings for passenger ships is, in addition, to comply with the following:

- For watertight bulkhead plating, the distance from a point one-third of the height of the plate above its lower edge to a point 0,91 m above the bulkhead deck at side, or to the deepest intermediate/equilibrium waterline in damaged condition obtained from applicable damage stability calculations, whichever is the greater.
- For watertight bulkhead stiffeners or girders, the distance from the middle of the effective length to a point 0,91 m above the bulkhead deck at side, or to the deepest intermediate/equilibrium waterline in damaged condition obtained from applicable damage stability calculations, whichever is the greater.

7.1.3 Partial watertight bulkheads and webs fitted above the bulkhead deck which are to be included in damage stability calculations, are to be assessed as watertight, see 7.1.2.

### 7.2 Ferries and passenger ships with a specified operating area service

7.2.1 The thickness of bulkhead plating for peak tanks and deep tanks, other than the collision bulkhead, may be reduced by 0,5 mm, and the modulus of bulkhead stiffeners, swedges, corrugations and girders may, in general, be reduced by 20 per cent from the values required by Ch 1,9.

## Section 8 Bow doors and inner doors

### 8.1 Symbols

8.1.1 The symbols used in this Section are defined as follows:

- $a$  = vertical distance, in metres, from the bow door pivot to the centroid of the vertical projected area of bow door, see Fig. 2.8.1
- $b$  = horizontal distance, in metres, from the bow door pivot to the centroid of the horizontal projected area of the bow door, see Fig. 2.8.1
- $c$  = horizontal distance, in metres, from bow door pivot to centre of gravity of bow door, see Fig. 2.8.1
- $d$  = vertical distance, in metres, from bow door pivot to the centre of gravity of the bow door, see Fig. 2.8.1
- $h$  = height of the door, in metres, between the levels of the bottom of the door and the upper deck or between the bottom of the door and the top of the door, whichever is the lesser, see Fig. 2.8.2
- $k$  = material factor (see Pt 3, Ch 2,1.2), but is not to be taken less than 0,72 unless demonstrated otherwise by a direct strength analysis with regard to relevant modes of failure
- $l$  = projected length, in metres, of the door at a height of  $\frac{h}{2}$  above the bottom of the door, see Fig. 2.8.2
- $w$  = width of bow door at half height, in metres

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 8

$A_z$  = area, in  $m^2$ , of the horizontal projection of the bow door, between the bottom of the door and the top of the upper deck bulwark, or between the bottom of the door and the top of the door, including the bulwark, where it is part of the door, whichever is the lesser, see Fig. 2.8.1. Where the flare angle of the bulwark is at least 15 degrees less than the flare angle of the adjacent shell plating, the height from the bottom of the door may be measured to the upper deck or to the top of the door, whichever is the lesser.

$A_s$  = area of stiffener web, in  $cm^2$

$A_x$  = area, in  $m^2$ , of the transverse vertical projection of the bow door, between the bottom of the door and the top of the door or between the bottom of the door and the upper deck bulwark, or between the bottom of the door and the top of the door, including the bulwark, where it is part of the door, whichever is the lesser, see Fig. 2.8.1. Where the flare angle of the bulwark is at least 15 degrees less than the flare angle of the adjacent shell plating, the height from the bottom of the door may be measured to the upper deck or to the top of the door, whichever is lesser. In determining the height from the bottom of the door to the upper deck or to the top of the door, the bulwark is to be excluded.

$A_y$  = area, in  $m^2$ , of the longitudinal vertical projection of the bow door, between the bottom of the door and the top of the upper deck bulwark, or between the bottom of the door and the top of the door, including the bulwark, where it is part of the door, whichever is the lesser, see Fig. 2.8.1. Where the flare angle of the bulwark is at least 15 degrees less than the flare angle of the adjacent shell plating, the height from the bottom of the door may be measured to the upper deck or to the top of the door, whichever is the lesser.

$W$  = weight of bow visor, in tonnes

$q$  = distance, in metres, from the centroid of the hydrostatic head profile, to the top of the cargo space

$C_H$  = 0,0125 $L$  where  $L < 80$  m

= 1,0 where  $L \geq 80$  m

$L$  = length of ship, but need not be taken greater than 200 m

$V$  as defined in 1.5.1

$\lambda$  = coefficient depending on the area where the ship is intended to be operated

= 1,0 for seagoing ships

= 0,8 for ships operated in coastal waters

= 0,5 for ships operated in sheltered waters

$\sigma$  = bending stress, in  $N/mm^2$  ( $kgf/mm^2$ )

$\sigma_e$  = equivalent stress, in  $N/mm^2$  ( $kgf/mm^2$ )

=  $\sqrt{\sigma^2 + 3\tau^2}$

$\sigma_y$  = yield stress of the bearing material, in  $N/mm^2$  ( $kgf/mm^2$ )

$\tau$  = shear stress, in  $N/mm^2$  ( $kgf/mm^2$ ).




Fig. 2.8.1 Bow door (upward hinging)




Fig. 2.8.2 Definition of  $\alpha$  and  $\beta$

### 8.2 General

8.2.1 Bow doors are defined by the following types:

- Visor doors opened by rotating upwards and outwards about a horizontal axis through two or more hinges located near the top of the door and connected to the primary structure of the door by longitudinally arranged lifting arms.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 8

- (b) Side-opening doors opened either by rotating outwards about a vertical axis through two or more hinges located near the outboard edges or by horizontal translation by means of linking arms arranged with pivoted attachments to the door and the ship. It is expected that side-opening bow doors will be arranged in pairs.

Other bow door types will be specially considered.

8.2.2 Bow doors are to be situated above the freeboard deck. A watertight recess in the freeboard deck located forward of the collision bulkhead and above the deepest waterline, fitted for arrangement of ramps or other related mechanical devices, may be regarded as a part of the freeboard deck for the purpose of this requirement.

8.2.3 Where bow doors lead to a complete or long forward enclosed superstructure, or to a long non-enclosed superstructure which is fitted to attain minimum bow height equivalence, an inner door is to be fitted. The inner door is to be part of the collision bulkhead. Where a sloping vehicle ramp forming the collision bulkhead above the freeboard deck is arranged, the inner door may be omitted if the ramp is weathertight over its complete length and fulfils the requirements of Pt 3, Ch 3 concerning the position of the collision bulkhead.

8.2.4 Bow doors are to be fitted with arrangement for ensuring weathertight sealing, such as gaskets, and to give effective protection to inner doors.

8.2.5 Inner doors forming part of the collision bulkhead are to be watertight over the full height of the cargo space and arranged with fixed sealing supports on the aft side of the doors.

8.2.6 Bow doors and inner doors are to be arranged so as to preclude the possibility of the bow door causing structural damage to the inner door or to the collision bulkhead in the case of damage to or detachment of the bow door. If this is not possible, a second separate inner weather-tight door, complying with 8.2.5, is to be installed.

8.2.7 The requirements for inner doors are based on the assumption that vehicles and cargo are effectively lashed and secured against movement from the stowed position.

8.2.8 For ships complying with the requirements of this Section, the securing, supporting and locking devices are defined as follows:

- A securing device is used to keep the door closed by preventing it from rotating about its hinges.
- A supporting device is used to transmit external and internal loads from the door to a securing device and from the securing device to the ship's structure, or a device other than a securing device, such as a hinge, stopper or other fixed device, that transmits loads from the door to the ship's structure.
- A locking device locks a securing device in the closed position.

8.2.9 The scantlings and arrangements of side shell and stern doors are to be in accordance with the requirements of Pt 3, Ch 11,8.

### 8.3 Scantlings

8.3.1 The strength of the bow door is to be equivalent to the surrounding structure, as given in Pt 3, Ch 5,6.

8.3.2 For bow doors, including bulwark, of unusual form or proportions, the areas and angles used for the determination of design values of external forces are to be specially considered.

8.3.3 Bow doors of the visor or hinged opening type are to be adequately stiffened, and means are to be provided to prevent lateral or vertical movement of the doors when closed. Care is to be taken to ensure that adequate strength is provided in the connections of the hinge or linking arms to the door structure and to the ship structure.

8.3.4 The thickness of the bow door plating is not to be less than the side shell plating calculated with the door stiffener spacing, and in no case to be less than the minimum shell plate end thickness or forecastle side thickness as appropriate.

8.3.5 The section modulus of horizontal or vertical stiffeners is not to be less than required for end framing. Consideration is to be given, where necessary, to differences in fixity between ship frames and bow door stiffeners.

8.3.6 The stiffener webs are to have a net sectional area not less than:

$$A_s = \frac{10Q}{\tau} \text{ cm}^2$$

$\tau$  is to be taken as  $\frac{100}{k} \text{ N/mm}^2$   $\left( \frac{10,2}{k} \text{ kgf/mm}^2 \right)$

where

$Q$  = shear force, in kN (tonne-f) calculated using the uniformly distributed external sea pressure,  $p_e$ , defined in 8.5.15.

8.3.7 Bow door secondary stiffeners are to be supported by primary members constituting the main stiffening elements of the door.

8.3.8 The scantlings of such primary members are to be based on direct strength calculations. Normally, formulae for simple beam theory may be applied to determine the bending stress. Members are to be considered to have simply supported end connections. The design load,  $P_e$ , is the uniformly distributed external sea pressure. The formulae for  $P_e$  given in 8.6.1, may be used with  $\alpha$  and  $\beta$  defined as:

$\alpha$  = flare angle, in degrees, generally to be measured normal to the shell between the vertical axis and the vertical tangent to the outer shell of the door measured at the point on the bow door, one half of the projected length ( $l/2$ ) aft of the stern line on the plane at the half height of the door ( $h/2$ ) (see Fig. 2.8.2)

$\beta$  = entry angle, in degrees, generally to be measured on the outer shell of the door between the longitudinal axis and the waterplane tangent measured at the point on the bow door, one half of the projected length ( $l/2$ ) aft of the stem line on the plane at the half height of the door ( $h/2$ ) (see Fig. 2.8.2)

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 8

The permissible stresses are as follows:

$$\tau = \frac{80}{k} \text{ N/mm}^2 \quad \left( \frac{8,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma = \frac{120}{k} \text{ N/mm}^2 \quad \left( \frac{12,2}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma_e = \frac{150}{k} \text{ N/mm}^2 \quad \left( \frac{15,3}{k} \text{ kgf/mm}^2 \right)$$

8.3.9 The webs of primary members are to be adequately stiffened, preferably in a direction perpendicular to the shell plating.

8.3.10 The primary members of the bow doors and hull structure in way are to have sufficient stiffness to ensure the integrity of the boundary support of the doors.

8.3.11 All load transmitting elements in the design load path, from door through securing arrangements and supporting devices into the ship structure, including welded connections, are to be to the same strength standard. These elements include pins, supporting brackets and back-up brackets. Where cut-outs are made in the supporting structure, the strength and stiffness will be specially considered.

8.3.12 For bow doors and inner doors, the distribution of forces acting on the securing devices and the supporting devices is to be supported by direct calculations taking into account the flexibility of the structure and the actual position and stiffness of the supports.

8.3.13 The buckling strength of primary members is to be specially considered.

### 8.4 Vehicle ramps

8.4.1 Where doors also serve as vehicle ramps, the scantlings are to be not less than would be required by 3.2.2 and 3.3.2 and where they form part of the collision bulkhead the arrangement is to be in accordance with Pt 3, Ch 3,4.5.

### 8.5 Arrangements for the closing, securing and supporting of doors

8.5.1 Bow doors are to be fitted with adequate means of closing, securing and supporting so as to be commensurate with the strength and stiffness of the surrounding structure. The hull supporting structure in way of the bow doors is to be suitable for the same design loads and design stresses as the securing and supporting devices. Where packing is required, the packing material is to be of a comparatively soft type, and the supporting forces are to be carried by the steel structure only. Maximum design clearance between securing and supporting devices is not to exceed 3 mm.

8.5.2 Securing devices are to be simple to operate and easily accessible. They are to be of a design approved by LR for the intended purpose.

8.5.3 Securing devices are to be equipped with positive locking arrangements. Arrangements are to be such that the devices are retained in the closed position within design limits of inclination, vibration and other motion-induced loads and in the event of loss of any actuating power supply.

8.5.4 Systems for door opening/closing and securing/locking are to be interlocked in such a way that they can only operate in a proper sequence. Hydraulic systems are to comply with Pt 5, Ch 14,9.

8.5.5 Means are to be provided to enable the bow doors to be mechanically fixed in the open position taking into account the self weight of the door and a minimum wind pressure of 1,5 kN/m<sup>2</sup> (0,153 tonne-f/m<sup>2</sup>) acting on the maximum projected area in the open position.

8.5.6 The spacing for side and top cleats should not exceed 2,5 m and there should be cleats positioned as close to the corners as practicable. Alternative arrangements for ensuring weathertight sealing will be specially considered.

8.5.7 Control and monitoring arrangements are to comply with Pt 6, Ch 2,18.

### 8.6 Design of securing and supporting devices

8.6.1 The external design forces for securing devices, supporting devices and surrounding structure are to be taken not less than  $P$ , taking the direction of the pressure into account:

$$P_x = A_x p_e$$

$$P_y = A_y p_e$$

$$P_z = A_z p_e$$

where

$p_e$  = external sea pressure, not to be taken less than:

(a) For bow doors:

$$p_e = 0,8 (0,15V + 0,6 \sqrt{L})^2 \text{ kN/m}^2$$

$$(0,082 (0,15V + 0,6 \sqrt{L})^2 \text{ tonne-f/m}^2)$$

or

$$p_e = 2,75\lambda C_H (0,22 + 0,15 \tan \alpha) (0,4V \sin \beta +$$

$$0,6 \sqrt{L})^2 \text{ kN/m}^2$$

or

$$(0,28\lambda C_H (0,22 + 0,15 \tan \alpha) (0,4V \sin \beta +$$

$$0,6 \sqrt{L})^2 \text{ tonne-f/m}^2)$$

whichever is the greater.

(b) For inner doors:

$$p_e = 0,45L \text{ kN/m}^2$$

$$(0,046L \text{ tonne-f/m}^2)$$

or

$$p_e = 10q \text{ kN/m}^2$$

$$(1,02q \text{ tonne-f/m}^2)$$

whichever is the greater

The symbols are as defined in 8.1.1

8.6.2 The inner door internal design pressure, considered for the scantlings of securing devices, is not to be less than 25 kN/m<sup>2</sup> (2,5 tonne-f/m<sup>2</sup>).

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 8

8.6.3 For visor doors, the pivot arrangement is to be such that the visor is self closing under external loads. The closing moment,  $M_c$ , is to be taken as:

$$M_c = P_x a + 10Wc - P_z b \quad \text{kN m} \\ (P_x a + 1,02Wc - P_z b \quad \text{tonne-f m})$$

but is not to be less than:

$$M_c = 10Wc + 0,1 \sqrt{(a^2 + b^2) (P_x^2 + P_z^2)} \quad \text{kN m} \\ (1,02Wc + 0,1 \sqrt{(a^2 + b^2) (P_x^2 + P_z^2)} \quad \text{tonne-f m})$$

8.6.4 For visor doors, two securing devices are to be provided at the lower part of the door, each capable of providing the full reaction force required to prevent opening of the door within the permissible stresses given in 8.6.7. The opening moment  $M_o$ , to be balanced by this reaction force, is to be taken as not less than:

$$M_o = 10Wd + 5A_x a \quad \text{kN m} \\ (1,02Wd + 0,51A_x a \quad \text{tonne-f m})$$

8.6.5 For visor type doors, the securing and supporting devices, excluding hinges, are to be capable of resisting the vertical design force  $(P_z - 10W)$  kN  $((P_z - 1,02W)$  tonne-f), within the permissible stresses given in 8.6.7.

8.6.6 For side-opening doors, securing devices are to be provided such that in the event of a failure of any single securing device the remainder are capable of providing the full reaction force required to prevent the opening of the door. The permissible stresses given in 8.6.7 are not to be exceeded. The opening moment about the hinges to be balanced by this reaction force is not to be less than that calculated when the following loads are applied:

- An internal pressure of 5 kN/m<sup>2</sup> (0,51 tonne-f/m<sup>2</sup>).
- A force of 10W kN (1,02W tonne-f) acting forward at the centroid of mass.

8.6.7 Securing devices and supporting devices are to be designed to withstand the forces given above using the following permissible stresses:

$$\tau = \frac{80}{k} \quad \text{N/mm}^2 \quad \left( \frac{8,2}{k} \quad \text{kgf/mm}^2 \right)$$

$$\sigma_e = \frac{120}{k} \quad \text{N/mm}^2 \quad \left( \frac{12,2}{k} \quad \text{kgf/mm}^2 \right)$$

$$\sigma_e = \frac{150}{k} \quad \text{N/mm}^2 \quad \left( \frac{15,3}{k} \quad \text{kgf/mm}^2 \right)$$

8.6.8 The arrangement of securing and supporting devices is to be such that threaded bolts are not to carry support forces. The maximum tensile stress in way of threads of bolts, not carrying support forces, is not to exceed:

$$\frac{125}{k} \quad \text{N/mm}^2 \quad \left( \frac{12,7}{k} \quad \text{kgf/mm}^2 \right).$$

8.6.9 For steel to steel bearings in securing and supporting devices, the nominal bearing pressure is not to exceed  $0,8\sigma_y$ . For other bearing materials, the permissible bearing pressure is to be determined according to the manufacturer's specification. The nominal bearing pressure is to be calculated by dividing the design force by the projected bearing area.

8.6.10 The reaction forces to be applied to the effective securing and supporting devices, are to be determined from the combination of external loads defined in Table 2.8.1.

**Table 2.8.1 Combination of external loads**

Bow door type	Combination of external loads	
	Case 1 (Head seas)	Case 2 (Quarterming seas)
Visor doors, see Notes 1 and 2	$P_x$ and $P_z$ , see Note 3	$0,7P_y$ acting on each side separately, together with $0,7P_x$ and $0,7P_z$
Side opening, see Notes 1 and 2	$P_x$ , $P_y$ and $P_z$ acting on both doors, see Note 3	$0,7P_x$ and $0,7P_z$ acting on both doors and $0,7P_y$ acting on each door separately
<b>NOTES</b> 1. $P_x$ , $P_y$ and $P_z$ are defined in 8.5.15. These forces are to be applied at the centroid of the projected areas. 2. The self weight of the door is to be included in the combination of external loads. 3. The Case 1 forces are generally to give rise to a zero moment about the transverse axis through the centroid of area $A_v$ , see Fig. 2.8.1.		

8.6.11 The distribution of the reaction forces acting on the securing and supporting devices is to be supported by direct calculations taking into account the flexibility of the hull structure and the actual position and stiffness of the supports. Small and/or flexible devices, such as cleats, intended to provide load compression of the packing material are not to be included in these calculations.

8.6.12 The hinge or linking arms of a bow door and its supports are to be designed for the static and dynamic opening forces. A minimum wind pressure of 1,5 kN/m<sup>2</sup> (0,153 tonne-f/m<sup>2</sup>), acting on the transverse projected area of the door is to be taken into account.

8.6.13 For side-opening doors, supporting devices are to be provided in way of girder ends at the closing of the two doors to prevent one side shifting towards the other under the effect of asymmetrical pressure. A typical arrangement is shown in Fig. 2.8.3.

8.6.14 Inner doors are to be gasketed and weathertight.


8.6.15 Only the active supporting and securing devices having an effective stiffness in the relevant direction are to be included and considered to calculate the reaction forces acting on the devices.

8.6.16 The number of securing and supporting devices is to be the minimum practicable whilst complying with 8.6.4 and 8.6.17 and taking account of the available space for adequate support in the hull structure.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 8 & 9



**Fig. 2.8.3**  
**Typical supporting device between doors**

8.6.17 The arrangement of securing devices and supporting devices in way of these securing devices is to be designed with redundancy so that in the event of failure of any single securing or supporting device the remaining devices are capable of withstanding the reaction forces, resulting from the external loads defined in Table 2.8.1, without exceeding, by more than 20 per cent, the permissible stresses as defined in 8.6.7.

### 8.7 Operating and Maintenance Manual

8.7.1 An Operating and Maintenance Manual for the bow doors and inner doors is to be provided on board and is to contain the following information:

- (a) main particulars and design drawings,
  - special safety precautions;
  - details of vessel, class and statutory certificates;
  - equipment and design loading for ramps;
  - key plan of equipment for doors and ramps;
  - manufacturers' recommended testing for equipment; and
  - a description of the following equipment:
    - bow doors;
    - inner bow doors;
    - bow ramp/doors;
    - side doors;
    - stern doors;
    - central power pack;
    - bridge panel;
    - ramps leading down from the main deck engine control room panel.
- (b) service conditions:
  - limiting heel and trim of the ship for loading/unloading;
  - limiting heel and trim for door operations;
  - operating instructions for doors and ramps; and
  - emergency operating instructions for doors and ramps.

- (c) maintenance:
  - schedule and extent of maintenance;
  - trouble shooting and acceptable clearances; and
  - manufacturers' maintenance procedures.
- (d) register of inspections, including inspection of locking, securing and supporting devices, repairs and renewals.

This Manual is to be submitted for approval, and is to contain a note recommending that recorded inspections of the door supporting and securing devices be carried out by the ship's staff at monthly intervals or following incidents that could result in damage, including heavy weather or contact in the region of the doors. Any damages recorded during such inspections are to be reported to LR.

8.7.2 Documented operating procedures for closing and securing the bow doors and inner doors are to be kept on board and posted at an appropriate place.

## Section 9 Subdivision structure on vehicle deck

### 9.1 General

9.1.1 The requirements of this Section cover subdivision structure fitted on the vehicle deck(s) of roll on–roll off passenger ships. Subdivision structure includes partition doors, bulk-heads and longitudinal casings.

9.1.2 Where a ship is provided with subdivision structure that complies with the requirements of this Section, the ship will be eligible to be assigned the descriptive note **SSDS** which will be entered in column 6 of the *Register Book*.

9.1.3 The fitting of subdivision structure on the vehicle deck(s) forms one option to mitigate the stability-reducing effects of water on the vehicle deck(s) after damage. Such measures may be required by the National Administration with whom the ship is registered and/or by the National Administration within whose territorial jurisdiction the ship is intended to operate, for example see The Stockholm Agreement.

### 9.2 Design loads

9.2.1 For calculation of the design loads, an equivalent depth of water on the first vehicle deck above the design waterline,  $d$ , in metres, is to be derived in accordance with the requirements of the National Administration, see 9.1.3.

9.2.2 It is assumed that vehicles and cargo are effectively lashed and secured to prevent movement from the stowed position.



# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 9

9.2.3 The design heads (see Fig. 2.9.1) are not to be taken less than the greater of 0,5 m and:

- (a) For transverse structure more than 1,5 m away from the longitudinal boundaries of the compartment:

$$h_T = 1,4 \sqrt{L_c d K} \text{ in metres, for } z < 1$$

$$= 1,4 \sqrt{L_c d K} \left( 1 - \frac{(z-1)}{1,4 \sqrt{L_c d K} - 1} \right) \text{ in metres, for } z \geq 1$$

Symbols are as defined in 9.2.4.

- (b) For longitudinal structure more than  $L_c/6$  away from the transverse boundaries of the compartment:

$$h_L = \sqrt{B_c d} \text{ in metres, for } z < 1$$

$$= \sqrt{B_c d} \left( 1 - \frac{z-1}{(1,4 \sqrt{B_c d} - 1)} \right) \text{ in metres, for } z \geq 1$$

Symbols are as defined in 9.2.4.

- (c) For structure elsewhere:

$$h_c = \frac{L_c K}{2} + \sqrt{R} \text{ in metres, for } z < 1$$

$$= \left( \frac{L_c K}{2} + \sqrt{R} \right) \left( 1 - \frac{(z-1)}{1,4 \left( \frac{L_c K}{2} + R \right) - 1} \right) \text{ in metres, for } z \geq 1$$

Symbols are as defined in 9.2.4.

$z$  = vertical distance, between the point under consideration and the flooded vehicle deck, in metres. For plate panels the point under consideration is to be taken as one third of the panel height above its lower edge. For stiffeners the point under consideration is to be taken as the midspan of the effective length

$B_c$  = breadth of compartment, in metres, see Fig. 2.9.1

$K$  =  $0,21e^{(-0,0033L_{pp})}$  and need not exceed 0,14

$L_c$  = length of compartment, in metres, see Fig. 2.9.1

$R = B_c d - \frac{L_c^2 K^2}{12}$  and is not to be taken less than 0

$e$  = base of natural logarithms, 2,7183

$L_{pp}$  = as defined in Pt 3, Ch 1,6.

9.2.5 The design heads calculated in 9.2.3 are based on the ship being in the upright condition. Where the actual damaged floating position is specified, the design heads will be specially considered taking this into account.

9.2.6 The subdivision structure, and access doors within the subdivision structure, are to be capable of withstanding the design loading applied from the side of the compartment under consideration.

9.2.7 Consideration will be given to the use of design heads agreed by the National Administration.

### 9.3 Height of subdivision structure

9.3.1 The height of the subdivision structure,  $H_D$ , is not to be less than:

- 4 m, or
- $8d$ , but not less than 2,2 m, or
- the height between the vehicle deck under consideration and the underside of the next watertight deck above, whichever is the lesser

where

$d$  = as defined in 9.2.4.

9.3.2 For special arrangements, such as hanging car decks or wide side casings, other subdivision structure heights may be accepted on the basis of detailed model tests in the flooded conditions under investigation by the National Administration.

### 9.4 Material

9.4.1 Where materials other than steel are used, the scantlings are to be specially considered.

### 9.5 Scantlings of subdivision structure other than doors

9.5.1 The minimum scantlings of subdivision bulkheads and casings are to be derived in accordance with Table 1.9.1 in Chapter 1 for watertight bulkheads, where  $h_4$  is to be substituted by either of  $h_T$ ,  $h_L$  or  $h_c$ , depending on the location under consideration.




Fig. 2.9.1

Design heads for different locations in compartment

9.2.4 Symbols, as used in 9.2.3, are defined as follows:

$d$  = equivalent depth of water on the vehicle deck, in metres, in the upright condition taking into account the volume of flooded and accumulated water on the vehicle deck calculated in accordance with the requirements of the National Administration, see 9.1.3 and 9.2.1

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 9

9.5.2 Where a cut-out is made in the subdivision structure for the fitting of an access door, the strength and integrity of the subdivision structure are to be maintained.

### 9.6 Scantlings of subdivision doors

9.6.1 The plate thickness of subdivision doors of single plate construction is not to be less than the greater of:

$$t = 0,004s f (h k)^{0,5} \text{ mm, or}$$

$$t = 5,0 \text{ mm}$$

where

$$s, k = \text{as defined in 1.5.1}$$

$$f = \text{as defined in Table 1.9.1 in Chapter 1}$$

$$h = h_T, h_L \text{ or } h_C \text{ as defined in 9.2.3, as appropriate.}$$

9.6.2 For subdivision doors of a double plate construction the plate thickness is to be specially considered.

9.6.3 The scantlings of primary and secondary stiffeners of subdivision doors are to be based on direct strength calculations.

9.6.4 The direct strength calculations are also to provide an assessment of the door, under the design load, to enable the leakage and hence the drainage requirements of 9.9 to be assessed.

9.6.5 For the purpose of the direct strength calculations, the stresses induced in the subdivision door, determined using the design loads from 9.2, are not to exceed the permissible values given in Table 2.9.1. Checks are also to be carried out to ensure that the door will not buckle under the design loads.

**Table 2.9.1 Permissible stress values**

Stress type	Permissible stress
Direct stress	$\sigma_o$
Shear stress	$\frac{\sigma_o}{3}$
Combined stress	$\sigma_o$
Symbols	
$\sigma_o$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

9.6.6 Where a cut-out is made within the subdivision door for the fitting of an access door, the strength of the subdivision door is to be maintained.

### 9.7 Closing, securing and supporting of subdivision doors

9.7.1 The closing and securing devices of doors are to comply with the following requirements:

- (a) Securing devices are to be simple to operate and easily accessible. They are to be of a design approved by LR for the intended purpose.

- (b) Securing devices and supporting devices are to be designed to withstand the design loads calculated in 9.2.1 in association with the permissible stresses shown in Table 2.9.2.
- (c) The arrangement of securing and supporting devices is to be such that threaded bolts do not carry support forces. The maximum tensile stress in way of threads of bolts not carrying support forces is not to exceed  $0,5\sigma_o$ .
- (d) For steel to steel bearings in securing and supporting devices, the bearing pressure is not to exceed  $0,8\sigma_o$ . For other bearing materials, the permissible bearing pressure is to be determined according to the manufacturer's specification. The bearing pressure is to be calculated by dividing the design force by the projected bearing area.
- (e) Only the active supporting and securing devices having an effective stiffness in the relevant direction are to be included when calculating the reaction forces acting on the devices.
- (f) Securing devices are to be equipped with positive locking arrangements. Arrangements are to be such that the securing devices are retained in the closed position within design limits of inclination, vibration and other motion-induced loads and in the event of loss of any actuating power supply.
- (g) Hydraulic systems are to comply with Pt 5, Ch 14,9.
- (h) Control and monitoring arrangements are to comply with Pt 6, Ch 2,18.

**Table 2.9.2 Permissible stress values**

Stress type	Permissible stress
Direct stress	$0,8\sigma_o$
Shear stress	$0,5\sigma_o$
Combined stress	$0,8\sigma_o$
Symbols	
$\sigma_o$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

9.7.2 The reaction forces to be applied to the effective securing and supporting devices are to be determined using the applicable design loads calculated using the heads in 9.2 together with the weight of the door.

### 9.8 Access doors

9.8.1 Access doors are permitted to be fitted in subdivision doors or bulkheads in order to provide access between compartments.

9.8.2 Access doors may be manually operated.

9.8.3 The strength of access doors is to be not less than that of the surrounding structure.

9.8.4 Means are to be provided to ensure that access doors are closed and secured when not in use after the ship has left the berth.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 9 & 10

9.8.5 A notice is to be displayed on the access doors stating that the door is to be closed and secured at all times when not in use, when the ship is under way.

9.8.6 Means are to be provided on the navigation bridge to indicate whether the access doors are open or closed.

### 9.9 Watertightness and drainage

9.9.1 Subdivision doors and access doors are to be fitted with gaskets in order to minimize leakage. For access doors where down flooding could result, particular attention is to be paid to drainage requirements.

9.9.2 The gasket arrangement shall provide sufficient flexibility to absorb possible racking deformation.

9.9.3 Attention is drawn to the drainage requirements of Pt 5, Ch 13.3.1 with respect to the compartments created by subdivision structures.

9.9.4 The drainage arrangement for each compartment is to have sufficient capacity to handle leakage from any adjacent flooded compartment.

### 9.10 Ventilation of vehicle deck spaces

9.10.1 Attention is drawn to the ventilation requirement of Pt 6, Ch 2, 13.12.4, since subdivision structure could disrupt air flow.

### 9.11 Operating and Maintenance Manual

9.11.1 An Operating and Maintenance Manual for the subdivision doors is to be provided on board and is to contain the following:

- main particulars and design drawings,
- service conditions (e.g. service area restrictions),
- maintenance and function testing,
- register of inspections, repairs and renewals.

9.11.2 The Manual is to be submitted for approval. It is to contain a note recommending that recorded inspections of supporting and securing devices are to be carried out by the ship's staff at monthly intervals, or following incidents that could result in damage, including heavy weather or contact in the region of the subdivision doors. Any damages recorded during such inspections are to be reported to LR.

9.11.3 Documented operating procedures for closing and securing the subdivision doors are to be kept on board and posted in an appropriate place.

## Section 10 Masts and standing rigging

### 10.1 General

10.1.1 Masts are generally to be of tubular construction and may be either stayed or unstayed. Special consideration will be given to other forms of construction.

10.1.2 Masts are to be of sufficient strength to withstand the worst combination of loads from both the operational case with full sail, reduced sail configurations where applicable and survival conditions.

10.1.3 Masts are to be adequately supported using stays if necessary.

10.1.4 Drainage is to be provided to prevent the build up of seawater or condensation within the mast structure. Steel masts should, where possible, be coated internally with a suitable anti-corrosive preparation.

10.1.5 Openings in the masts for entry and exit of running-rigging or cables should be adequately compensated with suitable insert plates or doublers.

10.1.6 Masts are to be efficiently integrated into the hull and in principle, carried through to the keel. Alternative arrangements of supporting masts will require to be specially considered.

10.1.7 Where ship response data are not available the values for roll, pitch and heave given in Table 2.10.1 should be used.

**Table 2.10.1 Ship motions**

Motion	Maximum single amplitude	Period, in seconds
Roll	$\phi = \sin^{-1} \theta$ degrees but need not exceed 30° and is not to be taken less than 22°	$T_r = \frac{0,7B}{\sqrt{GM}}$
Pitch	$\psi = 12e^{-0,0033L_{pp}}$ degrees, but need not exceed 8°	$T_p = 0,5\sqrt{L_{pp}}$
Heave	$\frac{L_{pp}}{80}$ m	$T_h = 0,5\sqrt{L_{pp}}$
where $L_{pp}$ , $B$ as defined in Pt 3, Ch 1,6 $GM$ = transverse metacentric height of loaded ship, in metres $\theta = \left(0,45 + 0,1 \frac{L}{B}\right) \left(0,54 - \frac{L}{1270}\right)$		

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 10

### 10.2 Design loadings and allowable stresses

10.2.1 The mast and standing rigging design is to be considered with respect to the loads from the following conditions:

- R1 – Operational case with full press of sails for the maximum operational apparent wind speed as specified by the designer.
- R2 – Storm conditions with reduced sail.
- R3 – Survival case with sails reefed/stowed/weather-vaning with the environmental loads resulting from the combination of a maximum wind speed of 63 m/sec and the accelerations produced by ship motions.

10.2.2 The mast section is to be designed to have a margin against failure due to column buckling using the greatest combined design axial and bending stress in both the transverse and fore and aft directions.

10.2.3 For loadcases R1 and R2 described in 10.2.1, the following condition is to be satisfied:

$$\frac{\sigma_b}{\sigma_y} + \frac{\sigma_a}{\sigma_c} \leq 0,67$$

For loadcase R3 the following condition is to be satisfied:

$$\frac{\sigma_b}{\sigma_y} + \frac{\sigma_a}{\sigma_c} \leq 0,85$$

where

$\sigma_b$  is the bending stress in the mast section under consideration

$\sigma_y$  is the tensile yield stress for the material

$\sigma_a$  is the axial stress in the mast section under consideration

$\sigma_c$  is the critical buckling stress for the mast section.

10.2.4 For thin walled masts, constructed from either flat or curved shells, calculations are to be submitted demonstrating adequate margin against local elastic instability.

### 10.3 Materials of mast construction

10.3.1 In general masts are to be constructed from either steel or aluminium alloy tubular members, extrusions and/or welded constructions, and are, generally, to comply with LR's *Rules for the Manufacture, Testing and Certification of Materials*, where appropriate.

10.3.2 Other materials will be specially considered.

### 10.4 Standing rigging

10.4.1 Standing rigging is to be so arranged such that it does not foul running rigging or interfere with the operation of the sails. Protection is to be provided against routine quay contacts.

10.4.2 Standing rigging is to be effectively attached to the masts, deck and hull structure and is to be so designed that it cannot become disconnected during operation.

10.4.3 Standing rigging is to be properly erected using tensioning devices to ensure that the correct pre-tension is applied as specified by the designer.

10.4.4 The initial pre-tension applied to standing rigging is to be measured and recorded.

### 10.5 Design loadings

10.5.1 The forces in the standing rigging are to be obtained by direct calculation methods for the load conditions given in 10.2.1.

10.5.2 The minimum factors of safety on the breaking strength of shrouds and stays are as follows:

Sail cases R1 and R2	3,5
Survival case R3	2,0

### 10.6 Shroud and stay attachment points

10.6.1 Standing rigging is to be effectively attached to the masts, ship's deck or bulwark structure. Chain plates, mast eyeplates and the structure in way is to be reinforced to withstand a load of 1,2 x breaking strength of the appropriate shroud or stay.

Generally the hull structure in way of shroud/stay attachment should be capable of withstanding the wire breaking load without permanent deformation of the structure.

10.6.2 Increased mast wall thickness, or, internal or external mast stiffening rings or diaphragms are to be arranged in way of the toes of shroud and stay eyeplates to resist mast wall punching shear loads. Where additional mast stiffening rings or diaphragms are not fitted, the mast wall is not to be less than:

$$t_{wall} = \frac{2 (h_{eye} B_s k_{mast})}{(t_{eye} l_{eye})} \text{ (mm)}$$

where

$h_{eye}$  = eyeplate pin axis from mast wall, mm, see Fig. 2.10.1

$B_s$  = breaking strength, in kN, of attached rigging component

$k_{mast}$  = mast material factor,  $k$

$t_{eye}$  = eyeplate thickness, mm, see Fig. 2.10.1

$l_{eye}$  = eyeplate length, mm, see Fig. 2.10.1.




Fig. 2.10.1 Definition of  $h_{eye}$  and  $l_{eye}$

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 10 &amp; 11

**10.6.3** The attachments of the stays and shrouds are to be efficiently integrated into the hull structure and due regard given to any attachments to the sheerstrake.

**10.6.4** Where it is intended to use mechanical attachments (bolting) of running rigging or other gear to the mast walls, the number of holes are to be kept to a minimum and are to be staggered in order to maintain the structural integrity of the mast. All details are to be submitted.

### 10.7 Materials for rigging

**10.7.1** In general, standing rigging is to be made from galvanised steel wire rope (GSRW) with galvanised steel rigging screws, shackles and terminations, and is to comply with the requirements of LR. Special consideration will however be given to other rigging materials.

**10.7.2** Alternatively, stainless steel wire rope or solid rod rigging may be used in place of GSRW.

**10.7.3** The steel wire rope, solid rods and loose fittings used for standing rigging are to be manufactured to a recognized National or International standard and at an LR approved works.

**10.7.4** Rigging components from other sources will be specially considered.

**10.7.5** Where stainless steel rigging is employed, particular attention is to be given to the selection of the grade of material used as some stainless steels are prone to stress corrosion cracking and consequent fatigue failure, the onset of which is not readily observed.

**10.7.6** Attention is drawn to the requirements of the Flag Administration for the vessel who may have requirements regarding the application of certain materials, systems or criteria.

### 10.8 Testing and certification

**10.8.1** All equipment items used for standing rigging, including loose items of gear such as shackles, bottle screws, sheaves, etc., are to be tested and surveyed in accordance with LR requirements. For systems employing specialised devices or materials, individual consideration will be given to the testing and survey requirements.

**10.8.2** For sailing passenger ships, the equipment requirement will be in accordance with the letter and numeral two grades higher than that corresponding to the calculated Equipment Numeral.

## Section 11 Miscellaneous openings

### 11.1 General

**11.1.1** The requirements of Pt 3, Ch 11,6 are to be complied with.

### 11.2 Openings in main vehicle deck

**11.2.1** Where the main vehicle deck is enclosed, all companionways and openings in the deck which lead to spaces below are generally to be protected by steel doors or hatch covers. Approved fire doors may be accepted in lieu of steel doors. The sills or coamings are to be not less than 230 mm above the main vehicle deck, with the exception of those leading to machinery spaces which are to have sills or coamings not less than 380 mm. Exceptionally, when such openings are to be kept closed at sea, sills or coamings may be reduced in height, provided that the sealing arrangements are adequate. In such cases, the doors or hatch covers are to be secured weathertight by gaskets and a sufficient number of clamping devices. Such items as portable plates in the main vehicle deck arranged for the removal of machinery parts, etc., may be arranged flush with the deck, provided they are secured by gaskets and closely spaced bolts at a pitch not exceeding five diameters.

**11.2.2** Scuppers from vehicle or cargo spaces fitted with an approved fixed pressure water spray fire-extinguishing system are to be led inboard to tanks. Alternatively they may be led overboard providing they comply with Pt 3, Ch 12,4.1.3 (a) and (b).

**11.2.3** Inboard draining scuppers do not require valves but are to be led to suitable drain tanks (not engine room or hold bilges) and the capacity of the tanks should be sufficient to hold approximately 10 minutes of drenching water. The arrangements for emptying these tanks are to be approved and suitable high level alarms provided.

**11.2.4** A drainage system is to be arranged in the area between bow door and ramp, or where no ramp is fitted, between the bow door and inner door. The system is to be equipped with an audible and visual alarm function to the navigation bridge being set off when the water levels in these areas exceed 0,5 m or the high water level alarm, whichever is the lesser.

**11.2.5** The drainage arrangement for each area is to have sufficient capacity to prevent accumulation of water in case of leakage. Scuppers are to be provided on both sides of the ship with a diameter not less than 50 mm and in accordance with Pt 3, Ch 12,4. Alternatively, a bilge suction should be provided.

**11.2.6** If the main vehicle deck is not totally enclosed, scuppers or freeing ports are to be provided consistent with the requirements of Pt 3, Ch 8,5.3.

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Section 11

11.2.7 Air pipes from cofferdams or void spaces may terminate in the enclosed 'tween deck space on the main vehicle deck provided the space is adequately ventilated and the air pipes are provided with weathertight closing appliances.

11.2.8 Between the bow door and the inner door a television surveillance system is to be fitted with a monitor on the navigation bridge and in the engine control room. The system must monitor the position of doors and a sufficient number of their securing devices. Special consideration is to be given for lighting and contrasting colour of objects under surveillance, see also 8.5.7.

### 11.3 Strength assessment of windows in large passenger ships

11.3.1 On windows in the second tier and higher above the freeboard deck, a glazing equivalent may be fitted in lieu of deadlights/storm covers. The thicknesses and arrangements are to be acceptable to the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the ship is intended to operate. For arrangements of glazing acceptable to LR, see Table 2.11.1. Alternative arrangement of glazing in lieu of deadlights/storm covers may be accepted provided details are submitted for consideration.



11.3.2 For passenger ships the design pressure,  $H_d$ , on windows is to be taken as given in Table 2.11.2, or an equivalent National or Internationally recognized standard.

11.3.3 The thickness,  $t_0$ , of toughened safety glass is to be taken as given in Table 2.11.3.

**Table 2.11.2 Design pressure,  $H_d$ , on windows**

Window location	Design pressure $H_d$ in $t/m^2$
Between the design waterline and a point $Z_{1,5}$ m above the waterline	Per BS MA 25: 1973
Between a point $Z_{1,5}$ m above the waterline and the deck immediately above (at $Z_{d1,5}$ )	1,5
Over the next 2 'tween deck heights	$1,5 - f_w \left( \frac{Z_w - Z_{d1,5}}{H_{t1} + H_{t2}} \right)$
For subsequent decks to the top of the navigation bridge	0,25 sides and aft ends 0,75 house fronts
From the top of the navigation bridge to the uppermost deck, for house fronts	0,75 at top of navigation bridge 0 at uppermost continuous deck, with linear variation between, but not less than 0,25
From the top of the navigation bridge to the uppermost deck, at sides and aft ends	0,25
Symbols	
$f_w$ = 1,25 in way of sides and ends of superstructures = 0,75 in way of house fronts $Z_{1,5}$ = the vertical location in metres above the waterline at which the BS MA:25 pressure as given in Annex E of BS MA:25 (1973) is 1,5 $t/m^2$ $Z_{d1,5}$ = the vertical location in metres of the deck at which the pressure is 1,5 $t/m^2$ from the table above $Z_w$ = the vertical location in metres above the waterline to the point under consideration $H_{t1} + H_{t2}$ = sum of the appropriate 'tween deck heights in metres	

**Table 2.11.1 Acceptable arrangements of glazing in lieu of portable storm covers/deadlights**

In lieu of portable storm covers	In lieu of deadlights and storm covers
 $t_1^2 + (0,77t_2)^2 + t_1^2 = (1,2t_0)^2$	 $t_0^2 + t_0^2 = (1,4t_0)^2$
Symbols	
$t_0$ = minimum thickness of toughened glass as calculated in Table 2.11.3.	

# Ferries, Roll on–Roll off Ships and Passenger Ships

## Part 4, Chapter 2

Sections 11 & 12

**Table 2.11.3 Thickness of toughened glass**

Window type	Thickness, $t_o$ , in mm
Rectangular	$b \sqrt{\frac{H_d \beta}{4000}}$
Circular	$0,0175 r \sqrt{H_d}$
Semi-circular	$0,011 r \sqrt{H_d}$
Symbols	
$b$ = length of shorter side of window, in mm $H_d$ = design pressure head, in metres, as calculated in Table 2.11.2 $\beta$ = $0,54A_R - 0,078A_R^2 - 0,17$ for $A_R \leq 3$ = $0,75$ for $A_R > 3$ $A_R$ = aspect ratio of window, in mm = $a/b$ $a$ = length of longer side of window, in mm $r$ = the radius of the window, in mm	

### 11.4 Frame design and testing

**11.4.1 Application.** The testing requirements contained in this Section are for all exterior window designs for passenger ships regardless of length. The testing is to be carried out for characteristic window sizes (largest, smallest) and forms (circular, semi-circular and rectangular) for each passenger ship. Window designs, which are not covered by Type Approval Certification, will require prototype testing in order to confirm structural integrity and water tightness. Tests are to be carried out to the satisfaction of the Surveyor.

**11.4.2 Water tightness.** A hydrostatic test is to be carried out in order to examine water tightness. This is carried out by applying the design pressure head  $H_d$ , as calculated in Section 11.3, and maintained at this level for at least 15 minutes.

**11.4.3 Structural testing.** A hydrostatic test is to be carried out in order to examine the capability of the frame, mullions and glass retaining arrangements. This is carried out by applying a test pressure of  $4H_d$  ( $H_d$  as calculated in Section 11.3). Alternatively this test may be carried out using a steel plate in place of the glass. Ideally, the steel plate thickness should be of a suitable reduced thickness in order to simulate the flexural performance of the glass.

**11.4.4** Equivalent proposals for testing will be considered. Where alternative testing procedures are proposed, these are to be agreed with LR before commencement.

#### 11.4.5 Chemically toughened glass.

- Chemically toughened glass may be used in lieu of thermally toughened glass provided it can be demonstrated the strength of the arrangement is at least equivalent in strength to that of thermally toughened glass.
- The glazing system is to be of laminated construction.
- Method of testing will be specially considered.

**11.4.6** The overlap between glazing and the retaining frame is not to be less than 12 mm.

## Section 12 Glass structures

### 12.1 General

**12.1.1** The requirements of 12.3 and 12.4 apply solely to external balcony balustrades.

### 12.2 Strength of mullions

**12.2.1** The section modulus of mullions is not to be less than:

$$Z = 10,78H_d l A_m k 10^{-9} \text{ cm}^3$$

where

- $a$  = see Table 2.12.1
- $b$  = see Table 2.12.1
- $r$  = see Table 2.12.1
- $l$  =  $a$  for rectangular windows  
      =  $2r$  for semi-circular windows
- $H_d$  = design pressure head, in metres, as calculated in 11.3.2
- $A_m$  =  $ab$  for rectangular windows  
      =  $1,22r^2$  for semi-circular windows
- $k$  = as defined in 1.5.1

### 12.3 Top rail of balcony balustrades

**12.3.1** The minimum section modulus of the steel top rail of glass wall balconies is given by:

$$Z = L_b^2 \text{ cm}^3$$

where

- $L_b$  = span of top rail, in metres.

### 12.4 Glass balustrades

**12.4.1** The minimum thickness of glass balustrades is to be not less than as given by Table 2.11.3 using a design pressure of  $H_d = 0,25 \text{ t/m}^2$ .

**12.4.2** The glazing is to be of laminated construction.





# Tugs

## Part 4, Chapter 3

Sections 1 & 2

### Section

- 1 **General**
- 2 **Longitudinal strength**
- 3 **Floors in single bottoms**
- 4 **Panting and strengthening of bottom forward**
- 5 **Machinery casings**
- 6 **Freeing arrangements**
- 7 **Towing arrangements**
- 8 **Fenders**
- 9 **Escort operation, performance numeral and trials**

### ■ Section 1 General

#### 1.1 Application

1.1.1 Sections 1 to 8 of this Chapter apply to tugs, but are not applicable to offshore tugs/supply ships, which are dealt with in Chapter 4.

1.1.2 Section 9 of this Chapter applies to tugs and offshore supply ships intended to provide escort operation.

1.1.3 The scantlings and arrangements are to be as required by Chapter 1 except as otherwise specified. The draught,  $T$ , used for the determination of scantlings is to be not less than  $0,85D$ .

#### 1.2 Class notations

1.2.1 In general, tugs for unrestricted service complying with the requirements of Sections 1 to 8 will be eligible to be classed **100A1 tug**.

1.2.2 Tugs for unrestricted service complying with the requirements of this Chapter, except 9.3, will be eligible to be classed **100A1 escort tug**.

1.2.3 Tugs for unrestricted service complying with the requirements of this Chapter will be eligible to be classed **100A1 escort tug EPN (F,B,V,C)**. The performance numeral (F,B,V,C) contains the performance ratings obtained from full scale trials in accordance with 9.3.

1.2.4 Tugs intended to be operated only in suitable areas or conditions which have been agreed by the Committee, as defined in Pt 1, Ch 2,2.3.6 to 2.3.10, will receive individual consideration on the basis of the Rules with respect to the environmental conditions agreed for the design basis and approval. In particular, tugs complying with the requirements of this Chapter and Pt 3, Ch 13,7 for the relevant reduced equipment requirements, will be eligible to be classed:

- **A1 tug protected waters service**; or
- **A1 escort tug protected waters service**; or
- **A1 escort tug EPN (F,B,V,C) protected waters service**, (see Pt 1, Ch 2,2.3.6); or
- **100A1 tug with service restriction notation**; or
- **100A1 escort tug with service restriction notation**; or
- **100A1 escort tug EPN (F,B,V,C) with service restriction notation**;

whichever is applicable.

1.2.5 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2 to which reference should be made.

### 1.3 Information required

1.3.1 In addition to the information and plans required by Pt 3, Ch 1,5, plans covering the following items are to be submitted for approval where applicable:

- Support structure and foundations of towing equipment.
- Skegs, propeller guards and other structures which support the weight of the vessel during dry-docking.

1.3.2 The following supporting documents are to be submitted for information:

- Towing arrangements, including lines of action, magnitudes and corresponding points of application of towline pulls on towing equipment.
- Details of the breaking strength of the components of the towline system, together with maximum pull and brake holding load, or equivalent, of towing winches where applicable.

### ■ Section 2 Longitudinal strength

#### 2.1 General

2.1.1 The longitudinal strength standard is to comply with the relevant requirements of Pt 3, Ch 4.

2.1.2 The requirements of Pt 3, Ch 4,8.3 regarding loading instruments are not applicable to tugs.

## ■ Section 3 Floors in single bottoms

### 3.1 Floors

3.1.1 Single bottom floors are to be in accordance with the requirements of Ch 1,7, except that floors clear of the machinery space may be flanged in lieu of a face plate being fitted.

## ■ Section 4 Panting and strengthening of bottom forward

### 4.1 Panting region reinforcement

4.1.1 The arrangements to resist panting required by Pt 3, Ch 5 do not apply to tugs less than 46 m in length. In tugs 46 m or more in length, additional stiffening is also to be fitted in the 'tween decks throughout the panting region.

### 4.2 Strengthening of bottom forward

4.2.1 The requirements for strengthening of bottom forward detailed in Pt 3, Ch 5 do not apply to tugs.

## ■ Section 5 Machinery casings

### 5.1 Escape hatches

5.1.1 Any emergency exit from the machinery room to the deck is to be capable of being used at extreme angles of heel, and should be positioned as high as possible above the waterline and on or near the ship's centreline. Covers to escape hatches are to have hinges arranged athwartships. Coaming heights are to be at least 600 mm above the upper surface of the deck.

## ■ Section 6 Freeing arrangements

### 6.1 General

6.1.1 If the only means of access to the wheelhouse is external, then stormboards, or an equivalent, are to be fitted between the deckhouse and the ship's sides forward of any deckhouse doors up to the height of the bulwark rail. A gap is to be left between the deck and the bottom board for freeing purposes.

## ■ Section 7 Towing arrangements

### 7.1 Towing equipment

7.1.1 For tugs which normally tow over the stern with the main towline connection to the hull ahead of the propellers, the position of towline connection is normally to be five to 10 per cent of the ship's length abaft amidships, but in no circumstances is it to be sited forward of a position, five per cent of the ship's Rule length abaft the longitudinal centre of gravity of the tug in any anticipated condition of loading.

7.1.2 The attachment of the towline to the tug is to be located as low as practicable in order to minimize heeling moments arising from working conditions. Reliable slip arrangements which facilitate towline release regardless of the angle of the towline are to be provided.

7.1.3 It is recommended that the slip arrangements should also be operable from the bridge. The arrangements should be tested to the Surveyor's satisfaction. The breaking strength of the hook, or its equivalent, should generally be 50 per cent in excess of that of the towline, see Pt 3, Ch 13,7.

### 7.2 Towing equipment foundations

7.2.1 Direct support for towing equipment by means of pillars and/or pillar bulkheads is to be arranged as far as this is practicable.

7.2.2 The design load for the support structure in way of towing equipment is to be not less than the breaking strength of the towline system. The design load is also to be taken as not less than the breaking strength of the tow hook or the brake holding load, or equivalent, of the winch, whichever is appropriate.

7.2.3 Scantlings of pillars and pillar bulkheads are to be in accordance with Ch 1,4.4.

7.2.4 Scantlings of deck girders and transverses forming the support structure of towing equipment are to be determined by direct calculations using the following stresses:

$$\tau = \left( \frac{87}{k} \text{ N/mm}^2 \right) \left( \frac{8,9}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma = \left( \frac{150}{k} \text{ N/mm}^2 \right) \left( \frac{15,3}{k} \text{ kgf/mm}^2 \right)$$

$$\sigma_e = \left( \frac{213}{k} \text{ N/mm}^2 \right) \left( \frac{21,7}{k} \text{ kgf/mm}^2 \right)$$

where

$\tau$  = shear stress, in N/mm<sup>2</sup>

$\sigma$  = bending stress, in N/mm<sup>2</sup>

$k$  = material factor, see Pt 3, Ch 2,1.2

$\sigma_e$  = equivalent stress, in N/mm<sup>2</sup>

$$\sqrt{\sigma^2 + 3\tau^2}$$

# Tugs

# Part 4, Chapter 3

Sections 7, 8 & 9

7.2.5 Generally, the foundations of towing fairleads are to be carried through the deck and integrated into suitable underdeck structure.

7.2.6 On tugs which utilise an indirect method of towing, attention is drawn to the increased out-of-plane forces that occur in towing fairleads.

## Section 8 Fenders

### 8.1 Ship's side fenders

8.1.1 An efficient fender is to be fitted to the ship's side at deck level extending all fore and aft.

## Section 9 Escort operation, performance numeral and trials

### 9.1 General

9.1.1 An escort tug is a tug intended for escort operation. Escort operation is an operation in which the tug closely follows the assisted ship providing control by steering and braking, as necessary.


9.1.2 Escort tugs are to be capable of utilizing methods of towing through which steering and braking forces are generated by a combination of propulsive and hydrodynamic forces developed by the tug, acting on the towline to the attended ship, see example in Fig. 3.9.1.

9.1.3 The intact stability of the tug during escort operation is to comply with a Standard recognized by the National Administration with whom the ship is registered and/or by the National Administration within whose territorial jurisdiction the tug is intended to operate, as applicable. Attention is drawn to the inherent problems relating to the quick release of the towline and the sudden loss of propulsion power during the escort operation in addition to the maximum steering and braking forces.

### 9.2 Towing arrangements

9.2.1 The specified breaking strength of the towline is to be at least 2,5 x maximum design towline force.

9.2.2 The towing winch is to include a system of continuous load monitoring, with a bridge readout display and an overload prevention system, which is to be operational during escort duties. The overload prevention system is to be designed with the capability to pay out the towline in a controlled manner when the load reaches the maximum design towline force, and is to be capable of alerting the Master and crew.



### 9.3 Performance trials

9.3.1 Escort tugs which carry out full scale performance trials in accordance with the requirements of this Section will be eligible to have the escort performance numeral **EPN (F,B,V,C)** appended to the **escort tug** notations, see 1.2.3, 1.2.4 and Ch 4, 1.2.2, where

**F** is the maximum steering force ( $F_s$ ), in tonnes, see Fig. 3.9.1 and 9.3.6.  
**B** is the maximum braking force ( $F_b$ ), in tonnes, see Fig. 3.9.1 and 9.3.6.  
**V** is the speed, in knots, at which **F** and **B** are determined.  
**C** is the time, in seconds (s), required for the escort tug in manoeuvring from maintained oblique position of tug giving maximum steering force  $F_s$  on one side of assisted vessel to mirror position on the other side, see 9.3.6. The towline angle,  $\alpha$ , need not be taken less than  $30^\circ$ , see Fig. 3.9.1.

9.3.2 The performance numeral may be determined with speed **V** equal to either 8 knots or 10 knots. If both sets of numerals are determined at the trials then the class notation will include them all.

9.3.3 A trials plan, which includes the estimated forces, is to be submitted and approved prior to trials being undertaken.

9.3.4 The trials of the escort tug are to be performed using a ship capable of maintaining almost constant heading and speed when subjected to the steering and braking forces from the escort tug.

9.3.5 The following trials are to be carried out in calm weather conditions and in the presence of a Lloyd's Register (hereinafter referred to as 'LR') Surveyor:

- Steering and braking force capability test, see 9.3.6.
- Bollard pull test, see 9.3.8.

A record of the results is to be kept on board the escort tug.

9.3.6 Prior to commencing a trial, the following data are to be recorded:

- Wind speed and direction.
- Sea state.
- Current speed and direction.
- Water depth.
- The main particulars and the loading condition of the assisted ship.
- Loading condition of the escort tug.

9.3.7 **Steering and braking force capability test** is a test by which the steering force,  $F_s$ , and braking force,  $F_b$ , are determined when utilizing the method, shown in Fig. 3.9.1, of towing at a range of towline angles,  $\alpha$ , from 0 to 90 degrees and for a range of operating speeds up to and including the maximum escort speed. The following parameters are to be continuously recorded during the test:

- Position, speed and heading of the assisted ship and the escort tug.
- Towline force,  $F_t$ .
- Angle of towline,  $\alpha$ .
- Heel angle of the escort tug.
- Direction of thrust and power absorbed by all propellers and thrusters of the tug.
- Rudder angles of the tug.

9.3.8 The length of the towline is to represent a typical operating condition and is to be recorded prior to and at the completion of the test. The steering and braking forces for a given speed and angle can be calculated by using the average values of the recorded towline force.

9.3.9 **Bollard pull test** is to be carried out in accordance with LR's *Bollard Pull Certification Procedures Guidance Information*.

# Offshore Supply Ships

## Part 4, Chapter 4

Sections 1, 2 & 3

### Section

- 1 **General**
- 2 **Longitudinal strength**
- 3 **Hull envelope plating**
- 4 **Hull envelope framing**
- 5 **Superstructures and deckhouses**
- 6 **Miscellaneous openings**
- 7 **Watertight bulkhead doors**
- 8 **Engine exhaust outlets**
- 9 **Transport and handling of limited amounts of hazardous and noxious liquid substances in bulk**

### ■ Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies to sea-going ships specially designed and constructed for the carriage of specialized stores and cargoes to mobile offshore units and other offshore installations, and also to offshore tug/supply ships which in addition to the above perform the duties of a tug.

1.1.2 The scantlings and arrangements are to be as required by Chapter 1, except as otherwise specified in this Chapter.

1.1.3 Attention is drawn to the need for Masters to be able to assess the stability of their ships quickly and accurately in all service conditions, see Pt 1, Ch 2,3.

#### 1.2 Class notations

1.2.1 In general, ships complying with the requirements of this Chapter will be eligible to be classed:

- **100A1 offshore supply ship;** or
- **100A1 offshore tug/supply ship;**

whichever is applicable.

1.2.2 Ships complying with the requirements of Ch 3,9 and the requirements of this Chapter will be eligible to be classed:

- **100A1 offshore escort tug/supply ship;** or
- **100A1 offshore escort tug EPN (F,B,V,C)/supply ship;**

whichever is applicable.

1.2.3 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2, to which reference should be made.

### 1.3 Information required

1.3.1 In addition to the information and plans required by Pt 3, Ch 1,5, plans covering the following items are to be submitted where applicable:

- Separate or independent cargo tanks.
- Cargo tank foundations and securing arrangements.
- Towing arrangements, including supports and foundations of towing winches.
- Supports and foundations for anchor handling and laying arrangements for anchors carried as cargo.
- Arrangements for the stowage of deck cargoes (cargo containment) and details of any associated racks or other similar structures and their supports and foundations.
- Movable decks, including the stowing arrangements for portable components.
- Freeing arrangements.

### 1.4 Symbols

1.4.1 The symbols are as defined in Ch 1,1.5.

### ■ Section 2 Longitudinal strength

#### 2.1 General

2.1.1 The longitudinal strength standard is to comply with the relevant requirements of Pt 3, Ch 4.

2.1.2 The requirements of Pt 3, Ch 4,8.3 regarding loading instruments are not applicable to offshore supply ships.

### ■ Section 3 Hull envelope plating

#### 3.1 Side shell

3.1.1 The thickness of side shell is to be that required by Ch 1,5.4 but is in no case to be less than 9 mm.

3.1.2 Efficient fenders are to be fitted, with adequate support behind them, in exposed areas.

3.1.3 Shell in way of stern rollers immediately adjacent to high duty bollards and in other high load areas is to be suitably reinforced.

# Offshore Supply Ships

## Part 4, Chapter 4

Sections 3 to 6

### 3.2 Weather decks

3.2.1 Where cargo is to be carried on weather decks, the scantlings are to be suitable for the specified loadings, but in no case is a head less than 3,5 m to be used. Additional local increases in scantlings may be required where specialized cargoes are likely to induce concentrated loads. The thickness,  $t$ , of deck plating is to be not less than:

$$t = (0,025L + 7) \text{ mm}$$

### 3.3 Cargo containment

3.3.1 Means are to be provided to enable deck cargoes to be adequately secured and protected. In general, suitable inner bulwarks, rails, bins or storage racks of substantial construction are to be provided and properly secured to adequately strengthened parts of the hull structure. Properly designed locking equipment or efficient means of lashing containers are to be fitted where appropriate. Small hatches (including escape hatches), valve controls, ventilators, air pipes, etc., are to be situated clear of the cargo containment areas.

## Section 4 Hull envelope framing

### 4.1 Transverse framing

4.1.1 The section moduli of the main and 'tween deck frames are to be 25 per cent greater than those required by Ch 1,6, Pt 3, Ch 5,4 and Pt 3, Ch 6,4. Frames are not to be scalloped.

## Section 5 Superstructures and deckhouses

### 5.1 Scantlings

5.1.1 The scantlings of deckhouses situated on the forecastle deck and above are to comply with the requirements of Table 4.5.1.

5.1.2 The scantlings of forecastle end bulkheads are to be not less than those required by Table 4.5.1 for aft ends of deckhouses or less than those required by Pt 3, Ch 8,2 for an exposed machinery casing.

**Table 4.5.1 Superstructures and deckhouses on forecastle deck**

Position	Thickness of plating, in mm	Modulus of stiffeners, in cm <sup>3</sup>	Depth of stiffeners, in mm
Fronts	The greater of $t = 0,012s$ or 8,0	$Z = 0,034sI_e^2$	Not less than 100
Sides	The greater of $t = 0,01s$ or 6,5	$Z = 0,027sI_e^2$	Not less than 75
Aft ends	The greater of $t = 0,008s$ or 6,5	$Z = 0,027sI_e^2$	Not less than 65
NOTE The ends of stiffeners are to be connected on all tiers.			

## Section 6 Miscellaneous openings

### 6.1 General

6.1.1 For offshore supply ships the requirements of Pt 3, Ch 11,6 are to be complied with.

### 6.2 Access from freeboard deck

6.2.1 There is to be no direct access from the freeboard deck to machinery or other spaces below the freeboard deck. Indirect access may be arranged via a space or passageway fitted with an outer door having a sill not less than 600 mm high and an inner door having a sill not less than 380 mm high. The inner door is to be self-closing and gastight. The space or passageway between the two doors is to be adequately drained. It is desirable, however, that access to spaces below the freeboard deck is arranged from a position above the superstructure deck. Where it is necessary to provide an emergency escape trunk which cannot terminate within a superstructure space, the arrangements for maintaining the integrity of the hatch or outlet are to be approved by Lloyd's Register (hereinafter referred to as 'LR').

### 6.3 Windows and side scuttles

6.3.1 The requirements of this Section are to be applied in conjunction with Pt 3, Ch 11,6.5.

6.3.2 Windows may only be fitted in the following locations:

- (a) Second tier and higher above the freeboard deck:
  - (i) in the after end bulkhead of deckhouses and superstructures,
  - (ii) in the sides of deckhouses and superstructures which are not part of the shell plating.

# Offshore Supply Ships

# Part 4, Chapter 4

## Section 6

- (b) Third tier and higher above the freeboard deck:
- (i) in the forward facing bulkheads of deckhouse and superstructures, except that in the first tier of the front bulkhead above the weather deck, only side scuttles will be accepted.

6.3.3 In locations not specified in 6.3.2, only side scuttles will be accepted.

6.3.4 Permanently attached deadlights are to be provided as follows:

- (a) Side scuttles:
- (i) in the side shell plating,
  - (ii) in the forward facing bulkheads of superstructures and deckhouses,
  - (iii) in the sides of deckhouses and superstructures up to and including the third tier above the freeboard deck,
  - (iv) in the after end bulkheads of superstructures, deckhouses, casings and companionways in the first and second tiers above the freeboard deck.
- (b) Windows in locations permitted in 6.3.2:
- (i) in the sides of deckhouses and superstructures in the second and third tiers above the freeboard deck.
  - (ii) in the after end bulkheads of superstructures, deckhouses, casings and companionways in the second tier above the freeboard deck.

6.3.5 On windows in the second tier and higher above the freeboard deck, hinged storm covers may be fitted in lieu of deadlights, provided there is safe access for closing.

6.3.6 Windows in the wheelhouse front are to have deadlights or storm covers. For storm covers, an arrangement for easy and safe access is to be provided, (e.g. gangway with railing). However, for practical purposes, the deadlights or storm covers may be portable if stowed adjacent to the window for quick fitting. At least two of the deadlights or storm covers are to have the means of providing a clear view.

6.3.7 Deadlights for side scuttles, and for windows not mentioned in 6.3.5 and 6.3.6, are to be internally hinged.

6.3.8 Side scuttles are to comply with ISO Standard 1751, as follows:

- (a) Type A side scuttles in the shell plating, in the sides of superstructures and in the forward facing bulkheads of superstructures and deckhouses on the weather deck;
- (b) Type B side scuttles in the after ends of superstructures and in the sides and ends of deckhouses; or
- (c) an equivalent National Standard.

6.3.9 The thickness of the toughened safety glass for windows is to be determined from Tables 4.6.1 and 4.6.2.

6.3.10 Windows of larger sizes than given in Tables 4.6.1 and 4.6.2 are not acceptable, except in the after ends of deckhouses which are to be submitted for consideration in each case.


6.3.11 For the location of windows and side scuttles, see Fig. 4.6.1.

**Table 4.6.1** Thickness of toughened safety glass fitted in windows in front and side bulkheads

Nominal dimensions of window, mm x mm	Thickness of toughened safety glass, mm			
	2nd tier	3rd tier	4th tier	5th tier
300 x 425	12	12	10	10
355 x 500	15	15	12	10
400 x 560	19	15	12	10
450 x 630	19	19	15	12
500 x 710	–	19	15	12
560 x 800	–	–	19	15
900 x 630	–	–	–	15
1000 x 710	–	–	–	19

**Table 4.6.2** Thickness of toughened safety glass fitted in windows in after end bulkheads

Nominal dimensions of window, mm x mm	Thickness of toughened safety glass, mm		
	2nd tier	3rd tier	4th tier and higher
300 x 425	10	10	10
355 x 500	10	10	10
400 x 560	12	12	10
450 x 630	15	12	10
500 x 710	15	15	10
560 x 800	–	15	10
900 x 630	–	19	12
1000 x 710	–	–	12



## Section 7 Watertight bulkhead doors

### 7.1 Watertight doors

7.1.1 Watertight doors are to be efficiently constructed and fitted in accordance with Pt 3, Ch 11,9 and hose tested in place as required by Pt 3, Ch 1,8.

## Section 8 Engine exhaust outlets

### 8.1 Location

8.1.1 Engine exhaust outlets are to be located as high as is practicable above the deck and are to be fitted with spark arresters.

## Section 9 Transport and handling of limited amounts of hazardous and noxious liquid substances in bulk

### 9.1 General

9.1.1 Attention is drawn to IMO Resolution A.673 (16) *Guidelines for the Transport and Handling of Hazardous and Noxious Liquid Substances in Bulk in Offshore Support Vessels*, which includes reference to:

- Stability, cargo tank location and ship design, and
- IMO Resolution A.469 (12) *The Guidelines for the Design and Construction of Offshore Supply Vessels*.

9.1.2 It is possible that the National Authority will require compliance with these IMO Guidelines and future amendments thereto, if it is intended to carry limited amounts of hazardous and noxious liquid cargoes in bulk.



# Barges and Pontoons

## Part 4, Chapter 5

Section 1

## Section

- 1 **General**
- 2 **Longitudinal strength**
- 3 **Hull envelope plating**
- 4 **Hull envelope framing**
- 5 **Strengthening of bottom forward**
- 6 **Bottom strengthening for loading and unloading aground**
- 7 **Watertight bulkheads**

### Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies, in general, to manned or unmanned non-self-propelled ships defined as follows:

- (a) Barges for the carriage of general dry cargoes in cargo holds.
- (b) Barges for the carriage of liquid cargoes in bulk.
- (c) Pontoons designed specifically for the carriage of non-perishable cargo on deck.
- (d) Shipborne barges for the carriage of general dry cargo in cargo holds and intended to operate afloat only within specified geographical limits, and suitable for regular carriage on board a larger ship.

1.1.2 Manned or unmanned barges for the carriage of liquid chemicals in bulk and barges for the carriage of liquefied gases will receive individual consideration on the basis of the Rules, see Table 5.1.1.

**Table 5.1.1 Applicable Rules**

Type of barge	Applicable Rules
Barge for the carriage of general dry cargo in cargo hold	Chapter 1
Barge for the carriage of liquid cargo in bulk	Chapter 10
Pontoon designed specifically for the carriage of non-perishable cargo on deck	Chapter 1
Shipborne barges for the carriage of general dry cargo in cargo holds	Chapter 1 and this Chapter for 'extended protected water service' barges
Barge for the carriage of liquid chemicals in bulk	<i>Rules for Ships for Liquid Chemicals in Bulk</i>
Barge for the carriage of liquefied gases	<i>Rules for Ships for Liquefied Gases</i>

1.1.3 The scantlings and arrangements, except where otherwise specified in this Chapter, are to comply with the Rules as indicated in Table 5.1.1.

1.1.4 The Rules assume that the structural arrangements of barges carrying cargo in holds will generally approximate to normal ship shape and construction. Barges of this type not doing so will receive individual consideration on the basis of the Rules.

1.1.5 The Rules also assume that barges and pontoons are homogeneously loaded. Barges or pontoons with other types of loading, e.g. crane pontoon, will receive individual consideration.

1.1.6 All barges and pontoons are to be fitted with adequate arrangements for towing. In general, such arrangements are to consist of, or be equivalent to, not less than two sets of bollards, each of which shall be suitable for accepting a towline of suitable breaking strength.

#### 1.2 Class notations

1.2.1 In general, ships complying with the requirements of this Chapter will be eligible for one of the following classes:

- (a) **100A1 barge**. This class will be assigned to non-self-propelled sea-going ships as defined in 1.1.1(a).
- (b) **100A1 oil barge**. This class will be assigned to non-self-propelled sea-going ships as defined in 1.1.1(b).
- (c) **100A1 pontoon**. This class will be assigned to non-self-propelled sea-going ships as defined in 1.1.1(c).

1.2.2 Barges and pontoons intended to be operated only in suitable areas or conditions which have been agreed by the Committee, as defined in Pt 1, Ch 2, 2.3.6 to 2.3.10, will receive individual consideration on the basis of the Rules with respect to the environmental conditions agreed for the design basis and approval. In particular, shipborne barges as defined in 1.1.1(d) complying with the requirements of this Chapter will be eligible to be classed **100A1 shipborne barge extended protected water service**.

1.2.3 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2, to which reference should be made.

#### 1.3 Information required

1.3.1 In addition to the information and plans required by Pt 3, Ch 1, 5, the following are to be submitted:

- Details of structure and fittings to which deck cargo securing lashings, etc., are attached.
- Details of the bollards and their supporting structure.
- Where pusher tugs or integral tug/barge systems are proposed, full details and data of the attachment and support arrangements.
- Details of the intended service areas required for barges or pontoons designed to operate within specified geographical limits.
- Longitudinal strength and lifting arrangements for shipborne barges.


# Barges and Pontoons

## Part 4, Chapter 5

Sections 1, 2 &amp; 3

### 1.4 Symbols and definitions

1.4.1 The Rule length,  $L$ , for vessels with swim ends is to be measured as shown in Fig. 5.1.1. Where a swim end is arranged aft but no rudder is fitted,  $L$  need not exceed 97 per cent of the extreme length on the summer load waterline. For tugs and barge units having rigid connections, the length,  $L$ , is to be taken as the combined length of the tug and barge.



### Section 2

#### Longitudinal strength

##### 2.1 General

2.1.1 Longitudinal strength calculations are to be made in accordance with the requirements given in Pt 3, Ch 4, and the ship service factor,  $f_1$ , is given in Table 5.2.1.

**Table 5.2.1 Ship service factor  $f_1$**

Type of ship	$f_1$	
	'100A1'	'100A1 extended protected water service'
Barge for the carriage of general cargo in holds and for the carriage of liquid cargoes in bulk	1,0	0,80
Pontoons for the carriage of non-perishable cargoes on deck		
Shipborne barges for the carriage of general cargo in holds and unmanned	—	0,70

2.1.2 The requirements of Pt 3, Ch 4.8.3 regarding loading instruments are not applicable to barges and pontoons.

2.1.3 For shipborne barges, where it is the intention to lift the barge on board ship by crane, a condition 'fully loaded barge suspended by crane' is to be submitted. For this condition the following stresses are permissible:

Bending stress  $\sigma_b = 147,2 \text{ N/mm}^2 (15,0 \text{ kgf/mm}^2)$

Shear stress  $\tau = 98,1 \text{ N/mm}^2 (10,0 \text{ kgf/mm}^2)$

### Section 3

#### Hull envelope plating

##### 3.1 Shell and deck plating

3.1.1 The thickness of shell and deck plating is to be as necessary to give the hull section modulus required by 2.1 and to satisfy the requirements listed in Table 5.3.1.

**Table 5.3.1 Shell and deck plating**

Item of plating	Thickness for ships classed 100A1	Thickness for ships having extended protected water service notation
(a) Keel	The separate requirements of Chapter 1 or Chapter 10, whichever is applicable, for keel width and thickness need not be applied, except where $L > 100 \text{ m}$ and the bottom has a rise of floor	
(b) Bottom shell and bilge	In accordance with the requirements of Chapter 1 or Chapter 10, whichever is applicable	In accordance with the requirements of Chapter 1 or Chapter 10, whichever is applicable, reduced by 12,5 per cent, but is to be not less than required by (c) below
	For chines, see 3.1.2	
(c) Side shell from upper turn of bilge or chine to deck	The greater of the values obtained from Chapter 1 or Chapter 10, whichever is applicable, for the appropriate framing arrangement	
(d) Deck	In accordance with the requirements of Chapter 1 or Chapter 10, whichever is applicable	In accordance with the requirements of Chapter 1 or Chapter 10, whichever is applicable, reduced by 2 mm, but is to be not less than the deck basic end thickness as required by Pt 3, Ch 5 and Ch 6
	In pontoon barges with deck cargoes the deck thickness derived from (d) may be required to be increased	
(e) Swim ends	The bottom shell plating thickness is to be maintained up to the summer load waterline for the rake plating. Above this point the thickness may be tapered to that of the side shell requirements from a point not less than 1 m above the load waterline	

# Barges and Pontoons

## Part 4, Chapter 5

Sections 3 &amp; 4

3.1.2 On ships with two chines each side, the bilge plating should generally be calculated from the bottom plating formulae. On hard chine ships, flanged chines will not, in general, be approved, but where a chine is formed by knuckling the shell plating, the radius of curvature, measured on the inside of the plate, is to be not less than 10 times the plate thickness. Where a solid round chine bar is fitted, the bar diameter is to be not less than three times the thickness of the thickest abutting plate. Where welded chines are used, the welding is to be built up as necessary to ensure that the shell plating thickness is maintained across the weld.

### Section 4

### Hull envelope framing

#### 4.1 Symbols

4.1.1 The symbols used in this Section are defined as follows:

$h$  = head or load height, in metres, and is to be taken as:

for bottom longitudinals, frames, girders and transverses: the depth  $D$

for side longitudinals: the distance of the longitudinal below the deck at side, but not less than  $0,01L + 0,7$

for side transverses: the distance from the mid-point of span to the deck at side, but not less than  $0,01L + 0,7$

for deck longitudinals and transverses: the head equivalent to cargo carried at a stowage rate of  $1,39 \text{ m}^3/\text{tonne}$ , but is not to be taken less than  $0,01L + 0,7$

for side frames: the distance from the midpoint of span to the deck at the side

for deck beams and girders: the head equivalent to cargo carried at a stowage rate of  $1,39 \text{ m}^3/\text{tonne}$ , but is not to be taken less than required by Table 3.5.1 in Pt 3, Ch 3

$l_e$  = effective length of stiffening member, in metres, see Pt 3, Ch 3,3

$s$  = spacing of frames, beams or longitudinals, in mm

$S$  = spacing or mean spacing of girders, transverses or floors, in metres

$Z$  = section modulus of stiffening member, in  $\text{cm}^3$ , see Pt 3, Ch 3,3.

#### 4.2 General

4.2.1 Bottom, side and deck transverses are to be connected in such a manner as to ensure continuity of the transverse ring system, and longitudinals are to be attached to transverses. In way of deck and bottom transverses, a deep web frame is to be fitted.

4.2.2 End connections of longitudinals at bulkheads are to provide adequate fixity and direct continuity of longitudinal strength.

4.2.3 Brackets at the top and bottom of side frames are to extend to the adjacent deck or bottom longitudinal to which they are to be attached.

4.2.4 In pontoons where truss arrangements, comprising top and bottom girders in association with pillars and diagonal bracing, are used in the support of the deck loads, the diagonal members are generally to have angles of inclination with the horizontal of about  $45^\circ$  and cross-sectional area of approximately 50 per cent of the adjacent pillar in accordance with Ch 1,4.4, with a head in accordance with 4.1.1.

4.2.5 Adequate support must be provided on the centreline for the loads imposed on the structure when the ship is in dry-dock.

#### 4.3 Longitudinal framing

4.3.1 The scantlings of bottom, side and deck longitudinals are to comply with the requirements of Table 5.4.1.

**Table 5.4.1 Longitudinal framing**

Position of longitudinals	Modulus, in $\text{cm}^3$
Bottom	* $Z = 11,0l_e^2sh \times 10^{-3}$
Side shell	* $Z = 8,0l_e^2sh \times 10^{-3}$
Deck	* $Z = 5,5l_e^2sh \times 10^{-3}$
* For the requirements for barges carrying liquid cargoes in bulk see Chapter 10	
NOTE The scantlings derived from above need not exceed the scantling requirements of Chapter 1 or Chapter 10, whichever is applicable.	

#### 4.4 Transverse framing

4.4.1 The scantlings of bottom and side frames and deck beams are to comply with the requirements of Table 5.4.2.

**Table 5.4.2 Transverse framing**

Position of member	Modulus, in $\text{cm}^3$
Bottom and side frames	* $Z = 9,5l_e^2sh \times 10^{-3}$
Deck beams	* $Z = 4,5l_e^2sh \times 10^{-3}$
* For the requirements for barges carrying liquid cargoes in bulk see Chapter 10	
NOTE The scantlings derived from above need not exceed the scantling requirements of Chapter 1 or Chapter 10, whichever is applicable.	

Barges and Pontoons

Part 4, Chapter 5

Sections 4, 5, 6 & 7

4.5 Primary supporting structure

4.5.1 Primary supporting members are to comply with the requirements of Table 5.4.3.

Table 5.4.3 Primary supporting structure

Position of member	Modulus, in cm <sup>3</sup>
Bottom transverse	* $Z = 11,0l_e^2Sh$
Side transverse	* $Z = 8,0l_e^2Sh$ (may be reduced by 5 per cent for vessels classed '100A1 extended protected water service')
Deck transverse	* $Z = 5,5l_e^2Sh$
Bottom girder	* $Z = 9,5l_e^2Sh$
Deck longitudinal girder	* $Z = 5,0l_e^2Sh$
	* For the requirements for barges carrying liquid cargoes in bulk see Chapter 10
NOTE The scantlings derived from above need not exceed the scantling requirements of Chapter 1 or Chapter 10, whichever is applicable.	

Section 7  
Watertight bulkheads

7.1 Collision bulkheads

7.1.1 Barges and pontoons are to have a collision bulkhead extending intact to the strength/weather deck and, in general, this is to be positioned as detailed in Table 5.7.1.

Table 5.7.1 Collision bulkhead position

Length $L$ , in metres	Distance of collision bulkhead aft of fore end of $L$ , in metres, see Fig. 5.1.1	
	Minimum	Maximum
$\leq 150$	$0,05L$	$0,05L + 4,5$
$> 150$	The lesser of: $0,05L$ or 10	$0,08L$

Section 5  
Strengthening of bottom forward

5.1 Application

5.1.1 The requirements for strengthening of bottom forward detailed in Pt 3, Ch 5 do not apply to barges or pontoons less than 50 m in length.

Section 6  
Bottom strengthening for loading  
and unloading aground

6.1 Application

6.1.1 For barges or pontoons intended to load or unload while aground, see Pt 3 Ch 9,13.

# Trawlers and Fishing Vessels

## Part 4, Chapter 6

Section 1

### Section

- 1 **General**
- 2 **Protection**
- 3 **Longitudinal strength**
- 4 **Deck structure**
- 5 **Shell envelope plating**
- 6 **Shell envelope framing**
- 7 **Watertight bulkheads**
- 8 **Stern ramp, and cruiser and transom sterns**
- 9 **Strengthening of bottom forward**

### ■ Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies to sea-going steel trawlers, stern trawlers and fishing vessels.

1.1.2 For the purpose of this Chapter, a fishing vessel is a ship used for fishing operations, but not equipped for trawling.

1.1.3 The scantlings and arrangements are to be as required by Chapter 1 except as otherwise specified in this Chapter. Consideration will be given to proposals for modified scantlings on vessels where  $L$  is less than 24 m.

#### 1.2 Assignment of load lines

1.2.1 The *International Convention on Load Lines, 1966* does not apply to trawlers and fishing vessels, but certain National Authorities may request the assignment of load lines for ships registered in their countries.

1.2.2 The Rules affecting the protection of openings and protection of crew, and particularly those contained in Pt 3, Ch 11 and Ch 12, may be modified to take account of National Regulations or practicabilities related to fishing operations.

#### 1.3 Class notations

1.3.1 In general, ships complying with the requirements of this Chapter will be eligible for one of the following classes:

- (a) **100A1 trawler**. This class will be assigned to side fishing trawlers.
- (b) **100A1 stern trawler**. This class will be assigned to stern fishing trawlers.
- (c) **100A1 fishing vessel**. This class will be assigned to fishing vessels, see 1.1.2.

1.3.2 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2 to which reference should be made.

#### 1.4 Information required

1.4.1 In addition to the information required by Pt 3, Ch 1,5, the position and arrangement of trawl gear and deck machinery and location of insulated compartments are to be indicated.

#### 1.5 Symbols and definitions

1.5.1 The Rule length,  $L$ , is the distance, in metres, on the classification waterline from the fore side of the stem to the after side of the rudder post, or to the centre of the rudder stock if there is no rudder post.  $L$  is to be not less than 96 per cent, and need not be greater than 97 per cent, of the extreme length on the classification waterline.

1.5.2 Breadth  $B$ , is the greatest moulded breadth, in metres.

1.5.3 Depth  $D$ , is measured, in metres, at the middle of the length,  $L$  from the base line to top of the deck beam at side on the uppermost continuous deck.

1.5.4 The classification waterline in single deck ships is the waterline taken perpendicular to the plane of the transverse bulkheads located at  $0,85D$  from the base line amidships, or at the maximum operational draught amidships, whichever is the greater. In two-deck ships, it is the waterline located at the maximum operational draught, but if this is unknown, it may be taken at 50 mm below the lower deck. If a load line is required by a National Authority, the classification waterline is the summer load waterline.

1.5.5 Keel line is the line parallel to the slope of the keel intersecting the top of the keel at amidships, or the line of intersection of the inside of shell plating with the keel where a bar keel is fitted.

1.5.6 Base line is a line parallel to the classification waterline and intersecting the keel line at amidships.

1.5.7 Draught  $T$ , is the distance in metres, between the classification waterline and the base line amidships.

1.5.8 The block coefficient  $C_b$  is to be taken at the classification waterline.

# Trawlers and Fishing Vessels

# Part 4, Chapter 6

Sections 1 to 5

1.5.9 The following symbols are also applicable to this Chapter:

- $k$  = material factor, see Ch 1, 1.5
- $l_e$  = effective length of stiffening member, in metres, see Pt 3, Ch 3,3
- $s$  = spacing of stiffeners, in mm
- $s_b = 470 + \frac{L}{0,6}$  with minimum limitation at ends as defined in Table 5.3.1 in Pt 3, Ch 5, for fore end structure and Table 6.3.1 in Pt 3, Ch 6, for aft end structure
- $s_1$  =  $s$ , but not less than  $s_b$
- $t$  = thickness of plating, in mm
- $Z$  = section modulus of stiffening member, in cm<sup>3</sup>, see Pt 3, Ch 3,3.

## Section 2 Protection

### 2.1 Protection of steelwork

2.1.1 Where wood sheathing is fitted, the material is to be of good quality, well seasoned and free from sapwood, and the thickness is to be not less than 65 mm. The plank widths should not normally exceed 150 mm. Thwartship planks are to be laid at the ends of deckhouses and at break of deck. Fastenings are to be sunk below the surface of the planking and covered with turned dowels, and the whole to be thoroughly bedded in a suitable composition. All weather decks are to be caulked and payed.

2.1.2 Where gutter waterways are fitted, the bar forming the inner edge of the waterway is to be not less than 7,5 mm thick.

2.1.3 Welded studs are to be not less than 9,5 mm diameter, and are to be coated with suitable composition before the planking is laid. Bolts used instead of studs may be 12,5 mm diameter galvanized. If the steel deck is penetrated for bolts, the deck is to be hose tested in accordance with Pt 3, Ch 1,8.

### 2.2 Protection of cargo

2.2.1 When an oil fuel bunker or double bottom carrying oil fuel, or a lubricating oil tank, is adjacent to a fish hold, the relevant requirements of Pt 6, Ch 3,4 are to be complied with.

2.2.2 Compartments used for the processing of fish, or for temporary storage during or while awaiting processing, need not comply with the requirements of 2.2.1, but the construction of the bulkheads, decks and insulation, if any, should be such as to minimize the risk of oil leakage.

## Section 3 Longitudinal strength

### 3.1 General

3.1.1 The longitudinal strength standard is to comply with the relevant requirements of Pt 3, Ch 4.

3.1.2 The requirements of Pt 3, Ch 4,8.3 regarding loading instruments are not applicable to trawlers and fishing vessels.

## Section 4 Deck structure

### 4.1 Deck plating

4.1.1 The thickness of deck plating is to be not less than that required by Ch 1,4. Under the trawl winch, windlass, mast, centre and side bollards and gallows, the plating thickness is to be not less than:

$$t = (0,04L + 7,5) \text{ mm}$$

where  $L$  is to be taken not less than 30 m.

4.1.2 When a raised deck is fitted, adequate scarfing is to be arranged at the step.

### 4.2 Factory deck beams

4.2.1 The section modulus of the beams of factory decks under fish handling spaces is to be not less than that required by Table 1.4.5(2) in Chapter 1, with  $h_2$  equal to 2 m, but extra strengthening may be required in way of heavy items of machinery or equipment.

## Section 5 Shell envelope plating

### 5.1 Shell plating

5.1.1 The thickness of shell plating is to be not less than that required by Ch 1,5 but in no case is it to be less than the following:

$$\begin{aligned} \text{For } L \leq 70 \text{ m} \quad t &= (5,5 + 0,033L) \sqrt{\frac{ks_1}{s_b}} \text{ mm} \\ \text{For } L > 70 \text{ m} \quad t &= (6,5 + 0,033L) \sqrt{\frac{ks_1}{s_b}} \text{ mm} \end{aligned}$$

5.1.2 For single deck side trawlers the thickness derived from the formulae in 5.1.1 is to be increased by 10 per cent.

# Trawlers and Fishing Vessels

# Part 4, Chapter 6

Sections 5 to 9

5.1.3 When nets or control wires are in contact with the ship's side, such as below the gallows in a side trawler, the side shell plating is to be increased by 40 per cent.

5.1.4 Where a bar keel is fitted, the breadth of the garboard strake is to be not less than 760 mm, and the thickness is to be 10 per cent greater than the bottom shell.

5.1.5 The thickness of the bottom shell plating is to be increased by 10 per cent where intercostal girders are not fitted.

5.1.6 For increase to sheerstrake at the break of a raised deck, see Ch 1,5.

5.1.7 Cope irons are to be fitted under gallows or any other area where excessive wear could occur.

## Section 6 Shell envelope framing

### 6.1 Transverse side framing

6.1.1 The section modulus of the side frames of single deck trawlers and fishing vessels need not be greater than 80 per cent of the modulus required by Ch 1,6, but in no case is the depth of the frame to be less than 60 mm. Where not specified the draught is to be taken as not less than  $0,85D$ .

6.1.2 For two deck trawlers and two deck fishing vessels and all vessels requiring a load line, the requirements of Ch 1,6 are to be complied with.

6.1.3 The section modulus of frames in the fore peak is to be the greater of the following:

- (a) 10 per cent greater than that required by Pt 3, Ch 5,4.
- (b)  $Z = (45D - 212) \text{ cm}^3$

6.1.4 The section modulus of frames in the aft end region is to be not less than that required by Pt 3, Ch 6,3.

6.1.5 Where frames are stopped at watertight flats they are to be bracketed.

## Section 7 Watertight bulkheads

### 7.1 Collision bulkheads

7.1.1 Consideration will be given to proposals for the collision bulkhead to be positioned further aft than  $0,08L$  from the fore end of the classification waterline, provided that bow damage will not result in excessive trim forward.

## Section 8 Stern ramp, and cruiser and transom sterns

### 8.1 Stern ramp

8.1.1 The thickness of plating of the stern ramp is to be not less than:

$$t = 0,025s \text{ mm or } 10 \text{ mm, whichever is the greater.}$$

8.1.2 The section modulus of stiffeners is to be not less than:

$$Z = 0,019s l_e^2 \text{ cm}^3$$

### 8.2 Cruiser and transom sterns

8.2.1 Cruiser and transom sterns are to have frames of the size required for peaks, and are to be additionally stiffened by web frames when required. The depth of plate floors is to be not less than that given in Ch 1,7, and the floors are to be associated with a suitable system of girders.

## Section 9 Strengthening of bottom forward

### 9.1 General

9.1.1 The requirements of Pt 3, Ch 5,1 are to be applied except when the forward draught contemplated for any sea-going condition is equal to or greater than  $0,03L$  in which case the bottom shell plating in the region to be strengthened may be taken as:

$$t = 0,00818s f L^{1/4} k^{1/2}$$

where the symbols are as defined in Table 5,1.1 in Pt 3, Ch 5. This thickness derivation may be adopted for both longitudinal and transverse framing.





# Bulk Carriers

## Part 4, Chapter 7

Section 1

## Section

- 1 **General**
- 2 **Materials and protection**
- 3 **Longitudinal strength**
- 4 **Deck structure**
- 5 **Shell envelope plating**
- 6 **Shell envelope framing**
- 7 **Topside tank structure**
- 8 **Double bottom structure**
- 9 **Hopper side tank structure**
- 10 **Bulkheads**
- 11 **Direct calculation**
- 12 **Steel hatch covers**
- 13 **Hatch coamings**
- 14 **Forecastles**

### Section 1 General

#### 1.1 General

1.1.1 This Chapter applies to sea-going self propelled ships, constructed generally with single deck double bottom, hopper side tanks and topside tanks and with single or double side skin construction in the cargo length area, and intended primarily for the carriage of bulk dry cargoes.

1.1.2 A 'bulk carrier of single side skin construction' is defined as a bulk carrier where one or more cargo holds are bound by the side shell only, or by two watertight boundaries, one of which is the side shell, which are less than 1000 mm apart.

1.1.3 The term 'bulk carrier of double side skin construction' is defined as a bulk carrier where all cargo holds are bound by two watertight boundaries, one of which is the side shell, which are greater than or equal to 1000 mm apart at any location within the hold length.


1.1.4 The 'ShipRight Procedures' for the hull construction of ships are detailed in Pt 3, Ch 16 and the classification notations and descriptive notes associated with these procedures are given in Pt 1, Ch 2,3.

1.1.5 The attention of Owners, Masters and Cargo Shippers is drawn to the IMO Code of Safe Practice for Solid Bulk Cargoes when shipping these cargoes. Attention is also drawn to any relevant statutory requirements of the National Authority of the country in which the ship is to be registered, and any special requirements of the Port Authorities at the ports of loading and discharge.

1.1.6 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2 to which reference should be made.

#### 1.2 Application

1.2.1 Single skin and double skin bulk carriers with length,  $L$ , greater than or equal to 90 m with structural configuration as shown in Fig. 7.1.1 are defined as '*CSR Bulk Carriers*' and are to comply with 1.4.



1.2.2 Single skin and double skin bulk carriers other than those described in 1.2.1 are defined as '*Non-CSR Bulk Carriers*' and are to comply with 1.5.

#### 1.3 General class notations

1.3.1 Class notations applicable to CSR bulk carriers are defined as follows:

- **CSR**  
Identifies the bulk carrier as being compliant with the *IACS Common Structural Rules for Bulk Carriers*;
- **ESP**  
Identifies the bulk carrier as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.3.12.

# Bulk Carriers

# Part 4, Chapter 7

Section 1

1.3.2 Class notations applicable to non-CSR bulk carriers are defined as follows:

- **Strengthened for heavy cargoes**  
For bulk carriers with scantlings complying with 8.2;
- **ESP**  
Identifies the bulk carrier as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.3.12;
- **ESN**  
Identifies the bulk carrier as having been assessed for enhanced survivability with respect to flooding. Scantlings and arrangements are to comply with 3.1.2, 8.8 and 10.4.

## 1.4 Class notation for CSR bulk carriers

1.4.1 In general, CSR bulk carriers less than 150 m in length are to comply with the requirements of 1.6, Pt 3, Ch 2 and the *IACS Common Structural Rules for Bulk Carriers* (CSR) and will be eligible for one of the following mandatory class notations:

- (a) **100A1 bulk carrier, CSR, {any holds may be empty}, ESP.** This class notation is normally assigned to a ship designed to carry dry bulk cargoes of cargo density 1,0 tonne/m<sup>3</sup> and above, with an approved arrangement of loaded holds such that any hold may be empty at the full loaded draught.
- (b) **100A1 bulk carrier, CSR, {holds a, b, ... may be empty}, ESP.** This class notation is normally assigned to a ship designed to carry dry bulk cargoes of cargo density 1,0 tonne/m<sup>3</sup> and above with specified holds empty at maximum draught.
- (c) **100A1 bulk carrier, CSR, ESP.** This class notation will be assigned to a ship designed to carry dry bulk cargoes of cargo density less than 1,0 tonne/m<sup>3</sup>.

1.4.2 In general, CSR bulk carriers equal to or greater than 150 m in length are to comply with the requirements of 1.6, Pt 3 Ch 2 and the *IACS Common Structural Rules for Bulk Carriers* (CSR) and will be eligible for one of the following mandatory class notations:

- (a) **100A1 bulk carrier, CSR, BC-A, {holds a, b, ... may be empty}, GRAB [X] ESP.** This class will be assigned for bulk carriers designed to carry dry bulk cargoes of cargo density 1,0 tonne/m<sup>3</sup> and above with specified holds empty at maximum draught.
- (b) **100A1 bulk carrier, CSR, BC-B, GRAB [X], ESP.** This class will be assigned for bulk carriers designed to carry dry bulk cargoes of cargo density 1,0 tonne/m<sup>3</sup> and above with all cargo holds loaded.
- (c) **100A1 bulk carrier, CSR, BC-C, ESP.** This class will be assigned for bulk carriers designed to carry dry bulk cargoes of cargo density less than 1,0 tonne/m<sup>3</sup> with all cargo holds loaded.

1.4.3 The following additional notations and annotations are to be provided giving further detailed description of limitations to be observed during operation as a consequence of the design loading condition applied during the design.

- **Notations:**  
**(maximum cargo density (in tonnes/m<sup>3</sup>))** For notations **BC-A** and **BC-B** if the maximum cargo density is less than 3,0 tonnes/m<sup>3</sup>;

**(no MP)** For all notations when the vessel has not been designed for loading and unloading in multiple ports in accordance with the conditions specified in *IACS Common Structural Rules for Bulk Carriers* (CSR) Ch 4,7.3.3;

**GRAB [X]** where the net thickness of inner bottom, lower strake of hopper tank sloping plate and transverse lower stool plating comply with *IACS Common Structural Rules for Bulk Carriers* (CSR) Ch 12,1 for **BC-A** and **BC-B**, see also CSR Ch 1,1;

- **Annotations:**  
(allowed combination of specified empty holds). For notation **BC-A**.

1.4.4 The 'Construction Monitoring' (CM) procedures detailed in the *ShipRight Procedures Manual*, published by LR, are mandatory for bulk carriers greater than 190 m in length.

1.4.5 Optional notations indicating compliance with specific requirements of Sections 3 to 14 on a voluntary basis may also be assigned.

## 1.5 Class notation for non-CSR bulk carriers

1.5.1 In general, non-CSR Bulk Carriers are to comply with the requirements of 1.5.2 to 1.5.7 and will be eligible for one of the following mandatory class notations:

- (a) **100A1 bulk carrier, ESP.**
- (b) **100A1 bulk carrier, strengthened for heavy cargoes, ESP.** This class notation will be assigned to a ship when the double bottom structure has been specially strengthened in accordance with the requirements of Table 7.8.1.
- (c) **100A1 bulk carrier, strengthened for heavy cargoes, {holds a, b, ... may be empty}, ESP.** This class notation is normally assigned to a ship which has been specially strengthened for heavy cargoes (see (b), so as to enable the ship to be fully loaded with an approved arrangement of empty holds, see also 1.3.5 and 1.4.3.
- (d) **100A1 bulk carrier, strengthened for heavy cargoes, {any holds may be empty}, ESP.** This class notation is normally assigned to a ship which has been specially strengthened for heavy and ore cargoes, with an approved arrangement of loaded holds such that any hold may be empty at the full loaded draught.

1.5.2 Plans and information are to be submitted in accordance with 1.7.

1.5.3 Requirements are also given for special strengthening for heavy cargoes, see 8.2.

1.5.4 The scantlings and arrangements of the cargo region are to be as specified in this Chapter in Sections 2 to 14. The requirements are intended to cover the midship region, but also apply, with suitable modification, to the taper regions forward and aft in way of cargo spaces.

# Bulk Carriers

# Part 4, Chapter 7

Section 1

1.5.5 The 'Structural Design Assessment' (SDA), 'Fatigue Design Assessment' (FDA) and 'Construction Monitoring' (CM) procedures detailed in the *ShipRight Procedures Manual*, published by LR, are mandatory for non-CSR bulk carriers greater than 190 m in length and for other non-CSR bulk carriers of abnormal hull form, or of unusual structural configuration or complexity see 1.1.5 and Section 11.

1.5.6 Where the class notation referred to in 1.5.1(d) is assigned such that any hold may be empty at the full draught the following items are to be considered and the corresponding requirements complied with:

- Longitudinal strength calculations are to be carried out for all the operational fully loaded, non-homogeneous, part loaded, heavy cargo conditions, and these conditions included in the approved Loading Manual, see Section 3. Envelopes of the still water bending moments and the shear forces covering these conditions are also to be submitted.
- The double bottom structure in each hold is to satisfy the requirements of 8.4.
- The arrangement and scantlings of cross-deck structure between the upper deck cargo hatchways, see 4.1.2.
- Transverse bulkheads in holds, see 10.1.4.
- For main cargo hatchway openings the requirements of 4.3.1 are to be complied with.

1.5.7 Where appropriate, other cargoes or particular loading arrangements will be included in the class notation. When the class notation referred to in 1.5.1(c) is to be assigned for other combinations of empty and loaded holds, for example where it is the intention to load fully any two adjoining holds with adjacent holds empty in sea-going or short voyage conditions, the longitudinal and local strength aspects will be specially considered, see also 4.1.2. In addition, permissible weights of cargo in each hold or pair of adjacent holds, plotted against ship's draught likely to be incurred, is to be included in the ship's approved Loading Manual.

1.5.8 The scantlings of structural items may be determined by direct calculation.

1.5.9 The additional requirements for bulk carriers for the alternate carriage of oil cargo and dry bulk cargo are given in Ch 9,11. When complying with the requirements of this Chapter, such ships may be excluded from all requirements and notations pertaining to vessels with length,  $L$ , greater than or equal to 150 m. The requirements of 1.5.5 are however to be complied with.

## 1.6 Information required for CSR bulk carriers

1.6.1 In addition to the plans and documents required by the CSR the following are to be submitted:

- Ice strengthening.
- Freeboard plan or equivalent showing freeboards and items relative to the conditions of assignment.
- In addition the supporting calculations given in Pt 3, Ch 1,5.2.3 are to be submitted.

## 1.7 Information required for non-CSR bulk carriers

1.7.1 In addition to the information and plans required by Pt 3, Ch 1,5, the following are to be submitted:

- Cargo loadings on decks, hatchways and inner bottom if these are to be in excess of Rule, see Pt 3, Ch 3,5.
- The maximum pressure head in service on tanks, also details of any double bottom tanks interconnected with hopper, and topside tanks.
- Details of the proposed depths of any partial fillings where water ballast or liquid cargo is intended to be carried in the holds.
- Details of loading arrangements where combinations of empty and loaded holds are envisaged, and where it is the intention to load fully any two adjoining holds with adjacent holds empty in sea-going or short voyage conditions.

1.7.2 Additional information required for bulk carriers of length,  $L$ , 150 m or above:

- The bulk cargo density to be used in the design homogeneous loading condition at scantling draught with all holds, including hatchways, being 100 per cent full.
- The maximum bulk cargo density the ship is designed to carry.
- The maximum bulk cargo weight to be carried in each hold.
- Tables or curves indicating the change of cargo hold volume as a function of height above moulded baseline.

## 1.8 Symbols and definitions

1.8.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:  $L$ ,  $B$ ,  $D$ ,  $T$  as defined in Pt 3, Ch 1,6

- $k_L$ ,  $k$  = higher tensile steel factor, see Pt 3, Ch 2,1
- $l$  = overall length of stiffening member, in metres, see Pt 3, Ch 3,3
- $l_e$  = effective length of stiffening member, in metres, see Pt 3, Ch 3,3
- $s$  = spacing of secondary stiffeners, in mm
- $t$  = thickness of plating, in mm
- $C$  = stowage rate, in  $\text{m}^3/\text{tonne}$ , as defined in Pt 3, Ch 3,5
- $I$  = inertia of stiffening member, in  $\text{cm}^4$ , see Pt 3, Ch 3,3
- $M_H$  = the actual cargo mass in a cargo hold corresponding to a homogeneously loaded condition at maximum draught
- $M_{Full}$  = the cargo mass in a cargo hold corresponding to cargo with virtual density (homogeneous mass/hold cubic capacity, minimum  $1,0 \text{ tonne}/\text{m}^3$ ) filled to the top of the hatch coaming.  $M_{Full}$  is in no case to be less than  $M_H$
- $M_{HD}$  = the maximum cargo mass allowed to be carried in a cargo hold according to design Loading conditions with specified holds empty at maximum draught
- $R$  =  $\sin \theta$
- $S$  = spacing, or mean spacing, of primary members, in metres

# Bulk Carriers

# Part 4, Chapter 7

Sections 1, 2 & 3

- $Z$  = section modulus of stiffening member, in  $\text{cm}^3$ , see Pt 3, Ch 3,3  
 $\rho$  = relative density (specific gravity) of liquid carried in a tank, and is not to be taken less than 1,025.  
 $\theta$  = roll angle, in degrees  
 $\sin \theta = \left( 0,45 + 0,1 \frac{L}{B} \right) \left( 0,54 - \frac{L}{1270} \right)$

## Section 2

### Materials and protection

#### 2.1 Materials and grades of steel

2.1.1 Materials and grades of steel are to comply with the requirements of Pt 3, Ch 2.

#### 2.2 Protection of steelwork

2.2.1 For the protection of steelwork, in addition to the requirements specified in Ch 1,2 and Pt 3, Ch 2,3 the requirements of 2.2.2 are to be complied with.

2.2.2 All internal and external surfaces of hatch coamings and hatch covers, and all internal surfaces of the cargo holds, except where excluded below, are to have an efficient protective coating (epoxy coating or equivalent) applied in accordance with the manufacturer's recommendations. In the selection of coating, due consideration is to be given to the intended cargo conditions in service. Areas which may remain uncoated are:

- The inner bottom plating.
- The hopper tank sloping plating between the intersection with the inner bottom plating and a line approximately 300 mm below the toe of the side shell frame end brackets.

2.2.3 For the notation '**strengthened for regular discharge by heavy grabs**', see Pt 3, Ch 9,13.

## Section 3

### Longitudinal strength

#### 3.1 General

3.1.1 Longitudinal strength calculations are to be made in accordance with the requirements given in Pt 3, Ch 4 and 1.5.6 and 1.5.7 where appropriate.

3.1.2 Longitudinal strength calculations for the flooded conditions defined in 3.2 to 3.4 are to be applied for bulk carriers which satisfy all of the following criteria:

- Single skin construction.
- Length,  $L$ , of 150 m or above.
- Intended for the carriage of cargoes having bulk densities of  $1,0 \text{ tonne/m}^3$  or above.

#### 3.2 Hull vertical bending stresses for flooded conditions

3.2.1 The maximum hull vertical bending stresses in the flooded condition at deck,  $\sigma_{Df}$ , and keel,  $\sigma_{Bf}$ , for use in Pt 3, Ch 4 are given by the following, using the appropriate combination of bending moments to give sagging and hogging stresses:

$$\sigma_{Df} = \frac{|M_{sf} + 0,8M_w| \times 10^{-3}}{Z_D} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$\sigma_{Bf} = \frac{|M_{sf} + 0,8M_w| \times 10^{-3}}{Z_B} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

$M_{sf}$  = maximum still water bending moment in the flooded condition, in  $\text{kN m}$  (tonne-f m), at the section under consideration, see 3.4

$M_w$  = design hull vertical wave bending moment, in  $\text{kN m}$  (tonne-f m), as defined in Pt 3, Ch 4,5 at the section under consideration

$Z_D, Z_B$  = actual hull section moduli, in  $\text{m}^3$ , at strength deck and keel respectively, at the section under consideration.

3.2.2 The maximum values of  $\sigma_{Df}$  and  $\sigma_{Bf}$  are to be used in Pt 3, Ch 4.

#### 3.3 Shear stresses for flooded conditions

3.3.1 The shear stress,  $\tau_{Af}$ , in the flooded condition to be used in Pt 3, Ch 4,6, is to be taken as:

$$\tau_{Af} = 100Az \frac{|Q_{sf}| + |0,8Q_w|}{I \delta_i} \text{ N/mm}^2$$

$$\left( \tau_{Af} = 10,2Az \frac{|Q_{sf}| + |0,8Q_w|}{I \delta_i} \text{ kgf/mm}^2 \right)$$

where

$Az$  = the first moment, in  $\text{cm}^3$ , about the neutral axis, of the area of the effective longitudinal members between the vertical level under consideration and the vertical extremity of the effective longitudinal members, taken at the section under consideration

$Q_{sf}$  = maximum hull still water shear force, in  $\text{kN}$  (tonne-f), in the flooded condition at the section under consideration

$Q_w$  = design hull wave shear force, in  $\text{kN}$  (tonne-f), as defined in Pt 3, Ch 4,6.3 at the section under consideration

$I$  = moment of inertia of the hull about the horizontal neutral axis, in  $\text{cm}^4$ , at the longitudinal section under consideration

$\delta_i$  = as defined in Pt 3, Ch 4,6.5.

#### 3.4 Flooded conditions

3.4.1 For the relevant loading conditions specified in Pt 3, Ch 4,5.3 and 5.4, each cargo hold is to be considered individually flooded up to the equilibrium waterline, except that cargo holds of double skin construction of not less than 1000 mm breadth at any location within the hold length, measured perpendicular to the side shell need not be

# Bulk Carriers

# Part 4, Chapter 7

Sections 3 & 4

considered flooded. The shear forces and still water bending moments are to be calculated for the most severe flooded conditions which will significantly load the ship's structure. Harbour conditions, docking conditions afloat, loading and unloading transitory conditions in port and loading conditions encountered during ballast water exchange need not be considered.

3.4.2 In calculating the weight of ingressed water into the cargo hold under consideration, the permeabilities and bulk densities given in Table 7.3.1 are to be used.

**Table 7.3.1 Permeability and bulk density factors**

Hold condition	Permeability (see Note 1)	Bulk density (tonne/m <sup>3</sup> )
Empty cargo space	0,95	—
Volume left in loaded cargo spaces above any cargo	0,95	—
Iron ore cargo	0,3 (see Note 2)	3,0
Cement	0,3 (see Note 2)	1,3
<b>NOTES</b> 1. Bulk cargo permeability is defined as the ratio of the voids within the cargo mass to the volume occupied by the cargo. 2. More specific information relating to the bulk cargo may be used where available, but permeabilities are not to be less than those given above. 3. For packed cargo, the actual density of the cargo is to be used with a permeability of zero.		

3.4.3 In calculating the strength of the ship's structure in the flooded condition it is to be assumed that the ship's structure will remain fully effective in resisting the applied loads.

## Section 4 Deck structure

### 4.1 General

4.1.1 Longitudinal framing is, in general, to be adopted outside line of openings. The arrangement of structure between hatches is to be such as to ensure continuity of the main deck structure to resist athwartship forces, and transverse stiffening is to be arranged. For and aft knuckles in cross deck strip plating between hatches should be arranged close to longitudinal girders or supported by brackets.

4.1.2 In the case of large bulk carriers with narrow deck strips between hatchways, or where it is the intention to fully load any two adjoining holds with adjacent holds empty for a sea-going condition or for bulk carriers to be classed 'any hold may be empty', the cross deck scantlings will be specially considered.

4.1.3 The requirements of Ch 1,4 are to be applied, together with the requirements of this Section.

4.1.4 The *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG), indicates recommended structural design configurations in critical areas, for the deck structure outside the line of openings and between hatches.

### 4.2 Deck plating

4.2.1 Where the difference between the thickness of plating inside and outside the line of main hatches exceeds 12 mm, a transitional plate of thickness equivalent to the mean of the adjacent plate thicknesses is to be fitted. The plate thickness outside the line of hatches is to be continued inboard between hatches beyond the end of the hatch corner curvature, to ensure that the chamfered plating is clear of the corner tangent point.

### 4.3 Main cargo hatchway openings

4.3.1 The following requirements apply to bulk carriers with vertically corrugated transverse bulkheads in cargo holds having one or more of the following characteristics:

- (a)  $B \geq 40$  m
- (b)  $\frac{b}{w} \geq 2,2$   
 $b$  = breadth of deck opening  
 $w$  = width of cross deck strip  
 $B$  = moulded breadth of ship
- (c) A structural arrangement where the hatch side coaming and deck opening are arranged inboard of the topside tank.
- (d) All bulk carriers to be classed 100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP.

4.3.2 The corners of main cargo hatchways in the strength deck are to be rounded with a radius not less than  $\frac{1}{20}$  of the breadth of the opening, with a maximum radius of 1000 mm.

4.3.3 Insert plates are to be fitted at the corners having a thickness not less than 25 per cent greater than the adjacent deck thickness outside the line of openings, with a minimum increase of 5 mm, see also 4.3.4.

The corner inserts are to be extended transversely into the cross deck plating for a minimum distance equal to  $0,075b$ , where  $b$ , is the breadth of deck opening.

4.3.4 For the extreme corners of the end hatchways of the cargo region furthest from amidships the thickness of the corner insert plates is to be not less than 60 per cent greater than the adjacent deck thickness outside the line of openings.

### 4.4 Deck supporting structure

4.4.1 For the scantlings of deck longitudinals and transverses in way of topside tanks, see 7.4 and 7.5, respectively.

## Bulk Carriers

## Part 4, Chapter 7

Sections 5 &amp; 6

## Section 5 Shell envelope plating

### 5.1 General

5.1.1 Longitudinal framing is, in general, to be adopted at the bottom, but special consideration will be given to proposals for transverse framing in this region. The side shell may be longitudinally or transversely framed.

5.1.2 The requirements of Ch 1,5 are to be applied together with the requirements of this Section.

### 5.2 Bottom shell

5.2.1 The thickness of the bottom shell plating below loaded holds may be required to be increased for local strength considerations.

### 5.3 Side shell

5.3.1 The thickness of the side shell plating may be required to be increased for shear forces to satisfy the requirements of 3.2.1.

5.3.2 The thickness of the side shell plating located between the hopper and topside tanks of single skin bulk carriers is to be not less than:

$$t = \sqrt{L} \text{ mm}$$

## Section 6 Shell envelope framing

### 6.1 Longitudinal stiffening

6.1.1 Side frames of all single skin bulk carriers with a hopper are to comply with 6.2 and 6.3.

6.1.2 Side frames and end brackets of all double skin bulk carriers are to comply with Ch 1,6.

6.1.3 Side frames and end brackets of other structural configurations will be specially considered.

6.1.4 The end connections for the longitudinal stiffening are to satisfy the requirements of Pt 3, Ch 10,3, see also 7.6.1 and 9.7.1.

6.1.5 The arrangements at the intersections of continuous secondary and primary members are to satisfy the requirements of Pt 3, Ch 10,5.2 and Ch 1,6.2.

### 6.2 Transverse stiffening

6.2.1 The modulus and inertia of main and topside tank frames in the midship region are to comply with the requirements given in Table 7.6.1. Arrangements of main frames in holds in association with web frames are not recommended in view of the vulnerability to cargo handling damage. Where such web frames are proposed the arrangements and scantlings will be specially considered.

**Table 7.6.1 Shell framing**

Location	Modulus, in cm <sup>3</sup>	Inertia, in cm <sup>4</sup>
(1) Main frames in dry cargo holds	$Z = 3,50skh_{T1}H^2 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(2) Main frames in cargo holds used for water ballast	The greater of the following: (a) $Z = 1,15 \times \text{modulus given in (1)}$ (b) $Z = 6,7skh_4H^2 \times 10^{-3}$	$I = \frac{3,2}{k} HZ$
(3) Transverse frames in topside wing tanks	The greater of the following: (a) $1,15 \times Z$ as given in location (1) of Table 1.6.2 in Chapter 1 (b) As required by 7.3.1 for the sloped bulkhead stiffeners	$I = \frac{3,2}{k} HZ$
Symbols		
<p><math>D, T, s, k</math> as defined in 1.7.1  <math>h_{T1}</math> = head, in metres, at middle of <math>H</math>  <math>= C_w \left(1 - \frac{h_6}{D-T}\right) F_{\lambda}</math>, in metres, for frames where the mid-length of frame is above the summer load waterline,  <math>\left(1 - \frac{h_6}{D-T}\right)</math> is not to be taken less than 0,7  <math>= \left(h_6 + C_w \left(1 - \frac{h_6}{2T}\right)\right) F_{\lambda}</math>, in metres, where the mid-length of frame is below the summer load waterline</p>		
<p><math>h_4</math> = head, in metres, measured from the middle of <math>H</math> to the deck at side, or half the distance from the middle of <math>H</math> to the top of the overflow, whichever is greater.  <math>h_6</math> = vertical distance in metres, from the summer load waterline at draught <math>T</math> to the mid-length of <math>H</math>  <math>C_w</math> = a wave head, in metres  <math>= 7,71 \times 10^{-2} L e^{-0,0044L}</math>  where <math>e</math> = base of natural logarithms 2,7183  <math>F_{\lambda} = 1,0</math> for <math>L \leq 200</math> m  <math>= (1,0 + 0,0023(L - 200))</math> for <math>L &gt; 200</math> m  <math>H</math> = length overall of frame, in metres, but is to be taken not less than 2,5 m</p>		

# Bulk Carriers

# Part 4, Chapter 7

Section 6

6.2.2 Main frames in the cargo and ballast holds are to have a web thickness not less than:

- In general:  
 $t_{\min} = 7 + 0,03L$  mm,  
or 13 mm whichever is the lesser
- In the foremost hold:  
 $t_{\min} = 1,15 (7 + 0,03L)$  mm,  
or 15 mm whichever is the lesser

where  $L$  is the Rule length, in metres.

6.2.3 The web depth to thickness ratio of the frames is not to be greater than:

$60\sqrt{k}$ , for symmetric sections

$50\sqrt{k}$ , for asymmetric sections

The breadth to thickness ratio of the flange outstand is not to be greater than:

$10\sqrt{k}$

6.2.4 The upper and lower end brackets of the main frames in the cargo and ballast holds are to satisfy the requirements of 6.2.5 to 6.2.14 inclusive, based on the mild steel section modulus  $Z$  in  $\text{cm}^3$ , derived from Table 7.6.1, or the equivalent mild steel section modulus for higher tensile steel frames.

6.2.5 The lengths of the arms of the brackets, measured as shown in Fig. 7.6.1, are not to be less than:

(a) Frame connection to hopper tank.

Athwartship arm:

Dry cargo hold  $l_a = 32,43\sqrt{Z}$  mm

Ballast hold  $l_a = 32,43(\sqrt{Z} - 7,5)$  mm

Vertical arm:

Dry cargo hold  $l_v = 27,6\sqrt{Z}$  mm

Ballast hold  $l_v = 27,6(\sqrt{Z} - 9,0)$  mm

(b) Frame connection to topside tank

Athwartship arm:

Dry cargo hold  $l_a = 30,0\sqrt{Z}$  mm

Ballast hold  $l_a = 30,0(\sqrt{Z} - 9,0)$  mm

Vertical arm:

Dry cargo hold  $l_v = 26,85\sqrt{Z}$  mm

Ballast hold  $l_v = 26,85(\sqrt{Z} - 11,0)$  mm

In no case are the bracket arm lengths to be taken less than  $0,125H$ , where  $H$  is as defined in Table 7.6.1.

6.2.6 The section modulus of the frame and bracket or integral bracket, and associated shell plating at the location marked  $Z_a$  in Fig. 7.6.1 is to be not less than  $2,0Z$ .

In addition, the minimum depth of the frame and bracket or integral bracket at the location indicated in Fig. 7.6.1 is to be not less than  $1,5d$ .

6.2.7 The upper and lower integral or separate brackets are to have a web thickness not less than the as built web thickness of the side frame. In addition, the lower bracket thickness is to be not less than:

$t = t_{\min} + 2$  mm, where  $t_{\min}$  is derived from 6.2.2

The toes of the brackets are to be designed to avoid notch effects by making the upper and lower toes concave or otherwise tapering them off, see also Pt 3, Ch 10,5.1.7.

6.2.8 Except as indicated in 6.2.9, frames are to be fabricated symmetrical sections with integral upper and lower brackets. The side frame face plate is to be curved (not knuckled) at the connection with the end brackets. The radius of curvature,  $r$ , is to be not less than:

$$r = \frac{0,4b_f^2}{t_f} \text{ mm}$$

where

$b_f$  = breadth of the bracket face plate, in mm

$t_f$  = thickness of the bracket face plate, in mm

The brackets are to be arranged with soft toes and the frame section face bar tapered symmetrically to the toes with a taper rate not exceeding 1 in 3. Where the free edge of the bracket is hollowed out, it is to be stiffened or increased in size to ensure that the section modulus of the bracket through the throat is not less than that of the required straight edged bracket.

6.2.9 In ships of length,  $L$ , less than 190 m, mild steel fabricated frames may be asymmetric and fitted with separate brackets. Brackets are to be arranged with soft toes. The free edges of the brackets are to be stiffened as follows:

(a) Where a flange is fitted, its breadth,  $b_f$ , is to be not less than:

$$b_f = 40 \left( 1 + \frac{Z}{1000} \right) \text{ mm}$$

or 50 mm, whichever is the greater.

The flange is to be tapered at the ends with a taper rate not exceeding 1 in 3.

(b) Where the edge is stiffened by a welded face flat, the cross-sectional area of the face flat is to be not less than:

(i)  $0,009b_f t$   $\text{cm}^2$  for offset edge stiffening

(ii)  $0,014b_f t$   $\text{cm}^2$  for symmetrically placed stiffening where

$t$  = web thickness of bracket, in mm


The face plate is to be tapered at the ends with a taper rate not exceeding 1 in 3.

6.2.10 For mild steel construction with separate brackets where the frames are lapped on to the bracket, the length of the overlap is to be adequate to provide for the required area of welding to achieve equivalent strength.

6.2.11 Double continuous welding is to be adopted for the connections of frames and brackets to side shell, hopper and topside tank plating and web to face plates. For this purpose, the following weld factors are to be adopted:

- 0,44 in Zone 'a' and
- 0,40 in Zone 'b', see Fig. 7.6.1.

Where the hull form is such that an effective fillet weld cannot be made, edge preparation of the web of the frame and bracket may be required, in order to ensure the required efficiency of the weld connection.



**Fig. 7.6.1 Diagrammatic arrangement of end brackets**



# Bulk Carriers

## Part 4, Chapter 7

### Section 6

6.2.12 Continuity of the frames is to be maintained by supporting brackets, see Fig. 7.6.2, in the topside and hopper tanks. The design of end connections and their supporting structure is to be such as to provide adequate resistance to rotation and displacement of the joint. For this purpose, in the hopper and topside tanks, the thickness of the supporting brackets (which must align with the hold main frame brackets) is to be not less than the following:

(a) Lower brackets (In hopper tank):

$$t = t_{\min} + 0,5 \text{ mm, where } t_{\min} \text{ is derived from 6.2.2, or}$$

$$t = 9,0 \text{ mm}$$

whichever is the greater.


(b) Upper brackets (in topside tank):

$$t = t_{\min}, \text{ where } t_{\min} \text{ is derived from 6.2.2, or}$$

$$t = 9,0 \text{ mm}$$

whichever is the greater.

The size and arrangement of stiffening of the supporting brackets will be specially considered. Where the toe of the hold frame bracket is situated on or in close proximity to the first longitudinal from the shell of the hopper or topside tank sloped bulkheads, the supporting brackets are to be extended to the next longitudinal. This extension is to be achieved by enlarging the supporting bracket or by fitting an intercostal flat bar stiffener the same depth as the longitudinal and connected to the webs of the longitudinals.




**Fig. 7.6.2**

**Supporting brackets in topside and hopper tanks**

6.2.13 The requirements are to be maintained throughout the cargo hold region. However, in the forward and aft cargo holds where the shape becomes finer because of the ship form, increased requirements may be necessary and each case will be specially considered.

6.2.14 In way of the foremost hold, side frames of asymmetric section are to be effectively supported by intercostal brackets, see Fig. 7.6.3.



**Fig. 7.6.3**


**Typical arrangement of intercostal brackets supporting asymmetric side shell frames in No. 1 hold**

6.2.15 The hold side shell frame adjacent to the collision bulkhead is to be suitably strengthened. As an alternative, at least two supporting structures are to be fitted which align with the forepeak stringers or flats, see Fig. 7.6.4. The supporting structures are to have adequate cross sectional shear resisting area at their connections to the hold frame.

6.2.16 Detail design guidelines for connection of side shell frames to hopper and topside tank plating are shown in the *ShipRight FDA Procedure, Structural Detail Design Guide (SDDG)*.

### 6.3 Primary supporting structure

6.3.1 For the requirements for primary supporting structure, see 7.5 and 9.6.



**Fig. 7.6.4**

**Hold frame supporting structures at fore end of No. 1 cargo hold**

## Section 7

### Topside tank structure

#### 7.1 General

7.1.1 Requirements are given in this Section for longitudinal or transverse framing in the topside tank, but, in general, the deck is to be longitudinally framed. The sloped bulkhead is to be of plane construction with the associated stiffening arranged inside or outside the tank.

7.1.2 The buckling requirements of Pt 3, Ch 4,7 are to be satisfied.

7.1.3 Recommended examples of structural design configurations around the transverse ring web of the topside tank can be seen in the *ShipRight FDA Procedure, Structural Detail Design Guide (SDDG)*.

#### 7.2 Bulkhead plating

7.2.1 The thickness of the sloped bulkhead, tank end bulkhead, and diaphragm, if fitted, is to be the greater of the following:

- (a) For watertight bulkheads, the thickness,  $t$ , as derived from Table 1.9.1 in Chapter 1 for a deep tank bulkhead using a head,  $h_4$ , in metres determined as follows:  
 $h_4 = h_o \cos\theta + Rb_1$  or  
 = the greater of the distance from a point one-third of the height of the plate above its lower edge to the top of the tank, or half the distance to the top of the overflow  
 whichever is the greater, or

- (b)  $t = 7,5 \text{ mm}$

In no case, however, is the thickness of the sloped bulkhead and diaphragm to be taken less than:

$$t = 0,012s \text{ mm, or}$$

$$t = 0,012s \sqrt{\frac{F_D}{k_D}} \text{ mm}$$

whichever is the greater

where

$k_D$  = the higher tensile steel factor equal to  $k_L$  value for deck material

$F_D$  = as defined in Pt 3, Ch 4,5.6

$R$  = as defined in 1.7.1

$h_o$  = the vertical distance, in metres, from a point one third of the height of the plate from its lower edge to the highest point of the tank excluding hatchway

$b_1$  = the larger horizontal distance, in metres, from the tank corner at top of tank either side to point of plate under consideration.

7.2.2 The thickness of the top strake of the sloped bulkhead, including the vertical plate attached to deck, may be required to be increased to form an effective girder below the deck. In general, this plate is to be not less in thickness than 60 per cent of the thickness of the deck plate outside the line of openings nor less than:

- (a)  $t = 0,018s \text{ mm, or}$

$$(b) t = 0,018s \sqrt{\frac{F_D}{k_D}} \text{ mm}$$

whichever is the greater.

7.2.3 The thickness of the transverse wash bulkhead, where fitted, is to be not less than:

$$t = 0,012s \text{ mm or } 7,5 \text{ mm}$$

whichever is the greater.

#### 7.3 Bulkhead stiffeners

7.3.1 The section modulus of longitudinal or transverse stiffeners on the sloped bulkhead or watertight diaphragms, if fitted, is to be not less than:

$$Z = 0,01skh_4 l_e^2 \text{ cm}^3$$

where

$$h_4 = h_o \cos\theta + Rb_1$$

= the greater of the distance, in metres, from the middle of the effective length to the top of the tank, or half the distance to the top of the overflow, or  
 = 1,5 m  
 whichever is the greatest

$R$  = as defined in 1.7.1

$h_o$  = the vertical distance, in metres, from the mid-point of span of the stiffener to the highest point of the tank excluding hatchway

$b_1$  = the larger horizontal distance, in metres, from the tank corner at top of tank, either side to midpoint of span.

7.3.2 Where the bulkhead stiffening is fitted on the hold side of the sloped bulkhead, suitable arrangements are to be made to prevent tripping.

# Bulk Carriers

# Part 4, Chapter 7

Sections 7 & 8

7.3.3 The scantlings of stiffeners on tank end bulkheads are to be not less than those given in Table 1.9.1 in Chapter 1 for deep tanks, using  $h$  as defined in 7.3.1.

7.3.4 The section modulus of stiffeners of non-watertight fore and aft diaphragms, or transverse wash bulkheads is to be not less than 50 per cent of that required by 7.3.3. The stiffeners are to be bracketed at both ends.

7.3.5 Tank end bulkheads are generally to be in line with the main hold bulkheads.

## 7.4 Shell and deck structure

7.4.1 The scantlings of shell and deck longitudinals are to comply with 7.3.1. The scantlings must also satisfy the requirements of Chapter 1, *see also* 7.6.1.

7.4.2 The scantlings of side shell frames are to comply with 6.2.

## 7.5 Primary supporting structure

7.5.1 The section modulus and inertia of deck, shell and bulkhead transverses or stringers are to be not less than:

$$Z = 7,5 k S h l_e^2 \text{ cm}^3$$

$$I = \frac{2,5}{k} l_e Z \text{ cm}^4$$

using  $h$  as defined in 7.3.1. The scantlings of shell and deck members must also satisfy the requirements of Chapter 1 for dry cargo holds.

7.5.2 Primary transverse members are, in general, to be spaced not more than 3,8 m apart where the length,  $L$ , is 100 m or less, and  $(0,006L + 3,2)$  m apart for lengths greater than 100 m.

7.5.3 Transverses are to be arranged in line with the primary structure at ends of hatchways, or equivalent scarfing arranged. Where the sloped bulkhead or side shell is transversely framed, arrangements are to be made to ensure effective continuity at the ends of the deck transverse.

7.5.4 Where non-watertight transverse diaphragms are arranged instead of open transverses, the thickness of plating is to be in accordance with 7.2.3. The diaphragms are to be efficiently stiffened.

## 7.6 Structural details

7.6.1 Bracket/diaphragm connections at the bottom of the topside tank are to be of sufficient size and thickness to provide effective rigidity, and care is to be taken to ensure alignment with brackets at the heads of the side frames in the holds, *see also* 6.2.12. The shell and sloped bulkhead longitudinals supporting the diaphragms are to be derived using the span taken between transverses.

7.6.2 For ships where  $L \geq 300$  m a fore and aft diaphragm extending vertically from the deck to the sloping plating of the topside tank is to be arranged at about the half-width of the tank.

7.6.3 Where longitudinal framing is fitted to the side shell, a bracket may be required in way of a rounded gunwale, approximately halfway between transverses and extending to the adjacent shell and deck longitudinal.

## Section 8 Double bottom structure

### 8.1 General

8.1.1 The double bottom is, in general, to be longitudinally framed, but special consideration will be given to proposals for a transverse framing system.

8.1.2 The requirements of Ch 1,8 are to be applied, together with the requirements of this Section, *see also* 2.2.3.

8.1.3 Where the double bottom tanks are interconnected with double skin side tanks or combined hopper and top side tanks, the double bottom scantlings are also to satisfy the requirements of Table 7.8.1(3)(c), (3)(d), (4)(c) and (4)(d) for ballast holds, and (3)(c) and (4)(c) in way of dry cargo holds, *see also* Ch 1,6.2.

8.1.4 The requirements given in 8.8 are to be applied to bulk carriers which satisfy the following criteria:

- Single skin construction.
- Length,  $L$ , of 150 m or above.
- Intended for the carriage of cargoes having bulk densities of 1,0 tonne/m<sup>3</sup> or above.

8.1.5 For all bulk carriers where bulk cargoes are discharged by grabs the maximum recommended unladen weight of the grab corresponding to the approved inner bottom plating thickness is to be calculated using the following formulae:

$$P = \left( \frac{s}{k} \right)^2 \frac{10^d}{1,775} \text{ tonnes}$$

where

$$d = \frac{40,875 (t - 1,5) \sqrt{k} + 344,5}{s} - 5,7633$$

$P$  = unladen grab weight, in tonnes

$s$  = spacing of inner bottom longitudinal, in mm

$k$  = higher tensile steel factor as defined in 1.7.1

$t$  = thickness of inner bottom plating, in mm

The maximum recommended unladen weight of the grab rounded up to the next tonne above, is to be recorded in the Loading Manual (*see also* Pt 3, Ch 4,8.2.4(e)) and does not preclude the use of heavier grabs. It is intended as an indication to the Builders, Owners and operators of the increased risk of local damage and the possibility of accelerated diminution of the plating thickness if grabs heavier than this are used regularly to discharge cargo.

**Bulk Carriers****Part 4, Chapter 7**

Section 8

**Table 7.8.1 Strengthening for heavy cargo requirements**

Symbols	Item	Requirement
$L, l_e, D, T, s, S, k, Z,$ and $t$ as defined in 1.7.1 $C_1 =$ a factor varying from 1,0 at $\frac{D}{2}$ to $\frac{75}{225 - 150F_B}$ at base line of ship $C =$ stowage rate, in m <sup>3</sup> /tonne, and is defined as the volume of the hold excluding the volume contained within the depth of the cargo hatchway divided by the weight of cargo stowed in the hold. The value is not to be taken greater than 0,865 $F_B$ as defined in Pt 3, Ch 4,5.6 $R$ and $\theta$ as defined in 1.5.1 $H =$ height from tank top, at position under consideration, to deck at side amidships, in metres $Y_1 =$ distance from $\frac{D}{2}$ to tank top, in metres $h_o =$ for plating and stiffeners the vertical distance, in metres, from the inner bottom to the highest point of the tank excluding hatchway $b_1 =$ the larger horizontal distance, in metres, from the tank corner at top of tank either side to the point of plate or stiffener under consideration	(1) Double bottom floors	The spacing of floors, generally, is not to exceed 2,5 m. Scantlings are to comply with the requirements of Ch 1,8.5
	(2) Double bottom side girders	The spacing of side girders, generally is not to exceed 3,7 m. Scantlings are to comply with requirements of Ch 1,8.3
	(3) Inner bottom plating, see Note 3	<p>The thickness of the inner bottom plating in the holds is to be not less than required by the greatest of the following:</p> <p>(a) <math>t = 0,00136 (s + 660) \sqrt[4]{k^2 L T + 5}</math> mm, or</p> <p>(b) <math>t = 0,00455 s \sqrt{\frac{Hk}{C}}</math> mm, or</p> <p>(c) Where the double bottom tanks are interconnected with double skin side tanks or combined hopper and topside tanks the scantlings are also to satisfy the requirements for deep tanks in Table 1.9.1(b) in Chapter 1, with the load head <math>h_4 = h_o \cos \theta + Rb_1</math> m</p> <p>(d) In way of ballast holds the scantlings are also to satisfy the requirements for deep tanks in Table 1.9.1 in Chapter 1, with the load head <math>h_4</math>, in metres, measured to the deck at centre, but see also Pt 3, Ch 9,13 if protection against heavy grabs is desired</p>
	(4) Inner bottom longitudinals, see Notes 1 and 2	<p>The section modulus of inner bottom longitudinals is to be not less than the greatest of the following:</p> <p>(a) <math>Z = 85</math> per cent of the Rule value for bottom longitudinals as given in Table 1.6.1(b) in Chapter 1, or</p> <p>(b) <math>Z = \frac{0,0083s l_e^2 H C_1 k}{\left(1 - 0,233 \frac{Y_1}{D}\right) C}</math> cm<sup>3</sup>, or</p> <p>(c) Where the double bottom tanks are interconnected with double skin side tanks or combined hopper and topside tanks <math>Z = 0,0073sk h_4 l_e^2</math> cm<sup>3</sup> where <math>h_4 = h_o \cos \theta + Rb_1</math> m <math>Z</math> is not to be less than the requirements for deep tanks in Table 1.9.1 in Chapter 1, with the load head <math>h_4</math>, in metres, measured to the highest point of the topside tank, or side tank, or</p> <p>(d) In way of ballast holds the section modulus of the longitudinals is to be not less than required for deep tanks in Table 1.9.1 in Chapter 1, with the load head <math>h_4</math>, in metres measured to the deck at centre</p>
<b>NOTES</b> 1. If plate girders are fitted alternately with built or rolled sections, the section modulus as given in (4)(b) may be reduced by 10 per cent. 2. Consideration will be given to the fitting of struts in way of double bottom tanks in ships with homogeneous loading. The arrangement and scantlings are, in general, to be confirmed by direct calculation. 3. See also 8.1.5 for the maximum recommended unladen weight of the grab corresponding to the approved inner bottom plating thickness.		

8.1.6 Detail design guidelines for stiffeners connecting inner bottom and bottom longitudinals are shown in the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG).

**8.2 Carriage of heavy cargoes**

8.2.1 When the notation 'strengthened for heavy cargoes' is to be assigned, the requirements of Table 7.8.1 are to be complied with.

**8.3 Carriage of heavy cargoes with specified or alternate holds empty**

8.3.1 For ships strengthened for heavy cargoes and having a class notation permitting specified or alternate holds to be empty, the requirements of 8.2.1 are to be complied with. In addition the scantlings and arrangements of the primary structure are to be confirmed by additional calculations, see 11.1.

# Bulk Carriers

# Part 4, Chapter 7

Section 8

## 8.4 Ships to be classed '100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP'


8.4.1 For ships to be classed '100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP', the requirements of 8.2.1 and 8.3.1 are to be complied with. In addition the value for C, the stowage rate in m<sup>3</sup>/tonne, as defined in Table 7.8.1, is not to be taken greater than 0,60 for each hold.

## 8.5 Ballast ducts

8.5.1 Where ballast ducts are arranged in lieu of suction and/or filling pipes, the scantlings will be approved as suitable for a specified equivalent static head of water. This head must not be exceeded in service, and details of methods to ensure this are to be submitted. The continuity of the floors is to be maintained in way of the ducts.

## 8.6 Structural details in way of double bottom tank and hopper tank knuckle

8.6.1 In all dry holds where the double bottom tank and hopper tank knuckle is of radiused construction and the floor spacing is 2,5 m or greater brackets as shown in Fig. 7.8.1 are to be arranged mid-length between floors in way of the intersection. The brackets are to be attached to the adjacent inner bottom and hopper longitudinals. The thickness of the brackets is to be in accordance with Ch 1,8.5.3 but need not exceed 15 mm. This requirement does not apply where the double bottom tank and hopper tank knuckle is of welded construction.



8.6.2 In way of floodable holds, two intermediate bracket arrangements, as shown in Fig. 7.8.1, are to be provided in all cases where the hopper to double bottom knuckle is radiused and are, in general, to be located at each frame space. Where the double bottom tank and hopper tank knuckle is of welded construction, a single intermediate bracket arrangement, as shown in Fig. 7.8.1, is to be provided only when the floor spacing is greater than 2,5 m.

8.6.3 The connections at the intersection are to be as follows:

- Where of welded construction the corner scallops in floors and transverses are to be omitted, or closed by welded collars where arranged for purposes of construction. In such cases to ensure satisfactory welding of the collars the radius of the scallops should not be less than 150 mm, see Fig. 7.8.2(a). Alternatively the scallop may be retained on the hopper tank side provided gusset plates are arranged in line with the inner bottom plating, see Fig. 7.8.2(b).
- Where of radiused construction the corner scallops are to be omitted, and full penetration welding arranged locally for the connection to the inner bottom plating. The centre of the flange is not to be greater than 70 mm from the side girder, see Fig. 7.8.2(c).

8.6.4 Detail design guidelines for the connection of hopper tank sloping plating to inner bottom plating are shown in the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG).


## 8.7 Combined double bottom/hopper tank and topside tank

8.7.1 Where a double bottom/hopper tank is interconnected with a topside tank the dimensions of the connecting trunks or pipes, and the air/overflow pipe(s) and the type of closing appliance are to comply with the requirements of Pt 5, Ch 13,10.10.

## 8.8 Allowable hold loading in the flooded condition

8.8.1 The requirements of this sub-Section are to be applied as defined in 8.1.4.

8.8.2 The maximum load which may be carried in each cargo hold in combination with flood water is to be determined for the most severe homogeneous, non-homogeneous and packed cargo conditions contained in the Loading Manual. The maximum density of cargo intended to be carried in each condition is to be used.



**Fig. 7.8.2 Connection at intersection of double bottom and hopper**

# Bulk Carriers

# Part 4, Chapter 7


Section 8

8.8.3 The ship is to be assumed immersed to the draught,  $T_F$ , in metres, in way of the flooded cargo hold under consideration. The flooding head,  $h_f$ , see Fig. 7.8.3, is to be taken as the distance, in metres, measured vertically with the ship in the upright position, from the inner bottom to position,  $d_f$ , in metres, from the base line given by:

- (a) In general:
  - (i)  $d_f = D$  for the foremost hold
  - (ii)  $d_f = 0,9D$  for other holds
- (b) For ships less than 50 000 tonnes deadweight with Type B freeboard:
  - (i)  $d_f = 0,95D$  for the foremost hold
  - (ii)  $d_f = 0,85D$  for other holds

where

$D$  = distance, in metres, from the base line to the freeboard deck at side amidships.



**Fig. 7.8.3 Loading**

8.8.4 For this application, the double bottom is defined as the structure bounded by the transverse bulkhead lower stools (or bulkhead plating if no lower stools are fitted) and the hopper sides. The floors and girders immediately in way of these structures are excluded.

8.8.5 The determination of shear strength required for the permissible load assessment in 8.8.9, is to be performed using the net plate thickness,  $t_{net}$ , for the floors and girders:

$$t_{net} = t - t_c$$

where

- $t$  = as built thickness, in mm  
 $t_c$  = thickness deduction for corrosion, in mm, generally to be taken as 2,5 mm.

8.8.6 Shear capacity of the double bottom is defined as the sum of the shear strengths for:

- (a) all the floors adjacent to both hoppers, less one half the strength of the floors adjacent to each lower stool (or transverse bulkhead if no lower stool is fitted), see Fig. 7.8.4, and
- (b) all the girders adjacent to the lower stools (or transverse bulkheads if no lower stool is fitted).

Where a girder or floor terminates without direct attachment to the boundary stool or hopper side girder, its shear capacity is to include only that for the effectively connected end.

8.8.7 The shear strengths,  $S_{f1}$ , of floors adjacent to hoppers and,  $S_{f2}$ , of floors in way of openings in bays nearest to the hoppers, are as follows:

$$S_{f1} = 0,001 A_f \tau_p / \eta_1 \text{ kN (tonne-f)}$$

$$S_{f2} = 0,001 A_{f,h} \tau_p / \eta_2 \text{ kN (tonne-f)}$$

where

- $A_f$  = net sectional area, in mm<sup>2</sup>, of floor panel adjacent to hopper  
 $A_{f,h}$  = net sectional area, in mm<sup>2</sup>, of floor panel in way of opening in the bay closest to hopper  
 $\eta_1 = 1,10$   
 $\eta_2 = 1,20$  generally  
 = 1,10 where appropriate reinforcement is fitted in way of the opening  
 $\sigma_0$  = specified minimum yield stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)  
 $\tau_p$  = permissible shear stress, to be taken equal to the lesser of:

$$\tau_0 = \frac{\sigma_0}{\sqrt{3}} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{) and}$$

$$\tau_c = \frac{162 \sigma_0^{0,6}}{\left(\frac{s_1}{t_{net}}\right)^{0,8}} \text{ N/mm}^2$$

$$\left( \tau_c = \frac{65 \sigma_0^{0,6}}{\left(\frac{s_1}{t_{net}}\right)^{0,8}} \text{ kgf/mm}^2 \right)$$

where

- $s_1$  = spacing of stiffening members, in mm, for the panel under consideration  
 $t_{net}$  = net thickness, in mm, of the panel under consideration.

For floors adjacent to the stools (or bulkhead plating if no lower stools are fitted),  $\tau_p$  may be taken as  $\frac{\sigma_0}{\sqrt{3}}$  N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).


8.8.8 The shear strengths  $S_{g1}$ , of girders adjacent to transverse bulkhead lower stools (or transverse bulkheads if no lower stools are fitted) and,  $S_{g2}$ , of girders in way of the largest openings in bays nearest to the lower stools (or transverse bulkheads if no lower stools are fitted), are as follows:

$$S_{g1} = 0,001 A_g \tau_p / \eta_1 \text{ kN (tonne-f)}$$

$$S_{g2} = 0,001 A_{g,h} \tau_p / \eta_2 \text{ kN (tonne-f)}$$

where

- $A_g$  = net sectional area, in mm<sup>2</sup>, of the girder adjacent to transverse bulkhead lower stool (or transverse bulkhead, if no lower stool is fitted)  
 $A_{g,h}$  = net sectional area, in mm<sup>2</sup>, of the girder in way of the largest openings in the bays closest to the transverse bulkhead lower stool (or transverse bulkhead if no lower stool is fitted)  
 $\eta_1 = 1,10$   
 $\eta_2 = 1,15$  generally  
 = 1,10 where appropriate reinforcement is fitted in way of the opening.



**Fig. 7.8.4 Double bottom structure**

8.8.9 The permissible cargo hold loading,  $W_p$ , is given by:

$$W_p = g \rho_c V / F_c \text{ kN}$$

$$(W_p = \rho_c V / F_c \text{ tonne-f})$$

where

$d_f, D$  = as defined in 8.8.3

$g$  = gravitational constant, 9,81 m/sec<sup>2</sup>

$h_f$  = flooding head, in metres, as defined in 8.8.3

$$h_1 = \frac{X}{\rho_c g} \text{ where } Y \text{ is in kN/m}^2$$

$$\left( h_1 = \frac{X}{\rho_c} \text{ where } Y \text{ is in tonne-f/m}^2 \right)$$

$n$  = number of floors between transverse bulkhead lower stools or transverse bulkheads, if no lower stools are fitted

$s$  = spacing, in metres, of double bottom longitudinals adjacent to hoppers

$$A_{DB,e} = \sum_{i=1}^n S_i (B_{DB} - s)$$


$$A_{DB,h} = \sum_{i=1}^n S_i B_{DB,i}$$

$B_{DB}$  = breadth of double bottom, in metres, between hoppers, see Fig. 7.8.5

$B_{DB,h}$  = distance, in metres, between openings, see Fig. 7.8.5

$B_{DB,i} = (B_{DB} - s)$  for floors where shear strength is given by  $S_{f1}$





**Fig. 7.8.5 Double bottom breadth**

$= B_{DB,h}$  for floors where shear strength is given by  $S_{f2}$

$C_e$  = shear capacity of the double bottom, in kN (tonne-f), as defined in 8.8.6, considering for each floor, the shear strength  $S_{f1}$ , see 8.8.7, and for each girder, the lesser of the shear strengths  $S_{g1}$  and  $S_{g2}$ , see 8.8.8

$C_h$  = shear capacity of the double bottom, in kN (tonne-f), as defined in 8.8.6, considering for each floor, the lesser of the shear strengths  $S_{f1}$  and  $S_{f2}$ , see 8.8.7, and for each girder, the lesser of the shear strengths  $S_{g1}$  and  $S_{g2}$ , see 8.8.8

$F_c$  = 1,1 in general

= 1,05 for steel mill products

$S_i$  = spacing of  $i$ th floor, in metres

$T_F$  =  $d_f - 0,1D$

$V$  = volume, in  $m^3$ , occupied by cargo at a level  $h_1$

$X$  = the lesser of  $X_1$  and  $X_2$  for bulk cargoes and

$X$  =  $X_1$  for steel mill products

where

$$X_1 = \frac{Y + \rho g (T_F - h_f)}{1 + \left(\frac{\rho}{\rho_c}\right) (\mu - 1)} \text{ where } Y \text{ is in kN/m}^2$$

$$\left( X_1 = \frac{Y + \rho (T_F - h_f)}{1 + \left(\frac{\rho}{\rho_c}\right) (\mu - 1)} \text{ where } Y \text{ is in tonne-f/m}^2 \right)$$

$X_2$  =  $Y + \rho g (T_F - h_f \mu)$  where  $Y$  is in kN/m<sup>2</sup>

$(X_2 = Y + \rho (T_F - h_f \mu)$  where  $Y$  is in tonne-f/m<sup>2</sup>)

$Y$  = the lesser of  $Y_1$  and  $Y_2$  given by:

$$Y_1 = \frac{C_h}{A_{DB,h}}$$

$$Y_2 = \frac{C_e}{A_{DB,e}}$$

$\mu$  = permeability of cargo but need not exceed 0,3

= 0,0 for steel mill products

$\rho$  = density of sea water, 1,025 tonne/m<sup>3</sup>

$\rho_c$  = cargo density, in tonne/m<sup>3</sup> (bulk density for bulk cargoes and actual cargo density for steel mill products).

## Section 9

### Hopper side tank structure

#### 9.1 General

9.1.1 Provision is made in this Section for longitudinal framing of the hopper side tank, but proposals for transverse framing will be specially considered.

9.1.2 Where oil cargoes are carried the scantlings of the sloped bulkhead are to comply with the requirements of 10.2.

9.1.3 For ships to be classed '**100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP**', the requirements of 9.2, 9.3 and 9.6 are to be complied with. In addition the value for  $C$ , the stowage rate in  $m^3$ /tonne, as defined in Table 7.8.1 is not to be taken greater than 0,60 for each hold.

9.1.4 The buckling requirements of Pt 3, Ch 4,7 are also to be satisfied.

9.1.5 The *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG), indicates recommended details of structural design configurations around the transverse ring web of the hopper tank.

#### 9.2 Sloped bulkhead plating

9.2.1 The thickness of the sloped bulkhead plating is to be as required by Ch 1,8.4.1 but based on actual spacing of sloped bulkhead stiffeners.

9.2.2 Where the ship is regularly discharged by grabs and the optional notation for heavy grabs is not desired (see Pt 3, Ch 9,13) the increase in thickness, as required by Ch 1,2.2, is to be tapered from the inner bottom knuckle to nil at the top corner of the tank.

# Bulk Carriers

# Part 4, Chapter 7

Sections 9 &amp; 10

9.2.3 Where a 'strengthened for heavy cargo notation' is desired, in addition to 9.2.2 the thickness of the sloped bulkhead plating is also to comply with the requirements of Table 7.8.1(3)(b) using the actual spacing of stiffeners and with  $H$ , in metres, measured vertically from a point one third of each plate width from its lower edge to the upper deck at side.

9.2.4 Where the hopper tanks are interconnected with the topside tanks, or in way of ballast holds, the plating is also to comply with the requirements of Table 7.8.1(3)(c) and (3)(d), whichever is appropriate.

## 9.3 Sloped bulkhead stiffeners

9.3.1 The scantlings of sloped bulkhead stiffeners are to be as required for inner bottom longitudinals, see Section 8. In ships strengthened for heavy cargoes, the scantlings of the stiffeners are to be derived from Table 7.8.1 using a head for heavy cargo measured vertically from the mid-point of the effective length to the underside of the topside tank sloped bulkhead. Where the hopper tanks are interconnected with the topside tanks, or in way of ballast holds, the scantlings of the stiffeners are also to comply with the requirements of Table 7.8.1(4)(c) and (4)(d), whichever is appropriate. For higher tensile steel longitudinals the requirements of 6.2.3 are to be complied with where applicable, see also 9.7.1.

## 9.4 Shell and bilge stiffeners

9.4.1 The scantlings of the shell and bilge longitudinals are to comply with the requirements of Ch 1,6.

## 9.5 Tank end bulkheads

9.5.1 The scantlings of tank end bulkheads are to comply with the requirements for deep tanks in Table 1.9.1 in Chapter 1. Where the hopper tanks are interconnected with the topside tanks, the scantlings are to be derived, using the load head  $h_4$ , in metres, from Table 7.8.1(3)(c) and (4)(c), as appropriate.

## 9.6 Primary supporting structure

9.6.1 Transverses supporting longitudinal stiffening are to comply with the requirements of Table 7.9.1, and are to be in line with the double bottom floors.

## 9.7 Structural details

9.7.1 Bracket/diaphragms at the top of the hopper tank are to be of sufficient size and thickness to provide effective rigidity, and care is to be taken to ensure alignment with brackets at the bottom of the side frames in the holds. The shell and sloped bulkhead longitudinals supporting the diaphragms are to be derived using the span taken between transverses, see also 6.2.11.

**Table 7.9.1 Hopper tank primary structure**

Item	Modulus, in $\text{cm}^3$	Inertia, in $\text{cm}^4$
(1) Bottom and side shell transverses	$Z = 11,71 \rho k S h l_e^2$	$I = \frac{2,5}{k} l_e Z$
(2) Sloped bulkhead transverses	The greater of: (a) $Z = 11,71 \rho k S h_1 l_e^2$ (b) $Z = 6,6 \frac{k S H_H l_e^2}{C}$	$I = \frac{2,5}{k} l_e Z$ $I = \frac{1,85}{k} l_e Z$
Symbols		
$S, k, l_e, Z, I, \rho$ as defined in 1.7.1 $h$ = distance, in metres, from the mid-point of the effective length to the upper deck at side $h_1$ = the greater of the distance, in metres, from the midpoint of the effective length to the top of the tank or half the distance, in metres, to the top of the overflow, or in way of cargo oil or ballast holds: the distance from the tank top to the deck at centre, or where the hopper tank is interconnected with the topside tank: the load head $h_4$ , as derived from Table 7.8.1(4)(c), whichever is the greatest $C$ = stowage rate, in $\text{m}^3/\text{tonne}$ , as defined in Table 7.8.1. For bulk carriers without the notation 'strengthened for heavy cargoes', the value to be used is 1,39 $\text{m}^3/\text{tonne}$ . For bulk carriers with the notation 'strengthened for heavy cargoes', the actual stowage rate is to be used, but the value is not to be taken greater than 0,865 $\text{m}^3/\text{tonne}$ $H_H$ = distance, in metres, measured vertically from the mid-point of the effective length to the underside of the topside tank sloped bulkhead		

## Section 10

## Bulkheads

### 10.1 General

10.1.1 The requirements of Ch 1,9 are to be applied, together with the requirements of this Section.

10.1.2 Where vertically corrugated transverse watertight bulkheads are fitted, the scantlings and arrangements are also to satisfy the requirements of 10.4 to 10.6. Other transverse watertight bulkhead types will be specially considered.

10.1.3 In way of ballast holds, the scantlings are to satisfy the requirements of Table 1.9.1 in Chapter 1 for deep tanks with the load head,  $h_4$ , in metres, taken to the deck at centre. This includes the scantlings of vertically corrugated and double plate transverse bulkheads supported by stools. In addition, the thickness of corrugations is to be not less than given by 10.5.8 for watertight corrugated bulkheads. Alternatively, the scantlings may be based on direct calculations which are to be submitted.

10.1.4 All bulk carriers to be classed '**100A1 bulk carrier, strengthened for heavy cargoes, any hold may be empty, ESP**' are to be arranged with top and bottom stools. The requirements of 10.2 are to be complied with as appropriate.

10.2.5 The *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG), indicates recommended structural design configurations in the critical areas of the lower stool and of the upper boundaries.


### 10.3 Structural details in way of holds confined to dry cargoes

10.3.2 Where transverse corrugated bulkheads are arranged without top stools, transverse beams are to be arranged under the deck in way.

#### 10.4 Vertically corrugated transverse watertight bulkheads – application and definitions

**10.4.2** For ships of length,  $L$ , 190 m or above, the vertically corrugated transverse bulkheads are to be fitted with a bottom stool and, generally, with a top stool below the deck. The requirements of 10.6 are to be complied with as appropriate.

**10.4.4** The cargo surface is to be taken as horizontal and at a distance  $d_1$ , in metres, from the base line, see Fig. 7.10.1, where  $d_1$  is calculated taking into account the cargo properties and the hold dimensions. Unless the ship is designed to carry only cargo of bulk density greater than or equal to 1,78 tonne/m<sup>3</sup> in non-homogeneous loading conditions, the maximum mass of cargo which may be carried in the hold is to be taken as filling that hold to the upper deck level at centreline. A permeability,  $\mu$ , of 0,3 and angle of repose,  $\psi$ , of 35° is to be assumed for this application.



10.4.6 The permeability,  $\mu$ , may be taken as 0,3 for ore, coal and cement cargoes. The bulk density and angle of repose,  $\psi$ , may generally be taken as 3,0 tonne/m<sup>3</sup> and 35° respectively for iron ore and 1,3 tonne/m<sup>3</sup> and 25° respectively for cement.

# Bulk Carriers

# Part 4, Chapter 7

Section 10

10.4.7 The flooding head,  $h_f$ , see Fig. 7.10.1, is the distance, in metres, measured vertically with the ship in the upright position, from the location  $P$ , under consideration, to a position  $d_f$ , in metres, from the base line as given in Table 7.10.1.

10.4.8 In considering a flooded hold, the total load is to be taken as that of the cargo and flood water at the appropriate permeability. Where there is empty volume above the top of the cargo, this is to be taken as flooded to the level of the flooding head.

10.4.9 Corrugations may be constructed of flanged plates or fabricated from separate flange and web plates, which may be of different thicknesses. The corrugation angle is to be not less than  $55^\circ$ , see Fig. 7.10.2.

10.4.10 The term net plate thickness is used to describe the calculated minimum thickness of plating of the web,  $t_w$ , or flange,  $t_f$ . The plate thickness to be fitted is the net plate thickness plus a corrosion addition of 3,5 mm.

## 10.5 Vertically corrugated transverse watertight bulkheads – scantling assessment


10.5.1 The bending moment  $M$ , in kNm (tonne-f m), for the bulkhead corrugations is given by:

$$M = \frac{F l}{8}$$

where

$l$  = span of the corrugation, in metres, to be measured between the internal ends of the bulkhead upper and lower stools in way of the neutral axis of the corrugations or, where no stools are fitted, from inner bottom to deck, see Fig. 7.10.2 and Fig. 7.10.3. The lower end of the upper stool is not to be taken greater than a distance from the deck at the centreline equal to: 3 times the depth of the corrugation, in general, or 2 times the depth of the corrugation, for rectangular stools

$F$  = resultant force, in kN (tonne-f), see Table 7.10.3.



**Fig. 7.10.2**  
**Dimensions of bulkhead corrugation angles**

10.5.2 The shear force,  $Q$ , in kN (tonne-f) at the lower end of the bulkhead corrugation is given by:

$$Q = 0,8F$$

where

$F$  is defined in 10.5.1.

**Table 7.10.1 Flooding head**

Item	Bulkhead location	Bulk carriers with Type B freeboard and deadweight < 50 000 tonnes	Other bulk carriers
I <sup>(1)</sup>	Between holds 1 and 2	$d_f = 0,95D$	$d_f = D$
	Elsewhere	$d_f = 0,85D$	$d_f = 0,9D$
II <sup>(1)</sup>	Between holds 1 and 2	$d_f = 0,9D$	$d_f = 0,95D$
	Elsewhere	$d_f = 0,8D$	$d_f = 0,85D$
<p>NOTES</p> <p>1. Item II is to be used for non-homogeneous loading conditions where the bulk cargo density is less than 1,78 tonne/m<sup>3</sup>. Otherwise, Item I is to be used.</p> <p>2. <math>D</math> = distance, in metres, from the base line to the freeboard deck at side amidships, see Fig. 7.10.1.</p>			

## Bulk Carriers

## Part 4, Chapter 7

Section 10

Table 7.10.2 Bulkhead pressure and force

Item	Pressure, kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> )	Force, kN (tonne-f)
(1) In non-flooded bulk cargo holds	$p_c = g \rho_c h_1 \tan^2 \theta$ ( $\rho_c = \rho_c h_1 \tan^2 \theta$ )	$F_c = 0,5 \rho_c g s_1 (d_1 - h_{DB} - h_{LS})^2 \tan^2 \theta$ ( $F_c = 0,5 \rho_c s_1 (d_1 - h_{DB} - h_{LS})^2 \tan^2 \theta$ )
(2) In flooded bulk cargo holds, when $d_f \geq d_1$ (a) For positions between $d_1$ and $d_f$ from base line (b) For positions at a distance lower than $d_1$ from base line	$p_{cf} = g \rho h_f$ ( $\rho_{cf} = \rho h_f$ ) $p_{cf} = g (\rho h_f + (\rho_c - \rho (1 - \mu)) h_1 \tan^2 \theta)$ ( $\rho_{cf} = (\rho h_f + (\rho_c - \rho (1 - \mu)) h_1 \tan^2 \theta)$ )	$F_{cf} = 0,5 s_1 (\rho g (d_f - d_1)^2 + (\rho g (d_f - d_1) + \rho_{le}) (d_1 - h_{DB} - h_{LS}))$ ( $F_{cf} = 0,5 s_1 (\rho (d_f - d_1)^2 + (\rho (d_f - d_1) + \rho_{le}) (d_1 - h_{DB} - h_{LS}))$ )
(3) In flooded bulk cargo holds, when $d_f < d_1$ (a) For positions between $d_1$ and $d_f$ from base line (b) For positions at a distance lower than $d_f$ from base line	$p_{cf} = g \rho_c h_1 \tan^2 \theta$ ( $\rho_{cf} = \rho_c h_1 \tan^2 \theta$ ) $p_{cf} = g (\rho h_f + (\rho_c h_1 - \rho (1 - \mu) h_f) \tan^2 \theta)$ ( $\rho_{cf} = (\rho h_f + (\rho_c h_1 - \rho (1 - \mu) h_f) \tan^2 \theta)$ )	$F_{cf} = 0,5 s_1 (\rho_c g (d_1 - d_f)^2 \tan^2 \theta + (\rho_c g (d_1 - d_f) \tan^2 \theta + \rho_{le}) (d_1 - h_{DB} - h_{LS}))$ ( $F_{cf} = 0,5 s_1 (\rho_c (d_1 - d_f)^2 \tan^2 \theta + (\rho_c (d_1 - d_f) \tan^2 \theta + \rho_{le}) (d_1 - h_{DB} - h_{LS}))$ )
(4) In flooded empty holds	$p_f = g \rho h_f$ ( $\rho_f = \rho h_f$ )	$F_f = 0,5 s_1 \rho g (d_f - h_{DB} - h_{LS})^2$ ( $F_f = 0,5 s_1 \rho (d_f - h_{DB} - h_{LS})^2$ )
Symbols		
$d_f$ = see 10.4.7 $d_1$ = vertical distance, in metres, from the base line to the top of the cargo, see Fig. 7.10.1 $g$ = gravitational constant, 9,81 m/sec <sup>2</sup> $h_{DB}$ = height of double bottom, in metres $h_f$ = flooding head, see 10.4.7 $h_{LS}$ = mean height of lower stool, in metres $h_1$ = vertical distance, in metres, from the calculation point to the top of the cargo, see Fig. 7.10.1 $\rho_c, \rho_{cf}, \rho_f$ = pressure on the bulkhead at the point under consideration, in kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> ) $\rho_{le}$ = pressure at the lower end of the corrugation, in kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> ) $s_1$ = spacing of the corrugations, in metres, see Fig. 7.10.2 $\rho$ = density of sea water = 1,025 tonne/m <sup>3</sup> $\rho_c$ = bulk cargo density, in tonne/m <sup>3</sup> $\theta$ = 45° - ( $\Psi/2$ ) $\Psi$ = angle of repose of the cargo, in degrees $\mu$ = permeability of cargo, see 10.4.6		

Table 7.10.3 Resultant pressure and force

Loading condition	Resultant pressure kN/m <sup>2</sup> (tonne-f/m <sup>2</sup> )	Resultant force kN (tonne-f)
Homogeneous	$p_r = p_{cf} - 0,8 \rho_c$	$F = F_{cf} - 0,8 F_c$
Non-homogeneous	$p_r = p_{cf}$	$F = F_{cf}$
Flood water alone (adjacent holds empty)	$p_r = p_f$	$F = F_f$
NOTE For symbols, see Table 7.10.2.		

10.5.3 The section modulus of the corrugations is to be calculated using net plate thicknesses. At the lower end, the following requirements apply:

- An effective width of compression flange,  $b_{ef}$ , not greater than given in 10.5.7, is to be used.
- Where corrugation webs are not supported by local brackets below the shelf plate (or below the inner bottom if no lower stool is fitted), they are to be assumed 30 per cent effective in bending. Otherwise, the full area of web plates may be used, see also (e).




Fig. 7.10.3 Scantling assessment

- Where effective shedder plates are fitted, see Figs. 7.10.4(a) and 7.10.4(b), the net area of the corrugation flange plates, in cm<sup>2</sup>, may be increased by the lesser of:

$$2,5b \sqrt{(t_f t_{sh})} \quad \text{and} \quad 2,5b t_f$$

where

# Bulk Carriers

# Part 4, Chapter 7

Section 10

$b$  = width of corrugation flange, in metres, see Fig. 7.10.2

$t_f$  = net flange plate thickness, in mm

$t_{sh}$  = net shedder plate thickness, in mm

A shedder plate is considered effective when it:

- is not knuckled; and
- is welded to the corrugations and the lower stool shelf plate by one-side penetration welds or equivalent; and
- has a minimum slope of  $45^\circ$  and lower edges in line with the stool side plating; and
- has a thickness not less than 0,75 times the thickness of the corrugation flanges; and
- has material properties at least equal to those of the corrugation flanges.

(d) Where effective gusset plates are fitted, see Figs. 7.10.5(a) and (b) the net area of the corrugation flange plates, in  $\text{cm}^2$ , may be increased by:

$$7h_g t_f$$

where

$h_g$  = height of the gusset plate, in metres, but is not to be taken greater than  $\frac{10}{7} s_{gu}$

$t_f$  = net flange plate thickness, in mm

$s_{gu}$  = width of the gusset plate, in metres

A gusset plate is considered effective when it:

- is fitted in combination with an effective shedder plate as defined in (c); and
  - has height not less than half the flange plate width; and
  - is fitted in line with the stool side plating; and
  - has thickness and material properties at least equal to those of the flanges; and
  - is welded to the top of the lower stool by full penetration welds and to the corrugations and shedder plates by one-side penetration welds or equivalent.
- (e) Where the corrugation is welded to a sloping stool shelf plate, set at an angle of not less than  $45^\circ$  to the horizontal, the corrugation webs may be taken as fully effective in bending. Where the slope is less than  $45^\circ$ , the effectiveness is to be assessed by linear interpolation between fully effective at  $45^\circ$  and the appropriate value from (b) at  $0^\circ$ . Where effective gusset plates are also fitted, the area of the flange plates may be increased in accordance with (d). No increase is permitted in the case where shedder plates are fitted without gussets.

**10.5.4** The section modulus of corrugations at cross-sections other than the lower end is to be calculated with fully effective webs and an effective compression flange width,  $b_{ef}$  not greater than given in 10.5.7.

**10.5.5** The bending capacity of the bulkhead corrugations is to comply with the following relationship:

$$\frac{1000 M}{0,5Z_{le} \sigma_{p,le} + Z_m \sigma_{p,m}} \leq 0,95$$


where

$M$  = bending moment, in kNm (tonne-f m), see 10.5.1


$Z_{le}$  = section modulus at the lower end of the corrugations, in  $\text{cm}^3$

$Z_m$  = section modulus at mid-span of the corrugations, in  $\text{cm}^3$


$\sigma_{p,le}$  = permissible bending stress at the lower end of the corrugations, in  $\text{N/mm}^2$  ( $\text{kgf/mm}^2$ )



**Fig. 7.10.4(a) Symmetric shedder plates**




**Fig. 7.10.4(b) Asymmetric shedder plates**



**Table 7.10.4 Permissible shear and buckling stresses**

Bending, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Shear, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Shear buckling, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
$\sigma_p = \sigma_0$	$\tau_p = 0,5\sigma_0$	$\tau_{cr} = \tau_E$ when $\tau_E \leq \frac{\tau_0}{2}$ $= \tau_0 \left(1 - \frac{\tau_0}{4\tau_E}\right)$ when $\tau_E \leq \frac{\tau_0}{2}$
Symbols		
$b$ = width of corrugation flange, in metres, see Fig. 7.10.2 $c$ = width of corrugation web, in metres, see Fig. 7.10.2 $t_f$ = net flange plate thickness, in mm $t_w$ = web plate net thickness, in mm $E$ = modulus of elasticity = 206 000 N/mm <sup>2</sup> (21000 kgf/mm <sup>2</sup> ) $\sigma_0$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) $\tau_E$ = $5,706 E (t_w/1000c)^2$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> ) $\tau_0$ = $\frac{\sigma_0}{\sqrt{3}}$ N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )		



# Bulk Carriers

# Part 4, Chapter 7

Section 10

$\sigma_{p,m}$  = permissible bending stress at mid-span of the corrugations, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

In the above expression  $Z'_{le}$ , in cm<sup>3</sup>, is not to be taken greater than  $Z'_{le}$

where

$$Z'_{le} = Z_g + \left( \frac{1000 Q h_g - 0,5 h_g^2 s_1 \rho_g}{\sigma_{p,le}} \right)$$

and  $Z_m$  is not to exceed the lesser of  $1,15Z_{le}$  and  $1,15Z'_{le}$  where

$h_g$  = height of the gusset plate, in metres

$\rho_g$  = resultant pressure calculated in way of the middle of the shedder or gusset plates as appropriate, in kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>)

$s_1$  = spacing of the corrugations, in metres

$Q$  = shear force, in kN (tonne-f), see 10.5.2

$Z_g$  = section modulus of the corrugations in way of the upper end of shedder or gusset plates as appropriate, in cm<sup>3</sup>.

10.5.6 The applied shear stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>), is determined by dividing the shear force derived from 10.5.2 by the shear area of the corrugation, calculated using the net plate thickness. The shear area is to be reduced to account for non-perpendicularity between the corrugation webs and flanges. In general, the reduced area may be obtained by multiplying the web sectional area by  $\sin \phi$ , where  $\phi$  is the angle between the web and the flange, see Fig. 7.10.2. The applied shear stress is not to exceed the permissible shear stress or the shear buckling stress given in Table 7.10.4.

10.5.7 The width of the compression flange, in metres, to be used for calculating the effective modulus is:

$$b_{ef} = C_{ef} b$$

where

$$C_{ef} = \frac{2,25}{\beta} - \frac{1,25}{\beta^2} \text{ for } \beta > 1,25$$

$$C_{ef} = 1,0 \text{ for } \beta \leq 1,25$$

$$\beta = 10^3 \left( \frac{b}{t_f} \right) \sqrt{\frac{\sigma_0}{E}}$$

Other symbols are as defined in Table 7.10.4.

10.5.8 The corrugation flange and web local net plate thickness are not to be less than:

$$t = 14,9 s_w \sqrt{1,05 \frac{\rho_r}{\sigma_0}} \text{ mm}$$

where

$s_w$  = plate width, in metres, to be taken equal to the width of the corrugation flange or web, whichever is the greater

$\rho_r$  = resultant pressure, in kN/m<sup>2</sup> (tonne-f/m<sup>2</sup>), as defined in Table 7.10.3, at the lower edge of each strake of plating. The net thickness of the lowest strake is to be determined using the resultant pressure at the top of the lower stool, (or at the inner bottom, if no lower stool is fitted), or at the top of the shedders, if effective shedder or gusset and shedder plates are fitted

$\sigma_0$  = specified minimum yield stress of the material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

10.5.9 For built-up corrugations, where the thickness of the flange and of the web are different, the net thickness of the narrower plating is to be not less than:

$$t_n = 14,9 s_n \sqrt{1,05 \frac{\rho_r}{\sigma_0}} \text{ mm}$$

where

$s_n$  = width of the narrower plating, in metres.

The net thickness, in mm, of the wider plating is not to be taken less than the greater of:

$$t_{wp} = 14,9 s_w \sqrt{1,05 \frac{\rho_r}{\sigma_0}} \text{ mm or}$$

$$t_{wp} = \sqrt{\frac{462 s_w^2 \rho_r}{\sigma_0} - t_{np}^2} \text{ mm}$$

where

$t_{np} \leq$  actual net thickness of the narrower plating but not greater than:

$$14,9 s_w \sqrt{1,05 \frac{\rho_r}{\sigma_0}} \text{ mm}$$

10.5.10 The required thickness of plating is the net thickness plus the corrosion addition given in 10.4.10.

10.5.11 Scantlings required to meet the bending and shear strength requirements at the lower end of the bulkhead corrugation are to be maintained for a distance of  $0,15l$  from the lower end, where  $l$  is as defined in 10.5.1. Scantlings required to meet the bending requirements at mid-height are to be maintained to a location no greater than  $0,3l$  from the top of the corrugation. The section modulus of the remaining upper part of the corrugation is to be not less than  $0,75$  times that required for the middle part, corrected for differences in yield stress.

## 10.6 Vertically corrugated transverse bulkheads – support structure at ends

10.6.1 The requirements of 10.2 are to be complied with as applicable, together with the following.

### 10.6.2 Lower stool:


- The height of the lower stool is generally to be not less than three times the depth of the corrugations.
- The thickness and steel grade of the stool shelf plate are to be not less than those required for the bulkhead plating above.
- The thickness and steel grade of the upper portion of vertical or sloping stool side plating, within the depth equal to the corrugation flange width from the stool top, are to be not less than the flange plate thickness and steel grade needed to meet the bulkhead requirements at the lower end of the corrugation.
- The thickness of the stool side plating and the section modulus of the stool side stiffeners are to be not less than those required by Ch 1,9 for a plane transverse bulkhead and stiffeners using the greater of the pressures determined from the head,  $h_4$ , in Table 1.9.1 and the expressions given in Table 7.10.2.
- The ends of stool side vertical stiffeners are to be attached to brackets at the upper and lower ends of the stool.
- The width of the shelf plate is to be in accordance with Fig. 7.10.6.



# Bulk Carriers

# Part 4, Chapter 7

Section 10



**Fig. 7.10.6 Width of shelf plate**


- (g) The stool bottom is to have a width not less than 2,5 times the mean depth of the corrugation.
- (h) Scallops in the brackets and diaphragms in way of connections to the stool shelf plate are to be avoided.
- (j) Where corrugations are terminated on the bottom stool, corrugations are to be connected to the stool top plate by full penetration welds. The stool side plating is to be connected to the stool top plate and the inner bottom plating by either full penetration or deep penetration welds, see Fig. 7.10.7. The supporting floors are to be connected to the inner bottom by either full penetration or deep penetration welds.

## 10.6.3 Upper stool:

- (a) The upper stool, where fitted, is to have a height generally between two and three times the depth of corrugations.

- (b) Rectangular stools are to have a height generally equal to twice the depth of corrugations, measured from the deck level and at hatch side girder.
- (c) The upper stool is to be properly supported by girders or deep brackets between the adjacent hatch-end beams.
- (d) The width of the shelf plate is generally to be the same as that of the lower stool shelf plate.
- (e) The upper end of a non-rectangular stool is to have a width not less than twice the depth of corrugations.
- (f) The thickness and steel grade of the shelf plate are to be the same as those of the bulkhead plating below.
- (g) The thickness of the lower portion of stool side plating is to be not less than 80 per cent of that required for the upper part of the bulkhead plating where the same materials is used.
- (h) The thickness of the stool side plating and the section modulus of the stool side stiffeners are to be not less than those required by Ch 1,9 for plane transverse bulkheads and stiffeners using the greater of the pressures determined from the head,  $h_4$ , in Table 1.9.1 and the expressions given in Table 7.10.2.
- (j) Where vertical stiffening is fitted, the ends of stool side stiffeners are to be attached to brackets at the upper and lower end of the stool.
- (k) Diaphragms are to be fitted inside the stool, in line with, and effectively attached to, longitudinal deck girders extending to the hatch end coaming girders for effective support of the corrugated bulkhead.
- (l) Scallops in the brackets and diaphragms in way of the connection to the stool shelf plate are to be avoided.

10.6.4 If no upper stool is fitted, two transverse reinforced beams are to be fitted in line with the corrugation flanges.



**Fig. 7.10.7 Welding**

# Bulk Carriers

# Part 4, Chapter 7

Sections 10, 11 & 12

10.6.5 If no bottom stool is fitted, the corrugation flanges are to be in line with the supporting floors. Corrugations are to be connected to the inner bottom plating by full penetration welds. The thickness and steel grades of the supporting floors are to be at least equal to those provided for the corrugation flanges. The plating of supporting floors is to be connected to the inner bottom by either full penetration or deep penetration welds, see Fig. 7.10.7. The cut-outs for connections of the inner bottom longitudinals to double bottom floors are to be closed by collar plates. The supporting floors are to be connected to each other by suitably designed shear plates. Stool side plating is to align with the corrugation flanges. Stool side vertical stiffeners and their brackets in the lower stool are to align with the inner bottom longitudinals to provide appropriate load transmission between these stiffening members. The lower stool side plating is not to be knuckled.

10.6.6 Stool side plating is to align with the corrugation flanges. Stool side vertical stiffeners and their brackets in the lower stool are to align with the inner bottom longitudinals to provide appropriate load transmission between these stiffening members. The lower stool side plating is not to be knuckled.

10.6.7 The design of local details is to take into account the transfer of the bulkhead forces and moments to the boundary structures and particularly to the double bottom and cross-deck structures.

## Section 11 Direct calculation

### 11.1 Application

11.1.1 Direct calculations are to be employed in derivation of scantlings where required by the preceding Sections of this Chapter or by related provisions included in Part 3.

11.1.2 Direct calculation methods are also generally to be used where additional calculations are required by the Rules in respect of unusual structural arrangements.

### 11.2 Procedures

11.2.1 For details of LR's direct calculation procedures, see Pt 3, Ch 1,2. For requirements concerning use of other calculation procedures, see Pt 3, Ch 1,3.

## Section 12 Steel hatch covers

### 12.1 General

12.1.1 These requirements apply to hatch covers on exposed decks in Position 1, see Pt 3, Ch 1,6.5.1, and are in addition to the requirements of Pt 3, Ch 11,2.

12.1.2 The net plate thickness,  $t_{net}$ , is the calculated minimum thickness of the plating and stiffeners. The required thickness is the net thickness plus a corrosion addition,  $t_c$ , given in Table 7.12.1.

**Table 7.12.1 Corrosion addition  $t_c$**

Hatch cover type	$t_c$ , in mm
(a) Single skin	2,0
(b) Pontoon (double skin)	
(i) for the top and bottom plating	2,0
(ii) for the internal structures	1,5

12.1.3 Material for the hatch covers is to be steel according to the requirements for ship's hull.

### 12.2 Stiffener arrangement

12.2.1 The secondary stiffeners and primary supporting members of the hatch covers are to be continuous over the breadth and length of the hatch covers, as far as practical. When this is impractical, sniped end connections are not to be used and appropriate arrangements are to be adopted to ensure sufficient load carrying capacity.

12.2.2 The spacing of primary supporting members parallel to the direction of secondary stiffeners is not to exceed 1/3 of the span of primary supporting members.

### 12.3 Closing arrangements

12.3.1 Panel hatch covers are to be secured by appropriate devices (bolts, wedges or similar) suitably spaced alongside the coamings and between cover elements.

12.3.2 Arrangement and spacing are to be determined with due attention to the effectiveness for weather-tightness, depending upon the type and the size of the hatch cover, as well as on the stiffness of the cover edges between the securing devices.

12.3.3 The net sectional area of each securing device is not to be less than:

$$A = 1,4 a/f \text{ cm}^2$$

where

$a$  = spacing in m of securing devices, not being taken less than 2 m

$$f = (\sigma_Y/235)^e$$

$\sigma_Y$  = specified minimum upper yield stress in N/mm<sup>2</sup> of the steel used for fabrication, not to be taken greater than 70 per cent of the ultimate tensile strength

$$e = 0,75 \text{ for } \sigma_Y > 235 \\ = 1,0 \text{ for } \sigma_Y \leq 235$$

12.3.4 Rods or bolts are to have a net diameter not less than 19 mm for hatchways exceeding 5 m<sup>2</sup> in area.

# Bulk Carriers

# Part 4, Chapter 7

Section 12

12.3.5 Between cover and coaming and at cross-joints, a packing line force sufficient to obtain weathertightness is to be maintained by the securing devices. For packing line forces exceeding 5 N/mm, the cross section area is to be increased in direct proportion. The packing line force is to be specified.

12.3.6 The cover edge stiffness is to be sufficient to maintain adequate sealing pressure between securing devices. The moment of inertia,  $I$ , of edge elements is not to be less than:

$$I = 6p a^4 \text{ cm}^4$$

where

- $p$  = packing line pressure in N/mm, minimum 5 N/mm
- $a$  = spacing in m of securing devices

12.3.7 Securing devices are to be of reliable construction and securely attached to the hatchway coamings, decks or covers. Individual securing devices on each cover are to have approximately the same stiffness characteristics.

12.3.8 Where rod cleats are fitted, resilient washers or cushions are to be incorporated.

12.3.9 Where hydraulic cleating is adopted, a positive means is to be provided to ensure that it remains mechanically locked in the closed position in the event of failure of the hydraulic system.

12.3.10 Hatch covers are to be effectively secured, by means of stoppers, against transverse and longitudinal forces arising from a pressure of 175 kN/m<sup>2</sup>.

12.3.11 The equivalent stress:

- in stoppers and their supporting structures; and
- calculated in the throat of the stopper welds; is not to exceed the allowable value of  $0,8\sigma_F$ .

## 12.4 Load model

12.4.1 The pressure,  $p$ , in kN/m<sup>2</sup>, acting on the hatch covers is given by:

- For ships of length 100 m or greater, for hatchways located on the freeboard deck,  $p$  is to be the greater of 34,3 or the following:

$$p = 34,3 + \frac{p_{FP} - 34,3}{0,25} \left( 0,25 - \frac{x}{L} \right)$$

Where a hatchway is located in position 1 and at least one superstructure standard height higher than the freeboard deck, the pressure  $p$  may be 34,3 kN/m<sup>2</sup>.

- For ships less than 100 m in length, for hatchways located at the freeboard deck,  $p$  is to be the greater of  $0,195L + 14,9$  or the following:

$$p = 15,8 + \frac{L}{3} \left( 1 - \frac{5}{3} \frac{x}{L} \right) - 3,6 \frac{x}{L}$$

Where two or more panels are connected by hinges, each individual panel is to be considered separately.

where

- $p_{FP}$  = pressure at the forward perpendicular
- =  $49,1 + (L - 100) a$
- $a$  = 0,0726 for type B freeboard ships
- 0,356 for ships with reduced freeboard

$L$  = Freeboard length, in metres, as defined in Regulation 3 of Annex I to the 1966 Load Line Convention as modified by the Protocol of 1988, to be taken not greater than 340 m

$x$  = distance, in metres, of the mid length of the hatch cover under examination from the forward end of  $L$ .

## 12.5 Allowable stress

12.5.1 The normal and shear stresses calculated for the net section hatch cover structures are not to exceed the values given in Table 7.12.2.

**Table 7.12.2 Permissible stresses**

Failure mode	Permissible stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Bending	$\sigma_a = 0,80\sigma_F$
Shear	$\tau_a = 0,45\sigma_F$
Symbols	
$\sigma_F$ = minimum upper yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

12.5.2 The normal stress in compression of the attached flange of primary supporting members is not to exceed 0,8 times the critical buckling stress of the structure according to the buckling check as given in 12.10, 12.11 and 12.12.

12.5.3 The stresses in hatch covers that are designed as a grillage of longitudinal and transverse primary supporting members are to be determined by a grillage or a FE analysis. When such an analysis is used the secondary stiffeners are not to be included in the attached flange area of the primary members.

12.5.4 When calculating the stresses  $\sigma$  and  $\tau$  as defined in Table 7.12.2, the net scantlings are to be used.

## 12.6 Effective cross-sectional area of panel flanges for primary supporting members

12.6.1 The effective flange area,  $A_f$ , in cm<sup>2</sup>, of the attached plating, to be considered for the yielding and buckling checks of primary supporting members, when calculated by means of a beam or grillage model, is obtained as the sum of the effective flange areas of each side of the girder web as appropriate:

$$A_f = \sum_{nf} (10b_{ef} t)$$

where

- $nf$  = 2 if attached plate flange extends on both sides of girder web
- = 1 if attached plate flange extends on one side of girder web only
- $t$  = net thickness of considered attached plate, in mm
- $b_{ef}$  = effective breadth of attached plate flange on each side of girder web, in metres
- =  $b_p$ , but not to be taken greater than  $0,165l$

# Bulk Carriers

# Part 4, Chapter 7

Section 12

$b_p$  = half distance between the considered primary supporting member and the adjacent one, in metres  
 $l$  = span of primary supporting members, in metres

## 12.7 Local net plate thickness

12.7.1 The local net plate thickness of the hatch cover plating is to be not less than:

$$t = F_p 15,8s \sqrt{\frac{p}{0,95\sigma_F}}$$

or 1 per cent of the spacing of the stiffeners or 6 mm, whichever is greater

where

$F_p$  = factor for combined membrane and bending response  
 = 1,50 in general  
 =  $1,90\sigma/\sigma_a$ , where  $\sigma/\sigma_a \geq 0,8$ , for the attached plate flange of primary supporting members  
 $s$  = stiffener spacing, in metres  
 $p$  = pressure, in kN/m<sup>2</sup>, as defined in 12.4  
 $\sigma$  = as defined in 12.9  
 $\sigma_a$  = as defined in 12.5.

## 12.8 Net scantlings of secondary stiffeners

12.8.1 The required minimum section modulus,  $Z$ , in cm<sup>3</sup>, of secondary stiffeners of the hatch cover top plate, based on stiffener net member thickness, is given by:

$$Z = \frac{1000l^2 s p}{12\sigma_a}$$

where

$l$  = secondary stiffener span, in metres, to be taken as the spacing, in metres, of primary supporting members or the distance between a primary supporting member and the edge support, as applicable. When brackets are fitted at both ends of all secondary stiffener spans, the secondary stiffener span may be reduced by an amount equal to 2/3 of the minimum bracket arm length, but not greater than 10 per cent of the gross span, for each bracket  
 $s$  = secondary stiffener spacing, in metres  
 $p$  = pressure, in kN/m<sup>2</sup>, as defined in 12.4  
 $\sigma_a$  = as defined in 12.5.

12.8.2 The net section modulus of the secondary stiffeners is to be determined based on an attached plate width assumed equal to the stiffener spacing.

## 12.9 Net scantlings of primary supporting members

12.9.1 The section modulus and web thickness of primary supporting members, based on member net thickness, are to be such that the normal stress  $\sigma$  in both flanges and the shear stress  $\tau$ , in the web, do not exceed the allowable values  $\sigma_a$  and  $\tau_a$ , respectively, defined in 12.5.

12.9.2 The breadth of the primary supporting member flange is to be not less than 40 per cent of their depth for laterally unsupported spans greater than 3,0 m. Tripping brackets attached to the flange may be considered as a lateral support for primary supporting members.

12.9.3 The flange outstand is not to exceed 15 times the flange thickness.

## 12.10 Hatch cover plating

12.10.1 The compressive stress,  $\sigma$ , in N/mm<sup>2</sup>, in the hatch cover plate panels, induced by the bending of primary supporting members parallel to the direction of secondary stiffeners, is not to exceed 0,8 times the critical buckling stress  $\sigma_{C1}$ , to be evaluated as defined below:

$$\begin{aligned} \sigma_{C1} &= \sigma_{E1} & \text{when } \sigma_{E1} \leq \sigma_F/2 \\ &= \sigma_F [1 - \sigma_F/(4\sigma_{E1})] & \text{when } \sigma_{E1} > \sigma_F/2 \end{aligned}$$

where

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material  
 $\sigma_{E1} = 3,6E \left( \frac{t}{1000s} \right)^2$   
 $E$  = modulus of elasticity, in N/mm<sup>2</sup>  
 =  $2,06 \times 10^5$  for steel  
 $t$  = net thickness, in mm, of plate panel  
 $s$  = spacing of secondary stiffeners, in metres

12.10.2 The mean compressive stress  $\sigma$  in each of the hatch cover plate panels, induced by the bending of primary supporting members perpendicular to the direction of secondary stiffeners, is not to exceed 0,8 times the critical buckling stress  $\sigma_{C2}$ , to be evaluated as defined below:

$$\begin{aligned} \sigma_{C2} &= \sigma_{E2} & \text{when } \sigma_{E2} \leq \sigma_F/2 \\ &= \sigma_F [1 - \sigma_F/(4\sigma_{E2})] & \text{when } \sigma_{E2} > \sigma_F/2 \end{aligned}$$

where

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material  
 $\sigma_{E2} = 0,9m E \left( \frac{t}{1000s_s} \right)^2$   
 $m = c \left[ 1 + \left( \frac{s_s}{l_s} \right)^2 \right]^2 \frac{2,1}{\Psi + 1,1}$   
 $E$  = modulus of elasticity, in N/mm<sup>2</sup>  
 =  $2,06 \times 10^5$  for steel  
 $t$  = net thickness of plate panel, in mm  
 $s_s$  = length of the shorter side of the plate panel, in metres  
 $l_s$  = length of the longer side of the plate panel, in metres  
 $\Psi$  = ratio between smallest and largest compressive stress  
 $c$  = 1,3 when plating is stiffened by primary supporting members  
 = 1,21 when plating is stiffened by secondary stiffeners of angle or T type  
 = 1,1 when plating is stiffened by secondary stiffeners of bulb type  
 = 1,05 when plating is stiffened by flat bar.

# Bulk Carriers

# Part 4, Chapter 7

Section 12

12.10.3 The biaxial compressive stress in the hatch cover panels, when calculated by means of FEM shell element model will be specially considered.

## 12.11 Hatch cover secondary stiffeners

12.11.1 The compressive stress  $\sigma$ , in N/mm<sup>2</sup>, in the top flange of secondary stiffeners, induced by the bending of primary supporting members parallel to the direction of secondary stiffeners, is not to exceed 0,8 times the critical buckling stress  $\sigma_{CS}$ , to be evaluated as defined below:

$$\begin{aligned}\sigma_{CS} &= \sigma_{ES} && \text{when } \sigma_{ES} \leq \sigma_F/2 \\ &= \sigma_F [1 - \sigma_F/(4\sigma_{ES})] && \text{when } \sigma_{ES} > \sigma_F/2\end{aligned}$$

where

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material

$\sigma_{ES}$  = ideal elastic buckling stress, in N/mm<sup>2</sup>, of the secondary stiffener  
= minimum between  $\sigma_{E3}$  and  $\sigma_{E4}$

$$\sigma_{E3} = 0,001E I_a / (A l^2)$$

$E$  = modulus of elasticity, in N/mm<sup>2</sup>  
= 2,06 x 10<sup>5</sup> for steel

$I_a$  = moment of inertia of the secondary stiffener, including a top flange equal to the spacing of secondary stiffeners, in cm<sup>4</sup>

$A$  = cross-sectional area of the secondary stiffener, including a top flange equal to the spacing of secondary stiffeners, in cm<sup>2</sup>

$l$  = span of the secondary stiffener, in metres

$$\sigma_{E4} = \frac{\pi^2 E I_w}{10^4 I_p l^2} \left( m^2 + \frac{K}{m^2} \right) + 0,385E \frac{I_t}{I_p}$$

$$K = \frac{C l^4}{\pi^4 E I_w} 10^6 \text{ m}$$

$m$  = number of half waves, given in Table 7.12.3

$I_w$  = sectorial moment of inertia (warping constant) of the secondary stiffener about its connection with the plating, in cm<sup>6</sup>

$$= \frac{h_w^3 t_w^3}{36} 10^{-6} \text{ for flat bar secondary stiffeners}$$

$$= \frac{t_f b_f^3 h_w^2}{12} 10^{-6} \text{ for 'Tee' secondary stiffeners}$$

$$= \frac{b_f^3 h_w^2}{12(b_f + h_w)^2} [t_f(b_f^2 + 2b_f h_w + 4h_w^2) + 3t_w b_f h_w] 10^{-6}$$

for angles and bulb secondary stiffeners

$I_p$  = polar moment of inertia of the secondary stiffener about its connection with the plating, in cm<sup>4</sup>

$$= \frac{h_w^3 t_w}{3} 10^{-4} \text{ for flat bar secondary stiffeners}$$

$$= \left( \frac{h_w^3 t_w}{3} + h_w^2 b_f t_f \right) 10^{-4}$$

for flanged secondary stiffeners

$I_t$  = St.Venant's moment of inertia of the secondary stiffener without top flange, in cm<sup>4</sup>

$$= \frac{h_w^3 t_w}{3} 10^{-4} \text{ for flat bar secondary stiffeners}$$

$$= \frac{1}{3} \left[ h_w t_w^3 + b_f t_f^3 \left( 1 - 0,63 \frac{t_f}{b_f} \right) \right] 10^{-4}$$

for flanged secondary stiffeners

$h_w, t_w$  = height and net thickness of the secondary stiffener, respectively, in mm

$b_f, t_f$  = width and net thickness of the secondary stiffener bottom flange, respectively, in mm

$s$  = spacing of secondary stiffeners, in metres

$C$  = spring stiffness exerted by the hatch cover top plating

$$= \frac{k_p E t_p^3}{3s \left[ 1 + \frac{1,33k_p h_w t_p^3}{1000s t_w^3} \right]} 10^{-3}$$

$k_p$  = 1 -  $\eta_p$  to be taken not less than zero; for flanged secondary stiffeners,  $k_p$  need not be taken less than 0,1

$$\eta_p = \frac{\sigma}{\sigma_{E1}}$$

$\sigma$  = as defined in 12.9

$\sigma_{E1}$  = as defined in 12.10

$t_p$  = net thickness of the hatch cover plate panel, in mm.

**Table 7.12.3 Number of half waves**

$K$	m
$0 < K < 4$	1
$4 < K < 36$	2
$36 < K < 144$	3
$(m-1)^2 m^2 < K \leq m^2 (m+1)^2$	m

12.11.2 For flat bar secondary stiffeners and buckling stiffeners, the ratio  $h/t_w$  is to be not greater than  $15k^{0,5}$

where

$h, t_w$  = height and net thickness of the stiffener, respectively

$$k = 235/\sigma_F$$

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material.

## 12.12 Web panels of hatch cover primary supporting members

12.12.1 This check is to be carried out for the web panels of primary supporting members formed by web stiffeners or by the crossing with other primary supporting members, the face plate (or the bottom cover plate) or the attached top cover plate.

# Bulk Carriers

# Part 4, Chapter 7

Sections 12 & 13

12.12.2 The shear stress  $\tau$  in the hatch cover primary supporting members web panels is not to exceed 0,8 times the critical buckling stress  $\tau_C$ , to be evaluated as defined below:

$$\begin{aligned}\tau_C &= \tau_E & \text{when } \tau_E \leq \tau_F/2 \\ &= \tau_F [1 - \tau_F/(4\tau_E)] & \text{when } \tau_E > \tau_F/2\end{aligned}$$

where

$\sigma_F$  = minimum upper yield stress of the material, in N/mm<sup>2</sup>

$$\tau_F = \frac{\sigma_F}{3}$$

$$\tau_E = 0,9k_t E \left( \frac{t_{pr,n}}{1000d} \right)^2$$

$E$  = modulus of elasticity, in N/mm<sup>2</sup>

= 2,06 x 10<sup>5</sup> for steel

$t_{pr,n}$  = net thickness of primary supporting member, in mm

$k_t$  = 5,35 + 4,0/(a/d)<sup>2</sup>

$a$  = greater dimension of web panel of primary supporting member, in metres

$d$  = smaller dimension of web panel of primary supporting member, in metres.

12.12.3 For primary supporting members parallel to the direction of secondary stiffeners, the actual dimensions of the panels are to be considered.

12.12.4 For primary supporting members perpendicular to the direction of secondary stiffeners or for hatch covers built without secondary stiffeners, a presumed square panel of dimension  $d$  is to be taken for the determination of the stress  $\tau_C$ . In such a case, the average shear stress  $\tau$  between the values calculated at the ends of this panel is to be considered.

## 12.13 Deflection limit and connections between hatch cover panels

12.13.1 Load bearing connections between the hatch cover panels are to be fitted with the purpose of restricting the relative vertical displacements.

12.13.2 The vertical deflection of primary supporting members is to be not more than 0,0056*l*, where *l* is the greatest span of primary supporting members.

## Section 13 Hatch coamings

### 13.1 General

13.1.1 The height and construction of forward and side hatch coamings are to comply with the following requirements. All hatch coamings are to comply with the requirements of Pt 3, Ch 11,5.

13.1.2 For the structure of hatch coamings and coaming stays, the corrosion addition  $t_s$  is to be 1,5 mm.

13.1.3 Material for the hatch coamings is to be steel according to the requirements for the ship's hull.

13.1.4 The secondary stiffeners of the hatch coamings are to be continuous over the breadth and length of the hatch coamings.

### 13.2 Load model

13.2.1 The pressure  $p_{coam}$ , on hatch coamings is to be taken as 220 kN/m<sup>2</sup>.

### 13.3 Local net plate thickness

13.3.1 The local net plate thickness,  $t$ , in mm, of the hatch coaming plating is to be the greater of 9,5 mm or the following:

$$t = 14,9s \sqrt{\frac{p_{coam}}{\sigma_{a,coam}}} S_{coam}$$

where

$s$  = secondary stiffener spacing, in metres

$p_{coam}$  = pressure, in kN/m<sup>2</sup>, as defined in 13.2.1

$S_{coam}$  = safety factor to be taken equal to 1,15

$\sigma_{a,coam} = 0,95\sigma_F$ .

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material.

### 13.4 Net scantlings of longitudinal and transverse secondary stiffeners

13.4.1 The required section modulus,  $Z$ , in cm<sup>3</sup>, of the longitudinal or transverse secondary stiffeners of the hatch coamings, based on net member thickness, is given by:

$$Z = \frac{1000S_{coam} l^2 s p_{coam}}{m c_p \sigma_{a,coam}}$$

where

$m$  = 16 in general

= 12 for the end spans of stiffeners sniped at the coaming corners

$S_{coam}$  = safety factor to be taken equal to 1,15

$l$  = span of secondary stiffeners, in metres

$s$  = spacing of secondary stiffeners, in metres

$p_{coam}$  = pressure in kN/m<sup>2</sup> as defined in 13.2.1

$c_p$  = ratio of the plastic section modulus to the elastic section modulus of the secondary stiffeners with an attached plate breadth equal to 40*t*, where *t* is the plate net thickness, in mm

= 1,16 in the absence of more precise evaluation

$\sigma_{a,coam} = 0,95\sigma_F$

$\sigma_F$  = minimum upper yield stress, in N/mm<sup>2</sup>, of the material.

### 13.5 Net scantlings of coaming stays

13.5.1 The required minimum section modulus,  $Z$ , in  $\text{cm}^3$ , and web thickness,  $t_w$ , in mm of coaming stays designed as beams with flange connected to the deck or sniped and fitted with a bracket (see Fig. 7.13.1, Type A and B) at their connection with the deck, based on member net thickness, are given by:

$$Z = \frac{1000 H_C^2 s p_{\text{coam}}}{2 \sigma_{a,\text{coam}}}$$

$$t_w = \frac{1000 H_C s p_{\text{coam}}}{h \tau_{a,\text{coam}}}$$

where

$H_C$  = stay height, in metres

$s$  = stay spacing, in metres

$h$  = stay depth at the connection with the deck, in mm


$p_{\text{coam}}$  = pressure, in  $\text{kN/m}^2$ , as defined in 13.2.1

$\sigma_{a,\text{coam}}$  =  $0,95\sigma_F$

$\tau_{a,\text{coam}}$  =  $0,5\sigma_F$

$\sigma_F$  = minimum upper yield stress, in  $\text{N/mm}^2$ , of the material.

13.5.2 For calculating the section modulus of coaming stays, their face plate area is to be taken into account only when it is welded with full penetration welds to the deck plating and adequate underdeck structure is fitted to support the stresses transmitted by it.



**Fig. 7.13.1 Typical coaming stays**

# Bulk Carriers

# Part 4, Chapter 7

Sections 13 & 14

13.5.3 For other designs of coaming stays, such as those shown in Fig. 7.13.1 Type C and D, the stress levels in 12.5 apply and are to be checked at the highest stressed locations.

## 13.6 Local details

13.6.1 The design of local details is to comply with Pt 3, Ch 11,5 for the purpose of transferring the pressures on the hatch covers to the hatch coamings and, through them, to the deck structures below. Hatch coamings and supporting structures are to be adequately stiffened to accommodate the loading from hatch covers, in longitudinal, transverse and vertical directions.

13.6.2 Underdeck structures are to be checked against the load transmitted by the stays, adopting the same allowable stresses specified in 13.5.1.

13.6.3 Double continuous welding is to be adopted for the connections of stay webs with deck plating and the weld throat is to be not less than  $0,44t_W$ , where  $t_W$  is the gross thickness of the stay web.

13.6.4 Toes of stay webs are to be connected to the deck plating with deep penetration double bevel welds extending over a distance not less than 15 per cent of the stay width.




Fig. 7.14.1 Forecastle arrangement

14.1.4 All points of the aft edge of the forecastle deck are to be located at a distance:

$$l_f < 5 \sqrt{(H_F - H_C)}$$

from the hatch coaming, see Fig. 7.14.1.

14.1.5 A breakwater is not to be fitted on the forecastle deck with the purpose of protecting the hatch coaming or hatch covers. If fitted for other purposes, it is to be located such that its upper edge at centre line is not less than:

$$H_B / \tan 20^\circ$$

forward of the aft edge of the forecastle deck.

where

$H_B$  = the height, in metres, of the breakwater above the forecastle, see Fig. 7.14.1.

## Section 14 Forecastles

### 14.1 Arrangement

14.1.1 An enclosed forecastle is to be fitted on the free-board deck.

14.1.2 The aft bulkhead of the forecastle is to be fitted in way or aft of the forward bulkhead in the foremost cargo hold. See Fig. 7.14.1. However, if this requirement hinders hatch cover operation, the aft bulkhead of the forecastle may be fitted forward of the forward bulkhead of the foremost cargo hold provided the forecastle length is not less than 7% of ship length abaft the forward perpendicular where the ship length and forward perpendicular are defined in the International Convention on Load Line 1966 and its Protocol 1988.

14.1.3 The forecastle height  $H_F$ , in metres, above the main deck is to be not less than the greater of:

- the standard height of a superstructure as specified in the International Convention on Load Lines 1966 and its Protocol of 1988; or
- $H_C + 0,5$  m

where

$H_C$  = the height, in metres, of the forward transverse hatch coaming of cargo hold No.1.

### 14.2 Construction

14.2.1 The construction of the forecastle is to comply with the requirements of Pt 3, Ch 8,4.



## Section

1	<b>General</b>
2	<b>Materials</b>
3	<b>Longitudinal strength</b>
4	<b>Deck structure</b>
5	<b>Shell envelope plating</b>
6	<b>Shell envelope framing</b>
7	<b>Double bottom structure</b>
8	<b>Longitudinal bulkheads</b>
9	<b>Transverse bulkheads</b>
10	<b>Hatch coamings and support for hatch covers</b>
11	<b>Hatch covers</b>
12	<b>Strengthening for wave impact loads</b>
13	<b>Container stowage systems</b>
14	<b>Direct calculation</b>
15	<b>Requirements for ships with large deck openings</b>

## Section 1 General

### 1.1 Application and definitions

**1.1.1** A **container ship** is defined as a ship designed exclusively for the carriage of containers in holds and on deck. Containers in holds are normally stowed within cellular guide systems.

**1.1.2** The term 'Panamax' container ship is as defined in Lloyd's Register's (hereinafter referred to as 'LR') ShipRight SDA Procedures Manual *Primary Structure of Container Ships*.

**1.1.3** The term 'narrow side structures' applies where the breadth of hatch opening exceeds 90 per cent of the breadth of the ship.

**1.1.4** Other terms used to describe the various structural components of container ships are generally indicated in LR's ShipRight FDA Procedure, *Structural Detail Design Guide*.

**1.1.5** For container ships with a beam of Panamax size or greater, or where the structural arrangements are considered such as to necessitate it, the ShipRight notations **SDA** and **CM** are mandatory, see 1.3 and Section 14.


**1.1.6** Scantlings of the primary structure of double bottom, side and transverse bulkheads are to be verified by direct calculation as required by 14.2.

**1.1.7** Scantlings and arrangements are to be as required by Chapter 1, except as otherwise indicated in this Chapter.

### 1.2 Structural configuration

**1.2.1** This Chapter describes a basic structural configuration as shown in Fig. 8.1.1 which includes:

- An efficient torsion box girder or equivalent structure at the topsides comprising strength deck, side shell, inner skin and a second deck. The space within the torsion box is often utilised as an underdeck access passageway.
- Single or double skin side construction with or without bilge box.
- Double bottom.
- Continuous or discontinuous hatch coamings.
- Optional continuous deck girders to support hatch covers.



**Fig. 8.1.1 Structural configuration**

### 1.3 Class notations

**1.3.1** In general, ships complying with the requirements of this Chapter will be eligible to be classed **100A1 Container Ship**.

**1.3.2** The 'ShipRight Procedures' for the hull construction of ships are detailed in Pt 3, Ch 16 and the classification notations and descriptive notes associated with these procedures are given in Pt 1, Ch 2.2.

# Container Ships

# Part 4, Chapter 8

Sections 1, 2, 3 & 4

1.3.3 The notations **SDA** and **CM** are mandatory for container ships with any of the following features:

- (a) beam of a Panamax size or greater;
- (b) narrow side structures;
- (c) abnormal hull form; or
- (d) unusual structural configuration or complexity.

1.3.4 When required, other cargoes or particular loading arrangements will be included in the class or cargo notations.

1.3.5 Reference is made to Pt 1, Ch 2 with respect to the Regulations for classification and assignment of class notations.

## 1.4 Information required

1.4.1 In addition to the information and plans required by Pt 3, Ch 1,5, the following are to be submitted:

- (a) Details of overlap arrangement of steps in decks and longitudinal bulkheads.
- (b) Details of outline stowage arrangement of containers.
- (c) Details of design container stack weights.
- (d) Details of cell guides and supporting structure indicating the position of guides relative to hatch corners, and attachment to structural members.
- (e) Details of reinforcement to structure in way of container corners/supports.
- (f) Details of reinforcement to structure in way of lashing bridges where fitted.
- (g) Details showing the location of all openings in decks within the cargo holds.
- (h) Details of longitudinal girders supporting hatch coamings where fitted.

## 1.5 Symbols and definitions

1.5.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L, L_{pp}, B, D, T, V, C_b$  as defined in Pt 3, Ch 1,6

$e$  = base of natural logarithms, 2,7183

$k_L, k$  = higher tensile steel factor, see Pt 3, Ch 2,1

$s$  = spacing of secondary stiffeners, in mm

$s_1$  = spacing of secondary stiffeners, but is not to be taken less than  $470 + 1,67L$  mm

$t$  = thickness of plating, in mm

$L_1$  =  $L$  but need not be taken greater than 190 m

## Section 2 Materials

### 2.1 Materials

2.1.1 Materials are to comply with Pt 3, Ch 2.

2.1.2 Attention is drawn to the specific requirements for container ship hatch corners in Pt 3, Ch 2, Note 1 of Table 2.2.1.

## 2.2 Protection of steelwork

2.2.1 In addition to the requirements of Pt 3, Ch 2,3 the requirements of Ch 1,2.2.3 may also be applied.

## Section 3 Longitudinal strength

### 3.1 General

3.1.1 Longitudinal strength calculations are to be carried out in accordance with 3.2 and 3.3.

3.1.2 Alternatively the values and distributions of wave induced loads may be derived by direct calculation, see Pt 3, Ch 4,2.5.

3.1.3 For ships of abnormal hull form, or for ships of unusual structural configuration or complexity, the values and distributions of wave induced loads are to be agreed with LR.

### 3.2 Longitudinal strength

3.2.1 Longitudinal strength calculations are to be made in accordance with the requirements of Pt 3, Ch 4 and the additional notes contained in this Section.

3.2.2 The design vertical wave bending moments and design wave shear forces to be used in Pt 3, Ch 4 are to be determined in accordance with Ch 2,2.4 and 2.5.

### 3.3 Combined longitudinal and torsional strength

3.3.1 The strength of the ship to resist a combination of longitudinal and torsional loads is to be determined in accordance with 14.1.

## Section 4 Deck structure

### 4.1 General

4.1.1 The requirements of Ch 1,4 are to be complied with as modified by this Section.

4.1.2 The strength deck is to be longitudinally framed throughout the region of container holds for ships where  $L \geq 100$  m.

4.1.3 Lower decks/side stringers are to be efficiently scarfed into the machinery space, and the fore end and aft end structure.

# Container Ships

## Part 4, Chapter 8

### Section 4

4.1.4 The ShipRight FDA Procedure, *Structural Detail Design Guide (SDDG)*, indicates recommended examples of structural design configurations in critical areas of deck structures.

#### 4.2 Primary supporting structure

4.2.1 Where decks form part of the primary support structures described in 6.2 and 9.2 the scantlings of the decks are to be verified by direct calculation procedures in accordance with 14.2.

#### 4.3 Deck plating and stiffeners

4.3.1 Strength/weather deck scantlings outside the line of hatch openings are to satisfy the requirements of Section 3 and 4.2, and are to be not less than required by Ch 1,4.2 and Ch 1,4.3.

4.3.2 Within the cargo holds, strength/weather/second deck scantlings inside the line of hatch openings are to satisfy the requirements of Sections 3, 4.2 and 4.4.

4.3.3 Other deck scantlings are to satisfy the requirements of Sections 3, 4.2 and Ch 1,4 as appropriate.

#### 4.4 Cross decks

4.4.1 The width and scantlings of cross-deck strips are to satisfy the requirements of 4.2. The thickness,  $t$ , of cross deck strips is to comply with the requirements of Table 8.4.1.

**Table 8.4.1 Cross deck plating**

Location	Minimum thickness, in mm
At strength deck	The greater of the following: (a) $t = 0,012s_1$ (b) $t = 10 + 0,01L_1$
At second deck	The greater of the following: (a) $t = 0,012s_1$ but need not exceed 12 (b) $t = 8,0$
Symbols	
$s_1$ and $L_1$ as defined in 1.5.1.	

4.4.2 The thickness may require to be increased locally in way of access openings.

4.4.3 Where the difference between the thickness of plating inside and outside the line of main hatchway openings exceeds 25 mm, a single transition plate is to be fitted at the end of the cross deck strip. The thickness of the transition plate is to be equal to the mean of the adjacent plate thicknesses.

4.4.4 The scantlings of cross-deck stiffeners are to comply with Ch 1,4.

4.4.5 For initial design purposes the width of the cross deck strips,  $w$ , forming a transverse bulkhead top box (or equivalent) can be estimated according to the following formula:

$w = 32,5B + 400$ , or 1000 mm, whichever is the greater where  $B$  is given in 1.5.1.

#### 4.5 Deck openings

4.5.1 The corners of main hatchway openings are generally to be rounded. However, corners with negative radii, or parabolic or elliptic profiles will be specially considered.

4.5.2 The design of hold corners including deck thickness and corner profile is to comply with either 4.5.3 or 4.5.4.

4.5.3 The design of hatch corners is to be verified by direct calculations (see 14.1.1).

4.5.4 Alternatively, where the design of hatch corners has not been verified by direct calculations:

- The outboard radius of main hatchway openings at strength deck level is, in general, to be not less than 35 per cent of the width of the cross deck strip indicated in 4.4.5 with a minimum of 300 mm.
- The radius of the hatch corners of the main hatchway openings adjacent to the engine room is to be made as large as practicable, with a radius of approximately  $40B$  mm.
- Insert plates at main hatch corners, are to have an increased thickness above the adjacent plating outside the line of hatchways of 15 per cent in way of the container holds, and 25 per cent in container holds at engine room bulkheads. The minimum increase is to be not less than 4,0 mm, nor need exceed 7,0 mm, and the minimum fore and aft extent is to be 1,0 m from the edge of the openings.

#### 4.6 Local reinforcement

4.6.1 Attention is to be paid to structural continuity, and abrupt changes of shape, section or plate thickness are to be avoided, particularly in highly stressed areas. Arrangements in way of openings are to be such as to minimize the creation of stress concentrations.

4.6.2 In general, large access openings are not to be arranged in the strength deck outside the line of main hatchways in the region of container holds.

4.6.3 Small openings, such as those for ventilation pipes or scuppers, are to be kept clear of hold corners, ends of longitudinal hatch coamings, ends of cross deck strips and other critical locations.

## 4.7 Support for container corner seats

4.7.1 In general, local stiffening is to be fitted under seats for container supports.

4.7.2 The design of attachments to the strength deck is to minimise the effects of stress concentration, and consideration is to be given to the strength and grade of welding consumable used, (see Pt 3, Ch 10,2.10.3).

4.7.3 The strength of support arrangements is to be verified in accordance with Pt 3, Ch 14,4.

4.7.4 Doubler plates are not to be utilised in connections subject to tensile loads.

## Section 5 Shell envelope plating

### 5.1 General

5.1.1 The requirements of Ch 1,5 are to be applied, together with the requirements of this Section.

5.1.2 The bottom shell is, in general, to be longitudinally framed for ships where  $L > 100$  m.

5.1.3 The side shell may be longitudinally or transversely framed, except in way of the topside torsion box which is, in general, to be longitudinally framed.

### 5.2 Bottom shell and bilge

5.2.1 The thickness of the bottom shell plating is to satisfy the requirements of Section 3 and 7.2 and is to be not less than required by Ch 1,5.3.

5.2.2 In regions where transverse framing is adopted, particularly towards the end of the ship, the buckling stability of the plating will be specially considered.

### 5.3 Side shell and sheerstrake

5.3.1 The thickness of the side shell and sheerstrake plating is to satisfy the requirements of Section 3 and 6.2 and is to be not less than required by Ch 1,5.4.

5.3.2 At positions where high shear forces are present, local increases in thickness may be required.

5.3.3 The difference in thickness between the sheerstrake and shell plating below is not to exceed 25 mm.

## Section 6 Shell envelope framing

### 6.1 General

6.1.1 The requirements of Ch 1,6 are to be applied, together with the requirements of this Section.

6.1.2 The ShipRight FDA Procedure, *Structural Detail Design Guide (SDDG)* indicates recommended examples of configurations for end connections of shell envelope longitudinals.

### 6.2 Side shell primary supporting structure

6.2.1 A primary supporting structure for side shell envelope framing is to be provided of either single or double skin construction. This normally consists of a combination of vertical transverse webs and horizontal side stringers/decks.

6.2.2 Transverse webs supporting side shell envelope framing are to be arranged in line with the floors in the double bottom to ensure continuity of transverse strength.

6.2.3 The scantlings of double skin primary structure, including thickness of side shell envelope plating, are to be verified by direct calculations in accordance with 14.2.

6.2.4 The scantlings of single skin primary structure are to comply with Ch 1,6.4. Alternatively the scantlings are to be verified by direct calculations in accordance with 14.2.

### 6.3 Side stringers in double skin construction

6.3.1 The scantlings of side stringers are to satisfy the requirements of Sections 3, 6.2 and 6.5.

6.3.2 In addition, the scantlings of watertight side stringers are to satisfy the requirements of Ch 1,9.

### 6.4 Transverse webs in double skin construction

6.4.1 The scantlings of transverse webs are to satisfy the requirements of 6.2 and 6.5.

6.4.2 Transverse webs are to be efficiently stiffened, and the thickness increased locally where necessary on account of high shear stress.

6.4.3 Where, towards the end of the ship, the width of transverse webs reduces from that assumed in the direct calculations, the thickness may require to be increased locally.

### 6.5 Minimum thickness of transverse webs/side stringers in double skin construction

6.5.1 Transverse webs and side stringers are to have a thickness,  $t$ , not less than:

$$t = 7,5 + 0,015L \text{ or } 9 \text{ mm whichever is the lesser.}$$

## ■ Section 7 Double bottom structure

### 7.1 General

7.1.1 The double bottom is, in general, to be longitudinally framed for ships where  $L \geq 100$  m.

7.1.2 Longitudinally framed double bottoms are to comply with Ch 1,8.2 and the contents of this Section.

7.1.3 Transversely framed double bottoms are to comply with Ch 1,8.

7.1.4 The ShipRight FDA Procedure, *Structural Detail Design Guide (SDDG)*, indicates recommended examples of structural design configurations in critical areas of the double bottom.

### 7.2 Double bottom primary supporting structure

7.2.1 The primary supporting structure formed by the double bottom comprises inner bottom plating, floors, longitudinal girders and bottom shell plating.

7.2.2 The scantlings of this primary structure are to be verified by direct calculations in accordance with 14.2.

7.2.3 Where, towards the end of the ship, the depth of double bottom structure webs is reduced from that assumed in the direct calculations, the thickness may require to be increased locally.

7.2.4 Where mid-hold or quarter-length-of-hold supports for the double bottom structure are arranged, these are to take the form of an efficiently stiffened transverse box or open section structure, see 9.4.

### 7.3 Inner bottom plating and stiffening

7.3.1 The scantlings of the inner bottom are to satisfy the requirements of Section 3 and 7.2 and are to be not less than required by Ch 1,8.4 as modified by this sub-Section.

7.3.2 The requirements of Ch 1,8.4.2 need not be applied to container ships.

7.3.3 In applying Ch 1,8.4.5, the Rule value of bottom longitudinals may be calculated assuming  $F_{sb} = 1,05$ .

### 7.4 Girders

7.4.1 Girders are, in general, to be arranged under container corner seatings.

7.4.2 The scantlings of watertight centreline/side girders are to satisfy the requirements of Section 3 and 7.2 and are to be not less than required by Ch 1,8.3.

7.4.3 The scantlings of non-watertight centreline/side girders are to satisfy the requirements of Section 3 and 7.2.

7.4.4 For double bottoms having a depth greater than 1,6 m, additional longitudinal stiffening may have to be introduced in order to ensure the buckling stability of the girders.

### 7.5 Floors

7.5.1 Plate floors are to be fitted under watertight bulkheads, non-watertight bulkheads/mid-hold supports, under container corners at hold quarter length locations and at other locations to ensure that the maximum spacing does not, in general, exceed 3,8 m. Proposals for floor spacings greater than 3,8 m are to be supported by direct calculations agreed with LR.

7.5.2 The scantlings of watertight floors are to satisfy the requirements of 7.2 and are to be not less than required by Ch 1,8.5.

7.5.3 The thickness,  $t$ , of non-watertight floors is to satisfy the requirements of 7.2 and is to be not less than:

$$t = 6 + 0,03L \text{ or } 12 \text{ mm, whichever is the lesser.}$$

7.5.4 Non-watertight floor stiffeners are to be fitted at approximately the same spacing as the bottom longitudinals. The scantlings are to satisfy the requirements of Pt 3, Ch 10.

7.5.5 Docking brackets, or equivalent, are to be fitted in accordance with Ch 1,8.5.3.

### 7.6 Support for containers

7.6.1 In general, local stiffening is to be fitted to double bottom floors or girders under container corner seatings in order to ensure the effective transmission of load.

7.6.2 Such stiffening normally takes the form of additional brackets with suitable extensions to adjacent stiffening members. The scantlings of the adjacent stiffening members may require to be increased depending on the arrangements proposed.

7.6.3 Attention is drawn to the benefit of direct support in order to minimise the effect of eccentric loading on the support brackets.

7.6.4 The scantlings of these arrangements may be determined utilising simple beam models to verify the shear and bending strength. Based on static container loads, the stresses induced in the structure are not to exceed the permissible values stated in Table 8.7.1. Alternative more complex assessment methods are to be agreed with LR.

7.6.5 In general, doubling members or equivalent structures are to be attached to the inner bottom to distribute the load from container corners into the supporting structure. Doubler plates are to have well-rounded corners.

**Table 8.7.1 Permissible stress values**

	Permissible stress, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Normal stress (bending, tension, compression)	$0,67\sigma_0$
Shear stress	$0,4\sigma_0$
Combined stress	$0,86\sigma_0$
Symbols	
$\sigma_0$ = specified minimum yield stress, in N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	

## Section 8 Longitudinal bulkheads

### 8.1 General

8.1.1 The requirements of Ch 1,9 are to be applied, together with the requirements of this Section.

8.1.2 Longitudinal bulkheads may be transversely or longitudinally framed, except in way of the topside torsion box which is, in general, to be longitudinally framed.

8.1.3 Longitudinal bulkheads are to be maintained continuous in way of the machinery space where this is situated between container holds and as far forward and aft as practicable.

8.1.4 The scarfing arrangements in way of the steps are to be sufficient to ensure an efficient overlap of the inner skin bulkheads.

8.1.5 The ShipRight FDA Procedure, *Structural Detail Design Guide (SDDG)*, indicates recommended examples of structural design configurations in critical areas of the double side skin structures.

### 8.2 Side shell primary supporting structure

8.2.1 Where the longitudinal bulkhead forms the inner skin of the side shell primary supporting structure the thickness of longitudinal bulkhead plating is to be verified by direct calculations as described in 14.2.

### 8.3 Plating and stiffeners

8.3.1 The scantlings of longitudinal bulkheads are to satisfy the requirements of Section 3 and 8.2 and are to be not less than required by Ch 1,9.

8.3.2 Openings in the upper parts of longitudinal bulkheads are to have shapes which minimise stress concentrations and are to be framed to ensure adequate buckling stability.

8.3.3 The difference in thickness between the top strake and the bulkhead plating below is not to exceed 25 mm.

### 8.4 Support for container corner seats

8.4.1 Where direct support for 20 ft containers by the longitudinal bulkhead is required at the mid length of a cell arranged for 40 ft containers, adequate stiffening is to be fitted in order to ensure the effective transmission of load.

8.4.2 The strength of these arrangements is to be verified in accordance with Pt 3 Ch 14,4.

## Section 9 Transverse bulkheads

### 9.1 General

9.1.1 The requirements of Ch 1,9 are to be applied, together with the requirements of this Section.

9.1.2 Watertight transverse bulkheads may be vertically or horizontally framed.

9.1.3 The ShipRight FDA Procedure, *Structural Detail Design Guide (SDDG)*, indicates recommended examples of structural design configurations in critical areas of transverse bulkhead structures.

### 9.2 Transverse watertight/non-watertight bulkhead primary supporting structure

9.2.1 The primary supporting structure of transverse bulkheads normally comprises a grillage of vertical webs and horizontal stringers/decks.

9.2.2 Vertical webs are to be fitted in line with double bottom girders.

9.2.3 The scantlings of transverse bulkhead primary structure including bulkhead plating are to be verified by direct calculations as described in 14.2.

9.2.4 The scantlings are to be adequate for the static and dynamic loads imposed on the structure by the container stowage arrangements.

### 9.3 Transverse watertight bulkheads

9.3.1 The thickness of the transverse bulkhead plating is to satisfy the requirements of 9.2 and is to be not less than required by Ch 1,9.2 for watertight bulkheads.

9.3.2 In general, a transverse box structure or equivalent is to be arranged at upper deck level.

9.3.3 In certain cases, a transverse box structure at the inner bottom may also be required.

# Container Ships

## Part 4, Chapter 8

Sections 9, 10 &amp; 11

### 9.4 Transverse non-watertight mid-hold bulkheads

9.4.1 Where non-watertight bulkheads are arranged in conjunction with the double bottom mid-hold support, a transverse box is to be arranged at strength deck level.

9.4.2 Non-watertight bulkhead scantlings are to satisfy the requirements of 9.2 and Ch 1,4.4 for a non-watertight pillar bulkhead.

## Section 10 Hatch coamings and support for hatch covers

### 10.1 Hatch coamings

10.1.1 Scantlings of hatch coamings are to comply with Pt 3, Ch 11,5 in addition to the requirements of this Section. For ships where the base of the hatch coaming is more than one standard superstructure height (as defined in Pt 3, Ch 8,1.3.2) above the freeboard deck a reduction of the minimum thickness by 1 mm will be permitted.

10.1.2 Continuous side coamings are to be effectively scarfed into the deckhouse structure or gradually tapered at ends, as applicable. The scantlings are also to satisfy the requirements of Section 3.

10.1.3 The scantlings of transverse hatch coamings forming part of a transverse bulkhead top box are also to satisfy the requirements of 9.2.

10.1.4 The ShipRight FDA Procedure, *Structural Detail Design Guide* (SDDG), indicates examples of recommended structural design configurations in critical areas of the hatch side coamings.

### 10.2 Support for inboard edges of hatch covers by girders

10.2.1 Where longitudinal underdeck girders are fitted at deck level to support the hatch covers the requirements of this sub-Section are to be complied with.

10.2.2 The girders may take the form of open or closed box sections and these should align with webs on the transverse bulkheads to form a continuous ring structure.

10.2.3 The girders are, in general, to be continuous throughout the container hold area, including the engine room where this is situated between container holds.

10.2.4 Special attention is to be given to the intersection of the girders with transverse box girders and the integration into the fore end, aft end and machinery space structures.

10.2.5 Where girders are integrated into the cross deck strips, inserts plates with integral gussets are to be incorporated. The inserts are to have a thickness not less than that of the girder top and bottom plates, as appropriate. The radius of main hatchway openings in way of ends of hatch girders at upper deck level is, in general, to be not less than 20 per cent of the width of the cross deck strip indicated in 4.4.5 with a minimum of 250 mm.

10.2.6 Scantlings of girders are to comply with the requirements of Ch 1,4.

### 10.3 Support for hatch cover fittings

10.3.1 The width of hatch coaming top plates is to be suitable to accommodate the hatch covers and associated fittings.

10.3.2 Local stiffening is to be fitted below hatch cover supporting devices and in some cases the thickness of the coaming in way may need to be increased, (see also Pt 3, Ch 11,4.2.3 and 5.2.12).

## Section 11 Hatch covers

### 11.1 General

11.1.1 The requirements of Pt 3, Ch 11 are to be complied with in addition to the requirements of this Section.

11.1.2 For the purposes of this Section, hatch covers are categorized into two types as indicated in Table 8.11.1.

**Table 8.11.1 Definitions of hatch cover types**

Type	Description
I	All edges of the hatch cover are supported by external structures
II	One or more edges of the hatch cover are self-supporting

11.1.3 The primary structure of hatch covers normally consists of an arrangement of deep beams and girders including hatch cover top plating.

11.1.4 For hatch covers subjected to point loads from containers, the primary structure scantlings are to be verified by direct calculation in accordance with 11.2.

11.1.5 Local stiffening is to be arranged below container corners.

# Container Ships

## Part 4, Chapter 8

Section 11

### 11.2 Direct calculations


11.2.1 Direct calculations are to be based on 2D or 3D finite element analysis. Simplified boundary constraints may be applied in the modelling, provided this does not compromise the overall structural response.

11.2.2 The load cases, method of loading and acceptance criteria are indicated in Tables 8.11.2 and 8.11.3.

### 11.3 Omission of hatch cover gaskets

11.3.1 For ships which have hatch covers in the position defined in Pt 3, Ch 11,2.2.5, special consideration will be given to the omission of gaskets and a reduction in number of cleats. The agreement of the National Authority will be required in such cases.

11.3.2 The horizontal gap between panels is not to exceed 50 mm.



**Table 8.11.2 Loadcases for direct calculations**

Application	Loadcase	Applied loading
Type I, II	Loadcase 1 UDL Weather Load	Uniform distributed weather loading as defined in Pt 3, Ch 11,1.2 and 2.2.5
Type I, II	Loadcase 2 Container Load - Static Upright	Container loads normal to the hatch cover top plating, see Fig. 8.11.1 $F_a, F_b = \frac{W_T}{4}$
Type II	Loadcase 3 Container Load - Static Heeled	Static container loads normal to the hatch cover top plating, see Fig. 8.11.1 $F_a = 0,25\cos\theta W_T + 0,5 \frac{\sin\theta}{b_1} \sum_{i=1}^n (W_i Z_i)$ $F_b = 0,25\cos\theta W_T - 0,5 \frac{\sin\theta}{b_1} \sum_{i=1}^n (W_i Z_i)$
Symbols		
$F_a$ and $F_b$ = corner forces acting on a hatch cover at each end of the container $b_1$ = distance between the twistlocks $n$ = number of containers in stack, see Note $W_i$ = specified weight of each individual container, see Note $W_T$ = total stack weight $Z_i$ = lever to vertical centre of gravity of each container above base of stack. Vertical centre of gravity is assumed one third of the container depth above the base of the container $\theta$ = roll angle of 30°		
NOTE $W_i$ and $n$ are to be specified based on the most onerous stack weight combination.		



**Table 8.11.3 Assessment criteria for direct calculations**

Loadcase	Permissible bending stress N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Permissible shear stress N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Permissible deflection	Buckling requirement
1	Pt 3, Ch 11, Table 11.2.3 for uniform distributed (weather load)			
2	117,7/k (12,0/k)	68,7/k (7,0/k)	0,0035l <sub>0</sub>	Pt 3, Ch 11, Table 11.2.1 See Note 1
3	164,5/k (16,8/k)	98,7/k (10,1/k)	See Notes 2 and 3	
Symbols				
l <sub>0</sub> = unsupported span, in metres as shown in Fig. 11.1.2 in Pt 3 Ch 11.				
NOTES				
1. In using Table 11.2.1 in Pt 3, Ch 11, the ratio σ <sub>c</sub> /σ <sub>b</sub> (or σ <sub>ac</sub> /σ <sub>b</sub> ) is not to be less than 1,15 where the primary bending stress acts on either the longer or shorter panel edge.				
2. The weathertightness is to be maintained where appropriate.				
3. When the deflection exceeds 0,0045l <sub>0</sub> , ultimate strength of the hatch cover is to be specially considered.				
4. No allowance is to be given for the effect of cargo securing loads.				

## 11.4 Omission of hatch covers

11.4.1 Proposals for the omission of hatch covers will be specially considered. Such proposals are to include details, established by model tests or alternative means, of the quantity of water likely to ingress the cargo holds under the worst sea-going and weather conditions, and the means by which it is to be efficiently and safely discharged. The proposals will also require to be agreed by the National Authority in order that an exemption from the Load Line Convention requirements for hatch covers may be obtained.

## 13.2 Stowage on decks/hatch covers

13.2.1 Strength of support structures for pads/pedestals under container corners, lashing equipment and lashing bridges is to comply with Pt 3, Ch 14,4.

## Section 12 Strengthening for wave impact loads

### 12.1 General

12.1.1 The scantlings of plating, stiffeners and primary structure of forward and after portions of the hull are to be increased for protection against bow flare and wave impact pressure in accordance with Ch 2,4.3 and 5.2.

## Section 13 Container stowage systems

### 13.1 Cell guide systems

13.1.1 Where cell guide systems are fitted to support containers in holds or on deck, they are to comply with the requirements of Pt 3, Ch 14,7.

## Section 14 Direct calculation

### 14.1 Procedures for calculation of combined longitudinal and torsional strength

14.1.1 For container ships as defined in 1.3.3(b), (c) and (d) or with beam greater than Panamax, longitudinal strength calculations are to be made in accordance with LR's ShipRight SDA Procedures.

14.1.2 For other container ships with large deck openings, longitudinal strength calculations are to be made in accordance with the requirements of Section 15.

### 14.2 Procedures for verification of primary structure scantlings

14.2.1 For container ships defined in 1.3.3 the strength of the ship's primary structure scantlings of double bottom, side and transverse bulkheads is to be assessed in accordance with LR's ShipRight SDA Procedures.

14.2.2 For other container ships the method for analysis of primary structure of double bottom, side structure and transverse bulkheads is to be agreed with LR. Acceptable methods will include the application of LR's ShipRight SDA procedures or simplified 2D or 3D (grillage) finite element analysis. For simple structural arrangements a structural model based on elastic beam theory may also be accepted.

## Section 15

### Requirements for ships with large deck openings

#### 15.1 Application

15.1.1 A container ship has large deck openings where any of the following criteria apply:

- (a)  $\frac{b}{B_1} \geq 0,7$
- (b)  $\frac{l_H}{l_{BH}} \geq 0,89$
- (c)  $\frac{b}{B_1} \geq 0,6$  and  $\frac{l_H}{l_{BH}} \geq 0,7$

where

$b$  = overall breadth of the cargo hold, in metres. Where there are multiple openings abreast, these are regarded as a single opening, and  $b$  is to be the sum of individual breadths of these openings

$l_{BH}$  = distance between centres of the deck strip at each end of the opening, in metres. Where there is no further opening beyond the one under consideration,  $l_{BH}$  is to be measured to the end bulkhead position, see also Fig. 8.15.1

$l_H$  = length of the opening, in metres

$B_1$  = extreme breadth of ship measured at the mid-length of the opening, in metres.

#### 15.2 Definitions and information required

15.2.1 For the purposes of this Section the term 'open length' is defined as the distance between the aft end of the hatch opening adjacent to the engine room and the forward end of the foremost cargo hatch.

15.2.2 Combined stress calculations are to be carried out at a minimum of seven locations along the open length of the holds including the following:

- (a) At the forward end of the engine room.
- (b) At the forward end of the foremost cargo hatch.
- (c) Three locations within 0,4L intermediate between point (a) and point (b).
- (d) At any other sections where there are significant changes in cross-section properties.




Fig. 8.15.1 Deck openings

#### 15.3 Symbols and definitions

15.3.1 The following symbols and definitions are applicable to this Section unless otherwise stated:

- $Z_Y$  = actual hull section modulus about the transverse neutral axis at the position considered, in  $m^3$
- $Z_Z$  = actual hull section modulus about the vertical neutral axis at the position considered, in metres
- $\varepsilon$  = the distance of the shear centre below the baseline of the ship, in metres
- $M_s$  = design still water bending moment at the section under consideration, in kN m (tonne-f m)
- $\sigma_c$  = combined stress at the position considered.

#### 15.4 Design loadings

15.4.1 The design vertical wave bending moment,  $M_{WC}$ , at any position along the ship is defined as:

$$M_{WC} = 0,981C_3 C_0 L^2 B (C_b + 0,7) \text{ kN m} \\ = (0,1C_3 C_0 L^2 B (C_b + 0,7) \text{ tonne-f m})$$

$$C_0 = 0,6 + 0,0942 \left( \frac{L}{100} - 1 \right)$$

$C_3$  = coefficient depending on position along the length,  $L_{pp}$ , as defined in Table 8.15.1

$L, B, C_b$  are given in 1.5.1.

15.4.2 The design horizontal wave bending moment,  $M_{HC}$ , at any position along the ship is defined as:

$$M_{HC} = 0,431C_4 L^2 B \text{ kN m} \\ = (0,044C_4 L^2 B \text{ tonne-f m})$$

Table 8.15.1 Distribution of wave bending moments and cargo torque

Position		Distribution factors		
		$C_3$		$C_4$
		$F_n \leq 0,20$	$F_n = 0,30$	
Station	0 (A.P.)	0,00	0,00	0,0
	2	0,14	0,14	0,2
	4	0,30	0,30	0,4
	6	0,58	0,58	0,6
	8	0,87	0,87	0,8
	10 (mid - $L_{pp}$ )	1,00	1,00	1,0
	12	0,90	0,95	0,8
	14	0,68	0,80	0,6
	16	0,41	0,62	0,4
	18	0,20	0,33	0,2
	20 (F.P.)	0,00	0,00	0,0

NOTE  
For intermediate values of  $F_n$ , the factor is to be determined by linear interpolation, and for values greater than 0,3 linear extrapolation is to be used

$$F_n = \frac{0,164V}{\sqrt{L_{pp}}}$$

$C_4$  = coefficient depending on position along the length,  $L_{pp}$ , as defined in Table 8.15.1

$L$  and  $B$  are given in 1.5.1.

15.4.3 The design hydrodynamic torque,  $M_{WTC}$  at any position along the ship is defined as:

$$M_{WTC} = 0,000981 C_5 e^{-0,00295L} L B^3 C_T \left( 1,75 + 1,5 \frac{\varepsilon}{D} \right) \text{ kNm}$$

$$= \left( 0,0001 C_5 e^{-0,00295L} L B^3 C_T \left( 1,75 + 1,5 \frac{\varepsilon}{D} \right) \text{ tonne-fm} \right)$$

$$C_T = 13,2 - 43,4 C_w + 78,9 C_w^2$$

$C_w$  = the water plane area coefficient at draught  $T$ , but need not exceed  $0,165 + 0,95 C_b$

$$C_5 = \frac{1}{2} \left[ 1 - \cos \left( 2\pi \frac{x}{L_{pp}} \right) \right]$$

$x$  = position along the length  $L_{pp}$  measured from A.P.  
 $L$ ,  $L_{pp}$ ,  $B$ ,  $D$ ,  $T$  and  $C_b$ , are given in 1.5.1  
 $\varepsilon$  is given in 15.3.1.

15.4.4 The design value of static cargo torque,  $M_{STC}$  at any position along the ship is defined as:

$$M_{STC} = 15,7 C_4 B n_s n_t \text{ kN m}$$

$$(M_{STC} = 1,6 C_4 B n_s n_t \text{ tonne-f m})$$

$n_s$  = the number of stacks of containers over the breadth,  $B$

$n_t$  = the number of tiers of containers in cargo holds amidships, excluding containers on deck or on the hatch covers

$C_4$  = as defined in 15.4.2

$B$  is given in 1.5.1.

## 15.5 Combined stress

15.5.1 The combined stress,  $\sigma_c$  is to be calculated at a number of sections along the ship as defined in 15.2.2:

$$\sigma_c = \sigma_{HC} + \sigma_{WTC} + \sigma_{STC} + \sigma_{SC} + \sigma_{WC}$$

$$\sigma_{SC} = \frac{M_s}{Z_y} \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$\sigma_{WC} = 0,6 \frac{M_{WC}}{Z_y} \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$\sigma_{HC} = C_6 \frac{M_{HC}}{Z_z} \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$\sigma_{WTC}$ ,  $\sigma_{STC}$  are to be evaluated by approved calculation procedures

$\sigma_{STC}$  = warping stress due to static cargo torque

$\sigma_{WTC}$  = warping stress due to hydrodynamic torque

$C_6$  = co-efficient for shear lag depending on vertical location of the point under consideration

= 0,6 of inboard edge of strength deck

= 1,0 at base line

= intermediate positions by interpolation

other symbols are as defined in 15.3 and 15.4.

15.5.2 At each section the stresses are to be calculated at:

- the inboard edge of the strength deck;
- the point on the bilge where the combined stress is greatest; and
- the top of continuous hatch coaming (where fitted).

## 15.6 Permissible stress

15.6.1 The combined stress  $\sigma_c$  at any position along the open length is to be not more than indicated in Table 8.15.2.

15.6.2 The assessment of combined stress may conveniently be presented in the form of a combined stress diagram as indicated in Fig. 8.15.2.




Table 8.15.2 Permissible stress

Position	Permissible combined stress N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )
Top of continuous hatch coaming where fitted	$\sigma_c = \frac{175}{k_L} \left( \frac{17,84}{k_L} \right)$
Elsewhere	$\sigma_c = \frac{157}{k_L} \left( \frac{16,0}{k_L} \right)$

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 1

### Section

- 1 **General**
- 2 **Materials and protection**
- 3 **Longitudinal strength**
- 4 **Hull envelope plating**
- 5 **Hull framing**
- 6 **Inner hull, inner bottom and longitudinal oiltight bulkheads**
- 7 **Transverse oiltight bulkheads**
- 8 **Non-oiltight bulkheads**
- 9 **Primary members supporting longitudinal framing**
- 10 **Construction details and minimum thickness**
- 11 **Ships for alternate carriage of oil cargo and dry bulk cargo**
- 12 **Heated cargoes**
- 13 **Access arrangements and closing appliances**
- 14 **Direct calculations**

### ■ Section 1 General

#### 1.1 General

1.1.1 This Chapter applies primarily to the arrangements and scantlings within the cargo tank region of sea-going tankers having integral cargo tanks, for the carriage of oil having a flash point not exceeding 60°C (closed cup test), in association with the class notation indicated in 1.3.1 or 1.4.1. Except as indicated in 1.1.2, 1.1.3 and 1.1.4, the cargo spaces are to be bounded by side and bottom dedicated water ballast tanks or void spaces constituting a double hull for the ship, see Table 9.1.1.

1.1.2 Double side tanks may be dispensed with for tankers of less than 5000 tonnes deadweight where each cargo tank capacity does not exceed 700 m<sup>3</sup>, see Table 9.1.1.

1.1.3 Double bottom tanks may be dispensed with for tankers of 5000 tonnes deadweight or greater subject to compliance with the requirements of 1.2.18.

1.1.4 Double bottoms and double sides may be dispensed with for vessels less than 600 tonnes deadweight, see Table 9.1.1.

1.1.5 Where only oils having flash points exceeding 60°C are to be carried, the Rule requirements and class notation will be modified accordingly the additional class notation 'F.P. exceeding 60°C' will be entered in the *Register Book*.

1.1.6 Oil cargoes listed in Table 9.1.2 are those which are generally envisaged as being carried in ships classed in accordance with this Chapter.

1.1.7 The scantlings and arrangements of tankers intended for cargoes other than oil will be specially considered in relation to the characteristics of the cargo, and the class notation will be modified accordingly. A full list of such cargoes for a particular ship, with special requirements as applicable, can be provided by Lloyd's Register (hereinafter referred to as 'LR') on application. Chemical cargoes listed in Chapter 18 of the *Rules and Regulations for the Construction and Classification of Ships for the Carriage of Liquid Chemicals in Bulk* (hereinafter referred to as the Rules for Ships for Liquid Chemicals) may be carried in ships for which the arrangements, scantlings and materials comply with the requirements of that Chapter. Special consideration will also be given to the carriage of cargoes with a relative density greater than 1,025, see also 1.3 and 1.4.

1.1.8 Where higher tensile steel is incorporated in principal structural members, a suitable descriptive note may be entered in the *Register Book*.

1.1.9 The Regulations for classification and assignment of the above notations and other notations, as appropriate to the arrangements, scantlings and service are provided for in Pt 1, Ch 2.2.

#### 1.2 Application and ship arrangement

1.2.1 Double hull tankers with length, *L*, greater than or equal to 150 m with structural configuration as shown in Table 9.1.3 are defined as 'CSR Oil Tankers' and are to comply with 1.3.

1.2.2 The applicable Rules for Double hull tankers with length, *L*, greater than or equal to 150 m of unusual hull form or structural arrangements will be specially considered.

1.2.3 Double hull tankers with length, *L*, less than 150 m are defined as 'Non-CSR Oil Tankers' and are to comply with 1.4.

1.2.4 Any dry tanks, or tanks intended for water ballast and thus empty in the loaded condition, are to be so arranged that they cannot be used for any other purpose.

1.2.5 Cofferdams are to be provided at the forward and after ends of the oil cargo spaces; cofferdams are to be at least 760 mm in length and are to cover the whole area of the end bulkheads of the cargo spaces.

1.2.6 A pump room, oil fuel bunker or water ballast tank will be accepted in lieu of a cofferdam.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 1

**Table 9.1.1 Cargo tank boundary requirements**

Deadweight (DWT) tonnes	Minimum double side width ( $d_s$ ) metres	Minimum double bottom depth ( $d_b$ ) metres
DWT $\geq$ 5000	$d_s = 0,5 + \frac{DWT}{20\,000}$ or $d_s = 2,0$ whichever is the lesser, but not less than 1,0	$d_b = \frac{B}{15}$ or $d_b = 2,0$ whichever is the lesser, but not less than 1,0
600 $\leq$ DWT < 5000	$d_s = 0,4 + \frac{2,4\,DWT}{20\,000}$ or $d_s = 0,76$ whichever is the greater, see Note 2	$d_b = \frac{B}{15}$ or $d_b = 0,76$ whichever is the greater
DWT < 600	$d_s = 0$	$d_b = 0$
<p>NOTES</p> <p>1. The symbols DWT, <math>d_s</math> and <math>d_b</math> are defined in 1.5.</p> <p>2. Where each cargo tank capacity does not exceed 700 m<sup>3</sup>, the value of <math>d_s</math> is taken as 0 and the inner bottom line is to run parallel to the line of the midship flat of bottom as shown in Fig. 9.1.2.</p> <p>3. Where the double bottom tank is fitted, the centre girder depth is to be not less than as required by 9.3.3.</p>		

**Table 9.1.2 Oil cargoes suitable for carriage in oil tankers, see Note 1**

<p><b>Asphalt solutions</b> (see Note 2) Blending Stocks Roofers Flux Straight Run Residue</p> <p><b>Oils</b> Clarified Crude Oil Mixtures containing crude oil Diesel Oil Fuel Oil No. 4 Fuel Oil No. 5 Fuel Oil No. 6 Residual Fuel Oil Road Oil Transformer Oil Lubricating Oils and Blending Stocks Mineral Oil Motor Oil Penetrating Oil Spindle Oil Turbine Oil</p> <p><b>Distillates</b> Straight Run Flashed Feed Stocks</p> <p><b>Gas Oil</b> Cracked</p>	<p><b>Gasoline Blending Stocks</b> Alkylates - fuel Reformates Polymer - fuel</p> <p><b>Gasolines</b> Casinghead (natural) Automotive Aviation Straight Run Fuel Oil No. 1 (Kerosene) Fuel Oil No. 1-D Fuel Oil No. 2 Fuel Oil No. 2-D</p> <p><b>Jet Fuels</b> JP-1 (Kerosene) JP-3 JP-4 JP-5 (Kerosene, Heavy) Turbo Fuel Kerosene Mineral Spirit</p> <p><b>Naphtha</b> (see Note 3) Solvent Petroleum Heartcut Distillate Oil</p>
<p>NOTES</p> <p>1. This list of oils is taken from Appendix 1 to Annex 1 of the MARPOL Convention. Special consideration will be given to the carriage of oil cargoes not included in the above list.</p> <p>2. Asphalt solutions, see Chapter 18 of the Rules for Ships for Liquid Chemicals.</p> <p>3. For naphtha coal tar and naphthalene molten, see Chapter 17 of the Rules for Ships for Liquid Chemicals.</p>	

1.2.7 Where the lower portion of the pump room is recessed into the machinery space, the height of the recess is not, in general, to exceed one-third of the moulded depth above the keel, see also Pt 5, Ch 15,1.

1.2.8 Where a compartment or tank, such as a fore peak tank, forms a cofferdam, access is to be from the open deck. Alternatively, any space through which it is necessary to pass in order to obtain access is to conform to the requirements of Pt 6, Ch 2,13. Oil engine or electrically driven pumps are not to be sited in the space containing the access to such cofferdams.

1.2.9 A cofferdam is also to be arranged between a cargo oil tank and accommodation spaces, and between cargo oil tanks and spaces containing electrical equipment, other than spaces where the only items of electrical equipment are lighting fittings complying with Pt 6, Ch 2,13. Where a corner-to-corner situation occurs, protection may be formed by a diagonal plate across the corner. The scantlings and testing arrangements are to comply with Rule requirements for cofferdam bulkheads, and arrangements are to be made to enable the space to be filled with water ballast to assist in gas freeing, see also Pt 5, Ch 15,3. Suitable corrosion protection, drainage and gas-freeing arrangements are to be provided to such spaces.

1.2.10 Passages or tunnels passing through, or adjacent to, a cargo oil tank and not separated from it by a cofferdam, are to be provided with mechanical ventilation, and any access is to be from the open deck.

1.2.11 Arrangements are to be provided to enable double bottom and vertical wing tanks to be filled with water ballast to assist in gas freeing these tanks, see Pt 5, Ch 15,3.






1.2.12 Fittings within cargo tanks and pump rooms are to be securely fastened to the structure.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 1

**Table 9.1.3 Structural arrangement**

Arrangement	Typical configuration	$L < 150$	$L \geq 150$
No longitudinal bulkhead		Non CSR	CSR (specially considered)
One or two longitudinal bulkhead(s)		Non CSR	CSR
Trunk deck in association with longitudinal bulkhead(s) (see Ch 10,6)		Non CSR	CSR
Double deck in association with a centreline bulkhead		Non CSR	CSR (specially considered)
Mid-deck in association with a centreline bulkhead or centreline girders		Non CSR	CSR (specially considered)

**1.2.13** Accommodation, control and service spaces are to be located clear of the cargo tank region such that a single failure of deck or bulkhead will not allow cargo fumes into these spaces. Navigation positions, where fitted above the cargo tank region, are to be separated from the cargo tank deck by means of an open space with a height of at least 2,0 m.

**1.2.14** Where spill retainment flats are fitted at the sides of the weather deck, separate arrangements are to be provided for freeing the deck of oil and water respectively, see also Pt 3, Ch 10,5.1.1.

**1.2.15** Alternative arrangements which are proposed as being equivalent to the Rules will receive individual consideration, taking into account any relevant National Authority requirements.

**1.2.16** Reference should also be made to the relevant Regulations of the *International Convention for the Safety of Life at Sea, 1974* and applicable amendments.

**1.2.17** Cargo spaces are to be bounded by double bottom and double side tanks or void spaces such that the distance between the cargo tank boundary and the shell plating is not less than that given in Table 9.1.1 and Fig. 9.1.1, except as otherwise specified in 1.2.18 and 1.2.19. Cargo or oil fuel are not to be carried in double bottom or double side tanks.

**1.2.18** Where  $DWT \geq 5000$  tonnes, double bottom tanks as required by 1.2.17 may be dispensed with, provided the following requirements are complied with:

(a) The cargo height,  $h_c$ , in contact with the bottom shell plating is to be not greater than:

$$h_c = \frac{1,025T_m - 10,2P_v}{1,1p}$$

where the symbols are defined in 1.6.

(b) Where a mid-deck dividing the cargo oil tanks into upper and lower spaces is arranged, it is to be located at a height of not less than the lesser of  $\frac{B}{6}$  or 6 m, but not

more than  $0,6D$ , above the base line.

(c) Below a level  $1,5d_b$  above the base line, the cargo tank boundary line may be vertical down to the bottom shell plating as shown in Fig. 9.1.3.




**1.2.19** Alternative arrangements which are equivalent to 1.2.17 will receive individual consideration, taking into account any relevant National Authority requirements.

**1.2.20** The length of each cargo tank is not to exceed 10 m or the appropriate value obtained from Table 9.1.4, whichever is the greater.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 1



1.2.21 Where DWT  $\geq 5000$  tonnes, the cargo pump room shall be provided with a double bottom such that at any cross-section the depth of each double bottom tank or space shall be such that the distance  $d_c$ , as defined in 1.5, is not less than the lesser of  $\frac{B}{15}$  m and 2 m.

$d_c$  is in no case to be less than 1 m.  
In the case of cargo pump rooms whose bottom plate is located above the base line by at least the minimum height required, there will be no need for a double bottom construction in way of the cargo pump-room

1.2.22 Notwithstanding the requirements of 1.2.21, above, where the flooding of the cargo pump-room would not render the ballast or cargo pumping system inoperative, a double bottom need not be fitted.

**Table 9.1.4** Permissible length of cargo tanks, see 1.2.20

Number of longitudinal bulkheads inside cargo tanks		One (on centreline)	Two	Three (one on centreline)	Where no longitudinal bulkhead is arranged or where longitudinal bulkheads are perforated across breadth of cargo tanks
Length of wing cargo tank		$\left(0,25 \frac{b_i}{B} + 0,15\right) L_L$	$0,2L_L$	$0,2L_L$	$\left(0,5 \frac{b_i}{B} + 0,1\right) L_L$ or $0,2L_L$ whichever is the lesser
Length of centre tank	$b_i \geq 0,2B$	—	$0,2L_L$	$0,2L_L$ port and starboard	
	$b_i < 0,2B$	—	$\left(0,5 \frac{b_i}{B} + 0,1\right) L_L$	$\left(0,25 \frac{b_i}{B} + 0,15\right) L_L$ port and starboard	
NOTE The symbols $L_L$ , $B$ and $b_i$ are defined in 1.5.					



# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 1

### 1.3 Class notation and applicable Rules for CSR Double Hull Oil Tankers

1.3.1 In general, CSR Double Hull Oil Tankers are to comply with 1.3.2 to 1.3.8 and the *IACS Common Structural Rules for Double Hull Oil Tankers (CSR)* for the draught required and will be eligible to be classed **100A1 Double Hull Oil Tanker CSR, ESP**.

1.3.2 Class notations applicable to CSR double hull oil tankers are defined as follows:

- **CSR**  
Identifies the double hull oil tanker as being compliant with the *IACS Common Structural Rules for Double Hull Oil Tankers*
- **ESP**  
Identifies the double hull oil tanker as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.3.12.

1.3.3 Materials are to comply with the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials). Corrosion protection is to comply with Pt 3, Ch 2,3.

1.3.4 The rudder and rudder stock are to comply with Pt 3, Ch 13,2.

1.3.5 Ice strengthening is to be in accordance with Pt 3, Ch 9.

1.3.6 The 'Construction Monitoring' (CM) procedures detailed in the *ShipRight Procedures Manual*, published by LR, are mandatory for oil tankers greater than 190 m in length and for other tankers of abnormal hull form, or of unusual structural configuration or complexity.

1.3.7 The 'ShipRight Procedures' for the hull construction of ships are detailed in Pt 3, Ch 16 and the classification notations and descriptive notes associated with these procedures are given in Pt 1, Ch 2,2.

1.3.8 Ships intended to carry heated cargoes are to comply with Section 12.

### 1.4 Class notation and applicable Rules for non-CSR Double Hull Oil Tankers

1.4.1 In general, non-CSR Double Hull Oil Tankers are to comply with 1.4.2 to 1.4.7 for the draught required and will be eligible to be classed **100A1 Double Hull Oil Tanker, ESP**.

1.4.2 The notation **ESP** serves to identify the ship as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.3.12.

1.4.3 At the Owner's request, the notation **MARPOL 20.1.3** may be appended to the notation **100A1 Double Hull Oil Tanker** for vessels not meeting the minimum double side width ( $d_s$ ) requirements of Table 9.1.1 but which comply with MARPOL Annex I, Regulation 20.1.3.

1.4.4 At the Owner's request, the notation **MARPOL 21.1.2** may be appended to the notation **100A1 Double Hull Oil Tanker** for vessels of less than 5000 tonnes deadweight which have a complete double hull in accordance with MARPOL Annex I, Regulation 21.1.2.

1.4.5 Where the length of the ship is greater than 190 m, or where the structural arrangements are considered such as to necessitate it, the scantlings of the primary supporting structure are to be assessed by direct calculation and the ShipRight notations **SDA**, **FDA** and **CM** are mandatory, see 1.4.6 and Section 14.

1.4.6 The 'ShipRight Procedures' for the hull construction of ships are detailed in Pt 3, Ch 16 and the classification notations and descriptive notes associated with these procedures are given in Pt 1, Ch 2,2.

1.4.7 The disposition of transverse bulkheads is to comply with the requirements of Pt 3, Ch 3,4, as applicable to ships with machinery located aft.

1.4.8 Arrangements and scantlings forward and aft of the cargo tank region are to comply with Pt 3, Ch 5, Ch 6 and Ch 7. The remaining requirements of Part 3 are also to be complied with as appropriate to the intended arrangements.

1.4.9 Arrangements pertaining to gangways, bulwarks and rails are to comply with the requirements of Pt 3, Ch 8.

1.4.10 The structural configurations may include one or more of the arrangements shown in Table 9.1.3. these provisions do not preclude the fitting of additional bulkheads or the perforation of longitudinal bulkheads.

1.4.11 The bottom shell, inner bottom and deck are generally to be framed longitudinally in the cargo tank region where the ship length,  $L$ , exceeds 75 m. However, consideration will be given to alternative proposals for ships of special design.

1.4.12 The side shell, inner hull bulkheads and longitudinal bulkheads are generally to be longitudinally framed where the ship length,  $L$ , exceeds 150 m, but alternative proposals, taking account of resistance to buckling, will be considered.

1.4.13 Where the side shell is longitudinally framed, the inner hull bulkheads are to be similarly constructed.

1.4.14 Provided the ship length,  $L$ , does not exceed 200 m the longitudinal bulkheads may be horizontally corrugated. Vertically corrugated centreline bulkheads may also be considered on the basis of direct calculations.

1.4.15 In general, the primary member scantlings will require to be determined by direct calculation, see also 9.1.3.

1.4.16 Alternative arrangements, which are proposed as being equivalent to the Rules, will receive individual consideration. Particular attention is to be paid to deflection of members and to the ability of the structure to resist buckling. Where necessary, additional calculations will be required.

1.4.17 For additional requirements for single hull oil tankers, see Chapter 10.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 1

1.4.18 The scantlings of structural items may be determined by direct calculation.

### 1.5 General definitions and symbols

1.5.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L$ ,  $L_L$ ,  $B$ ,  $D$ ,  $T$  as defined in Pt 3, Ch 1,6.

$d_c$  = the height between the ship's base line and the bottom of the cargo pump room, in metres

$DWT$  = deadweight, in tonnes, at the summer load waterline

$b$  = the width of plating supported by the primary or secondary member, in metres or mm respectively

$b_e$  = the effective width, in metres, of end brackets as determined from Pt 3, Ch 3,3

$b_i$  = minimum distance from side shell to inner hull/outer longitudinal bulkhead of the tank in question measured inboard at right angles to the centreline at the summer load waterline, in metres, see Table 9.1.4

$d_b$  = the distance, in metres, between the bottom of the cargo tanks and the moulded line of the bottom shell plating measured at right angles to the bottom shell plating as shown in Fig. 9.1.1 and Fig. 9.1.2

$d_s$  = the distance, in metres, between the cargo tank boundary and the moulded line of the side shell plating measured at any cross-section at right angles to the side shell as shown in Fig. 9.1.1 and Fig. 9.1.3

$h$  = the load height applied to the item under consideration, in metres

$k_L$ ,  $k$  = higher tensile steel factors. For the determination of these factors, see Pt 3, Ch 2,1. For mild steel,  $k_L$ ,  $k$  may be taken as 1,0

$l_e$  = effective length, in metres, of the primary or secondary member, measured between effective span points. For determination of span points, see Pt 3, Ch 3,3

$s$  = spacing of secondary members, in mm

$t$  = thickness of plating, in mm

$I$  = the moment of inertia, in  $\text{cm}^4$ , of a primary or secondary member, in association with an effective width of attached plating determined in accordance with Pt 3, Ch 3,3

$L_1$  = length of ship, in metres, but need not be taken greater than 190 m

$P_v$  = pressure/vacuum relief valve positive setting, in bar


$T_m$  = minimum operating moulded draught of the ship at amidships under any expected cargo loading condition, in metres

$Z$  = the section modulus, in  $\text{cm}^3$ , of the primary or secondary member, in association with an effective width of attached plating determined in accordance with Pt 3, Ch 3,3

$\rho$  = maximum cargo density, in  $\text{t/m}^3$ .

1.5.2 Where symbols not defined in 1.5.1 are used these are defined at the head of the Section concerned.

1.5.3 For oil tankers of double hull configuration the main structural and spatial terminology within the cargo length, as used in this Chapter, is shown in Fig. 9.1.4.



**Fig. 9.1.4 Structural and spatial terminology**

1.5.4 The expression 'primary member' as used in this Chapter is defined as a girder, floor, transverse, vertical web, stringer, cross-tie or buttress. 'Secondary members' are supporting members other than primary members.

### 1.6 Information required for CSR Double Hull Oil Tankers

1.6.1 In addition to the plans required by *IACS Common Structural Rules for Double Hull Oil Tankers (CSR)* the following additional plans and information is to be submitted.

- Rudder, stock and tiller;
- Ice Strengthening.
- Freeboard plan or equivalent showing freeboards and items relative to the conditions of assignment.

### 1.7 Information required for non-CSR Double Hull Oil Tankers

1.7.1 In addition to the plans required by Pt 3, Ch 1,5, plans showing the connections for all longitudinals and other framing members and arrangements at intersections of transverse and longitudinal framing are also to be submitted.

1.7.2 Any dry tanks or tanks for water ballast only, are to be indicated on the principal structural and arrangement plans.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Sections 1, 2 & 3

1.7.3 The information required by Pt 3, Ch 4,4 is to be forwarded as soon as possible and preferably when the midship section is submitted.

1.7.4 A docking plan is to be submitted for consideration of strength requirements in association with the intended docking condition.

1.7.5 A plan showing the location of all openings in the deck is to be submitted. Where it is intended to provide holes in the deck for staging wires, these holes are also to be shown. Full particulars of the proposed closing arrangements for all deck openings are to be submitted.

1.7.6 Information is required indicating the equipment provided for the acceptable means of access to meet the minimum requirements for Close-up Surveys, see also 13.2.8, 13.2.9 and Pt 1, Ch 3,7.

1.7.7 A diagrammatic plan verifying compliance with the requirements of 1.2.17 or 1.2.18 as appropriate is to be submitted.

(d) The underside of heavy portable aluminium structures such as gangways, etc., is to be protected by means of hard plastic or wood cover in order to avoid the creation of smears when dragged or rubbed across steel, which if subsequently struck, may create an incendive spark. It is recommended that such protection be permanently and securely attached to the structures.

2.3.2 For permissible locations of aluminium anodes, see Pt 3, Ch 2,3.4.

2.3.3 Paint containing aluminium should not be used in positions where cargo vapours may accumulate unless it has been shown by appropriate tests that the paint to be used does not increase the incendive sparking hazard. Tests need not be performed for coatings containing less than 10 per cent aluminium by weight.

## 2.4 Other materials

2.4.1 The suitability of coatings and their compatibility with intended cargoes are the responsibility of the Builder and the Owner. LR will, however, require the confirmation of the coating manufacturers that coatings which are used to protect the cargo tank structure are in order for the list of defined cargoes. A copy of the coating manufacturer's product resistance list is to be placed on board.

2.4.2 Attention is drawn to the requirements of Pt 3, Ch 11,7.1.4 in respect of compatibility of cargoes and hatch packing materials. The packing material is to be resistant to both the liquids and vapours to which it is exposed.

2.4.3 Some plastics and rubbers are unsuitable for certain cargoes other than oil. In such cases the manufacturer's advice should be sought.

2.4.4 Some materials or their alloys are unsuitable for certain cargoes other than oil. Where such cargoes are to be carried, the use of these materials is not permitted in locations where they may come into contact with the cargo or its vapours, see also 1.1.7.

## Section 2 Materials and protection

### 2.1 General

2.1.1 Materials, grades of steel and protection of materials are to comply with the requirements of Pt 3, Ch 2 and the Rules for Materials (Part 2).

### 2.2 Corrosion protection coatings for salt water ballast spaces

2.2.1 The requirements of Pt 3, Ch 2,3.6 are to be complied with.

### 2.3 Aluminium structure, fittings and paint

2.3.1 Aluminium may, under certain circumstances give rise to incendive sparking on impact with steel, the following requirements are therefore to be complied with:

- (a) Aluminium fittings in tanks used for the carriage of oil, and in cofferdams and pump rooms are to be avoided wherever possible.
- (b) Where fitted, aluminium fittings, units and supports, in tanks used for the carriage of oil, cofferdams and pump rooms are to satisfy the requirements specified in Pt 3, Ch 2,3 for aluminium anodes.
- (c) The danger of mistaking aluminium anodes for zinc anodes must be emphasised. This gives rise to increased hazard if aluminium anodes are inadvertently fitted in unsuitable locations.

## Section 3 Longitudinal strength

### 3.1 General

3.1.1 The longitudinal strength standard is to comply with the relevant requirements of Pt 3, Ch 4.

3.1.2 The readout points for loading instruments, fitted in accordance with the requirements of Pt 3, Ch 4,8.3 are to be positioned at the transverse bulkheads. In general, except when the instrument calculates the maximum values between readout points, the spacing of readout points within the cargo tank length is not to exceed five per cent of the ship length with intermediate points arranged between bulkheads as necessary.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 3 &amp; 4

### 3.2 Symbols

3.2.1 The symbols used in this Section are defined in 1.6.

### 3.3 Loading conditions

3.3.1 The loading conditions which are to be included in the Loading Manual and examined for longitudinal strength are given in Pt 3, Ch 4,5.

3.3.2 The Loading Manual is to contain the calculated still water bending moments and shear forces for the conditions proposed and the maximum permissible values calculated in accordance with Pt 3, Ch 4.

3.3.3 The strengthening of bottom forward derived in accordance with the requirements of Pt 3, Ch 5,1 is to be based on the minimum draught forward obtained using segregated ballast tanks only, without recourse to ballasting of cargo tanks.

3.3.4 Where bottom forward strengthening has not been arranged, at least one ballast departure and one ballast arrival condition providing for a forward draught of at least  $0,045L$  is to be included in the Loading Manual, see also Pt 3, Ch 5,1.5.

3.3.5 Where part-load conditions are proposed with a forward draught less than that for which the bottom forward arrangements and scantlings have been approved, the Loading Manual is to provide for the addition of ballast in segregated ballast tanks only as necessary to attain the required draught in heavy weather.

3.3.6 Conditions which provide for wing and centre cargo tanks abreast to be filled, with adjacent wing and centre cargo tanks empty, should, in general, be avoided. Similarly, conditions which provide for differential loading of port and starboard wing cargo tanks with centre cargo tanks empty should also be avoided. Where such conditions are contemplated, they will be subject to special consideration which may involve additional calculation in respect of the resultant effects on transverse strength and centre tank cross-tie.

3.3.7 Where a double bottom tank is omitted in accordance with 1.3.7 a minimum operating draught  $T_m$  is to be indicated on the midship section plan, the Loading Manual and Loading Instrument.


3.3.8 Tanks intended for water ballast are to be indicated in the Loading Manual.

3.3.9 Where loading conditions having partially filled tanks are contemplated, attention is drawn to the need to ensure that the scantlings of the boundary bulkheads are capable of withstanding the loads imposed by the movement of liquid in the tanks, see 6.1.2, 7.1.2 and 14.2.2.

## Section 4 Hull envelope plating

### 4.1 General

4.1.1 The thickness of hull envelope plating amidships is to be as necessary to comply with the hull section modulus, shear strength and buckling requirements of Pt 3, Ch 4, but is to be not less than as shown in Table 9.4.1 for the parts itemised in Fig. 9.4.1. Panel stability is also to be confirmed by direct calculation taking account of shear stress and direct stresses derived from both transverse and longitudinal strength investigation.



**Fig. 9.4.1**  
**Hull envelope plating – Itemization of parts**  
(See Table 9.4.1)

4.1.2 For requirements in respect of structural details, bilge keels, attachments, etc., see Pt 3, Ch 10. In addition the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG), indicates recommended structural design configurations for double hull tanker structural details to assess and improve the relative fatigue life performance of the details in critical areas.

## Double Hull Oil Tankers

## Part 4, Chapter 9

Section 4

Table 9.4.1 Hull envelope plating – minimum thickness, in mm

Hull envelope plating – minimum thickness, in mm			
Longitudinally framed	Item	Item No. (see Fig. 9.4.1)	Transversely framed (see 1.3 for limits of application)
$t = \frac{S}{J} + 2,0$ (see Note 1)	Deck	1	see 1.3
$t = \frac{S}{J} + 2,0$ or $t = 0,0042s \sqrt{h_{T1}k}$ whichever is the greater (see Note 1)	Sheerstrake and gunwale	2	$t = \frac{0,00085s}{1 + \left(\frac{S}{S}\right)^2} (0,083L_1 + 10) \sqrt{\frac{F_D}{k_L}}$ (see Note 6) or $t = 0,0042s \sqrt{h_{T1}k}$ whichever is the greater (see Note 1)
$t = 0,001s (0,059L_1 + 7) \sqrt{\frac{F_D}{k_L}}$ (see Notes 6 & 7) or $t = 0,0042s \sqrt{h_{T1}k}$ whichever is the greater (see Note 1)	Side shell above mid-depth	3	$t = \frac{0,00085s}{1 + \left(\frac{S}{S}\right)^2} (0,083L_1 + 10) \sqrt{\frac{F_D}{k_L}}$ (see Notes 6 & 7) or $t = 0,0042s \sqrt{h_{T1}k}$ whichever is the greater (see Note 1)
$t = 0,001s (0,059L_1 + 7) \sqrt{\frac{F_B}{k_L}}$ (see Notes 6 & 7) But not less than: (a) $t = 0,0042s \sqrt{h_{T1}k}$ at mid-depth (b) $t = 0,0054s \sqrt{\frac{h_{T2}k}{2 - F_B}}$ at upper turn of bilge (see Notes 1 & 2) Intermediate thickness by interpolation	Side shell below mid-depth	4	$t = 0,001s (0,059L_1 + 7) \sqrt{\frac{F_M}{k_L}}$ (see Notes 6 & 7) or
		5	$t = 0,0051s \sqrt{h_{T1}k}$ whichever is the greater (see Note 1)
$t = \frac{S}{J} + 2,0$ or $t = 0,0052s \sqrt{\frac{h_{T2}k}{1,8 - F_B}}$ mm whichever is the greater (see Note 1)	Bilge (see Note 4)	6	$t = \frac{0,00085s}{1 + \left(\frac{S}{S}\right)^2} (0,083L_1 + 10) \sqrt{\frac{F_B}{k_L}}$ (see Notes 2, 6 & 7) or $t = 0,0056s \sqrt{\frac{h_{T2}k}{1,8 - F_B}}$ whichever is the greater (see Note 1)
		7	$t = \frac{0,00085s}{1 + \left(\frac{S}{S}\right)^2} (0,083L_1 + 10) \sqrt{\frac{F_B}{k_L}}$ (see Notes 6 & 7) or $t = 0,0063s \sqrt{\frac{h_{T2}k}{1,8 - F_B}}$ mm whichever is the greater (see Note 1)
As for item 8, +2 mm, but need not exceed $25 \sqrt{k}$ mm	Bottom shell	8	see 1.3
	Keel	9	

## NOTES

- The thickness is also to satisfy the buckling requirements of Pt 3, Ch 4,7.
- The thickness of side shell plating need not exceed that which would be required for the bottom shell using the spacing of the side shell longitudinals.
- In no case is the plating thickness to be less than the cargo tank minimum value given in Section 10, or the basic shell end thickness for taper given in Pt 3, Ch 5 and Ch 6.
- See also 4.6.2 concerning plating thickness where longitudinal framing is fitted at bottom and side, but omitted in way of bilge.
- Keel thickness is in no case to be less than that of the adjacent bottom shell plating.
- Where separate maximum sagging and hogging still water bending moments are assigned,  $F_D$  may be based on the sagging moment and  $F_B$  on the hogging moment.
- Outside the Rule minimum region of higher tensile steel as defined in Pt 3, Ch 3,2.6.1 the value of  $k_L$  may be taken as 1,0.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 4

## 4.2 Symbols

4.2.1 The symbols used in this Section are defined as follows:

$F_D, F_B$  = as defined in Pt 3, Ch 4.5.6

$F_M$  = the greater of  $F_D$  or  $F_B$

$$J = 1720,5 \sqrt{\frac{1 - \frac{1}{\alpha}}{\sigma_o}} \text{ for } \alpha \leq 2$$

$$\left( J = 549,3 \sqrt{\frac{1 - \frac{1}{\alpha}}{\sigma_o}} \text{ for } \alpha \leq 2 \right)$$

$$J = 860,7 \sqrt{\frac{\alpha}{\sigma_o}} \text{ for } \alpha > 2$$

$$\left( J = 274,8 \sqrt{\frac{\alpha}{\sigma_o}} \text{ for } \alpha > 2 \right)$$

$s$  = spacing, in mm, of longitudinals or transverse frames. Except where indicated in the text,  $s$  is not to be taken less than:

$$470 + \frac{L}{0,6} \text{ mm}$$

or 700 mm whichever is the lesser

For limitations in end regions, see Pt 3, Ch 5,3 and Ch 6,3

$C_w$  = a wave head, in metres

$$= 7,71 \times 10^{-2} L e^{-0,0044L}$$

where

$e$  = base of natural logarithms 2,7183

$R_B$  = bilge radius, in mm, as defined in Table 1.5.2 in Chapter 1

$S$  = overall span of frame, in mm, measured between deck and bottom support points or to, or between, stringers, where fitted

$T_1$  =  $T$  but to be taken not less than 0,05L m

$$\alpha = \frac{\sigma_o}{\sigma_c}$$

$\sigma_c$  = maximum compressive hull vertical bending stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) given by  $\sigma_D$  and  $\sigma_B$  as defined in Pt 3, Ch 4.5.6.1 as appropriate

For ships of normal design, not exceeding 90 m in length, the value of maximum compressive hull vertical bending stress may be determined as follows: at strength deck

$$\sigma_D = 654LB \frac{Z_{min}}{Z_D} \sigma \times 10^{-6} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

at keel

$$\sigma_B = 654LB \frac{Z_{min}}{Z_D} \sigma \times 10^{-6} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where  $Z_{min}$ ,  $Z_D$ ,  $Z_B$  and  $\sigma$  are in accordance with Pt 3, Ch 4,5.

$\sigma_o$  = specified minimum yield stress, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$h_{T1}$  =  $T + C_w$  m but need not be taken greater than 1,36T

$h_{T2}$  =  $T + 0,5C_w$  m but need not be taken greater than 1,2T  
For longitudinally framed bottom and bilge plating  $T$  is to be taken as  $T_1$

4.2.2 Other symbols are defined in 1.6.

## 4.3 Deck plating

4.3.1 The midship thickness of deck plating is to be maintained for 0,4L amidships and tapered outside this region in association with the deck longitudinals in accordance with 5.5. The midship thickness may, however, be required over an increased extent if it is shown to be necessary by the bending moment curves. Where partial filling of the tanks is contemplated the deck plating is also to comply with the requirements of 6.1.2.

4.3.2 For ships not exceeding 200 m in length, the deck thickness outside 0,4L amidships is to be not less than  $\frac{s}{80}$  at

any point within the cargo tank region. For lengths of 250 m and over, the thickness is to be not less than  $\frac{s}{70}$

Intermediate values are to be obtained by interpolation. For the purpose of this paragraph, the minimum value of  $s$  given in 4.2.1 is not to be applied.

4.3.3 The plating thickness outside 0,4L amidships is to be not less than:

$$t = \frac{s}{J} + 2,0 \text{ mm}$$

where  $J$  is defined in 4.2.1, using  $\sigma_o$  of the plating at the location under consideration.

## 4.4 Sheerstrake

4.4.1 The midship sheerstrake thickness is to be maintained for 0,4L amidships and tapered outside this region as provided for in Pt 3, Ch 5 and Ch 6. In the taper region, however, the sheerstrake thickness need not exceed the adjacent deck or shell thickness, whichever is the greater.

4.4.2 The width of sheerstrake for 0,4L amidships is to be not less than that required by Table 2.2.1 in Pt 3, Ch 2.

4.4.3 Where a rounded sheerstrake is incorporated, the radius is not, in general, to be less than 15 times the thickness. The radius is to be made by careful cold rolling or bending.

## 4.5 Shell plating

4.5.1 The midship thicknesses of side and bottom shell plating are to be maintained for 0,4L amidships and tapered outside this region as provided for in Pt 3, Ch 5 and Ch 6. The midship thicknesses may be required over an increased extent if it is shown to be necessary by the bending moment or shear force curves.

4.5.2 The requirements of Pt 3, Ch 5 are to be complied with in respect of the thickness of bottom shell forward.

# Double Hull Oil Tankers

# Part 4, Chapter 9

## Section 4

### 4.6 Bilge plating

4.6.1 The midship thickness of the bilge plating is to be maintained for  $0,4L$  amidships and tapered outside this region as provided for in Pt 3, Ch 5 and Ch 6.

4.6.2 Where longitudinal bottom and side framing is adopted, but longitudinals are omitted between the upper and lower extremities of the bilge radius, the bilge thickness is to be not less than  $\frac{R_B F_B}{165k_L}$  in addition to the required minimum

thickness derived from Table 9.4.1. The spacing of transverse supports associated with such an arrangement is to comply with the requirements of 5.4.

4.6.3 Where bilge longitudinals are omitted, the plating thickness outside  $0,4L$  amidships will be considered in relation to the support derived from the hull form and internal stiffening arrangements. Due regard will be taken of the possibility of increased loading in the forward region.

### 4.7 Keel

4.7.1 The midship keel thickness is to be maintained throughout the cargo tank region, except as required by Table 9.4.1, Note 5.

4.7.2 The width of the keel over the cargo tank region is to be not less than:  
 $70B$  mm but need not exceed 1800 mm and is to be not less than 750 mm.

### 4.8 Taper of higher tensile steel

4.8.1 Where higher tensile steel is used amidships and mild steel at the ends, the thickness of bottom shell, bilge and sheerstrake is to be tapered as provided for in Pt 3, Ch 3, Ch 5 and Ch 6.

4.8.2 Higher tensile steel deck plating is to be tapered in association with attached longitudinals as provided for in 5.5.

### 4.9 Thicknesses at ends of erections

4.9.1 The deck plating thickness at the poop front is to extend into the poop for a distance at least equal to one-third of the breadth,  $B$ .

4.9.2 If the poop front extends to within  $0,25L$  of amidships, the sheerstrake and the stringer plate at the break are to be increased by 20 per cent. No increase is required if the poop front is  $0,3L$  from amidships or greater. The increase at intermediate lengths is to be obtained by interpolation and is to be applied to the tapered thickness of the sheerstrake and stringer plate.

4.9.3 Where the poop extends to within  $0,3L$  of amidships and the enclosed machinery opening extends to within  $\frac{B}{3}$  of the poop front and has a width exceeding one-half of the

breadth of the ship at the poop front, the thickness of deck plating may require to be increased. The forward corners of the casing opening are to be well rounded.

### 4.10 Deck openings

4.10.1 Openings in the deck are to be kept to the minimum number consistent with operational requirements.

4.10.2 Plate panels in which openings are cut are to be adequately stiffened, where necessary, against compression and shear buckling.

4.10.3 The corners of all openings are to be well rounded, and the edges smooth.

4.10.4 Where the stress concentration factor in way of the opening exceeds 2,4, edge reinforcement is generally to be fitted. This is normally to be in the form of a spigot of adequate dimensions, but alternative arrangements will be considered.

4.10.5 Alternatively, the shape of the opening is to be such that a stress concentration factor of 2,4 is not exceeded.

4.10.6 In this respect, reinforcement will not, in general, be required in way of:

- (a) elliptical openings having their major axis fore and aft and ratios of length to breadth not less than 2 to 1, or
- (b) openings of other shapes, provided it has been shown by suitable tests that the stress concentration factor does not exceed 2,4.

4.10.7 Circular openings of diameter up to 325 mm will also be accepted, provided that they are situated at such a distance from any other opening that there is an intervening width of plating of not less than five times the diameter of the smaller of the two openings.

4.10.8 Where within  $0,4L$  amidships deck openings have a total breadth or shadow area breadth in one transverse section that exceeds the limitation given in Pt 3, Ch 3, 3.4.4 and 3.4.5, compensation will be required to restore the excess. This is generally to be arranged by increasing the deck plate thickness, but other proposals will be considered.

4.10.9 Where a deck longitudinal is cut in way of an opening, within  $0,4L$  amidships, compensation is to be arranged to ensure full continuity of area.

4.10.10 The area of any edge reinforcement which may be required is not to be taken into account in determining the required sectional area of compensation unless such reinforcement is designed to absorb the loadings from cut longitudinals in way of opening.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Sections 4 & 5

4.10.11 Increased scantlings and/or compensation may also be required for large openings outside 0,5L amidships, or where openings are close to breaks of superstructure or other areas of high stress in any location on the ship.

4.10.12 Where small diameter threaded openings for staging wires are arranged on the upper deck, they are to be located clear of the other openings and similar areas of stress concentration. Care is to be taken to ensure a gradual transition at the thread ends and the edges of the holes are to be smooth. The closing arrangements are to be as required by Section 13.

## 4.11 Shell openings

4.11.1 Sea inlets in pump rooms situated within 0,4L amidships, are, if practicable, to be fitted clear of the bilge radius. All openings are to be arranged so as to minimize discontinuity of transverse frames, longitudinals or bilge keels. Compensation is to be provided for all openings within 0,4L amidships and may also be required for openings in the vicinity of the poop front. The compensation should, if possible, take the form of an insert plate rather than a doubler.

4.11.2 If openings are not circular or oval, the corners are to be rounded with as large a radius as practicable.

## 4.12 Superstructures

4.12.1 The thickness of plating forming the deck and sides of forecastles and poops is to be as required by Pt 3, Ch 5, Ch 6 and Ch 8.

## Section 5 Hull framing

### 5.1 General

5.1.1 In the cargo tank region, the scantlings of deck, bottom and side longitudinals, and of transverse side framing, where fitted, are to be in accordance with the requirements of this Section.

5.1.2 Longitudinal and transverse framing members outside the cargo tank region are to comply with the requirements of Pt 3, Ch 5,4, Ch 6,4, and Ch 7, as appropriate to their location.

5.1.3 Outside the cargo tank region the structure is to be scarfed into the end structure as provided for in Pt 3, Ch 5, Ch 6 and Ch 7.

## 5.2 Symbols

5.2.1 The symbols used in this Section are defined as follows:

$b_f$  = the width of the face plate, in mm, of the side longitudinal under consideration, see Fig. 9.5.1

$b_{f1}$  = the minimum distance, in mm, from the edge of the face plate of the side longitudinal under consideration to the centre of the web plate, see Fig. 9.5.1

$b_1$  = the value as defined in Table 9.5.3

$c_1 = \frac{60}{225 - 165F_D}$  at deck

= 1,0 at  $\frac{D}{2}$

=  $\frac{75}{225 - 150F_B}$  at base line of ship

intermediate values of  $c_1$  by interpolation

$c_2 = \frac{165}{345 - 180F_D}$  at deck

= 1,0 at  $\frac{D}{2}$

=  $\frac{165}{345 - 180F_B}$  at base line of ship

intermediate values of  $c_2$  by interpolation

$d_w$  = depth of web, in mm

$h$  = distance of longitudinal below deck at side, in metres. For deck longitudinals,  $h = 0$

$h_0$  = the distance, in metres, from the mid-point of span of the stiffener to the highest point of tank, excluding hatchway

$h_1 = \left( h_0 + \frac{D_1}{8} \right)$ , but in no case to be taken less than

$\frac{L_1}{56}$  m or  $(0,01L_1 + 0,7)$  m, whichever is the

greater, and need not be taken greater than

$\left( 0,75D + \frac{D_1}{8} \right)$ , for bottom longitudinals

$h_2$  = distance, in metres, from mid-point of span of transverse side frame to deck at side measured at mid-length of tank, but to be taken not less than 2,5 m

$h_3 = h_0 + Rb_1$ , but need not be taken greater than  $(0,75D + Rb_1)$  for bottom longitudinals

$l_e$  = effective length, in metres, of longitudinals measured between span points, but to be taken not less than 1,5 m in double bottom and 2,5 m elsewhere. For determination of span points, see Pt 3, Ch 3,3.

$t_f$  = thickness of flange, in mm

$t_s$  = thickness of the bilge shell plating, in mm

$t_w$  = thickness of web, in mm

$D_1 = D$ , in metres, but is to be taken not less than 10 and need not be taken greater than 16

$F_B$  = as defined in Pt 3, Ch 4,5.6

$F_D$  = as defined in Pt 3, Ch 4,5.6

$F_1$  = a factor determined from Table 9.5.1


$F_2$  = a factor determined from Table 9.5.2



## Double Hull Oil Tankers

## Part 4, Chapter 9

## Section 5



$$R = \sin\theta$$

where  $\theta$  is the roll angle, in degrees

$$\text{and } \sin\theta = \left(0,45 + 0,1 \frac{L}{B}\right) \left(0,54 - \frac{L}{1270}\right)$$

$R_B$  = bilge radius, in mm, as defined in Table 1.5.2 in Chapter 1.

5.2.2 Other symbols are defined in 1.6.

**Table 9.5.1 Values of  $F_1$**

Item	$F_1$
Deck longitudinals and side longitudinals above $\frac{D}{2}$	$\frac{Dc_1}{4D + 20h}$
Side longitudinals and bottom longitudinals below $\frac{D}{2}$	$\frac{Dc_1}{25D - 20h}$
NOTE Minimum $F_1 = 0,12$	

**Table 9.5.2 Values of  $F_2$**

Item	$F_2$
Deck longitudinals and side longitudinals above $\frac{D}{2}$	$\frac{Dc_2}{D + 2,18h}$
Side longitudinals and bottom longitudinals below $\frac{D}{2}$	$\frac{Dc_2}{3,18D - 2,18h}$
NOTE Minimum $F_2 = 0,73$	

**Table 9.5.3 Determination of  $b_1$**

Item No.	Structural arrangement	Location	Value of $b_1$ , metres
1	Where wing and double bottom ballast tanks port and starboard are interconnected	(a) Bottom longitudinals	The greater horizontal distance from ship side to the longitudinal
		(b) Side longitudinals	Breadth of ship
		(c) Deck longitudinals	(i) In way of cargo tanks and inboard ballast tanks, the greater horizontal distance from tank corner at top of tank to longitudinal, either side  (ii) In way of wing ballast tanks, the greater horizontal distance from ship side to longitudinal, either side
2	Where wing ballast tanks port and starboard are separate	(a) Bottom longitudinals	The horizontal distance from ship side to longitudinal
		(b) Side longitudinals	Width of wing ballast tank

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 5

## 5.3 Deck, side and bottom longitudinals

5.3.1 The modulus of longitudinals within the cargo tank region, except as provided for in 5.3.2 and 5.5 is to be not less than the greater of the following:

(a)  $Z = 0,056skh_1 I_e^2 F_1 F_s \text{ cm}^3$ , or

(b)  $Z = 0,0051skh_3 I_e^2 F_2 \text{ cm}^3$

where  $F_1$  and  $F_2$  values are as given in Tables 9.5.1 and 9.5.2 and  $F_s$  is a fatigue factor to be taken as follows:

$$F_s = \frac{1,1}{k} \left[ 1 - \frac{2b_{f1}}{b_f} (1 - k) \right] \text{ at } 0,6D \text{ above the base line}$$

= 1,0 at upper deck at side and at the base line, intermediate values by linear interpolation

For flat bars and bulb plates  $\frac{b_{f1}}{b_f}$  may be taken as 0,5

The modulus of side longitudinals need not exceed that of a bottom longitudinal having the same spacing and configuration.

5.3.2 The modulus of bottom longitudinals is to satisfy the requirements of 5.3.1 or Table 1.6.1(3) in Chapter 1, whichever is the greater.

5.3.3 The section modulus given is that of the longitudinal and associated plating, for the extent of the associated plating, see Pt 3, Ch 3,3.2.3. The webs and flanges are to comply with the minimum thickness requirements of Section 10.

5.3.4 Where the spacing of transverses exceeds 5,5 m, the scantlings of side and bottom longitudinals in way of bulkheads and primary members, including end connections, are to be verified by direct calculation.

5.3.5 The side and bottom longitudinal scantlings derived from 5.3.1 and 5.3.2, using the midship thickness of plating, are to extend throughout the cargo tanks. Where the shell plating is inclined at an angle to the horizontal longitudinal axis of greater than  $10^\circ$ , the span of the longitudinals is to be measured along the member. Where the shell plating is inclined at an angle to the vertical axis of greater than  $10^\circ$ , the spacing of longitudinals is to be measured along the chord between members. Where the angle of attachment of side longitudinals clear of amidships varies by  $20^\circ$  or more from a line normal to the plane of the shell, the properties of the section are to be determined about an axis parallel to the attached plating. Angles of slope greater than  $40^\circ$  are to be avoided.

5.3.6 Fabricated longitudinals having the face plate welded to the underside of the web, leaving the edge of the web exposed, are not recommended for shell, inner hull or longitudinal bulkhead longitudinals. Where it is proposed to fit such sections, a symmetrical arrangement of connection to transverse members is to be incorporated. This can be achieved by fitting backing brackets on the opposite side of the transverse web or bulkhead. The primary member web stiffener and backing bracket are to be lapped to the longitudinal. Recommended examples of such backing structure can be seen in the *ShipRight FDA Procedure, Structural Detail Design Guide (SDDG)*.

5.3.7 Where partial filling of the tanks is also contemplated the deck longitudinals are to comply with the requirements of 6.1.2.

5.3.8 Stiffeners and brackets on vertical webs in wing ballast tanks, where fitted on one side and connected to higher tensile steel longitudinals between the base line and  $0,8D$  above the base line, are to have their heels well radiused to reduce stress concentrations. Where a symmetrical arrangement is fitted, i.e. bracket or stiffening on both sides, and they are connected to higher tensile steel longitudinals, the toes of the stiffeners or brackets are to be well radiused. Alternative arrangements will be considered if supported by appropriate fatigue life assessment calculations.

5.3.9 Where higher tensile steel side longitudinals pass through transverse bulkheads in the cargo area, well radiused brackets of the same material are to be fitted on both the fore and after side of the connection between the upper turn of bilge and  $0,8D$  above the base line. Particular attention should be given to ensuring the alignment of these brackets. Alternative arrangements will be considered if supported by appropriate fatigue life assessment calculations.

## 5.4 Bilge longitudinals and brackets

5.4.1 The scantlings of bilge longitudinals are to be graduated between those required for the bottom and lowest side longitudinals.

5.4.2 Where bilge longitudinals are omitted, the spacing of transverses or equivalent bilge brackets must not exceed:

$$8 \times 10^6 \frac{t_s^2}{DR_B} \sqrt{\frac{t_s}{R_B}} \text{ mm}$$

Where no intermediate brackets are fitted between transverses, the spacing between the two outermost bottom longitudinals and between the two lowest side longitudinals is not to exceed one-third of the bilge radius or 40 times the local shell thickness, whichever is the greater.

5.4.3 Attention is drawn to 4.6.2 and 4.6.3 concerning bilge plating thickness where longitudinals are omitted.

## 5.5 Deck longitudinals outside $0,4L$ amidships

5.5.1 Within the cargo tank region, deck longitudinals may be gradually tapered outside  $0,4L$  amidships in association with the deck plating, on the basis of area and modulus. For the requirements, see Pt 3, Ch 3,2.5 and Table 3.2.1, see also 5.3.5.

5.5.2 The midship spacing of longitudinals is, in general, to be maintained throughout the cargo tank region. The plating thickness and longitudinal depth and thickness are not to be increased at any point in the direction of the taper of area towards the ends of the ship, other than as may be required for compensation for openings. Changes of longitudinal section are, in general, to be avoided.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 5

5.5.3 Attention is also drawn to 5.3.3, which is to be complied with, where necessary, by maintaining a constant deck plating thickness in way of the ends of the cargo tank region.

5.5.4 Where the spacing of transverses in cargo tanks is not constant and variations in longitudinal scantlings are contemplated to suit differing spans, individual consideration will be given to the taper arrangements.

## 5.6 Stability of longitudinals

5.6.1 The lateral and torsional stability of longitudinals together with web and flange buckling criteria are to be verified in accordance with Pt 3, Ch 4,7.

5.6.2 In addition, the following requirements are to be satisfied:

- (a) Flat bar longitudinal
  - (i) when continuous at bulkheads
 
$$\frac{d_w}{t_w} \leq 18\sqrt{k_L}$$
  - (ii) when non-continuous at bulkheads
 
$$\frac{d_w}{t_w} \leq 15\sqrt{k_L}$$
- (b) Built sections
  - (i)  $\frac{d_w}{t_w} \leq 60\sqrt{k_L}$
  - (ii)  $\frac{b_f}{t_f} \leq 15$  for asymmetric sections
  - (iii)  $\frac{b_f}{t_f} \leq 30$  for symmetric sections

## 5.7 Connections of longitudinals

5.7.1 Connections of longitudinals to bulkheads are to provide adequate fixity and continuity of longitudinal strength. See also the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG), for recommended design details in critical areas.

5.7.2 Where the length of the ship exceeds 150 m, the longitudinals within 0,1D of the bottom and deck are to be continuous through the transverse bulkheads. Higher tensile steel longitudinals are to be continuous irrespective of ship length. Alternative arrangements will be individually considered.

5.7.3 Longitudinals are to be connected to transverse primary members as required by Pt 3, Ch 10,5.2.

## 5.8 Openings in longitudinals

5.8.1 In general, closely spaced scallops are not permitted in longitudinals within the range of cargo tanks except in way of ballast pipe suction, reinforcement in these areas will be specially considered.

5.8.2 Small air and drain holes, cut-outs at erection butts and similar widely spaced openings are, in general, to be not less than 200 mm clear of the toes of end brackets, intersections with primary supporting members and other areas of high stress. All openings are to be well rounded with smooth edges.

5.8.3 Drain holes in higher tensile steel longitudinals attached to higher tensile steel plating are to be elliptical in shape or of equivalent design to minimize stress concentrations. The opening is generally to be located clear of the welded connection to the plating, but where a flush opening is essential for drainage the weld connection is to end in a soft toe.

5.8.4 Small circular air holes may be arranged in higher tensile steel deck longitudinals.

5.8.5 Isolated openings spaced greater than 1 metre apart need not be taken into account in calculating the section modulus of the longitudinal, provided that the depth does not exceed 10 per cent of the web depth, or 75 mm, whichever is the greater, but in no case more than 25 per cent of the depth of the longitudinal.

5.8.6 Where the depths given in 5.8.5 are exceeded, the arrangements are to be such as will minimize resultant stress concentration.

## 5.9 Transverse side frames

5.9.1 For limits of application of transverse side framing, see 1.3.

5.9.2 The section modulus of transverse side frames is to be not less than:

$$Z = 0,01025k s h_2 l_e^2 \text{ cm}^3, \text{ where side webs are fitted;}$$

$$\text{or}$$

$$Z = 0,012k s h_2 l_e^2 \text{ cm}^3, \text{ where side webs are not fitted.}$$

5.9.3 The size of the frame is to be governed by the maximum modulus derived from the appropriate formula in 5.9.2, and is to be maintained for the full depth of the ship.

5.9.4 The section modulus given is that of the frame and associated side shell plating. The frame is to comply with the minimum thickness requirements of Section 10.

5.9.5 The inertia of transverse side frames is to be not less than:

$$\text{In the forward 0,15L: } I = 3,5I_e Z \text{ cm}^4$$

$$\text{Elsewhere: } I = 3,2I_e Z \text{ cm}^4$$

## Double Hull Oil Tankers

## Part 4, Chapter 9

Section 6

## Section 6

## Inner hull, inner bottom and longitudinal oiltight bulkheads

## 6.1 General

6.1.1 The inner hull, inner bottom and longitudinal bulkheads are generally to be longitudinally framed. Longitudinal bulkheads may be plane or horizontally corrugated. Centreline longitudinal bulkheads may also be vertically corrugated, see 1.3.13. Scantlings of inner hull and longitudinal oiltight bulkheads are to be in accordance with Table 9.6.1 and panel stability is also to be confirmed from primary structure direct calculations. The calculation is to take account of the shear stress and direct stresses derived from both the transverse and longitudinal strength investigations.

6.1.2 Where tanks are intended to be partially filled, the scantlings and structural arrangements of the boundary bulkheads are to be capable of withstanding the loads imposed by the movement of liquid in the tanks. The magnitude of the predicted loadings, together with the scantling calculations, may require to be submitted.

## 6.2 Symbols

6.2.1 The symbols used in this Section are defined as follows:

$b_1$  = the greater horizontal distance in metres, from a point one third of the height of the strake above its lower edge or mid-point of the stiffener span, to the corners at the top of the tank on either side.

Where the angle  $\alpha$  is less than  $\left(32,5 - \frac{L}{20}\right)$

degrees, the distance is measured to the widest point of the tank, see Fig. 9.6.1.

$\alpha$  = angle, in degrees, as indicated in Fig. 9.6.1.

$$c_1 = \frac{60}{225 - 165F_D} \text{ at deck}$$

$$= 1,0 \text{ at } \frac{D}{2}$$

$$= \frac{75}{225 - 150F_B} \text{ at base line of ship}$$

intermediate values of  $c_1$  by interpolation

$$c_2 = \frac{165}{345 - 180F_D} \text{ at deck}$$

Table 9.6.1 Inner hull and longitudinal oiltight bulkhead scantlings

Item	Horizontally stiffened/Vertically stiffened
(1) Plating thicknesses including corrugations (mm) (See Notes 1 and 7)	<p>(a) Within <math>0,1D</math> of the deck: <math>t = t_0</math></p> <p>(b) Within <math>0,1D</math> of the bottom shell: <math display="block">t = \frac{t_0}{\sqrt{2 - F_B}} \text{ (but not less than } t_1)</math></p> <p>(c) Elsewhere: <math>t = t_1</math> (see Note 6)</p> <p>(d) But not less than <math>t = 0,0009s (0,059L_1 + 7)</math></p>
(2) Stiffener modulus (cm <sup>3</sup> ) (See Notes 3 and 4)	<p>(a) Horizontally stiffened:</p> <div style="display: flex; align-items: center;"> <div style="margin-right: 10px;"> <p>(i) <math>Z = 0,056k h_2 s l_e^2 F_1</math></p> <p>(ii) <math>Z = 0,0051k h_4 s l_e^2 F_2</math></p> </div> <div style="font-size: 3em; margin-right: 10px;">}</div> <p>whichever is the greater</p> </div> <p>(b) Vertically stiffened: <math>Z = 0,0067ks l_e^2 h_5</math></p>
(3) Corrugation properties (See Note 7)	<p>(a) Modulus (cm<sup>3</sup>): <math>Z = 0,0085p h_5 l_e^2 k</math></p> <p>(b) Inertia (cm<sup>4</sup>): <math>I = 0,032p h_5 l_e^3</math></p>


## NOTES

- The plating thicknesses are not to be less than as necessary to comply with the buckling requirements of Pt 3, Ch 4.7.
- The section modulus given by the formula is that of the stiffener and associated plating or of the corrugation over pitch,  $p$ .
- For vertical stiffeners, the ratio of web depth to web thickness is not to exceed  $60 \sqrt{k}$  for stiffeners with flanges or face plates, and  $18 \sqrt{k}$  for flat bars. Horizontal stiffeners are to comply with 5.6.
- The minimum thickness criteria given in Section 10 are also to be complied with and the stiffener web thickness is to be sufficient to withstand the imposed shear forces.
- The minimum moment of inertia represented by item 3(b) of the Table is not to be reduced on account of higher tensile steel being incorporated.
- In applying item 1(c) of the Table, it is necessary to calculate values of  $t_0$  for plate panels within  $0,4D$  each side of mid-depth, take the minimum value,  $t_m$ , and then determine value of  $t_1$ .
- For vertically corrugated centreline longitudinal bulkheads see also Table 1.9.2 in Chapter 1 for deep tanks.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 6



**Fig. 9.6.1 Illustration of  $b_1$  determination**

$$= 1,0 \text{ at } \frac{D}{2}$$

$$= \frac{165}{345 - 180F_B} \text{ at base line of ship}$$

intermediate values of  $c_2$  by interpolation

$h$  = load height, in metres measured vertically as follows:

- For bulkhead plating, the distance from a point one third of the height of the plate panel above its lower edge to the highest point of the tank, excluding hatchway
- for bulkhead stiffeners or corrugations, the distance from the mid-point of span of the stiffener or corrugation to the highest point of the tank, excluding hatchway

$$h_1 = \left( h + \frac{D_1}{8} \right), \text{ but not less than } 0,72 (h + Rb_1)$$

$$h_2 = \left( h + \frac{D_1}{8} \right), \text{ in metres, but in no case to be}$$

$$\text{taken less than } \frac{L_1}{56} \text{ m or } (0,01L_1 + 0,7) \text{ m}$$

whichever is the greater

$h_3$  = distance of longitudinal below deck at side, in metres, but is not to be less than 0

$$h_4 = h + Rb_1$$

$$h_5 = h_2 \text{ but is to be not less than } 0,55h_4$$

$l_e$  = effective length, in metres, of longitudinals measured between span points, but is not to be taken less than 2,5 m. For determination of span points, see Pt 3, Ch 3,3

$\rho$  = pitch of symmetrical corrugations, in mm

$s$  = spacing, in mm, of bulkhead stiffeners for plane bulkheads. In case of symmetrical corrugations,  $s$  is to be taken as  $b$  or  $c$  in Fig. 3.3.1 in Pt 3, Ch 3, whichever is the greater

$$t_0 = 0,005s\sqrt{kh_1}$$

$$t_1 = t_0 \left( 0,84 + 0,16 \left( \frac{t_m}{t_0} \right)^2 \right)$$

$t_m$  = minimum value of  $t_0$  within  $0,4D$  each side of mid-depth of bulkhead

$D_1$  =  $D$ , in metres, but is to be taken not less than 10 and need not be taken greater than 16

$F_B$  = as defined in Pt 3, Ch 4,5,6

$F_D$  = as defined in Pt 3, Ch 4,5,6

$F_1$  = a factor determined from Table 9.6.2

$F_2$  = a factor determined from Table 9.6.3

$R$  =  $\sin \theta$

where  $\theta$  is the roll angle, in degrees

$$\text{and } \sin \theta = \left( 0,45 + 0,1 \frac{L}{B} \right) \left( 0,54 - \frac{L}{1270} \right).$$

6.2.2 Other symbols are defined in 1.6.

**Table 9.6.2 Values of  $F_1$**

Longitudinal bulkhead longitudinals	$F_1$
Above $\frac{D}{2}$	$\frac{Dc_1}{4D + 20h_3}$
Below $\frac{D}{2}$	$\frac{Dc_1}{25D - 20h_3}$
NOTE Minimum $F_1 = 0,12$	

**Table 9.6.3 Values of  $F_2$**

Longitudinal bulkhead longitudinals	$F_2$
Above $\frac{D}{2}$	$\frac{Dc_2}{D + 2,18h_3}$
Below $\frac{D}{2}$	$\frac{Dc_2}{3,18D - 2,18h_3}$
NOTE Minimum $F_2 = 0,73$	

## 6.3 Inner hull and longitudinal bulkheads

6.3.1 Inner hull and longitudinal bulkheads are to extend as far forward and aft as practicable and are to be effectively scarfed into the adjoining structure.

6.3.2 Longitudinal bulkheads only may be perforated provided suitable account is taken of the applied shear forces. Proposals to fit perforated longitudinal bulkheads in cargo tanks will be individually considered. See also 7.1 concerning penetration of pump room, cofferdam and cargo tank bulkheads.

6.3.3 The thickness of inner hull and longitudinal bulkhead plating required by Table 9.6.1 is to be maintained throughout the cargo tank length, with the exception of item (1)(a) which may be gradually tapered outside  $0,4L$  amidships to cargo tank minimum thickness or as required by item (1)(c), whichever is the greater, at  $0,075L$  from the ends.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 6

6.3.4 The bulkhead plating thicknesses throughout the cargo tank length are to be increased as necessary to attain compliance with the shear strength requirements of Pt 3, Ch 4,6.

6.3.5 For conditions which provide for wing and centre cargo tanks abreast to be filled, with adjacent cargo tanks fore and aft empty, the thickness of longitudinal bulkheads is to comply with the requirements of 8.3.2(d) and (e), see also 3.3.6.

6.3.6 Where bulkheads are penetrated by cargo or ballast piping, the structural arrangements in way are to be capable of withstanding the loads imparted to the bulkheads by the hydraulic forces in the pipes. The requirements for cargo and ballast piping is given in Pt 5, Ch 15,2.5 and Ch 15,3.

6.3.7 Openings in horizontal stiffeners are to comply with the requirements of 5.8.

### 6.4 Longitudinal corrugated bulkheads

6.4.1 Where horizontally corrugated bulkheads are adopted the angle of corrugation is to be not less than 40°.

6.4.2 In ships exceeding 150 m in length the upper and lower strakes of the longitudinal bulkhead are to be plane for a distance of 0,1D from the deck and bottom.

6.4.3 Corrugations are to be aligned, and stiffening arrangements on plane members are to be arranged to give adequate support in way of flanges of abutting corrugations. Where both the longitudinal and transverse bulkheads are horizontally corrugated, the arrangements at intersections are to be designed to facilitate attachment and maintain continuity.

6.4.4 Where asymmetrical girders or webs are fitted to corrugated bulkheads, the angle of corrugation is not to exceed 60°.

### 6.5 Inner bottom

6.5.1 The inner bottom is to be longitudinally framed and the inner bottom plating thickness is to be not less than the greater of:

$$(a) \quad t = \frac{t_0}{\sqrt{2 - F_B}} \text{ mm, or}$$

(b) deep tank requirements of Table 1.9.1 in Chapter 1.

6.5.2 The section modulus of inner bottom longitudinals is to be in accordance with Table 9.6.1(2) or deep tank requirements of Table 1.9.1 in Chapter 1, whichever is the greater, and the unsupported span may extend to the spacing between plate floors.

6.5.3 Buckling resistance to longitudinal and transverse stresses in the inner bottom is to be confirmed by direct calculation, see also Pt 3, Ch 4,7.

6.5.4 Transverse continuity of inner bottom is to be maintained outboard of inner hull, see 6.6.3. Recommended details are shown in the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG).

6.5.5 Particular attention is to be given to the through-thickness properties and continuity at the connection of bulkhead stools to the inner bottom. For requirements for plates with specified through thickness properties, see Ch 3,8 of the Rules for Materials (Part 2).

6.5.6 Connection of inner bottom longitudinals to plate floor is to satisfy the requirements given in Pt 3, Ch 10,5.2.

### 6.6 Hopper side tank

6.6.1 Where a hopper side tank is fitted the sloping bulkhead plating and attached longitudinals are to be as required by Table 9.6.1.

6.6.2 A transverse is to be arranged in the hopper tank in line with each double bottom plate floor, to ensure continuity of transverse strength.

6.6.3 Particular attention is to be paid to the continuity of the inner bottom plating into the hopper side tank. Scarfing brackets are to be fitted in the hopper in line with the inner bottom at each transverse. These brackets are to be arranged each side of the transverse.

6.6.4 Knuckles in the hopper tank plating are to be supported by side girders and stringers or by a deep longitudinal.

6.6.5 Detail design guidelines for connections in way of hopper tank knuckles are shown in the *ShipRight FDA Procedure, Structural Detail Design Guide* (SDDG).

### 6.7 Connections

6.7.1 Horizontal and vertical stiffeners are to be connected to supporting primary members as required by Pt 3, Ch 10,5.2.

6.7.2 Stiffeners are to be bracketed or otherwise efficiently connected at their ends to provide adequate fixity, as required by Pt 3, Ch 10.

6.7.3 Connections of horizontal stiffeners to transverse bulkheads are to provide adequate fixity and continuity of longitudinal strength. Horizontal stiffeners are to be continuous through bulkheads as required by 5.7, for longitudinals.

6.7.4 Where inner hulls, longitudinal and transverse bulkheads are horizontally stiffened, consideration will be given to the stability of the arrangements at intersections. Additional calculations may be required.

## Double Hull Oil Tankers

## Part 4, Chapter 9

Section 7

## Section 7

## Transverse oiltight bulkheads

## 7.1 General

7.1.1 Transverse oiltight bulkheads may be plane or with corrugations arranged horizontally or vertically. Scantlings are to be in accordance with Table 9.7.1, except as otherwise provided for in this Section. The arrangement of stiffening is to be such as will efficiently support loads transmitted by end connections of inner hull, longitudinal bulkhead, shell and deck longitudinals. The thickness of bulkhead plating is also to be confirmed by direct calculation in respect of panel stability. The calculation is to take account of the shear stresses and direct stresses derived from both the transverse and longitudinal strength investigations.

7.1.2 Where tanks are intended to be partially filled, the scantlings and structural arrangements of the boundary bulkheads are to be capable of withstanding the loads imposed by the movement of liquid in the tanks. The magnitude of the predicted loadings, together with the scantling calculations, may require to be submitted.

7.1.3 The scantlings of water ballast tank and cofferdam bulkheads not forming the boundary of a cargo tank are to be as required by Ch 1,9 for deep tanks. Where the bulkheads are boundaries of 'U' shaped tanks, the scantlings are also to be confirmed by the requirements of this Section.

7.1.4 Where the pump room acts as a cofferdam, a bulkhead which does not form part of the boundary of a cargo tank or an oil fuel bunker may be of watertight bulkhead scantlings in accordance with the requirements of Ch 1,9 provided that an inert gas system is fitted in the cargo tanks, and the corresponding notation provided for in Pt 1, Ch 2,2 is assigned.

7.1.5 Where penetration of the cofferdam or pump room bulkheads is permitted by the Rules, the integrity of the bulkhead is to be maintained, see also Pt 5, Ch 13,2, Ch 15,3 and Pt 6, Ch 2,13.

7.1.6 Where bulkheads are penetrated by cargo or ballast piping, the structural arrangements in way are to be capable of withstanding the loads imparted to the bulkheads by the hydraulic forces in the pipes.

7.1.7 Special consideration will be given to any proposals to fit permanent repair/maintenance access openings with oiltight covers in cargo tank bulkheads. Attention is drawn to the existence of National Authority Regulations concerning load line and oil outflow aspects of such arrangements.

## 7.2 Symbols

7.2.1 The symbols used in this Section are defined as follows:

- $a$  = the lesser dimension of an unstiffened plate panel, in mm
- $b$  = the greater dimension of an unstiffened plate panel, in mm
- $b_1$  = the greater horizontal distance, in metres, from the centre of the plate panel or mid-point of the stiffener span to the corners at the top of the tank on either side

Table 9.7.1 Transverse oiltight bulkhead scantlings

Item	Horizontally stiffened	Vertically stiffened
(1) Plating thickness (mm)	$t = 0,0044sf\sqrt{kh_1}$	
(a) Generally, including corrugations (see also item 3)		
(b) But not less than:		
(i) For the upper $3/4$ of the bulkhead (see Note 5)	$t = \frac{a}{\left(95 + 20 \frac{a}{b}\right)\sqrt{k}}$	$t = \frac{a}{\left(85 + 30 \left(\frac{a}{b}\right)^2\right)\sqrt{k}}$
(ii) For the lower $1/4$ of the bulkhead (see Note 5)	$t = \frac{a}{\left(80 + 20 \frac{a}{b}\right)\sqrt{k}}$	$t = \frac{a}{\left(73 + 27 \left(\frac{a}{b}\right)^2\right)\sqrt{k}}$
(2) Stiffener modulus (cm <sup>3</sup> )	$Z = 0,0067ksS_1^2 h_2$	
(3) Corrugation properties		
(a) Modulus (cm <sup>3</sup> )	$Z = 0,0085ph_2 I_e^2 k$	
(b) Inertia (cm <sup>4</sup> ) (see Note 4)	$I = 0,032ph_2 I_e^3$	

## NOTES

- The section modulus given by the formula is that of the stiffeners and associated plating or of the corrugation over pitch  $p$ .
- The ratio of web depth to web thickness is not to exceed  $60\sqrt{k}$  for stiffeners with flanges or face plates and  $18\sqrt{k}$  for flat bars.
- The minimum thickness criteria given in Section 10 are also to be complied with, and the stiffener web thickness is to be sufficient to withstand the imposed shear forces.
- The minimum moment of inertia required by item 3(b) of the Table is not to be reduced on account of higher tensile steel being incorporated.
- For vertically corrugated bulkheads, see Table 1.9.2 in Chapter 1 for deep tanks.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 7

$$f = 1,1 - \frac{s}{2500S_1} \text{ but not to be taken greater}$$

than 1,0

$h$  = load height, in metres measured vertically as follows:

- (a) for bulkhead plating, the distance from a point one-third of the height of the plate panel above its lower edge to the highest point of the tank, excluding hatchway
- (b) for bulkhead stiffeners or corrugations, the distance from the mid-point of span of the stiffener or corrugation to the highest point of the tank, excluding hatchway

$$h_1 = h + \frac{D_1}{8} \text{ but not less than } 0,72 (h + Rb_1)$$

$$h_2 = h + \frac{D_1}{8} \text{ but not less than } 0,55 (h + Rb_1)$$

$p$  = pitch of symmetrical corrugations, in mm

$s$  = spacing, in mm, of bulkhead stiffeners or the breadth, in mm, of flange or web, whichever is the greater, of symmetrical corrugations

$D_1$  =  $D$ , in metres, but is to be taken not less than 10 and need not be taken greater than 16

$R$  =  $\sin \theta$

where  $\theta$  is the roll angle, in degrees

$$\text{and } \sin \theta = \left( 0,45 + 0,1 \frac{L}{B} \right) \left( 0,54 - \frac{L}{1270} \right)$$

$S_1$  = spacing of primary members, in metres. For the span at top, span may be reduced by the depth of deck longitudinal.

7.2.2 Other symbols are defined in 1.6.

## 7.3 Corrugated bulkheads

7.3.1 Where corrugated bulkheads are adopted the angle of corrugation is to be not less than  $40^\circ$ , see Fig. 3.3.1 in Pt 3, Ch 3.

7.3.2 Where transverse bulkheads are vertically corrugated, adequate resistance to transverse compressive forces is to be provided by horizontal stringers or equivalent.

7.3.3 Where transverse bulkheads are horizontally corrugated, the span of the corrugations should not, in general, exceed 5,0 m. Consideration is to be given to providing an efficient connection between the corrugations and the inner hull and longitudinal bulkhead stiffeners including local reinforcement where necessary.

7.3.4 Corrugations are to be aligned and stiffening arrangements on plane members are to be arranged to give adequate support in way of flanges of abutting corrugations. Where both the longitudinal and transverse bulkheads are horizontally corrugated, the arrangements at intersections are to be designed to facilitate attachment and maintain continuity.

7.3.5 Where asymmetrical girders or webs are fitted to corrugated bulkheads, the angle of corrugation is not to exceed  $60^\circ$ .

7.3.6 Where corrugated bulkheads on stools are adopted, attention is to be paid to the design of end connection. The arrangements are to be in accordance with the requirements of 7.4.

7.3.7 Where vertically corrugated bulkheads are proposed without stools both flanges are to be adequately supported at deck and inner bottom. Proposals will be specially considered. Particular attention is to be given to the through thickness properties of the inner bottom plating and continuity at the connection to the inner bottom. For the requirements for plates with specified through thickness properties, see Ch 3,8 of the Rules for Materials (Part 2).

## 7.4 Bulkheads supported by stools

7.4.1 The scantlings of vertically corrugated and double plate bulkheads supported by stools are generally to be confirmed by direct calculations which are to be submitted.

7.4.2 In addition the scantlings are to be determined in accordance with the requirements of Ch 1,9.2.1 for deep tank bulkheads with the load head  $h_4$ , in metres, measured to the highest point of the tank, excluding hatchway, but is not to be taken less than  $0,44 (h_4 + Rb_1)$ .

7.4.3 The sloping stool plate thickness adjacent to the corrugation is to be not less than the thickness of the corrugation flange at mid span as required by 7.4.1 and 7.4.2. Where the plate thickness is increased locally, the vertical extent is to be not less than the width of the flange of the corrugation.

7.4.4 The stools are to be reinforced with plate diaphragms or deep webs, and in bottom stools the diaphragms are to be aligned with double bottom side girders. Continuity is also to be maintained between the diaphragms and the webs of bulkhead corrugations as far as practicable.

7.4.5 Additional double bottom girders are to be arranged extending at least to the first plate floor adjacent to the bulkhead each side and, in general, are to be spaced not more than 3,8 m apart.

7.4.6 The sloping plate of bottom stools is to be aligned with double bottom floors. Particular attention is to be given to the through thickness properties of the inner bottom plating and continuity at the connection to the inner bottom, and to the through thickness properties of the bottom stool shelf plate. For requirements for plates with specified through thickness properties, see Ch 3,8 of the Rules for Materials (Part 2).



# Double Hull Oil Tankers

# Part 4, Chapter 9

Sections 7 & 8

7.4.7 An efficient system of reinforcement is to be arranged in line with the tank transverse bulkheads or bulkhead stools at the intersection with the sloped plating of the double bottom hopper tanks and topside tanks. The reinforcement fitted in the tanks is to consist of girders or intercostal bulb plate or equivalent stiffeners fitted between and connected to the sloped bulkhead longitudinals.

7.4.8 The shelf plates of the bulkhead stools are to be arranged to align with the longitudinals in the double bottom hopper tank and topside tanks. Where sloping shelf plates are fitted to stools suitable scarfing is to be arranged in way of the connections of the stools to the adjoining structures.

7.4.9 The arrangement of stools and adjacent structure common with the cargo tank is to be designed to avoid pockets in which gas could collect.

## 7.5 Connections

7.5.1 Horizontal and vertical stiffeners are to be connected to supporting primary members as required by Pt 3, Ch 10,5.2.

7.5.2 Stiffeners are to be bracketed or otherwise efficiently connected at their ends to provide adequate fixity.

7.5.3 Arrangements and scantlings of end brackets for vertical stiffeners are to be as required by Pt 3, Ch 10.

7.5.4 Horizontal stiffener end brackets are generally to satisfy the requirements of Pt 3, Ch 10. However, the length of the bracket arm at the side shell, inner hull and longitudinal bulkhead longitudinals is, in general, not to exceed the depth of the longitudinal. In order to provide the necessary weld connection, consideration may require to be given to fitting brackets on both sides of the bulkhead or to welding the stiffener to the longitudinal. The arrangements are also to be such as to maintain transverse continuity at intersections. Examples can be seen in the *ShipRight FDA Procedure, Structural Detail Design Guide (SDDG)*.

## Section 8 Non-oiltight bulkheads

### 8.1 General

8.1.1 The requirements of this Section are applicable to longitudinal and transverse wash bulkheads, where fitted. Proposals to fit perforated longitudinal bulkheads in cargo tanks will be individually considered, see also 1.3.

8.1.2 Wash bulkheads are generally to be of plane construction, horizontally or vertically stiffened, having an area of perforations not less than 10 per cent of the total area of the bulkhead. The perforations are to be so arranged that the efficiency of the bulkhead as a support is not impaired.

8.1.3 Where tanks are intended to be partially filled, the scantlings and structural arrangements of the wash bulkheads are to be capable of withstanding the loads imposed by the movement of liquid in the tanks. The magnitude of the predicted loads, together with the scantling calculations, may require to be submitted.

## 8.2 Symbols

8.2.1 The symbols used in this Section are defined as follows:

- $a$  = the horizontal length of the plate panel, in mm
- $a_T$  = the cross sectional area of the vertical web on longitudinal bulkhead and associated bulkhead plating over one transverse space, in  $\text{cm}^2$
- $b_1$  = half the distance, in metres, between members supporting floors as shown in Fig. 9.8.1
- $b_L$  = half the distance, in metres, between members supporting horizontal girder, adjacent to the bulkhead under consideration, as shown in Fig. 9.8.1
- $b_T$  = overall breadth of tank, in metres
- $D_1$  =  $D$ , in metres, but is to be taken not less than 10 and need not be taken greater than 16
- $D_L$  = the depth of the longitudinal bulkhead, including double bottom girder, in metres
- $d_L$  = the distance, in metres, from the top of the longitudinal bulkhead to the centre of the plate panel under consideration and need not be taken greater than the distance to the bracket toe of the double bottom transverse primary member
- $h$  = the distance, in metres, from the centre of the load on the horizontal girder to  $\frac{D_1}{8}$  m above the highest point of the tank, excluding the hatchway
- $d_H$  = the mean depth of horizontal girders at the longitudinal bulkhead, in metres, including the depth of the end brackets as shown in Fig. 9.8.1
- $l_G$  = the distance, in metres, from the horizontal girders to the adjacent horizontal primary member below
- $t_3 = \frac{Q_{SL} + Q_{SW}}{D_L \tau}$  mm

$Q_S, Q_W$  = as defined in Pt 3, Ch 4,6.1.

$$\tau = \frac{110}{k_L} \text{ N/mm}^2 \quad \left( \frac{11,2}{k_L} \text{ kgf/mm}^2 \right)$$

$Q_{SL}$  = the maximum still water shear force on the longitudinal bulkhead, in kN (tonne-f), of the loading condition in question.

Where two longitudinal bulkheads are fitted,  $Q_{SL}$  may be taken as:

$$Q_{SL} = 0,34Q_S$$

Where one longitudinal bulkhead is fitted,  $Q_{SL}$  may be taken as:

$$Q_{SL} = 0,40Q_S$$

$Q_{SL}$  may also be derived by direct calculation to determine the distribution of shear force between the shell, inner hull and longitudinal bulkheads.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 8

$Q_{SW}$  = design wave shear force on the longitudinal bulkhead, in kN (tonne-f).

Where two longitudinal bulkheads are fitted,  $Q_{SW}$  may be taken as:

$$Q_{SW} = 0,20Q_w$$

Where one longitudinal bulkhead is fitted,  $Q_{SW}$  may be taken as:

$$Q_{SW} = 0,28Q_w$$

$l_T$  = overall length of tank, in metres

$$F_d = W_h S b_i \frac{d_L}{D_L}$$

$l_b$  = the distance between the transverse bulkheads (oiltight or non-oiltight) adjacent to the bulkhead under consideration, in metres

$S$  = spacing of the double bottom transverse primary members, in metres

$T_p$  = the maximum operating draught of ship, in metres, where the tank with non-oiltight bulkhead is empty.

$$W_h = T_p + 0,023Le^{-0,0044L}$$

$\alpha = \frac{s}{a}$ , but not to be taken greater than 1,0

8.2.2 Other symbols are defined in 1.6.




Fig. 9.8.1 Horizontal girder

### 8.3 Scantlings

8.3.1 The thickness of plating may be the compartment minimum, see Section 10, except as given in 8.3.2 and 8.3.4.

8.3.2 Where non-oiltight **longitudinal** wash bulkheads support a bottom primary member, the following additional requirements are to be met:

- The area of perforation is to be not greater than 25 per cent of the total area of the bulkhead, and consideration is to be given to the disposition and geometry of the perforations so that the shear rigidity of the bulkhead is a maximum.
- The net section area of the bulkhead is to be not less than  $0,135l_T b_T D$  cm<sup>2</sup>.
- The plating thickness is to comply with Table 9.6.1(1)(d).
- The thickness of longitudinal bulkhead plating and web plating of the vertical web on longitudinal bulkhead is generally to be not less than:

$$t = 0,026 \frac{s}{1 + \alpha^2} \sqrt{\frac{F_d}{a_T}} \text{ mm}$$

- The thickness of the longitudinal bulkheads supporting a transverse bulkhead horizontal girder is in general to be not less than:

$$(i) \quad t = \frac{0,0437 h l_G b_L k}{d_H} + \frac{0,892 t_3 k}{k_L} \text{ mm}$$

$$(ii) \quad t = 0,0011s (0,059L_1 + 7) \text{ mm}$$

whichever is the greater.

The thickness is also to satisfy the buckling requirements of Pt 3, Ch 4,7.

The increased thickness is to extend over the end bracket and buttress of the horizontal girder down to a distance of  $0,5l_G$ .

8.3.3 The section modulus of longitudinal wash bulkhead stiffeners is to be not less than, see also Pt 3, Ch 4,7:

$$Z = 0,0036 \left( 0,54 - \frac{L}{1270} \right) b_T k s S^2 \text{ cm}^3$$

8.3.4 Where non-oiltight **transverse** wash bulkheads support a primary fore and aft bottom centreline girder, the following additional requirements are to be met:

- The area of perforation is to be not greater than 25 per cent of the total area of the bulkhead, and consideration is to be given to the disposition and geometry of the perforations so that the shear rigidity of the bulkhead is a maximum.
- The net section area of the bulkhead is to be not less than  $0,135l_b b_T D$  cm<sup>2</sup>.
- The plating thickness is to comply with Table 9.7.1(1)(b). In no case is either panel dimension to exceed 180 times the thickness required by this sub-paragraph or by 8.3.1, whichever is the greater.

8.3.5 The section modulus of transverse wash bulkhead stiffeners is to be not less than:

$$Z = 0,1215k s l_e^2 \frac{l_b}{L} \text{ cm}^3$$

# Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 8 & 9

### 8.4 Connections

8.4.1 Stiffeners are to be bracketed or otherwise efficiently connected at their ends and to primary supporting members, in accordance with the requirements of Pt 3, Ch 10.

## Section 9 Primary members supporting longitudinal framing

### 9.1 General

9.1.1 These requirements are applicable to ships having structural arrangements in accordance with 1.3.

9.1.2 The minimum thickness and constructional detail requirements of Section 10 are also to be complied with.

9.1.3 The scantlings of primary members are, in general, to be determined from direct calculations carried out in accordance with the requirements of Section 14 or in accordance with the requirements of this Section or the relevant Sections of Chapter 10. The direct calculations are to be submitted with the plans for confirmatory purposes, see also 1.1.9.

### 9.2 Symbols

9.2.1 The symbols used in this Section are defined as follows:

$b_{e1}, b_{e2}$  = effective end bracket leg length, in metres, at each end of the member, see Pt 3, Ch 3,3

$d_{DB}$  = Rule depth of centre girder, in mm

$h_c$  = vertical distance from the centre of the cross-ties to deck at side amidships, in metres

$h_s$  = distance between the lower span point of the vertical web and the moulded deck line at centreline, in metres

$l_b$  = the distance, in metres, between the transverse bulkheads (oiltight or non-oiltight) adjacent to the bulkhead under consideration

$l_c$  = one-half the vertical distance, in metres, between the centres of the adjacent cross-tie or between the centre of the adjacent bottom or deck transverse, or double bottom, see Fig. 9.9.1

$s$  = spacing of transverses, in metres

$A_c$  = cross sectional area of the cross-tie material which is continuous over the span of the cross-tie in  $\text{cm}^2$

$I_c$  = least moment of inertia of the cross-tie in  $\text{cm}^4$

$S_c$  = length of cross-tie, in metres, measured as follows:

(a) For centre tank cross-ties:  $S_c$  is the distance between the face plates of the vertical webs on the longitudinal bulkheads.

(b) For wing tank cross-ties:  $S_c$  is the distance between the face plate of the vertical web on the longitudinal bulkhead and the inner hull.

$S_s$  = span of the vertical web, in metres, and is to be measured between end span points, see Fig. 9.9.1.




Fig. 9.9.1 Wing tank construction

9.2.2 Other symbols are defined in 1.6.

### 9.3 Girders and floors in double bottom

9.3.1 Girders are to be arranged at the centreline or duct keel, at the hopper side and in way of longitudinal bulkheads and bulkhead stools. Plate floors are to be arranged in way of transverse bulkheads and bulkhead stools.

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 9

9.3.2 In way of vertically corrugated transverse bulkheads supported by stools, additional girders are to be arranged extending at least to the first plate floor adjacent to the bulkhead each side and spaced not more than 3,8 m apart, see 7.4.5.

9.3.3 The centre girder is to have a depth of not less than that given by:

$$d_{DB} = 28B + 205\sqrt{T} \text{ mm}$$

The height of the double bottom is also to satisfy the requirements given in 1.3.

9.3.4 Thickness of floors and girders is to be confirmed by means of a direct calculation. Due account is to be taken of access and other openings. The minimum thickness however, is to be not less than that given by:

(a) Centre girder or duct keel:

$$t = (0,008d_{DB} + 1,0)\sqrt{k} \text{ mm}$$

(b) Floors and side girders:

$$t = (0,007d_{DB} + 1,0)\sqrt{k} \text{ mm but need not exceed } 12,0\sqrt{k} \text{ mm}$$

9.3.5 The scantlings of plating and stiffeners of longitudinal girders are not to be less than necessary to comply with the buckling requirements of Pt 3, Ch 4,7.

9.3.6 Floors and girders forming the boundaries of tanks are also to satisfy the requirements of tank bulkheads given in Ch 1,9.

9.3.7 Provision is to be made for the free passage of air and water from all parts of the tanks to the air pipes and suction, account being taken of the pumping rates required. Adequate access is also to be provided to all parts of the double bottom. The edges of all openings are to be smooth. The size of the opening should not, in general, exceed 50 per cent of the double bottom depth, unless edge reinforcement is provided. In way of ends of floors and fore and aft girders at transverse bulkheads, the number and size of openings are to be kept to a minimum, and the openings are to be circular or elliptical. Edge stiffening may be required in these positions.

9.3.8 For ships intended to load or unload while aground, see Pt 3, Ch 9,13.

9.3.9 The structure of girders and duct keels is to be sufficient to withstand the forces imposed by dry-docking the ship, see also 10.10.

## 9.4 Vertical webs and horizontal girders in wing ballast tanks and hopper spaces

9.4.1 The width of the double skin side structure is to comply with the requirements given in 1.3.

9.4.2 Vertical webs are to be arranged in line with the floors in the double bottom to ensure continuity of transverse strength.

9.4.3 A horizontal girder is to be arranged at the top of the hopper space and is to be located close to the knuckle between the hopper and inner hull. Where additional longitudinal girders are provided to satisfy access requirements in accordance with 13.2.8, these are to be arranged in line with horizontal girders on the transverse bulkhead and wing tank cross-ties where these are fitted.

9.4.4 The scantlings of vertical webs and horizontal girders are to be determined by means of direct calculations and due account is to be taken of openings in the structure, see also the buckling requirements in Pt 3, Ch 4,7 for horizontal girders.

9.4.5 Access openings are to be kept clear of other small openings and are to have smooth edges. Edge stiffening is also to be arranged in regions of high shear stress.

## 9.5 Deck transverses and girders

9.5.1 Deck transverses are to be arranged in line with the vertical webs at the side and vertical transverses at longitudinal bulkheads, where fitted, to ensure continuity of transverse structure.

9.5.2 Deck girders are to be supported at transverse bulkheads by vertical webs or equivalent.

9.5.3 The scantlings of deck transverses and girders are to be determined by means of direct calculations or, alternatively, in accordance with the requirements of Ch 10,2.8 and 2.9.

## 9.6 Cross-ties

9.6.1 Cross-ties, where fitted, may be of plate or sectional material and are to have an area and least moment of inertia to satisfy the following:

$$A_c \geq \frac{0,765 l_c h_c s k}{\left(1 - \frac{0,45 S_c}{r\sqrt{k}}\right)} \text{ cm}^2$$

$$\text{where } r = \sqrt{\frac{I_c}{A_c}} \text{ cm}$$

(As a first approximation the area and inertia of the cross-tie may be calculated in accordance with Ch 10,2.10.1.)

9.6.2 The scantlings of the webs and flanges of cross-ties are also to be confirmed by means of direct calculation.

9.6.3 Design of end connections is to be such that the area of the welding, including vertical brackets, where fitted, is to be not less than the minimum cross-sectional area of the cross-tie derived from 9.6.1. To achieve this, full penetration welding may be required and thickness of brackets may require further consideration. Attention is to be given to the full continuity of area of the backing structure on the vertical webs and within the wing ballast tank. Particular attention is also to be paid to the welding at the toes of all vertical end brackets on the cross-tie.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 9 &amp; 10

### 9.7 Primary members supporting oiltight bulkheads

9.7.1 The scantlings of primary members supporting oiltight bulkheads are, in general, to be determined by means of direct calculation, see also 9.7.4 and 9.7.5.

9.7.2 Alternatively, the scantlings of vertical webs and horizontal girders on transverse bulkheads are to be determined in accordance with the requirements of Ch 10,4.

9.7.3 Where longitudinal oiltight bulkheads are fitted, vertical webs are to be arranged in line with the deck transverses and the double bottom floors. Particular attention is to be paid to the alignment of the bulkhead web end brackets with the double bottom floors.

9.7.4 The section modulus of vertical webs on longitudinal bulkheads in ships with one or two longitudinal bulkheads is to be not less than:

$$Z = K_3 s h_s S_s^2 k \text{ cm}^3$$

where  $K_3$  is given in Table 9.9.1.

9.7.5 In ships with two longitudinal bulkheads, the net sectional area of the web at any section is not to be less than:

$$A = 0,12 Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where  $Q_x$  is calculated from shear force diagrams constructed as shown in Fig. 9.9.1. For this purpose the values of  $K_4$  and  $K_5$  and the range of application are given in Table 9.9.1.

9.7.6 The moment of inertia of vertical webs on longitudinal bulkheads is to be not less than:

$$I = \frac{7,5}{k} S_s Z \text{ cm}^4$$

9.7.7 Where horizontal girders and vertical webs on transverse bulkheads do not form part of a ring structure, they are to be arranged with substantial end brackets forming a buttress extending to the adjacent vertical web or transverse. The shear and combined stresses in the buttress arrangements are to be examined.

9.7.8 Where the cross-ties are omitted from the transverse ring in the wing or centre tanks adjacent to the transverse bulkhead, the design of the horizontal girder, end buttress and vertical webs is to take account of the loads imposed and the deflection of the structure.

**Table 9.9.1 Vertical web on longitudinal bulkhead coefficient**

Number of cross-ties	$K_3$	$K_4$	$K_5$	Range of application
1	2,16	$0,455 - 0,316\phi$	0,103	$0,5 \leq \phi \leq 0,7$
2	1,88	$0,441 - 0,267\phi_1$	$0,498\phi_2 - 0,249$	$0,4 \leq \phi_1 \leq 0,5$ $0,65 \leq \phi_2 \leq 0,8$

9.7.9 Where, in ships exceeding 150 m in length, the longitudinal bulkhead is corrugated, the transverses are generally to be symmetrical on both sides of the bulkhead, and the scantlings may require to be increased to limit deflection.

### 9.8 Primary members supporting non-oiltight bulkheads

9.8.1 These requirements are applicable to primary members supporting non-oiltight transverse bulkheads. Where non-oiltight longitudinal bulkheads are proposed, the requirements for primary members will be individually considered.

9.8.2 Direct calculation procedures will generally be required where non-oiltight bulkhead primary members will interact with, or tend to support, the primary bottom, longitudinal bulkhead or side structure, and in other cases where warranted by structural design features. In general the section modulus of horizontal girders is to be not less than:

$$Z = 145 k b l_e^2 \frac{l_b}{L} \text{ cm}^3$$

9.8.3 When determining the width of plating supported and the effective breadth for calculating the section modulus, no deduction is to be made on account of perforations.

## Section 10 Construction details and minimum thickness

### 10.1 Symbols

10.1.1 The symbols used in this Section are defined as follows:

For the primary member:

$d_w$  = depth of member web, in mm

$s_t$  = spacing of tripping or docking brackets on the web of the member, in metres

$t_w$  = thickness of member web, in mm

$S_w$  = spacing of members, in metres

For the primary member web stiffener:

$d$  = depth of web plate panel, in mm

$l_s$  = span of stiffeners between effective support points, in metres

$s$  = spacing of stiffeners on the web, in mm

$A_s$  = cross-sectional area of the web stiffener and associated web plating, in  $\text{cm}^2$

$I_s$  = moment of inertia of the web stiffener and associated web plating, in  $\text{cm}^4$

For the primary member end bracket, see Fig. 9.10.2:

$d_b$  = arm length, in metres

$l_b$  = effective length of the free edge, in metres

$t_b$  = thickness of the end bracket plating, in mm

$A_b$  = cross-sectional area of the end bracket edge stiffeners and associated plating, in  $\text{cm}^2$

$I_b$  = moment of inertia of the end bracket edge stiffeners and associated plating, in  $\text{cm}^4$

# Double Hull Oil Tankers

# Part 4, Chapter 9

Section 10

10.1.2 Other symbols are defined in 1.6.

## 10.2 Compartment minimum thickness

10.2.1 Within the cargo tank region, including wing ballast tanks and cofferdams at the ends of or between cargo tanks, the thickness of primary member webs and face plates, hull envelope and bulkhead plating is to be not less than:

$$t = 2,15L^{0,3} \text{ mm, or}$$

$$t = 7,5 \text{ mm}$$

whichever is the greater.

10.2.2 The minimum thickness of secondary members is to be determined as above, but need not exceed 11,0 mm.

10.2.3 In pump rooms the minima apply to shell, deck, longitudinal bulkhead and associated longitudinals. For other items solely within the pump room, including transverse bulkheads separating the adjacent machinery spaces from the pump room, the minima may be reduced by 1,0 mm, subject to a lower limit of 7,5 mm.

10.2.4 Within the fore peak tank, minimum thicknesses are to be in accordance with 10.2.1 and 10.2.2 reduced by 1,0 mm but are to be not less than 7,5 mm.

## 10.3 Geometric properties and proportions of members

10.3.1 The depth of the web of any primary member is to be not less than 2,5 times the depth of the cut-outs for the passage of secondary members, except where compensation is arranged to provide satisfactory resistance to deflection and shear buckling in the web.

10.3.2 The area of material in the face plate of any primary member structure is not to exceed:

$$0,00667d_w t_w \text{ cm}^2$$

nor is it to be less than:

$$0,00417s_t d_w \text{ cm}^2.$$

10.3.3 The geometric properties of rolled stiffeners and built sections are to be calculated in association with an effective width of attached plating in accordance with Pt 3, Ch 3,3.

## 10.4 Continuity of primary members

10.4.1 Primary members are to be so arranged as to ensure effective continuity of strength throughout the range of tank structure. Abrupt changes of depth or section are to be avoided. Where members abut on both sides of a bulkhead or on other members, arrangements are to be made to ensure that they are in alignment.

10.4.2 The members are to have adequate end fixity, lateral support and web stiffening, and the structure is to be arranged to minimize hard spots or other sources of stress concentration. Openings are to have well rounded corners and smooth edges and are to be located having regard to the stress distribution and buckling strength of the plate panel.

## 10.5 Primary member web plate stiffening

10.5.1 The webs of primary members are to be supported and stiffened in accordance with the following requirements, which are designated as requirements 'A', 'B', 'C', 'D' and 'E'. The application of these requirements is detailed in 10.7, and the corresponding locations indicated in Fig. 9.10.1. Where webs are slotted for the passage of secondary members, the web stiffeners are to be arranged to provide adequate support for the loads transmitted, see Pt 3, Ch 10,5.2. Where direct calculations are carried out in accordance with 1.1.9 and Section 14, other stiffening arrangements will be accepted subject to compliance with the maximum permissible stress and plate panel buckling criteria given in the *ShipRight SDA Procedure, Guidance Notes on Direct Calculations: Primary Structure of Tankers*.

10.5.2 Where higher tensile steel is used for the primary members, the maximum spacing of stiffeners given in this Section is to be multiplied by  $\sqrt{k}$ .

10.5.3 In addition to these stiffeners, tripping brackets as required by 10.11 are also to be fitted.

10.5.4 For requirement 'A' stiffening:

(a) The thickness,  $t_w$  of the web is to be not less than  $\frac{s}{80}$

(b) Stiffening is generally to be fitted normal to the face plate of the member, but the stiffeners parallel to the face plate will be required when the web depth,  $d_w$ , exceeds a value,  $d_{max}$  which is to be taken as:

$$\text{for } s \leq 55t_w \quad d_{max} = 3s$$

$$\text{for } s > 55t_w \quad d_{max} = \frac{45s t_w}{s - 40t_w}$$

(c) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $65t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the shell or bulkhead plating does not exceed  $d_{max}$ . In way of end brackets to transverse bulkhead primary structure, stiffeners are to be fitted normal to the face plate of the member so that web plate panel dimensions parallel to the face plate do not exceed  $80t_w$ .

10.5.5 For requirement 'B' stiffening:

(a) The thickness,  $t_w$  of the web is to be not less than  $\frac{s}{85}$


(b) Stiffening is generally to be fitted normal to the face plate of the member, but stiffeners parallel to the face plate will be required when the web depth,  $d_w$ , exceeds a value  $d_{max}$ , which is to be taken as:

$$\text{for } s \leq 70t_w \quad d_{max} = 3s$$

# Double Hull Oil Tankers

## Part 4, Chapter 9

Section 10



**Fig. 9.10.1 Key to application requirements**

$$\text{for } s > 70t_w \quad d_{\max} = \frac{48s t_w}{s - 54t_w}$$

- (c) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $80t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the shell or bulkhead plating does not exceed  $d_{\max}$ .

10.5.6 For requirement 'C' stiffening:

- (a) Stiffening is generally to be fitted normal to the face plate of the member in line with alternate secondary members, but stiffeners parallel to the face plate will be required, when the web depth,  $d_w$  exceeds a value,  $d_{\max}$  which is to be taken as:

$$\text{for } s \leq 76t_w \quad d_{\max} = 3s$$

$$\text{for } s > 76t_w \quad d_{\max} = \frac{48s t_w}{s - 60t_w}$$

- (b) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $90t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the deck plating does not exceed  $d_{\max}$ .

10.5.7 For requirement 'D' stiffening:

- (a) Stiffening parallel to the face plate will be required such that the distance between the stiffener and face plate, or between two stiffeners, does not exceed:  
 $80t_w$  where  $L \leq 90$  m  
 $55t_w$  where  $L \geq 190$  m  
 with intermediate values by interpolation.
- (b) Brackets are to be fitted to support the face plates and stiffeners.

10.5.8 For requirement 'E' stiffening:

- (a) Stiffening parallel to the face plate will be required such that the distance between the stiffener and face plate, or between two stiffeners, does not exceed:  
 $85t_w$  where  $L \leq 90$  m  
 $60t_w$  where  $L \geq 190$  m  
 with intermediate values by interpolation.
- (b) Brackets are to be fitted to support the face plates and stiffeners.

## Double Hull Oil Tankers

## Part 4, Chapter 9

Section 10

## 10.6 Inertia and dimensions of stiffeners

10.6.1 The moment of inertia is to be not less than:

- (a) For stiffeners normal to the primary member face plate:

$$I_s = \rho s t_w^3 \times 10^{-4} \text{ cm}^4$$

where

$t_w$  need not be greater than the values in Table 9.10.1 and

$\rho$  is to be obtained from Table 9.10.2.

- (b) For stiffeners parallel to the primary member face plate:

On transverses, webs and stringers

$$I_s = 2I_s^2 A_s \text{ cm}^4$$

On longitudinal deck, side and double bottom girders, see also Pt 3, Ch 4,7

$$I_s = 2,85I_s^2 A_s \text{ cm}^4$$

**Table 9.10.1 Maximum web thickness for stiffener inertia**

Requirement	Web thickness $t_w$ , in mm
'A'	$\frac{s}{55}$
'B' and 'C'	$\frac{s}{70}$
'D'	$\frac{s}{80}$ where $L \leq 90 \text{ m}$ $\frac{s}{55}$ where $L \geq 190 \text{ m}$
'E'	$\frac{s}{85}$ where $L \leq 90 \text{ m}$ $\frac{s}{60}$ where $L \geq 190 \text{ m}$
NOTE Intermediate values by interpolation.	

10.6.2 Where stiffeners are fitted in both directions, the inertia of the stiffeners parallel to the face plate of the member is to be not less than that of the stiffeners fitted normally.

10.6.3 The depth of web stiffeners is to be not less than 75 mm.

10.6.4 Where flat bar stiffeners are used, the ratio of depth to thickness is not to exceed  $18\sqrt{k}$ .

**Table 9.10.2 Coefficients for stiffener inertia**

Aspect ratio of plate panel, $\frac{s}{d}$	1,0 or more	0,9	0,8	0,7	0,6	0,5	0,4	0,3 or less
$\rho$	1,5	2,1	2,9	4,2	6,1	9,2	14,6	30,0
NOTES 1. Intermediate values by interpolation. 2. The depth of panel, $d$ , used in calculating aspect ratio may be measured from the face of the secondary member to which the primary member web stiffener is attached.								

## 10.7 Application of stiffening requirements

10.7.1 The requirements as detailed in 10.5 and 10.6 are to be applied in the following locations, see also Fig. 9.10.1.

- (a) For transverses at longitudinal bulkhead:

Requirement 'A' stiffening is to extend at least as far as the lower surface of the lower cross-tie. Elsewhere, requirement 'B' stiffening is to be fitted.

- (b) For deck transverses:

Requirement 'C' stiffening is to be fitted.

- (c) For stringers and horizontal girders on bulkheads:

Requirement 'A' stiffening is to extend for a distance from each end of 20 per cent of the span of the stringer or girder, but at least beyond the toes of the end brackets. Elsewhere, requirement 'B' stiffening is to be fitted.

- (d) For cross-ties:

Cross-ties are to be suitably stiffened to prevent buckling and twisting. Requirement 'D' stiffening is to be fitted to the lower or to a single cross-tie. Requirement 'E' stiffening is to be fitted to the upper cross-ties where two cross-ties are arranged.

- (e) For shell stringers and vertical webs in fore peak:

Requirement 'A' stiffening is to extend the full length of the member.

10.7.2 The application of stiffening requirements to transverse structures where no cross-ties are fitted and within double hull structures are to be based on the results of direct calculation and will be specially considered.

## 10.8 Stiffening of continuous longitudinal girders

10.8.1 The webs of continuous longitudinal deck and double bottom girders are to be stiffened longitudinally. Particular attention is to be given to the stiffening of docking girders, see also the buckling requirements in Pt 3, Ch 4,7.

10.8.2 The stiffeners on deck girders are to be spaced not more than  $55t_w$  mm apart except in way of vertical webs and end brackets, where the spacing is not to exceed  $45t_w$  mm. Alternatively, a combination of parallel stiffeners at  $55t_w$  mm spacing and normal stiffeners at  $45t_w$  mm spacing may be adopted. Particular attention is to be given to the stiffening of the docking girder.

10.8.3 The application of stiffening requirements to girders within double hull structures is to be based on the results of direct calculation, see also 10.10.1.



# Double Hull Oil Tankers

## Part 4, Chapter 9

### Section 10

10.8.4 The moment of inertia of the stiffeners is to comply with 10.6.

#### 10.9 Stiffening of vertical webs on transverse bulkheads

10.9.1 Vertical webs are to be fitted with stiffeners parallel to the face plate of the web and spaced not more than  $60t_w$  mm apart. Stiffeners normal to the face plate are to be fitted when a vertical web supports horizontal stiffeners on transverse bulkheads. The length of stiffener is to be sufficient to distribute the load transmitted, and the connection between web stiffener and bulkhead stiffener is to comply with the relevant requirements of Pt 3, Ch 10,5.2.

10.9.2 The moment of inertia of the stiffeners is to comply with 10.6.

#### 10.10 Double bottom girders in way of docking supports

10.10.1 Additional vertical stiffeners may be required on the bottom panels of the girder to resist docking pressures.

#### 10.11 Lateral stability of primary members

10.11.1 Tripping brackets are generally to be fitted close to the toes of end brackets, in way of cross-ties and elsewhere, so that the spacing between brackets does not exceed the lesser of 4,5 m or 15 times the width of the face plate (20 times in the case of deck transverses). Arrangements in way of the intersections of primary members are to be such as to prevent tripping. A closer spacing of brackets may be required to be adopted with asymmetrical face plates.

10.11.2 To maintain continuity of strength, substantial horizontal and vertical brackets are to be fitted to transverses or stringers at ends of cross-ties. Horizontal brackets are to be aligned with the cross-tie face plates, and vertical end brackets are to be aligned with the cross-tie web.

10.11.3 Wide face plates may require additional support between brackets.

10.11.4 In the fore peak tank, if the angle between the normal to the shell plating and the vertical webs exceeds  $20^\circ$ , tripping brackets are to be fitted at the toes of end brackets and elsewhere, such that their spacing does not exceed 3 m.

#### 10.12 Openings in web plating

10.12.1 Where openings are cut in the webs of primary supporting members, the greatest dimension of the opening is not to exceed 20 per cent of the web depth. The openings are to be kept equidistant from the corners of notches for frames and stiffeners. In the case of webs supporting single skin structures the openings are to be located so that the edges are not less than 40 per cent of web depth from the face plate. Openings are to be suitably framed where required.

10.12.2 In way of cross-ties and their end connections lightening holes are not to be cut in horizontal girders on the ship's side and longitudinal bulkheads, in symmetrical webs nor in vertical webs on longitudinal bulkheads and wing ballast tanks.

10.12.3 Holes cut in primary longitudinal members within  $0,1D$  of the deck and bottom are, in general, to be reinforced as required by 4.10. Access holes may be cut in deep transverses and girders with suitable compensation to provide satisfactory resistance to deflection and shear buckling in the web.

10.12.4 All holes are to have smooth edges and are to be kept well clear of notches and the toes of brackets.

10.12.5 Small air and drain holes cut in primary members are to be kept clear of the toes of brackets and are to be well rounded with smooth edges. Where holes are cut in primary longitudinal members in areas of high stress, or where primary members are of higher tensile steel, they are to be elliptical, or equivalent, to minimize stress concentration.

10.12.6 Where holes are cut for heating coils, the lower edge of the hole is to be not less than 100 mm from the inner bottom. Where large notches are cut in the transverses for the passage of longitudinal framing, adjacent to openings for heating coils, the longitudinal notches are to be collared. Examination of the buckling strength of the web plate panel between notches for longitudinals may be required.

#### 10.13 Brackets connecting primary members

10.13.1 The arm length of brackets connecting primary supporting members should, in general, be not less than the depth of the member web, nor exceed 1,5 times the web depth. The two arms should be of approximately equal lengths.

10.13.2 In a ring system where the end bracket is integral with the webs of the members, and the face plate is carried continuously along the edges of the members and the bracket, the full area of the largest face plate is to be maintained to the mid-point of the bracket and gradually tapered to the smaller face plates. Butts in face plates are to be kept well clear of the toes of brackets. Where a wide face plate abuts on a narrower one, the taper is generally not to exceed 1 in 4. Where a thick face plate abuts against a thinner one, if the difference in thickness exceeds 3 mm, the taper on thickness is not to exceed 1 in 3.


10.13.3 The thickness of separate end brackets is generally to be not less than that of the thicker of the primary member webs being connected, but may be required to be increased locally at the toes. The bracket is to extend to adjacent tripping brackets, stiffeners or other support points. Bracket toes are to be well radiused. Where the bracket is attached to a corrugated bulkhead, suitable arrangements are to be made to dissipate the load at the bracket toe. Details of the welding to be used in way of toes of separate brackets are to be submitted, see *also* Pt 3, Ch 10,5.1.7.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 10 &amp; 11

10.13.4 Brackets are to be fitted with suitable face plates and stiffeners. The maximum distance from the face plate to the first parallel stiffener is to be  $30t_b$ . Subsequent stiffeners lying parallel to the face may be spaced not more than  $45t_b$  apart. The maximum arm length for an unstiffened triangular panel is  $100t_b$ , see Fig. 9.10.2. The depth of stiffeners is to be not less than 75 mm, and their moment of inertia is to comply with 10.6.



10.13.5 The area of discontinuous face plates is generally to be about 80 per cent of the area of the face plates of the adjacent members. However, where the stiffener adjacent to the face plate is of increased size, consideration will be given to the face area required. In addition, the following expression is to be satisfied:

$$\sqrt{\frac{I_b}{A_b}} \geq 2 l_b$$

10.13.6 The ends of discontinuous face plates are to be well tapered. The taper may be 1 in 3, but where the width of the face plate exceeds 500 mm, a taper not less than 1 in 4 is generally to be adopted. Stiffeners adjacent to the face plate should be tapered 1 in 2, and other stiffeners may be cut at  $45^\circ$ .

10.13.7 Face plates and web stiffeners are to be suitably supported against tripping, see Fig. 9.10.2.

10.13.8 In the case of very large brackets with heavy face plates, it is recommended that the effective span,  $l_b$ , be reduced by extending the primary member main supporting brackets to provide lateral stability to the face plate, see Fig. 9.10.2.

### 10.14 Arrangements at intersections of continuous secondary and primary members

10.14.1 For details and connections of collars, see Pt 3, Ch 10.5.2.

## Section 11 Ships for alternate carriage of oil cargo and dry bulk cargo

### 11.1 Application

11.1.1 The requirements of this Section apply to ships intended to carry oil in bulk with a flash point not exceeding  $60^\circ\text{C}$  (closed cup test) or dry bulk cargo alternatively.

11.1.2 In addition to this Chapter the requirements of Chapter 7 and Chapter 11 are also to be complied with as applicable. Particular attention is drawn to the minimum thickness requirements of Section 10.

### 11.2 Class notations

11.2.1 Ships complying with the requirement of this section will be eligible for one of the following class notations, as applicable.

- (a) **100A1 Oil or Bulk Carrier, ESP**
- (b) **100A1 Oil or Bulk Carrier strengthened for heavy cargoes, holds ... may be empty, ESP**
- (c) **100A1 Oil or Bulk Carrier strengthened for heavy cargoes, any hold may be empty, ESP**
- (d) **100A1 Ore or Oil Carrier, ESP.**

11.2.2 The notation **ESP** serves to identify the ship as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3.3 and Ch 3.6, see also Pt 1, Ch 2.2.3.12.

11.2.3 The above notations assume that dry cargoes and oil cargoes will not be carried simultaneously. However, oil may be retained in slop tanks when the ship is carrying dry cargo, provided that these tanks comply with the requirements of the Rules. Gas freeing, inerting, and isolating by approved arrangements of the remaining tanks and holds before loading ore or other dry cargoes is the responsibility of the Owner and is to be accordance with National and Port Authority requirements.

11.2.4 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2 to which reference should be made.

# Double Hull Oil Tankers


## Part 4, Chapter 9

Section 11

### 11.3 Structural configuration and ship arrangement

11.3.1 The requirements contained in this Section apply to the following ship types:

- (a) Oil or bulk carrier with a basic structural configuration having a single deck hull and which includes, a double skin side structure, double bottom, hopper side tanks and topside tanks fitted below the upper deck. A typical cross section is indicated in Fig. 9.11.1(a). However, consideration will be given to other arrangements on the basis of the requirements of this Section. The requirements of Chapter 7 are to be applied.
- (b) Ore or oil carrier with a basic structural configuration having a single deck hull and which includes, a double skin side structure, two longitudinal bulkheads, and a double bottom throughout the centre hold and wing tanks. A typical cross section is indicated in Fig. 9.11.1(b). The requirements of Chapter 11 are to be applied.



**Fig. 9.11.1 Structural configuration**

11.3.2 Where oil residues are to be retained on board, slop tanks of sufficient capacity to meet MARPOL requirements are to be provided and are to be separated from adjacent spaces by cofferdams which are to be capable of being flooded, except where the adjacent space is used as a pump room, ballast tank, or an oil fuel bunker tank, see also 1.2.2, Pt 5, Ch 15, 1.9, and SOLAS Reg. II-2/D, 56.4.

11.3.3 Arrangements are to be provided for the mechanical ventilation of cargo spaces and any enclosed spaces adjacent to cargo spaces, see Pt 5, Ch 15,3. Similar arrangements are to be provided for cargo oil ducts which are used as pipe tunnels when the ship is carrying dry cargo, see also 11.3.5.

11.3.4 Openings which may be used for cargo operations, for example in the bottom of topside tanks, are not permitted in bulkheads and decks separating oil cargo spaces from other spaces not designed and equipped for the carriage of oil cargoes unless such openings are equipped with alternative approved means to ensure equivalent integrity.

11.3.5 For the requirements of ducts for cargo oil lines below decks on ore or oil carriers, see Pt 5, Ch 15,3.3.

11.3.6 For the requirements for access arrangements to pipe tunnels and spaces in the cargo area, see Section 13.

### 11.4 Bulkheads in way of dry/oil cargo holds

11.4.1 In way of cargo oil holds, the scantlings of the cargo space boundaries are to comply with 11.4.2 and 11.4.6.

11.4.2 The scantlings of vertically corrugated and double plate transverse bulkheads supported by stools are to be determined in accordance with the requirements of 7.4.1, 7.4.2 and Ch 7,10.2. In general, the bulkheads are to have stiffening or corrugations arranged vertically, supported by top and bottom end stools. Alternative arrangements will, however, be considered.

11.4.3 The longitudinal bulkheads including bulkhead forming inner hull, and the sloped bulkheads of the topside and double bottom tanks are to comply with Section 6. However, in way of cargo holds  $b_1$  is to be taken as the horizontal distance from the plate or longitudinal under consideration to the vertical projection of the hatch side furthest away from the bulkhead. For longitudinal framing the determination of the span point may be in accordance with Pt 3, Ch 3,3. The scantlings of the sloped bulkhead of the double bottom hopper tanks in way of the dry cargo holds are to be not less than the requirements of Ch 7,9.

11.4.4 The arrangement of stools and adjacent structure common with dry cargo holds is to be designed to avoid pockets in which gas could collect.

11.4.5 Where the form of construction used for transverse bulkheads in wing tanks is different from that used in centre holds, arrangements are to be made to ensure continuity of transverse strength through the longitudinal bulkhead.

11.4.6 Where partial filling of centre holds with liquid is contemplated, the scantlings and structural arrangements of the boundary bulkheads are to be capable of withstanding the loads imposed by the movement of liquid in the holds. The magnitude of the predicted loadings, together with the scantling calculations, may require to be submitted.

# Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 11, 12 & 13

### 11.5 Bulkheads in wing tanks of ore or oil carriers

11.5.1 Oiltight bulkheads in wing tanks of ore or oil carriers, see 11.3.1(b), are to comply with the requirements for transverse oiltight bulkhead plating, stiffening and primary structure given in Sections 7 and 9.

11.5.2 Non-oiltight bulkheads in wing tanks are to comply with the requirements given in Sections 8 and 9. The bulkhead plating is to be suitably reinforced in way of double bottom scarfing arrangements and the ends of centre hold deck transverses. Openings in wing tank bulkheads are to be kept clear of these areas.

### 11.6 Cofferdam bulkheads

11.6.1 The scantlings of cofferdam bulkheads not forming the boundary of a cargo space are to be as required by Section 7.

### 11.7 Hatchways

11.7.1 The scantlings of the cargo hold hatch coamings are to comply with Pt 3, Ch 11,5 and the cargo hold hatch covers with Pt 3, Ch 11,2 and Pt 4, Ch 7,12.

11.7.2 Where cargo holds are intended to be partly filled the hatch covers may require to be additionally strengthened, see also 11.4.6.

11.7.3 Slop tank hatches and cleaning openings are only permitted on open deck. Unless these openings are closed with a watertight bolted plate, the locking arrangements are to be under the control of a responsible officer.

### 11.8 Hatch coamings

11.8.1 The height and construction of hatch coamings are to comply with Pt 3, Ch 11,5 and Pt 4, Ch 7,13.

## Section 12 Heated cargoes

### 12.1 General

12.1.1 This Section applies to the carriage of heated cargoes in vessels having a structural configuration as shown in Table 9.1.3 and Fig. 9.11.1.

### 12.2 Carriage of heated cargoes

12.2.1 Where cargoes are to be carried at temperatures above  $T$  during the voyage, temperature distribution investigations and thermal stress calculations are to be submitted. These are to be carried out using the actual temperature of the cargo during the voyage and compared with calculations carried out for a cargo temperature of  $T$ . For the purpose of these calculations,  $T$  is to be taken as follows:

- (a) Where longitudinal framing is adopted,  $T = 65^{\circ}\text{C}$ .
- (b) Where transverse framing is adopted for the longitudinal bulkhead, inner hull and side shell,  $T = 80^{\circ}\text{C}$ .

12.2.2 The calculations are to give the resultant stresses on the hull structure, based on a sea temperature of  $0^{\circ}\text{C}$  and an air temperature of  $5^{\circ}\text{C}$ . Any proposals for reinforcement of the hull structure and/or limitation of the still water bending moment for heated cargo conditions are to be submitted.

12.2.3 Submitted proposals are to take account of non-uniform loading patterns with resultant variations in temperature distribution, where applicable.

### 12.3 Loading of hot oil cargoes

12.3.1 Hot oil cargoes may be loaded at the permitted carriage temperature in 12.2.1 or the temperature given below, whichever is the greater, without the need for temperature distribution and thermal stress calculations, providing the temperature specified in 12.2.1(a) and (b) is not exceeded during the voyage:

- (a)  $65^{\circ}\text{C}$  for sea temperatures of  $0^{\circ}\text{C}$  and below.
- (b)  $75^{\circ}\text{C}$  for sea temperatures of  $5^{\circ}\text{C}$  and above.
- (c) By linear interpolation between (a) and (b) above, for sea temperatures between  $0^{\circ}\text{C}$  and  $5^{\circ}\text{C}$ .

## Section 13 Access arrangements and closing appliances

### 13.1 General

13.1.1 For requirements in respect of coamings and closing of deck openings, see Pt 3, Ch 11,7.

13.1.2 Openings in cargo oil tanks are not to be located in enclosed spaces.

13.1.3 Ladders and platforms in cargo tanks, pump rooms and cofferdams are to be securely fastened to the structure, see also 2.3.

### 13.2 Access to spaces in the cargo area

13.2.1 Access to cofferdams, vertical wing and double bottom ballast tanks, cargo tanks and other spaces in the cargo area shall be direct from the open deck and such as to ensure their complete inspection. Access to double bottom tanks in way of cargo oil tanks, where wing ballast tanks are omitted, is to be provided by trunks from the exposed deck led down the bulkhead. Alternative proposals will, however, be considered provided the integrity of the inner bottom is maintained. Access to double bottom spaces may also be through a cargo pump room, pump room, deep cofferdam, pipe tunnel or similar compartments, subject to consideration of ventilation aspects.

## Double Hull Oil Tankers

## Part 4, Chapter 9

Sections 13 &amp; 14

**13.2.2** Where a duct keel or pipe tunnel is fitted, and access is normally required for operational purposes, access is to be provided at each end and at least one other location at approximately mid-length. Access is to be directly from the exposed deck. Where an after access is to be provided from the pump room to the duct keel, the access manhole from the pump room to the duct keel is to be provided with an oiltight cover plate. Access is not to be via the engine room. Mechanical ventilation is to be provided and such spaces are to be adequately ventilated prior to entry. A notice-board is to be fitted at each entrance to the pipe tunnel stating that before any attempt is made to enter, the ventilating fan must have been in operation for an adequate period. In addition, the atmosphere in the tunnel is to be sampled by a reliable gas monitor, and where an inert gas system is fitted in cargo tanks, an oxygen monitor is to be provided.

**13.2.3** In ships for the alternate carriage of oil cargo and dry bulk cargo where the boundary of a slop tank is part of a cargo pump room bulkhead any openings from the cargo pump room to the double bottom, pipe tunnel or other enclosed space are to be provided with a gas tight bolted cover.

**13.2.4** Every double bottom space is to be provided with separate access without passing through other neighbouring double bottom spaces.

**13.2.5** Where the tanks are of confined or cellular construction, two separate means of access from the weather deck are to be provided, one to be provided at either end of the tank space.

**13.2.6** For access through horizontal openings, hatches or manholes, the dimensions are to be sufficient to allow a person wearing a self-contained air-breathing apparatus and protective equipment to ascend or descend any ladder without obstruction and also to provide a clear opening to facilitate the hoisting of an injured person from the bottom of the space. The minimum clear opening is to be not less than 600 mm x 600 mm.

**13.2.7** At least one horizontal access opening of 600 mm x 800 mm clear opening is to be fitted in each horizontal girder in the vertical wing ballast space and weather deck to assist in rescue operations.

**13.2.8** For access through vertical openings, or manholes providing passage through the length and breadth of the space, the minimum clear opening is to be not less than 600 mm x 800 mm at a height of not more than 600 mm from the bottom shell plating unless gratings or other footholds are provided.

**13.2.9** For oil tankers of less than 5000 tonnes DWT smaller dimensions may be approved by the National Administration concerned in special circumstances, if the ability to traverse such openings or to remove an injured person can be proved to the satisfaction of the Administration.

**13.2.10** In double hull construction with the wing ballast tanks having restricted access through the vertical transverse webs, permanent arrangements are to be provided within the tanks to permit access for inspection at all heights in each bay. These arrangements which should comprise fixed platforms or other means are to provide sufficiently close access to carry out Close-Up Surveys as defined in Pt 1, Ch 3,7, using limited portable equipment where appropriate. Details of these arrangements are to be submitted for approval.

**13.2.11** On very large tankers it is recommended that consideration be given to providing permanent facilities for staging the interior of cargo tanks situated within the cargo tank region and of large tanks elsewhere. Suitable provisions would be:

- Staging which can be carried on board and utilized in any tank, including power-operated lift or platform systems.
- Enlargement of structural members to form permanent, safe platforms, e.g. bulkhead longitudinals widened to form stringers (in association with manholes through primary members).
- Provision of inspection/rest platforms at intervals down the length of access ladders.
- Provision of manholes in upper deck for access to staging in cargo tanks.

**13.2.12** Attention is drawn to 7.1.7, concerning provision of manholes in transverse bulkheads.

## Section 14 Direct calculations

### 14.1 Application

**14.1.1** Direct calculations are to be carried out for the derivation of scantlings where they are required by the preceding Sections of this Chapter or by related provisions included in Part 3.

**14.1.2** Direct calculation methods are also generally to be used where additional calculations are required by the Rules in respect of unusual structural arrangements.

### 14.2 Procedures

**14.2.1** For details of LR's direct calculation procedures, see Pt 3, Ch 1,2. For requirements concerning use of other calculation procedures, see Pt 3, Ch 1,3.

**14.2.2** Details of direct calculation procedures for determining the scantlings of boundary bulkheads for partially filled tanks are given in *ShipRight SDA Procedure, Sloshing loads and Scantling Assessment*.



# Single Hull Oil Tankers

# Part 4, Chapter 10

Sections 1 & 2

## Section

- 1 **General**
- 2 **Primary members supporting longitudinal framing**
- 3 **Primary members supporting transverse side framing**
- 4 **Primary members supporting oiltight bulkheads**
- 5 **Primary members supporting non-oiltight bulkheads**
- 6 **Trunked construction**
- 7 **Construction details and minimum thickness**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements specified in Chapter 9 are applicable to small conventional single hull oil tankers where relevant, together with the additional requirements of this Chapter.

1.1.2 For tankers intended to load or unload whilst aground, see Pt 3, Ch 9,13.

### 1.2 Class notations

1.2.1 Sea-going ships complying with the requirements of Chapter 9, where relevant, together with the additional requirements of this Chapter will be eligible to be classed **100A1 Oil Tanker, ESP**.

1.2.2 The Notation **ESP** serves to identify the ships as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.

## ■ Section 2 Primary members supporting longitudinal framing

### 2.1 General

2.1.1 These requirements are applicable to the following structural arrangements for ships with two longitudinal bulkheads:

- (a) Centre tank structure:
  - (i) Primary supporting centreline girder between oiltight transverse bulkheads, in association with up to five transverses.

- (ii) Bottom transverses spanning between longitudinal bulkheads in association with a non-primary centreline docking girder.
  - (iii) Double bottom.
- (b) Wing tank structure:
  - (i) Transverse ring structure consisting of bottom, side shell, longitudinal bulkhead and deck transverses and incorporating one cross-tie or no cross-ties in tankers not exceeding 75 m in length.
  - (ii) Double bottom.

2.1.2 The requirements are also applicable to structural arrangements incorporating a single longitudinal bulkhead located on the ship's centreline without cross-ties, for tankers not exceeding 75 m in length.

2.1.3 The minimum thickness and constructional detail requirements of Section 7 are to be complied with. Particular attention is to be paid to the design of end connections between primary members and buttresses. The shear and combined stress levels in these connections are to be examined and should be within the limits specified in *ShipRight SDA Procedure, Guidance Notes on Direct Calculations*.

### 2.2 Symbols

2.2.1 The symbols used in this Section are defined as follows:

- $b_{e1}, b_{e2}$  = effective end bracket leg length, in metres, at each end of the member, see Pt 3, Ch 3,3
- $b_T$  = overall breadth of tank, in metres
- $h_b$  =  $0,75D + 2,45$  m
- $h_c$  = vertical distance from the centre of the cross-tie to deck at side amidships, in metres
- $h_s$  = distance between the lower span point of the side transverse and the moulded deck line at side, in metres
- $I_c$  = one-half the vertical distance, in metres, between the cross-tie and the centre of the adjacent bottom or deck transverse, or double bottom, see Fig. 10.2.3
- $l_T$  = overall length of tank, in metres
- $s$  = spacing of transverses, in metres
- $A$  = net sectional area of the web including end bracket where applicable, in  $\text{cm}^2$
- $I_G$  = moment of inertia of the girder, in  $\text{cm}^4$
- $I_T$  = moment of inertia of the transverse, in  $\text{cm}^4$
- $Q_x$  = shear force at the actual section under consideration, obtained from shear force diagrams constructed as indicated, in kN (tonne-f)
- $S_c$  = length of cross-tie between the face plates on the vertical transverse webs at the cross-ties, in metres
- $S_G$  = span of girder, in metres, and is in no case to be taken less than  $(l_T - 1,8s)$  metres
- $S_s$  = span of the side transverses, in metres, and is to be measured between end span points, see Fig. 10.2.3
- $S_T$  = span of transverses, in metres.

2.2.2 Other symbols are defined in Ch 9,1.6.

# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 2

## 2.3 Structural arrangements

2.3.1 The spacing of transverses is not to exceed 3,6 m.

2.3.2 Where a trunk is fitted, the scantlings of primary members are to be modified as required by Section 6.

## 2.4 Bottom structure coefficients

2.4.1 Where a primary supporting bottom centreline girder is fitted, in a single bottom, the requirements for the girder and transverses may be derived using bending moment and shear force coefficients  $K_1$  and  $K_2$  determined from Table 10.2.1. To obtain the coefficients, the following factors are required:

$$\alpha = \frac{I_T - S_G}{2s}$$

$$\beta = \frac{S_G^3 I_T}{S_T^3 I_G}$$

Initially, an estimated value of the ratio  $\frac{I_T}{I_G}$  may be used, and

an iterative process adopted to obtain the final required values.

2.4.2 Where bottom transverses are fitted in association with a non-primary centreline girder the coefficients for the transverse are to be taken as:

$$K_1 = 0,083$$

$$K_2 = 0,50$$

For the requirements for the non-primary girder, see 2.6.

2.4.3 In ships with one longitudinal bulkhead, the coefficient for the bottom transverse is to be taken as:

$$K_1 = 0,177.$$

## 2.5 Bottom transverses

2.5.1 The section modulus of bottom transverses is to be not less than:

$$Z = 62K_1 s h_b S_T^2 k \text{ cm}^3$$

2.5.2 In ships with two longitudinal bulkheads, the depth of the bottom transverse web plate is to be not less than  $0,2S_T$  and the net sectional area of the web at any section, including vertical end connections, is to be not less than:

$$A = 0,12Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where

$Q_x$  is calculated from shear force diagrams constructed as shown in Fig. 10.2.1. For end connections,  $Q_x$  is to be determined by projection of the shear force diagram as indicated.

2.5.3 The moment of inertia of bottom transverses is to be not less than:

$$I = \frac{10,5}{k} S_T Z \text{ cm}^4$$

## 2.6 Bottom girders

2.6.1 The section modulus of the primary centreline bottom girder, where fitted, is to be not less than:

$$Z = 31K_1 b_T S_G h_b s k \text{ cm}^3$$

2.6.2 The net sectional area of the web at any section, including vertical end connections, is to be not less than:

$$A = 0,12Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where  $Q_x$  is calculated from a shear force diagram constructed as shown in Fig. 10.2.2. For end connections,  $Q_x$  is to be determined by projection of the shear force diagram as indicated.

2.6.3 In a single bottom the section modulus and web area of a non-primary centreline docking girder are to be not less than:

$$Z = 3,6b_T D s^2 k \text{ cm}^3$$

$$A = 0,3b_T D s k \text{ cm}^2$$

The scantlings of this girder may, however, be required to be increased, depending upon the docking condition and support arrangements, details of which are to be submitted. Consideration may be required to be given to restricting the level of ballast tank filling for docking purposes. The loads are to be specially considered when wing tanks are ballasted for docking.

2.6.4 Consideration will be given to alternative methods of stiffening in way of the keel blocks when accompanied by supporting calculations.

2.6.5 In way of the vertical centreline web and centreline supports to horizontal girders of transverse bulkheads, the docking girder is to be increased in depth and scantlings as necessary to provide an effective support.

## 2.7 Side transverses

2.7.1 The section modulus of side transverses in ships with one or two longitudinal bulkheads is to be not less than:

$$Z = K_3 s h_s S_s^2 k \text{ cm}^3$$

where

$K_3$  is given in Table 10.2.2.



## Single Hull Oil Tankers

## Part 4, Chapter 10

Section 2

**Table 10.2.1 Bottom structure coefficients** (see continuation)

(a) 1 GIRDER, 2 TRANSVERSES

$\beta$	Girder											
	$K_1$						$K_2$					
	$\alpha$						$\alpha$					
	0,0	0,2	0,4	0,6	0,8	1,0	0,0	0,2	0,4	0,6	0,8	1,0
0,02	0,210	0,210	0,195	0,175	0,125	0,0	1,000	1,000	1,000	1,000	1,000	1,000
0,04	0,210	0,210	0,195	0,175	0,125	0,0	0,960	0,960	0,980	1,000	1,000	1,000
0,06	0,210	0,210	0,195	0,170	0,125	0,0	0,940	0,940	0,960	0,980	1,000	1,000
0,08	0,205	0,205	0,190	0,167	0,125	0,0	0,920	0,920	0,940	0,970	1,000	1,000
0,10	0,200	0,200	0,185	0,165	0,125	0,0	0,900	0,900	0,920	0,960	0,990	1,000
0,20	0,180	0,180	0,170	0,150	0,120	0,0	0,800	0,820	0,860	0,920	0,980	1,000
0,40	0,150	0,150	0,150	0,135	0,115	0,0	0,670	0,730	0,760	0,840	0,950	1,000
0,60	0,130	0,130	0,135	0,125	0,110	0,0	0,580	0,630	0,690	0,790	0,910	1,000
0,80	0,120	0,120	0,120	0,120	0,105	0,0	0,520	0,540	0,630	0,730	0,880	1,000
1,00	0,100	0,100	0,115	0,115	0,100	0,0	0,460	0,500	0,580	0,680	0,850	1,000
	Transverses											
	0,02	0,022	0,022	0,022	0,021	0,020	0,255	0,255	0,255	0,255	0,250	0,250
	0,04	0,023	0,023	0,023	0,022	0,021	0,263	0,263	0,257	0,255	0,250	0,250
	0,06	0,025	0,025	0,023	0,022	0,021	0,265	0,265	0,263	0,260	0,250	0,250
	0,08	0,026	0,026	0,024	0,023	0,021	0,270	0,270	0,267	0,260	0,253	0,250
	0,10	0,027	0,027	0,025	0,023	0,022	0,275	0,275	0,270	0,263	0,255	0,250
	0,20	0,033	0,033	0,029	0,026	0,023	0,300	0,300	0,285	0,272	0,257	0,250
	0,40	0,041	0,041	0,036	0,032	0,025	0,330	0,330	0,307	0,287	0,265	0,250
	0,60	0,047	0,047	0,041	0,036	0,026	0,355	0,355	0,325	0,302	0,273	0,250
	0,80	0,051	0,051	0,045	0,038	0,028	0,370	0,370	0,342	0,315	0,278	0,250
	1,00	0,054	0,054	0,048	0,041	0,030	0,385	0,385	0,355	0,327	0,285	0,250

(b) 1 GIRDER, 3 TRANSVERSES

$\beta$	Girder											
	$K_1$						$K_2$					
	$\alpha$						$\alpha$					
	0,0	0,2	0,4	0,6	0,8	1,0	0,0	0,2	0,4	0,6	0,8	1,0
0,02	0,290	0,290	0,290	0,270	0,200	0,120	1,400	1,400	1,500	1,500	1,500	1,500
0,04	0,290	0,290	0,290	0,270	0,200	0,120	1,400	1,400	1,500	1,500	1,500	1,500
0,06	0,290	0,290	0,290	0,260	0,200	0,120	1,380	1,400	1,500	1,500	1,500	1,500
0,08	0,280	0,280	0,280	0,250	0,195	0,115	1,340	1,370	1,470	1,470	1,480	1,500
0,10	0,275	0,275	0,275	0,240	0,190	0,115	1,320	1,340	1,420	1,440	1,460	1,480
0,20	0,245	0,245	0,245	0,220	0,175	0,105	1,180	1,210	1,280	1,330	1,380	1,450
0,40	0,200	0,200	0,200	0,185	0,160	0,090	0,970	1,030	1,080	1,200	1,280	1,420
0,60	0,170	0,170	0,170	0,170	0,145	0,080	0,840	0,900	0,960	1,110	1,210	1,380
0,80	0,150	0,150	0,150	0,150	0,135	0,075	0,740	0,800	0,870	1,040	1,150	1,330
1,00	0,135	0,135	0,135	0,135	0,125	0,070	0,680	0,740	0,810	0,960	1,100	1,300
	Transverses											
	0,02	0,025	0,025	0,024	0,023	0,022	0,258	0,258	0,257	0,252	0,252	0,252
	0,04	0,026	0,026	0,025	0,024	0,023	0,267	0,267	0,267	0,262	0,262	0,260
	0,06	0,028	0,028	0,026	0,026	0,025	0,275	0,275	0,275	0,270	0,270	0,265
	0,08	0,030	0,030	0,028	0,028	0,026	0,285	0,285	0,280	0,272	0,272	0,272
	0,10	0,032	0,032	0,029	0,029	0,028	0,292	0,292	0,287	0,277	0,275	0,275
	0,20	0,040	0,040	0,037	0,035	0,033	0,325	0,325	0,315	0,310	0,300	0,282
	0,40	0,052	0,052	0,049	0,046	0,041	0,372	0,372	0,360	0,345	0,332	0,320
	0,60	0,059	0,059	0,057	0,054	0,048	0,405	0,405	0,392	0,375	0,357	0,342
	0,80	0,065	0,065	0,063	0,059	0,053	0,425	0,425	0,415	0,390	0,377	0,360
	1,00	0,069	0,069	0,066	0,063	0,056	0,440	0,440	0,432	0,415	0,395	0,375

# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 2

**Table 10.2.1 Bottom structure coefficients (conclusion)**

(c) 1 GIRDER, 4 TRANSVERSES

$\beta$	Girder											
	$K_1$						$K_2$					
	$\alpha$						$\alpha$					
	0,0	0,2	0,4	0,6	0,8	1,0	0,0	0,2	0,4	0,6	0,8	1,0
0,02	0,370	0,350	0,330	0,315	0,275	0,215	1,890	1,890	1,920	1,940	1,960	1,990
0,04	0,370	0,350	0,330	0,315	0,275	0,215	1,870	1,870	1,900	1,930	1,940	1,960
0,06	0,360	0,350	0,330	0,310	0,270	0,205	1,820	1,820	1,870	1,890	1,920	1,940
0,08	0,350	0,340	0,320	0,300	0,260	0,200	1,760	1,800	1,820	1,840	1,880	1,920
0,10	0,340	0,330	0,315	0,290	0,255	0,195	1,700	1,750	1,790	1,830	1,860	1,900
0,20	0,300	0,300	0,275	0,260	0,230	0,180	1,500	1,580	1,630	1,700	1,780	1,820
0,40	0,240	0,240	0,230	0,220	0,200	0,155	1,240	1,300	1,400	1,540	1,620	1,700
0,60	0,200	0,200	0,200	0,200	0,175	0,135	1,060	1,120	1,250	1,400	1,500	1,600
0,80	0,175	0,175	0,175	0,175	0,165	0,120	0,940	1,000	1,150	1,270	1,420	1,520
1,00	0,150	0,150	0,150	0,150	0,150	0,105	0,850	0,920	1,050	1,200	1,340	1,460
Transverses												
0,02	0,025	0,025	0,024	0,024	0,023	0,023	0,255	0,255	0,255	0,255	0,253	0,250
0,04	0,027	0,026	0,026	0,025	0,025	0,024	0,272	0,270	0,268	0,266	0,260	0,255
0,06	0,029	0,029	0,028	0,027	0,026	0,025	0,282	0,280	0,275	0,272	0,270	0,263
0,08	0,031	0,031	0,030	0,028	0,028	0,027	0,292	0,287	0,285	0,280	0,275	0,270
0,10	0,033	0,033	0,032	0,030	0,029	0,028	0,300	0,295	0,290	0,285	0,280	0,275
0,20	0,042	0,041	0,039	0,037	0,035	0,033	0,335	0,325	0,320	0,313	0,307	0,300
0,40	0,053	0,051	0,050	0,047	0,044	0,041	0,380	0,372	0,362	0,352	0,342	0,330
0,60	0,061	0,059	0,057	0,054	0,050	0,047	0,412	0,405	0,387	0,376	0,365	0,355
0,80	0,066	0,065	0,062	0,058	0,054	0,051	0,435	0,425	0,412	0,400	0,382	0,370
1,00	0,070	0,068	0,065	0,062	0,058	0,055	0,450	0,437	0,427	0,412	0,395	0,385



(d) 1 GIRDER, 5 TRANSVERSES

$\beta$	Girder											
	$K_1$						$K_2$					
	$\alpha$						$\alpha$					
	0,0	0,2	0,4	0,6	0,8	1,0	0,0	0,2	0,4	0,6	0,8	1,0
0,02	0,455	0,440	0,410	0,380	0,345	0,300	2,330	2,350	2,370	2,400	2,420	2,450
0,04	0,445	0,430	0,410	0,380	0,345	0,300	2,310	2,340	2,360	2,380	2,410	2,440
0,06	0,430	0,415	0,395	0,370	0,340	0,295	2,250	2,290	2,300	2,340	2,380	2,400
0,08	0,415	0,400	0,385	0,365	0,330	0,290	2,180	2,230	2,280	2,290	2,340	2,360
0,10	0,400	0,390	0,375	0,355	0,320	0,280	2,110	2,170	2,200	2,240	2,300	2,320
0,20	0,345	0,340	0,330	0,315	0,285	0,250	1,840	1,920	2,000	2,040	2,130	2,180
0,40	0,270	0,265	0,265	0,265	0,235	0,200	1,500	1,600	1,700	1,790	1,900	1,970
0,60	0,220	0,220	0,220	0,220	0,200	0,165	1,280	1,380	1,500	1,610	1,650	1,840
0,80	0,185	0,185	0,185	0,185	0,175	0,140	1,140	1,230	1,370	1,500	1,620	1,740
1,00	0,165	0,165	0,165	0,165	0,160	0,125	1,040	1,140	1,280	1,420	1,540	1,650
Transverses												
0,02	0,025	0,025	0,025	0,024	0,024	0,023	0,265	0,265	0,263	0,260	0,257	0,255
0,04	0,028	0,028	0,028	0,027	0,026	0,025	0,280	0,280	0,275	0,270	0,267	0,265
0,06	0,031	0,031	0,030	0,029	0,028	0,027	0,290	0,287	0,284	0,280	0,277	0,275
0,08	0,034	0,034	0,033	0,032	0,031	0,030	0,303	0,300	0,295	0,290	0,287	0,283
0,10	0,037	0,036	0,036	0,034	0,033	0,032	0,312	0,309	0,305	0,300	0,297	0,292
0,20	0,046	0,046	0,045	0,043	0,043	0,041	0,352	0,349	0,343	0,337	0,330	0,325
0,40	0,060	0,058	0,057	0,055	0,054	0,053	0,405	0,402	0,393	0,383	0,378	0,375
0,60	0,068	0,067	0,065	0,064	0,063	0,061	0,435	0,432	0,426	0,417	0,412	0,407
0,80	0,073	0,072	0,071	0,069	0,068	0,067	0,455	0,452	0,446	0,440	0,436	0,432
1,00	0,077	0,076	0,074	0,073	0,071	0,070	0,470	0,467	0,461	0,455	0,450	0,445

# Single Hull Oil Tankers

# Part 4, Chapter 10

## Section 2




2.7.2 In ships with two longitudinal bulkheads, the net sectional area of the web at any section is to be not less than:

$$A = 0,12 Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where  $Q_x$  is calculated from shear force diagrams constructed as shown in Fig. 10.2.3. For this purpose the values of  $K_4$  and  $K_5$  and the range of application is given in Table 10.2.2.



2.7.3 The moment of inertia of side transverses is to be not less than:

$$I = \frac{7,5}{k} S_s Z \text{ cm}^4.$$

## 2.8 Deck transverses

2.8.1 The section modulus of deck transverses is to be not less than:

$$Z = 53,75 (0,0269 s L + 0,8) (S_T + 1,83) k \text{ cm}^3$$

Where a continuous deck girder is fitted, the term  $S_T$  in the above formula is to be replaced by  $\frac{S_T}{2}$ .

**Table 10.2.2 Side transverse coefficients**

Number of cross-ties	$K_3$	$K_4$	$K_5$	Range of application
0	8	Not applicable		$L \leq 75 \text{ m}$ (see 2.3)
1	2,16	$0,455 - 0,316 \alpha$	0,103	$0,5 \leq \alpha \leq 0,7$

# Single Hull Oil Tankers

# Part 4, Chapter 10

Sections 2 & 3

2.8.2 The net sectional area of the web is to satisfy the requirements of 2.5.2 using a head,  $h_b = \frac{L_1}{56}$  m.

2.8.3 The moment of inertia of the transverses is to be not less than:

$$I = \frac{7,5}{k} S_T Z \text{ cm}^4.$$

## 2.9 Deck girders

2.9.1 Where a continuous deck centreline girder supporting deck transverses is fitted, it is to have a section modulus not less than:

$$Z = 0,0476 S_G^2 b_T L k \text{ cm}^3$$

2.9.2 The net sectional area of the web is to satisfy the requirements of 2.6.2 using a head,  $h_b = \frac{L_1}{56}$  m.

2.9.3 In way of the vertical centreline web on transverse bulkheads, the continuous deck girder is to be increased in depth and scantlings as necessary to provide an effective support.

2.9.4 Where an intercostal deck girder is fitted, it is to have a depth not less than 50 per cent of the depth of the deck transverse and the area of the face flat is to be not less than that of the transverse.

2.9.5 In way of the vertical centreline web and centreline supports to horizontal girder on transverse bulkheads, the intercostal deck girder may be required to be increased in depth and scantlings to provide an effective support.

## 2.10 Cross-ties

2.10.1 Cross-ties, where fitted, may be of plate or sectional material and are to have an area and least moment of inertia not less than:

$$A = (64 + 1,035 I_c h_c s) k \text{ cm}^2$$

$$I = 2,45 I_c h_c s S_c^2 \text{ cm}^4.$$

2.10.2 Design of end connections is to be such that the area of the welding, including vertical brackets, where fitted, is to be not less than the minimum cross-sectional area of the cross-tie derived from 2.10.1. To achieve this full penetration may be required and thickness of brackets may require further consideration. Attention is to be given to the full continuity of area of the backing structure on the transverses. Particular attention is also to be paid to the welding at the toes of all vertical end brackets on the cross-tie.

## 2.11 Double bottom girders and floors

2.11.1 The scantlings of girder and floors are to satisfy the requirements of Ch 1,8.3 and Ch 1,8.5 respectively for longitudinally framed ships.

## Section 3 Primary members supporting transverse side framing

### 3.1 General

3.1.1 The requirements of this Section are applicable to side stringers and transverse webs associated with transverse framing.

3.1.2 The minimum thickness and constructional detail requirements of Section 7 are to be complied with.

### 3.2 Symbols

3.2.1 The symbols used in this Section are defined as follows:

- $h_1$  = head, in metres, from stringer to highest point of tank excluding hatchway, but not less than 2,5 m
- $Q_x$  = shear force at the actual section under consideration, obtained from shear force diagrams constructed as indicated, in kN (tonne-f)
- $S_1$  = span, in metres, of the horizontal girder measured between span points, but to be taken not less than the lesser of (1,2 + 0,02L) m or 3 m.

3.2.2 Other symbols are defined in Ch 9,1.6.

### 3.3 Structural arrangements

3.3.1 Side shell stringers are to be fitted as required by Table 10.3.1. Alternatively, the number of stringers may be derived by direct calculation, particular regard being given to secondary bending effects on the frames supported.

**Table 10.3.1 Requirements for stringers**

Ship depth, in metres	Number of stringers
$D \leq 6,0$	0
$6,0 < D \leq 7,5$	1
$7,5 < D \leq 11,0$	2

3.3.2 Where the spacing of bulkheads (oiltight or non-oiltight) exceeds 15 m, side transverses are to be fitted in line with each bottom transverse.

3.3.3 Where side transverses are not required, bottom transverses are to be adequately supported at the side shell and longitudinal bulkhead, and the lower side stringer is to be suitably buttressed from the bottom transverse.

3.3.4 Cross-ties, where fitted, are to comply with the requirements of 2.10 and are, in general, to be aligned with the stringers.

3.3.5 Where the ship is fitted with a trunk, the scantlings as given in this Section are to be modified as required by Section 6.

# Single Hull Oil Tankers

# Part 4, Chapter 10

Sections 3 & 4

## 3.4 Scantlings

3.4.1 The section modulus of side stringers is to be not less than:

$$Z = 10b h_1 S_1^2 k \text{ cm}^3.$$

3.4.2 The net sectional area of the web at any section is to be not less than:

$$A = 0,12Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where  $Q_x$  is calculated from a shear force diagram constructed using the shear force at the span point,  $Q_1$  given by the following:

$$Q_1 = 5,03s h_1 S_1 \text{ kN}$$

$$(Q_1 = 0,513s h_1 S_1 \text{ tonne-f}).$$

3.4.3 The moment of inertia of the stringer is to be not less than:

$$I = S_1 Z \frac{7,5}{k} \text{ cm}^4.$$

3.4.4 Where side transverses supporting side stringers are fitted, they are to have a section modulus not less than that required by 2.7. Where the side transverse does not support side stringers, the section modulus required by 2.7 may be reduced by 20 per cent.

$Q_x$  = shear force at the actual section under consideration, obtained from shear force diagrams constructed as indicated, in kN (tonne-f).

4.2.2 Other symbols are defined in Ch 9, 1.6.

## 4.3 Structural arrangements

4.3.1 Where horizontal girders and vertical webs do not form part of a ring structure, they are to be arranged with substantial end brackets forming a buttress extending to the adjacent vertical web or transverse.

4.3.2 Where the cross-ties are omitted from the transverse ring in the wing tank adjacent to the bulkhead, the design of the horizontal girder, of the end buttress and of the transverse is to take account of the loads imposed and the deflection of the structure.

4.3.3 The spacing of transverses on longitudinal bulkheads is not to exceed 3,6 m.

4.3.4 Where, on ships with transverse side framing, transverses are required by Section 3, vertical webs are also to be fitted in line on the longitudinal bulkhead. Where such vertical webs are not required the lower horizontal girder on the bulkhead is to be suitably buttressed from the bottom transverses.

## 4.4 Scantlings

4.4.1 The scantlings of vertical webs on longitudinal bulkheads are to be as required for side transverses by Section 2.

4.4.2 The section modulus of vertical webs on transverse bulkheads and of horizontal girders is to be not less than:

$$Z = 8b h l_e^2 k \text{ cm}^3.$$

4.4.3 The net sectional area of the web at any section is to be not less than:

$$A = 0,12Q_x k \text{ cm}^2$$

$$\left( A = \frac{Q_x k}{0,85} \text{ cm}^2 \right)$$

where  $Q_x$  is the shear force at the section. For the horizontal girders on ships with two longitudinal bulkheads,  $Q_x$  is calculated from shear force diagrams as shown in Fig. 10.4.1. For end connections,  $Q_x$  is to be determined by projection of the shear force diagrams as indicated.

4.4.4 The moment of inertia of vertical webs and horizontal girders is to be not less than:

$$I = \frac{10,5}{k} l_e Z \text{ cm}^4.$$

4.4.5 For the calculation of section modulus, the minimum span of horizontal girders on longitudinal bulkheads is to be taken as not less than the lesser of  $(1,2 + 0,02L)$  m or 3 m.

## Section 4 Primary members supporting oiltight bulkheads

### 4.1 General

4.1.1 These requirements are applicable to ships having two longitudinal bulkheads, and to ships not exceeding 75 m in length having one longitudinal bulkhead located on the centreline of the ship.

4.1.2 The minimum thickness and construction detail requirements of Section 7 are to be complied with. Particular attention is to be paid to the design of end connections between primary members and buttresses. Where considered necessary, the shear and combined stresses in the connections may require to be examined and the scantlings and stiffening increased.

### 4.2 Symbols

4.2.1 The symbols used in this Section are defined as follows:

$h$  = the distance from the centre of the load on the member to a point 2,45 m above the highest point of the tank, excluding the hatchway, in metres




Fig. 10.4.1 Horizontal girders

4.4.6 Where a trunk is fitted, the scantlings of primary members are to be modified as required by Section 6.

## Section 5 Primary members supporting non-oiltight bulkheads

### 5.1 General

5.1.1 These requirements are applicable to primary members supporting non-oiltight transverse bulkheads. Where non-oiltight longitudinal bulkheads are proposed, the requirements for the primary members will be individually considered.

5.1.2 The minimum thickness and constructional detail requirements of Section 7 are to be complied with.

### 5.2 Symbols

5.2.1 The symbol,  $l_b$ , used in this Section is defined as follows:

$l_b$  = the distance, in metres, between the transverse bulkheads (oiltight or non-oiltight) adjacent to the bulkhead under consideration.

5.2.2 Other symbols are defined in Ch 9, 1.6.

### 5.3 Direct calculations

5.3.1 Direct calculation procedures will generally be required where the non-oiltight bulkhead primary members will interact with, or tend to support, the primary bottom, longitudinal bulkhead or side structure, and in other cases where warranted by structural design features.

### 5.4 Scantlings and arrangements

5.4.1 The section modulus of vertical webs is to be not less than that required for a vertical web on an oiltight transverse bulkhead in the same position, see Section 4

multiplied by the factor  $\left(0,3 + 2 \frac{l_b}{L}\right)$ .

5.4.2 The section modulus of horizontal girders is to be not less than:

$$Z = 145 k b l_e^2 \frac{l_b}{L} \text{ cm}^3.$$

5.4.3 When determining the width of plating supported and the effective breadth for calculating the section modulus, no deduction is to be made on account of perforations.

## Section 6 Trunked construction

### 6.1 General

6.1.1 The requirements of this Section are additional to those of Sections 1 to 5.

6.1.2 Where a trunk is fitted it is to extend over the full length of the cargo tanks and is to be effectively scarfed into the main hull structure.

6.1.3 The minimum thickness and constructional detail requirements of Section 7 are also to be complied with.

### 6.2 Symbols

6.2.1 The symbols used in this Section are defined as follows:

$b_t$  = breadth of trunk, in metres

$h_t$  = height of trunk, in metres, above the deck at the trunk side. Where the trunk top has excess camber, the value of  $h_t$  will be considered.

$D_1$  = equivalent depth of ship and is to be taken as:

$$D + 0,6 \frac{b_t h_t}{B} \text{ where } \frac{b_t}{B} \leq 0,8 \text{ and}$$

$$D + h_t \left(2,6 \frac{b_t}{B} - 1,6\right), \text{ where } \frac{b_t}{B} > 0,8$$


(see Fig. 10.6.1).

6.2.2 Other symbols are defined in Ch 9, 1.6.

# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 6



**Fig. 10.6.1** Equivalent depth

## 6.3 Structural arrangements

6.3.1 The trunk deck and sides are to be longitudinally framed, and the transverse primary members are to be aligned with the deck transverses.

6.3.2 Particular attention is to be given to the arrangements in way of the connection of the trunk side to the deck at side. The construction is to be such as to ensure adequate rigidity and continuity of strength.

6.3.3 Typical arrangements of primary structure are shown diagrammatically in Fig. 10.6.2, which also indicates the effective spans to be used in the determination of scantlings.

6.3.4 Where the trunk primary stiffening is fitted externally, individual consideration will be given to the arrangement and scantlings.

6.3.5 Where longitudinal stiffening is fitted externally to the trunk, tripping brackets are to be fitted to maintain lateral stability in way of transverse bulkheads and elsewhere as necessary.

6.3.6 Extension brackets and web stiffeners or equivalent arrangements are to be provided at the forward and after ends of the trunk to ensure full continuity of strength from the trunk into hull and superstructures.


6.3.7 Where the carriage of heated cargoes is contemplated and, in particular, bituminous cargoes, special attention is to be given to the alignment of the scarfing arrangements and softening of the extension bracket toes at the trunk ends to alleviate the effects of thermal stressing.

## 6.4 Trunk scantlings

6.4.1 The thickness of the trunk top and side plating is to be not less than as required by Ch 9,4 for hull envelope plating, the item numbers for these being as given in Fig. 10.6.3.

6.4.2 The section modulus of trunk longitudinals is to be not less than as required by Ch 9,5 for deck longitudinals.

6.4.3 The section modulus and moment of inertia of the transverses is to be not less than as required by 2.8 for deck transverses.



**Fig. 10.6.2** Primary structure

## 6.5 Modification to hull scantlings


6.5.1 The thickness of the deck plating outboard of the trunk side is to be that necessary to obtain the required hull section modulus, but is to be not less than that required by Ch 9,4 multiplied by the factor

$$\frac{2BD}{2BD + b_t h_t}$$

6.5.2 The scantlings of the shell plating, framing, primary structure and bulkheads are to be determined on the basis of the equivalent ship depth  $D_1$ , i.e. where the depth,  $D$ , enters into the calculation or structural arrangement it is to be replaced by  $D_1$ .

6.5.3 The head to the deck at side is to be increased by  $(D_1 - D)$ .

6.5.4 The head to the highest point of the tank is to be replaced by the actual distance to the highest point of the tank, reduced by the amount  $(D + h_t - D_1)$ .



7.3.3 The geometric properties of rolled stiffeners and built sections are to be calculated in association with an effective width of attached plating in accordance with Pt 3, Ch 3.3.


## 7.4 Continuity of primary members

7.4.1 Primary members are to be so arranged as to ensure effective continuity of strength throughout the range of tank structure. Abrupt changes of depth or section are to be avoided. Where members abut on both sides of a bulkhead or on other members, arrangements are to be made to ensure that they are in alignment.

7.4.2 The members are to have adequate end fixity, lateral support and web stiffening, and the structure is to be arranged to minimize hard spots or other sources of stress concentration. Openings are to have well rounded corners and smooth edges and are to be located having regard to the stress distribution and buckling strength of the plate panel.

## 7.5 Primary member web plate stiffening

7.5.1 The webs of primary members are to be supported and stiffened in accordance with the following requirements, which are designated as requirements 'A', 'B', 'C' and 'D'. The application of these requirements is detailed in 7.5, and the corresponding locations indicated in Fig. 10.7.1. Where webs are slotted for the passage of secondary members, the web stiffeners are to be arranged to provide adequate support for the loads transmitted, see Pt 3, Ch 10.5.2.



## Section 7

## Construction details and minimum thickness

### 7.1 Symbols

7.1.1 The symbols used in this Section are defined in Ch 9, 10.1.

### 7.2 Compartment minimum thickness

7.2.1 The requirements of Ch 9, 10.2 are also applicable to small conventional single hull tankers.

### 7.3 Geometric properties and proportions of members

7.3.1 The depth of the web of any primary member is to be not less than 2.5 times the depth of the cut-outs for the passage of secondary members, except where compensation is arranged to provide satisfactory resistance to deflection and shear buckling in the web.

7.3.2 The area of material in the face plate of any primary member is not to exceed:

$$0,00667d_w t_w \text{ cm}^2$$

nor is it to be less than:

$$0,0167s_t d_w \text{ cm}^2 \text{ for the bottom centreline girder}$$

$$0,00417s_t d_w \text{ cm}^2 \text{ elsewhere.}$$



# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 7

7.5.2 Where higher tensile steel is used for the primary members, the maximum spacing of stiffeners given in this Section is to be multiplied by  $\sqrt{k}$ .

7.5.3 In addition to these stiffeners, tripping brackets as required by Ch 9,10.11 are also to be fitted.

7.5.4 For requirement 'A' stiffening:

(a) The thickness,  $t_w$  of the web is to be not less than  $\frac{s}{80}$

(b) Stiffening is generally to be fitted normal to the face plate of the member, but the stiffeners parallel to the face plate will be required when the web depth,  $d_w$ , exceeds a value,  $d_{max}$  which is to be taken as:

$$\text{for } s \leq 55t_w \quad d_{max} = 3s$$

$$\text{for } s > 55t_w \quad d_{max} = \frac{45s t_w}{s - 40t_w}$$

(c) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $65t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the shell or bulkhead plating does not exceed  $d_{max}$ . In way of end brackets to transverse bulkhead primary structure, stiffeners are to be fitted normal to the face plate of the member so that web plate panel dimensions parallel to the face plate do not exceed  $80t_w$ .

7.5.5 For requirement 'B' stiffening:

(a) The thickness,  $t_w$  of the web is to be not less than  $\frac{s}{85}$

(b) Stiffening is generally to be fitted normal to the face plate of the member, but stiffeners parallel to the face plate will be required when the web depth,  $d_w$ , exceeds a value  $d_{max}$ , which is to be taken as:

$$\text{for } s \leq 70t_w \quad d_{max} = 3s$$

$$\text{for } s > 70t_w \quad d_{max} = \frac{48s t_w}{s - 54t_w}$$

(c) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $80t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the shell or bulkhead plating does not exceed  $d_{max}$ .

7.5.6 For requirement 'C' stiffening:

(a) Stiffening is generally to be fitted normal to the face plate of the member in line with alternate secondary members, but stiffeners parallel to the face plate will be required, when the web depth,  $d_w$  exceeds a value,  $d_{max}$  which is to be taken as:

$$\text{for } s \leq 76t_w \quad d_{max} = 3s$$

$$\text{for } s > 76t_w \quad d_{max} = \frac{48s t_w}{s - 60t_w}$$

(b) Where stiffening parallel to the face plate is required, the distance from the face plate of the member to the nearest stiffener is not to exceed  $90t_w$ . Further stiffeners are to be fitted at similar spacing so that the distance between the last stiffener and the deck plating does not exceed  $d_{max}$ .

7.5.7 For requirement 'D' stiffening:

(a) Stiffening parallel to the face plate will be required such that the distance between the stiffener and face plate, or between two stiffeners, does not exceed:

$$80t_w \text{ where } L \leq 90 \text{ m}$$

$$55t_w \text{ where } L \geq 190 \text{ m}$$

with intermediate values by interpolation.

(b) Brackets are to be fitted to support the face plates and stiffeners.

## 7.6 Inertia and dimensions of stiffeners

7.6.1 The moment of inertia is to be not less than:

(a) For stiffeners normal to the primary member face plate:

$$I_s = p s t_w^3 \times 10^{-4} \text{ cm}^4$$

Where  $t_w$  need not be greater than the values in Table 10.7.1 and  $p$  is to be obtained from Table 10.7.2.

(b) For stiffeners parallel to the primary member face plate: On transverses, webs and stringers

$$I_s = 2I_s^2 A_s \text{ cm}^4$$

On longitudinal deck and bottom girders

$$I_s = 2,85I_s^2 A_s \text{ cm}^4.$$

**Table 10.7.1 Maximum web thickness for stiffener inertia**

Requirement	Web thickness $t_w$ , in mm
'A'	$\frac{s}{55}$
'B' and 'C'	$\frac{s}{70}$
'D'	$\frac{s}{80}$ where $L \leq 90 \text{ m}$ $\frac{s}{60}$ where $L \geq 190 \text{ m}$
NOTE Intermediate values by interpolation.	

7.6.2 Where stiffeners are fitted in both directions, the inertia of the stiffeners parallel to the face plate of the member is to be not less than that of the stiffeners fitted normally.

7.6.3 The depth of web stiffeners is to be not less than 75 mm.

7.6.4 Where flat bar stiffeners are used, the ratio of depth to thickness is not to exceed  $18\sqrt{k}$ .

# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 7

**Table 10.7.2 Coefficient for stiffener inertia**

Aspect ratio of plate panel, $\frac{s}{d}$	1,0 or more	0,9	0,8	0,7	0,6	0,5	0,4	0,3 or less
$\rho$	1,5	2,1	2,9	4,2	6,1	9,2	14,6	30,0

NOTES

- Intermediate values by interpolation.
- The depth of panel,  $d$ , used in calculating aspect ratio may be measured from the face of the secondary member to which the primary member web stiffener is attached.

## 7.7 Application of stiffening requirements

7.7.1 The requirements as detailed in 7.5 and 7.6 are to be applied in the following locations, see also Fig. 10.7.1.

- For bottom transverses:  
In the centre tank requirement 'A' stiffening is to extend for 20 per cent of the breadth of the tank from the longitudinal bulkhead, but at least beyond the toe of the end bracket. In the wing tank, requirement 'A' stiffening is to extend at least as far as the toes of the end brackets from the longitudinal bulkhead and the shell. Elsewhere, requirement 'B' stiffening is to be fitted.
- For transverses at side shell and longitudinal bulkhead:  
Requirement 'A' stiffening is to extend at least as far as the lower surface of the lower cross-tie. Elsewhere, requirement 'B' stiffening is to be fitted.
- For deck transverses:  
Requirement 'C' stiffening is to be fitted.
- For stringers and horizontal girders:  
Requirement 'A' stiffening is to extend for a distance from each end of 20 per cent of the span of the stringer or girder, but at least beyond the toes of the end brackets. Elsewhere, requirement 'B' stiffening is to be fitted.
- For cross-ties:  
Cross-ties are to be suitably stiffened to prevent buckling and twisting. Requirement 'D' stiffening is to be fitted.
- For shell stringers and vertical webs in fore peak:  
Requirement 'A' stiffening is to extend the full length of the member.

7.7.2 The application of stiffening requirements to transverse wing structures in wing tanks where no cross-ties are fitted is to be based on the results of direct calculation and will be specially considered.

## 7.8 Stiffening of continuous longitudinal girders

7.8.1 The webs of continuous longitudinal deck and bottom girders are to be stiffened parallel to the girder face plate.

7.8.2 The stiffeners are to be spaced not more than  $55t_w$  mm apart except in way of vertical webs and end brackets, where the spacing is not to exceed  $45t_w$  mm. Alternatively, a combination of parallel stiffeners at  $55t_w$  mm spacing and normal stiffeners at  $45t_w$  mm spacing may be adopted. Particular attention is to be given to the stiffening of the docking girder.

7.8.3 The moment of inertia of stiffeners is to comply with 7.6.

## 7.9 Stiffening of vertical webs on transverse bulkheads

7.9.1 Vertical webs are to be fitted with stiffeners parallel to the face plate of the web and spaced not more than  $60t_w$  mm apart. Stiffeners normal to the face plate are to be fitted when a vertical web supports horizontal stiffeners on transverse bulkheads. The length of stiffener is to be sufficient to distribute the load transmitted, and the connection between web stiffener and bulkhead stiffener is to comply with the relevant requirements of Pt 3, Ch 10,5.2.

7.9.2 The moment of inertia of the stiffeners is to comply with 7.6.

## 7.10 Docking brackets on bottom centreline girder

7.10.1 Stiffened docking brackets are to be fitted on both sides of the bottom centreline girder, midway between transverses, and are to be connected to a suitable bottom shell longitudinal. The bracket on one side is to be connected to the face plate of the girder but the other may be stopped at a suitable horizontal stiffener.

7.10.2 Additional vertical stiffeners may be required on the bottom panels of the girder to resist docking pressures.

## 7.11 Lateral stability of primary members

7.11.1 Tripping brackets are generally to be fitted close to the toes of end brackets, in way of cross-ties and elsewhere, so that the spacing between brackets does not exceed the lesser of 4,5 m or 15 times the width of the face plate (20 times in the case of deck transverses). Arrangements in way of the intersections of primary members are to be such as to prevent tripping. A closer spacing of brackets may be required to be adopted with asymmetrical face plates.

7.11.2 To maintain continuity of strength, substantial horizontal and vertical brackets are to be fitted to transverses or stringers at ends of cross-ties. Horizontal brackets are to be aligned with the cross-tie face plates, and vertical end brackets are to be aligned with the cross-tie web.

# Single Hull Oil Tankers

# Part 4, Chapter 10

Section 7

7.11.3 Tripping brackets are to be connected to the face plate of the bottom transverses. Elsewhere, other than for docking girders, the bracket is to be connected to the face plate whenever the unsupported width of the latter exceeds 150 mm. Where the width of symmetrically placed face plates exceeds 400 mm, a small bracket is to be fitted opposite, and in line with, the tripping bracket. Equivalent support arrangements are to be provided for cross-tie face plates. Particular attention is to be paid to the support of continuous face plates in way of the radius at toes of brackets.

7.11.4 Wide face plates may require additional support between brackets.

7.11.5 In the fore peak tank, if the angle to the normal of the shell plating and the vertical webs exceeds 20°, double tripping brackets are to be fitted to the web at about midspan, but in no case greater than 3,0 m apart.

## 7.12 Openings in web plating

7.12.1 Where openings are cut in the webs of primary supporting members, the greatest dimension of the opening is not to exceed 20 per cent of the web depth. The opening is to be located so that the edges are not less than 40 per cent of the web depth from the face, and are equidistant from the corners of notches for frames or stiffeners. Openings are to be suitably framed where required.

7.12.2 Lightening holes are not to be cut in horizontal girders on the ship's side and longitudinal bulkheads, in symmetrical webs nor in side transverses and vertical webs in way of cross-ties and their end connections.

7.12.3 Holes cut in primary longitudinal members within 0,1D of the deck and bottom are, in general, to be reinforced as required by Ch 9,4.10. Access holes may be cut in deep transverses and girders with suitable compensation to provide satisfactory resistance to deflection and shear buckling in the web.

7.12.4 All holes are to have smooth edges and are to be kept well clear of notches and the toes of brackets.

7.12.5 Small air and drain holes cut in primary members are to be kept clear of the toes of brackets and are to be well rounded with smooth edges. Where holes are cut in primary longitudinal members of higher tensile steel, they are to be elliptical or equivalent to minimize stress concentration.

7.12.6 Where holes are cut for heating coils, the lower edge of the hole is to be not less than 100 mm from the inside of the shell plating. Where large notches are cut in the transverses for the passage of longitudinal framing, adjacent to openings for heating coils, the longitudinal notches are to be collared. Examination of the buckling strength of the web plate panel between notches for longitudinals may be required.

## 7.13 Brackets connecting primary members

7.13.1 The requirements of Ch 9,10.13 are also applicable to small conventional single hull tankers.

## 7.14 Arrangements at intersections of continuous secondary and primary members

7.14.1 For details and connections of collars, see Pt 3, Ch 10,5.2.



# Ore Carriers

## Part 4, Chapter 11

Section 1

## Section

- 1 **General**
- 2 **Materials and protection**
- 3 **Longitudinal strength**
- 4 **Hull envelope plating**
- 5 **Hull framing**
- 6 **Double bottom construction**
- 7 **Longitudinal bulkheads**
- 8 **Transverse bulkheads**
- 9 **Primary structure in wing tanks**
- 10 **Direct calculations**
- 11 **Forecastles**

### ■ Section 1 General

#### 1.1 Application

1.1.1 This Chapter applies to the arrangements and scantlings within the cargo region of sea-going ore carriers, intended for the carriage of ore in centre holds.

1.1.2 The requirements of Chapter 9 are to be applied to ore carriers, except as required by the provisions of this Chapter.

1.1.3 The scantlings of structural items may be determined by direct calculation. Where the length of the ship exceeds 150 m, certain scantlings will be required to be assessed by direct calculation. In such cases, the calculations are to be submitted for approval.

1.1.4 The additional requirements for ore-carriers for the alternate carriage of oil cargo and dry bulk cargo are given in Pt 4, Ch 9,11.

#### 1.2 Structural configuration and ship arrangement

1.2.1 The requirements contained in the Chapter apply to single deck ships with machinery aft, having two longitudinal bulkheads and a double bottom throughout the centre hold. A typical cross section is indicated in Fig. 11.1.1.




Fig. 11.1.1 Typical cross section

1.2.2 The bottom, and the deck outside the line of ore hatchways, are to be framed longitudinally within the cargo region. The side shell and longitudinal bulkheads are generally to be framed longitudinally where the length of the ship exceeds 150 m, but alternative proposals will be specially considered. Inside the line of openings, the deck is to be transversely framed.

#### 1.3 Class notation

1.3.1 Sea-going ships complying with the requirements of this Chapter and other relevant Rule requirements for the draught required, will be eligible to be classed **100A1 ore carrier, ESP**.

1.3.2 The notation **ESP** serves to identify the ship as being subject to an Enhanced Survey Programme as detailed in Pt 1, Ch 3,3 and Ch 3,6, see also Pt 1, Ch 2,2.3.12.

1.3.3 The Regulations for classification and the assignment of class notations are given in Pt 1, Ch 2,2.

#### 1.4 Symbols and definitions

1.4.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

$L, B, D, T$  as defined in Pt 3, Ch 1,6.

$b$  = the width of plating supported by the primary member, in metres or mm

$h$  = the load head, in metres, applied to the item under consideration

$k$  = higher tensile steel factor. For the determination of this factor, see Pt 3, Ch 2,1. For mild steel  $k$  may be taken as 1,0

$l_e$  = effective length of primary or secondary member, in metres, see Pt 3, Ch 3,3

$s$  = spacing, in mm, of secondary members

$Z$  = the section modulus, in  $\text{cm}^3$ , of the primary or secondary member, in association with an effective width of attached plating determined in accordance with Pt 3, Ch 3,3.

# Ore Carriers

# Part 4, Chapter 11

Sections 1 to 5

1.4.2 The expression 'primary member' as used in this Chapter is defined as a girder, transverse, vertical web, stringer, cross tie, buttress or double bottom floor. 'Secondary members' are supporting members other than primary members.

## Section 2 Materials and protection

### 2.1 Materials and grades of steel

2.1.1 Materials and grades of steel are to comply with the requirements of Pt 3, Ch 2.

### 2.2 Corrosion protection coating for salt water ballast spaces

2.2.1 The requirements of Pt 3, Ch 2,3.6 are to be complied with.

## Section 3 Longitudinal strength

### 3.1 General

3.1.1 The longitudinal strength standard is to comply with the relevant requirements of Pt 3, Ch 4.

## Section 4 Hull envelope plating

### 4.1 General

4.1.1 The requirements for hull envelope plating as given for oil tankers in Ch 9,4 are to be applied, except as provided for in this Section.

### 4.2 Deck plating in way of ore hatchways

4.2.1 The arrangement and scantlings of deck plating inside the line of ore hatchways and in way of ore hatchway corners are to be in accordance with the requirements for bulk carriers given in Ch 7,4.

### 4.3 Hatchways

4.3.1 The scantlings of the cargo hold hatch coamings are to comply with Pt 3, Ch 11,5 and the cargo hold hatch covers with Pt 3, Ch 11,2 and Pt 4, Ch 7,12.

### 4.4 Hatch coamings

4.4.1 The height and construction of hatch coamings are to comply with Pt 3, Ch 11,5 and Pt 4, Ch 7,13.

## Section 5 Hull framing

### 5.1 General

5.1.1 The framing requirements given for oil tankers in Ch 9,5 are to be applied, except as provided for in this Section.

### 5.2 Symbols

5.2.1 The symbols used in this Section are defined as follows:

$h$  = load height, in metres, on the weather deck for primary and secondary members between ore hatchways  
 = 1,8 for secondary members forward of 0,075L from F.P.  
 = 4,2 + 2,04E for primary members forward of 0,075L from F.P.  
 = 1,5 between 0,075L and 0,12L from F.P.  
 = 1,2 + 2,04E elsewhere

where

$E = \frac{0,0914 + 0,003L}{D - T} - 0,15$  but not to be greater than 0,147

$K_1 = 1,6$  in the forward 0,12L  
 = 1,06 elsewhere

$K_2 = 0,00054$  in the forward 0,075L  
 = 0,00033 elsewhere.

5.2.2 Other symbols are defined in 1.4.

### 5.3 Bottom longitudinals in double bottom tanks

5.3.1 The section modulus of bottom longitudinals in the double bottom in the centre hold is to satisfy the requirements of Table 1.6.1 in Chapter 1.

5.3.2 In general, the span of longitudinals in the double bottom in the centre hold is not to exceed 2,5 m or 0,01L, whichever is the greater, and the span in the wing tanks is not to exceed the greater of 3,6 m or 0,02L.

### 5.4 Deck structure in way of centre hold

5.4.1 Where the hatch coamings are situated inboard of the longitudinal bulkhead, the deck between the two is to be fitted with suitably supported longitudinals complying with Ch 9,5.

# Ore Carriers

# Part 4, Chapter 11

Sections 5 to 8

## 5.5 Primary and secondary members inside line of ore hatchways

5.5.1 The section modulus of secondary members between hatches is to be not less than:

$$Z = k (K_1 T D + K_2 h B I_e^2 s) \text{ cm}^3$$

but need not exceed twice the value given by the second term within the brackets in the formula.

5.5.2 The section modulus of primary members between hatches is to be not less than:

$$Z = 5,46k b h I_e^2 \text{ cm}^3$$

Forward of 0,075L from the forward perpendicular, the depth of the primary member is to be not less than twice that of the secondary member supported.

5.5.3 Particular attention is to be paid to the scarfing of deck beams into the structure outside the line of openings. Substantial brackets or equivalent arrangements are to be provided.

## Section 6 Double bottom construction

### 6.1 General

6.1.1 The double bottom depth and scantlings are to be as required by Ch 7,8 for the double bottom structure of a bulk carrier to which the notation 'strengthened for heavy cargoes' is to be assigned. The required depth of double bottom and scantlings of double bottom structure are, however, to be verified by direct calculation. The calculation is to be submitted.

6.1.2 Where the proposed depth of double bottom exceeds 1,5 times the Rule minimum depth given in Ch 1,8, the scantlings of the floors and girders may be required to be increased to ensure adequate resistance to buckling.

6.1.3 The thickness of inner bottom plating in the cargo hold is to be not less than required by Ch 7,8 for ships having the notation 'strengthened for heavy cargoes'. The requirements of Ch 7,8.1 relating to discharge by grabs are to be applied.

### 6.2 Arrangement

6.2.1 In way of the cargo hold a centreline girder is to be fitted and side girders spaced not more than 3,8 m apart are generally to be arranged in way of transverse bulkheads. The side girders are to extend at least to the first plate floor adjacent to the bulkhead each side. The outboard side girder is to be continuous, forming the lower part of the longitudinal bulkhead.

6.2.2 Plate floors are to be fitted in line with each transverse in the wing tanks and in way of transverse bulkhead stools. Additional floors are to be so arranged that the spacing of floors does not exceed 2,5 m or 0,01L, whichever is the greater.

6.2.3 Attention is to be given to structural continuity and alignment between double bottom structure and transverses in wing tanks, see also 9.2.

6.2.4 Alternative arrangements will be considered on the basis of the results of direct calculations.

## Section 7 Longitudinal bulkheads

### 7.1 General

7.1.1 The requirements for longitudinal oiltight bulkheads given in Ch 9,6 and Ch 9,9 are to be applied, together with the additional requirements of this Section.

7.1.2 Longitudinal bulkheads on ore carriers are to be plane with rolled or fabricated longitudinal stiffeners. The bulkhead may be sloped to form a hopper shape in the lower part of the hold or over its full depth.

7.1.3 Where the upper part of the bulkhead is vertical and the lower part sloped to form a hopper shape, the thickness of the bulkhead plating in way of the knuckle may be required to be increased to resist transverse compressive buckling stresses. The knuckle is to be arranged in way of a longitudinal.

7.1.4 The thickness of the lowest strake of sloped bulkhead plating is also to comply with inner bottom requirements as given in 6.1.3. Where this provision results in an increase in thickness, the latter may be gradually tapered above the lowest strake to the required longitudinal bulkhead thickness at the position of the knuckle, or at a point one-third of the depth of the bulkhead above the inner bottom, whichever is the lower.

## Section 8 Transverse bulkheads

### 8.1 General

8.1.1 Where the form of construction used for transverse bulkheads in wing tanks is different from that used in centre holds, arrangements are to be made to ensure continuity of transverse strength through the longitudinal bulkhead.

# Ore Carriers

# Part 4, Chapter 11

Sections 8 to 11

## 8.2 Transverse watertight bulkheads in wing tanks

8.2.1 The requirements for transverse bulkhead plating, stiffening and primary structure given in Ch 1,9 for deep tank bulkheads are to be applied.

## 8.3 Transverse watertight bulkheads in centre holds

8.3.1 The requirements for transverse hold bulkheads given for the carriage of dry bulk cargoes in Ch 7,10 are to be applied.

8.3.2 In general, the bulkheads are to have stiffening or corrugations arranged vertically, supported by top and bottom end stools. Alternative arrangements will, however, be considered.

## 8.4 Non-watertight bulkheads

8.4.1 Non-watertight bulkheads in wing tanks are to comply with the requirements given in Ch 9,8 and Ch 9,9.8.

8.4.2 The bulkhead plating is to be suitably reinforced in way of double bottom scarfing arrangements and the ends of centre hold deck transverses. Openings in wing tank bulkheads are to be kept clear of these areas.

## Section 9 Primary structure in wing tanks

### 9.1 General

9.1.1 The primary structure in the wing tanks is to comply with the requirements given in Ch 9,9.

### 9.2 Scarfing of double bottom

9.2.1 The inner bottom plating is to be extended into the wing tank in the form of a horizontal diaphragm, arranged to ensure a smooth structural transition in way of transverse primary members and to maintain longitudinal continuity. The diaphragms are to be of sufficient width to provide effective scarfing of the inner bottom into the wing tank structure.

9.2.2 Floors intermediate between transverses are to be backed in the wing tanks by substantial vertical brackets extending transversely over at least three bottom longitudinal spaces and vertically to a sufficient height above the horizontal diaphragms to provide effective support for the double bottom structure.

## Section 10 Direct calculations

### 10.1 Application

10.1.1 Direct calculations are to be employed in the derivation of scantlings where required by the preceding Sections of this Chapter or by related provisions included in Part 3.

10.1.2 Direct calculation methods are also generally to be used where additional calculations are required by the Rules in respect of unusual arrangements.

10.1.3 For complex structural arrangements, e.g. a double plate transverse bulkhead with stool in a centre hold, associated with plane wing tank bulkheads supported by stringers and buttresses, an investigation of bottom primary structure over a full cargo hold length and three-dimensional analysis of the transverse bulkhead structure will generally be required, taking account of applied longitudinal hull bending effects.

10.1.4 The cross-deck structure is to be verified as being capable of supporting transverse compressive stresses resulting from lightship weight, cargo weight and inertia, hydrostatic and wave loads. The cross-deck structure is to comprise the hatch coamings and beams, the plating and attached stiffeners and the upper stool. Non-corrugated bulkhead plating may also be included.

### 10.2 Procedures

10.2.1 For details of Lloyd's Register's (hereinafter referred to as LR) direct calculation procedures, see Pt 3, Ch 1,2. For requirements concerning use of other calculation procedures, see Pt 3, Ch 1,3.

10.2.2 Where appropriate to the structural configuration, the direct calculation procedures for tanker primary structure, see Ch 9,14, will be adapted for application to ore carriers.

## Section 11 Forecastles

### 11.1 General

11.1.1 A forecastle is to be fitted in accordance with the requirements of Pt 4, Ch 7,14.



# Dredging and Reclamation Craft

# Part 4, Chapter 12

Section 1

## Section

- 1 **General**
- 2 **Longitudinal strength**
- 3 **Deck structure**
- 4 **Shell envelope plating**
- 5 **Shell envelope framing**
- 6 **Bottom structure**
- 7 **Bottom strengthening for operating aground**
- 8 **Spoil space and well structure**
- 9 **Watertight bulkheads**
- 10 **Exposed casings**
- 11 **Dredging machinery seats and dredging gear**
- 12 **Ladder wells**
- 13 **Fenders**
- 14 **Rudders**
- 15 **Spoil space weirs and overflows**
- 16 **Scuppers and sanitary discharges and side scuttles**
- 17 **Split hopper dredgers and barges**
- 18 **Direct calculations**

- suction pipes or similar gear are not to be regarded as hoppers unless adequate bottom doors or valves are also fitted.
- (c) Split hopper dredgers, which are designed similarly to that described in (b) but arranged such that the spoil is discharged through the bottom of the ship by means of the split hull being separated using hinges and actuating devices.
- (d) Reclamation craft, reclamation ships, etc., which work in a manner similar to dredgers but draw their spoil from dredging craft and discharge it ashore.
- (e) Hopper barges designed to carry spoil or dredged material in hoppers within the ship. For the definition of a hopper, see 1.1.1(b).
- (f) Split hopper barges, which are designed similarly to that described in (e) but arranged such that the spoil is discharged through the bottom of the ship by means of the split hull being separated using hinges and actuating devices.

1.1.2 The scantlings and arrangements are to be as required by Chapter 1, except as otherwise specified in this Chapter.

1.1.3 Where bottom dump doors or valves are fitted, hatch covers are not required. Proposals for the omission of hatch covers where bottom dump doors or valves are not fitted will be specially considered.

1.1.4 Ships which have their machinery placed on a shallow raft, rather than within a hull, will have their scantlings specially considered. Dredgers which resemble drilling rigs, or similar offshore structures, in their design or mode of operation will be considered under the Rules for such structures.

1.1.5 Ships of unusual form or proportions, or intended for unusual dredging methods, will receive individual consideration on the basis of the general standards of the Rules.

1.1.6 The requirements provide for transverse and longitudinal framing of the structure. In general, the midship region scantlings are to extend over the full length of hoppers and holds. The extent is to be not less than 0,4L amidships, and may need to be increased if the design and loading conditions of a particular ship result in its maximum bending moment occurring other than at amidships.

## ■ Section 1 General

### 1.1 Application

1.1.1 This Chapter applies, in general, to manned or unmanned self-propelled or non-self-propelled ships defined as follows:

- (a) Dredgers designed to operate wholly or generally for the purpose of raising spoil such as mud, silt, gravel, clay, sand or similar substances, general rubbish or ore, minerals, etc., for the bed of the sea, rivers, lakes, canals or harbours, etc. The dredged material may be placed in suitably designed holds or similar spaces within the ship.
- (b) Hopper dredgers, designed to raise spoil, as described in (a), and so arranged that the dredged material may be placed in one or more hoppers within the ship. For the purpose of this definition, a hopper is a hold or other space designed to carry dredged spoil and also arranged to enable such spoil to be discharged through doors or valves in the bottom of the ship. Spaces arranged to be unloaded by means of conveyor belts,

### 1.2 Stability

1.2.1 Attention is drawn to the thixotropic properties of certain types of dredged material which, as a result of the ship's motions, can cause the spoil to shift within spoil spaces, resulting in undesirable changes in trim or angles of heel. This can be particularly dangerous in ships with closed top spaces.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Section 1

## 1.3 Class notations

1.3.1 In general, ships complying with the requirements of this Chapter will be eligible for one of the following classes:

- (a) **100A1 dredger**. This class will be assigned to ships as defined in 1.1.1(a).
- (b) **100A1 hopper dredger**. This class will be assigned to ships as defined in 1.1.1(b).
- (c) **100A1 split hopper dredger**. This class will be assigned to ships as defined in 1.1.1(c).
- (d) **100A1 reclamation craft**. This class will be assigned to ships as defined in 1.1.1(d).
- (e) **100A1 hopper barge**. This class will be assigned to ships as defined in 1.1.1(e).
- (f) **100A1 split hopper barge**. This class will be assigned to ships as defined in 1.1.1(f).

1.3.2 These classes will be assigned to ships which are intended to make unrestricted sea-going voyages either as part of their work or while transferring from one work area to another as part of their normal operations. However, unrestricted sea-going service notations will not normally be assigned to bucket dredgers, nor to dredging and reclamation craft unless spoil spaces are provided with adequate hatch covers. Attention is drawn to the special requirements imposed by National Authorities involving loading limitations and stability requirements.

1.3.3 Ships intended to be operated only in suitable areas or conditions which have been agreed by the Committee, as defined in Pt 1, Ch 2,2.3.6, 2.3.7, 2.3.8 and 2.3.10, will receive individual consideration on the basis of the Rules with respect to the environmental conditions agreed for the design basis and approval. In particular, dredgers complying with the requirements of this Chapter, and Pt 3, Ch 13,7 for the reduced equipment requirements, will be eligible to be classed:

**A1 dredger protected waters service**, see Pt 1, Ch 2,2.3.6, or

**100A1 dredger with service restriction notation**, whichever is applicable. Hopper dredgers, split hopper dredgers, reclamation craft, hopper barges and split hopper barges would be considered similarly.

1.3.4 Where a ship complying with the requirements of this Chapter has the bottom structure additionally strengthened for operating aground in accordance with Section 7, it will be eligible for the special feature notation 'bottom strengthened for operating aground'.

1.3.5 In addition to the above notations, an appropriate descriptive note may be entered in the *Register Book* indicating the type of dredging or reclamation craft (see Pt 1, Ch 2,2.6.1), e.g. 'trailing suction dredger', 'cutter suction dredger', 'bucket dredger', 'grab dredger', 'dipper dredger', 'self-discharging sand dredger', etc.

1.3.6 The Regulations for classification and assignment of class notations are given in Pt 1, Ch 2 to which reference should be made.

## 1.4 Information required

1.4.1 In addition to the information and plans required by Pt 3, Ch 1,5 details of the following are to be submitted:

- Sections through hoppers, wells, pump-rooms and dredging machinery spaces.
- Hopper, hold and well bulkheads and associated weirs.
- Scarfing arrangements at hopper, hold and well ends.
- Hinges, actuating and locking arrangements, together with supporting structure, weld connection details and calculations of design forces for split hull separation devices.
- Deckhouse and deckhouse support structure.
- Outline arrangement and main scantlings of 'A' frames, gantries, positioning spuds, hopper doors and similar items, the strength and integrity of which directly affect the hull structure of the vessel. Support structure in way of 'A' frames, positioning spuds and other dredging structures. Seats of dredging machinery and pumps. If dredging equipment is stored during voyages, plans of any special arrangements for dismantling, storage and reassembly. Sufficient particulars of static and dynamic loading for these items are to accompany the details to enable verification of the strength and effectiveness of the supporting ship structure.
- A full set of stability data which is to be placed on board the ship, see Pt 1, Ch 2,3.
- Calculations of hull girder still water bending moment and shear force where applicable, see 2.1.1, for the proposed loading conditions, including densities of spoil. When the still water bending moment and block coefficient are being calculated, any water within spoil spaces should be regarded as added weight, whilst that in dredging ladder wells and spud wells should be regarded as lost buoyancy.

## 1.5 Symbols

1.5.1 The following symbols and definitions are applicable to this Chapter unless otherwise stated:

- $B$  = breadth, in metres, defined as the greatest moulded breadth excluding any localized bulge on the hull associated with the attachment or handling of the dredging gear
- $C_b$  = the moulded block coefficient at draught  $T$  but is to be taken as not less than 0.6. The block coefficient is to be determined using the length,  $L$ . Spoil spaces should be regarded as added weight, whilst dredging ladder wells and spud wells should be regarded as lost buoyancy
- $C_{bm}$  = the moulded block coefficient at the dredging draught  $T_m$ , but is to be taken as not less than 0.6. The block coefficient is to be determined using length,  $L$ . Spoil spaces should be regarded as added weight, whilst dredging ladder wells and spud wells should be regarded as lost buoyancy
- $D$  = moulded depth, in metres, to the uppermost continuous deck
- $L$  = Rule length, in metres, as defined in Pt 3, Ch 1,6 for ships classed for unrestricted service. For ships classed **A1 protected waters service** where the load waterline is not required to be determined by the International Load Line Convention method, the

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 1 & 2

length is to be measured on the deepest waterline at which the ship is designed to operate. On sea-going vessels with unusual stern arrangement, or with unusual bow arrangement associated with a dredging draught in excess of the summer load line draught, the length,  $L$ , will be specially considered

$M_s$  = design still water bending moment, in kNm (tonne-f m), at draught,  $T$ , or less

$\bar{M}_s$  = maximum permissible still water bending moment, in kNm (tonne-f m), at draught,  $T$ , or less

$M_{sm}$  = design still water bending moment, in kNm (tonne-f m), under dredging conditions at draught,  $T_m$

$\bar{M}_{sm}$  = maximum permissible still water bending moment, in kNm (tonne-f m), under dredging conditions at draught,  $T_m$

$M_w$  = design hull vertical wave bending moment amidships, in kN m (tonne f m), see 2.4.1

$T$  = summer draught, in metres, as established by the method described in the International Load Line Convention, measured from top of keel amidships

$T_m$  = maximum dredging draught, in metres, at which the ship is designed to operate. It is to be measured amidships from the top of keel and is to be taken not less than  $T$ , see 15.1.4

$\rho$  = relative density (specific gravity) which, in general, is to be taken not less than 1,86, or as derived from the stowage rate of spoil. This stowage rate of dredged spoil is to be determined from the maximum spoil weight at dredging draught and volume of spoil space up to the sill of the uppermost overflow weir. The value used in the calculations of scantlings is to be clearly marked on the relevant plans

Hogging bending moments are positive.

1.5.2 For symbols not defined in this Chapter, see Chapter 1.

## Section 2

## Longitudinal strength

### 2.1 General

2.1.1 Longitudinal strength calculations are to be made in accordance with the relevant requirements given in Pt 3, Ch 4, except as indicated in this Section.

### 2.2 Loading conditions

2.2.1 Details are to be submitted of the following loading conditions for examination of longitudinal strength:

- Homogeneous load conditions (including details of densities of spoil) for both departure and arrival at draught,  $T$ , and maximum dredging draught,  $T_m$ , where this exceeds  $T$ , see also 15.1.4.
- Part loaded conditions (including details of densities of spoil) and ballast conditions for both departure and arrival.
- Any specified non-homogeneous load conditions.

2.2.2 If any dredging equipment has to be unshipped, lowered or otherwise specially arranged or stowed before the ship proceeds on a sea-going voyage, this fact is to be indicated on the longitudinal strength information required to be submitted and is also to be clearly stated in the final Loading Manual supplied to the ship.

2.2.3 For loading conditions, and any other preparations required to permit ships with a notation specifying some service limitation to undertake a sea-going voyage, either from port or building to service area or from one service area to another, see Pt 1, Ch 2, 1.

2.2.4 Where a ship is arranged with two spoil spaces account is to be taken in the calculation of the still water bending moment of either one of these spaces being empty, unless such loading is specifically precluded in the Loading Manual supplied to the ship.

2.2.5 The requirements of Pt 3, Ch 4, 8.3 regarding loading instruments are not applicable to dredging and reclamation craft.

## 2.3 Hull bending strength

2.3.1 Hull bending strength standards are to comply with the relevant requirements of Pt 3, Ch 4, taking account of the contents of 2.4 and 2.5.

2.3.2 For split hopper dredgers or barges, due account is to be taken of the lateral forces and moments on each half hull which are exerted by the pressure of the spoil and dynamic wave loading, see 17.2.

## 2.4 Design vertical wave bending moments

2.4.1 The design vertical wave bending moment at amidships,  $M_w$ , is to be determined from Pt 3, Ch 4, 5.2 with the ship service factor,  $f_1$ , given in Table 12.2.1.

Table 12.2.1 Ship service factor  $f_1$

$f_1$		
'100A1'	'100A1 extended protected waters service'	'A1 protected water service'
0,75	0,70	0,65

2.4.2 The design hull vertical wave bending moment at amidships for dredging conditions,  $M_{wd}$ , where draught  $T_m$  exceeds  $T$ , is given by the following expression:

$$M_{wd} = 0,56f_2 M_{wo}$$

where

$M_{wo}$  is determined from Pt 3, Ch 4, 5.2, using  $C_{bm}$  in place of  $C_b$  and  $f_2$  is given in Pt 3, Ch 4, 5.2.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 2, 3 & 4

## 2.5 Permissible still water bending moment for dredging conditions

2.5.1 The maximum permissible still water bending moment,  $\bar{M}_{sm}$ , for dredging conditions where draught  $T_m$  exceeds  $T$  is not to exceed:

$$|\bar{M}_{sm}| = |\bar{M}_s + f_1 f_2 M_{wo} - M_{wd}| \quad \text{kN m (tonne-f m)}$$

where  $M_{wd}$  is defined in 2.4.2.

Where applicable, the relevant loading conditions are to be included in the final Loading Manual, see 15.1.4 and Pt 3, Ch 4.8.1.

## 2.6 Calculation of hull section modulus

2.6.1 The hull midship section modulus is to be calculated in accordance with the requirements of Pt 3, Ch 3.3.4 taking account of 2.6.2 and 2.6.3. See also 17.1 for split hull arrangements.

2.6.2 Centreline box keels within the hopper spaces may normally be regarded as 100 per cent effective provided that they are effectively scarfed to the vertical keels or equivalent structure at each end of the hopper spaces.

2.6.3 Where a long superstructure or deckhouse is fitted extending within the midship region, the requirements for longitudinal strength in the hull and erection will be specially considered.

## 2.7 Hull shear strength

2.7.1 Special attention is to be paid to the actual shear forces at the spoil space end bulkheads. The inclusion of the effective thickness of longitudinal bulkheads, centre box keel plating and other longitudinal material at these positions, will be considered in relation to the arrangement of structure proposed.

2.7.2 For ships classed **A1 protected waters service**, see 4.6.1.

## Section 3 Deck structure

### 3.1 Deck plating

3.1.1 Dredgers, hopper dredgers and hopper barges classed for unrestricted service are to have the minimum thicknesses required by Ch 1.4 increased by 2 mm for those areas of the strength deck outside line of openings which are exposed to the weather.

3.1.2 Ships classed **100A1 extended protected waters service** are to have the minimum thicknesses required by Ch 1.4 for all strength deck plating outside line of openings. The minimum value of  $s$ , used in the formulae may be taken as 550 mm.

3.1.3 Ships classed **A1 protected waters service** may have the minimum thicknesses as given in Ch 1.4 for all strength deck plating outside line of openings reduced by 1 mm, with an overall minimum of 5 mm. The minimum value of  $s$ , used in the formulae may be taken as 550 mm.

3.1.4 Strength deck plating within the line of openings in the midship region, and for 0,075L from the ends, is to have a thickness not less than:

$$t = 0,01s \quad \text{mm}$$

3.1.5 The deck plating thickness and supporting structure may be required to be reinforced in those areas of deck which are liable to be subjected to regular, heavy, impact loads such as could occur when maintaining or inspecting large items of dredging gear, etc. It is recommended that consideration be given to increasing the plating thickness in these areas to:

$$t = 0,02s \quad \text{mm}$$

with a minimum

$$t = 10 \quad \text{mm}$$

## 3.2 Deck stiffening

3.2.1 The scantlings of deck beams or longitudinal are to comply with the requirements of Ch 1.4.3.

## 3.3 Deck supporting structure

3.3.1 The scantlings of the deck supporting structure are to comply with the requirements of Ch 1.4.4.

## Section 4 Shell envelope plating

### 4.1 Keel

4.1.1 On ships over 50 m in length, where there is a centreline well, or where hopper doors are fitted on the ship's centreline, i.e. where no centreline box keel is fitted in a hopper, a keel strake is to be fitted on each side of the well or hopper door opening, dependent upon the proposed docking arrangements for the ship. The width of each keel strake is to be not less than half that required for a centreline keel nor less than 400 mm. The thickness of each keel strake is to be not less than the thickness required for a centreline keel in Ch 1.5.2.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 4 & 5

## 4.2 Bottom shell

4.2.1 The minimum thickness of bottom shell plating amidships on hopper dredgers and hopper barges classed for unrestricted service is to be 15 per cent greater than that required by Ch 1,5.3. The thickness of bottom shell plating on ships classed **A1 protected waters service** is to be not less than:

$$t = (5sL\sqrt{D} \times 10^{-5} + 5) \text{ mm}$$

or that required for Ch 1,5.3 whichever is the lesser, but with an overall minimum thickness of 6 mm.

4.2.2 Where hoppers extend outside 0,4L amidships, the thicknesses required for the bottom shell amidships are to be maintained for at least two frame spaces beyond the ends of the hoppers before being tapered to the end thicknesses.

## 4.3 Operating aground

4.3.1 For ships intended to operate aground, see Section 7.

## 4.4 Bottom openings

4.4.1 The corners of hopper door openings and of bucket and ladder wells are generally to be parabolic or elliptical on all ships where  $L$  is greater than 50 m, and should generally be rounded on smaller ships. On ships where  $L$  is greater than 90 m, the arrangement of hopper and well corners within 0,5L amidships should generally be as required for deck hatch corners. The sealing arrangements for hopper doors may lie within the line of the corners, provided that the construction is such as to avoid high stress concentrations in the structure.

## 4.5 Ships with chines

4.5.1 On ships arranged with two chines each side, the bilge plating should generally be calculated from the bottom plating formulae. On hard chine ships, flanged chines will not generally be approved, but where a chine is formed by knuckling the shell plating, the radius of curvature, measured on the inside of the plate, is to be not less than 10 times the plate thickness. Where a solid round chine bar is fitted, the bar diameter is to be not less than 50 mm or three times the thickness of the thickest abutting plate whichever is the greater. Where welded chines are used, the welding is to be built up as necessary to ensure that the shell plating thickness is maintained across the weld.

## 4.6 Side shell

4.6.1 The thickness of the side shell is to be in accordance with Ch 1,5.4. On ships classed **A1 protected waters service** the thickness of the side shell throughout, including at ends, may be reduced 20 per cent from that required by Ch 1,5.4 and Pt 3, Ch 5 and Pt 3, Ch 6 as appropriate, provided that the combined shear stress does not exceed 110 N/mm<sup>2</sup> (11,2 kgf/mm<sup>2</sup>).

4.6.2 Where high compressive loads occur in the sheer-strake, the thickness may be required to be increased to minimize the likelihood of buckling.

## 4.7 Swim ends

4.7.1 The plating of swim ends is to have a thickness not less than that required for the bottom shell up to the waterline at draught  $T$ , see also Table 12.7.1. It is to have a thickness not less than that required for side shell in the areas more than 1 m above the waterline at draught  $T_m$ . In intermediate areas the thickness may be tapered from the bottom to the side shell requirements.

## Section 5 Shell envelope framing

### 5.1 Longitudinal stiffening

5.1.1 The scantlings of bottom and side shell longitudinals are to comply with the requirements given in Table 12.5.1.

5.1.2 For ships intended to operate aground, see Section 7.

### 5.2 Transverse stiffening

5.2.1 For bottom structure with transverse framing, see Section 6.

5.2.2 For ships intended to operate aground, see Section 7.

5.2.3 The scantlings of side frames amidships are to be in accordance with Ch 1,6 for ships classed for unrestricted service or **100A1 extended protected waters service**. The modulus of side frames may be reduced by eight per cent for ships classed **A1 protected waters service**.

### 5.3 Primary supporting structure at sides

5.3.1 The spacing of transverses supporting side longitudinals is generally to be in accordance with Ch 1,6.4, but is not to exceed 4,0 m.

5.3.2 Transverses supporting side longitudinals are to comply with the requirements of Ch 1,6.4, except for ships classed with a service restriction notation and all ships classed **A1 protected waters service**, where the requirements are given in Table 12.5.2.

5.3.3 In way of transverse framing, web frames may be required in way of hopper cross members. Alternative arrangements may be submitted for consideration.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 5 & 6

**Table 12.5.1 Longitudinal stiffening**

Position of longitudinals	Modulus
(1) Bottom	$Z = \frac{l_e^2 s H}{K_1} c \text{ cm}^3$ <p>where  <math>l_e</math> = effective span of longitudinals, in metres, and is to be taken as not less than 1,85 m except as provided for in 6.3.1  In way of single bottoms  <math>H = D</math>  In way of double bottoms  <math>H = D</math> on ships classed <b>100A1</b> or <b>100A1 extended protected waters service</b>  <math>= T_m</math> for ships classed <b>A1 protected waters service</b>  <math>c</math> = a factor varying from 1,0 at <math>\frac{D}{2}</math> to <math>\frac{2060}{3620 - 1560F_B}</math> at bottom, intermediate values by interpolation.  For ships with hogging still water bending moments in loaded conditions and for split hull vessels, <math>c = 1,0</math>  <math>F_B</math> = as defined in Pt 3, Ch 4,5.1  <math>K_1</math> = 120 on ships classed <b>100A1</b> or <b>100A1 extended protected waters service</b>  <math>= 150</math> on ships classed <b>A1 protected waters service</b></p>
(2) Side shell	<p>(a) For ships classed <b>100A1</b> or <b>100A1 extended protected waters service</b>  The minimum modulus of side longitudinals is to be in accordance with Ch 1,6.2  (b) For ships classed <b>A1 protected waters service</b>  The modulus required by (a) and reduced by 5 per cent</p>
(3) Bilge	The scantlings of bilge longitudinals are to be graduated between those required for the bottom longitudinals and the lowest side longitudinals

5.3.4 The end connections of side transverses and web frames to deck and bottom transverses abreast of spoil spaces are to be arranged to prevent shear buckling of the members' webs.

5.3.5 For wash bulkheads fitted in lieu of web frames abreast spoil spaces, see 8.3.6.

**Table 12.5.2 Primary supporting structure at sides**

Symbols	Item	Requirement
$h$ = vertical distance from mid-point of span to deck at side, in metres $l_e$ = effective length of supporting member, in metres, see Pt 3, Ch 3,3 $I$ = moment of inertia of supporting member, in $\text{cm}^4$ , see Pt 3, Ch 3,3 $S$ = spacing, or mean spacing, of supporting member, in metres $Z$ = section modulus of supporting member, in $\text{cm}^3$ , see Pt 3, Ch 3,3	Transverses supporting side longitudinals amidships	<p>All ships classed <b>100A1 extended protected waters service</b>:</p> $Z = 9,5S h l_e^2 \text{ cm}^3$ <p>All ships classed <b>A1 protected waters service</b>:</p> $Z = 9,0S h l_e^2 \text{ cm}^3$
	Transverses and web frames supporting side longitudinals abreast of spoil spaces	Inertia of not less than: $I = 2,5l_e Z \text{ cm}^4$

## Section 6 Bottom structure

### 6.1 General

6.1.1 This Section provides for longitudinal or transverse framing of the bottom structure of ships with single or double bottoms.

6.1.2 For ships intended to operate aground, see Section 7.

### 6.2 Single bottoms transversely framed

6.2.1 The scantlings of single bottom floors, extending for the full width of the ship, are to be in accordance with Ch 1,7 irrespective of the length of the ship. Floors below dredging pumps or similar items which could induce large concentrated loads or large dynamic forces, may be required to be of increased strength. Floors may be recessed locally in way of dredging pumps, etc., provided that suitable compensation is arranged.

6.2.2 The spacing of intercostals and longitudinal side girders is to be such as to ensure continuity of strength at bulkheads, ends of spoil spaces and wells and at ends of machinery seats so far as practicable, see also Ch 1,7. An intercostal is to be fitted in the buoyancy space abreast hopper openings when the distance between the hopper opening and the ship's side exceeds 4,0 m.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Section 6

6.2.3 Abreast of dredging wells and spoil spaces the minimum depth of floor at its inboard end is to be not less than:

$$d_w = 20 (B + l_e + 2T_m) \text{ mm}$$

The thickness of the web and area of the face plate are to be as required by Ch 1,7.2.

## 6.3 Single bottoms longitudinally framed

6.3.1 The spacing of transverses is to be in accordance with 5.3.1, and are to be supplemented by the following arrangements of brackets:

- On the ship's centreline, or on each side of dredging wells where there is no structure on the centreline, the brackets are to be spaced not more than 1,25 m apart and are to extend outboard to the first longitudinal, port and starboard. The longitudinals supported by the brackets may be calculated using a nominal transverse spacing of 1,6 m.
- On ships where the sides are transversely framed, the brackets are to be fitted at every frame and are to extend inboard to the first longitudinal on the flat of bottom. This longitudinal is to be based on a span equal to the spacing of the transverses.
- The thickness of these intermediate brackets is to be not less than:

$$t = (0,25B + 1,85 \sqrt{T_m}) \text{ mm}$$

6.3.2 In areas of high shear loading, the thickness and stiffening of the web plates on transverses, etc., may have to be increased. The depth of transverses is to be not less than 2,5 times the depth of the slot for the bottom longitudinals, and thickness of the web plates is to be not less than 8 mm.

6.3.3 Bottom transverses in spoil space side buoyancy tanks in way of cross ties are to have a depth,  $d$ , of not less than:

$$d = 28B + 205 \sqrt{T_m} \text{ mm}$$

Their arrangement, scantlings and end connections are to be such as to provide proper continuity of strength across the ship. The transverses are to be fitted with stiffeners in way of every shell longitudinal. The stiffeners should, in general, be equivalent to flat bars with a depth one-eighth of the transverse at that point and a thickness not less than the thickness of the transverse.

## 6.4 Double bottom – General

6.4.1 Self-propelled dredgers and reclamation ships of more than 500 tons gross and intended for International voyages are to be provided with a double bottom extending from the collision bulkhead to the after peak bulkhead, as far as this is practicable and compatible with the design and proper working of the ship.

6.4.2 A double bottom need not be fitted in way of watertight compartments used exclusively for the carriage of liquids provided the safety of the ship, in the event of bottom damage, is not thereby impaired.

6.4.3 The double bottom may, however, be interrupted locally, or fitted with wells in way of dredging pumps and other equipment. Where such openings are large, their scantlings and arrangements will be specially considered.

6.4.4 The scantlings are to be in accordance with Ch 1,8 except for the following:

- The Rule thickness of centre girders may be reduced by 2,0 mm on ships classed **A1 protected waters service**.
- The Rule thickness of side girders may be reduced by 1,0 mm on ships classed **100A1 extended protected waters service**.
- The scantlings of floors, longitudinals and plating supporting the bottom of spaces intended to carry spoil are to be determined in accordance with Section 8.

## 6.5 Double bottom with transverse framing

6.5.1 Plate floors may be fitted at every frame or may be spaced not more than 3,0 m apart with the shell and inner bottom plating between these floors supported by bracket floors. However, plate floors are to be fitted at every frame in the following areas:

- As required for Ch 1,8.5.
- Below spaces from which dredged material will be discharged by grabs.
- In main propulsion and dredging machinery rooms and in peak tanks.
- For three frame spaces at ends of spoil spaces and dredging wells.

## 6.6 Double bottom with longitudinal framing

6.6.1 In locations other than below spaces intended for dredged spoil the section modulus of inner bottom longitudinals is to be not less than:

$$Z = \frac{l_e^2 s H}{K_1} c \text{ cm}^3$$

where

- $l_e$  = effective span of longitudinals, in metres, and is to be taken as not less than 1,85 m
- $s$  = spacing of longitudinals, in mm
- $H$  = height, in metres, from the tank top to the deck at side, (but need not exceed  $T_m$  on ships classed **A1 protected waters service**)
- $c$  = as defined in Table 12.5.1
- $K_1$  = 120 in machinery spaces on ships classed **100A1**  
= 150 otherwise.

6.6.2 The section modulus of longitudinals below spaces intended for dredged spoil is to comply with the requirements of 8.3.7.

6.6.3 The spacing of transverses is generally to be as for dry cargo ships but is not to exceed 4,0 m. Below main dredging machinery the transverses are generally to be spaced not more than 1,0 m apart.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 6 & 7

6.6.4 The ends of longitudinal girders under dredging machinery are to be tapered off or efficiently scarfed into other longitudinal structural items.

## Section 7 Bottom strengthening for operating aground

### 7.1 Application

7.1.1 The scantlings of bottom structure are to comply with the requirements given in Table 12.7.1.

7.1.2 Unless otherwise specified by the Owner, it should be assumed that non-self-propelled dredging and reclamation craft are to operate aground.

**Table 12.7.1 Bottom strengthening for operating aground**

Item	Requirement	
The following requirements are to be applied to the bottom structure upon which the ship is likely to be supported whilst aground		
(1) Bottom shell, keel and swim end plating	Thickness to be increased by 20% over the minimum requirements of Ch 1,5, with a minimum of 8 mm	
(2) Bottom longitudinals	Scantlings as required by Table 12.5.1(1) taking $K_1 = 74$ and $c = 1,0$	
(3) Bilge longitudinals (where fitted)	Scantlings to be the same as bottom longitudinals	
(4) Primary stiffening in way of single bottoms, see Notes 1 and 2	Transverse framing	Longitudinal framing
	(a) Floors to be fitted at every frame with vertical stiffeners spaced, in general, not more than 1,25 m apart (b) Side girders to be spaced not more than 2,2 m apart and intermediate 100 mm x 10 mm bulb plate longitudinals, or equivalent, fitted	(a) The spacing of transverses or floors is, in general, not to exceed 2,5 m outboard of wells or 1,85 m elsewhere (b) The panel size nearest the shell plating of web plates of transverses or floors is, in general, not to exceed $80t \times 80t$ where $t$ is the actual web thickness (c) Side girders to be spaced not more than 2,2 m apart
(5) Primary stiffening in way of double bottoms, see Notes 1 and 2	(a) Plate floors are to be fitted at every frame with vertical stiffeners spaced, in general, not more than 1,25 m apart (b) Side girders to be spaced not more than 2,5 m apart and intermediate 100 mm x 10 mm bulb plate longitudinals, or equivalent, fitted (c) Where the span of floors between a hopper space and the ship's side exceeds 3,75 m, a longitudinal girder is to be fitted	(a) The spacing of plate floors is, in general, not to exceed 1,85 m (b) Side girders to be spaced not more than 2,5 m apart
NOTES		
1. The scantlings of floors, girders and transverses are to be determined in accordance with the requirements of Section 6.		
2. The number and size of holes in floors, girder and transverses are to be kept to a minimum, see Ch 1,8.		



## Section 8 Spoil space and well structure

### 8.1 Symbols and definitions

8.1.1 The symbols used in this Section are defined as follows:

$h$  = load head, in metres, measured vertically as follows:

- (a) For plating, the distance from a point one-third of the height of the plate above its lower edge to the sill of the uppermost overflow weir.
- (b) For stiffeners or girders, the distance from the middle of the effective length to the sill of the uppermost overflow weir.

$l_e$  = effective length of stiffening members, in metres, see Pt 3, Ch 3,3

$s$  = spacing of stiffeners, in mm

$t$  = plate thickness, in mm

$A_1$  = cross-sectional area of flange or stiffener, in cm<sup>2</sup>, including coaming plating.

8.1.2 Other symbols are defined in 1.5.1.

### 8.2 General

8.2.1 This Section provides for:

- (a) horizontally and vertically stiffened boundary bulkheads to hoppers, and holds intended for dredged spoil, to ladder wells and to spud wells,
- (b) protection against flooding in the event of the ladder well or adjacent bottom plating being damaged by objects dredged up by bucket dredgers, and
- (c) continuity of transverse strength in spoil spaces and wing tanks abreast of spoil spaces.

8.2.2 As an alternative to the requirements of this Section regarding primary structure, scantlings may be derived on the basis of direct calculation methods, see Section 18.

8.2.3 **Continuity of strength.** Arrangements are to be made to ensure continuity of strength at the ends of longitudinal and well side bulkheads. In general, the design should be such that the bulkheads are connected to bottom and deck girders by means of large, suitably shaped brackets arranged to give a good stress flow at their junctions with both the girders and the bulkheads.

8.2.4 **Ladder well cofferdams.** Ladder wells of trailing suction dredgers are to be isolated from the remainder of the dredger's structure by local cofferdams at least 600 mm wide, or are to be otherwise protected to prevent serious flooding due to the well side plating being breached by the ladder structure should this be damaged in service. Ladder wells of bucket dredgers are to be isolated by cofferdams, the extent and widths of which are to be sufficient to contain any damage to the well side bulkheads or bottom shell plating that could result from the impact of large objects brought up in the dredge buckets. In way of the buckets the cofferdam may be extended outboard in the form of a local watertight double bottom.

### 8.3 Spoil space and well boundaries

8.3.1 The minimum plating thickness of spoil space boundaries is to be the thickness required for deep tanks by Ch 1,9.2, or 8,5 mm, whichever is the greater. In the case of grab dredgers the minimum thickness is to be 10 mm. These thickness requirements also apply to the plating of watertight box keels and inner bottom plating. The value of  $p$  used in the calculations and the height(s) of the overflow weir(s) are to be clearly shown on the midship section plan.

8.3.2 Attention is drawn to the high rate of wear that can occur on spoil space boundaries, and it is recommended that an additional corrosion allowance of 3,0 mm be added on areas subject to particularly onerous conditions. Where such an allowance is added, the fact is to be marked on the relevant plans.

8.3.3 The thickness of plating forming the sides and ends of bucket ladder wells is to be not less than:

$$t = (0,0055s\sqrt{T_m} + 3,0) \text{ mm}$$

In no case, however, is the side plating to have a thickness less than 12 mm nor is the well end plating to have a thickness less than 8,5 mm. Plating forming the boundaries of suction pipe ladder wells is generally to be as required for shell plating. Corrosion allowance on well end plating below bucket ladders may be 2,0 mm.

8.3.4 The thickness of spoil space and ladder well bulkheads may be required to be increased where high shear forces are present.

8.3.5 Bulkheads forming the boundaries of spud wells are to be of increased strength. Each case will be considered on its merits, but in general such bulkheads should have a thickness of not less than 12 mm.

8.3.6 Where non-watertight bulkheads are fitted in the side buoyancy tanks, the thickness of the plating is to be not less than:

(a)  $t = 6,5$  mm, or

(b)  $t = (5,35 + 0,024L)$  mm

whichever is the greater. Where the bulkhead is in the form of a wash bulkhead, the openings should be so arranged that, in general, the distance from lightening holes to any slots cut to accommodate side shell or bulkhead longitudinals is at least equal to 1,5 times the depth of the slot. The edges of large openings are to be stiffened.

8.3.7 The Section modulus of framing on spoil space boundaries is to be not less than:

$$Z = \frac{0,0113p s h l_e^2 c}{\gamma} \text{ cm}^3$$

where

$c$  has the value given in Table 12.8.1 for longitudinal framing and  $c = 1,0$  for transverse framing

$g = 1,4$  for rolled or built sections  
 $= 1,6$  for flat bars.

The section modulus of longitudinals below  $\frac{D}{2}$  is to be taken not less than the value obtained at  $\frac{D}{2}$ .

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Section 8

**Table 12.8.1 Definition of  $c$**

Symbols	Location	$c$
$F_B$ as defined in Pt 3, Ch 4.5.1	$\frac{D}{2}$ and above	1,0
	0,2D above base (see Note)	$\frac{550}{1590 - 1040F_B}$
	Base line (see Note)	$\frac{2060}{3620 - 1560F_B}$
NOTE For ships with hogging still water bending moments in loaded conditions and for split hull vessels, $c = 1,0$ .		

8.3.8 The section modulus of stiffeners bounding wells and deep tanks is to satisfy the requirements of Ch 1,9.2.

8.3.9 For non-watertight bulkheads, the modulus of the stiffeners may be 50 per cent of that required for intact bulkheads. The stiffeners are to be bracketed at top and bottom.

8.3.10 Structure supporting spud well plating and bulkheads below, and in way of, 'A' frames and dredging machinery supports, is to be of substantial construction, account being taken of the dynamic loads likely to occur with the dredging machinery in operation.

8.3.11 Horizontal girders supporting stiffeners on spoil space and ladder well boundaries are, in general, to have scantlings as required by Ch 1,9.2 for deep tanks, with  $p$  and  $h$  as defined in 1.5.1 and 8.1.1 respectively and with span,  $l_s$  for horizontal girders supporting vertical stiffeners on longitudinal bulkheads, measured between bulkhead bracket and bulkhead bracket, i.e. ignoring any struts which may be fitted between spoil space girder and shell stringer. Alternatively, the section modulus of these horizontal girders may be reduced by 40 per cent from the formula value if struts are fitted on alternate frames between the spoil space girder and a shell stringer. These struts should generally be horizontal and are to have a sectional area as required for pillars by Ch 1,4.4 with  $p$  as defined in 1.5.1 and  $h$  measured from the inboard end of the strut to the height defined in 8.1.1. Web frames and girders are to have scantlings as required by Chapter 1, with  $p$  and  $h$  as defined in 1.5.1 and 8.1.1 respectively.

## 8.4 Cross-members

8.4.1 Cross-members are to be fitted within the hopper space in line with the bottom and side shell transverses and with the bulkheads in the side buoyancy spaces. Cross-members need not be fitted at every frame, but their spacing is not to exceed 4,0 m. Where a box keel is fitted on the centreline, webs are to be fitted within the box keel to ensure proper continuity of strength across the ship in way of the hopper cross-member. The webs required within centreline watertight box keels may have a thickness 3,5 mm less than that required for the hopper cross-members with which they are associated, but their minimum thickness is to be not less than 6,5 mm.

8.4.2 The upper edge of the hopper lower cross-members should, in general, be a height of not less than  $\frac{D}{4}$  above the

above the keel in ships with the number 100 in their character of classification. The lower edge should be as low as practicable after allowing for the proper design of hopper doors, suction passages, etc. Lower cross-members may be fabricated from flat plate suitably stiffened or may take the form of a hollow box, generally of triangular cross-section.

8.4.3 The scantlings of box-type cross-members should be determined from the requirements for hopper bulkheads where applicable. When flat plate lower cross-members are fitted, the thickness of the web is to be not less than:

$$t = (0,7B + 3) \text{ mm or } 8,5 \text{ mm}$$

whichever is the greater.

8.4.4 The cross-sectional area of the cross-member web after deducting access openings, lightening holes, etc., is to be not less than:

$$A = 6h_w S_M \text{ cm}^2$$

where

$h_w$  = height, in metres, of the uppermost hopper overflow weir above the keel

$S_M$  = spacing of the cross-member webs, in metres.

8.4.5 The upper edge of the cross-member is to be stiffened by means of a tube having an outside diameter not less than:

$$\delta = 30l_s \text{ mm}$$

where

$l_s$  = span, in metres, of the upper edge of the cross-member (to the centreline box girder if fitted),

and a thickness equal to the minimum required cross tie web thickness, or by an equivalent flange or structure. The lower edge of the cross-member is also to be suitably stiffened.

8.4.6 The cross-member web is to be fitted with stiffeners, spaced not more than 80t mm apart having a modulus of not less than:

$$Z = 0,04s l_e^2 \text{ cm}^3$$

8.4.7 Upper cross-members spanning hopper spaces at or above deck level are to be designed on the basis of actual loads carried, including dynamic factors if applicable, and 60 per cent fixity. Stresses are to be as follows:

Bending stress,  $\sigma_b$  is not to exceed:

$$74,5 \text{ N/mm}^2 (7,6 \text{ kgf/mm}^2)$$

Shear stress,  $\sigma_s$  is not to exceed:

$$68,6 \text{ N/mm}^2 (7,0 \text{ kgf/mm}^2)$$

Total stress,  $\sigma_c = \sqrt{\sigma_b^2 + 3\sigma_s^2}$  and is not to exceed:

$$118 \text{ N/mm}^2 (12 \text{ kgf/mm}^2)$$

The members should, in general, be connected to the centreline box keel by one or more pillars, where such a keel is fitted.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 8 to 11

## 8.5 Pillars within hoppers

8.5.1 Pillars are generally to comply with the requirements of Ch 1,4.4, account being taken of the maximum forces that can be applied by rams or other gear fitted for the purpose of activating hopper doors or valves.

## 8.6 Continuous coamings

8.6.1 Continuous coamings are to have a plate thickness of not less than 8,5 mm. A minimum thickness of 10 mm is recommended for coamings on grab dredgers. Where the depth of the coaming exceeds 80t, the plating is to be stiffened by one or more horizontal members so spaced that the width of the upper panel of plating does not exceed 65t and the width(s) of the lower panel(s) do(es) not exceed 80t.

8.6.2 Where the coaming is stiffened with flat bar members, the members are to have a breadth not less than  $0,04S_s$  and a thickness not less than 0,05 times their breadth, or 8,5 mm, whichever is the greater. They are to have a minimum inertia of:

$$I = 2S_s^2 A_1 \text{ cm}^4$$

where

$A_1$  and  $I$  include the coaming plating for mid-panel above to mid-panel below the stiffener, and  
 $S_s$  = spacing of the brackets required by this sub-Section, in metres.

Where stiffeners other than flat bars are used, they are to have at least the same minimum thickness and inertia as required for flat bars.

8.6.3 The upper edge of the coaming is to be stiffened by a fabricated flange, box girder or equivalent structure having a width not less than  $0,05S_s$  and an inertia not less than:

$$I = 2,86S_s^2 A_1 \text{ cm}^4$$

where

$A_1$  and  $I$  include the coaming plating down to mid-panel below

The thickness and/or attachments of the stiffening member are to be such as to minimize any likelihood of local instability under compression loading.

8.6.4 The coamings are to be supported by substantial brackets spaced generally not more than 3,0 m apart where the coamings have a height of more than 600 mm, nor more than 2,5 m where the coamings have a height of more than 1,0 m but on longitudinally framed ships the brackets are to be arranged in way of each deck transverse. Additional brackets may be required in way of the ends of hopper upper cross ties, especially those which themselves support hopper door operating rams or similar equipment.

8.6.5 The ends of continuous coamings are to be well scarfed into the ship's structure at the ends of spoil spaces. Unless longitudinal deckhouse bulkheads are fitted in this area, the coamings are to be extended beyond the end of the spoil space opening for a distance of at least one frame space, or 1,5 times the coaming height, whichever is the greater.

## Section 9 Watertight bulkheads

### 9.1 Arrangements of bulkheads

9.1.1 The number of watertight bulkheads is to be not less than that required for dry cargo ships, see Pt 3, Ch 3,4. Their positioning is to be such that one extends the full width of the ship at each end of the spoil spaces, see also 8.2. Proposals to dispense with one or more of the watertight bulkheads in that part of the ship in way of spoil spaces may be submitted for consideration. In particular, watertight bulkheads need not be fitted within spoil spaces and an increased spacing of bulkheads in the spaces abreast of spoil spaces will generally be accepted provided that:

- (a) Suitable structural compensation is arranged; and
- (b) the stability is checked in the damaged condition.

## Section 10 Exposed casings

### 10.1 Scantlings and access

10.1.1 Exposed casings on ships classed **A1 protected waters service** are to have scantlings as required for deck-houses on dry cargo ships classed **100A1**. On ships classed **100A1**, where  $T_m$  equals or exceeds the draught corresponding to a Type 'B-60' ship freeboard, direct access is not permitted to the machinery spaces (including dredging pump-rooms) from the freeboard deck. Doors may be fitted in exposed casing bulkheads, provided that they lead to a space which is of equivalent strength to the casing and is separated from the machinery space by a second watertight door.

## Section 11 Dredging machinery seats and dredging gear

### 11.1 Dredging machinery seats

11.1.1 The seats supporting the main dredging machinery are to be at least as substantial as those required for the main propulsion machinery for dry cargo ships, see Pt 3, Ch 7,6. Continuity between the longitudinal and transverse members of main engine seats and the ship's bottom structure is to be arranged where practicable. Where floors are cut away below dredging pumps, they are to be fitted with face bars, and special care is to be taken to minimize stress-raising details and to ensure good workmanship.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 11 to 15

## 11.2 Dredging gear

11.2.1 Where masts or derrick posts support dredging gear which will be subjected to vibration or other dynamic loads in addition to its true weight, this must be taken into account in the calculations. The dynamic multiplier should be taken between two and three according to the type of machinery and gear used.

## Section 12 Ladder wells

### 12.1 Transverse strength at deck

12.1.1 Where ladder wells are incorporated so that the length of the well exceeds 1,5 times the width of the deck remaining on each side of the well, the portions of the ship on each side of the well are to be adequately cross connected in the region of their free ends, unless the design of the ship renders this impracticable, in which case alternative arrangements are to be made to avoid high stress concentrations at the inboard end of the well.

## Section 13 Fenders

### 13.1 Fenders and reinforcement in way

13.1.1 Dredgers designed to work in conjunction with hopper barges are to be fitted with permanent rubbing strakes or fenders extending down to their lowest normal operating waterline. On transversely framed vessels it is recommended that the side structure in way of the lower edge of the fender be reinforced by a stringer and/or cross ties. It is recommended that, where wooden fenders are fitted to dredgers operating in tropical sea-water, the fenders be cut just above the deepest working waterline and a gap be left sufficient to prevent water soaking up into the fenders.

## Section 14 Rudders

### 14.1 Rudders on bucket dredgers

14.1.1 Where bucket dredgers are arranged with bucket ladders at their stern, the ship's rudders are to be kept well clear of the buckets to minimize the likelihood of damage to the rudders by large objects which may be dredged up. For rudder calculations, see Pt 3, Ch 13.

## Section 15 Spoil space weirs and overflows

### 15.1 General

15.1.1 All spoil spaces are to be arranged to allow the safe and efficient overboard discharge of excess water in all weather conditions in which the ship is classed to operate. In ships over 90 m in length and in all ships classed for unrestricted service the spoil space overflows are to be arranged via enclosed overflow trunks so designed as to keep the decks of the ship clear of spoil and water.

15.1.2 In general, bulwarks are not to be fitted in way of open top spoil spaces on dredging and reclamation craft.

15.1.3 Where a ship operates at the maximum draught that could be assigned in accordance with the *International Convention on Load Lines, 1966*, the overflow arrangements fitted should ensure that when the spoil space is loaded, this draught is not exceeded.

15.1.4 Where a hopper dredger having releasing arrangements for cargo dumping, e.g. bottom doors, etc., is permitted by an Administration to be assigned a freeboard less than that which could be assigned by the *International Convention on Load Lines, 1966*:

- The structural strength and bending moments are to be acceptable for the deeper draught indicated, and
- the dredger is to be operated in a zone of operation and in such weather conditions as are considered appropriate.

15.1.5 Adequate arrangements are to be fitted to prevent overloading under any condition of loading having due regard to trim. The size and position of the overflows are to be confirmed by a loading trial, which is to be carried out when the spoil space is loaded with dredgings of the same density as is likely to be loaded in service.

15.1.6 The cutting of overflow discharge trunk openings in the sheerstrake is to be avoided wherever practicable. In ships over 70 m in length, spoil space overflow discharge trunk openings are not to be cut within 800 mm of the upper edge of the sheerstrake. They are to have corner radii of not less than 150 mm, and suitable compensation is to be arranged. In no case is a discharge trunk to pierce the sheerstrake in way of discontinuities such as breaks of superstructure.

# Dredging and Reclamation Craft

# Part 4, Chapter 12

Sections 16 & 17

## Section 16 Scuppers and sanitary discharges and side scuttles

### 16.1 General

16.1.1 In all areas where mechanical damage might be likely, all side scuttles, scuppers and discharges, including their valves, controls and indicators, are to be well protected. Consideration is to be given to the likelihood of impact damage to scuttles and discharges due to barges coming alongside, and to scuppers becoming blocked by sand or other spoil which may spill onto the decks or other areas being drained.

16.1.2 Consideration will be given to requests for relaxation of requirements relating to scuttles, scuppers and discharges on ships classed **A1 protected waters service**.

## Section 17 Split hopper dredgers and barges

### 17.1 Symbols and definitions

17.1.1 The symbols used in this Section are defined as follows:

- $H$  = height of spoil above base line, in metres
- $H_s$  = depth of hopper seal, in metres
- $L_h$  = length of hopper well, in metres
- $M_H$  = design horizontal bending moment in hopper side wall, in kN m (tonne-f m). A moment giving rise to tensile stress in the side shell is to be taken as positive
- $P$  = net pressure per metre ship length resulting from the spoil pressure and the hydrostatic load, see Fig. 12.17.2  
 $= 4,9 (\rho (H - H_s)^2 - 1,025 (T - H_s)^2)$  kN/m  
 $(0,5 (\rho (H - H_s)^2 - 1,025 (T - H_s)^2)$  tonne-f/m)
- $S_h$  = span between the centres of hinges, in metres

17.1.2 Other symbols are defined in 1.5.1.

### 17.2 Hull bending strength

17.2.1 The modulus of the cross-section of the vessel is to be not less than that required by 2.3.1. In addition, the combined stress  $\sigma_c$ , at any point on the cross-section of one half hull, is not to exceed the permissible combined stress  $\sigma$  given in Pt 3, Ch 4.5.5. The combined stress at any point on the cross-section is to be determined from the following expression:

$$\sigma_c = \left( \frac{M_N}{Z_N} + \frac{M_p}{Z_p} \right) \times 10^{-3} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

- $M_N$  =  $\pm M_V \cos \phi \pm M_H \sin \phi$  kN m (tonne-f m)
- $M_p$  =  $\pm M_H \cos \phi \pm M_V \sin \phi$  kN m (tonne-f m)
- $M_V$  =  $\pm 0,5 (M_s + M_w)$  kN m (tonne-f m)

where the still water bending moments hogging and sagging are to be combined with the appropriate wave bending moment to give a total moment,  $M_V$ , hogging (positive) and sagging (negative)

$M_w$  is defined in 1.5.1.

$f_1$  = ship service factor, see Table 12.2.1

$M_H$  =  $0,125 P L_h (2S_h - L_h) \pm M_L$  kN m (tonne-f m)

$M_L$  =  $0,286 f_1 L^2 B$  kN m ( $0,029 f_1 L^2 B$  tonne-f m)

$P$  =  $4,9 (\rho (H - H_s)^2 - 1,025 (T - H_s)^2)$  kN m  
 $(0,5 (\rho (H - H_s)^2 - 1,025 (T - H_s)^2)$  tonne-f m)

Account is to be taken of the sign of individual bending moment component in the determination of  $M_N$ ,  $M_p$ ,  $M_V$  and  $M_H$

$I_{NN}$  = second moment of area of the section of one half hull for all longitudinal continuous material about principal axis NN, in  $m^4$

$I_{PP}$  = second moment of area of the section of one half hull for all longitudinal continuous material about principal axis PP, in  $m^4$

$Z_p = \frac{I_{PP}}{y_P}$  in  $m^3$ , the modulus of section to a point  $y_P$  m,

from the principal axis PP

$Z_N = \frac{I_{NN}}{y_N}$  in  $m^3$ , the modulus of section to a point

$y_N$  m, from the principal axis NN

$\phi$  = angle of rotation of the principal axis NN with respect to the global horizontal axis YY, in degrees.

See also Fig. 12.17.1.

17.2.2 The combined stress for dredging conditions, where draught  $T_m$  exceeds  $T$ , is not to exceed the permissible combined stress  $\sigma_c$  obtained from 17.2.1.

The combined stress is to be obtained from the expression for  $\sigma_c$  given in 17.2.1, substituting the following expression of  $M_V$ :

$M_V = \pm 0,5 (M_{sm} + M_{wd})$  kN m (tonne-f m)


where

$M_{wd} = 0,56 f_2 M_{wo}$  and  $M_{wo}$  is determined from Pt 3, Ch 4.5.2, using  $C_{bm}$  in place of  $C_b$  and  $f_2$  is given in Pt 3, Ch 4.5.2.

### 17.3 Separation arrangements


17.3.1 Hinges, actuating and locking devices provided to facilitate separation of the split hulls to discharge spoil are to be of efficient design and of adequate strength and scantlings to ensure safe discharge operations. Hydraulic rams or other actuating devices are to have sufficient power to ensure controlled opening operations and to achieve closing of the hulls in all anticipated weather conditions.

17.3.2 Locking devices are to be of a suitable design and strength to ensure that accidental separation of the hulls cannot occur due to ship motions and vibrations.



17.3.3 Hinge pin gudgeons are to be efficiently connected to the hull structure by means of brackets or equivalent and effectively integrated with local structure which is to be suitably reinforced. Suitable reinforcement is to be fitted to local hull structure in way of anchorages for rams and locking devices to ensure efficient transmission of loading from these devices into the hull.

17.3.4 The forces acting on hinges, actuating mechanisms and locking devices are to be determined by direct calculations based on the maximum combination of loading which can be expected in any service condition. In general, this will require the resolution of the static and dynamic systems of force acting on the hulls taking due account of the relative locations of hinges, actuating mechanisms and locking devices. Fig. 12.17.2 illustrates a typical arrangement of hinges and mechanisms together with associated static loads. In general, one half of the load acting on one half hull may be assumed to act on the forward hinge assembly and one half on the after hinge assembly.



# Dredging and Reclamation Craft

## Part 4, Chapter 12

Sections 17 &amp; 18

### 17.4 Hinge pins

17.4.1 The diameter of the hinge pins is to be determined using the maximum resultant shear force acting on the pin cross section in conjunction with an average shear stress not exceeding  $\frac{62}{k}$  N/mm<sup>2</sup>  $\left( \frac{6,3}{k} \text{ kgf/mm}^2 \right)$ .

In no case is the diameter of the hinge pin to be less than that calculated from the following expression:

$$D_p = 20 \sqrt{\frac{L^{0,5} B D K}{n}} \text{ mm}$$

where

$k$  = higher tensile steel factor, see Pt 3, Ch 2,1

$n$  = the number of pin cross sections resisting shear forces

and  $L$ ,  $B$  and  $D$  are defined in 1.5.1.

17.4.2 Where arrangements are such that hinge pins are subjected to significant bending, the diameter of the pins will be specially considered.

## Section 18

### Direct calculations

#### 18.1 Application

18.1.1 Direct calculations may be used to assess the scantlings of primary structure in spoil spaces and adjacent structure.

18.1.2 Direct calculations may be required to be submitted in respect of unusual structural arrangements.

#### 18.2 Procedures

18.2.1 Methods applied for direct calculations of scantlings will be given individual consideration dependent on the particular structural configuration, see also Pt 3, Ch 1,3.1.







© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

MAIN AND AUXILIARY MACHINERY

JULY 2007

PART 5

**Lloyd's**  
**Register**

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

---

PART	1	REGULATIONS
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
PART	3	SHIP STRUCTURES (GENERAL)
PART	4	SHIP STRUCTURES (SHIP TYPES)
<b>PART</b>	<b>5</b>	<b>MAIN AND AUXILIARY MACHINERY</b>
	<b>Chapter 1</b>	<b>General Requirements for the Design and Construction of Machinery</b>
	<b>2</b>	<b>Oil Engines</b>
	<b>3</b>	<b>Steam Turbines</b>
	<b>4</b>	<b>Gas Turbines</b>
	<b>5</b>	<b>Gearing</b>
	<b>6</b>	<b>Main Propulsion Shafting</b>
	<b>7</b>	<b>Propellers</b>
	<b>8</b>	<b>Shaft Vibration and Alignment</b>
	<b>9</b>	<b>Strengthening for Navigation in Ice</b>
	<b>10</b>	<b>Steam Raising Plant and Associated Pressure Vessels</b>
	<b>11</b>	<b>Other Pressure Vessels</b>
	<b>12</b>	<b>Piping Design Requirements</b>
	<b>13</b>	<b>Ship Piping Systems</b>
	<b>14</b>	<b>Machinery Piping Systems</b>
	<b>15</b>	<b>Piping Systems for Oil Tankers</b>
	<b>16</b>	<b>Spare Gear for Machinery Installations</b>
	<b>17</b>	<b>Requirements for Fusion Welding of Pressure Vessels and Piping</b>
	<b>18</b>	<b>Integrated Propulsion Systems</b>
	<b>19</b>	<b>Steering Gear</b>
	<b>20</b>	<b>Azimuth Thrusters</b>
	<b>21</b>	<b>ShipRight Procedures for Machinery Planned Maintenance and Condition Monitoring</b>
	<b>22</b>	<b>Propulsion and Steering Machinery Redundancy</b>
	<b>23</b>	<b>Podded Propulsion Units</b>
PART	6	CONTROL, ELECTRICAL, REFRIGERATION AND FIRE
PART	7	OTHER SHIP TYPES AND SYSTEMS

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.



<b>CHAPTER</b>	<b>1</b>	<b>GENERAL REQUIREMENTS FOR THE DESIGN AND CONSTRUCTION OF MACHINERY</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Machinery to be constructed under survey
	1.2	Survey for classification
	1.3	Alternative system of inspection
	1.4	Departures from the Rules
<b>Section</b>	<b>2</b>	<b>Plans and particulars</b>
	2.1	Plans
	2.2	Materials
<b>Section</b>	<b>3</b>	<b>Operating conditions</b>
	3.1	Availability for operation
	3.2	Fuel
	3.3	Power ratings
	3.4	Definitions
	3.5	Ambient reference conditions
	3.6	Ambient operating conditions
	3.7	Inclination of ship
	3.8	Power conditions for generator sets
	3.9	Astern power
	3.10	Machinery interlocks
<b>Section</b>	<b>4</b>	<b>Machinery room arrangements</b>
	4.1	Accessibility
	4.2	Machinery fastenings
	4.3	Resilient mountings
	4.4	Ventilation
	4.5	Fire protection
	4.6	Means of escape
	4.7	Communications
	4.8	Category A machinery spaces
<b>Section</b>	<b>5</b>	<b>Trials</b>
	5.1	Inspection
	5.2	Sea trials
<b>Section</b>	<b>6</b>	<b>Quality Assurance Scheme for Machinery</b>
	6.1	General
	6.2	Requirements for approval
	6.3	Arrangements for acceptance and certification of purchased material
	6.4	Information required for approval
	6.5	Assessment of works
	6.6	Approval of works
	6.7	Maintenance of approval
	6.8	Suspension or withdrawal of approval
	6.9	Identification of products
<b>CHAPTER</b>	<b>2</b>	<b>OIL ENGINES</b>
<b>Section</b>	<b>1</b>	<b>Plans and particulars</b>
	1.1	Plans
<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	Crankshaft materials
	2.2	Material test and inspections

---

<b>Section</b>	<b>3</b>	<b>Design</b>
	3.1	Scope
	3.2	Information to be submitted
	3.3	Symbols
	3.4	Stress concentration factors
	3.5	Nominal stresses
	3.6	Maximum stress levels
	3.7	Equivalent alternating stress
	3.8	Fatigue strength
	3.9	Acceptability criteria
	3.10	Oil hole
	3.11	Shrink fit of semi-built crankshafts
<b>Section</b>	<b>4</b>	<b>Construction and welded structures</b>
	4.1	Crankcases
	4.2	Welded joints
	4.3	Materials and construction
	4.4	Post-weld heat treatment
	4.5	Inspection
<b>Section</b>	<b>5</b>	<b>Safety arrangements on engines</b>
	5.1	Cylinder relief valves
	5.2	Main engine governors
	5.3	Auxiliary engine governors
	5.4	Overspeed protective devices
<b>Section</b>	<b>6</b>	<b>Crankcase safety fitting</b>
	6.1	Relief valves
	6.2	Number of relief valves
	6.3	Size of relief valves
	6.4	Vent pipes
	6.5	Alarms
	6.6	Warning notice
	6.7	Crankcase access and lighting
	6.8	Fire-extinguishing system for scavenge manifolds
	6.9	Oil mist detection/monitoring
<b>Section</b>	<b>7</b>	<b>Piping</b>
	7.1	Oil fuel systems
	7.2	High pressure oil systems
	7.3	Exhaust systems
	7.4	Starting air pipe systems and safety fittings
<b>Section</b>	<b>8</b>	<b>Starting arrangements and air compressors</b>
	8.1	Dead ship condition starting arrangements
	8.2	Air compressors
	8.3	Air receiver capacity
	8.4	Electric starting
	8.5	Starting of the emergency source of power
<b>Section</b>	<b>9</b>	<b>Component tests and engine type testing</b>
	9.1	Hydraulic tests
	9.2	Alignment gauges
	9.3	Engine type testing
<b>Section</b>	<b>10</b>	<b>Turbo-chargers</b>
	10.1	Plans and particulars
	10.2	Type test
	10.3	Dynamic balancing
	10.4	Overspeed test
	10.5	Mechanical running test



<b>Section</b>	<b>11</b>	<b>Mass produced engines</b>
	11.1	Definition
	11.2	Procedure for approval of mass produced engines
	11.3	Continuous review of production
	11.4	Compliance and inspection certificate
	11.5	Type test conditions
<b>Section</b>	<b>12</b>	<b>Mass produced turbo-chargers</b>
	12.1	Application
	12.2	Procedure for approval fo mass produced turbo-chargers
	12.3	Continuous inspection of individual units
	12.4	Compliance and certificate
<b>Section</b>	<b>13</b>	<b>Type testing procedure for crankcase explosion relief valves</b>
	13.1	Scope
	13.2	Purpose
	13.3	Test facilities
	13.4	Explosion test process
	13.5	Valves to be tested
	13.6	Method
	13.7	Assessment
	13.8	Design series qualification
	13.9	The report
	13.10	Approval
<b>Section</b>	<b>14</b>	<b>Type testing procedure for crankcase oil mist detection/monitoring and alarm arrangements</b>
	14.1	Scope
	14.2	Purpose
	14.3	Test facilities
	14.4	Equipment testing
	14.5	Functional test process
	14.6	Detectors/monitors and equipment to be tested
	14.7	Method
	14.8	Assessment
	14.9	Design series qualification
	14.10	The Report
	14.11	Acceptance
<b>Section</b>	<b>15</b>	<b>Electronically controlled engines</b>
	15.1	Scope
	15.2	Plans and particulars
	15.3	Oil fuel and hydraulic oil systems
	15.4	Electronic control systems
	15.5	FMEA analysis
<b>Section</b>	<b>16</b>	<b>Alarms and safeguards for emergency diesel engines</b>
	16.1	Application
	16.2	Plans and information
	16.3	Alarms and safeguards
<b>Section</b>	<b>17</b>	<b>General requirements</b>
	17.1	Turning gear
<b>Section</b>	<b>18</b>	<b>Program for trials of diesel engines to assess operational capability</b>
	18.1	Works trials (acceptance test)
	18.2	Shipboard trials
<b>CHAPTER</b>	<b>3</b>	<b>STEAM TURBINES</b>
<b>Section</b>	<b>1</b>	<b>Plans and particulars</b>
	1.1	Plans

# Contents

# Part 5

---

<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	General
	2.2	Materials for forgings
<b>Section</b>	<b>3</b>	<b>Design and construction</b>
	3.1	General
	3.2	Welded components
	3.3	Stress raisers
	3.4	Shrunk-on rotor discs
	3.5	Vibration
	3.6	External influences
	3.7	Steam supply and water system
	3.8	Turning gear
<b>Section</b>	<b>4</b>	<b>Safety arrangements</b>
	4.1	Overspeed protective devices
	4.2	Speed governors
	4.3	Low vacuum and overpressure protective devices
	4.4	Bled steam connections
	4.5	Steam strainers
<b>Section</b>	<b>5</b>	<b>Emergency arrangements</b>
	5.1	Lubricating oil failure
	5.2	Single screw ships
	5.3	Single main boiler
<b>Section</b>	<b>6</b>	<b>Tests and equipment</b>
	6.1	Stability testing of turbine rotors
	6.2	Balancing
	6.3	Hydraulic tests
	6.4	Indicators for movement
	6.5	Weardown gauge
<b>CHAPTER</b>	<b>4</b>	<b>GAS TURBINES</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Standard reference conditions
	1.3	Power ratings
	1.4	Gas turbine type approval
	1.5	Inclination of vessel
<b>Section</b>	<b>2</b>	<b>Particulars to be submitted</b>
	2.1	Plans and information
<b>Section</b>	<b>3</b>	<b>Materials</b>
	3.1	Materials for forgings
	3.2	Material tests and inspection
<b>Section</b>	<b>4</b>	<b>Design and construction</b>
	4.1	General
	4.2	Vibration
	4.3	Containment
	4.4	Intake and exhaust ducts
	4.5	External influences
	4.6	Corrosive deposits
	4.7	Acoustic enclosures
	4.8	Thermal insulation
	4.9	Welded construction
	4.10	Turning gear

<b>Section</b>	<b>5</b>	<b>Piping systems</b>
	5.1	General
	5.2	Oil fuel systems
	5.3	Lubricating oil systems
	5.4	Cooling systems
<b>Section</b>	<b>6</b>	<b>Starting arrangements</b>
	6.1	General
	6.2	Purging before ignition
	6.3	Air starting
	6.4	Electric starting
	6.5	Hydraulic starting
<b>Section</b>	<b>7</b>	<b>Tests</b>
	7.1	Dynamic balancing
	7.2	Hydraulic testing
	7.3	Overspeed tests
<b>Section</b>	<b>8</b>	<b>Control, alarm and safety systems</b>
	8.1	General
	8.2	Overspeed protection and shutdown system
	8.3	Power turbine inlet over-temperature control
	8.4	Flameout
	8.5	Lubricating oil system
	8.6	Hand trip arrangement
	8.7	Fire detection, alarm and extinguishing systems
<b>Section</b>	<b>9</b>	<b>Planned maintenance and condition monitoring procedures, and 'upkeep by exchange'</b>
	9.1	Planned maintenance approach
	9.2	Preventive maintenance
	9.3	Unscheduled maintenance
	9.4	Condition monitoring
	9.5	Condition monitoring techniques
	9.6	Upkeep by exchange
<b>CHAPTER</b>	<b>5</b>	<b>GEARING</b>
<b>Section</b>	<b>1</b>	<b>Plans and particulars</b>
	1.1	Gearing plans
	1.2	Material specifications
<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	Material properties
	2.2	Non-destructive tests
<b>Section</b>	<b>3</b>	<b>Design</b>
	3.1	Symbols
	3.2	Tooth form
	3.3	Tooth loading factors
	3.4	Tooth loading for surface stress
	3.5	Tooth loading for bending stress
	3.6	Factors of safety
<b>Section</b>	<b>4</b>	<b>Construction</b>
	4.1	Gear wheels and pinions
	4.2	Accuracy of gear cutting and alignment
	4.3	Gearcases
<b>Section</b>	<b>5</b>	<b>Tests</b>
	5.1	Balance of gear pinions and wheels
	5.2	Meshing tests
	5.3	Alignment

---

<b>CHAPTER</b>	<b>6</b>	<b>MAIN PROPULSION SHAFTING</b>
<b>Section</b>	<b>1</b>	<b>Plans and particulars</b>
	1.1	Shafting plans
<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	Materials for shafts
	2.2	Ultrasonic tests
<b>Section</b>	<b>3</b>	<b>Design</b>
	3.1	Intermediate shafts
	3.2	Gear quill shafts
	3.3	Final gear wheel shafts
	3.4	Thrust shafts
	3.5	Screwshafts and tube shafts
	3.6	Hollow shafts
	3.7	Couplings and transitions of diameters
	3.8	Coupling bolts
	3.9	Bronze or gunmetal liners on shafts
	3.10	Keys and keyways
	3.11	Propellers
	3.12	Sternbushes
	3.13	Vibration and alignment
<b>CHAPTER</b>	<b>7</b>	<b>PROPELLERS</b>
<b>Section</b>	<b>1</b>	<b>Plans and particulars</b>
	1.1	Details to be submitted
<b>Section</b>	<b>2</b>	<b>Materials</b>
	2.1	Castings
<b>Section</b>	<b>3</b>	<b>Design</b>
	3.1	Minimum blade thickness
	3.2	Keyless propellers
<b>Section</b>	<b>4</b>	<b>Fitting of propellers</b>
	4.1	Propeller boss
	4.2	Shop tests of keyless propellers
	4.3	Final fitting of keyless propellers
<b>CHAPTER</b>	<b>8</b>	<b>SHAFT VIBRATION AND ALIGNMENT</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Basic requirements
	1.2	Resilient mountings
<b>Section</b>	<b>2</b>	<b>Torsional vibration</b>
	2.1	General
	2.2	Particulars to be submitted
	2.3	Scope of calculations
	2.4	Symbols and definitions
	2.5	Limiting stress in propulsion shafting
	2.6	Generator sets
	2.7	Other auxiliary machinery systems
	2.8	Other machinery components
	2.9	Measurements
	2.10	Vibration monitoring
	2.11	Restricted speed and/or power ranges
	2.12	Tachometer accuracy
	2.13	Governor control

---

<b>Section</b>	<b>3</b>	<b>Axial vibration</b>
	3.1	General
	3.2	Particulars to be submitted
	3.3	Calculations
	3.4	Measurements
	3.5	Restricted speed ranges
	3.6	Vibration monitoring
<b>Section</b>	<b>4</b>	<b>Lateral vibration</b>
	4.1	General
	4.2	Particulars to be submitted
	4.3	Calculations
	4.4	Measurements
<b>Section</b>	<b>5</b>	<b>Shaft alignment</b>
	5.1	General
	5.2	Particulars to be submitted for approval – shaft alignment calculations
	5.3	Particulars to be submitted for review – shaft alignment procedure
	5.4	Design and installation criteria
	5.5	Measurements
	5.6	Flexible couplings
<b>CHAPTER</b>	<b>9</b>	<b>STRENGTHENING FOR NAVIGATION IN ICE</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Class notations
	1.2	Materials for shafting
	1.3	Materials for propellers
<b>Section</b>	<b>2</b>	<b>Ice Classes 1AS FS, 1A FS, 1B FS and 1C FS</b>
	2.1	General
	2.2	Determination of ice torque
	2.3	Propeller blade sections
	2.4	Propeller blade minimum tip thickness
	2.5	Intermediate blade sections
	2.6	Blade edge thickness
	2.7	Mechanisms for controllable pitch propellers
	2.8	Keyless propellers
	2.9	Screwshafts
	2.10	Intermediate and thrust shafts
	2.11	Reduction gearing
	2.12	Fire pumps in motor ships
<b>Section</b>	<b>3</b>	<b>Ice Class 1D and 1E</b>
	3.1	General
	3.2	Main engine shafting, gearing and propellers
	3.3	Minimum propeller blade tip thickness
	3.4	Blade edge thickness
	3.5	Ship-side valves
	3.6	Cooling water lines
	3.7	Fire pumps in motor ships
<b>Section</b>	<b>4</b>	<b>Ice Classes 1AS FS(+), 1A FS(+), 1B FS(+), and 1C FS(+)</b>
	4.1	Powering of ice strengthened ships

## CHAPTER 10 STEAM RAISING PLANT AND ASSOCIATED PRESSURE VESSELS

### Section 1 General requirements

- 1.1 Application
- 1.2 Definition of symbols
- 1.3 Design pressure
- 1.4 Metal temperature
- 1.5 Classification of fusion welded pressure vessels
- 1.6 Plans
- 1.7 Materials
- 1.8 Allowable stress
- 1.9 Joint factors
- 1.10 Pressure parts of irregular shape
- 1.11 Adverse working conditions
- 1.12 Furnace explosion prevention

### Section 2 Cylindrical shells and drums subject to internal pressure

- 2.1 Minimum thickness
- 2.2 Efficiency of ligaments between tube holes
- 2.3 Compensating effect of tube stubs
- 2.4 Unreinforced openings
- 2.5 Reinforced openings

### Section 3 Spherical shells subject to internal pressure

- 3.1 Minimum thickness

### Section 4 Dished ends subject to internal pressure

- 4.1 Minimum thickness
- 4.2 Shape factors for dished ends
- 4.3 Dished ends with unreinforced openings
- 4.4 Flanged openings in dished ends
- 4.5 Location of unreinforced and flanged openings in dished ends
- 4.6 Dished ends with reinforced openings
- 4.7 Torispherical dished ends with reinforced openings

### Section 5 Conical ends subject to internal pressure

- 5.1 General
- 5.2 Minimum thickness

### Section 6 Standpipes and branches

- 6.1 Minimum thickness

### Section 7 Boiler tubes subject to internal pressure

- 7.1 Minimum thickness
- 7.2 Tube bending

### Section 8 Headers

- 8.1 Circular section headers
- 8.2 Rectangular section headers
- 8.3 Toroidal furnace headers
- 8.4 Header ends

### Section 9 Flat surfaces and flat tube plates

- 9.1 Stayed flat surfaces
- 9.2 Combustion chamber tube plates under compression
- 9.3 Girders for combustion chamber top plates
- 9.4 Flat plate margins

### Section 10 Flat plates and ends of vertical boilers

- 10.1 Tube plates of vertical boilers
- 10.2 Horizontal shelves of tube plates forming part of the shell
- 10.3 Dished and flanged ends for vertical boilers
- 10.4 Flat crowns of vertical boilers

<b>Section</b>	<b>11</b>	<b>Furnaces subject to external pressure</b>
	11.1	Maximum thickness
	11.2	Corrugated furnaces
	11.3	Plain furnaces, flue sections and combustion chamber bottoms
	11.4	Plain furnaces of vertical boilers
	11.5	Hemispherical furnaces
	11.6	Dished and flanged ends for supported vertical boiler furnaces
	11.7	Dished and flanged ends for unsupported vertical boiler furnaces
	11.8	Ogee rings
	11.9	Uptakes of vertical boilers
<b>Section</b>	<b>12</b>	<b>Boiler tubes subject to external pressure</b>
	12.1	Tubes
<b>Section</b>	<b>13</b>	<b>Tubes welded at both ends and bar stays for cylindrical boilers</b>
	13.1	Loads on tubes welded at both ends and bar stays
<b>Section</b>	<b>14</b>	<b>Construction</b>
	14.1	Access arrangements
	14.2	Torispherical and semi-ellipsoidal ends
	14.3	Hemispherical ends
	14.4	Welded-on flanges, butt welded joints and fabricated branch pieces
	14.5	Welded attachments to pressure vessels
	14.6	Fitting of tubes in water tube boilers
<b>Section</b>	<b>15</b>	<b>Mountings and fittings for cylindrical and vertical boilers, steam generators, pressurized thermal liquid and pressurized hot water heaters</b>
	15.1	General
	15.2	Safety valves
	15.3	Waste steam pipes
	15.4	Adjustment and accumulation tests
	15.5	Stop valves
	15.6	Water level indicators
	15.7	Low water level fuel shut-off and alarm
	15.8	Feed check valves
	15.9	Pressure gauges
	15.10	Blow-down and scum valves
	15.11	Salinometer valve or cock
<b>Section</b>	<b>16</b>	<b>Mountings and fittings for water tube boilers</b>
	16.1	General
	16.2	Safety valves
	16.3	Safety valve settings
	16.4	Waste steam pipes
	16.5	Accumulation tests
	16.6	Water level indicators
	16.7	Low water level fuel shut-off and alarm
	16.8	Feed check valves and water level regulators
<b>Section</b>	<b>17</b>	<b>Hydraulic tests</b>
	17.1	General
	17.2	Mountings

---

<b>CHAPTER</b>	<b>11</b>	<b>OTHER PRESSURE VESSELS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Definition of symbols
	1.3	Design pressure
	1.4	Metal temperature
	1.5	Classification of fusion welded pressure vessels
	1.6	Plans
	1.7	Materials
	1.8	Allowable stress
	1.9	Joint factors
	1.10	Pressure parts of irregular shape
	1.11	Adverse working conditions
<b>Section</b>	<b>2</b>	<b>Cylindrical shells and drums subject to internal pressure</b>
	2.1	Minimum thickness
<b>Section</b>	<b>3</b>	<b>Spherical shells subject to internal pressure</b>
	3.1	Minimum thickness
<b>Section</b>	<b>4</b>	<b>Dished ends subject to internal pressure</b>
	4.1	Minimum thickness
<b>Section</b>	<b>5</b>	<b>Dished ends for Class 3 pressure vessels</b>
	5.1	Minimum thickness
<b>Section</b>	<b>6</b>	<b>Conical ends subject to internal pressure</b>
	6.1	General
	6.2	Minimum thickness
<b>Section</b>	<b>7</b>	<b>Standpipes and branches</b>
	7.1	Minimum thickness
<b>Section</b>	<b>8</b>	<b>Construction</b>
	8.1	Access arrangements
	8.2	Torispherical and semi-ellipsoidal ends
<b>Section</b>	<b>9</b>	<b>Mountings and fittings</b>
	9.1	General
	9.2	Receivers containing pressurized gases
<b>Section</b>	<b>10</b>	<b>Hydraulic tests</b>
	10.1	General
	10.2	Mountings
<b>Section</b>	<b>11</b>	<b>Plate heat exchangers</b>
	11.1	General
<b>CHAPTER</b>	<b>12</b>	<b>PIPING DESIGN REQUIREMENTS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Design symbols
	1.3	Design pressure
	1.4	Design temperature
	1.5	Classes of pipes
	1.6	Materials



<b>Section</b>	<b>2</b>	<b>Carbon and low alloy steels</b>
	2.1	Carbon and low alloy steel pipes, valves and fittings
	2.2	Wrought steel pipes and bends
	2.3	Pipe joints – General
	2.4	Steel pipe flanges
	2.5	Screwed-on flanges
	2.6	Welded-on flanges, butt welded joints and fabricated branch pieces
	2.7	Loose flanges
	2.8	Socket weld joints
	2.9	Welded sleeve joints
	2.10	Threaded sleeve joints
	2.11	Screwed fittings
	2.12	Other mechanical couplings
	2.13	Non-destructive testing
<b>Section</b>	<b>3</b>	<b>Copper and copper alloys</b>
	3.1	Copper and copper alloy pipes, valves and fittings
	3.2	Heat treatment
<b>Section</b>	<b>4</b>	<b>Cast iron</b>
	4.1	Spheroidal or nodular graphite cast iron
	4.2	Grey cast iron
<b>Section</b>	<b>5</b>	<b>Plastics pipes</b>
	5.1	General
	5.2	Design and performance criteria
	5.3	Design strength
	5.4	Fire performance criteria
	5.5	Electrical conductivity
	5.6	Manufacture and quality control
	5.7	Installation and construction
	5.8	Testing
<b>Section</b>	<b>6</b>	<b>Valves</b>
	6.1	Design requirements
<b>Section</b>	<b>7</b>	<b>Flexible hoses</b>
	7.1	General
	7.2	Applications
	7.3	Design requirements
	7.4	Testing
<b>Section</b>	<b>8</b>	<b>Hydraulic tests on pipes and fittings</b>
	8.1	Hydraulic tests before installation on board
	8.2	Testing after assembly on board
<b>Appendix</b>		
<b>Section</b>	<b>9</b>	<b>Guidance notes on metal pipes for water services</b>
	9.1	General
	9.2	Materials
	9.3	Steel pipes
	9.4	Copper and copper alloy pipes
	9.5	Flanges
	9.6	Water velocity
	9.7	Fabrication and installation
	9.8	Metal pipes for fresh water services
<b>CHAPTER</b>	<b>13</b>	<b>SHIP PIPING SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Prevention of progressive flooding in damage condition
	1.3	Plans and particulars

---

<b>Section</b>	<b>2</b>	<b>Construction and installation</b>
	2.1	Materials
	2.2	Pipe wall thickness
	2.3	Valves – Installation and control
	2.4	Attachment of valves to watertight plating
	2.5	Ship-side valves and fittings (other than those on scuppers and sanitary discharges)
	2.6	Piping systems – Installation
	2.7	Provision for expansion
	2.8	Piping in way of refrigerated chambers
	2.9	Miscellaneous requirements
	2.10	Testing after installation
<b>Section</b>	<b>3</b>	<b>Drainage of compartments, other than machinery space</b>
	3.1	General
	3.2	Cargo holds
	3.3	Holds and deep tanks for alternative carriage of liquid or dry cargo
	3.4	Tanks and cofferdams
	3.5	Fore and after peaks
	3.6	Spaces above fore peaks, after peaks and machinery spaces
	3.7	Maintenance of integrity of bulkheads
<b>Section</b>	<b>4</b>	<b>Bilge drainage of machinery space</b>
	4.1	General
	4.2	Machinery space with double bottom
	4.3	Machinery space without double bottom
	4.4	Additional bilge suction
	4.5	Separate machinery spaces
	4.6	Machinery space – Emergency bilge drainage
	4.7	Tunnel drainage
<b>Section</b>	<b>5</b>	<b>Sizes of bilge suction pipes</b>
	5.1	Main bilge line
	5.2	Branch bilge suction to cargo and machinery spaces
	5.3	Direct bilge suction, other than emergency suction
	5.4	Main bilge line – Tankers and similar ships
	5.5	Distribution chest branch pipes
	5.6	Tunnel suction
<b>Section</b>	<b>6</b>	<b>Pumps on bilge service and their connections</b>
	6.1	Number of pumps
	6.2	General service pumps
	6.3	Capacity of pumps
	6.4	Self-priming pumps
	6.5	Pump connections
	6.6	Direct bilge suction
<b>Section</b>	<b>7</b>	<b>Piping systems and their fittings</b>
	7.1	Main bilge line suction
	7.2	Prevention of communication between compartments
	7.3	Isolation of bilge system
	7.4	Machinery space suction – Mud boxes
	7.5	Hold suction – Strum boxes
	7.6	Bilge wells
	7.7	Tail pipes
	7.8	Location of fittings
	7.9	Bilge pipes in way of double bottom tanks
	7.10	Bilge pipes in way of deep tanks
	7.11	Hold bilge non-return valves
	7.12	Blanking arrangements

<b>Section</b>	<b>8</b>	<b>Additional requirements for bilge drainage and cross-flooding arrangements for passenger ships</b>
	8.1	Location of bilge pumps and bilge main
	8.2	Prevention of communication between compartments in the event of damage
	8.3	Arrangement and control of bilge valves
	8.4	Cross-flooding arrangements
<b>Section</b>	<b>9</b>	<b>Additional requirements relating to fixed pressure water spray fire-extinguishing systems</b>
	9.1	Bilge drainage requirements
<b>Section</b>	<b>10</b>	<b>Drainage arrangements for ships not fitted with propelling machinery</b>
	10.1	Hand pumps
	10.2	Ships with auxiliary power
<b>Section</b>	<b>11</b>	<b>Ballast system</b>
	11.1	Stand-by arrangements for ballast pumping
<b>Section</b>	<b>12</b>	<b>Air, overflow and sounding pipes</b>
	12.1	Definitions
	12.2	Materials
	12.3	Nameplates
	12.4	Air pipes
	12.5	Termination of air pipes
	12.6	Gauze diaphragms
	12.7	Air pipe closing appliances
	12.8	Size of air pipes
	12.9	Overflow pipes
	12.10	Air and overflow systems
	12.11	Sounding arrangements
	12.12	Termination of sounding pipes
	12.13	Short sounding pipes
	12.14	Elbow sounding pipes
	12.15	Striking plates
	12.16	Sizes of sounding pipes
<b>CHAPTER</b>	<b>14</b>	<b>MACHINERY PIPING SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
<b>Section</b>	<b>2</b>	<b>Oil fuel – General requirements</b>
	2.1	Flash point
	2.2	Special fuels
	2.3	Oil fuel sampling
	2.4	Ventilation
	2.5	Boiler insulation and air circulation in boiler room
	2.6	Funnel dampers
	2.7	Heating arrangements
	2.8	Temperature indication
	2.9	Precautions against fire
	2.10	Oil fuel contamination

<b>Section</b>	<b>3</b>	<b>Oil fuel burning arrangements</b>
	3.1	Oil burning units
	3.2	Gravity feed
	3.3	Starting-up unit
	3.4	Steam connections to burners
	3.5	Burner arrangements
	3.6	Quick-closing valve
	3.7	Spill arrangements
	3.8	Alternately-fired furnaces
	3.9	Oil fuel treatment for supply to main and auxiliary oil engines and gas turbines
	3.10	Booster pumps
	3.11	Fuel valve cooling pumps
	3.12	Oil-fired galleys
<b>Section</b>	<b>4</b>	<b>Oil fuel pumps, pipes, fittings, tanks, etc.</b>
	4.1	Transfer pumps
	4.2	Control of pumps
	4.3	Relief valves on pumps
	4.4	Pump connections
	4.5	Pipes conveying oil
	4.6	Low pressure pipes
	4.7	Valves and cocks
	4.8	Valves on deep tanks and their control arrangements
	4.9	Water drainage from settling tanks
	4.10	Relief valves on oil heaters
	4.11	Filling arrangements
	4.12	Transfer arrangements – Passenger ships
	4.13	Alternative carriage of oil fuel and water ballast
	4.14	Deep tanks for the alternative carriage of oil, water ballast or dry cargo
	4.15	Separation of cargo oils from oil fuel
	4.16	Fresh water piping
	4.17	Separate oil fuel tanks
	4.18	Oil fuel service tanks
	4.19	Arrangements for fuels with a flash point between 43° and 60°
<b>Section</b>	<b>5</b>	<b>Steam piping systems</b>
	5.1	Provision for expansion
	5.2	Drainage
	5.3	Pipes in way of holds
	5.4	Reduced pressure lines
	5.5	Steam for fire-extinguishing in cargo holds
<b>Section</b>	<b>6</b>	<b>Boiler feed water and condensate systems</b>
	6.1	Feed water piping
	6.2	Feed pumps
	6.3	Harbour feed pumps
	6.4	Condensate pumps
	6.5	Valves and cocks
	6.6	Reserve feed water
<b>Section</b>	<b>7</b>	<b>Engine cooling water systems</b>
	7.1	Main supply
	7.2	Standby supply
	7.3	Selection of standby pumps
	7.4	Relief valves on main cooling water pumps
	7.5	Sea inlets
	7.6	Strainers
<b>Section</b>	<b>8</b>	<b>Lubricating oil systems</b>
	8.1	General requirements
	8.2	Pumps
	8.3	Alarms
	8.4	Emergency supply for propulsion turbines and propulsion turbo-generators
	8.5	Maintenance of bearing lubrication

	8.6	Filters
	8.7	Cleanliness of pipes and fittings
	8.8	Lubricating oil drain tank
	8.9	Lubricating oil contamination
	8.10	Deep tank valves and their control arrangements
<b>Section</b>	<b>9</b>	<b>Hydraulic systems</b>
	9.1	General
	9.2	System arrangements
<b>Section</b>	<b>10</b>	<b>Low pressure compressed air systems</b>
	10.1	General
	10.2	Compressors and reducing valves/stations
	10.3	Air receivers
	10.4	Distribution system
	10.5	Pneumatic remote control valves
	10.6	Control arrangements
<b>Section</b>	<b>11</b>	<b>Multi-engined ships</b>
	11.1	General
<b>CHAPTER</b>	<b>15</b>	<b>PIPING SYSTEMS FOR OIL TANKERS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Plans and particulars
	1.3	Materials
	1.4	Design
	1.5	Dangerous spaces
	1.6	Cargo pump room
	1.7	Cargo pump room ventilation
	1.8	Non-sparking fans for hazardous areas
	1.9	Slop tanks
	1.10	Steam connections to cargo tanks
<b>Section</b>	<b>2</b>	<b>Piping systems for bilge, ballast, oil fuel, etc.</b>
	2.1	Pumping arrangements at ends of ship outside dangerous zones and spaces
	2.2	Cargo pump room drainage
	2.3	Deep cofferdam drainage
	2.4	Drainage of ballast tanks and void spaces within the range of the cargo tanks
	2.5	Air and sounding pipes
	2.6	Ballast piping in pump room double bottoms
<b>Section</b>	<b>3</b>	<b>Cargo handling system</b>
	3.1	General
	3.2	Cargo pumps
	3.3	Cargo piping system
	3.4	Terminal fittings at cargo loading stations
	3.5	Bow or stern loading and discharge arrangements
	3.6	Connections to cargo tanks
	3.7	Remote control valves
	3.8	Cargo handling controls
<b>Section</b>	<b>4</b>	<b>Cargo tank venting, purging and gas-freeing</b>
	4.1	Cargo tank venting
	4.2	Cargo tank purging and/or gas-freeing
	4.3	Venting, purging and gas measurement of double hull and double bottom spaces
	4.4	Gas measurement
<b>Section</b>	<b>5</b>	<b>Cargo tank level gauging equipment</b>
	5.1	General
	5.2	Restricted sounding device
	5.3	Closed sounding devices

**Section 6 Cargo heating arrangements**

- 6.1 General
- 6.2 Blanking arrangements
- 6.3 Heating medium
- 6.4 Heating circuits
- 6.5 Temperature indication

**Section 7 Inert gas systems**

- 7.1 General
- 7.2 Gas supply
- 7.3 Gas scrubber
- 7.4 Gas blowers
- 7.5 Gas distribution lines
- 7.6 Venting arrangements
- 7.7 Instrumentation and alarms
- 7.8 Installation and tests

**CHAPTER 16 SPARE GEAR FOR MACHINERY INSTALLATIONS**

**Section 1 General**

- 1.1 Application
- 1.2 Tables of spare parts

**CHAPTER 17 REQUIREMENTS FOR FUSION WELDING OF PRESSURE VESSELS AND PIPING**

**Section 1 General**

- 1.1 Scope
- 1.2 General requirements for welding plant and welding quality

**Section 2 Manufacture and workmanship of fusion welded pressure vessels**

- 2.1 General requirements
- 2.2 Materials of construction
- 2.3 Cutting of materials
- 2.4 Forming shell sections and end plates
- 2.5 Fittings of shell plates and attachments
- 2.6 Welding during construction
- 2.7 Tolerances for cylindrical shells

**Section 3 Routine weld tests for pressure vessels**

- 3.1 General requirements for routine weld tests
- 3.2 Test plate requirements
- 3.3 Inspection and testing
- 3.4 Mechanical testing requirements
- 3.5 Failure to meet requirements

**Section 4 Repairs to welds on fusion welded pressure vessels**

- 4.1 General
- 4.2 Re-repairs

**Section 5 Post weld heat treatment of pressure vessels**

- 5.1 General
- 5.2 Basic requirements for heat treatment of fusion welded pressure vessels

**Section 6 Welded pressure pipes**

- 6.1 General
- 6.2 Fit-up and alignment
- 6.3 Welding workmanship
- 6.4 Heat treatment after bending of pipes
- 6.5 Post weld heat treatment of pipe welds

---

<b>Section</b>	<b>7</b>	<b>Non-Destructive Examination</b>
	7.1	General
	7.2	NDE personnel
	7.3	Extent of NDE
	7.4	Procedures
	7.5	Method
	7.6	Repairs
	7.7	Evaluation and reports
 <b>CHAPTER</b>	 <b>18</b>	 <b>INTEGRATED PROPULSION SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Plans
<b>Section</b>	<b>2</b>	<b>Machinery arrangements</b>
	2.1	Main propulsion machinery
	2.2	Supply of electric power and essential services
	2.3	Controllable pitch propellers
<b>Section</b>	<b>3</b>	<b>Control arrangements</b>
	3.1	Bridge control
	3.2	Alarm system
	3.3	Communication
	3.4	Engine starting safeguards
	3.5	Operational safeguards
	3.6	Automatic control of essential services
	3.7	Local control
 <b>CHAPTER</b>	 <b>19</b>	 <b>STEERING GEAR</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Definitions
	1.3	General
	1.4	Plans
	1.5	Materials
	1.6	Rudder, rudder stock, tiller and quadrant
<b>Section</b>	<b>2</b>	<b>Performance</b>
	2.1	General
	2.2	Rudder angle limiters
<b>Section</b>	<b>3</b>	<b>Construction and design</b>
	3.1	General
	3.2	Components
	3.3	Valve and relief valve arrangements
	3.4	Flexible hoses
<b>Section</b>	<b>4</b>	<b>Steering control systems</b>
	4.1	General
<b>Section</b>	<b>5</b>	<b>Electric power circuits, electric control circuits, monitoring and alarms</b>
	5.1	Electric power circuits
	5.2	Electric control circuits
	5.3	Monitoring and alarms
<b>Section</b>	<b>6</b>	<b>Emergency power</b>
	6.1	General

---

<b>Section</b>	<b>7</b>	<b>Testing and trials</b>
	7.1	Testing
	7.2	Trials
<b>Section</b>	<b>8</b>	<b>Additional requirements</b>
	8.1	For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards and every other ship of 70 000 tons gross and upwards
	8.2	For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards
	8.3	For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards but of less than 100 000 tons deadweight
<b>Section</b>	<b>9</b>	<b>'Guidelines' for the acceptance of non-duplicated rudder actuators for tankers, chemical tankers and gas carriers of 10 000 tons gross and upwards but of less than 100 000 tons deadweight</b>
	9.1	Materials
	9.2	Design
	9.3	Construction details
	9.4	Non-destructive testing
	9.5	Testing
	9.6	Additional requirements for steering gear fitted to ships with Ice Class notations
<b>CHAPTER</b>	<b>20</b>	<b>AZIMUTH THRUSTERS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Plans
<b>Section</b>	<b>2</b>	<b>Performance</b>
	2.1	General
<b>Section</b>	<b>3</b>	<b>Construction and design</b>
	3.1	Materials
	3.2	Design
	3.3	Steering gear elements
	3.4	Components
<b>Section</b>	<b>4</b>	<b>Control engineering arrangements</b>
	4.1	General
	4.2	Monitoring and alarms
<b>Section</b>	<b>5</b>	<b>Electrical equipment</b>
	5.1	General
	5.2	Generating arrangements
	5.3	Distribution arrangements
	5.4	Auxiliary supplies
<b>Section</b>	<b>6</b>	<b>Testing and trials</b>
	6.1	General
<b>CHAPTER</b>	<b>21</b>	<b>SHIPRIGHT PROCEDURES FOR MACHINERY PLANNED MAINTENANCE AND CONDITION MONITORING</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Classification notations and descriptive notes
	1.3	Information and plans required to be submitted
<b>Section</b>	<b>2</b>	<b>Machinery Planned Maintenance Scheme</b>
	2.1	Descriptive note <b>MPMS</b>
<b>Section</b>	<b>3</b>	<b>Machinery Condition Monitoring</b>
	3.1	Descriptive note <b>MCM</b>



---

<b>Section</b>	<b>4</b>	<b>Turbine Condition Monitoring</b>
	4.1	Descriptive note TCM
<b>Section</b>	<b>5</b>	<b>Screwshaft Condition Monitoring</b>
	5.1	Descriptive note SCM
<b>Section</b>	<b>6</b>	<b>Reliability Centred Maintenance</b>
	6.1	Descriptive note RCM
<b>CHAPTER</b>	<b>22</b>	<b>PROPULSION AND STEERING MACHINERY REDUNDANCY</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Plans and information
<b>Section</b>	<b>2</b>	<b>Failure Mode and Effects Analysis (FMEA)</b>
	2.1	General
<b>Section</b>	<b>3</b>	<b>Machinery arrangements</b>
	3.1	Main propulsion machinery
	3.2	Steering machinery
	3.3	Electrical power supply
	3.4	Essential services for machinery
	3.5	Oil fuel storage and transfer systems
<b>Section</b>	<b>4</b>	<b>Control arrangements</b>
	4.1	General
	4.2	Bridge control
<b>Section</b>	<b>5</b>	<b>Separate machinery spaces ★ (star) Enhancement</b>
	5.1	General
	5.2	Machinery arrangements
	5.3	Electrical power supply
	5.4	Essential services for machinery
	5.5	Bilge drainage arrangements
	5.6	Oil fuel storage
	5.7	FMEA
<b>Section</b>	<b>6</b>	<b>Testing and trials</b>
	6.1	Sea trials
<b>CHAPTER</b>	<b>23</b>	<b>PODDED PROPULSION UNITS</b>
<b>Section</b>	<b>1</b>	<b>Scope</b>
	1.1	General
<b>Section</b>	<b>2</b>	<b>General requirements</b>
	2.1	Pod arrangement
	2.2	Plans and information to be submitted
	2.3	Pod internal atmospheric conditions
	2.4	Global loads
	2.5	Failure Modes and Effects Analysis (FMEA)
	2.6	Ice Class requirements
<b>Section</b>	<b>3</b>	<b>Functional capability</b>
	3.1	General
<b>Section</b>	<b>4</b>	<b>Materials</b>
	4.1	General

---

<b>Section</b>	<b>5</b>	<b>Structure design and construction requirements</b>
	5.1	Pod structure
	5.2	Hull support structure
	5.3	Direct calculations
<b>Section</b>	<b>6</b>	<b>Machinery design and construction requirements</b>
	6.1	General
	6.2	Gearing
	6.3	Propulsion shafting
	6.4	Propeller
	6.5	Bearing lubrication system
	6.6	Steering system
	6.7	Ventilation and cooling systems
	6.8	Pod drainage requirements
	6.9	Hydraulic actuating systems
<b>Section</b>	<b>7</b>	<b>Electrical equipment</b>
	7.1	General
<b>Section</b>	<b>8</b>	<b>Control engineering arrangements</b>
	8.1	General
	8.2	Monitoring and alarms
<b>Section</b>	<b>9</b>	<b>Testing and trials</b>
	9.1	General
<b>Section</b>	<b>10</b>	<b>Installation, maintenance and replacement procedures</b>
	10.1	General

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 1

## Section

- 1 **General**
- 2 **Plans and particulars**
- 3 **Operating conditions**
- 4 **Machinery room arrangements**
- 5 **Trials**
- 6 **Quality Assurance Scheme for Machinery**

### ■ Scope

The Chapters in this Part cover the construction and installation of main propulsion and auxiliary machinery systems, together with their associated equipment, boilers, pressure vessels, pumping and piping arrangements and steering gear fitted in classed ships.

### ■ Section 1 General

#### 1.1 Machinery to be constructed under survey

1.1.1 In ships built under Special Survey, all important units of equipment are to be surveyed at the manufacturer's works. The workmanship is to be to the Surveyor's satisfaction and the Surveyor is to be satisfied that the components are suitable for the intended purpose and duty. Examples of such units are:

- Main propulsion engines including their associated gearing, flexible couplings, scavenge blowers and superchargers.
- Boilers supplying steam for propulsion or for services essential for the safety or the operation of the ship at sea, including superheaters, economizers, desuperheaters, steam heated steam generators and steam receivers. All other boilers having working pressures exceeding 3,4 bar (3,5 kgf/cm<sup>2</sup>), and having heating surfaces greater than 4,65 m<sup>2</sup>.
- Auxiliary engines which are the source of power for services essential for safety or for the operation of the ship at sea.
- Steering machinery.
- Athwartship thrust units, their prime movers and control mechanisms.
- All pumps necessary for the operation of main propulsion and essential machinery, e.g. boiler feed, cooling water circulating, condensate extraction, oil fuel and lubricating oil pumps.
- All heat exchangers necessary for the operation of main propulsion and essential machinery, e.g. air, water and lubricating oil coolers, oil fuel and feed water heaters, de-aerators and condensers, evaporators and distiller units.

- Air compressors, air receivers and other pressure vessels necessary for the operation of main propulsion and essential machinery. Any other unfired pressure vessels for which plans are required to be submitted as detailed in Ch 11, 1.6.
- All pumps essential for safety of the ship, e.g. fire, bilge and ballast pumps.
- Valves and other components intended for installation in pressure piping systems having working pressures exceeding 7 bar.
- Alarm and control equipment as detailed in Pt 6, Ch 1.
- Electrical equipment and electrical propelling machinery as detailed in Pt 6, Ch 2.

#### 1.2 Survey for classification

1.2.1 The Surveyors are to examine and test the materials and workmanship from the commencement of work until the final test of the machinery under full power working conditions. Any defects, etc., are to be indicated as early as possible. On completion, the Surveyors will submit a report and if this is found to be satisfactory by the Committee a certificate will be granted and an appropriate notation will be assigned in accordance with Pt 1, Ch 2.

#### 1.3 Alternative system of inspection

1.3.1 Where items of machinery are manufactured as individual or series produced units the Committee will be prepared to give consideration to the adoption of a survey procedure based on quality assurance concepts utilizing regular and systematic audits of the approved manufacturing and quality control processes and procedures as an alternative to the direct survey of individual items.

1.3.2 In order to obtain approval, the requirements of Section 6 are to be complied with.

#### 1.4 Departures from the Rules

1.4.1 Where it is proposed to depart from the requirements of the Rules, the Committee will be prepared to give consideration to the circumstances of any special case.

1.4.2 Any novelty in the construction of the machinery, boilers or pressure vessels is to be reported to the Committee.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Sections 2 & 3

### Section 2 Plans and particulars

#### 2.1 Plans

2.1.1 Before the work is commenced, plans in triplicate of all machinery items, as detailed in the Chapters giving the requirements for individual systems, are to be submitted for consideration. The particulars of the machinery, including power ratings, grade(s) of fuel and design calculations, where applicable, necessary to verify the design, are also to be submitted. Any subsequent modifications are subject to approval before being put into operation. It will not be necessary for plans and particulars to be submitted for each ship, provided the basis plans for the engine size and type have previously been approved as meeting the requirements of these Rules. Any alterations to basis design materials or manufacturing procedure are to be re-submitted for consideration.

#### 2.2 Materials

2.2.1 The materials used in the construction are to be manufactured and tested in accordance with the requirements of the Rules for Materials (Part 2). Materials for which provision is not made therein may be accepted, provided that they comply with an approved specification and such tests as may be considered necessary.

2.2.2 Materials used in the construction of machinery and installation should not be a recognized hazard to personnel. This includes the prohibition of asbestos except in the following applications:

- (a) Vanes used in rotary vane compressors and rotary vane pumps.
- (b) Watertight joints and linings used for the circulation of fluids when at high temperature (in excess of 350°C) or pressure (in excess of  $7 \times 10^6$  Pa) there is a risk of fire, corrosion or toxicity.
- (c) Supple and flexible thermal insulation assemblies used for temperatures above 1000°C.

### Section 3 Operating conditions

#### 3.1 Availability for operation

3.1.1 The design and arrangement are to be such that the machinery can be started and controlled on board ship, without external aid, so that the operating conditions can be maintained under all circumstances.

3.1.2 Machinery is to be capable of operating at defined power ratings with a range of fuel grades specified by the engine manufacturer and agreed by the Owner/Operator.

#### 3.2 Fuel

3.2.1 The flash point (closed cup test) of oil fuel for use in ships classed for unrestricted service is, in general, to be not less than 60°C.

3.2.2 For emergency generator engines, fuel having a flash point of not less than 43°C may be used.

3.2.3 Fuels with flash points lower than 60°C, but not less than 43°C unless specially approved, may be used in ships intended for service restricted to geographical limits where it can be ensured that the temperature of the machinery and boiler spaces will always be 10°C below the flash point of the fuel. In such cases, safety precautions and the arrangements for storage and pumping will be specially considered.

3.2.4 The use of fuel having a lower flash point than specified in 3.2.1 to 3.2.3 as applicable may be permitted provided that such fuel is not stored in any machinery space and the arrangements for the complete installation are specially approved.

3.2.5 For engines operating on 'boil-off' vapours from the cargo, see Lloyd's Register's (hereinafter referred to as 'LR') *Rules for Ships for Liquefied Gases*.

#### 3.3 Power ratings

3.3.1 In the Chapters where the dimensions of any particular component are determined from shaft power,  $P$ , in kW ( $H$ , in shp), and revolutions per minute,  $R$ , the values to be used are to be derived from the following:

- For main propelling machinery, the maximum shaft power and corresponding revolutions per minute giving the maximum torque for which the machinery is to be classed.
- For auxiliary machinery, the maximum continuous shaft power and corresponding revolutions per minute which will be used in service.

#### 3.4 Definitions

3.4.1 Main propulsion engines and turbines are defined as those which drive main propelling machinery directly or indirectly through mechanical shafting and which may also drive electrical generators to provide power for auxiliary services. Auxiliary engines and turbines are defined as those coupled to electrical generators which provide power for auxiliary services, for electrical main propulsion motors or a combination of both.

3.4.2 Units and formulae included in the Rules are shown in SI units followed by metric units in brackets, where appropriate.

3.4.3 Where the metric version of shaft power, i.e. (shp), appears in the Rules, 1 shp is equivalent to 75 kgf m/s or 0,735 kW.

3.4.4 Pressure gauges may be calibrated in bar, where:  
1 bar = 0,1 N/mm<sup>2</sup> = 1,02 kgf/cm<sup>2</sup>.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 3

### 3.5 Ambient reference conditions

3.5.1 The rating for classification purposes of main and essential auxiliary machinery intended for installation in sea-going ships to be classed for unrestricted (geographical) service is to be based on a total barometric pressure of 1000 mb, an engine room ambient temperature or suction air temperature of 45°C, a relative humidity of 60 per cent and sea-water temperature or, where applicable, the temperature of the charge air coolant at the inlet of 32°C. The engine manufacturer is not expected to provide simulated ambient reference conditions at a test bed.

3.5.2 In the case of a ship to be classed for restricted service, the rating is to be suitable for the temperature conditions associated with the geographical limits of the restricted service, see Pt 1, Ch 2.

### 3.6 Ambient operating conditions

3.6.1 Main and essential auxiliary machinery and equipment is to be capable of operating satisfactorily under the conditions shown in Table 1.3.1.

**Table 1.3.1 Ambient operating conditions**

Air		
Installations, Components	Location, arrangement	Temperature range (°C)
Machinery and electrical installations	In enclosed spaces	0 to +45, see Note 1
	On machinery component, boilers. In spaces subject to higher and lower temperatures	According to specific local conditions, see Note 2
	On the open deck	–25 to +45, see Note 1
Water		
Coolant		Temperature (°C)
Sea-water or charge air coolant inlet to charge air cooler		+32, see Note 1
NOTES 1. For ships intended to be classed for restricted service, a deviation from the temperatures stated may be considered. 2. Details of local environmental conditions are stated in Annex B of IEC 60092: <i>Electrical installations in ships – Part 101: Definitions and general requirements</i> .		

### 3.7 Inclination of ship

3.7.1 Main and essential auxiliary machinery is to operate satisfactorily under the conditions as shown in Table 1.3.2.

3.7.2 Any proposal to deviate from the angles given in Table 1.3.2 will be specially considered taking into account the type, size and service conditions of the ship.

**Table 1.3.2 Inclination of ship**

Installations, components	Angle of inclination, degrees, see Note 1			
	Athwartships		Fore-and-aft	
	Static	Dynamic	Static	Dynamic
Main and auxiliary machinery essential to the propulsion and safety of the ship	15	22,5	5 see Note 2	7,5
Emergency machinery and equipment fitted in accordance with Statutory Requirements	22,5 see Note 3	22,5	10	10
NOTES 1. Athwartships and fore-and-aft inclinations may occur simultaneously. 2. Where the length of the ship exceeds 100 m, the fore-and-aft static angle of inclination may be taken as: $\frac{500}{L} \text{ degrees}$ where $L$ = length of ship, in metres. 3. In ships for the carriage of liquefied gas and of liquid chemicals the emergency machinery and equipment fitted in accordance with Statutory Requirements is also to remain operable with the ship flooded to a final athwartships inclination to a maximum angle of 30°.				

3.7.3 The dynamic angles of inclination in Table 1.3.2 may be exceeded in certain circumstances dependent upon ship type and operation. The Shipbuilder is, therefore, to ensure that the machinery is capable of operating under these angles of inclination.

### 3.8 Power conditions for generator sets

3.8.1 Auxiliary engines coupled to electrical generators are to be capable under service conditions of developing continuously the power to drive the generators at full rated output (kW) and in the case of oil engines and gas turbines, of developing for a short period (15 minutes) an overload power of not less than 10 per cent, see Pt 6, Ch 2,8.2.

3.8.2 Engine builders are to satisfy the Surveyors by tests on individual engines that the above requirements, as applicable, can be complied with, due account being taken of the difference between the temperatures under test conditions and those referred to in 3.5. Alternatively, where it is not practicable to test the engine/generator set as a unit, type tests (e.g. against a brake) representing a particular size and range of engines may be accepted. With oil engines and gas turbines any fuel stop fitted is to be set to permit the short period overload power of not less than 10 per cent above full rated output (kW) being developed.

### 3.9 Astern power

3.9.1 Sufficient astern power is to be provided to maintain control of the ship in all normal circumstances.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Sections 3 & 4

3.9.2 Astern turbines are to be capable of maintaining in free route astern 70 per cent of the ahead revolutions, corresponding to the maximum propulsion shaft power for which the machinery is to be classed, for a period of at least 30 minutes without undue heating of the ahead turbines and condensers.

### 3.10 Machinery interlocks

3.10.1 Interlocks are to be provided to prevent any operation of engines or turbines under conditions that could hazard the machinery and personnel. These are to include 'turning gear engaged', 'low lubricating oil pressure', where oil pressure is essential for the prevention of damage during start up, 'shaft brake engaged' and where machinery is not available due to maintenance or repairs. The interlock system is to be arranged to be 'fail safe'.

3.10.2 Where machinery is provided with manual turning gear, warning devices or notices may be provided as an alternative to interlocks as required by 3.10.1.

## Section 4 Machinery room arrangements

### 4.1 Accessibility

4.1.1 Accessibility, for attendance and maintenance purposes, is to be provided for machinery plants.

### 4.2 Machinery fastenings

4.2.1 Bedplates, thrust seatings and other fastenings are to be of robust construction, and the machinery is to be securely fixed to the ship's structure to the satisfaction of the Surveyor.

### 4.3 Resilient mountings

4.3.1 The dynamic angles of inclination in Table 1.3.2 may be exceeded in certain circumstances dependent upon ship type and operation. The Shipbuilder is, therefore, to ensure that the vibration levels of flexible pipe connections, shaft couplings and mounts remain within the limits specified by the component manufacturer for the conditions of maximum dynamic inclinations to be expected during service, start-stop operation and the natural frequencies of the system. Due account is to be taken of any creep that may be inherent in the mount.

4.3.2 Anti-collision chocks are to be fitted together with positive means to ensure that manufacturers' limits are not exceeded. Suitable means are to be provided to accommodate the propeller thrust.

4.3.3 A plan showing the arrangement of the machinery together with documentary evidence of the foregoing is to be submitted.

### 4.4 Ventilation

4.4.1 All spaces including engine and cargo pump spaces, where flammable or toxic gases or vapours may accumulate, are to be provided with adequate ventilation under all conditions.

4.4.2 Machinery spaces shall be sufficiently ventilated so as to ensure that when machinery or boilers therein are operating at full power in all weather conditions, including heavy weather, a sufficient supply of air is maintained to the spaces for the operation of the machinery.

### 4.5 Fire protection

4.5.1 All surfaces of machinery where the surface temperature may exceed 220°C and where impingement of flammable liquids may occur are to be effectively shielded to prevent ignition. Where insulation covering these surfaces is oil-absorbing or may permit penetration of oil, the insulation is to be encased in steel or equivalent.

### 4.6 Means of escape

4.6.1 For means of escape from machinery spaces, see SOLAS 1974 as amended Regulation II-2/13.4.1 or 13.4.2 or Pt 6, Ch 4,3.4, as applicable.

### 4.7 Communications

4.7.1 Two independent means of communication are to be provided between the bridge and engine room control station from which the engines are normally controlled, see *also* Pt 6, Ch 1,2.

4.7.2 One of these means is to visually indicate the order and response, both at the engine room control station and on the bridge.

4.7.3 At least one means of communication is to be provided between the bridge and any other control position(s) from which the propulsion machinery may be controlled.

### 4.8 Category A machinery spaces

4.8.1 'Machinery spaces of Category A' are those spaces and trunks to such spaces which contain:

- (a) internal combustion machinery used for main propulsion; or
- (b) internal combustion machinery used for purposes other than main propulsion where such machinery has in the aggregate a total power output of not less than 375 kW; or
- (c) any oil-fired boiler or oil fuel unit.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Sections 5 & 6

### ■ Section 5 Trials

#### 5.1 Inspection

5.1.1 Tests of components and trials of machinery, as detailed in the Chapters giving the requirements for individual systems, are to be carried out to the satisfaction of the Surveyors.

#### 5.2 Sea trials

5.2.1 For all types of installation, the sea trials are to be of sufficient duration, and carried out under normal manoeuvring conditions, to prove the machinery under power. The trials are also to demonstrate that any vibration which may occur within the operating speed range is acceptable.

5.2.2 The trials are to include demonstrations of the following:

- (a) The adequacy of the starting arrangements to provide the required number of starts of the main engines.
- (b) The ability of the machinery to reverse the direction of thrust of the propeller in sufficient time, under normal manoeuvring conditions, and so bring the ship to rest from maximum service speed. Results of the trials are to be recorded.
- (c) In turbine installations, the ability to permit astern running at 70 per cent of the full power ahead revolutions without adverse effects. This astern trial need only be of 15 minutes' duration, but may be extended to 30 minutes at the Surveyor's discretion.

5.2.3 Where controllable pitch propellers are fitted, the free route astern trial is to be carried out with the propeller blades set in the full pitch astern position. Where emergency manual pitch setting facilities are provided, their operation is to be demonstrated to the satisfaction of the Surveyors.

5.2.4 In geared installations, prior to full power sea trials, the gear teeth are to be suitably coated to demonstrate the contact markings, and on conclusion of the sea trials all gears are to be opened up sufficiently to permit the Surveyors to make an inspection of the teeth. The marking is to indicate freedom from hard bearing, particularly towards the ends of the teeth, including both ends of each helix where applicable. The contact is to be not less than that required by Ch 5,4.2 or Ch 5,5.2, as applicable.

5.2.5 The stopping times, ship headings and distances recorded on trials, together with the results of trials to determine the ability of ships having multiple propellers to navigate and manoeuvre with one or more propellers inoperative, are to be available on board for the use of the master or designated personnel.

5.2.6 Where the ship is provided with supplementary means for manoeuvring or stopping, the effectiveness of such means are to be demonstrated and recorded as referred to in 5.2.5.

5.2.7 All trials are to be to the Surveyor's satisfaction.

### ■ Section 6 Quality Assurance Scheme for Machinery

#### 6.1 General

6.1.1 This certification scheme is applicable to both individual and series produced items manufactured under closely controlled conditions and will be restricted to works where the employment of quality control procedures is well established. LR will have to be satisfied that the practices employed will ensure that the quality of finished products is to standards which would be demanded when using traditional survey techniques.

6.1.2 The Committee will consider proposed designs for compliance with LR's Rules or other appropriate requirements and the extent to which the manufacturing processes and control procedure ensure conformity of the product to the design. A comprehensive survey will be made by the Surveyors of the actual operation of the quality control programme and of the adequacy and competence of the staff to implement it.

6.1.3 The procedures and practices of manufacturers which have been granted approval will be kept under review.

6.1.4 Approval by another organization will not be accepted as sufficient evidence that a manufacturer's arrangements comply with LR's requirements.

#### 6.2 Requirements for approval

6.2.1 **Facilities.** The manufacturer is required to have adequate equipment and facilities for those operations appropriate to the level of design, development and manufacture being undertaken.

6.2.2 **Experience.** The manufacturer is to demonstrate that the firm has experience consistent with technology and complexity of the product type for which approval is sought and that the firm's products have been of a consistently high standard.

6.2.3 **Quality policy.** The manufacturer is to define management policies and objectives or quality and ensure that these policies and objectives are implemented and maintained throughout all phases of the work.

6.2.4 **Quality system documentation.** The manufacturer is to establish and maintain a documented quality system capable of ensuring that material or services conform to the specified requirements, including the requirements of this Section.

6.2.5 **Management representative.** The manufacturer is to appoint a management representative preferably independent of other functions, who is to have defined authority and responsibilities for the implementation and maintenance of the quality system.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 6

**6.2.6 Responsibility and authority.** The responsibilities and authorities of senior personnel within the quality system are to be clearly documented.

**6.2.7 Internal audit.** The manufacturer is to conduct internal audits to ensure continued adherence to the system. An audit programme is to be established with audit frequencies scheduled on the basis of the status and importance of the activity and adjusted on the basis of previous results.

**6.2.8 Management review.** The quality system established in accordance with the requirements of this Section is to be systematically reviewed at appropriate intervals by the manufacturer to ensure its continued effectiveness. Records of such management reviews are to be maintained and be made available to the Surveyors.

**6.2.9 Contract review.** The manufacturer is to establish and implement procedures for conducting a contract review prior to and after acceptance to ensure that:

- (a) the requirements of the contract are adequately defined and documented;
- (b) any requirements differing from those specified in the original enquiry/tender are resolved; and
- (c) the manufacturer has the capability to meet and verify compliance to the specified requirements.

**6.2.10 Work instruction.** The manufacturer is to establish and maintain clear and complete written work instructions that prescribe the communication of specified requirements and the performance of work in design, development and manufacture which would be adversely affected by lack of such instructions.

**6.2.11 Documentation and change control.** The manufacturer is to establish and maintain control of all documentation that relates to the requirements of this scheme. This control is to ensure that:

- (a) documents are reviewed and approved for adequacy by authorized personnel prior to use, are uniquely identified and include indication of approval and revision status;
- (b) all changes to documentation are in writing and are processed in a manner that will ensure their availability at the appropriate location and preclude the use of non-applicable documents;
- (c) provision is made for the prompt removal of obsolete documentation from all points of issue or use; and
- (d) documents are to be re-issued after a practical number of changes have been issued.

**6.2.12 Records.** The manufacturer is to develop and maintain a system for collection, use and storage of quality records. The period of retention of such records is to be established in writing and is to be subject to agreement by the Committee.

**6.2.13 Design.** The manufacturer is to establish and maintain a design control system appropriate to the level of design being undertaken. Documented design procedures are to be established which:

- (a) identify the design practices of the manufacturer's organization including departmental instructions to ensure the orderly and controlled preparation of design and subsequent verification;
- (b) make provision for the identification, documentation and appropriate approval of all design change and modifications;
- (c) prescribe methods for resolving incomplete, ambiguous or conflicting requirements; and
- (d) identify design inputs such as sources of data, preferred standard parts or materials and design information and provide procedures for their selection and review by the manufacturer for adequacy.

**6.2.14 Purchasing.** The manufacturer is to ensure that purchased material and services conform to specified requirements.

**6.2.15 Selection and approval of sub-contractors and suppliers.** The manufacturer is to establish and maintain records of acceptable suppliers and sub-contractors. The selection of such sources, and the type and extent of control exercised, are to be appropriate to the type of product or service and the suppliers' or sub-contractors' previously demonstrated capability and performance. Documented procedures for approval of new suppliers are to be established and records of vendor assessments (where carried out) are to be maintained and made available to the Surveyors upon request.

**6.2.16 Purchasing data.** Each purchasing document should contain a clear description of the material or service ordered including as applicable, the following:

- (a) The type, class, grade, or other precise identification;
- (b) The title or other positive identification and applicable issue of specifications, drawings, process requirements, inspection instructions and other relevant data.

**6.2.17 Verification of purchased material and services.** The manufacturer is to ensure that the Surveyors are afforded the right to verify at source or upon receipt that purchased material and services conform to specified requirements. Verification by the Surveyors shall not relieve the manufacturer of his responsibility to provide acceptable material nor is it to preclude subsequent rejection.

**6.2.18 Product identification.** The manufacturer is to establish and maintain a system for identification of the product to relevant drawings, specifications or other documents during all stages of production, delivery and installation.

**6.2.19 Manufacturing control.** The manufacturer is to ensure that those operations which directly affect quality are carried out under controlled conditions. These are to include the following:

- (a) Written work instructions wherever the absence of such instructions could adversely affect compliance with specified requirements. These should define the method of monitoring and control of product characteristics.
- (b) Established criteria for workmanship through written standards or representative samples.



# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 6

**6.2.20 Special processes.** Those processes where effectiveness cannot be verified by subsequent inspection and test of the product are to be subjected to continuous monitoring in accordance with documented procedures in addition to the requirements specified in 6.2.19.

**6.2.21 Receiving inspection.** The manufacturer is to ensure that all incoming material is not to be used or processed until it has been inspected or otherwise verified as conforming to specified requirements. In establishing the amount and nature of receiving inspection, consideration is to be given to the control exercised by the supplier and documented evidence of quality conformance supplied.

**6.2.22 In-process inspection.** The manufacturer is to:

- (a) perform inspection during manufacture on all characteristics that cannot be inspected at a later stage;
- (b) inspect test and identify products in accordance with specified requirements;
- (c) establish product conformance to specified requirements by use of process monitoring and control methods where appropriate;
- (d) hold products until the required inspections and tests are completed and verified; and
- (e) clearly identify non-conforming products to prevent unauthorized use, shipment, or mixing with conforming material.

**6.2.23 Final inspection.** The manufacturer is to perform all inspections and tests on the finished product necessary to complete the evidence of conformance to the specified requirements. The procedures for final inspection and test are to ensure that:

- (a) all activities defined in the specification, quality plan or other documented procedure have been completed;
- (b) all inspections and tests that should have been conducted at earlier stages have been completed and that the data is acceptable; and
- (c) no product is to be dispatched until all the activities defined in the specifications, quality plan or other documented procedure have been completed, unless products have been released with the permission of the Surveyors.

**6.2.24 Inspection equipment.** The manufacturer is to be responsible for providing, controlling, calibrating and maintaining the inspection, measuring and test equipment necessary to demonstrate the conformance of material and services to the specified requirements or used as part of the manufacturing control system required by 6.2.19 and 6.2.20.

**6.2.25 Inspection and test status.** The manufacturer is to establish and maintain a system for the identification of inspection status of all material, components and assemblies by suitable means which distinguish between conforming, non-conforming and uninspected items. The relevant inspection and test procedures and records are to identify the authority responsible for the release of conforming products.

**6.2.26 Control of non-conforming material.**

- (a) The manufacturer is to establish and maintain procedures to ensure that material that does not conform to the specified requirements is controlled to prevent inadvertent use, mixing or shipment. Repair, rework or concessions on non-conforming material and reinspection is to be in accordance with documented procedures.
- (b) Records clearly identifying the material, the nature and extent of non-conformance and the disposition are to be maintained.

**6.2.27 Sampling procedures.** Where sampling techniques are used by the manufacturer to verify the acceptability of groups of products, the procedures adopted are to be in accordance with the specified requirements or are to be subject to agreement by the Surveyors.

**6.2.28 Corrective action.** The manufacturer is to establish and maintain documented procedures for the review of non-conformances and their disposition. These should provide for:

- (a) monitoring of process and work operations and analysis of records to detect and eliminate potential causes of non-conforming material;
- (b) continuing analysis of concessions granted and material scrapped or reworked to determine causes and the corrective action required;
- (c) an analysis of customer complaints;
- (d) the initiation of appropriate action with suppliers or sub-contractors with regard to receipt of non-conforming material; and
- (e) an assurance that corrective actions are effective.

**6.2.29 Purchaser supplied material.** The manufacturer is to establish and maintain documented procedures for the control of purchaser supplied material.

**6.2.30 Handling, storage, and delivery.**

- (a) The manufacturer is to establish and maintain a system for the identification preservation, segregation and handling of all material from the time of receipt through the entire production process. The system is to include methods of handling that prevent abuse, misuse, damage or deterioration.
- (b) Secure storage areas or rooms are to be provided to isolate and protect material pending use. To detect deterioration, at an early stage, the condition of material is to be periodically assessed.
- (c) The manufacturer is to arrange for the protection of the quality of his product during transit. The manufacturer is to ensure, in so far as it is practicable, the safe arrival and ready identification of the product at destination.

**6.2.31 Training.** The manufacturer is to follow a policy for recruitment and training which provides an adequate labour force with such skills as are required for each type of work operation. Appropriate records are to be maintained to demonstrate that all personnel performing process control, special processes inspection and test or quality system maintenance activities have appropriate experience or training.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 6

### 6.3 Arrangements for acceptance and certification of purchased material

6.3.1 The manufacturer is to establish and maintain procedures and controls to ensure compliance with LR's requirements for certification of materials and components at the supplier's plant. The manufacturer's system for control of such purchased material may be based on one of the following alternatives subject to the approval of LR:

- (a) Product certification by LR's Surveyors at the supplier's works in accordance with the requirements of the Rules for Materials (Part 2).
- (b) Agreed Inspection Procedures at the manufacturer's plant combined with documentary evidence of vendor assessments, vendor rating records and annual surveillance visits to the suppliers.
- (c) Recognition of quality agreements between the manufacturer and his suppliers which are to provide for initial vendor assessments and regular surveillance visits (a minimum of four per year). The quality agreement must identify the individual in the supplier's plant who is charged with the responsibility for release of materials or components and the procedures to be adopted.

6.3.2 The alternatives proposed in 6.3.1(b) and (c) are not acceptable to LR for the following items:

- (a) Engine components for which testing is a Rule requirement; and
  - (i) the cylinder bore is equal to or exceeds 300 mm; or
  - (ii) which are made by open forging techniques.
- (b) Cast crankshafts where the journal diameter exceeds 85 mm.

6.3.3 Where the manufacturer's system for control of purchased material is based upon 6.3.1(b) or (c) the Surveyors shall also make surveillance visits to the supplier's works at the minimum specified intervals. The manufacturer is also to make available to the Surveyors documentary evidence of the operation of quality agreements or Agreed Inspection Procedures where applicable.

### 6.4 Information required for approval

6.4.1 Manufacturers applying for approval under this scheme are to submit the following information:

- (a) A description of the products for which certification is required including, where applicable, model or type number.
- (b) Applicable plans and details of material used.
- (c) An outline description of all important manufacturing plant and equipment.
- (d) A summary of equipment used for measuring and testing during manufacture and completion.
- (e) The Quality Manual.
- (f) A typical production flow chart and quality plan covering all stages from ordering of materials to delivery of the finished product.
- (g) The system used for the identification of raw materials, semi-finished and finished products.
- (h) The number and qualifications of all staff engaged in testing, inspection and quality control duties.

- (j) A list of suppliers of components and manufacturers, proposed procedures to ensure compliance with LR's requirements for certification of materials and components at the supplier's plant.

### 6.5 Assessment of works

6.5.1 After receipt and appraisal of the information requested in 6.4 an inspection of the works is to be carried out by the Surveyors to examine in detail all aspects of production, and in particular the arrangements for quality control.

6.5.2 The Surveyors will not specify in detail acceptable quality control procedures, but will consider the arrangements proposed by the works in relation to the manufacturing processes and products.

6.5.3 In the event of procedures being considered inadequate, the Surveyors will advise the manufacturer how such procedures are to be revised in order to be acceptable to LR.

6.5.4 Gauging, measuring and testing devices are to be made available to the Surveyors, and where appropriate, personnel for the operation of such devices.

### 6.6 Approval of works

6.6.1 If the initial assessment of the works confirms that the manufacturing and quality control procedures are satisfactory, the Committee will issue to the manufacturer a Quality Assurance Approval Certificate which will include details of the products for which approval has been given. This Certificate will be valid for three years with renewal subject to satisfactory performance and to a satisfactory triennial re-assessment.

6.6.2 An extension of approval in respect of product type may be given at the discretion of the Committee without any additional survey of the works.

6.6.3 LR will publish a list of manufacturers whose works have been approved.

### 6.7 Maintenance of approval

6.7.1 The arrangements authorized at each works are to be kept under review by the Surveyors in order to ensure that the approved procedures for manufacture and quality control are being maintained in a satisfactory manner. This is to be carried out by:

- (a) regular and systematic surveillance;
- (b) intermediate audits at intervals of six months;
- (c) triennial re-assessment of the entire quality system.

6.7.2 For the purpose of regular and systematic surveillance the Surveyors are to visit the works at intervals determined by the type of product and the rate of production. The Surveyors are to advise a senior member of the quality control department in regard to any matter with which they are not satisfied.

# General Requirements for the Design and Construction of Machinery

## Part 5, Chapter 1

Section 6

6.7.3 When minor deficiencies in the approved procedures are disclosed during the systematic surveillance the Surveyors may, at their discretion, apply more intensive supervision, including the direct inspection of products.

6.7.4 Any noteworthy departures from the approved plans of specifications are to be reported to the Surveyors and their written approval obtained prior to despatch of the item.

6.7.5 Minor alterations in the approved procedures may be permitted provided that the Surveyors are advised and their prior concurrence obtained.

6.7.6 In addition to the regular visits by the Surveyors, an intermediate audit is to be carried out every six months. This will normally be carried out by Surveyors other than those regularly in attendance at the works. This audit is to consist of an examination of part of the manufacturer's quality system. An audit plan will be established indicating those areas of the quality system which will be examined during every intermediate audit and the frequency of examination of other areas such that all areas are subject to audit before re-assessment is due.

6.7.7 The manufacturer's entire quality system is to be subject to re-assessment at three-yearly intervals. This is to be conducted by Surveyors nominated by Headquarters.

### 6.8 Suspension or withdrawal of approval

6.8.1 When the Surveyors have drawn attention to significant faults or deficiencies in the manufacturing or quality control procedures and these have not been rectified, approval of the works will be suspended. In these circumstances the manufacturer will be notified in writing of the Committee's reasons for the suspension of approval.

6.8.2 When approval has been suspended and the manufacturer does not effect corrective measures within a reasonable time, the Committee will withdraw the Quality Assurance Approval Certificate.

### 6.9 Identification of products

6.9.1 In addition to the normal marking by the manufacturer, all certified products are to be hard stamped on a principal component with a suitable identification, LR's brand and the number of the approved works.

6.9.2 After issue of the Quality Assurance Approval Certificate, products may be dispatched with certificates signed on behalf of the manufacturer by an authorized senior member of the quality control department or by an authorized deputy. These certificates are to be countersigned by the Surveyor to certify that the approved arrangements are being kept under review by regular and systematic auditing of the manufacturer's quality system.

6.9.3 The following declarations are to be included on each certificate:

(a) 'This is to certify that the items described above have been constructed and tested with satisfactory results in accordance with the Rules of Lloyd's Register.

Signed.....  
Manager of QC Department.'

(b) 'This certificate is issued by the manufacturer in accordance with the arrangements authorized by Lloyd's Register in Quality Assurance Approval Certificate No. QA.M..... I certify that these arrangements are being kept under review by regular and systematic auditing of the approved manufacturing and quality control procedures.

Signed.....  
Surveyor to Lloyd's Register'.

6.9.4 In the event of noteworthy departures from the approved plan or specification being accepted, a standard 'Concession' form is to be completed and signed by the following authorized persons: the Design Manager, the Quality Control Manager or their deputies. In all cases, where strength or functioning may be affected, the form is to be submitted to the Surveyors for approval and endorsement.



## Section

- 1 **Plans and particulars**
- 2 **Materials**
- 3 **Design**
- 4 **Construction and welded structures**
- 5 **Safety arrangements on engines**
- 6 **Crankcase safety fitting**
- 7 **Piping**
- 8 **Starting arrangements and air compressors**
- 9 **Component tests and engine type testing**
- 10 **Turbo-chargers**
- 11 **Mass produced engines**
- 12 **Mass produced turbo-chargers**
- 13 **Type testing procedure for crankcase explosion relief valves**
- 14 **Type testing procedure for crankcase oil mist detection/monitoring and alarm arrangements**
- 15 **Electronically controlled engines**
- 16 **Alarms and safeguards for emergency diesel engines**
- 17 **General requirements**
- 18 **Program for trials of diesel engines to assess operational capability**

## ■ Scope

The requirements of this Chapter are applicable to oil engines (generally known as diesel engines) for main propulsion and to engines intended for essential auxiliary services. Section 3 is not applicable to auxiliary engines having powers of less than 110 kW.

The requirements for type testing of engines at the manufacturer's works are also included.

Arrangements for dual fuel engines will be specially considered.

## ■ Section 1 Plans and particulars

### 1.1 Plans

1.1.1 The following plans and particulars as applicable are to be submitted for consideration:

- Crankshaft assembly plan (for each crank-throw).
- Crankshaft details plan (for each crank-throw).
- Thrust shaft or intermediate shaft (if integral with engine).
- Output shaft coupling bolts.
- Main engine securing arrangements where non-metallic chocks are used.
- Type and arrangement of crankcase explosion relief valves.
- Arrangement and welding specifications with details of the procedures for fabricated bedplate, thrust bearing bedplate, crankcases, frames and entablatures. Details of materials welding consumables, fit-up conditions fabrication sequence and heat treatments are to be included.
- Schematic layouts of the following systems. See also 1.1.4:
  - Starting air.
  - Oil fuel.
  - Lubricating oil.
  - Cooling water.
  - Control and safety.
  - Hydraulic oil (for valve lift)
- Shielding of high pressure fuel pipes.
- Combustion pressure-displacement relationship.
- Crankshaft design data as outlined in Section 3.
- High pressure parts for fuel oil injection system with specification of pressures, pipe dimensions and materials.
- For new engine types that have not been approved by LR, the proposed type test programme.
- The type test report on completion of type testing for a new engine type. For mass produced engines a separate report is to be submitted for each engine requiring approval, see 11.5.
- The specification for a mass produced engine including manufacturing processes and quality control procedures, see 11.1.4 and 11.2.3.
- Schematic layouts showing details and arrangements of oil mist detection/monitoring and alarm systems.

1.1.2 The following plans are to be submitted for information:

- Longitudinal and transverse cross-section.
- Cast bedplate, thrust bearing bedplate, crankcase and frames.
- Cylinder head assembly.
- Cylinder liner.
- Piston assembly.
- Tie rod.
- Connecting rod, piston rod, and crosshead assemblies.
- Camshaft drive and camshaft general arrangement.
- Shielding and insulation of exhaust pipes.
- Details of turbochargers, see Section 10.
- Operation and service manuals.
- Vibration dampers/detuners and moment compensators.
- Thrust bearing assembly (if integral with engine and not integrated in the bedplate).
- Counterweights, where attached to crank-throw, including fastening.
- Main engine holding down arrangement (metal chocks).

1.1.3 Material specifications covering the listed components in 1.1.1 and 1.1.2 are to be forwarded together with details of any surface treatments, non-destructive testing and hydraulic tests.

1.1.4 Where engines incorporate electronic control systems, a failure mode and effects analysis (FMEA) is to be submitted to demonstrate that failure of an electronic control system will not result in the loss of essential services for the operation of the engine and that operation of the engine will not be lost or degraded beyond an acceptable performance criteria of the engine. This is concerned with the functioning of the control system and not failure of the software itself.

1.1.5 Where considered necessary Lloyd's Register (hereinafter referred to as 'LR') may require additional documentation to be submitted.

1.1.6 For engine types built under license it is intended that the above documentation be submitted by the Licensor. Each Licensee is then to submit the following:

- A list, based on the above, of all documents required with the relevant drawing numbers and revision status from both Licensor and Licensee.
- The associated documents where the Licensee proposes design modifications to components. In such cases a statement is to be made confirming the Licensor's acceptance of the proposed changes.

In all cases a complete set of endorsed documents will be required by the Surveyor(s) attending the Licensee's works.

1.1.7 Plans and details for dead ship condition starting arrangements are to be submitted for appraisal, see 8.1.

## 2.2 Material test and inspections

2.2.1 Components for engines are to be tested as indicated in Table 2.2.1 and in accordance with the relevant requirements of the Rules for Materials.

2.2.2 For components of novel design special consideration will be given to the material test and non-destructive testing requirements.

## ■ Section 2 Materials

### 2.1 Crankshaft materials

2.1.1 The specified minimum tensile strength of castings and forgings for crankshafts is to be selected within the following general limits:

- (a) Carbon and carbon-manganese steel castings – 400 to 550 N/mm<sup>2</sup>
- (b) Carbon and carbon-manganese steel forgings (normalized and tempered) – 400 to 600 N/mm<sup>2</sup>
- (c) Carbon and carbon-manganese steel forgings (quenched and tempered) – not exceeding 700 N/mm<sup>2</sup>
- (d) Alloy steel castings – not exceeding 700 N/mm<sup>2</sup>
- (e) Alloy steel forgings – not exceeding 1000 N/mm<sup>2</sup>
- (f) Spheroidal or nodular graphite iron castings – 370 to 800 N/mm<sup>2</sup>.

2.1.2 Where it is proposed to use alloy castings, micro alloyed or alloy steel forgings or iron castings, details of the chemical composition, heat treatment and mechanical properties are to be submitted for approval.

**Table 2.2.1 Test requirements for oil engine components**

Component	Material tests	Non-destructive tests	
		Magnetic particle or Liquid penetrant	Ultrasonic
Crankshaft	all	all	all
Crankshaft coupling flange (non-integral) for main propulsion engines	above 400 mm bore	–	–
Crankshaft coupling bolts	above 400 mm bore	–	–
Steel piston crowns	above 400 mm bore	above 400 mm bore	all
Piston rods	above 400 mm bore	above 400 mm bore	above 400 mm bore
Connecting rods, including bearing caps	all	all	above 400 mm bore
Crosshead	above 400 mm bore	–	–
Cylinder liner	above 300 mm bore	–	–
Cylinder cover	above 300 mm bore	above 400 mm bore	all
Steel castings for welded bedplates	all	all	all
Steel forgings for welded bedplates	all	–	–
Plates for welded bedplates, frames and entablatures	all	–	–
Crankcases, welded or cast	all	–	–
Tie rods	all	above 400 mm bore	–
Turbo-charger, shaft and rotor	above 300 mm bore	–	–
Bolts and studs for cylinder covers, crossheads, main bearings, connecting rod bearings	above 300 mm bore	above 400 mm bore	–
Steel gear wheels for camshaft drives	above 400 mm bore	above 400 mm bore	–
<b>NOTES</b> 1. For closed-die forged crankshafts the ultrasonic examination may be confined to the initial production and to subsequent occasional checks. 2. Magnetic particle or liquid penetrant testing of tie rods may be confined to the threaded portions and the adjacent material over a length equal to that of the thread. 3. Cylinder covers and liners manufactured from spheroidal or nodular graphite iron castings may not be suitable for ultrasonic NDE, depending upon the grain size and geometry. An alternative NDE procedure is to be agreed with LR. 4. Bore dimensions refer to engine cylinder bores. 5. All required material tests are to be witnessed by the Surveyor unless alternative arrangements have been specifically agreed by LR. 6. For mass produced engines, see Section 11.			

## ■ Section 3 Design

### 3.1 Scope

3.1.1 The formulae given in this Section are applicable to solid, or semi-built crankshafts, having a main support bearing adjacent to each crankpin, and are intended to be applied to a single crankthrow analysed by the static determinate method.

3.1.2 Alternative methods, including a fully documented stress analysis, will be specially considered.

3.1.3 Calculations are to be carried out for the maximum continuous power rating for all intended operating conditions.

3.1.4 Designs of crankshafts not included in this scope will be subject to special consideration.

### 3.2 Information to be submitted

3.2.1 In addition to detailed dimensioned plans, the following information is required to be submitted:

- Engine type – 4SCSA/2SCSA/in-line/vee.
- Output power at maximum continuous rating (MCR), in kW.
- Output speed at maximum continuous power, in rpm.
- Maximum cylinder pressure, in bar g.
- Mean indicated pressure, in bar g.
- Cylinder air inlet pressure, in bar g.
- Digitized gas pressure/crank angle cycle for MCR.
- Maximum pressure/speed relationship.
- Compression ratio.
- Vee angle and firing interval (if applicable), in degrees.
- Firing order numbered from driving end, see Fig. 2.3.1.
- Cylinder diameter, in mm.
- Piston stroke, in mm.
- Mass of connecting rod (including bearings), in kg.




Fig. 2.3.1 Designation of cylinders

- Mass of piston (including piston rod and crosshead where applicable), in kg.
- All individual reciprocating masses acting on one crank, in kg.
- Material specification(s).
- Specified minimum UTS, in N/mm<sup>2</sup>.
- Specified minimum yield strength, in N/mm<sup>2</sup>.
- Method of manufacture.
- Details of fatigue enhancement process (if applicable).
- For semi-built crankshafts – minimum and maximum diametral interference, in mm.

### 3.3 Symbols

3.3.1 For the purposes of this Chapter the following symbols apply, see also Fig. 2.3.2:

- $h$  = radial thickness of web, in mm
- $k_e$  = bending stress factor
- $B$  = transverse breadth of web, in mm
- $D_p, D_j$  = outside diameter of pin or main journal, in mm
- $D_{pi}, D_{ji}$  = internal diameter of pin or main journal, in mm
- $D_s$  = shrink diameter of main journal in web, in mm
- $d_o$  = diameter of radial oil bore in crankpin, in mm
- $F$  = alternating force at the web centreline, in N
- $K_1$  = fatigue enhancement factor due to manufacturing process
- $K_2$  = fatigue enhancement factor due to surface treatment
- $M_b$  = alternating bending moment at web centreline, in N-mm (NOTE: alternating is taken to be 1/2 range value)
- $M_{BON}$  = alternating bending moment calculated at the outlet of crankpin oil bore
- $M_p, M_j$  = undercut of fillet radius into web measured from web face, in mm
- $R_p, R_j$  = fillet radius at junction of web and pin or journal, in mm
- $S$  = stroke, in mm
- $T$  = axial thickness of web, in mm
- $T_a$  = alternating torsional moment at crankpin or crank journal, in N-mm (NOTE: alternating is taken to be 1/2 range value)

- Centre of gravity of connecting rod from large end centre, in mm.
- Radius of gyration of connecting rod, in mm.
- Length of connecting rod between bearing centres, in mm.
- Mass of single crankweb (indicate if webs either side of pin are of different mass values), in kg.
- Centre of gravity of crankweb mass from shaft axis, in mm.
- Mass of counterweights fitted (for complete crankshaft) indicate positions fitted, in kg.
- Centre of gravity of counterweights (for complete crankshaft) measured from shaft axis, in mm.





Fig. 2.3.2(a) Crank dimensions necessary for the calculation of stress concentration factors





$$U = \text{pin overlap} \\ = \frac{(D_p + D_j - S)}{2} \text{ mm}$$

- $\alpha_B$  = bending stress concentration factor for crankpin  
 $\alpha_T$  = torsional stress concentration factor for crankpin  
 $\beta_B$  = bending stress concentration factor for main journal  
 $\beta_Q$  = direct shear stress concentration factor for main journal  
 $\beta_T$  = torsional stress concentration factor for main journal  
 $\gamma_B$  = bending stress concentration factor for radially drilled oil hole in the crankpin  
 $\gamma_T$  = torsional stress concentration factor for radially drilled oil hole in the crankpin  
 $\sigma_{ax}$  = alternating axial stress, in N/mm<sup>2</sup>  
 $\sigma_b$  = alternating bending stress, in N/mm<sup>2</sup>  
 $\sigma_{BON}$  = alternating bending stress in the outlet of the oil bore, in N/mm<sup>2</sup>  
 $\sigma_p, \sigma_j$  = maximum bending stress in pin and main journal taking into account stress raisers, in N/mm<sup>2</sup>  
 $\sigma_{BO}$  = maximum bending stress in the outlet of the oil bore, in N/mm<sup>2</sup>  
 $\sigma_Q$  = alternating direct stress, in N/mm<sup>2</sup>  
 $\sigma_U$  = specified minimum UTS of material, in N/mm<sup>2</sup>  
 $\sigma_y$  = specified minimum yield stress of material, in N/mm<sup>2</sup>  
 $\tau_a$  = alternating torsional stress, in N/mm<sup>2</sup>  
 $\tau_p, \tau_j$  = maximum torsional stress in pin and main journals taking into account stress raisers, in N/mm<sup>2</sup>  
 $\tau_{tob}$  = maximum torsional stress in outlet of crankpin oil bore taking into account stress raisers, in N/mm<sup>2</sup>.

### 3.4 Stress concentration factors

**3.4.1 Geometric factors.** Crankshaft variables to be used in calculating the geometric stress concentrations together with their limits of applicability are shown in Table 2.3.1.

**Table 2.3.1 Crankshaft variables**

Variable	Range	
	Lower	Upper
$b = B/D_p$	1,10	2,20
$d_j = D_{ji}/D_p$	0,00	0,80
$d_p = D_{pi}/D_p$	0,00	0,80
$m_j = M_j/D_p$	0,00	$r_{jB}$
$m_p = M_p/D_p$	0,00	$r_p$
$r_{jB} = R_j/D_p$	0,03	0,13
$r_{iT} = R_i/D_i$	0,03	0,13
$r_p = R_p/D_p$	0,03	0,13
$t = T/D_p$	0,20	0,80
$t = T_{red}/D_p$ see Note 3	0,20	0,80
$d = d_o/D_p$	0,00	0,20
$u = U/D_p$ see Note 2		0,50

#### NOTES

- Where variables fall outside the range, alternative methods are to be used and full details submitted for consideration.
- A lower limit of  $u$  can be extended down to large negative values provided that:
  - If calculated  $f(\text{rec}) < 1$  then the factor  $f(\text{rec})$  is not to be considered ( $f(\text{rec}) = 1$ )
  - If  $u < -0,5$  then  $f(\text{ut})$  and  $f(\text{ru})$  are to be evaluated replacing actual value of  $u$  by  $-0,5$ .
- For crankshafts without overlap see also 3.4.6.

#### 3.4.2 Crankpin stress concentration factors:

##### • Bending

$$\alpha_B = 2,70 f(\text{ut}). f(\text{t}). f(\text{b}). f(\text{r}). f(\text{dp}). f(\text{dj}). f(\text{rec})$$

where

$$f(\text{ut}) = 1,52 - 4,1t + 11,2t^2 - 13,6t^3 + 6,07t^4 - u(1,86 - 8,26t + 18,2t^2 - 18,5t^3 + 6,93t^4) - u^2(3,84 - 25,0t + 70,6t^2 - 87,0t^3 + 39,2t^4)$$

$$f(\text{t}) = 2,18t^{0,717}$$

$$f(\text{b}) = 0,684 - 0,0077b + 0,147b^2$$

$$f(\text{r}) = 0,208r_p^{(-0,523)}$$

$$f(\text{dp}) = 1 + 0,315(d_p) - 1,52(d_p)^2 + 2,41(d_p)^3$$

$$f(\text{dj}) = 1 + 0,27d_j - 1,02(d_j)^2 + 0,531(d_j)^3$$

$$f(\text{rec}) = 1 + (m_p + m_j)(1,8 + 3,2u) \text{ valid only between } u = -0,5 \text{ and } 0,5.$$

##### • Torsion

$$\alpha_T = 0,8 f(\text{ru}). f(\text{b}). f(\text{t})$$

where

$$f(\text{ru}) = r_p^{(-0,22 + 0,1u)}$$

$$f(\text{b}) = 7,9 - 10,65b + 5,35b^2 - 0,857b^3$$

$$f(\text{t}) = t^{(-0,145)}.$$

3.4.3 Crank journal stress concentration factors (not applicable to semi-built crankshafts):

- Bending
 
$$\beta_B = 2,71f_B(ut) \cdot f_B(t) \cdot f_B(b) \cdot f_B(r) \cdot f_B(dj) \cdot f_B(dp) \cdot f(rec)$$
 where
 
$$f_B(ut) = 1,2 - 0,5t + 0,32t^2 - u(0,80 - 1,15t + 0,55t^2) - u^2(2,16 - 2,33t + 1,26t^2)$$

$$f_B(t) = 2,24t^{0,755}$$

$$f_B(b) = 0,562 + 0,12b + 0,118b^2$$

$$f_B(r) = 0,191r_{jB}^{(-0,557)}$$

$$f_B(dj) = 1 - 0,644d_j + 1,23(d_j)^2$$

$$f_B(dp) = 1 - 0,19d_p + 0,0073(d_p)^2$$

$$f(rec) = 1 + (m_p + m_i)(1,8 + 3,2u)$$
 valid only between  $u = -0,5$  and  $0,5$ .
- Direct shear
 
$$\beta_Q = 3,01f_Q(u) \cdot f_Q(t) \cdot f_Q(b) \cdot f_Q(r) \cdot f_Q(dp) \cdot f(rec)$$
 where
 
$$f_Q(u) = 1,08 + 0,88u - 1,52u^2$$

$$f_Q(t) = \frac{t}{0,0637 + 0,937t}$$

$$f_Q(b) = b - 0,5$$

$$f_Q(r) = 0,533r_{jB}^{(-0,204)}$$

$$f_Q(dp) = 1 - 1,19d_p + 1,74(d_p)^2$$

$$f(rec) = 1 + (m_p + m_i)(1,8 + 3,2u)$$
 valid only between  $u = -0,5$  and  $0,5$ .
- Torsion
 where
 
$$\beta_T = 0,8f(ru) \cdot f(b) \cdot f(t)$$

$$f(ru) = r_{jT}^{(-0,22 + 0,1u)}$$

$$f(b) = 7,9 - 10,65b + 5,35b^2 - 0,857b^3$$

$$f(t) = t^{(-0,145)}$$

3.4.4 Crankpin oil bore stress concentration factors for radially drilled oil holes:

- Bending
 
$$\gamma_B = 3 - 5,88 \cdot d_o + 34,6 \cdot d_o^2$$
- Torsion
 
$$\gamma_T = 4 - 6 \cdot d_o + 30 \cdot d_o^2$$

3.4.5 Where experimental measurements of the stress concentrations are available these may be used. The full documented analysis of the experimental measurements is to be submitted for consideration.

3.4.6 In the case of semi-built crankshafts when  $M_p > R_p$  the web thickness is to be taken as:

$$T_{red} = T - (M_p - R_p) \text{ and the web width } B \text{ is to be taken in way of the crankpin fillet radius centre see Fig. 2.3.2.}$$

## 3.5 Nominal stresses

3.5.1 The nominal alternating bending stress,  $\sigma_b$ , is to be calculated from the maximum and minimum bending moment at the web centreline taking into account all forces being applied to the crank throw in one working cycle with the crank throw simply supported at the mid length of the main journals.

3.5.2 Nominal bending stresses are referred to the web bending modulus.

3.5.3 Nominal alternating bending stress:

$$\sigma_b = \pm \frac{M_b}{Z_{web}} k_e \text{ N/mm}^2$$

$$Z_{web} = \frac{BT^2}{6} \text{ mm}^3$$

$$k_e = 0,8 \text{ for crosshead engines}$$

$$= 1,0 \text{ for trunk piston engines.}$$

3.5.4 Nominal alternating bending stress in the outlet of the crankpin oil bore:

$$\sigma_{BON} = \pm \frac{M_{BON}}{Z_{crankpin}}$$

where

$$M_{BON} \text{ is taken as the } \frac{1}{2} \text{ range value } M_{BON} = \pm \frac{1}{2} (M_{BOMax} - M_{BOMin})$$

and

$$M_{BO} = (M_{BTO} \cos \psi + M_{BRO} \sin \psi) \text{ see Fig. 2.3.3}$$

The two relevant bending moments are taken in the crankpin cross-section through the oil bore.

$M_{BRO}$  = bending moment of the radial component of the connecting-rod force

$M_{BTO}$  = bending moment of the tangential component of the connecting-rod force

$$Z_{crankpin} = \frac{\pi}{32} \frac{D^4 - d^4}{D} \text{ related to the cross-section of axially bored crankpin.}$$




Fig. 2.3.3 Crankpin section through the oil bore

3.5.5 The nominal direct shear stress in the web for the purpose of assessing the main journal is to be added algebraically to the bending stress, using the alternating forces which have been used in deriving  $M_b$  in 3.5.3.

3.5.6 Nominal stress is referred to the web cross-section area or the pin cross-section area as applicable.

3.5.7 Nominal alternating direct shear stress:

$$\sigma_Q = \pm \frac{F}{A_{web}} k_e \text{ N/mm}^2$$

where

$$A_{web} = BT \text{ mm}^2.$$

3.5.8 The nominal alternating torsional stress,  $\tau_a$ , is to be taken into consideration. The value is to be derived from forced-damped vibration calculations of the complete dynamic system. Alternative methods will be given consideration. The engine designer is to advise the maximum level of alternating vibratory stress that is permitted.

3.5.9 The results of torsional vibration calculations for the full dynamic system, carried out in accordance with Ch 8,2.2, are to be submitted.

3.5.10 Nominal alternating torsional stress:

$$\tau_a = \pm \frac{T_a}{Z_T} \text{ N/mm}^2$$

where

$Z_T$  = torsional modulus of crankpin and main journal

$$= \frac{\pi}{16} \left[ \frac{(D^4 - d^4)}{D} \right] \text{ mm}^3$$

$D$  = outside diameter of crankpin or main journal, in mm

$d$  = inside diameter of crankpin or main journal, in mm

$\tau_a$  is to be ascertained from assessment of the torsional vibration calculations where the maximum and minimum torques are determined for every mass point of the complete dynamic system and for the entire speed range by means of a harmonic synthesis of the forced vibrations from the 1st order up to and including the 15th order for 2-stroke cycle engines and from the 0,5th order up to and including the 12th order for 4-stroke cycle engines. Whilst doing so, allowance must be made for the damping that exists in the system and for unfavourable conditions (misfiring in one of the cylinders when no combustion occurs but only compression cycle). The speed step calculation shall be selected in such a way that any resonance found in the operational speed range of the engine shall be detected.

3.5.11 For the purpose of the crankshaft assessment, the nominal alternating torsional stress considered in calculations is to be the highest calculated value, according to the method described in 3.5.9, occurring at the most torsionally loaded mass point of the crankshaft system.

3.5.12 The approval of the crankshaft will be based on the installation having the largest nominal alternating torsional stress (but not exceeding the maximum figure specified by the engine manufacturer). For each installation it is to be ensured by calculation that the maximum approved nominal alternating torsional stress is not exceeded.

3.5.13 In addition to the bending stress,  $\sigma_b$ , the axial vibratory stress,  $\sigma_{ax}$ , is to be taken into consideration, for crosshead type engines. For trunk type engines,  $\sigma_{ax} = 0$ . The value is to be derived from forced-damped vibration calculations of the complete dynamic system. Alternative methods will be given consideration. The engine designer is to advise the maximum level of alternating vibratory stress that is permitted. The corresponding crankshaft free-end deflection is also to be stated.

## 3.6 Maximum stress levels

3.6.1 Crankpin fillet.

- Maximum alternating bending stress:

$$\sigma_p = \alpha_B (\sigma_b + \sigma_{ax}) \text{ N/mm}^2$$

where

$\alpha_B$  = bending stress concentration, see 3.4.2

- Maximum alternating torsional stress:

$$\tau_p = \alpha_T \tau_a \text{ N/mm}^2$$

where

$\alpha_T$  = torsional stress concentration, see 3.4.2

$\tau_a$  = nominal alternating torsional stress in crankpin N/mm<sup>2</sup>.

3.6.2 Outlet of crankpin oil bore.

- Maximum alternating bending stress:

$$\sigma_{BO} = \gamma_B (\sigma_{BON} + \sigma_{ax}) \text{ N/mm}^2$$

where

$\gamma_B$  = bending stress concentration factor, see 3.4.4

- Maximum alternating torsional stress:

$$\tau_{tob} = \gamma_T \tau_a \text{ N/mm}^2$$

where

$\gamma_T$  = torsional stress concentration factor, see 3.4.4

$\tau_a$  = nominal alternating torsional stress in crankpin N/mm<sup>2</sup>.

3.6.3 Crank journal fillet (not applicable to semi-built crankshafts).

- Maximum alternating bending stress:

$$\sigma_j = \beta_B (\sigma_b + \sigma_{ax}) + \beta_Q \sigma_Q \text{ N/mm}^2$$

where

$\beta_B$  = bending stress concentration, see 3.4.3

$\beta_Q$  = direct stress concentration, see 3.4.3

- Maximum alternating torsional stress:

$$\tau_j = \beta_T \tau_a \text{ N/mm}^2$$

where

$\beta_T$  = torsional stress concentration, see 3.4.3

$\tau_a$  = nominal alternating torsional stress in main journal N/mm<sup>2</sup>.

## 3.7 Equivalent alternating stress

3.7.1 Equivalent alternating stress of the crankpin,  $\sigma_{ep}$ , or crank journal  $\sigma_{ej}$ , is defined as:

$$\sigma_{ep}, \sigma_{ej} = \sqrt{(\sigma + 10)^2 + 3\tau^2} \text{ N/mm}^2$$

where

$$\sigma = \sigma_p \text{ or } \sigma_j \text{ N/mm}^2$$

$$\tau = \tau_p \text{ or } \tau_j \text{ N/mm}^2.$$

# Oil Engines

# Part 5, Chapter 2

Section 3

3.7.2 Equivalent alternating stress for the outlet of the crankpin oil bore  $\sigma_{eob}$ , is defined as:

$$\sigma_{eob} = \pm \frac{1}{3} \sigma_{bo} \left( 1 + 2 \sqrt{1 + \frac{9}{4} \frac{\tau_{to}}{\sigma_{bo}}^2} \right) \text{ N/mm}^2$$

## 3.8 Fatigue strength

3.8.1 The fatigue strength of a crankshaft is based upon the crankpin and crank journal as follows:

$$\sigma_{fp} = K_1 K_2 (0,42\sigma_u + 39,3) \left( 0,264 + 1,073D_p^{-0,2} + \frac{785 - \sigma_u}{4900} + \frac{196}{\sigma_u} \sqrt{\frac{1}{R_p}} \right)$$

To calculate the fatigue strength in the oil bore area, replace  $R_p$  with  $\frac{1}{2}d_o$  and  $\sigma_{fp}$  with  $\sigma_{fob}$ .

$$\sigma_{fj} = K_1 K_2 (0,42\sigma_u + 39,3) \left( 0,264 + 1,073D_j^{-0,2} + \frac{785 - \sigma_u}{4900} + \frac{196}{\sigma_u} \sqrt{\frac{1}{R_j}} \right)$$

where

- $\sigma_u$  = UTS of crankpin or crank journal as appropriate
- $K_1$  = fatigue endurance factor appropriate to the manufacturing process
  - = 1,05 for continuous grain-flow (CGF) or die-forged
  - = 1,0 for freeform forged (without CGF)
  - = 0,93 for cast steel manufactured using a LR approved cold rolling process
- $K_2$  = fatigue enhancement factor for surface treatment.

These treatments are to be applied to the fillet radii. A value for  $K_2$  will be assigned upon application by the engine designers. Full details of the process, together with the results of full scale fatigue tests will be required to be submitted for consideration. Alternatively, the following values may be taken (surface hardened zone to include fillet radii):

- $K_2$  = 1,15 for induction hardened
- = 1,25 for nitrided

Where a value of  $K_1$  or  $K_2$  greater than unity is to be applied then details of the manufacturing process are to be submitted.

## 3.9 Acceptability criteria

3.9.1 The acceptability factor, Q, is to be greater than 1,15:

$$Q = \frac{\sigma_f}{\sigma_e} \text{ for crankpin, journal and the outlet of crankpin oil bore}$$

where

- $\sigma_f$  =  $\sigma_{fp}$  or  $\sigma_{fj}$  or  $\sigma_{fob}$
- $\sigma_e$  =  $\sigma_{ep}$  or  $\sigma_{ej}$  or  $\sigma_{eob}$ .

## 3.10 Oil hole

3.10.1 The junction of the oil hole with the crankpin or main journal surface is to be formed with an adequate radius and smooth surface finish down to a minimum depth equal to 1,5 times the oil bore diameter.

3.10.2 Fatigue strength calculations or alternatively fatigue test results may be required to demonstrate acceptability.

3.10.3 When journal diameter is equal or larger than the crankpin diameter, the outlets of main journal oil bores are to be formed in a similar way to the crankpin oil bores, otherwise separate fatigue strength calculations or, alternatively, fatigue test results may be required.

## 3.11 Shrink fit of semi-built crankshafts

3.11.1 The maximum permissible internal diameter in the journal pin is to be calculated in accordance with the following formula:

$$D_{ji} = D_s \sqrt{1 - \frac{4000 \text{FoS } M_{\max}}{\mu \pi D_s^2 L_s \sigma_{yj}}}$$

where the symbols are as defined in 3.11.7.

3.11.2 When 3.11.1 cannot be complied with, then 3.11.7 is not applicable. In such cases  $\delta_{\min}$  and  $\delta_{\max}$  are to be established from FEM calculations.

3.11.3 The following formulae are applicable to crankshafts assembled by shrinking main journals into the crankwebs.

3.11.4 In general, the radius of transition,  $R_j$ , between the main journal diameter,  $D_j$ , and the shrink diameter,  $D_s$ , is to be not less than  $0,015D_j$  or  $0,5(D_s - D_j)$ .

3.11.5 The distance, y, between the underside of the pin and the shrink diameter should be greater than  $0,05D_s$ .

3.11.6 Deviations from these parameters will be specially considered.

3.11.7 The proposed diametral interference is to be within the following limits, see also Fig. 2.3.4:

The minimum required diametral interference is to be taken as the greater of:

$$\delta_{\min} = \frac{12,156 \times 10^6 (\text{FoS})}{TD_s \mu E} \frac{P}{R} (1 + C) \frac{k^2 - l^2}{(k^2 - 1)(1 - l^2)} \text{ mm}$$

or

$$\delta_{\min} = \frac{\sigma_y D_s}{E} \text{ mm}$$

where

$h$  = minimum radial thickness of the web around the diameter  $D_s$ , mm

$$k = \frac{D_o}{D_s}$$

$$l = \frac{D_{ji}}{D_s}$$

$C$  = ratio of torsional vibratory torque to the mean transmitted torque at the P/R rating being considered

$$D_o = D_s + 2h, \text{ in mm}$$

$D_s$  = shrink diameter, in mm

$E$  = Young's modulus of elasticity of crankshaft material, in N/mm<sup>2</sup>


FoS = Factor of Safety against rotational slippage to be taken as 2,0. A value less than 2,0 may be used where documented by experiments to demonstrate acceptability

$P$  = output power, in kW

- $R$  = speed at associated power, in rpm  
 $T$  = crankweb thickness, in mm  
 $\mu$  = coefficient of static friction to be taken as 0,2 for degreased surfaces. A value greater than 0,2 may be used where documented by experiments to demonstrate acceptability  
 $\sigma_{yj}$  = minimum yield strength of material for journal pin  
 $M_{max}$  = absolute maximum value of the torque taking Ch 8,2 into consideration  
 $L_s$  = length of shrink fit, in mm.

Maximum diametral interference,  $\delta_{max}$ , is not to be greater than:

$$\delta_{max} = \frac{\sigma_y D_s}{E} + \frac{0,8 D_s}{1000} \text{ mm.}$$



**Fig. 2.3.4 Crank throw of semi-built crankshaft**

3.11.8 Reference marks are to be provided on the outer junction of the crankwebs with the journals.



## Section 4

## Construction and welded structures

### 4.1 Crankcases

4.1.1 Crankcases and their doors are to be of robust construction to withstand anticipated crankcase pressures that may arise during a crankcase explosion, taking into account the installation of explosion relief valves required by Section 6 and the doors are to be securely fastened so that they will not be readily displaced by a crankcase explosion.

### 4.2 Welded joints

4.2.1 Bedplates and major components of engine structures are to be made with a minimum number of welded joints.

4.2.2 Double welded butt joints are to be adopted wherever possible in view of their superior fatigue strength.

4.2.3 Girder and frame assemblies should, so far as possible, be made from one plate or slab, shaped as necessary, rather than by welding together a number of small pieces.

4.2.4 Steel castings are to be used for parts which would otherwise require complicated weldments.

4.2.5 Care is to be taken to avoid stress concentrations such as sharp corners and abrupt changes in section.

4.2.6 Joints in parts of the engine structure which are stressed by the main gas or inertia loads are to be designed as continuous full strength welds and for complete fusion of the joint. They are to be so arranged that, in general, welds do not intersect, and that welding can be effected without difficulty and adequate inspection can be carried out. Abrupt changes in plate section are to be avoided and where plates of substantially unequal thickness are to be butt welded, the thickness of the heavier plate is to be gradually tapered to that of the thinner plate. Tee joints are to be made with full bevel or equivalent weld preparation to ensure full penetration.

4.2.7 In single plate transverse girders the castings for main bearing housings are to be formed with web extensions which can be butt welded to the flange and vertical web plates of the girder. Stiffeners in the transverse girder are to be attached to the flanges by full penetration welds.

### 4.3 Materials and construction

4.3.1 Plates, sections, forgings and castings are to be of welding quality in accordance with the requirements of the Rules for Materials (Part 2), and with a carbon content generally not exceeding 0,23 per cent. Steels with higher carbon contents may be approved subject to satisfactory results from welding procedure tests.

4.3.2 Plates and weld preparations are to be accurately machined or flame-cut to shape. Flame-cut surfaces are to be cleaned by machining or grinding; if the flame-cut surfaces are smooth, wire brushing may be accepted.

4.3.3 Before welding is commenced the component parts of bedplates and framework are to be accurately fitted and aligned.

4.3.4 The welding is to be carried out in positions free from draughts and is to be downhand (flat) wherever practicable. Welding consumables are to be suitable for the materials being joined. Preheating is to be adopted when heavy plates or sections are welded. The finished welds are to have an even surface and are to be free from undercutting.

4.3.5 Welds attaching bearing housings to the transverse girders are to have a smooth contour and, if necessary, are to be made smooth by grinding.

# Oil Engines

# Part 5, Chapter 2

Sections 4, 5 & 6

## 4.4 Post-weld heat treatment

4.4.1 Bedplates are to be given a stress relieving heat treatment except engine types where the bedplate as a whole is not subjected to direct loading from the cylinder pressure. For these types, only the transverse girder assemblies need be stress relieved.

4.4.2 Stress relieving is to be carried out by heating the welded structure uniformly and slowly to a temperature between 580°C and 620°C, holding that temperature for not less than one hour per 25 mm of maximum plate thickness and thereafter allowing the structure to cool slowly in the furnace.

## 4.5 Inspection

4.5.1 Welded engine structures are to be examined during fabrication, special attention being given to the fit of component parts of major joints prior to welding.

4.5.2 On completion of welding and stress relief heat treatment, all welds are to be examined.

4.5.3 Welds in transverse girder assemblies are to be crack detected by an approved method to the satisfaction of the Surveyors. Other joints are to be similarly tested if required by the Surveyors.

## Section 5 Safety arrangements on engines

### 5.1 Cylinder relief valves

5.1.1 Scavenge spaces in open connection with cylinders are to be provided with explosion relief valves.

### 5.2 Main engine governors

5.2.1 An efficient governor is to be fitted to each main engine so adjusted that the speed does not exceed that for which the engine is to be classed by more than 15 per cent.

5.2.2 Oil engines coupled to electrical generators which are the source of power for main electric propulsion motors are to comply with the requirements for auxiliary engines in respect of governors and overspeed protection devices.

### 5.3 Auxiliary engine governors

5.3.1 Auxiliary engines intended for driving electric generators are to be fitted with governors which, with fixed setting, are to control the speed within 10 per cent momentary variation and 5 per cent permanent variation when full load is suddenly taken off or, when after having run on no-load for at least 15 minutes, load is suddenly applied as follows:

- (a) For engines with BMEP less than 8 bar, full load, or
- (b) For engines with BMEP greater than 8 bar,  $\frac{800}{\text{BMEP}}$  per cent, but not less than one-third, of full load, the full load being attained in not more than two additional equal stages as rapidly as possible.

5.3.2 Emergency engines are to comply with 5.3.1 except that the initial load required by 5.3.1(b) is to be not less than the total connected emergency statutory load.

5.3.3 For alternating current installations, the permanent speed variation of the machines intended for parallel operation are to be equal within a tolerance of  $\pm 0.5$  per cent. Momentary speed variations with load changes in accordance with 5.3.1 are to return to and remain within one per cent of the final steady state speed. This should normally be accomplished within five but in no case more than eight seconds. For quality of power supplies, see Pt 6, Ch 2, 1.7.

## 5.4 Overspeed protective devices

5.4.1 Each main engine developing 220kW (300 shp) or over which can be declutched or which drives a controllable (reversible) pitch propeller, also each auxiliary engine developing 220 kW (300 shp) and over for driving an electric generator, is to be fitted with an approved overspeed protective device.

5.4.2 The overspeed protective device, including its driving mechanism, is to be independent of the governor required by 5.2 or 5.3 and is to be so adjusted that the speed does not exceed that for which the engine and its driven machinery are to be classed by more than 20 per cent for main engines and 15 per cent for auxiliary engines.

## Section 6 Crankcase safety fitting

### NOTE

For the purpose of this Section, starting air compressors are to be treated as auxiliary engines.

### 6.1 Relief valves

6.1.1 Crankcases are to be provided with lightweight spring-loaded valves or other quick-acting and self-closing devices, to relieve the crankcases of pressure in the event of an internal explosion and to prevent any inrush of air thereafter. The valves are to be designed and constructed to open quickly and be fully open at a pressure not greater than 0,2 bar.

6.1.2 The valve lids are to be made of ductile material capable of withstanding the shock of contact with stoppers at the full open position.

6.1.3 Each valve is to be fitted with a flame arrester that permits flow for crankcase pressure relief and prevents the passage of flame following a crankcase explosion. The valves are to be type tested in a configuration that represent the installation arrangements that will be used on an engine and in accordance with a standard acceptable to LR. The valves are to be positioned on engines to minimise the possibility of danger and damage arising from emission of the crankcase atmosphere. Where shielding from the emissions is fitted to a valve, the valve is to be type tested to demonstrate that the shielding does not adversely affect the operational effectiveness of the valve.

6.1.4 The valves are to be provided with a copy of the manufacturer's installation and maintenance manual for the size and type of valve being supplied for installation on a particular engine. The manual is to contain the following information:

- Description of valve with details of function and design limits.
- Copy of type test certification.
- Installation instructions.
- Maintenance and in service instructions to include testing and renewal of any sealing arrangements.
- Actions required after a crankcase explosion.

6.1.5 A copy of the installation and maintenance manual required by 6.1.4 is to be provided on board the ship.

6.1.6 Plans showing details and arrangements of the relief valves are to be submitted for approval, see 1.1.

6.1.7 The valves are to be provided with suitable markings that include the following information:

- Name and address of manufacturer.
- Designation and size.
- Month/Year of manufacture.
- Approved installation orientation.

## 6.2 Number of relief valves

6.2.1 In engines having cylinders not exceeding 200 mm bore or having a crankcase gross volume not exceeding 0,6 m<sup>3</sup>, relief valves may be omitted.

6.2.2 In engines having cylinders exceeding 200 mm but not exceeding 250 mm bore, at least two relief valves are to be fitted; each valve is to be located at or near the ends of the crankcase. Where the engine has more than eight crank throws an additional valve is to be fitted near the centre of the engine.

6.2.3 In engines having cylinders exceeding 250 mm but not exceeding 300 mm bore, at least one relief valve is to be fitted in way of each alternate crank throw with a minimum of two valves. For engines having 3, 5, 7, 9, etc., crank throws, the number of relief valves is not to be less than 2, 3, 4, 5, etc., respectively.

6.2.4 In engines having cylinders exceeding 300 mm bore at least one valve is to be fitted in way of each main crank throw.

6.2.5 Additional relief valves are to be fitted for separate spaces on the crankcase, such as gear or chaincases for camshaft or similar drives, when the gross volume of such spaces exceeds 0,6 m<sup>3</sup>.

## 6.3 Size of relief valves

6.3.1 The combined free area of the crankcase relief valves fitted on an engine is to be not less than 115 cm<sup>2</sup>/m<sup>3</sup> based on the volume of the crankcase.

6.3.2 The free area of each relief valve is to be not less than 45 cm<sup>2</sup>.

6.3.3 The free area of the relief valve is the minimum flow area at any section through the valve when the valve is fully open.

6.3.4 In determining the volume of the crankcase for the purpose of calculating the combined free area of the crankcase relief valves, the volume of the stationary parts within the crankcase may be deducted from the total internal volume of the crankcase.

## 6.4 Vent pipes

6.4.1 Through ventilation, and any arrangement which could produce a flow of external air within the crankcase, is in principle not permitted except for trunk piston type dual fuel engines where crankcase ventilation is to be provided. Where crankcase vent or breather pipes are fitted, they are to be made as small as practicable and/or as long as possible to minimize the inrush of air after an explosion. Vents or breather pipes from crankcases of main engines are to be led to a safe position on deck or other approved position.

6.4.2 If provision is made for the extraction of gases from within the crankcase, e.g. for oil mist detection purposes, the vacuum within the crankcase is not to exceed 25 mm of water.

6.4.3 Lubricating oil drain pipes from engine sump to drain tank are to be submerged at their outlet ends. Where two or more engines are installed, vent pipes, if fitted, and lubrication oil drain pipes are to be independent to avoid intercommunication between crankcases.

## 6.5 Alarms

6.5.1 Alarms giving warning of the overheating of engine running parts, indicators of excessive wear of thrusts and other parts, and crankcase oil mist detectors are recommended as means for reducing the explosion hazard. These devices should be arranged to give an indication of failure of the equipment or of the instrument being switched off when the engine is running.

# Oil Engines

# Part 5, Chapter 2

Section 6

## 6.6 Warning notice

6.6.1 A warning notice is to be fitted in a prominent position, preferably on a crankcase door on each side of the engine, or alternatively at the engine room control station. This warning notice is to specify that whenever overheating is suspected in the crankcase, the crankcase doors or sight holes are not to be opened until a reasonable time has elapsed after stopping the engine, sufficient to permit adequate cooling within the crankcase.

## 6.7 Crankcase access and lighting

6.7.1 Where access to crankcase spaces is necessary for inspection purposes, suitably positioned rungs or equivalent arrangements are to be provided as considered appropriate.

6.7.2 When interior lighting is provided it is to be flame-proof in relation to the interior and details are to be submitted for approval. No wiring is to be fitted inside the crankcase.

## 6.8 Fire-extinguishing system for scavenge manifolds

6.8.1 Crosshead type engine scavenge spaces in open connection with cylinders are to be provided with approved fixed or portable fire-extinguishing arrangements which are to be independent of the fire-extinguishing system of the engine room.

## 6.9 Oil mist detection/monitoring

6.9.1 Where crankcase oil mist detection/monitoring arrangements are fitted, they are to be of a type approved by LR, tested in accordance with Section 14 and comply with 6.9.2 to 6.9.15.

6.9.2 The oil mist detection/monitoring system and arrangements are to be installed in accordance with the engine designer's and oil mist detection equipment manufacturer's instructions/recommendations. The following particulars are to be included in the instructions:

- (a) Schematic layout of engine oil mist detection/monitoring and alarm system showing locations of engine crankcase sample points and piping arrangements together with pipe dimensions to detector/monitor.
- (b) Evidence of study to justify the selected locations of sample points and sample extraction rate (if applicable) in consideration of the crankcase arrangements and geometry and the predicted crankcase atmosphere where oil mist can accumulate.
- (c) The manufacturer's maintenance and test manual.
- (d) Information relating to type or in-service testing of the engine with engine protection system test arrangements having approved types of oil mist monitoring equipment.

6.9.3 A copy of the oil mist detection/monitoring equipment maintenance and test manual required by 6.9.2 is to be provided on board ship.

6.9.4 Oil mist monitoring and alarm information is to be capable of being read from a safe location away from the engine.

6.9.5 In the case of multi engine installations, each engine is to be provided with oil mist detection/monitoring and a dedicated alarm.

6.9.6 Oil mist detection/monitoring and alarm systems are to be capable of being tested on the test bed and on board when the engine is at a standstill and when the engine is running at normal operating conditions in accordance with test procedures that are acceptable to LR.

6.9.7 Alarms and shutdowns for the oil mist detection/monitoring system are to be in accordance with Pt 6, Ch 1 as applicable.

6.9.8 The oil mist detection/monitoring arrangements are to provide an alarm indication in the event of a foreseeable functional failure in the equipment and installation arrangements. See Pt 6, Ch 1, 2.4.6.

6.9.9 The oil mist detection/monitoring system is to provide an indication that any lenses fitted in the equipment and used in determination of the oil mist level have been partially obscured to a degree that will affect the reliability of the information and alarm indication.

6.9.10 Where oil mist detection/monitoring equipment includes the use of programmable electronic systems, the arrangements are to be in accordance with Pt 6, Ch 1 as applicable.

6.9.11 Schematic layouts showing details and arrangements of oil mist detection/monitoring and alarm systems are to be submitted. See Pt 5, Ch 1, 1.

6.9.12 The equipment together with detectors/monitors is to be tested when installed on the test bed and on board ship to demonstrate that the detection/monitoring and alarm system functions correctly. The testing arrangements are to be to the satisfaction of the Surveyor.

6.9.13 Where sequential oil mist detection/monitoring arrangements are provided, the sampling frequency and time is to be as short as reasonably practicable.

6.9.14 Where alternative methods are provided for the prevention of the build-up of oil mist that may lead to a potentially explosive condition within the crankcase, detailed information is to be submitted for consideration. The information is to include:

- (a) Engine particulars – type, power, speed, stroke, bore and crankcase volume.
- (b) Details of arrangements designed to prevent the build up of potentially explosive conditions within the crankcase, e.g., bearing temperature monitoring, oil splash temperature monitoring, crankcase pressure monitoring, and recirculation arrangements.
- (c) Evidence to demonstrate that the arrangements are effective in preventing the build up of potentially explosive conditions together with details of in-service experience.



- (d) Operating instructions and the maintenance and test instructions.

6.9.15 Where it is proposed to use the introduction of inert gas into the crankcase to minimise a potential crankcase explosion, details of the arrangements are to be submitted for consideration.

## ■ Section 7 Piping

### 7.1 Oil fuel systems

7.1.1 All external high pressure fuel delivery lines between the high pressure fuel pumps and fuel injectors are to be protected with a jacketed piping system capable of containing fuel from a high pressure line failure. If flexible hoses are used for shielding purposes, these arrangements are to be approved.

7.1.2 The protection is to prevent oil fuel or oil fuel mist from reaching a source of ignition on the engine or its surroundings. Suitable drainage arrangements are to be made for draining any oil fuel leakage to collector tank(s) fitted in a safe position. An alarm is to be provided to indicate that leakage is taking place.

7.1.3 Oil fuel pipe systems in general, tanks and their fittings are to comply with the requirements of Chapter 14 and Part 3.

7.1.4 Diesel engine fuel system components are to be designed to accommodate the maximum peak pressures experienced in service. In particular this applies to the fuel injection pump supply and spill line piping which may be subject to high-pressure pulses from the pump. Connections on such piping systems should be chosen to minimise the risk of pressurised oil fuel leaks.

7.1.5 Where multi-engined installations are supplied from the same fuel source, means of isolating the fuel supply and spill piping to individual engines are to be provided. These means of isolation are not to affect the operation of the other engines and are to be operable from a position not rendered inaccessible by a fire on any of the engines.

### 7.2 High pressure oil systems

7.2.1 Where flammable oils are used in high pressure systems, the oil pipe lines between the high pressure oil pump and actuating oil pistons are to be protected with a jacketed piping system capable of preventing oil spray from a high-pressure line failure.

### 7.3 Exhaust systems

7.3.1 Where the surface temperature of the exhaust pipes and silencer may exceed 220°C, they are to be water cooled or efficiently lagged to minimize the risk of fire and to prevent damage by heat. Where lagging covering the exhaust piping system including flanges is oil-absorbing or may permit penetration of oil, the lagging is to be encased in sheet metal or equivalent. In locations where the Surveyor is satisfied that oil impingement could not occur, the lagging need not be encased.

7.3.2 Where the exhaust is led overboard near the waterline, means are to be provided to prevent water from being siphoned back to the engine. Where the exhaust is cooled by water spray, the exhaust pipes are to be self-draining overboard.

7.3.3 Where the exhausts of two or more engines are led to a common silencer or exhaust gas-heated boiler or economizer, an isolating device is to be provided in each exhaust pipe.

7.3.4 For alternatively fired furnaces of boilers using exhaust gases and oil fuel, the exhaust gas inlet pipe is to be provided with an isolating device and interlocking arrangements whereby oil fuel can only be supplied to the burners when the isolating device is closed to the boiler.

7.3.5 In two-stroke main engines fitted with exhaust gas turbo-blowers which operate on the impulse system, provision is to be made to prevent broken piston rings entering the turbine casing and causing damage to blades and nozzle rings.

### 7.4 Starting air pipe systems and safety fittings

7.4.1 In designing the compressed air installation, care is to be taken that the compressor air inlets will be located in an atmosphere reasonably free from oil vapour or, alternatively, an air duct from outside the machinery space is to be led to the compressors.

7.4.2 The air discharge pipe from the compressors is to be led direct to the starting air receivers. Provision is to be made for intercepting and draining oil and water in the air discharge for which purpose a separator or filter is to be fitted in the discharge pipe between compressors and receivers.

7.4.3 The starting air pipe system from receivers to main and auxiliary engines is to be entirely separate from the compressor discharge pipe system. Stop valves on the receivers are to permit slow opening to avoid sudden pressure rises in the piping system. Valve chests and fittings in the piping system are to be of ductile material.

7.4.4 Drain valves for removing accumulations of oil and water are to be fitted on compressors, separators, filters and receivers. In the case of any low-level pipelines, drain valves are to be fitted to suitably located drain pots or separators.

7.4.5 The starting air piping system is to be protected against the effects of explosions by providing an isolating non-return valve or equivalent at the starting air supply to each engine.

# Oil Engines

# Part 5, Chapter 2

Sections 7 &amp; 8

7.4.6 In direct reversing engines bursting discs or flame arresters are to be fitted at the starting valves on each cylinder; in non-reversing and auxiliary engines at least one such device is to be fitted at the supply inlet to the starting air manifold on each engine. The fitting of bursting discs or flame arresters may be waived in engines where the cylinder bore does not exceed 230 mm.

7.4.7 Alternative safety arrangements may be submitted for consideration.

## ■ Section 8 Starting arrangements and air compressors

### 8.1 Dead ship condition starting arrangements

8.1.1 Means are to be provided to ensure that machinery can be brought into operation from the dead ship condition without external aid.

8.1.2 Dead ship condition for the purpose of 8.1.1 is to be understood to mean a condition under which the main propulsion plant, boilers and auxiliaries are not in operation. In restoring propulsion, no stored energy for starting and operating the propulsion plant is assumed to be available. Additionally, neither the main source of electrical power nor other essential auxiliaries are assumed to be available for starting and operating the propulsion plant.

8.1.3 Where the emergency source of power is an emergency generator which fully complies with the requirements of Pt 6, Ch 2 of the Rules, this generator may be used for restoring operation of the main propulsion plant, boilers and auxiliaries where any power supplies necessary for engine operation are also protected to a similar level as the starting arrangements.

8.1.4 Where there is no emergency generator installed or an emergency generator does not comply with Pt 6, Ch 2 of the Rules, the arrangements for bringing main and auxiliary machinery into operation are to be such that the initial charge of starting air or initial electrical power and any power supplies for engine operation can be developed on board ship without external aid. If for this purpose an emergency air compressor or an electric generator is required, these units are to be powered by a hand-starting oil engine or a hand-operated compressor. The arrangements for bringing main and auxiliary machinery into operation are to have capacity such that the starting energy and any power supplies for engine operation are available within 30 minutes of a dead ship condition.

8.1.5 For cargo ships of less than 500 gross tons and which are not required to comply with the *International Convention for the Safety of Life at Sea, 1974*, as amended (SOLAS 74), alternative arrangements to those specified in 8.1.3 or 8.1.4 may be proposed for consideration. Details of the alternative arrangements are to be included in the plans and details required by 1.1.6 and are to demonstrate that the arrangements provide for starting from the dead ship condition and are in accordance with any applicable statutory requirements of the National Authority of the country in which the ship is to be registered.

### 8.2 Air compressors

8.2.1 Two or more air compressors are to be fitted having a total capacity, together with a topping-up compressor where fitted, capable of charging the air receivers within 1 hour from atmospheric pressure, to the pressure sufficient for the number of starts required by 8.3. At least one of the air compressors is to be independent of the main propulsion unit and the capacity of the main air compressors is to be approximately equally divided between them. The capacity of an emergency compressor which may be installed to satisfy the requirements of 8.1 is to be ignored.

8.2.2 The compressors are to be so designed that the temperature of the air discharged to the starting air receivers will not substantially exceed 93°C in service. A small fusible plug or an alarm device operating at 121°C is to be provided on each compressor to give warning of excessive air temperature. The emergency air compressor is excepted from these requirements.

8.2.3 Each compressor is to be fitted with a safety valve so proportioned and adjusted that the accumulation with the outlet valve closed will not exceed 10 per cent of the maximum working pressure. The casings of the cooling water spaces are to be fitted with a safety valve or bursting disc so that ample relief will be provided in the event of the bursting of an air cooler tube. It is recommended that compressors be cooled by fresh water.

### 8.3 Air receiver capacity

8.3.1 Where the main engine is arranged for air starting the total air receiver capacity is to be sufficient to provide without replenishment, not less than 12 consecutive starts of the main engine, alternating between ahead and astern if of the reversible type and not less than six consecutive starts if of the non-reversible type. At least two air receivers of approximately equal capacity are to be provided. For scantlings and fittings of air receivers, see Chapter 11.

8.3.2 For multi-engine installations, the number of starts required for each engine will be specially considered.

# Oil Engines

## Part 5, Chapter 2

Sections 8 &amp; 9

### 8.4 Electric starting

8.4.1 Where main engines are fitted with electric starters, two batteries are to be fitted. Each battery is to be capable of starting the engines when cold and the combined capacity is to be sufficient without recharging to provide the number of starts of the main engines as required by 8.3. In other respects batteries are to comply with the requirements of Pt 6, Ch 2, 11.

8.4.2 Electric starting arrangements for auxiliary engines are to have two separate batteries or be supplied by separate circuits from the main engine batteries when such are provided. Where one of the auxiliary engines only is fitted with an electric starter one battery will be acceptable.

8.4.3 The combined capacity of the batteries for starting the auxiliary engines is to be sufficient for at least three starts for each engine.

8.4.4 Engine starting batteries are to be used only for the purposes of starting the engines and for the engines' own monitoring arrangements. Means are to be provided to ensure that the stored energy in the batteries is maintained at a level required to start the engines, as defined in 8.4.1 and 8.4.3.

8.4.5 Where engines are fitted with electric starting batteries, an alarm is to be provided for low battery charge level.

8.4.6 For cargo ships of less than 500 gross tons which are not required to comply with the *International Convention for the Safety of Life at Sea, 1974*, as amended (SOLAS 74), the emergency source of electrical power may be used as one of the sources of energy required by 8.4.1 or 8.4.2 for electric starting. Where the emergency source of electrical power is an accumulator battery and it is to be used for electric starting, it is to have the additional capacity required to ensure emergency supplies are not compromised and is to be adequately protected and suitably located for use in an emergency.

### 8.5 Starting of the emergency source of power

8.5.1 Emergency generators are to be capable of being readily started in their cold conditions down to a temperature of 0°C. If this is impracticable, or if lower temperatures are likely to be encountered, consideration is to be given to the provision and maintenance of heating arrangements, so that ready starting will be assured.

8.5.2 Each emergency generator that is arranged to be automatically started is to be equipped with an approved starting system having two independent sources of stored energy, each of which is sufficient for at least three consecutive starts. When hand (manual) starting is demonstrated to be effective, only one source of stored energy need be provided. However, this source of stored energy is to be protected against depletion below the level required for starting.

8.5.3 Provision is to be made to maintain continuously the stored energy at all times, and for this purpose:

- (a) Electrical and hydraulic starting systems are to be maintained from the emergency switchboard.
- (b) Compressed air starting systems may be maintained by the main or auxiliary compressed air receivers, through a suitable non-return valve, or by an emergency air compressor energized by the emergency switchboard.
- (c) All these starting, charging and energy storing devices are to be located in the emergency generator room. These devices are not to be used for any purpose other than the operation of the emergency generator.

8.5.4 When automatic starting is not required by the Rules and where it can be demonstrated as being effective, hand (manual) starting is permissible, such as manual cranking, inertial starters, manual hydraulic accumulators, powder charge cartridges.

8.5.5 When hand (manual) starting is not practicable, the provisions under 8.5.2 and 8.5.3 are to be complied with except that starting may be manually initiated.

8.5.6 Engine starting batteries are to be used only for the purposes of starting the engines and for the engines' own monitoring arrangements.

## Section 9 Component tests and engine type testing

### 9.1 Hydraulic tests

9.1.1 In general, items are to be tested by hydraulic pressure as indicated in Table 2.9.1. Where design features are such that modifications to the test requirements shown in Table 2.9.1 are necessary, alternative proposals for hydraulic tests are to be submitted for special consideration.

9.1.2 Where a manufacturer has demonstrated to LR that they have an acceptable quality management system, a manufacturer's hydraulic test certificate may be accepted for engine driven pumps as detailed in Table 2.9.1. Recognition and acceptance of the works quality control processes can be by one of the following routes:

- (a) Approval under the LR Quality Scheme for Machinery.
- (b) Approval of an alternative quality scheme recognized by LR.
- (c) Approval by LR through auditing of the manufacturer's quality system.

### 9.2 Alignment gauges

9.2.1 All main and auxiliary oil engines exceeding 220 kW (300 shp) are to be provided with an alignment gauge which may be either a bridge wear-down gauge, or a micro-meter clock gauge for use between the crankwebs. Only one micrometer clock gauge need be supplied for each ship provided the gauge is suitable for use on all engines.

# Oil Engines

## Part 5, Chapter 2

Sections 9 &amp; 10

**Table 2.9.1 Test pressures for oil engine components**

Item	Test pressure
Fuel injection system { Pump body, pressure side Valve Pipe }	The lesser of $1,5p$ or $p + 295$ bar
Cylinder cover, cooling space Cylinder liner, over the whole length of cooling space Piston crown, cooling space (where piston rod seals cooling space, test after assembly)	7,0 bar
Cylinder jacket, cooling space Exhaust valve, cooling space Turbo-charger, cooling space Exhaust pipe, cooling space Coolers, each side Engine driven pumps (oil, water, fuel, bilge)	The greater of 4,0 bar or $1,5p$
Air compressor, including cylinders, covers, intercoolers and aftercoolers	Air side: $1,5p$ Water side: The greater of 4,0 bar or $1,5p$
Scavenge pump cylinder	4,0 bar
<b>NOTES</b> 1. $p$ is the maximum working pressure in the item concerned. 2. Pumps used in jerk or timed pump systems need only have the assembled high pressure-containing components hydraulically tested. 3. Turbo-charger air coolers need only be tested on the water side. 4. For forged steel cylinder covers alternative testing methods will be specially considered.	

### 9.3 Engine type testing

9.3.1 New engine types or developments of existing types are to be subjected to an agreed programme of type testing to complement the design appraisal and review of documentation.

9.3.2 Guidelines for type testing of engines will be supplied on application.

9.3.3 An engine type is defined in terms of:

- basic engine data: e.g. bore, stroke
- working cycle: 2 stroke, 4 stroke
- cylinder arrangement: in-line, vee
- cylinder rating
- fuel supply: e.g. direct, or indirect injection, dual fuel
- gas exchange: natural aspiration, pressure charging arrangement.

9.3.4 Where an engine type has subsequently proved satisfactory in service with a number of applications a maximum uprating of 10 per cent may be considered without a further complete type test.

9.3.5 A type test will be considered to cover engines of a given design for a range of cylinder numbers in a given cylinder arrangement.

### Section 10

### Turbo-chargers

#### 10.1 Plans and particulars

10.1.1 The following plans and particulars are to be submitted for information:

- Cross sectional plans of the assembled turbocharger with main dimensions.
- Fully dimensioned plans of the rotor.
- Material particulars with details of welding and surface treatments.
- Turbo-charger operating and test data.
- A selected turbocharger is to be type tested.
- Manufacturer's burst test assessment.

#### 10.2 Type test

10.2.1 A type test is to consist of a hot gas running test of at least one hour duration at the maximum permissible speed and maximum permissible temperature. Following the test the turbocharger is to be completely dismantled for examination of all parts.

10.2.2 Alternative arrangements will be specially considered.

#### 10.3 Dynamic balancing

10.3.1 All rotors are to be dynamically balanced on final assembly to the Surveyor's satisfaction.

# Oil Engines

# Part 5, Chapter 2

Sections 10 &amp; 11

## 10.4 Overspeed test

10.4.1 All fully bladed rotor sections and impeller/inducer wheels are to be overspeed tested for three minutes at either 20 per cent above the maximum permissible speed at room temperature or 10 per cent above the maximum permissible speed at the normal working temperature.

## 10.5 Mechanical running test

10.5.1 Turbo-chargers are to be given a mechanical running test of 20 minutes duration at the maximum permissible speed.

10.5.2 Upon application, with details of an historical audit covering previous testing of turbochargers manufactured under an approved quality assurance scheme, consideration will be given to confining the test outlined in 10.5.1 to a representative sample of turbochargers.

## Section 11 Mass produced engines

### 11.1 Definition

11.1.1 Mass produced engines, for main and auxiliary purposes, are defined as those which are produced under the following criteria:

- (a) In quantity under strict quality control of material and parts, according to a quality assurance scheme acceptable to LR.
- (b) By the use of jigs and automatic machine tools designed to machine parts to specified tolerances for interchangeability, and which are verified on a regular inspection basis.
- (c) By assembly with parts taken from stock and requiring little or no fitting.
- (d) With bench tests carried out on individual assembled engines according to a specified programme.
- (e) With appraisal by final examination of engines selected at random after workshop testing.

11.1.2 Castings, forgings and other parts for use in mass produced engines are also to be produced by methods similar to those given in 11.1.1(a), (b) and (c), with appropriate inspection.

11.1.3 Pressure testing of components is to comply with 9.1.1.

11.1.4 The specification of a mass produced engine is to define the limits of manufacture of all component parts. The total production output is to be certified by the manufacturer and verified as may be required, by LR in accordance with the agreed manufacturer's quality assurance scheme, see 11.1.1(a).

## 11.2 Procedure for approval of mass produced engines

11.2.1 The procedure outlined in 11.2.2 to 11.2.5 applies to the inspection and certification of mass produced oil engines having a bore not exceeding 300 mm.

11.2.2 For the approval of a mass produced engine type, the manufacturer is to submit, in addition to the plans and particulars required by 1.1 and information required by 3.2, a list of subcontractors for main parts.

11.2.3 The manufacturer is to supply full information regarding the manufacturing processes and quality control procedures applied in the workshops. The information is to address the following:

- (a) Organisation of quality control systems.
- (b) Recording of quality control operations.
- (c) Qualification and independence of personnel in charge of quality control.

11.2.4 A running type test of at least 100 hours duration is to be carried out on an engine chosen from the production line. The type testing is to comply with 11.5.

11.2.5 LR reserves the right to limit the duration of validity of approval of a mass produced engine. LR is to be informed, without delay, of any change in the design of the engine, in the manufacturing or control processes, in the selection of materials or in the list of subcontractors for main parts.

## 11.3 Continuous review of production

11.3.1 LR Surveyors are to be provided free access to the manufacturer's workshops and to the quality control files.

11.3.2 The control of production, which is subject to survey, is to include the following:

- (a) Inspection and testing records are to be maintained to the satisfaction of the Surveyor.
- (b) The system for identification of parts is to be in accordance with recognised practice, and acceptable to LR.
- (c) The manufacturer is to provide full information about the quality control of the parts supplied by subcontractors for which certification may be required. LR reserves the right to apply direct and individual inspection procedures for parts supplied by subcontractors when deemed necessary.
- (d) At the request of an attending LR surveyor, a workshop test may be required for an individual engine.

## 11.4 Compliance and inspection certificate

11.4.1 Each engine which is to be installed on a ship classed by LR is to be supplied with a statement certifying that the engine is identical to the one which underwent the tests specified in 11.2.4, and state the test and inspection results. The statement is to be made on a form agreed with LR. Each statement is to include the identification number which appears on the engine. A copy of this statement is to be submitted to LR.

# Oil Engines

# Part 5, Chapter 2

Sections 11 & 12

## 11.5 Type test conditions

**11.5.1** The requirements in this section are applicable to the type testing of mass produced internal combustion engines where the manufacturer has requested approval. Omission or simplification of the type test requirements will be considered by LR for engines of an established type on application by the manufacturer.

**11.5.2** The engine to be tested is to be selected from the production line and agreed by LR.

**11.5.3** The duration and programme of type tests is to include the following:

- (a) 80 h at rated output.
- (b) 8 h at 110 per cent overload.
- (c) 10 h at varying partial loads (25 per cent, 50 per cent, 75 per cent and 90 per cent of rated output).
- (d) 2 h at maximum intermittent loads.
- (e) Starting tests.
- (f) Reverse running of direct reversing engines.
- (g) Testing of speed governor.
- (h) Testing of over-speed device.
- (j) Testing of lubricating oil system failure alarm device.
- (k) Testing of the engine with turbocharger out of action when applicable.
- (l) Testing of minimum speed for main propulsion engines and the idling speed for auxiliary engines.

**11.5.4** The type tests in 11.5.3 at the required outputs are to be combined together in working cycles for the whole duration within the limits indicated. See also 11.5.10 and 11.5.11.

**11.5.5** The overload testing required by 11.5.3 is to be carried out with the following conditions:

- (a) 110 per cent of rated power at 103 per cent revolutions per minute for engines directly driving propellers.
- (b) 110 per cent of rated power at 100 per cent revolutions per minute for engines driving electrical generators or for other auxiliary purposes.

**11.5.6** For prototype engines, the duration and programme of tests are to be specially agreed between the manufacturer and LR.

**11.5.7** As far as practicable during type testing the following particulars are to be continuously recorded:

- (a) Ambient air temperature.
- (b) Ambient air pressure.
- (c) Atmospheric humidity.
- (d) External cooling water temperature.
- (e) Fuel and lubrication oil characteristics.

**11.5.8** In addition to the particulars stated in 11.5.7 and as far as practicable, the following are also to be continuously measured and recorded:

- (a) Engine revolutions per minute.
- (b) Brake power.
- (c) Torque.
- (d) Maximum combustion pressure.
- (e) Indicator pressure diagrams where practicable.
- (f) Exhaust smoke (with an approved smoke meter).
- (g) Lubricating oil pressure and temperature.

- (h) Exhaust gas temperature in exhaust manifold, and, where facilities are available, from each cylinder.

(j) For turbocharged engines:

- Turbocharger revolutions per minute.
- Air temperature and pressures before and after turbo-blower and charge cooler.
- Exhaust gas temperature and pressures before and after the turbine.
- The cooling water inlet temperature to the charge air cooler.

**11.5.9** After the type test, the main parts and especially those subject to wear are to be dismantled for examination by LR Surveyors.

**11.5.10** For engines that are required to be approved for different purposes (multi-purpose engines), and that have different performances for each purpose, the programme and duration of test is to be modified to cover the whole range of the engine performance, taking into account the most severe conditions and intended purpose(s).

**11.5.11** The rated output for which the engine is to be tested is the output corresponding to that declared by the manufacturer and agreed by LR, i.e. actual maximum power which the engine is capable of delivering continuously between the normal maintenance intervals stated by the manufacturer at the rated speed and under the stated ambient conditions.

## Section 12

## Mass produced turbo-chargers

### 12.1 Application

**12.1.1** The following procedure applies to the inspection of exhaust driven turbo chargers which are manufactured on the basis of mass production methods similar to 11.1 as applicable and for which the maker has requested the approval.

### 12.2 Procedure for approval of mass produced turbo-chargers

**12.2.1** The procedure outlined in 12.2.2 to 12.2.5 applies to the inspection and certification of mass produced turbo-chargers when a simplified method of inspection has been requested by the manufacturers.

**12.2.2** For the approval of a mass produced turbo-charger, the manufacturer is to submit, in addition to the plans and particulars required by 10.1.1, a list of main current suppliers and subcontractors for rotating parts and an operation and maintenance manual.

**12.2.3** The manufacturer will supply full information regarding the material and quality control system used in the organization as well as the inspection methods, the way of recording and proposed frequency, and the method of material testing of important parts.

12.2.4 A Type test, see 10.2, is to be carried out on a standard unit taken from the assembly line and is to be witnessed by the Surveyor. The performance data which may have to be verified are to be made available at the time of the type test. For manufacturers who have facilities for testing the turbo-charger unit on an engine for which the turbo-charger is intended, substitution of the hot running test by a test run of one hour's duration at overload (110 per cent of the rated output) may be considered.

12.2.5 LR reserves the right to limit the duration of validity of approval of a mass produced turbo-charger. LR is to be informed, without delay, of any change in the design of the turbo-charger, in the manufacturing or control processes, in the selection of materials or in the list of subcontractors for main parts.

### **12.3 Continuous inspection of individual units**

12.3.1 LR Surveyors are to be provided with free access to the manufacturer's workshop to inspect at random the quality control measures and to witness the tests required by 12.3.3 to 12.3.7 as deemed necessary, and to have free access to all control records and subcontractor's certificates.

12.3.2 Each individual unit is to be tested in accordance with 12.3.4 to 12.3.7 by the maker who is to issue a final certificate.

12.3.3 Rotating parts of the turbo-charger blower are to be marked for easy identification with the appropriate certificate.

12.3.4 Material tests of the rotating parts are to be carried out by the maker or his subcontractor in accordance with the requirements of the Rules for Materials as applicable. The relevant certificate is to be produced and filed to the satisfaction of the Surveyor.

12.3.5 Pressure tests are to be carried out in accordance with Table 2.9.1. Special consideration will be given where design or testing features may require modification of the test requirements.

12.3.6 Dynamic balancing and overspeed tests are to be carried out, see 10.3 and 10.4, in accordance with the approved procedure for quality control. If each forged wheel is individually controlled by an approved non-destructive examination method, then no overspeed test may be required except for wheels of the test unit.

12.3.7 A mechanical running test, see 10.5, is to be carried out. The duration of the running test may be reduced to 10 minutes provided that the manufacturer is able to verify the distribution of defects established during the running tests on the basis of a sufficient number of tested turbo-chargers. For manufacturers who have facilities in their works for testing the turbo-chargers on an engine for which the turbo-chargers are intended, the bench test may be replaced by a test run of 20 minutes at overload (110 per cent of the rated output) on this engine.

### **12.4 Compliance and certificate**

12.4.1 For every turbo-charger unit liable to be installed on an engine intended for a ship classed by LR, the manufacturer is to supply a statement certifying that the turbo-charger is identical with one that underwent the tests specified in 12.2.4 and that prescribed tests were carried out. Results of these tests are to be also stated. This statement is to be made on a form agreed with LR and a copy is to be sent to LR. Each statement must have a number which is to appear on the turbo-charger.

## **Section 13 Type testing procedure for crankcase explosion relief valves**

### **13.1 Scope**

13.1.1 This test procedure identifies standard conditions by which crankcase explosion relief valves intended to be fitted to diesel engines can be tested to demonstrate that they satisfy LR requirements for type testing to a defined standard.

13.1.2 This test procedure is also applicable to explosion relief valves intended for gear cases.

13.1.3 Standard repeatable test conditions have been established using a methane gas and air mixture.

13.1.4 The test procedure is only applicable to explosion relief valves fitted with flame arresters.

### **13.2 Purpose**

13.2.1 The purpose of type testing crankcase explosion relief valves is fourfold:

- To verify the effectiveness of the flame arrester.
- To verify that the valve closes after an explosion.
- To verify that the valve is gas/air tight after an explosion.
- To establish the level of over-pressure protection provided by the valve.

### **13.3 Test facilities**

13.3.1 The test facilities for carrying out type testing of crankcase explosion relief valves are to meet the following requirements:

- The test facilities where testing is carried out are to be accredited to a National or International Standard for the testing of explosion protection devices.
- The test facilities are to be acceptable to LR.
- The test facilities are to be equipped so that they can control and record explosion testing in accordance with this procedure.
- The test facilities are to have equipment for controlling and measuring a methane gas in air concentration within a test vessel to an accuracy of  $\pm 0.1\%$ .
- The test facilities are to be capable of effective point-located ignition of a methane gas in air mixture.

- (f) The pressure measuring equipment is to be capable of measuring the pressure in the test vessel in at least two positions, one at the valve and the other at the test vessel centre. The measuring arrangements are to be capable of measuring and recording the pressure changes throughout an explosion test. The result of each test is to be documented by video recording and if necessary by recording with a heat sensitive camera.
- (g) The test vessel for explosion testing is to have documented dimensions that are to be such that its height or length between dished ends is approximately 2 times its diameter but not more than 2.5 times. The internal volume of the test vessel is to be determined from the vessel dimensions that include any standpipe arrangements.
- (h) The test vessel for explosion testing is to be provided with a flange for mounting the explosion relief valve in an orientation consistent with how it will be installed in service, i.e., in the vertical plane or the horizontal plane. The flange arrangement is to be made approximately one third of the height or length of the test vessel.
- (j) A circular flat plate having the following dimensions is to be provided for fitting between the pressure vessel flange and valve to be tested:
  - (i) Outside diameter =  $2 \times D$  where  $D$  is the outer diameter of the valve top cover. The circular plate is to provide simulation of the crankcase surface.
  - (ii) Internal bore having the same internal diameter as the valve to be tested.
- (k) The test vessel for explosion testing is to have connections for measuring the methane in air mixture in at least two positions, i.e., top and bottom.
- (l) The test vessel for explosion testing is to be provided a means of fitting an ignition source at a position approximately one third the height or length of the vessel, see 13.4.3.
- (m) The test vessel volume is to be as far as practicable, related to the size of relief valve to be tested. In general, the volume is to correspond to the requirement in 6.3.1 for the free area of explosion relief valve to be not less than  $115 \text{ cm}^2/\text{m}^3$  of crankcase gross volume, e.g., the testing of a valve having  $1150 \text{ cm}^2$  of free area, would require a test vessel with a volume of  $10 \text{ m}^3$ . In no case is the volume of the test vessel to vary by more than +15 per cent to -10 per cent or from the  $115 \text{ cm}^2/\text{m}^3$  volume ratio.

## 13.4 Explosion test process

**13.4.1** All explosion tests to verify the functionality of crankcase explosion relief valves are to be carried out using an air and methane mixture with a methane concentration of 9,5 per cent  $\pm 0,5$  per cent. The pressure in the test vessel is to be not less than atmospheric and not exceed 0,2 bar.

**13.4.2** The concentration of methane in the test vessel is to be measured at the top and bottom of the vessel and these concentrations are not to differ by more than 0,5 per cent.

**13.4.3** The ignition of the methane and air mixture is to be made at a position approximately one third of the height or length of the test vessel opposite to where the valve is mounted.

**13.4.4** The ignition is to be made using a 100 joule explosive charge.

## 13.5 Valves to be tested

**13.5.1** The valves used for type testing are to be manufactured and tested in accordance with procedures acceptable to LR and selected from the manufacturer's usual production line for such valves by the LR Surveyor witnessing the tests.

**13.5.2** For approval of a specific valve size, three valves of that specific size are to be tested. The valves are to have been tested at the manufacturer's works to demonstrate that the opening pressure is in accordance with that agreed by the engine builder and valve manufacturer within a tolerance of  $\pm 20$  per cent and that the valve is air tight at a pressure below the opening pressure for at least 30 seconds.

**13.5.3** The selection of valves for type testing is to recognize the orientation in which they are intended to be installed on the engine or gear case. Where it is intended that valves be installed in the vertical or near vertical or the horizontal or near horizontal position, then three valves of each size are to be tested for each intended orientation.

## 13.6 Method

**13.6.1** The following requirements are to be satisfied at explosion testing:

- (a) The explosion testing is to be witnessed by a LR Surveyor where type testing approval is required by LR.
- (b) Valves are to be tested in the vertical or horizontal position consistent with the orientation in which they are intended to be installed on an engine or gear case, usually in the vertical position, see 13.5.3.
- (c) Where valves are to be installed on an engine or gear case with shielding arrangements to deflect the emission of explosion combustion products, the valves are to be tested with the shielding arrangements fitted.
- (d) Type testing is to be carried out for each range of valves for which a manufacturer requires LR approval.
- (e) Successive explosion testing to establish a valve's functionality is to be carried out as quickly as possible during stable weather conditions.
- (f) The pressure rise and decay during all explosion testing is to be recorded.
- (g) The external condition of the valves is to be monitored during each test. The test facility is to produce a report on the explosion test findings.

**13.6.2** The explosion testing is to be in three stages for each valve that is required to be approved as being type tested.

**13.6.3 Stage 1.** Two explosion tests are to be carried out with the flange opening fitted with the circular plate covered by a 0,05 mm thick polythene film. These tests establish a reference pressure level for determination of the effects of a relief valve in terms of pressure rise in the test vessel, see 13.7.1(f).



## 13.6.4 Stage 2:

- (a) Two explosion tests are to be carried out on three different valves of the same size. Each valve is to be mounted in the orientation for which approval is sought i.e., in the vertical or horizontal position with the circular plate described in 13.3.1(j) located between the valve and pressure vessel mounting flange.
- (b) The first of the two tests on each valve is to be carried out with a 0,05mm thick polythene bag, having a minimum diameter of three times the diameter of the circular plate and volume not less than 30 per cent of the test vessel, enclosing the valve and circular plate. Before carrying out the explosion test the polythene bag is to be empty of air. The polythene bag is required to provide a readily visible means of assessing whether there is flame transmission through the relief valve following an explosion.
- (c) Provided that the first explosion test successfully demonstrated that there was no indication of combustion outside the flame arrester and there are no signs of damage to the flame arrester or valve, a second explosion test without the polythene bag arrangement is to be carried out. During the second explosion test, the valve is to be visually monitored for any indication of combustion outside the flame arrester. The second test is required to demonstrate that the valve can still function in the event of a secondary crankcase explosion.
- (d) After each explosion, the test vessel is to be maintained in the closed condition for at least 10 seconds to enable the tightness of the valve to be ascertained. The tightness of the valve can be verified during the test from the pressure/time records or by a separate test after completing the second explosion test.

**13.6.5 Stage 3.** Carry out two further explosion tests as described in Stage 1. These further tests are required to provide an average baseline value for assessment of pressure rise, recognizing that the test vessel ambient conditions may have changed during the testing of the explosion relief valves in Stage 2.

## 13.7 Assessment

**13.7.1** Assessment of the valves after explosion testing is to address the following:

- (a) The valves to be tested are to have evidence of appraisal/approval by LR, see also 13.5.1.
- (b) The designation, dimensions and characteristics of the valves to be tested are to be recorded. This is to include the free area of the valve and of the flame arrester and the amount of valve lift at 0,2 bar.
- (c) The test vessel volume is to be determined and recorded.
- (d) For acceptance of the functioning of the flame arrester there is not to be any indication of flame or combustion outside the valve during an explosion test.
- (e) The pressure rise and decay during an explosion is to be recorded, with indication of the pressure variation showing the maximum overpressure and steady under-pressure in the test vessel during testing. The pressure variation is to be recorded at two points in the pressure vessel.

- (f) The effect of an explosion relief valve in terms of pressure rise following an explosion is ascertained from maximum pressures recorded at the centre of the test vessel during the three stages. The pressure rise within the test vessel due to the installation of a relief valve is the difference between average pressure of the four explosions from Stages 1 and 3 and the average of the first tests on the three valves in Stage 2.
- (g) The valve tightness is to be ascertained by verifying from records that an underpressure of at least 0,3 bar is held by the test vessel for at least 10 seconds following an explosion.
- (h) After each explosion test in Stage 2, the external condition of the flame arrester is to be examined for signs of damage and/or deformation.
- (j) After completing the explosion tests, the valves are to be dismantled and the condition of all components ascertained and documented. In particular, any indication of valve sticking or uneven opening is to be noted. Photographic records of the valve condition are to be taken and included in the report.

## 13.8 Design series qualification

**13.8.1** The qualification of quenching devices to prevent the passage of flame can be evaluated for other similar devices of identical type where one device has been tested and found satisfactory.

**13.8.2** The quenching ability of a flame screen depends on the total mass of quenching lamellas/mesh. Provided the materials, thickness of materials, depth of lamellas/thickness of mesh layer and the quenching gaps are the same, then the same quenching ability can be qualified for different size of flame arrestors subject to (a) and (b) being satisfied.

$$(a) \quad \frac{n_1}{n_2} = \sqrt{\frac{S_1}{S_2}}$$

$$(b) \quad \frac{A_1}{A_2} = \frac{S_1}{S_2}$$

where

- $n_1$  = number of lamellas of size 1 quenching device for a valve with a relief area equal to  $S_1$
- $n_2$  = number of lamella of size 2 quenching device for a valve with a relief area equal to  $S_2$
- $A_1$  = free area of quenching device for a valve with a relief area equal to  $S_1$
- $A_2$  = free area of quenching device for a valve with a relief area equal to  $S_2$

## 13.9 The report

**13.9.1** The test facility is to deliver a full report that includes the following information and documents:

- (a) Test specification.
- (b) Details of test pressure vessel and valves tested.
- (c) The orientation in which the valve was tested, (vertical or horizontal position).
- (d) Methane in air concentration for each test.
- (e) Ignition source.

- (f) Pressure curves for each test.
- (g) Video recordings of each valve test.

## 13.10 Approval

13.10.1 Approval of an explosion relief valve is the prerogative of LR based on the appraisal of plans and particulars and the test facility's report of the results of type testing.

## ■ Section 14 Type testing procedure for crankcase oil mist detection/monitoring and alarm arrangements

### 14.1 Scope

14.1.1 This test procedure identifies standard conditions by which crankcase oil mist detection/monitoring and alarm equipment and systems intended to be fitted to diesel engines can be tested to demonstrate that they satisfy LR requirements for type testing to a defined standard.

14.1.2 This test procedure is also applicable to oil mist detection/monitoring and alarm arrangements intended for gear cases.

### 14.2 Purpose

14.2.1 The purpose of type testing crankcase oil mist detection/monitoring and alarm arrangements is seven fold:

- (a) To verify the functionality of the system.
- (b) To verify the effectiveness of the oil mist detectors.
- (c) To verify the accuracy of oil mist detectors.
- (d) To verify the alarm set points.
- (e) To verify time delays between mist extraction from crankcase and alarm activation.
- (f) To verify the operation of alarms to indicate functional failure in the equipment and associated arrangements.
- (g) To verify that there is an indication when optical obscuration has reached a level that will affect the reliability of information and alarms.

### 14.3 Test facilities

14.3.1 The test house carrying out type testing of crankcase oil mist detection/monitoring and alarm equipment and arrangements is to satisfy the following criteria:

- (a) The test facilities are to have the full range of facilities for carrying the type and functionality tests required by this procedure and be acceptable to LR.
- (b) The test house that verifies that the equipment ascertains the levels of oil mist concentration is to be equipped so that it can control, measure and record oil mist concentration levels in terms of mg/l to an accuracy of  $\pm 10$  per cent in accordance with this procedure.

- (c) The type tests are to be witnessed by a LR Surveyor unless otherwise agreed.
- (d) The oil mist concentrations are to be ascertained by the gravimetric deterministic method or equivalent. The gravimetric deterministic method is a laboratory process where the difference in weight of a millipore (typically 0,8  $\mu\text{m}$ ) filter is ascertained by weighing the filter before and after drawing 1 dm<sup>3</sup> of oil mist through the filter.
- (e) The results of a gravimetric analysis are considered invalid and are to be rejected if the resultant calibration curve has an increasing gradient with respect to the oil mist detection/monitoring reading. This situation occurs when insufficient time has been allowed for the oil mist to become homogeneous. Single results that are more than 10 per cent below the calibration curve are to be rejected. This situation occurs when the integrity of the filter unit has been compromised and not all of the oil is collected on the filter paper.
- (f) The filters are required to be weighed to a precision of 0,1 mg and the volume of air/oil mist sampled to a precision of 10 ml.

### 14.4 Equipment testing

14.4.1 The range of tests is to include the following for the alarm/monitoring panel:

- (a) Functional tests described in 14.5.
- (b) Electrical power supply failure test.
- (c) Power supply variation test.
- (d) Dry heat test.
- (e) Damp heat test.
- (f) Vibration test.
- (g) EMC test.
- (h) Insulation resistance test.
- (i) High voltage test.
- (k) Static and dynamic inclinations, if moving parts are contained.

14.4.2 The range of tests is to include the following for the detectors:

- (a) Functional tests described in 14.5.
- (b) Electrical power supply failure test.
- (c) Power supply variation test.
- (d) Dry heat test.
- (e) Damp heat test.
- (f) Vibration test.
- (g) Insulation resistance test.
- (h) High voltage test.
- (i) Static and dynamic inclinations, if moving parts are contained.

### 14.5 Functional test process

14.5.1 All tests to verify the functionality of crankcase oil mist detection/monitoring devices are to be carried out in accordance with 14.5.2 to 14.5.6 with an oil mist concentration in air, known in terms of mg/l to an accuracy of  $\pm 10$  per cent.

14.5.2 The concentration of oil mist in the test vessel is to be measured in the top and bottom of the vessel and these concentrations are not to differ by more than 10 per cent.

# Oil Engines

# Part 5, Chapter 2

Section 14

14.5.3 The oil mist monitoring arrangements are to be capable of detecting oil mist in air concentrations of between 0 and 10 per cent of the lower explosive limit (LEL), which corresponds to an oil mist concentration of approximately 50 mg/l (13 per cent oil-air mixture).

14.5.4 The operation of the alarm indicators for oil mist concentration in air are to be verified and are to provide an alarm at a maximum setting corresponding to 5 per cent of the LEL or approximately 2,5 mg/l.

14.5.5 Where alarm set points can be altered, the means of adjustment and indication are to be verified against the equipment manufacturer's instructions.

14.5.6 Where oil mist is drawn into a detector/monitor via piping arrangements, the time delay between the sample leaving the crankcase and operation of the alarm is to be determined for the longest and shortest lengths of pipes recommended by the manufacturer. The pipe arrangements are to be in accordance with the manufacturer's instructions/recommendations.

## 14.6 Detectors/monitors and equipment to be tested

14.6.1 The detectors/monitors and equipment used in type testing are to be manufactured and tested in accordance with procedures acceptable to LR and selected from the manufacturer's usual production line for such equipment by the LR Surveyor witnessing the tests.

14.6.2 Two sets of detectors/monitors requiring approval are to be tested. One set is to be tested in the clean condition and the other in a condition that represents the maximum degree of lens obscuration that is stated as being acceptable by the manufacturer.

## 14.7 Method

14.7.1 The following requirements are to be satisfied at type testing:

- (a) The testing is to be witnessed by a LR surveyor where type testing approval is required by LR.
- (b) Oil mist detection/monitoring devices are to be tested in the orientation in which they intended to be installed on an engine or gear case.
- (c) Type testing is to be carried out for each range of oil mist detection/monitoring devices that a manufacturer requires LR approval.
- (d) The test house is to produce a test report.

## 14.8 Assessment

14.8.1 Assessment of oil mist detection/monitoring devices after testing is to address the following:

- (a) The devices to be tested are to have evidence of appraisal/approval by LR, See *also* 14.6.1.

- (b) The details of the detection/monitoring devices to be tested are to be recorded. This is to include manufacturer, type designation, oil mist concentration assessment capability and alarm settings.
- (c) After completing the tests, the detection/monitoring devices are to be examined and the condition of all components ascertained and documented. Photographic records of the monitoring devices condition are to be taken and included in the report.

## 14.9 Design series qualification

14.9.1 The approval of one detection/monitoring device may be used to qualify other devices having identical construction details. Proposals are to be submitted for consideration.

## 14.10 The Report

14.10.1 The test house is to provide a full report which includes the following information and documents:

- (a) Test specification.
- (b) Details of devices tested.
- (c) Results of tests.

## 14.11 Acceptance

14.11.1 Acceptance of crankcase oil mist detection/monitoring devices is the prerogative of LR based on the appraisal of plans and particulars and the test house report of the results of type testing.

14.11.2 The following information is to be submitted to LR for acceptance of oil mist detection/monitoring and alarm arrangements:

- (a) Description of oil mist detection/monitoring equipment and system including alarms.
- (b) Copy of the test house report identified in 14.10.
- (c) Schematic layout of engine oil mist detection/monitoring arrangements showing location of detectors/sensors and piping arrangements and dimensions.
- (d) Maintenance and test manual which is to include the following information:
  - Intended use of equipment and its operation.
  - Functionality tests.
  - Maintenance routines and spare parts recommendations.
  - Limit setting and instructions for safe limit levels.
  - Where necessary, details of configurations in which the equipment is and is not to be used.

## Section 15 Electronically controlled engines

### 15.1 Scope

15.1.1 The requirements of this section are applicable to engines for propulsion, auxiliary and emergency power purposes with software-based electronic control of fuel, air and exhaust systems.

15.1.2 These engines may be of the slow, medium or high-speed type. They generally have no camshaft to drive fuel, air and exhaust systems, but have common rail fuel/hydraulic arrangements and hydraulic actuating systems for the functioning of the fuel, air and exhaust systems.

15.1.3 The operation of these engines relies on the effective monitoring of a number of parameters such as crank angle, engine speed, temperatures and pressures using one or more electronic control systems to provide the services essential for the operation of the engine such as fuel injection, air inlet, exhaust and speed control.

15.1.4 Deviation from Rule requirements are to be submitted and will be considered on the basis of technical justification by the engine builder.

15.1.5 During the life of the engine any changes to hardware, software, control and monitoring systems which may affect the safety and reliable operation of the engine are to be submitted and approved by LR.

### 15.2 Plans and particulars

15.2.1 In addition to the plans and particulars required by Section 1 the following information is to be submitted:

- (a) A general overview of the operating principles, supported by schematics explaining the functionality of individual systems and sub-systems. The information is to relate to the engine capability and functionality under defined operating and emergency conditions such as recovery from a failure or malfunction, with particular reference to the functioning of electronic control systems and any sub-systems. The information is also to indicate if the engine has different modes of operation, such as to limit exhaust gas emissions and/or to run under an economic fuel consumption mode or any other mode that can be controlled by electronic control systems.
- (b) Details of hydraulic systems for actuation of sub-systems (fuel injection, air inlet and exhaust), to include details of the design/construction of pipes, pumps, valves, accumulators and the control of valves/pumps. Details of pump drive arrangements are also to be included.
- (c) Failure Modes and Effects Analysis (FMEA) of the mechanical, pressure containing and electrical systems and arrangements that support the operation of the engine. The analysis is to demonstrate that suitable risk mitigation has been achieved so that a system will tolerate a single failure in equipment or loss of an associated sub-system such that operation of the engine will not be lost or degraded beyond acceptable performance criteria of the engine. See 13.5.

- (d) A schedule of testing and trials to demonstrate that the engine is capable of operating as described in the design statement, and any testing required to verify the conclusions of the FMEA.
- (e) Operating manuals which describe the particulars of each system and, together with maintenance instructions, include reference to the arrangements for making modifications and changes to electronic control systems and for the functioning of sub-systems.
- (f) Quality plan for sourcing, design, installation and testing of all components used in the oil fuel and hydraulic oil systems installed with the engine for engine operation.
- (g) Fatigue analysis for all high pressure oil fuel and hydraulic oil piping arrangements required for engine operation where failure of the pipe or its connection or a component would be the cause of engine unavailability. The analysis is to concentrate on high pressure components and sub-systems and recognise the pressures and fluctuating stresses that the pipe system may be subject to in normal service.
- (h) Schedule of testing at engine builders, pre-sea trial commissioning and sea trials. The test schedules are to identify all modes of engine operation and the sea trials are to include typical port manoeuvres under all intended engine operating modes.
- (j) Evidence of type testing of the engine with electronic controls, or a proposed test plan at the engine builders with the electronic controls functioning, to verify the functionality and behaviour under fault conditions of the electronic control system.

15.2.2 In addition to the plans and particulars required by Pt 6, Ch 1 the following information for control, alarm, monitoring and safety systems relating to the operation of an electronically controlled engine is to be submitted:

- (a) System requirements specification.
- (b) Description of operation with explanatory diagrams.
- (c) Line diagrams of control circuits.
- (d) List of monitored points.
- (e) List of control points.
- (f) List of alarm points.
- (g) List of safety functions and details of any overrides, including consequences of use.
- (h) Details of hardware configuration.
- (j) Hardware certification details.
- (k) Software quality plan.
- (l) System integration plan.
- (m) Failure Mode and Effects Analysis (FMEA). See Pt 5, Ch 2, 1.1.4.
- (n) Factory acceptance, integration, harbour and sea trials/test schedules for hardware and software.
- (o) Software certification details.
- (p) Quality plan for sourcing, design installation and testing of all components used in the control, alarm, monitoring and safety systems installed with the engine for engine operation.

### 15.3 Oil fuel and hydraulic oil systems

15.3.1 Oil fuel and hydraulic oil piping systems arrangements are to comply with Chapters 2, 11, 12, 13 and 14 as applicable.

15.3.2 Where pumps are essential for engine operation, not less than two oil fuel and two hydraulic oil pressure pumps are to be provided for their respective service and arranged such that failure of one pump does not render the other inoperative. Each oil fuel pump and hydraulic oil pump is to be capable of supplying the quantity of oil for engine operation at its maximum continuous rating and arranged ready for immediate use.

15.3.3 The oil fuel pressure piping between the oil fuel high pressure pumps and the fuel injectors is to be protected with a jacketed piping system capable of containing oil fuel leakage from a high pressure pipe failure.

15.3.4 The hydraulic oil pressure piping between the high pressure hydraulic pumps and hydraulic actuators is to be protected with a jacketed piping system capable of containing hydraulic oil leakage from a high pressure pipe failure.

15.3.5 Accumulators and associated high pressure piping are to be designed, manufactured and tested in accordance with a standard applicable to the maximum pressure and temperature rating of the system.

15.3.6 All valves, cocks and screwed connections are to be of a type-tested type applicable to the maximum service conditions anticipated in normal service.

15.3.7 Isolating valves and cocks are to be located as near as practicable to the equipment to be isolated. All valves forming part of the oil fuel and hydraulic oil installation are to be capable of being controlled from readily accessible positions above the working platform.

15.3.8 High pressure oil fuel and high pressure hydraulic oil piping systems are to be provided with high pressure alarms with set points that do not exceed the system design pressures.

15.3.9 High pressure oil fuel and high pressure hydraulic piping systems are to be provided with suitable relief valves on any part of the system that can be isolated and in which pressure can be generated. The settings of the relief valves are not to exceed the design pressures. The valves are to be of adequate size and so arranged as to avoid an undue rise in pressure above the design pressures.

15.3.10 Equipment fitted for monitoring pressures and temperatures in the high pressure oil fuel and high pressure hydraulic oil systems is to comply with a recognised standard suitable to the anticipated vibration and temperature conditions.

15.3.11 A fatigue analysis is to be carried out in accordance with a standard applicable to the system under consideration and all anticipated pressure, pulsation and vibration loads are to be addressed. The analysis is to demonstrate that the design and arrangements are such that the likelihood of failure is as low as reasonably practicable. The analysis is to identify all assumptions made and standards to be applied during manufacture and testing of the system. Any potential weak points which may develop due to incorrect construction or assembly are also to be identified.

15.3.12 For high pressure oil containing and mechanical power transmission systems, the quality plan for sourcing, design, installation and testing of components is to address the following issues:

- (a) Design and manufacturing standard(s) applied.
- (b) Materials used for construction of key components and their sources.
- (c) Details of the quality control system applied during manufacture and testing.
- (d) Details of type approval, type testing or approved type status assigned to the machinery or equipment.
- (e) Details of installation and testing recommendations for the machinery or equipment.

## 15.4 Electronic control systems

15.4.1 Plans and details of electronic control systems are to comply with Pt 6, Ch 1 and Ch 2 as applicable.

15.4.2 For electronic control systems and electrical actuating systems, the quality plan for sourcing, design, installation and testing of components is to address the following issues:

- (a) Standard(s) applied.
- (b) Details of the quality control system applied during manufacture and testing.
- (c) Details of type approval, type testing or approved type status assigned to the equipment.
- (d) Details of installation and testing recommendations for the equipment.
- (e) Details of any local and/or remote diagnostic arrangements where assessment and alteration of control parameters can be made which can affect the operation of the engine.
- (f) Details of arrangements for software upgrades.

15.4.3 The system integration plan is required to identify the process for verification of the functional outputs from the electronic control systems with particular reference to system integrity, consistency, security against unauthorised changes to software and maintaining the outputs within acceptable tolerances for safe and reliable operation of the engine within stated performance criteria.

## 15.5 FMEA analysis

15.5.1 A Failure Mode and Effects Analysis (FMEA) is to demonstrate that a failure of the functioning of an electronic control system:

- (a) Will not result in the loss of the ability to provide the services essential for the operation of the engine (see Pt 6, Ch 1, 2.5.8 and 2.12.2);
- (b) will not affect the normal operation of the services essential for the operation of the engine other than those services dependent upon the failed part (see Pt 6, Ch 1, 2.13.4 and 2.13.5); and
- (c) will not leave either the engine, or any equipment or machinery associated with the engine, or the ship in an unsafe condition (see Pt 6, Ch 1, 2.3.12, 2.4.6, 2.5.4, 2.10.3, 2.13.5).

# Oil Engines

## Part 5, Chapter 2

Sections 15 &amp; 16

15.5.2 Where FMEA analysis is required to be carried out the reports submitted are to address the following issues:

- Identify the standards used for analysis and system design.
- Identify the objectives of the analysis.
- Identify any assumptions made in the analysis.
- Identify the equipment, system or sub-system, mode of operation and the equipment.
- Identify potential failure modes and their causes.
- Evaluate the local effects (e.g. fuel injection failure) and the effects on the system as a whole (e.g. loss of propulsion power) of each failure mode.
- Identify measures for reducing the risks associated with each failure mode. This may be through system design, provision of redundant systems and/or quality control procedures for sourcing, manufacture and testing.
- Identify trials and testing necessary to prove conclusions.

15.5.3 At sub-system level it is acceptable to consider failure of equipment items and their functions, e.g. failure of a pump to produce flow or pressure head. It is not required that the failure of components within that pump be analysed, and failure need only be dealt with as a cause of failure of the pump.

15.5.4 In an electronically controlled engine it is necessary to define the essential services on which the operation of the engine relies and the control functions, alarm functions and safety functions for the equipment and machinery providing these services. Examples of essential services are:

- Starting arrangements.
- Fuel supply arrangements.
- Lubricating oil arrangements.
- Hydraulic oil arrangements.
- Cooling arrangements.
- Power supply arrangements.

## Section 16 Alarms and safeguards for emergency diesel engines

### 16.1 Application

16.1.1 These requirements apply to emergency diesel engines required to be immediately available in an emergency and capable of being controlled remotely or automatically.

### 16.2 Plans and information

16.2.1 Plans, information and test schedules to be submitted for design appraisal are to be in accordance with Pt 6, Ch 1.

### 16.3 Alarms and safeguards

16.3.1 Alarm and safety systems are to comply with the requirements of Pt 6, Ch 1.

16.3.2 Alarms and safeguards are to be fitted in accordance with Table 2.16.1.

**Table 2.16.1 Alarms and safeguards for emergency diesel engines**

Item	Alarm	Alarm	Note
Emergency Diesel Engine	≥ 220 kW	<220 kW	
Fuel oil leakage from pressure pipes	Leakage	Leakage	See 7.1.2
Lubricating oil temperature	High	—	—
Lubricating oil pressure	Low	Low	—
Oil mist concentration in crankcase	High	—	See Note
Coolant pressure or flow	Low	—	—
Coolant Temperature (can be air )	High	High	—
Overspeed	High	—	Automatic shutdown
NOTE For engines having a power of more than 2250 kW or a cylinder bore of more than 300 mm.			

16.3.3 The safety and alarm systems are to be designed to 'fail safe'. The characteristics of the 'fail safe' operation are to be evaluated on the basis not only of the system and its associated machinery, but also the complete installation, as well as the ship.

16.3.4 Regardless of the engine output, if shutdowns additional to those specified in Table 2.14.1 are provided except for the overspeed shutdown, they are to be automatically overridden when the engine is in automatic or remote control mode during navigation.

16.3.5 Grouped alarms of at least those items listed in Table 2.14.1 are to be arranged on the bridge.

16.3.6 In addition to the fuel oil control from outside the space, a local means of engine shutdown is to be provided.

16.3.7 Local indications of at least those items listed in Table 2.14.1 are to be provided within the same space as the diesel engines and are to remain operational in the event of failure of the alarm and safety systems.

## ■ Section 17 General requirements

### 17.1 Turning gear

17.1.1 Turning gear is to be provided for all engines to facilitate operating and maintenance regimes as required by the manufacturer.

17.1.2 The turning gear for all main propulsion engines is to be power-driven and, if electric, is to be continuously rated at a value to ensure protection to the weakest part of the machinery.

17.1.3 The turning gear for auxiliary engines may be hand operated (manual) except where this is not practicable, in which case the provision of 17.1.2 is to be complied with.

17.1.4 The turning gear for all engines is to be fitted with safety interlocks which prevent engine operation when engaged, see Ch 1.3.10. Indication of engaged/not engaged is to be provided at all start positions.<sup>1</sup>

17.1.5 The remote control device of power-driven turning gear is to be so designed that power is removed from the turning gear when the operating switch is released.

17.1.6 Means are to be provided to secure the turning gear when disengaged.

17.1.7 Overload protection arrangements are to be provided to prevent damage to the electric motor and the turning gear train.

## ■ Section 18 Program for trials of diesel engines to assess operational capability

### 18.1 Works trials (acceptance test)

18.1.1 Diesel engines which are to be subjected to trials on the test bed at the manufacturer's works and under attendance by the Surveyor(s) are to be tested in accordance with the scope of works trials specified in 18.1.2 to 18.1.9. The scope of the trials is to be agreed between the LR Surveyor and the manufacturer prior to testing. At the discretion of the Surveyor, the scope of the trials may be extended depending on the engine application.

18.1.2 For all stages of the works trials the pertaining operation values are to be measured and recorded by the engine manufacturer. All results are to be compiled in an acceptance protocol to be issued by the engine manufacturer.

18.1.3 In each case given in Table 2.18.1, all measurements conducted at the various load points shall be carried out at steady operating conditions. The readings for 100 per cent power (rated power at rated speed) are to be taken twice at an interval of at least 30 minutes.

18.1.4 The data to be measured and recorded, when testing the engine at various load points, are to include all necessary parameters for the engine operation. The crankshaft deflection is to be checked when this check is required by the manufacturer during the operating life of the engine. Crankshaft deflection measurements are to be taken before (cold condition) and after (hot condition) works acceptance trials.

18.1.5 Checks of components to be presented for inspection after the works trials are left to the discretion of the Surveyor.

18.1.6 The Surveyor may require that after the trials the fuel delivery system is restricted so as to limit the engines to run at not more than 100 per cent power. The setting of the restriction is to be made as applicable to the intended fuel. Any restriction settings, and other changes to the engine's fuel injection equipment required for operation on special fuels, are to be recorded and included by the engine manufacturer.

18.1.7 For the duration of the acceptance test, no interventions or adjustments will be made to the machinery under test.

18.1.8 The testing of exhaust gas emissions is to comply with MARPOL as applicable.

18.1.9 For all stages that the engine is to be tested and where no duration is specified in Table 2.18.1, the load point is to be maintained for a sufficient period to allow pertaining values to be measured and recorded when the engine has achieved a steady operating condition.

### 18.2 Shipboard trials

18.2.1 After the conclusion of the running-in programme prescribed by the engine manufacturer, engines are to undergo shipboard trials as specified in Table 2.18.2. The scope of the trials is to be agreed between the LR Surveyor and the Shipyard prior to testing.

18.2.2 Engines driving generators or important auxiliaries are to be subjected to an operational test for at least 4 hours. During the test, the set concerned is required to operate at its rated power for an extended period. It is to be demonstrated that the engine is capable of supplying 100 per cent of its rated power, and in the case of shipboard generating sets account shall be taken of the times needed to actuate the generator's overload protection system.

18.2.3 In addition to 18.2.2, for engines driving generators for electric propulsion motors as well as auxiliaries, an operational test is to be carried out of at least 4 hours duration at a load which corresponds to 100 per cent of the electric propulsion motor(s) rated power. The astern/ahead manoeuvring capability of the propulsion system is to be demonstrated.

**Table 2.18.1 Scope of works trials for diesel engines**

Main engines driving propellers and waterjets		
Trial condition	Duration	Note
100% power (rated power) at rated engine speed, $R$	$\geq 60$ minutes	After having reached steady conditions
110% power at engine speed corresponding to $1,032 \cdot R$	30–45 minutes	After having reached steady conditions (1)
90% (or maximum continuous power), 75%, 50% and 25%	—	Powers in accordance with the nominal propeller curve
Starting and reversing manoeuvres	—	—
Testing of governor and independent overspeed protective device	—	See 5.2
Shut down device	—	See 5.4
Engines driving generators		
Trial condition	Duration	Note
100% power (rated power) at rated engine speed, $R$	$\geq 50$ minutes	After having reached steady conditions (2)
110% power	15 minutes	After having reached steady conditions (2) (3)
75%, 50% and 25% power and idle run	—	(2)
Start-up tests	—	—
Testing of governor and independent overspeed protective device	—	See 5.3
Shut-down device	—	See 5.4
<b>NOTES</b> 1. After running on the test bed, the fuel delivery system of main engines is normally to be so adjusted that overload power cannot be given in service. 2. The test is to be performed at rated speed with a constant governor setting. 3. After running on the test bed, the fuel delivery system of diesel engines driving generators must be adjusted such that overload (110%) power can be given in service after installation on board, so that the governing characteristics including the activation of generator protective devices can be fulfilled at all times.		

18.2.4 The suitability of an engine to burn residual or other special fuels is to be demonstrated, if the machinery installation is arranged to burn such fuels in service. *See also* Pt 6, Ch 1,7.2.1.

18.2.5 At the discretion of the attending Surveyor, the scope of the trials may be expanded in consideration of special operating conditions, such as towing, trawling, etc

## ■ Cross-references

The pumping arrangements, including cooling water and lubricating oil systems, are to comply with the requirements of Chapter 14.

For spare gear, see Chapter 16.



**Table 2.18.2 Scope of shipboard trials for diesel engines**

Main engines driving fixed-pitch propellers (1) (2)		
Trial condition	Duration	Note
At rated engine speed, $R$	$\geq 4$ hours	—
At engine speed corresponding to normal continuous power	$\geq 2$ hours	—
At engine speed corresponding to $1,032 \cdot R$	30 minutes	Where the engine adjustment permits, see 18.1.6
At minimum on-load speed	—	—
Starting and reversing manoeuvres	—	See Section 8
In reverse direction of propeller rotation during the dock or sea trials at a minimum engine speed of $0,7 \cdot R$	10 minutes	—
Monitoring, alarms and safety systems	—	—
Where imposed, test to ensure engine can pass safely through barred speed range	—	—
Engines driving generators for propulsion		
Trial condition	Duration	Note
100% power (rated power) see 18.2.3	$\geq 4$ hours	(3) (4)
At normal continuous power	$\geq 4$ hours	(3) (4)
In reverse direction of propeller rotation at a minimum speed of 70% of the nominal propeller speed	10 minutes	(3) (4)
Starting manoeuvres	—	—
Monitoring, alarm and safety systems	—	—
<b>NOTES</b> 1. For main propulsion engines driving controllable pitch propellers, waterjets or reversing gears, the tests for main engines driving fixed-pitch propellers apply as appropriate. 2. Controllable pitch propellers are to be tested with various propeller pitches. 3. The tests are to be performed at rated speed with a constant governor setting. 4. Tests are to be based on the rated electrical powers of the driven generators.		



# Steam Turbines

## Part 5, Chapter 3

Sections 1, 2 & 3

### Section

- 1 **Plans and particulars**
- 2 **Materials**
- 3 **Design and construction**
- 4 **Safety arrangements**
- 5 **Emergency arrangements**
- 6 **Tests and equipment**

### ■ Scope

The requirements of this Chapter are applicable to steam turbines for main propulsion and also, where powers exceed 110 kW (150 shp), to those for essential auxiliary services.

### ■ Section 1 Plans and particulars

#### 1.1 Plans

1.1.1 The following plans are to be submitted for consideration, together with particulars of materials, maximum shaft powers and revolutions per minute, see Ch 1,3.3. The pressures and temperatures applicable at maximum shaft power and under the emergency conditions of 5.2 are to be stated or indicated on the plans.

- General arrangement.
- Sectional assembly.
- Rotors and couplings.
- Casings.

1.1.2 For the emergency conditions of 5.3, full particulars of the means proposed for emergency propulsion are to be submitted.

1.1.3 Where rotors and castings are of welded construction, details of the welded joints are also to be submitted for consideration.

1.1.4 In general, plans for auxiliary turbines need not be submitted.

### ■ Section 2 Materials

#### 2.1 General

2.1.1 In the selection of materials, consideration is to be given to their creep strength, corrosion resistance and scaling properties at working temperatures to ensure satisfactory performance and long life under service conditions.

2.1.2 Grey cast iron is not to be used for temperatures exceeding 260°C.

#### 2.2 Materials for forgings

2.2.1 Turbine rotors and discs are to be of forged steel. For carbon and carbon-manganese steel forgings, the specified minimum tensile strength is to be selected within the limits of 400 and 600 N/mm<sup>2</sup> (41 and 61 kgf/mm<sup>2</sup>). For alloy steel rotor forgings, the specified minimum tensile strength is to be selected within the limits of 500 and 800 N/mm<sup>2</sup> (51 and 82 kgf/mm<sup>2</sup>). For discs and other alloy steel forgings, the specified minimum tensile strength is to be selected within the limits of 500 and 1000 N/mm<sup>2</sup> (51 and 102 kgf/mm<sup>2</sup>).

2.2.2 For alloy steels, details of the proposed chemical composition, heat treatment and mechanical properties are to be submitted for approval.

2.2.3 When it is proposed to use material of higher tensile strength, full details are to be submitted for approval.

### ■ Section 3 Design and construction

#### 3.1 General

3.1.1 In the design and arrangement of turbine machinery, adequate provision is to be made for the relative thermal expansion of the various turbine parts, and special attention is to be given to minimizing casing and rotor distortion under all operating conditions.

3.1.2 Turbine bearings are to be so disposed and supported that lubrication is not adversely affected by heat flow from adjacent hot parts of the turbine. Effective means are to be provided for intercepting oil leakage and preventing oil from reaching high temperature glands and casings and steam pipes. Drainage openings and drain pipes from oil baffle pockets are to be sufficiently large to prevent excessive accumulation and leakage of oil.

# Steam Turbines

## Part 5, Chapter 3

Section 3

### 3.2 Welded components

3.2.1 Turbine rotors, cylinders and associated components fabricated by means of welding will be considered for acceptance if constructed by firms whose works are properly equipped to undertake welding to equivalent standards, for rotors and cylinders respectively, to those required by the Rules for Class 1 and Class 2/1 welded pressure vessels, see Ch 17, Sections 1 to 8.

3.2.2 Before work is commenced, manufacturers are to submit for consideration details of proposed welding procedures and their proposals for routine examination of joints by non-destructive means.

3.2.3 Materials used in the construction of turbine rotors, cylinders, diaphragms, condensers, etc., are to be of welding quality.

3.2.4 Where it is proposed to construct rotors from two or more forged components joined by welding, full details of the chemical composition, mechanical properties and heat treatment of the materials, together with particulars of the welding consumables, an outline of the welding procedure, method of fabrication and heat treatment, are to be submitted for consideration.

3.2.5 Joints in rotors and major joints in cylinders are to be designed as full-strength welds and for complete fusion of the joint.

3.2.6 Adequate preheating is to be employed for mild steel cylinders and components and where the metal thickness exceeds 44 mm, and for all low alloy steel cylinders and components and for any part where necessitated by joint restraint.

3.2.7 Stress relief heat treatment is to be applied to all cylinders and associated components on completion of the welding of all joints and attached structures. For details of stress relief procedure, temperature and duration, see Ch 17, 8.2.

3.2.8 The heat treatment of welded rotors is to be carried out as approved.

3.2.9 Surveyors are to be satisfied that the desired quality of welding is attainable with the proposed welding equipment and procedure and, for this purpose, test specimens representative of the welded joints are to be provided for radiographic examination and mechanical tests.

3.2.10 For cylinders, the mechanical tests of butt joints are to include tensile, bend and macro-tests as detailed in Chapter 17, Sections 1 to 8.

3.2.11 For diaphragms, nozzle plates, etc., representative samples are to be sectioned and macro-etched.

3.2.12 For rotors, the mechanical tests are to include tensile (all weld metal), tensile (joint), bend (transverse), bend (longitudinal) and macro-tests as detailed in Chapter 17, Sections 1 to 8, or such other tests as may be approved.

3.2.13 In subsequent production, check tests of the quality of the welding are to be carried out at the discretion of the Surveyors.

### 3.3 Stress raisers

3.3.1 Smooth fillets are to be provided at abrupt changes of section of rotors, spindles, discs, blade roots and tenons. The rivet holes in blade shrouds are to be rounded and radiused on top and bottom surfaces, and tenons are to be radiused at their junction with blade tips. Balancing holes in discs are to be well rounded and polished.

3.3.2 Surveyors are to be satisfied as to the workmanship and riveting of blades to shroud bands, and that the blade tenons are free from cracks, particularly with high tensile blade material. Test samples are to be sectioned and examined, and pull-off tests made if considered necessary by the Surveyors.

### 3.4 Shrunk-on rotor discs

3.4.1 Main turbine rotor discs fitted by shrinking are to be secured with keys, dowels or other approved means.

### 3.5 Vibration

3.5.1 Care is to be taken in the design and manufacture of turbine rotors, rotor discs and blades to ensure freedom from undue vibration within the operating speed range. Consideration of blade vibration should include the effect of centrifugal force, blade root fixing, metal temperature and disc flexibility where appropriate.

3.5.2 For the vibration and alignment of main propulsion systems formed by the turbines geared to the line shafting, see Chapter 8.

### 3.6 External influences

3.6.1 Pipes and ducts connected to turbine casings are to be so designed that no excessive thrust loads or moments are applied by them to the turbines. Gratings and any fittings in way of sliding feet or flexible-plate supports are to be so arranged that casing expansion is not restricted. Where main turbine seatings incorporate a tank structure, consideration is to be given to the temperature variation of the tank in service to ensure that turbine alignment will not be adversely affected.

### 3.7 Steam supply and water system

3.7.1 In the arrangement of the gland sealing system, the pipes are to be made self-draining and every precaution is to be taken against the possibility of condensed steam entering the glands and turbines. The steam supply to the gland sealing system is to be fitted with an effective drain trap. In the air ejector re-circulating water system, the connection to the condenser is to be so located that water cannot impinge on the L.P. rotor or casing.

# Steam Turbines

## Part 5, Chapter 3

Sections 3, 4 & 5

### 3.8 Turning gear

3.8.1 Turning gear is to be provided for all turbines to facilitate operating and maintenance regimes as required by the manufacturer.

3.8.2 The turning gear for all propulsion turbines is to be power-driven and, if electric, is to be continuously rated.

3.8.3 The turning gear for auxiliary turbines may be hand operated (manual) except where this is not practicable, in which case the provision of 3.8.2 is to be complied with.

3.8.4 The turning gear for all turbines is to be fitted with safety interlocks which prevent steam valve actuation for turbine operation when engaged see Ch1,3.9. Indication of engaged / not engaged is to be provided at all start positions.

3.8.5 The remote control device of power-driven turning gear is to be so designed that power is removed from the turning gear when the operating switch is released.

3.8.6 Means are to be provided to secure the turning gear when disengaged.

### 4.3 Low vacuum and overpressure protective devices

4.3.1 In order to provide a warning, due to excessive pressure, to personnel in the vicinity of the exhaust ends of main turbines, sentinel relief valves are to be provided at the exhaust ends or other approved positions. The relief valve discharge outlets are to be visible and suitably guarded if necessary. Where a low vacuum cut-out device is provided, the sentinel relief valve at the L.P. exhaust may be omitted.

4.3.2 In order to provide a warning, due to excessive pressure, to personnel in the vicinity of the exhaust ends of auxiliary turbines, sentinel relief valves are to be provided at the exhaust ends. The relief valve discharge outlets are to be visible and suitably guarded if necessary. Low vacuum or overpressure cut-out devices, as appropriate, are also to be provided for auxiliary turbines not installed with their own condensers.

### 4.4 Bled steam connections

4.4.1 Non-return or other means, which will prevent steam and water returning to the turbines, are to be fitted in bled steam connections.

### 4.5 Steam strainers

4.5.1 Efficient steam strainers are to be provided close to the inlets to ahead and astern high pressure turbines, or alternatively at the inlets to the manoeuvring valves.

## Section 4 Safety arrangements

### 4.1 Overspeed protective devices

4.1.1 An overspeed protective device is to be provided for main and auxiliary turbines to shut-off the steam automatically and prevent the maximum designed speed being exceeded by more than 15 per cent.

4.1.2 Where two or more turbines of a compound main turbine installation are separately coupled to the same main gear wheel, and one overspeed protective device is provided, this is to be fitted to the L.P. ahead turbine. Hand trip gear for shutting off the steam in an emergency is to be provided at the manoeuvring platform.

### 4.2 Speed governors

4.2.1 Where a turbine installation incorporates a reverse gear, electric transmission or reversible propeller, a speed governor in addition to, or in combination with, the overspeed protective device is to be fitted, and is to be capable of controlling the speed of the unloaded turbine without bringing the overspeed protective device into action.

4.2.2 Auxiliary turbines intended for driving electric generators are to be fitted with speed governors which, with fixed setting, are to control the speed within 10 per cent momentary variation and 5 per cent permanent variation when full load is suddenly taken off or put on. The permanent speed variations of alternating current machines intended for parallel operations are to equalize within a tolerance of  $\pm 0,5$  per cent.

## Section 5 Emergency arrangements

### 5.1 Lubricating oil failure

5.1.1 Arrangements are to be made for the steam to the ahead propulsion turbines to be automatically shut-off in the event of failure of the lubricating oil pressure; however, steam is to be made available at the astern turbine for braking purposes in such an emergency, see Chapter 14 for emergency oil supply.

5.1.2 Auxiliary turbine arrangements are to be such that steam supply is automatically shut-off in the event of failure of the lubricating oil pressure.

# Steam Turbines

# Part 5, Chapter 3

Sections 5 & 6

## 5.2 Single screw ships

5.2.1 In single screw ships fitted with cross compound steam turbine installations in which two or more turbines are separately coupled to the same main gear wheel, the arrangements are to be such as to enable safe navigation when the steam supply is led direct to the L.P. turbine and either the H.P. or L.P. turbine can exhaust direct to the condenser. Adequate arrangements and controls are to be provided for these emergency operating conditions so that the pressure and temperature of the steam will not exceed those which the turbines and condenser can safely withstand.

5.2.2 The necessary pipes and valves or fittings for these arrangements are to be readily available and properly marked. A fit up test of all combinations of pipes and valves is to be performed prior to the first sea trials.

5.2.3 The permissible power/speeds of the operating turbines(s) when operating without one of the turbines (all combinations) is to be specified and information provided on board.

5.2.4 The operation of the turbines under emergency conditions is to be assessed for the potential influence on shaft alignment and gear teeth loading conditions.

## 5.3 Single main boiler

5.3.1 Ships intended for unrestricted service, fitted with steam turbines and having a single main boiler, are to be provided with means to ensure emergency propulsion in the event of failure of the main boiler.

## ■ Section 6 Tests and equipment

### 6.1 Stability testing of turbine rotors

6.1.1 All solid forged H.P. turbine rotors intended for main propulsion service where the inlet steam temperature exceeds 400°C are to be subjected to at least one thermal stability test. This requirement is also applicable to rotors constructed from two or more forged components joined by welding. The test may be carried out at the forge or turbine builders' works:

- (a) after heat treatment and rough machining of the forging; or
- (b) after final machining; or
- (c) after final machining and blading of the rotor.

The stabilizing test temperature is to be not less than 28°C above the maximum steam temperature to which the rotor will be exposed, and not more than the tempering temperature of the rotor material. For details of a recommended test procedure and limits of acceptance, see the Rules for Materials. Other test procedures may be adopted if approved.

6.1.2 Where main turbine rotors are subjected to thermal stability tests at both forge and turbine builders' works, the foregoing requirements are applicable to both tests. It is not required that auxiliary turbine rotors be tested for thermal stability, but, if such tests are carried out, the requirement for main turbine rotors will be generally applicable.

### 6.2 Balancing

6.2.1 All rotors as finished-bladed and complete with half-coupling are to be dynamically balanced to the Surveyor's satisfaction, in a machine of sensitivity appropriate to the size of rotor.

### 6.3 Hydraulic tests

6.3.1 Manoeuvring valves are to be tested to twice the working pressure. The nozzle boxes of impulse turbines are to be tested to 1,5 times the working pressure.

6.3.2 The cylinders of all turbines are to be tested to 1,5 times the working pressure in the casing, or to 2,0 bar (2,0 kgf/cm<sup>2</sup>), whichever is the greater.

6.3.3 For test purposes, the cylinders may be subdivided with temporary diaphragms for distribution of test pressures.

6.3.4 Condensers are to be tested in the steam space to 1,0 bar (1,0 kgf/cm<sup>2</sup>). The water space is to be tested to the maximum pressure which the pump can develop at ship's full draught with the discharge valve closed plus 0,7 bar (0,7 kgf/cm<sup>2</sup>), with a minimum test pressure of 2,0 bar (2,0 kgf/cm<sup>2</sup>). Where the operating conditions are not known, the test pressure is to be not less than 3,4 bar (3,5 kgf/cm<sup>2</sup>), see Chapter 14.

### 6.4 Indicators for movement

6.4.1 Indicators for determining the axial position of rotors relative to their casings, and for showing the longitudinal expansion of casings at the sliding feet, if fitted, are to be provided for main turbines. The latter indicators should be fitted at both sides and be readily visible.

### 6.5 Wear-down gauges

6.5.1 Main and auxiliary turbines are to be provided with bridge wear-down gauges for testing the alignment of the rotors.

### ■ *Cross-references*

The pumping arrangements, including cooling water and lubricating oil systems, are to comply with the requirements of Chapters 13 and 14.

For lists of spare gear to be carried, see Chapter 16.

---





# Gas Turbines

# Part 5, Chapter 4

Sections 1 & 2

## Section

- 1 **General requirements**
- 2 **Particulars to be submitted**
- 3 **Materials**
- 4 **Design and construction**
- 5 **Piping systems**
- 6 **Starting arrangements**
- 7 **Tests**
- 8 **Control, alarm and safety systems**
- 9 **Planned maintenance and condition monitoring procedures, and 'upkeep by exchange'**



## Scope

The requirements of this Chapter are applicable to gas turbines for main propulsion and also, where powers exceed 110 kW (150 shp), to those for essential auxiliary services. The requirements do not apply to exhaust gas turbo-blowers.

Approval will be in respect of the mechanical integrity of the gas turbine (including gas generator and power turbine), intake and exhaust ducting configuration, acoustic enclosure configuration (where appropriate), fuel, lubricating oil and starter systems, control alarm and monitoring systems and other critical support systems.

Type approval of the gas turbine bare engine will be required as part of the approval process for first of type.



## Section 1

### General requirements

#### 1.1 Application

1.1.1 This Chapter is to be read in conjunction with Chapter 1 *General Requirements for the Design and Construction of Machinery*, Pt 6, Ch 1 *Control Engineering Systems*, and Pt 6, Ch 2 *Electrical Engineering*.

#### 1.2 Standard reference conditions

1.2.1 Where power, efficiency, heat rate or specific consumption refer to standard conditions (ISO 2314), such conditions are to be:

- (a) for the intake air at the compressor flange (compressor intake flare):
  - a total pressure of 101,3 kPa;
  - an ambient temperature of 15°C;
  - a relative humidity of 60 per cent; and

- (b) for the exhaust at the turbine exhaust flange (or recuperator outlet):
  - a static pressure of 101,3 kPa.

#### 1.3 Power ratings

1.3.1 Where the dimensions of any particular component are determined from shaft power,  $P$ , in kW, and revolutions per minute,  $R$ , the values are those defined in Chapter 1.

#### 1.4 Gas turbine type approval

1.4.1 New gas turbine types or developments of existing types are to be type approved in accordance with Lloyd's Register's (hereinafter referred to as 'LR') *Type Approval System Procedure – Test Specification GT98*.

1.4.2 Where a gas turbine type has subsequently proved satisfactory in service with a number of applications, a maximum power uprating of 10 per cent may be considered without a further complete design re-assessment and type test.

#### 1.5 Inclination of vessel

1.5.1 Gas turbines are to operate satisfactorily under the conditions of inclinations as shown in Table 1.3.2 of Chapter 1.



## Section 2

### Particulars to be submitted

#### 2.1 Plans and information

2.1.1 The following plans are to be submitted for consideration:

- Casings.
- Combustion chambers, intercoolers and heat exchangers.
- Compressor and gas generator rotating components.
- Control engineering systems, see Pt 6, Ch 1.
- Cooling and sealing air arrangements for compressor and gas generator components: Schematic only.
- Cooling water system: Schematic only, where applicable.
- Fuel systems: Schematic only.
- Gas turbine unit acoustic enclosure, if applicable, including ventilation and drainage systems: Schematic only.
- Inlet and exhaust ducting arrangement.
- Lubricating oil systems: Schematic only.
- Nozzles, blades and blade attachments.
- Oil fuel systems: Schematic only.
- Power turbine components.
- Rotors, bearings and couplings.
- Sectional assembly.
- Securing arrangement, including details of resilient mounts, where applicable.
- Starting system: Schematic only.

# Gas Turbines

# Part 5, Chapter 4

Sections 2, 3 & 4

2.1.2 The following information and calculations, where applicable, are to be submitted:

- (a) Operational requirements:
  - Proposed field of application and operational limitations.
  - Power/speed operational envelope.
  - Calculations and information for short-term high power operation.
  - Operation and maintenance manuals including the declared lives of critical components and overhaul schedules recommended by the manufacturer.
- (b) Calculations of the critical speeds of blade and rotor vibration, giving full details of the basic assumptions, see *also* 4.3.1.
- (c) Analysis of the effect of rotor blade release together with details of operating experience, see *also* 4.3.2.
- (d) High temperature characteristics of the materials, including (at working temperatures) the associated creep rate and rupture strength for the designed service life, fatigue strength, corrosion resistance and scaling properties.
- (e) Material requirements:
  - Particulars of heat treatment, including stress relief.
  - Material specifications covering the listed components together with details of any surface treatments, non-destructive testing and hydraulic tests.
- (f) The most onerous pressures and temperatures to which each component may be subjected are to be indicated on plans or provided as part of the design specification.
- (g) Calculations of the steady state stresses, including the effect of stress raisers, etc., in the compressor and turbine rotors and blading at the maximum speed and temperature in service. Such calculations are to indicate the designed service life and be accompanied, where possible, by test results substantiating the limiting criteria.
- (h) Details of calculations and tests to establish the service life of other stressed or safety critical components, including bearings, seals, couplings and gearing. Calculations and tests are to take account of all relevant environmental factors including the particular type of service and fuel intended to be used.
- (i) Mounting requirements:
  - Securing arrangements, including details of resilient mounts.
  - Calculations concerning the amplitude and frequency of vibration associated with resilient type mountings.
- (k) A Failure Mode and Effects Analysis (FMEA).
- (l) Miscellaneous:
  - Design standard of intake filtration for water particulate and corrosive marine salts.
  - Details of compressor washing system.
  - Fuel specification.

2.1.3 Components fabricated by means of welding will be considered for acceptance if constructed by firms whose works are properly equipped to undertake welding of the standards appropriate to the components. Details are to be submitted for consideration.

2.1.4 Before work is commenced, manufacturers are to submit for consideration details of proposed welding procedures and their proposals for routine examination of joints by non-destructive means.

2.1.5 The manufacturer's proposals for testing the gas turbine are to be submitted for consideration and are to include rotor balancing techniques, methods of determining the soundness of pressure casings and heat exchanger tests, see Section 1.

## Section 3 Materials

### 3.1 Materials for forgings

3.1.1 Details of materials for rotors and discs are to be submitted for approval.

### 3.2 Material tests and inspection

3.2.1 Components are to be tested in accordance with the relevant requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials (Part 2)).

3.2.2 For components of novel design, special consideration will be given to the material test and non-destructive testing requirements.

## Section 4 Design and construction

### 4.1 General

4.1.1 All parts of compressors, turbines, etc., are to have clearances and fits consistent with adequate provision for the relative thermal expansion of the various components. Provision is to be made to limit the distortion of the casing and rotor under all normal operating conditions.

4.1.2 Gas generator and power turbine bearings are to be so disposed and supported that lubrication is not adversely affected by heat flow from adjacent hot parts. Effective means are to be provided for intercepting oil leakage and preventing oil from reaching high temperature glands and casings.

# Gas Turbines

## Part 5, Chapter 4

Section 4

### 4.2 Vibration

4.2.1 The design and manufacture of compressor and turbine rotors, rotor discs and rotor blades are to ensure freedom from undue vibration within the full operating speed range. Where critical speeds are found by calculation to occur within the operating speed range, vibration tests may be required in order to verify the calculations, *see also* Chapter 8.

4.2.2 Vibration monitoring is to form an integral part of the gas turbine safety and control system. The vibration monitoring system is to be capable of detecting the out-of-balance of major parts with means being provided to shutdown the gas turbine, before an over-critical situation occurs, i.e. multiple rotor blade or disc release.

### 4.3 Containment

4.3.1 Gas turbines and power turbines are to be designed and installed, so far as is practicable, to contain debris in the event of rotor blade release.

4.3.2 In the event of a major component failure, when the turbine casing may not contain the debris; oil fuel, lubricating oil and other potentially hazardous systems or equipment are, where practicable, to be located outside of the plane of high speed rotating parts. This requirement also applies to fire detection and extinction equipment, *see also* Section 5.

4.3.3 Gas turbine ancillaries containing flammable products are to be segregated or protected from high temperature areas.

### 4.4 Intake and exhaust ducts

4.4.1 Air intakes are to be designed and located to minimize the possibility of ingestion of harmful objects. Means are also to be provided for detecting and preventing icing up of air intakes.

4.4.2 Suitable intake filtration is to be provided to control the ingestion of water, particulate and corrosive marine salts within the gas turbine manufacturer's specified limits.

4.4.3 Where an air intake enclosure forms the connection between the ship's downtake and the gas turbine installation, a suitable alarm function is to be provided to give warning when an unacceptable air intake pressure loss is reached at the air inlet (bellmouth) of the gas turbine.

4.4.4 Intakes are to be designed such that material cannot become detached due to air flow or corrosion. Fixing bolts and fastenings are to be positively locked so that they cannot work loose.

4.4.5 Multi-engine installations are to have separate intakes and exhausts so arranged as to prevent induced circulation through a stopped gas turbine unit.

4.4.6 The arrangement of the exhaust duct is to be such as to prevent, under normal conditions of ship motion and atmospheric conditions, exhaust gases being drawn into machinery spaces, air conditioning systems and intakes.

4.4.7 Where the exhaust is led overboard near the waterline, means are to be provided to prevent water from being siphoned back into the gas turbine. Where the exhaust is cooled by water spray, the exhaust pipes are to be self-draining overboard. Erosion/corrosion-resistant shut-off flaps or other devices are to be fitted on the hull side shell or pipe end with suitable arrangements made to prevent water flooding the machinery space.

### 4.5 External influences

4.5.1 Pipes and ducting connected to casings are to be so designed that they apply no excessive loads or moments to the compressors and turbines.

4.5.2 Platform gratings and fittings in way of the supports are to be so arranged that casing expansion is not restricted.

4.5.3 Where the gas turbine seating incorporates a tank structure, any temperature variation of the tank in service is not to adversely affect the gas generator and power turbine alignment.

4.5.4 For machinery fastening arrangements, including resilient mounting, *see* Chapter 1.

### 4.6 Corrosive deposits

4.6.1 Means are to be provided for periodic removal of salt deposits and atmospheric contaminants from blading and internal surfaces.

### 4.7 Acoustic enclosures

4.7.1 Acoustic enclosures, where fitted, are to be provided with an access door, adequate internal lighting and one or more observation windows to allow the viewing of critical parts of the gas turbine.

4.7.2 A suitable ventilation system, designed to maintain all components within their safe working temperature under all operating conditions is to be provided.

4.7.3 The ventilation system is to be fitted with shut-off flaps arranged to close automatically upon activation of the enclosure's fire detection and extinguishing system.

4.7.4 Acoustic enclosure fire safety arrangements are to comply with the requirements of Pt 6, Ch 1 and the *International Convention for the Safety of Life at Sea, 1974*, as amended (SOLAS 74), *see also* 8.7.1.

# Gas Turbines

# Part 5, Chapter 4

Sections 4 & 5

## 4.8 Thermal insulation

4.8.1 Where surfaces of the gas generator, power turbine and exhaust volute exceed a temperature of 220°C during operation, these are to be suitably insulated and clad to minimize the risk of fire and prevent damage by heat to adjacent components, see 5.1.5.

## 4.9 Welded construction

4.9.1 Full strength welds are to be used for all major joints and be designed so as to ensure complete fusion of the joint.

4.9.2 Stress relief heat treatment is to be applied to all cylinders, rotors and associated components on completion of all welding, see Chapter 17.

## 4.10 Turning gear

4.10.1 Gas generator turning gear is to be provided to facilitate operating and maintenance regimes as required by the manufacturer.

4.10.2 The turning gear may be hand operated (manual) except where this is not practicable. If electrically driven, the motor is to be continuously rated.

4.10.3 The turning gear is to be fitted with safety interlocks which prevent engine operation when engaged, see Ch 1,3.9. Indication of engaged / not engaged is to be provided at all start positions.

4.10.4 The remote control device of power-driven turning gear is to be so designed that power is removed from the turning gear when the operating switch is released.

4.10.5 If permanently attached, means are to be provided to secure the turning gear when disengaged.

## Section 5 Piping systems

### 5.1 General

5.1.1 Gas turbine piping systems are, in general, to comply with the requirements given in Chapter 12 and Chapter 14, due regard being paid to the particular type of installation. For the burning of compressed natural gas, see the *Rules for Ships for Liquefied Gases*.

5.1.2 The materials and/or their surface treatment used for the storage and distribution of oil fuel are to be selected such that they do not introduce contamination or modify the properties of the fuel.

5.1.3 Corrosion resistant materials are to be used in all fuel pipes between the treatment and combustion systems.

5.1.4 Suitable fuel treatment systems, including filtration and centrifuging, are to be provided to control the level of water and particulate contamination within the engine manufacturer's specified limits.

5.1.5 The gas turbine design and construction are to minimize the possibility of a fire fed by fuel or lubricating oil leaks.

5.1.6 In dual-fuel applications, provision is to be made for automatic isolation of both primary and standby fuel supplies to the engine in the event of a fire.

### 5.2 Oil fuel systems

5.2.1 Oil fuel arrangements are to comply with the requirements of Chapter 14.

5.2.2 All external high pressure oil fuel delivery lines between the pressure fuel pumps and fuel metering valves are to be protected with a jacketed piping system capable of containing fuel from a high pressure line failure to prevent oil fuel or oil fuel mist from reaching a source of ignition on the engine or its surroundings.

5.2.3 Suitable arrangements are to be made for draining any oil fuel leakage from the protection required by 5.2.2 and to prevent contamination of the lubricating oil by oil fuel. An alarm is to be provided to indicate that leakage is taking place.

5.2.4 At least two filters are to be fitted in the oil fuel supply lines to the gas turbine and be so arranged that any filter may be cleaned without interrupting the supply of filtered oil fuel to the gas turbine.

### 5.3 Lubricating oil systems

5.3.1 Lubricating oil arrangements are to comply with the requirements of Chapter 14.

5.3.2 Where the lubricating oil for gas turbines is circulated under pressure, provision is to be made for the efficient filtration of the oil. At least two filters are to be fitted in the lubricating oil supply lines to the gas turbine and be so arranged that any filter may be cleaned without interrupting the supply of filtered lubricating oil to the gas turbine.

### 5.4 Cooling systems

5.4.1 Cooling water arrangements are to comply with the requirements of Chapter 14, where appropriate.

## ■ Section 6 Starting arrangements

### 6.1 General

6.1.1 Equipment for initial starting of gas turbines is to be provided and arranged such that the necessary initial charge of starting air, hydraulic or electrical power can be developed on board the ship without external aid. If, for this purpose, an emergency air compressor or electric generator is required, these units are to be power-driven by manually-started oil engines, except in the case of small installations where a hand-operated compressor of approved capacity may be accepted.

6.1.2 Alternatively, other devices of approved type may be accepted as a means of providing the initial start.

6.1.3 Where the integrity of the starting system is susceptible to overspeed conditions, appropriate alarm and/or trip functions are to be provided, see *also* Pt 6, Ch 1.

### 6.2 Purging before ignition

6.2.1 Means are to be provided to clear all parts of the gas turbine of the accumulation of oil fuel or for purging gaseous fuel before ignition commences on starting, or recommences after failure to start. The purge is to be of sufficient duration to displace at least three times the volume of the exhaust system.

### 6.3 Air starting

6.3.1 Where the gas turbine is arranged for air starting, the total air receiver capacity is to be sufficient to provide, without replenishment, not less than six consecutive starts. At least two air receivers of approximately equal capacity are to be provided to satisfy the plant air start requirements. For scantlings and fittings of air receivers, see Chapter 11.

6.3.2 For multi-engine installations, three consecutive starts per engine are required.

### 6.4 Electric starting

6.4.1 Where the gas turbine is fitted with electric starters powered from batteries, two batteries are to be fitted. Each battery is to be capable of starting the gas turbine and the combined capacity is to be sufficient without recharging to provide the number of starts required by 6.3.1 or 6.3.2.

6.4.2 The requirements for battery installations are given in Pt 6, Ch 2.

### 6.5 Hydraulic starting

6.5.1 Where the gas turbine is arranged for hydraulic starting, the capacity of the power pack is to be sufficient to provide the number of starts of the gas turbine as required by 6.3.1 or 6.3.2.

## ■ Section 7 Tests

### 7.1 Dynamic balancing

7.1.1 All compressor and turbine rotors as finished-bladed and complete with all relevant parts such as half-couplings, are to be dynamically balanced in accordance with the manufacturer's specification in a machine of sensitivity appropriate to the size of rotor.

### 7.2 Hydraulic testing

7.2.1 Where design permits, casings are to be tested to a hydraulic pressure equal to 1,5 times the highest pressure in the casing during normal operation, or 1,5 times the pressure during starting, whichever is the higher. For test purposes, if necessary, the casings may be subdivided with temporary diaphragms for distribution of test pressure. Where the operating temperature exceeds 300°C the test pressure is to be suitably corrected.

7.2.2 Where hydraulic testing is impracticable, 100 per cent non-destructive tests by ultrasonic or radiographic methods are to be carried out on all casing parts with satisfactory results. Where ultrasonic tests have been carried out, the manufacturer is to provide documentary evidence that ultrasonic examination has been carried out by an approved operator and that there were no indications of defects which could be expected to have a prejudicial effect on the operational performance of the gas turbine.

7.2.3 The shell and tube arrangement of intercoolers and heat exchangers are to be tested to 1,5 times their maximum working pressure.

### 7.3 Overspeed tests

7.3.1 Before installation, it is to be satisfactorily demonstrated that the gas turbine is capable of safe operation for five minutes at 5 per cent above the nominal setting of the overspeed protective device, or 15 per cent above the maximum design speed, whichever is the higher.

7.3.2 Where it is impracticable to overspeed the complete installation, each compressor and turbine rotor completely bladed and with all relevant parts such as half-couplings, are to be overspeed-tested individually at the appropriate speed.

## ■ Section 8 Control, alarm and safety systems

### 8.1 General

8.1.1 Control alarm and safety systems are to comply with the requirements of Pt 6, Ch 1.

### 8.2 Overspeed protection and shutdown system

8.2.1 The gas turbine is to be protected against overspeed by the provision of a suitable device(s) capable of shutting-down the gas turbine safely before a dangerous overspeed condition occurs.

### 8.3 Power turbine inlet over-temperature control

8.3.1 The power turbine is to be protected against over-temperature by the provision of a suitable device(s) capable of controlling the temperature within acceptable limits or shutting-down the gas turbine safely to prevent damage.

### 8.4 Flameout

8.4.1 Indication is to be provided for identifying poor combustion from each combustion chamber, flame-out and failure to ignite conditions, see *also* 6.2.1.

### 8.5 Lubricating oil system

8.5.1 Means are to be provided to accurately determine the pressure and temperature of the lubricating oil supply to the various parts of the gas generator and power turbine, and scavenge oil and return systems to ensure safe operation.

8.5.2 Means are to be provided to ensure that the temperature of the lubrication oil supply is automatically controlled to maintain steady-state conditions throughout the normal operating range of the gas turbine.

8.5.3 Where the oil supply to the power turbine is fed from a separate supply system, similar arrangements to those detailed above are to be provided.

### 8.6 Hand trip arrangement

8.6.1 Means are to be provided, at both the local and remote control/operating positions, to manually initiate the shut-down of the gas turbine in an emergency.

### 8.7 Fire detection, alarm and extinguishing systems

8.7.1 The gas turbine installation is to be provided with a fire detection, alarm and extinguishing system. The requirements of Pt 6, Ch 1 and the *International Convention for the Safety of Life at Sea, 1974* as amended (SOLAS 74) are to be complied with.

## ■ Section 9 Planned maintenance and condition monitoring procedures, and 'upkeep by exchange'

### 9.1 Planned maintenance approach

9.1.1 Suitable gas turbine installation Planned Maintenance and Condition Monitoring Schemes (MPMS, MCM) will be accepted as part of LR's Continuous Survey Machinery (CSM) cycle provided the principles defined in 9.2 to 9.4 are satisfied (see *also* Pt 5, Ch 21).

### 9.2 Preventive maintenance

9.2.1 Preventive maintenance requires items to be opened out for inspection and overhaul at specified time periods or after a specified number of running hours.

9.2.2 Maintenance is normally carried out irrespective of the condition of the gas turbine in order to retain it in a satisfactory operational condition.

### 9.3 Unscheduled maintenance

9.3.1 The planned maintenance scheme is to be capable of dealing effectively with breakdown or corrective maintenance, i.e. unscheduled maintenance.

### 9.4 Condition monitoring

9.4.1 Condition monitoring requires the use of instrumentation to make regular or continuous measurements of certain parameters, in order to indicate the physical state of the gas turbine, without disturbing its normal operation.

9.4.2 The data collected is to be used to determine the actual condition of the gas turbine at any given time or, based on the trend characteristics of the condition, used for predicting the remaining useful life before complete deterioration or loss of performance terminates its ability to carry out its required function.

### 9.5 Condition monitoring techniques

9.5.1 The condition monitoring techniques, to support the trend away from preventive maintenance, listed in Table 4.9.1 are considered the minimum acceptable to obviate the need for a fully opened out inspection of engine components at Periodical Survey.

9.5.2 Alternative arrangements to those in Table 4.9.1, which provide an equivalent level of confidence in the condition of the gas turbine installation, will be considered.

**Table 4.9.1 Condition monitoring techniques**

Method	Requirement
Visual inspection	Periodic inspection of intakes and exhaust ducts, inlet guide vanes, compressor 1st stage, compressor and gas generator casings and auxiliary components and systems. The running clearances and dimensional changes, where practicable
Visual inspection by borescope/endoscope	Periodic inspection of compressor stators, guide vanes and blades, combustion chambers, turbine nozzles and blades and power turbine
Vibration monitoring	Continuous monitoring and trend analysis of gas generator and power turbine rotor vibration. The equipment used for vibration measurement should be capable of determining vibration throughout the operating range of the gas turbine
Lubrication, oil trend analysis programme	<ul style="list-style-type: none"> <li>• Periodic inspection of magnetic particle detectors (manual records and/or automatic recording via debris counters in oil scavenge lines)</li> <li>• Periodic inspection of oil filters</li> <li>• Periodic sampling and laboratory analysis of lubricant quality</li> </ul>
Fuel quality	<ul style="list-style-type: none"> <li>• Maintenance of fuel bunker/marine gas oil analysis records</li> <li>• Periodic sampling and laboratory analysis of fuel quality</li> </ul>
Performance monitoring	Continuous monitoring and trend analysis of critical gas turbine operating parameters including: <ul style="list-style-type: none"> <li>• Compressor conditions (inlet and exit temperature, delivery pressure and speed)</li> <li>• Power turbine (inlet entry temperature and speed)</li> <li>• Engine breather temperature</li> <li>• Low cycle fatigue counter</li> </ul> See Note.
NOTE Manual recording and trend analysis methods may also be acceptable.	

**9.6 Upkeep by exchange**

9.6.1 Where the gas turbine is maintained using an 'upkeep by exchange' policy, details of the system are to be submitted to LR for approval.

9.6.2 Where an 'upkeep by exchange' system has been approved, details of units that can be changed independently of each other are not required to be submitted provided there have been no changes since the original approval. The manufacture and testing of the replacement units are to be in accordance with relevant Rule requirements.

9.6.3 Records of each 'upkeep by exchange' are to be kept on board the ship and LR Surveyors are to witness running tests on load after each exchange. A record history is to be maintained for each exchange unit in the engine logbook.





## Section

- 1 **Plans and particulars**
- 2 **Materials**
- 3 **Design**
- 4 **Construction**
- 5 **Tests**

## ■ Scope

The requirements of this Chapter, except where otherwise stated are applicable to oil engine gearing for main propulsion purposes and for oil engine gearing for driving auxiliary machinery which is essential for the safety of the ship or for safety of persons on board where the transmitted powers exceed 220 kW (300 shp) for propulsion drives, and 110 kW (150 shp) for auxiliary drives. In any mesh, the terms pinion and wheel refer to the smaller and larger gear respectively. For turbine gearing the loading factors  $K_A$ ,  $K_{F\alpha}$ ,  $K_{F\beta}$ ,  $K_{H\alpha}$ ,  $K_{H\beta}$  and  $K_\gamma$  will be specially considered. Bevel gears will be specially considered on the basis of a conversion to equivalent helical gears. For torsional vibration requirements, see Ch 8,2.3.

## ■ Section 1 Plans and particulars

### 1.1 Gearing plans

1.1.1 Particulars of the gearing are to be submitted with the plans for all propulsion gears and for auxiliary gears where the transmitted power exceeds 110 kW (150 shp), as follows:

- Shaft power and revolution for each pinion.
- Number of teeth in each gear.
- Reference diameters.
- Helix angles at reference diameters.
- Normal pitches of teeth at reference diameters.
- Tip diameters.
- Root diameters.
- Face widths and gaps, where applicable.
- Pressure angles of teeth (normal or transverse) at reference diameters.
- Accuracy grade Q in accordance with ISO 1328 or an equivalent standard.
- Surface texture of tooth flanks and roots.
- Minimum backlash.
- Centre distance.
- Basic rack tooth form.
- Protuberance and final machining allowance.
- Details of post hobbing processes, if any.
- Details of tooth flank corrections, if adopted.
- Case depth for surface-hardened teeth.
- Shrinkage allowance for shrunk-on rims and hubs.
- Type of coupling proposed for oil engine applications.

### 1.2 Material specifications

1.2.1 Specifications for materials of pinions, pinion sleeves, wheel rims, gear wheels, and quill shafts, giving chemical composition, heat treatment and mechanical properties, are to be submitted for approval with the plans of gearing.

1.2.2 Where the teeth of a pinion or gear wheel are to be surface hardened, i.e. carburized, nitrided, tufftrided or induction-hardened, the proposed specification and details of the procedure are to be submitted for approval.

## ■ Section 2 Materials

### 2.1 Material properties

2.1.1 In the selection of materials for pinions and wheels, consideration is to be given to their compatibility in operation. Except in the case of low reduction ratios, for gears of through-hardened steels, provision is also to be made for a hardness differential between pinion teeth and wheel teeth. For this purpose, the specified minimum tensile strength of the wheel rim material is not to be more than 85 per cent of that of the pinion.

2.1.2 Subject to 2.1.1, the specified minimum tensile strength is to be selected within the following limits:

Pinion and pinion sleeves	550 to 1050 N/mm <sup>2</sup> (56 to 107 kgf/mm <sup>2</sup> )
Gear wheels and rims	400 to 850 N/mm <sup>2</sup> (41 to 87 kgf/mm <sup>2</sup> )

A tensile strength range is also to be specified and is not to exceed 120 N/mm<sup>2</sup> (12 kgf/mm<sup>2</sup>) when the specified minimum tensile strength is 600 N/mm<sup>2</sup> (61 kgf/mm<sup>2</sup>) or less. For higher strength steels, the range is not to exceed 150 N/mm<sup>2</sup> (15 kgf/mm<sup>2</sup>).

2.1.3 Unless otherwise agreed, the full specified minimum tensile strength of the core is to be 800 N/mm<sup>2</sup> (82 kgf/mm<sup>2</sup>) for induction-hardened or nitrided gearing and 750 N/mm<sup>2</sup> (76 kgf/mm<sup>2</sup>) for carburized gearing.

2.1.4 For nitrided gearing, the full depth of the hardened zone is to be not less than 0,5 mm and the hardness is to be not less than 500 HV for a depth of 0,25 mm.

### 2.2 Non-destructive tests

2.2.1 An ultrasonic examination is to be carried out on all gear blanks where the finished diameter of the surfaces, where teeth will be cut, is in excess of 200 mm.

2.2.2 Magnetic particle or liquid penetrant examination is to be carried out on all surface-hardened teeth. This examination may also be requested on the finished machined teeth of through-hardened gears.

## Section 3 Design

### 3.1 Symbols

3.1.1 For the purposes of this Chapter the following symbols apply:

- $a$  = centre distance, in mm
- $b$  = face width, in mm
- $d$  = reference diameter, in mm
- $d_a$  = tip diameter, in mm
- $d_{an}$  = virtual tip diameter, in mm
- $d_b$  = base diameter, in mm
- $d_{bn}$  = virtual base diameter, in mm
- $d_{en}$  = virtual diameter to the highest point of single tooth pair contact, in mm
- $d_f$  = root diameter, in mm
- $d_{fn}$  = virtual root diameter, in mm
- $d_n$  = virtual reference diameter, in mm
- $d_s$  = shrink diameter, in mm
- $d_w$  = pitch circle diameter, in mm
- $f_{ma}$  = tooth flank misalignment due to manufacturing errors, in  $\mu\text{m}$
- $f_{pb}$  = maximum base pitch deviation of wheel, in  $\mu\text{m}$
- $f_{Sh}$  = tooth flank misalignment due to wheel and pinion deflections, in  $\mu\text{m}$
- $f_{Sho}$  = intermediary factor for the determination of  $f_{Sh}$
- $g_\alpha$  = length of line of action for external gears, in mm:  

$$= 0,5 \sqrt{(d_{a1}^2 - d_{b1}^2)} + 0,5 \sqrt{(d_{a2}^2 - d_{b2}^2)} - a \sin \alpha_{tw}$$
 for internal gears:  

$$= 0,5 \sqrt{(d_{a1}^2 - d_{b1}^2)} - 0,5 \sqrt{(d_{a2}^2 - d_{b2}^2)} + a \sin \alpha_{tw}$$
- $h$  = total depth of tooth, in mm
- $h_{ao}$  = basic rack addendum of tool, in mm
- $h_F$  = bending moment arm for root stress, in mm
- $m_n$  = normal module, in mm
- $n$  = rev/min of pinion
- $q$  = machining allowances, in mm
- $q_s$  = notch parameter
- $q'$  = intermediary factor for the determination of  $C_\gamma$
- $u$  = gear ratio =  $\frac{\text{Number of teeth in wheel}}{\text{Number of teeth in pinion}} \geq 1$
- $v$  = linear speed at pitch circle, in m/s
- $x$  = addendum modification coefficient
- $y_\alpha$  = running in allowance, in  $\mu\text{m}$
- $y_\beta$  = running in allowance, in  $\mu\text{m}$
- $z$  = number of teeth
- $z_n$  = virtual number of teeth  

$$= \frac{z}{\cos^2 \beta_b \cos \beta}$$
- $C_\gamma$  = tooth mesh stiffness (mean total mesh stiffness per unit face width), in N/mm  $\mu\text{m}$
- $F_t$  = nominal tangential tooth load, in N  

$$= \frac{P}{nd} \cdot 19,098 \times 10^6$$
- $F_\beta$  = total tooth alignment deviation (maximum value specified), in  $\mu\text{m}$
- $F_{\beta x}$  = actual longitudinal tooth flank deviation before running in, in  $\mu\text{m}$
- $F_{\beta y}$  = actual longitudinal tooth flank deviation after running in, in  $\mu\text{m}$

- HV = Vickers hardness number
- $K_A$  = application factor
- $K_{F\alpha}$  = transverse load distribution factor
- $K_{F\beta}$  = longitudinal load distribution factor
- $K_{H\alpha}$  = transverse load distribution factor
- $K_{H\beta}$  = longitudinal load distribution factor
- $K_v$  = dynamic factor
- $K_{v\alpha}$  = dynamic factor for spur gears
- $K_{v\beta}$  = dynamic factor for helical gears
- $K_\gamma$  = load sharing factor
- $P$  = transmitted power, in kW
- $P_r$  = radial pressure at shrinkage surface, in N/mm<sup>2</sup>
- $P_{ro}$  = protuberance of tool, in mm
- $Q$  = accuracy grade from ISO 1328 – 1975
- $R_a$  = surface roughness – arithmetical mean deviation (C.L.A.) as determined by an instrument having a minimum wavelength cut-off of 0,8 mm and for a sampling length of 2,5 mm, in  $\mu\text{m}$
- $S_{pr}$  = residual undercut left by protuberance in mm
- $S_{Fmin}$  = minimum factor of safety for bending stress
- $S_{Fn}$  = tooth root chord in the critical section, in mm
- $S_{Hmin}$  = minimum factor of safety for Hertzian contact stress
- $Y_D$  = design factor
- $Y_F$  = tooth form factor
- $Y_{R \text{ rel } T}$  = relative surface finish factor
- $Y_S$  = stress concentration factor
- $Y_{ST}$  = stress correction factor
- $Y_x$  = size factor
- $Y_\beta$  = helix angle factor
- $Y_{\delta \text{ rel } T}$  = relative notch sensitivity factor
- $Z_E$  = material elasticity factor
- $Z_H$  = zone factor
- $Z_R$  = surface finish factor
- $Z_V$  = velocity factor
- $Z_X$  = size factor
- $Z_\beta$  = helix angle factor
- $Z_\epsilon$  = contact ratio factor
- $\alpha_{en}$  = pressure angle at the highest point of single tooth contact, in degrees
- $\alpha_n$  = normal pressure angle at reference diameter, in degrees
- $\alpha_t$  = transverse pressure angle at reference diameter, in degrees
- $\alpha_{tw}$  = transverse pressure angle at pitch circle diameter, in degrees
- $\alpha_{Fen}$  = angle for application of load at the highest point of single tooth contact, in degrees
- $\beta$  = helix angle at reference diameter, in degrees
- $\beta_b$  = helix angle at base diameter, in degrees
- $\gamma$  = intermediary factor for the determination of  $f_{Sh}$
- $\epsilon_\alpha$  = transverse contact ratio  

$$= \frac{g_\alpha \cos \beta}{\pi m_n \cos \alpha_t}$$
- $\epsilon_{\alpha n}$  = virtual transverse contact ratio
- $\epsilon_\beta$  = overlap ratio  

$$= \frac{b \sin \beta}{\pi m_n}$$
- $\epsilon_\gamma$  = total contact ratio
- $\rho_{ao}$  = tip radius of tool, in mm
- $\rho_c$  = relative radius of curvature at pitch point, in mm  

$$= \frac{a \sin \alpha_{tw} u}{\cos \beta_b (1 + u)^2}$$

# Gearing

# Part 5, Chapter 5

Section 3

- $\rho_F$  = tooth root fillet radius at the contact of the 30° tangent, in mm  
 $\sigma_y$  = yield or 0,2 per cent proof stress, in N/mm<sup>2</sup>  
 $\sigma_B$  = ultimate tensile strength, in N/mm<sup>2</sup>  
 $\sigma_F$  = bending stress at tooth root, in N/mm<sup>2</sup>  
 $\sigma_{F\lim}$  = endurance limit for bending stress in N/mm<sup>2</sup>  
 $\sigma_{FP}$  = allowable bending stress at the tooth root, in N/mm<sup>2</sup>  
 $\sigma_H$  = Hertzian contact stress at the pitch circle, in N/mm<sup>2</sup>  
 $\sigma_{H\lim}$  = endurance limit for Hertzian contact stress, in N/mm<sup>2</sup>  
 $\sigma_{HP}$  = allowable Hertzian contact stress, in N/mm<sup>2</sup>  
 Subscript:

- 1 = pinion  
 2 = wheel  
 0 = tool.

## 3.2 Tooth form

3.2.1 The tooth profile in the transverse section is to be of involute shape, and the roots of the teeth are to be formed with smooth fillets of radii not less than  $0,25m_n$ .

3.2.2 All sharp edges left on the tips and ends of pinion and wheel teeth after hobbing and finishing are to be removed.

## 3.3 Tooth loading factors

3.3.1 For values of application factor,  $K_A$  see Table 5.3.1.

**Table 5.3.1 Values of  $K_A$**

Main and auxiliary gears	$K_A$
Main propulsion oil engine reduction gears:	
Hydraulic coupling or equivalent on input	1,10
High elastic coupling on input	1,30
Other coupling	1,50
Auxiliary gears:	
Electric and diesel engine drives with hydraulic coupling or equivalent on input	1,00
Diesel engine drives with high elastic coupling on input	1,20
Diesel engine drives with other couplings	1,40

3.3.2 Load sharing factor,  $K_\gamma$ . The value for  $K_\gamma$  is to be taken as 1,15 for multi-engine drives or split torque arrangements. Otherwise  $K_\gamma$  is to be taken as 1,0. Alternatively, where measured data exists, a derived value will be considered.

3.3.3 Dynamic factor,  $K_v$ :

- For helical gears with  $\varepsilon_\beta \geq 1$ :  
 $K_v = 1 + Q^2 v z_1 10^{-5} = K_{v\beta}$   
 For helical gears with  $\varepsilon_\beta < 1$ :  
 $K_v = K_{v\alpha} - \varepsilon_\beta (K_{v\alpha} - K_{v\beta})$   
 For spur gears:  
 $K_v = 1 + 1,8 Q^2 v z_1 10^{-5} = K_{v\alpha}$

where  $\frac{v z_1}{100} > 14$  for heli gears, and

where  $\frac{v z_1}{100} > 10$  for spur gears the value of  $K_v$  will be specially considered.

3.3.4 Longitudinal load distribution factors,  $K_{H\beta}$  and  $K_{F\beta}$ :

$$K_{H\beta} = 1 + \frac{b F_{\beta y} C_\gamma}{2 F_t K_A K_\gamma K_v}$$

Calculated values of  $K_{H\beta} > 2$  are to be reduced by improved accuracy and helix correction as necessary:

where

- $F_{\beta y} = F_{\beta x} - y_\beta$  and  
 $F_{\beta x} = 1,33 f_{Sh} + f_{ma}$   
 $f_{ma} = \frac{2}{3} F_\beta$  at the design stage, or  
 $f_{ma} = \frac{1}{3} F_\beta$  where helix correction has been applied

$$f_{Sh} = f_{Sho} \frac{F_t K_A K_\gamma K_v}{b} \text{ where}$$

- $f_{Sho} = 23\gamma 10^{-3} \mu\text{m mm/N}$  for gears without helix correction and without end relief, or  
 $= 16\gamma 10^{-3} \mu\text{m mm/N}$  for gears without helix correction but with end relief, where

$$\gamma = \left( \frac{b}{d_1} \right)^2 \text{ for single helical and spur gears}$$

$$= 3 \left( \frac{b}{2d_1} \right)^2 \text{ for double helical gears}$$

The following minimum values are applicable, these also being the values where helix correction has been applied:

- $f_{Sho} = 10 \times 10^{-3} \mu\text{m mm/N}$  for helical gears, or  
 $= 5 \times 10^{-3} \mu\text{m mm/N}$  for spur gears

For through-hardened steels and surface hardened steels running on through-hardened steels:

$$y_\beta = \frac{320}{\sigma_{H\lim}} F_{\beta x} \text{ when}$$

$$y_\beta \leq \frac{12800}{\sigma_{H\lim}} \mu\text{m, and}$$

For surface hardened steels, when

$$y_\beta = 0,15 F_{\beta x}$$

$$y_\beta \leq 6 \mu\text{m}$$

$$K_{F\beta} = K_{H\beta}^n$$

where

$$n = \frac{\left( \frac{b}{h} \right)^2}{1 + \frac{b}{h} + \left( \frac{b}{h} \right)^2}$$

NOTES

- $\frac{b}{h}$  is to be taken as the smaller of  $\frac{b_1}{h_1}$  or  $\frac{b_2}{h_2}$
- For double helical gears  $\frac{b}{2}$  is to be substituted for  $b$  in the equation for  $n$ .

# Gearing

# Part 5, Chapter 5

Section 3

3.3.5 Transverse load distribution factors,  $K_{H\alpha}$  and  $K_{F\alpha}$

$$K_{H\alpha} = K_{F\alpha} \geq 1,00$$

where

$$\varepsilon_\gamma \leq 2$$

$$K_{H\alpha} = \frac{\varepsilon_\gamma}{2} \left\{ 0,9 + \frac{0,4C_\gamma (f_{pb} - y_\alpha) b}{F_t K_A K_\gamma K_V K_{H\beta}} \right\}$$

where

$$\varepsilon_\gamma > 2$$

$$K_{H\alpha} = 0,9 + 0,4 \sqrt{\frac{2(\varepsilon_\gamma - 1)}{\varepsilon_\gamma}} \left\{ \frac{C_\gamma (f_{pb} - y_\alpha) b}{F_t K_A K_\gamma K_V K_{H\beta}} \right\}, \text{ but}$$

$$K_{H\alpha} \leq \frac{\varepsilon_\gamma}{\varepsilon_\alpha Z_\varepsilon^2} \text{ and}$$

$$K_{F\alpha} \leq \frac{\varepsilon_\gamma}{0,25\varepsilon_\gamma + 0,75}$$

When tip relief is applied  $f_{pb}$  is to be half of the maximum specified value:

$$y_\alpha = \frac{160}{\sigma_{H \text{ lim}}} f_{pb} \text{ for through-hardened steels, when}$$

$$y_\alpha \leq \frac{6400}{\sigma_{H \text{ lim}}} \mu\text{m and}$$

$$y_\alpha = 0,075f_{pb} \text{ for surface hardened steels, when}$$

$$y_\alpha \leq 3 \mu\text{m}$$

When pinion and wheel are manufactured from different materials:

$$y_\alpha = \frac{y_{\alpha 1} + y_{\alpha 2}}{2}$$

3.3.6 Tooth mesh stiffness,  $C_\gamma$ :

$$C_\gamma = \frac{0,8}{q'} \cos \beta (0,75\varepsilon_\alpha + 0,25) \text{ N/mm } \mu\text{m}$$

where

$$q' = 0,04723 + \frac{0,1551}{z_{n1}} + \frac{0,25791}{z_{n2}} - 0,00635x_1 - \frac{0,11654x_1}{z_{n1}} - 0,00193x_2 - \frac{0,24188x_2}{z_{n2}} + 0,00529x_1^2 + 0,00182x_2^2$$

For internal gears  $z_{n2} = \infty$

Other calculation methods for  $C_\gamma$  will be specially considered.

## 3.4 Tooth loading for surface stress

3.4.1 The Hertzian contact stress,  $\sigma_H$ , at the pitch circle is not to exceed the allowable Hertzian contact stress,  $\sigma_{HP}$ .

$$\sigma_H = Z_H Z_E Z_\varepsilon Z_\beta \sqrt{\frac{F_t (u + 1)}{d_1 b u}} K_A K_\gamma K_V K_{H\beta} K_{H\alpha} \text{ and}$$

$$\sigma_{HP} = \frac{\sigma_{H \text{ lim}} Z_R Z_V Z_X}{S_{H \text{ min}}} \text{ for the pinion/wheel combination}$$

where

$$Z_H = \sqrt{\frac{2 \cos \beta_b \cos \alpha_{tw}}{\cos^2 \alpha_t \sin \alpha_{tw}}}$$

$$Z_E = 189,8 \text{ for steel}$$

$$Z_\varepsilon = \sqrt{\frac{4 - \varepsilon_\alpha}{3} (1 - \varepsilon_\beta) + \frac{\varepsilon_\beta}{\varepsilon_\alpha}} \text{ for } \varepsilon_\beta < 1 \text{ and}$$

$$Z_\varepsilon = \sqrt{\frac{1}{\varepsilon_\alpha}} \text{ for } \varepsilon_\beta \geq 1$$

$$Z_\beta = \sqrt{\cos \beta}$$

$$Z_R = \left( \frac{1}{R_a} \right)^{0,11} \text{ but } Z_R \leq 1,14$$

Where  $R_a$  is the surface roughness value of the tooth flanks. When pinion and wheel tooth flanks differ then the larger value of  $R_a$  is to be taken.

$$Z_V = 0,88 + 0,23 \left( 0,8 + \frac{32}{v} \right)^{-0,5}$$

For values of  $Z_X$ , see Table 5.3.2

$\sigma_{H \text{ lim}}$ , see Table 5.3.3

$S_{H \text{ lim}}$ , see Table 5.3.4.

**Table 5.3.2 Values of  $Z_X$**

Pinion heat treatment		$Z_X$
Carburized and induction-hardened	$m_n \leq 10$	1,00
	$10 < m_n < 30$	$1,05 - 0,005m_n$
	$30 \leq m_n$	0,9
Nitrided	$m_n < 7,5$	1,00
	$7,5 < m_n < 30$	$1,08 - 0,011m_n$
	$30 \leq m_n$	0,75
Through-hardened	All modules	1,00

**Table 5.3.3 Values of endurance limit for Hertzian contact stress,  $\sigma_{H \text{ lim}}$**

Heat treatment		$\sigma_{H \text{ lim}} \text{ N/mm}^2$
Pinion	Wheel	
Through-hardened	Through-hardened	$0,46\sigma_{B2} + 255$
Surface-hardened	Through-hardened	$0,42\sigma_{B2} + 415$
Carburized, nitrided or induction-hardened	Soft bath nitrided (Tufftrided)	1000
Carburized, nitrided or induction-hardened	Induction-hardened	$0,88 \text{ HV}_2 + 675$
Carburized or nitrided	Nitrided	1300
Carburized	Carburized	1500

**Table 5.3.4 Factors of safety**

	$S_{H \min}$	$S_{F \min}$
Main propulsion gears	1,4	1,8
Main propulsion gears for yachts and small craft, single screw	1,25	1,50
Main propulsion gears for yachts and small craft, multiple screw	1,20	1,45
Auxiliary gears	1,15	1,40
<b>NOTE</b> For the purposes of the above, yachts and small craft are considered to be pleasure craft not engaged in trade, passenger carrying or intended for charter service. Small craft are considered to be generally not greater than 24 m in length.		

## 3.5 Tooth loading for bending stress

3.5.1 The bending stress at the tooth root,  $\sigma_F$  is not to exceed the allowable tooth root bending stress  $\sigma_{FP}$

$$\sigma_F = \frac{F_t}{b m_n} Y_F Y_S Y_\beta K_A K_Y K_V K_{F\beta} K_{F\alpha} \quad \text{N/mm}^2$$

$$\sigma_{FP} = \frac{\sigma_{F \lim} Y_{ST} Y_{\delta \text{ rel T}} Y_{R \text{ rel T}} Y_X}{S_{F \min} Y_D} \quad \text{N/mm}^2$$

For values of  $S_{F \min}$ , see Table 5.3.4

$\sigma_{F \lim}$ , see Table 5.3.5

Stress correction factor  $Y_{ST} = 2$ .

3.5.2 Tooth form factor,  $Y_F$ :

$$Y_F = \frac{6 \frac{h_F}{m_n} \cos \alpha_{F \text{ en}}}{\left( \frac{S_{Fn}}{m_n} \right)^2 \cos \alpha_n}$$

where  $h_F$ ,  $\alpha_{F \text{ en}}$  and  $S_{Fn}$  are shown in Fig. 5.3.1.

$$\frac{S_{Fn}}{m_n} = z_n \sin \left( \frac{\pi}{3} - \nu \right) + \sqrt{3} \left( \frac{G}{\cos \nu} - \frac{\rho_{ao}}{m_n} \right)$$

where

$$\nu = \frac{2G}{z_n} \tan \nu - H$$

$$G = \frac{\rho_{ao}}{m_n} - \frac{h_{ao}}{m_n} + x$$

$$H = \frac{2}{z_n} \left( \frac{\pi}{2} - \frac{E}{m_n} \right) - \frac{\pi}{3}$$

$$E = \frac{\pi}{4} m_n - h_{ao} \tan \alpha_n + \frac{S_{pr}}{\cos \alpha_n} - (1 - \sin \alpha_n) \frac{\rho_{ao}}{\cos \alpha_n}$$

$E$ ,  $h_{ao}$ ,  $\alpha_n$ ,  $S_{pr}$  and  $\rho_{ao}$  are shown in Fig. 5.3.2

$$\frac{\rho_F}{m_n} = \frac{\rho_{ao}}{m_n} + \frac{2G^2}{\cos \nu (z_n \cos^2 \nu - 2G)}$$

$$d_{en} = \frac{2z}{|z|} \left\{ \left[ \sqrt{\left( \frac{d_{an}}{2} \right)^2 - \left( \frac{d_{bn}}{2} \right)^2} - \frac{\pi d \cos \beta \cos \alpha_n}{|z|} (\epsilon_{an} - 1) \right]^2 + \left( \frac{d_{bn}}{2} \right)^2 \right\}^{1/2}$$

where

$$d_{an} = d_n + d_a - d$$

$$d_n = \frac{d}{\cos^2 \beta_b}$$

$$d_{bn} = d_n \cos \alpha_n$$

$$\epsilon_{an} = \frac{\epsilon_a}{\cos^2 \beta_b}$$

$$\gamma_e = \frac{\frac{\pi}{2} + 2x \tan \alpha_n}{z_n} + \text{inv. } \alpha_n - \text{inv. } \alpha_{en}$$

where

$$\alpha_{en} = \arccos \frac{d_{bn}}{d_{en}}$$

$$\frac{h_F}{m_n} = \frac{1}{2} \left[ (\cos \gamma_e - \sin \gamma_e \tan \alpha_{F \text{ en}}) \frac{d_{en}}{m_n} - z_n \cos \left( \frac{\pi}{3} - \nu \right) - \frac{G}{\cos \nu} + \frac{\rho_{ao}}{m_n} \right]$$

where

$$\alpha_{F \text{ en}} = \alpha_{en} - \gamma_e.$$

**Table 5.3.5 Values of endurance limit for bending stress,  $\sigma_{F \lim}$**

Heat treatment	$\sigma_{F \lim}$ N/mm <sup>2</sup>
Through-hardened carbon steel	$0,09\sigma_B + 150$
Through-hardened alloy steel	$0,1\sigma_B + 185$
Soft bath nitrided (Tufftrided)	330
Induction hardened	$0,35 \text{ HV} + 125$
Gas nitrided	390
Carburized A	450
Carburized B	410
<b>NOTES</b> 1. A is applicable for Cr Ni Mo carburizing steels. 2. B is applicable for other carburizing steels.	

3.5.3 For internal tooth forms the form factor is calculated, as an approximation, for a substitute gear rack with the form of the basic rack in the normal section, but having the same tooth depth as the internal gear:

$$\frac{S_{Fn2}}{m_n} = 2 \left[ \frac{\pi}{4} + \tan \alpha \left( \frac{h_{ao2} - \rho_{ao2}}{m_n} \right) + \left( \frac{\rho_{ao2} - S_{pr}}{m_n \cos \alpha_n} - \frac{\rho_{ao2}}{m_n} \cos \frac{\pi}{6} \right) \right], \text{ and}$$

Fig. 5.3.2 External tooth forms

NOTES

1. Dimensions shown on rack profile of tooth
2.  $S_{pr} = P_{ro} - q$

**Fig. 5.3.2 External tooth forms**

$$\frac{h_{F2}}{m_n} = \frac{d_{en2} - d_{fn2}}{2m_n} - \left[ \frac{\pi}{4} + \left( \frac{h_{ao2}}{m_n} - \frac{d_{en2} - d_{fn2}}{2m_n} \right) \tan \alpha_n \right] \tan \alpha_n - \frac{\rho_{ao2}}{m_n} \left( 1 - \sin \frac{\pi}{6} \right)$$

$$\rho_{F2} = \frac{\rho_{ao2}}{2}$$

$d_{en2}$  is calculated as  $d_{en}$  for external gears, and  $d_{fn} = d - d_f - d_n$ .

$$Y_s = (1,2 + 0,13L) q_s \left( \frac{1}{1,21 + 2,3/L} \right)$$
$$L = \frac{S_{Fn}}{h_F}$$

$$q_s = \frac{S_{Fn}}{2\rho_F}$$

### 3.5.5 Helix angle factor $Y_B$

$$Y_{\beta} = 1 - \left( \varepsilon_{\beta} \frac{\beta}{120} \right), \text{ if } \varepsilon_{\beta} > 1 \text{ let } \varepsilon_{\beta} = 1$$

but  $Y_b \geq 1 - 0,25\varepsilon_b \geq 0,75$ .

3.5.6 Relative notch sensitivity factor,  $Y_{\delta \text{ rel T}}$

$Y_{\delta \text{ rel T}} = 1 + 0,036 (q_s - 2,5) \left( 1 - \frac{\sigma_y}{1200} \right)$  for through-hardened steels

$Y_{\delta \text{ rel T}} = 1 + 0,008 (q_s - 2,5)$  for carburized and induction-hardened steels, and

$Y_{\delta \text{ rel T}} = 1 + 0,04 (q_s - 2,5)$  for nitrided steels.

3.5.7 Relative surface finish factor,  $Y_{R \text{ rel T}}$

$Y_{R \text{ rel T}} = 1,674 - 0,529 (6R_a + 1)^{0,1}$  for through-hardened, carburized and induction hardened steels, and

$Y_{R \text{ rel T}} = 4,299 - 3,259 (6R_a + 1)^{0,005}$  for nitrided steels.

3.5.8 Size factor,  $Y_x$

$Y_x = 1,00$ , when  $m_n \leq 5$

$Y_x = 1,03 - 0,006m_n$  for through hardened steels

$Y_x = 0,85$ , when  $m_n \geq 30$

$Y_x = 1,05 - 0,01m_n$  for surface-hardened steels

$Y_x = 0,80$ , when  $m_n \geq 25$ .

3.5.9 Design factor,  $Y_D$

$Y_D = 0,83$  for gears treated with a controlled shot peening process

$Y_D = 1,5$  for idler gears

$Y_D = 1,25$  for shrunk on gears, or

$Y_D = 1 + \frac{0,2d_s^2 d P_t b}{F_t \sigma_{F \text{ lim}} (d_f^2 - d_s^2)}$ , otherwise

$Y_D = 1,00$ .

## 3.6 Factors of safety

3.6.1 Factors of safety are shown in Table 5.3.4.

## Section 4 Construction

### 4.1 Gear wheels and pinions

4.1.1 Where castings are used for wheel centres, any radial slots in the periphery are to be fitted with permanent chocks before shrinking-on the rim.

4.1.2 Where bolts are used to secure side plates to rim and hub, the bolts are to be a tight fit in the holes and the nuts are to be suitably locked by means other than welding.

4.1.3 Where welding is employed in the construction of wheels, the welding procedure is to be approved by the Surveyors before work is commenced. For this purpose, welding procedure approval tests are to be carried out with satisfactory results. Such tests are to be representative of the joint configuration and materials. Wheels are to be stress relieved after welding. All welds are to have a satisfactory surface finish and contour. Magnetic particle or liquid penetrant examination of all important welded joints is to be carried out to the satisfaction of the Surveyors.

4.1.4 In general, arrangements are to be made so that the interior structure of the wheel may be examined. Alternative proposals will be specially considered.

### 4.2 Accuracy of gear cutting and alignment

4.2.1 The machining accuracy (Q grade) of pinions and wheels is to be demonstrated to the satisfaction of the Surveyors. For this purpose records of measurements should be available for review by Surveyors on request.

4.2.2 Where allowance has been given for end relief or helix correction the normal shop meshing tests are to be supplemented by tooth alignment traces or other approved means to demonstrate the effectiveness of such modifications.

### 4.3 Gearcases

4.3.1 Gearcases and their supports are to be designed sufficiently stiff such that misalignment at the mesh due to movements of the external foundations and the thermal effects under all conditions of service do not disturb the overall tooth contact.

4.3.2 For gearcases fabricated by fusion welding the carbon content of steels should generally not exceed 0,23 per cent. Steels with higher carbon content may be approved subject to satisfactory results from weld procedure tests.

4.3.3 The welding is to be carried out in positions free from draughts and is to be downhand (flat) wherever practicable. Welding consumables are to be suitable for the materials being joined.

4.3.4 Gearcases are to be stress relief heat treated on completion of all welding.

4.3.5 Inspection openings are to be provided at the peripheries of gearcases to enable the teeth of pinions and wheels to be readily examined. Where the construction of gearcases is such that sections of the structure cannot readily be moved for inspection purposes, access openings of adequate size are also to be provided at the ends of the gearcases to permit examination of the structure of the wheels. Their attachment to the shafts is to be capable of being examined by removal of bearing caps or by equivalent means.

# Gearing

# Part 5, Chapter 5

Section 5

## Section 5 Tests

### 5.1 Balance of gear pinions and wheels

5.1.1 All rotating elements, (e.g. pinion and wheel shaft assemblies and coupling parts), are to be appropriately balanced.

5.1.2 The permissible residual unbalance,  $U$ , is defined as follows:

$$U = \frac{60m}{N} \times 10^3 \text{ g mm for } N \leq 3000$$

$$U = \frac{24m}{N} \times 10^3 \text{ g mm for } N > 3000$$

where

$m$  = mass of rotating element, kg

$N$  = maximum service rev/min of the rotating element.

5.1.3 Where the size or geometry of a rotating element precludes measurement of the residual unbalance, a full speed running test of the assembled gear unit at the manufacturer's works will normally be required to demonstrate satisfactory operation.

### 5.2 Meshing tests

5.2.1 Initially, meshing gears are to be carefully matched on the basis of the accuracy measurements taken. The alignment is to be demonstrated in the workshop by meshing in the gearbox without oil clearance in the bearings. Meshing is to be carried out with the gears locating in their light load positions and a load sufficient to overcome pinion weight and axial movement is to be imposed.

5.2.2 The gears are to be suitably coated to demonstrate the contact marking. The marking is to reflect the accuracy grade specified and end relief of helix correction, where these have been applied.

5.2.3 For gears without helix correction the marking is to be not less than shown in Table 5.5.1.

**Table 5.5.1 No load tooth contact marking**

ISO accuracy grade	Contact marking area
$Q \leq 5$	40% $h_w$ for 50% $b$ and 20% $h_w$ for a further 40% $b$
$Q \geq 6$	40% $h_w$ for 35% $b$ and 20% $h_w$ for a further 35% $b$
NOTES 1. Where $b$ is face width and $h_w$ is working tooth depth. 2. For spur gears the values of $h_w$ should be increased by a further 10%.	

5.2.4 For gears with end relief of helix correction the marking is to correspond to the designed no load contact pattern.

5.2.5 A permanent record is to be made of the meshing contact for purpose of checking the alignment when installed on board ship.

5.2.6 The full load tooth contact marking is to be not less than shown in Table 5.5.2.

**Table 5.5.2 Full load tooth contact marking**

ISO accuracy grade	Contact marking area
$Q \leq 5$	70% $h_w$ for 60% $b$ and 50% $h_w$ for a further 30% $b$
$Q \geq 6$	60% $h_w$ for 45% $b$ and 40% $h_w$ for a further 35% $b$
NOTES 1. Where $b$ is face width and $h_w$ is working tooth depth. 2. For spur gears the values of $h_w$ should be increased by a further 10%.	

### 5.3 Alignment

5.3.1 Reduction gears with sleeve bearings, for main and auxiliary purposes are to be provided with means for checking the internal alignment of the various elements in the gearcases.

5.3.2 In the case of separately mounted reduction gearing for main propulsion, means are to be provided by the gear manufacturer to enable the Surveyors to verify that no distortion of the gearcase has taken place, when chocked and secured to its seating on board ship.

5.3.3 Further requirements are given in Ch 8,5.

## Cross-reference

For lubricating oil systems, see Chapter 14.



# Main Propulsion Shafting

## Part 5, Chapter 6

Sections 1 &amp; 2

### Section

- 1 **Plans and particulars**
- 2 **Materials**
- 3 **Design**

### ■ Scope

The requirements of this Chapter relate, in particular, to formulae for determining the diameters of shafting for main propulsion installations, but requirements for couplings, coupling bolts, keys, keyways, sternbushes and other associated components are also included. The diameters may require to be modified as a result of alignment considerations and vibration characteristics, see Chapter 8, or the inclusion of stress raisers, other than those contained in this Chapter.

Alternative calculation methods for determining the diameters of shafting for main propulsion and their permissible torsional stresses will be considered by LR. Any alternative calculation method is to include all relevant loads on the complete dynamic shafting system under all permissible operating conditions. Consideration is to be given to the dimensions and arrangements of all shaft connections. Moreover, an alternative calculation method is to take into account design criteria for continuous and transient operating loads (dimensioning for fatigue strength) and for peak operating loads (dimensioning for yield strength). The fatigue strength analysis may be carried out separately for different load assumptions, for example as given below.

Shafts complying with the applicable Rules in Chapter 6 and Chapter 8 satisfy the following:

- (a) Low cycle fatigue criterion (typically  $<10^4$ ), i.e. the primary cycles represented by zero to full load and back to zero, including reversing torque if applicable. This is addressed by the formulas in Ch 6,3.1, 3.5 and 3.6.
- (b) High cycle fatigue criterion (typically  $>>10^7$ ), i.e. torsional vibration stresses permitted for continuous operation as well as reverse bending stresses and the accumulated fatigue due to torsional vibration when passing through a barred speed range or any other transient condition with associated stresses beyond those permitted for continuous operation. This is addressed by the formulas in Ch 8,2.5. The influence of reverse bending stresses is addressed by the safety margins inherent in the formulas from Ch 6,3.1, 3.5 and 3.6.

### ■ Section 1 Plans and particulars

#### 1.1 Shafting plans

1.1.1 The following plans, together with the necessary particulars of the machinery, including the maximum power and revolutions per minute, are to be submitted for consideration before the work is commenced:

- Final gear shaft.
- Thrust shaft.
- Intermediate shafting.
- Tube shaft, where applicable.
- Screwshaft.
- Screwshaft oil gland.
- Sternbush.

1.1.2 The specified minimum tensile strength of each shaft is to be stated.

1.1.3 In addition, a shafting arrangement plan indicating the relative positions of the main engines, flywheel, flexible coupling, gearing, thrust block, line shafting and bearings, sterntube, 'A' bracket and propeller, as applicable, is to be submitted for information.

### ■ Section 2 Materials

#### 2.1 Materials for shafts

2.1.1 The specified minimum tensile strength of forgings for shafts is to be selected within the following general limits:

- (a) Carbon and carbon-manganese steel – 400 to 760 N/mm<sup>2</sup> (41 to 77,5 kgf/mm<sup>2</sup>). See also 3.5.1.
- (b) Alloy steel – not exceeding 800 N/mm<sup>2</sup> (82 kgf/mm<sup>2</sup>).

2.1.2 Where it is proposed to use alloy steel, details of the chemical composition, heat treatment and mechanical properties are to be submitted for approval.

2.1.3 Where shafts may experience vibratory stresses close to the permissible stresses for transient operation, the materials are to have a specified minimum tensile strength of 500 N/mm<sup>2</sup> (51 kgf/mm<sup>2</sup>).

2.1.4 Where materials with greater specified or actual tensile strengths than the limitations given above are used, reduced shaft dimensions or higher permissible vibration stresses are not acceptable when derived from the formulae used in Section 3.1, 3.5, 3.6 and Ch 8,2.5.

#### 2.2 Ultrasonic tests

2.2.1 Ultrasonic tests are required on shaft forgings where the diameter is 250 mm or greater.

# Main Propulsion Shafting

# Part 5, Chapter 6

Section 3

## Section 3 Design

### 3.1 Intermediate shafts

3.1.1 The diameter,  $d$ , of the intermediate shaft is to be not less than determined by the following formula:

$$d = Fk \sqrt[3]{\frac{P}{R} \left( \frac{560}{\sigma_u + 160} \right)} \text{ mm}$$

$$\left( d = Fk \sqrt[3]{\frac{H}{R} \left( \frac{57}{\sigma_u + 16} \right)} \text{ mm} \right)$$

where

$k = 1,0$  for shafts with integral coupling flanges complying with 3.7 or with shrink fit couplings, see 3.1.4

$= 1,10$  for shafts with keyways in tapered or cylindrical connections, where the fillet radii in the transverse section of the bottom of the keyway are to be not less than  $0,0125d$

$= 1,10$  for shafts with transverse or radial holes where the diameter of the hole ( $d_h$ ) is not greater than  $0,3d$

$= 1,20$  for shafts with longitudinal slots, see 3.1.6

$F = 95(86)$  for turbine installations, electric propulsion installations and oil engine installations with slip type couplings

$= 100(90,5)$  for other oil engine installations

$P(H)$  and  $R$  are defined in Ch 1,3.3 (losses in gearboxes and bearings are to be disregarded)

$\sigma_u$  = specified minimum tensile strength of the shaft material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>), see 2.1.3

After a length of  $0,2d$  from the end of a keyway, transverse hole or radial hole and  $0,3d$  from the end of a longitudinal slot, the diameter of the shaft may be gradually reduced to that determined with  $k = 1,0$ .

3.1.2 For shafts with design features other than stated in 3.1.1, the value of  $k$  will be specially considered.

3.1.3 The Rule diameter of the intermediate shaft for oil engines, turbines and electric propelling motors may be reduced by 3,5 per cent for ships classed exclusively for smooth water service, and by 1,75 per cent for ships classed exclusively for service on the Great Lakes.

3.1.4 For shrink fit couplings  $k$  refers to the plain shaft section only. Where shafts may experience vibratory stresses close to the permissible stresses for continuous operation, an increase in diameter to the shrink fit diameter is to be provided, e.g. a diameter increase of 1 to 2 per cent and a blending radius as described in 3.8.

3.1.5 Keyways are in general not to be used in installations with a barred speed range.

3.1.6 The application of  $k = 1,20$  is limited to shafts with longitudinal slots having a length of not more than  $0,8d$  and a width of not more than  $0,1d$  and a diameter of central hole  $d_i$  of not more than  $0,8d$ , see 3.7. The end rounding of the slot is not to be less than half the width. An edge rounding should preferably be avoided as this increases the stress concentration slightly. The values of  $c_K$ , see Table 8.2.1 in Pt 5, Ch 8, are valid for 1, 2 and 3 slots, i.e. with slots at 360, 180 and 120 degrees apart respectively.

### 3.2 Gear quill shafts

3.2.1 The diameter of the quill shaft is to be not less than given by the following formula:

$$\text{Diameter of quill shaft} = 101 \sqrt[3]{\frac{P \cdot 400}{R \sigma_u}} \text{ mm}$$

$$\left( 91 \sqrt[3]{\frac{H \cdot 41}{R \sigma_u}} \text{ mm} \right)$$

where  $P(H)$  and  $R$  are as defined in Ch 1,3.3.

$\sigma_u$  = specified minimum tensile strength of the material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) but is not to exceed 1100 N/mm<sup>2</sup> (112 kgf/mm<sup>2</sup>).

### 3.3 Final gear wheel shafts

3.3.1 Where there is only one pinion geared into the final wheel, or where there are two pinions which are set to subtend an angle at the centre of the shaft of less than 120 degrees, the diameter of the shaft at the final wheel and the adjacent journals is to be not less than 1,15 times that required for the intermediate shaft.

3.3.2 Where there are two pinions geared into the final wheel opposite, or nearly opposite, to each other, the diameter of the shaft at the final wheel and the adjacent journals is to be not less than 1,1 times that required for the intermediate shaft.

3.3.3 In both 3.3.1 and 3.3.2, abaft the journals, the shaft may be gradually tapered down to the diameter required for an intermediate shaft determined according to 3.1, where  $\sigma_u$  is to be taken as the specified minimum tensile strength of the final wheel shaft material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

### 3.4 Thrust shafts

3.4.1 The diameter at the collars of the thrust shaft transmitting torque, or in way of the axial bearing where a roller bearing is used as a thrust bearing, is to be not less than that required for the intermediate shaft in accordance with 3.1 with a  $k$  value of 1,10. Outside a length equal to the thrust shaft diameter from the collars, the diameter may be tapered down to that required for the intermediate shaft with a  $k$  value of 1,0. For the purpose of the foregoing calculations,  $\sigma_u$  is to be taken as the minimum tensile strength of the thrust shaft material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

# Main Propulsion Shafting

# Part 5, Chapter 6

Section 3

## 3.5 Screwshafts and tube shafts

3.5.1 The diameter,  $d_p$  of the screwshaft immediately forward of the forward face of the propeller boss or, if applicable, the forward face of the screwshaft flange, is to be not less than determined by the following formula:

$$d_p = 100k \sqrt[3]{\frac{P}{R} \left( \frac{560}{\sigma_u + 160} \right)} \text{ mm}$$

$$\left( d_p = 90,5k \sqrt[3]{\frac{P}{R} \left( \frac{57}{\sigma_u + 16} \right)} \text{ mm} \right)$$

where

$k = 1,22$  for a shaft carrying a keyless propeller fitted on a taper, or where the propeller is attached to an integral flange, and where the shaft is fitted with a continuous liner or is oil lubricated and provided with an approved type of oil sealing gland

$= 1,26$  for a shaft carrying a keyed propeller and where the shaft is fitted with a continuous liner or is oil lubricated and provided with an approved type of oil sealing gland

$P$  (H) and  $R$  are defined in Ch 1,3.3, (losses in gearboxes and bearings are to be disregarded)

$\sigma_u$  = specified minimum tensile strength of the shaft material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>) but is not to be taken as greater than 600 N/mm<sup>2</sup> (61 kgf/mm<sup>2</sup>). See 2.1.3.

3.5.2 The diameter,  $d_p$  of the screwshaft determined in accordance with the formula in 3.5.1 is to extend over a length not less than that to the forward edge of the bearing immediately forward of the propeller or  $2,5d_p$  whichever is the greater.

3.5.3 The diameter of the portion of the screwshaft and tube shaft, forward of the length required by 3.5.2 to the forward end of the forward stern tube seal, is to be determined in accordance with the formula in 3.5.1 with a  $k$  value of 1,15. The change of diameter from that determined with  $k = 1,22$  or 1,26 to that determined with  $k = 1,15$  should be gradual, see 3.7.

3.5.4 Screwshafts which run in sterntubes and tube shafts may have the diameter forward of the forward stern tube seal gradually reduced to the diameter of the intermediate shaft. Abrupt changes in shaft section at the screwshaft/tube shaft to intermediate shaft couplings are to be avoided, see 3.7.

3.5.5 Unprotected screwshafts and tube shafts of corrosion-resistant material will be specially considered.

3.5.6 For shafts of non-corrosion-resistant materials which are exposed to sea-water, the diameter of the shaft is to be determined in accordance with the formula in 3.5.1 with a  $k$  value of 1,26 and  $\sigma_u$  taken as 400 N/mm<sup>2</sup> (41 kgf/mm<sup>2</sup>).

## 3.6 Hollow shafts

3.6.1 Where the thrust, intermediate and tube shafts and screwshafts have central holes, the outside diameters of the shafts are to be not less than given by the following formula:

$$d_o = d \sqrt[3]{\frac{1}{1 - \left( \frac{d_i}{d_o} \right)^4}}$$

where

$d_o$  = outside diameter, in mm

$d$  = Rule size diameter of solid shaft, in mm

$d_i$  = diameter of central hole, in mm.

However, where the diameter of the central hole does not exceed 0,4 times the outside diameter, no increase over Rule size need be provided.

## 3.7 Couplings and transitions of diameters

3.7.1 The minimum thicknesses of the coupling flanges are to be equal to the diameters of the coupling bolts at the face of the couplings as required by 3.8 and, for this purpose, the minimum tensile strength of the bolts is to be taken as equivalent to that of the shafts. For intermediate shafts, thrust shafts and the inboard end of the screwshaft, the thickness of the coupling flange is in no case to be less than 0,20 of the diameter of the intermediate shaft as required by 3.1.

3.7.2 The fillet radius at the base of the coupling flange is to be not less than 0,08 of the diameter of the shaft at the coupling but, in the case of crankshafts, the fillet radius at the centre coupling flanges may be 0,05 of the diameter of the shaft at the coupling. The fillets are to have a smooth finish and are not to be recessed in way of nut and bolt heads.

3.7.3 Where the propeller is attached by means of a flange, the thickness of the flange is to be not less than 0,25 of the actual diameter of the adjacent part of the screwshaft. The fillet radius at the base of the coupling flange is to be not less than 0,125 of the diameter of the shaft at the coupling.

3.7.4 All couplings which are attached to shafts are to be of approved dimensions.

3.7.5 Where couplings are separate from the shafts, provision is to be made to resist the astern pull.

3.7.6 Where a coupling is shrunk on to the parallel portion of a shaft or is mounted on a slight taper, e.g. by means of the oil pressure injection method, full particulars of the coupling including the interference fit are to be submitted for special consideration.

3.7.7 Transitions of diameters are to be designed with either a smooth taper or a blending radius. In general, a blending radius equal to the change in diameter is recommended.

# Main Propulsion Shafting

# Part 5, Chapter 6

Section 3

## 3.8 Coupling bolts

3.8.1 The diameter of the bolts at the joining faces of the couplings is to be not less than given by the following formula:

$$\text{Diameter of coupling bolts} = \sqrt{\frac{240}{nD} \frac{10^6}{\sigma_u} \frac{P}{R}} \text{ mm}$$

where

$n$  = number of bolts in the coupling

$D$  = pitch circle diameter of bolts, in mm

$\sigma_u$  = specified minimum tensile strength of bolts, in N/mm<sup>2</sup>

$P$  ( $H$ ) and  $R$  are as defined in Ch 1,3.3.

3.8.2 At the joining faces of couplings, other than within the crankshaft and at the thrust shaft/crankshaft coupling, the Rule diameter of the coupling bolts may be reduced by 5,2 per cent for ships classed exclusively for smooth water service, and 2,6 per cent for ships classed exclusively for service on the Great Lakes.

## 3.9 Bronze or gunmetal liners on shafts

3.9.1 The thickness,  $t$ , of liners fitted on screwshafts or on tube shafts, in way of the bushes, is to be not less, when new, than given by the following formula:

$$t = \frac{D + 230}{32} \text{ mm}$$

where

$t$  = thickness of the liner, in mm

$D$  = diameter of the screwshaft or tube shaft under the liner, in mm.

3.9.2 The thickness of a continuous liner between the bushes is to be not less than  $0,75t$ .

3.9.3 Continuous liners should preferably be cast in one piece.

3.9.4 Where liners consist of two or more lengths, these are to be butt welded together. In general, the lead content of the gunmetal of each length forming a butt welded liner is not to exceed 0,5 per cent. The composition of the electrodes or filler rods is to be substantially lead-free.

3.9.5 The circumferential butt welds are to be of multi-run, full penetration type. Provision is to be made for contraction of the weld by arranging for a suitable length of the liner containing the weld, if possible about three times the shaft diameter, to be free of the shaft. To prevent damage to the surface of the shaft during welding, a strip of heat resisting material covered by a copper strip should be inserted between the shaft and the liner in way of the joint. Other methods for welding this joint may be accepted if approved. The welding is to be carried out by an approved method and to the Surveyor's satisfaction.

3.9.6 Each continuous liner or length of liner is to be tested by hydraulic pressure to 2,0 bar (2,0 kgf/cm<sup>2</sup>) after rough machining.

3.9.7 Liners are to be carefully shrunk on, or forced on, to the shafts by hydraulic pressure. Pins are not to be used to secure the liners.

3.9.8 Effective means are to be provided for preventing water from reaching the shaft at the part between the after end of the liner and the propeller boss.

## 3.10 Keys and keyways

3.10.1 Round ended or sled-runner ended keys are to be used, and the keyways in the propeller boss and cone of the screwshaft are to be provided with a smooth fillet at the bottom of the keyways. The radius of the fillet is to be at least 0,0125 of the diameter of the screwshaft at the top of the cone. The sharp edges at the top of the keyways are to be removed.

3.10.2 Two screwed pins are to be provided for securing the key in the keyway, and the forward pin is to be placed at least one-third of the length of the key from the end. The depth of the tapped holes for the screwed pins is not to exceed the pin diameter, and the edges of the holes are to be slightly bevelled.

3.10.3 The distance between the top of the cone and the forward end of the keyway is to be not less than 0,2 of the diameter of the screwshaft at the top of the cone.

3.10.4 The effective sectional area of the key in shear, is to be not less than  $\frac{d^3}{2,6d_1}$  mm<sup>2</sup>

where

$d$  = diameter, in mm, required for the intermediate shaft determined in accordance with 3.1, based on material having a specified minimum tensile strength of 400 N/mm<sup>2</sup> (41 kgf/mm<sup>2</sup>) and  $k = 1$

$d_1$  = diameter of shaft at mid-length of the key, in mm.

## 3.11 Propellers

3.11.1 For keyed and keyless propellers, see Chapter 7.

## 3.12 Sternbushes

3.12.1 The length of the bearing in the sternbush next to and supporting the propeller is to be as follows:

- For water lubricated bearings which are lined with lignum vitae, rubber composition or staves of approved plastics material, the length is to be not less than four times the diameter required for the screwshaft under the liner.
- For water lubricated bearings lined with two or more circumferentially spaced sectors of an approved plastics material, in which it can be shown that the sectors operate on hydrodynamic principles, the length of the bearing is to be such that the nominal bearing pressure will not exceed 5,5 bar (5,6 kgf/cm<sup>2</sup>). The length of the bearing is to be not less than twice its diameter.

# Main Propulsion Shafting

## Part 5, Chapter 6

Section 3

- (c) For oil lubricated bearings of synthetic material the flow of lubricant is to be such that overheating, under normal operating conditions, cannot occur. The acceptable nominal bearing pressure will be considered upon application and is to be supported by the results of an agreed test programme. In general, the length of the bearing is not to be less than 2,0 times the rule diameter of the shaft in way of the bearing.
- (d) For bearings which are white-metal lined, oil lubricated and provided with an approved type of oil sealing gland, the length of the bearing is to be approximately twice the diameter required for the screwshaft and is to be such that the nominal bearing pressure will not exceed 8,0 bar (8,1 kgf/cm<sup>2</sup>). The length of the bearing is to be not less than 1,5 times its diameter.
- (e) For bearings of cast iron and bronze which are oil lubricated and fitted with an approved oil sealing gland, the length of the bearing is, in general, to be not less than four times the diameter required for the screwshaft.
- (f) For bearings which are grease lubricated, the length of the bearing is to be not less than four times the diameter required for the screwshaft.

3.12.2 Forced water lubrication is to be provided for all bearings lined with rubber or plastics and for those bearings lined with lignum vitae where the shaft diameter is 380 mm or over. The supply of water may come from a circulating pump or other pressure source. Flow indicators are to be provided for the water service to plastics and rubber bearings. The water grooves in the bearings are to be of ample section and of a shape which will be little affected by wear down, particularly for bearings of the plastics type.

3.12.3 Bearings of synthetic material are to be supplied finished machined to design dimensions within a rigid bush. Means are to be provided to prevent rotation of the lining within the bush during operation.

3.12.4 All sternbushes are to be adequately secured in the sterntube/housings.

3.12.5 The shut-off valve or cock controlling the supply of water is to be fitted direct to the after peak bulkhead, or to the sterntube where the water supply enters the sterntube forward of the bulkhead.

3.12.6 Oil sealing glands fitted in ships classed for unrestricted service must be capable of accommodating the effects of differential expansion between hull and line of shafting in sea temperatures ranging from arctic to tropical. This requirement applies particularly to those glands which span the gap and maintain oiltightness between the sterntube and the propeller boss.

3.12.7 Where a tank supplying lubricating oil to the sternbush is fitted, it is to be located above the load waterline and is to be provided with a low level alarm device in the engine room.

3.12.8 Where sternbush bearings are oil lubricated, provision is to be made for cooling the oil by maintaining water in the after peak tank above the level of the sterntube or by other approved means. Means for ascertaining the temperature of the oil in the sterntube are also to be provided.

3.12.9 Where there is compliance with the terms of 3.12.1(c) and (d) to the Surveyor's satisfaction, a screwshaft will be assigned the notation **OG** in the *Supplement to the Register Book* for Periodical Survey purposes, see Pt 1, Ch 3.

3.12.10 Screwshafts which are grease lubricated are not eligible for the **OG** notation.

3.12.11 Where an **\*IWS** (In-water Survey) notation is to be assigned, see Pt 1, Ch 2,2.3.11, means are to be provided for ascertaining the clearance in the sternbush with the vessel afloat.

### 3.13 Vibration and alignment

3.13.1 For the requirements for torsional, axial and lateral vibration, and for alignment of the shafting, see Chapter 8.



## Section

- 1 **Plans and particulars**
- 2 **Materials**
- 3 **Design**
- 4 **Fitting of propellers**

## Section 1 Plans and particulars


### 1.1 Details to be submitted

1.1.1 A plan, in triplicate, of the propeller is to be submitted for approval, together with the following particulars using the symbols shown:

- (a) Maximum blade thickness of the expanded cylindrical section considered,  $T$ , in mm.
- (b) Maximum shaft power, see Ch 1,3.3,  $P$ , in kW ( $H$ , in shp).
- (c) Estimated ship speed at design loaded draught in the free running condition at maximum shaft power and corresponding revolutions per minute, see (b) and (d).
- (d) Revolutions per minute of the propeller at maximum power,  $R$ .
- (e) Propeller diameter,  $D$ , in metres.
- (f) Pitch at 25 per cent radius (for solid propellers only),  $P_{0,25}$ , in metres.
- (g) Pitch at 35 per cent radius (for controllable pitch propellers only),  $P_{0,35}$ , in metres.
- (h) Pitch at 60 per cent radius  $P_{0,6}$ , in metres.
- (i) Pitch at 70 per cent radius  $P_{0,7}$ , in metres.
- (k) Length of blade section of the expanded cylindrical section at 25 per cent radius (for solid propellers only),  $L_{0,25}$ , in mm.
- (l) Length of blade section of the expanded cylindrical section at 35 per cent radius (for controllable pitch propellers only)  $L_{0,35}$ , in mm.
- (m) Length of blade section of the expanded cylindrical section at 60 per cent radius,  $L_{0,6}$ , in mm.
- (n) Rake at blade tip measured at shaft axis (backward rake positive, forward rake negative),  $A$ , in mm.
- (o) Number of blades,  $N$ .
- (p) Developed area ratio,  $B$ .
- (q) Material: type and specified minimum tensile strength.
- (r)  $\theta_s$ , skew angle, in degrees, see Fig. 7.1.1.
- (s) Connection of propeller to shaft – details of fit, push-up, securing, etc.

1.1.2 For propellers having a skew angle equal to or greater than  $50^\circ$ , in addition to the particulars detailed in 1.1.1, details are to be submitted of:

- (a) Full blade section details at each radial station defined for manufacture.
- (b) A detailed blade stress computation supported by the following hydrodynamic data for the ahead mean wake condition and when absorbing full power:



**Fig. 7.1.1 Definition of skew angle**

- (i) Radial distribution of lift and drag coefficients, section inflow velocities and hydrodynamic pitch angles.
- (ii) Section pressure distributions calculated by either an advised inviscid or viscous procedure.

1.1.3 For blades of fixed pitch propellers with skew angle of  $30^\circ$  or greater, the stresses in the propeller blade during astern operation are not to exceed 80 per cent of the propeller blade material proof stress. Consideration is to be given to failure conditions and a factor of safety of 1,5 is to be attained using an acceptable fatigue failure criteria. Documentary evidence confirming that these criteria are satisfied is to be submitted.

1.1.4 The maximum skew angle of a propeller blade is defined as the angle, in projected view of the blade, between a line drawn through the blade tip and the shaft centreline and a second line through the shaft centreline which acts as a tangent to the locus of the mid-points of the helical blade sections, see Fig. 7.1.1.

1.1.5 Where propellers and similar devices of unusual design are intended for more than one operating regime, such as towing or trawling, then a detailed blade stress calculation for each operating condition, indicating the rotational and ship speed, is to be submitted for consideration.

1.1.6 Where it is proposed to fit the propeller to the screwshaft without the use of a key, plans of the boss, tapered end of screwshaft, propeller nut and, where applicable, the sleeve, are to be submitted.

# Propellers

# Part 5, Chapter 7

Sections 1, 2 & 3

1.1.7 Where a sleeve is fitted, details of the proposed type of material and mechanical properties are also to be submitted.

1.1.8 In cases where the ship has been the subject of model wake field tests, a copy of the results is to be submitted.

## Section 2 Materials

### 2.1 Castings

2.1.1 Castings for propellers and propeller blades are to comply with the requirements of the Rules for Materials (Part 2). The specified minimum tensile strength is to be not less than stated in Table 7.2.1.

2.1.2 Where it is proposed to use materials which are not included in Table 7.2.1, details of the chemical composition, mechanical properties and density are to be submitted for approval.

2.1.3 Spheroidal cast iron load transmitting components of controllable pitch mechanisms, are to be manufactured, tested and certified in accordance with Chapter 7 of the Rules for Materials, and have an elongation of not less than 12 per cent.

## Section 3 Design

### 3.1 Minimum blade thickness

3.1.1 For propellers having a skew angle of less than 25°, as defined in 1.1.4, the minimum blade thickness,  $T$ , of the propeller blades at 25 per cent radius for solid propellers, 35 per cent radius for controllable pitch propellers, neglecting any increase due to fillets, and at 60 per cent radius, is to be not less than:

$$T = \frac{KCA}{EFULN} + 100 \sqrt{\frac{3150MP}{EFRULN}} \text{ mm}$$

$$\left( T = \frac{KCA}{9,81EFULN} + 27,4 \sqrt{\frac{3150MH}{EFRULN}} \text{ mm} \right)$$

where

$L = L_{0,25}, L_{0,35}, \text{ or } L_{0,6}, \text{ as appropriate}$

$$K = \frac{GBD^3R^2}{675}$$

$G = \text{density, in g/cm}^3, \text{ see Table 7.2.1}$

$U = \text{allowable stress, in N/mm}^2 \text{ (kgf/mm}^2\text{) see 3.1.2, 3.1.3, 3.1.4, and Table 7.2.1}$

$$E = \frac{\text{actual face modulus}}{0,09T^2L}$$

For aerofoil sections with and without trailing edge washback,  $E$  may be taken as 1,0 and 1,25 respectively

**Table 7.2.1 Materials for propellers**

Material	SI units			Metric units		
	Specified minimum tensile strength N/mm <sup>2</sup>	$G$ Density g/cm <sup>3</sup>	$U$ Allowable stress N/mm <sup>2</sup>	Specified minimum tensile strength kgf/mm <sup>2</sup>	$G$ Density g/cm <sup>3</sup>	$U$ Allowable stress kgf/mm <sup>2</sup>
Grey cast iron	250	7,2	17,2	25	7,2	1,75
Spheroidal or nodular graphite cast iron	400	7,3	20,6	41	7,3	2,1
Carbon steels	400	7,9	20,6	41	7,9	2,1
Low alloy steels	440	7,9	20,6	45	7,9	2,1
13% chromium stainless steels	540	7,7	41	55	7,7	4,2
Chromium-nickel austenitic stainless steel	450	7,9	41	46	7,9	4,2
Duplex stainless steels	590	7,8	41	60	7,8	4,2
Grade Cu 1 Manganese bronze (high tensile brass)	440	8,3	39	45	8,3	4,0
Grade Cu 2 Ni-Manganese bronze (high tensile brass)	440	8,3	39	45	8,3	4,0
Grade Cu 3 Ni-Aluminium bronze	590	7,6	56	60	7,6	5,7
Grade Cu 4 Mn-Aluminium bronze	630	7,5	46	64	7,5	4,7



# Propellers

# Part 5, Chapter 7

Section 3

$$\left. \begin{aligned} C &= 1,0 \\ F &= \frac{P_{0,25}}{D} + 0,8 \\ M &= 1,0 + \frac{3,75D}{P_{0,7}} + 2,8 \frac{P_{0,25}}{D} \end{aligned} \right\} \begin{array}{l} \text{for solid} \\ \text{propellers at} \\ \text{25 per cent} \\ \text{radius} \end{array}$$

$$\left. \begin{aligned} C &= 1,4 \\ F &= \frac{P_{0,35}}{D} + 1,6 \\ M &= 1,35 + \frac{5D}{P_{0,7}} + 2,6 \frac{P_{0,35}}{D} \end{aligned} \right\} \begin{array}{l} \text{for controllable} \\ \text{pitch propellers at} \\ \text{35 per cent} \\ \text{radius} \end{array}$$

$$\left. \begin{aligned} C &= 1,6 \\ F &= \frac{P_{0,6}}{D} + 4,5 \\ M &= 1,35 + \frac{5D}{P_{0,7}} + 1,35 \frac{P_{0,6}}{D} \end{aligned} \right\} \begin{array}{l} \text{for all propellers} \\ \text{at 60 per cent} \\ \text{radius} \end{array}$$

3.1.2 The fillet radius between the root of a blade and the boss of a propeller is to be not less than the Rule thickness of the blade or equivalent at this location. Composite radiused fillets or elliptical fillets which provide a greater effective radius to the blade are acceptable and are to be preferred. Where fillet radii of the required size cannot be provided, the value of

$U$  is to be multiplied by  $\left(\frac{r}{T}\right)^{0,2}$

where

$r$  = proposed fillet radius at the root, in mm

$T$  = Rule thickness of the blade at the root, in mm

Where a propeller has bolted-on blades, consideration is also to be given to the distribution of stress in the palms of the blades. In particular, the fillets of recessed bolt holes and the lands between bolt holes are not to induce stresses which exceed those permitted at the outer end of the fillet radius between the blade and the palm.

3.1.3 For propellers having skew angles of 25° or greater, but less than 50°, the mid-chord thickness,  $T_{sk0,6}$ , at the 60 per cent radius is to be not less than:

$$T_{sk0,6} = 0,54T_{0,6} \sqrt{1 + 0,1\theta_s} \text{ mm}$$

The mid-chord thickness,  $T_{sk \text{ root}}$ , at 25 or 35 per cent radius, neglecting any increase due to fillets, is to be not less than:

$$T_{sk \text{ root}} = 0,75T_{\text{root}} \sqrt[4]{1 + 0,1\theta_s} \text{ mm}$$

where

$\theta_s$  = proposed skew angle as defined in 1.1.4

$T_{0,6}$  = thickness at 60 per cent radius, calculated by 3.1.1, in mm

$T_{\text{root}}$  = thickness at 25 per cent radius or 35 per cent radius, calculated by 3.1.1, in mm

The thicknesses at the remaining radii are to be joined by a fair curve and the sections are to be of suitable aerofoil section.

3.1.4 Results of detailed calculations where carried out, are to be submitted.

3.1.5 For cases where the composition of the propeller material is not specified in Table 7.2.1, or where propellers of the cast irons and carbon and low alloy steels shown in this Table are provided with an approved method of cathodic protection, special consideration will be given to the value of  $U$ .

3.1.6 The value  $U$  may be increased by 10 per cent for twin screw and outboard propellers of triple screw ships.

3.1.7 Where the design of a propeller has been based on analysis of reliable wake survey data in conjunction with a detailed fatigue analysis and is deemed to permit scantlings less than required by 3.1.1 or 3.1.3, a detailed stress computation for the blades is to be submitted for consideration.

## 3.2 Keyless propellers

3.2.1 The symbols used in 3.2.2 (oil injection method of fitting) and 3.2.3 to 3.2.7 (dry fitting cast iron sleeve) are defined as follows:

$d_1$  = diameter of the screwshaft cone at the mid-length of the boss or sleeve, in mm

$d_2$  = outside diameter of the sleeve at its mid-length, in mm

$d_3$  = outside diameter of the boss at its mid-length, in mm

$d_i$  = bore diameter of screwshaft, in mm

$$h = \frac{2}{E_2} \left( \frac{1}{k_1^2 - 1} \right)$$

$$k_1 = \frac{d_2}{d_1}$$

$$k_2 = \frac{d_3}{d_2}$$

$$k_3 = \frac{d_3}{d_1}$$

$$l = \frac{d_i}{d_1}$$

$$\rho_1 = \frac{2M}{A_1\theta_1V_1} \left( -1 + \sqrt{1 + V_1 \left( \frac{F_1^2}{M^2} + 1 \right)} \right)$$

$$\rho_2 = \frac{2M}{A_2\theta_2V_2} \left( -1 + \sqrt{1 + V_2 \left( \frac{F_2^2}{M^2} + 1 \right)} \right)$$

$$\rho_{10} = \frac{2M}{A_1\theta_1V_1} \left( -1 + \sqrt{1 + V_1 \left( \frac{F_{10}^2}{M^2} + 1 \right)} \right)$$

$$\rho_{20} = \frac{2M}{A_2\theta_2V_2} \left( -1 + \sqrt{1 + V_2 \left( \frac{F_{20}^2}{M^2} + 1 \right)} \right)$$

$A_1$  = contact area of fitting at screwshaft, in mm<sup>2</sup>

$A_2$  = contact area of fitting at outside of sleeve, in mm<sup>2</sup>

$$B_1 = \frac{1}{E_2} \left( \frac{k_1^2 + 1}{k_1^2 - 1} + v_2 \right) + \frac{1}{E_1} \left( \frac{1 + l^2}{1 - l^2} - v_1 \right)$$

# Propellers

# Part 5, Chapter 7

Section 3

$$B_2 = \frac{1}{E_3} \left( \frac{k_2^2 + 1}{k_2^2 - 1} + \nu_3 \right) + \frac{1}{E_2} \left( \frac{k_1^2 + 1}{k_1^2 - 1} - \nu_2 \right)$$

$$B_3 = \frac{1}{E_3} \left( \frac{k_3^2 + 1}{k_3^2 - 1} + \nu_3 \right) + \frac{1}{E_1} \left( \frac{1 + l^2}{1 - l^2} - \nu_1 \right)$$

$$C = 0 \text{ for turbine installations}$$

$$= \frac{\text{vibratory torque at the maximum service speed}}{\text{mean torque at the maximum service speed}}$$

for oil engine installations

$$E_1 = \text{modulus of elasticity of screwshaft material, in N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$E_2 = \text{modulus of elasticity of sleeve material, in N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$E_3 = \text{modulus of elasticity of propeller material, in N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

$$F_1 = \frac{2Q}{d_1} (1 + C)$$

$$F_2 = \frac{2Q}{d_2} (1 + C)$$

$$F_{10} = \frac{2Q}{d_1} \left( 1 + C + \frac{I_f}{100} \right)$$

$$F_{20} = \frac{2Q}{d_2} \left( 1 + C + \frac{I_f}{100} \right)$$

$$I_f = \text{percentage increase for Ice Class 1D, obtained from Ch 9,3.2.1}$$

$$M = \text{propeller thrust, in N (kgf)}$$

$$Q = \text{mean torque corresponding to } P \text{ (H) and } R \text{ as defined in Ch 1,3.3, in N mm (kgf mm)}$$

$$T_1 = \text{temperature at time of fitting propeller on shaft, in } ^\circ\text{C}$$

$$T_2 = \text{temperature at time of fitting sleeve into boss, in } ^\circ\text{C}$$

$$V_1 = 0,51 \left( \frac{\mu_1}{\theta_1} \right)^2 - 1$$

$$V_2 = 0,51 \left( \frac{\mu_2}{\theta_2} \right)^2 - 1$$

$$Y = B_1 B_2 - h^2 k_1^2$$

$$\alpha_1 = \text{coefficient of linear expansion of screwshaft material, in mm/mm/}^\circ\text{C}$$

$$\alpha_2 = \text{coefficient of linear expansion of sleeve material, in mm/mm/}^\circ\text{C}$$

$$\alpha_3 = \text{coefficient of linear expansion of propeller material, in mm/mm/}^\circ\text{C}$$

$$\theta_1 = \text{taper of the screwshaft cone, but is not to exceed}$$

$$\frac{1}{15} \text{ on the diameter, i.e. } \theta_1 \leq \frac{1}{15}$$

$$\theta_2 = \text{taper of the outside of the sleeve}$$

$$\mu_1 = \text{coefficient of friction for fitting of boss assembly on shaft}$$

$$= 0,13 \text{ for oil injection method of fitting}$$

$$\mu_2 = \text{coefficient of friction for fitting sleeve into the boss}$$

$$\nu_1 = \text{Poisson's ratio for screwshaft material}$$

$$\nu_2 = \text{Poisson's ratio for sleeve material}$$

$$\nu_3 = \text{Poisson's ratio for propeller material}$$

Consistent sets of units are to be used in all formulae.

3.2.2 Where it is proposed to fit a keyless propeller by the oil shrink method, the pull-up,  $\delta$  on the screwshaft is to be not less than:

$$\delta_T = \frac{d_1}{\theta_1} (\rho_1 B_3 + (\alpha_3 - \alpha_1)(35 - T_1)) \text{ mm}$$

or, where Ice Class notation is required, the greater of  $\delta_T$  or  $\delta_O$ , where

$$\delta_O = \frac{d_1}{\theta_1} (\rho_{10} B_3 - (\alpha_3 - \alpha_1) T_1) \text{ mm}$$

The yield stress or 0,2 per cent proof stress,  $\sigma_o$  of the propeller material is to be not less than:

$$\sigma_o = \frac{1,4}{B_3} \left( \frac{\theta_1 \delta_p}{d_1} + T_1 (\alpha_3 - \alpha_1) \right) \frac{\sqrt{3k_3^4 + 1}}{k_3^2 - 1} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

$$\delta_p = \text{proposed pull-up at the fitting temperature}$$

The start point load,  $W$ , to determine the actual pull-up is to be not less than:

$$W = A_1 \left( 0,002 + \frac{\theta_1}{20} \right) \left( \rho_1 + \frac{18}{B_3} (\alpha_3 - \alpha_1) \right) \text{ N (kgf)}$$

3.2.3 Where a cast iron sleeve is first fitted to the bore of the propeller boss by an interference fit, the push-up load of the sleeve into the boss,  $W_2$ , is to be not less than:

$$W_{2T} = \frac{A_2}{B_2} \left( \mu_2 + \frac{\theta_2}{2} \right) (B_2 \rho_2 - h \rho_1 + (\alpha_3 - \alpha_2)(35 - T_2)) \text{ N (kgf)}$$

or, where Ice Class notation is required, the greater of  $W_{2T}$  or  $W_{20}$  where

$$W_{20} = \frac{A_2}{B_2} \left( \mu_2 + \frac{\theta_2}{2} \right) (B_2 \rho_{20} - h \rho_{10} - (\alpha_3 - \alpha_2) T_2) \text{ N (kgf)}$$

The pull-up of the sleeve in the boss at the fitting temperature is to be in accordance with the following formula:

$$\delta_2 = \frac{W_2 B_2 d_2}{A_2 \left( \mu_2 + \frac{\theta_2}{2} \right) \theta_2} \text{ mm}$$

The push-up load,  $W_1$ , of the combined boss and sleeve on a steel screwshaft is to be not less than:

$$W_{1T} = A_1 \left( \mu_1 + \frac{\theta_1}{2} \right) \left( \rho_1 + \frac{h k_1^2}{Y} (\alpha_3 - \alpha_2)(35 - T_1) \right) \text{ N (kgf)}$$

or where Ice Class notation is required, the greater of  $W_{1T}$  or  $W_{10}$  where

$$W_{10} = A_1 \left( \mu_1 + \frac{\theta_1}{2} \right) \left( \rho_{10} - \frac{h k_1^2}{Y} (\alpha_3 - \alpha_2) T_1 \right) \text{ N (kgf)}$$

The push-up distance of the combined boss and sleeve on a steel screwshaft is to be in accordance with the following formula:

$$\delta_1 = \frac{W_1 d_1 Y}{A_1 B_2 \theta_1 \left( \mu_1 + \frac{\theta_1}{2} \right)} \text{ mm}$$

# Propellers

# Part 5, Chapter 7

Sections 3 & 4

3.2.4 Where a cast iron sleeve is fitted into the boss by means of Araldite, the conditions are to satisfy those of 3.2.3 except that the value of  $W_2$  is to be taken as equivalent to:

$$W_2 = A_2 \left( 0,25 + \frac{\theta_2}{2} \right) \left( p_A + \frac{(\alpha_3 - \alpha_2)(18 - T_2)}{B_2} \right) \text{ N (kgf)}$$

where

$$\begin{aligned} p_A &= 3,5 \text{ N/mm}^2 \\ p_A &= 0,35 \text{ kgf/mm}^2 \end{aligned}$$

3.2.5 For the triple element keyless propeller, the yield stress or 0,2 per cent proof stress of the propeller material,  $\sigma_o$  is to be not less than:

$$\sigma_o = 1,4 p_3 \sqrt{\frac{3k_2^4 + 1}{k_2^2 - 1}} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

$$p_3 = \frac{W_1 h}{A_1 B_2 \left( \mu_1 + \frac{\theta_1}{2} \right)} + \frac{W_2}{A_2 \left( \mu_2 + \frac{\theta_2}{2} \right)} + \frac{\alpha_3 - \alpha_2}{B_2} \left( T_2 + \frac{h^2 k_1^2}{Y} T_1 \right)$$

3.2.6 Where the sleeve is manufactured of material having an elongation in excess of five per cent, the yield point or 0,2 per cent proof stress of the sleeve material,  $\sigma_o$  is to be not less than:

$$\sigma_o = \frac{1,6}{k_1^2 - 1} \sqrt{3k_1^4 (p_3 - p_5)^2 + (p_3 k_1^2 - p_5)^2} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

or

$$\sigma_o = \frac{1,6}{k_1^2 - 1} \sqrt{3k_1^4 (p_4 - p_6)^2 + (p_4 k_1^2 - p_6)^2} \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

where

$$p_4 = p_3 - \frac{35B_1}{Y} (\alpha_3 - \alpha_2)$$

$$p_5 = \frac{W_1}{A_1 \left( \mu_1 + \frac{\theta_1}{2} \right)} + \frac{h k_1^2}{Y} (\alpha_3 - \alpha_2) T_1$$

$$p_6 = p_5 - \frac{35h k_1^2}{Y} (\alpha_3 - \alpha_2)$$

3.2.7 Where the sleeve is manufactured of material having an elongation not more than five per cent, the minimum specified ultimate tensile strength  $\sigma_u$ , based on the ruling section, is to be not less than:

$$\sigma_u = \frac{2,4}{k_1^2 - 1} \left( p_5 \left( \frac{5k_1^2 + 3}{4} \right) - 2p_3 k_1^2 \right) \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

or

$$\sigma_u = \frac{2,4}{k_1^2 - 1} \left( p_6 \left( \frac{5k_1^2 + 3}{4} \right) - 2p_4 k_1^2 \right) \text{ N/mm}^2 \text{ (kgf/mm}^2\text{)}$$

3.2.8 Where it is proposed to use a sleeve manufactured from a material other than cast iron, full details are to be submitted for consideration.

## Section 4 Fitting of propellers

### 4.1 Propeller boss

4.1.1 The propeller boss is to be a good fit on the screw-shaft cone. The forward edge of the bore of the propeller boss is to be rounded to about a 6 mm radius. In the case of keyed propellers, the length of the forward fitting surface is to be about one diameter and where the fitting is by means of a hydraulic nut, the requirements of 4.2 and 4.3, where appropriate, are applicable.

### 4.2 Shop tests of keyless propellers

4.2.1 The bedding of the propeller, or the sleeve where applicable with the shaft, is to be demonstrated in the shop to the satisfaction of the Surveyors. Sufficient time is to be allowed for the temperature of the components to equalize before bedding. Alternative means for demonstrating the bedding of the propeller will be considered.

4.2.2 Means are to be provided to indicate the relative axial position of the propeller boss on the shaft taper.

### 4.3 Final fitting of keyless propellers

4.3.1 After verifying that the propeller and shaft are at the same temperature and the mating surfaces are clean and free from oil or grease, the propeller is to be fitted on the shaft to the satisfaction of the Surveyors. The propeller nut is to be securely locked to the shaft.

4.3.2 Permanent reference marks are to be made on the propeller boss, nut and shaft to indicate angular and axial positioning of the propeller. Care is to be taken in marking the inboard end of the shaft taper to minimize stress raising effects.

4.3.3 The outside of the propeller boss is to be hard stamped with the following details:

- For the oil injection method of fitting, the start point load and the axial pull-up at 0°C and 35°C.
- For the dry fitting method, the push-up load at 0°C and 35°C.

4.3.4 A copy of the fitting curve relative to temperature and means for determining any subsequent movement are to be placed on board.



# Shaft Vibration and Alignment

## Part 5, Chapter 8

Sections 1 & 2

### Section

- 1 **General**
- 2 **Torsional vibration**
- 3 **Axial vibration**
- 4 **Lateral vibration**
- 5 **Shaft alignment**

### ■ Scope

The requirements of this Chapter are applicable to the following systems:

- (a) Main propulsion systems formed by oil engines, turbines or electric motors, directly driven or geared to the shafting.
- (b) Machinery driven at constant speed by oil engines, developing 110 kW and over, for essential auxiliary services including generator sets which are the source of power for main electric propulsion motors.

Unless otherwise advised, it is the responsibility of the Shipbuilder as main contractor to ensure, in co-operation with the Enginebuilders, that the information required by this Chapter is prepared and submitted.

### ■ Section 1 General

#### 1.1 Basic requirements

1.1.1 The systems are to be free from excessive torsional, axial, lateral and linear vibration, and are to be aligned in accordance with accepted tolerances and taking into account the requirements of 5.5.

1.1.2 System designs are to take account of the potential effects of engine and component malfunction and variability in characteristic values such as stiffness and damping of flexible couplings and dampers or engine misfire conditions.

1.1.3 Where torques, stresses or amplitudes are found to exceed the limits for continuous operation, restrictions in speed and/or power will be imposed.

1.1.4 Where significant changes are subsequently made to a dynamic system which has been approved, (e.g. by changing the original design parameters of the prime movers and/or propulsion shafting system or by fitting a propeller or flexible coupling of different design from the previous), revised calculations may require to be submitted for consideration. Details of all such changes are to be submitted.

#### 1.2 Resilient mountings

1.2.1 For resilient mountings, see Ch 1,4.3.

### ■ Section 2 Torsional vibration

#### 2.1 General

2.1.1 In addition to the shafting complying with the requirements of Chapters 1 to 7 and 20 (where applicable), approval is also dependent on the torsional vibration characteristics of the complete shafting system(s) being found satisfactory.

2.1.2 Further to the Scope of this Chapter, the requirements of this Section are not applicable to ships that are not:

- (a) required to comply with the *International Convention for the Safety at Sea, 1974*, as amended, (SOLAS); or
- (b) where a main engine does not have a power output exceeding 500 kW.

#### 2.2 Particulars to be submitted

2.2.1 Torsional vibration calculations, showing the mass elastic values, associated natural frequencies and an analysis of the vibratory torques and stresses for the full dynamic system.

2.2.2 Particulars of the division of power and utilisation, throughout the speed range, for turbines, multi-engine or other combined power installations, and those with power take-off systems. For multi-engined installations, special considerations associated with the possible variations in the mode of operation and phasing of engines.

2.2.3 Details of operating conditions encountered in service for prolonged periods, e.g. idling speed, range of trawling revolutions per minute, combinator characteristics for installations equipped with controllable pitch propellers.

2.2.4 Details, obtained from the manufacturers, of the principal characteristics of machinery components such as dampers and couplings, confirming their capability to withstand the effects of vibratory loading including, where appropriate, heat dissipation. Evidence that the data which is used to represent the characteristics of components, which has been quoted from other sources, is supported by a programme of physical measurement and control.

2.2.5 Where installations include electric motors, generators or non-integral pumps, drawings showing the principal dimensions of the shaft, together with manufacturer's estimates of mass moment of inertia for the rotating parts.

2.2.6 Details of vibration or performance monitoring proposals where required.

# Shaft Vibration and Alignment

# Part 5, Chapter 8

Section 2

## 2.3 Scope of calculations

2.3.1 Calculations are to be carried out, by recognized techniques, for the full dynamic system formed by the oil engines, turbines, motors, generators, flexible couplings, gearing, shafting and propeller, where applicable, including all branches.

2.3.2 Calculations are to give due consideration to the potential deviation in values used to represent component characteristics due to manufacturing/service variability.

2.3.3 The calculations carried out on oil engine systems are to be based on the Enginebuilders' harmonic torque data (on request, Lloyd's Register (hereinafter referred to as 'LR') can provide a table of generalized harmonic torque components for use where appropriate). The calculations are to take account of the effects of engine malfunctions commonly experienced in service, such as a cylinder not firing (i.e. no injection but with compression) giving rise to the highest torsional vibration stresses in the shafting. Calculations are also to take account of a degree of imbalance between cylinders, which is characteristic of the normal operation of an engine under service conditions.

2.3.4 Whilst limits for torsional vibration stress in crankshafts are no longer stated explicitly, calculations are to include estimates of crankshaft stress at all designated operating/service speeds, as well as at any major critical speed.

2.3.5 Calculations are to take into account the possible effects of excitation from propeller rotation. Where the system shows some sensitivity to this phenomenon, propeller excitation data for the installation should be used as a basis for calculation, and submitted.

2.3.6 Where the torsional stiffness of flexible couplings varies with torque, frequency or speed, calculations should be representative of the appropriate range of effective dynamic stiffness.

## 2.4 Symbols and definitions

2.4.1 The symbols used in this Section are defined as follows:

- $d$  = minimum diameter of shaft considered, in mm
- $d_i$  = diameter of internal bore, in mm
- $k$  = the factor used in determining minimum shaft diameter, defined in Ch 6,3.1.1 and 3.5.1
- $r$  = ratio  $N/N_s$  or  $N_c/N_s$  whichever is applicable
- $C_d$  = a size factor defined as  $0,35 + 0,93d^{-0,2}$
- $C_k$  = a factor for different shaft design features, see Table 8.2.1
- $N$  = engine speed, in rev/min
- $N_c$  = critical speed, in rev/min
- $N_s$  = maximum continuous engine speed, in rev/min, or, in the case of constant speed generating sets, the full load speed, in rev/min
- $Q_s$  = rated full load mean torque
- $\sigma_u$  = specified minimum tensile strength of the shaft material, in N/mm<sup>2</sup>

- $\tau_c$  = permissible stress due to torsional vibrations for continuous operation, in N/mm<sup>2</sup>
- $\tau_t$  = permissible stress due to torsional vibrations for transient operation, in N/mm<sup>2</sup>
- $e$  = slot width, in mm
- $l$  = slot length, in mm.

**Table 8.2.1  $C_k$  factors**

<b>Intermediate shafts with</b>	
Integral coupling flange and straight sections	1,0
Shrink fit coupling	1,0
Keyway, tapered connection	0,60
Keyway, cylindrical connection	0,45
Radial hole	0,50
Longitudinal slot	0,30 (see 2.4.4)
<b>Thrust shafts external to engines</b>	
On both sides of thrust collar	0,85
In way of axial bearing where a roller bearing is used as a thrust bearing	0,85
<b>Propeller shafts</b>	
Flange mounted or keyless taper fitted propellers	0,55
Key fitted propellers	0,55
Between forward end of aft most bearing and forward stern tube seal	0,80
<b>NOTE</b>	
The determination of $C_k$ – factors for shafts other than shown in this Table will be specially considered by LR.	

2.4.2 Alternating torsional vibration stresses are to be based on half-range amplitudes of stress resulting from the alternating torque (which is superimposed on the mean torque) representing the synthesis of all harmonic orders present.

2.4.3 All vibration stress limits relate to the synthesis or measurement of total nominal torsional stress and are to be based on the plain section of the shafting neglecting stress raisers.

2.4.4 For a longitudinal slot  $C_k = 0,3$  is applicable within the dimension limitations given in Pt 5 Ch 6,3.1.6. If the slot dimensions are outside these limitations, or if the use of another  $C_k$  is desired, the actual stress concentration factor ( $scf$ ) is to be documented or determined from 2.4.5, in which case:

$$C_k = \frac{1,45}{scf}$$

Note that the  $scf$  is defined as the ratio between the maximum local principal stress and  $\sqrt{3}$  times the nominal torsional stress (determined for the bored shaft without slots).

2.4.5 **Stress concentration factor of slots.** The stress concentration factor ( $scf$ ) at the ends of slots can be determined by means of the following empirical formulae:

$$scf = \alpha_{t(hole)} + 0,57 \frac{\frac{(l - e)}{d}}{\sqrt{\left(1 - \frac{d_i}{d}\right) \frac{e}{d}}}$$

# Shaft Vibration and Alignment

# Part 5, Chapter 8

Section 2

This formula applies to:

- Slots at 120 or 180 or 360 degrees apart.
- Slots with semicircular ends. A multi-radii slot end can reduce the local stresses, but this is not included in this empirical formula.
- Slots with no edge rounding (except chamfering), as any edge rounding increases the scf slightly.

$\alpha_{t(hole)}$  represents the stress concentration of radial holes and can be determined as :

$$\alpha_{t(hole)} = 2,3 - 3 \frac{e}{d} + 15 \left( \frac{e}{d} \right)^2 + 10 \left( \frac{e}{d} \right)^2 \left( \frac{d_i}{d} \right)^2$$

where  $e$  = hole diameter, in mm  
or simplified to  $\alpha_{t(hole)} = 2,3$ .

## 2.5 Limiting stress in propulsion shafting

2.5.1 The following stress limits apply to intermediate shafts, thrust shafts and to screwshafts fully protected from seawater. For screwshafts, the limits apply to the minimum sections of the portions of the screwshaft as defined in Ch 6,3.5.

2.5.2 In the case of unprotected screwshafts, special consideration will be given.

2.5.3 In no part of the propulsion shafting system may the alternating torsional vibration stresses exceed the values of  $\tau_c$  for continuous operation, and  $\tau_t$  for transient running, given by the following formulae:

$$\tau_c = \frac{\sigma_u + 160}{18} C_k C_d (3 - 2r^2) \text{ for } r < 0,9 \text{ N/mm}^2$$

$$\tau_c = \frac{\sigma_u + 160}{18} C_k C_d 1,38 \text{ for } 0,9 \leq r \leq 1,05 \text{ N/mm}^2$$

$$\tau_t = \pm 1,7 \tau_c \frac{1}{\sqrt{C_k}} \text{ for } r \leq 0,8 \text{ N/mm}^2$$

2.5.4 In general, the tensile strength of the steel used is to comply with the requirements of Ch 6,2. For the calculation of the permissible limits of stresses due to torsional vibration,  $\sigma_u$  is not to be taken as more than 800 N/mm<sup>2</sup> in the case of alloy steel intermediate shafts, or 600 N/mm<sup>2</sup> in the case of carbon and carbon-manganese steel intermediate thrust and propeller shafts.

2.5.5 Where the scantlings of coupling bolts and straight shafting differ from the minimum required by the Rules, special consideration will be given.

## 2.6 Generator sets

2.6.1 Natural frequencies of the complete set are to be sufficiently removed from the firing impulse frequency at the full load speed, particularly where flexible couplings are interposed between the engine and generator.

2.6.2 Within the speed limits of  $0,95N_s$  and  $1,05N_s$  the vibration stresses in the transmission shafting are not to exceed the values given by the following formula:

$$\tau_c = \pm (21 - 0,014d) \text{ N/mm}^2.$$

2.6.3 Vibration stresses in the transmission shafting due to critical speeds which have to be passed through in starting and stopping, are not to exceed the values given by the following formula:

$$\tau_t = 5,5 \tau_c.$$

2.6.4 The amplitudes of the total vibratory inertia torques imposed on the generator rotors are to be limited to  $\pm 2,0Q_s$  in general, or to  $\pm 2,5Q_s$  for close-coupled revolving field alternating current generators, over the speed range from  $0,95N_s$  to  $1,05N_s$ . Below  $0,95N_s$  the amplitudes are to be limited to  $\pm 6,0Q_s$ . Where two or more generators are driven from one engine, each generator is to be considered separately in relation to its own rated torque.

2.6.5 The rotor shaft and structure are to be designed to withstand these magnitudes of vibratory torque. Where it can be shown that they are capable of withstanding a higher vibratory torque, special consideration will be given.

2.6.6 In addition to withstanding the vibratory conditions over the speed range from  $0,95N_s$  to  $1,05N_s$ , flexible couplings, if fitted, are to be capable of withstanding the vibratory torques and twists arising from transient criticals and short-circuit currents.

2.6.7 In the case of alternating current generators, resultant vibratory amplitudes at the rotor are not to exceed  $\pm 3,5$  electrical degrees under both full load working conditions and the malfunction condition mentioned in 2.3.3.

## 2.7 Other auxiliary machinery systems

2.7.1 The relevant requirements of 2.6.1, 2.6.2 and 2.6.3 are also applicable to other machinery installations such as pumps or compressors with the speed limits being taken as  $0,95N_s$  to  $1,10N_s$ .

## 2.8 Other machinery components

2.8.1 **Torsional vibration dampers.** The use of dampers or detuners to limit vibratory stress due to resonances which occur within the range between  $0,85N_s$  and  $1,05N_s$  are to be considered. If fitted, these should be of a type which makes adequate provision for dissipation of heat. Where necessary, performance monitoring may be required.

### 2.8.2 Flexible couplings:

- Flexible couplings included in an installation are to be capable of transmitting the mean and vibratory loads without exceeding the makers' recommended limits for angular amplitude or heat dissipation.
- Where calculations indicate that the limits recommended by the manufacturer may be exceeded under misfiring conditions, a suitable means is to be provided for detecting and indicating misfiring. Under these circumstances power and/or speed restrictions may be required. Where machinery is non-essential, disconnection of the branch containing the coupling would be an acceptable action in the event of misfiring.

# Shaft Vibration and Alignment

# Part 5, Chapter 8

Section 2

## 2.8.3 Gearing:

- (a) The torsional vibration characteristics are to comply with the requirements of 2.3. The sum of the mean and of the vibratory torque should not exceed four-thirds of the full transmission torque, at MCR, throughout the speed range. In cases where the proposed transmission torque loading on the gear teeth is less than the maximum allowable, special consideration will be given to the acceptance of additional vibratory loading on the gears.
- (b) Where calculations indicate the possibility of torque reversal, the operating speed range is to be determined on the basis of observations during sea trials.

## 2.9 Measurements

2.9.1 Where calculations indicate that the limits for torsional vibration within the range of working speeds are exceeded, measurements, using an appropriate technique, may be taken from the machinery installation for the purpose of approval of torsional vibration characteristics, or determining the need for restricted speed ranges, and the confirmation of their limits.

2.9.2 Where differences between calculated and measured levels of stress, torque or angular amplitude arise, the stress limits are to be applied to the stresses measured on the completed installation.

2.9.3 The method of measurement is to be appropriate to the machinery components and the parameters which are of concern. Where shaft stresses have been estimated from angular amplitude measurements, and are found to be close to limiting stresses as defined in 2.5, strain gauge techniques may be required. When measurements are required, detailed proposals are to be submitted.

## 2.10 Vibration monitoring

2.10.1 Where calculations and/or measurements have indicated the possibility of excessive vibratory stresses, torques or angular amplitudes in the event of a malfunction, vibration or performance monitoring, directly or indirectly, may be required.

## 2.11 Restricted speed and/or power ranges

2.11.1 Restricted speed and/or power ranges will be imposed to cover all speeds where the stresses exceed the limiting values,  $\tau_c$ , for continuous running, including one-cylinder misfiring conditions if intended to be continuously operated under such conditions. For controllable pitch propellers with the possibility of individual pitch and speed control, both full and zero pitch conditions are to be considered. Similar restrictions will be imposed, or other protective measures required to be taken, where vibratory torques or amplitudes are considered to be excessive for particular machinery items. At each end of the restricted speed range the engine is to be stable in operation.

2.11.2 The restricted speed range is to take account of the tachometer speed tolerances at the barred speeds.

2.11.3 Critical responses which give rise to speed restrictions are to be arranged sufficiently removed from the maximum revolutions per minute to ensure that, in general, at  $r = 0,8$  the stress due to the upper flank does not exceed  $\tau_c$ .

2.11.4 Provided that the stress amplitudes due to a torsional critical response at the borders of the barred speed range are less than  $\tau_c$  under normal and stable operating conditions the speed restriction derived from the following formula may be applied:

$$\frac{16}{18-r} N_c \text{ to } \frac{18-r}{16} N_c \text{ inclusive.}$$

2.11.5 Where calculated vibration stresses due to criticals below  $0,8N_s$  marginally exceed  $\tau_c$  or where the critical speeds are sharply tuned, the range of revolutions restricted for continuous operation may be reduced.

2.11.6 In cases where the resonance curve of a critical speed has been derived from measurements, the range of revolutions to be avoided for continuous running may be taken as that over which the measured vibration stresses are in excess of  $\tau_c$ , having regard to the tachometer accuracy.

2.11.7 Where restricted speed ranges under normal operating conditions are imposed, notice boards are to be fitted at the control stations stating that the engine is not to be run continuously between the speed limits obtained as above, and the engine tachometers are to be marked accordingly.

2.11.8 Where vibration stresses approach the limiting value,  $\tau_t$ , the range of revolutions restricted for continuous operation may be extended. The notice boards are to indicate that this range must be passed through rapidly.

2.11.9 For excessive vibratory torque, stress or amplitude in other components, based on 2.8.1 to 2.8.3, the limits of any speed/power restriction are to be such as to maintain acceptable levels during continuous operation.

2.11.10 Where the restrictions are imposed for the contingency of an engine malfunction or component failure, the limits are to be entered in the machinery Operating Manual.

2.11.11 Restricted speed ranges in one-cylinder misfiring conditions on ships with single engine propulsion are to enable safe navigation whereby sufficient propulsion power is available to maintain control of the ship.

2.11.12 There are to be no restricted speed ranges imposed above a speed ratio of  $r = 0,8$  under normal operating conditions.



# Shaft Vibration and Alignment

## Part 5, Chapter 8

Sections 2 & 3

### 2.12 Tachometer accuracy

2.12.1 Where restricted speed ranges are imposed as a condition of approval, the tachometer accuracy is to be checked against the counter readings, or by equivalent means, in the presence of the Surveyors to verify that it reads correctly within  $\pm 2$  per cent in way of the restricted range of revolutions.

### 2.13 Governor control

2.13.1 Where there is a significant critical response above and close to the maximum service speed, consideration is to be given to the effect of temporary overspeed.

## Section 3 Axial vibration

### 3.1 General

3.1.1 For all main propulsion shafting systems, the Shipbuilders are to ensure that axial vibration amplitudes are satisfactory throughout the speed range. Where natural frequency calculations indicate significant axial vibration responses, sufficiently wide restricted speed ranges will be imposed. Alternatively, measurements may be used to determine the speed ranges at which amplitudes are excessive for continuous running.

### 3.2 Particulars to be submitted

3.2.1 The results of calculations, together with recommendations for any speed restrictions found necessary.

3.2.2 Enginebuilder's recommendation for axial vibration amplitude limits at the non-driving end of the crankshaft or at the thrust collar.

3.2.3 Estimate of flexibility of the thrust bearing and its supporting structure.

3.2.4 The requirement for calculations to be submitted may be waived upon request provided evidence of satisfactory service experience of similar dynamic installations is submitted.

### 3.3 Calculations

3.3.1 Calculations of axial vibration natural frequency are to be carried out using appropriate techniques, taking into account the effects of flexibility of the thrust bearing, for shaft systems where the propeller is:

- Driven directly by a reciprocating internal combustion engine.
- Driven via gears, or directly by an electric motor, and where the total length of shaft between propeller and thrust bearing is in excess of 60 times the intermediate shaft diameter.

3.3.2 Where an axial vibration damper is fitted, the calculations are to consider the effect of a malfunction of the damper.

3.3.3 For those systems as defined in 3.3.1(b) the propeller speed at which the critical frequency occurs may be estimated using the following formula:

$$\frac{0,98}{N} \left( \frac{ab}{a+b} \right)^{1/2} \text{ rev/min}$$

where

$$a = \frac{E}{G I^2} (66,2 + 97,5A - 8,88A^2) \text{ (c/min)}^2$$

$$b = 91,2 \frac{k}{M_e} \text{ (c/min)}^2$$

$d$  = internal diameter of shaft, in mm

$k$  = estimated stiffness at thrust block bearing, in N/m

$l$  = length of shaft line between propeller and thrust bearing, in mm

$m$  = mass of shaft line considered, in kg  
 $= 0,785 (D^2 - d^2) G l$

$$A = \frac{m}{M}$$

$D$  = outside diameter of shaft, taken as an average over length  $l$ , in mm

$E$  = modulus of elasticity of shaft material, in N/mm<sup>2</sup>

$G$  = density of shaft material, in kg/mm<sup>3</sup>

$M$  = dry mass of propeller, in kg

$M_e = M (A + 2)$

$N$  = number of propeller blades

Where the results of this method indicate the possibility of an axial vibration resonance in the vicinity of the maximum service speed, calculations using a more accurate method will be required.

### 3.4 Measurements

3.4.1 Where calculations indicate the possibility of excessive axial vibration amplitudes within the range of working speeds under normal or malfunction conditions, measurements are required to be taken from the shafting system for the purpose of determining the need for restricted speed ranges.

### 3.5 Restricted speed ranges

3.5.1 The limits of any speed restriction are to be such as to maintain axial amplitudes within recommended levels during continuous operation.

3.5.2 Limits of a speed restriction, where required, may be determined by calculation or on the basis of measurement.

3.5.3 Where a speed restriction is imposed for the contingency of a damper malfunction, the speed limits are to be entered in the machinery Operating Manual and regular monitoring of the axial vibration amplitude is required. Details of proposals for monitoring are to be submitted.

# Shaft Vibration and Alignment

# Part 5, Chapter 8

Sections 3, 4 & 5

## 3.6 Vibration monitoring

3.6.1 Where a vibration monitoring system is to be specified, details of proposals are to be submitted.

## Section 4 Lateral vibration

### 4.1 General

4.1.1 For all main propulsion shafting systems, the Shipbuilders are to ensure that lateral vibration characteristics are satisfactory throughout the speed range.

### 4.2 Particulars to be submitted

4.2.1 Calculations of the lateral vibration characteristics of shafting systems having supports outboard of the hull or incorporating cardan shafts are to be submitted.

### 4.3 Calculations

4.3.1 The calculations in 4.2.1, taking account of bearing, oil-film (where applicable) and structural dynamic stiffnesses, are to investigate the excitation frequencies giving rise to all critical speeds which may result in significant amplitudes within the speed range, and are to indicate relative deflections and bending moments throughout the shafting system.

4.3.2 Requirements for calculations may be waived upon request provided evidence of satisfactory service experience of similar dynamic installations is submitted.

### 4.4 Measurements

4.4.1 Where calculations indicate the possibility of significant lateral vibration responses within the range of  $\pm 20$  per cent of the M.C.R. speed, measurements using an appropriate recognized technique may be required to be taken from the shafting system for the purpose of determining the need for restricted speed ranges.

4.4.2 The method of measurement is to be appropriate to the machinery arrangement and the modes of vibration which are of concern. When measurements are required, detailed proposals are to be submitted in advance.

## Section 5 Shaft alignment

### 5.1 General

5.1.1 The Builder is to carry out shaft alignment calculations for all installations and to prepare alignment procedures detailing the proposed alignment method and the alignment checks to demonstrate compliance with requirements of this section.

### 5.2 Particulars to be submitted for approval – shaft alignment calculations

5.2.1 Shaft alignment calculations are to be submitted to LR for approval for the following shafting systems where the screwshaft has a diameter of 250 mm or greater in way of the aftermost sterntube bearing:

- (a) All geared installations.
- (b) Installations with one shaftline bearing, or less, inboard of the sterntube bearing/seal.
- (c) Where prime movers or shaftline bearings are installed on resilient mountings.

5.2.2 The shaft alignment calculations are to take into account the:

- (a) thermal displacements of the bearings between cold static and hot dynamic machinery conditions;
- (b) buoyancy effect of the propeller immersion due to the ship's operating draughts;
- (c) effect of predicted hull deformations over the range of the ship's operating draughts, where known;
- (d) effect of filling the aft peak ballast tank upon the bearing loads, where known;
- (e) gear forces, where appropriate, due to prime-mover engagement on multiple-input single-output installations;
- (f) propeller offset thrust effects;
- (g) maximum allowed bearing wear, for water or grease-lubricated sterntube bearings, and its effect on the bearing loads.

5.2.3 The shaft alignment calculations are to state the:

- (a) expected bearing loads at light and normal ballast, fully loaded and any other draughts deemed to be part of the ship's operating profile, for the machinery in cold and hot, static and dynamic conditions;
- (b) bearing influence coefficients and the deflection, slope, bending moment and shear force along the shaftline;
- (c) details of propeller offset thrust;
- (d) details of proposed slope-bore of the aftermost sterntube bearing, where applicable;
- (e) manufacturer's specified limits for bending moment and shear force at the shaft couplings of the gearbox/prime movers;
- (f) estimated bearing wear rates for water or grease-lubricated sterntube bearings;
- (g) expected hull deformation effects and their origin, viz. whether finite element calculations or measured results from sister or similar ships have been used;
- (h) anticipated thermal rise of prime movers and gearing units between cold static and hot running conditions; and
- (j) manufacturer's allowable bearing loads.

# Shaft Vibration and Alignment

## Part 5, Chapter 8

Section 5

### 5.3 Particulars to be submitted for review – shaft alignment procedure

5.3.1 A shaft alignment procedure is to be submitted for all main propulsion installations detailing, as a minimum, the:

- (a) expected bearing loads at light and normal ballast, fully loaded and any other draughts deemed to be part of the ship's operating profile, for the machinery in cold and hot, static and dynamic conditions;
- (b) maximum permissible loads for the proposed bearing designs;
- (c) design bearing offsets from the straight line;
- (d) design gaps and sags;
- (e) location and loads for the temporary shaft supports;
- (f) expected relative slope of the shaft and the bearing in the aftermost sterntube bearing;
- (g) details of slope-bore of the aftermost sterntube bearing, where applied;
- (h) proposed bearing load measurement technique and its estimated accuracy;
- (j) jack correction factors for each bearing where the bearing load is measured using a specified jacking technique;
- (k) proposed shaft alignment acceptance criteria, including the tolerances; and
- (l) flexible coupling alignment criteria.

### 5.4 Design and installation criteria

5.4.1 For main propulsion installations, the shafting is to be aligned to give, in all conditions of ship loading and machinery operation, bearing load distribution satisfying the requirements of 5.4.2.

5.4.2 Design and installation of the shafting is to satisfy the following criteria:

- (a) The Builder is to position the bearings and construct the bearing seatings to minimize the effects of hull deflections under any of the ship's operating conditions with the aim of optimising the bearing load distribution.
- (b) Relative slope between the propeller shaft and the aftermost sterntube bearing is, in general, not to exceed  $3 \times 10^{-4}$  rad in the static condition.
- (c) Sterntube bearing loads are to satisfy the requirements of Ch 6,3.12.
- (d) Evidence is to be provided to LR demonstrating that bearings of synthetic material have been verified as being within the tolerance stated by the bearing manufacturer for diameter, ovality, and straightness after installation.
- (e) Bearings of synthetic material are to be verified as being within tolerance for ovality and straightness, circumferentially and longitudinally, after installation.
- (f) The sterntube forward bearing static load is to be sufficient to prevent unloading in all static and dynamic operating conditions, including the transient conditions experienced during manoeuvring turns and during operation in heavy weather.
- (g) Intermediate shaft bearings' loads are not to exceed 80 per cent of the bearing manufacturer's allowable maximum load, for plain journal bearings, based on the bearing projected area.

- (h) Equipment manufacturer's bearing loads are to be within the manufacturer's specified limits, i.e. prime movers, gearing.
- (j) Resulting shear forces and bending moments are to meet the equipment manufacturer's specified coupling conditions.
- (k) The manufacturer's radial, axial and angular alignment limits for the flexible couplings are to be maintained.

### 5.5 Measurements

5.5.1 The system bearing load measurements are to be carried out to verify that the design loads have been achieved. In general the measurements will be carried out by the jack-up measurement technique using calibrated equipment.

5.5.2 For the first vessel of a new design an agreed programme of static shaft alignment measurements is to be carried out in order to verify that the shafting has been installed in accordance with the design assumptions and to verify the design assumptions in respect of the hull deflections and the effects of machinery temperature changes. The programme is to include static bearing load measurements in a number of selected conditions. Depending on the ship type and the operational loading conditions that are achievable prior to and during sea trials these should include, where practicable, combinations of light ballast cold, full ballast cold, full ballast hot and full draught hot with aft peak tank empty and full.

5.5.3 For vessels of an existing design or similar to an existing design where evidence of satisfactory service experience is submitted for consideration and for subsequent ships in a series a reduced set of measurements may be accepted. In such cases the minimum set of measurements is to be sufficient to verify that the shafting has been installed in accordance with the design assumptions and are to include at least one cold and one hot representative condition.

5.5.4 Where calculations indicate that the system is sensitive to changes in alignment under different service conditions, the shaft alignment is to be verified by measurements during sea trials using an approved strain gauge technique.

### 5.6 Flexible couplings

5.6.1 Where the shafting system incorporates flexible couplings, the effects of such couplings on the various modes of vibration are to be considered, see Sections 2, 3 and 4.



## Section

- 1 **General**
- 2 **Ice Classes 1AS FS, 1A FS, 1B FS and 1C FS**
- 3 **Ice Class 1D and 1E**
- 4 **Ice Classes 1AS FS(+), 1A FS(+), 1B FS(+) and 1C FS(+)**

## ■ Section 1 General

### 1.1 Class notations

1.1.1 For ships where ice class notation **Ice Class 1AS FS**, **Ice Class 1A FS**, **Ice Class 1B FS** or **Ice Class 1C FS** is requested, the requirements of this Chapter, as applicable, in addition to the Finnish Swedish Ice Class Rules in force at the time of contract, are to be complied with. Section 2 of this Chapter replaces Section 6 of the Finnish Swedish Ice Class Rules.

1.1.2 Ships strengthened in accordance with the requirements of **Ice Class 1D** are not intended for operation in the northern part of the Baltic in the winter season. For ships where **Ice Class 1D** is requested, the requirements of Section 3 are to be complied with.

1.1.3 Offshore supply ships strengthened in accordance with the requirements of Ice Class **1E** are only intended for navigation in very light first-year ice conditions. The requirements of Section 3 are to be complied with.

1.1.4 For ships where the ice class notation **Ice Class 1AS FS(+)**, **Ice Class 1A FS(+)**, **Ice Class 1B FS(+)** or **Ice Class 1C FS(+)** is requested, the requirements of Sections 2 and 4 of this Chapter, in addition to the Finnish Swedish Ice Class Rules, in force at the time of contract, are to be complied with. The Finnish Swedish Ice Class Rules may be obtained from the following website:

[www.fma.fi](http://www.fma.fi)

### 1.2 Materials for shafting

1.2.1 All components of the main propulsion system are to be of steel or other approved ductile material.

1.2.2 For screwshafts in ships intended for the notation **Ice Class 1AS FS** or **Ice Class 1A FS** and where the connection between the propeller and the screwshaft is by means of a key, Charpy impact tests are to be made in accordance with the requirements of Ch 5,3.4.12 of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

### 1.3 Materials for propellers

1.3.1 Propellers and propeller blades are to be of cast steel or copper alloys and are to be manufactured, tested and certified in accordance with Ch 4,1, Ch 4,5 and Ch 9,1 of the Rules for Materials respectively.

1.3.2 For steel propellers, the elongation of the material used is to be not less than 19 per cent for a test piece length of 5*d*. Charpy impact tests are to be carried out in accordance with the requirements of the Rules for Materials.

1.3.3 Cast steel load transmitting components of controllable pitch mechanisms are to be manufactured, tested and certified in accordance with the requirements of Ch 4,5 of the Rules for Materials.

1.3.4 Forged steel load transmitting components of controllable pitch propellers are to be manufactured, tested, and certified in accordance with Ch 5,1 and Ch 5,2 of the Rules for Materials. Impact tests are to be carried out at minus 10°C and the average energy value is to be not less than 27J.

1.3.5 Spheroidal cast iron load transmitting-components of controllable-pitch mechanisms are to be manufactured, tested and certified in accordance with the requirements of Table 7.3.2 in Ch 7,3 of the Rules for Materials.

## ■ Section 2 Ice Classes 1AS FS, 1A FS, 1B FS and 1C FS

### 2.1 General

2.1.1 Where the notation **Ice Class 1AS FS**, **Ice Class 1A FS**, **Ice Class 1B FS** or **Ice Class 1C FS** is desired, the requirements of this Section, in addition to those for open water service, are to be complied with, so far as these are applicable.

### 2.2 Determination of ice torque

2.2.1 Dimensions of propellers, shafting and gearing are determined by formulae taking into account the impact when a propeller blade hits ice. The ensuing load is hereinafter defined by ice torque, *M*.

$$M = m D^2 \text{ kN m (tonne-f m)}$$

where

$$\begin{aligned} m &= 21,10 (2,15) \text{ for Ice Class 1AS FS} \\ &= 15,69 (1,60) \text{ for Ice Class 1A FS} \\ &= 13,04 (1,33) \text{ for Ice Class 1B FS} \\ &= 11,96 (1,22) \text{ for Ice Class 1C FS} \\ D &= \text{diameter of propeller, in metres.} \end{aligned}$$

2.2.2 If the propeller is not fully submerged when the ship is in ballast condition, the ice torque for **Ice Class 1A FS** is to be used for **Ice Class 1B FS** and **Ice Class 1C FS**.

# Strengthening for Navigation in Ice

# Part 5, Chapter 9

Section 2

## 2.3 Propeller blade sections

2.3.1 The width,  $L$ , and thickness,  $T$ , of propeller blade sections are to be determined so that:

(a) at the radius  $0,25D/2$ , for solid propellers

$$LT^2 \geq \frac{26\,478\,000}{\sigma_u (0,65 + 0,7p_r/D)} \left( 27,2 \frac{P}{NR} + 2,24M \right)$$

$$\left( LT^2 \geq \frac{2\,700\,000}{\sigma_u (0,65 + 0,7p_r/D)} \left( 20 \frac{H}{NR} + 22M \right) \right)$$

(b) at radius  $0,35D/2$  for controllable pitch propellers

$$LT^2 \geq \frac{21\,084\,300}{\sigma_u (0,65 + 0,7p_r/D)} \left( 27,2 \frac{P}{NR} + 2,35M \right)$$

$$\left( LT^2 \geq \frac{2\,150\,000}{\sigma_u (0,65 + 0,7p_r/D)} \left( 20 \frac{H}{NR} + 23M \right) \right)$$

(c) at the radius  $0,6D/2$

$$LT^2 \geq \frac{9\,316\,320}{\sigma_u (0,65 + 0,7p_r/D)} \left( 27,2 \frac{P}{NR} + 2,86M \right)$$

$$\left( LT^2 \geq \frac{950\,000}{\sigma_u (0,65 + 0,7p_r/D)} \left( 20 \frac{H}{NR} + 28M \right) \right)$$

where

$D$  = diameter of propeller, in metres

$L$  = length of the expanded cylindrical section of the blade, at the radius in question, in mm

$M$  = ice torque as defined in 2.2

$N$  = number of blades

$p_r$  = propeller pitch at the radius in question, for solid propellers, in metres

= 0,7 nominal pitch for controllable pitch propellers, in metres

$P(H)$  = shaft power as defined in Ch 1,3.3

$R$  = propeller speed, in rev/min

$T$  = the corresponding maximum blade thickness, in mm

$\sigma_u$  = specified minimum tensile strength of the material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

2.3.2 Where the blade thickness derived from these formulae is less than the blade thickness derived by Ch 7,3.1 the latter is to apply.

## 2.4 Propeller blade minimum tip thickness

2.4.1 The blade tip thickness,  $t$ , at the radius  $D/2$  is to be determined by the following formulae:

### Ice Class 1A FS

$$t = (20 + 2D) \sqrt{\frac{490}{\sigma_u}} \text{ mm}$$

$$\left( t = (20 + 2D) \sqrt{\frac{50}{\sigma_u}} \text{ mm} \right)$$

### Ice Classes 1A FS, 1B FS and 1C FS

$$t = (15 + 2D) \sqrt{\frac{490}{\sigma_u}} \text{ mm}$$

$$\left( t = (15 + 2D) \sqrt{\frac{50}{\sigma_u}} \text{ mm} \right)$$

where  $D$  and  $\sigma_u$  are as defined in 2.3.

## 2.5 Intermediate blade sections

2.5.1 The thickness of other sections is to conform to a smooth curve connecting the section thicknesses as determined by 2.3 and 2.4.

## 2.6 Blade edge thickness

2.6.1 The thickness of blade edges is to be not less than 50 per cent of the derived tip thickness,  $t$ , measured at  $1,25t$  from edge. For controllable pitch propellers this applies only to the leading edge.

## 2.7 Mechanisms for controllable pitch propellers

2.7.1 The strength of mechanisms in the boss of a controllable pitch propeller is to be 1,5 times that of the blade when a load is applied at the radius  $0,9D/2$  in the weakest direction of the blade.

## 2.8 Keyless propellers

2.8.1 When it is proposed to use keyless propellers, the fit of the propeller boss to the screwshaft will be specially considered.

## 2.9 Screwshafts

2.9.1 The diameter  $d_s$  at the aft bearing of the screwshaft fitted in conjunction with a solid propeller is to be not less than:

$$d_s = 1,08 \sqrt[3]{\frac{\sigma_u LT^2}{\sigma_o}} \text{ mm}$$

where

$L$  and  $T$  = proposed width and thickness respectively of the propeller blade section at  $0,25D/2$ , in mm

$\sigma_o$  = specified minimum yield stress of the material of the screwshaft, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)

$\sigma_u$  = specified minimum tensile strength of the blade material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

2.9.2 The diameter,  $d_s$  at the aft bearing of the screwshaft fitted in conjunction with a controllable pitch propeller is to be not less than:

$$d_s = 1,15 \sqrt[3]{\frac{\sigma_u LT^2}{\sigma_o}} \text{ mm}$$

where

$L$  and  $T$  = proposed width and thickness respectively of the propeller blade section at  $0,35D/2$ , in mm

# Strengthening for Navigation in Ice

# Part 5, Chapter 9

Sections 2 & 3

- $\sigma_o$  = specified minimum yield stress of the material of the screwshaft, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>)  
 $\sigma_u$  = specified minimum tensile strength of the blade material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

2.9.3 Where the screwshaft diameter as derived by 2.9.1 or 2.9.2 is less than the diameter derived by Ch 6,3.5.1, the latter is to apply.

2.9.4 The shaft may be tapered at the forward end in accordance with Ch 6,3.5.4.

## 2.10 Intermediate and thrust shafts

2.10.1 The diameters of intermediate shafts and thrust shafts in external bearings are to comply with Ch 6,3.1 and Ch 6,3.4 respectively, except for **Ice Class 1AS FS** ice strengthening where these diameters are to be increased by 10 per cent.

## 2.11 Reduction gearing

2.11.1 Where gearing is fitted between the engine and the propeller shafting, the gearing is to be in accordance with Chapter 5, and is to be designed to transmit a torque,  $Y_i$ , determined by the following formula:

$$Y_i = Y + \frac{M I_h u^2}{I_1 + I_h u^2} \text{ kN m (tonne-f m)}$$

where

$$u = \text{gear ratio} = \frac{\text{pinion speed}}{\text{wheel speed}}$$

$I_h$  = mass moment of inertia of machinery components rotating at higher speed

$I_1$  = mass moment of inertia of machinery components rotating at lower speed, including propeller with an addition of 30 per cent of entrained water

( $I_h$  and  $I_1$  are to be expressed in the same units)

$M$  = ice torque as defined in 2.2

$$Y = 9,55 \frac{P}{R}$$

$$\left( Y = 0,716 \frac{H}{R} \right)$$

$P$  ( $H$ ) and  $R$  are as defined in 2.3.

## 2.12 Fire pumps in motor ships

2.12.1 In motor ships where clearing steam is not available, fire pumps are to be provided with suctions from the cooling water inlet chest.

## Section 3 Ice Class 1D and 1E

### 3.1 General

3.1.1 Where the notation Ice Class **1D** or Ice Class **1E** is desired, the requirements of this Section, in addition to those for open water service, are to be complied with.

3.1.2 For Ice Class **1D** or Ice Class **1E**, the total engine output is to be not less than determined by the following formula:

$$P = 0,72LB \text{ kW}$$

$$(H = 0,98LB) \text{ Hp}$$

where

$L$  = Rule length, in metres, see Pt 3, Ch 1,6.1.1

$B$  = moulded breadth of ship, in metres, see Pt 3, Ch 1,6.1.3

### 3.2 Main engine shafting, gearing and propellers

3.2.1 The diameters of the shafting and propeller blade thickness as required by the Rules for open water service are to be increased by the following percentages. No increase in the diameter of crankshafts, thrustshafts or intermediate shafts is required.

Screwshaft, increase in diameter as required by Ch 6,3.5 5%

Propeller, increase in blade thickness at root and at 60 per cent radius as required by Ch 7,3.1 8%

Keyless propeller fitting, increase in mean torque  $Q$  as defined in Ch 7,3.2. 15%

3.2.2 The screwshaft may be tapered at the forward end in accordance with Ch 6,3.5.4.

### 3.3 Minimum propeller blade tip thickness

3.3.1 The tip thickness,  $t$ , of the blade at 95 per cent radius is to be not less than that obtained by the following formula:

$$t = 0,14 (T + 57) \sqrt[3]{\frac{430}{\sigma_u}} \text{ mm}$$

$$\left( t = 0,14 (T + 57) \sqrt[3]{\frac{44}{\sigma_u}} \text{ mm} \right)$$

where

$T$  = blade root thickness required by 3.2.1, in mm

$\sigma_u$  = specified minimum tensile strength of material, in N/mm<sup>2</sup> (kgf/mm<sup>2</sup>).

### 3.4 Blade edge thickness

3.4.1 The edges of the blades are to be suitably thickened for the operating conditions but are to be not less than 50 per cent of the required tip thickness,  $t$ , measured at 1,25 times tip thickness,  $t$ , from the edge. For controllable pitch propellers, this requirement need only be applied to the leading edges of the blades.

# Strengthening for Navigation in Ice

## Part 5, Chapter 9

Sections 3 & 4

### 3.5 Ship-side valves

3.5.1 The sea inlet and overboard discharge valves which are situated at or below the maximum Load Line, are to be provided with low pressure steam or compressed air connection for clearing purposes, see Chapter 13.

3.5.2 When steam is not available for clearing, it is recommended that arrangements be made for supplying water for machinery cooling purposes by circulating from ballast tanks(s) of adequate capacity, preferably situated in the double bottom. Such tank(s) must be used only for storage of water ballast or fresh water.

### 3.6 Cooling water lines

3.6.1 Connections are to be fitted between the cooling water overboard discharge lines and sea inlets for main and/or auxiliary engine cooling water systems so that warm water may be used to assist in maintaining the suction pipes free from ice.

3.6.2 Where the cooling water inlet valves are fitted to a common water box, the connections from the cooling water discharge lines may be led to the water box in a position as near as possible to the inlet valves.

### 3.7 Fire pumps in motor ships

3.7.1 In motor ships where clearing steam is not available, fire pumps are to be provided with suctions from the main cooling water inlet pipe.

## Section 4

### Ice Classes 1AS FS(+), 1A FS(+), 1B FS(+) and 1C FS(+)

#### 4.1 Powering of ice strengthened ships

4.1.1 For ships that require additional strengthening in ice the total shaft power installed is to be calculated using the following sections, but is not to be less than required by the Finnish Swedish Ice Class Rules in force at the time of contract.

4.1.2 Ice strengthened ships which are to be considered to have an icebreaking capability are to be able to develop sufficient thrust to permit continuous mode icebreaking at a speed of at least five knots in ice having a thickness equal to the nominal value for the desired Ice Class and a snow cover of at least 0,3 m.

4.1.3 The shaft power necessary to provide an icebreaking capability can be determined by the equation:

$$P_1 = 0,736 C_1 C_2 C_3 C_4 [240 B h (1 + h + 0,035 v^2) + 70 S_c \sqrt{L}]$$

$$(H_1 = C_1 C_2 C_3 C_4 [240 B h (1 + h + 0,035 v^2) + 70 S_c \sqrt{L}])$$

where

$B$  = moulded breadth of ship, in metres, see Pt 3, Ch 1,6.1.3

$L$  = Rule length, in metres, see Pt 3, Ch 1,6.1.1.

$\Delta$  = displacement, in tonnes, see Pt 3, Ch 9,7.2.1

$C_1 = \frac{1,2B}{\sqrt[3]{\Delta}}$ , but is not to be taken as less than 1,0

$C_2$  = 0,9 if the ship is fitted with a controllable pitch propeller, otherwise 1,0

$C_3$  = 0,9 if the rake of the stem is 45° or less, otherwise 1,0. The product  $C_2 C_3$  is not to be taken as less than 0,85

$C_4$  = 1,1 if the ship is fitted with a bulbous bow, otherwise 1,0

$h$  = ice thickness

$S_c$  = depth of snow cover

$v$  = ship speed, in knots, when breaking ice of thickness  $h$ .



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 1

### Section

- 1 **General requirements**
- 2 **Cylindrical shells and drums subject to internal pressure**
- 3 **Spherical shells subject to internal pressure**
- 4 **Dished ends subject to internal pressure**
- 5 **Conical ends subject to internal pressure**
- 6 **Standpipes and branches**
- 7 **Boiler tubes subject to internal pressure**
- 8 **Headers**
- 9 **Flat surfaces and flat tube plates**
- 10 **Flat plates and ends of vertical boilers**
- 11 **Furnaces subject to external pressure**
- 12 **Boiler tubes subject to external pressure**
- 13 **Tubes welded at both ends and bar stays for cylindrical boilers**
- 14 **Construction**
- 15 **Mountings and fittings for cylindrical and vertical boilers, steam generators, pressurized thermal liquid and pressurized hot water heaters**
- 16 **Mountings and fittings for water tube boilers**
- 17 **Hydraulic tests**

### ■ Section 1 General requirements

#### 1.1 Application

1.1.1 The requirements of this Chapter are applicable to fusion welded pressure vessels and their mountings and fittings, for the following uses:

- (a) Production or storage of steam.
- (b) Heating of pressurized hot water above 120°C.
- (c) Heating of pressurized thermal liquid.

The formulae in this Chapter may be used for determining the thickness of seamless pressure vessels using a joint factor of 1,0. Seamless pressure vessels are to be manufactured and tested in accordance with the requirements of Chapter 5 of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

1.1.2 The scantlings of coil type heaters with pumped circulation, which are fired or heated by exhaust gas, are to comply with the appropriate requirements of this Chapter.

#### 1.2 Definition of symbols

1.2.1 The symbols used in the various formulae in Sections 2 to 8, unless otherwise stated, are defined as follows and are applicable to the specific part of the pressure vessel under consideration:

- $d$  = diameter of hole or opening, in mm
- $p$  = design pressure, see 1.3, in bar
- $r_i$  = inside knuckle radius, in mm
- $r_o$  = outside knuckle radius, in mm
- $s$  = pitch, in mm
- $t$  = minimum thickness, in mm
- $D_i$  = inside diameter, in mm
- $D_o$  = outside diameter, in mm
- $J$  = joint factor applicable to welded seams, see 1.9, or ligament efficiency between tube holes (expressed as a fraction, see 2.2)
- $R_i$  = inside radius, in mm
- $R_o$  = outside radius, in mm
- $T$  = design temperature, in °C
- $\sigma$  = allowable stress, see 1.8, in N/mm<sup>2</sup>.

1.2.2 Where reference is made to calculated or actual plate thickness for the derivation of other values, these thicknesses are to be minus the standard Rule corrosion allowance of 0,75 mm, if not so stated.

#### 1.3 Design pressure

1.3.1 The design pressure is the maximum permissible working pressure and is to be not less than the highest set pressure of any safety valve.

1.3.2 The calculations made to determine the scantlings of the pressure parts are to be based on the design pressure, adjusted where necessary to take account of pressure variations corresponding to the most severe operational conditions.

1.3.3 It is desirable that there should be a margin between the normal pressure at which the boiler or pressure vessel operates and the lowest pressure at which any safety valve is set to lift, to prevent unnecessary lifting of the safety valve.

#### 1.4 Metal temperature

1.4.1 The metal temperature,  $T$ , used to evaluate the allowable stress,  $\sigma$ , is to be taken as the actual mean wall metal temperature expected under operating conditions for the pressure part concerned, and is to be stated by the manufacturer when plans of the pressure parts are submitted for consideration.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 1

1.4.2 The following values are to be regarded as the minimum:

- (a) For fired steam boilers,  $T$ , is to be taken as not less than 250°C.
- (b) For steam heated generators, secondary drums of double evaporation boilers, steam receivers and pressure parts of fired pressure vessels, not heated by hot gases and adequately protected by insulation,  $T$ , is to be taken as the maximum temperature of the internal fluid.
- (c) For pressure parts heated by hot gases,  $T$ , is to be taken as not less than 25°C in excess of the maximum temperature of the internal fluid.
- (d) For boiler, superheater, reheater and economizer tubes,  $T$ , is to be taken as indicated in 7.1.2.
- (e) For combustion chambers of the type used in horizontal wet-back boilers,  $T$ , is to be taken as not less than 50°C in excess of the maximum temperature of the internal fluid.
- (f) For furnaces, fireboxes, rear tube plates of dry-back boilers and pressure parts subject to similar rates of heat transfer,  $T$ , is to be taken as not less than 90°C in excess of the maximum temperature of the internal fluid.

1.4.3 In general any parts of boiler drums or headers not protected by tubes, and exposed to radiation from the fire or to the impact of hot gases, are to be protected by a shield of good refractory material or by other approved means.

1.4.4 Drums and headers of thickness greater than 35 mm are not to be exposed to combustion gases having an anticipated temperature in excess of 650°C unless they are efficiently cooled by closely arranged tubes.

### 1.5 Classification of fusion welded pressure vessels

1.5.1 For Rule purposes, pressure vessels with fusion welded seams are graded as Class 1 if they comply with the following conditions:

- (a) For pressure parts of fired steam boilers, fired thermal liquid heaters and exhaust gas heated shell type steam boilers where the design pressure exceeds 3,4 bar.
- (b) For pressure parts of steam heated steam generators and separate steam receivers where the design pressure exceeds 11,3 bar, or where the pressure, in bar, multiplied by the internal diameter of the shell, in mm, exceeds 14 420.

1.5.2 For Rule purposes, pressure vessels with fusion welded seams, used for the production or storage of steam, the heating of pressurized hot water above 120°C or the heating of pressurized thermal liquid not included in Class 1 are graded as Class 2/1 and 2/2.

1.5.3 Pressure vessels which are constructed in accordance with Class 2/1 or Class 2/2 standards (as indicated above) will, if manufactured in accordance with requirements of a superior class, be approved with the scantlings appropriate to that class.

1.5.4 Pressure vessels which have only circumferential fusion welded seams, will be considered as seamless with no class being assigned. Preliminary weld procedure tests and non-destructive examination for the circumferential seam welds should be carried out for the equivalent class as determined by 1.5.1 and 1.5.2.

1.5.5 In special circumstances relating to service conditions, materials, operating temperature, the carriage of dangerous gases and liquids, etc., it may be required that certain pressure vessels be manufactured in accordance with the requirements of a superior class.

1.5.6 Heat treatment, non-destructive examinations and routine tests, where required, for the three classes of fusion welded pressure vessels are indicated in Table 10.1.1. Details are given in Chapter 17.

### 1.6 Plans

1.6.1 Plans of boilers, superheaters and economizers are to be submitted in triplicate for consideration. When plans of water tube boilers are submitted for approval, particulars of the safety valves and their disposition on boilers and superheaters, together with the estimated pressure drop through the superheaters, are to be stated. The pressures proposed for the settings of boiler and superheater safety valves are to be indicated on the boiler plan.

1.6.2 Plans, in triplicate, showing full constructional features of fusion welded pressure vessels and dimensional details of the weld preparation for longitudinal and circumferential seams and attachments, together with particulars of the welding consumables and of the mechanical properties of the materials, are to be submitted before construction is commenced.

**Table 10.1.1 Heat treatment, non-destructive examination and testing requirements**

Class	Radiographic examination	Heat treatment	Routine weld tests	Hydraulic test
1	Required, see Chapter 17	See Chapter 17	Required	Required
2/1	Spot required, see Chapter 17	See Chapter 17	Required	Required
2/2	—	See Chapter 17	Required	Required

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 1

1.6.3 Plans, in triplicate, showing details of the air flow through the combustion chamber, boiler furnace and boiler uptake spaces, including measures taken to assure effective purging in all of the spaces, are to be submitted for consideration. See also Pt 6, Ch 1,3.5 and 3.6.

1.6.4 Plans, in triplicate, showing all areas of refractory material in the combustion chamber and boiler furnace spaces, are to be submitted for consideration. See 1.12.1.

1.6.5 Calculations, in triplicate, showing that a minimum of 4 air changes of the combustion chamber, boiler furnace and boiler uptake spaces will be achieved during automatic purging operations, with details of the forced draft fans and arrangements of air flow from fan intake to flue outlet, are to be submitted for consideration, see 1.12.1.

1.6.6 Calculations, in triplicate, are to be submitted showing that the ventilation of machinery spaces containing boilers is adequate for the air consumers within the space with an unimpaired air supply, in accordance with the equipment manufacturer's recommendations, under operating conditions as defined in Ch 1,4.4.2.

### 1.7 Materials

1.7.1 Materials used in the construction are to be manufactured and tested in accordance with the requirements of the Rules for Materials.

1.7.2 The specified minimum tensile strength of carbon and carbon-manganese steel plates, pipes, forgings and castings is to be within the following general limits:

- (a) For seamless, Class 1, Class 2/1 and Class 2/2 fusion welded pressure vessels:  
340 to 520 N/mm<sup>2</sup>.
- (b) For boiler furnaces, combustion chambers and flanged plates:  
400 to 520 N/mm<sup>2</sup>.

1.7.3 The specified minimum tensile strength of low alloy steel plates, pipes, forgings and castings is to be within the general limits of 400 to 500 N/mm<sup>2</sup> and pressure vessels made in these steels are to be either seamless or Class 1 fusion welded.

1.7.4 The specified minimum tensile strength of boiler and superheater tubes is to be within the following general limits:

- (a) Carbon and carbon-manganese steels:  
320 to 460 N/mm<sup>2</sup>.
- (b) Low alloy steels:  
400 to 500 N/mm<sup>2</sup>.

1.7.5 Where it is proposed to use materials other than those specified in the Rules for Materials, details of the chemical compositions, heat treatment and mechanical properties are to be submitted for approval. In such cases the values of the mechanical properties used for deriving the allowable stress are to be subject to agreement by Lloyd's Register (hereinafter referred to as 'LR').

1.7.6 Where a fusion welded pressure vessel is to be made of alloy steel, and approval of the scantlings is required on the basis of the high temperature properties of the material, particulars of the welding consumables to be used, including typical mechanical properties and chemical composition of the deposited weld metal, are to be submitted for approval.

### 1.8 Allowable stress

1.8.1 The term 'allowable stress',  $\sigma$ , is the stress to be used in the formulae for the calculation of scantlings of pressure parts.

1.8.2 The allowable stress,  $\sigma$ , is to be the lowest of the following values:

$$\sigma = \frac{E_t}{1,5} \quad \sigma = \frac{R_{20}}{2,7} \quad \sigma = \frac{S_R}{1,5}$$

where

$E_t$  = specified minimum lower yield stress or 0,2 per cent proof stress at temperature,  $T$

$R_{20}$  = specified minimum tensile strength at room temperature

$S_R$  = average stress to produce rupture in 100 000 hours at temperature,  $T$

$T$  = metal temperature, see 1.4.

1.8.3 The allowable stress for steel castings is to be taken as 80 per cent of the value determined by the method indicated in 1.8.2, using the appropriate values for cast steel.

1.8.4 Where steel castings, which have been tested in accordance with the Rules for Materials, are also subjected to non-destructive tests, consideration will be given to increasing the allowable stress using a factor up to 90 per cent in lieu of the 80 per cent referred to in 1.8.3. Particulars of the non-destructive test proposals are to be submitted for consideration.

### 1.9 Joint factors

1.9.1 The following joint factors are to be used in the equations in Sections 2 to 8, where applicable. Fusion welded pressure parts are to be made in accordance with Chapter 17.

Class of pressure vessel	Joint factor
Class 1	1,0
Class 2/1	0,85
Class 2/2	0,75

1.9.2 The longitudinal and circumferential joints for all classes of pressure vessels for the purposes of this Chapter are to be butt joints. For typical acceptable methods of attaching dished ends, see Fig. 10.14.1.

### 1.10 Pressure parts of irregular shape

1.10.1 Where pressure parts are of such irregular shape that it is impracticable to design their scantlings by the application of formulae in Sections 2 to 8, the suitability of their construction is to be determined by hydraulic proof test of a prototype or by agreed alternative method.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 1 & 2

### 1.11 Adverse working conditions

1.11.1 Where working conditions are adverse, special consideration may be required to be given to increasing the scantlings derived from the formulae. In this connection, where necessary, account should also be taken of any excess of loading resulting from:

- impact loads, including rapidly fluctuating pressures,
- weight of the vessel and normal contents under operating and test conditions,
- superimposed loads such as other pressure vessels, operating equipment, insulation, corrosion-resistant or erosion-resistant linings and piping,
- reactions of supporting lugs, rings, saddles or other types of supports, or
- the effect of temperature gradients on maximum stress.

### 1.12 Furnace explosion prevention

1.12.1 The design of combustion chamber and furnace arrangements is to incorporate measures to minimise the risk of explosion as far as practicable. Measures are to be taken to prevent the accumulation of flammable gases in spaces which may not effectively be reached by purging air. Measures are to be taken to minimise heat retaining surfaces e.g. refractory which can become sources of ignition in the furnace and uptakes.

## Section 2 Cylindrical shells and drums subject to internal pressure

### 2.1 Minimum thickness

2.1.1 Minimum thickness,  $t$ , of a cylindrical shell is to be determined by the following formula:

$$t = \frac{p R_i}{10\sigma J - 0,5p} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$  and  $\sigma$  are defined in 1.2,

$J$  = efficiency of ligaments between tube holes or other openings in the shell or the joint factor of the longitudinal joints (expressed as a fraction). See 1.9 or 2.2, whichever applies. In the case of seamless shells clear of tube holes or other openings,  $J = 1,0$ .

2.1.2 The formula in 2.1.1 is applicable only where the resulting thickness does not exceed half the internal radius, i.e. where  $R_o$  is not greater than  $1,5R_i$ .

2.1.3 Irrespective of the thickness determined by the above formula,  $t$  is to be not less than:

- 6,0 mm for cylindrical shell plates.
- For tube plates, such thickness as will give a minimum parallel seat of 9,5 mm, or such greater width as may be necessary to ensure tube tightness, see 14.6.

### 2.2 Efficiency of ligaments between tube holes

2.2.1 Where tube holes are drilled in a cylindrical shell in a line or lines parallel to its axis, the efficiency,  $J$ , of the ligaments is to be determined as in 2.2.2, 2.2.3 and 2.2.4.

2.2.2 **Regular drilling.** Where the distance between adjacent tube holes is constant, see Fig. 10.2.1,

$$J = \frac{s - d}{s}$$

where

$d$  = the mean effective diameter of the tube holes, in mm, after allowing for any serrations, counter-boring or recessing, or the compensating effect of the tube stub. See 2.3 and 2.4.

$s$  = pitch of tube holes, in mm.




Fig. 10.2.1 Regular drilling

2.2.3 **Irregular drilling.** Where the distance between centres of adjacent tube holes is not constant, see Fig. 10.2.2:

$$J = \frac{s_1 + s_2 - 2d}{s_1 + s_2}$$

where  $d$  is as defined in 2.2.2

$s_1$  = the shorter of any two adjacent pitches, in mm

$s_2$  = the longer of any two adjacent pitches, in mm.




Fig. 10.2.2 Irregular drilling

2.2.4 When applying the formula in 2.2.3, the double pitch ( $s_1 + s_2$ ) chosen is to be that which makes  $J$ , a minimum, and in no case is  $s_2$  to be taken as greater than twice  $s_1$ .

# Steam Raising Plant and Associated Pressure Vessels


## Part 5, Chapter 10

Section 2


2.2.5 Where the circumferential pitch between tube holes measured on the mean of the external and internal drum or header diameters is such that the circumferential ligament efficiency determined by the formulae in 2.2.2 and 2.2.3 is less than one-half of the ligament efficiency on the longitudinal axis,  $J$  in 2.1 is to be taken as twice the circumferential efficiency.

2.2.6 Where tube holes are drilled in a cylindrical shell along a diagonal line with respect to the longitudinal axis, the efficiency,  $J$ , of the ligaments is to be determined as in 2.2.7 to 2.2.10.

2.2.7 For spacing of tube holes on a diagonal line as shown in Fig. 10.2.3, or in a regular saw-tooth pattern as shown in Fig. 10.2.4,  $J$  is to be determined from the formula in 2.2.8, where  $a$  and  $b$ , as shown in Figs. 10.2.3 and 10.2.4, are measured, in mm, on the median line of the plate, and  $d$ , is as defined in 2.2.2.



**Fig. 10.2.3 Spacing of holes on a diagonal line**



**Fig. 10.2.4 Regular saw-tooth pattern of holes**

2.2.8 For tube holes on a diagonal line:

$$J = \frac{2}{A + B + \sqrt{(A - B)^2 + 4C^2}}$$

where

$$A = \frac{\cos^2 \alpha + 1}{2 \left( 1 - \frac{d \cos \alpha}{a} \right)}$$

$$B = 0,5 \left( 1 - \frac{d \cos \alpha}{a} \right) (\sin^2 \alpha + 1)$$


$$C = \frac{\sin \alpha \cos \alpha}{2 \left( 1 - \frac{d \cos \alpha}{a} \right)}$$

$$\cos \alpha = \frac{1}{\sqrt{1 + \frac{b^2}{a^2}}}$$

$$\sin \alpha = \frac{1}{\sqrt{1 + \frac{a^2}{b^2}}}$$

$\alpha$  = angle between centreline of cylinder and centreline of diagonal holes.

2.2.9 For regularly staggered spacing of tube holes as shown in Fig. 10.2.5, the smallest value of the efficiency,  $J$ , of all ligaments (longitudinal, circumferential and diagonal) is obtained from Fig. 10.2.6, where  $a$  and  $b$  as shown in Fig. 10.2.5 are measured, in mm, on the median line of the plate, and  $d$  is as defined in 2.2.2.



**Fig. 10.2.5 Regular staggering of holes**

2.2.10 For irregularly spaced tube holes whose centres do not lie on a straight line, the formula in 2.2.3 is to apply, except that an equivalent longitudinal width of the diagonal ligament is to be used. An equivalent longitudinal width is that width which gives, using the formula in 2.2.2, the same efficiency as would be obtained using the formula in 2.2.8 for the diagonal ligament in question.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 2




Fig. 10.2.6 Efficiency of ligaments between holes

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 2

### 2.3 Compensating effect of tube stubs

2.3.1 Where a drum or header is drilled for tube stubs fitted by strength welding, either in line or in staggered formation, the effective diameter of holes is to be taken as:

$$d_e = d_a - \frac{A}{t}$$

where

- $d_e$  = the equivalent diameter of the hole, in mm
- $d_a$  = the actual diameter of the hole, in mm
- $t$  = the thickness of the shell, in mm
- $A$  = the compensating area provided by each tube stub and its welding fillets, in mm<sup>2</sup>.



2.3.2 The compensating area,  $A$ , is to be measured in a plane through the axis of the tube stub parallel to the longitudinal axis of the drum or header and is to be calculated as follows, see Figs. 10.2.7 and 10.2.8:

- The cross-sectional area of the stub, in excess of that required by 7.1 for the minimum tube thickness, from the interior surface of the shell up to a distance,  $b$ , from the outer surface of the shell;
- plus the cross-sectional area of the stub projecting inside the shell within a distance,  $b$ , from the inner surface of the shell;
- plus the cross-sectional area of the welding fillets inside and outside the shell;

where

$$b = \sqrt{d_a t_b}$$

$$t_b = \text{actual thickness of tube stub, in mm.}$$



2.3.3 Where the material of the tube stub has an allowable stress lower than that of the shell, the compensating cross-sectional area of the stub is to be multiplied by the ratio:

$$\frac{\text{allowable stress of stub at design metal temperature}}{\text{allowable stress of shell at design metal temperature}}$$

### 2.4 Unreinforced openings

2.4.1 Openings in a definite pattern, such as tube holes, may be designed in accordance with the Rules for ligaments in 2.2, provided that the diameter of the largest hole in the group does not exceed that permitted by 2.4.2.

2.4.2 The maximum diameter,  $d$ , of any unreinforced isolated openings is to be determined by the following formula:

$$d = 8,08 [D_o t (1 - K)]^{1/3} \text{ in mm}$$

The value of  $K$  to be used is calculated from the following formula:

$$K = \frac{p D_o}{18,2 \sigma t} \text{ but is not to be taken as greater than } 0,99$$

where

$p$ ,  $D_o$  and  $\sigma$  are as defined in 1.2

$t$  = actual thickness of shell, in mm.

2.4.3 For elliptical or oval holes,  $d$ , for the purposes of 2.4.2, refers to the major axis when this lies longitudinally or to the mean of the major and minor axes when the minor axis lies longitudinally.

2.4.4 No unreinforced opening is to exceed 200 mm in diameter.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

### Section 2

2.4.5 Holes may be considered isolated if the centre distance between two holes on the longitudinal axis of a cylindrical shell is not less than:

$$d + 1,1 \sqrt{D t} \text{ with a minimum } 5d$$

$d$  = diameter of openings in shell (mean diameter if dissimilarly sized holes involved)

$D$  = mean diameter of shell

$t$  = actual thickness of shell

Where the centre distance is less than so derived, the holes are to be fully compensated.

Where two holes are offset on a diagonal line, the diagonal efficiency from Fig. 10.2.6 may be used to derive an equivalent longitudinal centre distance for the purposes of this paragraph.

## 2.5 Reinforced openings

2.5.1 Openings larger than those permitted by 2.4 are to be compensated in accordance with Fig. 10.2.9(a) or (b). The following symbols are used in Fig. 10.2.9(a) and (b):

$t_s$  = calculated thickness of a shell without joint or opening or corrosion allowance, in mm

$t_d$  = thickness calculated in accordance with 7.1 without corrosion allowance, in mm

$t_a$  = actual thickness of shell plate without corrosion allowance, in mm

$t_b$  = actual thickness of standpipe without minus tolerances and corrosion allowance, in mm

$t_r$  = thickness of added reinforcement, in mm

$D_i$  = internal diameter of cylindrical shell, in mm

$d_o$  = diameter of hole in shell, in mm

$L$  = width of added reinforcement not exceeding  $D$ , in mm

$C = \sqrt{d_o t_b}$  in mm

$D = \sqrt{D_i t_a}$  and is not to exceed  $0,5d_o$ , in mm

$\sigma$  = shell plate allowable stress, N/mm<sup>2</sup>

$\sigma_p$  = standpipe allowable stress, N/mm<sup>2</sup>

$\sigma_r$  = added reinforcement allowable stress, N/mm<sup>2</sup>

$\sigma_w$  = weld metal allowable stress, N/mm<sup>2</sup>


NOTE

$\sigma_p$ ,  $\sigma_r$  and  $\sigma_w$  are not to be taken as greater than  $\sigma$ .

2.5.2 For elliptical or oval holes, the dimension on the meridian of the shell is to be used for  $d_o$  in 2.5.1.

2.5.3 Compensation is to be distributed equally on either side of the centreline of the opening.

2.5.4 The welds attaching standpipes and reinforcing plates to the shell are to be of sufficient size to transmit the full strength of the reinforcing areas and all other loadings to which they may be subjected.





# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 3 & 4

### Section 3 Spherical shells subject to internal pressure

#### 3.1 Minimum thickness

3.1.1 The minimum thickness of a spherical shell is to be determined by the following formula:

$$t = \frac{p R_i}{20\sigma J - 0,5p} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$ ,  $\sigma$  and  $J$  are as defined in 1.2.

3.1.2 The formula in 3.1.1 is applicable only where the resulting thickness does not exceed half the internal radius.

3.1.3 Openings in spherical shells requiring compensation are to comply, in general, with 2.5, using the calculated and actual thicknesses of the spherical shell as applicable.

### Section 4 Dished ends subject to internal pressure

#### 4.1 Minimum thickness

4.1.1 The thickness,  $t$ , of semi-ellipsoidal and hemispherical unstayed ends, and the knuckle section of torispherical ends, dished from plate, having pressure on the concave side and satisfying the conditions listed below, is to be determined by the following formula:

$$t = \frac{p D_o K}{20\sigma J} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $D_o$ ,  $\sigma$  and  $J$  are as defined in 1.2

$K$  = a shape factor, see 4.2 and Fig 10.4.1.

4.1.2 For semi-ellipsoidal ends:

the external height,  $H \geq 0,18D_o$

where

$D_o$  = the external diameter of the parallel portion of the end, in mm.

4.1.3 For torispherical ends:

the internal radius,  $R_i \leq D_o$

the internal knuckle radius,  $R_i \geq 0,1D_o$

the internal knuckle radius,  $R_i \geq 3t$

the external height,  $H \geq 0,18D_o$  and is determined as follows:

$$H = R_o - \sqrt{(R_o - 0,5D_o)(R_o + 0,5D_o - 2r_o)} .$$

4.1.4 In addition to the formula in 4.1.1 the thickness,  $t$ , of a torispherical head, made from more than one plate, in the crown section is to be not less than that determined by the following formula:

$$t = \frac{p R_i}{20\sigma J - 0,5p} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$ ,  $\sigma$  and  $J$  are as defined in 1.2.

4.1.5 The thickness required by 4.1.1 for the knuckle section of a torispherical head is to extend past the common tangent point of the knuckle and crown radii into the crown section for a distance not less than  $0,5\sqrt{R_i t}$  mm, before reducing to the crown thickness permitted by 4.1.4, where

$t$  = the required thickness from 4.1.1.

4.1.6 In all cases,  $H$ , is to be measured from the commencement of curvature, see Fig. 10.4.2.

4.1.7 The minimum thickness of the head,  $t$ , is to be not less than 6,0 mm.

4.1.8 For ends which are butt welded to the drum shell, see 1.8, the thickness of the edge of the flange for connection to the shell is to be not less than the thickness of an unpierced seamless or welded shell, whichever is applicable, of the same diameter and material and determined by 2.1.

#### 4.2 Shape factors for dished ends

4.2.1 The shape factor,  $K$ , to be used in 4.1.1 is to be obtained from the curves in Fig. 10.4.1, and depends on the ratio of height to diameter  $\frac{H}{D_o}$ .

4.2.2 The lowest curve in the series provides the factor,  $K$ , for plain (i.e. unpierced) ends. For lower values of  $\frac{H}{D_o}$ ,

$K$  depends upon the ratio of thickness to diameter,  $\frac{t}{D_o}$ , as

well as on the ratio  $\frac{H}{D_o}$ , and a trial calculation may be necessary to arrive at the correct value of  $K$ .

#### 4.3 Dished ends with unreinforced openings

4.3.1 Openings in dished ends may be circular, obround or approximately elliptical.

4.3.2 The upper curves in Fig. 10.4.1 provide values of  $K$ , to be used in 4.1.1, for ends with unreinforced openings. The selection of the correct curve depends on the value  $\frac{d}{\sqrt{D_o t}}$  and trial calculation is necessary to select the correct

curve, where

$d$  = the diameter of the largest opening in the end plate, in mm (in the case of an elliptical opening, the larger axis of the ellipse)

$t$  = minimum thickness, after dishing, in mm

$D_o$  = outside diameter of dished end, in mm.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 4





Fig. 10.4.1 Shape factor

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 4



**Fig. 10.4.2 Typical dished ends**

4.3.3 The following requirements must in any case be satisfied:

$$\frac{t}{D_o} \leq 0,1$$

$$\frac{d}{D_o} \leq 0,7.$$

4.3.4 From Fig.10.4.1 for any selected ratio of  $\frac{H}{D_o}$  the curve for unpierced ends gives a value for  $\frac{d}{\sqrt{D_o t}}$  as well as for  $K$ . Openings giving a value of  $\frac{d}{\sqrt{D_o t}}$  not greater than the value so obtained may thus be pierced through an end designed as unpierced without any increase in thickness.

### 4.4 Flanged openings in dished ends

4.4.1 The requirements in 4.3 apply equally to flanged openings and to unflanged openings cut in the plate of an end. No reduction may be made in end plate thickness on account of flanging.

4.4.2 Where openings are flanged, the radius,  $r_m$  of the flanging is to be not less than 25 mm, see Fig. 10.4.2(d). The thickness of the flanged portion may be less than the calculated thickness.


### 4.5 Location of unreinforced and flanged openings in dished ends

4.5.1 Unreinforced and flanged openings in dished ends are to be so arranged that the distance from the edge of the hole to the outside edge of the plate and the distance between openings are not less than those shown in Fig. 10.4.3.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 4



**Fig. 10.4.3 Opening in dished ends**

### 4.6 Dished ends with reinforced openings

4.6.1 Where it is desired to use a large opening in a dished end of less thickness than would be required by 4.3, the end is to be reinforced. This reinforcement may consist of a ring or standpipe welded into the hole, or of reinforcing plates welded to the outside and/or inside of the end in the vicinity of the hole, or a combination of both methods, see Fig. 10.4.4. Forged reinforcements may be used.

4.6.2 Reinforcing material with the following limits may be taken as effective reinforcement:

- The effective width,  $l_1$  of reinforcement is not to exceed  $\sqrt{2R_i t}$  or  $0,5d_o$  whichever is the lesser.
- The effective length,  $l_2$  of a reinforcing ring is not to exceed  $\sqrt{d_o t_b}$

where

$R_i$  = the internal radius of the spherical part of a torispherical end, in mm, or

$R_i$  = internal radius of the meridian of the ellipse at the centre of the opening, of a semi-ellipsoidal end, in mm, and is given by the following formula:


$$\frac{[a^4 - x^2(a^2 - b^2)]^{3/2}}{a^4 b}$$

where  $a$ ,  $b$  and  $x$  are shown in Fig. 10.4.2(c)

$d_o$  = external diameter of ring or standpipe, in mm

$l_1$  and  $l_2$  are shown in Fig. 10.4.4

$t_b$  = actual thickness of ring or standpipe, in mm.



**Fig. 10.4.4 Limits of reinforcement**

4.6.3 The shape factor,  $K$ , for a dished end having a reinforced opening can be read from Fig. 10.4.1 using the value obtained from:

$$\frac{d_o - \frac{A}{t}}{\sqrt{D_o t}} \text{ instead of from } \frac{d}{\sqrt{D_o t}}$$

where

$A$  = the effective cross-sectional area of reinforcement and is to be twice the area shown shaded on Fig. 10.4.4.

As in 4.3, a trial calculation is necessary in order to select the correct curve.

4.6.4 The area shown in Fig. 10.4.4 is to be obtained as follows:

- Calculate the cross-sectional area of reinforcement both inside and outside the end plate within the length,  $l_1$
- plus the full cross-sectional area of that part of the ring or standpipe which projects inside the end plate up to a distance,  $l_2$
- plus the full cross-sectional area of that part of the ring or standpipe which projects outside the internal surface of the end plate up to a distance,  $l_2$  and deduct the sectional area which the ring or standpipe would have if its thickness were as calculated in accordance with 7.1.

4.6.5 If the material of the ring or the reinforcing plates has an allowable stress value lower than that of the end plate, then the effective cross-sectional area,  $A$ , is to be multiplied by the ratio:

$$\frac{\text{allowable stress of reinforcing plate at design temperature}}{\text{allowable stress of end plate at design temperature}}$$

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 4 & 5


### 4.7 Torispherical dished ends with reinforced openings

4.7.1 If an opening and its reinforcement are positioned entirely within the crown section, the compensation requirements are to be as for a spherical shell, using the crown radius as the spherical shell radius. Otherwise the requirements of 4.6 are to be applied.

### Section 5 Conical ends subject to internal pressure

#### 5.1 General

5.1.1 Conical ends and conical reducing sections, as shown in Fig. 10.5.1, are to be designed in accordance with the equations given in 5.2.



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 5 & 6

**Table 10.5.1** Values of  $K$  as a function of  $\psi$  and  $r_i/D_o$

$\psi$	Values of $K$ for $r_i/D_o$ ratios of											
	0,01	0,02	0,03	0,04	0,06	0,08	0,10	0,15	0,20	0,30	0,40	0,50
10°	0,70	0,65	0,60	0,60	0,55	0,55	0,55	0,55	0,55	0,55	0,55	0,55
20°	1,00	0,90	0,85	0,80	0,70	0,65	0,60	0,55	0,55	0,55	0,55	0,55
30°	1,35	1,20	1,10	1,00	0,90	0,85	0,80	0,70	0,65	0,55	0,55	0,55
45°	2,05	1,85	1,65	1,50	1,30	1,20	1,10	0,95	0,90	0,70	0,55	0,55
60°	3,20	2,85	2,55	2,35	2,00	1,75	1,60	1,40	1,25	1,00	0,70	0,55
75°	6,80	5,85	5,35	4,75	3,85	3,50	3,15	2,70	2,40	1,55	1,00	0,55

5.1.2 Connections between cylindrical shell and conical sections and ends should preferably be by means of a knuckle transition radius. Typical permitted details are shown in Fig. 10.5.1. Alternatively, conical sections and ends may be butt welded to cylinders without a knuckle radius where the change in angle of slope,  $\psi$ , between the two sections under consideration does not exceed 30°.

5.1.3 Conical ends may be constructed of several ring sections of decreasing thickness, as determined by the corresponding decreasing diameter.

## 5.2 Minimum thickness

5.2.1 The minimum thickness,  $t$ , of cylinder, knuckle and conical section at the junction and within the distance,  $L$ , from the junction is to be determined by the following formula:

$$t = \frac{p D_o K}{20\sigma J} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $\sigma$  and  $J$  are as defined in 1.2

$K$  = a factor, taking into account the stress in the knuckle, see Table 10.5.1.

$D_o$  = outside diameter, in mm, of the conical section or end, see Fig. 10.5.1.

5.2.2 If the distance of a circumferential seam from the knuckle or junction is not to be less than  $L$ , then  $J$  is to be taken as 1,0; otherwise  $J$  is to be taken as the weld joint factor appropriate to the circumferential seam, where

$L$  = distance, in mm, from the knuckle or junction within which meridional stresses determine the required thickness, see Fig. 10.5.1

$$= 0,5 \sqrt{\frac{D_o t}{\cos \psi}}$$

$r_i$  = inside radius of transition knuckle, in mm, which is to be taken as  $0,01D_o$  in the case of conical sections without knuckle transition.

$\psi$  = difference between angle of slope of two adjoining conical sections, see Fig. 10.5.1.

5.2.3 The minimum thickness,  $t$ , of those parts of conical sections not less than a distance,  $L$ , from the junction with a cylinder or other conical section is to be determined by the following formula:

$$t = \frac{p D_c}{(20\sigma J - p)} \frac{1}{\cos \alpha} + 0,75 \text{ mm}$$

where

$D_c$  = inside diameter, in mm of conical section or end at the position under consideration, see Fig. 10.5.1

$\alpha, \alpha_1, \alpha_2$  = angle of slope of conical section (at the point under consideration) to the vessel axis, see Fig. 10.5.1.

5.2.4 The greater of the two thicknesses determined by the formulae in 5.2.1 and 5.2.3 is to apply at the junction or knuckle and within the limits of reinforcement.

5.2.5 The thickness of conical sections having an angle of inclination to the vessel axis of more than 75° is to be determined as for a flat plate.

## Section 6 Standpipes and branches

### 6.1 Minimum thickness

6.1.1 The minimum wall thickness of standpipes and branches is to be not less than that determined by 7.1 increased by the addition of a corrosion allowance of 0,75 mm, making such additions as may be necessary on account of bending, static loads and vibration. The wall thickness, however, is to be not less than:

$$t = 0,015D_o + 3,2 \text{ mm}$$

This thickness need only be maintained for a length,  $L$ , from the outside surface of the vessel, but need not extend past the first connection, butt weld or flange, where:

$$L = 3,5 \sqrt{D_o t} \text{ mm}$$

where  $t$  and  $D_o$  are as defined in 1.2.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 6 & 7

6.1.2 For boilers having a working pressure exceeding 50 bar and safety valves of full lift or full bore type, the thickness of the branch pipe carrying the superheater or drum safety valves is to be not less than:

$$t = \frac{1}{\sigma} \left[ 1,7d + \frac{DWK}{1,3d^2} \right] \text{ mm}$$

where  $t$  and  $\sigma$  are as defined in 1.2

$d$  = inside diameter of branch, in mm

$D$  = inside diameter of safety valve discharge, in mm

$K$  = 2 for superheater safety valves

= 1 for drum safety valves

$W$  = total valve throughput, in kg/h.

6.1.3 The offset from the centreline of the waste steam pipe to the centreline of the safety valve is not to exceed four times the outside diameter of the safety valve discharge pipe. The waste steam pipe system is to be supported and arrangements made for expansion such that no direct loading is imposed on the safety valve chests and the effects of vibration are to be minimized.

6.1.4 The pipe or header which carries the superheater safety valve is to be suitably thickened but is to be not less than the thickness required for the branch for a distance of

$\sqrt{D_2 t}$  on either side of the opening

where

$t$  = thickness required for the branch

$D_2$  = inside diameter of the pipe or header.

6.1.5 Except as required by 6.1.4, in no case need the wall thickness exceed the minimum shell thickness as required by 2.1, 3.1 or 4.1 as applicable.

6.1.6 Where a standpipe or branch is connected by screwing, the thickness is to be measured at the root of the thread.

6.1.7 For boiler, superheater or economizer tubes, the minimum thickness of the drum or the header connection or tube stub is to be calculated as part of the tube in accordance with 7.1.

2. Thickness is in no case to be less than the minimum shown in Table 10.7.1.

**Table 10.7.1 Minimum thickness of tubes**

Nominal outside diameter of tube, in mm	Minimum thickness, in mm
$\leq 38$	1,75
$> 38 > 50$	2,16
$\leq 50 \leq 70$	2,40
$> 70 \leq 75$	2,67
$> 75 \leq 95$	3,05
$> 95 \leq 100$	3,28
$> 100 \leq 125$	3,50

7.1.2 The minimum thickness of boiler, superheater, reheater and economizer tubes is to be determined by using the design stress appropriate to the mean wall temperature, which will be considered to be the metal temperature. Unless it is otherwise agreed between the manufacturer and LR, the metal temperature used to decide the value of  $\sigma$  for these tubes is to be determined as follows:

- The calculation temperature for boiler tubes is to be taken as not less than the saturated steam temperature, plus 25°C for tubes mainly subject to convection heat, or plus 50°C for tubes mainly subject to radiant heat.
- The calculation temperature for superheater and reheater tubes is to be generally taken as not less than the steam temperature expected in the part being considered, plus 35°C for tubes mainly subject to convection heat. For tubes mainly subject to radiant heat the calculation temperature is generally to be taken as not less than the steam temperature expected in the part being considered, plus 50°C, but the actual metal temperature expected is to be stated when submitting plans.
- The calculation temperature for economizer tubes is to be taken as not less than 35°C in excess of the maximum temperature of the internal fluid.

7.1.3 The minimum thickness of downcomer tubes and pipes which form an integral part of the boiler and which are not exposed to combustion gases is to comply with the requirements for steam pipes.

### 7.2 Tube bending

7.2.1 Where boiler, superheater, reheater and economizer tubes are bent, the resulting thickness of the tubes at the thinnest part is to be not less than that required for straight tubes, unless it can be demonstrated that the method of forming the bend results in no decrease in strength at the bend. The manufacturer is to demonstrate in connection with any new method of tube bending that this condition is satisfied.

7.2.2 Tube bending, and subsequent heat treatment, where necessary, is to be carried out as to ensure that residual stresses do not adversely affect the strength of the tube for the design purpose intended.

## Section 7

### Boiler tubes subject to internal pressure

#### 7.1 Minimum thickness

7.1.1 The minimum wall thickness of straight tubes subject to internal pressure is to be determined by the following formula:

$$t = \frac{p D_o}{20\sigma + p} \text{ mm}$$

where  $t$ ,  $p$ ,  $D_o$  and  $\sigma$  are as defined in 1.2.

#### NOTES

- Provision must be made for minus tolerances where necessary and also in cases where abnormal corrosion or erosion is expected in service. For bending allowances, see 7.2.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 7 & 8

### Cross-references

For details of manholes, sight holes and doors, see 14.1.  
For details of tube holes and fitting of tubes, see 14.6.

### Section 8 Headers

#### 8.1 Circular section headers

8.1.1 The minimum thickness of circular section headers is to be calculated in accordance with the formula for cylindrical shells in 2.1.

#### 8.2 Rectangular section headers

8.2.1 The thickness of the flat walls of rectangular section headers is to be determined at the centre of the sides, at all the lines of holes and at the corners. The minimum required is to be the greatest thickness determined by the following formula:

$$t = \frac{pn}{20\sigma J} + \sqrt{\frac{0,4Yp}{\sigma J_1}} + 0,75 \text{ mm}$$

where  $t$ ,  $p$  and  $\sigma$  are as defined in 1.2

- $n$  = one half of the internal width of the wall perpendicular to that under consideration, in mm, see Fig. 10.8.1(b)
- $J$  = ligament efficiency for membrane stresses determined in accordance with 8.2.3
- $J_1$  = ligament efficiency for bending stresses determined in accordance with 8.2.3.
- $Y$  = a coefficient determined in accordance with 8.2.2. In all cases if the value of  $Y$  is negative, the sign is to be ignored.

8.2.2 The coefficient  $Y$  for use in 8.2.1 is to be determined as follows:

(a) at the centre of the side with internal width,  $2m$ :

$$Y = \frac{1}{3} \left( \frac{m^3 + n^3}{m + n} \right) - \frac{1}{2} m^2$$

where

$m$  = one half of the internal width of the wall under consideration, in mm, see Fig. 10.8.1(b)

(b) at a line of holes parallel to the longitudinal axis of the header on the wall of width,  $2m$ :

$$Y = \frac{1}{3} \left( \frac{m^3 + n^3}{m + n} \right) - \frac{m^2 - b^2}{2}$$


where

$b$  = distance from the centre of the holes to the centreline of the wall, in mm, see Fig. 10.8.1(a)

(c) to check the effect of the off-set on a staggered hole arrangement where the holes are positioned equidistant from the centreline of the wall:

$$Y = \cos \alpha \left\{ \frac{1}{3} \left( \frac{m^3 + n^3}{m + n} \right) - \frac{m^2}{2} \right\}$$

where



**Fig. 10.8.1 Rectangular section headers**

$\alpha$  = the angle subtended by the diagonal ligament on the longitudinal ligament, see Fig.10.8.1(a)

(d) at the corners:

$$Y = \frac{1}{3} \left( \frac{m^3 + n^3}{m + n} \right)$$

8.2.3 The ligament efficiencies  $J$  and  $J_1$  are to be determined as follows:

(a) for a line of holes parallel to the longitudinal axis of the header:

$$J = \frac{s - d}{s}$$

Symbols are as defined in 8.2.4.

(b) for the diagonals:

$$J = \frac{s_1 - d}{s_1}$$

Symbols are as defined in 8.2.4.

(c) for a line of holes parallel to the longitudinal axis of the header:

$$J_1 = \frac{s - d}{s} \text{ when } d < 0,6m$$

or

$$J_1 = \frac{s - 0,6m}{s} \text{ when } d \geq 0,6m$$

Symbols are as defined in 8.2.4.

(d) for the diagonals:

$$J_1 = \frac{s_1 - d}{s_1} \text{ when } d < 0,6m$$






# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 8 & 9



**Fig. 10.8.3 Toroidal furnace headers**

8.4.3 Ends attached by welding are to be designed as follows:

- Dished ends: these are to be in accordance with 4.1.
- Flat ends: the minimum thickness of flat end plates is to be determined by the following formula:

$$t = d_i \sqrt{\frac{pC}{\sigma}} + 0,75 \text{ mm}$$

where  $p$  and  $\sigma$  are as defined in 1.2.

$t$  = minimum thickness of end plate, in mm

$d_i$  = internal diameter of circular header or least width between walls of rectangular header, in mm

$C$  = a constant depending on method of end attachment, see Fig. 10.8.2.

- For end plates welded as shown in Fig. 10.8.2(a):  
 $C = 0,019$  for circular headers  
 $C = 0,032$  for rectangular headers.
- For end plates welded as shown in Figs. 10.8.2(b) and (c):  
 $C = 0,028$  circular headers  
 $C = 0,040$  for rectangular headers.

8.4.4 Where flat end plates are bolted to flanges attached to the ends of headers, the flanges and end plates are to be in accordance with recognized pipe flange standards.

8.4.5 Openings in flat plates are to be compensated in accordance with Fig. 10.2.9 (a) or (b), with the value of  $A_1$  the compensation required, calculated as follows:

$$A_1 = \frac{d_o}{2,4} t_f \text{ mm}$$

where

$d_o$  = diameter of hole in flat plate, in mm

$t_f$  = required thickness of the flat plate in the area under consideration, in mm, calculated in accordance with 8.4.3, 8.3.3 or 9.1.6, as applicable, without corrosion allowance

Limit  $D = 0,5d_o$ .

### Section 9


### Flat surfaces and flat tube plates

#### 9.1 Stayed flat surfaces

9.1.1 Where flat end plates are flanged for connection to the shell, the inside radius of flanging is to be not less than 1,75 times the thickness of the plate, with a minimum of 38 mm.

9.1.2 Where combustion chamber or firebox plates are flanged for connection to the wrapper plate, the inside radius of flanging is to be equal to the thickness of the plate, with a minimum of 25 mm.

9.1.3 Where unflanged flat plates are connected to the shell by welding, typical methods of attachment are shown in Fig. 10.9.1. Similar forms of attachment may be used where unflanged combustion chamber or firebox plates are connected to the wrapper plate by welding.



**Fig. 10.9.1**

**Typical attachment of unflanged flat end plates to shell**

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 9

9.1.4 Where the flange curvature is a point of support, this is to be taken at the commencement of curvature, or at a line distant 3,5 times the thickness of the plate from the outside of the plate, whichever is nearer to the flange.

9.1.5 Where a flat plate is welded directly to a shell or wrapper plate, the point of support is to be taken at the inside of the shell or wrapper plate.

9.1.6 The thickness,  $t$ , of those portions of flat plates supported by stays and around tube nests is to be determined by the following formula:

$$t = Cd \sqrt{\frac{p}{\sigma}} + 0,75 \text{ mm}$$

where  $t$ ,  $p$  and  $\sigma$  are as defined in 1.2



$d$  = diameter of the largest circle which can be drawn through at least three points of support. At least one point of support must lie on one side of any diameter of the circle

$C$  = a constant, dependent on the method of support as detailed in 9.1.7. Where various forms of support are used,  $C$  is to be the mean of the values for the respective methods adopted.

9.1.7 The value of  $C$  in the formula in 9.1.6 is to be as follows:

- Where plain bar stays are strength welded into the plates as shown in Fig. 10.9.2  
 $C = 0,134$
- Where plain bar stays pass through holes in the plates and are fitted on the outside with washers as shown in Fig. 10.9.3  
 $C = 0,12$  where the diameter of the washer is 3,5 times the diameter of the stay  
 $C = 0,113$  where the diameter of the washer is 0,67 times the pitch of the stays.
- Where the flat plate is flanged for attachment to the shell, flue, furnace or wrapper or, alternatively, is welded directly to shell, flue, furnace or wrapper, see 9.1.4 and 9.1.5:  
 $C = 0,113$
- Where the support is a gusset stay  
 $C = 0,134$
- Where the support is a tube secured as shown in Fig. 10.9.4  
 $C = 0,144$ .


9.1.8 Where tubes are fixed by expanding only, sufficient tubes welded at both ends in accordance with Fig. 10.9.4 are to be provided within the tube nest to comply with 9.1.6, to carry the flat plate loading within the tube nest. Tubes welded in accordance with Fig. 10.9.4 are also to be provided in the boundary rows in sufficient numbers to carry the flat plate loading outside the tube areas.



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 9



**Fig. 10.9.4 Detail of weld for tube**

9.1.9 In the case of small boilers with a single tube nest of expanded tubes which does not exceed an area of 0,65 m<sup>2</sup>, welded tubes need not be fitted provided the tubes are beaded at the inlet end. In this instance the support afforded by the expanded tubes is not to be taken to extend beyond the line enclosing the outer surfaces of the tubes except that, between the outside of the nest and the attachment of the end plate to shell, there may be an unsupported width equal to the flat plate margin, as given by the formula in 9.4.1. The required tube plate thickness within such a tube nest is to be determined using the formula in 9.1.6, where:

$$C = 0,154$$

$d$  = four times the mean pitch, in mm, of the expanded tubes in the nest.

9.1.10 The thickness,  $t$ , of any tube plate in the tube area is to be not less than that required for the surrounding plate determined by 9.1.6 and in no case less than:

- (a) 12,5 mm where the diameter of the tube hole does not exceed 50 mm, or
- (b) 14 mm where the diameter of the tube hole is greater than 50 mm.

9.1.11 Alternative methods of support will be specially considered.

9.1.12 The spacing of tube holes is to be such that the minimum width,  $b$ , in mm of any ligament between tube holes is not less than:

for expanded tubes:

$$b = 0,125d + 12,5 \text{ mm}$$

for welded tubes:

$$b = 0,125d + 8 \text{ mm}$$

where

$d$  = diameter of the hole drilled in the plate, in mm.

9.1.13 Where a flat plate has a manhole or sight hole and the opening is strengthened by flanging, the total depth,  $H$ , of the flange, measured from the outer surface of the plate, is to be not less than:

$$H = \sqrt{tW}$$

where

$t$  = thickness of plate, in mm

$H$  = depth of flange, in mm

$W$  = minor axis of manhole or sight hole, in mm.

9.1.14 Where the flat top plates of combustion chambers are supported by welded-on girders, the equation in 9.1.6 is to apply as follows:

- (a) In the case of welded-on girders provided with waterways

$$C = 0,144$$

$$d = \sqrt{X^2 + Y^2}$$

where

$X$  = width of waterway in the girder plus the thickness of the girder, in mm

$Y$  = pitch of girders, in mm.

- (b) In the case of continuously welded-on girders

$$C = 0,175$$

$$d = D$$

where

$D$  = distance between inside faces of girders, in mm.

### 9.2 Combustion chamber tube plates under compression

9.2.1 The thickness of combustion chamber tube plates under compression due to the pressure on the top plate, based on a compressive stress not exceeding 96 N/mm<sup>2</sup> is to be determined by the following formula:

$$t = \frac{pWs}{1930(s-d)} \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2

$d$  = internal diameter of the plain tubes, in mm

$s$  = pitch of tubes, in mm, measured horizontally where tubes are chain pitched, or diagonally where the tubes are staggered pitched and the diagonal pitch is less than the horizontal pitch

$W$  = internal width of the combustion chamber, in mm, measured from tube plate to back chamber plate.

### 9.3 Girders for combustion chamber top plates

9.3.1 The formula in 9.3.2 is applicable to plate girders welded to the top combustion chamber plate by means of a full penetration weld.

9.3.2 The thickness of steel plate girders supporting the tops of combustion chambers is to be determined by the following formula:

$$t = \frac{0,32p l^2 s}{d^2 R_{20}} \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2

$d$  = effective depth of girder, in mm

$l$  = length of girder measured internally from tube plate to back chamber plate, in mm

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 9 & 10

$s$  = pitch of the girders, in mm  
 $R_{20}$  = specified minimum tensile strength of the girder plate, in N/mm<sup>2</sup>.

### 9.4 Flat plate margins

9.4.1 The width of margin,  $b$ , of a flat plate which may be regarded as being supported by the shell, furnaces or flues to which the flat plate is attached is not to exceed that determined by the following formula:

$$b = C(t - 0,75) \sqrt{\frac{\sigma}{p}} \text{ mm}$$

where  $p$  and  $\sigma$  are as defined in 1.2

$t$  = thickness of the flat plate, in mm

$b$  = width of margin, in mm

$C$  = 3,12.

9.4.2 Where an unflanged flat plate is welded directly to the shell, furnaces or flues and it is not practicable to effect the full penetration weld from both sides of the flat plate, the constant  $C$  used in the formula in 9.4.1 is to be:

$C$  = 2,38.

9.4.3 In the case of plates which are flanged, the margin is to be measured from the commencement of curvature of flanging, or from a line 3,5 times the thickness of the plate measured from the outside of the plate, whichever is nearer to the flange.

9.4.4 Where the flat plate is not flanged for attachment to the shell, furnaces or flues, the margin is to be measured from inside of the shell or the outside of the furnaces or flues, whichever is applicable.

9.4.5 In no case is the diameter  $D$ , in mm, of the circle forming the boundary of the margin supported by the uptake of a vertical boiler to be greater than determined by the following formula:

$$D = \sqrt{\frac{345A}{p} + d^2}$$

where  $p$  is as defined in 1.2

$d$  = external diameter of uptake, in mm

$d_i$  = internal diameter of uptake, in mm

$A$  = cross-sectional area of the uptake tube material,

i.e.  $\frac{\pi}{4} (d^2 - d_i^2)$  mm<sup>2</sup>.

### Section 10

## Flat plates and ends of vertical boilers

### 10.1 Tube plates of vertical boilers

10.1.1 Where vertical boilers have a nest or nests of horizontal tubes, so that there is direct tension on the tube plates due to the vertical load on the boiler ends or to their acting as horizontal ties across the shell, the thickness of the tube plates in way of the outer rows of tubes is to be determined by the following formula:

$$t = \frac{pD}{5J R_{20}} + 0,75 \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2

$D$  = twice the radial distance of the centre of the outer row of tube holes from the axis of the shell, in mm

$J$  = efficiency of ligaments between tube holes in the outer vertical rows (expressed as a fraction)

$$= \frac{s - d}{s}$$

$R_{20}$  = specified minimum tensile strength of tube plate, in N/mm<sup>2</sup>

where

$d$  = diameter of tube holes, in mm

$s$  = vertical pitch of tubes, in mm.

10.1.2 Each alternate tube in the outer vertical rows of tubes is to be a tube welded at both ends as shown in Fig. 10.9.4. Further, the arrangement of tubes in the nests is to be such that the thickness of the tube plates meets the requirements of 9.1.

10.1.3 Where the vertical height of the tube plates between the top and bottom shelves exceeds 0,65 times the internal diameter of the boiler, the staying of the tube plates, and the scantlings of the tube plates and shell plates to which the sides of the tube plates are connected, will require to be specially considered. It is recommended, however, that for this type of boiler the vertical height of the tube plates between the top and bottom shelves should not exceed 1,25 times the internal diameter of the boiler.

### 10.2 Horizontal shelves of tube plates forming part of the shell

10.2.1 For vertical boilers of the type referred to in 10.1, in order to withstand vertical load due to pressure on the boiler ends, the horizontal shelves of the tube plates are to be supported by gussets in accordance with the following formula:

$$C = \frac{AD_i p}{t}$$

where

$p$  = design pressure, in bar

$t$  = thickness of the tube plate, in mm

$A$  = maximum horizontal dimension of the shelf from the inside of the shell plate to the outside of the tube plate, in mm

$D_i$  = inside diameter of the boiler, in mm.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 10 & 11

10.2.2 For the combustion chamber tube plate the minimum number of gussets is to be:

- 1 gusset, where  $C$  exceeds 255 000
- 2 gussets, where  $C$  exceeds 350 000
- 3 gussets where  $C$  exceeds 420 000.

10.2.3 For the smokebox tube plate the minimum number of gussets is to be:

- 1 gusset where  $C$  exceeds 255 000
- 2 gussets where  $C$  exceeds 470 000.

10.2.4 The shell plates to which the sides of the tube plates are connected are to be not less than 1,6 mm thicker than is required by the formula applicable to shell plates with continuous circularity, and where gussets or other stays are not fitted to the shelves, the strength of the parts of the circumferential seams at the top and bottom of these plates from the outside of one tube plate to the outside of the other, is to be sufficient to withstand the whole load on the boiler end with a factor of safety of not less than 4,5 related to  $R_{20}$  (where  $R_{20}$  is the specified minimum tensile strength of the shell plates, in N/mm<sup>2</sup>).

### 10.3 Dished and flanged ends for vertical boilers

10.3.1 The minimum thickness,  $t$ , of dished and flanged ends for vertical boilers which are subject to pressure on the concave side and are supported by central uptakes is to be determined by the following formula:

$$t = \frac{pR_i}{13\sigma} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$  and  $\sigma$  are as defined in 1.2.

10.3.2 The inside radius of curvature,  $R_i$ , of the end plate is to be not greater than the external diameter of the cylinder to which it is attached.

10.3.3 The inside knuckle radius,  $r_i$ , see Fig. 10.4.2(a), of the arc joining the cylindrical flange to the spherical surface of the end is to be not less than four times the thickness of the end plate, and in no case less than 65 mm.

10.3.4 The inside radius of curvature of flange to uptake is to be not less than twice the thickness of the end plate, and in no case less than 25 mm.

10.3.5 If the dished end has a manhole, the opening is to be strengthened by flanging. The total depth,  $H$ , of the flange, measured from the outer surface of the plate on the minor axis, is to be not less than:

$$H = \sqrt{tW}$$

where

- $t$  = thickness of the flange, in mm
- $H$  = depth of flange, in mm
- $W$  = minor axis of the manhole, in mm.

### 10.4 Flat crowns of vertical boilers

10.4.1 The minimum thickness of flat crown plates of vertical boilers is to be determined as in 9.1;  $d$  and  $C$  are defined as follows:

- Where the crown is supported by an uptake only,
  - $d$  = diameter, in mm, of the largest circle which can be drawn between the connections to the shell or firebox and uptake, see 9.1.1 to 9.1.5
  - $C = 0,161$
- Where bar stays are fitted in accordance with 9.1.6 and 9.1.7:
  - $d$  = diameter of the largest circle which can be drawn through at least three points of support, in mm
  - $C$  = the mean of the values for the respective points of support through which the circle passes.

## Section 11 Furnaces subject to external pressure

### 11.1 Maximum thickness

11.1.1 Furnaces, plain or corrugated, are not to exceed 22,5 mm in thickness.

### 11.2 Corrugated furnaces

11.2.1 The minimum thickness,  $t$ , of corrugated furnaces is to be determined by the following formula:

$$t = \frac{pD_o}{C} + 0,75 \text{ mm}$$

where  $p$  is as defined in 1.2

- $t$  = thickness of the furnace plate measured at the bottom of the corrugations, in mm
- $C = 1060$  for Fox, Morison and Deighton corrugations
- $C = 1130$  for Suspension Bulb corrugations
- $D_o$  = external diameter of the furnace measured at the bottom of the corrugations, in mm.

### 11.3 Plain furnaces, flue sections and combustion chamber bottoms

11.3.1 The minimum thickness,  $t$ , between points of substantial support, of plain furnaces or furnaces strengthened by stiffening rings, of flue sections and of the cylindrical bottoms of combustion chambers is to be determined by the following formulae, the greater of the two thicknesses obtained being taken:

$$t = \sqrt{\frac{pD_o(L + 610)}{102\,400}} + 0,75 \text{ mm}$$

$$t = \frac{C p D_o}{1100} + \frac{L}{320} + 0,75 \text{ mm}$$

where

$t$  and  $p$  are as defined in 1.2

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

### Section 11

$$C = \frac{2x}{x + \sigma} \text{ or } 0,85 \text{ whichever is the greater}$$

$D_o$  = external diameter of the furnace, flue or combustion chamber, in mm

$L$  = length of section between the centres of points of substantial support, in mm

$x$  and  $\sigma$  are as defined in 11.7.1.

11.3.2 Where stiffeners are used for strengthening plain cylindrical furnaces, or combustion chambers, the second moment of area,  $I$ , of the stiffener is to be determined by the following formula:


$$I = \frac{p D_o^3 L}{13,3 \times 10^6} \text{ mm}^4$$

where  $p$  is as defined in 1.2

$D_o$  = external diameter of the furnace flue or combustion chamber, in mm

$L$  = length of section between the centres of points of substantial support, in mm

For proportion of stiffening rings, see Fig 10.11.1.



### 11.4 Plain furnaces of vertical boilers


11.4.1 The thickness of plain furnaces not exceeding 2000 mm in external diameter is to be determined by the formulae given in 11.3.1, the greater of the two thicknesses being taken:

where

$D_o$  = external diameter of the furnace, in mm. Where the furnace is tapered, the diameter to be taken for calculation purposes is to be the mean of that at the top and that at the bottom where it meets the substantial support from flange, ring or row of stays

$L$  = effective length, in mm, of the furnace between the points of substantial support as indicated in Fig. 10.11.2.

11.4.2 For furnaces under 760 mm in external diameter, the thickness is to be not less than 8 mm, and for furnaces 760 mm in external diameter and over, the thickness is to be not less than 9,5 mm.



11.4.3 A circumferential row of stays connecting the furnace to the shell will be considered to provide substantial support to the furnace, provided that:

- The diameter of the stay is not less 22,5 mm or twice the thickness of the furnace, whichever is the greater.
- The pitch of the stays at the furnace does not exceed 14 times the thickness of the furnace.

### 11.5 Hemispherical furnaces

11.5.1 The minimum thickness,  $t$ , of unsupported hemispherical furnaces subject to pressure on the convex surface is to be determined by the following formula:

$$t = \frac{C p R_o}{608} + 0,75 \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2  
 $x$  and  $\sigma$  are as defined in 11.7.1

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 11 & 12

$$C = \frac{2x}{x + \sigma} \text{ or } 0,85 \text{ whichever is the greater}$$

$R_o$  = outer radius of curvature of the furnace, in mm.

11.5.2 In no case is the maximum thickness to exceed 22,5 mm, or the ratio  $\frac{R_o}{t - 0,75}$  to exceed 100.

### 11.6 Dished and flanged ends for supported vertical boiler furnaces

11.6.1 The minimum thickness,  $t$ , of dished and flanged ends for vertical boiler furnaces that are subject to pressure on the convex side and are supported by central uptakes, is to be determined by the following formula:

$$t = \frac{p R_o}{10\sigma} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_o$  and  $\sigma$  are as defined in 1.2.

11.6.2 The inside radius of dishing and flanging are to be as required by 10.3.

### 11.7 Dished and flanged ends for unsupported vertical boiler furnaces

11.7.1 The minimum thickness,  $t$ , of dished and flanged ends for vertical boiler furnaces that are subject to pressure on the convex side and are without support from stays of any kind, is to be determined by the following formula, but is in no case to be less than the thickness of the firebox:

$$t = \frac{CpR_o}{660} + 0,75 \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2.

$x$  = specified minimum lower yield stress or 0,2 per cent proof stress in N/mm<sup>2</sup> at a temperature 90°C above the saturated steam temperature corresponding to the design pressure for carbon and carbon manganese steel with a specified minimum tensile strength of 400 N/mm<sup>2</sup>

$$C = \frac{2x}{x + \sigma} \text{ or } 0,85 \text{ whichever is the greater}$$

$R_o$  = outside radius of the crown plate, in mm

(in no case is  $\frac{R_o}{t}$  to exceed 88)

$\sigma$  = specified minimum lower yield stress or 0,2 per cent proof stress in N/mm<sup>2</sup> at a temperature 90°C above the saturated steam temperature corresponding to the design pressure for the steel actually used

11.7.2 The inside radius of curvature,  $R_i$ , of the end plate is to be not greater than the external diameter of the cylinder to which it is attached.

11.7.3 The inside knuckle radius,  $r_i$ , see Fig.10.4.2(a), of the arc joining the cylindrical flange to the spherical surface of the end is to be not less than four times the thickness of the end plate and in no case less than 65 mm.

### 11.8 Ogee rings

11.8.1 The minimum thickness,  $t$ , of the ogee ring which connects the bottom of the furnace to the shell of a vertical boiler and sustains the whole vertical load on the furnace is to be determined by the following formula:

$$t = \sqrt{\frac{p D_i (D_i - D_o)}{9\,900}} + 0,75 \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2

$D_i$  = inside diameter of boiler shell, in mm

$D_o$  = outside diameter of the lower part of the furnace where it joins the ogee ring, in mm.

11.8.2 Proposals to use a flat plate annular ring which connects the bottom of the furnace to the shell of a vertical boiler and sustains any unbalanced vertical load on the furnace will be the subject of special consideration.

### 11.9 Uptakes of vertical boilers

11.9.1 The minimum thickness,  $t$ , of internal uptakes of vertical boilers is to be determined by the following formulae, the greater of the two thicknesses obtained being taken:

$$t = \sqrt{\frac{p D_o (L + 610)}{102\,400}} + 4 \text{ mm}$$

$$t = \frac{p D_o}{1100} + \frac{L}{320} + 4 \text{ mm}$$

where  $t$  and  $p$  are as defined in 1.2

$D_o$  = external diameter of uptake, in mm

$L$  = length of uptake between the centres of points of substantial support, in mm.

## Section 12

### Boiler tubes subject to external pressure

#### 12.1 Tubes

12.1.1 The thickness of tubes is to be in accordance with Table 10.12.1 for the appropriate outside diameter and design pressure.

12.1.2 Tubes may be welded at both ends, welded at the inlet end and expanded at the outlet end, or expanded at both ends. In addition to expanding, tubes may be bell mouthed or beaded at the inlet end. Where tubes are welded, the weld detail is to be as shown in Fig. 10.9.4 and the tubes are to be expanded into the tube plates in addition to welding, except as permitted by 12.1.3.



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 12, 13 & 14

**Table 10.12.1 Thickness of plain tubes under external pressure**

Design pressure, in bar											Thickness, in mm
Outside diameter, in mm											
38	44,5	51	57	63,5	70	76	82,5	89	95	102	
—	—	—	—	—	—	—	—	—	26,9	25,2	5,89
—	—	—	—	—	—	—	26,2	24,1	22,8	21,4	5,38
—	—	—	—	—	—	24,1	22,1	20,7	19,3	17,9	4,88
—	—	—	27,6	24,8	22,8	20,7	19,3	17,9	16,6	15,9	4,47
—	29,3	25,5	22,8	20,7	18,9	17,3	15,9	14,8	13,7	12,7	4,06
26,6	22,8	20,7	17,9	15,9	14,8	13,1	12,4	11,4	10,3	9,6	3,66
20,3	16,9	14,8	13,1	12,1	11,0	9,6	8,9	8,2	7,6	6,9	3,25
14,8	12,4	10,7	9,6	8,6	7,6	—	—	—	—	—	2,95

12.1.3 For tubes of thickness greater than 6,0 mm, expanding in addition to welding is not required if a recessed weld of depth not less than the tube thickness is provided.

### Section 13 Tubes welded at both ends and bar stays for cylindrical boilers

#### 13.1 Loads on tubes welded at both ends and bar stays

13.1.1 Each tube or bar stay is to be designed to carry its due proportion of the load on the plates which it supports.

13.1.2 For a tube or bar stay, the net area to be supported is to be the area, in mm<sup>2</sup>, enclosed by the lines bisecting at right angles the lines joining the stay and the adjacent points of support, less the area of any tubes or stays enclosed. In the case of a tube or bar stay in the boundary rows, the support afforded by the flat plate margin, where applicable, should be taken into account. Where flat margins overlap stays are not required.

13.1.3 The thickness of tubes welded at both ends to tube plates is to be such that the longitudinal stress due to the flat plate loading does not exceed 70 N/mm<sup>2</sup>.

13.1.4 Tubes may be welded into the boiler after post-weld heat treatment has been carried out.

13.1.5 The permissible longitudinal stress in combustion chamber bar stays or similar stays where an end is heated by flame, is not to exceed 70 N/mm<sup>2</sup>, and the diameter of this type of bar stay is not to be less than 19 mm.

13.1.6 The permissible longitudinal stress in longitudinal bar stays not subject to heating, is not to exceed 20 per cent of the minimum specified tensile strength, in N/mm<sup>2</sup>, and the diameter of this type of bar stay is not to be less than 25 mm.

### Section 14 Construction

#### 14.1 Access arrangements

14.1.1 In watertube boilers, manholes are to be provided in all drums of sufficient size to allow access for internal examination and cleaning, and for fitting and expanding the tubes. In the case of headers for water walls, superheaters or economizers, and of drums which are too small to permit entry, sight holes or mudholes sufficiently large and numerous for these purposes are to be provided.

14.1.2 Cylindrical boilers are to be provided, where possible with means for ingress to permit examination and cleaning of the inner surfaces of plates and tubes exposed to flame. Where the boilers are too small to permit this, there are to be sight holes and mudholes sufficiently large and numerous to allow the inside to be satisfactorily cleaned.

14.1.3 Where the cross tubes of vertical boilers are large, there is to be a sight hole in the shell opposite to one end of each tube sufficiently large to allow the tube to be examined and cleaned. These sight holes are to be in positions accessible for that purpose.

14.1.4 Manholes in cylindrical shells should preferably have their shorter axes arranged longitudinally.

14.1.5 Doors for manholes, mudholes and sight holes are to be formed from steel plate or other approved construction, and all jointing surfaces are to be machined.

14.1.6 Doors of the internal type are to be provided with spigots which have a clearance of not more than 1,5 mm all round, i.e. the axes of the opening are not to exceed those of the door by more than 3 mm. The width of the manhole gasket seat is to be not less than 16 mm.

14.1.7 Doors of the internal type for openings not larger than 230 mm x 180 mm need be fitted with one stud only, which may be forged integral with the door. Doors for openings larger than 230 mm x 180 mm are to be fitted with two studs or bolts. The strength of the attachment to the door is to be not less than the strength of the stud or bolt.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 14

14.1.8 The crossbars or dogs for doors are to be of steel.

14.1.9 For smaller circular openings in headers and similar fittings, an approved type of plug may be used.

14.1.10 Circular flat cover plates may be fitted to raised circular manhole frames not exceeding 400 mm diameter, and for an approved design pressure not exceeding 18 bar.

14.1.11 External circular flat cover plates are to be in accordance with a recognized National Standard.

### 14.2 Torispherical and semi-ellipsoidal ends

14.2.1 For typical acceptable types of attachment for dished ends to cylindrical shells, see Fig. 10.14.1.

14.2.2 Where the difference in thickness is the same throughout the circumference, the thicker plate is to be reduced in thickness by machining to a taper for a distance not less than four times the offset, so that the two plates are of equal thickness at the position of the circumferential weld. A parallel portion may be provided between the end of the taper and weld edge preparation; alternatively, if so desired, the width of the weld may be included as part of the smooth taper of the thicker plate.

14.2.3 The thickness of the plates at the position of the circumferential weld is to be not less than that of an unpierced cylindrical shell of seamless or welded construction, whichever is applicable, of the same diameter and material, see 4.1.

### 14.3 Hemispherical ends

14.3.1 Where hemispherical ends are butt welded to cylindrical shells, the thickness of the shell is to be reduced by taper to that of the end, and the centre of the hemisphere is to be so located that the entire tapered portion of the shell and the butt weld are within the hemisphere, see Fig. 10.14.2.

14.3.2 If the hemispherical end is provided with a parallel portion, the thickness of this portion is to be not less than that of a seamless or welded shell, whichever is applicable, of the same diameter and material.

### 14.4 Welded-on flanges, butt welded joints and fabricated branch pieces

14.4.1 Flanges may be cut from plates or may be forged or cast. Hubbed flanges are not to be machined from plate. Flanges are to be attached to branches by welding. Alternative methods of flange attachment will be subject to special consideration.

14.4.2 The types of welded-on flanges are to be suitable for the pressure, temperature and service for which the branches are intended.

14.4.3 Flange attachments and pressure-temperature ratings in accordance with materials and design of recognized standards will be accepted.





Fig. 10.14.1 Typical attachments of dished ends to cylindrical shells

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 14




14.4.4 Typical examples of welded-on flange connections are shown in Fig. 10.14.3(a) to (f), and limiting design conditions for the flange types are shown in Table 10.14.1. In Fig. 10.14.3  $t$  is the minimum Rule thickness of the standpipe or branch.

14.4.5 Welded-on flanges are not to be a tight fit on the branch. The maximum clearance between the bore of the flange and the outside diameter of the branch is to be 3 mm at any point, and the sum of the clearances diametrically opposite is not to exceed 5 mm.

14.4.6 Where butt welds are employed in the attachment of flange type (a), or in the construction of standpipes or branch pieces, the adjacent pieces are to be matched at the bores. This may be effected by drifting, roller expanding or machining, provided the pipe wall is not reduced below the designed thickness. If the parts to be joined differ in wall thickness, the thicker wall is to be gradually tapered to that of the thinner at the butt joint.

14.4.7 Welding may be carried out by means of the shielded metal arc, inert gas metal arc, oxy-acetylene or other approved process, but in general, oxy-acetylene welding is suitable only for flange type (a) and is not to be applied to branches exceeding 100 mm diameter or 9,5 mm thick. The welding is to be carried out in accordance with the appropriate paragraphs of Chapter 17.

14.4.8 Threaded sleeve joints complying with Ch 12.2.8.1 may be used on the steam and water piping of small oil fired package boilers of the once through coil type, used for auxiliary or domestic purposes, where the feed pump capacity limits the output.



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 14

**Table 10.14.1 Limiting design conditions for flanges**

Flange type	Maximum pressure	Maximum temperature °C	Maximum pipe o.d. mm	Minimum pipe bore mm
(a)	Pressure-temperature ratings to be in accordance with a recognized standard	No restriction	No restriction	No restriction
(b)		No restriction	168,3 for alloy steels*	No restriction
(c)		No restriction	168,3 for alloy steels*	75
(d)		425	No restriction	No restriction
(e)		425	No restriction	75
(f)		425	No restriction	No restriction

\* No restriction for carbon steels

14.4.9 Socket weld joints are not to be used where fatigue, severe erosion, crevice corrosion or stress corrosion is expected to occur, for example, blow down, drain, scum and chemical dosing connections.

### 14.5 Welded attachments to pressure vessels


14.5.1 Unless the actual thickness of the shell or end is at least twice that required by calculation for a seamless shell or end, whichever is applicable, doubling plates with well rounded corners are to be fitted in way of attachments such as lifting lugs, supporting brackets and feet, to minimize load concentrations on pressure shells and ends. Compensating plates, pads, brackets and supporting feet are to be bedded closely to the surface before being welded, and are to be provided with a 'tell-tale' hole not greater than 9,5 mm in diameter, open to the atmosphere to provide for the release of entrapped air during heat treatment of the vessel, or as a means of indicating any leakage during hydraulic testing and in service, see Chapter 17.

14.5.2 For acceptable methods of attaching standpipes, branches, compensating plates and pads, see Fig. 10.14.4. Alternative methods of attachment may be accepted provided details are submitted for consideration.

14.5.3 Where fillet welds are used to attach standpipes or set-in pads, there are to be equal sized welds both inside and outside the vessel, see Fig 10.14.4(a) and (l). The leg length of each of the fillet welds is to be not less than 1,4 times the actual thickness of the thinner of the parts being joined.

### 14.6 Fitting of tubes in water tube boilers

14.6.1 The tube holes in drums or headers are to be formed in such a way that the tubes can be effectively tightened in them. Where the tube ends are not normal to the tube plates, there is to be a neck or belt of parallel seating of at least 13 mm in depth, measured in a plane through the axis of the tube at the holes. Where the tubes are practically normal to their plates, this parallel seating is to be not less than 9,5 mm in depth.



14.6.2 Tubes are to be carefully fitted in the tube holes and secured by means of welding, expanding and belling or by other approved methods. Tubes are to project through the neck or belt of parallel seating by at least 6 mm and where they are secured from drawing out by means of bellmouthing only, the included angle of belling is to be not less than 30°.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 15

### Section 15 Mountings and fittings for cylindrical and vertical boilers, steam generators, pressurized thermal liquid and pressurized hot water heaters

#### 15.1 General

15.1.1 Valves over 38 mm diameter are to be fitted with outside screws, and the covers are to be secured by bolts or studs. All valves are to be arranged to shut with a right-hand (clockwise) motion of the wheels.

15.1.2 All valves and cocks connected to the boiler are to be such that it is seen without difficulty whether they are open or shut. Where boiler mountings are secured by studs, the studs are to have a full thread holding in the plate for a length of at least one diameter.

15.1.3 Where a superheater is fitted which can be shut-off from the boiler, it is to be provided with a separate safety valve fitted with easing gear. The valve as regards construction is to comply with the regulations for ordinary safety valves, but the easing gear may be fitted to be workable from the stokehold only. The superheater is also to be fitted with a drain valve or cock to free it from water when necessary.

15.1.4 Safety valve chests and other boiler and superheater mountings subjected to pressures exceeding 13,0 bar or to steam temperatures exceeding 220°C, and boiler blow-down fittings, are to be made of steel or other approved material.

#### 15.2 Safety valves

15.2.1 Boilers and steam generators are to be fitted with not less than two safety valves, each having a minimum internal diameter of 25 mm, but those having a total heating surface of less than 50 m<sup>2</sup> may have one valve not less than 50 mm diameter. Small oil fired package boilers of the once through coil type used for auxiliary or domestic purposes, where the feed pump capacity limits the output, may have one safety valve not less than 19 mm internal diameter, or two safety valves with internal diameters not less than 16 mm, provided the capacity is in accordance with 15.2.11.

15.2.2 The valves, spindles, springs and compression screws are to be so encased and locked or sealed that the safety valves and pilot valves, after setting to the working pressure, cannot be tampered with or overloaded in service.

15.2.3 Valves are to be so designed that in the event of fracture of springs they cannot lift out of their seats.

15.2.4 Easing gear is to be provided for lifting the safety valves and is to be operable by mechanical means at a safe position from the boiler or engine room platforms.

15.2.5 Safety valves are to be made with working parts having adequate clearances to ensure complete freedom of movement.

15.2.6 Valve seats are to be effectively secured in position. Any adjusting devices which control discharge capacity are to be positively secured so that the adjustment will not be affected when the safety valves are dismantled at surveys.

15.2.7 All the safety valves of each boiler and steam generator may be fitted in one chest, which is to be separate from any other valve chest and is to be connected directly to the shell by a strong and stiff neck, the passage through which is to be of cross-sectional area not less than the aggregate area of the safety valves in the chest in the case of full lift valves, and one-half of that area in the case of other valves. For the meaning of aggregate area, see 15.2.11.

15.2.8 Each safety valve chest is to be drained by a pipe fitted to the lowest part and led with a continuous fall to the bilge or to a tank, clear of the boilers. No valves or cocks are to be fitted to these drain pipes. It is recommended that the bore of the drain pipes be not less than 19 mm.

15.2.9 Safety valves for shell type exhaust gas steaming economizers are to incorporate fail safe features which will ensure operation of the valve even with solid matter deposits on the valve and guide. Alternatively, a bursting disc discharging to a suitable waste steam pipe is to be fitted. These emergency devices are to function at a pressure not exceeding 1,5 times the economizer approved design pressure. Full particulars of the proposed arrangements are to be submitted for consideration.

15.2.10 Where the receiver is fitted with safety valves to relieve the steam output of the economizer and the economizer cannot be isolated from the receiver the requirements of 15.2.9 may be waived.

15.2.11 The designed discharge capacities of the safety valves on each boiler and steam generator are to be found from the following formulae:

Saturated steam safety valves:

$$E = \frac{AC(p + 1,03)}{98,1}$$

Superheated steam safety valves:

$$E = \frac{AC(p + 1,03)}{98,1} \sqrt{\frac{V_S}{V_H}}$$

where

- $p$  = set pressure, in bar gauge
- $A$  = for ordinary, high lift or improved high lift safety valves, the aggregate area, in mm<sup>2</sup>, of the orifices through the seatings of the valves, neglecting the area of guides and other obstructions
- = for full lift safety valves, the net aggregate area, in mm<sup>2</sup>, through the seats after deducting the area of the guides or other obstructions when the valves are fully lifted

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 15

- $C$  = 4,8 for valves of ordinary type having a minimum lift of  $\frac{D}{24}$   
 = 7,2 for valves of high lift type, having a minimum lift of  $\frac{D}{16}$   
 = 9,6 for valves of improved high lift type having a minimum lift of  $\frac{D}{12}$   
 = 19,2 for valves of full lift type having a minimum lift of  $\frac{D}{4}$

$D$  = bore of valve seat, in mm

$E$  = the maker's specified peak load evaporation, in kg/hour (including all evaporation from water walls, integral, or steaming economizers and other heating surfaces in direct communication with the boiler)

$V_H$  = specific volume of superheated steam ( $\text{m}^3/\text{kg}$ )

$V_S$  = specific volume of saturated steam ( $\text{m}^3/\text{kg}$ ).

15.2.12 When the discharge capacity of a safety valve of approved design has been established by type tests, carried out in the presence of the Surveyors or by an independent authority recognized by LR, on valves representative of the range of sizes and pressures intended for marine application, consideration will be given to the use of a constant higher than  $C = 19,2$ , based on 90 per cent of the measured capacity up to a maximum of  $C = 45$  for full lift safety valves.

15.2.13 Pressurized thermal liquid and pressurized hot water heaters are to be provided with a safety relief device.

### 15.3 Waste steam pipes

15.3.1 For ordinary, high lift and improved high lift type valves, the cross-sectional area of the waste steam pipe and passages leading to it is to be at least 10 per cent greater than the aggregate area of the safety valves as used in the formulae in 15.2.11. For full lift and other approved valves of high discharge capacity, the cross-sectional area of the waste steam pipe and passages is to be not less than 0,1C times the aggregate valve area.

15.3.2 The cross-sectional area of the main waste steam pipe is to be not less than the combined cross-sectional areas of the branch waste steam pipes leading thereto from the boiler safety valves.

15.3.3 Waste steam pipes are to be led to the atmosphere and are to be adequately supported and provided with suitable expansion joints, bends or other means to relieve the safety valve chests of undue loading.

15.3.4 The scantlings of waste steam pipes and silencers are to be suitable for the maximum pressure to which the pipes may be subjected in service, and in any case not less than 10 bar.

15.3.5 Silencers fitted to waste steam pipes are to be so designed that the clear area through the baffle plates is not less than that required for the pipes.

15.3.6 The safety valves of each exhaust gas heated economizer and exhaust gas heated boiler which may be used as an economizer are to be provided with entirely separate waste steam pipes.

15.3.7 External drains and exhaust steam vents to atmosphere are not to be led to waste steam pipes.

15.3.8 It is recommended that a scale trap and means for cleaning be provided at the base of each waste steam pipe.

### 15.4 Adjustment and accumulation tests

15.4.1 All safety valves are to be set under steam to a pressure not greater than the approved pressure of the boiler. As a working tolerance the setting is acceptable provided the valves lift at not more than 103 per cent of the approved design pressure. During a test of 15 minutes with the stop valves closed and under full firing conditions the accumulation of pressure is not to exceed 10 per cent of the design pressure. During this test no more feed water is to be supplied than is necessary to maintain a safe working water level.

### 15.5 Stop valves

15.5.1 One main stop valve is to be fitted to each boiler and secured directly to the shell. There are to be as few auxiliary stop valves as possible so as to avoid piercing the boiler shell more than is absolutely necessary.

15.5.2 Where two or more boilers are connected together:

- Stop valves of self-closing or non-return type are to be fitted.
- Essential services are to be capable of being supplied from at least two boilers.

### 15.6 Water level indicators

15.6.1 Every boiler designed to contain water at a specified level is to be fitted with at least two means for indicating its water level, at least one of which is to be a direct reading gauge glass. The other means is to be either an additional gauge glass or an approved equivalent device. The required water level indicators are to be independent of each other.

15.6.2 Where a pair of gauge glasses are set at different levels to provide an extended range of water level indication they will only be considered as one water level indicator.

15.6.3 An approved equivalent device for level indication may derive its level input signal from one of the low water level detection systems required by 15.7.1 provided that in the event of a power supply failure to that system an alarm is initiated and the oil fuel supply to the burners, or any other fuel used to fire the boiler, is automatically shut-off. The fuel supply shut-off will only be required if the power supply failure

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 15 &amp; 16

results in the direct reading gauge glass being the only functioning water level indicator.

15.6.4 The water gauges are to be readily accessible and placed so that the water level is clearly visible. The lowest visible parts of water gauges are to be situated at the lowest safe working level.

15.6.5 The level of the highest part of the effective heating surfaces, e.g. combustion chamber top of a horizontal boiler and the furnace crown of a vertical boiler, is to be clearly marked in a position adjacent to the glass water gauge.

15.6.6 The cocks of all water gauges are to be operable from positions free from danger in the event of the glass breaking.

### 15.7 Low water level fuel shut-off and alarm

15.7.1 Every fired boiler designed to contain water at a specified level is to be fitted with two systems of water level detection which are to be independent of each other, and which will operate an alarm and shut-off automatically the fuel supply to the burners, or any other fuel used to fire the boiler, when the water level falls to a predetermined low level. These level detectors, in addition, may be used for other functions, e.g. high level alarm, feed pump control, etc.

### 15.8 Feed check valves

15.8.1 Two feed check and stop valves, connected to separate feed lines, are to be provided for all main and auxiliary boilers which are required for essential services. The feed check and stop valves may be connected to a single standpipe at the shell. In the case of steam/steam generators one feed check valve is acceptable provided steam for essential services is simultaneously available from another source.

### 15.9 Pressure gauges

15.9.1 Each boiler is to be provided with a separate steam pressure gauge.

15.9.2 The gauges are to be placed where they are easily read.

### 15.10 Blow-down and scum valves

15.10.1 Each boiler is to be fitted with at least one blow-down valve.

15.10.2 The blow-down valve is to be attached, wherever practicable, direct to the lower part of the boiler. Where it is not practicable to attach the blow-down valve directly, a steel pipe supported from the boiler may be fitted between the boiler and valve.

15.10.3 The blow-down valve and its connections to the sea need not be more than 38 mm, and is to be not less than 19 mm internal diameter. For cylindrical boilers the size of the valve may be generally 0,0085 times the diameter of the boiler.

15.10.4 Blow-down valves and scum valves (where the latter are fitted) of two or more boilers may be connected to one common discharge, but where thus arranged there are to be screw-down non-return valves fitted for each boiler to prevent the possibility of the contents of one boiler passing to another.

15.10.5 For blow-down valves or cocks on the ship's side and attachments, see Ch 13,2.

### 15.11 Salinometer valve or cock

15.11.1 Each boiler is to be provided with a salinometer valve or cock secured direct to the boiler in a convenient position. The valve or cock is not to be on the water gauge standpipe.

## Section 16 Mountings and fittings for water tube boilers

### 16.1 General

16.1.1 Mountings and fittings not mentioned in this Section are to be in accordance with the requirements in Section 15.

### 16.2 Safety valves

16.2.1 Water tube boilers are to be fitted with not less than two safety valves of area and design in general accordance with the requirements of 15.2.

16.2.2 Each saturated steam drum and each superheater are to be provided with at least one safety valve.

16.2.3 Where the superheater forms an integral part of the boiler, the relieving capacity of the superheater safety valve(s), based on the reduced pressure at the superheater outlet, may be included as part of the total relieving capacity required for the boiler. As some National Authorities limit the proportion of the superheater safety valve relieving capacity which may be credited towards the total capacity for the boiler, builders should give attention to any relevant Statutory Requirements of the National Authority of the country in which the ship is to be registered.

16.2.4 The boiler and superheater valves are to be so disposed and proportioned between saturated steam drum and superheater outlet that the superheater will be protected from overheating under all service conditions, including an emergency stop of the ship at full power.

# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Section 16

16.2.5 Where it is proposed to fit full bore safety valves operated by independent pilot valves, the arrangements are to be submitted for consideration. The pipes connecting pilot valves and main valves are to be of ample bore and wall thickness to minimize the possibility of obstruction and damage.

16.2.6 Where it is impracticable to attach safety valves directly to the superheater, the valves are to be located as near as possible thereto and fitted to a branch piece connected to the superheater outlet pipe.

16.2.7 In high temperature installations the drains from safety valves are to be led to a tank or other place where high temperature steam can be safely discharged.

### 16.3 Safety valve settings

16.3.1 All boiler and superheater safety valves are to be set under steam to their respective working pressures, which are not to be greater than the approved design pressure of the boiler. As a working tolerance the setting is acceptable provided the valves lift at not more than 103 per cent of the approved pressure.

16.3.2 In the setting of superheater safety valves, allowance is to be made for the pressure drop through the superheater so that under discharge conditions the pressure in the boiler will not exceed the approved boiler pressure.

16.3.3 In no case is the superheater safety valve setting to exceed by more than three per cent the pressure for which the steam piping is approved.

### 16.4 Waste steam pipes

16.4.1 The waste steam pipe and passages leading to it from the safety valves are to be in general accordance with the requirements of 15.3.

16.4.2 In installations operating with a high degree of superheat, consideration is to be given to the high temperatures which waste steam pipes, silencers and surrounding spaces will attain when the superheater safety valves are blowing during accumulation tests and in service, adequate protection against heat effects is to be provided to the Surveyor's satisfaction.

16.4.3 Waste steam pipes are to be led well clear of electric cables and any parts or structures sensitive to heat or likely to distort; the pipes are to be insulated where necessary. In these installations each boiler should have a separate waste steam pipe system to atmosphere, with supporting and expansion arrangements such that no direct loading is imposed on the safety valve chests.

### 16.5 Accumulation tests

16.5.1 Tests for accumulation of pressure are to be carried out with the stop valve closed and under full firing conditions for a period not exceeding seven minutes. The accumulation is not to exceed 10 per cent of the design pressure.

16.5.2 Where accumulation tests might endanger the superheaters, consideration will be given in cases of fired boilers to the omission of these tests, provided that application is made when the boiler plan and sizes of safety valves are submitted for approval, and that the safety valves are of an approved type for which the capacity has been established by test in the presence of the Surveyors or an approved independent authority, or for which LR is satisfied, by long experience of accumulation tests, that the capacity is adequate. When it is agreed to waive accumulation tests, it will be required that the valve makers provide a certificate for each safety valve, stating its rated capacity at the approved working conditions of the boilers and that the boiler makers provide a certificate for each boiler stating its maximum evaporation.

16.5.3 The safety valves are to be found satisfactory in operation under working conditions during the trials of the machinery on board ship.

### 16.6 Water level indicators

16.6.1 Every boiler designed to contain water at a specified level is to be fitted with at least two means for indicating its water level, at least one of which is to be a direct reading gauge glass. The other means is to be either an additional gauge glass or an approved equivalent device. The required water level indicators are to be independent of each other.

16.6.2 Where a pair of gauge glasses are set at different levels to provide an extended range of water level indication they will only be considered as one water level indicator.

16.6.3 An approved equivalent device for level indication may derive its level input signal from one of the low water level detection systems required by 16.7.1 provided that, in the event of a power supply failure to that system, an alarm is initiated and the oil fuel supply to the burners, or any other fuel used to fire the boiler, is automatically shut-off. The fuel supply shut-off will only be required if the power supply failure results in the direct reading gauge glass being the only functioning water level indicator.

16.6.4 Where a steam and water drum exceeding 4 m in length is fitted athwartships, two glass water gauges are to be fitted in suitable positions, one near each end of the drum.

16.6.5 The position of the glass water gauge of boilers in which the tubes are entirely drowned when cold is to be such that water is just showing in the glass when the water level in the steam drum is just above the top of the uppermost tubes when the boiler is cold.



# Steam Raising Plant and Associated Pressure Vessels

## Part 5, Chapter 10

Sections 16 &amp; 17

16.6.6 In boilers, the tubes of which are not entirely drowned when cold, the glass water gauges are to be placed, to the Surveyor's satisfaction, in the positions which have been found by experience to indicate satisfactorily that the water content is sufficient for safety when the boiler is worked under all service conditions.

### 16.7 Low water level fuel shut-off and alarm

16.7.1 Every fired boiler designed to contain water at a specified level is to be fitted with two systems of water level detection which are to be independent of each other, and which will operate an alarm and shut-off automatically the fuel supply to the burners when the water level falls to a predetermined low level. These level detectors may be used for other functions, e.g. high level alarm, feed pump control, etc.

16.7.2 Any proposals to depart from these requirements in the case of small auxiliary boilers will be the subject of special consideration.

16.7.3 See Pt 6, Ch 1 for requirements for control, alarm and safety systems, and additional requirements for unattended operation.

### 16.8 Feed check valves and water level regulators

16.8.1 Two feed check and stop valves, connected to separate feed lines, are to be provided for each boiler and are to be attached, wherever practicable, direct to the boiler or to an economizer which forms an integral part of the boiler.

16.8.2 Where the arrangements necessitate the use of a common inlet pipe on the economizer for both main and auxiliary feed systems, this pipe is to be as short as practicable, and the arrangements of check valves are to be such that either feed line can be effectively isolated without interruption of the feed water supply to the boiler.

16.8.3 At least one of the feed water systems is to be fitted with an approved feed water regulator whereby the water level in the boilers is controlled automatically. See Ch 14,6 for arrangements and details of boiler feed systems.

16.8.4 The feed check valves are to be fitted with efficient gearing, whereby they can be satisfactorily worked from the stokehold floor, or other convenient position.

16.8.5 Standpipes on boilers, for feed inlets, are to be designed with an internal pipe to prevent direct contact between the feed pipe and the boiler shell or end plates with the object of minimizing thermal stresses in these plates. Similar arrangements are to be provided for desuperheater and other connections where significant temperature differences occur in service.

## Section 17 Hydraulic tests

### 17.1 General

17.1.1 Boilers and pressure vessels, together with their components are to withstand the following hydraulic tests without any sign of weakness or defect.

17.1.2 Having regard to the variation in the types and design of boilers, the hydraulic test may be carried out by either of the methods indicated below:

- (a) boilers are to be tested on completion to a pressure 1,5 times the approved design pressure, or
- (b) where construction permits, all components of the boiler are to be tested on completion of the work including heat treatment to 1,5 times the design pressure. In the case of components such as drums or headers, which are to be drilled for tube holes, the test may be before drilling the tube holes, but is to be after the attachment of standpipes, stubs and similar fittings and also after heat treatment has been carried out. Where all the components have been tested as above, each completed boiler after assembly is to be tested to 1,25 times the design pressure.

### 17.2 Mountings

17.2.1 All boiler mountings are to be subjected to a hydraulic test of twice the approved design pressure with the exception of feed check valves and other mountings connected to the main feed system which are to be tested to 2,5 times the approved boiler design pressure, or twice the maximum pressure which can be developed in the feed line in normal service, whichever is greater.



# Other Pressure Vessels

# Part 5, Chapter 11

Section 1

## Section

- 1 **General requirements**
- 2 **Cylindrical shells and drums subject to internal pressure**
- 3 **Spherical shells subject to internal pressure**
- 4 **Dished ends subject to internal pressure**
- 5 **Dished ends for Class 3 pressure vessels**
- 6 **Conical ends subject to internal pressure**
- 7 **Standpipes and branches**
- 8 **Construction**
- 9 **Mountings and fittings**
- 10 **Hydraulic tests**
- 11 **Plate heat exchangers**



## Section 1

### General requirements

#### 1.1 Application

1.1.1 The requirements of this Chapter are applicable to fusion welded pressure vessels and plate heat exchangers, intended for marine purposes but not included in Chapter 10. The equations in this Chapter may be used for determining the thickness of seamless pressure vessels using a joint factor of 1,0. Seamless pressure vessels are to be manufactured and tested in accordance with the requirements of Chapter 5 of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials). For the construction and design of pressure vessels and plate heat exchangers for liquefied gas or chemical cargo applications, see the *Rules and Regulations for the Construction and Classification of Ships for the Carriage of Liquefied Gases in Bulk* (hereinafter referred to as the Rules for Ships for Liquefied Gases) or the *Rules and Regulations for the Construction and Classification of Ships for the Carriage of Liquid Chemicals in Bulk* (hereinafter referred to as the Rules for Ships for Liquid Chemicals) as applicable.

1.1.2 Where the required design criteria for pressure vessels are not indicated within this Chapter, the relevant Sections of Chapter 10 are applicable.

1.1.3 Seamless pressure vessels are to be manufactured in accordance with the requirements of the Rules for Materials where applicable.

#### 1.2 Definition of symbols

1.2.1 The symbols used in the various formulae in Sections 2 to 7 inclusive, unless otherwise stated, are defined as follows, and are applicable to the specific part of the pressure vessel under consideration:

- $d$  = diameter of hole, or opening, in mm
- $p$  = design pressure, see 1.3, in bar
- $r_i$  = inside knuckle radius, in mm
- $r_o$  = outside knuckle radius, in mm
- $s$  = pitch, in mm
- $t$  = minimum thickness, in mm
- $D_i$  = inside diameter, in mm
- $D_o$  = outside diameter, in mm
- $J$  = joint factor applicable to welded seams, see 1.9, or ligament efficiency between tube holes (expressed as a fraction, see Ch 10,2.2)
- $R_i$  = inside radius, in mm
- $R_o$  = outside radius, in mm
- $T$  = design temperature, in °C
- $\sigma$  = allowable stress, see 1.8, in N/mm<sup>2</sup>.

1.2.2 Where reference is made to calculated or actual plate thickness for the derivation of other values, these thicknesses are to be minus the standard Rule corrosion allowance of 0,75 mm, if not so stated.

#### 1.3 Design pressure

1.3.1 The design pressure is the maximum permissible working pressure, and is to be not less than the highest set pressure of any relief valve.

1.3.2 Calculations made to determine the scantlings of the pressure parts are to be based on the design pressure, adjusted where necessary to take account of pressure variations corresponding to the most severe operational conditions.

1.3.3 It is desirable that there should be a margin between the normal pressure at which the pressure vessel operates and the lowest pressure at which any relief valve is set to lift, to prevent unnecessary lifting of the relief valve.

#### 1.4 Metal temperature

1.4.1 The metal temperature,  $T$ , used to evaluate the allowable stress,  $\sigma$ , is to be taken as the actual metal temperature expected under operating conditions for the pressure part concerned, and is to be stated by the manufacturer when plans of the pressure parts are submitted for consideration.

1.4.2 The design temperature,  $T$ , for calculation purposes is to be not less than 50°C.

#### 1.5 Classification of fusion welded pressure vessels

1.5.1 For Rule purposes, pressure vessels are graded as Class 1 where the shell thickness exceeds 38 mm.

# Other Pressure Vessels

# Part 5, Chapter 11

Section 1

1.5.2 For Rule purposes, pressure vessels are graded as Class 2/1 and Class 2/2 if they comply with the following conditions:

- (a) where the design pressure exceeds 17,2 bar, or
- (b) where the metal temperature exceeds 150°C, or
- (c) where the design pressure, in bar, multiplied by the actual thickness of the shell, in mm, exceeds 157, or
- (d) where the shell thickness does not exceed 38 mm.

1.5.3 For Rule purposes, Class 3 pressure vessels are to have a maximum shell thickness of 16 mm, and are pressure vessels not included in Classes 1, 2/1 or 2/2.

1.5.4 Pressure vessels which are constructed in accordance with Classes 2/1, 2/2 or 3 standards (as indicated above) will, if manufactured in accordance with the requirements of superior Class, be approved with the scantlings appropriate to that Class.

1.5.5 Pressure vessels which only have circumferential fusion welded seams, will be considered as seamless with no Class being assigned. Preliminary weld procedure tests and non-destructive examination for the circumferential seam welds should be carried out for the equivalent Class as determined by 1.5.1, 1.5.2 and 1.5.3.

1.5.6 In special circumstances relating to service conditions, materials, operating temperature, the carriage of dangerous gases and liquids, etc., it may be required that certain pressure vessels be manufactured in accordance with the requirements of a superior Class.

1.5.7 Heat treatment, non-destructive and routine tests where required, for the four Classes of fusion welded pressure vessel are indicated in Table 11.1.1. Details of these requirements are given in Chapter 17.

1.5.8 For a full definition of Classes of pressure vessels relating to boilers and associated pressure vessels, see Ch 10,1.

## 1.6 Plans

1.6.1 Plans of pressure vessels are to be submitted in triplicate for consideration where all the conditions in (a) or (b) are satisfied:

- (a) The vessel contains vapours or gases, e.g. air receivers, hydrophore or similar vessels and gaseous CO<sub>2</sub> vessels for fire-fighting, and

$$pV > 600$$

$$p > 1$$

$$V > 100$$

$$V = \text{volume (litres) of gas or vapour space}$$

- (b) The vessel contains liquefied gases, for fire-fighting or flammable liquids, and

$$p > 7$$

$$V > 100$$

$$V = \text{volume (litres)}$$

$p$  is as defined in 1.2.1.

1.6.2 Plans of full constructional features of the vessel and dimensional details of the weld preparations for longitudinal and circumferential seams and attachments, together with particulars of the welding consumables and of the mechanical properties of the materials, are to be submitted before construction is commenced.

## 1.7 Materials

1.7.1 Materials used in the construction of Class 1, 2/1 and 2/2 pressure vessels are to be manufactured, tested and certified in accordance with the requirements of the Rules for Materials. Materials used in the construction of Class 3 pressure vessels may be in accordance with the requirements of an acceptable national or international specification. The manufacturer's certificate will be accepted in lieu of LR's material certificate for such materials.

1.7.2 The specified minimum tensile strength of carbon and carbon-manganese steel plates, pipes, forgings and castings is to be within the general limits of 340 to 520 N/mm<sup>2</sup>.

1.7.3 The specified minimum tensile strength of low alloy steel plates, pipes, forgings and castings is to be within the general limits of 400 to 500 N/mm<sup>2</sup>, and pressure vessels made in these steels are to be either seamless or Class 1 fusion welded.

1.7.4 Where it is proposed to use materials other than those specified in the Rules for Materials, details of the chemical compositions, heat treatment and mechanical properties are to be submitted for approval. In such cases, the values of the mechanical properties used for deriving the allowable stress are to be subject to agreement by Lloyd's Register (hereinafter referred to as LR).

**Table 11.1.1 Heat treatment, non-destructive examination and testing requirements**

Class	Radiographic examination	Heat treatment	Routine weld tests	Hydraulic test
1	Required see Chapter 17	see Chapter 17	Required	Required
2/1	Spot required see Chapter 17	see Chapter 17	Required	Required
2/2	—	see Chapter 17	Required	Required
3	—	—	—	Required

# Other Pressure Vessels

# Part 5, Chapter 11

Sections 1 & 2

## 1.8 Allowable stress

1.8.1 The term 'allowable stress',  $\sigma$ , is the stress to be used in the formulae for the calculation of scantlings of pressure parts.

1.8.2 The allowable stress,  $\sigma$ , is to be the lowest of the following values:

$$\sigma = \frac{E_t}{1,5} \quad \sigma = \frac{R_{20}}{2,7} \quad \sigma = \frac{S_R}{1,5}$$

where

$E_t$  = specified minimum lower yield stress or 0,2 per cent proof stress at temperature,  $T$ , for carbon and carbon-manganese steels. In the case of austenitic steels, the 1,0 per cent proof stress at temperature,  $T$ , is to be used

$R_{20}$  = specified minimum tensile strength at room temperature

$S_R$  = average stress to produce rupture in 100 000 hours at temperature,  $T$

$T$  = metal temperature, see 1.4.

1.8.3 The allowable stress for steel castings is to be taken as 80 per cent of the value determined by the method indicated in 1.8.2 using the appropriate values for cast steel.

1.8.4 Where steel castings, which have been tested in accordance with the Rules for Materials are also subjected to non-destructive tests, consideration will be given to increasing the allowable stress using a factor up to 90 per cent in lieu of the 80 per cent referred to in 1.8.3. Particulars of the non-destructive test proposals are to be submitted for consideration.

## 1.9 Joint factors

1.9.1 The following joint factors are to be used in the equations in Sections 2 to 6, where applicable. Fusion welded pressure parts are to be made in accordance with Chapter 17.

Class of pressure vessel	Joint factor
Class 1	1,0
Class 2/1	0,85
Class 2/2	0,75
Class 3	0,60

1.9.2 The longitudinal joints for all Classes of vessels are to be butt joints. Circumferential joints for Class 1 vessels are also to be butt welds. Circumferential joints for Classes 2/1, 2/2 and 3 vessels should also be butt joints with the following exceptions:

- Circumferential joints for Classes 2/1, 2/2 and 3 vessels may be of the joggle type provided neither plate at the joints exceeds 16 mm thickness.
- Circumferential joints for Class 3 vessels may be of the lap type provided neither plate at the joint exceeds 16 mm thickness nor the internal diameter of the vessel exceeds 610 mm.

For typical acceptable methods of attaching flat ends, see Fig. 10.8.2 and Fig. 10.9.1 in Chapter 10.

For typical acceptable methods of attaching dished ends, see Fig 11.8.1.

1.9.3 Where a pressure vessel is to be made of alloy steel, particulars of the welding consumables to be used, including typical mechanical properties and chemical composition of the deposited weld metal, are to be submitted for approval.

## 1.10 Pressure parts of irregular shape

1.10.1 Where pressure parts are of such irregular shape that it is impracticable to design their scantlings by the application of the formulae in Sections 2 to 7, the suitability of their construction is to be determined by hydraulic proof test of a prototype or by an agreed alternative method.

## 1.11 Adverse working conditions

1.11.1 Where working conditions are adverse, special consideration may require to be given to increasing the scantlings derived from the formulae. In this connection, where necessary, account should also be taken of any excess of loading resulting from:

- impact loads, including rapidly fluctuating pressures,
- weight of the vessel and normal contents under operating and test conditions,
- superimposed loads, such as other pressure vessels, operating equipment, insulation, corrosion-resistant or erosion-resistant linings and piping,
- reactions of supporting lugs, rings, saddles or other types of supports, or
- the effect of temperature gradients on maximum stress.

## Section 2 Cylindrical shells and drums subject to internal pressure

### 2.1 Minimum thickness

2.1.1 The minimum thickness,  $t$ , of a cylindrical shell is to be determined by the following formula:

$$t = \frac{p R_i}{10\sigma J - 0,5p} + 0,75 \text{ mm}$$

where

$t$ ,  $p$ ,  $R_i$  and  $\sigma$  are as defined in 1.2

$J$  = the joint factor of the longitudinal joints (expressed as a fraction). See 1.9 in the case of seamless shells clear of openings  $J = 1,0$ .

2.1.2 The formula in 2.1.1 is applicable only where the resulting thickness does not exceed half the internal radius, i.e. where  $R_o$  is not greater than  $1,5R_i$ .

2.1.3 Irrespective of the thickness determined by the formula in 2.1.1,  $t$  is to be not less than  $3 + \frac{D_i}{1500}$  mm, where

$D_i$  is as defined in 1.2. The minimum thickness permitted for vessels manufactured in corrosion resistant steels will be the subject of special consideration.

# Other Pressure Vessels

# Part 5, Chapter 11

Sections 2, 3 & 4

## ■ Cross-references

For efficiency of ligaments between tube holes, see Ch 10,2.2.

For compensating effect of tube stubs, see Ch 10,2.3.

For unreinforced openings, see Ch 10,2.4.

For reinforced openings, see Ch 10,2.5.

## ■ Section 3

### Spherical shells subject to internal pressure

#### 3.1 Minimum thickness

3.1.1 The minimum thickness,  $t$ , of a spherical shell is to be determined by the following formula:

$$t = \frac{p R_i}{20\sigma J - 0,5p} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$ ,  $\sigma$  and  $J$  are as defined in 1.2.

3.1.2 The formula in 3.1.1 is applicable only where the resulting thickness does not exceed half the internal radius.

3.1.3 Irrespective of the thickness determined by the formula in 3.1.1,  $t$  is to be not less than  $3 + \frac{D_i}{1500}$  mm, where

$D_i$  is as defined in 1.2. The minimum thickness permitted for vessels manufactured in corrosion resistant steels will be the subject of special consideration.

3.1.4 Openings in spherical shells requiring compensation are to comply, in general, with Ch 10,2.5, using the calculated and actual thickness of the spherical shell as applicable.

## ■ Section 4

### Dished ends subject to internal pressure

#### 4.1 Minimum thickness

4.1.1 The thickness,  $t$ , of semi-ellipsoidal and hemispherical unstayed ends and the knuckle section of torispherical ends, dished from plate, having pressure on the concave side and satisfying the conditions listed below, is to be determined by the following formula:

$$t = \frac{p D_o K}{20\sigma J} + 0,75 \text{ mm}$$

where

$t$ ,  $p$ ,  $D_o$ ,  $\sigma$  and  $J$  are as defined in 1.2

$K$  = a shape factor, see Ch 10,4.2 and Fig. 10.4.1.

4.1.2 For semi-ellipsoidal ends:

the external height,  $H \geq 0,18D_o$

where

$D_o$  = the external diameter of the parallel portion of the end, in mm.

4.1.3 For torispherical ends:

the internal radius,  $R_i \leq D_o$

the internal knuckle radius,  $r_i \geq 0,1D_o$

the internal knuckle radius,  $r_i \geq 3t$

the external height,  $H \geq 0,18D_o$ , and is determined as follows:

$$H = R_o - \sqrt{(R_o - 0,5D_o)(R_o + 0,5D_o - 2r_o)}$$

4.1.4 In addition to the formula in 4.1.1 the thickness,  $t$ , of a torispherical head, made from more than one plate, in the crown section, is to be not less than that determined by the following formula:

$$t = \frac{p R_i}{20\sigma J - 0,5p} + 0,75 \text{ mm}$$

where  $t$ ,  $p$ ,  $R_i$ ,  $\sigma$ , and  $J$  are as defined in 1.2.

4.1.5 The thickness required by 4.1.1 for the knuckle section of a torispherical head is to extend past the common tangent point of the knuckle and crown radii into the crown section for a distance not less than  $0,5\sqrt{R_i t}$  mm, before reducing to the crown thickness permitted by 4.1.4

where

$t$  = the required thickness from 4.1.1.

4.1.6 In all cases,  $H$  is to be measured from the commencement of curvature (shown in Fig. 10.4.2, in Chapter 10).

4.1.7 The minimum thickness of the head,  $t$ , is in no case to be less than  $3 + \frac{D_i}{1500}$  mm, where  $D_i$  is as defined in

1.2. The minimum thickness permitted for vessels manufactured in corrosion resistant steels will be the subject of special consideration.

4.1.8 For ends which are butt welded to the drum shell, see 1.9, the thickness of the edge of the flange for connection to the shell is to be not less than the thickness of an unpierced seamless or welded shell, whichever is applicable, of the same diameter and material and determined by 2.1.

## ■ Cross-references

For shape factors for dished ends, see Ch 10,4.2.

For dished ends with unreinforced openings, see Ch 10,4.3.

For flanged openings in dished ends, see Ch 10,4.4.

For location of unreinforced and flanged openings in dished ends, see Ch 10,4.5.

For dished ends with reinforced openings, see Ch 10,4.6 and 4.7.

## Section 5 Dished ends for Class 3 pressure vessels

### 5.1 Minimum thickness

5.1.1 As an alternative to the formula in 4.1.1, for Class 3 vessels only, the minimum thickness,  $t$ , of a torispherical unstayed end dished from plate and having pressure on the concave or convex side is to be determined by the following formula:

$$t = \frac{p R_i}{CS}$$

where

$t$ ,  $p$ , and  $R_i$  are as defined in 1.2

$C = 2,57$  for ends concave to pressure

$= 1,65$  for ends convex to pressure

$S =$  specified minimum tensile strength of plate, in N/mm<sup>2</sup>, which should be not less than 410 N/mm<sup>2</sup>.

5.1.2 The inside radius of curvature,  $R_i$ , of the end plate is to be not greater than the external diameter of the cylinder to which it is attached.

5.1.3 The inside knuckle radius,  $r_i$ , of the arc joining the cylindrical flange to the spherical surface of the end is to be not less than four times the thickness of the end plate, and in no case less than 65 mm.

5.1.4 Ends convex to pressure are not to be used for vessels exceeding 610 mm internal diameter.

5.1.5 Where the end is provided with a flanged manhole, the thickness of the end, in mm, determined by 5.1.1, is to be increased by 3 mm, and the total depth,  $H$ , of the manhole flange, measured from the outer surface of the plate on the minor axis, is to be not less than:

$$H = t_1 W$$

where

$t_1 =$  required thickness of the plate, in mm

$H =$  depth of flange, in mm

$W =$  minor axis of the manhole, in mm.

## Section 6 Conical ends subject to internal pressure

### 6.1 General

6.1.1 Conical ends and conical reducing sections, as shown in Fig. 10.5.1 in Chapter 10, are to be designed in accordance with the equations given in 6.2.

6.1.2 Connections between cylindrical shell and conical sections and ends should preferably be by means of a knuckle transition radius. Typical permitted details are shown in Fig. 10.5.1 in Chapter 10. Alternatively, conical sections and ends may be butt welded to cylinders without a knuckle radius when the change in angle of slope,  $\psi$ , between the two sections under consideration does not exceed 30°.

6.1.3 Conical ends may be constructed of several ring sections of decreasing thickness as determined by the corresponding decreasing diameter.

### 6.2 Minimum thickness

6.2.1 The minimum thickness,  $t$ , of the cylinder, knuckle and conical section at the junction and within the distance  $L$  from the junction is to be determined by the following formula:

$$t = \frac{p D_o K}{20 \sigma J} + 0,75 \text{ mm}$$

where

$t$ ,  $p$ ,  $\sigma$  and  $J$  are as defined in 1.2

$D_o =$  outside diameter, in mm of the conical section or end, see Fig. 10.5.1 in Chapter 10

$K =$  a factor, taking into account the stress in the knuckle, see Table 10.5.1 in Chapter 10.

6.2.2 If the distance of a circumferential seam from the knuckle or junction is not less than  $L$ , then  $J$  is to be taken as 1,0; otherwise  $J$  is to be taken as the weld joint factor appropriate to the circumferential seam, where

$r_i =$  inside radius of transition knuckle, in mm, which is to be taken as  $0,01 D_o$  in the case of conical sections without knuckle transition

$L =$  distance, in mm, from knuckle or junction within which meridional stresses determine the required thickness, see Fig. 10.5.1 in Chapter 10

$$= 0,5 \sqrt{\frac{D_o t}{\cos \psi}}$$

$\psi =$  difference between angle of slope of two adjoining conical sections, see Fig. 10.5.1 in Chapter 10.

6.2.3 The minimum thickness,  $t$ , of those parts of conical sections not less than a distance  $L$  from the junction with a cylinder or other conical section, is to be determined by the following formula:

$$t = \frac{p D_c}{20 \sigma J - p} \frac{1}{\cos \alpha} + 0,75 \text{ mm}$$

where

$D_c =$  inside diameter, in mm, of conical section or end at the position under consideration, see Fig. 10.5.1 in Chapter 10

$\alpha, \alpha_1, \alpha_2 =$  angle of slope of conical section (at the point under consideration) to the vessel axis, see Fig. 10.5.1 in Chapter 10.

6.2.4 The thickness of conical sections having an angle of inclination to the vessel axis of more than 75° is to be determined as for a flat plate.

# Other Pressure Vessels

# Part 5, Chapter 11

Sections 7 &amp; 8

## Section 7 Standpipes and branches

### 7.1 Minimum thickness

7.1.1 The minimum wall thickness,  $t$ , of standpipes and branches is to be not less than the greater of the two values determined by the following formulae, making such additions as may be necessary on account of bending, static loads and vibrations:

$$t = \frac{p D_o}{20\sigma + p} + 0,75 \text{ mm, or}$$

$$t = 0,015D_o + 3,2 \text{ mm}$$

where

$t$ ,  $p$ ,  $D_o$  and  $\sigma$  are defined in 1.2.

If the second formula applies, the thickness need only be maintained for a length,  $L$ , from the outside surface of the vessel, but need not extend past the first connection, butt weld or flange, where:

$$L = 3,5 \sqrt{D_o t} \text{ mm}$$

7.1.2 In no case need the wall thickness exceed the minimum shell thickness as required by 2.1, 3.1 or 4.1 as applicable.

## Section 8 Construction

### 8.1 Access arrangements

8.1.1 Pressure vessels are to be so made that the internal surfaces may be examined. Wherever practicable, the openings for this purpose are to be sufficiently large for access and for cleaning the inner surfaces.

8.1.2 Manholes in cylindrical shells should preferably have their shorter axes arranged longitudinally.

8.1.3 Doors for manholes and sightholes are to be formed from steel plate or of other approved construction, and all jointing surfaces are to be machined.

8.1.4 Doors of the internal type are to be provided with spigots which have a clearance of not more than 1,5 mm all round, i.e. the axes of the opening are not to exceed those of the door by more than 3 mm. The width of the manhole gasket seat is not to be less than 16 mm.

8.1.5 Doors of the internal type for openings not larger than 230 x 180 mm need be fitted with only one stud, which may be forged integral with the door. Doors for openings larger than 230 mm x 180 mm are to be fitted with two studs or bolts. The strength of the attachment to the door is not to be less than the strength of the stud or bolt.

8.1.6 The crossbars or dogs for doors are to be of steel.

8.1.7 External circular flat cover plates are to be in accordance with a recognized standard.

### 8.2 Torispherical and semi-ellipsoidal ends

8.2.1 For typical acceptance types of attachment for dished ends to cylindrical shells, see Fig. 11.8.1. Types (d) and (e) are to be made a tight fit in the cylindrical shell.

8.2.2 Where the difference in thickness is the same throughout the circumference, the thicker plate is to be reduced in thickness by machining to a taper for a distance not less than four times the offset, so that the two plates are of equal thickness at the position of the circumferential weld. A parallel portion may be provided between the end of the taper and the weld edge preparation; alternatively, if so desired, the width of the weld may be included as part of the smooth taper of the thicker plate.

8.2.3 The thickness of the plates at the position of the circumferential weld is to be not less than that of an unpierced cylindrical shell of seamless or welded construction, whichever is applicable, of the same diameter and material, see 2.1.

## Cross-references

For hemispherical ends, see Ch 10,14.3.


For openings in flat ends, see Ch 10,8.4.

For unstayed circular flat end plates, see Ch 10,8.4.

For welded-on flanges, butt joints and fabricated branch pieces, see Ch 10,14.4.

For welded attachments to pressure vessels, see Ch 10,14.5.





**Fig. 11.8.1**  
**Typical attachment of dished ends to cylindrical shell**

## Section 9

### Mountings and fittings

#### 9.1 General

9.1.1 Each pressure vessel or system is to be fitted with a stop valve situated as close as possible to the shell.

9.1.2 Adequate arrangements are to be provided to prevent over-pressure of any part of a pressure vessel which can be isolated. Pressure gauges are to be fitted in positions where they can be easily read.

9.1.3 Adequate arrangements are to be provided for draining and venting the separate parts of each pressure vessel.

#### 9.2 Receivers containing pressurized gases

9.2.1 Each air receiver is to be fitted with a drain arrangement at its lowest part, permitting oil and water to be blown out.

9.2.2 Each receiver which can be isolated from a relief valve is to be provided with a suitable fusible plug to discharge the contents in case of fire. The melting point of the fusible plug is to be approximately 150°C, see also 9.2.3 and 9.2.4.

9.2.3 Where a fixed system utilizing fire-extinguishing gas is fitted, to protect a machinery space containing an air receiver(s), fitted with a fusible plug, it is recommended that the discharge from the fusible plug be piped to the open deck.

9.2.4 Receivers used for the storage of air for the control of remotely operated valves are to be fitted with relief valves and not fusible plugs.

## Cross-references

For starting air pipe systems and safety fittings, see Ch 2,7.  
For mountings for liquefied gas vessels, see the Rules for Ships for Liquefied Gases.

# Other Pressure Vessels

# Part 5, Chapter 11

Sections 10 & 11

## ■ Section 10 Hydraulic tests

### 10.1 General

10.1.1 Pressure vessels covered by this Chapter are to be tested on completion to a pressure,  $p_T$ , determined by the following formula, without showing signs of weakness or defect:

$$p_T = 1,3 \frac{\sigma_{50}}{\sigma_T} \frac{t}{(t - 0,75)} p$$

but in no case is to exceed

$$= 1,5 \frac{t}{(t - 0,75)} p$$

where

$p$  = design pressure, in bar

$p_T$  = test pressure, in bar

$t$  = nominal thickness of shell as indicated on the plan, in mm

$\sigma_T$  = allowable stress at design temperature, in N/mm<sup>2</sup>

$\sigma_{50}$  = allowable stress at 50°C, in N/mm<sup>2</sup>.

### 10.2 Mountings

10.2.1 Mountings are to be subjected to a hydraulic test of twice the approved design pressure.

## ■ Section 11 Plate heat exchangers

### 11.1 General

11.1.1 Plate heat exchangers are to be classed as follows. Class 2 where either of the following conditions apply:

(a) the maximum metal design temperature is 150°C or greater, or

(b) design pressure is 17,2 bar or greater.

Class 3 in all other cases.

11.1.2 Where the design temperature is equal to or lower than minus 10°C, a higher class is to apply.

# Piping Design Requirements

# Part 5, Chapter 12

Section 1

## Section

- 1 **General**
- 2 **Carbon and low alloy steels**
- 3 **Copper and copper alloys**
- 4 **Cast iron**
- 5 **Plastics pipes**
- 6 **Valves**
- 7 **Flexible hoses**
- 8 **Hydraulic tests on pipes and fittings**

## Appendix

- 9 **Guidance notes on metal pipes for water services**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to the design and construction of piping systems, including pipe fittings forming parts of such systems.

1.1.2 The materials used for pipes, valves and fittings are to be suitable for the medium and the service for which the piping is intended.

### 1.2 Design symbols

1.2.1 The symbols used in this Chapter are defined as follows:

- $a$  = percentage negative manufacturing tolerance on thickness
- $c$  = corrosion allowance, in mm
- $d$  = inside diameter of pipe, in mm, see 1.2.3
- $e$  = weld efficiency factor, see 1.2.4
- $p$  = design pressure, in bar (kgf/cm<sup>2</sup>), see 1.3
- $p_t$  = hydraulic test pressure, in bar (kgf/cm<sup>2</sup>)
- $t$  = the minimum thickness of a straight pipe, in mm, including corrosion allowance and negative tolerance, where applicable
- $t_b$  = the minimum thickness of a straight pipe to be used for a pipe bend, in mm, including bending allowance, corrosion allowance and negative tolerance, where applicable
- $D$  = outside diameter of pipe, in mm, see 1.2.2
- $R$  = radius of curvature of a pipe bend at the centreline of the pipe, in mm
- $T$  = design temperature, in °C, see 1.4
- $\sigma$  = maximum permissible design stress, in N/mm<sup>2</sup> (kgf/cm<sup>2</sup>).

1.2.2 The outside diameter,  $D$ , is subject to manufacturing tolerances, but these are not to be used in the evaluation of formulae.

1.2.3 The inside diameter,  $d$ , is not to be confused with nominal size, which is an accepted designation associated with outside diameters of standard rolling sizes.

1.2.4 The weld efficiency factor,  $e$ , is to be taken as 1 for seamless and electric resistance and induction welded steel pipes. Where other methods of pipe manufacture are proposed, the value of  $e$  will be specially considered.

### 1.3 Design pressure

1.3.1 The design pressure,  $p$ , is the maximum permissible working pressure and is to be not less than the highest set pressure of the safety valve or relief valve.

1.3.2 In water tube boiler installations, the design pressure for steam piping between the boiler and integral superheater outlet is to be taken as the design pressure of the boiler, i.e. not less than the highest set pressure of any safety valve on the boiler drum. For piping leading from the superheater outlet, the design pressure is to be taken as the highest set pressure of the superheater safety valves.

1.3.3 The design pressure of feed piping and other piping on the discharge from pumps is to be taken as the pump pressure at full rated speed against a shut valve. Where a safety valve or other protective device is fitted to restrict the pressure to a lower value than the shut valve load, the design pressure is to be the highest set pressure of the device.

1.3.4 For design pressure of steering gear components and piping, see Ch 19,3.1.5.

### 1.4 Design temperature

1.4.1 The design temperature is to be taken as the maximum temperature of the internal fluid, but in no case is it to be less than 50°C.

1.4.2 In the case of pipes for superheated steam, the temperature is to be taken as the designed operating steam temperature for the pipeline, provided that the temperature at the superheater outlet is closely controlled. Where temperature fluctuations exceeding 15°C above the designed temperature are to be expected in normal service, the steam temperature to be used for determining the allowable stress is to be increased by the amount of this excess.

### 1.5 Classes of pipes

1.5.1 Pressure piping systems are divided into three classes for the purpose of assigning appropriate testing requirements, types of joints to be adopted, heat treatment and weld procedure.

# Piping Design Requirements

## Part 5, Chapter 12

Sections 1 &amp; 2


1.5.2 Dependent on the service for which they are intended, Class II and III pipes are not to be used for design pressure or temperature conditions in excess of those shown in Table 12.1.1. Where either the maximum design pressure or temperature exceeds that applicable to Class II pipes, Class I pipes are to be used. To illustrate this, see Fig. 12.1.1.

**Table 12.1.1 Maximum pressure and temperature conditions for Class II and III piping systems**

Piping system	Class II		Class III	
	p	T	p	T
	bar	°C	bar	°C
Steam	16,0	300	7,0	170
Thermal oil	16,0	300	7,0	150
Flammable Liquids, see Note 1	16,0	150	7,0	60
Other media	40,0	300	16,0	200
Cargo oil	40,0	300	16,0	200

NOTE

1. Flammable liquids include: oil fuel, lubricating oil and flammable hydraulic oil.
2. For grey cast iron, see also 4.2.2.



**Fig. 12.1.1 Classes of piping system**

1.5.3 In addition to the pressure piping systems in Table 12.1.1, Class III pipes may be used for open ended piping, e.g. overflows, vents, boiler waste steam pipes, open ended drains, etc.

### 1.6 Materials

1.6.1 Materials for ferrous castings and forgings of Class I and Class II piping systems are to be produced at a works approved by Lloyd's Register (hereinafter referred to as 'LR') and are in general to be tested in accordance with the Rules for Materials.

1.6.2 The manufacturer's test certificate for materials for pipes, valves and fittings of Class I and Class II piping systems will be accepted in lieu of LR's materials certificate where the maximum conditions are less than shown in Table 12.1.2.

**Table 12.1.2 Maximum conditions for pipes, valves and fittings for which manufacturer's materials test certificate is acceptable**

Material	Working temperature °C	$DN$ = nominal diameter, mm $p_w$ = working pressure, bar
Carbon and low alloy steel Spheroidal or nodular cast iron	< 300	$DN < 50$ or $p_w \times DN < 2500$
Copper alloy	< 200	$DN < 50$ or $p_w \times DN < 1500$

1.6.3 The manufacturer's test certificate for materials for ship-side valves and fittings and valves on the collision bulkhead equal to or less than 500 mm nominal diameter will be accepted in lieu of LR's materials certificate where the valves and fittings are in accordance with a recognized National Standard applicable to the intended application and are manufactured and tested in accordance with the appropriate requirements of the Rules for Materials.

### Section 2

#### Carbon and low alloy steels

##### 2.1 Carbon and low alloy steel pipes, valves and fittings

2.1.1 Materials for Class I and Class II piping systems, also for ship-side valves and fittings and valves on the collision bulkhead, are to be manufactured and tested in accordance with the appropriate requirements of the Rules for Materials, see also 1.6.

2.1.2 Materials for Class III piping systems are to be manufactured and tested in accordance with the requirements of acceptable national specifications. Pipes having forge butt welded longitudinal seams are not to be used for oil fuel systems, for heating coils in oil tanks, or for pressures exceeding 4,0 bar (4,1 kgf/cm<sup>2</sup>). The manufacturer's test certificate will be acceptable and is to be provided for each consignment of material.

# Piping Design Requirements

# Part 5, Chapter 12

Section 2

2.1.3 Steel pipes, valves and fittings may be used within the temperature limits indicated in Tables 12.2.1 and 12.2.2. Where rimming steel is used for pipes manufactured by electric resistance or induction welding processes, the design temperature is limited to 400°C, see Ch 6,3 of the Rules for Materials.

## 2.2 Wrought steel pipes and bends

2.2.1 The maximum permissible design stress,  $\sigma$ , is to be taken as the lowest of the following values:

$$\sigma = \frac{E_t}{1,6} \quad \sigma = \frac{R_{20}}{2,7} \quad \sigma = \frac{S_R}{1,6}$$

where

$E_t$  = specified minimum lower yield or 0,2 per cent proof stress at the design temperature

$R_{20}$  = specified minimum tensile strength at ambient temperature

$S_R$  = average stress to produce rupture in 100 000 hours at the design temperature

Values of the maximum permissible design stress,  $\sigma$ , obtained from the properties of the steels specified in Chapter 6 of the Rules for Materials are shown in Tables 12.2.1 and 12.2.2. For intermediate values of specified minimum strengths and temperatures, values of the permissible design stress may be obtained by interpolation.

2.2.2 Where it is proposed to use, for high temperature service, alloy steels other than those detailed in Table 12.2.2 particulars of the tube sizes, design conditions and appropriate national or proprietary material specifications are to be submitted for consideration.

2.2.3 The minimum thickness,  $t$ , of straight steel pipes is to be determined by the following formula:

$$t = \left( \frac{pD}{20\sigma e + p} + c \right) \frac{100}{100 - a} \text{ mm}$$

$$\left( t = \left( \frac{pD}{2\sigma e + p} + c \right) \frac{100}{100 - a} \text{ mm} \right)$$

where

$p$ ,  $D$ ,  $e$  and  $a$  are as defined in 1.2.1

$c$  is obtained from Table 12.2.3

$\sigma$  is defined in 2.2.1 and obtained from Table 12.2.1 or Table 12.2.2

For pipes passing through tanks, an additional corrosion allowance is to be added to take account of external corrosion; the addition will depend on the external medium and the value is to be in accordance with Table 12.2.3. Where the pipes are efficiently protected, the corrosion allowance may be reduced by not more than 50 per cent.

2.2.4 The minimum thickness,  $t_b$ , of a straight steel pipe to be used for a pipe bend is to be determined by the following formula, except where it can be demonstrated that the use of a thickness less than  $t_b$  would not reduce the thickness below  $t$  at any point after bending:

$$t_b = \left[ \left( \frac{pD}{20\sigma e + p} \right) \left( 1 + \frac{D}{2,5R} \right) + c \right] \frac{100}{100 - a} \text{ mm}$$

$$\left( t_b = \left[ \left( \frac{pD}{2\sigma e + p} \right) \left( 1 + \frac{D}{2,5R} \right) + c \right] \frac{100}{100 - a} \text{ mm} \right)$$

where

$p$ ,  $D$ ,  $R$ ,  $e$  and  $a$  are as defined in 1.2.1

$\sigma$  and  $c$  are as defined in 2.2.3. In general,  $R$  is to be not less than  $3D$ .

2.2.5 Where the minimum thickness calculated by 2.2.3 or 2.2.4 is less than that shown in Table 12.2.4, the minimum nominal thickness for the appropriate standard pipe size shown in the Table is to be used. No allowance is required for negative tolerance, or reduction in thickness due to bending on this nominal thickness. For larger diameters, the minimum thickness will be specially considered. For threaded pipes, where permitted, the minimum thickness is to be measured at the bottom of the thread.

2.2.6 For sounding pipes, except those for cargo tanks with cargo having a flash point of less than 60°C, the minimum thickness is intended to apply to the part outside the tank.

**Table 12.2.1 Carbon and carbon-manganese steel pipes**

Specified minimum tensile strength, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Maximum permissible stress, N/mm <sup>2</sup> (kgf/cm <sup>2</sup> )												
	Maximum design temperature, °C												
	50	100	150	200	250	300	350	400	410	420	430	440	450
320 (33)	107 (1091)	105 (1070)	99 (1010)	92 (938)	78 (795)	62 (632)	57 (581)	55 (561)	55 (561)	54 (551)	54 (551)	54 (551)	49 (500)
360 (37)	120 (1224)	117 (1193)	110 (1122)	103 (1050)	91 (928)	76 (775)	69 (704)	68 (693)	68 (693)	68 (693)	64 (653)	56 (571)	49 (500)
410 (42)	136 (1387)	131 (1336)	124 (1264)	117 (1193)	106 (1081)	93 (948)	86 (877)	84 (857)	79 (806)	71 (724)	64 (653)	56 (571)	49 (500)
460 (47)	151 (1540)	146 (1489)	139 (1417)	132 (1346)	122 (1244)	111 (1132)	101 (1030)	99 (1010)	98 (999)	85 (876)	73 (744)	62 (632)	53 (540)
490 (50)	160 (1632)	156 (1591)	148 (1509)	141 (1438)	131 (1336)	121 (1234)	111 (1132)	109 (1111)	98 (999)	85 (867)	73 (744)	62 (632)	53 (540)

# Piping Design Requirements

## Part 5, Chapter 12

Section 2

**Table 12.2.2 Alloy steel pipes**

Type of steel	Specified minimum tensile strength, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Maximum permissible stress, N/mm <sup>2</sup> (kgf/cm <sup>2</sup> )									
		Maximum design temperature, °C									
		50	100	200	300	350	400	440	450	460	470
1 Cr 1/2 Mo	440 (46)	159 (1621)	150 (1530)	137 (1397)	114 (1162)	106 (1081)	102 (1040)	101 (1030)	101 (1030)	100 (1020)	99 (1010)
2 1/4 Cr 1 Mo annealed	410 (42)	76 (775)	67 (683)	57 (581)	50 (510)	47 (479)	45 (459)	44 (449)	43 (438)	43 (438)	42 (428)
2 1/4 Cr 1 Mo normalized and tempered, see Note 1	490 (50)	167 (1703)	163 (1662)	153 (1550)	144 (1468)	140 (1428)	136 (1387)	130 (1326)	128 (1305)	127 (1295)	116 (1183)
2 1/4 Cr 1 Mo normalized and tempered, see Note 2	490 (50)	167 (1703)	163 (1662)	153 (1560)	144 (1468)	140 (1428)	136 (1387)	130 (1326)	122 (1244)	114 (1162)	105 (1071)
1/2 Cr 1/2 Mo 1/4 V	460 (47)	166 (1693)	162 (1652)	147 (1499)	120 (1224)	115 (1173)	111 (1132)	106 (1081)	105 (1071)	103 (1050)	102 (1040)
		Maximum design temperature, °C									
		480	490	500	510	520	530	540	550	560	570
1 Cr 1/2 Mo	440 (46)	98 (999)	97 (989)	91 (928)	76 (775)	62 (632)	51 (520)	42 (428)	34 (347)	27 (275)	22 (224)
2 1/4 Cr 1 Mo annealed	410 (42)	42 (428)	42 (428)	41 (418)	41 (418)	41 (418)	40 (408)	40 (408)	40 (408)	37 (377)	32 (326)
2 1/4 Cr 1 Mo normalized and tempered, see Note 1	490 (50)	106 (1081)	96 (979)	86 (877)	76 (775)	67 (683)	58 (591)	49 (500)	43 (438)	37 (377)	32 (326)
2 1/4 Cr 1 Mo normalized and tempered, see Note 2	490 (50)	96 (979)	88 (897)	79 (806)	72 (734)	64 (653)	56 (571)	49 (500)	43 (438)	37 (377)	32 (326)
1/2 Cr 1/2 Mo 1/4 V	460 (47)	101 (1030)	99 (1010)	97 (989)	94 (959)	82 (836)	72 (734)	62 (632)	53 (540)	45 (459)	37 (377)

NOTES

- Maximum permissible stress values applicable when the tempering temperature does not exceed 750°C.
- Maximum permissible stress values applicable when the tempering temperature exceeds 750°C.

**Table 12.2.3 Values of c for steel pipes**

Piping service	c mm
Superheated steam systems	0,3
Saturated steam systems	0,8
Steam coil systems in cargo tanks	2,0
Feed water for boilers in open circuit systems	1,5
Feed water for boilers in closed circuit systems	0,5
Blow down (for boilers) systems	1,5
Compressed air systems	1,0
Hydraulic oil systems	0,3
Lubricating oil systems	0,3
Oil fuel systems	1,0
Cargo oil systems	2,0
Refrigerating plants	0,3
Fresh water systems	0,8
Sea-water systems in general	3,0

2.2.7 For air, bilge, ballast, fuel, overflow, sounding and venting pipes as listed in Table 12.2.4, where the pipes are efficiently protected against corrosion, the thickness may be reduced by not more than 1 mm.

2.2.8 The internal diameter for bilge, venting and overflow pipes listed in Table 12.2.4 is to be not less than 50 mm. The internal diameter for sounding pipes is to be not less than 32 mm.

# Piping Design Requirements

## Part 5, Chapter 12

Section 2

**Table 12.2.4 Minimum thickness for steel pipes**

External diameter, <i>D</i> , in mm	Pipes in general, in mm	Venting, overflow and sounding pipes for structural tanks, in mm	Bilge, ballast and general sea-water pipes, in mm	Bilge, air, overflow and sounding pipes through ballast and fuel tanks, ballast lines through fuel tanks and fuel lines through ballast tanks, in mm
10,2–12	1,6	—	—	—
13,5–19	1,8	—	—	—
20	2,0	—	—	—
21,3–25	2,0	—	3,2	—
26,9–33,7	2,0	—	3,2	—
38–44,5	2,0	4,5	3,6	6,3
48,3	2,3	4,5	3,6	6,3
51–63,5	2,3	4,5	4,0	6,3
70	2,6	4,5	4,0	6,3
76,1–82,5	2,6	4,5	4,5	6,3
88,9–108	2,9	4,5	4,5	7,1
114,3–127	3,2	4,5	4,5	8,0
133–139,7	3,6	4,5	4,5	8,0
152,4–168,3	4,0	4,5	4,5	8,8
177,8	4,5	5,0	5,0	8,8
193,7	4,5	5,4	5,4	8,8
219,1	4,5	5,9	5,9	8,8
244,5–273	5,0	6,3	6,3	8,8
298,5–368	5,6	6,3	6,3	8,8
406,4–457,2	6,3	6,3	6,3	8,8

NOTE  
The pipe diameters and wall thicknesses given in the Table are based on common international standards. Diameter and thickness according to other National or International Standards will be considered.

### 2.3 Pipe joints – General

2.3.1 Joints in pressure pipelines may be made by:

- Screwed-on or welded-on bolted flanges, see 2.5 and 2.6.
- Butt welds between pipes or between pipes and valve chests or other fittings, see 2.6.
- Socket weld joints, see 2.8.
- Welded sleeve joints, see 2.9.
- Threaded sleeve joints, see 2.10.
- Special types of approved joints that have been shown to be suitable for the design conditions. Details are to be submitted for consideration.

2.3.2 The dimensions and materials of flanges, gaskets and bolting, and the pressure – temperature rating of bolted flanges in pressure pipelines, are to be in accordance with national or other established standards.

2.3.3 With the welded pressure piping systems referred to in 2.3.1 it is desirable that a few flanged joints be provided at suitable positions to facilitate installation, cold 'pull up' and inspection at Periodical Surveys.

2.3.4 Piping with joints is to be adequately adjusted, aligned and supported. Supports or hangers are not to be used to force alignment of piping at the point of connection.

2.3.5 Pipes passing through, or connected to, watertight decks are to be continuous or provided with an approved bolted or welded connection to the deck or bulkhead.

2.3.6 Consideration will be given to accepting joints in accordance with a recognized National Standard which is applicable to the intended service and media conveyed.

### 2.4 Steel pipe flanges

2.4.1 Flanges may be cut from plates or may be forged or cast. The material is to be suitable for the design temperature. Flanges may be attached to the pipes by screwing and expanding or by welding. Alternative methods of flange attachment may be accepted provided details are submitted for consideration.

2.4.2 Flange attachments to pipes and pressure – temperature ratings in accordance with national or other approved standards will be accepted.


### 2.5 Screwed-on flanges

2.5.1 Where flanges are secured by screwing, as indicated in Fig. 12.2.1, the pipe and flange are to be screwed with a vanishing thread and the diameter of the screwed portion of the pipe over the thread is not to be appreciably less than the outside diameter of the unscrewed pipe. After the flange has been screwed hard home the pipe is to be expanded into the flange.

# Piping Design Requirements

## Part 5, Chapter 12

Section 2



2.5.2 The vanishing thread on a pipe is to be not less than three pitches in length, and the diameter at the root of the thread is to increase uniformly from the standard root diameter to the diameter at the top of the thread. This may be produced by suitably grinding the dies, and the flange should be tapered out to the same formation.

2.5.3 Such screwed and expanded flanges may be used for steam for a maximum design pressure of 30,0 bar (30,5 kgf/cm<sup>2</sup>) and a maximum design temperature of 370°C and for feed for a maximum design pressure of 50 bar (51 kgf/cm<sup>2</sup>).

### 2.6 Welded-on flanges, butt welded joints and fabricated branch pieces


2.6.1 The types of welded-on flanges are to be suitable for the pressure, temperature and service for which the pipes are intended.

2.6.2 Typical examples of welded-on flange attachments are shown in Fig. 12.2.2, and limiting design conditions for flange types (a) to (f) are shown in Table 12.2.5.

2.6.3 Butt welded joints are generally to be of the full penetration type and are to meet the requirements of Chapter 17.

2.6.4 Welded-on flanges are not to be a tight fit on the pipes. The maximum clearance between the bore of the flange and the outside diameter of the pipe is to be 3 mm at any point, and the sum of the clearances diametrically opposite is not to exceed 5 mm.

2.6.5 Where butt welds are employed in the attachment of flange type (a), in pipe-to-pipe joints or in the construction of branch pieces, the adjacent pieces are to be matched at the bores. This may be effected by drifting, roller expanding or machining, provided that the pipe wall is not reduced below the designed thickness. If the parts to be joined differ in wall thickness, the thicker wall is to be gradually tapered to the thickness of the thinner at the butt joint. The welding necks of valve chests are to be sufficiently long to ensure that the valves are not distorted as the result of welding and subsequent heat treatment of the joints.



2.6.6 Where backing rings are used with flange type (a) they are to fit closely to the bore of the pipe and should be removed after welding. The rings are to be made of the same material as the pipes or of mild steel having a sulphur content not greater than 0,05 per cent.

2.6.7 Branches may be attached to pressure pipes by means of welding provided that the pipe is reinforced at the branch by a compensating plate or collar or other approved means, or, alternatively, that the thickness of pipe and branch is increased to maintain the strength of the pipe. These requirements also apply to fabricated branch pieces.



# Piping Design Requirements

## Part 5, Chapter 12

Section 2


**Table 12.2.5 Limiting design conditions for flange types**

Flange type	Maximum pressure	Maximum temperature, in °C	Maximum pipe o.d., in mm	Minimum pipe bore, in mm
(a)	Pressure-temperature ratings to be in accordance with a recognized standard	No restriction	No restriction	No restriction
(b)		No restriction	168,3 for alloy steels*	No restriction
(c)		No restriction	168,3 for alloy steels*	75
(d)		425	No restriction	No restriction
(e)		425	No restriction	75
(f)		425	No restriction	No restriction
* No restriction for carbon steels				

2.6.8 Welding may be carried out by means of the shielded metal arc, inert gas metal arc, oxy-acetylene or other approved process, but in general oxy-acetylene welding is suitable only for flange type (a) and is not to be applied to pipes exceeding 100 mm diameter or 9,5 mm thick. The welding is to be carried out in accordance with the appropriate paragraphs of Chapter 17.

### 2.7 Loose flanges

2.7.1 Loose flange designs as shown in Fig. 12.2.3 may be used provided they are in accordance with a recognized National or International Standard.



2.7.2 Loose flange designs where the pipe end is flared as shown in Fig 12.2.3(b) are only to be used for water pipes and on open ended lines.

### 2.8 Socket weld joints

2.8.1 Socket weld joints may be used in Class III systems with carbon steel pipes of any outside diameter. Socket weld fittings are to be of forged steel and the material is to be compatible with the associated piping. In particular cases, socket welded joints may be permitted for piping systems of Class I and II having outside diameter not exceeding 88,9 mm. Such joints are not to be used where fatigue, severe erosion or crevice corrosion is expected to occur or where toxic media are conveyed. See also Ch 10,14.4.9.

2.8.2 The thickness of the socket weld fittings is to meet the requirements of 2.2.3 but is to be not less than 1,25 times the nominal thickness of the pipe or tube. The diametrical clearance between the outside diameter of the pipe and the bore of the fitting is not to exceed 0,8 mm, and a gap of approximately 1,5 mm is to be provided between the end of the pipe and the bottom of the socket. See also Ch 17,6.2.3.

2.8.3 The leg lengths of the fillet weld connecting the pipe to the socket weld fitting are to be such that the throat dimension of the weld is not less than the nominal thickness of the pipe or tube.

### 2.9 Welded sleeve joints

2.9.1 Welded sleeve joints may be used in Class III systems with carbon steel pipes of any outside diameter. In particular cases, welded sleeve joints may be permitted for piping systems of Class I and II having outside diameter not exceeding 88,9 mm. Such joints are not to be used where fatigue, severe erosion or crevice corrosion is expected to occur or where toxic media are conveyed.

2.9.2 Welded sleeve joints are not to be used in the following locations:

- Bilge pipes in way of deep tanks.
- Cargo oil piping outside of the cargo area for bow or stern loading/discharge.
- Air and sounding pipes passing through cargo tanks.

# Piping Design Requirements

# Part 5, Chapter 12

Section 2

2.9.3 Welded sleeve joints may be used in piping systems for the storage, distribution and utilisation of oil fuel, lubricating or other flammable oil systems in machinery spaces provided they are located in readily visible and accessible positions. See also Pt 5, Ch 14, 2.9.2.

2.9.4 Welded sleeve joints are not to be used at deck/bulkhead penetrations that require continuous pipe lengths.

2.9.5 The thickness of the sleeve is to satisfy the requirements of 2.2.3 and Table 12.2.4 but is to be not less than the nominal thickness of the pipe. The radial clearance between the outside diameter of the pipe and the internal diameter of the sleeve is not to exceed 1 mm for pipes up to a nominal diameter of 50 mm, 2 mm on diameters up to 200 mm nominal size and 3 mm for larger size pipes. The pipe ends are to be separated by a clearance of approximately 2 mm at the centre of the sleeve.

2.9.6 The sleeve material is to be compatible with the associated piping and the leg lengths of the fillet weld connecting the pipe to the sleeve are to be such that the throat dimension of the weld is not less than the nominal thickness of the pipe or tube.

2.9.7 The minimum length of the sleeve is to conform to the following formula:

$$L_{si} = 0,14D + 36 \text{ mm}$$

where

$L_{si}$  is the length of the sleeve

$D$  is defined in 1.2.1.

## 2.10 Threaded sleeve joints

2.10.1 Threaded sleeve joints, in accordance with national or other established standards, may be used with carbon steel pipes within the limits given in Table 12.2.6. Such joints are not to be used where fatigue, severe erosion or crevice corrosion is expected to occur or where flammable or toxic media is conveyed.

**Table 12.2.6 Limiting design conditions for threaded sleeve joints**

Thread type	Outside pipe diameter, in mm		
	Class I	Class II	Class III
Tapered thread	<33,7	<60,3	<60,3
Parallel thread	—	—	<60,3

## 2.11 Screwed fittings

2.11.1 Screwed fittings, including compression fittings, of an approved type may be used in piping systems for pipes not exceeding 51 mm outside diameter. Where the fittings are not in accordance with an acceptable standard then LR may require the fittings to be subjected to special tests to demonstrate their suitability for the intended service and working conditions.

## 2.12 Other mechanical couplings

2.12.1 Pipe unions, compression couplings, or slip-on joints, as shown in Fig. 12.2.4, may be used if Type Approved for the service conditions and the intended application. The Type Approval is to be based on the results of testing of the actual joints. The acceptable use for each service is indicated in Table 12.2.7 and dependence upon the Class of piping, with limiting pipe dimensions, is indicated in Table 12.2.8.

2.12.2 Where the application of mechanical joints results in a reduction in pipe wall thickness due to the use of bite type rings or other structural elements, this is to be taken into account in determining the minimum wall thickness of the pipe to withstand the design pressure.

2.12.3 Construction of mechanical joints is to prevent the possibility of tightness failure affected by pressure pulsation, piping vibration, temperature variation and other similar adverse effects occurring during operation on board.

2.12.4 Materials of mechanical joints are to be compatible with the piping material and internal and external media.

2.12.5 Mechanical joints for pressure pipes are to be tested to a burst pressure of 4 times the design pressure. For design pressures above 200 bar the required burst pressure will be specially considered.

2.12.6 In general, mechanical joints are to be of fire resistant type where required by Table 12.2.7.

2.12.7 Mechanical joints, which in the event of damage could cause fire or flooding, are not to be used in piping sections directly connected to the sea openings or tanks containing flammable fluids.

2.12.8 The mechanical joints are to be designed to withstand internal and external pressure as applicable and where used in suction lines are to be capable of operating under vacuum.

2.12.9 Generally, slip-on joints are not to be used in pipelines in cargo holds, tanks, and other spaces which are not easily accessible. Application of these joints inside tanks may only be accepted where the medium conveyed is the same as that in the tanks.

2.12.10 Unrestrained slip-on joints are only to be used in cases where compensation of lateral pipe deformation is necessary. Usage of these joints as the main means of pipe connection is not permitted.

2.12.11 Restrained slip-on joints are permitted in steam pipes on the weather decks of oil and chemical tankers to accommodate axial pipe movement, see Ch 13, 2.7.

## 2.13 Non-destructive testing

2.13.1 For details of non-destructive tests on piping systems, other than hydraulic tests, see Chapter 17.






Pipe Unions	
Welded and Brazed Types	
Compression Couplings	
Swage Type	
Press Type	
Bite Type	
Flared Type	

Fig. 12.2.4 Examples of mechanical joints (see continuation)




	Slip-on Joints
Grip Type	
Machine Grooved Type	
SlipType	

Fig. 12.2.4 Examples of mechanical joints (conclusion)

## Piping Design Requirements

## Part 5, Chapter 12

Section 2

Table 12.2.7 Application of mechanical joints

Systems	Kind of connections		
	Pipe unions	Compression couplings (6)	Slip-on joints
<b>Flammable fluids (Flash point &lt;60°)</b>			
Cargo oil lines	+	+	+5
Crude oil washing lines	+	+	+5
Vent lines	+	+	+3
<b>Inert gas</b>			
Water seal effluent lines	+	+	+
Scrubber effluent lines	+	+	+
Main lines	+	+	+2,5
Distribution lines	+	+	+5
<b>Flammable fluids (Flash point &gt; 60°)</b>			
Cargo oil lines	+	+	+5
Fuel oil lines	+	+	+2,3
Lubricating oil lines	+	+	+2,3
Hydraulic oil	+	+	+2,3
Thermal oil	+	+	+2,3
<b>Sea-water</b>			
Bilge lines	+	+	+1
Fire main and water spray	+	+	+3
Foam system	+	+	+3
Sprinkler system	+	+	+3
Ballast system	+	+	+1
Cooling water system	+	+	+1
Tank cleaning services	+	+	+
Non-essential systems	+	+	+
<b>Fresh water</b>			
Cooling water system	+	+	+1
Condensate return	+	+	+1
Non-essential system	+	+	+
<b>Sanitary/Drains/Scuppers</b>			
Deck drains (internal)	+	+	+4
Sanitary drains	+	+	+
Scuppers and discharge (overboard)	+	+	—
<b>Sounding/vent</b>			
Water tanks/Dry spaces	+	+	+
Oil tanks (f.p.> 60°C)	+	+	+2,3
<b>Miscellaneous</b>			
Starting/Control air (1)	+	+	—
Service air (non-essential)	+	+	+
Brine	+	+	+
CO <sub>2</sub> system	+	+	—
Steam	+	+	-7
<b>KEY</b> + Application is allowed — Application is not allowed			
<b>NOTES</b> 1. Inside machinery spaces of Category A – only approved fire resistant types. 2. Not inside machinery spaces of Category A or accommodation spaces. May be accepted in other machinery spaces provided the joints are located in easily visible and accessible positions. 3. Approved fire resistant types. Fire resistant type is a type of connection which, when installed in the system and in the event of failure caused by fire, the failure would not result in fire spread, flooding or the loss of an essential service. 4. Above freeboard deck only. 5. In pump rooms and open decks – only approved fire resistant types. 6. If compression couplings include any components which are sensitive to heat, they are to be of approved fire resistant type as required for slip-on joints. 7. See 2.12.11.			

# Piping Design Requirements

## Part 5, Chapter 12

Sections 2 & 3

**Table 12.2.8 Application of mechanical joints depending on class of piping**

Types of joints	Classes of piping systems		
	Class I	Class II	Class III
<b>Pipe unions</b> Welded and brazed type	+(OD ≤ 60,3 mm)	+(OD ≤ 60,3 mm)	+
<b>Compression couplings</b> Swage type Bite type Flared type Press type	– +(OD ≤ 60,3 mm) +(OD ≤ 60,3 mm) –	– +(OD ≤ 60,3 mm) +(OD ≤ 60,3 mm) –	+ + + +
<b>Slip-on joints</b> Machine grooved type Grip type Slip type	+ – –	+ + +	+ + +
<b>KEY</b> + Application is allowed – Application is not allowed			

### Section 3

### Copper and copper alloys

#### 3.1 Copper and copper alloy pipes, valves and fittings

**3.1.1** Materials for Class I and Class II piping systems, also for ship-side valves and fittings and valves on the collision bulkhead, are to be manufactured and tested in accordance with the requirements of Chapter 9 of the Rules for Materials, see also 1.6.

**3.1.2** Materials for Class III piping systems are to be manufactured and tested in accordance with the requirements of acceptable national specifications. The manufacturer's test certificate will be acceptable and is to be provided for each consignment of material.

**3.1.3** Pipes are to be seamless, and branches are to be provided by cast or stamped fittings, pipe pressings or other approved fabrications.

**3.1.4** Brazing and welding materials are to be suitable for the operating temperature and for the medium being carried. All brazing and welding are to be carried out to the satisfaction of the Surveyors.

**3.1.5** In general, the maximum permissible service temperature of copper and copper alloy pipes, valves and fittings is not to exceed 200°C for copper and aluminium brass, and 300°C for copper-nickel. Cast bronze valves and fittings complying with the requirements of Chapter 9 of the Rules for Materials may be accepted up to 260°C.

**3.1.6** The minimum thickness,  $t$ , of straight copper and copper alloy pipes is to be determined by the following formula:

$$t = \left( \frac{pD}{20\sigma + p} + c \right) \frac{100}{100 - a} \text{ mm}$$

$$\left( t = \left( \frac{pD}{2\sigma + p} + c \right) \frac{100}{100 - a} \text{ mm} \right)$$

where

$p$ ,  $D$  and  $a$  are as defined in 1.2.1

$c$  = corrosion allowance

= 0,8 mm for copper, aluminium brass, and copper-nickel alloys where the nickel content is less than 10 per cent

= 0,5 mm for copper-nickel alloys where the nickel content is 10 per cent or greater

= 0 where the media are non-corrosive relative to the pipe material

$\sigma$  = maximum permissible design stress, in N/mm<sup>2</sup> (kgf/cm<sup>2</sup>), from Table 12.3.1. Intermediate values of stresses may be obtained by linear interpolation.

**3.1.7** The minimum thickness,  $t_b$ , of a straight seamless copper or copper alloy pipe to be used for a pipe bend is to be determined by the formula below, except where it can be demonstrated that the use of a thickness less than  $t_b$  would not reduce the thickness below  $t$  at any point after bending:

$$t_b = \left[ \left( \frac{pD}{20\sigma + p} \right) \left( 1 + \frac{D}{2,5R} \right) + c \right] \frac{100}{100 - a} \text{ mm}$$

$$\left( t_b = \left[ \left( \frac{pD}{2\sigma + p} \right) \left( 1 + \frac{D}{2,5R} \right) + c \right] \frac{100}{100 - a} \text{ mm} \right)$$

where

$p$ ,  $D$ ,  $R$  and  $a$  are as defined in 1.2.1

$\sigma$  and  $c$  are as defined in 3.1.6. In general,  $R$  is to be not less than  $3D$ .

# Piping Design Requirements

## Part 5, Chapter 12

Sections 3 &amp; 4

**Table 12.3.1 Copper and copper alloy pipes**

Pipe material	Condition of supply	Specified minimum tensile strength, N/mm <sup>2</sup> (kgf/mm <sup>2</sup> )	Permissible stress, N/mm <sup>2</sup> (kgf/cm <sup>2</sup> )											
			Maximum design temperature, °C											
			50	75	100	125	150	175	200	225	250	275	300	
Copper	Annealed	220 (22)	41,2 (420)	41,2 (420)	40,2 (410)	40,2 (410)	34,3 (350)	27,5 (280)	18,6 (190)	–	–	–	–	
Aluminium brass	Annealed	320 (33)	78,5 (800)	78,5 (800)	78,5 (800)	78,5 (800)	78,5 (800)	51,0 (520)	24,5 (250)	–	–	–	–	
90/10 Copper-nickel-iron	Annealed	270 (28)	68,6 (700)	68,6 (700)	67,7 (690)	65,7 (670)	63,7 (650)	61,8 (630)	58,8 (600)	55,9 (570)	52,0 (530)	48,1 (490)	44,1 (450)	
70/30 Copper-nickel	Annealed	360 (37)	81,4 (830)	79,4 (810)	77,5 (790)	75,5 (770)	73,5 (750)	71,6 (730)	69,6 (710)	67,7 (690)	65,7 (670)	63,7 (650)	61,8 (630)	

3.1.8 Where the minimum thickness calculated by 3.1.6 or 3.1.7 is less than shown in Table 12.3.2, the minimum nominal thickness for the appropriate standard pipe size shown in the Table is to be used. No allowance is required for negative tolerance or reduction in thickness due to bending on this nominal thickness. For threaded pipes, where permitted, the minimum thickness is to be measured at the bottom of the thread.

**Table 12.3.2 Minimum thickness for copper and copper alloy pipes**

Standard pipe sizes (outside diameter), in mm			Minimum overriding nominal thickness, in mm	
			Copper	Copper alloy
8	to	10	1,0	0,8
12	to	20	1,2	1,0
25	to	44,5	1,5	1,2
50	to	76,1	2,0	1,5
88,9	to	108	2,5	2,0
133	to	159	3,0	2,5
193,7	to	267	3,5	3,0
273	to	457,2	4,0	3,5
		508	4,5	4,0

### 3.2 Heat treatment

3.2.1 Pipes which have been hardened by cold bending are to be suitably heat treated on completion of fabrication and prior to being tested by hydraulic pressure. Copper pipes are to be annealed and copper alloy pipes are to be either annealed or stress relief heat treated.

4.1.2 Spheroidal or nodular graphite iron castings for pipes, valves and fittings in Class II and Class III piping systems are to be made in a grade having a specified minimum elongation not less than 12 per cent on a gauge length of  $5,65\sqrt{S_0}$ , where  $S_0$  is the actual cross-sectional area of the test piece.

4.1.3 Castings for Class II systems, also for ship-side valves and fittings and valves on the collision bulkhead, are to be manufactured and tested in accordance with the requirements of Chapter 7 of the Rules for Materials. Castings for Class III systems are to comply with the requirements of acceptable national specifications. A manufacturer's test certificate will be accepted and is to be provided for each consignment of material for Class III systems, see also 1.6.

4.1.4 Proposals for the use of this material in Class I piping systems will be specially considered, but in no case is the material to be used in systems where the design temperature exceeds 350°C.

4.1.5 Where the elongation is less than the minimum required by 4.1.1, the material is, in general, to be subject to the same limitations as grey cast iron.

### 4.2 Grey cast iron

4.2.1 Grey cast iron pipes, valves and fittings will, in general, be accepted in Class III piping systems except as stated in 4.2.3.

4.2.2 Grey cast iron is not to be used for pipes, valves and other fittings handling media having temperatures above 220°C or for piping subject to pressure shock, excessive strains or vibrations.

## Section 4 Cast iron

### 4.1 Spheroidal or nodular graphite cast iron

4.1.1 Spheroidal or nodular graphite iron may be accepted for bilge, ballast and cargo oil piping.

# Piping Design Requirements

## Part 5, Chapter 12

Sections 4 & 5

- 4.2.3 Grey cast iron is not to be used for the following:
- Pipes for steam systems and fire extinguishing systems.
  - Pipes, valves and fittings for boiler blow-down systems and other piping systems subject to shock or vibration.
  - Ship-side valves and fittings, see Ch 13,2.5.
  - Valves fitted on the collision bulkhead, see Ch 13,3.5.
  - Bilge lines in tanks.
  - Pipes and fittings in flammable oil systems where the design pressure exceeds 7 bar or the design operating temperature is greater than 60°C.
  - Valves fitted to tanks containing flammable oil under static pressure.
  - Valve chests and fittings for starting air systems, see Ch 2,7.4.3.

4.2.4 Castings for Class III piping systems are to comply with acceptable national specifications.

### Section 5 Plastics pipes

#### 5.1 General

5.1.1 Proposals to use plastics pipes in shipboard piping systems will be considered in relation to the properties of the materials, the operating conditions, the intended service and location. Details are to be submitted for approval. Special consideration will be given to any proposed service for plastics pipes not mentioned in these Rules.

5.1.2 Attention is also to be given to the *Guidelines for the Application of Plastic Pipes on Ships* contained in IMO Resolution A.753(18).

5.1.3 Plastics pipes and fittings will, in general, be accepted in Class III piping systems. Proposals for the use of plastics in Class I and Class II piping systems will be specially considered.

5.1.4 For Class I, Class II and any Class III piping systems for which there are Rule requirements, the pipes are to be of a type which has been approved by LR.

5.1.5 For domestic and similar services where there are no Rule requirements, the pipes need not be of a type which has been approved by LR. However, the fire safety aspects as referenced in 5.4, are to be considered.

5.1.6 The use of plastics pipes may be restricted by statutory requirements of the National Authority of the country in which the ship is to be registered.

#### 5.2 Design and performance criteria

5.2.1 Pipes and fittings are to be of robust construction and are to comply with a National or other established Standard, consistent with the intended use. Particulars of pipes, fittings and joints are to be submitted for consideration.

5.2.2 The design and performance criteria of all piping systems, independent of service or location, are to meet the requirements of 5.3.

5.2.3 Depending on the service and location, the fire safety aspects are to meet the requirements of 5.4.

5.2.4 Plastics piping is to be electrically conductive when:

- (a) carrying fluids capable of generating electrostatic charges.
- (b) passing through dangerous zones and spaces, regardless of the fluid being conveyed.

Suitable precautions against the build up of electrostatic charges are to be provided in accordance with the requirements of 5.5, see also Pt 6, Ch 2,1.12.

#### 5.3 Design strength

5.3.1 The strength of pipes is to be determined by hydrostatic pressure tests to failure on representative sizes of pipe. The strength of fittings is to be not less than the strength of the pipes.

5.3.2 The nominal internal pressure,  $pN_i$ , of the pipe is to be determined by the lesser of the following:

$$pN_i \leq \frac{p_{st}}{4}$$

$$pN_i \leq \frac{p_{lt}}{2,5}$$

where

$p_{st}$  = short term hydrostatic test failure pressure, in bar

$p_{lt}$  = long term hydrostatic test failure pressure (100 000 hours), in bar

Testing may be carried out over a reduced period of time using suitable standards, such as ASTM D2837 and D1598.

5.3.3 The nominal external pressure,  $pN_e$ , of the pipe, defined as the maximum total of internal vacuum and external static pressure head to which the pipe may be subjected, is to be determined by the following:

$$pN_e \leq \frac{p_{col}}{3}$$

where

$p_{col}$  = pipe collapse pressure, in bar

The pipe collapse pressure is not to be less than 3 bar.

5.3.4 Piping is to meet these design requirements over the range of service temperature it will experience.

5.3.5 High temperature limits and pressure reductions relative to nominal pressures are to be according to a recognized standard, but in each case the maximum working temperature is to be at least 20°C lower than the minimum temperature of deflection under load of the resin or plastics material without reinforcement. The minimum heat distortion temperature is not to be less than 80°C, see also Ch 14,4 of the Rules for Materials.

5.3.6 Where it is proposed to use plastics piping in low temperature services, design strength testing is to be made at a temperature 10°C lower than the minimum working temperature.



# Piping Design Requirements

## Part 5, Chapter 12

Section 5

**Table 12.5.1 Typical temperature and pressure limits for thermoplastic pipes**

Material	Nominal pressure, bar	Maximum permissible working pressure, bar						
		–20 to 0°C	30°C	40°C	50°C	60°C	70°C	80°C
PVC	10 16		7,5 12	6 9	6			
ABS	10 16	7,5 12	7,5 12	7 10,5	6 9	7,5	6	
HDPE	10 16	7,5 12	6 9,5	6				
Abbreviations PVC Polyvinyl chloride ABS Acrylonitrile – butadiene – styrene HDPE High density polyethylene								

**Table 12.5.2 Typical temperature and pressure limits for glassfibre reinforced epoxy (GRE) and polyester (GRP) pipes**

Minimum heat distortion temperature of resin	Nominal pressure, bar	Maximum permissible working pressure, bar							
		–50 to 30°C	40°C	50°C	60°C	70°C	80°C	90°C	95°C
80°C	10	10	9	7,5	6				
	16	16	14	12	9,5				
	25	16	16	16	15				
100°C	10	10	10	9,5	8,5	7	6		
	16	16	16	15	13,5	11	9,5		
	25	16	16	16	16	16	15		
135°C	10	10	10	10	10	9,5	8,5	7	6
	16	16	16	16	16	15	13,5	11	9,5
	25	16	16	16	16	16	16	16	15

5.3.7 For guidance, typical temperature and pressure limits are indicated in Tables 12.5.1 and 12.5.2. The Tables are related to water service only. Transport of chemicals or other media is to be considered on a case by case basis.

5.3.8 The selection of plastics materials for piping is to take account of other factors such as impact resistance, ageing, fatigue, erosion resistance, fluid absorption and material compatibility such that the design strength of the piping is not reduced below that required by these Rules.

5.3.9 Design strength values may be verified experimentally or by a combination of testing and calculation methods.

### 5.4 Fire performance criteria

5.4.1 Where plastics pipes are used in systems essential to the safe operation of the ship, or for containing combustible liquids or sea-water where leakage or failure could result in fire or in the flooding of watertight compartments, the pipes and fittings are to be of a type which have been fire endurance tested in accordance with the requirements of Table 12.5.3.

5.4.2 Where a fire protective coating of pipes and fittings is necessary for achieving the fire endurance standards required, the coating is to be resistant to products likely to come into contact with the piping and be suitable for the intended application.

### 5.5 Electrical conductivity

5.5.1 Where a piping system is required to be electrically conductive for the control of static electricity, the resistance per unit length of the pipe, bends, elbows, fabricated branch pieces, etc., is not to exceed 0,1 MΩ/m, *see also* 5.2.4.

5.5.2 Electrical continuity is to be maintained across the joints and fittings and the system is to be earthed, *see also* Pt 6, Ch 2, 1.12. The resistance to earth from any point in the piping system is not to exceed 1 MΩ.

### 5.6 Manufacture and quality control

5.6.1 All materials for plastics pipes and fittings are to be approved by LR, and are in general to be tested in accordance with Ch 14,4 of the Rules for Materials.

# Piping Design Requirements

## Part 5, Chapter 12

Section 5

**Table 12.5.3 Fire endurance requirements** (see continuation)

	Location										
	A	B	C	D	E	F	G	H	I	J	K
Piping systems	Machinery spaces of Category A	Other machinery spaces and pump rooms	Cargo pump rooms	Ro-Ro cargo holds	Other dry cargo holds	Cargo tanks	Fuel oil tanks	Ballast water tanks	Cofferdams void spaces pipe tunnel and ducts	Accommodation service and control spaces	Open decks
CARGO (FLAMMABLE CARGOES f.p. ≤ 60°C)											
1 Cargo lines	N/A	N/A	L1	N/A	N/A	0	N/A	0 <sup>10</sup>	0	N/A	L1 <sup>2</sup>
2 Crude oil washing lines	N/A	N/A	L1	N/A	N/A	0	N/A	0 <sup>10</sup>	0	N/A	L1 <sup>2</sup>
3 Vent lines	N/A	N/A	N/A	N/A	N/A	0	N/A	0 <sup>10</sup>	0	N/A	X
INERT GAS											
4 Water seal effluent line	N/A	N/A	0 <sup>1</sup>	N/A	N/A	0 <sup>1</sup>	0 <sup>1</sup>	0 <sup>1</sup>	0 <sup>1</sup>	N/A	0
5 Scrubber effluent line	0 <sup>1</sup>	0 <sup>1</sup>	N/A	N/A	N/A	N/A	N/A	0 <sup>1</sup>	0 <sup>1</sup>	N/A	0
6 Main line	0	0	L1	N/A	N/A	N/A	N/A	N/A	0	N/A	L1 <sup>6</sup>
7 Distribution lines	N/A	N/A	L1	N/A	N/A	0	N/A	N/A	0	N/A	L1 <sup>2</sup>
FLAMMABLE LIQUIDS (f.p. > 60°C)											
8 Cargo lines	X	X	L1	X	X	N/A <sup>3</sup>	0	0 <sup>10</sup>	0	N/A	L1
9 Fuel oil	X	X	L1	X	X	N/A <sup>3</sup>	0	0	0	L1	L1
10 Lubricating oil	X	X	L1	X	X	N/A	N/A	N/A	0	L1	L1
11 Hydraulic oil	X	X	L1	X	X	0	0	0	0	L1	L1
SEAWATER <sup>1</sup>											
12 Bilge main and branches	L1 <sup>7</sup>	L1 <sup>7</sup>	L1	X	X	N/A	0	0	0	N/A	L1
13 Fire main and water spray	L1	L1	L1	X	N/A	N/A	N/A	0	0	X	L1

# Piping Design Requirements

## Part 5, Chapter 12

Section 5

**Table 12.5.3 Fire endurance requirements** (continued)

	Location										
	A	B	C	D	E	F	G	H	I	J	K
Piping systems	Machinery spaces of Category A	Other machinery spaces and pump rooms	Cargo pump rooms	Ro-Ro cargo holds	Other dry cargo holds	Cargo tanks	Fuel oil tanks	Ballast water tanks	Cofferdams void spaces pipe tunnel and ducts	Accommodation service and control spaces	Open decks
14	Foam system	L1	L1	N/A	N/A	N/A	N/A	N/A	0	L1	L1
15	Sprinkler system	L1	L3	X	N/A	N/A	N/A	0	0	L3	L3
16	Ballast	L3	L3	L3	X	0 <sup>10</sup>	0	0	0	L2	L2
17	Cooling water, essential services	L3	N/A	N/A	N/A	N/A	N/A	0	0	N/A	L2
18	Tank cleaning services fixed machines	N/A	L3	N/A	N/A	0	N/A	0	0	N/A	L3 <sup>2</sup>
19	Non-essential systems	0	0	0	0	N/A	0	0	0	0	0
FRESHWATER											
20	Cooling water essential services	L3	N/A	N/A	N/A	N/A	0	0	0	L3	L3
21	Condensate return	L3	L3	0	0	N/A	N/A	N/A	0	0	0
22	Non-essential systems	0	0	0	0	N/A	0	0	0	0	0
SANITARY/DRAINS/SCUPPERS											
23	Deck drains (internal)	L <sup>14</sup>	N/A	L <sup>14</sup>	0	N/A	0	0	0	0	0
24	Sanitary drains (internal)	0	N/A	0	0	N/A	0	0	0	0	0
25	Scuppers and discharges (overboard)	0 <sup>1,8</sup>	0 <sup>1,8</sup>	0 <sup>1,8</sup>	0 <sup>1,8</sup>	0	0	0	0	0 <sup>1,8</sup>	0
SOUNDING/AIR											
26	Water tanks/dry spaces	0	0	0	0	0 <sup>10</sup>	0	0	0	0	0 <sup>11</sup>

# Piping Design Requirements

## Part 5, Chapter 12

Section 5

**Table 12.5.3 Fire endurance requirements** *(continued)*

Location											
	A	B	C	D	E	F	G	H	I	J	K
Piping systems	Machinery spaces of Category A	Other machinery spaces and pump rooms	Cargo pump rooms	Ro-Ro cargo holds	Other dry cargo holds	Cargo tanks	Fuel oil tanks	Ballast water tanks	Cofferdams void spaces pipe tunnel and ducts	Accommodation service and control spaces	Open decks
27 Oil tanks (f.p. > 60°C)	X	X	X	X	X	X <sup>3</sup>	0	0 <sup>10</sup>	0	X	X
MISCELLANEOUS											
28 Control air	L1 <sup>5</sup>	L1 <sup>5</sup>	L1 <sup>5</sup>	L1 <sup>5</sup>	L1 <sup>5</sup>	N/A	0	0	0	L1 <sup>5</sup>	L1 <sup>5</sup>
29 Service air (non-essential)	0	0	0	0	0	N/A	0	0	0	0	0
30 Brine	0	0	N/A	0	0	N/A	N/A	N/A	0	0	0
31 Auxiliary low pressure steam (≤ 7 bar)	L2	L2	0 <sup>9</sup>	0 <sup>9</sup>	0 <sup>9</sup>	0	0	0	0	0 <sup>9</sup>	0 <sup>9</sup>
LOCATION DEFINITIONS											
Location		Definition									
A	Machinery spaces of Category A		Machinery spaces of Category A as defined in SOLAS* regulation II-2/3.19.								
B	Other machinery spaces and pump rooms		Spaces, other than Category A machinery spaces and cargo pump rooms, containing propulsion machinery, boilers, steam and internal combustion engines, generators and major electrical machinery, pumps, oil filling stations, refrigerating, stabilizing, ventilation and air-conditioning machinery, and similar spaces, and trunks to such spaces.								
C	Cargo pump rooms		Spaces containing cargo pumps and entrances and trunks to such spaces.								
D	Ro-Ro cargo holds		Ro-Ro cargo holds are Ro-Ro cargo spaces and special category spaces as defined in SOLAS* regulation II-2/3.14 and 3.18.								
E	Other dry cargo holds		All spaces other than Ro-Ro cargo holds used for non-liquid cargo and trunks to such spaces.								
F	Cargo tanks		All spaces used for liquid cargo and trunks to such spaces.								
G	Fuel oil tanks		All spaces used for oil fuel (excluding cargo tanks) and trunks to such spaces.								
H	Ballast water tanks		All spaces used for ballast water and trunks to such spaces.								
I	Cofferdams, voids, etc.		Cofferdams and voids are those empty spaces between two bulkheads separating two adjacent compartments.								
J	Accommodation, service		Accommodation spaces, service spaces and control stations as defined in SOLAS* regulation II-2/3.10, 3.12, 3.22.								
K	Open decks		Open deck spaces, as defined in SOLAS* regulation II-2/26.2.2(5).								
*	SOLAS 74 as amended by the 1978 SOLAS Protocol and the 1981 and 1983 amendments (consolidated text).										
ABBREVIATIONS											
L1	Fire endurance test in dry conditions, 60 minutes, IMO Resolution A.753(18) Appendix 1.										
L2	Fire endurance test in dry conditions, 30 minutes, IMO Resolution A.753(18) Appendix 1.										
L3	Fire endurance test in wet conditions, 30 minutes, IMO Resolution A.753(18) Appendix 2.										
0	No fire endurance test required.										
N/A	Not applicable.										
X	Metallic materials having a melting point greater than 925°C.										

# Piping Design Requirements

## Part 5, Chapter 12

Section 5

**Table 12.5.3** Fire endurance requirements (conclusion)

NOTES	
1.	Where non-metallic piping is used, remotely controlled valves to be provided at ship's side (valve is to be controlled from outside space).
2.	Remote closing valves to be provided at the cargo tanks.
3.	When cargo tanks contain flammable liquids with f.p. > 60°C, 'O' may replace 'N/A' or 'X'.
4.	For drains serving only the space concerned, 'O' may replace 'L1'.
5.	When controlling functions are not required by the Rules or statutory requirements, 'O' may replace 'L1'.
6.	For pipe between machinery space and deck water seal, 'O' may replace 'L1'.
7.	For passenger vessels, 'X' is to replace 'L1'.
8.	Scuppers serving open decks in positions 1 and 2, as defined in regulation 13 of the International Convention on Load Lines, 1966, should be 'X' throughout unless fitted at the upper end with the means of closing capable of being operated from a position above the freeboard deck in order to prevent downflooding.
9.	For essential services, such as oil fuel tank heating and ship's whistle, 'X' is to replace 'O'.
10.	For tankers where compliance with MARPOL Annex I, Regulation 19.3.6 is required, 'N/A' is to replace 'O'.
11.	Air and sounding pipes on open deck are to be of substantial construction, see Pt 5, Ch 13, 10.2.2.

5.6.2 The material manufacturer's test certificate, based on actual tested data, is to be provided for each batch of material.

5.6.3 Plastics pipes and fittings are to be manufactured at a works approved by LR in accordance with agreed quality control procedures which shall be capable of detecting at any stage (e.g. incoming material, production, finished article, etc.) deviations in the material, product or process.

5.6.4 Plastics pipes are to be manufactured and tested in accordance with Ch 14.4 of the Rules for Materials. For Class III piping systems the pipe manufacturer's test certificate may be accepted in lieu of an LR Certificate and is to be provided for each consignment of pipe.

### 5.7 Installation and construction

5.7.1 All pipes are to be adequately but freely supported. Suitable provision is to be made for expansion and contraction to take place without unduly straining the pipes.

5.7.2 Pipes may be joined by mechanical couplings or by bonding methods such as welding and laminating.

5.7.3 Where bonding systems are used, the manufacturer or installer shall provide a written procedure covering all aspects of installation, including temperature and humidity conditions. The bonding procedure is to be approved by LR.

5.7.4 The person carrying out the bonding is to be qualified. Records are to be available to the Surveyor for each qualified person showing the bonding procedure and performance qualification, together with dates and results of the qualification testing.

5.7.5 In the case of pipes intended for essential services each qualified person is, at the place of construction, to make at least one test joint, representative of each type of joint to be used. The joined pipe section is to be tested to an internal hydrostatic pressure of four times the design pressure of the pipe system and the pressure held for not less than one hour, with no leakage or separation of joints. The bonding procedure test is to be witnessed by the Surveyor.

5.7.6 Conditions during installation, such as temperature and humidity, which may affect the strength of the finished joints, are to be in accordance with the agreed bonding procedure.

5.7.7 The required fire endurance level of the pipe is to be maintained in way of pipe supports, joints and fittings, including those between plastics and metallic pipes.

5.7.8 Where piping systems are arranged to pass through watertight bulkheads or decks, provision is to be made for maintaining the integrity of the bulkhead or deck by means of metallic bulkhead, or deck, pieces. The bulkhead pieces are to be protected against corrosion, and so constructed to be of a strength equivalent to the intact bulkhead; attention is drawn to 5.7.1, see also Pt 5, Ch 13, 2.4.1. Details of the arrangements are to be submitted for approval.

# Piping Design Requirements

## Part 5, Chapter 12

Sections 5, 6 & 7

5.7.9 Where a piping system is required to be electrically conductive, for the control of static electricity, continuity is to be maintained across the joints and fittings, and the system is to be earthed, *see also* Pt 6, Ch 2,1.12.

### 5.8 Testing

5.8.1 The hydraulic testing of pipes and fittings is to be in accordance with Section 8.

5.8.2 Where a piping system is required to be electrically conductive, tests are to be carried out to verify that the resistance to earth from any point in the system does not exceed 1 MΩ, *see also* Pt 6, Ch 2,20.2.3.

## Section 6 Valves

### 6.1 Design requirements

6.1.1 The design, construction and operational capability of valves is to be in accordance with an acceptable National or International Standard appropriate to the piping system. Where valves are not in accordance with an acceptable standard, details are to be submitted for consideration. Where valves are fitted, the requirements of 6.1.2 to 6.1.8 are to be satisfied.

6.1.2 Valves are to be made of steel, cast iron, copper alloy, or other approved material suitable for the intended purpose.

6.1.3 Valves having isolation or sealing components sensitive to heat are not to be used in spaces where leakage or failure caused by fire could result in fire spread, flooding or the loss of an essential service.

6.1.4 Where valves are required to be capable of being closed remotely in the event of fire, the valves, including their control gear, are to be of steel construction or of an acceptable fire tested design.

6.1.5 Valves are to be arranged for clockwise closing and are to be provided with indicators showing whether they are open or shut unless this is readily obvious. Legible nameplates are to be fitted.

6.1.6 Valves are to be so constructed as to prevent the possibility of valve covers or glands being slackened back or loosened when the valves are operated.

6.1.7 Valves are to be used within their specified pressure and temperature rating for all normal operating conditions, and are to be suitable for the intended purpose.

6.1.8 Valves intended for submerged installation are to be suitable for both internal and external media. Spindle sealing is to prevent ingress of external media at the maximum external pressure head expected in service.

## Section 7 Flexible hoses

### 7.1 General

7.1.1 A flexible hose assembly is a short length of metallic or non-metallic hose normally with prefabricated end fittings ready for installation.

7.1.2 For the purpose of approval for the applications in 7.2, details of the materials and construction of the hoses, and the method of attaching the end fittings together with evidence of satisfactory prototype testing, are to be submitted for consideration.

7.1.3 The use of hose clamps and similar types of end attachments are not to be used for flexible hoses in piping systems for steam, flammable media, starting air systems or for sea-water systems where failure may result in flooding. In other piping systems, the use of hose clamps may be accepted where the working pressure is less than 5 bar and provided that there are two clamps at each end connection.

7.1.4 Flexible hoses are to be limited to a length necessary to provide for relative movement between fixed and flexibly mounted items of machinery/equipment or systems.

7.1.5 Flexible hoses are not to be used to compensate for misalignment between sections of piping.

7.1.6 Flexible hose assemblies are not to be installed where they may be subjected to torsional deformation (twisting) under normal operating conditions.

7.1.7 The number of flexible hoses in piping systems mentioned in this Section is to be kept to a minimum and to be limited for the purpose stated in 7.2.1.

7.1.8 Where flexible hoses are intended for conveying flammable fluids in piping systems that are in close proximity to hot surfaces, electrical installation or other sources of ignition, the risk of ignition due to failure of the hose assembly and subsequent release of fluids is to be mitigated as far as practicable by the use of screens or other suitable protection.

7.1.9 Flexible hoses are to be installed in clearly visible and readily accessible locations.

7.1.10 The installation of flexible hose assemblies is to be in accordance with the manufacturer's instructions and use limitations with particular attention to the following:

- Orientation.
- End connection support (where necessary).
- Avoidance of hose contact that could cause rubbing and abrasion.
- Minimum bend radii.

# Piping Design Requirements

## Part 5, Chapter 12

Section 7

7.1.11 Flexible hoses are to be permanently marked by the manufacturer with the following details:

- (a) Hose manufacturer's name or trademark.
- (b) Date of manufacture (month/year).
- (c) Designation type reference.
- (d) Nominal diameter.
- (e) Pressure rating.
- (f) Temperature rating.

Where a flexible hose assembly is made up of items from different manufacturers, the components are to be clearly identified and traceable to evidence of prototype testing.

### 7.2 Applications

7.2.1 Short joining lengths of flexible hoses complying with the requirements of this Section may be used, where necessary, to accommodate relative movement between various items of machinery connected to permanent piping systems. The requirements of this Section may also be applied to temporarily-connected flexible hoses or hoses of portable equipment.

7.2.2 Rubber or plastics hoses, with integral cotton or similar braid reinforcement, may be used in fresh and sea-water cooling systems. In the case of sea-water systems, where failure of the hoses could give rise to the danger of flooding, the hoses are to be suitably enclosed, as indicated in Ch 13,2.7.

7.2.3 Rubber or plastics hoses, with single or double closely woven integral wire braid or other suitable material reinforcement, or convoluted metal pipes with wire braid protection, may be used in bilge, ballast, compressed air, fresh water, sea-water, oil fuel, lubricating oil, Class III steam hydraulic and thermal oil oil systems. Where rubber or plastics hoses are used for oil fuel supply to burners, the hoses are to have external wire braid protection in addition to the integral wire braid. Flexible hoses for use in steam systems are to be of metallic construction.

7.2.4 Flexible hoses are not to be used in high pressure fuel oil injection systems.

7.2.5 The requirements in this Section for flexible hose assemblies are not applicable to hoses intended to be used in fixed fire-extinguishing systems.

### 7.3 Design requirements

7.3.1 Flexible hose assemblies are to be designed and constructed in accordance with recognised National or International standards acceptable to LR.

7.3.2 Flexible hoses are to be complete with approved end fittings in accordance with manufacturer's specification. End connections which do not have flanges are to comply with 2.12 as applicable and each type of hose/fitting combination is to be subject to prototype testing to the same standard as that required by the hose with particular reference to pressure and impulse tests.

7.3.3 Flexible hose assemblies intended for installation in piping systems where pressure pulses and/or high levels of vibration are expected to occur in service, are to be designed for the maximum expected impulse peak pressure and forces due to vibration. The tests required by 7.4 are to take into consideration the maximum anticipated in-service pressures, vibration frequencies and forces due to installation.

7.3.4 Flexible hose assemblies constructed of non-metallic materials intended for installation in piping systems for flammable media, and sea-water systems where failure may result in flooding, are to be of fire-resistant type. Fire resistance is to be demonstrated by testing to ISO 15540 and ISO 15541.

7.3.5 Flexible hose assemblies are to be suitable for the intended location and application, taking into consideration ambient conditions, compatibility with fluids under working pressure and temperature conditions consistent with the manufacturer's instructions and any other applicable requirements in the Rules.

### 7.4 Testing

7.4.1 Acceptance of flexible hose assemblies is subject to satisfactory prototype testing. Prototype test programmes for flexible hose assemblies are to be submitted by the manufacturer and are to be sufficiently detailed to demonstrate performance in accordance with the specified standards.

7.4.2 For a particular hose type complete with end fittings, the tests, as applicable, are to be carried out on different nominal diameters for pressure, burst, impulse and fire resistance in accordance with the requirements of the relevant standard. The following standards are to be used as applicable:

- ISO 6802 – *Rubber and plastics hoses and hose assemblies – Hydraulic pressure impulse test without flexing.*
- ISO 6803 – *Rubber and plastics hoses and hose assemblies – Hydraulic pressure impulse test with flexing.*
- ISO 15540 – *Ships and marine technology – Fire resistance of hose assemblies – Test methods.*
- ISO 15541 – *Ships and marine technology – Fire resistance of hose assemblies – Requirements for test bench.*
- ISO 10380 – *Pipework – Corrugated metal hoses and hose assemblies.*

Other standards may be accepted where agreed by LR.

7.4.3 All flexible hose assemblies are to be satisfactorily prototype burst tested to an international standard\* to demonstrate they are able to withstand a pressure of not less than four times the design pressure without indication of failure or leakage.

NOTE

\* The international standards, e.g. EN or SAE for burst testing of non-metallic hoses, require the pressure to be increased until burst without any holding period at 4 x Maximum Working Pressure.

# Piping Design Requirements

# Part 5, Chapter 12

Sections 8 & 9

## Section 8 Hydraulic tests on pipes and fittings

### 8.1 Hydraulic tests before installation on board

8.1.1 All Class I and II pipes and their associated fittings are to be tested by hydraulic pressure to the Surveyor's satisfaction. Further, all steam, feed, compressed air and oil fuel pipes, together with their fittings, are to be similarly tested where the design pressure is greater than 3,5 bar (3,6 kgf/cm<sup>2</sup>). The test is to be carried out after completion of manufacture and before installation on board and, where applicable, before insulating and coating.

8.1.2 Where the design temperature does not exceed 300°C, the test pressure is to be 1,5 times the design pressure, as defined in 1.3.

8.1.3 For steel pipes and integral fittings for use in systems where the design temperature exceeds 300°C, the test pressure is to be as follows:

- (a) For carbon and carbon-manganese steel pipes, the test pressure is to be twice the design pressure, as defined in 1.3.
- (b) For alloy steel pipes, the test pressure is to be determined by the following formula, but need not exceed 2p:

$$p_t = 1,5 \frac{\sigma_{100}}{\sigma} p \text{ bar (kgf/cm}^2\text{)}$$

where

- $p_t$  and  $p$  are as defined in 1.2.1
- $\sigma$  = permissible stress for the design temperature, in N/mm<sup>2</sup> (kgf/cm<sup>2</sup>), as stated in Table 12.2.2
- $\sigma_{100}$  = permissible stress for 100°C, in N/mm<sup>2</sup> (kgf/cm<sup>2</sup>), as stated in Table 12.2.2.

8.1.4 Where alloy steels not included in Table 12.2.2 are used, the permissible stresses will be specially considered, as indicated in 2.2.2.

8.1.5 Consideration will be given to the reduction of the test pressure to not less than 1,5p, where it is necessary to avoid excessive stress in way of bends, branches, etc.

8.1.6 All valve bodies are to be tested by hydraulic pressure to 1,5 times the nominal pressure rating at ambient temperature. However, the test pressure need not be more than 70 bar (71 kgf/cm<sup>2</sup>) above the design pressure specified for the design temperature.

8.1.7 In no case is the membrane stress to exceed 90 per cent of the yield stress at the testing temperature.

### 8.2 Testing after assembly on board

8.2.1 Heating coils in tanks, gas fuel and oil fuel piping are to be tested by hydraulic pressure, after installation on board, to 1,5 times the design pressure but in no case to less than 4 bar (4,1 kgf/cm<sup>2</sup>).

8.2.2 Where pipes specified in 8.1.1 are butt welded together during assembly on board, they are to be tested by hydraulic pressure in accordance with the requirements of 8.1 after welding. The pipe lengths may be insulated, except in way of the joints made during installation and before the hydraulic test is carried out.

8.2.3 The hydraulic test required by 8.2.2 may be omitted provided non-destructive tests by ultrasonic or radiographic methods are carried out on the entire circumference of all butt welds with satisfactory results. Where ultrasonic tests have been carried out, the manufacturer is to provide the Surveyor with a signed statement confirming that ultrasonic examination has been carried out by an approved operator and that there were no indications of defects which could be expected to have a prejudicial effect on the service performance of the piping.

8.2.4 Where bilge pipes are accepted in way of double bottom tanks or deep tanks, see Ch 13,7.9 and 7.10, the pipes after fitting are to be tested by hydraulic pressure to the same pressure as the tanks through which they pass.

## Cross-reference

See also Ch 13,2.10 for testing after installation.

## APPENDIX

### Section 9 Guidance notes on metal pipes for water services

#### 9.1 General

9.1.1 These guidance notes, except where it is specifically stated, apply to sea-water piping systems.

9.1.2 In addition to the selection of suitable materials, careful attention should be given to the design details of the piping system and the workmanship in fabrication, construction and installation of the pipework in order to obtain maximum life in service.

#### 9.2 Materials

9.2.1 Materials used in sea-water piping systems include:

- Galvanized steel.
- Steel pipes lined with rubber, plastics or stoved coatings.
- Copper.
- 90/10 copper-nickel-iron.
- 70/30 copper-nickel.
- Aluminium brass.



# Piping Design Requirements

## Part 5, Chapter 12

Section 9

9.2.2 Selection of materials should be based on:

- the ability to resist general and localized corrosion, such as pitting, impingement attack and cavitation throughout all the flow velocities likely to be encountered;
- compatibility with the other materials in the system, such as valve bodies and casings, (e.g. in order to minimize bimetallic corrosion);
- the ability to resist selective corrosion, e.g. dezincification of brass, dealuminification of aluminium brass and graphitization of cast iron;
- the ability to resist stress corrosion and corrosion fatigue; and
- the amenability to fabrication by normal practices.

### 9.3 Steel pipes

9.3.1 Steel pipes should be protected against corrosion, and protective coatings should be applied on completion of all fabrication, i.e. bending, forming and welding of the steel pipes.

9.3.2 Welds should be free from lack of fusion and crevices. The surfaces should be dressed to remove slag and spatter and this should be done before coating. The coating should be continuous around the ends of the pipes and on the faces of flanges.

9.3.3 Galvanizing the bores and flanges of steel pipes as protection against corrosion is common practice, and is recommended as the minimum protection for pipes in sea-water systems, including those for bilge and ballast service.

9.3.4 Austenitic stainless steel pipes are not recommended for salt-water services as they are prone to pitting, particularly in polluted waters.

9.3.5 Rubber lined pipes are effective against corrosion and suitable for higher water velocities. The rubber lining should be free from defects, e.g. discontinuities, pinholes, etc., and it is essential that the bonding of the rubber to the bore of the pipe and flange face is sound. Rubber linings should be applied by firms specializing in this form of protection.

9.3.6 The foregoing comments on rubber lined pipes also apply to pipes lined with plastics.

9.3.7 Stove coating of pipes as protection against corrosion should only be used where the pipes will be efficiently protected against mechanical damage.

### 9.4 Copper and copper alloy pipes

9.4.1 Copper pipes are particularly susceptible to perforation by corrosion/erosion and should only be used for low water velocities and where there is no excessive local turbulence.

9.4.2 Aluminium brass and copper-nickel-iron alloy pipes give good service in reasonably clean sea-water. For service with polluted river or harbour waters, copper-nickel-iron alloy pipes with at least 10 per cent nickel are preferable. Alpha-brasses, i.e. those containing 70 per cent or more copper, must be inhibited effectively against dezincification by suitable additions to the composition. Alpha beta-brasses, (i.e. those containing less than 70 per cent copper), should not be used for pipes and fittings.

9.4.3 New copper alloy pipes should not be exposed initially to polluted water. Clean sea-water should be used at first to allow the metals to develop protective films. If this is not available the system should be filled with inhibited town mains water.

### 9.5 Flanges

9.5.1 Where pipes are exposed to sea-water on both external and internal surfaces, flanges should be made, preferably, of the same material. Where sea-water is confined to the bores of pipes, flanges may be of the same material or of less noble metal than that of the pipe, *see also* 2.3.

9.5.2 Fixed or loose type flanges may be used. The fixed flanges should be attached to the pipes by fillet welds or by capillary silver brazing. Where welding is used, the fillet weld at the back should be a strength weld and that in the face, a seal weld.

9.5.3 Inert gas shielded arc welding is the preferred process but metal arc welding may be used on copper-nickel-iron alloy pipes.

9.5.4 Mild steel flanges may be attached by argon arc welding to copper-nickel-iron pipes and give satisfactory service, provided that no part of the steel is exposed to the sea-water.

9.5.5 Where silver brazing is used, strength should be obtained by means of the bond in a capillary space over the whole area of the mating surfaces. A fillet braze at the back of the flange or at the face is undesirable. The alloy used for silver brazing should contain not less than 49 per cent silver.

9.5.6 The use of a copper-zinc brazing alloy is not permitted.

### 9.6 Water velocity

9.6.1 Water velocities should be carefully assessed at the design stage and the materials of pipes, valves, etc., selected to suit the conditions.

9.6.2 The water velocity in copper pipes should not exceed 1 m/s.

# Piping Design Requirements

## Part 5, Chapter 12

Section 9

9.6.3 The water velocity in the pipes of the materials below should normally be not less than about 1 m/s in order to avoid fouling and subsequent pitting, but should not be greater than the following:

- |                            |         |
|----------------------------|---------|
| • Galvanized steel         | 3,0 m/s |
| • Aluminium brass          | 3,0 m/s |
| • 90/10 copper-nickel-iron | 3,5 m/s |
| • 70/30 copper-nickel      | 5,0 m/s |

### 9.7 Fabrication and installation

9.7.1 Attention should be given to ensuring streamlined flow and reducing entrained air in the system to a minimum. Abrupt changes in the direction of flow, protrusions into the bores of pipes and other restrictions of flow should be avoided. Branches in continuous flow lines should be set at a shallow angle to the main pipe, and the junction should be smooth.

9.7.2 Pipe bores should be smooth and clean.

9.7.3 Jointing should be flush with the bore surfaces of pipes and misalignment of adjacent flange faces should be reduced to a minimum.

9.7.4 Pipe bends should be of as large a radius as possible, and the bore surfaces should be smooth and free from puckering at these positions. Any carbonaceous films or deposits formed on the bore surfaces during the bending processes should be carefully removed. Organic substances are not recommended for the filling of pipes for bending purposes.

9.7.5 The position of supports should be given special consideration in order to minimize vibration and ensure that excessive bending moments are not imposed on the pipes.

9.7.6 Systems should not be left idle for long periods, especially where the water is polluted.

9.7.7 Strainers should be provided at the inlet to sea-water systems.

### 9.8 Metal pipes for fresh water services

9.8.1 Mild steel or copper pipes are normally satisfactory for service in fresh water applications. Hot fresh water, however, may promote corrosion in mild steel pipes unless the hardness and pH of the water are controlled.

9.8.2 Water with a slight salt content should not be left stagnant for long periods in mild steel pipes. Low salinity and the limited supply of oxygen in such conditions promote the formation of black iron oxide, and this may give rise to severe pitting. Where stagnant conditions are unavoidable, steel pipes should be galvanized, or pipes of suitable non-ferrous material used.

9.8.3 Copper alloy pipes should be treated to remove any carbonaceous films or deposits before the tubes are put into service.

9.8.4 Brass fittings and flanges in contact with water should be made of an alpha-brass effectively inhibited against dezincification by suitable additions to the composition.

9.8.5 Aluminium brass has been widely used as material for heat exchanger and condenser tubes, but its use in 'once through' systems is not recommended since, under certain conditions, it is prone to pitting and cracking.

# Ship Piping Systems

## Part 5, Chapter 13

Section 1

## Section

- 1 **General requirements**
- 2 **Construction and installation**
- 3 **Drainage of compartments, other than machinery space**
- 4 **Bilge drainage of machinery space**
- 5 **Sizes of bilge suction pipes**
- 6 **Pumps on bilge service and their connections**
- 7 **Piping systems and their fittings**
- 8 **Additional requirements for bilge drainage and cross-flooding arrangements for passenger ships**
- 9 **Additional requirements relating to fixed pressure water spray fire-extinguishing systems**
- 10 **Drainage arrangements for ships not fitted with propelling machinery**
- 11 **Ballast system**
- 12 **Air, overflow and sounding pipes**

### Section 1

#### General requirements

##### 1.1 Application

1.1.1 The requirements of this Chapter apply to piping systems on all types of ship except where otherwise stated.

1.1.2 Whilst the requirements satisfy the relevant regulations of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments, attention should be given to any relevant statutory requirements of the National Authority of the country in which the ship is to be registered.

1.1.3 Consideration will be given to special cases or to arrangements which are equivalent to those required by these Rules. Consideration will also be given to the pumping arrangements of small ships and ships to be assigned class notations for restricted or special services.

##### 1.2 Prevention of progressive flooding in damage condition

1.2.1 For ships to which subdivision and damage stability requirements apply, precautions are to be taken to prevent progressive flooding between compartments resulting from damage to piping systems. For this purpose, piping systems are to be located inboard of the assumed extent of damage applicable to the ship type.

1.2.2 Where it is not practicable to locate piping systems as required by 1.2.1, the following precautions are to be taken:

- (a) Bilge suction pipes are to be provided with non-return valves of approved type.
- (b) Other piping systems are to be provided with shut-off valves capable of being operated from positions accessible in the damage condition, or from above the bulkhead deck where required by the Rules.

These valves are to be located in the compartment containing the open end or in a suitable position such that the compartment may be isolated in the event of damage to the piping system.

1.2.3 Where subdivision and damage stability requirements apply and where penetration of watertight divisions by pipes, ducts, trunks or other penetrations is necessary, arrangements are to be made to maintain the watertight integrity.

##### 1.3 Plans and particulars

1.3.1 The following plans (in diagrammatic form) and particulars are to be submitted for approval. Additional plans should not be submitted unless the arrangements are of a novel or special character affecting classification:

- (a) Arrangements of air pipes and closing devices for all tanks and enclosed spaces.
- (b) Sounding arrangements for all tanks, enclosed spaces and cargo holds.
- (c) Arrangements of level alarms fitted in tanks, cargo holds, machinery spaces, pump rooms and any other spaces.
- (d) Arrangements of any cross flooding or heeling tank systems.
- (e) Bilge drainage arrangements for all compartments which are to include details of location, number and capacity of pumping units on bilge service. In the case of passenger ships, the criterion numeral, as defined in the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments are to be stated, together with the number of flooded compartments which the ship is required to withstand under damage conditions.
- (f) Ballast filling and drainage arrangements.
- (g) Oil fuel filling, transfer, relief and spill/drainage arrangements.
- (h) Tank overflow arrangements.
- (i) Blanking arrangements for bilge and ballast piping systems for bulk carriers having floodable holds.
- (k) Isolation arrangements for bilge systems where cargo holds are intended for the carriage of dangerous goods.
- (l) Details verifying compliance with the sizing of air pipes required by 12.8.
- (m) Arrangements of oil fuel piping in connection with oil burning installations and oil fired galleys.
- (n) Arrangements of oil fuel burning units for boilers and thermal fluid heaters.
- (o) Arrangement of boiler feed system.
- (p) Arrangements of thermal fluid circulation systems.
- (q) Arrangement of compressed air systems for main and auxiliary services.
- (r) Arrangements of lubricating oil systems.
- (s) Arrangements of flammable liquids used for power transmission, control and heating systems.

- (t) Arrangements of cooling water systems for main and auxiliary services.
- (u) Oil fuel settling service and other oil fuel tanks not forming part of the ship's structure.
- (v) Arrangements and dimensions of all steam pipes where the design pressure or temperature exceeds 16,0 bar (16,3 kgf/cm<sup>2</sup>) or 300°C, respectively, and the outside diameter exceeds 76,1 mm, with details of flanges, bolts and weld attachments, and particulars of the material of pipes, flanges, bolts and electrodes.
- (w) Details verifying compliance with the capacity of the oil fuel treatment plant required by Ch 14,3.9.1.
- (x) Details verifying compliance of demands on low pressure air systems by essential users as required by Ch 14,10.1.3.

## Section 2

### Construction and installation

#### 2.1 Materials

2.1.1 Except where otherwise stated in this Chapter, pipes, valves and fittings are to be made of steel, cast iron, copper, copper alloy, or other approved material suitable for the intended service.

2.1.2 Where applicable, the materials are to comply with the relevant requirements of Chapter 12.

2.1.3 Materials sensitive to heat, such as aluminium, lead or plastics, are not to be used in systems essential to the safe operation of the ship, or for containing combustible liquids or sea-water where leakage or failure could result in fire or in the flooding of watertight compartments, see Chapter 12 for plastics pipes.

2.1.4 Aluminium alloy pipes are not acceptable for fire extinguishing pipes unless they are suitably protected against the effect of heat. The proposed use of aluminium alloy with appropriate insulation will be considered when it has been demonstrated that the arrangements provide equivalent structural and integrity properties compared to steel. In open and exposed locations where the insulation material is likely to suffer from mechanical damage suitable protection is to be provided.

#### 2.2 Pipe wall thickness

2.2.1 The minimum nominal wall thickness of steel, copper and copper alloy pipes are to be in accordance with Chapter 12.

2.2.2 Special consideration will be given to the wall thickness of pipes made of materials other than steel, copper and copper alloy.

#### 2.3 Valves – Installation and control

2.3.1 Valves and cocks are to be fitted in places where they are at all times readily accessible, unless otherwise specifically mentioned in the Rules. Valves in cargo oil and ballast systems may be fitted inside tanks, subject to 2.3.2.

2.3.2 All valves which are provided with remote control are to be arranged for local manual operation, independent of the remote operating mechanism. For shipside valves and valves on the collision bulkhead, the means for local manual operation are to be permanently attached. For submerged valves in cargo oil and ballast systems, as permitted by 2.3.1, local manual operation may be by extended spindle or a portable hand pump. Where manual operation is by hand pump, the control lines to each submerged valve are to incorporate quick coupling connections, as close to the valve actuator as practicable, to allow easy connection of the hand pump. Not less than two hand pumps are to be provided.

2.3.3 In case of valves which are required by the Rules to be provided with remote control, opening and/or closing of the valves by local manual means are not to render the remote control system inoperable.

#### 2.4 Attachment of valves to watertight plating

2.4.1 Valve chests, cocks, pipes or other fittings attached direct to the plating of tanks, and to bulkheads, flats or tunnels which are required to be of watertight construction, are to be secured by means of studs screwed through the plating or by tap bolts, and not by bolts passing through clearance holes. Alternatively, the studs or the bulkhead piece may be welded to the plating.

2.4.2 For requirements relating to valves on the collision bulkhead, see 3.5.4.

#### 2.5 Ship-side valves and fittings (other than those on scuppers and sanitary discharges)

2.5.1 All sea inlet and overboard discharge pipes are to be fitted with valves or cocks secured direct to the shell plating, or to the plating of fabricated steel water boxes attached to the shell plating. These fittings are to be secured by bolts tapped into the plating and fitted with countersunk heads, or by studs screwed into heavy steel pads fitted to the plating. The stud holes are not to penetrate the plating.

2.5.2 Valves for ship-side applications are to be installed such that the section of piping immediately inboard of the valve can be removed without affecting the watertight integrity of the hull.

2.5.3 Distance pieces of short, rigid construction, and made of approved material, may be fitted between the valves and shell plating. Distance pieces of steel may be welded to the shell plating. Details of the welded connections and of fabricated steel water boxes are to be submitted.

# Ship Piping Systems

## Part 5, Chapter 13

### Section 2

2.5.4 Gratings are to be fitted at all openings in the ship's side for sea inlet valves and inlet water boxes. The net area through the gratings is to be not less than twice that of the valves connected to the sea inlets, and provision is to be made for clearing the gratings by use of low pressure steam or compressed air, see 2.5.9.

2.5.5 All suction and discharge valves and cocks secured direct to the shell plating of the ship are to be fitted with spigots passing through the plating, but the spigots on the valves or cocks may be omitted if these fittings are attached to pads or distance pieces which themselves form spigots in way of the shell plating. Blow-down valves or cocks are also to be fitted with a protection ring through which the spigot is to pass, the ring being on the outside of the shell plating. Where alternative forms of attachment are proposed, details are to be submitted for consideration.

2.5.6 Blow-down valves or cocks on the ship's side are to be fitted in accessible positions above the level of the working platform, and are to be provided with indicators showing whether they are open or shut. Cock handles are not to be capable of being removed unless the cocks are shut, and, if valves are fitted, the hand wheels are to be suitably retained on the spindle.

2.5.7 Sea inlet and overboard discharge valves and cocks are in all cases to be fitted in easily accessible positions and, so far as practicable, are to be readily visible. Indicators are to be provided local to the valves and cocks, showing whether they are open or shut. Provision is to be made for preventing any discharge of water into lifeboats. The valve spindles are to extend above the lower platform, and the hand wheels of the main cooling water sea inlet and emergency bilge suction valves are to be situated not less than 460 mm above this platform.

2.5.8 Ship-side valves and fittings, if made of steel or other approved material with low corrosion resistance, are to be suitably protected against wastage.

2.5.9 The scantlings of valves and valve stools fitted with steam or compressed air clearing connections are to be suitable for the maximum pressure to which the valves and stools may be subjected.

2.5.10 Valves, cocks and distance pieces, intended for installation on the ship's side below the load waterline, are to be tested by hydraulic pressure to not less than 5 bar.

2.5.11 For sea connections for ships having notation for ice navigation, see Ch 9,2.13 and Ch 9,3.5.

### 2.6 Piping systems – Installation

2.6.1 Bilge, ballast and cooling water suction and discharge pipes are to be permanent pipes made in readily removable lengths with flanged joints, except as mentioned in 7.10, and are to be efficiently secured in position to prevent chafing or lateral movement. For joints in oil fuel piping systems, see Ch 14,4.5 and 4.6.

2.6.2 Where lack of space prevents the use of normal circular flanges, details of the alternative methods of joining the pipes are to be submitted.

2.6.3 Long or heavy lengths of pipes are to be supported by bearers so that no undue load is carried by the flanged connections of the pumps or fittings to which they are attached.

### 2.7 Provision for expansion

2.7.1 Suitable provision for expansion is to be made, where necessary, in each range of pipes.

2.7.2 Where expansion pieces are fitted, they are to be of an approved type and are to be protected against over extension and compression. The adjoining pipes are to be suitably aligned, supported, guided and anchored. Where necessary, expansion pieces of the bellows type are to be protected against mechanical damage.

2.7.3 Expansion pieces of an approved type incorporating special quality oil resistant rubber or other suitable synthetic material may be used in cooling water lines in machinery spaces. Where fitted in sea- water lines, they are to be provided with guards which will effectively enclose, but not interfere with, the action of the expansion pieces and will reduce to the minimum practicable any flow of water into the machinery spaces in the event of failure of the flexible elements. Proposals to use such fittings in water lines for other services, including:

- ballast lines in machinery spaces, in duct keels and inside double bottom water ballast tanks, and
  - bilge lines inside duct keels only,
- will be specially considered when plans of the pumping systems are submitted for approval.

2.7.4 For requirements relating to flexible hoses, see Chapter 12.

### 2.8 Piping in way of refrigerated chambers

2.8.1 All pipes, including scupper pipes, air pipes and sounding pipes which pass through chambers intended for the carriage or storage of refrigerated produce are to be well insulated.

2.8.2 Where the pipes referred to in 2.8.1 pass through chambers intended for temperatures of 0°C or below, they are also to be insulated from the steel structure, except in positions where the temperature of the structure is mainly controlled by the external temperature and will normally be above freezing point. Pipes passing through a deckplate within the ship side insulation, where the deck is fully insulated below and has an insulation ribband on top, are to be attached to the deck plating. In the case of pipes adjacent to the shell plating, metallic contact between the pipes and the shell plating or frames is to be arranged so far as practicable.

2.8.3 The air refreshing pipes to and from refrigerated compartments need not, however, be insulated from the steel work.

# Ship Piping Systems

## Part 5, Chapter 13

Sections 2 & 3

### 2.9 Miscellaneous requirements

2.9.1 All pipes situated in cargo spaces, fish holds, chain lockers or other positions where they are liable to mechanical damage are to be efficiently protected.

2.9.2 Wash deck pipes and discharge pipes from the pumps to domestic water tanks are not to be led through cargo holds. Any proposed departure from this requirement is to be submitted for consideration.

2.9.3 So far as practicable, pipelines, including exhaust pipes from oil engines, are not to be led in the vicinity of switchboards or other electrical appliances in positions where the drip or escape of liquid, gas or steam from joints or fittings could cause damage to the electrical installation. Where it is not practicable to comply with these requirements, drip trays or shields are to be provided as found necessary. Short sounding pipes to tanks are not to terminate near electrical appliances, see 12.13.2.

### 2.10 Testing after installation

2.10.1 After installation on board, all steam, hydraulic, compressed air and other piping systems covered by 1.3.1, together with associated fittings which are under internal pressure, are to be subjected to a running test at the intended maximum working pressure.

### ■ Cross-reference

For guidance on metal pipes for water services, see Ch 12,9.

## ■ Section 3 Drainage of compartments, other than machinery space

### 3.1 General

3.1.1 All ships are to be provided with efficient pumping plant having the suctions and means for drainage so arranged that any water within any compartment of the ship, or any watertight section of any compartment, can be pumped out through at least one suction when the ship is on an even keel and is either upright or has a list of not more than 5°. For this purpose, wing suctions will generally be necessary, except in short, narrow compartments where one suction can provide effective drainage under the above conditions.

3.1.2 In passenger ships, the pumping plant is to be capable of draining any watertight compartment under all practicable conditions after a casualty, whether the ship is upright or listed.

3.1.3 In the case of dry compartments, the suctions required by 3.1.1 are, except where otherwise stated, to be branch bilge suctions, i.e. suctions connected to a main bilge line.

3.1.4 For drainage arrangements of non-self-propelled ships, see Section 10.

3.1.5 For additional drainage arrangements on ferries and Roll on-Roll off ships, see Pt 4, Ch 2,9.9.

### 3.2 Cargo holds

3.2.1 In ships having only one hold, and this over 30 m in length, bilge suctions are to be fitted in suitable positions in the fore and after sections of the hold.

3.2.2 Where close ceiling or continuous gusset plates are fitted over the bilges, arrangements are to be made whereby water in a hold compartment may find its way to the suction pipes.

3.2.3 Where the inner bottom plating extends to the ship's side, the bilge suctions are to be led to wells placed at the wings. If the tank top plating has inverse camber, a well is also to be fitted at the centreline, but in the case of trawlers and fishing vessels, a single well fitted at the centre may be accepted. For capacity and construction of bilge wells, see 7.6.

3.2.4 For drainage arrangements from refrigerated cargo spaces, see Pt 6, Ch 3,4.19.

3.2.5 For cargo holds having non-weathertight hatch covers or where hatch covers have been omitted, drainage arrangements are to take into account the effects of additional water ingress into the hold(s). High level bilge alarms are to be provided in cargo holds having non-weathertight hatch covers or where hatch covers have been omitted, see also Pt 4, Ch 8,11.

3.2.6 Drainage arrangements of cargo holds intended for the carriage of flammable or toxic liquids are to be designed to prevent inadvertent drainage of such products through machinery space piping systems.

### 3.3 Holds and deep tanks for alternative carriage of liquid or dry cargo

3.3.1 Where holds and deep tanks are intended for the alternative carriage of liquid or dry cargo, the drainage arrangements are to be in accordance with the following:

- (a) For dry cargoes, 3.1 and 3.2.
- (b) For water ballast, oil fuel or cargo oil having a flash point of 60°C or above, 3.4.
- (c) For cargo oil having a flash point below 60°C, Chapter 15.

3.3.2 For blanking arrangements of filling and suction pipes, see 7.12.

# Ship Piping Systems

## Part 5, Chapter 13

Section 3

### 3.4 Tanks and cofferdams

3.4.1 All tanks (including double bottom tanks), whether used for water ballast, oil fuel or liquid cargoes, are to be provided with suction pipes, led to suitable power pumps, from the after end of each tank.

3.4.2 In general, the drainage arrangements are to be in accordance with 3.1. However, where the tanks are divided by longitudinal watertight bulkheads or girders into two or more tanks, a single suction pipe, led to the after end of each tank, will normally be acceptable.

3.4.3 Similar drainage arrangements are to be provided for cofferdams, except that the suctions may be led to the main bilge line.

3.4.4 The pumping arrangements for tanks that are intended to carry cargo oil having a flash point of 60°C or above, are also to comply with the requirements of Chapter 14, Sections 2, 3 and 4, as far as they are applicable.

### 3.5 Fore and after peaks

3.5.1 Fuel oil, lubrication oil and other flammable liquids are not to be carried in forepeak tanks.

3.5.2 Where the peaks are used as tanks, a power pump suction is to be led to each tank, except in the case of small tanks used for the carriage of domestic fresh water, where hand pumps may be used.

3.5.3 Where the peaks are not used as tanks, and main bilge line suctions are not fitted, drainage of both peaks may be effected by hand pump suctions, provided that the suction lift is well within the capacity of the pumps and in no case exceeds 7,3 m. In the case of trawlers and fishing vessels, drainage of the after peak may be effected by means of a self-closing cock fitted in a well lighted and readily accessible position.

3.5.4 Except as permitted by 3.5.5, the collision bulkhead in passenger ships is not to be pierced below the bulkhead deck by more than one pipe for dealing with the contents of the fore peak. The pipe is to be provided with a screw-down valve capable of being operated from an accessible position above the bulkhead deck, the chest being secured to the bulkhead inside the fore peak. An indicator is to be provided to show whether the valve is open or closed.

3.5.5 Where the fore peak (in passenger ships) is divided into two compartments, the collision bulkhead may be pierced below the bulkhead deck by two pipes (i.e. one for each compartment) provided there is no practical alternative to the fitting of a second pipe. Each pipe is to be provided with a screw-down valve, fitted and controlled as in 3.5.4.

3.5.6 In ships other than passenger ships, pipes piercing the collision bulkhead are to be fitted with suitable valves operable from above the freeboard deck and the valve chests are to be secured to the bulkhead inside the fore peak. The valves may be fitted on the after side of the collision bulkhead, provided that the valve is readily accessible under all service conditions and the space in which it is located is not a cargo space.

### 3.6 Spaces above fore peaks, after peaks and machinery spaces

3.6.1 Provision is to be made for the drainage of the chain locker and watertight compartments above the fore peak tank by hand or power pump suctions.

3.6.2 Steering gear compartments or other small enclosed spaces situated above the after peak tank are to be provided with suitable means of drainage, either by hand or power pump bilge suctions.

3.6.3 Subject to special approval of any applicable subdivision requirements, compartments referred to in 3.6.2 that are adequately isolated from the adjacent 'tween decks, may be drained by scuppers of not less than 38 mm bore, discharging to the tunnel (or machinery space in the case of ships with machinery aft) and fitted with self-closing cocks situated in well lighted and visible positions.

3.6.4 In case of trawlers and fishing vessels, accommodation spaces which overhang the machinery space, may also be drained as in 3.6.3.

3.6.5 For drainage of the fore and after peaks, see 3.5.

### 3.7 Maintenance of integrity of bulkheads

3.7.1 The intactness of the machinery space bulkheads, and of tunnel plating required to be of watertight construction, is not to be impaired by the fitting of scuppers discharging to machinery space or tunnels from adjacent compartments which are situated below the bulkhead deck. These scuppers may, however, be led into a strongly constructed scupper drain tank situated in the machinery space or tunnel, but closed to these spaces and drained by means of a suction of appropriate size led from the main bilge line through a screw-down non-return valve.

3.7.2 The scupper tank air pipe is to be led to above the bulkhead deck, and provision is to be made for ascertaining the level of water in the tank.

3.7.3 Where one tank is used for the drainage of several watertight compartments, the scupper pipes are to be provided with screw-down non-return valves.

3.7.4 No drain valve or cock is to be fitted to the collision bulkhead. Drain valves or cocks are not to be fitted to other watertight bulkheads if alternative means of drainage are practicable.

3.7.5 Where drain valves or cocks are fitted to bulkheads other than the collision bulkhead, as permitted by 3.7.4, the drain valves or cocks are to be at all times readily accessible and are to be capable of being shut off from positions above the bulkhead deck. Indicators are to be provided to show whether the drains are open or shut. These arrangements are not permissible in passenger ships.

3.7.6 Bilge drain valves or cocks may be used for draining accommodation spaces and the after dry peak of trawlers and fishing vessels as stated in 3.6.4 and 3.5.3.

3.7.7 For drainage of stern compartment, see 3.6.

# Ship Piping Systems

## Part 5, Chapter 13

Section 4

### ■ Section 4 Bilge drainage of machinery space

#### 4.1 General

4.1.1 The bilge drainage arrangements in the machinery space are to comply with 3.1, except that the arrangements are to be such that any water which may enter this compartment can be pumped out through at least two bilge suction when the ship is on an even keel, and is either upright or has a list of not more than 5°. One of these suction is to be a branch bilge suction, i.e. a suction connected to the main bilge line, and the other is to be a direct bilge suction, i.e. a suction led direct to an independent power pump. Examples of the necessary arrangements are detailed in 4.2 and 4.3.

4.1.2 In passenger ships, the drainage arrangements are to be such that machinery spaces can be pumped out under all practical conditions after a casualty, whether the ship is upright or listed.

#### 4.2 Machinery space with double bottom

4.2.1 Where the double bottom extends the full length of the machinery space and forms bilges at the wings, it will be necessary to provide one branch and one direct bilge suction at each side.

4.2.2 Where the double bottom plating extends the full length and breadth of the compartment, one branch bilge suction and one direct bilge suction are to be led to each of two bilge wells, situated one at each side.

4.2.3 For capacity and construction of bilge wells, see 7.6.

#### 4.3 Machinery space without double bottom

4.3.1 Where there is no double bottom and the rise of floor is not less than 5°, one branch and one direct bilge suction are to be led to accessible positions as near the centreline as practicable.

4.3.2 In ships where the rise of floor is less than 5°, and in all passenger ships, additional bilge suction are to be provided at the wings.

#### 4.4 Additional bilge suction

4.4.1 Additional bilge suction may be required for the drainage of depressions in the tank top formed by crankpits, or other recesses, by tank tops having inverse camber or by discontinuity of the double bottom.

4.4.2 In ships in which the propelling machinery is situated at the after end of the ship, it will generally be necessary for bilge suction to be fitted in the forward wings as well as in the after end of the machinery space, but each case will be dealt with according to the size and structural arrangements of the compartment.

4.4.3 In ships propelled by electrical machinery, special means are to be provided to prevent the accumulation of bilge water under the main propulsion generators and motors.

#### 4.5 Separate machinery spaces

4.5.1 Where the machinery space is divided by watertight bulkheads to separate the boiler room(s), or auxiliary engine room(s) from the main engine room, the number and position of the branch bilge suction in the boiler room(s) or auxiliary engine room(s) are to be the same as for cargo holds.

4.5.2 In addition to the branch bilge suction, required by 4.5.1, at least one independent power pump direct bilge suction is to be fitted in each compartment. Similar provision is to be made in separate motor rooms of electrically propelled ships.

4.5.3 In passenger ships, each independent bilge pump is to have a direct bilge suction from the space in which it is situated, but not more than two such suction are required in any one space. Where two or more such suction are provided, there is to be at least one suction on each side of the space.

#### 4.6 Machinery space – Emergency bilge drainage

4.6.1 In addition to the bilge suction detailed in 4.1 to 4.5, an emergency bilge suction is to be provided in each main machinery space. This suction is to be led to the main cooling water pump from a suitable low level in the machinery space and is to be fitted with a screw-down non-return valve having the spindle so extended that the hand wheel is not less than 460 mm above the bottom platform.

4.6.2 Where two or more cooling water pumps are provided, each capable of supplying cooling water for normal power, only one pump need be fitted with an emergency bilge suction.

4.6.3 In ships with steam propelling machinery, the suction is to have a diameter of at least two-thirds that of the pump suction. In other ships, the suction is to be the same size as the suction branch of the pump.

4.6.4 Where main cooling water pumps are not suitable for bilge pumping duties, the emergency bilge suction is to be led to the largest available power pump, which is not a bilge pump detailed in 6.1 and 6.2. This pump is to have a capacity not less than that required for a bilge pump and the bilge suction is to be the same size as that of the pump suction branch.

4.6.5 Where the pump to which the emergency bilge suction is connected is of the self-priming type, the direct bilge suction on the same side of the ship as the emergency suction may be omitted, except in passenger ships.

4.6.6 Emergency bilge suction valve nameplates are to be marked 'For emergency use only'.



# Ship Piping Systems

# Part 5, Chapter 13

Sections 4, 5 & 6

## 4.7 Tunnel drainage

4.7.1 The tunnel well is to be drained by a suction from the main bilge line. In all ships, including passenger ships, this well may extend to the outer bottom.

4.7.2 Where the tank top in the tunnel slopes down from aft to forward, a bilge suction is to be provided at the forward end of the tunnel, in addition to the tunnel well suction required by 4.7.1.

5.3.3 For sizes of emergency bilge suctions, see 4.6.

## 5.4 Main bilge line – Tankers and similar ships

5.4.1 In oil tankers and similar ships, where the engine room pumps do not deal with bilge drainage outside the machinery space, the diameter of the main bilge line may be less than that required by the formula in 5.1.1, provided that the cross-sectional area is not less than twice that required for the branch bilge suctions in the machinery space.

## 5.5 Distribution chest branch pipes

5.5.1 The area of each branch pipe connecting the bilge main to a distribution chest is to be not less than the sum of the areas required by the Rules for the two largest branch bilge suction pipes connected to that chest, but need not be greater than that required for the main bilge line.

## 5.6 Tunnel suction

5.6.1 The bilge suction pipe to the tunnel well is to be not less than 65 mm bore, except in ships not exceeding 60 m in length, in which case it may be 50 mm bore.

## Section 5 Sizes of bilge suction pipes

### 5.1 Main bilge line

5.1.1 The diameter,  $d_m$ , of the main bilge line is to be not less than required by the following formula, to the nearest 5 mm, but in no case is the diameter to be less than that required for any branch bilge suction:

$$d_m = 1,68 \sqrt{L (B + D)} + 25 \text{ mm}$$

where

- $d_m$  = internal diameter of main bilge line, in mm
- $B$  = greatest moulded breadth of ship, in metres
- $D$  = moulded depth to bulkhead deck, in metres
- $L$  = Rule length of ship as defined in Pt 3, Ch 1.6.1, in metres, for ships other than passenger ships  
= length between perpendiculars at the extremities of the deepest subdivision load line, in metres, for passenger ships.

### 5.2 Branch bilge suctions to cargo and machinery spaces

5.2.1 The diameter,  $d_b$ , of branch bilge suction pipes to cargo and machinery spaces is to be not less than required by the following formula, to the nearest 5 mm, but in no case is the diameter of any suction to be less than 50 mm:

$$d_b = 2,15 \sqrt{C (B + D)} + 25 \text{ mm}$$

where

- $d_b$  = internal diameter of branch bilge suction, in mm
- $C$  = length of compartment, in metres, and
- $B$  and  $D$  are as defined in 5.1.1.

### 5.3 Direct bilge suctions, other than emergency suctions

5.3.1 The direct bilge suctions in the main engine room, and the direct bilge suctions in large separate boiler rooms, motor rooms of electrically propelled ships and auxiliary engine rooms are not to be of a diameter less than that required for the main bilge line.

5.3.2 Where the separate machinery spaces are of small dimensions, the sizes of the direct bilge suctions to these spaces will be specially considered.

## Section 6 Pumps on bilge service and their connections

### 6.1 Number of pumps

6.1.1 For ships other than passenger ships, at least two power bilge pumping units are to be provided in the machinery space. In ships of 90 m in length and under, one of these units may be worked from the main engines and the other is to be independently driven. In larger ships both units are to be independently driven.

6.1.2 Each unit may consist of one or more pumps connected to the main bilge line, provided that their combined capacity is adequate.

6.1.3 In ships other than passenger ships, a bilge ejector in combination with a high pressure sea-water pump may be accepted as a substitute for an independent bilge pump as required by 6.1.1.

6.1.4 Special consideration will be given to the number of pumps for small ships and, in general, if there is a class notation restricting a small ship to harbour or river service, a hand pump may be accepted in lieu of one of the bilge pumping units.

# Ship Piping Systems

## Part 5, Chapter 13

Sections 6 & 7

6.1.5 For passenger ships, at least three power bilge pumps are to be provided, one of which may be operated from the main engines. Where the criterion numeral as derived from Regulation 6.3 of Chapter II-1 of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments, is 30 or more, one additional independent power pump is to be provided.

6.1.6 For location of pumps on passenger ships, see 8.1.

### 6.2 General service pumps

6.2.1 The bilge pumping units, or pumps, required by 6.1 may also be used for ballast, fire or general service duties of an intermittent nature, but they are to be immediately available for bilge duty when required, see also SOLAS 1974 as amended Reg. II-2/C,10, as applicable.

### 6.3 Capacity of pumps

6.3.1 Each bilge pumping unit, or bilge pump in the case of passenger ships, is to be connected to the main bilge line and is to be capable of giving a speed of water through the Rule size of main bilge pipe of not less than 122 m/min.

6.3.2 The capacity of each bilge pumping unit or bilge pump is to be not less than required by the following formula:

$$Q = \frac{5,75}{10^3} d_m^2$$

where

$d_m$  = Rule internal diameter of main bilge line, in mm  
 $Q$  = capacity, in m<sup>3</sup>/hour.

6.3.3 In ships other than passenger ships, where one bilge pumping unit is of slightly less than Rule capacity, the deficiency may be made good by an excess capacity of the other unit. In general, the deficiency is to be limited to 30 per cent.

### 6.4 Self-priming pumps

6.4.1 All power pumps which are essential for bilge services are to be of the self-priming type, unless an approved central priming system is provided for these pumps. Details of this system are to be submitted.

6.4.2 Cooling water pumps having emergency bilge suction need not be of the self-priming type.

6.4.3 For requirements regarding emergency bilge suction, see 4.6.

### 6.5 Pump connections

6.5.1 The connections at the bilge pumps are to be such that one unit may continue in operation when the other unit is being opened up for overhaul.

6.5.2 Pumps required for essential services are not to be connected to a common suction or discharge chest or pipe unless the arrangements are such that the working of any pumps so connected is unaffected by the other pumps being in operation at the same time.

### 6.6 Direct bilge suction

6.6.1 The direct bilge suction in the machinery space(s) are to be led to independent power pump(s), and the arrangements are to be such that these direct suction can be used independently of the main bilge line suction.

## Section 7 Piping systems and their fittings

### 7.1 Main bilge line suction

7.1.1 Suctions from the main bilge line, i.e. branch bilge suction, are to be arranged to draw water from any hold or machinery compartment of the ship, excepting small spaces such as those mentioned in 3.5 and 3.6, where manual pump suction are accepted, and are not to be of smaller diameter than that required by the formula in 5.2.1. For special arrangements for oil tankers, see Chapter 15.

7.1.2 Where passenger or cargo ships are of a design having enclosed car decks or cargo spaces located on the bulkhead deck or on the freeboard deck, special consideration will be given to the drainage arrangements where any fixed pressure water spray system is fitted, see also Pt 3, Ch 12,4.1 and 9.1.

### 7.2 Prevention of communication between compartments

7.2.1 The arrangement of valves, cocks and their connections is to be such as to prevent the possibility of one watertight compartment being placed in communication with another, or of dry cargo spaces, machinery spaces or other dry compartments being placed in communication with the sea or with tanks. For this purpose, screw-down non-return valves are to be provided in the following fittings:

- Bilge valve distribution chests.
- Bilge suction hose connections, whether fitted direct to the pump or on the main bilge line.
- Direct bilge suction and bilge pump connections to main bilge line.

# Ship Piping Systems

## Part 5, Chapter 13

Section 7

### 7.3 Isolation of bilge system

7.3.1 Bilge pipes which are required for draining cargo or machinery spaces are to be entirely distinct from sea inlet pipes or from pipes which may be used for filling or emptying spaces where water or oil is carried. This does not, however, exclude a bilge ejection connection, a connecting pipe from a pump to its suction valve chest, or a deep tank suction pipe suitably connected through a changeover device to a bilge, ballast or oil line.

### 7.4 Machinery space suctions – Mud boxes

7.4.1 Suctions for bilge drainage in machinery spaces and tunnels, other than emergency suctions, are to be led from easily accessible mud boxes fitted with straight tail pipes to the bilges and having covers secured in such a manner as to permit their being expeditiously opened or closed. Strum boxes are not to be fitted to the lower ends of these tail pipes or to the emergency bilge suctions.

### 7.5 Hold suctions – Strum boxes

7.5.1 The open ends of bilge suctions in holds and other compartments outside machinery spaces and tunnels are to be enclosed in strum boxes having perforations of not more than 10 mm diameter, whose combined area is not less than twice that required for the suction pipe. The boxes are to be so constructed that they can be cleared without breaking any joint of the suction pipe.

### 7.6 Bilge wells

7.6.1 Bilge wells required by 3.2.3 and 4.2.2 are to be formed of steel plates and are to be not less than 0,15 m<sup>3</sup> capacity. In small compartments, steel bilge hats of reasonable capacity may be fitted.

7.6.2 In passenger ships, the depth of bilge wells in double bottom tanks will be specially considered.

7.6.3 Where access manholes to bilge wells are necessary, they are to be fitted as near to the suction strums as practicable.

### 7.7 Tail pipes

7.7.1 The distance between the foot of all bilge tail pipes and the bottom of the bilge well is to be adequate to allow a full flow of water and to facilitate cleaning.

### 7.8 Location of fittings

7.8.1 Bilge valves, cocks and mud boxes are to be fitted at, or above, the machinery space and tunnel platforms. Where it is not practicable to avoid the fittings being situated at the starting platform or in passageways, they may be situated just below the platform, provided readily removable traps or covers are fitted and nameplates indicate the presence of these fittings.

7.8.2 Where relief valves are fitted to pumps having sea connections, these valves are to be fitted in readily visible positions above the platform. The arrangements are to be such that any discharge from the relief valves will also be readily visible.

### 7.9 Bilge pipes in way of double bottom tanks

7.9.1 Bilge suction pipes are not to be led through double bottom tanks if it is possible to avoid doing so.

7.9.2 Bilge pipes which have to pass through these tanks are to have a wall thickness in accordance with Table 12.2.4 in Chapter 12. (The thickness of pipes made from material other than steel will be specially considered.)

7.9.3 Expansion bends, not glands, are to be fitted to these pipes within the tanks, and the pipes are to be tested, after installation, to the same pressure as the tanks through which they pass.

### 7.10 Bilge pipes in way of deep tanks

7.10.1 In way of deep tanks, bilge pipes should preferably be led through pipe tunnels but, where this is not done, the pipes are to be of steel, having a wall thickness in accordance with Table 12.2.4 in Chapter 12, with welded joints or heavy flanged joints. The number of joints is to be kept to a minimum.

7.10.2 Expansion bends, not glands, are to be fitted to these pipes within the tanks, and the open ends of the bilge suction pipes in the holds are to be fitted with non-return valves of the special type approved for use in holds, see 7.11.1.

7.10.3 The pipes are to be tested, after installation, to a pressure not less than the maximum head to which the tanks can be subjected in service.

### 7.11 Hold bilge non-return valves

7.11.1 Where non-return valves are fitted to the open ends of bilge suction pipes in cargo holds in order to decrease the risk of flooding, they are to be of an approved type which does not offer undue obstruction to the flow of water.

### 7.12 Blanking arrangements

7.12.1 In case of deep tanks and cargo holds which may be used for either water ballast or dry cargo, provision is to be made for blank flanging the water ballast filling and suction pipes when the tank or hold is being used for the carriage of dry cargo, and for blank flanging the bilge suction pipes when the tank or hold is being used for the carriage of water ballast. Change-over devices may be used for this purpose.

7.12.2 For arrangements when oil fuel or cargo oil (having a flash point of 60°C or above) is carried in deep tanks, see Ch 14, 4.14.

# Ship Piping Systems

## Part 5, Chapter 13

Sections 7, 8 & 9

7.12.3 Where a ship is designed for the alternative carriage of dry cargo or oil having a flash point below 60°C, the blanking arrangements will be specially considered.

### ■ Section 8 Additional requirements for bilge drainage and cross-flooding arrangements for passenger ships

#### 8.1 Location of bilge pumps and bilge main

8.1.1 In passenger ships, the power bilge pumps required by 6.1.5 are to be placed, if practicable, in separate watertight compartments which will not readily be flooded by the same damage. If the engines and boilers are in two or more watertight compartments, the bilge pumps are to be distributed throughout these compartments so far as is possible.

8.1.2 In passenger ships of 91,5 m or more in length, or having a criterion numeral of 30 or more (see 6.1.5), the arrangements are to be such that at least one power pump will be available for use in all ordinary circumstances in which the ship may be flooded at sea. This requirement will be satisfied if:

- one of the pumps is an emergency pump of a submersible type having a source of power situated above the bulkhead deck, or
- the pumps and their sources of power are so disposed throughout the length of the ship that, under any conditions of flooding which the ship is required by statutory regulation to withstand, at least one pump in an undamaged compartment will be available.

8.1.3 The bilge main is to be so arranged that no part is situated nearer the side of the ship than  $\frac{B}{5}$ , measured at right angles to the centreline at the level of the deepest subdivision load line, where  $B$  is the breadth of the ship.

8.1.4 Where any bilge pump or its pipe connection to the bilge main is situated outboard of the  $\frac{B}{5}$  line, then a non-return valve is to be provided in the pipe connection at the junction with the bilge main. The emergency bilge pump and its connections to the bilge main are to be so arranged that they are situated inboard of the  $\frac{B}{5}$  line.

#### 8.2 Prevention of communication between compartments in the event of damage

8.2.1 Provision is to be made to prevent the compartment served by any bilge suction pipe being flooded, in the event of the pipe being severed, or otherwise damaged by collision or grounding in any other compartment. For this purpose, where the pipe is at any part situated nearer the side of the ship than  $\frac{B}{5}$  or in a duct keel, a non-return valve is to be fitted to the pipe in the compartment containing the open end.

#### 8.3 Arrangement and control of bilge valves

8.3.1 All the distribution boxes, valves and cocks in connection with the bilge pumping arrangements are to be so arranged that, in the event of flooding, one of the bilge pumps may be operative on any compartment. If there is only one system of pipes common to all pumps, the necessary valves or cocks for controlling the bilge suctions must be capable of being operated from the bulkhead deck. Where, in addition to the main bilge pumping system, an emergency bilge pumping system is provided, it is to be independent of the main system and so arranged that a pump is capable of operating on any compartment under flooding conditions; in this case, only the valves and cocks necessary for the operation of the emergency system need be capable of being operated from above the bulkhead deck.

8.3.2 All valves and cocks mentioned in 8.3.1 which can be operated from above the bulkhead deck are to have their controls at their place of operation clearly marked and provided with means to indicate whether they are open or closed.

#### 8.4 Cross-flooding arrangements

8.4.1 Where divided deep tanks or side tanks are provided with cross-flooding arrangements to limit the angle of heel after side damage, the arrangements are to be self-acting where practicable. In any case, where controls to cross flooding fittings are provided, they are to be operable from above the bulkhead deck.

### ■ Section 9 Additional requirements relating to fixed pressure water spray fire-extinguishing systems

#### 9.1 Bilge drainage requirements

9.1.1 Where arrangements for cooling underdeck cargo spaces, or fire-fighting by means of fixed spraying nozzles or by flooding of the cargo space with water are provided, the following provisions are to apply:

- (a) The drainage system is to be sized to remove no less than 125 per cent of the combined capacity of both the water spraying system pumps and the required number of fire hose nozzles.
- (b) The drainage system valves are to be operable from outside the protected space at a position in the vicinity of the extinguishing system controls.
- (c) Adequately sized bilge wells are to be located at the side shell of the ship at a distance of not more than 40 m in each watertight compartment, see also Pt 3, Ch 12, 4.1.4 and Pt 4, Ch 2, 11.2. For cargo ships only, if this is not possible, the free surface effect on the ship's stability is to be determined and submitted to the flag administration for appraisal.

# Ship Piping Systems

# Part 5, Chapter 13

Sections 9 to 12

9.1.2 If drainage of vehicle or cargo spaces is by gravity, the drainage is to be led directly overboard or to a closed drain tank. If led overboard the scuppers are to comply with Pt 3, Ch 12,4.1.3(a) and (b). If led to a closed drain tank, this tank is to be located outside the machinery spaces and provided with a vent pipe leading to a safe location on the open deck. See also Pt 4, Ch 2,11.2.

9.1.3 Drainage from a cargo space into bilge wells in a lower space is only permitted if that space satisfies the same requirements as the cargo space above.

## Section 10 Drainage arrangements for ships not fitted with propelling machinery

### 10.1 Hand pumps

10.1.1 Where auxiliary power is not provided, hand pumps are to be fitted, in number and position, as may be required for the efficient drainage of the ship.

10.1.2 In general, one hand pump is to be provided for each compartment. Alternatively, two pumps connected to a bilge main, having at least one branch to each compartment, are to be provided.

10.1.3 The pumps are to be capable of being worked from the upper deck or from positions above the load waterline which are at all times readily accessible. The suction lift is not to exceed 7,3 m and is to be well within the capacity of the pump.

10.1.4 The sizes of the hand pumps are to be not less than those given in Table 13.10.1. Where the ship is closely subdivided into small watertight compartments, 50 mm bore suctions will be accepted.

**Table 13.10.1 Sizes of hand pumps**

Tonnage under upper deck	Diameter of barrel of bucket pump mm	Bore of suction pipe of bucket pumps and semi-rotary pumps mm
Not exceeding 500 tons	100	50
Above 500 tons but not exceeding 1000 tons	115	57
Above 1000 tons but not exceeding 2000 tons	125	65
Above 2000 tons	140	70

### 10.2 Ships with auxiliary power

10.2.1 In ships in which auxiliary power is available on board, power pump suctions are to be provided for dealing with the drainage of tanks and of the bilges of the principal compartments.

10.2.2 The pumping arrangements are to be as required for self-propelled ships, so far as these requirements are applicable, duly modified to suit the size and service of the ship.

10.2.3 Details of the pumping arrangements are to be submitted for special consideration.

## Section 11 Ballast system

### 11.1 Stand-by arrangements for ballast pumping

11.1.1 Where ballasting/de-ballasting is required for ship operation or trading purposes stand-by ballast pumping arrangements are to be provided, see also 6.2.1 and Ch 15,2.4.4.

## Section 12 Air, overflow and sounding pipes

### 12.1 Definitions

12.1.1 Reference to cargo oil in this Section is to be taken to mean cargo oil which has a flash point 60°C or above (closed cup test).

### 12.2 Materials

12.2.1 Air, overflow and sounding pipes are to be made of steel or other approved material. For use of plastics pipes of approved type, see Chapter 12.

12.2.2 The portions of air, overflow and sounding pipes fitted above the weather deck are to be of steel or equivalent material.

### 12.3 Nameplates

12.3.1 Nameplates are to be affixed to the upper ends of all air and sounding pipes.

### 12.4 Air pipes

12.4.1 Air pipes are to be fitted to all tanks, cofferdams, tunnels and other compartments which are not fitted with alternative ventilation arrangements.

# Ship Piping Systems

## Part 5, Chapter 13

Section 12

12.4.2 The air pipes are to be fitted at the opposite end of the tank to that which the filling pipes are placed and/or at the highest part of the tank. Where the tank top is of unusual or irregular profile, special consideration will be given to the number and position of the air pipes.

### 12.5 Termination of air pipes

12.5.1 Air pipes to double bottom tanks, deep tanks extending to the shell plating, or tanks which can be run up from the sea are to be led to above the bulkhead deck. Air pipes to oil fuel and cargo oil tanks, cofferdams and all tanks which can be pumped up are to be led to the open. For height of air pipes above deck, see Pt 3, Ch 12,3.

12.5.2 Air pipes from storage tanks containing lubricating or hydraulic oil may terminate in the machinery space, provided that the open ends are so situated that issuing oil cannot come into contact with electrical equipment or heated surfaces. Air pipes from heated lubricating oil tanks are to be led to the open.

12.5.3 The open ends of air pipes to oil fuel and cargo oil tanks are to be situated where no danger will be incurred from issuing oil vapour when the tank is being filled.

12.5.4 The location and arrangement of air pipes for oil fuel service, settling and lubricating oil tanks are to be such that in the event of a broken vent pipe, this does not directly lead to the risk of ingress of sea-water or rainwater.

12.5.5 For special requirements for the termination of air pipes on ferries, see Pt 3, Ch 12,3 and Pt 4, Ch 2,10.

### 12.6 Gauze diaphragms

12.6.1 The open ends of air pipes to oil fuel and cargo oil tanks are to be furnished with a wire gauze diaphragm of incorrodible material which can be readily removed for cleaning or renewal.

12.6.2 Where wire gauze diaphragms are fitted at air pipe openings, the area of the opening through the gauze is to be not less than the cross-sectional area required for the pipe, see 12.8.

### 12.7 Air pipe closing appliances

12.7.1 The closing appliances fitted to tank air pipes in accordance with Pt 3, Ch 12,3.3 are to be of an automatic opening type which will allow the free passage of air or liquid to prevent the tanks being subjected to a pressure or vacuum greater than that for which they are designed.

12.7.2 Air pipe closing devices are to be of a type acceptable to Lloyd's Register (hereinafter referred to as 'LR') and are to be tested in accordance with a National or International Standard recognized by LR. The flow characteristic of the closing device is to be determined using water, see 12.8.1 and 12.8.2.

12.7.3 Wood plugs and other devices which can be secured closed are not to be fitted at the outlets.

### 12.8 Size of air pipes

12.8.1 For every tank which can be filled by the ship's pumps, the total cross-sectional area of the air pipes and the design of the air pipe closing devices are to be such that when the tank is overflowing at the maximum pumping capacity available for the tank, it will not be subjected to a pressure greater than that for which it is designed.

12.8.2 In all cases, whether a tank is filled by ship's pumps or other means, the total cross-sectional area of the air pipes is to be not less than 25 per cent greater than the effective area of the respective filling pipe.

12.8.3 Where tanks are fitted with cross flooding connections, the air pipes are to be of adequate area for these connections.

12.8.4 Air pipes are to be not less than 50 mm bore.

### 12.9 Overflow pipes

12.9.1 For all tanks which can be filled by the ship's pumps or by shore pumps, overflow pipes are to be fitted where:

- (a) The total cross-sectional area of the air pipe is less than that required by 12.8.
- (b) The pressure head corresponding to the height of the air pipe is greater than that for which the tank is designed.

12.9.2 In the case of oil fuel and lubricating oil tanks, the overflow pipe is to be led to an overflow tank of adequate capacity or to a storage tank having a space reserved for overflow purposes. Suitable means are to be provided to indicate when overflow is occurring, or when the contents reach a predetermined level in the tanks.

12.9.3 Overflow pipes are to be self draining under normal conditions of trim.

12.9.4 Where overflow sight glasses are provided, they are to be in a vertically dropping line and designed such that the oil does not impinge on the glass. The glass is to be of heat resisting quality, adequately protected from mechanical damage and well lit.

### 12.10 Air and overflow systems

12.10.1 Where a combined air or overflow system is fitted, the arrangement is to be such that in the event of any one of the tanks being bilged, tanks situated in other watertight compartments of the ship cannot be flooded from the sea through combined air pipes or the overflow main. For this purpose, it will normally be necessary to lead the overflow pipe to a point close to the bulkhead deck.

# Ship Piping Systems

## Part 5, Chapter 13

Section 12

12.10.2 In the case of trawlers and fishing vessels, the arrangement is to be such that in the event of any one of the tanks being bilged, the other tanks cannot be flooded from the sea through the combined air pipes or the overflow main.

12.10.3 Where overflow from tanks which are used for the alternative carriage of oil and water ballast is connected to an overflow system, arrangements are to be made to prevent water ballast overflowing into tanks containing oil, *see also* Ch 14,4.14.

12.10.4 Where a common overflow main is provided, the main is to be sized to allow any two tanks connected to that main to overflow simultaneously.

### 12.11 Sounding arrangements

12.11.1 Provision is to be made for sounding all tanks and the bilges of those compartments which are not at all times readily accessible. The soundings are to be taken as near the suction pipes as practicable.

12.11.2 Bilges of compartments which are not at all times readily accessible are to be provided with sounding pipes.

12.11.3 Where fitted, sounding pipes are to be as straight as practicable, and if curved to suit the structure of the ship, the curvature must be sufficiently easy to permit the ready passage of the sounding rod or chain.

12.11.4 Sounding devices of approved type may be used in lieu of sounding pipes for sounding tanks. These devices are to be tested, after fitting on board, to the satisfaction of the Surveyors.

12.11.5 Where gauge glasses are used for indicating the level of liquid in tanks containing lubricating oil, oil fuel or other flammable liquid, the glasses are to be of the flat type of heat-resisting quality, adequately protected from mechanical damage, and fitted with self-closing valves at the lower ends and at the top ends if these are connected to the tanks below the maximum liquid level.

12.11.6 If means of sounding, other than a sounding pipe, is fitted in any ship for indicating the level of liquid in tanks containing oil fuel, lubricating oil or other flammable liquid, failure of such means or over filling of the tank should not result in the release of tank contents.

12.11.7 In passenger ships, sounding devices for oil fuel tanks, lubricating oil tanks and other tanks which may contain flammable liquids are to be of a type which does not require penetration below the top of the tank.

### 12.12 Termination of sounding pipes

12.12.1 Sounding pipes are to be led to positions above the bulkhead deck which are at all times accessible and, in the case of oil fuel tanks, cargo oil tanks, lubricating oil tanks and tanks containing other flammable oils, the sounding pipes are to be led to safe positions on the open deck.

12.12.2 For closing requirements, *see also* Pt 3, Ch 12,3.

### 12.13 Short sounding pipes

12.13.1 In machinery spaces and tunnels, in circumstances where it is not practicable to extend the sounding pipes as mentioned in 12.12, short sounding pipes extending to well lighted readily accessible positions above the platform may be fitted to double bottom tanks. Where such pipes serve tanks containing oil fuel or other flammable liquid, an additional sounding device of approved type is to be fitted. An additional sounding device is not required for lubricating oil tanks. Any proposal to terminate in the machinery space, sounding pipes to tanks, other than double bottom tanks, will be the subject of special consideration.

12.13.2 Short sounding pipes to oil fuel, cargo oil (flash point not less than 60°C), lubricating oil tanks and other flammable oil tanks (flash point not less than 60°C) are to be fitted with cocks having parallel plugs with permanently attached handles, so loaded that, on being released, they automatically close the cocks. In addition, a small diameter self-closing test cock is to be fitted below the cock mentioned above in order to ensure that the sounding pipe is not under a pressure of oil before opening-up the sounding cock. Provision is to be made to ensure that discharge of oil through this test cock does not present an ignition hazard. An additional small diameter self-closing test cock is not required for lubricating oil tanks.

12.13.3 As a further precaution against fire, such sounding pipes are to be located in positions as far removed as possible from any heated surface or electrical equipment and, where necessary, effective shielding is to be provided in way of such surfaces and/or equipment.

12.13.4 In ships that are required to be provided with a double bottom, short sounding pipes, where fitted to double bottom tanks, are in all cases to be provided with self-closing cocks as described in 12.13.2.

12.13.5 Where a double bottom is not required to be fitted, short sounding pipes to tanks other than oil tanks are to be fitted with shut-off cocks or with screw caps attached to the pipes by chains.

12.13.6 In passenger ships, short sounding pipes are permissible only for sounding cofferdams and double bottom tanks situated in a machinery space, and are in all cases to be fitted with self-closing cocks as described in 12.13.2.

### 12.14 Elbow sounding pipes

12.14.1 Elbow sounding pipes are not to be used for deep tanks unless the elbows and pipes are situated within closed cofferdams or within tanks containing similar liquids. They may, however, be fitted to other tanks and may be used for sounding bilges, provided that it is not practicable to lead them direct to the tanks or compartments, and subject to any subdivision and damage stability requirements that may apply, *see* 1.2.1.

12.14.2 The elbows are to be of heavy construction and adequately supported.

12.14.3 In passenger ships, elbow sounding pipes are not permissible.

### 12.15 Striking plates

12.15.1 Striking plates of adequate thickness and size are to be fitted under open-ended sounding pipes.

12.15.2 Where slotted sounding pipes having closed ends are employed, the closing plugs are to be of substantial construction.

### 12.16 Sizes of sounding pipes

12.16.1 Sounding pipes are to be not less than 32 mm bore.

12.16.2 All sounding pipes, whether for compartments or tanks, which pass through refrigerated spaces or the insulation thereof, in which the temperatures contemplated are 0°C or below, are to be not less than 65 mm bore, *see also* 2.8.1 for insulation.

---

### ■ Cross-references

For 'Ice Class' requirements, *see* Chapter 9.

For venting and gauging equipment for cargo tanks in oil tankers, *see* Ch 15,4 and Ch 15,5.

For control engineering equipment, *see* Pt 6, Ch 1.

For requirements relating to scuppers and sanitary discharges, *see* Pt 3, Ch 12.

---



# Machinery Piping Systems

# Part 5, Chapter 14

Sections 1 & 2

## Section

- 1 **General requirements**
- 2 **Oil fuel – General requirements**
- 3 **Oil fuel burning arrangements**
- 4 **Oil fuel pumps, pipes, fittings, tanks, etc.**
- 5 **Steam piping systems**
- 6 **Boiler feed water and condensate systems**
- 7 **Engine cooling water systems**
- 8 **Lubricating oil systems**
- 9 **Hydraulic systems**
- 10 **Low pressure compressed air systems**
- 11 **Multi-engined ships**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 In addition to the requirements detailed in this Chapter, the requirements of Ch 13,1 and 2 are to be complied with, where applicable.

1.1.2 The requirements of Ch 13,3 are also to be complied with, so far as they are applicable, for the drainage of tanks, oily bilges and cofferdams, etc.

1.1.3 The requirements of Sections 2 and 4 are to be complied with, as far as they are applicable, for all flammable liquids.

## ■ Section 2 Oil fuel – General requirements

### 2.1 Flash point

2.1.1 The flash point (closed cup test) of oil fuel for use in ships classed for unrestricted service is, in general, to be not less than 60°C. For emergency generator engines a flash point of not less than 43°C is permissible.

2.1.2 The use of oil fuel having a flash point of less than 60° but not less than 43° may be permitted for emergency generators, emergency fire pumps, engines and auxiliary machines which are not located in machinery spaces subject to the requirements of 4.19.

2.1.3 The use of fuel having a lower flash point than specified in 2.1.1 or 2.1.2 may be permitted in cargo ships provided that such fuel is not stored in any machinery space and the arrangements for the complete installation are specially approved.

2.1.4 In general, oil fuel in storage and service tanks is not to be heated to a temperature exceeding 10°C below its flash point. Higher temperatures will be considered where:

- (a) The tanks are vented to a safe position outside the engine room and, as in the case of all oil fuel tanks, the ends of the ventilation pipes are fitted with gauze diaphragms.
- (b) Openings in the drainage systems of tanks containing heated oil fuel are located in spaces where no accumulation of oil vapours at temperatures close to the flash point can occur.
- (c) There is no source of ignition in the vicinity of the ventilation pipes or near the openings in the drainage systems or in the tanks themselves.

2.1.5 The temperature of any heating medium is not to exceed 220°C.

### 2.2 Special fuels

2.2.1 When it is desired to carry a quantity of fuel having a flash point below 43°C for special services, e.g. aviation spirit for use in helicopters, full particulars of the proposed arrangements are to be submitted for special consideration. For helicopter refuelling, as a minimum, the requirements of SOLAS 1974 as amended II-2/G, 18-7 will apply.

2.2.2 For the burning of methane gas in methane tankers, see the *Rules for Ships for the Carriage of Liquefied Gases* (hereinafter referred to as the Rules for Ships for Liquefied Gases).

2.2.3 Where it is proposed to use gaseous fuels for main or auxiliary engines in ships other than methane tankers, the relevant requirements of the Rules for Ships for Liquefied Gases are to be complied with. Full particulars of the proposed arrangements are to be submitted for special consideration. Attention is to be given to any relevant statutory requirements of the National Authority of the country in which the ships are to be registered.

### 2.3 Oil fuel sampling

2.3.1 Sampling points are to be provided at locations within the oil fuel system that enable samples of oil fuel to be taken in a safe manner.

2.3.2 The position of a sampling point is to be such that the sample of the oil fuel is representative of the oil fuel quality at that location within the system.

#### NOTE:

Samples taken from sounding pipes are not considered to be representative of the tank's contents.

# Machinery Piping Systems

## Part 5, Chapter 14

Section 2

2.3.3 The sampling arrangements within the machinery space are to be capable of safely providing samples when machinery is running and are to be provided with isolating valves and cocks of the self-closing type. The sampling points are to be located in positions as far removed as possible from any heated surface or electrical equipment so as to preclude impingement of oil fuel onto such surfaces on equipment under all operating conditions, see Pt 5, Ch 1,3.7.

### 2.4 Ventilation

2.4.1 The spaces in which the oil fuel burning appliances and the oil fuel settling and service tanks are fitted are to be well ventilated and easy of access.

### 2.5 Boiler insulation and air circulation in boiler room

2.5.1 The boilers are to be suitably lagged. The clearance spaces between the boilers and tops of the double bottom tanks, and between the boilers and the sides of the storage tanks in which oil fuel and cargo oil is carried, are to be adequate for the free circulation of the air necessary to keep the temperature of the stored oil sufficiently below its flash point.

2.5.2 Where water tube boilers are installed, there is to be a space of at least 760 mm between the tank top and the underside of the pans forming the bottom of the combustion spaces.

2.5.3 Smoke-box doors are to be shielded and well fitting, and the uptake joints made gastight. Where the surface temperature of the uptakes may exceed 220°C, they are to be efficiently lagged to minimize the risk of fire and to prevent damage by heat. Where lagging covering the uptakes, including flanges, is oil-absorbing or may permit penetration of oil, the lagging is to be encased in sheet metal or equivalent. In locations where the Surveyor is satisfied that oil impingement could not occur, the lagging need not be encased.

### 2.6 Funnel dampers

2.6.1 Dampers which are capable of completely closing the gas passages are not to be fitted to inner funnels of ships equipped for burning oil fuel only. In ships burning oil or coal alternatively, dampers may be retained, if they are provided with a suitable device whereby they may be securely locked in the fully open position.

### 2.7 Heating arrangements

2.7.1 Where steam is used for heating oil fuel, cargo oil or lubricating oil, in bunkers, tanks, heaters or separators, the exhaust drains are to discharge the condensate into an observation tank in a well lighted and accessible position where it can be readily seen whether or not it is free from oil, see Ch 15,6.4.

2.7.2 Where hot water is used for heating, means are to be provided for detecting the presence of oil in the return lines from the heating coils.

2.7.3 Where it is proposed to use any heating medium other than steam or hot water, full particulars of the proposed arrangements are to be submitted for special consideration.

2.7.4 The heating pipes in contact with oil are to be of iron, steel, approved aluminium alloy or approved copper alloy, and, after being fitted on board, are to be tested by hydraulic pressure in accordance with the requirements of Ch 12,8.1.

2.7.5 Where electric heating elements are fitted means are to be provided to ensure that all elements are submerged at all times when electric current is flowing and that their surface temperature cannot exceed 220°C.

### 2.8 Temperature indication

2.8.1 Tanks and heaters in which oil is heated are to be provided with suitable means for ascertaining the temperature of the oil. Where thermometers or temperature sensing devices are not fitted in blind pockets, a warning notice, in raised letters, is to be affixed adjacent to the fittings stating 'Do not remove unless tank/heater is drained'.

2.8.2 Controls are to be fitted to limit oil temperatures in oil storage and service tanks in accordance with 2.1.4 and in oil heaters to the maximum approved operating temperature, see Pt 6, Ch 1.

### 2.9 Precautions against fire

2.9.1 Oil fuel tanks and oil fuel filters are not to be situated immediately above boilers or other highly heated surfaces, see also Ch 1,4.5.

2.9.2 Oil fuel pipes are not to be installed above or near high temperature equipment. Oil fuel pipes should also be installed and screened or otherwise suitably protected to avoid oil spray or oil leakages onto hot surfaces, into machinery air intakes, or other sources of ignition such as electrical equipment. Pipe joints are to be kept to a minimum, and where provided are to be of a type acceptable to LR. Pipes are to be led in well lit and readily visible positions, see also Ch 2,7.

2.9.3 Pumps, filters and heaters are to be located to avoid oil spray or oil leakages onto hot surfaces or other sources of ignition, or onto rotating machinery parts. Where necessary, shielding is to be provided and the arrangements are to allow easy access for routine maintenance. The design of filter and strainer arrangements is to be such as to avoid the possibility of them being opened inadvertently when under pressure. This may be achieved by either mechanically preventing the pressurized filter from being opened or by providing pressure gauges which clearly indicate which filter is under pressure. In either case, suitable means for pressure release are to be provided, with drain pipes led to a safe location.

# Machinery Piping Systems

# Part 5, Chapter 14

Sections 2 & 3

2.9.4 The arrangement and location of short sounding pipes to oil tanks are to be in accordance with Ch 13,12.13. For alternative sounding arrangements, see Ch 13,12.11.

2.9.5 Water service pipes and hoses are to be fitted in order that the floor plates and tank top or shell plating in way of boilers, oil fuel apparatus or deep storage tanks in the engine and boiler spaces can at any time be flushed with sea-water.

2.9.6 So far as is practicable, the use of wood is to be avoided in the engine rooms, boiler rooms and tunnels of ships burning oil fuel.

2.9.7 Drip trays are to be fitted at the furnace mouths to intercept oil escaping from the burners, and under all other oil fuel appliances which are required to be opened up frequently for cleaning or adjustment.

2.9.8 Oil-tight drip trays of ample size having suitable drainage arrangements are to be provided at pipes, pumps, valves and other fittings where there is a possibility of leakage. Valves should be located in well lighted and readily visible positions. Drip trays will not be required where pumps, valves and other fittings are placed in special compartments either inside or outside the machinery space with approved overall drainage arrangements or for valves which are so positioned that any leakage will drain directly into the bilges see 2.9.2.

2.9.9 Where drainage arrangements are provided from collected leakages, they are to be led to a suitable oil drain tank not forming part of an overflow system.

2.9.10 Separate oil fuel tanks are to be placed in an oil-tight spill tray of ample size having drainage arrangements leading to a drain tank of suitable size, see 4.17.

## 2.10 Oil fuel contamination

2.10.1 The materials and/or their surface treatment used for the storage and distribution of oil fuel are to be selected such that they do not introduce contamination or modify the properties of the fuel. The use of copper or zinc compounds in oil fuel distribution and utilisation piping is not permitted except for small diameter pipes in low pressure systems, see 4.6.1.

2.10.2 For prevention of ingress of water into oil fuel tanks via air pipes, see Ch 13,10.5.4.

2.10.3 The piping arrangements for oil fuel are to be separate and distinct from those intended for lubricating oil systems to prevent contamination of fuel oil by lubricating oil.

2.10.4 The piping arrangements for gas oil, distillate and diesel grades are to be separate and distinct from those intended for residual grades, up to the service tanks required by 4.18, to prevent cross-contamination. Cross-connection is permitted between separate arrangements in the event of failure of a designated item of equipment.

## ■ Cross-reference

For requirements regarding refrigerated cargo spaces in way of oil storage tanks, see Pt 6, Ch 3,4.

## ■ Section 3 Oil fuel burning arrangements

### 3.1 Oil burning units

3.1.1 Where steam is required for the main propelling engines, or where steam or thermal oil is required for auxiliary machinery for essential services, or for heating of heavy oil fuel and is generated by burning oil fuel under pressure, there are to be not less than two oil burning units. For auxiliary boilers, a single oil burning unit may be accepted, provided that alternative means, such as an exhaust gas boiler or composite boiler, are available for supply of essential services. Where the oil burning unit is not of the monobloc type (i.e. separate register and oil supply unit), each oil burning unit is to comprise a pressure pump, suction filter, discharge filter and, when required, a heater.

3.1.2 In installations consisting of two or more oil burning units, the number, arrangement and capacity of such units is to be capable of supplying sufficient fuel to allow the steam to be generated or thermal oil heated, as applicable to provide essential services with any one unit out of action.

3.1.3 Unit pressure pumps are to be entirely separate from the feed, bilge or ballast systems.

3.1.4 In dual oil fuel burning systems for boilers which are primarily designed for operation with residual fuel oil grades, arrangements are to be such that atomising steam cannot be used in combination with distillate fuel oil grades where the burner arrangements have not been designed for such use.

3.1.5 Whenever the oil fuel burning units are stopped, shut-off arrangements for oil fuel to the units are to be provided as follows:

- (a) If the supply oil fuel is under pressure during shut-off to oil burning units, duplicated shut-off valves in series are to be fitted. Arrangements are to be such to allow manual testing for leakage from each of the valves in the installed condition, the test arrangement is to be such to prevent inadvertent operation, and any discharges are to be led to a safe position to ensure that discharge of leakage oil does not present an ignition hazard.
- (b) If arrangements are such that oil fuel pressure is released through drainage during oil fuel shut-off to oil burning units, a single shut-off device may be accepted subject to approval by LR.

3.1.6 When combined air and fuel/steam/air combustion systems are used for multiple boiler installations, they are to be such that single boiler operation will not be adversely affected by the operation of another boiler system at any time.

# Machinery Piping Systems

## Part 5, Chapter 14

Section 3

3.1.7 Arrangements are to be such that furnace pre-purging is completed prior to any burner ignition sequence. The purge time is to be based on a minimum of 4 air changes of the combustion chamber, furnace and uptake spaces. The purge timing is to take account of the air flow rate and the sequence is not to commence until all air registers and dampers, as applicable, are fully open and the forced draft fans are operating.

3.1.8 The effect of multiple light-off failures is to be assessed and the need to lock out further ignition sequences established. The manufacturer's recommended procedures are to be followed before further attempts to ignite the boiler are made. These procedures are to be displayed at the ignition control positions and included in the warning notice required by 3.1.11.

3.1.9 Means are to be provided so that, in the event of flame failure, the oil fuel supply to the burner(s) is shut-off automatically, and an alarm is given, see Pt 6, Ch 1,3.5 to 3.8, as applicable.

3.1.10 It is to be demonstrated to the Surveyor's satisfaction during trials that burner shut-off times due to flame failure comply with the following requirements, and details of the procedures and means used to set this time interval are to be submitted for consideration:

- (a) The time interval at burner start up between the burner oil fuel valve(s) being opened and then closed in the event of flame failure is to be long enough to allow a stable flame to be established and detected under normal operational circumstances, but is to be set to minimise the quantity of oil fuel delivered to the furnace and the possibility of subsequent damage as a result of unintended ignition.
- (b) The time interval between flame failure detection and closing of burner oil fuel valve(s) is to be long enough to prevent shutdown due to incorrect detection of a flame failure under normal operational circumstances, but is to be set to minimise the quantity of unburned oil fuel delivered to the furnace and the possibility of subsequent damage as a result of unintended ignition.

3.1.11 A warning notice is to be fitted in a prominent position at every oil burning unit local manual control station which specifies that burners operated with manual or local overrides in use are only to be ignited after sufficient purging of the furnace and of any additional precautions required when operating in this condition.

### 3.2 Gravity feed

3.2.1 In systems where oil is fed to the burners by gravity, duplex filters are to be fitted in the supply pipeline to the burners and so arranged that one filter can be opened up when the other is in use.

### 3.3 Starting-up unit

3.3.1 A starting-up oil fuel unit, including an auxiliary heater and hand pump, or other suitable starting-up device, which does not require power from shore, is to be provided.

3.3.2 Alternatively, where auxiliary machinery requiring compressed air or electric power is used to bring the boiler plant into operation, the arrangements for starting such machinery are to comply with Ch 2,8.1.

### 3.4 Steam connections to burners

3.4.1 Where burners are provided with steam purging and/or atomizing connections, the arrangements are to be such that oil fuel cannot find its way into the steam system in the event of valve leakage.

### 3.5 Burner arrangements

3.5.1 The burner arrangements are to be such that a burner cannot be withdrawn unless the oil fuel supply to that burner is shut-off, and that the oil cannot be turned on unless the burner has been correctly coupled to the supply line.

### 3.6 Quick-closing valve

3.6.1 A quick-closing master valve is to be fitted to the oil supply to each boiler manifold, suitably located so that the valve can be readily operated in an emergency, either directly or by means of remote control, having regard to the machinery arrangements and location of controls.

### 3.7 Spill arrangements

3.7.1 Provision is to be made, by suitable non-return arrangements, to prevent oil from spill systems being returned to the burners when the oil supply to these burners has been shut-off.

### 3.8 Alternately-fired furnaces

3.8.1 For alternately-fired furnaces of boilers using exhaust gases and oil fuel, the exhaust gas inlet pipe is to be provided with an isolating device and interlocking arrangements whereby oil fuel can only be supplied to the burners when the isolating device is closed to the boiler.

### 3.9 Oil fuel treatment for supply to main and auxiliary oil engines and gas turbines

3.9.1 A suitable fuel treatment plant that may include filtration, centrifuging and/or coalescing is to be provided to reduce the level of water and particulate contamination of the oil fuel to within the engine or gas turbine manufacturer's limits for inlet to the combustion system. The capacity and arrangements of the treatment plant is to be suitable for ensuring availability of treated oil fuel for the maximum

# Machinery Piping Systems

# Part 5, Chapter 14

Sections 3 & 4

continuous demand of the propulsion and electrical generating plant.

3.9.2 Two or more treatment systems are to be provided as part of the fuel treatment plant such that failure of one system will not render the other system(s) inoperative. Arrangements are to ensure that the failure of a treatment system will not interrupt the supply of clean oil fuel to oil engines or gas turbines used for propulsion and electrical generating purposes where treatment plant is installed between oil fuel service tanks and the inlet to the combustion system. Any treatment equipment in the system is to be capable of being cleaned without interrupting the flow of treated fuel to supply the combustion system.

3.9.3 Centrifuges used for oil fuel treatment are to be type tested for their intended usage when installed on board a ship in accordance with a standard acceptable to LR.

3.9.4 Where heating of the oil fuel is required for the efficient functioning of the oil fuel treatment plant, a minimum of two heating units are to be provided. Each heating unit is to be of sufficient capacity to raise and maintain the required temperature of the oil fuel for the required delivery flow rate.

3.9.5 Heating units may be in circuit with separate treatment systems or provided with connections such that any heating unit can be connected to any treatment system.

3.9.6 Where heating of the oil fuel is required for combustion, not less than two pre-heaters are to be provided, each with sufficient capacity to raise the temperature of the fuel to provide a viscosity suitable for combustion.

3.9.7 Filters and/or coalescers are to be fitted in the oil fuel supply lines to each oil engine and gas turbine to ensure that only suitably filtered oil is fed to the combustion system. The arrangements are to be such that any unit can be cleaned without interrupting the supply of filtered oil to the combustion system.

## 3.10 Booster pumps

3.10.1 Where an oil fuel booster pump is fitted, which is essential to the operation of the main engine, a standby pump is to be provided.

3.10.2 The standby pump is to be connected ready for immediate use but where two or more main engines are fitted, each with its own pump, a complete spare pump may be accepted provided that it is readily accessible and can easily be installed.

## 3.11 Fuel valve cooling pumps

3.11.1 Where pumps are provided for fuel valve cooling, the arrangements are to be in accordance with 3.10.

## 3.12 Oil-fired galleys

3.12.1 The oil fuel tank is to be located outside the galley and is to be fitted with approved means of filling and venting.

3.12.2 The fuel supply to the burners is to be controlled from a position which will always be accessible in the event of a fire occurring in the galley.

3.12.3 The galley is to be well ventilated.

3.12.4 When liquefied petroleum gas is used, bottles are to be stored on the open deck or in a well ventilated space which only opens to the open deck.

## Section 4 Oil fuel pumps, pipes, fittings, tanks, etc.

### 4.1 Transfer pumps

4.1.1 Where a power driven pump is necessary for transferring oil fuel, a standby pump is to be provided and connected ready for use, or, alternatively, emergency connections may be made to one of the unit pumps or to another suitable power driven pump.

### 4.2 Control of pumps

4.2.1 The power supply to all independently-driven oil fuel transfer and pressure pumps is to be capable of being stopped from a position outside the space which will always be accessible in the event of fire occurring in the compartment in which they are situated, as well as from the compartment itself.

### 4.3 Relief valves on pumps

4.3.1 All pumps which are capable of developing a pressure exceeding the design pressure of the system are to be provided with relief valves. Each relief valve is to be in close circuit, i.e. arranged to discharge back to the suction side of the pump and to effectively limit the pump discharge pressure to the design pressure of the system.

### 4.4 Pump connections

4.4.1 Valves or cocks are to be interposed between the pumps and the suction and discharge pipes, in order that any pump may be shut-off for opening-up and overhauling.

# Machinery Piping Systems

## Part 5, Chapter 14

Section 4

### 4.5 Pipes conveying oil

4.5.1 Pipes conveying oil under pressure are to be of seamless steel or other approved material having flanged or welded joints, and are to be placed in sight above the platform in well lighted and readily accessible parts of the machinery spaces. The number of flanged joints is to be kept to a minimum.

4.5.2 Where pipes convey heated oil under pressure the flanges are to be machined, and the jointing material, which is to be impervious to oil heated to 150°C, is to be the thinnest possible, so that flanges are practically metal to metal. The scantlings of the pipes and their flanges are to be suitable for a pressure of at least 13,7 bar (14 kgf/cm<sup>2</sup>) or for the design pressure, whichever is the greater.

4.5.3 The short joining lengths of pipes to the burners from the control valves at the boiler may have cone unions, provided these are of specially robust construction.

4.5.4 Flexible hoses of approved material and design may be used for the burner pipes, provided that spare lengths, complete with couplings, are carried on board.

4.5.5 For requirements relating to flexible hoses, see Ch 12.7.

### 4.6 Low pressure pipes

4.6.1 Transfer, suction and other low pressure oil pipes and all pipes passing through oil storage tanks are to be made of cast iron or steel, having flanged joints suitable for a working pressure of not less than 6,9 bar (7 kgf/cm<sup>2</sup>). The flanges are to be machined and the jointing material is to be impervious to oil. Where the pipes are 25 mm bore or less, they may be of seamless copper or copper alloy, except those which pass through oil storage tanks. Oil pipes within the engine and boiler spaces are to be fitted where they can be readily inspected and repaired.

4.6.2 For requirements regarding bilge pipes in way of double bottom tanks and deep tanks, see Ch 13,7.9 and 7.10.

### 4.7 Valves and cocks

4.7.1 Valves, cocks and their pipe connections are to be so arranged that oil cannot be admitted into tanks which are not structurally suitable for the carriage of oil or into tanks which can be used for the carriage of fresh water.

4.7.2 All valves and cocks forming part of the oil fuel installation are to be capable of being controlled from readily accessible positions which, in the engine and boiler spaces, are to be above the working platform, see also Ch 13,2.3.

4.7.3 Every oil fuel suction pipe from a double bottom tank is to be fitted with a valve or cock.

### 4.8 Valves on deep tanks and their control arrangements

4.8.1 Every oil fuel suction pipe from a storage, settling and daily service tank situated above the double bottom, and every oil fuel levelling pipe within the boiler room or engine room, is to be fitted with a valve or cock secured to the tank.

4.8.2 The valves and cocks mentioned in 4.8.1 are to be capable of being closed locally and from positions outside the space in which the tank is located. The remote controls are to be accessible in the event of fire occurring in the deep tank's space. Instructions for closing the valves or cocks are to be indicated at the valves and cocks and at the remote control positions.

4.8.3 The control for remote operation of the valve on the emergency generator fuel tank is to be in a separate location from the controls for the remote operation of other valves for tanks located in machinery spaces.

4.8.4 In the case of tanks of less than 500 litres capacity, consideration will be given to the omission of remote controls.

4.8.5 Every oil fuel suction pipe which is led into the engine and boiler spaces, from a tank situated above the double bottom outside these spaces, is to be fitted in the machinery space with a valve controlled as in 4.8.2, except where the valve on the tank is already capable of being closed from an accessible position above the bulkhead deck.

4.8.6 Where the filling pipes to deep oil tanks are not connected to the tanks near the top, they are to be provided with non-return valves at the tanks or with valves or cocks fitted and controlled as in 4.8.2.

### 4.9 Water drainage from settling tanks

4.9.1 Settling tanks are to be provided with means for draining water from the bottom of the tanks.

4.9.2 If settling tanks are not provided, the oil fuel bunkers or daily service tanks are to be fitted with water drains.

4.9.3 Open drains for removing the water from oil tanks are to be fitted with valves or cocks of self-closing type, and suitable provision is to be made for collecting the oily discharge.

### 4.10 Relief valves on oil heaters

4.10.1 Relief valves are to be fitted on the oil side of heaters and are to be adjusted to operate at a pressure of 3,4 bar (3,5 kgf/cm<sup>2</sup>) above that of the supply pump relief valve, see 4.3. The discharge from the relief valves is to be led to a safe position.

### 4.11 Filling arrangements

4.11.1 Filling stations are to be isolated from other spaces and are to be efficiently drained and ventilated.

# Machinery Piping Systems

## Part 5, Chapter 14

Section 4

4.11.2 Provision is to be made against over-pressure in the filling pipelines, and any relief valve fitted for this purpose is to discharge to an overflow tank or other safe position.

### 4.12 Transfer arrangements – Passenger ships

4.12.1 In passenger ships, provision is to be made for the transfer of oil fuel from any oil fuel storage or settling tank to any other oil fuel storage or settling tank in the event of fire or damage.

### 4.13 Alternative carriage of oil fuel and water ballast

4.13.1 Where it is intended to carry oil fuel and water ballast in the same compartments alternatively, the valves or cocks connecting the suction pipes of these compartments with the ballast pump and those connecting them with the oil fuel transfer pump are to be so arranged that the oil may be pumped from any one compartment by the oil fuel pump at the same time as the ballast pump is being used on any other compartment. In passenger ships the arrangement will require to be specially approved.

4.13.2 Where settling or service tanks are fitted, each having a capacity sufficient to permit 12 hours normal service without replenishment, the above requirement may be dispensed with.

4.13.3 Attention is drawn to the statutory regulations issued by National Authorities in connection with the *International Convention for the Prevention of Pollution of the Sea by Oil, 1973/78*.

### 4.14 Deep tanks for the alternative carriage of oil, water ballast or dry cargo

4.14.1 In the case of deep tanks which can be used for the carriage of oil fuel, cargo oil, water ballast or dry cargo, provision is to be made for blank flanging the oil and water ballast filling and suction pipes, also the steam heating coils if retained in place, when the tank is used for dry cargo, and for blank flanging the bilge suction pipes when the tanks are used for oil or water ballast.

4.14.2 If the deep tanks are connected to an overflow system, the arrangements are to be such that liquid or vapour from other tanks cannot enter the deep tanks when dry cargo is carried in them.

### 4.15 Separation of cargo oils from oil fuel

4.15.1 Pipes conveying vegetable oils or similar cargo oils are not to be led through oil fuel tanks, nor are oil fuel pipes to be led through tanks containing these cargo oils. For requirements regarding provision of cofferdams between oil and water tanks, see Pt 3, Ch 3,4.7.

### 4.16 Fresh water piping

4.16.1 Pipes in connection with compartments used for storing fresh water are to be separate and distinct from any pipes which may be used for oil or oily water, and are not to be led through tanks which contain oil, nor are oil pipes to be led through fresh water tanks.

### 4.17 Separate oil fuel tanks

4.17.1 Where separate oil fuel tanks are permitted, their construction is to be in accordance with the requirements of 4.17.2 to 4.17.6, see also SOLAS 1974 as amended Reg.II-2/B4.2.2.3.2.

4.17.2 In general, the minimum thickness of the plating of service, settling and other oil tanks, where they do not form part of the structure of the ship, is to be 5 mm, but in the case of very small tanks, the minimum thickness may be 3 mm.

4.17.3 For rectangular steel tanks of welded construction, the plate thicknesses are to be not less than those indicated in Table 14.4.1. The stiffeners are to be of approved dimensions.

**Table 14.4.1 Plate thickness of separate oil fuel tanks**

Thickness of plate, mm	Head from bottom of tank to top of overflow pipe, metres				
	2,5	3,0	3,7	4,3	4,9
Breadth of panel, mm					
5	585	525	—	—	—
6	725	645	590	—	—
7	860	770	700	650	—
8	1000	900	820	750	700
10	1280	1140	1040	960	900

4.17.4 The dimension given in Table 14.4.1 for the breadth of the panel is the maximum distance allowable between continuous lines of support, which may be stiffeners, wash-plates or the boundary of the tank.

4.17.5 Where necessary, stiffeners are to be provided, and if the length of the stiffener exceeds twice the breadth of the panel, transverse stiffeners are also to be fitted, or, alternatively, tie bars are to be provided between stiffeners on opposite sides of the tank.

4.17.6 On completion, the tanks are to be tested by a head of water equal to the maximum to which the tanks may be subjected, but not less than 2,5 m above the crown of the tank.

# Machinery Piping Systems

# Part 5, Chapter 14

Sections 4 & 5

## 4.18 Oil fuel service tanks

4.18.1 An oil fuel service tank is an oil fuel tank which contains only the required quality of fuel ready for immediate use.

4.18.2 Two oil fuel service tanks, for each type of fuel used on board, necessary for propulsion and generator systems, are to be provided. Each tank is to have a capacity for at least eight hours' operation, at sea, at maximum continuous rating of the propulsion plant and/or generating plant associated with that tank.

4.18.3 The arrangement of oil fuel service tanks is to be such that one tank can continue to supply oil fuel when the other is being cleaned or opened up for repair.

4.18.4 For ships of less than 500 gross tonnage, the capacity of each oil fuel service tank required by 4.18.2 may be less than for eight hours operation, where the class notation includes a service restriction.

## 4.19 Arrangements for fuels with a flash point between 43° and 60°

4.19.1 Fuel oil tanks other than those in double bottom compartments shall be located outside 'Category A' machinery spaces, see also Pt 3, Ch 3,4.7.

4.19.2 Provisions are to be made for the measurement of oil fuel temperature at the pump suction pipe.

4.19.3 Stop valves are to be provided at the inlet and outlet side of oil fuel strainers.

4.19.4 Pipe joints shall be either welded or spherical type union joints.

## Section 5 Steam piping systems

### 5.1 Provision for expansion

5.1.1 In all steam piping systems, provision is to be made for expansion and contraction to take place without unduly straining the pipes.

5.1.2 Where expansion pieces are used, particulars are to be submitted.

5.1.3 For installation requirements regarding expansion pieces, see Ch 13,2.7.

## 5.2 Drainage

5.2.1 The slope of the pipes and the number and position of the drain valves or cocks are to be such that water can be efficiently drained from any portion of the steam piping system when the ship is in normal trim and is either upright or has a list of up to 5°.

5.2.2 Arrangements are to be made for ready access to the drain valves or cocks.

## 5.3 Pipes in way of holds

5.3.1 In general, steam pipes are not to be led through spaces which may be used for cargo, but where it is impracticable to avoid this arrangement, plans are to be submitted for consideration. The pipes are to be efficiently secured and insulated, and well protected from mechanical damage. Pipe joints are to be as few as practicable and preferably butt welded.

5.3.2 If these pipes are led through shaft tunnels, pipe tunnels in way of cargo holds or through duct keels, they are to be efficiently secured and insulated.

## 5.4 Reduced pressure lines

5.4.1 Pipelines which are situated on the low pressure side of reducing valves, and which are not designed to withstand the full pressure at the source of supply, are to be fitted with pressure gauges and with relief valves having sufficient discharge capacity to protect the piping against excessive pressure.

## 5.5 Steam for fire-extinguishing in cargo holds

5.5.1 Where steam is used for fire-extinguishing in cargo holds provision is to be made to prevent damage to cargo by leakage of steam or by drip.

5.5.2 Details of the proposed precautionary measures are to be submitted.

## Cross-reference

For steam heating arrangements for oil fuel, cargo oil or lubricating oil, see 2.7.



# Machinery Piping Systems

# Part 5, Chapter 14

Sections 6 & 7

## ■ Section 6

### Boiler feed water and condensate systems

#### 6.1 Feed water piping

6.1.1 Two separate means of feed are to be provided for all main and auxiliary boilers which are required for essential services. In the case of steam/steam generators, one means of feed will be accepted provided steam for essential services is available simultaneously from another source.

#### 6.2 Feed pumps

6.2.1 Two or more feed pumps are to be provided of sufficient capacity to supply the boilers under full load conditions with any one pump out of action.

6.2.2 Feed pumps may be worked from the main engines or may be independently driven, but at least one of the pumps required in 6.2.1 is to be independently-driven.

6.2.3 In twin screw ships in which there is only one independent feed pump, each main engine is to be fitted with a feed pump. Where all the feed pumps are independently driven, the pumps are to be connected to deal with the condensate from both engines or from either engine. 6.2.4 Independent feed pumps required for feeding the main boilers are to be fitted with automatic regulators for controlling their output.

6.2.4 Independent feed pumps required for feeding the main boilers are to be fitted with automatic regulators for controlling their output.

#### 6.3 Harbour feed pumps

6.3.1 Where main-engine driven feed pumps are fitted and there is only one independent feed pump, a harbour feed pump or an injector is to be fitted to provide the second means of feed to the boilers which are in use when the main engines are not working. This requirement need not be complied with in the case of trawlers and fishing vessels.

6.3.2 The harbour feed pump required by 6.3.1 may be used for general service, provided that it is not connected to tanks containing oil, or to tanks, cofferdams and bilges which may contain oily water.

6.3.3 The valves on the suction pipes from the hotwell or condenser and the feed drain tank or filter are to be of the non-return type.

#### 6.4 Condensate pumps

6.4.1 Two or more extraction pumps are to be provided for dealing with the condensate from the main and auxiliary condensers, at least one of which is to be independently driven. Where one of the independent feed pumps is fitted with direct suction from the condensers and a discharge to the feed tank, it may be accepted for this purpose.

#### 6.5 Valves and cocks

6.5.1 Feed and condensate pumps are to be provided with valves or cocks, interposed between the pumps and the suction and the discharge pipes, so that any pump may be opened-up for overhaul while the others continue in operation.

#### 6.6 Reserve feed water

6.6.1 All ships fitted with boilers are to be provided with storage space for reserve feed water, the structural and piping arrangements being such that this water cannot be contaminated by oil or oily water, see Pt 3, Ch 3,4.7 for structural arrangements.

6.6.2 For main boilers, one or more evaporators, of adequate capacity, are also to be provided.

## ■ Cross-reference

For feed water level regulators for water tube boilers, see Ch 10,16.8.

## ■ Section 7

### Engine cooling water systems

#### 7.1 Main supply

7.1.1 Provision is to be made for an adequate supply of cooling water to the main propelling machinery and essential auxiliary engines, also to the lubricating oil and fresh water coolers and air coolers for electric propelling machinery, where these coolers are fitted. The cooling water pump(s) may be worked from the engines or be driven independently.

7.1.2 In the case of main steam turbine installations, a sea inlet scoop arrangement may replace the main sea-water circulating pump, subject to the conditions stated in 7.2.2(c).

#### 7.2 Standby supply

7.2.1 Provision is also to be made for a separate supply of cooling water from a suitable independent pump of adequate capacity.

# Machinery Piping Systems

# Part 5, Chapter 14

Sections 7 & 8

7.2.2 The following arrangements are acceptable depending on the purpose for which the cooling water is intended:

- (a) Where only one main engine is fitted, the standby pump is to be connected ready for immediate use.
- (b) Where more than one main engine is fitted, each with its own pump, a complete spare pump of each type may be accepted.
- (c) Where a sea inlet scoop arrangement is fitted, and there is only one independent condenser circulating pump, a further pump, or a connection to the largest available pump suitable for circulation duties, is to be fitted to provide the second means of circulation when the ship is manoeuvring. The pump is to be connected ready for immediate use.
- (d) Where fresh water cooling is employed for main and/or auxiliary engines, a standby fresh water pump need not be fitted if there are suitable emergency connections from a salt water system.
- (e) Where each auxiliary is fitted with a cooling water pump, standby means of cooling need not be provided. Where, however, a group of auxiliaries is supplied with cooling water from a common system, a standby cooling water pump is to be provided for this system. This pump is to be connected ready for immediate use and may be a suitable general service pump.

## 7.3 Selection of standby pumps

7.3.1 When selecting a pump for standby purposes, consideration is to be given to the maximum pressure which it can develop if the overboard discharge valve is partly or fully closed and, when necessary, condenser doors, water boxes, etc., are to be protected by an approved device against inadvertent over-pressure. See Ch 3,6.3 for the hydraulic test pressure which condensers are required to withstand.

## 7.4 Relief valves on main cooling water pumps

7.4.1 Where cooling water pumps can develop a pressure head greater than the design pressure of the system, they are to be provided with relief valves on the pump discharge to effectively limit the pump discharge pressure to the design pressure of the system. For location of relief valves, see Ch 13,7.8.

## 7.5 Sea inlets

7.5.1 Not less than two sea inlets are to be provided for the pumps supplying the sea-water cooling system, one for the main pump and one for the standby pump. Alternatively, the sea inlets may be connected to a suction line available to main and standby pumps.

7.5.2 Where standby pumps are not connected ready for immediate use, see 7.2.2(b), the main pump is to be connected to both sea inlets.

7.5.3 Cooling water pump sea inlets are to be low inlets and one of them may be the ballast pump or general service pump sea inlet.

7.5.4 The auxiliary cooling water sea inlets are preferably to be located one on each side of the ship.

## 7.6 Strainers

7.6.1 Where sea-water is used for the direct cooling of the main engines and essential auxiliary engines, the cooling water suction pipes are to be provided with strainers which can be cleaned without interruption to the cooling water supply.

## ■ Cross-reference

For guidance on metal pipes for water services, see Ch 12,9.

## ■ Section 8 Lubricating oil systems

### 8.1 General requirements

8.1.1 In addition to the requirements detailed in this Section, the requirements of Sections 2 and 4 are to be complied with in so far as they are applicable. In all cases 2.9.1 to 2.9.3, 4.2, 4.3, 4.5, 4.8, 4.11 and 4.17 are to apply.

### 8.2 Pumps

8.2.1 Where lubricating oil for the main engine(s) is circulated under pressure, a standby lubricating oil pump is to be provided where the following conditions apply:

- (a) The lubricating oil pump is independently driven and the total output of the main engine(s) exceeds 370 kW (500 shp).
- (b) One main engine with its own pump is fitted and the output of the engine exceeds 370 kW (500 shp).
- (c) More than one main engine each with its own lubricating oil pump is fitted and the output of each engine exceeds 370 kW (500 shp).

8.2.2 The standby pump is to be of sufficient capacity to maintain the supply of oil for normal conditions with any one pump out of action. The pump is to be fitted and connected ready for immediate use, except that where the conditions referred to in 8.2.1(c) apply a complete spare pump may be accepted. In all cases satisfactory lubrication of the engines is to be ensured while starting and manoeuvring.

8.2.3 Similar provisions to those of 8.2.1 and 8.2.2 are to be made where separate lubricating oil systems are employed for piston cooling, reduction gears, oil operated couplings and controllable pitch propellers, unless approved alternative arrangements are provided.

8.2.4 Independently-driven pumps of rotary type are to be fitted with a non-return valve on the discharge side of the pump.

# Machinery Piping Systems

## Part 5, Chapter 14

Section 8

### 8.3 Alarms

8.3.1 All main and auxiliary engines and turbines intended for essential services are to be provided with means of indicating the lubricating oil pressure supply to them. Where such engines and turbines are of more than 37 kW (50 shp), audible and visual alarms are to be fitted to give warning of an appreciable reduction in pressure of the lubricating oil supply. Further, these alarms are to be actuated from the outlet side of any restrictions, such as filters, coolers, etc.

### 8.4 Emergency supply for propulsion turbines and propulsion turbo-generators

8.4.1 A suitable emergency supply of lubricating oil is to be arranged to come automatically into use in the event of a failure of the supply from the pump.

8.4.2 The emergency supply may be obtained from a gravity tank containing sufficient oil to maintain adequate lubrication for not less than six minutes, and, in the case of propulsion turbo-generators, until the unloaded turbine comes to rest from its maximum rated running speed.

8.4.3 Alternatively, the supply may be provided by the standby pump or by an emergency pump. These pumps are to be so arranged that their availability is not affected by a failure in the power supply.

8.4.4 For automatic shutdown arrangements of main turbines in the event of failure of the lubrication system, see Ch 3,5.1 and Pt 6, Ch 1,3.4.

### 8.5 Maintenance of bearing lubrication

8.5.1 The arrangements for lubricating bearings and for draining crankcase and other oil sumps of main and auxiliary engines, gearcases, electric generators, motors, and other running machinery are to be so designed that lubrication will remain efficient with the ship inclined under the conditions as shown in Ch 1,3.7.

8.5.2 For details of the requirements relating to the lubrication of bearings of electric generators and motors, see Pt 6, Ch 2,1.9.

### 8.6 Filters

8.6.1 Where the lubricating oil for main propelling engines is circulated under pressure, provision is to be made for the efficient filtration of the oil. The filters are to be capable of being cleaned without stopping the engine or reducing the supply of filtered oil to the engine. Proposals for an automatic by-pass for emergency purposes in high speed engines are to be submitted for special consideration.

8.6.2 In the case of propulsion turbines and their gears, arrangements are to be made for the lubricating oil to pass through magnetic strainers and fine filters. Generally, the openings in the filter elements are to be not coarser than required by the manufacturer of the turbines, especially for the supply to turbine thrust bearings.

### 8.7 Cleanliness of pipes and fittings

8.7.1 Extreme care is to be taken to ensure that lubricating oil pipes and fittings, before installation, are free from scale, sand, metal particles and other foreign matter.

### 8.8 Lubricating oil drain tank

8.8.1 Where an engine lubricating oil drain tank extends to the bottom shell plating in ships that are required to be provided with a double bottom, a shut-off valve is to be fitted in the drainpipe between the engine casing and the double bottom tank. This valve is to be capable of being closed from an accessible position above the level of the lower platform.

### 8.9 Lubricating oil contamination

8.9.1 The materials used in the storage and distribution of lubricating oil are to be selected such that they do not introduce contaminants or modify the properties of the oil. The use of cadmium or zinc in lubricating oil systems where they may normally come into contact with the oil is not permitted.

8.9.2 Arrangements are to be made for each forced lubrication system, renovation system, ready to use tank(s) and their associated rundown lines to drain tanks to be flushed after system installation and prior to running of machinery. The flushing arrangements are to be in accordance with the equipment manufacturer's procedures and recommendations.

8.9.3 For prevention of ingress of water into lubricating oil tanks via air pipes, see Ch 13,12.5.4.

8.9.4 The design and construction of engine and gear box piping arrangements are to prevent contamination of engine lubricating oil systems by leakage of cooling water or from bilge water where engines or gearboxes are partly installed below the lower platform. Where flexibility is required to accommodate movement between the engine and sump tank, any flexible joint assembly is to be of an approved type suitable for its intended application.

8.9.5 Where there is a permanently attached oil filling pipe and cap provided for an engine or other item of machinery, provision is to be made for the topping up oil to safely pass through a suitable strainer to prevent unwanted matter getting into the lubricating oil system. The caps are to be capable of being secured in the closed position.

# Machinery Piping Systems

## Part 5, Chapter 14

Sections 8, 9 & 10

8.9.6 Sampling points are to be provided that enable samples of lubricating oil to be taken in a safe manner. The sampling arrangements are to have the capability to provide samples when machinery is running and are to be provided with valves and cocks of the self-closing type and located in positions as far removed as possible from any heated surface or electrical equipment.

### 8.10 Deep tank valves and their control arrangements

8.10.1 The requirements for remote operation of valves on deep tank suction pipes may be waived where the valves are closed during normal operation.

8.10.2 Remotely operated valves on lubricating oil deep tank suction should not be of the quick-closing type where inadvertent use would endanger the safe operation of the main propulsion and essential auxiliary machinery.

### ■ Cross-references

For air, sounding pipes and gauge glasses, see Ch 13,12. For separation of lubricating oil tanks from fuel tanks, see Pt 3, Ch 3,4.7.

## ■ Section 9 Hydraulic systems

### 9.1 General

9.1.1 The arrangements for storage, distribution and utilisation of hydraulic and other flammable oils employed under pressure in power transmission systems, control and actuating systems and heating systems in locations where means of ignition are present are to comply with the provisions of 2.9.1 to 2.9.3, 4.3, 4.5, 4.11 and 4.17 where applicable.

### 9.2 System arrangements

9.2.1 Hydraulic fluids are to be suitable for the intended purpose under all operating service conditions.

9.2.2 Materials used for all parts of hydraulic seals are to be compatible with the working fluid at the appropriate working temperature and pressure.

9.2.3 Over-pressure protection is to be provided on the discharge side of all pumps. Where relief valves are fitted for this purpose they are to be fitted in closed circuit, i.e. arranged to discharge back to the system oil tank.

9.2.4 Provision is to be made for hand operation of the systems in an emergency, unless an acceptable alternative is available.

9.2.5 Where hydraulic securing arrangements are applied, the system is to be capable of being locked in the closed position so that in the event of hydraulic system failure the securing arrangements will remain locked.

9.2.6 Where pilot operated non-return valves are fitted to hydraulic cylinders for locking purposes, the valves are to be connected directly to the actuating cylinder(s) without intermediate pipes or hoses.

9.2.7 Hydraulic circuits for securing and locking of bow, inner, stern or shell doors are to be arranged such that they are isolated from other hydraulic circuits when securing and locking devices are in the closed position. For requirements relating to hydraulic steering gear arrangements see Ch 19,3.

9.2.8 Suitable oil collecting arrangements for leaks shall be fitted below hydraulic valves and cylinders.

## ■ Section 10 Low pressure compressed air systems

### 10.1 General

10.1.1 The requirements of this Section are applicable to low pressure (LP) compressed air systems which are essential for pneumatic control and instrumentation purposes.

10.1.2 Low pressure compressed air systems are to produce and distribute cooled compressed air throughout the ship to supply all pneumatic control and instrumentation systems where the air pressure requirements are typically 3 to 10 bar. LP compressed air systems may include air compressors, oil/water separators, filters, dryers, distribution lines and air receivers.

10.1.3 The design of LP compressed air systems is to be capable of providing a continuous flow of air to meet the demands of all essential users under all ambient conditions. This demand may include the use of intermittently used equipment that is part of the ship's equipment, such as power tools for machinery maintenance, testing equipment and line cleaning. Compressed air systems used for diesel engine or gas turbine starting are to comply with the requirements of Ch 2,8 and Ch 4,6 as applicable.

10.1.4 User equipment requirements for the quality of compressed air in terms of dewpoint (dryness), oil content and solid particle count are to be recognized in the selection and configuration of compressors, equipment, filters and dryers which are included in the system.

10.1.5 Configuration arrangements of LP compressed air systems may consist of:

- (a) Dedicated LP air compressors and LP air receivers with a distribution system for LP users; or
- (b) Supply from the starting air system to dedicated air pressure reducing valves/cross-over stations feeding into a distribution system for LP users.

# Machinery Piping Systems

# Part 5, Chapter 14

Sections 10 & 11

## 10.2 Compressors and reducing valves/stations

10.2.1 Where LP air is not derived from the starting air system, at least two LP air compressors are to be provided. The output of any one compressor is to match the total demand of all essential users. The system is to be arranged for auto-start of the compressors and means are to be provided to indicate if any compressor is operating longer and more frequently than the manufacturer's recommended operating periods.

10.2.2 If only one LP air compressor is to be provided, a cross connection to the starting air system is to be made via a reducing valve/cross-connection station.

10.2.3 Where LP air is derived only from the starting air system, at least two means of supplying air to the LP air system are to be provided. Each of the two means of supplying air is to have sufficient capability of supplying the total demand on the LP air system with one of the means out of action. To ensure that LP compressed air users do not cause the starting air compressors to operate the starting air system is to be fitted with an auxiliary compressor which is to be capable of continuous running and which can maintain the stored capacity of starting compressed air in the air receivers as required by Ch 2,8 and Ch 4,6 as applicable, whilst supplying essential LP users.

## 10.3 Air receivers

10.3.1 The LP air system and any associated air receivers are to be configured to provide sufficient stored energy to supply LP compressed air without the pressure in the system falling below a level that is insufficient for the operation of all essential users. See also Pt 6, Ch 1,2.5.8.

10.3.2 All air receivers are to comply with the requirements of Chapter 11 as applicable.

10.3.3 Stop valves on air receivers are to permit slow opening to avoid sudden pressure rises in the piping system.

## 10.4 Distribution system

10.4.1 Drain pots with drain valves are to be provided throughout the distribution system at all low points.

10.4.2 Pipelines that are situated on the low pressure side of reducing valves/stations and that are not designed to withstand the full pressure of the source supply, are to be provided with pressure gauges and with relief valves having sufficient capacity to protect the piping against excessive pressure.

10.4.3 In-line filters capable of being cleaned/changed without interrupting the flow of filtered air are to be fitted in the system.

## 10.5 Pneumatic remote control valves

10.5.1 Where valves, which are required by the Rules to be capable of being closed from outside a machinery space, have pneumatic closing arrangements, a dedicated air receiver is to be fitted to supply compressed air to the valves. This air receiver is to be located outside the machinery space.

10.5.2 The air receiver is to be maintained fully charged from the main LP air system via a non-return valve located at the air receiver inlet which is to be locked in the open position.

10.5.3 In the case of passenger ships, a permanently attached hand-operated air compressor capable of charging the air receiver is to be provided in the space in which the air receiver is located.

10.5.4 The capacity of the air receiver is to be sufficient to operate all valves and any other essential supplies such as ventilation flaps without replenishment.

## 10.6 Control arrangements

10.6.1 The control, alarm and monitoring systems are to comply with Pt 6, Ch 1.

## Section 11 Multi-engined ships

### 11.1 General

11.1.1 This Section is applicable to ships of less than 500 gross tons and which are not required to comply with the *International Convention for the Safety of Life at Sea, 1974*, as amended (SOLAS 74), and that have multi-engine installations for propulsion purposes.

11.1.2 For vessels in which the propulsion systems are independent and the propulsion system prime movers are also fully independent of each other such that in the event of the failure of one of the sources of propulsion power the vessels will retain the capability of safely manoeuvring under all conditions of service, the following may not be required:

- (a) Spare fuel oil booster pump stipulated in 3.10.2.
- (b) Spare lubricating oil pump stipulated in 8.2.1(c), 8.2.2 and 8.2.3.
- (c) Spare cooling water pump stipulated in 7.2.2(b).



# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 1

## Section

- 1 **General requirements**
- 2 **Piping systems for bilge, ballast, oil fuel, etc.**
- 3 **Cargo handling system**
- 4 **Cargo tank venting, purging and gas-freeing**
- 5 **Cargo tank level gauging equipment**
- 6 **Cargo heating arrangements**
- 7 **Inert gas systems**

### ■ Section 1 General requirements

#### 1.1 Application

1.1.1 The requirements of this Chapter are additional to those of Chapter 13 and are applicable to ships which are intended for the carriage of oil in bulk.

1.1.2 The requirements are based on the assumption that the ships are of normal tanker type having the main propelling machinery aft. Departures from this arrangement will require special consideration.

1.1.3 The requirements are primarily intended for ships which are to carry flammable liquids having a flash point not exceeding 60°C (closed-cup test).

1.1.4 Where ships are intended to carry specific cargoes which are non-flammable or which have a flash point exceeding 60°C, the requirements will be modified, where necessary, to take account of the lesser hazards associated with the cargoes.

1.1.5 For a list of cargoes which can be carried in oil tankers, see Table 9.1.2 in Pt 4, Ch 9.

#### 1.2 Plans and particulars

1.2.1 In addition to the plans and particulars required in Chapter 13, the following plans (in a diagrammatic form) are to be submitted for consideration:

- Pumping arrangement at the fore and aft ends and drainage of cofferdams and pump rooms.
- General arrangement of cargo piping in tanks and on deck.
- General arrangement of cargo tank vents. The plan is to indicate the type and position of the vent outlets from any superstructure, erection, air intake, etc.
- Arrangement of inert gas piping system together with details of inert gas generating plant including all control and monitoring devices.
- Piping arrangements for cargo oil (F.P. 60°C or above, closed cup test).

- Ventilation arrangements of cargo and/or ballast pump rooms and other enclosed spaces which contain cargo handling equipment.
- Arrangements for venting, purging and gas measurement for double hull and double bottom spaces.
- Details of alarms and safety arrangements required by 1.6, see also Pt 6, Ch 1.2.

#### 1.3 Materials

1.3.1 All materials used in the cargo pumping and piping systems are to be suitable for use with the intended cargoes and, where applicable, they are to comply with the requirements of Chapter 12.

1.3.2 The requirements of 1.3.1 are also applicable to other piping systems which may come into contact with cargo.

#### 1.4 Design

1.4.1 All piping, valves and fittings are to be suitable for the maximum pressure to which the system can be subjected.

1.4.2 Piping subject to pressure is to be of seamless or other approved type, and is to comply with the requirements of Chapter 12.

#### 1.5 Dangerous spaces

1.5.1 Oil engines, or any other equipment which could constitute a possible source of ignition, are not to be situated within cargo tanks, pump rooms, cofferdams or other spaces liable to contain petroleum or other explosive vapours, or in spaces or zones immediately adjacent to cargo oil or slop tanks. The temperature of steam, or other fluid, in pipes (or heating coils) in these spaces is not to exceed 220°C. On gas tankers and chemical tankers, the maximum temperature is not to exceed that of the required temperature class of electrical equipment in the cargo area.

1.5.2 For definition of dangerous zones or spaces and requirements for electrical equipment within such spaces, see Pt 6, Ch 2, 13.4.

1.5.3 For the requirements for earthing and bonding of pipework for the control of static electricity, see Pt 6, Ch 2, 1.12.

#### 1.6 Cargo pump room

1.6.1 Cargo pump rooms are to be totally enclosed and are to have no direct communication with machinery spaces. For bilge drainage arrangements in pump room, see 2.2.

1.6.2 Pump rooms are to be situated within, or adjacent to the cargo tank area and are to be provided with ready means of access from the open deck, see also Pt 4, Ch 9, 13.

# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 1

1.6.3 In cargo pump rooms any drain pipes from steam or exhaust pipes from the steam cylinders of the pumps are to terminate well above the level of the bilges.

1.6.4 Alarms and safety arrangements are to be provided as indicated in 1.6.5 and Table 15.1.1. These requirements are applicable to pump rooms where pumps for cargo, such as cargo pumps, stripping pumps, pumps for slop tanks, pumps for COW or similar pumps are provided and not for pump rooms intended solely for ballast transfer. See also 1.6.6.

**Table 15.1.1 Alarms and safety arrangements**

Item	Alarm	Note
Temperature sensing of bulkhead shaft glands, bearings and pump casings	High see Note 1	Cargo, ballast and stripping pumps
Bilge level	High	—
Hydrocarbon concentration	High see Note 2	> 10% LEL
<b>NOTES</b> 1. The alarm signals shall trigger continuous visual and audible alarms in the cargo control room or the pump control station. 2. This alarm signal shall trigger a continuous audible and visual alarm in the pump room, cargo control room, engine control room and bridge.		

1.6.5 A system for continuously monitoring the concentrations of hydrocarbon gases within the cargo pump room is to be fitted. Monitoring points are to be located in positions where potentially dangerous concentrations may be readily detected. Gas analysing units with non-safe-type measuring equipment may be located outside cargo areas (e.g. in cargo control room, navigation bridge or engine room when mounted on the forward bulkhead) provided that:

- sampling lines do not pass through gas safe spaces, except where permitted by (e);
- the gas sampling pipes are fitted with flame arresters. Sample gas is to be led to the atmosphere with outlets arranged in a safe location, in the open atmosphere;
- bulkhead penetrations of sample pipes between safe and dangerous areas are of an approved type. A manual isolating valve is to be fitted in each of the sampling lines at the bulkhead in the safe area;
- the gas detection equipment including sampling piping, sampling pumps, solenoid valves and analysing units, are located in a fully enclosed steel cabinet, with a gasketed door, monitored by its own sampling point. At gas concentrations above 30 per cent LEL inside the steel cabinet, the entire gas-analysing unit is to be automatically shutdown; and
- where the cabinet cannot be arranged on the bulkhead, sample pipes are to be of steel or other equivalent material and without detachable connections, except for the connection points for isolating valves at the bulkhead and analysing units. The sample pipes are to be led by their shortest route.

Sequential sampling is acceptable as long as it is dedicated for the pump room only, including exhaust ducts, and the detection equipment is capable of monitoring from each sampling head location at intervals not exceeding 30 minutes.

1.6.6 Where items of equipment other than described in Table 15.1.1 are located in the pump room and are driven by shafts passing through bulkheads, the potential risk of ignition of hydrocarbon gas is to be assessed and proposals for mitigation submitted to LR for consideration.

### 1.7 Cargo pump room ventilation

1.7.1 Cargo pump rooms and other closed spaces which contain cargo handling equipment, and to which regular access is required during cargo handling operations, are to be provided with permanent ventilation systems of the mechanical extraction type.

1.7.2 The ventilation system is to be capable of being operated from outside the compartment being ventilated and a notice to be fixed near the entrance stating that no person is to enter the space until the ventilation system has been in operation for at least 15 minutes.

1.7.3 The ventilation systems are to be capable of 20 air changes per hour, based on the gross volume of the pump room or space.

1.7.4 The ventilation ducting is to be arranged to permit extraction from the vicinity of the pump room bilges, immediately above the transverse floor plates or bottom longitudinals. An emergency intake is also to be arranged in the ducting at a height of 2 m above the pump room lower platform and is to be provided with a damper capable of being opened or closed from the weather deck and lower platform level. An arrangement involving a specific ratio of areas of upper emergency and lower main ventilation openings, which can be shown to result in at least the required number of air changes through the lower inlets, can be accepted without the use of dampers. When the lower inlets are sealed off, owing to flooding of the bilges, then at least 75 per cent of the required number of air changes is to be obtainable through the upper inlets. Means are to be provided to ensure the free flow of gases through the lower platform to the duct intakes.

1.7.5 Protection screens of not more than 13 mm square mesh are to be fitted in outside openings of ventilation ducts, and ventilation intakes are to be so arranged as to minimize the possibility of re-cycling hazardous vapours from any ventilation discharge opening. Vent exits are to be arranged to discharge upwards.

1.7.6 The vent exits from pump rooms are to discharge at least 3 m above deck, and from the nearest air intakes or openings to accommodation and enclosed working spaces, and from possible sources of ignition.



# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 1

1.7.7 The ventilation is to be interlocked to the lighting system (except emergency lighting) such that the cargo pump room lighting may only come on when the ventilation is in operation. Failure of the ventilation system shall not cause the lighting to go out.

### 1.8 Non-sparking fans for hazardous areas

1.8.1 The air gap between impeller and housing of the fan is to be not less than 0,1 of the impeller shaft bearing diameter or 2 mm whichever is the larger, subject also to compliance with 1.8.2(e). Generally, however, the air gap need be no more than 13 mm.

1.8.2 The following combinations of materials are permissible for the impeller and the housing in way of the impeller:

- (a) impellers and/or housings of non-metallic material, due regard being paid to the elimination of static electricity,
- (b) impellers and housings of non-ferrous metals,
- (c) impellers and housings of austenitic stainless steel,
- (d) impellers of aluminium alloys or magnesium alloys and a ferrous housing provided that a ring of suitable thickness of non-ferrous material is fitted in way of the impeller,
- (e) any combination of ferrous impellers and housings with not less than 13 mm tip clearance,
- (f) any combination of materials for the impeller and housing which are demonstrated as being spark proof by appropriate rubbing tests.

1.8.3 The following combinations of materials for impellers and housing are not considered spark proof and are not permitted:

- (a) impellers of an aluminium alloy or magnesium alloy and a ferrous housing, irrespective of tip clearance,
- (b) impellers of a ferrous material and housings made of an aluminium alloy, irrespective of tip clearance,
- (c) any combination of ferrous impeller and housing with less than 13 mm tip clearance, other than permitted by 1.8.2(c).

1.8.4 Electrostatic charges both in the rotating body and the casing are to be prevented by the use of antistatic materials (i.e. materials having an electrical resistance between  $5 \times 10^4$  ohms and  $10^8$  ohms), or special means are to be provided to avoid dangerous electrical charges on the surface of the material.

1.8.5 Type tests on the complete fan are to be carried out to the Surveyor's satisfaction.

1.8.6 Protection screens of not more than 13 mm square mesh are to be fitted in the inlet and outlet of ventilation ducts to prevent the entry of objects into the fan housing.

1.8.7 The installation of the ventilation units on board is to be such as to ensure the safe bonding to the hull of the units themselves.

### 1.9 Slop tanks

1.9.1 The requirements in 1.9.2 to 1.9.7 are applicable to ships intended for the carriage of ore or oil when oil residues are to be retained in the slop tanks and the ship is otherwise gas free, *see also* Pt 4, Ch 9, 11.3.

1.9.2 Slop tanks are to be provided with an approved independent venting system, *see* Section 4.

1.9.3 At least two portable instruments are to be available on board for gas detection.

1.9.4 Means are to be provided for isolating the piping connecting the pump room with the slop tanks. The means of isolation is to consist of a valve followed by a spectacle flange or a spool piece with appropriate blank flanges. This arrangement is to be located adjacent to the slop tanks, but where this is unreasonable or impracticable it may be located within the pump room directly after the piping penetrates the bulkhead. A separate permanently installed pumping and piping arrangement is to be provided for discharging the contents of the slop tanks directly to the open deck for transfer to shore reception facilities when the ship is in the dry cargo mode. When this transfer system is used for slop transfer in dry cargo mode, it shall have no connection to other systems. Separation by means of removal of spool pieces may be accepted.

1.9.5 Adequate ventilation is to be provided for spaces surrounding slop tanks, *see also* Pt 4, Ch 9, 11.3.

1.9.6 Warning notices are to be erected at suitable points detailing precautions to be observed prior to the ship loading or unloading, or when the ship is carrying dry cargo with liquid in the slop tanks.

1.9.7 In order to satisfy the requirements of certain National and/or Terminal Authorities, it may be necessary to provide an inert gas system for blanketing the slop tank contents.

### 1.10 Steam connections to cargo tanks

1.10.1 Where steaming out and/or fire-extinguishing connections are provided for cargo tanks or cargo pipe lines, they are to be fitted with valves of the screw-down non-return type. The main supply to these connections is to be fitted with a master valve placed in a readily accessible position clear of the cargo tanks.

### ■ Cross-reference

*See* Pt 6, Ch 1, 3 for alarm system requirements.

# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 2

### ■ Section 2 Piping systems for bilge, ballast, oil fuel, etc.

#### 2.1 Pumping arrangements at ends of ship outside dangerous zones and spaces

2.1.1 The pumping arrangements in the machinery space and at the forward end of the ship are to comply with the requirements for general cargo ships, in so far as they are applicable, and with the special requirements detailed in this Section.

2.1.2 Bilge, ballast and oil fuel lines, etc., which are connected to pumps, tanks or compartments at the ends of the ship outside dangerous zones and spaces, are not to pass through cargo tanks or have any connections to cargo tanks, or cargo piping. No objection will be made to these lines being led through ballast tanks or void spaces within the range of the cargo tanks.

2.1.3 The oil fuel bunkering system is to be entirely separate from the cargo handling system.

#### 2.2 Cargo pump room drainage

2.2.1 Provision is to be made for the bilge drainage of the cargo pump rooms by pump or bilge ejector suction. The cargo pumps or cargo stripping pumps may be used for this purpose, provided that the bilge suction is fitted with screw-down non-return valves and, in addition, an isolating valve or cock is fitted on the pump connection to the bilge chest. The pump room bilges of small tankers may be drained by means of a hand pump having a 50 mm bore suction. Pump room suction is not to enter machinery spaces.

#### 2.3 Deep cofferdam drainage

2.3.1 Cofferdams, which are required to be provided at the fore and aft ends of the cargo spaces in accordance with Pt 4, Ch 9, 1.2 are to be provided with suitable drainage arrangements. Examples of acceptable arrangements are detailed in 2.3.2 and 2.3.3.

2.3.2 Where deep cofferdams can be filled with water ballast, a ballast pump in the main engine room may be used for emptying the after cofferdam. Where fitted, a ballast pump in a forward pump room may be used for emptying the forward cofferdam. In each case, the suction is to be led direct to the pump and not to a pipe system.

2.3.3 Where intended to be dry compartments, after cofferdams adjacent to the pump room may be drained by a cargo pump, provided that isolating arrangements are fitted in the bilge system as required by 2.2.1; forward cofferdams may be drained by a bilge and ballast pump in a forward pump room. Alternatively, cofferdams may be drained by bilge ejectors or, in the case of small ships, by hand pumps.

2.3.4 Cofferdams are not to have any direct connections to the cargo tanks or cargo lines.

#### 2.4 Drainage of ballast tanks and void spaces within the range of the cargo tanks

2.4.1 Ballast tanks and void spaces within the range of the cargo tanks are not to be connected to cargo pumps, or have any connections to the cargo system. A separate ballast/bilge pump is to be provided for dealing with the contents of these spaces. This pump is to be located in the cargo pump room or other suitable space within the range of the cargo tanks.

2.4.2 Ballast pumps shall be provided with suitable arrangements to ensure efficient suction from ballast tanks.

2.4.3 Where submerged water ballast pumps are fitted, they are to be located in separate compartments on opposite sides of the ship such that, in the event of hull damage due to grounding or collision, the risk of total loss of ballast pumping capability is minimised.

2.4.4 Ballast piping is not to pass through cargo tanks and is not to be connected to cargo oil piping. Provision may, however, be made for emergency discharge of water ballast by means of a portable spool connection to a cargo oil pump and where this is arranged, a non-return valve is to be fitted in the ballast suction to the cargo oil pump.

2.4.5 Consideration will be given to connecting double bottom and/or wing tanks, which are in the range of the cargo tanks, to pumps in the machinery space where the tanks are completely separated from the cargo tanks by cofferdams, heating ducts or containment spaces, etc.

#### 2.5 Air and sounding pipes

2.5.1 Deep cofferdams at the fore and aft ends of the cargo spaces and other tanks or cofferdams within the range of the cargo tanks, which are not intended for cargo, are to be provided with air and sounding pipes led to the open deck. The air pipes are to be fitted with gauze diaphragms at their outlets.

2.5.2 The air and sounding pipes required by 2.5.1 are not to pass through cargo tanks.

2.5.3 On oil tankers of less than 5000 tonnes dead-weight, where wing ballast tanks or spaces are not required, the sounding and air pipes to double bottom spaces below cargo tanks may pass through the cargo tanks. However, the pipes are to be of heavy gauge steel, and are to be in continuous lengths or with welded joints.

#### 2.6 Ballast piping in pump room double bottoms

2.6.1 Ballast piping is permitted to be located within the cargo pump room double bottom provided any damage to that piping does not render the ship's ballast and cargo pumps, located in the cargo pump room, ineffective.

# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 3

### ■ Section 3 Cargo handling system

#### 3.1 General

3.1.1 A complete system of piping and pumps is to be fitted for dealing with the cargo.

3.1.2 Standby means for pumping out each cargo tank are to be provided.

3.1.3 Where cargo tanks are provided with single deep well pumps, or submerged pumps, it will be necessary to provide alternative means for emptying the tanks in the event of the failure of a pump. Portable submersible pumps may be provided on board for this purpose, but the arrangements are to be such that a portable pump could be safely introduced into a full or part-full tank. Details of the arrangements are to be submitted.

3.1.4 Provision is to be made for the gas freeing of the cargo oil tanks when the cargo has been discharged, and for the ventilation and gas freeing of all compartments adjacent to cargo oil tanks. It is recommended that arrangements be provided to enable double bottom tanks situated below cargo tanks to be filled with water ballast to assist in the gas freeing of these tanks, *see also* 7.6.2.

3.1.5 At least two portable instruments are to be available on board for gas detection.

3.1.6 Cargo tank access hatches and all other openings to cargo tanks, such as ullage and tank cleaning openings and restricted sounding devices, *see* 5.2, are to be located on the weather deck.

#### 3.2 Cargo pumps

3.2.1 Pumps for the purpose of filling or emptying the cargo oil tanks are to be used exclusively for this purpose, except as provided in 2.2.1. They are not to have any connections to compartments outside the range of cargo oil tanks.

3.2.2 Means are to be provided for stopping the cargo oil pumps from a position outside the pump rooms, as well as at the pumps.

3.2.3 The pumps are to be provided with effective relief valves which are to be in close-circuit, i.e. discharging to the suction side of the pumps. Alternative proposals to safeguard against over-pressure on the discharge side of the pump will be specially considered.

3.2.4 Where cargo pumps are driven by shafting which passes through a pump room bulkhead or deck, gastight glands are to be fitted to the shaft at the pump room plating. The glands are to be efficiently lubricated from outside the pump room. The seal parts of the glands are to be of materials that will not initiate sparks. The glands are to be of an approved type and are to be attached to the bulkhead in accordance with Ch 13.2.4. Where a bellows piece is incorporated in the design, it is to be hydraulically tested to 3,4 bar (3,5 kgf/cm<sup>2</sup>) before fitting.

3.2.5 Where cargo pumps are driven by hydraulic motors which are located inside cargo tanks, the design is to be such that contamination of the operating medium with cargo liquid cannot take place under normal operating conditions. The arrangements are to comply with 3.7.7 and 3.7.8, in so far as they are applicable.

#### 3.3 Cargo piping system

3.3.1 Cargo piping and similar piping to cargo tanks are not to pass through ballast tanks.

3.3.2 Cargo pipes are not to pass through tanks or compartments which are outside the cargo tank area.

3.3.3 Means are to be provided to enable the contents of the cargo lines pumps to be drained to a cargo tank or other suitable tank. Where drain tanks are fitted in pump rooms, they are to be of the closed type with air and sounding pipes led to the open deck.

3.3.4 Expansion joints of approved type or bends are to be provided, where necessary, in the cargo pipe lines.

3.3.5 Expansion pieces of an approved type, incorporating oil resistant rubber or other suitable material, may be accepted in cargo piping, *see also* Ch 13.2.7.2.

3.3.6 In combination carriers where cargo wing tanks are provided, cargo oil lines below deck are to be installed inside these tanks. However, Lloyd's Register (hereinafter referred to as 'LR') may permit cargo oil lines to be placed in special ducts which are to be capable of being adequately cleaned and ventilated to the satisfaction of LR's Surveyors. Where cargo wing tanks are not provided cargo oil lines below deck are to be placed in special ducts.

3.3.7 Means are to be provided for keeping deck spills away from accommodation and service areas. This may be accomplished by means of a 300 mm coaming extending from side to side. Special consideration shall be given to the arrangements associated with stern loading.

#### 3.4 Terminal fittings at cargo loading stations

3.4.1 Terminal pipes, valves and other fittings in the cargo loading and discharging lines to which shore installation hoses are directly connected, are to be of steel or approved ductile material. They are to be of robust construction and strongly supported, *see also* 1.3 and 1.4.

# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 3

3.4.2 A manually operated shut-off valve is to be fitted to each shore loading/discharging connection.

3.4.3 Drip pans for collecting cargo residues in cargo lines and hoses are to be provided beneath pipe and hose connections in the manifold area.

### 3.5 Bow or stern loading and discharge arrangements

3.5.1 Where a ship is arranged for bow and/or stern loading and discharge of cargo outside the cargo tank area, the pipe lines and related piping and equipment forward and/or aft of the cargo area are to have only welded joints and are to be provided with spectacle flanges or removable spool pieces, where branched off from the main line, and a blank flange at the bow and/or stern end connections, irrespective of the number and type of valves in the line.

3.5.2 The spaces within 3 m of discharge manifolds are to be considered as dangerous spaces with regard to electrical or incensive equipment, see also Pt 6, Ch 2, 13.9.

### 3.6 Connections to cargo tanks

3.6.1 Where cargo tanks are provided with direct filling connections, the loading pipes are to be led to as low a level as practicable inside the tank.

3.6.2 Where cargo suction and/or filling lines are led through cargo tanks, or through other spaces situated below the weather deck, the connection to each tank is to be provided with a valve situated inside the tank, and capable of being operated from the deck. In the case of cargo tanks which are located adjacent to below-deck pump rooms, or pipe tunnels, the deck operated valves may be located in these spaces at the bulkhead. In any case, not less than two isolating shut-off valves are to be provided in the pipe lines between the tanks and the cargo pumps.

### 3.7 Remote control valves

3.7.1 Valves on deck and in pump rooms which are provided with remote control, are, in general, to be arranged for local manual operation independent of the remote operating mechanism, see also Ch 13, 2.3.2 and 2.3.3.

3.7.2 Where the valves and their actuators are located inside the cargo tanks, two separate suctions are to be provided in each tank, or alternative means of emptying the tank, in the event of a defective actuator, are to be provided.

3.7.3 All actuators are to be of a type which will prevent the valves from opening inadvertently in the event of the loss of pressure in the operating medium. Indication is to be provided at the remote control station showing whether the valve is open or shut.

3.7.4 Materials of construction of the actuators and piping inside the cargo tanks are to be suitable for use with the intended cargo.

3.7.5 Compressed air is not to be used for operating actuators inside cargo tanks.

3.7.6 The actuator operating medium in hydraulic systems is to have a flash point of 60°C or above (closed cup test) and is to be compatible with the intended cargoes.

3.7.7 The design of the actuators is to be such that contamination of the operating medium with cargo liquid cannot take place under normal operating conditions.

3.7.8 Where the operating medium is oil, or other fluid, the supply tank is to be located as high as practicable above the level of the top of the cargo tanks, and all actuator supply lines are to enter the cargo tanks through the highest part of the tanks. Furthermore, the supply tank is to be of the closed type with an air pipe led to a safe space on the open deck and fitted with a flameproof wire gauze diaphragm at its open end. This tank is also to be fitted with a high and low level audible and visual alarm. The requirements of this paragraph need not be complied with if the actuators and piping are located external to the cargo tanks.

3.7.9 It is recommended that for remote control valves not arranged for manual operation, emergency means be provided for operating the valve actuators in the event of damage to the main hydraulic circuits on deck. In the case of valves located inside cargo tanks, this could be achieved by ensuring that the supply lines to the actuators are led vertically inside the tanks from deck, and that connections, with necessary isolating valves, are provided on deck for coupling to a portable pump carried on board.

### 3.8 Cargo handling controls

3.8.1 Electrical measuring, monitoring control and communication circuits located in dangerous spaces are to be intrinsically-safe.

3.8.2 The handling controls and instruments are to be arranged for safe and easy operation. They may be grouped at a number of control stations or at one main control station.

3.8.3 A satisfactory means of communication is to be provided between cargo handling stations, open deck, the bridge and the machinery space.

3.8.4 The cargo handling controls and instrumentation are, so far as possible, to be separate from the propulsion and auxiliary machinery controls and instrumentation.

# Piping Systems for Oil Tankers

## Part 5, Chapter 15

### Section 4

#### ■ Section 4 Cargo tank venting, purging and gas-freeing

##### 4.1 Cargo tank venting

4.1.1 The venting systems of cargo tanks are to be entirely distinct from the air pipes of the other compartments of the ship. The arrangements and position of openings in the cargo tank deck from which emission of flammable vapours can occur are to be such as to minimize the possibility of flammable vapours being admitted to enclosed spaces containing a source of ignition, or collecting in the vicinity of deck machinery and equipment which may constitute an ignition hazard.

4.1.2 The venting arrangements are to be so designed and operated as to ensure that neither pressure nor vacuum in cargo tanks exceeds design parameters and are to be such as to provide for:

- (a) the flow of the small volumes of vapour, air or inert gas mixtures caused by thermal variations in a cargo tank in all cases through pressure/vacuum valves; and
- (b) the passage of large volumes of vapour, air or inert gas mixtures during cargo loading and ballasting, or during discharging.
- (c) a secondary means of allowing full flow relief of vapour, air or inert gas mixtures to prevent overpressure or underpressure in the event of failure of the arrangements in 4.1.2(b). Alternatively, pressure sensors may be fitted to monitor the pressure in each tank protected by the arrangement required in 4.1.2(b), with a monitoring system in the ship's cargo control room or the position from which cargo operations are normally carried out. Such monitoring equipment is also to provide an alarm facility which is activated by detection of overpressure or underpressure conditions within a tank.

4.1.3 The venting arrangements in each cargo tank may be independent or combined with other cargo tanks and may be incorporated into the inert gas piping.

4.1.4 Where the arrangements are combined with other cargo tanks either stop valves or other acceptable means are to be provided to isolate each cargo tank. Where stop valves are fitted, they are to be provided with locking arrangements which are to be under the control of the responsible ship's officer.

4.1.5 There is to be a clear visual indication of the operational status of the valves, or other acceptable means. Where tanks have been isolated, it is to be ensured that the relevant isolating valves are opened before cargo loading or ballasting or discharging of those tanks is commenced. Any isolation is to continue to permit the flow caused by thermal variations in a cargo tank in accordance with 4.1.2(a).

4.1.6 If cargo loading and ballasting or discharging of a cargo tank or cargo tank group, which is isolated from a common venting system is intended, that cargo tank or cargo tank group is to be fitted with a means for overpressure or underpressure protection as required in 4.1.2(c).

4.1.7 The venting arrangements are to be connected to the top of each cargo tank and are to be self-draining to the cargo tanks under all normal conditions of trim and list of the ship. Where it may not be possible to provide self-draining lines permanent arrangements are to be provided to drain the vent lines to a cargo tank.

4.1.8 The venting system is to be provided with devices to prevent the passage of flame into the cargo tanks. The design, testing and locating of these devices are to comply with recognized International Standards.

4.1.9 Ullage openings are not to be used for pressure equalisation and they should be fitted with self-closing tightly sealing covers. Flame arrestors and screens are not permitted in these openings.

4.1.10 Provision is to be made to guard against liquid rising in the venting system to a height which would exceed the design head of cargo tanks. This is to be accomplished by overflow control systems, or other equivalent means, e.g. overfill alarms, together with gauging devices and cargo tank filling procedures but not spill valves which are not considered equivalent to an overflow system. The system for guarding against liquid rising to a height which would exceed the design head of cargo tanks is to be independent of the gauging devices.

4.1.11 Openings for pressure release required by 4.1.2(a) are to:

- (a) have as great a height as is practicable above the cargo tank deck to obtain maximum dispersal of flammable vapours but in no case less than 2 m above the cargo tank deck, and
- (b) be arranged at the furthest distance practicable but not less than 5 m from the nearest air intakes and openings to enclosed spaces containing a source of ignition and from deck machinery, chain locker openings and equipment which may constitute an ignition hazard.

4.1.12 Pressure/vacuum valves required by 4.1.2(a) may be provided with a by-pass arrangement when they are located in a vent main or masthead riser. Where such an arrangement is provided there are to be suitable indicators to show whether the by-pass is open or closed.

4.1.13 Vent outlets for cargo loading, discharging and ballasting required by 4.1.2(b) are to:

- (a) permit the free flow of vapour mixtures or alternatively, permit the throttling of the discharge of the vapour mixtures to achieve a velocity of not less than 30 m/sec;
- (b) be so arranged that the vapour mixture is discharged vertically upwards;
- (c) where the method is by free flow of vapour mixtures, be such that the outlet is not less than 6 m above the cargo tank deck or fore and aft gangway if situated within 4 m of the gangway and located not less than 10 m measured horizontally from the nearest air intakes and openings to enclosed spaces containing a source of ignition and from deck machinery, chain locker openings and equipment which may constitute an ignition hazard;

# Piping Systems for Oil Tankers

# Part 5, Chapter 15

Section 4

- (d) where the method is by high velocity discharge, be located at a height not less than 2 m above the cargo tank deck and not less than 10 m measured horizontally from the nearest air intakes and openings to enclosed spaces containing a source of ignition and from deck machinery, chain locker openings and equipment which may constitute an ignition hazard. These outlets are to be provided with high velocity devices of an approved type; and
- (e) be designed on the basis of the maximum designed loading rate multiplied by a factor of at least 1,25 to take account of gas evolution, in order to prevent the pressure in any cargo tank from exceeding the design pressure. The master is to be provided with information regarding the maximum permissible loading rate for each cargo tank and in the case of combined venting systems, for each group of cargo tanks.

4.1.14 Pressure/vacuum valves are to be set at a positive pressure of not more than 0,2 bar (0,2 kgf/cm<sup>2</sup>) above atmospheric and a negative pressure of not more than 0,07 bar (0,07 kgf/cm<sup>2</sup>) below atmospheric. Higher positive pressures not exceeding 0,7 bar (0,7 kgf/cm<sup>2</sup>) gauge may be permitted in specially designed integral tanks.

4.1.15 In combination carriers the arrangements to isolate slop tanks containing oil or residues from other cargo tanks are to consist of blank flanges which will remain in position at all times when cargoes other than liquid cargoes referred to in 7.5.16 are carried.

## 4.2 Cargo tank purging and/or gas-freeing

4.2.1 Arrangements for purging and/or gas-freeing are to be such as to minimize the hazards due to the dispersal of flammable vapours in the atmosphere and to flammable mixtures in cargo tank, thus the requirements of 4.2.2 to 4.2.4 are to be complied with, as applicable.

4.2.2 When the ship is provided with an inert gas system the cargo tanks are first to be purged in accordance with the provisions of 7.6.2 until the concentration of hydrocarbon vapours in the cargo tanks has been reduced to less than two per cent by volume. Thereafter gas freeing may take place at the cargo tank deck level.

4.2.3 When the ship is not provided with an inert gas system, the operation is to be such that the flammable vapour is initially discharged either:

- (a) through the vent outlets as specified in 4.1.13, or
- (b) through outlets at least 2 m above the cargo tank deck level with a vertical efflux velocity of at least 30 m/sec. maintained during gas freeing operation, or
- (c) through outlets at least 2 m above the cargo tank deck level with a vertical efflux velocity of at least 20 m/sec. and which are protected by suitable devices to prevent the passage of flame.

4.2.4 When the flammable vapour concentration at the outlet has been reduced to 30 per cent of the lower flammable limit, gas-freeing may thereafter be continued at the cargo tank deck level.

## 4.3 Venting, purging and gas measurement of double hull and double bottom spaces

4.3.1 Double hull and double bottom spaces are to be fitted with suitable connections for the supply of air.

4.3.2 On tankers required to be fitted with inert gas systems:

- (a) double hull spaces are to be fitted with suitable connections for the supply of inert gas;
- (b) where such spaces are connected to a permanently fitted inert gas distribution system means are to be provided to prevent hydrocarbon gases from the cargo tanks entering the double hull spaces through the system;
- (c) where such spaces are not permanently connected to an inert gas distribution system, appropriate means are to be provided to allow connection to the inert gas main.

4.3.3 When selecting portable instruments for measuring oxygen and flammable vapour, due attention is to be given to their use in combination with the fixed gas sampling line systems referred to in paragraph 4.3.4.

4.3.4 Where the atmosphere in double hull spaces cannot be reliably measured using flexible gas sampling hoses, such spaces are to be fitted with permanent gas sampling lines. The configuration of such line systems is to be adapted to the design of such spaces.

4.3.5 The materials of construction and the dimensions of gas sampling lines are to be such as to prevent restriction. Where plastics materials are used, they are to be electrically conductive.

## 4.4 Gas measurement

4.4.1 All tankers are to be equipped with at least two portable instruments for measuring % LEL of hydrocarbon concentrations in air.

4.4.2 All tankers are to be equipped with at least two portable oxygen analysers.

4.4.3 For tankers fitted with an inert gas system two portable gas detectors capable of measuring flammable vapour concentrations in inerted atmospheres are to be provided, see 7.7.5.

4.4.4 Suitable means are to be provided for the calibration of gas measurement instruments.

# Piping Systems for Oil Tankers

# Part 5, Chapter 15

Sections 5, 6 & 7

## ■ Section 5 Cargo tank level gauging equipment

### 5.1 General

5.1.1 Each cargo tank is to be fitted with suitable means for ascertaining the liquid level in the tank in accordance with the requirements of 5.2 and 5.3.

### 5.2 Restricted sounding device

5.2.1 Sounding pipes or other approved devices, which may permit a limited amount of vapour to escape to atmosphere when being used, would be accepted for those tanks which are not required to be fitted with closed sounding devices, see 5.3. The devices are to be so designed as to minimize the sudden release of vapour or liquid under pressure and the possibility of liquid spillage on deck. Means are also to be provided for relieving tank pressure before the device is operated.

5.2.2 Separate ullage openings may be fitted as a reserve means for sounding cargo tanks.

5.2.3 Arrangements which permit the escape of vapour to the atmosphere are not to be fitted in enclosed spaces.

### 5.3 Closed sounding devices

5.3.1 In all tankers fitted with a fixed inert gas system, the cargo tanks are to be fitted with closed sounding devices of an approved type, which do not permit the escape of cargo to the atmosphere when being used.

5.3.2 Proposals to use indirect sounding or measuring devices which do not penetrate the tank plating will be specially considered.

## ■ Section 6 Cargo heating arrangements

### 6.1 General

6.1.1 Where heating systems are provided for the cargo tanks, the arrangements are to comply with the requirements of 6.2 to 6.5.

### 6.2 Blanking arrangements

6.2.1 Spectacle flanges of spool pieces are to be provided in the heating medium supply and return pipes to the cargo heating system, at a suitable position within the cargo area, so that lines can be blanked off in circumstances where the cargo does not require to be heated or where the heating coils have been removed from the tanks. Alternatively, blanking arrangements may be provided for each tank heating circuit.

### 6.3 Heating medium

6.3.1 Where a combustible liquid is used as the heating medium it is to have a flash point of 60°C or above (closed-cup test).

6.3.2 In general, the temperature of the heating medium is not to exceed 220°C, see 1.5.

### 6.4 Heating circuits

6.4.1 The heating medium supply and return lines are not to penetrate the cargo tank plating, other than at the top of the tank, and the main supply lines are to be run above the weather deck.

6.4.2 Isolating shut-off valves or cocks are to be provided at the inlet and outlet connections to the heating circuit(s) of each tank, and means are to be provided for regulating the flow.

6.4.3 Where steam or water is employed in the heating circuits, the returns are to be led to an observation tank which is to be in a well ventilated and well lighted part of the machinery space remote from the boilers.

6.4.4 Where a thermal oil is employed in the heating circuits, the arrangements will be specially considered but, in any case, they are to be such that contamination of the thermal oil with cargo liquid cannot take place under normal operating conditions. In general, the arrangements are, at least, to comply with 3.7.8, in so far as they are applicable.

6.4.5 In any heating system, a higher pressure is to be maintained within the heating circuit than the maximum pressure head which can be exerted by the contents of the cargo tank on the circuit. Alternatively, when the heating circuit is not in use, it may be drained and blanked.

### 6.5 Temperature indication

6.5.1 Means are to be provided for measuring the cargo temperature. Where overheating could result in a dangerous condition, an alarm system which monitors the cargo temperature is to be provided.

## ■ Section 7 Inert gas systems

### 7.1 General

7.1.1 The following requirements apply where an inert gas system, based on flue gas, is fitted on board ships intended for the carriage of oil in bulk having a flash point not exceeding 60°C (closed-cup test). Any proposal to use an inert gas other than flue gas, e.g. nitrogen, will be specially considered.

# Piping Systems for Oil Tankers

# Part 5, Chapter 15

Section 7

7.1.2 Ships complying with these requirements will be eligible for the additional notation **IGS** in the *Register Book*, see Pt 1, Ch 2.

7.1.3 Throughout this Section the term 'cargo tank' includes also 'slop tanks'. For definition of Machinery spaces of Category 'A', see SOLAS Reg. II-2/A.

## 7.2 Gas supply

7.2.1 The inert gas may be treated flue gas from the main or auxiliary boiler(s), gas turbine(s), or from a separate inert gas generator. In all cases, automatic combustion control, capable of producing suitable inert gas under all service conditions, is to be fitted.

7.2.2 Two oil fuel pumps are to be fitted to the inert gas generator. One fuel pump only may be accepted provided sufficient spares for the oil fuel pump and its prime mover are carried on board to enable any failure of the oil fuel pump and its prime mover to be rectified by the ship's crew.

7.2.3 The inert gas system is to be capable of:

- (a) inerting empty cargo tanks by reducing the oxygen content of the atmosphere in each tank to a level at which combustion cannot be supported;
- (b) maintaining the atmosphere in any part of any cargo tank with an oxygen content not exceeding eight per cent by volume and at a positive pressure at all times in port and at sea except when it is necessary for such a tank to be gas free;
- (c) eliminating the need for air to enter a tank during normal operations except when it is necessary for such a tank to be gas free;
- (d) purging empty cargo tanks of hydrocarbon gas, so that subsequent gas freeing operations will at no time create a flammable atmosphere within the tank.

7.2.4 The system is to be capable of delivering inert gas to the cargo tanks at a rate of at least 125 per cent of the maximum rate of discharge capacity of the ship expressed as a volume.

7.2.5 The system is to be capable of delivering inert gas with an oxygen content of not more than five per cent by volume in the inert gas supply main to the cargo tanks at any required rate of flow.

7.2.6 Flue gas isolating valves are to be fitted in the inert gas supply mains between the boiler uptakes and the flue gas scrubber. These valves are to be provided with indicators to show whether they are open or shut, and precautions are to be taken to maintain them gastight and keep the seatings clear of soot. Arrangements are to be made to ensure that boiler soot blowers cannot be operated when the corresponding flue gas valve is open.

## 7.3 Gas scrubber

7.3.1 A flue gas scrubber is to be fitted which will effectively cool the volume of gas specified in 7.2.4 and remove solids and sulphur combustion products. The cooling water arrangements are to be such that an adequate supply of water will always be available without interfering with any essential services on the ship. Provision is also to be made for alternative supply of cooling water.

7.3.2 Filters or equivalent devices are to be fitted to minimize the amount of water carried over to the inert gas blowers.

7.3.3 The scrubber is to be located aft of all cargo tanks, cargo pump rooms and cofferdams separating these spaces from machinery spaces of Category A.

## 7.4 Gas blowers

7.4.1 At least two blowers are to be fitted which together are capable of delivering to the cargo tanks at least the volume of gas required by 7.2.4. In no case is one of these blowers to have a capacity less than one-third of the total capacity required. In a system with gas generators one blower only may be accepted if that system is capable of delivering the total volume of gas required by 7.2.4 to the protected cargo tanks, provided that sufficient spares for the blower and its prime mover are carried on board to enable any failure of the blower and its prime mover to be rectified by the ship's crew.

7.4.2 The inert gas system is to be so designed that the maximum pressure which it can exert on any cargo tank will not exceed the test pressure of any cargo tank. Suitable shut-off arrangements are to be provided on the suction and discharge connections of each blower. Arrangements are to be provided to enable the functioning of the inert gas plant to be stabilized before commencing cargo discharge. If the blowers are to be used for gas freeing, their air inlets are to be provided with blanking arrangements.

7.4.3 The blowers are to be located aft of all cargo tanks, cargo pump rooms and cofferdams separating these spaces from machinery spaces of Category A.

## 7.5 Gas distribution lines

7.5.1 Special consideration is to be given to the design and location of scrubber and blowers with relevant piping and fittings in order to prevent flue gas leakages into enclosed spaces.

7.5.2 To permit safe maintenance, an additional water seal or other effective means of preventing flue gas leakage is to be fitted between the flue gas isolating valves and scrubber or incorporated in the gas entry to the scrubber.



# Piping Systems for Oil Tankers

## Part 5, Chapter 15

Section 7

7.5.3 A gas regulating valve is to be fitted in the inert gas supply main. This valve is to be automatically controlled to close as required in 7.7.9 and 7.7.10. It is also to be capable of automatically regulating the flow of inert gas to the cargo tanks unless means are provided to automatically control the speed of the inert gas blowers required in 7.4.1.

7.5.4 The valve referred to in 7.5.3 is to be located at the forward bulkhead of the forwardmost gas safe space through which the inert gas supply main passes.

7.5.5 At least two non-return devices, one of which is to be a water seal, are to be fitted in the inert gas supply main, in order to prevent the return of hydrocarbon vapour to the machinery space uptakes or to any gas safe spaces under all normal conditions of trim, list and motion of the ship. They are to be located between the automatic valve required by 7.5.3 and the aftermost connection to any cargo tank or cargo pipeline.

7.5.6 The devices referred to in 7.5.5 are to be located in the cargo area on deck.

7.5.7 The water seal referred to in 7.5.5 is to be capable of being supplied by two separate pumps, each of which is to be capable of maintaining an adequate supply at all times.

7.5.8 The arrangement of the seal and its associated fittings is to be such that it will prevent backflow of hydrocarbon vapours and will ensure the proper functioning of the seal under operating conditions.

7.5.9 Provision is to be made to ensure that the water seal is protected against freezing in such a way that the integrity of seal is not impaired by overheating.

7.5.10 A water loop or other approved arrangement is also to be fitted to each associated water supply and drain pipe and each venting or pressure-sensing pipe leading to gas safe spaces. Means are to be provided to prevent such loops from being emptied by vacuum.

7.5.11 The deck water seal and all loop arrangements are to be capable of preventing return of hydrocarbon vapours at a pressure equal to the test pressure of the cargo tanks.

7.5.12 The second non-return device is to be a non-return valve or equivalent capable of preventing the return of vapours or liquids and fitted forward of the deck water seal required in 7.5.5. It is to be provided with positive means of closure. As an alternative to positive means of closure, an additional valve having such means of closure may be provided forward of the non-return valve to isolate the deck water seal from the inert gas main to the cargo tanks.

7.5.13 As an additional safeguard against the possible leakage of hydrocarbon liquids or vapours back from the deck main, means are to be provided to permit this section of the line between the valve having positive means of closure referred to in 7.5.12 and the valve referred to in 7.5.3 to be vented in a safe manner when the first of these valves is closed.

7.5.14 The inert gas main may be divided into two or more branches forward of the non-return devices required by 7.5.5.

7.5.15 The inert gas supply mains are to be fitted with branch piping leading to each cargo tank. Branch piping for inert gas is to be fitted with either stop valves or equivalent means of control for isolating each tank. Where stop valves are fitted, they are to be provided with locking arrangements, which are to be under the control of a responsible ship's officer. The method of control is to provide positive indication of the operational status of such valves.

7.5.16 In combination carriers, the arrangement to isolate the slop tanks containing oil or oil residues from other tanks is to consist of blank flanges which will remain in position at all times other than when cargoes other than oil are being carried except as provided for in 1.9.

7.5.17 Means are to be provided to protect cargo tanks against the effect of overpressure or vacuum caused by thermal variations when the cargo tanks are isolated from the inert gas mains.

7.5.18 Piping systems are to be so designed as to prevent the accumulation of cargo or water in the pipelines under all normal conditions.

7.5.19 Arrangements are to be provided to enable the inert gas main to be connected to an external supply of inert gas. The arrangement is to consist of a 250 mm nominal size pipe bolted flange connection, isolated from the inert gas main by a valve and connected to the system forward of the non-return valve referred to in 7.5.12.

### 7.6 Venting arrangements

7.6.1 The arrangements for the venting of all vapours displaced from the cargo tanks during loading and ballasting are to comply with Section 4 and are to consist of either one or more mast risers, or a number of high velocity vents. The inert gas supply mains may be used for such venting.

7.6.2 The arrangements for inerting, purging or gas freeing of empty tanks as required in 7.2.3 are to be such that the accumulation of hydrocarbon vapours in pockets formed by the internal structural members in a tank is minimized and that:

- (a) on individual cargo tanks the gas outlet pipe, if fitted, is to be positioned as far as practicable from the inert gas/air inlet and in accordance with Section 4. The inlet of such outlet pipes may be located either at deck level or at not more than 1 m above the bottom of the tank;
- (b) the cross sectional area of such gas outlet pipes referred to in (a) is to be such that an exit velocity of at least 20 m/s can be maintained when any three tanks are being simultaneously supplied with inert gas. Their outlets are to extend not less than 2 m above deck level;
- (c) each gas outlet referred to in (b) is to be fitted with suitable blanking arrangements;

# Piping Systems for Oil Tankers

# Part 5, Chapter 15

Section 7

- (d) if a connection is fitted between the inert gas supply mains and the cargo piping system, arrangements are to be made to ensure an effective isolation having regard to the large pressure difference which may exist between the systems. This is to consist of two shut-off valves with an arrangement to vent the space between the valves in a safe manner or an arrangement consisting of a spool-piece with associated blanks. The valve separating the inert gas supply main from the cargo main and which is on the cargo main side is to be a non-return valve with a positive means of closure.

7.6.3 One or more pressure-vacuum breaking devices are to be provided to prevent the cargo tanks from being subject to:

- (a) a positive pressure in excess of the test pressure of the cargo tank if the cargo were to be loaded at the maximum rated capacity and all other outlets were left shut; and
- (b) a negative pressure in excess of 700 mm water gauge if cargo were to be discharged at the maximum rated capacity of the cargo pumps and the inert gas blowers were to fail.

Such devices shall be installed on the inert gas main unless they are installed in the venting system required by Section 4 or on individual cargo tanks.

7.6.4 The location and design of the devices referred to in 7.6.3 are to be in accordance with Section 4.

## 7.7 Instrumentation and alarms

7.7.1 Means are to be provided for continuously indicating the temperature and pressure of the inert gas at the discharge side of the gas blowers, whenever the gas blowers are operating.

7.7.2 Instrumentation is to be fitted for continuously indicating and permanently recording, when the inert gas is being supplied:

- (a) the pressure of the inert gas supply mains forward of the non-return devices required by 7.5.5; and
- (b) the oxygen content of the inert gas in the inert gas supply mains on the discharge side of the gas blowers.

7.7.3 The devices referred to in 7.7.2 are to be placed in the cargo control room where provided. But where no cargo control room is provided, they are to be placed in a position easily accessible to the officer in charge of cargo operations.

7.7.4 In addition to 7.7.2, meters are to be fitted:

- (a) in the navigating bridge to indicate at all times the pressure referred to in 7.7.2(a) and the pressure in the slop tanks of combination carriers, whenever those tanks are isolated from the inert gas supply main; and
- (b) in the machinery control room or in the machinery space to indicate the oxygen content referred to in 7.7.2(b).

7.7.5 Portable instruments for measuring oxygen and flammable vapour concentration are to be provided. In addition, suitable arrangement is to be made on each cargo tank such that the condition of the tank atmosphere can be determined using these portable instruments.

7.7.6 Suitable means are to be provided for the zero and span calibration of both fixed and portable gas concentration measurement instruments, referred to in 7.7.2, 7.7.4 and 7.7.5.

7.7.7 For inert gas systems of both flue gas type and the inert gas generator type audible and visual alarms are to be provided to indicate:

- (a) low water pressure or low water flow rate to the flue gas scrubber as referred to in 7.3.1;
- (b) high water level in the flue gas scrubber as referred to in 7.3.1;
- (c) high gas temperature as referred to in 7.7.1;
- (d) failure of the inert gas blowers referred to in 7.4;
- (e) oxygen content in excess of eight per cent by volume as referred to in 7.7.2(b);
- (f) failure of the power supply to the automatic control system for the gas regulating valve and to the indicating devices as referred to in 7.5.3 and 7.7.2;
- (g) low water level in the water seal as referred to in 7.5.5;
- (h) gas pressure less than 100 mm water gauge as referred to in 7.7.2(a). The alarm arrangements is to be such as to ensure that pressure in slop tanks in combination carriers can be monitored at all times; and
- (j) high gas pressure as referred to in 7.7.2(a).

7.7.8 For inert gas systems of the inert gas generator type additional audible and visual alarms are to be provided to indicate:

- (a) insufficient oil fuel supply,
- (b) failure of the power supply to the generator,
- (c) failure of the power supply to the automatic control system for the generator.

See also Pt 6, Ch 1 for requirements for control, alarm and safety systems, and additional requirements for unattended operation.

7.7.9 Automatic shutdown of the inert gas blowers and gas regulating valve is to be arranged on predetermined limits being reached in respect of (a), (b) and (c) of 7.7.7.

7.7.10 Automatic shutdown of the gas regulating valve is to be arranged in respect of 7.7.7(d).

7.7.11 In respect of 7.7.7(e), when the oxygen content of the inert gas exceeds eight per cent by volume, immediate action is to be taken to improve the gas quality. Unless the quality of the gas improves, all cargo tank operations are to be suspended so as to avoid air being drawn into the tanks and the isolation valve referred to in 7.5.12 is to be closed.

7.7.12 The alarms required in (e), (f) and (h) of 7.7.7 are to be fitted in the machinery space and cargo control room, where provided, but in each case in such a position that they are immediately received by responsible members of the crew.

7.7.13 In respect of 7.7.7(g), where a semi-dry or dry water seal is fitted, the arrangements are to be such that the maintenance of an adequate reserve of water will be ensured at all times and that the water seal will be automatically formed when the gas flow ceases. The audible and visual alarm on the low level of water in the water seal is to operate when the inert gas is not being supplied.

7.7.14 An audible alarm system independent of that required in 7.7.7(h) or automatic shutdown of cargo pumps is to be provided to operate on predetermined limits of low pressure in the inert gas mains being reached.

7.7.15 Detailed instruction manuals are to be provided on board, covering the operations, safety and maintenance requirements and occupational health hazards relevant to the inert gas system and its application to the cargo tank system. The manuals are to include guidance on procedures to be followed in the event of a fault or failure of the inert gas system.

## 7.8 Installation and tests

7.8.1 The inert gas system, including alarms and safety devices, is to be installed on board and tested under working conditions to the satisfaction of the Surveyors.

## ■ Cross-reference

For vapour detection, see also Ch 13,2 of the *Rules and Regulations for the Construction and Classification of Ships for the Carriage of Liquid Chemicals in Bulk*.



## Section

**1 General**

---

**■ Section 1  
General****1.1 Application**

**1.1.1** Adequate spare parts for the propelling and essential auxiliary machinery together with the necessary tools for maintenance and repair shall be readily available for use.

**1.1.2** The spare parts to be supplied and their location are to be the responsibility of the Owner but must take into account the design and arrangements of the machinery and the intended service and operation of the ship. Account should also be taken of the recommendations of the manufacturers and any applicable statutory requirement of the country of registration of the ship.

**1.2 Tables of spare parts**

**1.2.1** For general guidance purposes, spare parts for main and auxiliary machinery installations are shown in the following Tables:

Table 16.1.1	Spare parts for main oil engines
Table 16.1.2	Spare parts for auxiliary oil engines
Table 16.1.3	Spare parts for main steam turbines
Table 16.1.4	Spare parts for auxiliary steam turbines
Table 16.1.5	Spare parts for auxiliary air compressors
Table 16.1.6	Spare parts for boilers supplying steam propulsion and for essential services.

## Spare Gear for Machinery Installations

## Part 5, Chapter 16

Section 1

Table 16.1.1 Spare parts for main oil engines (see continuation)

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Main bearings	Main bearings or shells for one bearing of each size and type fitted, complete with shims, bolts and nuts	1	—
Main thrust block	Pads for one face of Michell-type thrust block Inner and outer race with rollers where roller thrust bearings are fitted	1 set or 1	1 set 1
Cylinder liner	Cylinder liner complete with joint rings and gaskets	1	—
Cylinder cover	Cylinder cover, complete with valves, joint rings and gaskets. For engines without covers, the respective valves for one cylinder unit	1	—
	Cylinder cover studs or bolts, with nuts, as applicable for one cylinder	1/2 set	—
Cylinder valves	Exhaust valves, complete with casings, seats, springs and other fittings for one cylinder	2 sets	1 set
	Air inlet valves, complete with casings, seats, springs and other fittings for one cylinder	1 set	1 set
	Starting air valve, complete with casing, seat, springs and other fittings	1	1
	Relief valve, complete	1	1
	Fuel injection valves of each size and type fitted, complete with all fittings, for one engine	1 set, see Note	1/4 set
Connecting rod bearings	Bottom end bearings or shells of each size and type fitted, complete with shims, bolts and nuts, for one cylinder	1 set	—
	Top end bearings or shells of each size and type fitted, complete with shims, bolts and nuts, for one cylinder	1 set	—
Pistons	Crosshead type, piston of each type fitted, complete with piston rod, stuffing box, skirt, rings, studs and nuts	1	—
	Trunk piston type, piston of each type fitted, complete with skirt, rings, studs, nuts, gudgeon pin and connecting rod	1	—
Piston rings	Piston rings, for one cylinder	1 set	—
Piston cooling	Telescopic cooling pipes and fittings or their equivalent, for one cylinder unit	1 set	—
NOTE 1. Engines with three or more fuel injection valves per cylinder: two fuel injection valves complete per cylinder and a sufficient number of valve parts, excluding the body, to provide, with those fitted, a full engine set.			

# Spare Gear for Machinery Installations

# Part 5, Chapter 16

Section 1

**Table 16.1.1** Spare parts for main oil engines (conclusion)

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Gear and chain for camshaft drives	Chain drive: separate links with pins and rollers of each size and type fitted	6	—
	Bearing bushes of each type fitted	1 set	—
Cylinder lubricators	Lubricator complete, of the largest size, with its chain drive or gear wheels	1	—
Fuel injection pumps	Fuel pump complete, or, when replacement at sea is practicable, a complete set of working parts for one pump (plunger, sleeve, valves, springs, etc.)	1	—
Fuel injection piping	High pressure fuel pipe of each size and shape fitted, complete with couplings	1	—
Scavenge blowers (including turbo-chargers)	Rotors, rotor shafts, bearings, nozzle rings and gear wheels or equivalent working parts if of other types, see Note 2	1 set	—
Scavenging system	Suction and delivery valves for one pump of each type fitted	1 set	—
Reduction and/or reverse gear	Complete bearing bush, of each size fitted in the gearcase assembly	1 set	—
	Roller or ball race, of each size fitted in the gearcase assembly	1 set	—
Main engine-driven air compressors	Piston rings of each size fitted	1 set	—
	Suction and delivery valves complete of each size fitted	1/2 set	—
Gaskets and packings	Special gaskets and packings of each size and type fitted for cylinder covers and cylinder liners for one cylinder	1 set	—
<p>NOTE</p> <p>2. The spare parts may be omitted where it has been demonstrated at the Enginebuilder's Works, or during sea trials, for an engine of the type concerned, that the engine can be manoeuvred satisfactorily with one blower out of action. The requisite blanking and/or blocking arrangements, applicable for running with one blower out of action as demonstrated, are to be available on board.</p>			

**Spare Gear for Machinery Installations****Part 5, Chapter 16**

Section 1

**Table 16.1.2 Spare parts for auxiliary oil engines**

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Main bearings	Main bearing or shells for one bearing of each size and type fitted, complete with shims, bolts and nuts	1	—
Cylinder valves	Exhaust valves, complete with casings, seats, springs and other fittings for one cylinder	2 sets	—
	Air inlet valves, complete with casings, seats, springs and other fittings for one cylinder	1 set	—
	Starting air valve, complete with casing, seat, springs and other fittings	1	—
	Relief valve, complete	1	—
	Fuel valves of each size and type fitted, complete with all fittings, for one engine	1/2 set	—
Connecting rod bearings	Bottom end bearings or shells of each size and type fitted, complete with shims, bolts and nuts, for one cylinder	1 set	—
	Top end bearings or shells of each size and type fitted, complete with shims, bolts and nuts for one cylinder	1 set	—
	Trunk piston type: gudgeon pin with bush for one cylinder	1 set	—
Piston rings	Piston rings, for one cylinder	1 set	—
Piston cooling	Piston cooling fittings, for one cylinder unit	1 set	—
Fuel injection pumps	Fuel pump complete, or, when replacement at sea is practicable, a complete set of working parts for one pump (plunger, sleeve, valve springs, etc.)	1	—
Fuel injection piping	High pressure fuel pipe of each size and shape fitted, complete with couplings	1	—
Gaskets and packings	Special gaskets and packings of each size and type fitted, for cylinder covers and cylinder liners for one cylinder	1 set	—



**Spare Gear for Machinery Installations****Part 5, Chapter 16**

## Section 1

**Table 16.1.3 Spare parts for main steam turbines**

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Main bearings	Complete bearing bush, of each size and type fitted, for the rotor, pinion and gear wheel shafts, for one engine	1	—
Turbine thrust	Pads of each size for one face of Michell-type thrust, or rings for turbine adjusting block, of each size for one engine Assorted liners for one block where fitted	1 set	1 set
Main thrust block	Pads for one face of Michell-type thrust block or Inner and outer race with rollers where roller thrust bearings are fitted	1 set 1	1 set 1
Turbine shaft sealing rings	Carbon sealing rings, where fitted, with springs, for each size and type of gland, for one engine	1 set	—
Oil filters	Disposable filter elements of each type and size fitted	1 set	—

**Table 16.1.4 Spare parts for auxiliary steam turbines**

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Main bearings	Complete bearing bush, of each size and type fitted, for the rotor, pinion and gear wheel shafts, for one engine	1	—
Turbine thrust	Pads of each size for one face of Michell-type thrust, or rings for turbine adjusting block, of each size for one engine Assorted liners for one block where fitted	1 set	1 set
Turbine shaft sealing rings	Carbon sealing rings, where fitted, with springs, for each size and type of gland, for one engine	1 set	—
Oil filters	Disposable filter elements of each type and size fitted	1 set	—

**Table 16.1.5 Spare parts for auxiliary air compressors**

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Piston rings	Rings, of each size fitted, for one piston	1 set	1 set
Valves	Suction and delivery valves, complete, of each size fitted	1/2 set	1/2 set

**Spare Gear for Machinery Installations****Part 5, Chapter 16**

Section 1

**Table 16.1.6 Spare parts for boilers supplying steam propulsion and for essential services**

Item	Spare parts	Number	
		Ships for unrestricted service	Ships for restricted service
Tube stoppers or plugs	Tube stoppers or plugs, of each size used, for boiler, superheater and economizer tubes	10	6
Oil fuel burners	Oil fuel burners complete or a complete set of wearing parts for the burners, for one boiler	1 set	1 set
Gauge glasses	Gauge glasses of round type	2 sets per boiler	2 sets per boiler
	Gauge glasses of flat type	1 set for every two boilers	1 set for every two boilers

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Sections 1 & 2

### Section

- 1 **General**
- 2 **Manufacture and workmanship of fusion welded pressure vessels**
- 3 **Routine weld tests for pressure vessels**
- 4 **Repairs to welds on fusion welded pressure vessels**
- 5 **Post weld heat treatment of pressure vessels**
- 6 **Welded pressure pipes**
- 7 **Non-Destructive Examination**

### ■ Section 1 General

#### 1.1 Scope

1.1.1 The requirements of this Chapter apply to the welding of pressure vessels and process equipment, heating and steam raising boilers and pressure pipes. The allocation of Class is determined from the design criteria referenced in Chapters 10, 11 and 12.

1.1.2 Fusion welded pressure vessels will be accepted only if manufactured by firms equipped and competent to undertake the quality of welding required for the Class of vessel proposed. The manufacturer's works are to be approved in accordance with the requirements specified in *Materials and Qualification Procedures for Ships*, Book A Procedure MQPS 0-4.

1.1.3 The term 'fusion weld', for the purpose of these requirements, is applicable to welded joints made by manual, semi-automatic or automatic electric arc welding processes. Special consideration will be given to the proposed use of other fusion welding processes, see Section 6 for oxy-acetylene welding of pipes.

1.1.4 For pressure vessels which only have circumferential seams, see Ch 10,1.5.4 and Ch 11,1.5.5.

#### 1.2 General requirements for welding plant and welding quality

1.2.1 In the first instance, and before work is commenced, the Surveyors are to be satisfied that the required quality of welding is attainable with the proposed welding plant, equipment and procedures.

1.2.2 The procedures are to include the regular systematic supervision of all welding, and the welders are to be subjected by the work's supervisors to periodic tests for quality of workmanship. Records of these tests are to be kept and are to be available for inspection by the Surveyors.

1.2.3 All welding is to be to the satisfaction of the Surveyors.

### ■ Section 2 Manufacture and workmanship of fusion welded pressure vessels

#### 2.1 General requirements

2.1.1 Prior to commencing construction, the design of the vessel is to be approved where required by Ch 10,1.6 and Ch 11,1.6.

2.1.2 Pressure vessels will be accepted only if manufactured by firms that have been assessed and approved in accordance with MQPS 0-4.

#### 2.2 Materials of construction

2.2.1 Materials used in welded construction are to be readily weldable and shall have proven weldability.

2.2.2 Materials are to be supplied by firms that have been approved in accordance with the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

2.2.3 Where the construction details are such that materials are subject to through thickness strains, consideration should be given to using materials with specified through thickness properties as specified in Ch 3,8 of the Rules for Materials).

2.2.4 Where the construction requires post weld heat treatment, consideration should be given to certifying the material after subjecting the test pieces to a simulated heat treatment.

2.2.5 The identity of materials is to be established by way of markings, etc., so that traceability to the original manufacturer's certificate is maintained.

#### 2.3 Cutting of materials

2.3.1 Materials may be cut to the required dimensions by thermal means, shearing or machining in accordance with the manufacturing drawings or specifications.

2.3.2 Cold shearing should not be used on materials in excess of 25 mm thick and, where used, the cut edges are to be cut back by machining or grinding for a minimum distance of 3 mm.

2.3.3 Material which has been thermally cut is to be machined or ground back to remove all oxides, scale and notches.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

### Section 2

2.3.4 Thermal cutting of alloy and high carbon steels may require the application of preheat, and special examination of these cut edges will be required to ensure freedom from cracking. In these cases the cut edges are to be machined or ground back a distance of at least 2,0 mm, unless it has been demonstrated that the cutting process has not damaged the material.

2.3.5 Any material damaged in the process of cutting is to be removed by machining, grinding or chipping back to sound metal; weld repair may only be performed with the agreement of the Surveyors.

2.3.6 All plate edges, after being cut, shall be examined for defects, including laminations, to ensure that these are free from cracks. Visual methods may be augmented by other techniques at the discretion of the Surveyors.

2.3.7 Edges that have been cut by machining or chipping, which will not be subsequently covered by weld metal, are to be ground smooth.

### 2.4 Forming shell sections and end plates

2.4.1 Shell plates and heads are to be formed to the correct contour up to the extreme edge of the plate.

2.4.2 Plates may be formed to the required shape either hot or cold and by any process that does not impair the quality of the material. Tests to demonstrate the suitability of the forming process may be requested at the discretion of the Surveyors.

2.4.3 Wherever possible, forming is to be performed by the application of steady continuous loading using a machine designed for that purpose. The use of hammering, in either the hot or cold condition should not be employed.

2.4.4 Material may be welded prior to forming or bending, provided that it can be demonstrated that the mechanical properties of the welds are not impaired by the forming operation. All welds subjected to bending are to be inspected on completion to ensure freedom from surface breaking defects.

2.4.5 Vessels manufactured from carbon or carbon manganese steel plates which have been hot formed or locally heated for forming are to be re-heat treated in accordance with the original supplied condition on completion of this operation. Vessels formed from plates supplied in the as-rolled condition shall be heat treated in accordance with the material manufacturer's recommendations.

2.4.6 Where these steels are supplied in the as-rolled, normalized or normalized rolled condition, if hot forming is carried out entirely at a temperature within the normalizing range, subsequent heat treatment will not be required.

2.4.7 For alloy steel vessels, where hot forming is employed the plates are to be heat treated on completion in accordance with the material manufacturer's recommendations.

2.4.8 Where plates are cold formed, subsequent heat treatment is to be performed where the internal radius is less than 10 times the plate thickness. For carbon and carbon-manganese steels this heat treatment may be a stress relief heat treatment.

2.4.9 In all cases where hot forming is employed, and for cold forming to an internal radius less than 10 times the thickness, the manufacturer is required to demonstrate that the forming process and subsequent heat treatments result in acceptable properties.

### 2.5 Fitting of shell plates and attachments

2.5.1 Careful consideration is to be given to the assembly sequence to be employed, in order to minimize overall shrinkage and distortion and to reduce the build up of residual stresses.

2.5.2 Excessive force is not to be used in fairing and closing the work. Where excessive root gaps exist between surfaces or edges to be joined, the corrective measures adopted are to be to the satisfaction of the Surveyors.

2.5.3 Provision is to be made for retaining correct alignment during welding operations.

2.5.4 In all cases where tack welds are used to retain plates or parts in position prior to welding they are to be made using approved welding procedures.

2.5.5 Where temporary bridge pieces or strong-backs are used they are to be of similar materials to the base materials and are to be welded in accordance with approved welding procedures.

2.5.6 Where welding to clad materials, any fit-up aids and tack welds are to be attached to the base materials and not to the cladding.

2.5.7 The location of welded joints are to be such as to avoid intersecting butt welds in the vessel shell plates. The attachment of nozzles and openings in the vessels are to be arranged to avoid main shell weld seams.

2.5.8 The surfaces of the plates at the longitudinal or circumferential seams are not to be out of alignment with each other, at any point, by more than 10 per cent of the plate thickness. In no case is the mis-alignment to exceed 3 mm for longitudinal seams, or 4 mm for circumferential seams.

2.5.9 Where a vessel is constructed of plates of different thicknesses (tube plate and wrapper plate), the plates are to be so arranged that their centrelines form a continuous circle.

2.5.10 For longitudinal seams, the thicker plate is to be equally chamfered inside and outside by machining over a circumferential distance not less than twice the difference in thickness, so that the plates are of equal thickness at the longitudinal weld seam. For the circumferential seam, the thickest plate is to be similarly prepared over the same distance longitudinally.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

### Section 2

2.5.11 For the circumferential seam, where the difference in the thickness is the same throughout the circumference, the thicker plate is to be reduced in thickness by machining to a taper for a distance not less than four times the offset, so that the two plates are of equal thickness at the weld joint. A parallel portion may be provided between the end of the taper and the weld edge preparation; alternatively, if so desired, the width of the weld may be included as part of the smooth taper to the thicker plate.

## 2.6 Welding during construction

2.6.1 Welding plant and equipment is to be suitable for the purpose intended and properly maintained, taking due cognisance of relevant safety precautions. Electrical meters are to be properly maintained and have current calibrations.

2.6.2 Welding consumables are to be suitable for the type of joint and grade of material to be welded and satisfactory storage and handling facilities are to be provided close to working areas.

2.6.3 Prior to use, welding consumables should be dried and/or baked in accordance with the consumable manufacturer's recommendations. The condition of welding consumables shall be subject to regular inspections.

2.6.4 All welders and welding operators are to be suitably skilled and qualified for the type of welding work to be undertaken.

2.6.5 Welding procedures are to be established for all welds joining pressure containing parts and for welds made directly onto pressure containing parts.

2.6.6 Welding should be performed wherever possible in covered workshops. Where this is not possible, provision is to be made in the welding area to give adequate protection from wind, rain and cold, etc.

2.6.7 Surfaces of all parts to be welded are to be clean, dry and free from rust, scale and grease. Where prefabrication primers are applied over areas which will be subsequently welded, they are to be approved for that application.

2.6.8 Preheat shall be applied, as specified in the approved welding procedure, for a distance of at least 75 mm from the joint preparation edges. The method of application and temperature control are to be such as to maintain the required level during welding and is to be to the satisfaction of the Surveyors.

2.6.9 When the ambient temperature is 0°C or less, or where moisture resides on the surfaces to be welded, due care should be taken to pre-warm and dry the weld joint.

2.6.10 The welding arc is to be struck on the parent metal which forms part of the weld joint or on previously deposited weld metal.

2.6.11 Tack welds made in the root of the weld joint are to be removed in the process of welding the seam.

2.6.12 Where the welding process used is slag forming (e.g. manual metal arc, submerged arc, etc.) each run of deposit is to be cleaned and free from slag before the next run is applied.

2.6.13 Wherever possible, full penetration welds are to be made from both sides of the joint. Prior to welding the second side, the weld root is to be cleaned, in accordance with the requirements of the approved welding procedure, to ensure freedom from defects. When air-arc gouging is used, care is to be taken to ensure that the ensuing groove is slag and oxide free and has a profile suitable for welding.

2.6.14 After welding has been stopped for any reason, care is to be taken in restarting to ensure that the previously deposited weld metal is thoroughly cleaned of slag and debris, and preheat has been re-established.

2.6.15 Where welding from one side only cannot be avoided, care is to be exercised to ensure the root gap is in accordance with the approved welding procedure and the root is properly fused.

2.6.16 Steel backing strips may be used for the circumferential seams of Class 2/1, Class 2/2 and Class 3 pressure vessels and are to be the same nominal composition as the plates to be welded.

2.6.17 Fillet welds are to be made to ensure proper fusion and penetration at the root of the fillet. At least two layers of weld metal are to be deposited at each weld affixing branch pipes, flanges and seatings.

2.6.18 Where attachment of lugs, brackets, branches, manhole frames, reinforcement plates and other members are to be made to the main pressure shell by welding, these shall be to the same standard as that required for the main vessel shell construction.

2.6.19 The attachment by welding of such fittings to the main pressure shell after post weld heat treatment is not permitted.

2.6.20 Completed welds shall be at least flush with the surface of the plates joined and have the shape and size specified in the approved drawings or specifications. Welds shall have an even contour and blend smoothly with the base materials.

2.6.21 The main weld seams and all welded attachments made to pressure containing parts are to be completed prior to post weld heat treatment. Tubes that have been expanded into headers or drums may be seal welded without further post weld heat treatment.

2.6.22 The finish of welds attaching pressure parts and non-pressure parts to the main pressure shell is to be such as to allow satisfactory examination of the welds. In the case of Class 1 and Class 2/1 pressure vessels, these welds are to be ground smooth, if necessary, to provide a suitable finish for examination.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Sections 2 &amp; 3

### 2.7 Tolerances for cylindrical shells

2.7.1 Measurements are to be made to the surface of the parent plate and not to a weld, fitting or other raised part.

2.7.2 In assessing the out-of-roundness of pressure vessels, the difference between the maximum and minimum internal diameters measured at one cross-section is not to exceed the amount given in Table 17.2.1.

**Table 17.2.1 Tolerances for cylindrical shells**


Nominal internal diameter of vessel in mm	Difference between maximum and minimum diameters	Maximum departure from designed form
$\leq 300$	1,0 per cent of internal diameter	1,2 mm
$> 300 \leq 460$		1,6 mm
$> 460 \leq 600$		2,4 mm
$> 600 \leq 900$		3,2 mm
$> 900 \leq 1200$		4,0 mm
$> 1220 \leq 1520$		4,8 mm
$> 1520 \leq 1900$		5,6 mm
$> 1900 \leq 2300$	19 mm	6,4 mm
$> 2300 \leq 2670$		7,2 mm
$> 2670 \leq 3950$		8,0 mm
$> 3950 \leq 4650$	19 mm 0,4 per cent of internal diameter	0,2 per cent of internal diameter
$> 4650$		

2.7.3 The profile measured on the inside or outside of the shell, by means of a gauge of the designed form of the shell, and having a chord length equal to one-quarter of the internal diameter of the vessel, is not to depart from the designed form by more than the amount given in Table 17.2.1. This amount corresponds to  $x$  in Fig. 17.2.1.

2.7.4 Shell sections are to be measured for out-of-roundness, either when laid flat on their sides or when set up on end. When the shell sections are checked while lying on their sides, each measurement for diameter is to be repeated after turning the shell through  $90^\circ$  about its longitudinal axis. The two measurements for each diameter are to be averaged, and the amount of out-of-roundness calculated from the average values so determined.

2.7.5 Where there is any local departure from circularity due to the presence of flats or peaks at welded seams, the departure from designed form shall not exceed that of Table 17.2.1.

2.7.6 The external circumference of the completed shell is not to depart from the calculated circumference (based upon nominal inside diameter and the actual plate thickness) by more than the amounts given in Table 17.2.2.



**Fig. 17.2.1 Tolerances for cylindrical shells**

**Table 17.2.2 Circumferential tolerances**

Outside diameter (nominal inside diameter plus twice actual plate thickness), in mm	Circumferential tolerance
300 to 600 inclusive	$\pm 5$ mm
Greater than 600	$\pm 0,25$ per cent



### Section 3

## Routine weld tests for pressure vessels

### 3.1 General requirements for routine weld tests

3.1.1 Routine or production weld tests are specified as a means of monitoring the quality of the welded joints and are required for pressure vessel Classes 1, 2/1 and 2/2.

3.1.2 Routine test plates are required during the manufacture of vessels and as part of the initial approval test programme for Class 1 vessel manufacturers, refer to MQPS 0-4.

3.1.3 Routine weld tests are not required for Class 3 pressure vessels unless the minimum design temperature is below minus  $10^\circ\text{C}$ . However, occasional check tests may be requested at the discretion of the Surveyors.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Section 3

3.1.4 Routine test plates are not required for circumferential seams of cylindrical pressure vessels. Spherical vessels are to have one test plate prepared having a welded joint which is a simulation of the circumferential seams.

3.1.5 In addition, routine weld tests may be requested by the Surveyor where there is reason to doubt the quality of workmanship.

### 3.2 Test plate requirements

3.2.1 Two test plates, each of sufficient dimensions to provide one complete set of specimens, are to be prepared for each vessel and are to be welded as a continuation and simulation of the longitudinal weld joint.

3.2.2 For Class 2/2 vessels, where a large number are made concurrently at the same works using the same welding procedure and the plate thicknesses do not vary by more than 5 mm, one test may be performed for each 37 m of longitudinal plus circumferential weld seam with the agreement of the Surveyor. In these cases, the thickness of the test plate is to be equal to the thickest shell plate used in the construction.

3.2.3 Where the vessel size or design results in a small number of longitudinal weld seams, with the agreement of the Surveyors, one test plate may be prepared for testing provided that the welding details are the same for each seam.

3.2.4 Test plate materials shall be of the same grade, thickness and supply condition and from the same cast as that of the vessel shell. The test plate shall be welded at the same time as the vessel weld to which it relates and is to be supported so that distortion during welding is minimized.

3.2.5 Where there is a requirement for several routine tests to be welded, welding is to be performed by different welders, wherever possible.

3.2.6 The test assembly may be detached from the vessel weld only after the Surveyor has performed a visual examination and has added his mark or stamp. Straightening of test weld prior to mechanical testing is not permitted.

3.2.7 Where the pressure vessel is required to be subjected to post weld heat treatment, the test weld shall be heat treated, after welding, in accordance with the same requirements. Subject to agreement with the Surveyor this may be performed separately from the vessel.

### 3.3 Inspection and testing

3.3.1 The test weld is to be subjected to the type of non-destructive examination and acceptance criteria as specified for the weld seam to which the test relates. Non-destructive examination shall be performed prior to removing specimens for mechanical testing, but after any post weld heat treatment.

3.3.2 The test weld is to be sectioned to remove the number and type of test specimens for mechanical testing as follows.

### 3.4 Mechanical testing requirements

3.4.1 The test plates are to be machined to provide the following test specimens:

- Tensile.
- Bend.
- Hardness.
- Impact, see Table 17.3.1.
- Macrograph and hardness survey of full weld section.
- Chemical analysis of deposited weld metal.

**Table 17.3.1 Impact test requirements**

Pressure vessel Class	Minimum design temperature	Plate material thickness <i>t</i> mm	Impact test temperature
Class 1	−10°C or above	All	5°C below the minimum design temperature or 20°C whichever is the lower
All Classes	Below −10°C	$t \leq 20$	5°C below the minimum design temperature
		$20 < t \leq 40$	10°C below the minimum design temperature
		$t > 40$	Subject to agreement

3.4.2 One set of specimens for mechanical testing is to be removed, as shown in Fig. 17.3.1 or Fig. 17.3.2 as appropriate for the Class of approval. Impact tests shall be removed and tested where required by Table 17.3.1.

3.4.3 **Longitudinal tensile test for weld metal.** An all weld metal longitudinal tensile test is required and, for thicknesses in excess of 20 mm where more than one welding process or type of consumable has been used to complete the joint, additional longitudinal tests are required from the respective area of the weld. This does not apply to the welding process or consumables used solely to deposit the root weld. Specimens shall be tested in accordance with the following requirements:


- The diameter and gauge length of the test specimen shall be in accordance with Fig. 11.2.1 in Chapter 11 of the Rules for Materials.
- For carbon steels, the tensile strength of the weld metal is to be not less than the minimum specified for the plate material and not more than 145 N/mm<sup>2</sup> above this value. The percentage elongation, *A*, is to be not less than that given by:

$$A = \frac{(980 - R)}{21,6}$$

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

### Section 3




**Fig. 17.3.1**

### Routine test plate – Test specimens for Class 1 and 2/1

1. All weld metal tensile test specimen.
2. Bend test specimens.
3. Tensile test for joints.
4. Macro-test specimen.
5. Charpy V-notch impact test specimens.  
(For all Class 1 pressure vessels and other Classes of pressure vessels where the minimum design temperature is below  $-10^{\circ}\text{C}$ ).

where  $R$  is the tensile strength, in  $\text{N/mm}^2$ , obtained from the all weld metal tensile test. In addition, this elongation is to be not less than 80 per cent of the minimum elongation specified for the plate.

- (c) For other materials, the tensile strength and percentage elongation shall not be less than that specified for the base materials welded.



**Fig. 17.3.2**

### Routine test plate – Test specimens for Class 2/2

1. Tensile test for joints.
2. Bend test specimens.
3. Macro-test specimen.
4. Charpy V-notch impact test specimens (if required by Table 17.3.1).

**Table 17.3.2 Bend test requirements**

Material grade	Former diameter
Up to Grade 460	$3t$
490 and 510	$4t$
13Cr Mo 45	$5t$
11Cr Mo 910	$5t$
Other materials	Subject to agreement
where $t$ is the thickness of the bend test specimen.	



# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Section 3

**3.4.4 Transverse tensile test for joint.** For the transverse tensile test, the weld reinforcement is to be removed, and shall meet the following requirements:

- (a) One reduced section tensile test specimen is to be cut transversely to the weld in accordance with the dimensions shown in Fig. 11.2.2 in Chapter 11 of the Rules for Materials.
- (b) In general, where the plate thickness exceeds 30 mm, or where the capacity of the tensile test machine prevents full thickness tests, each tensile test may be made up of several reduced section specimens, provided that the whole thickness of the weld is subjected to testing.
- (c) The tensile strength obtained is to be not less than the minimum specified tensile strength for the plate material, and the location of the fracture is to be reported.

**3.4.5 Transverse bend test.** The bend test specimens shall meet the following:

- (a) Two bend test specimens of rectangular section are to be cut from the test plate transversely to the weld, one bent with the outer surface of the weld in tension (face bend), and the other one with the inner surface in tension (root bend).
- (b) The specimens are to be in accordance with Ch 11,2.1.3 of the Rules for Materials.
- (c) Each specimen is to be mounted on roller supports with the centre of the weld midway between the supports. The plunger shall have the diameter shown in Table 17.3.2 based on the specimen thickness, *t*.
- (d) After bending through an angle of at least 120°, there is to be no crack or defect exceeding 1,5 mm measured across the specimen or 3 mm measured along the specimen. Premature failure at the edges of the specimen should not be cause for rejection, unless this is associated with a weld defect.

**3.4.6 Macro-specimen and hardness survey.** A macro examination specimen is to be removed from the test plate near the end where welding started. The specimen is to include the complete cross-section of the weld and the heat affected zone. The specimen is to be prepared and examined in accordance with the following:

- (a) The cross-section of the specimen is to be ground, polished and etched to clearly reveal the weld runs, and the heat affected zones.
- (b) The specimen shall show an even weld profile that blends smoothly with the base material and have satisfactory penetration and fusion, and an absence of significant inclusions or other defects.
- (c) Should there be any doubt as to the condition of the weld as shown by macro-etching, the area concerned is to be microscopically examined.
- (d) For carbon, carbon manganese and low alloy steels, a hardness survey is to be performed on the macro specimen using either a 5 kg or 10 kg load, testing is to include the base material, the weld and the heat affected zone. Hardness scans on the cross-section are to be performed in the cap weld areas within 2 mm of the weld surface. The maximum recorded hardness shall not exceed 350 Hv10.

**3.4.7 Charpy V-notch impact test.** Charpy V-notch impact test specimens are to be prepared for testing when required by Table 17.3.1. Tests are to be performed and satisfy the following requirements:

- (a) Each test is to consist of a set of three Charpy V-notch impact specimens and are to be removed with the vee notch perpendicular to the plate surface.
- (b) The dimensions and tolerances of the specimens are to be in accordance with Chapter 2 of the Rules for Materials.
- (c) Specimens are to be removed for testing from the weld centreline and the heat affected zone (fusion line and fusion line + 2 mm locations). Heat affected zone impact tests may be omitted where the minimum design temperature is above +20°C.
- (d) For thicknesses in excess of 20 mm, where more than one welding process or type of consumable has been used to complete the joint, impact tests are required from the respective area of the weld. This does not apply to the welding process or consumables used solely to deposit the root weld.
- (e) The average energy of a set of three specimens is not to be less than 27 Joules or the minimum specified for the base material, whichever is the higher. The minimum energy for each individual specimen is to meet the requirements of Ch 1,4.5.2 of the Rules for Materials.

**3.4.8 Nick break bend tests.** A nick bend or fracture test specimen is to be a minimum of 100 mm long measured along the weld direction and shall be tested in accordance with and meet the following requirements:

- (a) The specimen is to have a slot cut into each side along the centreline of the weld and perpendicular to the plate surface.
- (b) The specimen is to be bent along the weld centreline until fracture occurs and the fracture faces have been examined for defects. The weld shall be sound, with no evidence of cracking or lack of fusion or penetration and shall be substantially free from slag inclusions and porosity.

### 3.5 Failure to meet requirements

**3.5.1** If any test specimen fails to meet the requirements, additional specimens may be removed and tested in accordance with Ch 1,1.11 of the Rules for Materials.

**3.5.2** Where a routine weld test fails to meet requirements, the welds to which it relates will be considered as not having met the requirements. The reason for the failure is to be established and the manufacturer is to take such steps as necessary to either:

- (a) Remove the affected welds and have them re-welded to the Surveyor's satisfaction, or
- (b) demonstrate that the affected production welds have acceptable properties.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Sections 4 &amp; 5

### Section 4

#### Repairs to welds on fusion welded pressure vessels

##### 4.1 General

4.1.1 Where non-destructive examinations reveal unacceptable defects in the welded seams, they are to be repaired in accordance with the following:

- Major repairs shall not be carried out without the prior consent of the Surveyors.
- Where cracks have developed as a result of welding, these are to be reported to the Surveyors and the cause established prior to undertaking weld repair.
- Defects may be removed by grinding, chipping or thermal gouging. Where thermal gouging is used, the repair groove shall be subsequently ground to remove oxides and debris. In all cases, the groove shall have a profile suitable for welding.
- Prior to commencing repair welding, confirmation that the original defect has been removed is required by performing visual examination. This may be augmented by surface crack detection examination at the discretion of the Surveyors.
- Repair welding is to be performed using welding procedures agreed with the Surveyors.
- Where the pressure vessel requires post weld heat treatment in accordance with Section 5, this shall be performed after completion of the weld repairs.
- Weld repairs are to be shown by further non-destructive examinations to have removed the defect to the Surveyor's satisfaction.

##### 4.2 Re-repairs

4.2.1 In general, only two repair attempts are to be made of the same defect. Any subsequent repairs will be at the discretion of the Surveyors and may require the removal of the heat affected zone of the original repair.

### Section 5

#### Post weld heat treatment of pressure vessels

##### 5.1 General

5.1.1 Fusion welded pressure vessels, where indicated in Table 17.5.1 are to be heat treated on completion of the welding of the seams and of all attachments to the shell and ends, and before the hydraulic test is carried out.

5.1.2 Tubes which have been expanded into headers or drums may be seal welded without further post weld heat treatment.

**Table 17.5.1 Post weld heat treatment requirements**

Type of steel	Plate thickness above which post weld heat treatment (PWHT) is required	
	Steam raising plant	Other pressure vessels
Carbon and carbon/manganese steels without low temperature impact values	20 mm	30 mm
Carbon and carbon/manganese steels with low temperature impact values	20 mm	40 mm
1Cr 1/2Mo	All thicknesses	All thicknesses
2 1/4Cr 1Mo	All thicknesses	All thicknesses
1/2Cr 1/2Mo 1/4V	All thicknesses	All thicknesses
Other alloy steels	Subject to special consideration	

5.1.3 Where the weld connects parts of different thicknesses, the thickness to be used when applying the requirements for post weld heat treatment is to be either the thinner of the two plates for butt welded connections, or the thickness of the shell for connections to flanges, tubeplates and similar connections.

5.1.4 Parts are to be properly prepared for heat treatment, sufficient temporary supports are to be provided to prevent undue distortion or collapse of the structure and any machined faces are to be adequately protected against scaling.

5.1.5 Care is to be exercised to provide drilled holes in double reinforcing plates and other closed spaces prior to heat treatment.

##### 5.2 Basic requirements for heat treatment of fusion welded pressure vessels

5.2.1 Heat treatment is to be carried out in a properly constructed furnace which is efficiently maintained.

5.2.2 The heat treatment facilities shall be capable of controlling the temperature throughout the heat treatment cycle and adequate means of measuring and recording the vessel temperature are to be provided. To this end, thermo-couples are to be attached such that they are in contact with the vessel.

5.2.3 Unless stated otherwise, post weld heat treatment is to be carried out by means of slow, even heating from 300°C to the soak temperature, holding within the prescribed soaking temperature range for the time specified (usually one hour per 25 mm of weld thickness), followed by slow even cooling to 300°C.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Sections 5 &amp; 6

5.2.4 Recommended soaking temperatures and periods are given in Table 17.5.2 for different materials. Where other materials are used for pressure vessel construction, full details of the proposed heat treatment are to be submitted for consideration.

**Table 17.5.2 Post weld soak temperatures and times**

Material type	Soak temperature, °C (see Note)	Soak period
Carbon and carbon/manganese grades:	580–620°	1 hour per 25 mm of thickness, minimum of 1 hour
1Cr 1/2Mo	620–660°	1 hour per 25 mm of thickness, minimum of 1 hour
2 1/4Cr 1Mo	650–690°	1 hour per 25mm of thickness, minimum of 1 hour
1 1/2Cr 1/2Mo 1/4V	670–720°	1 hour per 25mm of thickness, minimum of 1 hour
<b>NOTE</b> For materials supplied in the tempered condition, the post weld soak temperature shall be lower than the material tempering temperature.		

5.2.5 Where pressure vessels are of such dimensions that the whole length cannot be accommodated in the furnace at one time, the pressure vessels may be heated in sections, provided that sufficient overlap is allowed to ensure the heat treatment of the entire length of the longitudinal seam.

5.2.6 Where it is proposed to adopt special methods of heat treatment, full particulars are to be submitted for consideration. In such cases it may be necessary to carry out tests to show the effect of the proposed heat treatment.

## Section 6 Welded pressure pipes

### 6.1 General

6.1.1 Fabrication of pipework is to be carried out in accordance with the requirements of this section unless other more stringent requirements have been specified.

6.1.2 Piping systems are to be constructed in accordance with approved plans and specifications.

6.1.3 Pipe welding may be performed using manual, semi-automatic or fully automatic electric arc welding processes. The use of oxy-acetylene welding will be limited to Class 3 pipework in carbon steel material that is not carrying flammable fluids and limited to butt joints in pipes not exceeding 100 mm diameter or 9,5 mm wall thickness.

6.1.4 Where pressure pipework is assembled and butt welded *in situ*, the piping is to be arranged well clear of adjacent structures to allow sufficient access for preheating, welding, heat treatment and examination of the joints.

### 6.2 Fit-up and alignment

6.2.1 Acceptable methods of flange attachment are illustrated in Fig. 12.2.2 in Chapter 12. If backing rings are used with flange type (a) then they are to fit closely to the bore of the pipe and should be removed after welding. The rings are to be made of the same material as the pipes. The use of flange types (b) and (c) with alloy steel pipes is limited to pipes up to and including 168,3 mm outside diameter.

6.2.2 Alignment of pipe butt welds shall be in accordance with Table 17.6.1. Where fusible inserts are used the alignment shall be within 0,5 mm in all cases.

**Table 17.6.1 Pipe alignment tolerances**

Pipe size	Maximum permitted mis-alignment
$D < 150\phi$ mm and $t \leq 6$ mm	1,0 mm or 25% of $t$ whichever is the lesser
$D < 300\phi$ mm and $t \leq 9,5$ mm	1,5 mm or 25% of $t$ whichever is the lesser
$D \geq 300$ and $t > 9,5$ mm	2,0 mm or 25% of $t$ whichever is the lesser
$D$ = pipe internal diameter $t$ = pipe wall thickness	

6.2.3 Where socket welded fittings are employed, they are to comply with the requirements of Ch 12,2.8. The diametrical clearance between the outside diameter of the pipe and the bore of the fitting is not to exceed 0,8 mm, and a gap of approximately 1,5 mm is to be provided between the end of the pipe and the bottom of the socket.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Section 6

### 6.3 Welding workmanship

6.3.1 Welding procedures are to be established for welding of pipework including attachment welds directly to pressure retaining parts and are to be qualified by testing on simulated joints.

6.3.2 Where the work requires a significant number of branch connections, tests may also be required to demonstrate that the type of joint(s) and welding techniques employed are capable of achieving the required quality.

6.3.3 Welding consumables and, where used, fusible root inserts, are to be suitable for the materials being joined.

6.3.4 For welding of carbon and low alloy steels, preheat is to be applied depending on the material grade, thickness and hydrogen grading of the welding consumable in accordance with Table 17.6.2 unless welding procedure testing indicates that higher levels are required.

**Table 17.6.2 Minimum preheat requirements**

Material grade	Thickness $t$ , in mm <sup>(4)</sup>	Minimum preheat temperature <sup>(1)</sup> , °C	
		Non-low H <sub>2</sub>	Low H <sub>2</sub> ( <sup>2</sup> )
Carbon and carbon/manganese grades: 320 and 360	$t \leq 10$	50	10
	$t \geq 20$	100	50
Carbon and carbon/manganese grades: 410, 460 and 490	$t \leq 10$	75	20
	$t \geq 20$	150	100
1Cr 1/2Mo	$t < 13$ $t \geq 13$	(3)	100 150
2 1/4Cr 1Mo	$t < 13$ $t \geq 13$	(3)	150 200
1/2Cr 1/2Mo 1/4V	$t < 13$ $t \geq 13$	(3)	150 200

NOTES

1.

For thicknesses up to 6 mm, the preheat levels specified may be reduced subject to satisfactory hardness testing during welding procedure qualification.  
In all cases where the ambient temperature is 0°C or below, preheat is required.

2.

Low hydrogen process or consumables are those which have been tested and have achieved a grading of H15 or better, see Chapter 11 of the Rules for Materials.

3.

Low hydrogen process is required for these materials.

4.

$t$  = the thickness of the thicker member.

6.3.5 Preheating is to be effected by a method which ensures uniformity of temperature at the joint. The method of heating and the means adopted for temperature control are to be to the satisfaction of the Surveyors.

6.3.6 All welding is to be performed in accordance with the approved welding procedures (see 6.3.1) by welders who are qualified for the materials, joint types and welding processes employed.

6.3.7 Welding without filler metal is generally not permitted for welding of duplex stainless steel materials.

6.3.8 All welds in high pressure and high temperature pipelines are to have a smooth surface finish and even contour; if necessary, they are to be made smooth by grinding.

6.3.9 Check tests of the quality of the welding are to be carried out periodically at the discretion of the Surveyors.

### 6.4 Heat treatment after bending of pipes

6.4.1 Heat treatment should be carried out in a suitable furnace provided with temperature recording equipment in accordance with 5.2.

6.4.2 Hot forming should generally be carried out within the normalizing temperature range. When carried out within this temperature range, no subsequent heat treatment is required for carbon and carbon/manganese steels. For alloy steels, 1Cr 1/2Mo, 2 1/4Cr 1Mo and 1/2Cr 1/2Mo 1/4V, a subsequent stress relieving heat treatment in accordance with Table 17.5.2 is required irrespective of material thickness.

6.4.3 When hot forming is performed outside the normalizing temperature range, a subsequent heat treatment in accordance with Table 17.6.3 is required.

**Table 17.6.3 Heat treatment after forming of pipes**

Type of steel	Heat treatment required
Carbon and carbon/manganese: Grades 320, 360, 410, 460 and 490	Normalize at 880 to 940°C
1Cr 1/2Mo	Normalize at 900 to 960°C, followed by Tempering at 640 to 720°C
2 1/4Cr 1Mo	Normalize at 900 to 960°C, followed by Tempering at 650 to 780°C
1/2Cr 1/2Mo 1/4V	Normalize at 930 to 980°C, followed by Tempering at 670 to 720°C
Other alloy steels	Subject to special consideration

6.4.4 After cold forming to a radius measured at the centreline of the pipe of less than four times the outside diameter, heat treatment in accordance with Table 17.6.3 is required.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Sections 6 &amp; 7

6.4.5 The heat treatments specified above shall be applied unless the pipe material manufacturer specifies or recommends other requirements.

6.4.6 Bending procedures and subsequent heat treatment for other alloy steels will be subject to special consideration.

### 6.5 Post weld heat treatment of pipe welds

6.5.1 Post weld heat treatment shall be carried out in accordance with the general requirements specified in 5.2 for pressure vessels.

6.5.2 Post weld heat treatment is to be performed on steel pipes and fabricated branch pieces on completion of welding where the material thickness exceeds that specified in Table 17.6.4.

**Table 17.6.4 Thickness limits for post weld heat treatment of pipe welds**

Type of steel	Requirements for heat treatment
Carbon and carbon/manganese: Grades 320, 360, 410, 460 and 490	Thicknesses exceeding 30 mm
1Cr 1/2Mo	Thicknesses exceeding 8 mm
2 <sup>1</sup> / <sub>4</sub> Cr 1Mo	All thicknesses
1/2Cr 1/2Mo 1/4V	All thicknesses
Other alloy steels	Subject to special consideration

6.5.3 Recommended soaking temperatures and periods for post weld heat treatment are given in Table 17.5.2.

6.5.4 Where oxy-acetylene welding has been used, due consideration should be given to the need for normalizing and tempering after such welding.

## Section 7

### Non-Destructive Examination

#### 7.1 General

7.1.1 Non-Destructive Examinations (NDE) of pressure vessel welds are to be carried out in accordance with a nationally recognized code or standard.

7.1.2 NDE should not be applied until an interval of at least 48 hours has elapsed since the completion of welding.

#### 7.2 NDE personnel

7.2.1 NDE Personnel are to be qualified to an appropriate level of a nationally recognized certification scheme.

7.2.2 Generally, operators subject to direct supervision are to be qualified to Level I, unsupervised personnel to Level II and more senior personnel to Level III.

7.2.3 Qualification schemes are to include assessments of practical ability for Levels I and II individuals; these examinations to be made on representative test pieces containing relevant defects.

#### 7.3 Extent of NDE

7.3.1 For Class 1 pressure vessels:

- All butt welded seams in drums, shells, headers and test plates, together with tubes or nozzles over 170 mm outside diameter are subject to 100 per cent volumetric and surface crack detection inspections.
- For circumferential butt welds in extruded connections, tubes, headers and other tubular parts of 170 mm outside diameter or less, at least 10 per cent of the total number of welds is to be subjected to volumetric examination and surface crack detection inspections.

7.3.2 For Class 2/1 pressure vessels, volumetric and surface crack detection inspections are to be applied at selected regions of each main seam. At least 10 per cent of each main seam is to be examined together with the full length of each welded test plate. When an unacceptable indication is detected, at least two additional check points in the seam are to be selected by the surveyor for examination using the same inspection method. If further unacceptable defects are found then either:

- the whole length of weld represented is to be cut out and re-welded and re-examined as if it was a new weld with the test plates being similarly treated; or
- the whole length of the weld represented is to re-examined using the same inspection methods.

7.3.3 Butt welds in Class 1 pipes of 75mm or more outside diameter are subject to 100 per cent volumetric and surface crack detection inspections. The extent and method of testing applied to butt welds in Class 1 pipes of less than 75 mm outside diameter is at the Surveyor's discretion.

7.3.4 For Class II pipes of 100 mm or more outside diameter, random volumetric examination is to be carried out on at least 10 per cent of butt welds. The extent and method of testing to be applied to fillet welds is at the Surveyor's discretion.

7.3.5 NDE is not required for Class II pipes less than 100 mm outside diameter.

7.3.6 Butt welds in furnaces, combustion chambers and other pressure parts for fired pressure vessels under external pressure are to be subject to spot volumetric examination, the minimum length of each check point being 300 mm.

# Requirements for Fusion Welding of Pressure Vessels and Piping

## Part 5, Chapter 17

Section 7

---

### 7.4 Procedures

7.4.1 Non-Destructive Examinations are to be made in accordance with a definitive written procedure prepared in accordance with a nationally recognized standard and endorsed by a Level III individual. As a minimum, the procedure will identify personnel qualification levels, NDE datum and identification system, extent of testing, methods to be applied with technique sheets, acceptance criteria and reporting requirements.

### 7.5 Method

7.5.1 Volumetric examinations may be made by radiography or, in the case of welds of nominal thickness 15 mm or above, by ultrasonic testing. The preferred method for surface crack detection in ferrous metals is magnetic particle inspection, and that for non-magnetic materials is liquid penetrant inspection.

### 7.6 Repairs

7.6.1 Unacceptable defects are to be repaired and re-examined using the NDE methods originally applied.

### 7.7 Evaluation and reports

7.7.1 The manufacturer shall be responsible for the review, interpretation, evaluation and acceptance of the results of NDE. Reports stating compliance or otherwise with the criteria established in the inspection procedure are to be issued. Reports are to include the following information where appropriate:

- (a) date of inspection;
  - (b) names, qualifications and signatures of operator and supervisor;
  - (c) component identification;
  - (d) location and extent of testing;
  - (e) heat treatment status;
  - (f) weld type, procedure and configuration;
  - (g) surface condition;
  - (h) inspection procedure reference;
  - (i) equipment used;
  - (k) results showing size, position and nature of any defects repaired; and
  - (l) statement of final acceptability to established criteria.
-

# Integrated Propulsion Systems

# Part 5, Chapter 18

Sections 1 & 2

## Section

- 1 **General requirements**
- 2 **Machinery arrangements**
- 3 **Control arrangements**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 This Chapter applies to both cargo ships and passenger ships and is in addition to other relevant Chapters of the Rules.

1.1.2 The Rules contained in this Chapter cover machinery arrangements and control systems necessary for operating essential machinery from a (centralized) control station on the bridge under normal sea-going and manoeuvring conditions, but do not signify that the machinery space may be operated unattended.

1.1.3 In general, ships complying with the requirements of this Chapter will be eligible for the machinery class notation **IP**, see Pt 1, Ch 2,2.4.

1.1.4 The details of control systems will vary with the type of machinery being controlled, and special consideration will be given to each case.

### 1.2 Plans

1.2.1 **Control systems.** Where control systems are applied to essential machinery or equipment the following plans are to be submitted in triplicate:

- Details of operating medium, i.e. pneumatic, hydraulic or electric including standby sources of power.
- Description of operation with explanatory diagrams.
- Line diagrams of control circuits.
- List of monitored points.
- List of control points.
- List of alarm points.
- Test schedule including test facilities provided.

1.2.2 Plans for the control systems of the following machinery are to be submitted:

- Main propelling machinery, including all auxiliaries essential for propulsion.
- Controllable pitch propellers.
- Electric generating plant.
- Evaporating and distilling systems for use with main steam machinery.
- Steam raising plant for essential services.

1.2.3 **Alarm systems.** Details of the overall alarm system linking the machinery space control station with the bridge control station are to be submitted.

1.2.4 **Control stations.** Details of bridge and machinery space control stations are to be submitted, e.g. control panels and consoles.

1.2.5 **Machinery configurations.** Plans showing the general arrangement of the machinery space, together with the layout and configuration of the main propulsion and essential machinery, are to be submitted.

## ■ Section 2 Machinery arrangements

### 2.1 Main propulsion machinery

2.1.1 The main propulsion machinery may be oil engines, turbines or electric motors but the configuration of the propulsion system and its relationship with other essential equipment is to comply with the remaining requirements of this Section.

2.1.2 The main propulsion machinery is to drive one of the generators required by 2.2.2. This generator is to be capable of supplying the essential electrical load under all normal sea-going and manoeuvring conditions.

2.1.3 Standby machinery is to be provided capable of being readily connected to the main propulsion system so as to provide emergency propulsion. This standby machinery is to be capable of connection so as to provide an alternative drive to the generator required in 2.1.2. It need not provide power to both systems simultaneously, see *also* 2.2.2.

### 2.2 Supply of electric power and essential services

2.2.1 Continuity of electrical power supply and essential services are to be ensured under all normal sea-going and manoeuvring conditions without manual intervention in the machinery space. Methods by which this may be achieved include automatic start-up of generating sets and essential pumps or manual start-up of these services from the bridge.

2.2.2 Generating sets and converting sets are to be sufficient to ensure the operation of services essential for the propulsion and safety of the ship even when one generating set or converting set is out of service.

### 2.3 Controllable pitch propellers

2.3.1 For propulsion systems with controllable pitch propellers a standby or alternative power source for the actuating medium for controlling the pitch of the propeller blades is to be provided.

# Integrated Propulsion Systems

# Part 5, Chapter 18

Section 3

## Section 3 Control arrangements

### 3.1 Bridge control

3.1.1 Means are to be provided to ensure satisfactory control of propulsion from the bridge in both the ahead and astern directions when operating on either the main or standby engine(s).

3.1.2 Instrumentation to indicate the following is to be fitted on the bridge and at any other station from which the propulsion machinery may be controlled:

- (a) Propeller speed.
- (b) Direction of rotation of the propeller for a fixed pitch propeller.
- (c) Pitch position for a controllable pitch propeller.
- (d) Direction and magnitude of thrust.
- (e) Clutch position, where applicable.

3.1.3 An alarm is to operate in the event of a failure of the power supply to the bridge control system.

3.1.4 Means, independent of the bridge control system, are to be provided on the bridge to enable the watchkeeping officer to stop the main propulsion machinery in an emergency.

### 3.2 Alarm system

3.2.1 An alarm system is to be provided to indicate faults in essential machinery and control systems in accordance with this Chapter.

3.2.2 Machinery faults are to be indicated at the control stations on the bridge and in the machinery space.

3.2.3 In the event of a machinery fault occurring, the alarm system is to be such that the watchkeeping officer on the bridge is made aware of the following:

- (a) A machinery fault has occurred.
- (b) The machinery fault is being attended to, and
- (c) The machinery fault has been rectified. (Alternative means of communication between the bridge control station and the machinery control station may be used for this function.)

3.2.4 The alarm system should be designed with self-monitoring properties. As far as practicable, any fault in the alarm system should cause it to fail to the alarm condition.

3.2.5 The alarm system should be capable of being tested during normal machinery operation.

3.2.6 Failure of the power supply to the alarm system is to be indicated as a separate fault alarm.

3.2.7 Alarm indication is to be both audible and visual. If arrangements are made to silence audible alarms they are not to extinguish visual alarms.

3.2.8 The acceptance of an alarm on the bridge is not to silence the audible alarm in the machinery space.

3.2.9 Machinery alarms should be distinguishable from other audible alarms, e.g. fire, carbon dioxide.

3.2.10 Acknowledgement of visual alarms is to be clearly shown.

3.2.11 If the audible alarm has been silenced and a second fault occurs before the first has been rectified, the audible alarm is again to operate. To assist in the detection of transient faults which are subsequently self-correcting, fleeting alarms should lock-in until accepted.

3.2.12 Arrangements should be made to enable alarm lights on the bridge to be dimmed as required.

### 3.3 Communication

3.3.1 Two means of communication are to be provided between the bridge and the control station in the machinery space. One of these means may be the bridge control system; the other is to be independent of the main electrical power supply.

3.3.2 The bridge, machinery space control station and any other control position from which the propulsion machinery can be controlled are to be fitted with means to indicate which station is in command.

3.3.3 Change-over between control stations is to be possible under all normal sea-going and manoeuvring conditions without affecting the speed or direction of propulsion. This changeover may be effected only with the acceptance of the station taking control.

### 3.4 Engine starting safeguards

3.4.1 Where it is possible to start a main propulsion or auxiliary oil engine from the bridge, an indication that sufficient starting air pressure is available is to be provided on the bridge.

3.4.2 The number of automatic consecutive attempts which fail to produce a start is to be limited to safeguard sufficient starting air pressure, or, in the case of electric starting, a sufficient charge level in the batteries.

3.4.3 An alarm is to be provided for low starting air pressure, set at a limit which will still permit engine starting operations.

3.4.4 Where propulsion or auxiliary engines are started from the bridge, interlocks are to be provided to prevent starting of the engine under conditions which could hazard the machinery. These are to include 'turning gear engaged', 'low lubricating oil pressure' and 'shaft brake engaged'.

### 3.5 Operational safeguards

3.5.1 Means are to be provided to prevent the machinery and shafting being subjected to excessive torque or other detrimental mechanical and thermal overloads.



# Integrated Propulsion Systems

# Part 5, Chapter 18

Section 3

3.5.2 Prolonged running in a restricted speed range is to be prevented automatically or, alternatively, an indication of restricted speed ranges is to be provided at each control station.

3.5.3 For ships propelled by steam turbines the risk of thermal distortion of the turbines is to be prevented by automatic steam spinning when the shaft is stopped in the manoeuvring mode. An audible and visual alarm is to operate on the bridge and in the machinery space when the shaft has been stopped for two minutes.

3.5.4 In the case of lubricating oil systems for main propulsion and standby engine(s), the engine(s) is to be stopped automatically on failure of the lubricating oil supply. The circuit and sensor employed for this automatic shutdown are to be additional to the alarm circuit and sensor required by Ch 14.8. Where means are provided to over-ride the automatic shutdown required by this paragraph, the arrangements are to be such as to preclude inadvertent operation. Visual indication of operation of the over-ride is to be fitted.

3.5.5 In the case of oil engines, oil mist monitoring is to be provided for crankcase protection where arrangements are fitted to over-ride the automatic stop for failure of the lubricating oil supply.

3.5.6 Boilers with automatic controls which under normal operating conditions do not require any manual intervention by the operators are to be provided with safety arrangements which automatically shut-off the oil fuel to all the burners in the event of either low water level or combustion air failure. Oil fuel is to be shut-off automatically to any burner in the event of flame failure.

3.5.7 Arrangements are to be provided to automatically stop propulsion gas turbines for the following fault conditions:

- (a) Overspeed, see Ch 4.4.
- (b) High exhaust temperature, see Ch 4.3.
- (c) Flame failure, or
- (d) Excessive vibration.

3.5.8 Where standby pumps are arranged to start automatically in the event of low discharge pressure from the working pump an alarm is to be given to indicate when the standby pump has started.

## 3.6 Automatic control of essential services

3.6.1 All control systems for essential services are to be stable throughout the operating range of the main propulsion machinery.

3.6.2 The temperature of the following is to be automatically controlled within normal operating limits:

### Oil engines:

- (a) Lubricating oil to the main engine and/or auxiliary engines.
- (b) Oil fuel – temperature or viscosity.
- (c) Piston coolant, where applicable.
- (d) Cylinder coolant main and auxiliary engines, where applicable.
- (e) Fuel valve coolant, where applicable.

### Steam plant:

- (a) Lubricating oil to main engine and/or auxiliary engines.
- (b) Oil fuel to burners – temperature or viscosity.
- (c) Superheated steam.
- (d) External de-superheated steam.

### Gas turbines:

- (a) Lubricating oil to main engine and auxiliary engines.
- (b) Oil fuel – temperature or viscosity.
- (c) Exhaust gas.

3.6.3 The pressure of the following is to be automatically controlled within normal operating limits:

### Steam plant:

- (a) Superheated steam.
- (b) Oil fuel.
- (c) External de-superheated steam system(s).
- (d) Gland steam.
- (e) Reduced steam ranges.

3.6.4 The level of the following is to be automatically controlled within normal operating limits:

### Steam plant:

- (a) Boiler drum level.
- (b) De-aerator level.
- (c) Condenser level.

3.6.5 Boilers essential for the propulsion of the vessel are to be provided with an automatic combustion control system.

## 3.7 Local control

3.7.1 The arrangements are to be such that essential machinery can be operated with the system of bridge control or any automatic controls out of action. Alternatively, the control systems should have sufficient redundancy so that failure of the control equipment in use does not render essential machinery inoperative.



# Steering Gear

## Part 5, Chapter 19

Section 1

### Section

- 1 **General**
- 2 **Performance**
- 3 **Construction and design**
- 4 **Steering control systems**
- 5 **Electric power circuits, electric control circuits, monitoring and alarms**
- 6 **Emergency power**
- 7 **Testing and trials**
- 8 **Additional requirements**
- 9 **'Guidelines' for the acceptance of non-duplicated rudder actuators for tankers, chemical tankers and gas carriers of 10 000 tons gross and upwards but of less than 100 000 tons deadweight**

### ■ Section 1 General

#### 1.1 Application

1.1.1 The requirements of this Chapter apply to the design and construction of steering gear.

1.1.2 Whilst the requirements satisfy the relevant regulations of the *International Convention for the Safety of Life at Sea 1974* as amended, and the IMO Protocol of 1978, attention should be given to any relevant statutory requirements of the National Authority of the country in which the ship is to be registered.

1.1.3 Consideration will be given to other cases, or to arrangements which are equivalent to those required by the Rules.

#### 1.2 Definitions

1.2.1 **Steering gear control system** means the equipment by which orders are transmitted from the navigating bridge to the steering gear power units. Steering gear control systems comprise transmitters, receivers, hydraulic control pumps and their associated motors, motor controllers, piping and cables.

1.2.2 **Main steering gear** means the machinery, rudder actuator(s), the steering gear power units, if any, and ancillary equipment and the means of applying torque to the rudder stock (e.g. tiller or quadrant) necessary for effecting movement of the rudder for the purpose of steering the ship under normal service conditions.

1.2.3 **Steering gear power unit** means:

- (a) in the case of electric steering gear, an electric motor and its associated electrical equipment;
- (b) in the case of electrohydraulic steering gear, an electric motor and its associated electrical equipment and connected pump;
- (c) in the case of other hydraulic steering gear, a driving engine and connected pump.

1.2.4 **Auxiliary steering gear** means the equipment other than any part of the main steering gear necessary to steer the ship in the event of failure of the main steering gear but not including the tiller, quadrant or components serving the same purpose.

1.2.5 **Power actuating system** means the hydraulic equipment provided for supplying power to turn the rudder stock, comprising a steering gear power unit or units, together with the associated pipes and fittings, and a rudder actuator. The power actuating systems may share common mechanical components, i.e. tiller quadrant and rudder stock, or components serving the same purpose.

1.2.6 **Maximum ahead service speed** means the maximum service speed which the ship is designed to maintain, at the summer load waterline at maximum propeller RPM and corresponding engine MCR.

1.2.7 **Rudder actuator** means the components which converts directly hydraulic pressure into mechanical action to move the rudder.

1.2.8 **Maximum working pressure** means the maximum expected pressure in the system when the steering gear is operated to comply with 2.1.2(b).

#### 1.3 General

1.3.1 The steering gear is to be secured to the seating by fitted bolts, and suitable chocking arrangements are to be provided. The seating is to be of substantial construction.

1.3.2 The steering gear compartment is to be:

- (a) readily accessible and, as far as practicable, separated from machinery spaces; and
- (b) Provided with suitable arrangements to ensure working access to steering gear machinery and controls. These arrangements are to include handrails and gratings or other non-slip surfaces to ensure suitable working conditions in the event of hydraulic fluid leakage.

#### 1.4 Plans

1.4.1 Before starting construction, the steering gear machinery plans, specifications and calculations are to be submitted. The plans are to give:

- (a) Details of scantlings and materials of all load bearing and torque transmitting components and hydraulic pressure retaining parts together with proposed rated torque and all relief valve settings.
- (b) Schematic of the hydraulic system(s), together with pipe material, relief valves and working pressures.
- (c) Details of control and electrical aspects.

# Steering Gear

## Part 5, Chapter 19

Section 1

### 1.5 Materials

1.5.1 All the steering gear components and the rudder stock are to be of sound reliable construction to the Surveyor's satisfaction.

1.5.2 All components transmitting mechanical forces to the rudder stock are to be tested according to the requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials).

1.5.3 Ram cylinders; pressure housings of rotary vane type actuators, hydraulic power piping, valves, flanges and fittings; and all steering gear components transmitting mechanical forces to the rudder stock (such as tillers, quadrants, or similar components) are to be of steel or other approved ductile material, duly tested in accordance with the requirements of the Rules for Materials. In general, such material is to have an elongation of not less than 12 per cent nor a tensile strength in excess of 650 N/mm<sup>2</sup>. Special consideration will be given to the acceptance of grey cast iron for valve bodies and redundant parts with low stress levels.

1.5.4 Where appropriate, consideration will be given to the acceptance of non-ferrous material.

### 1.6 Rudder, rudder stock, tiller and quadrant

1.6.1 For the requirements of rudder and rudder stock, see Pt 3, Ch 13,2.

1.6.2 For the requirements of tillers and quadrants including the tiller to stock connection, see Table 19.1.1.

1.6.3 In bow rudders having a vertical locking pin operated from the deck above, positive means are to be provided to ensure that the pin can be lowered only when the rudder is exactly central. In addition, an indicator is to be fitted at the deck to show when the rudder is exactly central.

1.6.4 The factor of safety against slippage,  $S$  (i.e. for torque transmission by friction) is generally based on

$$S = \frac{\text{the torque transmissible by friction}}{M}$$

where

$M$  is the maximum torque at the relief valve pressure which is generally equal to the design torque as specified by the steering gear manufacturer.

1.6.5 For conical sections,  $S$  is based on the following equation:

$$S = \frac{\mu A \sigma_r}{\sqrt{(W + A \sigma_r \theta)^2 + Q^2}}$$

where

$A$  = interfacial surface area, in mm<sup>2</sup>

$W$  = weight of rudder and stock, if applicable, when tending to separate the fit, in N

$Q$  = shear force =  $\frac{2M}{d_m}$  in N

where

$d_m$  in mm is the mean contact diameter of tiller/stock interface and  $M$  in Nmm is defined in 1.6.4

$\theta$  = cone taper half angle in radians (e.g. for cone taper 1:10,  $\theta = 0,05$ )

$\mu$  = coefficient of friction

$\sigma_r$  = radial interfacial pressure or grip stress, in N/mm<sup>2</sup>.

## Steering Gear

## Part 5, Chapter 19

Section 1

Table 19.1.1 Connection of tiller to stock

Item	Requirements
(1) Dry fit – tiller to stock, see also 1.6.4 and 1.6.5	(a) For keyed connection, factor of safety against slippage, $S = 1,0$ The maximum stress in the fillet radius of the tiller keyway should not exceed the yield stress For conical sections, the cone taper should be $\leq 1:10$ (b) For keyless connection, factor of safety against slippage, $S = 2,0$ The maximum equivalent von Mises stress should not exceed the yield stress For conical sections, the cone taper should be $\leq 1:15$ (c) Coefficient of friction (maximum) = 0,17 (d) Grip stress not to be less than 20 N/mm <sup>2</sup>
(2) Hydraulic fit – tiller to stock, see also 1.6.4 and 1.6.5	(a) For keyed connection, factor of safety against slippage, $S = 1,0$ The maximum stress in the fillet radius of the tiller keyway should not exceed the yield stress For conical sections, the cone taper should be $\leq 1:10$ (b) For keyless connection, factor of safety against slippage, $S = 2,0$ The maximum equivalent von Mises stress should not exceed the yield stress For conical sections, the cone taper should be $\leq 1:15$ (c) Coefficient of friction (maximum) = 0,14 (d) Grip stress not to be less than 20 N/mm <sup>2</sup>
(3) Ring locking assemblies fit – tiller to stock, see also 1.6.3	(a) Factor of safety against slippage, $S = 2,0$ The maximum equivalent von Mises stress should not exceed the yield stress (b) Coefficient of friction = 0,12 (c) Grip stress not to be less than 20 N/mm <sup>2</sup>
(4) Bolted tiller and quadrant (this arrangement could be accepted provided the proposed rudder stock diameter in way of tiller does not exceed 350 mm diameter), see symbols	Shim to be fitted between two halves before machining to take rudder stock, then removed prior to fitting Minimum thickness of shim, For 4 connecting bolts: $t_s = 0,0014 \delta_t$ mm For 6 connecting bolts: $t_s = 0,0012 \delta_t$ mm Key(s) to be fitted $\delta_{tb} = \frac{0,60 \delta_{su}}{\sqrt{n_{tb}}} \text{ mm}$ A predetermined setting-up load equivalent to a stress of approximately 0,7 of the yield strength of the bolt material should be applied to each bolt on assembly. A lower stress may be accepted provided that two keys, complying with item (5), are fitted. Distance from centre of stock to centre of bolts should generally be equal to $\delta_t \left(1,0 + \frac{0,30}{\sqrt{n_{tb}}}\right)$ mm Thickness of flange on each half of the bolted tiller $\geq \frac{0,66 \delta_t}{\sqrt{n_{tb}}}$ mm
(5) Key/keyway, see symbols	Effective sectional area of key in shear $\geq 0,25 \delta_t^2$ mm <sup>2</sup> Key thickness $\geq 0,17 \delta_t$ mm Keyway is to extend over full depth of tiller and is to have a rounded end. Keyway root fillets are to be provided with suitable radii to avoid high local stress
(6) Section modulus – tiller arm (at any point within its length about vertical axis), see symbols	To be not less than the greater of: (a) $Z_{TA} = \frac{0,15 \delta_t^3 (b_T - b_s)}{1000 b_T}$ cm <sup>3</sup> (b) $Z_{TA} = \frac{0,06 \delta_t^3 (b_T - 0,9 \delta_t)}{1000 b_T}$ cm <sup>3</sup> If more than one arm fitted, combined modulus is to be not less than the greater of (a) or (b) For solid tillers, the breadth to depth ratio is not to exceed 2
(7) Boss, see symbols	Depth of boss $\geq \delta_t$ Thickness of boss in way of tiller $\geq 0,4 \delta_t$
Symbols	
$b_s$ = distance between the section of the tiller arm under consideration and the centre of the rudder stock, in mm NOTE: $b_T$ and $b_s$ are to be measured with zero rudder angle $b_T$ = distance from the point of application of the load on the tiller to the centre of the rudder stock, in mm $n_{tb}$ = number of bolts in the connection flanges, but generally not to be taken greater than six	$t_s$ = thickness of shim for machining bolted tillers and quadrants, in mm $Z_{TA}$ = section modulus of tiller arm, in cm <sup>3</sup> $\delta_t$ = Rule rudderstock diameter in way of tiller, see Pt 3, Ch 13 $\delta_{tb}$ = diameter of bolts securing bolted tillers and quadrants, in mm

# Steering Gear

## Part 5, Chapter 19

Sections 2 &amp; 3

### ■ Section 2 Performance

#### 2.1 General

2.1.1 Unless the main steering gear comprises two or more identical power units, in accordance with 2.1.4 or 8.1.1, every ship is to be provided with a main steering gear and an auxiliary steering gear in accordance with the requirements of the Rules. The main steering gear and the auxiliary steering gear is to be so arranged that the failure of one of them will not render the other one inoperative.

2.1.2 The main steering gear and rudder stock is to be:

- (a) Of adequate strength and capable of steering the ship at maximum ahead service speed which shall be demonstrated in accordance with 7.2;
- (b) Capable of putting the rudder over from 35° on one side to 35° on the other side with the ship at its deepest sea-going draught and running ahead at maximum ahead service speed and under the same conditions, from 35° on either side to 30° on the other side in not more than 28 seconds.
- (c) Operated by power where necessary to meet the requirements of (b) and in any case when the Rules excluding strengthening for navigation in ice, require a rudder stock over 120 mm diameter in way of the tiller; and
- (d) So designed that they will not be damaged at maximum astern speed; however, this design requirement need not be proved by trials at maximum astern speed and maximum rudder angle.

2.1.3 The auxiliary steering gear is to be:

- (a) Of adequate strength and capable of steering the ship at navigable speed and of being brought speedily into action in an emergency;
- (b) Capable of putting the rudder over from 15° on one side to 15° on the other side in not more than 60 seconds with the ship at its deepest sea-going draught and running ahead at one half of the maximum ahead service speed or 7 knots, whichever is the greater; and
- (c) Operated by power where necessary to meet the requirements of (b) and in any case when the Rules, excluding strengthening for navigation in ice, require a rudder stock over 230 mm diameter in way of the tiller.

2.1.4 Where the main steering gear comprises two or more identical power units, an auxiliary steering gear need not be fitted, provided that:

- (a) In a passenger ship, the main steering gear is capable of operating the rudder as required by 2.1.2(b) while any one of the power units is out of operation;
- (b) In a cargo ship, the main steering gear is capable of operating the rudder as required by 2.1.2(b) while operating with all power units;
- (c) The main steering gear is arranged so that after a single failure in its piping system or in one of the power units the defect can be isolated so that steering capability can be maintained or speedily regained.

2.1.5 Main and auxiliary steering gear power units are to be:

- (a) Arranged to re-start automatically when power is restored after power failure;
- (b) Capable of being brought into operation from a position on the navigating bridge. In the event of a power failure to any one of the steering gear power units, an audible and visual alarm is to be given on the navigating bridge;
- (c) Arranged so that transfer between units can be readily effected.

2.1.6 Where the steering gear is so arranged that more than one power or control system can be simultaneously operated, the risk of hydraulic locking caused by a single failure is to be considered.

2.1.7 A means of communication is to be provided between the navigating bridge and the steering gear compartment.

2.1.8 Steering gear, other than of the hydraulic type, will be accepted provided the standards are considered equivalent to the requirements of this Section.

2.1.9 Manually operated gears are only acceptable when the operation does not require an effort exceeding 16 kg under normal conditions.

#### 2.2 Rudder angle limiters

2.2.1 Power-operated steering gears are to be provided with positive arrangements, such as limit switches, for stopping the gear before the rudder stops are reached. These arrangements are to be synchronized with the gear itself and not with the steering gear control.

### ■ Section 3 Construction and design

#### 3.1 General

3.1.1 Rudder actuators other than those covered by 8.3 and the 'Guidelines' are to be designed in accordance with the relevant requirements of Chapter 11 for Class I pressure vessels (notwithstanding any exemptions for hydraulic cylinders).

3.1.2 Accumulators, if fitted, are to comply with the relevant requirements of Chapter 11.

3.1.3 The welding details and welding procedures are to be approved. All welded joints within the pressure boundary of a rudder actuator or connecting parts transmitting mechanical loads are to be of full penetration type or of equivalent strength.

3.1.4 The construction is to be such as to minimize local concentrations of stress.

# Steering Gear

# Part 5, Chapter 19

Section 3

3.1.5 The design pressure for calculations to determine the scantlings of piping and other steering gear components subjected to internal hydraulic pressure shall be at least 1,25 times the maximum working pressure to be expected under the operational conditions specified in 2.1.2(b) taking into account any pressure which may exist in the low pressure side of the system. Fatigue criteria may be applied for the design of piping and components, taking into account pulsating pressures due to dynamic loads, see Section 9.

3.1.6 For the rudder actuator, the permissible primary general membrane stress is not to exceed the lower of the following values:

$$\frac{\sigma_B}{A} \text{ or } \frac{\sigma_Y}{B}$$

where

$\sigma_B$  = specified minimum tensile strength of material at ambient temperature

$\sigma_Y$  = specified minimum yield stress or 0,2 per cent proof stress of the material, at ambient temperature

A and B are given by the following Table:

	<i>Wrought steel</i>	<i>Cast steel</i>	<i>Nodular cast iron</i>
A	3,5	4	5
B	1,7	2	3

## 3.2 Components

3.2.1 Special consideration is to be given to the suitability of any essential component which is not duplicated. Any such essential component shall, where appropriate, utilize anti-friction bearings such as ball bearings, roller bearings or sleeve bearings which shall be permanently lubricated or provided with lubrication fittings.

3.2.2 All steering gear components transmitting mechanical forces to the rudder stock, which are not protected against overload by structural rudder stops or mechanical buffers, are to have a strength at least equivalent to that of the rudder stock in way of the tiller.

3.2.3 Actuator oil seals between non-moving parts, forming part of the external pressure boundary, are to be of the metal upon metal type or of an equivalent type.

3.2.4 Actuator oil seals between moving parts, forming part of the external pressure boundary, are to be duplicated, so that the failure of one seal does not render the actuator inoperative. Alternative arrangements providing equivalent protection against leakage may be accepted.

3.2.5 Piping, joints, valves, flanges and other fittings are to comply within the requirements of Chapter 12 for Class I piping systems components. The design pressure is to be in accordance with 3.1.5.

3.2.6 Hydraulic power operated steering gear are to be provided with the following:

- Arrangements to maintain the cleanliness of the hydraulic fluid taking into consideration the type and design of the hydraulic system;

- A fixed storage tank having sufficient capacity to recharge at least one power actuating system including the reservoir, where the main steering gear is required to be power operated. The storage tank is to be permanently connected by piping in such a manner that the hydraulic systems can be readily recharged from a position within the steering gear compartment and provided with a contents gauge.

## 3.3 Valve and relief valve arrangements

3.3.1 For vessels with non-duplicated actuators, isolating valves are to be fitted at the connection of pipes to the actuator, and are to be directly fitted on the actuator.

3.3.2 Arrangements for bleeding air from the hydraulic system are to be provided, where necessary.

3.3.3 Relief valves are to be fitted to any part of the hydraulic system which can be isolated and in which pressure can be generated from the power source or from external forces. The settings of the relief valves is not to exceed the design pressure. The valves are to be of adequate size and so arranged as to avoid an undue rise in pressure above the design pressure.

3.3.4 Relief valves for protecting any part of the hydraulic system which can be isolated, as required by 3.3.3 are to comply with the following:

- The setting pressure is not to be less than 1,25 times the maximum working pressure.
- the minimum discharge capacity of the relief valve(s) is not to be less than 110 per cent of the total capacity of the pumps which can deliver through it (them). Under such conditions the rise in pressure is not to exceed 10 per cent of the setting pressure. In this regard, due consideration is to be given to extreme foreseen ambient conditions in respect of oil viscosity.

## 3.4 Flexible hoses

3.4.1 Hose assemblies approved by Lloyd's Register (hereinafter referred to as 'LR') may be installed between two points where flexibility is required but are not to be subjected to torsional deflection (twisting) under normal operating conditions. In general, the hose should be limited to the length necessary to provide for flexibility and for proper operation of machinery, see also Ch 12,7.

3.4.2 Hoses should be high pressure hydraulic hoses according to recognized standards and suitable for the fluids, pressures, temperatures and ambient conditions in question.

3.4.3 Burst pressure of hoses is to be not less than four times the design pressure.

## ■ Section 4 Steering control systems

### 4.1 General

4.1.1 Steering gear control is to be provided:

- (a) For the main steering gear, both on the navigating bridge and in the steering gear compartment;
- (b) Where the main steering gear is arranged according to 2.1.4, by two independent control systems, both operable from the navigating bridge. This does not require duplication of the steering wheel or steering lever. Where the control system consists of a hydraulic telemotor, a second independent system need not be fitted, except in a tanker, chemical tanker or gas carrier of 10 000 gross tonnage and upwards;
- (c) For the auxiliary steering gear, in the steering gear compartment and, if power operated, it shall also be operable from the navigating bridge and is to be independent of the control system for the main steering gear.
- (d) Where the steering gear is so arranged that more than one control system can be simultaneously operated, the risk of hydraulic locking caused by single failure is to be considered.

4.1.2 Any main and auxiliary steering gear control system operable from the navigating bridge is to comply with the following:

- (a) Means are to be provided in the steering gear compartment for disconnecting any control system operable from the navigating bridge from the steering gear it serves;
- (b) The system is to be capable of being brought into operation from a position on the navigating bridge.

4.1.3 The angular position of the rudder shall:

- (a) If the main steering gear is power-operated, be indicated on the navigating bridge. The rudder angle indication is to be independent of the steering gear control system;
- (b) Be recognizable in the steering gear compartment.

4.1.4 Appropriate operating instructions with a block diagram showing the changeover procedures for steering gear control systems and steering gear actuating systems are to be permanently displayed in the wheelhouse and in the steering gear compartment.

4.1.5 Where the system failure alarms for hydraulic lock, see Table 19.5.1, are provided, appropriate instructions shall be placed on the navigating bridge to shutdown the system at fault.

## ■ Section 5 Electric power circuits, electric control circuits, monitoring and alarms

### 5.1 Electric power circuits

5.1.1 Short circuit protection, an overload alarm and, in the case of polyphase circuits, an alarm to indicate single phasing is to be provided for each main and auxiliary motor circuit. Protective devices are to operate at not less than twice the full load current of the motor or circuit protected and are to allow excess current to pass during the normal accelerating period of the motors.

5.1.2 The alarms required by 5.1.1 are to be provided on the bridge and in the main machinery space or control room from which the main machinery is normally controlled.

5.1.3 Indicators for running indication of each main and auxiliary motor are to be installed on the navigating bridge and at a suitable main machinery control position.

5.1.4 A low-level alarm is to be provided for each power actuating system hydraulic fluid reservoir to give the earliest practicable indication of hydraulic fluid leakage. Alarms are to be given on the navigation bridge and in the machinery space where they can be readily observed.

5.1.5 Two exclusive circuits are to be provided for each electric or electrohydraulic steering gear arrangement consisting of one or more electric motors.

5.1.6 Each of these circuits is to be fed from the main switchboard. One of these circuits may pass through the emergency switchboard.

5.1.7 One of these circuits may be connected to the motor of an associated auxiliary electric or electrohydraulic power unit.

5.1.8 Each of these circuits is to have adequate capacity to supply all the motors which can be connected to it and which can operate simultaneously.

5.1.9 These circuits are to be separated throughout their length as widely as is practicable.

5.1.10 In ships of less than 1600 gross tonnage, if an auxiliary steering gear is not electrically powered or is powered by an electric motor primarily intended for other services, the main steering gear may be fed by one circuit from the main switchboard. Consideration would be given to other protective arrangements than described in 5.1.1, for such a motor primarily intended for other services.

### 5.2 Electric control circuits

5.2.1 Electric control systems are to be independent and separated as far as is practicable throughout their length.



# Steering Gear

# Part 5, Chapter 19

Sections 5, 6 & 7

5.2.2 Each main and auxiliary electric control system which is to be operated from the navigating bridge is to comply with the following:

- (a) It is to be served with electric power by a separate circuit supplied from the associated steering gear power circuit, from a point within the steering gear compartment, or directly from the same section of switchboard busbars, main or emergency, to which the associated steering gear power circuit is connected.
- (b) Each separate circuit is to be provided with short-circuit protection only.

## 5.3 Monitoring and alarms

5.3.1 Alarms and monitoring requirements are indicated in 5.3.2 and Table 19.5.1.

**Table 19.5.1 Alarm requirements**

Item	Alarm	Note
Rudder position	—	Indication, see 4.1.3
Steering gear power units, power	Failure	—
Steering gear motors	Overload, Single phase	For alarm and running indication locations, see 5.1.2 and 5.1.3
Control system power	Failure	—
Steering gear hydraulic oil level	Low	Each reservoir to be monitored. For alarm locations, see 5.1.4
Auto pilot	Failure	Running indication
Hydraulic oil temperature	High	Where oil cooler is fitted
Hydraulic lock	Fault	Where more than one system (either power or control) can be operated simultaneously each system is to be monitored, see Note 1
Hydraulic oil filter differential pressure	High	When oil filters are fitted
<b>NOTE</b> This alarm is to identify the system at fault and to be activated when (for example): <ul style="list-style-type: none"><li>• position of the variable displacement pump control system does not correspond with given order; or</li><li>• incorrect position of 3-way full flow valve or similar in constant delivery pump system is detected.</li></ul>		

5.3.2 The alarms described in Table 19.5.1 are to be indicated on the navigating bridge and the additional locations described and are to be in accordance with the alarm system specified by Pt 6, Ch 1,2.3.

## Section 6 Emergency power

### 6.1 General

6.1.1 Where the rudder stock is required to be over 230 mm diameter in way of the tiller, excluding strengthening for navigation in ice, an alternative power supply, sufficient at least to supply the steering gear power unit which complies with the requirements of 2.1.3 and also its associated control system and the rudder angle indicator, shall be provided automatically, within 45 seconds, either from the emergency source of electrical power or from an independent source of power located in the steering gear compartment. This independent source of power shall be used only for this purpose.

6.1.2 In every ship of 10 000 gross tonnage and upwards, the alternative power supply shall have a capacity for at least 30 minutes of continuous operation and in any other ship for at least 10 minutes.

6.1.3 Where the alternative power source is a generator, or an engine driven pump, starting arrangements are to comply with the requirements relating to the starting arrangements of emergency generators.

## Section 7 Testing and trials

### 7.1 Testing

7.1.1 The requirements of the Rules relating to the testing of Class 1 pressure vessels, piping, and related fittings including hydraulic testing apply.

7.1.2 After installation on board the vessel the steering gear is to be subjected to the required hydrostatic and running tests.

7.1.3 Each type of power unit pump is to be subjected to a type test. The type test shall be for a duration of not less than 100 hours, the test arrangements are to be such that the pump may run in idling conditions, and at maximum delivery capacity at maximum working pressure. During the test, idling periods are to be alternated with periods at maximum delivery capacity at maximum working pressure. The passage from one condition to another should occur at least as quickly as on board. During the whole test no abnormal heating, excessive vibration or other irregularities are permitted. After the test, the pump is to be opened out and inspected. Type tests may be waived for a power unit which has been proven to be reliable in marine service.

# Steering Gear

## Part 5, Chapter 19

Sections 7 & 8

### 7.2 Trials

7.2.1 The steering gear is to be tried out on the trial trip in order to demonstrate to the Surveyor's satisfaction that the requirements of the Rules have been met. The trial is to include the operation of the following:

- (a) The steering gear, including demonstration of the performances required by 2.1.2(b) and 2.1.3(b):
    - For the main steering gear trial, the propeller pitch of controllable pitch propellers is to be at the maximum design pitch approved for the maximum continuous ahead RPM;
    - If the ship cannot be tested at the deepest draught, alternative trial conditions may be specially considered. In this case, for the main steering gear trial, the speed of the ship corresponding to the maximum continuous revolutions of the main engine should apply;
  - (b) The steering gear power units, including transfer between steering gear power units;
  - (c) The isolation of one power actuating system, checking the time for regaining steering capability;
  - (d) The hydraulic fluid recharging system;
  - (e) The emergency power supply required by 6.1.1;
  - (f) The steering gear controls, including transfer of control and local control;
  - (g) The means of communication between the steering gear compartment and the wheelhouse, also the engine room, if applicable;
  - (h) The alarms and indicators;
  - (j) Where the steering gear is designed to avoid hydraulic locking this feature shall be demonstrated.
- Test items (d), (g), (h) and (j) may be effected at the dockside.

- (b) The main steering gear is to comprise either:
  - (i) two independent and separate power actuating systems, each capable of meeting the requirements of 2.1.2(b); or
  - (ii) at least two identical power actuating systems which, acting simultaneously in normal operation, are capable of meeting the requirements of 2.1.2(b). Where necessary to comply with these requirements, inter-connection of hydraulic power actuating systems is to be provided. Loss of hydraulic fluid from one system is to be capable of being detected and the defective system automatically isolated so that the other actuating system or systems remain fully operational.
- (c) Steering gears other than of the hydraulic type are to achieve equivalent standards.

### 8.3 For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards but of less than 100 000 tons deadweight

8.3.1 Solutions other than those set out in 8.2.1 which need not apply the single failure criterion to the rudder actuator or actuators, may be permitted provided that an equivalent safety standard is achieved and that:

- (a) Following loss of steering capability due to a single failure of any part of the piping system or in one of the power units, steering capability is regained within 45 seconds; and
- (b) Where the steering gear includes only a single rudder actuator special consideration is given to stress analysis for the design including fatigue analysis and fracture mechanics analysis, as appropriate, the material used, the installation of sealing arrangements and the testing and inspection and provision of effective maintenance. In consideration of the foregoing, regard will be given to the 'Guidelines' in Section 9.

8.3.2 Manufacturers of steering gear who intend their product to comply with the requirements of the 'Guidelines' are to submit full details when plans are forwarded for approval.

## Section 8 Additional requirements

### 8.1 For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards and every other ship of 70 000 tons gross and upwards

8.1.1 The main steering gear is to comprise two or more identical power units complying with provisions of 2.1.4.

### 8.2 For tankers, chemical tankers or gas carriers of 10 000 tons gross and upwards

8.2.1 Subject to 8.3 the following are to be complied with:

- (a) The main steering gear is to be so arranged that in the event of loss of steering capability due to a single failure in any part of one of the power actuating systems of the main steering gear, excluding the tiller, quadrant or components serving the same purpose, or seizure of the rudder actuators, steering capability is to be regained in not more than 45 seconds after the loss of one power actuating system.

# Steering Gear

# Part 5, Chapter 19

Section 9



## Section 9

### 'Guidelines' for the acceptance of non-duplicated rudder actuators for tankers, chemical tankers and gas carriers of 10 000 tons gross and upwards but of less than 100 000 tons deadweight

#### 9.1 Materials

9.1.1 Parts subject to internal hydraulic pressure or transmitting mechanical forces to the rudder-stock are to be made of duly tested ductile materials complying with recognized standards. Materials for pressure retaining components are to be in accordance with recognized pressure vessel standards. These materials are not to have an elongation less than 12 per cent nor a tensile strength in excess of 650 N/mm<sup>2</sup>.

#### 9.2 Design

9.2.1 **Design pressure.** The design pressure should be assumed to be at least equal to the greater of the following:

- 1,25 times the maximum working pressure to be expected under the operating conditions required in 2.1.2(b).
- The relief valve(s) setting.

9.2.2 **Analysis.** In order to analyse the design the following are required:

- The manufacturers of rudder actuators should submit detailed calculations showing the suitability of the design for the intended service.
- A detailed stress analysis of pressure retaining parts of the actuator should be carried out to determine the stresses at the design pressure.
- Where considered necessary because of the design complexity or manufacturing procedures, a fatigue analysis and fracture mechanics analysis may be required. In connection with these analyses, all foreseen dynamic loads should be taken into account. Experimental stress analysis may be required in addition to, or in lieu of, theoretical calculations depending upon the complexity of the design.

9.2.3 **Dynamic loads for fatigue and fracture mechanics analysis.** The assumption for dynamic loading for fatigue and fracture mechanics analysis where required by 3.1.5, 8.3 and 9.2.2 are to be submitted for appraisal. Both the case of high cycle and cumulative fatigue are to be considered.

9.2.4 **Allowable stresses.** For the purpose of determining the general scantlings of parts of rudder actuators subject to internal hydraulic pressure the allowable stresses should not exceed:

$$\begin{aligned}\sigma_m &\leq f \\ \sigma_1 &\leq 1,5f \\ \sigma_b &\leq 1,5f \\ \sigma_1 + \sigma_b &\leq 1,5f \\ \sigma_m + \sigma_b &\leq 1,5f\end{aligned}$$

where

$$f = \text{the lesser of } \frac{\sigma_B}{A} \text{ or } \frac{\sigma_y}{B}$$

$\sigma_b$  = equivalent primary bending stress

$\sigma_m$  = equivalent primary general membrane stress

$\sigma_y$  = specified minimum yield stress or 0,2 per cent proof stress of material at ambient temperature

$\sigma_B$  = specified minimum tensile strength of material at ambient temperature

$\sigma_1$  = equivalent primary local membrane stress

A and B are as follows:

	<i>Wrought steel</i>	<i>Cast steel</i>	<i>Nodular cast iron</i>
A	4	4,6	5,8
B	2	2,3	3,5

9.2.5 **Burst test.** Pressure retaining parts not requiring fatigue analysis and fracture mechanics analysis may be accepted on the basis of a certified burst test and the detailed stress analysis required by 9.2.2 need not be provided. The minimum bursting pressure should be calculated as follows:

$$P_b = P A \frac{\sigma_{Ba}}{\sigma_B}$$

where

A = as from table in 9.2.4

P = design pressure as defined in 9.2.1

$P_b$  = minimum bursting pressure

$\sigma_B$  = tensile strength as defined in 9.2.4

$\sigma_{Ba}$  = actual tensile strength.

#### 9.3 Construction details

9.3.1 **General.** The construction should be such as to minimize local concentrations of stress.

##### 9.3.2 Welds.

- The welding details and welding procedures should be approved.
- All welded joints within the pressure boundary of a rudder actuator or connection parts transmitting mechanical loads should be full penetration type or of equivalent strength.

9.3.3 **Oil seals.** Oil seals forming part of the external pressure boundary are to comply with 3.2.3 and 3.2.4.

9.3.4 **Isolating valves** are to be fitted at the connection of pipes to the actuator, and should be directly mounted on the actuator.

9.3.5 **Relief valves** for protecting the rudder actuator against over-pressure as required in 3.3.3 are to comply with the following:

- The setting pressure is not to be less than 1,25 times the maximum working pressure expected under operating conditions required by 2.1.2(b).

- (b) The minimum discharge capacity of the relief valve(s) is to be not less than 110 per cent of the total capacity of all pumps which provided power for the actuator. Under such conditions the rise in pressure should not exceed 10 per cent of the setting pressure. In this regard due consideration should be given to extreme foreseen ambient conditions in respect of oil viscosity.

## 9.4 Non-destructive testing

9.4.1 The rudder actuator should be subjected to suitable and complete non-destructive testing to detect both surface flaws and volumetric flaws. The procedure and acceptance criteria for non-destructive testing should be in accordance with requirements of recognized standards. If found necessary, fracture mechanics analysis may be used for determining maximum allowable flaw size.

## 9.5 Testing

9.5.1 Tests, including hydrostatic tests, of all pressure parts at 1,5 times the design pressure should be carried out.

9.5.2 When installed on board the ship, the rudder actuator should be subjected to a hydrostatic test and a running test.

## 9.6 Additional requirements for steering gear fitted to ships with Ice Class notations

9.6.1 See Pt 3, Ch 9.

# Azimuth Thrusters

## Part 5, Chapter 20

Sections 1, 2 & 3

### Section

- 1 **General requirements**
- 2 **Performance**
- 3 **Construction and design**
- 4 **Control engineering arrangements**
- 5 **Electrical equipment**
- 6 **Testing and trials**

### ■ Section 1 General requirements

#### 1.1 Application

1.1.1 This Chapter applies to azimuth or rotatable thruster units, for propulsion or D.P. duty which transmit a power greater than 220 kW used as the sole means of steering and are in addition to the relevant requirements of Chapter 19.

1.1.2 In general, for a vessel to be assigned an unrestricted service notation a minimum of two azimuth thruster units are to be provided where these form the sole means of propulsion. Where a single thruster installation is proposed, it will be subject to special consideration.

#### 1.2 Plans

1.2.1 The following additional plans are to be submitted for consideration together with particulars of materials and the maximum shaft power and revolutions per minute:

- Sectional assembly including nozzle ring structure, nozzle support struts, etc.
- Shafts, gears and couplings.
- Steering mechanisms with details of ratings.
- Bearing specifications.
- Schematic piping systems.

### ■ Section 2 Performance

#### 2.1 General

2.1.1 The arrangement of thrusters is to be such that the ship can be satisfactorily manoeuvred.

2.1.2 In addition to the requirements of Chapter 19, the azimuthing mechanism is to be capable of a maximum rotational speed of not less than 1,5 rev/min.

### ■ Section 3 Construction and design

#### 3.1 Materials

3.1.1 Specification for materials of gears, shafts, couplings and propeller, giving chemical composition, heat treatment and mechanical properties are to be submitted for approval.

3.1.2 Specification for materials for the stock, struts, etc., are to be submitted for approval.

3.1.3 Where an ice class notation is included in the class of a ship, additional requirements are applicable as detailed in Chapter 9 and Pt 3, Ch 9.

#### 3.2 Design

3.2.1 The requirements detailed in Chapters 1, 5, 6, 7, 8, 9, 14 and 19 are to be complied with where applicable.

3.2.2 For steerable thrusters with a nozzle, the equivalent rudder stock diameter in way of tiller, used in Table 19.1.1 in Chapter 19, is to be determined as follows:

$$\delta_t = 26,03 \sqrt[3]{(V + 3)^2 A_N x_P} \text{ mm}$$

where

$V$  = maximum service speed, in knots, which the ship is designed to maintain under thruster operation

$A_N$  = projected nozzle area, in m<sup>2</sup>, and is equal to the length of the nozzle multiplied by the mean external vertical height of the nozzle

and

$x_P$  = horizontal distance from the centreline of the steering tube to the centre of pressure, in metres. The position of the centre of pressure is determined for both ahead and astern cases from Pt 3, Ch 13, 2.2.1

The corresponding maximum turning moment,  $M_T$ , is to be determined as follows:

$M_T$  = turning moment for conical couplings and is to be taken as the greatest of  $M_F$ ,  $M_A$  or  $M_W$

$M_F$  =  $P_L x_P \times 10^6$  N mm (kgf mm) in the ahead condition

$M_A$  =  $P_L x_P \times 10^6$  N mm (kgf mm) in the astern condition

$M_W$  = the torque generated by the steering gear at the maximum working pressure supplied by the manufacturer, in N mm (kgf mm).  $M_W$  is not to exceed the greater of  $3,0M_F$  or  $3,0M_A$

$P_L$  = lateral force on rudder acting at centre of pressure, as defined in Pt 3, Ch 13, 2.1.1 (where  $A_R$  equals  $2A_N$ ), in kN (tonne-f)

3.2.3 The nozzle structure is to be in accordance with Pt 3, Ch 13, 3.

# Azimuth Thrusters

## Part 5, Chapter 20


Sections 3 &amp; 4

3.2.4 In addition to the requirements of Table 13.3.1, in Pt 3, Ch 13, the scantlings of the nozzle stock or steering tube are to be such that the section modulus against transverse bending at any section xx is not less than:

$$Z = 1,73 \sqrt{(V + 3)^4 A_N^2 x_P^2 + \frac{a^2}{4} T_M^2 10^4} \text{ cm}^3$$

where

- $a$  = dimension, in metres, as shown in Fig. 20.3.1  
 $T_M$  = maximum thrust of the thruster unit in tonnes.



**Fig. 20.3.1 Steerable thruster**

3.2.5 The scantlings of nozzle connections or struts will be specially considered. In the case of certain high powered ships, direct calculation may be required.

3.2.6 For steerable thrusters without a nozzle the scantlings in way of the tiller will be specially considered.

### 3.3 Steering gear elements

3.3.1 These gears are to be considered for the following conditions:

- a design maximum dynamic duty steering torque;
  - a static duty ( $\leq 10^3$  load cycles) steering torque, and the static duty steering torque should be not less than  $M_T$ .
- Values for the above should be submitted together with the plans.

### 3.4 Components

3.4.1 The hydraulic power operating systems for each azimuth thruster are to be provided with the following:

- (a) arrangements to maintain the cleanliness of the hydraulic fluid, taking into consideration the type and design of the hydraulic system;

- (b) a fixed storage tank having sufficient capacity to recharge at least one azimuth power actuating system including the reservoir. The piping from the storage tank is to be permanent and arranged in such a manner as to allow recharging from within the thruster space.

## Section 4 Control engineering arrangements

### 4.1 General

4.1.1 Except where indicated in this Section the control engineering systems are to be in accordance with Pt 6, Ch 1.

4.1.2 Steering control is to be provided for the azimuth thrusters from the navigating bridge, the main machinery control station and locally.

4.1.3 An indication of the angular position of the thruster(s) and the magnitude of the thrust are to be provided at each station from which it is possible to control the direction of thrust.

4.1.4 Means are to be provided at the remote control station(s) to stop each thrust unit.

### 4.2 Monitoring and alarms

4.2.1 Alarms and monitoring requirements are indicated in 4.2.2 and Table 20.4.1.

4.2.2 The alarms described in Table 20.4.1 are to be indicated individually on the navigating bridge and in accordance with the alarm system specified by Pt 6, Ch 1,2,3.

**Table 20.4.1 Alarms for control systems**

Item	Alarm	Note
Thruster azimuth	–	Indicator, see 4.1.3
Steering motor	Power failure, single phase	Also running indication on bridge and at machinery control station
Propulsion motor	Overload, power failure	Also running indication on bridge and at machinery control station
Control system power	Failure	
Hydraulic oil supply tank level	Low	
Hydraulic oil system pressure	Low	
Hydraulic oil system temperature	High	Where oil cooler is fitted
Hydraulic oil filters differential pressure	High	Where oil filters are fitted
Lubricating oil supply	Low	If separate forced lubrication

## ■ Section 5 Electrical equipment

### 5.1 General

5.1.1 The electrical installation is to be designed, constructed and installed in accordance with the requirements of 5.2 to 5.4.

5.1.2 Where the thruster units are electrically driven the relevant requirements, including surveys, of Pt 6, Ch 2 are to be complied with.

### 5.2 Generating arrangements

5.2.1 Where a central power generation system is employed, the requirements of Pt 6, Ch 2, 15.2.5 are to be complied with.

5.2.2 The generating and distribution system is to be so arranged that after any single failure, steering capability can be maintained or regained within a period not exceeding 45 seconds, and the effectiveness of the steering after such a fault will not be reduced by more than 50 per cent. This may be achieved by the parallel operation of two or more generating sets, or alternatively when the electrical requirements may be met by one generating set in operation, on loss of power, the automatic starting and connection to the switchboard of a standby set, provided that this set can restart and run a thruster with its auxiliaries.

5.2.3 The failure of one thruster unit or its control system is not to render any other thruster inoperative.

### 5.3 Distribution arrangements

5.3.1 Thruster auxiliaries and controls are to be served by individual circuits. Services that are duplicated are to be separated throughout their length as widely as is practicable and without the use of common feeders, transformers, convertors, protective devices or control circuits.

### 5.4 Auxiliary supplies

5.4.1 Where the auxiliary services and thruster units are supplied from a common source, the following requirements are to be complied with:

- (a) the voltage regulation and current sharing requirements defined in Pt 6, Ch 2, 8.4.2 and 8.4.7 are to be maintained over the full range of power factors that may occur in service,
- (b) auxiliary equipment and services are to operate with any waveform distortion introduced by convertors without deleterious effect. (This may be achieved by the provision of suitably filtered/converted supplies).

## ■ Section 6 Testing and trials

### 6.1 General

6.1.1 The requirements detailed in Chapters 1, 5 and 19 are to be complied with and, in addition, the performance specified in 2.1.2 is to be demonstrated to the Surveyor's satisfaction.

6.1.2 The actual values of steering torque should be verified during sea trials to confirm that the design maximum dynamic duty torque has not been exceeded.





# ShipRight Procedures for Machinery Planned Maintenance and Condition Monitoring

## Part 5, Chapter 21

Sections 1, 2, 3 & 4

### Section

- 1 **General**
- 2 **Machinery Planned Maintenance Scheme**
- 3 **Machinery Condition Monitoring**
- 4 **Turbine Condition Monitoring**
- 5 **Screwshaft Condition Monitoring**
- 6 **Reliability Centred Maintenance**

### ■ Section 1 General

#### 1.1 Application

1.1.1 This Chapter is applicable to all machinery, and the requirements are to be applied in conjunction with the relevant Chapters of Parts 5 and 6 and the ShipRight procedures.

1.1.2 Details of LR's ShipRight procedures are given in LR's *ShipRight Procedures Overview* and in this Chapter, where related to particular items and notes.

1.1.3 Details of hull ShipRight procedures are to be found in Pt 3, Ch 16.

#### 1.2 Classification notations and descriptive notes

1.2.1 In addition to the machinery class notations defined in Pt 1, Ch 2, ships complying with the requirements of this Chapter will be eligible to be assigned the descriptive notes as defined in Pt 1, Ch 2, 2.6 and associated with the ShipRight procedures.

#### 1.3 Information and plans required to be submitted

1.3.1 The information and plans required to be submitted are as specified in the relevant Chapters of Parts 5 and 6 applicable to the particular machinery and in this Chapter where related to particular items and notes.

### ■ Section 2 Machinery Planned Maintenance Scheme

#### 2.1 Descriptive note MPMS

2.1.1 Where an Owner operates an approved Planned Maintenance Scheme as part of the Continuous Survey Machinery (CSM) cycle, the descriptive note **MPMS** will, at the Owner's request, be entered in column 6 of the *Register Book*.

2.1.2 The descriptive note will indicate that procedures and documentation are in place to control and record the inspection and maintenance routines of all machinery and equipment in the ship.

2.1.3 For the requirements and approval procedures, see the appropriate procedures in the *ShipRight Procedures Overview*.

### ■ Section 3 Machinery Condition Monitoring

#### 3.1 Descriptive note MCM

3.1.1 Where an Owner operates an Approved Planned Maintenance Scheme as part of the Continuous Survey Machinery (CSM) cycle, and monitoring techniques and equipment are used to record the condition against agreed acceptable limits, the descriptive note **MCM** will, at the Owner's request, be entered in column 6 of the *Register Book*.

3.1.2 The descriptive note will indicate that equipment, procedures and documentation are in place to monitor, control and record the physical and operational condition of the equipment on the ship and control the maintenance routines accordingly.

3.1.3 For the requirements and approval procedures, see the appropriate procedures in the *ShipRight Procedures Overview*.

### ■ Section 4 Turbine Condition Monitoring

#### 4.1 Descriptive note TCM

4.1.1 Where an Owner adopts the requirements for monitoring of the main steam turbine, the descriptive note **TCM** will, at the Owner's request, be entered in column 6 of the *Register Book*.

# ShipRight Procedures for Machinery Planned Maintenance and Condition Monitoring

## Part 5, Chapter 21

Sections 4, 5 & 6

4.1.2 The descriptive note will indicate that equipment and procedures are in place, in order to determine the physical and operational condition of that equipment.

4.1.3 For the requirements, see the appropriate procedure in the *ShipRight Procedures Overview*.

---

### ■ Section 5 Screwshaft Condition Monitoring

#### 5.1 Descriptive note SCM

5.1.1 Where an Owner adopts the requirements for monitoring of the screwshaft, the descriptive note **SCM** will, at the Owner's request, be entered in column 6 of the *Register Book*.

5.1.2 The descriptive note will indicate that equipment and procedures are in place, in order to determine the physical and operational condition of that equipment.

5.1.3 For the requirements, see Pt 1, Ch 3,17.3 and the appropriate procedure in the *ShipRight Procedures Overview*.

---

### ■ Section 6 Reliability Centred Maintenance

#### 6.1 Descriptive note RCM

6.1.1 Where an Owner operates an Approved Planned Maintenance Scheme based on the use of Reliability Centred Maintenance as part of the Continuous Survey Machinery (CSM) cycle, the descriptive note **RCM** will, at the Owner's request, be entered in column 6 of the *Register Book*.

6.1.2 The descriptive note will indicate that procedures and documentation are in place to control and record the inspection and maintenance routines of all machinery and equipment in the ship, and that they are based on acceptable and applicable methodology.

6.1.3 For the requirements and approval procedures, see the appropriate procedures in the *ShipRight Procedures Overview*.

---

## Section

- 1 **General requirements**
- 2 **Failure Mode and Effects Analysis (FMEA)**
- 3 **Machinery arrangements**
- 4 **Control arrangements**
- 5 **Separate machinery spaces ★ (star) Enhancement**
- 6 **Testing and trials**



## Section 1

**General requirements****1.1 General**

1.1.1 This Chapter states the requirements for ships having machinery redundancy, and are in addition to the relevant requirements in other relevant Sections of these Rules.

1.1.2 The requirements, which are optional, cover machinery arrangements and control systems necessary for ships which have propulsion and steering systems configured such that, in the event of a single failure of a system or item of active equipment, see 1.1.3, the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and retain steering capability at a service speed of not less than seven knots. 100 per cent propulsion power is the approved total power of all the main propulsion units at maximum continuous rating (MCR). The requirements also cover machinery arrangements where the propulsion and steering systems are installed in separate compartments such that, in the event of a loss of one compartment, the ship will retain availability of propulsion power and manoeuvring capability.

1.1.3 For the purpose of this Chapter, items of active equipment are those which have a defined function for operation of a propulsion or steering system, such as but not limited to:

- Prime movers, i.e. diesel engines, electric motors, steam turbines and gas turbines;
- Generators and their excitation equipment;
- Transformers and converters;
- Gearing and shafting systems;
- Propulsion devices, i.e. propellers, water-jets and thrusters;
- Pumps;
- Valves (where power actuated);
- Fuel treatment plant;
- Coolers/heaters;
- Filters;

Piping and electrical cables connecting items of active equipment are not considered to be active.

1.1.4 Requirements additional to these Rules may be imposed by the Flag State with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the ship is intended to operate.

1.1.5 Sections 2, 3 and 4 state the applicable requirements for arrangements necessary to maintain availability of propulsion and manoeuvring capability, in the event of a single failure in equipment. Ships complying with the applicable requirements of Sections 2 to 4 of this Chapter will be eligible for the machinery class notation **PMR** (Propulsion Machinery Redundancy), **SMR** (Steering Machinery Redundancy) or **PSMR** (Propulsion and Steering Machinery Redundancy), which will be recorded in the *Register Book*.

1.1.6 Section 5 states the additional requirements necessary to maintain availability of propulsion and manoeuvring capability where machinery is installed in separate compartments and the loss of any one compartment due to fire or flooding has been addressed. Ships complying with the applicable requirements of Sections 2 to 5 of this Chapter will be eligible for the machinery class notation **PMR★** (Propulsion Machinery Redundancy in separate machinery spaces), **SMR★** (Steering Machinery Redundancy in separate machinery spaces) or **PSMR★** (Propulsion and Steering Machinery Redundancy in separate machinery spaces) which will be recorded in the *Register Book*.

**1.2 Plans and information**

1.2.1 The requirements, which are optional, cover machinery arrangements and control systems necessary for ships which have propulsion and steering systems configured such that, in the event of a single failure in equipment, the ship will retain in operation not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and retain steering capability at a service speed of not less than seven knots.

1.2.2 **Machinery spaces.** Plans showing the general arrangement of the machinery spaces, together with a description of the propulsion system, main and emergency electrical power supply systems and steering arrangements are to be submitted. The plans are to indicate segregation and access arrangements for machinery spaces and associated control rooms/stations.

1.2.3 **Failure Mode and Effects Analysis (FMEA).** For the propulsion systems, electrical power supplies, essential services, control systems and steering arrangements, a FMEA report is to be submitted and is to address the requirements identified in Sections 2 and 5.

**1.2.4 Manoeuvring capability.** An assessment of the ship's ahead and astern manoeuvring capability, under the following operating conditions, is to be submitted:

- (a) Where only 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems are available.
- (b) Where the steering capability requirements described in 3.2.1 are available.

IMO Resolution A.751(A) *Interim Standards for Ship Manoeuvrability*, provides guidance on standard manoeuvres required in an assessment of the manoeuvrability of ships.

**1.2.5 Testing and trials procedures.** A schedule of testing and trials to demonstrate that the ship is capable of being operated with machinery functioning as described in 4.2 is to be submitted. In addition, any testing programme that may be necessary to prove the conclusions of the FMEA is to be submitted.

**1.2.6 Operating Manuals.** Operating Manuals are to be submitted for information and provided on board. The manuals are to include the following information:

- (a) Particulars of machinery and control systems.
- (b) General description of systems for propulsion and steering.
- (c) Operating instructions for all machinery and control systems used for propulsion and steering.
- (d) Procedures for dealing with the situations identified in the FMEA report.

**1.2.7** The FMEA is to establish that in the event of a single component failure, for ships assigned:

- (a) **PSMR** and **PSMR★** notations, at least 50 per cent of the propulsion power and steering capability remains available;
- (b) **PMR** and **PMR★** notations, at least 50 per cent of the propulsion power remains available; and
- (c) **SMR** and **SMR★** notations, the steering capability remains available.



## Section 2

## Failure Mode and Effects Analysis (FMEA)

### 2.1 General

**2.1.1** An FMEA is to be carried out in accordance with 2.1.2 to 2.1.7 for the propulsion systems, electrical power supply systems and steering systems to demonstrate that a single failure in active equipment or loss of an associated sub-system, see 1.1.3, will not cause loss of all propulsion and/or steering capability as required by a class notation. Typical sub-systems include associated control and monitoring arrangements, data communications, power supplies (electrical, hydraulic or pneumatic), fuel, lubricating, cooling, etc.

**2.1.2** The FMEA is to be carried out using the format presented in Table 22.2.1 or an equivalent format that addresses the same safety issues. Analyses in accordance with IEC 60812, *Analysis techniques for system reliability – Procedure for failure mode and effects analysis (FMEA)* or IMO MSC Resolution 36(63) Annex 4 – *Procedures for Failure Mode and Effects Analysis*, would be acceptable.

**2.1.3** The FMEA is to be organized in terms of equipment and function. The effects of item failures at a stated level and at higher levels are to be analysed to determine the effects on the system as a whole. Actions for mitigation are to be determined.

**2.1.4** The FMEA is to:

- (a) identify the equipment or sub-system, mode of operation and the equipment;
- (b) identify potential failure modes and their causes;
- (c) evaluate the effects on the system of each failure mode;
- (d) identify measures for reducing the risks associated with each failure mode; and
- (e) identify trials and testing necessary to prove conclusions.

**Table 22.2.1 Failure Mode and Effects Analysis**

Project: Failure Mode and Effects Analysis											
System:				Element:							Sheet No:
Item No.	Component Description	Function	Mode of Operation	Failure Mode	Failure Cause	Failure Detection	Effect of Failure		Severity	Corrective Action	Remarks
							On Item	On System			
NOTE The 'severity category' is to be in accordance with the following: (a) Catastrophic; (b) Hazardous; (c) Major; or (d) Minor.											

2.1.5 At sub-system level it is acceptable, for the purpose of these Rules, to consider failure of equipment items and their functions, e.g. failure of a pump to produce flow or pressure head. It is not required that the failure of components within that pump be analysed. In addition, their failure need only be dealt with as a cause of failure of the pump.

2.1.6 Where FMEA is used for consideration of systems that depend on software-based functions for control or co-ordination, the analysis is to investigate failure of the functions rather than a specific analysis of the software code itself.

2.1.7 The FMEA is to establish that following failure:

- (a) for **PSMR** and **PSMR★** notations, that the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems and retain steering capability;
- (b) for **PMR** and **PMR★** notations, that the ship will retain not less than 50 per cent of the installed prime mover capacity and not less than 50 per cent of the installed propulsion systems; and
- (c) for **SMR** and **SMR★** notations, that the steering capability remains available.



### Section 3

## Machinery arrangements

### 3.1 Main propulsion machinery

3.1.1 For **PSMR**, **PSMR★**, **PMR** and **PMR★** notations, independent main propulsion systems are to be provided so that the ship will retain not less than 50 per cent of the prime mover capacity and not less than 50 per cent of the installed propulsion systems in the event of a single failure of a system or active item of equipment, see 1.1.3. In the event of a single failure in equipment, the remaining system(s) is to be capable of maintaining a service speed of not less than seven knots and, for **PSMR** and **PSMR★** notations, give adequate manoeuvring capability, see 1.2.4.

### 3.2 Steering machinery

3.2.1 For **PSMR**, **PSMR★**, **SMR** and **SMR★** notations, independent steering systems for manoeuvring the ship are to be installed, such that steering capability will continue to be available in the event of any of the following:

- (a) Single failure in the steering gear equipment.
- (b) Loss of power supply or control system to any steering system.

### 3.3 Electrical power supply

3.3.1 The main busbars of the switchboard supplying the propulsion machinery and essential services are to be capable of being isolated by a multi-pole linked circuit breaker, disconnecter, or switch-disconnector into at least two independent sections.

3.3.2 In the event of the loss of one section or failure of the power supply from one generator, there is to be continuity of sufficient electrical power to supply essential services such that the ship will retain not less than 50 per cent of the prime mover capacity and not less than 50 per cent of the installed propulsion systems where **PSMR**, **PSMR★**, **PMR** and **PMR★** notations are required. See 3.2.1 for steering machinery requirements.

3.3.3 For ships capable of operating with one service generator connected to the switchboard, arrangements are to be such that a standby generator will automatically start and connect to the switchboard on loss of the service generator. Sequential starting of essential services is to be provided.

3.3.4 For ships operating with two or more generator sets in service connected to the switchboard, arrangements are to be such that, in the event of loss of one generator, the remaining set(s) is to be adequate for the continuity of essential services supplied from that switchboard. This may be achieved by preferential tripping of non-essential services. Alternatively, arrangements can be such that a standby generator will start automatically and connect to the switchboard on loss of one of the generator sets in service.

### 3.4 Essential services for machinery

3.4.1 Services essential for the operation of the propulsion machinery, steering and the supply of electrical power are to be arranged so to that the ship will retain not less than 50 per cent of the prime mover capacity and 50 per cent of the installed propulsion systems and retain steering capability in the event of a single failure in any of the services, where required by the respective class notations.

### 3.5 Oil fuel storage and transfer systems

3.5.1 The arrangements for the storage of oil fuel bunkers are to ensure that there is an adequate supply of existing oil fuel on board to allow sufficient time for a shore-based quality analysis of new bunkers, in accordance with ISO 8217 *Petroleum Products – Fuels (Class F) Specification of Marine Fuels* prior to use.

3.5.2 Provision is to be made to enable samples of oil fuel to be taken at the bunkering manifolds.

## ■ Section 4 Control arrangements

### 4.1 General

4.1.1 This Section states the requirements for the installation of control, alarm and safety systems but does not signify that machinery spaces may be operated unattended. For unattended machinery space operation, compliance with Pt 6, Ch 1,4 is also required.

4.1.2 The control, alarm and safety systems required in 4.2 are to comply with Pt 6, Ch 1,2.

### 4.2 Bridge control

4.2.1 The controls, alarms, instrumentation and safeguards required in 4.2.2 to 4.2.6 are to be provided on the bridge.

4.2.2 For **PSMR**, **PSMR★**, **PMR** and **PMR★** notations, means are to be provided to ensure satisfactory control of propulsion in both the ahead and astern directions when all main propulsion systems are functioning and when one propulsion system is not available.

4.2.3 For **PSMR**, **PSMR★**, **SMR** and **SMR★** notations, means are to be provided to ensure satisfactory control of steering when all steering systems are functioning and when any one steering system is not available.

4.2.4 Where required by 5.4.3, isolation of essential services is to be carried out either automatically or manually from the bridge. Indication of the status of isolation arrangements is to be provided.

4.2.5 Instrumentation to indicate the operational status of running and standby machinery is to be provided for the propulsion systems, the supply of electrical power, steering systems and other essential services.

4.2.6 Alarms are to be provided in the event of:

- (a) A fire in any machinery compartment.
- (b) A high bilge level in any machinery compartment. Irrespective of the assignment of the **UMS** notation, the bilge level detection system and arrangements for automatically pumping bilges, if applicable, are to comply with Pt 6, Ch 1,4.6.

## ■ Section 5 Separate machinery spaces ★ (star) Enhancement

### 5.1 General

5.1.1 This Section states the additional requirements where propulsion and steering machinery are installed in separate compartments such that, in the event of the loss of one compartment, the ship will retain availability of propulsion power and manoeuvring capability.

5.1.2 The machinery arrangements, control arrangements and FMEA required by Sections 2 to 4, together with testing and trials requirements in Section 6, are to be complied with in addition to 5.2 to 5.7.

### 5.2 Machinery arrangements

5.2.1 The main propulsion machinery is to be arranged in not less than two compartments such that, in the event of the loss of one compartment, propulsion power and/or manoeuvring capability will continue to be available, where required by the respective class notations.

5.2.2 The steering systems are to be arranged in not less than two separate compartments, such that steering capability will continue to be available in the event of the loss of one compartment, where required by the respective class notations.

### 5.3 Electrical power supply

5.3.1 The generating sets and converting sets required by Pt 6, Ch 2,2 are to be arranged so that they are located in at least two separate machinery compartments.

5.3.2 The independent sections of the switchboard required by 3.3.1 are to be arranged in not less than two separate compartments.

5.3.3 In the event of the loss of one compartment, there is to be continuity of sufficient electrical power to supply essential services, such that propulsion power and steering capability will continue to be available.

### 5.4 Essential services for machinery

5.4.1 Services essential for the operation of the propulsion machinery, steering and the supply of electrical power are to be arranged, so that propulsion power and steering capability are maintained in the event of the loss of one machinery compartment.

5.4.2 The design of systems which may have a common source, such as those used for supplying oil fuel, lubricating oil, fresh and sea-water cooling, ventilation of compartments and engine starting energy, is to ensure continuous availability of supply in the event of the loss of any one compartment. Where applicable, continuous availability of heating services, oil fuel and water treatments is also to be provided. See 3.5 and 5.6 for oil fuel storage and transfer systems.

5.4.3 Where essential services are arranged so that they may supply machinery in another compartment, means of isolation from that compartment is to be provided.

5.4.4 Where pumps for essential services are arranged to supply more than one compartment, standby pumps for the same supplies are to be provided in a different compartment. The standby pumps are to be arranged to start automatically if the discharge pressure from the working pumps falls below a predetermined value.

## 5.5 Bilge drainage arrangements

5.5.1 The independent power pumps for bilge drainage are to be located in two separate watertight compartments. Each pump is to be capable of draining any compartment. Means of isolation from other compartments is to be provided.

5.5.2 In addition to the independent power pumps installed to comply with 5.5.1, an emergency bilge drainage arrangement is to be provided in each main propulsion machinery space.

5.5.3 Each separate machinery compartment is to be provided with at least one independent power pump direct bilge suction.

## 5.6 Oil fuel storage

5.6.1 The oil fuel service tanks required by Ch 14,4.18 are to be located in separate compartments.

5.6.2 Provision is to be made to ensure that oil fuel preparation and transfer arrangements to the oil fuel service tanks are continuously available in the event of the loss of any one compartment, see also 5.4.2.

## 5.7 FMEA

5.7.1 The FMEA required by 2.1.1 for the propulsion systems, electrical power supplies, essential services, control systems and steering arrangements is also to address the following:

- (a) Fire in a machinery space or control room.
- (b) Flooding of any watertight compartment which could affect propulsion or steering capability.
- (c) Separation of machinery spaces.

## Section 6 Testing and trials

### 6.1 Sea trials

6.1.1 In addition to the requirements for sea trials in Ch 1,5.2, trials are to be carried out to demonstrate that when the ship is operating 50 per cent of the prime mover capacity and 50 per cent of the installed propulsion systems, a speed of not less than 7 knots can be maintained with adequate steering capability, where required by the respective class notations.

6.1.2 Trials are to be carried out to demonstrate the ship's steering capability in accordance with the assessment required by 1.2.4 with one steering system out of action.

6.1.3 Where the FMEA report has identified the need to prove the conclusions, testing and trials are to be carried out as necessary to investigate the following:

- (a) The effect of a specific component failure.
- (b) The effectiveness of automatic/manual isolation systems.
- (c) The behaviour of any interlocks that may inhibit operation of essential systems.

6.1.4 During sea trials, the operational envelope(s) is to be determined under the conditions detailed in 3.1.1 and/or 3.2.1, as required for the class notation.






# Podded Propulsion Units

## Part 5, Chapter 23

Sections 1 & 2

### Section

- 1 **Scope**
- 2 **General requirements**
- 3 **Functional capability**
- 4 **Materials**
- 5 **Structure design and construction requirements**
- 6 **Machinery design and construction requirements**
- 7 **Electrical equipment**
- 8 **Control engineering arrangements**
- 9 **Testing and trials**
- 10 **Installation, maintenance and replacement procedures**



**Fig. 23.1.1 Podded propulsion unit**

**1.1.6** It is the shipbuilder's responsibility to ensure that all installed equipment is suitable for operation in the location and under all anticipated environmental conditions associated with the design of the ship which is to include temperature, humidity, vibration and impulsive accelerations.

### ■ Section 1 Scope

#### 1.1 General

**1.1.1** This Chapter applies to podded propulsion units where used for propulsion, dynamic positioning duty or as the sole means of steering.

**1.1.2** For the purposes of these Rules, a podded propulsion unit is any propulsion or manoeuvring device that is external to the normal form of the ship's hull and houses a propeller powering device.

**1.1.3** The requirements of this Chapter relate to podded propulsion units powered by electric propulsion motors. Podded propulsion units with other drive arrangements will be subject to individual consideration.

**1.1.4** The structural requirements stated in 5.1, 5.2 and 5.3 relate to podded propulsion units having a pod body with single supporting strut with or without an integral slewing ring arrangement, see Fig. 23.1.1. Novel and unconventional arrangements will be subject to individual consideration. In such cases, the designers are advised to contact LR in the early stages of the design for advice on the manner and content of design information required for formal classification appraisal.

**1.1.5** The aft end structures associated with podded installations are to be examined with respect to potential slamming, see Pt 4, Ch 2.

### ■ Section 2 General requirements

#### 2.1 Pod arrangement

**2.1.1** In general, for a ship to be assigned an unrestricted service notation, a minimum of two podded propulsion units are to be provided where these form the sole means of propulsion. For vessels where a single podded propulsion unit is the sole means of propulsion, an evaluation of a detailed engineering and safety justification will be conducted by LR, see 2.2.2. This evaluation process will include the appraisal of a Failure Modes and Effects Analysis (FMEA) to verify that sufficient levels of redundancy and monitoring are incorporated in the podded propulsion unit's essential support systems and operating equipment.

#### 2.2 Plans and information to be submitted

**2.2.1** In addition to the plans required by Chapters 5, 6, 7, 8, 14 and 19, and Pt 6, Ch 1 and Ch 2, the following plans and information are required to be submitted for appraisal:


- (a) Description of the ship's purpose/capabilities together with the pod's intended operational modes in support of these capabilities.
- (b) Power transmitted at MCR condition (shaft power and rpm) and other maximum torque conditions, e.g. bollard pull.

# Podded Propulsion Units

# Part 5, Chapter 23

Section 2

- (c) Maximum transient thrust, torque and other forces and moments experienced during all envisaged operating modes as permitted by the steering and propulsor drive control systems.
- (d) Details of the electric propulsion motor short-circuit torque and motor air gap tolerance.
- (e) Sectional assembly in the Z-X plane, see Fig. 23.2.1.
- (f) Specifications of materials and NDE procedures for components essential for propulsion and steering operation to include propulsion shaft and slewing ring bearings, gearing and couplings, see 4.1.
- (g) Details of intended manoeuvring capability of the ship in each operating condition. (To be declared by the shipyard, see also 3.1.1).
- (h) Design loads for both the pod structure and propeller together with podded propulsion unit design operating modes (see 2.4.1, 6.3.7, 6.6.5 and 6.6.6).
- (j) Supporting data calculations and direct calculation reports. This is to include an assessment of anticipated global accelerations acting on the ship's machinery and equipment which may potentially affect the reliable operation of the propulsion system. See also 1.1.5.
- (k) Structural component details including: strut, pod body, bearing supports, bearing end caps, ship's structure in way of podded propulsion unit integration and a welding Table showing a key to weld symbols used on the plans specifying weld size, type, preparation and heat treatment. The information should include the following:
  - Detailed drawings showing the structural arrangement, dimensions and scantlings.
  - Welding and structural details.
  - Connections between structural components (bolting).
  - Casting's chemical and mechanical properties.
  - Forging's chemical and mechanical properties.
  - Material grades for plate and sections.
- (l) Nozzle ring structure and nozzle support details if applicable to the application.
- (m) Propeller shaft bearing mounting and housing arrangement details, see also 6.3.6.
- (n) Details of propeller shaft and steering bearings, where roller bearings are used supporting calculations are to be submitted, see 6.3.7 and 6.6.6.
- (o) Propeller shaft seal details.
- (p) Details of propeller shaft and pod steering securing/locking and means of aligning the securing/locking arrangements.
- (q) Cooling systems piping system schematic.
- (r) Details of any lubricating oil conditioning systems (filtering/cooling/heating) and control arrangements necessary to ensure the continuous availability of the required lubricating oil quality to the propeller shaft bearings.
- (s) Details of installed condition monitoring equipment.
- (t) Details of the derivation of any duty factor used in the design of the steering gears.
- (u) Recommended installation, inspection, maintenance and component replacement procedures (see also 5.1.2). This is to include any in-water/underwater engineering procedures where recommended by the pod manufacturer. See also 6.5.7 and Section 10.



**Fig. 23.2.1 Pod co-ordinate system**

- (v) Identification of any potentially hazardous atmospheric conditions together with details of how the hazard will be countered, this should include a statement of the maximum anticipated air temperature within the pod during full power steady state operation, see 2.3.
- (w) Access and closing arrangements for pod unit inspection and maintenance.
- (x) Heat balance calculations for pods having an electric propulsion motor but no active cooling system, see 6.7.4.
- (y) Details of proposed testing and trials required by Section 9.
- (z) Details of emergency steering and pod securing arrangements. See 6.3.11.

2.2.2 Where an engineering and safety justification report is required, the following supporting information is to be submitted:

- A Failure Mode and Effects Analysis (FMEA), see 2.5.
- Design standards and assumptions.
- Limiting operating parameters.
- A statement and evidence in respect of the anticipated reliability of any non-duplicated components.

## 2.3 Pod internal atmospheric conditions

2.3.1 Machinery and electrical equipment installed within the pod unit are to be suitable for operation, without degraded performance, at the maximum anticipated air temperature and humidity conditions within the pod unit with the pod operating at its maximum continuous rating in sea water of not less than 32°C after steady state operating conditions have been achieved.

2.3.2 Precautions are to be taken to prevent as far as reasonably practicable the possibility of danger to personnel and damage to equipment arising from the development of hazardous atmospheric conditions within the pod unit. Circumstances that may give rise to these conditions are to be identified and the counter measures taken are to be defined.

# Podded Propulsion Units

# Part 5, Chapter 23

Section 2

## 2.4 Global loads

2.4.1 The overall strength of the podded propulsion unit structure is to be based upon the maximum anticipated in-service loads, including the effects of ship manoeuvring and of ship motion (see Table 14.8.1 in Pt 3, Ch 14). This is to include the effects of any pod to pod and/or pod to ship hydrodynamic interference effects. The designer is to supply the following maximum load and moment values to which the unit may be subjected with a description of the operating condition at which they occur.

- $F_x$ , Force in the longitudinal direction;
- $F_y$ , Force in the transverse direction;
- $F_z$ , self weight, in water, augmented by the ship's pitch and heave motion and flooded volume where applicable, see Pt 3, Ch 14;
- $M_x$ , moment at the slewing ring about the pod unit's global longitudinal axis;
- $M_y$ , moment at the slewing ring about the pod unit's global transverse axis;
- $M_z$ , moment at the slewing ring about the pod unit's vertical axis (maximum dynamic duty steering torque on steerable pods).

The directions of the X, Y and Z axes, with the origin at the centre of the slewing ring, are shown in Fig. 23.2.1.

2.4.2 Where the maximum loads and moments described in 2.4.1 cannot be readily identified from calculation methods or are based on model testing, the estimated loads and moments are to be stated at pod unit steering angular intervals of 5 degrees over the range from ahead to astern for the relevant combinations of shaft rotational and ship speed. In the case of pod to pod and/or pod to ship hydrodynamic interaction effects these must be defined for the most severely affected propulsor.

2.4.3 Where control systems are installed to limit the operation of the podded drive to defined angles at defined ship speeds, this information may be taken into consideration when determining the pod unit loading.

2.4.4 Where pod units are fixed about their Z axis, then maximum global loads, to be used as the basis of the structural appraisal, are to be determined for inflows in 5 degree increments between the extremes of anticipated inflow angle during manoeuvring with ship at full speed and maximum propeller thrust.

## 2.5 Failure Modes and Effects Analysis (FMEA)

2.5.1 An FMEA is to be carried out where a single podded propulsion unit is the vessel's sole means of propulsion, see 2.1.1. The FMEA is to identify components where a single failure could cause loss of all propulsion and/or steering capability and the proposed arrangements for preventing and mitigating the effects of such a failure.

2.5.2 The FMEA is to be carried out using the format presented in Table 22.2.1 in Chapter 22 or an equivalent format that addresses the same reliability issues. Analyses in accordance with IEC 60812, *Analysis techniques for system reliability – Procedure for failure mode and effects analysis (FMEA)*, or IMO MSC Resolution 36(63) Annex 4 – *Procedures for Failure Mode and Effects Analysis*, would be acceptable.

2.5.3 The FMEA is to be organised in terms of equipment and function. The effects of item failures at a stated level and at higher levels are to be analyzed to determine the effects on the system as a whole. Actions for mitigation of the effects of failure are to be determined, see 2.5.1.

2.5.4 The FMEA is to:

- (a) identify the equipment or sub-system and mode of operation;
- (b) identify potential failure modes and their causes;
- (c) evaluate the effects on the system of each failure mode;
- (d) identify measures for reducing the risks associated with each failure mode;
- (e) identify measures for preventing failure; and
- (f) identify trials and testing necessary to prove conclusions.

2.5.5 At sub-system level it is acceptable, for the purpose of these Rules, to consider failure of equipment items and their functions, e.g. failure of a pump to produce flow or pressure head. It is not required that the failure of components within that pump be analyzed. In addition, their failure need only be dealt with as a cause of failure of the pump.

2.5.6 Where FMEA is used for consideration of systems that depend on software-based functions for control or co-ordination, the analysis is to investigate failure of the functions rather than a specific analysis of the software code itself.

## 2.6 Ice Class requirements

2.6.1 Where an ice class notation is included in the class of a ship, additional requirements as detailed in Chapter 9 and Pt 3, Ch 9 are to be complied with as applicable.

# Podded Propulsion Units

# Part 5, Chapter 23

Sections 3, 4 & 5

## ■ Section 3 Functional capability

### 3.1 General

3.1.1 The arrangement of podded propulsion units is to be such that the ship can be satisfactorily manoeuvred to a declared performance capability. The operating conditions covered are to include the following:

- (a) Maximum continuous shaft power/speed to the propeller in the ahead condition at the declared steering angles and sea conditions.
- (b) Manoeuvring speeds of the propeller shaft in the ahead and astern direction at the declared steering angles and sea conditions.
- (c) The stopping manoeuvre described in Ch 1,5.2.2(b).
- (d) All astern running conditions for the ship.
- (e) Manoeuvring in ice where ice class is required.

3.1.2 In general, the steering mechanism is to be capable of turning the pod between the declared steering angle limits at an average rotational speed of not less than 0,4 rev/min with the ship initially operating at its maximum ahead service speed.

3.1.3 The steering mechanism for podded units used for Dynamic Positioning applications with an associated class notation, is to be capable of a rotational speed of not less than 1,5 rev/min.

## ■ Section 4 Materials

### 4.1 General

4.1.1 The materials used for major structural and machinery components are to be manufactured and tested in accordance with the requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials). These components include hull support structure, pod body, pod strut, shafting and propellers.

4.1.2 Components of novel design or components manufactured from materials not covered by the Rules for Materials are to be subject to evaluation and approval by Lloyd's Register (hereinafter referred to as 'LR') prior to manufacture.

4.1.3 Material specifications, see 2.2.1(f), for propulsion shaft and slewing ring bearings, gearing and couplings are to be approved by LR prior to manufacture. The specification is to include details of the grade of material, including the target range of chemical composition that is to be reported on the certificate, the required mechanical properties, heat treatment details including temperatures and hold times, details of necessary non-destructive examinations including acceptance levels. Additionally, any steel cleanness or microstructure requirements are to be included. These components are to be manufactured under survey.

4.1.4 For propulsion shaft rolling element bearings, the amount of retained austenite is to be determined and is not to exceed 4 per cent for nominally bainitic structures.

4.1.5 Where load carrying threaded fasteners screw directly into structural castings, the integrity of the casting is to be such that there is no porosity or shrinkage in the area of the connection.

## ■ Section 5 Structure design and construction requirements

### 5.1 Pod structure

5.1.1 Podded unit struts and pod bodies may be of cast, forged or fabricated construction or a combination of these construction methods.

5.1.2 Means are to be provided to enable the shaft, bearings and seal to be fully examined in accordance with the manufacturer's recommendations at docking Survey to the Surveyor's satisfaction.

5.1.3 When high tensile steel fasteners are used as part of the structural arrangement and there is a risk that these fasteners may come into contact with sea-water, carbon-manganese and low alloy steels with a specified tensile strength of greater than 950 N/mm<sup>2</sup> are not to be used due to the risk of hydrogen embrittlement.

5.1.4 For steerable pod units, an integral slewing ring is to be arranged at the upper extremity of the strut to provide support for the slewing bearing.

5.1.5 The strut is to have a smooth transition from the upper mounting to the lower hydrodynamic sections.

5.1.6 Vertical and horizontal plate diaphragms are to be arranged within the strut and, where necessary, secondary stiffening members are to be arranged.

5.1.7 Pod unit structure scantling requirements are shown in Table 23.5.1. Where the scantling requirements in Table 23.5.1 are not satisfied, direct calculations carried out in accordance with 5.3 may be considered.

5.1.8 The connection between the strut and the pod body should generally be effected through large radiused fillets in cast pod units or curved plates in fabricated pod units.

5.1.9 The structural response under the most onerous combination of loads is not to exceed the operational requirements of the propulsion or steering system components.

# Podded Propulsion Units

# Part 5, Chapter 23

Section 5

**Table 23.5.1 Podded propulsion unit structural requirements**


Location	Requirement	Notes
Strut external shell plating	Thickness, in mm, is to be not less than: $t = 0,0063s f (h_7 k)^{0,5}$	The minimum thickness of plating diaphragms and primary webs within the strut is to be not less than the Rule requirement for the strut external plating. For internal diaphragms, panel stiffening is to be provided where the ratio of spacing to plate thickness (s/t) exceeds 100. Where there are no secondary members, s is to be replaced by S.
Strut primary framing	The section modulus in cm <sup>3</sup> is to be not less than: $z = 7,75h_7 l_e^2 S k$	This does not apply to full breadth plate diaphragms.
Strut secondary stiffening	The section in cm <sup>3</sup> is to be not less than: $z = 0,0056h_7 l_e^2 s k$	This does not apply to full breadth plate diaphragms.
Cylindrical pod body external shell plating	Thickness, in mm, is to be not less than: $t = 3,0R_g (h_7 k)^{0,5}$	Not to be less than the Rule basic shell end thickness from Table 3.2.1 in Pt 3, Ch 3,2
Symbols		
$f$ = panel aspect ratio correction factor = $[1,1 - s/(2500S)]$ $h_7$ = $(T + C_w + 0.014V^2)$ $k$ = local higher tensile steel factor, as in Pt 3, Ch 2 $l_e$ = effective span of the member under consideration, in metres $s$ = the frame spacing of secondary members, in mm $C_w$ = design wave amplitude, in metres, as in Pt 4, Ch 1,1.5 $R_g$ = mean radius of pod body tube, in metres $S$ = the spacing of primary members, in metres $T$ = the vessel scantling draft, in metres, as in Pt 3, Ch 1,6.1 $V$ = ship service speed, in knots, as in Pt 3, Ch 1,6.1		

## 5.2 Hull support structure

5.2.1 For supporting the main slewing bearing outer races, a system of primary structural members is to be provided in order to transfer the maximum design loads and moments from the podded propulsion unit into the ship's hull without undue deflection. Due account is also to be taken of the loads induced by the maximum ship's motions in the vertical direction resulting from combined heave and pitch motion of the ship. Account is also to be taken of any manoeuvring conditions that are likely to give rise to high mean or vibratory loadings induced by the podded propulsion unit. See 2.2.1(c).

5.2.2 The hull support structure in way of the slewing bearing should be sufficiently stiff that the bearing manufacturer's limits on seating flatness are not exceeded due to hull flexure as a consequence of the loads defined under 5.2.1.

5.2.3 Generally, the system of primary members is to comprise a pedestal girder directly supporting the slewing ring and bearing. The pedestal girder is to be integrated with the ship's structure by means of radial girders and transverses aligned at their outer ends with the ship's bottom girders and transverses, see Fig. 23.5.1. Proposals to use alternative arrangements that provide an equivalent degree of strength and rigidity may be submitted for appraisal.

**Fig. 23.5.1 Hull support structure**

5.2.4 The ship's support structure in way of the podded unit may be of double or single bottom construction. Generally, podded drives should be supported where practical within a double bottom structure; however final acceptance of the supporting arrangements will be dependent upon satisfying the stress criteria set out in Table 23.5.2, see also 5.3.5.

# Podded Propulsion Units

## Part 5, Chapter 23

Sections 5 &amp; 6

**Table 23.5.2 Direct calculation maximum permissible stresses**

Permissible stress values		
Location	Podded drive structure	Podded drive/hull interface
X-Y shear stress	$0,26\sigma_0$	$0,35\sigma_0$
Direct stress due to bending	$0,33\sigma_0$	$0,63\sigma_0$
Von Mises stress	$0,40\sigma_0$	$0,75\sigma_0$
Localised Von Mises peak stresses	$\sigma_0$	$\sigma_0$
Symbols		
$\sigma_0$ = minimum yield strength of the material		
<b>NOTES</b> 1. The values stated above are intended to give an indication of the levels of stress in the pod and ship structure for the maximum loads which could be experienced during normal service. 2. If design is based on extreme or statistically low probability loads, then proposals to use alternative acceptance stress criteria may be considered.		

5.2.5 The shell envelope plating and tank top plating in way of the aperture for the podded drive (i.e. over the extent of the radial girders shown in Fig. 23.5.1) are to be increased by 50 per cent over the Rule minimum thickness to provide additional local stiffness and robustness. However the thickness of this plating is not to be less than the actual fitted thickness of the surrounding shell or tank top plating.

5.2.6 The scantlings of the primary support structure in way of the podded drive are to be based upon the limiting design stress criteria specified in Table 23.5.2, *see also* 5.3.5. Primary member scantlings are, however, not to be less than those required by Pt 3, Ch 6,5.

5.2.7 The pedestal girder is to have a thickness not less than the required shell envelope minimum Rule thickness in way. Where abutting plates are of dissimilar thickness then the taper requirements of Pt 3, Ch 10,2 are to be complied with.

5.2.8 In general, full penetration welds are to be applied at the pedestal girder boundaries and in way of the end connections between the radial girders and the pedestal girder. Elsewhere, for primary members, double continuous fillet welding is to be applied using a minimum weld factor of 0,34.

### 5.3 Direct calculations

5.3.1 Finite element or other direct calculation techniques may be employed in the verification of the structural design. The mesh density used is to be sufficient to accurately demonstrate the response characteristics of the structure and to provide adequate stress and deflection information. A refined mesh density is to be applied to geometry transition areas and those locations where high localised stress or stress gradients are anticipated.

5.3.2 Model boundary constraints are generally to be applied in way of the slewing ring/ship attachment only.

5.3.3 The loads applied to the mathematical model, *see* 2.4.1, are to include the self weight, dynamic acceleration due to ship motion, hydrodynamic loads, hydrostatic pressure, propeller forces and shaft bearing support forces. In situations where a pod can operate in the flooded conditions or where flooding of a pod adds significant mass to the pod, details are to be included.

5.3.4 Based on the most onerous combination of normal service loading conditions, the stress criteria shown in Table 23.5.2 are not to be exceeded. *See also* 2.2.1(c).

5.3.5 Where the structural design is based on a fatigue assessment and the stress criteria shown in Table 23.5.2 are not applicable, details of cumulative load history and stress range together with the proposed acceptance criteria are to be submitted for consideration.

## Section 6 Machinery design and construction requirements

### 6.1 General

6.1.1 The requirements detailed in Chapter 1 are applicable.

### 6.2 Gearing

6.2.1 If gearing is used in the propulsion system then the requirements of Chapter 5 are applicable.

# Podded Propulsion Units

## Part 5, Chapter 23

Section 6

### 6.3 Propulsion shafting

6.3.1 In addition to meeting the requirements of Chapter 6 and Chapter 8, the pod propulsion shafting supporting an electric motor is to be sufficiently stiff that both static and dynamic shaft flexure are within the motor manufacturer's limits for all envisaged operating conditions.

6.3.2 There is to be no significant lateral vibration response that may cause damage to the shaft seals within  $\pm 20$  per cent of the running speed range. For vibration analysis computations the influence of the slewing ring and shaft bearing stiffnesses together with the contribution from the seating stiffnesses are to be included in the calculation procedures.

6.3.3 As an alternative to the requirements of Chapter 6, a fatigue strength analysis of shafting components indicating a factor of safety of 1,5 at the design loads based on a suitable fatigue failure criterion may be submitted for consideration. The effects of stress concentrations, material properties and operating environment are to be taken into account.

6.3.4 With the exception of the propeller connection (requirements stated in Chapter 7) couplings relying on friction are to have a factor of safety of 2,5 against slippage at the maximum rated torque. In order to reduce the possibility of fretting, a grip stress of not less than 20 N/mm<sup>2</sup> is to be attained.

6.3.5 The effects of motor short-circuit torque on the shafting system should not prevent continued operation once the fault has been rectified.

6.3.6 The arrangement of shaft bearings is to take account of shaft thermal expansion, misalignment of bearings, shaft slope through the bearings and manufacturing tolerances. Additionally, the influence of the pod deflection on the shaft bearing alignment is to be considered under the most onerous mechanical and hydrodynamic loading conditions.

6.3.7 Propeller shaft roller bearing life calculations are to take account of the following loadings:

- Shaft, motor, propeller and other shaft appendages' weights;
- Forces due to ship's motion;
- The propeller-generated forces and moments about the three Cartesian axes related to the shaft;  $f_x$ ,  $f_y$ ,  $f_z$ ,  $m_x$ ,  $m_y$ ,  $m_z$ , see Fig. 23.2.1.
- Variance of propeller-generated forces and moments with pod azimuth angle. This load variance should take account of the motor control characteristics;
- Forces due to pod rotation, including gyroscopic forces;
- A predicted azimuth service profile for the pod indicating the proportion of time spent at various azimuth angles;
- Loads due to hydrodynamic interaction between pods;
- Any additional loads experienced during operation in ice conditions (for Ice Class notations);

- Where validation of the above loadings is available, detailed calculations must demonstrate that the bearing life when operating at the normal duty profile will comfortably exceed the time between 5-yearly surveys. Parameters used to justify the bearing life, i.e. those related to oil cleanliness, viscosity limits and material quality are to be quoted.

6.3.8 Where detailed validation of the loadings identified in 6.3.7. is not available, the calculations for roller bearings are to indicate a bearing life greater than 65,000 hours at the maximum continuous rating of the podded drive taking into account the azimuth angle duty cycle. Any parameters used to justify this life, i.e. those related to oil cleanliness, water contamination and viscosity limits are to be quoted. Proposals for the use of a shaft bearing of life less than 65,000 hours will be considered on application with details of alleviating factors and supporting documentation; however, this bearing life must exceed the time between surveys.

6.3.9 The design of the shaft line bearings is to take account of the maximum and minimum operating temperatures likely to be encountered during both a voyage cycle and, more widely, during the ship's operational life. Furthermore, any anticipated temperature distributions through the bearing components and structures are to be included in the design calculations.

6.3.10 Means are to be provided for detecting shaft bearing deterioration. Where rolling element shaft bearings are used in single pod applications or in pods where the motor power exceeds 6 MW, vibration monitoring of the shaft bearings is to be provided. The bearing monitoring system is to be suitable for the local bearing conditions and is to be able to differentiate from other vibration sources such as propeller cavitation or ship motions.

6.3.11 On multi podded ships, means are to be provided to hold the propeller on an inoperable unit stationary whilst the other pod(s) propel the vessel at a manoeuvring speed of not less than 7 knots. Operating instructions displayed at the holding mechanism's operating position are to include a direction to inform the bridge of any limitation in ship's speed required as a result of the holding mechanism being activated.

6.3.12 Shaft seals for maintaining the watertight integrity of the pod are to be Type Approved to a standard acceptable to LR. The seals are to be designed to withstand the extremes of operation for which they are intended and this is to include extremes of temperature, vibration, pressure and shaft movement.

6.3.13 In single pod installations, the integrity of shaft seals is to be evaluated on the basis of a double failure. In such installations, seal duplication is to be used with indication of failure of one seal being provided.

### 6.4 Propeller

6.4.1 The requirements of Chapter 7 are to be complied with.

# Podded Propulsion Units

# Part 5, Chapter 23

Section 6

6.4.2 Where propeller scantlings have been determined by a detailed fatigue analysis, based on reliable wake survey data as described in Ch 7,3.1.7, a factor of safety of 1,5 against suitable fatigue failure criteria is to be demonstrated. The effects of fillet stress concentrations, residual stress, fluctuating loads and material properties are to be taken into account.

## 6.5 Bearing lubrication system

6.5.1 The bearing lubrication system is to be arranged to provide a sufficient quantity of lubricating oil of a quality, viscosity and temperature acceptable to the bearing manufacturer under all ship operating conditions.

6.5.2 In addition to the requirements detailed in this Section, the requirements of Chapter 14, sub-Sections 8.1, 8.5, 8.7 and 8.9 are to be complied with.

6.5.3 The sampling points required by Ch 14,8.9 are to be located such that the sample taken is representative of the oil present at the bearing.

6.5.4 Where continuous operation of the lubricating oil system is essential for the pod to operate at its maximum continuous rating, a standby pump in accordance with Ch 14,8.2.2 is to be provided. In such systems, provision is to be made for the efficient filtration of the oil. The filters are to be capable of being cleaned without stopping the pod.

6.5.5 Where bearings are grease lubricated, means are to be provided for collecting waste grease to enable analysis for particulates and water. The arrangements for collecting waste grease are to be in accordance with the pod manufacturer's recommendations.

6.5.6 Pipework conveying lubricating oil is to be sited such that any possible leakage from joints will not impinge on electrical equipment, hot surfaces or other sources of ignition, see also Ch 13,2.9.3.

6.5.7 The procedures for flushing the lubrication system are to be defined. This procedure is to embrace the following conditions:

- (a) Initial installation.
- (b) Post maintenance situations.
- (c) Major dry-docking refits.

See Section 10.

## 6.6 Steering system

6.6.1 The requirements of Chapter 19, Sections 1, 2, 3, 6, 7 and 8 are to be complied with where applicable. See also 3.1.

6.6.2 For vessels where a single podded propulsion unit is the sole means of propulsion, the requirement for auxiliary steering gear in Ch 19,2 is to be achieved by means of two or more identical power units.

6.6.3 Steering arrangements, other than of the hydraulic type, may be accepted provided that there are means of limiting the maximum torque to which the steering arrangement may be subjected.

6.6.4 The steering mechanism is to be provided with power that is sufficient for the maximum steering torques present during the declared functional capability identified in 3.1 and is to be demonstrated for the most onerous specified manoeuvring trial, see Section 9.

6.6.5 Geared arrangements employed for steering are to consider the following conditions:

- A design maximum dynamic duty steering torque,  $M_z$ , see 2.4.1;
- A static duty ( $\leq 10^3$  load cycles) steering torque. The static duty steering torque should not be less than  $M_w$ , the maximum torque which can be generated by the steering gear mechanism.

The minimum factors of safety, as derived using ISO 6336 Calculation of load capacity of spur and helical gears, or a recognized National Standard, are to be 1.5 on bending stress and 1,0 on Hertzian contact stress. The use of a duty factor in the dynamic duty strength calculations is acceptable but the derivation of such a factor, based on percentage of time spent at a percentage of the maximum working torque, should be submitted to LR for consideration and acceptance.

6.6.6 Slewing ring bearing capacity calculations are to take account of:

- Pod weight in water;
- Gyroscopic forces from the propeller and motor;
- Hydrodynamic loads on pod; and
- Forces due to ship's motions.

The calculations are to demonstrate that the factor of safety against the maximum combination of the above forces is not less than 2. The calculations are to be carried out in accordance with a suitable declared standard.

6.6.7 Means of allowing the condition of the slewing gears and bearings to be assessed are to be provided.

6.6.8 On multi podded ships, means are to be provided to secure each pod unit's slewing mechanism in its mid position in the event of a steering system failure. These arrangements are to be of sufficient strength to hold the pod in position at the ship's manoeuvring speed to be taken as not less than 7 knots (see also 6.3.9). Operating instructions displayed at the securing mechanism's operating position are to include a direction to inform the bridge of any limitation in ship's speed required as a result of the securing mechanism being activated.

## 6.7 Ventilation and cooling systems

6.7.1 Means are to be provided to ensure that air used for motor cooling purposes is of a suitable temperature and humidity as well as being free from harmful particles.

6.7.2 Cooling water supplies are to comply with Ch 14,7. See also Pt 6, Ch 2,8.6.



## Podded Propulsion Units

## Part 5, Chapter 23

Sections 6, 7 &amp; 8

6.7.3 On single podded installations, a standby cooling arrangement of the same capacity as the main cooling system, is to be provided and available for immediate use.

6.7.4 For pods having an electric propulsion motor but no active cooling system, heat balance calculations as required by 2.2.1(x) are to demonstrate that the pod unit and associated systems are able to function satisfactorily over all operating conditions, see Ch 1,3.5.

### 6.8 Pod drainage requirements

6.8.1 Unless the electrical installation is suitable for operation in a flooded space, means are to be provided to ensure that leakage from shaft bearings or the propeller seal do not reach the motor windings, or other electrical components. Account is to be taken of cooling air flow circulating within the pod unit.

6.8.2 Two independent means of drainage are to be provided so that liquid leakage may be removed from the pod unit at all design angles of heel and trim, see Ch 1,3.6.

6.8.3 Pipework conveying leakage from the pod is to be sited such that any leakage from joints will not impinge on electrical equipment, see *also* Ch 13,2.9.3.

### 6.9 Hydraulic actuating systems

6.9.1 Hydraulic actuating systems are to comply with Ch 14,9 and Ch 19,3 as applicable.

## Section 7 Electrical equipment

### 7.1 General

7.1.1 The electrical installation is to be designed, constructed and installed in accordance with the requirements of Pt 6, Ch 2.

7.1.2 Means are to be provided to prevent electrical currents flowing across shaft bearings, which may cause their premature failure.

7.1.3 Steering gear electrical systems are to comply with Ch 19,5.

## Section 8 Control engineering arrangements

### 8.1 General

8.1.1 Control engineering arrangements are to be in accordance with Pt 6, Ch 1.

8.1.2 Steering gear control, monitoring and alarm systems are to comply with Ch 19,4 and Ch 19,5.

8.1.3 Steering control is to be provided for podded drives from the navigating bridge, the main machinery control station and locally.

8.1.4 An indication of the angular position of the podded propulsion unit(s) and the magnitude of the thrust is to be provided at each station from which it is possible to control the direction of thrust. This indication is to be independent of the steering control system.

8.1.5 Means are to be provided at the remote control station(s), independent of the podded drive control system, to stop each podded drive in an emergency. See *also* Pt 6, Ch 2,15.3.7.

8.1.6 Where programmable electronic equipment is used to prevent loads exceeding those for which the system has been designed (see 2.4.3), then either:

- (a) A fully independent hard wired backup is to be provided; or
- (b) The software is to be certified in accordance with LR's Software Conformity Assessment System – Assessment Module GEN1 (1994) and have an independent solution showing redundancy with design diversity, etc., see Pt 6, Ch 1,2.12 of the Rules.

8.1.7 Where a propulsion system which includes a podded propulsor unit is controlled by a series of interactive and integrated programmable electronic systems, then these are to comply with the requirements of Pt 6, Ch 1,2.13 of the Rules.

### 8.2 Monitoring and alarms

8.2.1 The requirements for alarms and monitoring arrangements are to be in accordance with Ch 19,5.3 and Table 23.8.1.

8.2.2 Alarms specified in Table 23.8.1 are to be in accordance with the alarm system specified by Pt 6, Ch 1,2,3.

8.2.3 Sensors for control, monitoring and alarm systems required by the Rules and located within the pod are to be duplicated in order that a single sensor failure does not inhibit system functionality.

8.2.4 Pod unit bilge pumping arrangements are to function automatically in the event of a high liquid level being detected in the pod unit.

8.2.5 The number and location of bilge level detectors are to be such that accumulation of liquids will be detected at all design angles of heel and trim.

8.2.6 Condition monitoring arrangements are not to interface with the operation of safety systems which may cause slow-down or shut-down of the propulsion system. See *also* Pt 6, Ch 1,2.6.9.

# Podded Propulsion Units

## Part 5, Chapter 23

Sections 8, 9 &amp; 10

**Table 23.8.1 Specific alarms for pod control systems**

Item	Alarm	Note
Podded drive azimuth angle	—	Indicator, see 8.1.4
Propulsion motors	Overload, power failure	To be indicated on the navigating bridge
Hydraulic oil system pressure	Low	To be indicated on the navigating bridge
Lubricating oil supply pressure	Low	If separate forced lubrication for shaft bearings; to be indicated on the navigating bridge
Lubricating oil temperature	High	
Lubricating oil tank level for motor bearings	Low	
Water in lubricating oil for motor bearings	High	Required for single podded propulsion units only
Motor cooling air inlet temperature	High	
Motor cooling air outlet temperature	High	
Motor cooling air flow	Low	
Shaft bearing vibration monitoring	High	See 6.3.10. Monitoring is to allow bearing condition to be gauged using trend analysis
Bilge pump operation	Abnormal	Alarm set to indicate a frequency or duration exceeding that which would normally be expected
Bilge level	High	

### Section 9 Testing and trials

#### 9.1 General

9.1.1 The following requirements are to be complied with:

- Ch 1,5.2 for sea trials.
- Ch 19,7.2 for steering trials.

In addition, the functional capability specified in 3.1.1 is to be demonstrated to the Surveyor's satisfaction.

9.1.2 The actual values of steering torque are to be verified during sea trials to confirm that the design maximum dynamic duty torque has not been exceeded.

9.1.3 Electric motor cooling systems are to be verified, as far as possible, to ensure that they are capable of limiting the extremes of ambient temperature to those specified in 2.3.1.

9.1.4 Any trials and testing identified from the FMEA report, see 2.5.4(f), are also to be carried out.

### Section 10

### Installation, maintenance and replacement procedures

#### 10.1 General

10.1.1 All podded propulsion units are to be supplied with a copy of the manufacturer's installation and maintenance manual that is pertinent to the actual equipment. See 2.2.1(u).

10.1.2 The manual required by 10.1.1 is to be placed on board and is to contain the following information:

- Description of the podded propulsion unit with details of function and design operating limits. This is also to include details of support systems such as lubrication, cooling and condition monitoring arrangements.
- Identification of all components together with details of any that have a defined maximum operating life.
- Instructions for installation of unit(s) on board ship with details of any required specialised equipment.
- Instructions for commissioning at initial installation and following maintenance.
- Maintenance and service instructions to include inspection/renewal of bearings, seals, motors, slip rings and other major components. This is also to include component fitting procedures, special environmental arrangements, clearance and push-up measurements and lubricating oil treatment where applicable.
- Actions required in the event of fault/failure conditions being detected.
- Precautions to be taken by personnel working during installation and maintenance.



© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

CONTROL, ELECTRICAL, REFRIGERATION AND FIRE

JULY 2007

PART 6

**Lloyd's**  
**Register**

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.

---

PART	1	REGULATIONS
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
PART	3	SHIP STRUCTURES (GENERAL)
PART	4	SHIP STRUCTURES (SHIP TYPES)
PART	5	MAIN AND AUXILIARY MACHINERY
<b>PART</b>	<b>6</b>	<b>CONTROL, ELECTRICAL, REFRIGERATION AND FIRE</b>
		<b>Chapter 1 Control Engineering Systems</b>
		<b>2 Electrical Engineering</b>
		<b>3 Refrigerated Cargo Installations</b>
		<b>4 Fire Protection, Detection and Extinction Requirements</b>
PART	7	OTHER SHIP TYPES AND SYSTEMS

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.





<b>CHAPTER</b>	<b>1</b>	<b>CONTROL ENGINEERING SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Plans
	1.3	Control, alarm and safety equipment
	1.4	Alterations and additions
<b>Section</b>	<b>2</b>	<b>Essential features for control, alarm and safety systems</b>
	2.1	General
	2.2	Control stations for machinery
	2.3	Alarm systems, general requirements
	2.4	Safety systems, general requirements
	2.5	Control systems, general requirements
	2.6	Bridge control for main propulsion machinery
	2.7	Valve control systems
	2.8	Fire detection alarm systems
	2.9	Fixed water-based local application fire-fighting systems
	2.10	Programmable electronic systems – General requirements
	2.11	Data communication links
	2.12	Programmable electronic systems – Additional requirements for essential services and safety critical systems
	2.13	Programmable electronic systems – Additional requirements for integrated systems
<b>Section</b>	<b>3</b>	<b>Control and supervision of unattended machinery</b>
	3.1	General
	3.2	Oil engines for propulsion purposes
	3.3	Steam turbine machinery for propulsion purposes
	3.4	Gas turbine machinery
	3.5	Main, auxiliary and other boilers
	3.6	Thermal fluid heaters
	3.7	Inert gas generators
	3.8	Incinerators
	3.9	Auxiliary engines and auxiliary steam turbines
	3.10	Controllable pitch propellers and transverse thrust units
	3.11	Monitoring in cargo pump rooms
	3.12	Electric system
	3.13	Steering gear
	3.14	Waterjets
	3.15	Miscellaneous machinery
<b>Section</b>	<b>4</b>	<b>Unattended machinery space(s) – UMS notation</b>
	4.1	General
	4.2	Alarm system for machinery
	4.3	Bridge control for main propulsion machinery
	4.4	Control stations for machinery
	4.5	Fire detection alarm system
	4.6	Bilge level detection
	4.7	Supply of electric power, general
<b>Section</b>	<b>5</b>	<b>Machinery operated from a centralized control station – CCS notation</b>
	5.1	General requirements
	5.2	Centralized control station for machinery
<b>Section</b>	<b>6</b>	<b>Integrated computer control – ICC notation</b>
	6.1	General
	6.2	General requirements
	6.3	Operator stations
<b>Section</b>	<b>7</b>	<b>Trials</b>
	7.1	General
	7.2	Unattended machinery space operation – <b>UMS</b> notation
	7.3	Operation from a centralized control station – <b>CCS</b> notation
	7.4	Record of trials

<b>CHAPTER</b>	<b>2</b>	<b>ELECTRICAL ENGINEERING</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Plans
	1.3	Surveys
	1.4	Additions or alterations
	1.5	Definitions
	1.6	Design and construction
	1.7	Quality of power supplies
	1.8	Ambient reference and operating conditions
	1.9	Inclination of ship
	1.10	Location and construction
	1.11	Earthing of non-current carrying parts
	1.12	Bonding for the control of static electricity
	1.13	Alarms
	1.14	Operation under fire conditions
	1.15	Protection of electrical equipment against the effects of lightning strikes
<b>Section</b>	<b>2</b>	<b>Main source of electrical power</b>
	2.1	General
	2.2	Number and rating of generators and converting equipment
	2.3	Starting arrangements
	2.4	Prime mover governors
	2.5	Main propulsion driven generators not forming part of the main source of electrical power
<b>Section</b>	<b>3</b>	<b>Emergency source of electrical power</b>
	3.1	General
	3.2	Emergency source of electrical power in passenger ships
	3.3	Emergency source of electrical power in cargo ships
	3.4	Starting arrangements
	3.5	Prime mover governor
	3.6	Radio installation
<b>Section</b>	<b>4</b>	<b>External source of electrical power</b>
	4.1	Temporary external supply
	4.2	Permanent external supply
<b>Section</b>	<b>5</b>	<b>Supply and distribution</b>
	5.1	Systems of supply and distribution
	5.2	Essential services
	5.3	Isolation and switching
	5.4	Insulated distribution systems
	5.5	Earthed distribution systems
	5.6	Diversity factor
	5.7	Lighting circuits
	5.8	Motor circuits
	5.9	Motor control
<b>Section</b>	<b>6</b>	<b>System design – Protection</b>
	6.1	General
	6.2	Protection against short-circuit
	6.3	Protection against overload
	6.4	Protection against earth faults
	6.5	Circuit-breakers
	6.6	Fuses
	6.7	Circuit-breakers requiring back-up by fuse or other device
	6.8	Protection of generators
	6.9	Load management
	6.10	Feeder circuits
	6.11	Motor circuits
	6.12	Protection of transformers

---

<b>Section</b>	<b>7</b>	<b>Switchgear and control gear assemblies</b>
	7.1	General requirements
	7.2	Busbars
	7.3	Circuit-breakers
	7.4	Contactors
	7.5	Creepage and clearance distances
	7.6	Degree of protection
	7.7	Distribution boards
	7.8	Earthing of high-voltage switchboards
	7.9	Fuses
	7.10	Handrails or handles
	7.11	Instruments for alternating current generators
	7.12	Instrument scales
	7.13	Labels
	7.14	Protection
	7.15	Wiring
	7.16	Position of switchboards
	7.17	Switchboard auxiliary power supplies
	7.18	Testing
	7.19	Disconnectors and switch-disconnectors
<b>Section</b>	<b>8</b>	<b>Rotating machines</b>
	8.1	General requirements
	8.2	Rating
	8.3	Temperature rise
	8.4	Generator control
	8.5	Overloads
	8.6	Machine enclosure
	8.7	Direct current machines
	8.8	Survey and testing
<b>Section</b>	<b>9</b>	<b>Converter equipment</b>
	9.1	Transformers
	9.2	Semiconductor equipment
	9.3	Uninterruptible power systems
<b>Section</b>	<b>10</b>	<b>Electric cables and busbar trunking systems (busways)</b>
	10.1	General
	10.2	Testing
	10.3	Voltage rating
	10.4	Operating temperature
	10.5	Construction
	10.6	Conductor size
	10.7	Correction factors for cable current rating
	10.8	Installation of electric cables
	10.9	Mechanical protection of cables
	10.10	Cable support systems
	10.11	Penetration of bulkheads and decks by cables
	10.12	Installation of electric cables in protective casings
	10.13	Single-core electric cables for alternating current
	10.14	Electric cable ends
	10.15	Joints and branch circuits in cable systems
	10.16	Busbar trunking systems (bustrunks)
<b>Section</b>	<b>11</b>	<b>Batteries</b>
	11.1	General
	11.2	Construction
	11.3	Location
	11.4	Installation
	11.5	Ventilation
	11.6	Charging facilities
	11.7	Recording of batteries for emergency and essential services

---

<b>Section</b>	<b>12</b>	<b>Equipment – Heating, lighting and accessories</b>
	12.1	Heating and cooking equipment
	12.2	Lighting – General
	12.3	Incandescent lighting
	12.4	Fluorescent lighting
	12.5	Discharge lighting
	12.6	Socket outlets and plugs
	12.7	Enclosures
<b>Section</b>	<b>13</b>	<b>Electrical equipment for use in explosive gas atmospheres or in the presence of combustible dusts</b>
	13.1	General
	13.2	Selection of equipment
	13.3	Installation of electrical equipment
	13.4	Dangerous zones and spaces
	13.5	Semi-enclosed spaces
	13.6	Ventilation
	13.7	Pressurization
	13.8	Cable and cable installation
	13.9	Requirements for tankers intended for the carriage in bulk of oil cargoes having a flash point not exceeding 60°C (closed-cup test)
	13.10	Requirements for ships for the carriage of liquefied gases in bulk
	13.11	Requirements for ships intended for the carriage in bulk of other flammable liquid cargoes
	13.12	Special requirements for ships with spaces for carrying vehicles with fuel in their tanks, for their own propulsion
	13.13	Special requirements for ships intended for the carriage of dangerous goods
<b>Section</b>	<b>14</b>	<b>Navigation and manoeuvring systems</b>
	14.1	Steering gear
	14.2	Thruster systems for steering
	14.3	Thruster systems for dynamic positioning
	14.4	Thruster systems for manoeuvring
	14.5	Navigation lights
	14.6	Navigational aids
<b>Section</b>	<b>15</b>	<b>Electric propulsion</b>
	15.1	General
	15.2	Power requirements
	15.3	Propulsion control
	15.4	Protection of propulsion system
	15.5	Instruments
<b>Section</b>	<b>16</b>	<b>Fire safety systems</b>
	16.1	Fire detection and alarm systems
	16.2	Automatic sprinkler system
	16.3	Fixed water-based local application fire-fighting systems
	16.4	Fire pumps
	16.5	Refrigerated liquid carbon dioxide systems
	16.6	Fire safety stops
	16.7	Fire doors
	16.8	Fire dampers
	16.9	Fire-extinguishing media release
<b>Section</b>	<b>17</b>	<b>Crew and passenger emergency safety systems</b>
	17.1	Emergency lighting
	17.2	General emergency alarm system
	17.3	Public address system
	17.4	Escape route or low location lighting (LLL)

<b>Section</b>	<b>18</b>	<b>Ship safety systems</b>
	18.1	Watertight doors
	18.2	Stem and side shell doors
	18.3	Bow and inner doors
	18.4	Subdivision doors on vehicle decks
	18.5	Bilge pumps
<b>Section</b>	<b>19</b>	<b>Lightning conductors</b>
	19.1	General
<b>Section</b>	<b>20</b>	<b>Testing and trials</b>
	20.1	Testing
	20.2	Trials
	20.3	High voltage cables
	20.4	Hazardous areas
<b>Section</b>	<b>21</b>	<b>Spare gear</b>
	21.1	General
<b>CHAPTER</b>	<b>3</b>	<b>REFRIGERATED CARGO INSTALLATIONS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	Plans and particulars
	1.3	Materials
	1.4	Equipment to be constructed under survey
	1.5	Type approved equipment
	1.6	Notation and temperature conditions
	1.7	Novel arrangements and design
	1.8	Heat balance tests
	1.9	Controlled atmosphere (CA) systems
	1.10	Spare gear and refrigerated charge
<b>Section</b>	<b>2</b>	<b>Design criteria</b>
	2.1	General
	2.2	Refrigerants and classes of pipes
	2.3	Refrigeration units
	2.4	Refrigeration capacity
	2.5	Design pressures
	2.6	Insulation
<b>Section</b>	<b>3</b>	<b>Refrigerating machinery and refrigerant storage compartments</b>
	3.1	General
	3.2	Arrangements for compartments housing machinery using ammonia
	3.3	Gas storage compartments
	3.4	Compartments housing carbon dioxide containing equipment
<b>Section</b>	<b>4</b>	<b>Refrigeration plant, pipes, valves and fittings</b>
	4.1	General requirements for refrigerating compressors
	4.2	Reciprocating compressors
	4.3	Screw compressors
	4.4	Pressure vessels and heat exchangers
	4.5	Condensers, oil coolers and evaporators
	4.6	Liquid receivers
	4.7	Oil separators
	4.8	Air coolers and cooling grids
	4.9	Refrigerant pumps
	4.10	Condenser cooling water pumps
	4.11	Piping systems
	4.12	Joints
	4.13	Liquid level indicators
	4.14	Automatic expansion valves
	4.15	Overpressure protection devices

---

	4.16	Filters, driers and moisture indicators
	4.17	Purging devices
	4.18	Piping in way of refrigerated spaces
	4.19	Drainage from refrigerated spaces
	4.20	Corrosion protection of metal fixtures
	4.21	Pressure testing at manufacturers' works
	4.22	Pressure test after installation on board ship
<b>Section</b>	<b>5</b>	<b>Refrigerant detection systems</b>
	5.1	General
	5.2	Ammonia vapour detection and alarm equipment
<b>Section</b>	<b>6</b>	<b>Electrical installation</b>
	6.1	General
	6.2	Electrical equipment for use in explosive gas atmospheres
<b>Section</b>	<b>7</b>	<b>Instrumentation, control, alarm, safety and monitoring systems</b>
	7.1	Instrumentation
	7.2	Control, alarm and safety systems
	7.3	Temperature monitoring and recording
<b>Section</b>	<b>8</b>	<b>Personnel safety equipment and systems</b>
	8.1	Personnel safety equipment
	8.2	Personnel warning systems
<b>Section</b>	<b>9</b>	<b>Refrigerated cargo spaces</b>
	9.1	Airtightness of refrigerated spaces
	9.2	Insulation systems
	9.3	Access plugs and panels
	9.4	Air circulation and distribution
	9.5	Air refreshing arrangements
	9.6	Heating arrangements for fruit cargoes
<b>Section</b>	<b>10</b>	<b>Container ships fitted with refrigerating plant to supply cooled air to insulated containers in holds</b>
	10.1	General
	10.2	Additional information and plans
	10.3	Air coolers
	10.4	Air duct systems
	10.5	Duct air leakage and distribution tests
	10.6	Cell air conditioning arrangements
<b>Section</b>	<b>11</b>	<b>Acceptance trials</b>
	11.1	Tests after completion
	11.2	Thermographic survey
	11.3	Acceptance tests
	11.4	Sea trials
	11.5	Reporting of tests
<b>CHAPTER</b>	<b>4</b>	<b>FIRE PROTECTION, DETECTION AND EXTINCTION REQUIREMENTS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
<b>Section</b>	<b>2</b>	<b>Fire detection, protection and extinction</b>
	2.1	General provisions
	2.2	Definitions
	2.3	Surveys and maintenance
	2.4	Requirements

# Control Engineering Systems

# Part 6, Chapter 1

Section 1

## Section

- 1 **General requirements**
- 2 **Essential features for control, alarm and safety systems**
- 3 **Control and supervision of unattended machinery**
- 4 **Unattended machinery space(s) – UMS notation**
- 5 **Machinery operated from a centralized control station – CCS notation**
- 6 **Integrated computer control – ICC notation**
- 7 **Trials**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 This Chapter applies to all ships intended to be classed with Lloyd's Register (hereinafter referred to as 'LR'), and is in addition to other relevant Sections of the Rules.

1.1.2 Whilst these requirements satisfy the regulations of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments, attention should also be given to any relevant statutory requirements of the National Administration of the country in which the ship is to be registered.

1.1.3 Section 2 of this Chapter states requirements for alarm systems, safety systems and automatic or remote controls where fitted.

1.1.4 Section 3 of this Chapter states the essential alarms and safeguards which are required for unattended machinery as defined in 1.2.3, which under normal operating conditions is remotely controlled or is automatic in operation.

1.1.5 Section 4 of this Chapter states requirements which shall apply where it is intended to operate the ship with machinery spaces unattended. In general, ships complying with the requirements of Section 4 will be eligible for the class notation **UMS**, see Pt 1, Ch 2,2.

1.1.6 Section 5 of this Chapter states requirements which shall apply where it is intended to operate the ship with machinery spaces under continuous supervision from a centralized control station. In general, ships complying with the requirements of Section 5 will be eligible for the class notation **CCS**, see Pt 1, Ch 2,2.

1.1.7 Section 6 of this Chapter states requirements which shall apply where it is intended that the control and supervision of ship operational functions are computer based. In general ships complying with the requirements of Section 6 will be eligible for the class notation **ICC**, see Pt 1, Ch 2,2.

1.1.8 LR will be prepared to give consideration to special cases or to arrangements which are equivalent to the Rules.

### 1.2 Plans

1.2.1 Plans required by 1.2.2 to 1.2.7 are to be submitted in triplicate.

1.2.2 Where control, alarm and safety systems are intended for the machinery or equipment as defined in 1.2.3 the following are to be submitted:

- Description of operation with explanatory diagrams.
- Line diagrams of control circuits.
- List of monitored points.
- List of control points.
- List of alarm points.
- Test schedules (for both works testing and sea trials) which should include methods of testing and test facilities provided, see 1.3.1.
- Failure Mode and Effects Analysis (FMEA) where required by other sections of the Rules.
- List of safety functions and details of any overrides, including consequences of use, see 2.4.9 and 2.6.9.

1.2.3 Plans for the control, alarm and safety systems of the following are to be submitted:

- Air compressors.
- Bilge and ballast systems.
- Cargo pumping systems for tankers.
- Cargo and ballast pumps in hazardous areas.
- Controllable pitch propellers.
- Electric generating plant.
- Fixed water based local application fire-fighting systems, see 2.9.
- Incinerators.
- Inert gas generators.
- Main propelling machinery including essential auxiliaries.
- Miscellaneous machinery or equipment (where control, alarm and safety systems are specified by other Sections of the Rules).
- Oil fuel transfer and storage systems.
- Steam raising plant. (Boilers and their ancillary equipment).
- Steering gear.
- Thermal fluid heaters.
- Transverse thrust units.
- Valve position indicating systems.
- Waste-heat boiler.
- Waterjets for propulsion purposes.
- Cargo tank, ballast tank and void space instrumentation where such arrangements are specified by other sections of the Rules (e.g. water ingress detection, gas detection).

1.2.4 **Alarm systems.** Details of the overall alarm system linking the main control station, subsidiary control stations, the bridge area and accommodation are to be submitted.

# Control Engineering Systems

# Part 6, Chapter 1

Sections 1 & 2

**1.2.5 Programmable electronic systems.** In addition to the documentation required by 1.2.2 the following is to be submitted:

- System requirements specification.
- System integration plan, see 2.13.2.
- Failure Mode and Effects Analysis (FMEA), see 2.13.5
- Details of the hardware configuration in the form of a system block diagram, including input/output schedules.
- Hardware certification details, see 2.10.5 and 2.12.3.
- Software quality plans, including applicable procedures, see 2.10.21.
- Factory acceptance, integration and sea trial test schedules for hardware and software.

**1.2.6 Control station.** Location and details of control stations are to be submitted, e.g. control panels and consoles.

**1.2.7 Fire detection systems.** Plans showing the system operation and the type and location of all machinery space fire detector heads, manual call points and the fire detector indicator panel(s) are to be submitted. The plans are to indicate the position of the fire detectors in relation to significant items of machinery, ventilation and extraction openings.

**1.2.8 Approved system.** Where it is intended to employ a standard system which has been previously approved, plans are not required to be submitted, providing there have been no changes in the applicable Rule requirements. The building port, where applicable, and date of the previous approval is to be advised.

**1.2.9 Cables.** For details of instrumentation and control system cabling requirements, see Ch 2, 10.

## 1.3 Control, alarm and safety equipment

**1.3.1** Major units of equipment associated with control, alarm and safety systems as defined in 1.2.3 are to be surveyed at the manufacturers' works in accordance with the approved test schedule (see 1.2.2), and the inspection and testing are to be to the Surveyor's satisfaction.

**1.3.2** Equipment used in control, alarm and safety systems is to be suitable for its intended purpose, and accordingly, whenever practicable, be selected from the *List of Type Approved Products* published by LR. A copy of the *Procedure for LR Type Approval System* will be supplied on application. For fire detection alarm systems, see 2.8.8 and for programmable electronic systems, see 2.10.5 and 2.12.3.

**1.3.3** Where equipment requires a controlled environment, an alternative means is to be provided to maintain the required environment in the event of a failure of the normal air conditioning system, see also Table 1.3.12.

**1.3.4** Assessment of performance parameters, such as accuracy, repeatability, etc., are to be in accordance with an acceptable National or International Standard, e.g. IEC 60051, Direct acting indicating analogue electrical measuring instruments and their accessories..

**1.3.5** Special consideration will be given to arrangements that comply with a relevant and acceptable national or international standard, such as IEC 60092-504, *Electrical Installation on Ships – Special Features: Control and Instrumentation*.

## 1.4 Alterations and additions

**1.4.1** When an alteration or addition to the approved system(s) is proposed, plans are to be submitted for approval. The alterations or additions are to be carried out under survey and the installation and testing are to be to the Surveyor's satisfaction.

**1.4.2** Details of proposed software modifications are to be submitted for consideration. Where the modification may affect compliance with these Rules, proposals for verification and validation are also to be submitted.

**1.4.3** Software versions are to be uniquely identified by number, date or other appropriate means. Modifications are not to be made without also changing the version identifier. A record of changes to the system since the original issue (and their identification) is to be maintained and made available to the LR Surveyor on request.

## Section 2 Essential features for control, alarm and safety systems

### 2.1 General

**2.1.1** Where it is proposed to install control, alarm and safety systems to the equipment defined in 1.2.3 the applicable features contained in this Section are to be incorporated in the system design.

**2.1.2** Systems complying with ISO 17894, *Ships and marine technology – Computer applications – General principles for the development and use of programmable electronic systems in marine applications*, may be accepted as meeting the requirements of this Section, in which case evidence of compliance is to be submitted for consideration.

### 2.2 Control stations for machinery

**2.2.1** A system of alarm displays and controls is to be provided which readily ensures identification of faults in the machinery and satisfactory supervision of related equipment. This may be provided at a main control station or, alternatively at subsidiary control stations. In the latter case, a master alarm display is to be provided at the main control station showing which of the subsidiary control stations is indicating a fault condition.

**2.2.2** At the main control station (if provided) or close to the subsidiary stations (if fitted) means of communication with the bridge area, the accommodation for engineering personnel and, if necessary, the machinery space are to be provided.



# Control Engineering Systems

# Part 6, Chapter 1

## Section 2

2.2.3 Provision is to be made at the main control station, or subsidiary control stations as appropriate, for the operation of an engineers' alarm which is to be clearly audible in the engineers' accommodation.

2.2.4 Provision is to be made at the main control station and any other subsidiary control station from which the main propulsion and auxiliary machinery or associated equipment may be controlled to indicate which station is in control.

2.2.5 Control of machinery and associated equipment is to be possible only from one station at a time.

2.2.6 Changeover between control stations is to be arranged so that it may only be effected with the acceptance of the station taking control. The system is to be provided with interlocks or other suitable means to ensure effective transfer of control.

2.2.7 For additional requirements where control stations incorporate visual display units and keyboard input facilities, see 2.10.

## 2.3 Alarm systems, general requirements

2.3.1 Where an alarm system, which will provide warning of faults in the machinery and the safety and control systems, is to be installed, the requirements of 2.3.2 to 2.3.18 are to be satisfied.

2.3.2 Machinery, safety and control system faults are to be indicated at the relevant control stations to advise duty personnel of a fault condition. The presence of unrectified faults is to be clearly indicated at all times.

2.3.3 Alarms associated with machinery, safety and control system faults are to be clearly distinguishable from other alarms (e.g. fire, general alarm).

2.3.4 Where alarms are displayed as group alarms provision is to be made to identify individual alarms at the main control station (if fitted) or alternatively at subsidiary control stations.

2.3.5 All alarms are to be both audible and visual. If arrangements are made to silence audible alarms they are not to extinguish visual alarms.

2.3.6 Acknowledgement of visual alarms is to be clearly indicated.

2.3.7 Acknowledgement of alarms at positions outside a machinery space is not to silence the audible alarm or extinguish the visual alarm in that machinery space.

2.3.8 If an alarm has been acknowledged and a second fault occurs prior to the first being rectified, audible and visual alarms are again to operate. Where alarms are displayed at a local panel adjacent to the machinery and with arrangements to provide a group or common fault alarm at the main control room alarm display, then the occurrence of a second fault prior to the first alarm being rectified need only be displayed at the local panel, however, the group alarm is to be

re-initiated. Unacknowledged alarms on monitors are to be distinguished by either flashing text or a flashing marker adjacent to the text. A change of colour will not in itself be sufficient to distinguish between acknowledged and unacknowledged alarms.

2.3.9 For the detection of transient faults which are subsequently self-correcting, alarms are required to lock in until accepted.

2.3.10 The alarm system is to be arranged with automatic changeover to a standby power supply in the event of a failure of the normal power supply. Where an alarm system could be adversely affected by an interruption in power supply, changeover to the standby power supply is to be achieved without a break.

2.3.11 Failure of any power supply to the alarm system is to operate an audible and visual alarm.

2.3.12 The alarm system should be designed with self-monitoring properties. Insofar as practicable, any fault in the alarm system should cause it to fail to the alarm condition.

2.3.13 The alarm system is to be capable of being tested during normal machinery operation, see 7.1.2.

2.3.14 The alarm system is to be designed as far as practicable to function independently of control and safety systems such that a failure or malfunction in these systems will not prevent the alarm system from operating.

2.3.15 Disconnection or manual overriding of any part of the alarm system should be clearly indicated.

2.3.16 When alarm systems are provided with means to adjust their set point, the arrangements are to be such that the final settings can be readily identified.

2.3.17 Where monitors are provided at the station in control and, if fitted, in the duty engineer's accommodation, they are to provide immediate display of new alarm information regardless of the information display page currently selected. This may be achieved by provision of a dedicated alarm monitor, a dedicated area of screen for alarms or other suitable means.

2.3.18 Where practicable, alarms displayed on monitors are to be displayed in the order in which they occur. Alarms requiring shutdown or slowdown action are to be given visual prominence.

## 2.4 Safety systems, general requirements

2.4.1 Where safety systems are provided the requirements of 2.4.2 to 2.4.13 are to be satisfied.

# Control Engineering Systems

# Part 6, Chapter 1

Section 2

2.4.2 Safety systems are to operate automatically in case of serious faults endangering the machinery, so that:

- (a) normal operating conditions are restored, e.g. by the starting of standby machinery, or
- (b) the operation of the machinery is temporarily adjusted to the prevailing conditions, e.g. by reducing the output of the machinery, or
- (c) the machinery is protected from critical conditions by shutting off the fuel or power supplies thereby stopping the machinery.

2.4.3 The safety system required by 2.4.2(c) is to be designed as far as practicable to operate independently of the control and alarm systems, such that a failure or malfunction in the control and alarm systems will not prevent the safety system from operating, see 3.1.4.

2.4.4 For safety systems required by 2.4.2(a) and (b) complete independence from other control systems is not necessary.

2.4.5 Safety systems for different items of the machinery plant are to be arranged so that failure of the safety system of one part of the plant will not interfere with the operation of the safety system in another part of the plant.

2.4.6 The safety system is to be designed to 'fail-safe'. The characteristics of the 'fail-safe' operation are to be evaluated on the basis not only of the safety system and its associated machinery, but also the complete installation. Failure of a safety system is to initiate an audible and visual alarm.

2.4.7 When a safety system is activated, an audible and visual alarm is to be provided to indicate the cause of the safety action.

2.4.8 The safety system is to be manually reset before the relevant machinery can be restarted.

2.4.9 Where arrangements are provided for overriding a safety system, they are to be such that inadvertent operation is prevented. Visual indication is to be given at the relevant control station(s) when a safety override is operated. The consequences of overriding a safety system are to be established and documented.

2.4.10 The safety system is to be arranged with automatic changeover to a standby power supply in the event of a failure of the normal power supply.

2.4.11 Failure of any power supply to a safety system is to operate an audible and visual alarm.

2.4.12 When safety systems are provided with means to adjust their set point, the arrangements are to be such that the final settings can be readily identified.

2.4.13 As far as practicable, the safety system required by 2.4.2(b) is to be arranged to effect a rapid reduction in speed or power.

## 2.5 Control systems, general requirements

2.5.1 Where control systems are provided, the requirements of 2.5.2 to 2.5.8 are to be satisfied.

2.5.2 Control systems for machinery operations are to be stable throughout their operating range.

2.5.3 Failure of any power supply to a control system is to operate an audible and visual alarm.

2.5.4 Control systems should be designed to 'fail-safe'. The characteristics of the 'fail-safe' operation are to be evaluated on the basis not only of the control system and its associated machinery, but also the complete installation.

2.5.5 The control system is to be designed such that normal operation of the controls cannot induce detrimental mechanical or thermal overloads in the machinery.

2.5.6 Remote or automatic controls are to be provided with sufficient instrumentation at the relevant control stations to ensure effective control and indicate that the system is functioning correctly.

2.5.7 When control systems are provided with means to adjust their sensitivity or set point, the arrangements are to be such that the final settings can be readily identified.

2.5.8 Failure of a control system is not to result in the loss of ability to provide essential services by alternative means. This may be achieved by manual control or redundancy within the control system or redundancy in machinery and equipment, see also 2.12.2. Instrumentation is to be provided at local manual control stations to ensure effective operation of the machinery.

## 2.6 Bridge control for main propulsion machinery

2.6.1 Where a bridge control system for main propulsion machinery is to be fitted, the requirements of 2.6.2 to 2.6.8 are to be satisfied.

2.6.2 Means are to be provided to ensure satisfactory control of propulsion from the bridge in both the ahead and astern directions.

2.6.3 The following indications are to be provided on the bridge:

- (a) Propeller speed.
- (b) Direction of rotation of propeller for a fixed pitch propeller or pitch position for a controllable pitch propeller, see also 3.10.
- (c) Direction and magnitude of thrust.
- (d) Clutch position, where applicable.
- (e) Shaft brake position, where applicable.

2.6.4 The propeller speed, direction of rotation and, if applicable, the propeller pitch are to be controlled from the bridge under all sea-going and manoeuvring conditions.

# Control Engineering Systems

# Part 6, Chapter 1

Section 2

2.6.5 Remote control of the propulsion machinery is to be from one control station at any one time, see *also* 2.2.5. Main propulsion control units on the navigating bridge may be interconnected. Means are to be provided at the main machinery control station to ensure smooth transfer of control between the bridge and machinery control stations.

2.6.6 Means of control, independent of the bridge control system, are to be provided on the bridge to enable the watch-keeper to stop the propulsion machinery in an emergency.

2.6.7 Audible and visual alarms are to operate on the bridge and in the alarm system required by 4.2 if any power supply to the bridge control system fails. Where practicable, the preset speed and direction of thrust are to be maintained until corrective action is taken.

2.6.8 Two means of communication are to be provided between the bridge and the main control station in the machinery space. One of these means may be the bridge control system; the other is to be independent of the main electrical power supply, see *also* 2.2.2 and Pt 5, Ch 1,4.

2.6.9 Automation systems are to be designed in a manner such that a threshold warning of impending or imminent slowdown or shutdown of the propulsion system is given to the officer in charge of the navigational watch in time to assess navigational circumstances in an emergency. In particular, the systems are to control, monitor, report, alert and take safety action to slow down or stop propulsion while providing the officer in charge of the navigational watch an opportunity to manually intervene, except for those cases where manual intervention will result in total failure of the engine and/or propulsion equipment within a short time, for example in the case of overspeed.

## 2.7 Valve control systems

2.7.1 Where cargo, bilge, ballast, oil fuel transfer and sea valves for engine services are operated by remote or automatic control, the requirements of 2.7.2 to 2.7.5 are to be satisfied.

2.7.2 Failure of control system power or actuator power is not to permit a valve to move to an unsafe condition.

2.7.3 Positive indication is to be provided at the remote control station for the service to show the actual valve position or alternatively that the valve is fully open or closed.

2.7.4 Equipment located in places which may be flooded is to be capable of operating when submerged.

2.7.5 A secondary means of operating the valves, which may be by local manual control, is to be provided.

2.7.6 For requirements applicable to closing appliances on scuppers and sanitary discharges, see Pt 3, Ch 12,4.2. For power supplies on passenger ships, see Ch 2,3.2.

## 2.8 Fire detection alarm systems

2.8.1 Where an automatic fire detection system is to be fitted in a machinery space the requirements of 2.8.2 to 2.8.14 are to be satisfied. See *also* SOLAS 1974 as amended Reg. II-2/C,7, or Ch 4,4 as applicable.

2.8.2 A fire detection control unit is to be located in the navigating bridge area, the fire-control station, or in some other position such that a fire in the machinery spaces will not render it inoperable.

2.8.3 Fire detection indicating panels are to denote the section in which a detector or manually operated call point has operated. At least one indicating panel is to be so located that it is easily accessible to responsible members of the crew at all times. An indicating panel is to be located on the navigating bridge.

2.8.4 An audible fire-alarm is to be provided having a characteristic tone which distinguishes it from the alarm system required by 2.3 or any other alarm system. The audible fire-alarm is to be immediately audible on all parts of the navigating bridge, the fire-control station, the crew accommodation areas and the machinery spaces.

2.8.5 Facilities are to be provided in the fire detection system to manually initiate the fire alarm from the following locations:

- (a) Positions adjacent to all exits from machinery spaces.
- (b) Navigating bridge.
- (c) Control station in engine room.
- (d) Fire control station.

2.8.6 The alarm system is to be designed with self-monitoring properties. Power or system failures are to initiate an audible alarm distinguishable from the fire alarm. This alarm may be incorporated in the machinery alarm system as required by 2.3.

2.8.7 For electrical engineering requirements, see Ch 2,16.1.

2.8.8 Fire detection control units (including addressable systems), indicating panels, detector heads, manual call points and short-circuit isolation units are to be Type Approved in accordance with *Test Specification Number 1* given in LR's *Type Approval System* for an environmental category appropriate for the locations in which they are intended to operate. For addressable systems, see *also* 2.10.

2.8.9 Detector heads are to be located in the machinery spaces so that all potential fire outbreak points are guarded. A combination of detectors is to be provided in order that the system will react to all possible fire characteristics.

2.8.10 When fire detectors are provided with means to adjust their sensitivity, the arrangements are to be such that the set point can be fixed and readily identified.

2.8.11 When it is intended that a particular loop is to be temporarily switched off, this state is to be clearly indicated at the fire detection indicating panels.

# Control Engineering Systems

# Part 6, Chapter 1

Section 2

2.8.12 When it is intended that a particular detector(s) is (are) to be temporarily switched off locally, this state is to be clearly indicated at the local position. Reactivation of the detector(s) is to be performed automatically after a preset time.

2.8.13 The fire detector heads are to be of a type which can be tested and reset without the renewal of any component. Facilities are to be provided on the fire-control panel for functional testing and reset of the system.

2.8.14 It is to be demonstrated to the Surveyor's satisfaction that detector heads are so located that air currents will not render the system ineffective at sea and in port.

## 2.9 Fixed water-based local application fire-fighting systems

2.9.1 Where fixed water-based local application fire-fighting systems are installed in accordance with SOLAS as amended Ch. II-2/C, Reg. 10.5.6, arrangements are to be in accordance with this sub-Section.

2.9.2 Systems are to be available for immediate use and arranged for manual activation from inside and outside the protected space. *See also* Ch 2,16.3.4.

2.9.3 The activation of a system is not to result in loss of electrical power or reduction of the manoeuvrability of the ship and is not to require confirmation of space evacuation or sealing.

2.9.4 A control panel is to be provided for managing actions such as opening of valves, starting of pumps and sounding of alarms and processing information from detectors.

2.9.5 Alarms are to be initiated upon activation of a system and are to indicate the specific zone activated at the control panel. Alarms are to be provided in each protected space, at an attended machinery control station and in the wheelhouse. The audible alarm is to be distinguishable from other safety system alarms.

2.9.6 Where SOLAS requires the system to, additionally, be capable of automatic release, the arrangements are to be in accordance with 2.9.7 to 2.9.9.

2.9.7 A minimum of two fire detectors is to be provided for each protected area. One is to be a flame detector and the other is to be a smoke or heat detector, as considered appropriate to the nature of the risk and ambient conditions. The system is to be activated upon detection by two of the detectors. A fault in one detector is to initiate an alarm and is not to inhibit activation of the system under the control of the other detector.

2.9.8 A fire detection alarm system panel in accordance with 2.8 may be used for receiving fire detection signals. Separate loops are not required provided that the address of the initiating device can be identified at the control panel. The received signals are then to be sent to the control panel required by 2.9.4 for processing and action.

2.9.9 The system's fire detection systems and control units are to meet the performance criteria of SOLAS Ch II/C, Reg. 7 and satisfy the requirements of LR's *Type Approval System Test Specification Number 1 (2002)*.

## 2.10 Programmable electronic systems – General requirements

2.10.1 The requirements of this sub-section are to be complied with where control, alarm or safety systems incorporate programmable electronic equipment. Systems for essential services and safety critical applications, systems incorporating shared data communication links and systems which are integrated are to comply with the additional requirements of 2.11, 2.12 and 2.13 as applicable. For systems complying with ISO 17894, *Ships and marine technology – Computer applications – General principles for the development and use of programmable electronic systems in marine applications*, see 2.1.2.

2.10.2 Where programmable electronic systems share resources, any components that can affect the ability to effectively provide required control, alarm or safety functions are to fulfil the requirements of 2.10 to 2.13 related to providing those required functions.

2.10.3 Programmable electronic equipment is to revert to a defined safe state on initial start-up or re-start in the event of failure.

2.10.4 In the event of failure of any programmable electronic equipment, the system, and any other system to which it is connected, is to fail to a defined safe state or maintain safe operation, as applicable.

2.10.5 Programmable electronic equipment is to be certified by a recognized authority as suitable for the environmental conditions in which it is intended to operate, *see also* 2.12.3.

2.10.6 Emergency stops are to be hard-wired and independent of any programmable electronic equipment. Alternatively, the system providing emergency stop functions is to comply with the requirements of 2.12.2 and/or 2.12.8.

2.10.7 Programmable electronic equipment is to be provided with self-monitoring capabilities such that hardware and functional failures will initiate an audible and visual alarm in accordance with the requirements of 2.3 and, where applicable, 4.2. Hardware failure indications are to enable faults to be identifiable at least down to the level of the lowest replaceable unit and the self-monitoring capabilities are to ensure that diagnostic information is readily available.

2.10.8 System configuration, programs and data are to be protected against loss or corruption in the event of failure of any power supply.

2.10.9 Access to system configuration, programs and data is to be restricted by physical and/or logical means providing effective security against unauthorized alteration.

# Control Engineering Systems

# Part 6, Chapter 1

## Section 2

2.10.10 Where date and time information is required by the equipment, this is to be provided by means of a battery backed clock with restricted access for alteration. Date and time information is to be fully represented and utilized.

2.10.11 Displays and controls are to be protected against liquid ingress due to spillage.

2.10.12 User interfaces are to be designed in accordance with appropriate ergonomic principles to meet user needs and enable timely access to desired information or control of functions. A system overview is to be readily available.

2.10.13 The keyboard is to be divided logically into functional areas. Alphanumeric, paging and specific system keys are to be grouped separately.

2.10.14 Where a function may be accessed from more than one interface, the arrangement of displays and controls is to be consistent.

2.10.15 The size, colour and density of information displayed to the operator are to be such that information may be easily read from the normal operator position under all operational lighting conditions.

2.10.16 Display units are to comply with the requirements of International Electrotechnical Commission Standard IEC 60950:1991, *Safety of information technology equipment, including electrical business equipment*, in respect of emission of ionising radiation.

2.10.17 Symbols used in mimic diagrams are to be visually representative and are to be consistent throughout the systems' displays.

2.10.18 Where systems detect fault conditions, any affected mimic diagrams are to ensure that the status of unreliable and incorrect data is clearly identified.

2.10.19 Multi-function displays and controls are to be duplicated and interchangeable where used for the control or monitoring of more than one system, machinery item or item of equipment. At least one unit at the main control station is to be supplied from an independent uninterruptible power system (UPS).

2.10.20 The number of multi-function display and control units provided at the main control station and their power supply arrangements are to be sufficient to ensure continuing safe operation in the event of failure of any unit or any power supply.

2.10.21 Software lifecycle activities, e.g. design, development, supply and maintenance, are to be carried out in accordance with an acceptable quality management system. Software quality plans are to be submitted. These are to demonstrate that the provisions of ISO/IEC 90003:2004, *Software engineering – Guidelines for the application of ISO 9001:2000 to computer software*, or equivalent, are incorporated. The plans are to define responsibilities for the lifecycle activities, including verification, validation, module testing and integration with other components or systems.

## 2.11 Data communication links

2.11.1 Where control, alarm or safety systems use shared data communication links to transfer data, the requirements of 2.11.2 to 2.11.10 are to be complied with. The requirements apply to local area networks, fieldbuses and other types of data communication link which make use of a shared medium to transfer control, alarm or safety related data between distributed programmable electronic equipment or systems.

2.11.2 Data communication is to be automatically restored within 45 seconds in the event of a single component failure. Upon restoration, priority is to be given to updating safety critical data and control, alarm and safety related data for essential services. Components comprise all items required to facilitate data communication, including cables, switches, repeaters, software components and power supplies.

2.11.3 Loss of a data communication link is not to result in the loss of ability to operate any essential service by alternative means, see also 2.12.2.

2.11.4 The properties of the data communication link (e.g. bandwidth, access control method, etc.) are to ensure that all connected systems will operate in a safe, stable and repeatable manner under all operating conditions. The latency of control, alarm and safety related data is not to exceed two seconds.

2.11.5 Protocols are to ensure the integrity of control, alarm and safety related data, and provide timely recovery of corrupted or invalid data.

2.11.6 Means are to be provided to monitor performance and identify hardware and functional failures. An audible and visual alarm is to operate in accordance with the requirements of 2.3 and, where applicable, 4.2 in the event of a failure of an active or standby component.

2.11.7 Means are to be provided to prevent unintended connection or disconnection of any equipment where this may affect the performance of any other systems in operation.

2.11.8 Data cables are to comply with the applicable requirements of Pt 6, Ch 2, 10. Other media will be subject to special consideration.

2.11.9 The installation is to provide adequate protection against mechanical damage and electromagnetic interference.

2.11.10 Components are to be located with appropriate segregation such that the risk of mechanical damage or electromagnetic interference resulting in the loss of both active and standby components is minimized. Duplicated data communication links are to be routed to give as much physical separation as is practical.

# Control Engineering Systems

# Part 6, Chapter 1

Section 2

## 2.12 Programmable electronic systems – Additional requirements for essential services and safety critical systems

2.12.1 The requirements of 2.12.2 to 2.12.10 are to be complied with where control, alarm or safety systems for essential services, as defined by Pt 6, Ch 2, 1.5, or safety critical systems, incorporate programmable electronic equipment.

- (a) Safety critical systems are those which provide functions intended to protect persons from physical hazards (e.g. fire, explosion, etc.), or to prevent mechanical damage which may result in the loss of an essential service (e.g. main engine low lubricating oil pressure shutdown).
- (b) Applications that are not essential services may also be considered to be safety critical (e.g. domestic boiler low water level shutdown).

2.12.2 Alternative means of safe and effective operation are to be provided for essential services and, wherever practicable, these are to be provided by a fully independent hard-wired backup system. Where these alternative means are not independent of any programmable electronic equipment, the software is to satisfy the requirements of LR's *Software Conformity Assessment System – Assessment Module GEN1 (1994)*.

2.12.3 Items of programmable electronic equipment used to implement control, alarm and safety functions are to satisfy the requirements of LR's *Type Approval System Test Specification Number 1 (2002)*.

2.12.4 The system is to be configured such that control, alarm and safety function groups are independent. A failure of the system is not to result in the loss of more than one of these function groups. Proposals for alternative arrangements providing an equivalent level of safety will be subject to special consideration.

2.12.5 For essential services, the system is to be arranged to operate automatically from an alternative power supply in the event of a failure of the normal supply.

2.12.6 Failure of any power supply is to initiate an audible and visual alarm in accordance with the requirements of 2.3 and, where applicable, 4.2.

2.12.7 Where it is intended that the programmable electronic system implements emergency stop or safety critical functions, the software is to satisfy the requirements of LR's *Software Conformity Assessment System – Assessment Module GEN1 (1994)*. Alternative proposals providing an equivalent level of system integrity will be subject to special consideration, e.g. fully independent hard-wired backup system, redundancy with design diversity, etc.

2.12.8 Control, alarm and safety related information is to be displayed in a clear, unambiguous and timely manner, and, where applicable, is to be given visual prominence over other information on the display.

2.12.9 Means of access to safety critical functions are to be dedicated to the intended function and readily distinguishable.

## 2.13 Programmable electronic systems – Additional requirements for integrated systems

2.13.1 The requirements of 2.13.2 to 2.13.7 apply to integrated systems providing control, alarm or safety functions in accordance with the Rules, including systems capable of independent operation interconnected to provide co-ordinated functions or common user interfaces. Examples include integrated machinery control, alarm and monitoring systems, power management systems and safety management systems providing a grouping of fire, passenger, crew or ship safety functions, see Pt 6, Ch 2, 16 to 18.

2.13.2 System integration is to be managed by a single designated party, and is to be carried out in accordance with a defined procedure identifying the roles, responsibilities and requirements of all parties involved. This procedure is to be submitted for consideration where the integration involves control functions for essential services or safety functions including fire, passenger, crew, and ship safety.

2.13.3 The system requirements specification, see 1.2.5, is to identify the allocation of functions between modules of the integrated system, and any common data communication protocols or interface standards required to support these functions.

2.13.4 Reversionary modes of operation are to be provided to ensure safe and graceful degradation in the event of one or more failures. In general, the integrated system is to be arranged such that the failure of one part will not affect the functionality of other parts, except those that require data from the failed part.

2.13.5 Where the integration involves control functions for essential services or safety functions, including fire, passenger, crew, and ship safety, a Failure Mode and Effects Analysis (FMEA) is to be carried out in accordance with IEC 60812, or an equivalent and acceptable national or international standard and the report and worksheets submitted for consideration. The FMEA is to demonstrate that the integrated system will 'fail-safe', see 2.4.6 and 2.5.4, and that essential services in operation will not be lost or degraded beyond acceptable performance criteria where specified by these Rules.

2.13.6 The quantity and quality of information presented to the operator are to be managed to assist situational awareness in all operating conditions. Excessive or ambiguous information that may adversely affect the operator's ability to reason or act correctly is to be avoided, but information needed for corrective or emergency actions is not to be suppressed or obscured in satisfying this requirement.

2.13.7 Where information is required by the Rules or by National Administration requirements to be continuously displayed, the system configuration is to be such that the information may be viewed without manual intervention, e.g. the selection of a particular screen page or mode of operation. See also 2.10.19 to 2.10.20.

## ■ Section 3 Control and supervision of unattended machinery

### 3.1 General

3.1.1 Where machinery, as listed in 1.2.3, is fitted with automatic or remote controls so that under normal operating conditions it does not require any manual intervention by the operators, it is to be provided with the alarms and safety arrangements required by 3.2 to 3.15 as appropriate. Alternative arrangements which provide equivalent safeguards will be considered.

3.1.2 Where machinery is arranged to start automatically or from a remote control station, interlocks are to be provided to prevent start-up under conditions which could hazard the machinery.

3.1.3 Where machinery specified in this Section is required to be provided with a standby pump, the standby pump is to start automatically if the discharge pressure from the working pumps falls below a predetermined value.

3.1.4 Where a first stage alarm together with a second stage alarm and automatic shutdown of machinery are required in the relevant Tables of this Section, the sensors and circuits utilized for the second stage alarm and automatic shutdown are to be independent of those required for the first stage alarm.

3.1.5 Means are to be provided to prevent leaks from high pressure oil fuel injection piping for main and auxiliary engines dripping or spraying onto hot surfaces or into machinery air inlets. Such leakage is to be collected and, where practicable, led to a collector tank(s) fitted in a safe position. An alarm is to be provided to indicate that leakage is taking place. These requirements may also be applicable to high pressure hydraulic oil piping depending upon the location.

3.1.6 Oil mist monitoring, or engine bearing temperature monitors or alternative methods for crankcase protection are to be provided:

- (a) When arrangements are fitted to override the automatic shutdown for excessive reduction of the lubricating oil supply pressure.
- (b) For engines of 2 250 kW and above or having cylinders of more than 300 mm bore.

#### NOTES

1. For medium and high speed engines automatic shutdown of the engine is to occur.
2. For slow speed engines, automatic slowdown is to occur.
3. Where arrangements are made to override the automatic slowdown or shutdown due to high oil mist or bearing temperature, the override is to be independent of other overrides.
4. Where the bearing temperature monitoring method is chosen, all bearings in the crankcase are to be monitored where practicable, e.g. main, crankpin, crosshead.

5. Where alternative methods are provided for the prevention of the build-up of oil mist that may lead to a potentially explosive condition within the crankcase, details are to be submitted for consideration. The submission is to demonstrate that the arrangements are equivalent to those provided by oil mist monitoring or engine bearing temperature monitors, see Pt 5, Ch 2,6.9.14.

### 3.2 Oil engines for propulsion purposes

3.2.1 Alarms and safeguards are indicated in 3.2.2 to 3.2.8 and Tables 1.3.1(a) and (b), *see also* 3.1.5 and 3.1.6.

3.2.2 Alarms are to operate for the fault conditions shown in Table 1.3.1(a). Where applicable, indication is to be given at the relevant control stations that the speed or power of the main propulsion engine(s) is to be manually reduced or has been reduced automatically.

3.2.3 Alarms are to operate, and automatic shutdown of machinery is to occur for the fault conditions shown in Table 1.3.1(b).

3.2.4 The following engine services are to be fitted with automatic temperature controls so as to maintain steady state conditions throughout the normal operating range of the propulsion engine(s).

- (a) Lubricating oil supply.
- (b) Oil fuel supply, *see also* 3.2.5.
- (c) Piston coolant supply, where applicable.
- (d) Cylinder coolant supply, where applicable.
- (e) Fuel valve coolant supply, where applicable.

3.2.5 The oil fuel supply may be fitted with an automatic control for viscosity instead of the temperature control required by 3.2.4.

3.2.6 Indication of the starting air pressure is to be provided at each control station from which it is possible to start the main propulsion engine(s).

3.2.7 The number of automatic consecutive attempts which fail to produce a start is to be limited to three. For reversible engines which are started and stopped for manoeuvring purposes, means are to be provided to maintain sufficient starting air in the air receivers. For electric starting, *see* Pt 5, Ch 2,8.4.

3.2.8 Prolonged running in a restricted speed range is to be prevented automatically or, alternatively, an indication of restricted speed ranges is to be provided at each control station.

### 3.3 Steam turbine machinery for propulsion purposes

3.3.1 Alarms and safeguards are indicated in 3.3.2 to 3.3.6 and Table 1.3.2.

## Control Engineering Systems

## Part 6, Chapter 1

Section 3

**Table 1.3.1(a) Oil engines for propulsion purposes:  
Alarms and slowdowns**  
(see continuation)

Item	Alarm	Note
Lubricating oil sump level	Low	Engines (and gearing if fitted)
Lubricating oil inlet pressure*	1st stage low	Engines (and gearing if fitted). Slowdown
Lubricating oil inlet temperature*	High	Engines (and gearing if fitted)
Lubricating oil filters differential pressure	High	—
Oil mist concentration in crankcase or bearing temperature	High	Automatic slowdown of slow speed engines, see 3.1.6
Cylinder lubricator flow	Low	One sensor per lubricator unit. Slowdown (automatic on medium and high speed engines)
Thrust bearing temperature*	High	Slowdown
Piston coolant inlet pressure	Low	If a separate system. Slowdown
Piston coolant outlet temperature*	High	Per cylinder (if a separate system). Slowdown
Piston coolant outlet flow*	Low	Per cylinder (if a separate system). Slowdown
Cylinder coolant inlet pressure or flow*	Low	Slowdown (automatic on medium and high speed engines)
Cylinder coolant outlet temperature*	1st stage high	Per cylinder (if a separate system). Slowdown (automatic on medium and high speed engines)
Engine cooling water system – oil content	High	Where engine cooling water used in oil/water heat exchangers
Sea water cooling pressure	Low	—
Fuel valve coolant pressure	Low	If a separate system
Fuel valve coolant temperature	High	If a separate system
Oil fuel pressure from booster pump	Low	—
Oil fuel temperature or viscosity*	High and Low	Heavy oil only
Oil fuel high pressure piping*	Leakage	See 3.1.5
Charge air cooler outlet temperature	High and Low	4-stroke medium and high speed engines
Scavenge air temperature (fire)	High	Per cylinder (2-stroke engines). Slowdown
Scavenge air receiver water level	High	—

**Table 1.3.1(a) Oil engines for propulsion purposes:  
Alarms and slowdowns**  
(conclusion)

Item	Alarm	Note
Exhaust gas temperature*	High	Per cylinder. Slowdown (automatic on medium and high speed engines) See Note 5
Exhaust gas temperature deviation from average*	High	Per cylinder, See Note 5
Turbocharger exhaust gas inlet temperature	High	Each turbocharger See Note 6
Turbocharger exhaust gas outlet temperature*	High	Each turbocharger
Turbocharger lubricating oil inlet pressure	Low	If system not integral with turbocharger
Turbocharger lubricating oil outlet temperature	High	Each bearing, if system not integral with turbocharger
Starting air pressure*	Low	Before engine manoeuvring valve
Control air pressure	Low	—
Direction of rotation	Wrong way	Reversible engines, see also 3.2.7
Overspeed*	High	See also Pt 5, Ch 2,5
Automatic start of engine	Failure	See 3.2.7
Electrical starting battery charge level	Low	—
<b>NOTES</b> 1. Where 'per cylinder' appears in this Table, suitable sensors may be situated on manifold outlets for medium and high speed engines. 2. For engines and gearing of 1500 kW or less only the items marked* are required. 3. Common sensors are acceptable for alarms and slowdown functions. 4. Except where stated otherwise in the Table, slowdown may be effected by either manual or automatic means, by reduction of speed or power as appropriate. 5. For medium and high speed engine power <500 kW/cylinder, a common sensor for exhaust gas manifold temperature may be fitted. 6. May be combined with exhaust gas outlet temperature high alarm where the turbocharger is mounted directly on the exhaust manifold.		

**Table 1.3.1(b) Oil engines for propulsion purposes:  
Alarms and shutdowns**

Item	Alarm	Note
Lubricating oil inlet pressure	2nd stage low	Automatic shutdown of engines (and gearing if fitted), see 3.1.4
Oil mist concentration in crankcase or bearing temperature	High	Automatic shutdown of medium and high speed engines, see 3.1.6
Cylinder coolant outlet temperature	2nd stage high	Automatic shutdown of medium and high speed engines, see 3.1.4



# Control Engineering Systems

## Part 6, Chapter 1

Section 3

**Table 1.3.2 Steam turbine machinery: Alarms and safeguards**

Item	Alarm	Note
Lubricating oil pressure for turbines and gearing	1st stage low	—
	2nd stage low	Automatic shutdown, see 3.1.4
Lubricating oil temperature for turbines and gearing	High	—
Lubricating oil sump level	Low	—
Lubricating oil filters differential pressure	High	—
Bearing temperatures or bearing oil outlet temperature of turbines and gearing	High	—
Astern turbine temperature	High	—
Gland steam pressure	High and Low	—
Thrust bearing temperature	High	—
Sea water pressure or flow	Low	—
Turbine vibration	High	Shutdown or speed reduction of turbine(s)
Axial movement of turbine rotor	High	
Main condenser vacuum	Low	
Main condenser condensate level	High	
Overspeed	High	See Pt 5, Ch 3,4

3.3.2 Audible and visual alarms are to operate, and indication is to be given at the relevant control stations to stop or reduce the speed of the turbine(s) for the following fault conditions:

- Excessive turbine vibration.
- Excessive axial movement of turbine rotor.
- Low vacuum in main condenser.
- High condensate level in main condenser.

3.3.3 Reduction of speed may be effected by either manual or automatic control.

3.3.4 Means are to be provided to prevent the risk of thermal distortion of the turbines, by automatic steam spinning, when the shaft is stopped in the manoeuvring mode. An audible and visual alarm is to be provided at the relevant control stations when the shaft has been stopped for a predetermined time.

3.3.5 The following turbine services are to be fitted with automatic controls so as to maintain steady state conditions throughout the normal operating range of the propulsion turbine(s):

- Lubricating oil supply temperature.
- Condenser condensate level.
- Gland steam pressure.

3.3.6 Prolonged running in a restricted speed range is to be prevented automatically, or alternatively, indication of restricted speed ranges is to be provided at each control station.

### 3.4 Gas turbine machinery

3.4.1 Alarms and safeguards are indicated in 3.4.2 to 3.4.4 and Table 1.3.3.

**Table 1.3.3 Gas turbine machinery: Alarms and safeguards**

Item	Alarm	Note
Overspeed	High	Automatic shutdown see also Pt 5, Ch 4,8.2
Power turbine inlet temperature	1st stage high	Automatic power reduction
	2nd stage high	Automatic shutdown, see also Pt 5, Ch 4,8.3
Flame failure	Failure	Automatic shutdown, see also Pt 5, Ch 4,8.4
Failure to ignite	Failure	Automatic shutdown, see also Pt 5, Ch 4,8.4
Lubricating oil pressure	1st stage low	—
	2nd stage low	Automatic shutdown, see also Pt 5, Ch 4,8.5
Lubricating oil temperature	High	See also Pt 5, Ch 4,8.5
Lubricating oil filter differential pressure	High	—
Scavenge oil temperature	High	—
Scavenge oil pressure	Low	Automatic shutdown
Bearing temperature	High	—
Turbine vibration	1st stage high	—
	2nd stage high	Automatic shutdown, see also Pt 5, Ch 4,4.2
Oil fuel supply pressure	Low	—
Oil fuel supply temperature	High	—
Oil fuel leakage	High	See also Pt 5, Ch 4,5.2
Automatic starting	Failure	Automatic shutdown
Control system	Failure	Automatic shutdown
Air intake pressure	Low	See also Pt 5, Ch 4,4.4.4

#### NOTES

- For two-stage alarms, see also 3.1.4.
- For requirements on purging before ignition, see Pt 5, Ch 4,6.2.1.
- Where a requirement for disabling the automatic protection and safety system devices for machinery and engineering systems has been defined by the Owner, the consequences of using the disabling arrangements are to be established and included in the operations procedures and orders provided onboard ship. Details of any disabling arrangements are to be submitted to LR for consideration in each instance.

# Control Engineering Systems

## Part 6, Chapter 1

Section 3

3.4.2 The following turbine services are to be fitted with automatic temperature controls so as to maintain steady state conditions throughout the normal operating range of the turbine:

- (a) Lubricating oil supply.
- (b) Oil fuel supply, *see also* 3.4.3.
- (c) Exhaust gas.

3.4.3 The oil fuel supply may be fitted with an automatic control for viscosity instead of the temperature control required by 3.4.2.

3.4.4 A means of manually shutting off the fuel in an emergency is to be provided at the manoeuvring station.

### 3.5 Main, auxiliary and other boilers

3.5.1 Alarms and safeguards are indicated in 3.5.2 to 3.5.9 and Table 1.3.4.

3.5.2 The following boiler services are to be fitted with automatic controls so as to maintain steady state conditions throughout the normal operating range of the boiler:

- (a) Combustion system.
- (b) Oil fuel supply temperature or viscosity, heavy oil only.
- (c) Boiler drum water level.
- (d) De-aerator water level, where applicable.
- (e) Superheated steam pressure, where applicable.
- (f) Superheated steam temperature, where applicable.
- (g) De-superheated steam pressure, where applicable.
- (h) De-superheated steam temperature, where applicable.

3.5.3 Safety systems and overrides are to comply with the requirements of 2.4.9.

3.5.4 Burner controls are to be arranged such that light off is only possible at the minimum firing rate compatible with flame establishment. If ignition is set to occur at a fuel rich condition then the burner is to revert to the correct operating air/fuel ratio on establishment of a stable flame.

3.5.5 Where water level indicators are dependent upon an external power supply, the oil fuel supply to the burners is to be automatically shut-off in the event of power or signal failure.

3.5.6 Arrangements are to be such that burner oil fuel valve(s) do not open:

- (a) prior to completion of required warm up times for residual fuel oil; or
- (b) when the power supply to the igniter has failed, as applicable; or
- (c) until a pilot flame is established, as applicable; or
- (d) prior to the completion of furnace purging, *see* Pt 5, Ch 14,3.1.7.

**Table 1.3.4 Main, auxiliary and other boilers: Alarms and safeguards** (*see continuation*)

Item	Alarm	Note
Water level*	Low	Two water level sensors are to be provided each to operate independently, and automatically shut-off the oil fuel to the burners and operate alarms, <i>see</i> Notes 1 to 3, and 5
Water level	<div style="display: inline-block; vertical-align: middle;"> <div style="font-size: 3em; vertical-align: middle;">{</div> <div style="display: inline-block; vertical-align: middle;"> 1st stage high* 2nd stage high </div> </div>	— Where applicable automatic closure of turbine steam inlet valves, <i>see</i> 3.1.4
Steam drum or superheater outlet pressure*	High and Low	—
Superheated steam temperature	High	—
De-superheated steam temperature*	High	—
Feed water forced circulation flow (if fitted)	Low	Oil fuel to burners to be shut-off automatically, <i>see</i> Note 5
Feed water pH	Low	When automatic dosing of feed water fitted
Feed water salinity	High	Fitted in boiler feed system
Feed water temperature	Low	When automatic temperature control fitted
Combustion air pressure*	Low	Oil fuel to burners to be shut-off automatically in operation or not released during start up, <i>see</i> Note 5. Purge sequence to be inhibited, <i>see</i> Pt 5, Ch 14,3.1.7
Oil fuel pressure*	Low	—
Oil fuel temperature or viscosity*	High and Low	Heavy oil only
Oil fuel atomizing steam/air pressure	Low	—
Burner flame	Failure	Each burner to be monitored. Oil fuel to burner(s) to be shut-off automatically, <i>see</i> Pt 5, Ch 14,3.1.9, 3.1.10 and Note 5
Flame monitoring device(s)*	Failure	<i>See</i> 3.5.7, and Note 5
Igniter power supply*	Failure	Each igniter to be checked before oil fuel is supplied to burner, <i>see</i> 3.5.6 and Note 5
Forced draft fan*	Power failure	Oil fuel to burners to be shut-off automatically in operation or not released during start up, <i>see</i> Note 5
Air registers and dampers (including those in the uptake)*	Not fully open	Purge sequence to be inhibited, <i>see</i> Pt 5, Ch 14,3.1.7

## Control Engineering Systems

## Part 6, Chapter 1

Section 3

**Table 1.3.4 Main, auxiliary and other boilers: Alarms and safeguards (conclusion)**

Item	Alarm	Note
Control system*	Power failure	Oil fuel to burners to be shut-off automatically. Control using alternative arrangements is to remain available, see 2.5.8
Uptake temperature	High	Where economizer and/or gas air heaters are integral with the boiler and also for independent extended surface exhaust gas boilers/economizers, to monitor for soot fires
<b>NOTES</b> 1. For dual-evaporation boilers, the primary circuit is to be fitted with two independent low water level detectors which will operate alarms and shut-off the oil fuel to the burners automatically. The secondary circuit is to be fitted with one low water level detector which will operate alarms and shut-off the oil fuel to the burners automatically. Additionally one high water level alarm is to be fitted on the secondary circuit which may be operated by the same detector as that provided for low water level detection. 2. Only one independent system of low water level detection, alarm and automatic oil fuel shut-off need be fitted in the case of small forced circulation or re-circulation coiled water tube 'package' type boilers when evaporation is less than 2900 kg/hr or the heating surface is less than 100 m <sup>2</sup> . 3. Where two level sensors are provided these may be used for other functions, e.g. high level alarm, level control, trip systems, etc.. 4. For boilers not supplying steam for propulsion or for services essential for the safety or the operation of the ship at sea, only the items marked* are required. 5. These safeguards are to remain operative during automatic, manual and emergency operation.		

3.5.7 Arrangements for flame failure detection are to be provided with self-monitoring capabilities which ensure that the flame detector is not erroneously indicating the presence of a flame. In the event of failure being detected by these self-monitoring capabilities:

- an alarm is to be activated.
- In the event of loss of flame detection capability for a burner;
- oil fuel to the burner is to be shut-off automatically; and
  - an alarm is to be activated

3.5.8 Where established as necessary by Pt 5, Ch 14, 3.1.8, means are to be provided to prevent starting of the ignition sequence following multiple flame failures until completion of the identified lock out period.

3.5.9 Following burner shutdown, the furnace is to be purged automatically for at least the required pre-purging time. In event of shutdown due to activation of a required safeguard, this purging is to be manually initiated.

**3.6 Thermal fluid heaters**

3.6.1 Alarms and safeguards are indicated in 3.6.2 to 3.6.8 and Table 1.3.5.

**Table 1.3.5 Thermal fluid heaters: Alarms and safeguards**

Item	Alarm	Note
Expansion tank level*	Low	Oil fuel burners to be shut-off automatically
Thermal fluid flow	Low	Oil fuel burners to be shut-off automatically
Thermal fluid pressure	Low	Oil fuel burners to be shut-off automatically
	1st stage high	—
Thermal fluid outlet temperature*	2nd stage high	Oil fuel burners to be shut-off automatically, see 3.1.4
Combustion air pressure*	Low	Oil fuel burners to be shut-off automatically in operation or not released during start up, see Note 3. Purge sequence to be inhibited see Pt 5, Ch 14,3.1.7
Oil fuel pressure*	Low	—
Oil fuel temperature or viscosity*	High and Low	Heavy oil only
Oil fuel atomizing steam/air pressure	Low	—
Burner flame*	Failure	Each burner to be monitored. Oil fuel to burner to be shut-off automatically, see Pt 5, Ch 14,3.1.9 and 3.1.10, and Note 3
Flame monitoring device(s)*	Failure	See 3.6.6 and Note 3
Igniter power supply*	Failure	Each igniter to be checked before oil fuel is supplied to burner(s), see 3.6.5 and Note 3
Forced draft fan*	Power failure	Oil fuel to burners to be shut-off automatically in operation or not released during start up, see Note 3
Air register and dampers (including those in the uptake)*	Not fully open	Purge sequence to be inhibited, see Pt 5, Ch 14, 3.1.7
Control system*	Power failure	Oil fuel to burners to be shut-off automatically. Control using alternative arrangements is to remain available, see 2.5.8
Uptake temperature	High	Where applicable, to monitor for soot fires
<b>NOTES</b> 1. Special consideration may be given to the requirements for oil-fired hot water heaters. 2. For heaters not supplying thermal oil for services essential for the safety or the operation of the ship at sea, only the items marked* are required. 3. These safeguards are to remain operative during automatic, manual and emergency operation.		

# Control Engineering Systems

## Part 6, Chapter 1

Section 3

3.6.2 The standby pumps for oil fuel and thermal fluid circulation are to start automatically when the discharge pressure from the working pump falls below a predetermined value. The standby pumps for thermal fluid circulation are to start before the shut-offs due to low thermal fluid pressure, see Table 1.3.5, are activated

3.6.3 The following heater services are to be fitted with automatic controls so as to maintain steady state conditions throughout the operating range of the heater:

- Combustion system.
- Oil fuel supply temperature or viscosity, heavy oil only.
- Thermal fluid temperature.

3.6.4 Burner controls are to be arranged such that light-off is only possible at the minimum firing rate compatible with flame establishment. If ignition is set to occur at a fuel rich condition then the burner is to revert to the correct operating air/fuel ratio on establishment of a stable flame.

3.6.5 Arrangements are to be such that burner oil fuel valve(s) do not open:

- prior to completion of required warm up times for residual fuel oil; or
- when the power supply to the igniter has failed, as applicable; or
- until a pilot flame is established, as applicable; or
- prior to the completion of furnace purging, see Pt 5, Ch 14,3.1.7.

3.6.6 Arrangements for flame failure detection are to be provided with self-monitoring capabilities which ensure that the flame detector is not erroneously indicating the presence of a flame. In the event of failure being detected by these self-monitoring capabilities:

- an alarm is to be activated.

In the event of loss of flame detection capability for a burner;

- oil fuel to the burner is to be shut-off automatically; and
- an alarm is to be activated.

3.6.7 Where established as necessary by Pt 5, Ch 14,3.1.8, means are to be provided to prevent starting of the ignition sequence following multiple flame failures until completion of the identified lock out period.

3.6.8 Following burner shutdown, the furnace is to be purged automatically for at least the required pre-purging time. In event of shutdown due to activation of a required safeguard, this purging is to be manually initiated.

### 3.7 Inert gas generators

3.7.1 Alarms and safeguards are indicated in 3.7.2 and Table 1.3.6.

3.7.2 Inert gas generators are to be fitted with an automatic combustion control system so as to maintain steady state conditions throughout the operating range of the generator.

3.7.3 For the requirements of flue gas inert gas systems, see Pt 5, Ch 15,7.

**Table 1.3.6 Inert gas generators: Alarms and safeguards**

Item	Alarm	Note
Inert gas outlet temperature	High	Oil fuel to burner to be shut-off automatically
Combustion air pressure	Low	Oil fuel to burner to be shut-off automatically
Oil fuel pressure	Low	—
Oil fuel temperature or viscosity	High and Low	Heavy oil only
Burner flame and ignition	Failure	Oil fuel to burner to be shut-off automatically, see Note 1
Cooling water pressure or flow	Low	Oil fuel to burner to be shut-off automatically
Cooling water temperature	High	—
Oil fuel supply	Insufficient	—
Power supply to inert gas generator	Failure	Gas regulating valve is to be shutdown automatically
Automatic control system power supply	Failure	—
NOTES		
1. Combustion spaces are to be purged automatically before re-ignition takes place in the event of a flame-out on all burners.		
2. See also Pt 5, Ch 15.		

### 3.8 Incinerators

3.8.1 Alarms and safeguards are indicated in 3.8.2, 3.8.3 and Table 1.3.7.

**Table 1.3.7 Incinerators: Alarms and safeguards**

Item	Alarm	Note
Oil fuel temperature or viscosity	High and Low	Heavy oil and sludge
Oil fuel pressure	Low	—
Combustion air pressure	Low	Oil fuel and/or sludge to burners to be shut-off automatically
Burner flame and ignition	Failure	Oil fuel and/or sludge to burners to be shut-off automatically, see Note
Furnace temperature	High	Oil fuel and/or sludge to burners to be shut-off automatically
Furnace temperature	Low	If applicable
Exhaust temperature	High	—
NOTE		
Combustion spaces are to be purged automatically before re-ignition takes place in the event of a flame-out on all burners.		

3.8.2 Where arrangements are provided to introduce solid waste into the furnace these are to be such that there is no risk of a fire hazard.

# Control Engineering Systems

## Part 6, Chapter 1

Section 3

3.8.3 The combustion temperature is to be controlled to ensure that all liquid and solid waste is efficiently burned without exceeding predetermined temperature limits.

### 3.9 Auxiliary engines and auxiliary steam turbines

3.9.1 Alarms and safeguards are indicated in Table 1.3.8, see also 3.1.5 and 3.1.6.

**Table 1.3.8 Auxiliary engines and auxiliary steam turbines: Alarms and safeguards**

Item	Alarm	Note
<b>OIL ENGINES</b>		
Lubricating oil inlet temperature	High	—
Lubricating oil inlet pressure	1st stage low	—
	2nd stage* low	Automatic shutdown of engine*, see 3.1.4
Oil mist concentration in crankcase or bearing temperature	High	Automatic shutdown of engine, see 3.1.6
Oil fuel high pressure piping*	Leakage	See 3.1.5
Coolant outlet temperature (for engines >220 kW)	1st stage high	—
	2nd stage	Automatic shutdown of engine*, see 3.1.4
Coolant pressure or flow	Low	—
Oil fuel temperature or viscosity	High and Low	Heavy oil only
Overspeed	High	See Pt 5, Ch 2,5
Starting air pressure	Low	—
Electrical starting battery charge level	Low	—
Exhaust gas temperature	High	Per cylinder for engine power <500 kW/cylinder, common sensors for each inlet to the turbo-charger may be accepted
<b>STEAM TURBINES</b>		
Lubricating oil inlet temperature	High	—
Lubricating oil inlet pressure	1st stage low	—
	2nd stage low*	Automatic shutdown of turbine*, see 3.1.4
Condenser vacuum	Low	Automatic shutdown of turbine*, see 3.1.4
Axial displacement of rotor	High	
Overspeed	High	See Pt 5, Ch 4,4
<b>NOTES</b>		
1. There are no classification requirements for the items marked * in the case of engines being used for the emergency source of electrical power required by SOLAS.		
2. The arrangements are to comply with the requirements of the National Authority concerned.		

3.9.2 For engines operating on heavy oil fuel, automatic temperature or viscosity controls are to be provided.

### 3.10 Controllable pitch propellers and transverse thrust units

3.10.1 Alarms and safeguards are indicated in 3.10.2 to 3.10.6 and Table 1.3.9. For azimuth thrusters, see also Pt 5, Ch 20.

**Table 1.3.9 Controllable pitch propellers and transverse thrust units: Alarms and safeguards**

Item	Alarm	Note
Hydraulic system pressure	Low	—
Hydraulic oil supply tank level	Low	—
Hydraulic oil temperature	High	Where an oil cooler is fitted
Power supply to the control system between the remote control station and hydraulic actuator	Failure	See 2.5.3
Propulsion motor	Overload	See Ch 2,15

3.10.2 For controllable pitch propellers for main propulsion, a standby or alternative power source of actuating medium for controlling the pitch of the propelling blades is to be provided. Automatic start of the standby pump supplying hydraulic power for pitch control is to be provided.

3.10.3 Controllable pitch propellers for main propulsion are to be provided with indications of shaft speed, direction and magnitude of thrust and propeller pitch as a measure of the propeller blade or actuator movement at each station from which it is possible to control shaft speed or propeller pitch.

3.10.4 Where transverse thrust units are remotely controlled means are to be provided at the remote control station to stop the propulsion unit.

3.10.5 Transverse thrust units are to be provided with indications of direction and magnitude of thrust and propeller pitch at each station from which it is possible to control the propeller pitch.

3.10.6 An indication of the angular position of rotatable thrust units is to be provided at each station from which it is possible to control the direction of thrust.

### 3.11 Monitoring in cargo pump rooms

3.11.1 Alarms and safeguards are indicated in Pt 5, Ch 15.

# Control Engineering Systems

## Part 6, Chapter 1

Section 3

### 3.12 Electric system

3.12.1 Alarms and safeguards are indicated in Table 1.3.10.

**Table 1.3.10 Electric system: Alarms and safeguards**

Item	Alarm	Note
Bus-bar voltage	High and Low	—
Bus-bar frequency	Low	—
Operation of load shedding	Warning	—
Generator cooling air temperature	High	For closed air circuit water cooled machines

### 3.13 Steering gear

3.13.1 For the requirements of steering gear, see Pt 5, Ch 19.

### 3.14 Waterjets

3.14.1 Alarms and safeguards are indicated in 3.14.2 to 3.14.4 and Table 1.3.11.

**Table 1.3.11 Waterjets: Alarms and safeguards**

Item	Alarm	Note
Hydraulic system pressure	Low	—
Hydraulic oil supply tank level	Low	—
Hydraulic oil temperature	High	Where an oil cooler is fitted
Hydraulic system flow	Low	—
Lubricating oil pressure	Low	—
Control system	Fault	—
Control system power supply	Failure	—

3.14.2 For waterjets used as the only means of propulsion, a standby or alternative power source of actuating medium for controlling the angular position and/or the reversing angle is to be provided. Automatic start of the standby pump supplying hydraulic power for steering and reversing is to be provided.

3.14.3 An indication of the angular position of waterjets is to be provided at each station from which it is possible to control the angular position.

3.14.4 An indication of the bucket position is to be provided at each station from which it is possible to control the reversal of thrust.

### 3.15 Miscellaneous machinery

3.15.1 Alarms and safeguards are indicated in 3.15.2 to 3.15.6 and Table 1.3.12.

**Table 1.3.12 Miscellaneous machinery: Alarms and safeguards**

Item	Alarm	Note
Stern tube lubricating oil tank level	Low	—
Stern tube bearing temperature (oil-lubricated)	High	—
Coolant tanks level	Low	—
Oil fuel service tanks level	High and Low	Where a common overflow tank is fitted, a high level alarm in the common overflow tank may be accepted
Oil fuel service tanks temperature	High	Where heating arrangements are fitted
Oil fuel settling tanks temperature	High	Where heating arrangements are fitted
Sludge tanks level	High	—
Feed water tanks level	Low	Service tank only
Purifier water seal broken	Fault	—
Purifier oil inlet temperature	High	—
Air compressor lubricating oil	Failure	Automatic shutdown
Air compressor discharge air temperature	High	—
Hydraulic control system pressure	Low	—
Pneumatic control system pressure	Low	—
Oil heater temperature	High	See also Pt 5, Ch 14
Controlled environmental conditions	Abnormal	See also 1.3.3

3.15.2 **Dual fuel systems.** Oil and gas dual-fired systems for boilers and engines are to be provided with indication to show which fuel is in use.

3.15.3 **Lifts.** For details of alarms and safeguards for lifts classed by LR, reference is to be made to LR's *Code for Lifting Appliances in a Marine Environment*.

# Control Engineering Systems

## Part 6, Chapter 1

Sections 3 &amp; 4

**3.15.4 Oil heaters.** Oil fuel or lubricating oil heaters are to be fitted with a high temperature alarm which may be incorporated in the temperature control system. In addition to the temperature control system, an independent sensor, with manual reset, is to be fitted which will automatically cut off the heating supply in the event of excessively high temperatures or loss of flow, except where the maximum temperature of the heating medium remains limited to a value below 220°C.

**3.15.5 Oil tank electric heating.** Oil fuel and lubricating oil tanks that are provided with electric heating elements are to be fitted with a high temperature alarm, which may be incorporated in the temperature control system, a low level alarm and an additional low level sensor to cut off the power supply at a level above that at which the heating element would be exposed.

**3.15.6 Oil fuel tanks.** Means are to be provided to eliminate the possibility of overflow from oil fuel service tanks into the machinery space and to safeguard against overflow of oil from oil fuel service tanks through the air pipe. See Pt 5, Ch 13 regarding the termination of air pipes.

### ■ Section 4 Unattended machinery space(s) – UMS notation

#### 4.1 General

**4.1.1** Where it is proposed to operate the following machinery in an unattended space, no matter what period is envisaged, the controls, alarms and safeguards required by Section 3, together with those given in 4.2 to 4.7 are to be provided:

- (a) Air compressors.
- (b) Controllable pitch propellers and transverse thrust units.
- (c) Electric generating plant.
- (d) Inert gas generators.
- (e) Incinerators.
- (f) Main propelling machinery including essential auxiliaries.
- (g) Oil fuel transfer and storage systems (purifiers and oil heaters).
- (h) Steam raising plant (boilers and their ancillary equipment).
- (j) Thermal fluid heaters.
- (k) Waste heat boilers.

#### 4.2 Alarm system for machinery

**4.2.1** An alarm system which will provide warning of faults in the machinery is to be installed. The system is to satisfy the requirements of 2.3.

**4.2.2** Audible and visual indication of machinery alarms is to be relayed to the engineers' accommodation so that engineering personnel are made aware that a fault has occurred.

**4.2.3** The engineers' alarm required by 2.2.3 is to be activated automatically in the event that a machinery alarm has not been acknowledged in the space within a predetermined time.

**4.2.4** Audible and visual indication of machinery alarms is to be relayed to the navigating bridge control station in such a way that the navigating officer of the watch is made aware when:

- (a) a machinery fault has occurred;
- (b) the machinery fault is being attended to; and
- (c) the machinery fault has been rectified.

Alternative means of communication between the bridge area, accommodation for engineering personnel and machinery spaces will be considered.

**4.2.5** Group alarms may be arranged on the bridge to indicate machinery faults, but alarms associated with faults requiring speed or power reduction or the automatic shut-down of propulsion machinery are to be identified by separate group alarms or by individual alarm parameters.

#### 4.3 Bridge control for main propulsion machinery

**4.3.1** A bridge control system for the main propulsion machinery is to be fitted. The system is to satisfy the requirements of 2.6.

#### 4.4 Control stations for machinery

**4.4.1** A control station(s) is to be provided in the space and on the bridge which satisfies the requirements of 2.2.

#### 4.5 Fire detection alarm system

**4.5.1** An automatic fire detection system is to be fitted in the space together with an audible and visual alarm system. The system is to satisfy the requirements of 2.8.

#### 4.6 Bilge level detection

**4.6.1** An alarm system is to be provided to warn when liquid in machinery space bilges has reached a predetermined level, and is to comply with 2.3. This level is to be sufficiently low to prevent liquid from overflowing from the bilges onto the tank top. The number and location of detectors are to be such that accumulation of liquids will be detected at all angles of heel and trim. In ships above 2000 gross tons there are to be two independent systems of bilge level detection in the machinery space, arranged such that each branch bilge as required by Pt 5, Ch 13 is provided with a level detector.

**4.6.2** Local or remote controls of any valve within the space serving a sea inlet, a discharge below the waterline, a bilge injection or a direct bilge system, should be so sited as to be readily accessible and to allow adequate time for operation in case of influx of water to the space, having regard to the time which could be taken to reach and operate such controls, see *a/so* 2.7 and Pt 5, Ch 13.2.

# Control Engineering Systems

# Part 6, Chapter 1

Sections 4, 5 & 6

4.6.3 Where the bilge pumps are arranged to start automatically, means are to be provided to indicate if the influx of liquids is greater than the pump capacity or, if the pump is operating more frequently than would be expected. Special attention should be given to oil pollution prevention requirements.

## 4.7 Supply of electric power, general

4.7.1 For ships operating with one generator set in service, arrangements are to be such that a standby generator will automatically start and connect to the switchboard in as short a time as practicable, but in any case within 45 seconds, on loss of the service generator. For ships operating with two or more generator sets in service, arrangements are to be such that on loss of one generator the remaining one(s) are to be adequate for continuity of essential services. For the detailed requirements of these arrangements, see Ch 2,2.2.

## ■ Section 5 Machinery operated from a centralized control station – CCS notation

### 5.1 General requirements

5.1.1 Where it is proposed to operate the machinery as listed in 4.1.1 with the continuous supervision from a centralized control station, the control station is to be such that the machinery operation will be as effective as it would be under direct supervision.

5.1.2 The arrangements are to be such that corrective actions can be taken at the control station in the event of machinery faults, e.g. stopping of machinery, starting of standby machinery, adjustment of operating parameters, etc. These actions may be effected by either remote manual or automatic control.

5.1.3 The controls, alarms and safeguards required by Section 3 and by 4.6 together with a fire detection system satisfying the requirements of 2.8 are to be provided. However, the automatic operation of machinery and certain safeguards required by Section 3 may be omitted.

5.1.4 Additional requirements for controls, alarms and safeguards are given in 5.2.

### 5.2 Centralized control station for machinery

5.2.1 A centralized control station which satisfies the requirements of 5.2.2 to 5.2.7 is to be provided at a suitable location.

5.2.2 A system of alarm displays and controls is to be provided which readily ensures identification of faults in the machinery and satisfactory supervision of related equipment. The alarm and control systems are to satisfy the requirements of 2.3 and 2.5, as applicable.

5.2.3 Indication of all essential parameters necessary for the safe and effective operation of the machinery is to be provided, e.g. temperatures, pressures, tank levels, speeds, powers, etc.

5.2.4 Indication of the operational status of running and standby machinery is to be provided.

5.2.5 At the centralized control station, means of communication with the bridge area, the accommodation for engineering personnel and, if necessary, the machinery space are to be provided.

5.2.6 In addition to the communication required by 5.2.5, a second means of communication is to be provided between the bridge and the centralized control station. One of these means is to be independent of the main electrical power supply, see also Pt 5, Ch 1.

5.2.7 Arrangements are to be provided in the centralized control station so that the normal supply of electrical power may be restored in the event of failure.

## ■ Section 6 Integrated computer control – ICC notation

### 6.1 General

6.1.1 Integrated Computer Control class notation **ICC** may be assigned where an integrated computer system in compliance with 6.1 to 6.3 provides fault tolerant control and monitoring functions for one or more of the following services:

- (a) Propulsion;
- (b) Electrical generation and distribution (power management systems);
- (c) Cargo and ballast.

6.1.2 A Failure Mode and Effects Analysis (FMEA) is to be carried out in accordance with IEC 60812 and the report and worksheets submitted for consideration. See also 2.13.5. The FMEA is to demonstrate that control and monitoring functions required by 6.2 will remain available at each operator station in the event of a single fault of the integrated computer control system, including input error, without adverse effect on the service(s).

6.1.3 Special consideration will be given to integrated computer control systems for other applications, except where these are addressed by other control engineering class notations. In particular, see Pt 7, Ch 9 for requirements of the optional class notation **IBS** – Integrated Bridge Navigation Systems, and Pt 7, Ch 12 for the requirements of the optional class notation **IFP** – Integrated Fire Protection.



# Control Engineering Systems

## Part 6, Chapter 1

Sections 6 &amp; 7

### 6.2 General requirements

6.2.1 The integrated computer control system is to comply with the programmable electronic system requirements of 2.10 to 2.13 and the control and monitoring requirements of the Rules applicable to particular equipment, machinery or systems.

6.2.2 Alarm displays are to be provided, in compliance with the requirements of 2.3, which ensure ready identification of faults in the equipment under control.

6.2.3 Alarm and indication functions required by 2.4 are to be provided by the integrated computer control system in response to the activation of any safety function for associated machinery. Systems providing the safety functions are in general to be independent of the integrated computer system. *See also* 2.12.7.

6.2.4 Controls are to be provided, in compliance with 2.5, to ensure the safe and effective operation of equipment and response to faults, e.g. stopping, starting, adjustment of parameters, etc. Indication of operational status and other such parameters necessary to satisfy this requirement, is to be provided for all equipment under control by the integrated computer control system.

### 6.3 Operator stations

6.3.1 Each operator station allowing control of equipment is to be provided with a minimum of two multi-function display and control units. The number of units is to be sufficient to allow simultaneous access to control and monitoring functions required by 6.2.2 to 6.2.4. *See also* 2.10.19 to 2.10.20.

6.3.2 Each multi-function display and control unit is to include a monitor, keyboard and tracker ball. Alternative arrangements will be considered where these enable each unit to be configured by the user to provide required control or monitoring functions.

6.3.3 Where the integrated computer control system is arranged such that control and monitoring functions may be accessed at more than one operator station, the selected mode of operation of each station (e.g. in control, standby, etc.) is to be clearly indicated. *See also* 2.2.

6.3.4 Means of communication are to be provided between operator stations and any other stations from which the equipment may be controlled. The arrangements are to be permanently installed and are to remain operational in the event of failure of the main electrical power supply to the integrated control system.

### Section 7 Trials

#### 7.1 General

7.1.1 Before a new installation (or any alteration or addition to an existing installation) is put into service, trials are to be carried out. These trials are in addition to any acceptance tests which may have been carried out at the manufacturers' works and are to be based on the approved test schedules list as required by 1.2.2. In the case of new construction it will be expected that most of these trials will be carried out before the official sea trials of the ship. During sea trials, system dynamic tests are to be carried out to demonstrate overall satisfactory performance of the control engineering installation.

7.1.2 Means are to be provided to facilitate testing during normal machinery operation, e.g. by the provision of three-way test valves or equivalent.

#### 7.2 Unattended machinery space operation – UMS notation

7.2.1 In addition to the tests required by 7.1 the suitability of the installation for operation in the unattended mode is to be demonstrated during sea trials over a four to six hour period observing the following:

- Occurring alarms and the frequency of operation both during steady steaming and under manoeuvring conditions using bridge control.
- Any intervention by personnel in the operation of the machinery.

#### 7.3 Operation from a centralized control station – CCS notation

7.3.1 In addition to the tests required by 7.1, the suitability of the installation for operation from the centralized control station is to be demonstrated during sea trials.

#### 7.4 Record of trials

7.4.1 Two copies of the alarm and control equipment test schedules signed by the Surveyor and builder are to be provided on completion of the survey. One copy is to be placed on board the vessel and the other submitted to LR.



# Electrical Engineering

# Part 6, Chapter 2

Section 1

## Section

- 1 **General requirements**
- 2 **Main source of electrical power**
- 3 **Emergency source of electrical power**
- 4 **External source of electrical power**
- 5 **Supply and distribution**
- 6 **System design – Protection**
- 7 **Switchgear and control gear assemblies**
- 8 **Rotating machines**
- 9 **Converter equipment**
- 10 **Electric cables and busbar trunking systems (busways)**
- 11 **Batteries**
- 12 **Equipment – Heating, lighting and accessories**
- 13 **Electrical equipment for use in explosive gas atmospheres or in the presence of combustible dusts**
- 14 **Navigation and manoeuvring systems**
- 15 **Electric propulsion**
- 16 **Fire safety systems**
- 17 **Crew and passenger emergency safety systems**
- 18 **Ship safety systems**
- 19 **Lightning conductors**
- 20 **Testing and trials**
- 21 **Spare gear**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 The requirements of this Chapter apply to passenger ships and cargo ships except where otherwise stated.

1.1.2 Whilst these requirements are considered to meet those of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments, attention should also be given to any relevant Statutory Regulations of the National Administration of the country in which the ship is to be registered. Compliance with the Statutory Regulations of

the National Administration may be accepted as meeting the requirements of the *International Convention for the Safety of Life at Sea, 1974*, and applicable amendments.

1.1.3 Electrical services required to maintain the ship in a normal sea-going, operational and habitable condition are to be capable of being maintained without recourse to the emergency source of electrical power.

1.1.4 Electrical services essential for safety are to be maintained under various emergency conditions.

1.1.5 The safety of passengers, crew and ship from electrical hazards is to be ensured.

1.1.6 Lloyd's Register (hereinafter referred to as 'LR') will be prepared to give consideration to special cases or to arrangements which are equivalent to the Rules. Consideration will also be given to electrical arrangements of small ships and ships to be assigned class notation for restricted or special services.

### 1.2 Plans

1.2.1 At least three copies of the plans and particulars in 1.2.2 to 1.2.13 are to be submitted for consideration. Single copies only are required of plans in 1.2.14 to 1.2.17. Additional copies are to be submitted when requested.

1.2.2 Single line diagram of main and emergency power and lighting systems which is to include:

- (a) ratings of machines, transformers, batteries and semi-conductor converters;
- (b) all feeders connected to the main and emergency switchboards;
- (c) section boards and distribution boards;
- (d) insulation type, size and current loadings of cables;
- (e) make, type and rating of circuit-breakers and fuses.
- (f) details of harmonic filters (where fitted).

1.2.3 Simplified diagrams of generator circuits, inter-connector circuits and feeder circuits showing:

- (a) protective devices, e.g. short-circuit, overload, reverse power protection;
- (b) instrumentation and synchronizing devices;
- (c) preference tripping;
- (d) remote stops;
- (e) earth fault indication/protection.

1.2.4 Calculations of short-circuit currents at main and emergency switchboards and section boards including those fed from transformers, details of circuit-breaker and fuse operating times and discrimination curves showing compliance with 6.1 and 10.6.2.

1.2.5 For ships in which explosive gas atmospheres and/or combustible dusts occur – a general arrangement of the ship showing hazardous zones and spaces is to be submitted.

# Electrical Engineering

# Part 6, Chapter 2

Section 1

1.2.6 A schedule of electrical equipment located in hazardous areas giving details of:

- (a) type of equipment;
- (b) type of protection, e.g. Ex 'd';
- (c) apparatus group, e.g. IIB;
- (d) temperature class, e.g. T3;
- (e) enclosure ingress protection, e.g. IP55;
- (f) certifying authority;
- (g) certificate number;
- (h) location of equipment.

1.2.7 Simplified circuit diagram of electrical propulsion system (where fitted) giving details of:

- (a) ratings of electrical machines, transformers, batteries and semiconductor converters;
- (b) insulation type, size and current loadings of cables;
- (c) make, type and rating of circuit-breakers and fuses;
- (d) instrumentation and protective devices;
- (e) earth fault indication/protection;
- (f) explanation of the system with details of the propulsion control systems and the procedures used to ensure that there is satisfactory control of the design in relation to the requirements of Section 15.

1.2.8 Details of electrically-operated fire, ship, crew and passenger emergency safety systems which are to include typical single line diagrams and arrangements, showing main vertical and, where applicable, horizontal fire zones and the location of equipment and cable routes to be employed for:

- (a) emergency lighting;
- (b) accommodation fire detection, alarm and extinction systems;
- (c) Fixed water-based local application fire-fighting systems;
- (d) public address system;
- (e) general alarm;
- (f) watertight doors, bow, stern and shell doors and other electrically operated closing appliances.
- (g) low location lighting.

## NOTE

A general arrangement plan of the complete ship showing the main vertical fire zones and the location of equipment and cable routes, for the above systems, is to be made available for the use of the Surveyor on board.

1.2.9 A test schedule which is to include the method of testing and the test facilities which are provided for the general emergency alarm system and the public address system.

1.2.10 For battery installations, arrangement plans and calculations are to show compliance with 11.5.

1.2.11 A schedule of batteries fitted for use for emergency and essential services, giving details of:

- type and manufacturer's type designation;
- voltage and ampere-hour rating;
- location;
- equipment and/or system(s) served;
- maintenance/replacement cycle dates;
- date(s) of maintenance and/or replacement; and
- for replacement batteries in storage, the date of manufacture and shelf life; with accompanying battery replacement procedure documentation to show compliance with 11.7.

1.2.12 Plans of propulsion generators, motors, converting equipment, reactors and filters.

1.2.13 For all cables that pass through atria or equivalent spaces, and for vertical runs in trunks or other restricted spaces, the information supplied is to show compliance with 10.8.8.

1.2.14 In order to establish compliance with 1.10.2 and 5.1.4 to 5.1.6, a general arrangement plan of the ship showing the location of major items of electrical equipment, for example:

- main and emergency generators;
- switchboards;
- section boards and distribution boards supplying essential and emergency services;
- emergency batteries;
- motors for emergency services; and
- cable routes between these items of equipment.

1.2.15 Arrangement plans of main and emergency switchboards, and section boards.

1.2.16 Schedule of normal and emergency operating loads on the system estimated for the different operating conditions expected.

1.2.17 In order to establish compliance with the requirements of 1.6.3, evidence is to be submitted to demonstrate the suitability of electrical equipment for its intended purpose in the conditions in which it is expected to operate.

## 1.3 Surveys

1.3.1 Electrical propelling machinery and associated equipment together with auxiliary services essential for the safety of the ship are to be installed in accordance with the relevant requirements of this Chapter, surveyed and have tests witnessed by the Surveyors.

1.3.2 The following equipment, where intended for use for essential and emergency services, is to be surveyed by the Surveyors during manufacture and testing:

- Converting equipment of 100 kW and over;
- Rotating machines of 100 kW and over;
- Switchboards and section boards; and
- UPS units of 50 kVA and over.

1.3.3 For electric propulsion systems, in addition to the equipment listed in 1.3.2, the following equipment is to be surveyed by the Surveyors during manufacture and testing:

- cables;
- exciters;
- filters;
- reactors;
- slip ring assemblies.

1.3.4 For refrigerating cargo installations having an **RMC** notation, motors are to be tested and certificates furnished by the manufacturer. Motors of 100 kW or over are to be surveyed by the Surveyors during manufacture and testing.

# Electrical Engineering

## Part 6, Chapter 2

Section 1

1.3.5 All other electrical equipment, not specifically referenced in 1.3.2 to 1.3.4, intended for use for essential or emergency services is to be supplied with a manufacturer's works test certificate showing compliance with the constructional standard(s) as referenced by the relevant requirements of this Chapter.

### 1.4 Additions or alterations

1.4.1 No addition, temporary or permanent, is to be made to the approved load of an existing installation until it has been ascertained that the current carrying capacity and the condition of the existing equipment including cables and switchgear are adequate for the increased load.

1.4.2 Plans are to be submitted for consideration, and the alterations or additions are to be carried out under the survey, and to the satisfaction of the Surveyors.

1.4.3 When it is proposed to replace permanently installed secondary valve-regulated sealed batteries with vented batteries, details are to be submitted for consideration to ensure continued safety in the presence of the products of electrolysis and evaporation being allowed to escape freely from the cells to the atmosphere. These details are to demonstrate that there will be adequate ventilation in accordance with 11.5.9 and that the location and installation requirements of 11.3 and 11.4 are complied with.

### 1.5 Definitions

1.5.1 Essential services are those necessary for the propulsion and safety of the ship, such as the following:

- air compressors for oil engines;
- air pumps;
- automatic sprinkler systems;
- ballast pumps;
- bilge pumps;
- circulating and cooling water pumps;
- communication systems;
- condenser circulating pumps;
- electric propulsion equipment;
- electric starting systems for oil engines;
- extraction pumps;
- fans for forced draught to boilers;
- feed water pumps;
- fire detection and alarm systems;
- fuel valve cooling pumps;
- hydraulic pumps for controllable pitch propellers and those serving essential services here listed that would otherwise be directly electrically-driven;
- lubricating oil pumps;
- inert gas fans and scrubber and deck seal pumps;
- lighting systems for those parts of the ship normally accessible to and used by personnel and passengers;
- navigational aids where required by Statutory Regulations;
- navigation lights and special purpose lights where required by Statutory Regulations;
- oil fuel pumps and oil fuel burning units;
- oil separators;
- pumps for fire-extinguishing systems;
- scavenge blowers;

- steering gear;
- thrusters for dynamic positioning;
- valves which are required to be remotely operated;
- ventilating fans for engine and boiler rooms;
- watertight doors, shell doors and other electrical operated closing appliances;
- windlasses;
- power sources and supply systems for supplying the above services.

1.5.2 Services such as the following are considered necessary for minimum comfortable conditions of habitability:

- cooking;
- heating;
- domestic refrigeration;
- mechanical ventilation;
- sanitary and fresh water.

1.5.3 Services such as the following, which are additional to those in 1.5.1 and 1.5.2, are considered necessary to maintain the ship in a normal sea-going operational and habitable condition:

- cargo handling and cargo care equipment;
- hotel services, other than those required for habitable conditions;
- thrusters, other than those for dynamic positioning.

1.5.4 A 'high voltage' is a voltage exceeding 1000 V a.c. or 1500 V d.c. between conductors, see also 5.1.3.

1.5.5 A 'switchboard' is a switchgear and control gear assembly for the control of power generated by a source of electrical power and its distribution to electrical consumers.

1.5.6 A 'section board' is a switchgear and control gear assembly for controlling the supply of electrical power from a switchboard and distributing it to other section boards, distribution boards or final sub-circuits.

1.5.7 A 'distribution board' is an assembly of one or more protective devices arranged for the distribution of electrical power to final sub-circuits.

1.5.8 A 'final sub-circuit' is that portion of a wiring system extending beyond the final overcurrent device of a board.

1.5.9 'Special category spaces' are those enclosed spaces above or below the bulkhead deck intended for the carriage of motor vehicles with fuel, for their own propulsion, in their tanks, into and from which such vehicles can be driven, and to which passengers have access. Special category spaces may be accommodated on more than one deck provided that the total overall clear height for vehicles does not exceed 10 m.

1.5.10 'Machinery spaces of Category A' are those spaces and trunks to such spaces which contain:

- (a) internal combustion machinery used for main propulsion; or
- (b) internal combustion machinery used for purposes other than main propulsion where such machinery has in the aggregate a total power output of not less than 375 kW; or
- (c) any oil-fired boiler or oil fuel unit.

1.5.11 'Dead ship condition' means that the entire machinery installation, including the power supply, is out of operation and that the auxiliary services for bringing the main propulsion systems into operation (e.g. compressed air, starting current from batteries, etc.) and for the restoration of the main power supply are not available. Means are to be available to start the emergency generator at all times, see Pt 5, Ch 2,8.5.

1.5.12 Protected space is a machinery space where a fixed water-based local application fire-fighting system is installed.

1.5.13 Protected areas are areas within a protected space which is required to be protected by a fixed water-based local application fire-fighting system.

1.5.14 Adjacent areas are areas, other than protected areas, exposed to direct spray or other areas where water may extend when a fixed water-based local application fire-fighting system is activated.

## 1.6 Design and construction

1.6.1 Electrical propelling machinery and associated equipment together with equipment for services essential for the propulsion and safety of the ship are to be constructed in accordance with the relevant requirements of this Chapter.

1.6.2 The design and installation of other equipment is to be such that risk of fire due to its failure is minimized. It is, as a minimum, to comply with a National or International Standard revised where necessary for ambient conditions.

1.6.3 Electrical equipment is to be suitable for its intended purpose and accordingly, whenever practicable, be selected from the *List of Type Approved Products* published by LR. A copy of the Procedure for LR Type Approval System will be supplied on application.

## 1.7 Quality of power supplies

1.7.1 All electrical equipment supplied from the main and emergency sources of electrical power and electrical equipment for essential and emergency services supplied from d.c. sources of electrical power is to be so designed and manufactured that it is capable of operating satisfactorily under normally occurring variations of voltage and frequency.

1.7.2 Unless specified otherwise, a.c. electrical equipment is to operate satisfactorily with the following simultaneous variations, from their nominal value, when measured at the consumer input terminals:

- (a) voltage:
  - permanent variations +6%, -10%
  - transient variations due to step changes in load ±20%
  - recovery time 1,5 seconds

- (b) frequency:
  - permanent variations ±5%
  - transient variations due to step changes in load ±10%
  - recovery time 5 seconds
  - A maximum rate of change of frequency not exceeding ±1,5 Hz per second during cyclic frequency fluctuations.

1.7.3 **Harmonics.** Unless specified otherwise, the total harmonic distortion (THD) of the voltage waveform at any a.c. switchboard or section board is not to exceed 8 per cent of the fundamental for all frequencies up to 50 times the supply frequency and no voltage at a frequency above 25 times supply frequency is to exceed 1,5 per cent of the fundamental of the supply voltage. THD is the ratio of the rms value of the harmonic content to the rms value of the fundamental, expressed in per cent and may be calculated using the expression:

$$THD = \frac{\sqrt{\sum_{h=2}^{\infty} V_h^2}}{V_1} \times 100$$

where

- $V_h$  = rms amplitude of a harmonic voltage of order  $h$
- $V_1$  = rms amplitude of the fundamental voltage.

1.7.4 Unless specified otherwise, d.c. electrical equipment, is to operate satisfactorily with the following simultaneous variations, from their nominal value, when measured at the consumer input terminals:

- (a) When supplied by d.c. generator(s) or a rectified a.c. supply:
  - Voltage tolerance (continuous) ±10%
  - Voltage cyclic variation deviation 5%
  - Voltage ripple 10% (a.c. rms over steady state d.c. voltage);
- (b) When supplied by batteries:
  - (i) Equipment connected to the batteries during charging: Voltage tolerance +30%, -25%;
  - (ii) Equipment not connected to batteries during charging: Voltage tolerance +20%, -25%.

Different voltage variations as determined by the charging/discharging characteristics, including ripple voltage from the charging device, may be considered. When battery chargers/battery combinations are used as d.c. power supply systems adequate measures are to be taken to keep the voltage within the specified limits during charging, boost charging and discharging of the battery.

## 1.8 Ambient reference and operating conditions

1.8.1 The rating for classification purposes of essential electrical equipment intended for installation in ships to be classed for unrestricted (geographical) service is to be based on an engine room ambient temperature of 45°C, and a sea-water temperature at the inlet of 32°C. The equipment manufacturer is not expected to provide simulated ambient reference conditions at a test bed.

1.8.2 In the case of a ship to be classed for restricted service, the rating is to be suitable for the ambient conditions associated with the geographical limits of the restricted service, see Pt 1, Ch 2.

# Electrical Engineering

## Part 6, Chapter 2

Section 1

1.8.3 Main and essential auxiliary machinery and equipment is to operate satisfactorily under the conditions shown in Pt 5, Ch 1.3.6. Electrical equipment satisfying alternative ambient operating condition requirements for installation on ships contained in an acceptable and relevant National or International Standard may be considered to satisfy this requirement.

### NOTE

Details of local environmental conditions are stated in Annex B of IEC 60092: *Electrical installations in ships – Part 101: Definitions and general requirements*.

1.8.4 Where electrical equipment is installed within environmentally controlled spaces, the ambient temperature for which the equipment is suitable for operation at its rated capacity may be reduced to a value not less than 35°C provided:

- the equipment is not for use for emergency services and is located outside of machinery space(s);
- temperature control is achieved by at least two cooling units so arranged that, in the event of loss of one cooling unit, for any reason, the remaining unit(s) will be capable of satisfactorily maintaining the design temperature;
- the equipment is able to be initially set to work safely within a 45°C ambient temperature until such a time that the lesser ambient temperature may be achieved; the cooling equipment is to be rated for an ambient temperature of not less than 45°C; and
- alarms are provided, at a continually attended control station, to indicate any malfunction of the cooling units.

See also Pt 6, Ch 1, 1.3.3.

1.8.5 Where equipment is to comply with 1.8.4, it is to be ensured that electrical cables for their entire length are adequately rated for the maximum ambient temperature to which they are exposed along their length.

1.8.6 Equipment used for cooling and maintaining the lesser ambient temperature in accordance with 1.8.4 are considered essential services and are to satisfy the requirements of 5.2.

## 1.9 Inclination of ship

1.9.1 Emergency and essential electrical equipment is to operate satisfactorily under the conditions as shown in Table 2.1.1.

1.9.2 In ships for the carriage of liquefied gas and of liquid chemicals the emergency source of electrical power is also to remain operable with the ship flooded to a final athwartships inclination up to a maximum of 30°.

1.9.3 Any proposal to deviate from the angles given in Table 2.1.1 will be specially considered taking into account the type, size and service of the ship.

1.9.4 The dynamic angles of inclination in Table 2.1.1 may be exceeded in certain circumstances dependent upon ship type and operation. The Shipbuilder is, therefore, to ensure that the electrical equipment is capable of operating under these angles of inclination.

**Table 2.1.1 Inclination of ship**

Installations, components	Angle of inclination, degrees (see Note 2)			
	Athwartships		Fore-and-aft	
	static	dynamic	static	dynamic
Essential electrical equipment	15	22,5	5 (see Note 3)	7,5
Safety systems, e.g. emergency power installations, crew and passenger safety systems	22,5	22,5	10	10
Switchgear, electrical and electronic appliances (see Note 1)				
<b>NOTES</b> 1. Up to an angle of 45° no undesired switching operations or operational changes may occur. 2. Athwartships and fore-and-aft inclinations may occur simultaneously. 3. Where the length of the ship exceeds 100 m, the fore-and-aft static angle of inclination may be taken as: $\frac{500}{L} \text{ degrees}$ where $L$ = Rule length, in metres (see Pt 3, Ch 1.6.1).				

## 1.10 Location and construction

1.10.1 All electrical equipment is to be constructed or selected, and installed such that:

- live parts cannot be inadvertently touched, unless they are supplied at the safety voltage specified in 1.11.2(h);
- it does not cause injury when handled or touched in the normal manner; and
- it is unaffected by any water, steam or oil and oil vapour to which it is likely to be exposed.

Electrical equipment having, as a minimum, the degrees of protection as specified in IEC 60092-201: *Electrical installations in ships – Part 201: System design – General* for the relevant location will satisfy these requirements.

1.10.2 Switchboards, section boards and distribution boards supplying essential and emergency services, as well as cables from the respective generators to and between these boards, are to be arranged to avoid areas of high fire risk and elevated temperatures, for example, in close proximity to incinerators and boilers.

# Electrical Engineering

## Part 6, Chapter 2

Section 1

**1.10.3** Electrical equipment, as far as is practicable, is to be located:

- (a) such that it is accessible for the purpose of maintenance and survey;
- (b) clear of flammable material;
- (c) in spaces adequately ventilated to remove the waste heat liberated by the equipment under full load conditions, at the ambient conditions specified in 1.8;
- (d) where flammable gases cannot accumulate. If this is not practicable, electrical equipment is to be of the appropriate 'safe-type', see Section 13;
- (e) where it is not exposed to the risk of mechanical injury or damage from water, steam or oil.

**1.10.4** Equipment design and the choice of materials are to reduce the likelihood of fire, ensuring that:

- (a) where the electrical energized part can cause ignition and fire, it is contained within the bounds of the enclosure of the electrotechnical product;
- (b) the design, material(s) and construction of the enclosure minimizes, as far as is practicable, any internal ignition causing ignition of adjacent materials; and
- (c) where surfaces of the electrotechnical products can be exposed to external fire, they do not, as far as practicable, contribute to the fire growth.

NOTE:

Compliance with IEC 60695: *Fire hazard testing*, or an alternative and acceptable Standard, will satisfy this requirement.

**1.10.5** Insulating materials and insulated windings are to be resistant to tracking, moisture, sea air, oil and oil vapour unless special precautions are taken to protect them.

**1.10.6** Studs, screw-type or spring-type clamp terminations, satisfactory for the normal operating currents and voltages, are to be provided in electrical equipment for the connection of external cable, or bus-bar conductors, as appropriate, see also 10.14. There is to be adequate space and access for the terminations.

**1.10.7** Equipment is not to remain alive through the control circuits and/or pilot lamps when switched off by the control switch. This does not apply to synchronizing switches and/or plugs.

**1.10.8** The operation of all electrical equipment and the lubrication arrangements are to be efficient under such conditions of vibration and shock as arise in normal practice.

**1.10.9** All nuts, screws and clamping devices used in connection with current-carrying, supporting and working parts are to be provided with means to ensure that they cannot work loose by vibration and shock as arise in normal practice.

**1.10.10** Conductors and equipment are to be placed at such a distance from the magnetic compasses, or are to be so disposed, that the interfering magnetic field is negligible when circuits are switched on and off.

**1.10.11** Where electrical power is used for propulsion, the equipment is to be so arranged that it will operate satisfactorily in the event of partial flooding by bilge water above the tank top up to the bottom floor plate level, under the normal angles of inclination given in 1.9 for essential electrical equipment, see Pt 5, Ch 13.

### 1.11 Earthing of non-current carrying parts

**1.11.1** Except where exempted by 1.11.2, all non-current carrying exposed metal parts of electrical equipment and cables are to be earthed for personal protection against electric shock.

**1.11.2** The following parts may be exempted from the requirements of 1.11.1:

- (a) lamp-caps, where suitably shrouded;
- (b) shades, reflectors and guards supported on lampholders or light fittings constructed of, or shrouded in, non-conducting material;
- (c) metal parts on, or screws in or through, non-conducting materials, which are separated by such material from current-carrying parts and from earthed non-current carrying parts in such a way that in normal use they cannot become live or come into contact with earthed parts;
- (d) apparatus which is constructed in accordance with the principle of double insulation;
- (e) bearing housings which are insulated in order to prevent circulation of current in the bearings;
- (f) clips for fluorescent lamps;
- (g) cable clips and short lengths of pipes for cable protection;
- (h) apparatus supplied at a safety voltage not exceeding 50 V d.c. or 50 V a.c., between conductors, or between any conductor and earth in a circuit isolated from the supply. Autotransformers are not to be used for the purpose of achieving the alternating current voltage;
- (j) apparatus or parts of apparatus which although not shrouded in insulating material is nevertheless otherwise so guarded that it cannot be touched and cannot come in contact with exposed metal.

**1.11.3** Armouring, braiding and other metal coverings of cables are to be effectively earthed. Where the armouring, braiding and other metal coverings are earthed at one end only, they are to be adequately protected and insulated at the unearthed end with the insulation being suitable for the maximum voltage that may be induced. See 13.8.3 for earthing of cables in dangerous zones or spaces.

**1.11.4** The electrical continuity of all metal coverings of cables throughout the length of the cable, particularly at joints and tappings, is to be ensured.

**1.11.5** Metal parts of portable appliances, other than current-carrying parts and parts exempted by 1.11.2 are to be earthed by means of an earth-continuity conductor in the flexible cable or cord through the associated plug and socket-outlet.



# Electrical Engineering

## Part 6, Chapter 2

### Section 1

1.11.6 Earthing conductors are to be of copper or other corrosion-resistant material and be securely installed and protected where necessary against damage and also, where necessary, against electrolytic corrosion. Connections are to be so secured that they cannot work loose under vibration.

1.11.7 The nominal cross-section areas of copper earthing conductors for electrical equipment are, in general to be equal to the cross-section of the current-carrying conductor up to 16 mm<sup>2</sup>, with a minimum of 1,5 mm<sup>2</sup>. Above this figure they are to be equal to at least half the cross-section of the current-carrying conductor with a minimum of 16 mm<sup>2</sup>.

1.11.8 The nominal cross-section areas of copper earthing conductors for armouring, braiding and other metal coverings of cables are, in general, to be equal to the equivalent cross-section of the armouring, braiding and other metal coverings with a minimum of 1,5 mm<sup>2</sup>.

1.11.9 Earthing conductors of materials other than copper are to have a conductance not less than that specified for an equivalent copper earthing conductor.

1.11.10 The connection of the earthing conductor to the hull of the ship is to be made in an accessible position, and is to be secured by a screw or stud of diameter not less than 6 mm which is to be used for this purpose only. Bright metallic surfaces at the contact areas are to be ensured immediately before the nut or screw is tightened and, where necessary, the joint is to be protected against electrolytic corrosion. The connection is to remain unpainted.

### 1.12 Bonding for the control of static electricity

1.12.1 Bonding straps for the control of static electricity are required for cargo tanks, process plant and piping systems, for flammable products and solids liable to release flammable gas and/or combustible dust, which are not permanently connected to the hull of the ship either directly or via their bolted or welded supports and where the resistance between them and the hull exceeds 1 MΩ.

1.12.2 Where bonding straps are required for the control of static electricity, they are to be robust, that is, having a cross-sectional area of about 10 mm<sup>2</sup>, and are to comply with 1.11.6 and 1.11.8.

### 1.13 Alarms

1.13.1 Where alarms are required by this Chapter they are to be arranged in accordance with Ch 1,2.3. Sound signal equipment, fire and general alarm bells are not required to be supplemented by visual alarms, except in areas having high levels of background noise, such as machinery spaces.

1.13.2 The alarms in this Chapter are additional to those required by Chapter 1. They may however form part of the alarm system that is required by Chapter 1.

1.13.3 Cables for emergency alarms and their power sources are to be in accordance with 1.14.

1.13.4 Electrical equipment and cables for emergency alarms are to be so arranged that the loss of alarms in any one area due to localized fire, collision, flooding or similar damage is minimized, see 1.14.

### 1.14 Operation under fire conditions

1.14.1 As a minimum, the following emergency services and their emergency power supplies, are required to be capable of being operated under fire conditions:

- Control and power systems to power-operated fire doors and status indication for all fire doors.
- Control and power systems to power-operated watertight doors and their status indication.
- Emergency lighting.
- Fire and general alarms.
- Fire detection systems.
- Fire-extinguishing systems and fire-extinguishing media release alarms.
- Fire safety stops, see *also* 16.6.
- Low location lighting, see *also* 17.4.3.
- Public address systems.
- Emergency fire pump.

1.14.2 Where cables for the emergency services listed in 1.14.1 pass through high fire risk areas, main vertical or horizontal fire zones other than those which they serve, they are to be so arranged that a fire in any of these areas or zones does not affect the operation of the emergency service in any other area or zone. This may be achieved either by:

- cables being of a fire resistant type complying with 10.5.3, and at least extending from the main control/monitoring panel to the nearest local distribution panel serving the relevant area or zone; or
- there being at least two-loops/radial distributions run as widely apart as is practicable and so arranged that in the event of damage by fire at least one of the loops/radial distributions remains operational.

1.14.3 Where the cables for the power supplies for the emergency services listed in 1.14.1 pass through high fire risk areas, main vertical or horizontal fire zones other than those which they serve, they are to be of a fire resistant type complying with 10.5.3, extending at least to the local distribution panel serving the relevant area or zone.

1.14.4 Fire resistant electrical cables for the emergency services listed in 1.14.1, including their power supplies, are to be run as directly as is practicable, having regard to any special installation requirements, for example those concerning minimum bend radii.

1.14.5 In addition to 1.10.4, materials used for electrical equipment, cables and accessories within passenger accommodation areas are not to be capable of producing excessive quantities of smoke and toxic products.

#### NOTE:

Compliance with IEC 60695: Fire hazard testing, or an alternative and acceptable Standard, will satisfy this requirement.

# Electrical Engineering

# Part 6, Chapter 2

Sections 1 & 2

## 1.15 Protection of electrical equipment against the effects of lightning strikes

1.15.1 Precautions are to be taken to protect essential electronic equipment that may be susceptible to damage from voltage pulses attributable to the secondary effects of lightning. This may be achieved by suitable design and/or the use of additional protective devices, such as surge arrestors. Resultant induced voltages may be further reduced by the use of earthed metallic screened cables. See *also* Section 19.

## Section 2 Main source of electrical power

### 2.1 General

2.1.1 The main source of electrical power is to comply with the requirements of this section without recourse to the emergency source of electrical power.

### 2.2 Number and rating of generators and converting equipment

2.2.1 Under sea-going conditions, the number and rating of service generating sets and converting sets, such as transformers and semi-conductor converters, when any one generating set or converting set is out of action, are:

- (a) to be sufficient to ensure the operation of electrical services for essential equipment, habitable conditions, cargo refrigeration machinery of ships having a **RMC** notation and the container socket outlets and ventilation system of container ships having a **CRC** notation. See 15.2.5 for electric propulsion systems;
- (b) to have sufficient reserve capacity to permit the starting of the largest motor without causing any motor to stall or any device to fail due to excessive voltage drop on the system;
- (c) to be capable of providing the electrical services necessary to start the main propulsion machinery from a dead ship condition. The emergency source of electrical power may be used to assist if it can provide power at the same time to those services required to be supplied by Section 3, see *also* 2.3.2.

2.2.2 The arrangement of the ship's main source of power is to be such that the operation of electrical services for essential equipment, habitable conditions and cargo refrigeration machinery of ships having a **RMC** notation can be maintained regardless of the speed and direction of the propulsion machinery shafting.

2.2.3 Where the electrical power requirement to maintain the ship in a normal operational and habitable condition is usually supplied by one generating set, arrangements are to be provided to prevent overloading of the running generator (see 6.9). On loss of power there is to be provision for automatic starting and connecting to the main switchboard of the standby set in as short a time as practicable, but in any case within 45 seconds, and automatic sequential restarting of essential services (see 1.5.1), in as short a time as is practicable.

#### NOTE

Where the prime mover starting time will result in exceeding this starting and connection time, details are to be submitted for consideration.

### 2.3 Starting arrangements

2.3.1 The starting arrangements of the generating sets prime movers are to comply with the requirements of Pt 5, Ch 2,8 as applicable.

2.3.2 Where the emergency source of electrical power is required to be used to restore propulsion from a 'dead ship condition', the emergency generator is to be capable of providing initial starting energy for the propulsion machinery within 30 minutes of the 'dead ship condition'. The emergency generator capacity is to be sufficient for restoring propulsion in addition to supplying those services in Section 3. See Pt 5, Ch 2,8.1.1 for dead ship condition starting arrangements.

### 2.4 Prime mover governors

2.4.1 The governing accuracy of the generating sets prime movers is to meet the requirements of Pt 5, Ch 2,5.3.

2.4.2 The maximum electrical step load switched on or off is not to cause the frequency variation of the electrical supply to exceed the parameters given in 1.7.2.

### 2.5 Main propulsion driven generators not forming part of the main source of electrical power

2.5.1 Generators and generator systems, having the ship's propulsion machinery as their prime mover but not forming part of the ship's main source of electrical power may be used whilst the ship is at sea to supply electrical services required for normal operational and habitable conditions provided that the requirements of 2.5.2 to 2.5.4 are satisfied.

2.5.2 Within the declared operating range of the generators and/or generator system, the specified voltage and frequency variations of the Rules are to be met.

2.5.3 Where there is remote control of the propulsion machinery, arrangements are to ensure that essential machinery power supplies are maintained during manoeuvring conditions in order to prevent a blackout situation.

2.5.4 In addition to the requirements of 2.2.3, arrangements are to be fitted to automatically start one of the generators forming the main source of power should the frequency variations exceed those permitted by the Rules.

# Electrical Engineering

## Part 6, Chapter 2

Section 3

### ■ Section 3 Emergency source of electrical power

#### 3.1 General

3.1.1 The requirements of this Section apply to passenger and cargo ships to be classed for unrestricted service. They do not apply to cargo ships of less than 500 tons gross tonnage.

3.1.2 For ships assigned a Service Restriction Notation in accordance with Pt 1, Ch 2, a lesser period than the 36 hour period and 18 hour period specified in 3.2.5 and 3.3.5 respectively may be considered, but not less than 12 hours.

3.1.3 The emergency source of power for cargo ships of less than 500 tons gross tonnage will be the subject of special consideration.

#### 3.2 Emergency source of electrical power in passenger ships

3.2.1 A self-contained emergency source of electrical power is to be provided.

3.2.2 The emergency source of electrical power, associated transforming equipment, if any, transitional source of emergency power, emergency switchboard and emergency lighting switchboard are to be located above the uppermost continuous deck and be readily accessible from the open deck. They are not to be located forward of the collision bulkhead.

3.2.3 The location of the emergency source of electrical power and associated transforming equipment, if any, the transitional source of emergency power, the emergency switchboard and the emergency lighting switchboard in relation to the main source of electrical power, associated transforming equipment, if any, and the main switchboard is to be such as to ensure that a fire or other casualty in spaces containing the main source of electrical power, associated transforming equipment, if any, and the main switchboard or in any machinery space of Category A will not interfere with the supply, control and distribution of emergency electrical power. The space containing the emergency source of electrical power, associated transforming equipment, if any, the transitional source of emergency electrical power and the emergency switchboard is not to be contiguous to the boundaries of machinery spaces of Category A and those spaces containing the main source of electrical power, associated transforming equipment, if any, or the main switchboard. Where this is not practicable, details of the proposed arrangements are to be submitted.

3.2.4 Provided that suitable measures are taken for safeguarding independent emergency operation under all circumstances, the emergency generator may be used exceptionally, and for short periods, to supply non-emergency circuits.

3.2.5 The electrical power available is to be sufficient to supply all those services that are essential for safety in an emergency, due regard being paid to such services as may have to be operated simultaneously. The emergency source of electrical power is to be capable, having regard to starting currents and the transitory nature of certain loads, of supplying simultaneously at least the following services for the periods specified hereinafter, if they depend upon an electrical source for their operation:

- (a) For a period of 36 hours, emergency lighting:
  - (i) at every lifeboat preparation station, muster and embarkation station and oversides;
  - (ii) in alleyways, stairways and exits, giving access to the muster and embarkation stations;
  - (iii) in all service and accommodation alleyways, stairways and exits, personnel lift cars;
  - (iv) in the machinery spaces and main generating stations including their control positions;
  - (v) in all control stations, machinery control rooms, and at each main and emergency switchboard;
  - (vi) at all stowage positions for fireman's outfits;
  - (vii) at the steering gear; and
  - (viii) at the fire pump, the sprinkler pump and the emergency bilge pump and at the starting position of their motors;
- (b) For a period of 36 hours:
  - (i) the navigation lights and other lights, as required by the *International Regulations for Preventing Collisions at Sea* in force; and
  - (ii) the radiocommunications, as required by Amendments to SOLAS 1974, Chapter IV.
- (c) For a period of 36 hours:
  - (i) all internal communication equipment required in an emergency;
  - (ii) the navigational aids as required by Amendments to SOLAS 1974 Reg V/19; where such provision is unreasonable or impracticable this requirement may be waived for ships of less than 5000 tons gross;
  - (iii) the fire detection, fire alarm and sample extraction smoke detection systems, and the fire door holding and release system; and
  - (iv) for intermittent operation of the daylight signalling lamp, the ship's whistle, the manually-operated call points and all internal signals that are required in an emergency;

unless such services have an independent supply for the period of 36 hours from an accumulator battery suitably located for use in an emergency.
- (d) For a period of 36 hours:
  - (i) emergency fire pump;
  - (ii) the automatic sprinkler pump, if any; and
  - (iii) the emergency bilge pump and all the equipment essential for the operation of electrically-powered remote controlled bilge valves.
- (e) The steering gear for the period of time required by Pt 5, Ch 19,6.
- (f) For a period of half an hour:
  - (i) any watertight doors if electrically-operated together with their control, indication and alarm circuits;

# Electrical Engineering

# Part 6, Chapter 2

Section 3

- (ii) the emergency arrangements to bring the lift cars to deck level for the escape of persons. The passenger lift cars may be brought to deck level sequentially in an emergency.
- (g) Where applicable, the services required by 2.3.2.

3.2.6 The emergency source of electrical power may be either a generator or an accumulator battery, which are to comply with the following:

- (a) Where the emergency source of electrical power is a generator it is to be:
  - (i) driven by a suitable prime mover with an independent supply of fuel having a flashpoint (closed-cup test) of not less than 43°C;
  - (ii) started automatically upon failure of the electrical supply from the main source of electrical power and is to be automatically connected to the emergency switchboard; those services referred to in 3.2.5 are then to be transferred automatically to the emergency generating set. The automatic starting system and the characteristics of the prime mover are to be such as to permit the emergency generator to carry its full rated load as quickly as is safe and practicable, subject to a maximum of 45 seconds; and
  - (iii) provided with a transitional source of emergency electrical power according to 3.2.7.
- (b) Where the emergency source of electrical power is an accumulator battery, it is to be capable of:
  - (i) carrying the emergency electrical load without recharging while maintaining the voltage of the battery throughout the discharge period within 12 per cent above or below its nominal voltage;
  - (ii) automatically connecting to the emergency switchboard in the event of failure of the main source of electrical power; and
  - (iii) immediately supplying at least those services specified in 3.2.7.

3.2.7 The transitional source of emergency electrical power required by 3.2.6 is to consist of an accumulator battery suitably located for use in an emergency which is to operate without recharging while maintaining the voltage of the battery throughout the discharge period within 12 per cent above or below its nominal voltage and be of sufficient capacity and so arranged as to supply automatically in the event of failure of either the main or emergency source of electrical power at least the following services, if they depend upon an electrical source for their operation:

- (a) For half an hour:
  - (i) the lighting required by 3.2.5(a) and (b);
  - (ii) all services required by 3.2.5(c)(i), (iii) and (iv) unless such services have an independent supply for the period specified from an accumulator battery suitably located for use in an emergency.
- (b) Power to operate the watertight doors at least three times, i.e. closed-open-closed against an adverse list of 15°, but not necessarily all of them simultaneously, together with their control, indication and alarm circuits as required by 3.2.5(f)(i).

3.2.8 The emergency switchboard is to be installed as near as is practicable to the emergency source of electrical power.

3.2.9 Where the emergency source of electrical power is a generator, the emergency switchboard is to be located in the same space unless the operation of the emergency switchboard would thereby be impaired.

3.2.10 No accumulator battery except for engine starting, fitted in accordance with this Section is to be installed in the same space as the emergency switchboard. An indicator is to be mounted in a suitable place on the main switchboard or in the machinery control room to indicate when the batteries constituting either the emergency source of electrical power or the transitional source of emergency electrical power are being discharged.

3.2.11 The emergency switchboard is to be supplied during normal operation from the main switchboard by an interconnector feeder which is to be adequately protected at the main switchboard against overload and short-circuit and which is to be disconnected automatically at the emergency switchboard upon failure of the main source of electrical power. Where the system is arranged for feedback operation, the interconnector feeder is also to be protected at the emergency switchboard at least against short-circuit.

3.2.12 In order to ensure the ready availability of the emergency source of electrical power to supply emergency circuits, arrangements are to be made, where necessary, to automatically disconnect non-emergency circuits from the emergency switchboard to ensure that electrical power is available to the emergency circuits. The arrangements are to automatically disconnect sufficient non-emergency loads to ensure continued safe operation of the emergency source of electrical power in the event of overloading.

3.2.13 Provision is to be made for the periodic testing of the complete emergency system and is to include the testing of automatic starting arrangements.

3.2.14 In addition to the emergency lighting required by 3.2.5(a) passenger ships with roll on-roll off cargo spaces or special category spaces are to be provided with the following:

- (a) in all passenger public spaces and alleyways supplementary electric lighting that can operate for at least three hours when all other sources of electric power have failed and under any condition of heel. The illumination provided is to be such that the approach to the means of escape can be readily seen. The source of power for the supplementary lighting is to consist of accumulator batteries within the lighting units that are continuously charged where practicable, from the emergency switchboard. Consideration may be given to other means of lighting which is at least as effective. The supplementary lighting is to be such that any failure of the lamp will be immediately apparent. Any accumulator battery provided is to be replaced at intervals having regard to the specified service life in the ambient conditions that they are subject to in service.
- (b) A portable rechargeable battery operated lamp is to be provided in every crew space alleyway, recreational space and every working space which is normally occupied unless supplementary emergency lighting, as required by (a) is provided.

# Electrical Engineering

## Part 6, Chapter 2

Section 3

### 3.3 Emergency source of electrical power in cargo ships

3.3.1 A self-contained emergency source of electrical power is to be provided.

3.3.2 The emergency source of electrical power, associated transforming equipment, if any, transitional source of emergency power, emergency switchboard and emergency lighting switchboard are to be located above the uppermost continuous deck and be readily accessible from the open deck. They are not to be located forward of the collision bulkhead.

3.3.3 The location of the emergency source of electrical power and associated transforming equipment, if any, the transitional source of emergency power, the emergency switchboard and the emergency lighting switchboard in relation to the main source of electrical power, associated transforming equipment, if any, and the main switchboard are to be such as to ensure that a fire or other casualty in the space containing the main source of electrical power, associated transforming equipment, if any, and the main switchboard, or in any machinery space of Category A will not interfere with the supply, control and distribution of emergency electrical power. The space containing the emergency source of electrical power, associated transforming equipment, if any, the transitional source of emergency electrical power and the emergency switchboard is not to be contiguous to the boundaries of machinery spaces of Category A or those spaces containing the main source of electrical power, associated transforming equipment, if any, and the main switchboard. Where this is not practicable, details of the proposed arrangements are to be submitted.

3.3.4 Provided that suitable measures are taken for safeguarding independent emergency operation under all circumstances, the emergency generator may be used, exceptionally, and for short periods, to supply non-emergency circuits.

3.3.5 The electrical power available is to be sufficient to supply all those services that are essential for safety in an emergency, due regard being paid to such services as may have to be operated simultaneously. The emergency source of electrical power is to be capable, having regard to starting currents and the transitory nature of certain loads, of supplying simultaneously at least the following services for the periods specified hereinafter, if they depend upon an electrical source for their operation:

- (a) For a period of three hours, emergency lighting at every lifeboat preparation station, muster and embarkation station and over the sides.
- (b) For a period of 18 hours, emergency lighting:
  - (i) in all service and accommodation alleyways, stairways and exits, personnel lift cars and personnel lift trunks;
  - (ii) in the machinery spaces and main generating stations including their control positions;
  - (iii) in all control stations, machinery control rooms, and at each main and emergency switchboard;
  - (iv) at all stowage positions for fireman's outfits;
  - (v) at the steering gear; and

- (vi) at the emergency fire pump, at the sprinkler pump, if any, and at the emergency bilge pump, if any, and at the starting positions of their motors;
- (vii) in all cargo pump rooms of tankers.
- (c) For a period of 18 hours:
  - (i) the navigation lights and other lights, as required by the *International Regulations for Preventing Collisions at Sea* in force; and
  - (ii) the radiocommunications, as required by Amendments to SOLAS 1974, Chapter IV.
- (d) For a period of 18 hours:
  - (i) all internal communication equipment as required in an emergency;
  - (ii) the navigational aids as required by Amendments to SOLAS 1974 Reg V/19; where such provision is unreasonable or impracticable this requirement may be waived for ships of less than 5000 tons gross;
  - (iii) the fire detection and fire-alarm system; and
  - (iv) intermittent operation of the daylight signalling lamp, the ship's whistle, the manually operated call points and all internal signals that are required in an emergency;

unless such services have an independent supply for the period of 18 hours from an accumulator battery suitably located for use in an emergency.
- (e) For a period of 18 hours the emergency fire pump if dependent upon the emergency generator for its source of power.
- (f) The steering gear for the period of time required by Pt 5, Ch 19.6.
- (g) Where applicable, the services required by 2.3.2.

3.3.6 The emergency source of electrical power may be either a generator or an accumulator battery, which is to comply with the following:

- (a) Where the emergency source of electrical power is a generator it is to be:
  - (i) driven by a suitable prime mover with an independent supply of fuel, having a flashpoint (closed-cup test) of not less than 43°C;
  - (ii) started automatically upon failure of the main source of electrical power supply unless a transitional source of emergency electrical power in accordance with 3.3.7 is provided; where the emergency generator is automatically started, it is to be automatically connected to the emergency switchboard; those services referred to in 3.3.7 are to be connected automatically to the emergency generator; and
  - (iii) provided with a transitional source of emergency electrical power as specified in 3.3.7 unless an emergency generator is provided capable both of supplying the services mentioned in that paragraph and of being automatically started and supplying the required load as quickly as is safe and practicable subject to a maximum of 45 seconds.

- (b) Where the emergency source of electrical power is an accumulator battery it is to be capable of:
- (i) carrying the emergency electrical load without recharging while maintaining the voltage of the battery throughout the discharge period within 12 per cent above or below its nominal voltage;
  - (ii) automatically connecting to the emergency switchboard in the event of failure of the main source of electrical power; and
  - (iii) immediately supplying at least those services specified in 3.3.7.

3.3.7 The transitional source of emergency electrical power where required by 3.3.6 is to consist of an accumulator battery suitably located for use in an emergency which is to operate without recharging while maintaining the voltage of the battery throughout the discharge period within 12 per cent above or below its nominal voltage and be of sufficient capacity and is to be so arranged as to supply automatically in the event of failure of either the main or the emergency source of electrical power for half an hour at least the following services if they depend upon an electrical source for their operation:

- (a) the lighting required by 3.3.5(a), (b) and (c). For this transitional phase, the required emergency electric lighting, in respect of the machinery space and accommodation and service spaces may be provided by permanently fixed, individual, automatically charged, relay operated accumulator lamps; and
- (b) all services required by 3.3.5(d)(i), (iii) and (iv) unless such services have an independent supply for the period specified from an accumulator battery suitably located for use in an emergency.

3.3.8 The emergency switchboard is to be installed as near as is practicable to the emergency source of electrical power.

3.3.9 Where the emergency source of electrical power is a generator, the emergency switchboard is to be located in the same space unless the operation of the emergency switchboard would thereby be impaired.

3.3.10 No accumulator battery fitted in accordance with this Section, unless for engine starting, is to be installed in the same space as the emergency switchboard. An indicator shall be mounted in a suitable place on the main switchboard or in the machinery control room to indicate when the batteries constituting either the emergency source of electrical power or the transitional source of electrical power are being discharged.

3.3.11 The emergency switchboard is to be supplied during normal operation from the main switchboard by an interconnector feeder which is to be adequately protected at the main switchboard against overload and short-circuit and which is to be disconnected automatically at the emergency switchboard upon failure of the main source of electrical power. Where the system is arranged for feedback operation, the interconnector feeder is also to be protected at the emergency switchboard at least against short-circuit.

3.3.12 In order to ensure the ready availability of the emergency source of electrical power to supply emergency circuits, arrangements are to be made, where necessary, to automatically disconnect non-emergency circuits from the emergency switchboard to ensure that electrical power is available to the emergency circuits. The arrangements are to automatically disconnect sufficient non-emergency loads to ensure continued safe operation of the emergency source of electrical power in the event of overloading.

3.3.13 Provision is to be made for the periodic testing of the complete emergency system and is to include the testing of automatic starting arrangements.

## 3.4 Starting arrangements

3.4.1 Where the emergency source of power is a generator, the starting arrangements are to comply with the requirements given in Pt 5, Ch 2,8.5.

## 3.5 Prime mover governor

3.5.1 Where the emergency source of power is a generator, the governor is to comply with 2.4.

## 3.6 Radio installation

3.6.1 Every radio installation as required by SOLAS 1974 as amended, Chapter IV, Part C, is to be provided with reliable, permanently arranged electrical lighting, independent of the main and emergency sources of electrical power, for the adequate illumination of the radio controls for operating the radio installation.

3.6.2 A reserve source or sources of energy is to be provided on every ship, for the purpose of conducting distress and safety radiocommunications, in the event of failure of the ship's main and emergency sources of electrical power. The reserve source or sources of energy is to be capable of simultaneously operating the VHF radio installation and, as appropriate for the sea or sea area for which the ship is equipped, either the MF radio installation, the MF/HF radio installation, or the INMARSAT ship earth station and any of the additional loads mentioned in 3.6.4, 3.6.5 and 3.6.7 for a period of at least one hour. The reserve source or sources of energy need not supply independent HF and MF radio installations at the same time.

3.6.3 The reserve source or sources of energy is to be independent of the propelling power of the ship and the ship's electrical system.

3.6.4 Where, in addition to the VHF radio installation, two or more of the other radio installations, referred to in 3.6.2, can be connected to the reserve source or sources of energy, the reserve source or sources are to be capable of simultaneously supplying, for the period specified by 3.6.2, the VHF radio installation and:

- (a) all other radio installations which can be connected to the reserve source or sources of energy at the same time; or

# Electrical Engineering

# Part 6, Chapter 2

Sections 3, 4 &amp; 5

- (b) whichever of the other radio installations will consume the most power, if only one of the other radio installations can be connected to the reserve source or sources of energy at the same time as the VHF radio installation.

3.6.5 The reserve source or sources of energy may be used to supply the electrical lighting required by 3.6.1.

3.6.6 Where a reserve source of energy consists of a rechargeable accumulator battery or batteries a means of automatically charging the batteries is to be provided which is to be capable of recharging them to minimum capacity requirements within 10 hours.

3.6.7 If an uninterrupted input of information from the ship's navigational or other equipment to a radio installation as referred to in 3.6.1 is needed to ensure its proper performance, means are to be provided to ensure the continuous supply of such information in the event of failure of the ship's main or emergency source of electrical power.

## Section 4 External source of electrical power

### 4.1 Temporary external supply

4.1.1 Where arrangements are made for the supply of electricity from a source on shore or elsewhere, a connection box is to be installed in a position suitable for the convenient reception of flexible cables from the external source and containing a circuit-breaker or isolating switch and fuses and terminals including one earthed, of ample size and suitable shape to facilitate a satisfactory connection of three-phase external supplies with earthed neutrals.

4.1.2 Suitable cables, permanently fixed, are to be provided, connecting the terminals in the connection box to a linked switch and/or a circuit-breaker at the main switchboard. An indicator is to be provided at the main switchboard in order to show when the cables are energized.

4.1.3 Means are to be provided for checking the phase sequence of the incoming supply.

4.1.4 At the connection box a notice is to be provided giving full information on the system of supply, the normal voltage and frequency of the installation's system and the procedure for carrying out the connection.

4.1.5 Alternative arrangements may be submitted for consideration.

### 4.2 Permanent external supply

4.2.1 Details are to be submitted.

## Section 5 Supply and distribution

### 5.1 Systems of supply and distribution

5.1.1 The following systems of generation and distribution are acceptable, other than for tankers intended for the carriage in bulk of oil, liquefied gases and other hazardous liquids having a flash point not exceeding 60°C (closed-cup test):

- (a) d.c., two-wire;
- (b) a.c., single-phase, two-wire;
- (c) a.c., three-phase:
  - (i) three-wire;
  - (ii) four-wire with neutral solidly earthed but without hull return.

5.1.2 For tankers intended for the carriage in bulk of oil, liquefied gases and other hazardous liquids having a flash point not exceeding 60°C (closed-cup test) only the following systems of generation and distribution are acceptable:

- (a) d.c., two-wire, insulated;
- (b) a.c., single-phase, two-wire, insulated;
- (c) a.c., three-phase, three-wire, insulated;
- (d) earthed systems, a.c. or d.c., limited to areas outside any dangerous space or zone, and arranged so that no current arising from an earth-fault in any part of the system could pass through a dangerous space or zone;
- (e) earthed systems, complying with 5.1.1 and 5.5.7, provided the Government of the flag state permits such an arrangement in accordance with the 'Equivalents' provisions of SOLAS Chapter I, Regulation 5, see Ch 1, 1.4 of the *Rules for Ships for Liquid Chemicals* and/or the *Rules for Ships for Liquefied Gases*, as appropriate, see also 13.1.2.

Earthed intrinsically-safe circuits are permitted to pass into and through dangerous spaces and zones.

5.1.3 System voltages for both alternating current and direct current in general are not to exceed:

- 15 000 V for generation and power distribution;
- 500 V for cooking and heating equipment permanently connected to fixed wiring;
- 250 V for lighting, heaters in cabins and public rooms, and other applications not mentioned above.

Voltages above these will be the subject of special consideration.

5.1.4 The arrangement of the main system of supply is to be such that a fire or other casualty in any space containing the main source of electrical power, associated converting equipment, if any, the main switchboard and the main lighting switchboard will not render inoperable any emergency service, other than those located within the space where the fire or casualty has occurred.

5.1.5 The main switchboard is to be so placed relative to the main source of power that, as far as is practicable, the integrity of the main system of supply will be affected only by a fire or other casualty in one space.

# Electrical Engineering

## Part 6, Chapter 2

Section 5

5.1.6 The arrangement of the emergency system of supply is to be such that a fire or other casualty in spaces containing the emergency source of electrical power, associated converting equipment, if any, the emergency switchboard and the emergency lighting switchboard, will not cause loss of services required to maintain the propulsion and safety of the ship.

5.1.7 Distribution systems required in an emergency are to be so arranged that a fire in any one main fire zone, as defined by SOLAS 1974 as amended Reg II-2/A, 3.32, will not interfere with the emergency distribution in any other such zone.

### 5.2 Essential services

5.2.1 Essential services that are required by Part 5 to be duplicated are to be served by individual circuits, separated in their switchboard or section board and throughout their length as widely as is practicable without the use of common feeders, protective devices, control circuits or control gear assemblies, so that any single fault will not cause the loss of both services.

5.2.2 Where 5.2.1 is applicable the main busbars of the switchboard, or section boards, are to be capable of being split, by a multipole linked circuit-breaker, disconnect or switch-disconnector, into at least two independent sections, each supplied by at least one generator, either directly or through a converter. The essential services are to be equally divided, as far as is practicable, between the independent sections.

5.2.3 Where 5.2.2 is applicable provision is to be made to transfer to a temporary circuit those essential services which are not required to be, and have not been, duplicated in the event of loss of their normal section of switchboard or section board.

### 5.3 Isolation and switching

5.3.1 The incoming and outgoing circuits from every switchboard or section board are to be provided with a means of isolation and switching to permit each circuit to be switched off:

- (a) on load;
- (b) for mechanical maintenance;
- (c) in an emergency to prevent or remove danger.

In addition the requirements of 5.3.2 and 5.3.3 are to be complied with.

5.3.2 Isolation and switching is to be by means of a circuit-breaker or switch arranged to open and close simultaneously all insulated poles. Where a switch is used as the means of isolation and switching, it is to be capable of:

- (a) switching off the circuit on load;
- (b) withstanding, without damage, the overcurrents which may arise during overloads and short-circuit.

In addition, these requirements do not preclude the provision of single pole control switches in final sub-circuits, for example light switches. For circuit-breakers, see 6.5.

5.3.3 Provision is to be made, in accordance with one of the following, to prevent any circuit being inadvertently energized:

- (a) the circuit-breaker or switch can be withdrawn, or locked in the open position;
- (b) the operating handle of the circuit-breaker or switch can be removed;
- (c) the circuit fuses, where fitted, can be readily removed and retained by authorized personnel.

5.3.4 Where a section board, distribution board or item of equipment can be supplied by more than one circuit, a switching device is to be provided to permit each incoming circuit to be isolated and the supply transferred to the alternative circuit. In addition, the requirements of 5.3.5 and 5.3.6 are to be complied with.

5.3.5 The switching device required by 5.3.4 is to be situated within or adjacent to the section board, distribution board or item of equipment. Where necessary, interlocking arrangements are to be provided to prevent circuits being inadvertently energized.

5.3.6 A notice is to be fixed to any section board, distribution board or item of equipment to which 5.3.4 applies warning personnel before gaining access to live parts of the need to open the appropriate circuit-breakers or switches, unless an interlocking arrangement is provided so that all circuits concerned are isolated before access is gained.

5.3.7 Tankers designed in accordance with IEC 60092-502: *Electrical Installations in Ships — Tankers — Special Features* (see 13.1.2) are to meet the requirements of 5.3 of that Standard.

5.3.8 Where high voltage equipment is contained in a room or protected area which also forms its enclosure, the access door(s) of the space is to be so interlocked that it cannot be opened until:

- the high voltage supply(ies) to the equipment is switched off;
- the equipment and its cable(s) are earthed down to dissipate stored energy sufficient to ensure personnel safety.

5.3.9 The access to the space(s) described in 5.3.8 are to be suitably marked to indicate the danger of high voltage.

### 5.4 Insulated distribution systems

5.4.1 A device(s) is to be installed for every insulated distribution system, whether primary or secondary, for power, heating and lighting circuits, to continuously monitor the insulation level to earth and to operate an alarm in the event of an abnormally low level of insulation resistance.

5.4.2 Where any insulated lower voltage system is supplied through transformers from a high voltage system, adequate precautions are to be taken to prevent the low voltage system being charged by capacitive leakage from the high voltage system.



# Electrical Engineering

## Part 6, Chapter 2

Section 5

5.4.3 Tankers designed in accordance with IEC 60092-502: *Electrical Installations in Ships — Tankers — Special Features* (see 13.1.2) are to meet the requirements of 5.3 of that Standard.

5.4.4 Where filters are fitted, for example to reduce EMC susceptibility, these are not to cause distribution systems to be unintentionally connected to earth.

### 5.5 Earthed distribution systems

5.5.1 No fuse, non-linked switch or non-linked circuit-breaker is to be inserted in an earthed conductor. Any switch or circuit-breaker fitted is to operate simultaneously in the earthed conductor and the insulated conductors. These requirements do not preclude the provision (for test purposes) of an isolating link to be used only when the other conductors are isolated.

5.5.2 For high voltage systems, where the earthed neutral system of generation and primary distribution is used, earthing is to be through an impedance in order to limit the total earth fault current to a magnitude which does not exceed that of the three phase short-circuit current for which the generators are designed.

5.5.3 Generator neutrals may be connected in common, provided that the third harmonic content of the voltage waveform of each generator does not exceed five per cent.

5.5.4 Where a switchboard is split into sections operated independently or where there are separate switchboards, neutral earthing is to be provided for each section or for each switchboard. Means are to be provided to ensure that the earth connection is not removed when generators are isolated.

5.5.5 A means of isolation is to be fitted in the earthing connection of each generator so that generators can be completely isolated for maintenance.

5.5.6 All earthing impedances are to be connected to the hull. The connections to the hull are to be so arranged that any circulating currents in the earth connections do not interfere with radio, radar, communication and control equipment circuits.

5.5.7 Tankers designed in accordance with IEC 60092-502: *Electrical Installations in Ships — Tankers — Special Features* (see 13.1.2) are to meet the requirements of 5.3 of that Standard.

### 5.6 Diversity factor

5.6.1 Circuits supplying two or more final sub-circuits are to be rated in accordance with the total connected load subject, where justified, to the application of a diversity factor. Where spare ways are provided on a section or distribution board, an allowance for future increase of load is to be added to the total connected load before application of any diversity factor.

5.6.2 A diversity factor may be applied to the calculation for size of cable and rating of switchgear and fusegear, taking into account the duty cycle of the connected loads and the frequency and duration of any motor starting loads.

5.6.3 For winches and crane motors the diversity factor is to be calculated and submitted when required.

### 5.7 Lighting circuits

5.7.1 Lighting circuits are to be supplied by final sub-circuits separate from those for heating and power. This does not preclude the supply from a lighting circuit supplying a single fixed appliance, such as a cabin fan, a dry shaver, a wardrobe or anti-condensation heater, taking a maximum current of 2 A.

5.7.2 Lighting for the following spaces is to be supplied from at least two final sub-circuits in such a way that failure of one of the circuits does not leave the space in darkness. One of these circuits may be an emergency circuit provided it is normally energized.

- Spaces that are required to be lit for the safe working of the ship, such as control stations, normal working spaces, etc.
- Spaces where there may be a hazard due to movement of crew, passengers and/or equipment, such as in corridors, working passage ways, stairways leading to boat decks, public rooms, etc.
- Spaces where there may be a hazard due to moving machinery and hot parts, such as in machinery spaces, workshops, large galleys, laundries, etc.

5.7.3 Lighting for enclosed hazardous spaces is to be supplied from at least two final sub-circuits to permit light from one circuit to be retained while maintenance is carried out on the other. One of these circuits may be an emergency circuit, provided it is normally energised in which case the arrangements are to comply with Section 3.

5.7.4 Emergency lighting is to be fitted in accordance with Section 3, *see also* Section 17.

5.7.5 Lighting of unattended spaces, such as cargo spaces, is to be controlled by multipole linked switches situated outside such spaces. Provision is to be made for the complete isolation of these circuits and locking the means of control in the off position.

5.7.6 Where lighting circuits in the cargo pump rooms of tankers are also used for emergency lighting, and have been interlocked with the ventilation, the interlocking arrangements are:

- not to cause the lighting to go out following a failure of the ventilation system; and
- not to prevent operation of the emergency lighting following the loss of the main source of electrical power.

### 5.8 Motor circuits

5.8.1 A separate final sub-circuit is to be provided for every motor for essential services, *see* 1.5.1.

## 5.9 Motor control

5.9.1 Every electric motor is to be provided with efficient means for starting and stopping so placed as to be easily operated by the person controlling the motor. Every motor above 0,5 kW is to be provided with control apparatus as given in 5.9.2 to 5.9.4.

5.9.2 Means to prevent undesired restarting after a stoppage due to low volts or complete loss of volts are to be provided. This does not apply to motors where a dangerous condition might result from the failure to restart automatically, e.g. steering gear motor.

5.9.3 Means for automatic disconnection of the supply in the event of excess current due to mechanical overloading of the motor are to be provided, *see also* 6.10.

5.9.4 Motor control gear is to be suitable for the starting current and for the full load rated current of the motor.

## Section 6 System design – Protection

### 6.1 General

6.1.1 Installations are to be protected against over-currents including short-circuits, and other electrical faults. The tripping/fault clearance times of the protective devices are to provide complete and co-ordinated protection to ensure:

- (a) availability of essential and emergency services under fault conditions through discriminative action of the protective devices; as far as practicable the arrangements are also to secure the availability of other services;
- (b) elimination of the fault to reduce damage to the system and hazard of fire.

6.1.2 Short-circuit and overload protection are to be provided in each non-earthed line of each system of supply and distribution, unless exempted under the provisions of any paragraph in this Section.

6.1.3 Protection systems are to be developed using a systematic design procedure incorporating verification and validation methods to ensure successful implementation of the requirements above. Details of the procedures used are to be submitted when requested.

6.1.4 Short circuit protection is to be provided for each source of power and at each point at which a distribution circuit branches into two or more subsidiary circuits.

6.1.5 Where protection for generator power circuits is provided at the associated switchboard, the cabling between generator and switchboard is to be of a type, and installed in a manner such as to minimize the risk of short-circuit.

6.1.6 Except where arrangements comply with 11.3.5, protection for battery circuits is to be provided at a position external and adjacent to the battery compartments.

6.1.7 Protection may be omitted from the following:

- (a) Engine starting battery circuits.
- (b) Circuits for which it can be shown that the risk resulting from spurious operation of the protective device may be greater than that resulting from a fault.

6.1.8 Short circuit protection may be omitted from cabling or wiring to items of equipment internally protected against short-circuit or where it can be shown that they are unlikely to fail to a short-circuit condition and where the cabling or wiring is installed in a manner such as to minimize the risk of short-circuit.

6.1.9 Overload protection may be omitted from the following:

- (a) one line of circuits of the insulated type;
- (b) circuits supplying equipment incapable of being overloaded, or overloading the associated supply cable, under normal conditions, and unlikely to fail to an overload condition.

### 6.2 Protection against short-circuit

6.2.1 Protection against short-circuit currents is to be provided by circuit-breakers or fuses.

6.2.2 The rated short-circuit making and breaking capacity of every protective device is to be adequate for the prospective fault level at its point of installation; the requirements for circuit-breakers and fuses are detailed in 6.5 and 6.6 respectively.

6.2.3 The prospective fault current is to be calculated for the following set of conditions:

- (a) all generators, motors and, where applicable, all transformers, connected as far as permitted by any interlocking arrangements;
- (b) a fault of negligible impedance close up to the load side of the protective device.

6.2.4 In the absence of precise data, the prospective fault current may be taken to be:

- (a) for alternating current systems at the main switchboard:  $10 \times \text{f.l.c.}$  (rated full load current) for each generator that may be connected, or, if the subtransient direct axis reactance,  $X''_d$ , of each generator is known,  $\frac{\text{f.l.c.}}{X''_d \text{ (p.u.)}}$  for each generator, and  $3 \times \text{f.l.c.}$  for motors

simultaneously in service.

The value derived from the above is an approximation to the r.m.s. symmetrical fault current; the peak asymmetrical fault current may be estimated to be 2,5 times this figure (corresponding to a fault power factor of approximately 0,1).

- (b) battery-fed direct current systems at the battery terminals:
  - (i) 15 times ampere hour rating of the battery for vented lead-acid cells, or of alkaline type intended for discharge at low rates corresponding to a battery duration exceeding three hours, or

- (ii) 30 times ampere hour rating of the battery for sealed lead-acid cells having a capacity of 100 ampere hours or more, or of alkaline type intended for discharge at high rates corresponding to a battery duration not exceeding three hours and,
- (iii) 6 x f.l.c. for motors simultaneously in service (if applicable).

## 6.3 Protection against overload

6.3.1 The characteristics of protective devices provided for overload protection are to ensure that cabling and electrical machinery is protected against overheating resulting from mechanical or electrical overload.

6.3.2 Fuses of a type intended for short-circuit protection only (e.g. fuse links complying with IEC 60269-1, of type 'a') are not to be used for overload protection.

## 6.4 Protection against earth faults

6.4.1 Every distribution system that has an intentional connection to earth, by way of an impedance, is to be provided with a means to continuously monitor and indicate the current flowing in the earth connection.

6.4.2 If the current in the earth connection exceeds 5 A there is to be an alarm and the fault current is to be automatically interrupted or limited to a safe value.

6.4.3 The rated short-circuit capacity of any device used for interrupting earth fault currents is to be not less than the prospective earth fault current at its point of installation.

6.4.4 Insulated neutral systems with harmonic distortion of the voltage waveform, which may result in earth fault currents exceeding the level given in 6.4.2 because of capacitive effects, are to be provided with arrangements to isolate the faulty circuit(s).

## 6.5 Circuit-breakers

6.5.1 Circuit-breakers for alternating current systems are to satisfy the following conditions:

- (a) the r.m.s. symmetrical breaking current for which the device is rated is to be not less than the r.m.s. value of the a.c. component of the prospective fault current, at the instant of contact separation;
- (b) the peak asymmetrical making current for which the device is rated is not to be less than the peak value of the prospective fault current at the first half cycle, allowing for maximum asymmetry;
- (c) the power factor at which the device short-circuit ratings are assigned is to be no greater than that of the prospective fault current; alternatively for high voltage, the rated percentage d.c. component of the short-circuit breaking current of the device is to be not less than that of the prospective fault current.

6.5.2 Circuit-breakers for d.c. systems are to have a breaking current not less than the initial prospective fault current. The time constant of the fault current is not to be greater than that for which the circuit-breaker was tested.

6.5.3 The fault ratings considered in 6.5.1 and 6.5.2, are to be assigned on the basis that the device is suitable for further use after fault clearance.

## 6.6 Fuses

6.6.1 Fuses for a.c. systems are to have a breaking current rating not less than the initial r.m.s. value of the a.c. component of the prospective fault current.

6.6.2 Fuses for d.c. systems are to have a d.c. breaking current rating not less than the initial value of the prospective fault current.

## 6.7 Circuit-breakers requiring back-up by fuse or other device

6.7.1 The use of a circuit-breaker having a short-circuit current capacity less than the prospective short-circuit current at the point of installation is permitted, provided that it is preceded by a device having at least the necessary short-circuit capacity. The generator circuit-breakers are not to be used for this purpose.

6.7.2 The same device may back-up more than one circuit-breaker provided that no essential or emergency service is supplied from there, or that any such service is duplicated by arrangements unaffected by tripping of the device.

6.7.3 The combination of back-up device and circuit-breaker is to have a short-circuit performance at least equal to that of a single circuit-breaker satisfying the requirements of 6.5.

6.7.4 Evidence of testing of the combination is to be submitted for consideration; alternatively, consideration may be given to arrangements where it can be shown that:

- (a) the takeover current, above which the back-up device would clear a fault, is not greater than the rated short-circuit breaking capacity of the circuit-breaker and;
- (b) the characteristics of the back-up device, and the prospective fault level, are such that the peak fault current rating of the circuit-breaker cannot be exceeded and;
- (c) the Joule integral of the let-through current of the back-up device does not exceed that corresponding to the rated breaking current and opening time of the circuit-breaker.

## 6.8 Protection of generators

6.8.1 The protective gear required by 6.8.2 and 6.8.3 is to be provided as a minimum.

6.8.2 Generators not arranged to run in parallel are to be provided with a circuit-breaker arranged to open simultaneously, in the event of short-circuit, overload or under-voltage, all insulated poles. In the case of generators rated at less than 50 kW, a multipole linked switch with a fuse, complying with 5.3.2, in each insulated pole will be acceptable.

6.8.3 Generators arranged to operate in parallel are to be provided with a circuit-breaker arranged to open simultaneously, in the event of a short-circuit, an overload or an under-voltage, all insulated poles. This circuit-breaker is to be provided with reverse power protection with time delay, selected or set within the limits of 2 per cent to 15 per cent of full load to a value fixed in accordance with the characteristics of the prime mover; a fall of 50 per cent in the applied voltage is not to render the reverse power mechanism inoperative, although it may alter the amount of reverse power required to open the breakers.

6.8.4 The generator circuit-breaker short-circuit and overload tripping arrangements, or fuse characteristics, are to be such that the machine's thermal withstand capability is not exceeded.

6.8.5 Generators having a capacity of 1500 kVA or above are to be equipped with a protective device which, in the event of a short-circuit in the generator or in the cables between the generator and its circuit breaker, will instantaneously open the circuit breaker and de-excite the generator.

6.8.6 The voltage and time delay settings of the under-voltage release mechanism(s) required by 6.8.2 and 6.8.3 are to be chosen to ensure that the discriminative action required by 6.1.1(a) is maintained.

## 6.9 Load management

6.9.1 Arrangements are to be made to disconnect automatically, after an appropriate time delay, circuits of the following categories, when the generator(s) is/are overloaded; sufficient to ensure the connected generating set(s) is/are not overloaded:

- (a) non-essential circuits;
- (b) circuits feeding services for habitability, see 1.5.2;
- (c) in cargo ships, circuits for cargo refrigeration.

NOTE:

For emergency generators see 3.2.12 and 3.3.12 as applicable.

6.9.2 If required, this load switching may be carried out in one or more stages, in which case the non-essential circuits are to be included in the first group to be disconnected.

6.9.3 The load management of power systems supplying electric propulsion motors is to satisfy the requirements of 15.2.

6.9.4 Consideration is to be given to providing means to inhibit automatically the starting of large motors, or the connection of other large loads, until sufficient generating capacity is available to supply them.

## 6.10 Feeder circuits

6.10.1 Isolation and protection of each feeder circuit is to be ensured by a multipole circuit-breaker or linked switch with a fuse in each insulated conductor. Protection is to be in accordance with 6.2 and 6.3. The protective devices are to allow excess current to pass during the normal accelerating period of motors.

## 6.11 Motor circuits

6.11.1 Motors of rating exceeding 0,5 kW and all motors for essential services are to be protected individually against overload and short-circuit. For motors which for essential services are duplicated, the overload protection may be replaced by an overload alarm; arrangements for steering gear motors are to comply with 14.1.

6.11.2 Protection for both the motor and its supply cable may be provided by the same device, provided that due account is taken of any differences between ratings of cable and motor.

6.11.3 Where operation of an item of equipment is dependent upon a number of motors, consideration may be given to the provision of a common means of short-circuit protection.

6.11.4 For motors for intermittent service, the characteristics of the arrangements for overload protection are to be chosen in relation to the load factor(s) of the motor(s).

6.11.5 Where fuses are used to protect polyphase motor circuits, means are to be provided to protect the motor from unacceptable overcurrent in the case of single phasing.

## 6.12 Protection of transformers

6.12.1 Short circuit protection for transformers is to be provided by circuit-breakers or fuses in the primary circuit and in addition, overload protection is to be provided either in the primary or secondary circuit.

6.12.2 Arrangements are to be made to prevent the primary windings of transformers being inadvertently energized from their secondary side when disconnected from their source of supply.

## Section 7 Switchgear and control gear assemblies

### 7.1 General requirements

7.1.1 Switchgear and control gear assemblies and their components are to comply with one of the following standards amended where necessary for ambient temperature and other environmental conditions:

- (a) IEC 60439: *Low voltage switchgear and control gear assemblies*;
- (b) IEC 60298: *AC Metal enclosed switchgear and control gear for rated voltages above 1 kV and up to and including 72.5 kV*;
- (c) IEC 60466: *AC insulated-enclosed switchgear for rated voltages above 1 kV and up to and including 38 kV*;
- (d) IEC 60255: *Electrical relays*;
- (e) acceptable and relevant National Standard.

In addition, the requirements of 7.2 to 7.19 are to be complied with.

## 7.2 Busbars

7.2.1 Busbars and their connections are to be of copper or aluminium, all connections being so made as to inhibit corrosion/oxidization between current-carrying mating faces, which may result in poor electrical contact giving rise to overheating. Busbars and their supports are to be designed to withstand the mechanical stresses which may arise during short-circuits. A test report or calculation to verify the short-circuit withstand strength of the busbar system is to be submitted for consideration when required.

7.2.2 For bare conductors, where no precautions are taken against surface oxidization, the temperature rise limit at rated normal current is not to exceed 45°C. Where suitable precautions are taken against surface oxidization, e.g. by using silver, nickel or tin coated terminations, a temperature rise limit not exceeding 60°C is permitted. Where the busbar temperature rises are above 45°C it is to be ensured that there is no adverse effect on equipment adjacent to and/or connected to the busbars and that the temperature rise limits of any materials in contact with the busbars are not exceeded. A test report or calculation to verify the rated current assigned to the busbar system is to be submitted for consideration when required.

## 7.3 Circuit-breakers

7.3.1 Circuit-breakers are to comply with one of the following standards amended where necessary for ambient temperature:

- (a) IEC 60947-2: *Low voltage switchgear and Control gear Pt 2: Circuit-breakers*;
- (b) IEC 62271-100: *High-voltage switchgear and control gear - Pt 100: High-voltage alternating-current circuit-breakers*;
- (c) acceptable and relevant National Standard.

Type test reports to verify the characteristics of a circuit-breaker are to be submitted for consideration when required.

7.3.2 Circuit-breakers are to be of the trip free type and, where applicable, be fitted with anti-pumping control.

7.3.3 High-voltage circuit-breakers are to be of the withdrawable type or with equivalent means or arrangements permitting safe maintenance whilst the busbars are live.

## 7.4 Contactors

7.4.1 High-voltage contactors are to comply with one of the following standards amended where necessary for ambient temperature.

- (a) IEC 60470: *High-voltage alternating current contactors*.
- (b) acceptable and relevant National Standard.

Type test reports to verify the characteristics of a contactor are to be submitted for consideration when required.

7.4.2 High-voltage contactors are to be of the withdrawable type or with equivalent means or arrangements permitting safe maintenance whilst the busbars are live.

## 7.5 Creepage and clearance distances

7.5.1 The shortest distances between conductive parts and between conductive parts and earth in air or along the surface of an insulating material, are to be suitable for the rated voltage having regard to the nature of the insulating material and the transient over voltages developed by switching and fault conditions. This requirement may be satisfied by subjecting each assembly type to an impulse voltage test in accordance with its constructional Standard or, alternatively, maintaining the minimum distances for bare conductive parts in switchgear and control gear assemblies given in Table 2.7.1.

**Table 2.7.1 Minimum clearance distances**

Rated Voltage V	Minimum clearance (mm) between phases and earth		Minimum clearance (mm) between phases
	Earthed neutral	Insulated neutral	
≤660	16	19	19
1000	25	25	25
3600	55	55	55
7200	70	100	100
12000	85	140	140
15000	100	165	165

7.5.2 Suitable shrouding or barriers are to be provided in way of connections to equipment, where necessary, to maintain the minimum distances in Table 2.7.1.

7.5.3 Creepage distances cannot be accurately specified as they depend upon the insulating material, dust deposits, humidity, etc. They are to be not less than the clearance distances given in Table 2.7.1, or less than 16 mm per 1000 V (rated voltage), whichever is the greater.

## 7.6 Degree of protection

7.6.1 Low voltage assemblies where the rated voltage between conductors or to earth exceeds 55 V a.c. or 250 V d.c. are to be of the deadfront or enclosed type. High-voltage assemblies are to be of the enclosed type.

7.6.2 Where switchboards or section boards are required to comply with 5.2.2, barriers are to be installed to provide protection for the independent sections against contamination due to the products of arcing, which may result in a fault.

## 7.7 Distribution boards

7.7.1 Distribution boards are to be suitably enclosed unless they are installed in a cupboard or compartment to which only authorized persons have access in which case the cupboard may serve as an enclosure, see 7.16.4.

## 7.8 Earthing of high-voltage switchboards

7.8.1 High-voltage switchboards are to be provided with suitable means to earth isolated circuits so that they are discharged and so maintained that they are safe to touch.

## 7.9 Fuses

7.9.1 Fuses are to comply with one of the following Standards amended where necessary for ambient temperature:

- (a) IEC 60269: *Low-voltage fuses*;
- (b) IEC 60282-1: *High voltage fuses Pt 1: Current-limiting fuses*;
- (c) acceptable and relevant National Standard for enclosed current-limiting fuses.

Type test reports to verify the characteristics of a fuse are to be submitted for consideration when required.

## 7.10 Handrails or handles

7.10.1 All main and emergency switchboards are to be provided with an insulated handrail or insulated handles suitably fitted on the front of the switchboard. Where access to the rear is required, a horizontal insulated handrail is to be suitably fitted on the rear of the switchboard.

## 7.11 Instruments for alternating current generators

7.11.1 For alternating current generators not operated in parallel, each generator is to be provided with at least one voltmeter, one frequency meter, and one ammeter with an ammeter switch to enable the current in each phase to be read, or an ammeter in each phase. Generators above 50 kVA are also to be provided with a wattmeter.

7.11.2 For alternating current generators operated in parallel, each generator is to be provided with a wattmeter, and one ammeter with an ammeter switch to enable the current in each phase to be read, or an ammeter in each phase.

7.11.3 For parallelling purposes, two voltmeters, two frequency meters and two synchronising devices, of which one at least is to be a synchroscope or a set of lamps are to be provided. One voltmeter and one frequency meter are to be connected to the busbars, the other voltmeter and frequency meter are to be switched to enable the voltage and frequency of any generator to be measured. Where the electrical power requirement to maintain the ship in a normal operational and habitable condition is usually supplied by two or more generators operating in parallel, the two synchronising devices are to be independent of each other (see also 2.2.1).

7.11.4 Where the indications of voltage, frequency, current and power are displayed digitally, the indications are to be separately displayed.

## 7.12 Instrument scales

7.12.1 The upper limit of the scale of every voltmeter is to be approximately 120 per cent of the nominal voltage of the circuit, and the nominal voltage is to be clearly indicated.

7.12.2 The upper limit of the scale of every ammeter is to be approximately 130 per cent of the normal rating of the circuit in which it is installed. Normal full load is to be clearly indicated.

7.12.3 Kilowatt meters for use with alternating current generators which may be operated in parallel are to be capable of indicating 15 per cent reverse power.

7.12.4 Where the indications provided by the instrumentation required by 7.11 are displayed digitally, nominal voltage, over voltage, over current and reverse power indications are to be indicated by an appropriate means.

## 7.13 Labels

7.13.1 The identification of individual circuits and their devices is to be made on labels of durable material. The ratings of fuses and settings of protective devices are also to be indicated. Section and distribution boards are to be marked with the rated voltage.

## 7.14 Protection

7.14.1 See Section 6.

## 7.15 Wiring

7.15.1 Insulated wiring connecting components are to be stranded, flame retardant and manufactured in accordance with a relevant and acceptable National Standard.

**7.16 Position of switchboards**

7.16.1 An unobstructed space not less than 1 m wide is to be provided in front of switchboards and section boards. When switchboards and section boards contain withdrawable equipment the unobstructed space is to be not less than 0,4 m wide with this equipment in its fully withdrawn position.

7.16.2 Where necessary, the space at the rear of switchboards and section boards is to be ample to permit maintenance and in general not less than 0,6 m except that this may be reduced to 0,5 m in way of stiffeners or frames.

7.16.3 The spaces defined in 7.16.1 and 7.16.2 are to have non-slip surfaces. Where access to live parts within switchboards and section boards is normally possible the surface is, in addition, to be electrically insulated.

7.16.4 So far as is practicable, pipes are not to be installed directly above or in front of or behind switchboards, section boards and distribution boards. If such placing is unavoidable, suitable protection is to be provided in these positions, see Pt 5, Ch 13,2.

7.16.5 For switchgear and control gear assemblies, for rated voltages above 1 kV, arrangements are to be made to protect personnel in the event of gases or vapours escaping under pressure as the result of arcing due to an internal fault.

**7.17 Switchboard auxiliary power supplies**

7.17.1 Where the operation of a protective device relies upon a power supply, an alarm is to be provided to indicate failure of the power supply, unless its failure causes automatic tripping of the protected circuit.

**7.18 Testing**

7.18.1 Tests in accordance with 7.18.2 to 7.18.4 are to be satisfactorily carried out on all assemblies, complete or in sections, at the manufacturer's premises, and a test report issued by the manufacturer, see also 1.3.2.

7.18.2 A high voltage test, see Section 20.

7.18.3 Calibration of protective devices and indicating instruments is to be verified by means of current and/or voltage injection.

7.18.4 Demonstration of the satisfactory operation of protection circuits, control circuits and interlocks by means of simulated functional tests.

7.18.5 For switchgear and control gear assemblies, for rated voltages above 1 kV, type tests are to be carried out, in accordance with an appropriate Standard, to verify that the assembly will withstand the effects of an internal arc occurring within the enclosure at a prospective fault level equal to, or in excess of, that of the installation.

**7.19 Disconnectors and switch-disconnectors**

7.19.1 Disconnectors, switch-disconnectors and their components are to comply with one of the following standards, amended where necessary for ambient temperature and other environmental conditions:

(a) IEC 60947-3: *Low voltage switchgear and control gear Part 3: switches, disconnectors, switch-disconnectors and fuse combination units*;

(b) IEC 62271-102: *High-voltage switchgear and control gear – Pt 102: High-voltage alternating current disconnectors and earthing switches*;

(c) acceptable and relevant National Standard.

Type test reports to verify the characteristics of a disconnector or switch-disconnector are to be submitted for consideration when required.

## ■ Section 8

### Rotating machines

**8.1 General requirements**

8.1.1 Rotating machines are to comply with the relevant part of IEC 60092, or an acceptable and relevant National Standard, and the requirements of this section.

8.1.2 For all the rotating machines a manufacturer's test certificate is to be provided, see also 1.3.2 to 1.3.4.

8.1.3 For rotating machines of 100 kW and over intended for essential services, shaft materials are to comply with LR's *Rules for the Manufacture, Testing and Certification of Materials*.

8.1.4 Where welding is applied to shafts of machines for securing arms or spiders, stress relieving is to be carried out after welding. The finalized assembly is to be visually examined by the Surveyors, crack detection carried out by an appropriate method and the finished welds found sound and free from cracks.

8.1.5 The rotating parts of machines are to be so balanced that when running at any speed in the normal working range the vibration does not exceed the levels of IEC 60034: *Rotating electrical machines Part 14*.

8.1.6 The lubrication arrangement for bearings are to be effective under all operating conditions including the maximum ship inclinations defined by 1.9 and there are to be effective means provided to ensure that lubricant does not reach the machine windings or other conductors and insulators.

8.1.7 Means are to be taken to prevent the ill effects of the flow of currents circulating between the shaft and machine bearings or bearings of connected machinery.

8.1.8 Alternating current machines are to be constructed such that, under any operating conditions, they are capable of withstanding the effects of a sudden short-circuit at their terminals without damage.

8.1.9 AC generators and motors for electrical propulsion systems are to have at least one embedded temperature detector (ETD) in each phase of the machine winding in locations which may be subjected to the highest temperature. Where there are two coil sides per slot the ETD's are to be located between the insulated coil sides in the slot, see 15.1.3.

## 8.2 Rating

8.2.1 Generators, including their excitation systems, and continuously rated motors are to be suitable for continuous duty at their full rated output at maximum cooling air or water temperature for an unlimited period, without the limits of temperature rise in 8.3 being exceeded. Generators are to be capable of an overload power of not less than 10 per cent at their rated power factor for a period of 15 minutes without injurious heating. Other machines are to be rated in accordance with the duty which they have to perform and, when tested under rated load conditions, the temperature rise is not to exceed the values in 8.3.

8.2.2 When a rotating machine is connected to a supply system with harmonic distortion the rating of the machine is to allow for the increased heating effect of the harmonic loading.

8.2.3 The design and construction of smoke extraction fan motors are to be suitable for the ambient temperature and operating time required. Type test reports to verify the performance of the electric motor are to be submitted for consideration.

## 8.3 Temperature rise

8.3.1 The limits of temperature rise specified in Table 2.8.1, are based on the cooling air temperature and cooling water temperature given in 1.8.

8.3.2 If it is known that the temperature of cooling medium exceeds the values given in 1.8 the permissible temperature rise is to be reduced by an amount equal to the excess temperature of the cooling medium.

8.3.3 If it is known that the temperature of cooling medium will be permanently less than the values given in 1.8 the permissible temperature rise may be increased by an amount equal to the difference between the declared temperature and that given in 1.8 up to a maximum of 15°C.

## 8.4 Generator control

8.4.1 Each alternating current generator, unless of the self-regulating type, is to be provided with automatic means of voltage regulation; voltage build-up is not to require an external source of power. Provision is to be made to safeguard the distribution system should there be a failure of the voltage regulating system resulting in a high voltage.

8.4.2 The voltage regulation of any alternating current generator with its regulating equipment is to be such that at all loads, from zero to full load at rated power factor, the rated voltage is maintained within  $\pm 2,5$  per cent under steady conditions. There is to be provision at the voltage regulator to adjust the generator no load voltage.

8.4.3 Generators, and their excitation systems, when operating at rated speed and voltage on no-load are to be capable of absorbing the suddenly switched, balanced, current demand of the largest motor or load at a power factor not greater than 0,4 with a transient voltage dip which does not exceed 15 per cent of rated voltage. The voltage is to recover to rated voltage within a time not exceeding 1,5 seconds.

8.4.4 The transient voltage rise at the terminals of a generator is not to exceed 20 per cent of rated voltage when rated kVA at a power factor not greater than 0,8 is thrown off.

8.4.5 Generators and their voltage regulation systems are to be capable of maintaining, without damage, under steady state short-circuit conditions a current of at least three times the full load rated current for a duration of at least two seconds or where precise data is available for the duration of any longer time delay which may be provided by a tripping device for discrimination purposes.

8.4.6 Generators required to run in parallel are to be stable from no load (kW) up to the total combined full load (kW) of the group, and load sharing is to be such that the load on any generator does not normally differ from its proportionate share of the total load by more than 15 per cent of the rated output (kW) of the largest machine or 25 per cent of the rated output (kW) of the individual machine, whichever is less.

8.4.7 When generators are operated in parallel, the kVA loads of the individual generating sets are not to differ from the proportionate share of the total kVA load by more than five per cent of the rated kVA output of the largest machines.

## 8.5 Overloads

8.5.1 Machines are to withstand on test, without injury, the following momentary overloads:

- (a) **Generators.** An excess current of 50 per cent for 15 seconds after attaining the temperature rise corresponding to rated load, the terminal voltage being maintained as near the rated value as possible. The foregoing does not apply to the overload torque capacity of the prime mover.
- (b) **Motors.** At rated speed or, in the case of a range of speeds, at the highest and lowest speeds, under gradual increase of torque, the appropriate excess torque given below. Synchronous motors and synchronous induction motors are required to withstand the excess torque without falling out of synchronism and without adjustment of the excitation circuit preset at the value corresponding to rated load:



**Table 2.8.1 Limits of temperature rise of machines cooled by air**

Limits of temperature rise of machines cooled by air, °C						
Part of machine	Method of temperature measurement	Insulation class				
		A	E	B	F	H
1. (a) a.c. windings of machines having output of 5000 kVA or more	ETD R	55 50	– –	75 70	95 90	115 110
(b) a.c. windings of machines having output of less than 5000 kVA	ETD R	55 50	– 65	80 70	100 95	115 110
2. Windings of armatures having commutators	R T	50 40	65 55	70 60	95 75	115 95
3. Field windings of a.c. and d.c. machines having d.c. excitation other than those in item 4	R T	50 40	65 55	70 60	95 75	115 95
4. (a) Field windings of synchronous machines with cylindrical rotors having d.c. excitation	R	–	–	80	100	125
(b) Stationary field windings of d.c. machines having more than one layer	R T	50 40	65 55	70 60	95 75	115 95
(c) Low resistance field windings of a.c. and d.c. machine and compensating windings of d.c. machines having more than one layer	R, T	50	65	70	90	115
(d) Single-layer windings of a.c. and d.c. machines with exposed bare or varnished metal surfaces and single-layer compensating windings of d.c. machines	R, T	55	70	80	100	125
5. Permanently short-circuited insulated windings	T	50	65	70	90	115
6. Permanently short-circuited uninsulated windings	T	The temperature rise of these parts shall in no case reach such a value that there is a risk to any insulation or other materials on adjacent parts or to the item itself				
7. Magnetic cores and other parts not in contact with windings	T					
8. Magnetic cores and other parts in contact with windings	T	50	65	70	90	110
9. Commutators and slip-rings open and enclosed	T	50	60	70	80	90
<b>NOTES</b> 1. Where water cooled heat exchangers are used in the machine cooling circuit the temperature rises are to be measured with respect to the temperature of the cooling water at the inlet to the heat exchanger and the temperature rises given in Table 2.8.1 shall be increased by 10°C provided the inlet water temperature does not exceed the values given in 1.8. 2. T = thermometer method R = resistance method ETD = embedded temperature detector 3. Temperature rise measurements are to use the resistance method whenever practicable. 4. The ETD method may only be used when the ETD's are located between coil sides in the slot.						

- d.c. motors 50 per cent for 15 seconds;  
 polyphase a.c. synchronous motors 50 per cent for 15 seconds;  
 polyphase a.c. synchronous induction motors 35 per cent for 15 seconds;  
 polyphase a.c. induction motors 60 per cent for 15 seconds.
- c) **Propulsion machines.** The overload tests for propulsion machines will be specially considered for each installation.
- (d) **Windlasses.** For the design and testing of windlass electric motors, see Pt 3, Ch 13,7.6.

**8.6 Machine enclosure**

8.6.1 Where water cooled heat exchangers are used in the machine cooling circuit there is to be provision for the detection of water leakage and the system is to be arranged so as to prevent the entry of water into the machine.

**8.7 Direct current machines**

8.7.1 The final running position of brushgear is to be clearly and permanently marked.

8.7.2 Direct current machines are to work with fixed brush setting from no load to the momentary overload specified without injurious sparking.

## 8.8 Survey and testing

8.8.1 On machines for essential services tests are to be carried out and a certificate furnished by the manufacturer. The tests are to include temperature rise, momentary overload, high voltage, and commutation. The insulation resistance and the temperature at which it was measured are to be recorded, see also 1.3.2 to 1.3.4.

8.8.2 In the case of duplicate machines, type tests of temperature rise, excess current and torque and commutation taken on a machine identical in rating and in all other essential details may be accepted in conjunction with abbreviated tests on each machine. Type tests for propulsion machines will be specially considered. For the abbreviated tests, each machine is to be run and is to be found electrically and mechanically sound and is to have a high voltage test and insulation resistance recorded.

8.8.3 A high voltage test, in accordance with Section 20, is to be applied to new machines, preferably at the conclusion of the temperature rise test. Where both ends of each phase are brought out to accessible separate terminals each phase is to be tested separately.

8.8.4 An impulse test is to be carried out on the coils of high voltage machines in order to demonstrate a satisfactory withstand level of the inter-turn insulation to voltage surges.

The test is to be carried out on all coils after they have been inserted in the slots and after wedging and bracing. Each coil shall be subjected to at least five impulses of injected voltage, the peak value of the injected voltage being given by the formula:

$$V_{\text{peak}} = 2,45V$$

where

$$V = \text{rated line voltage r.m.s.}$$

Alternative proposals to demonstrate the withstand level of inter-turn insulation will be considered.

## Section 9 Converter equipment

### 9.1 Transformers

9.1.1 Paragraphs 9.1.2 to 9.1.12 apply to transformers rated for 5 kVA upwards.

9.1.2 Transformers are to comply with the requirements of IEC 60076: *Power transformers*, or an acceptable and relevant National Standard amended where necessary for ambient temperature, see 1.8.

9.1.3 Transformers may be of the dry type, encapsulated or liquid-filled type.

9.1.4 The temperature rise of the winding of transformers above the ambient temperatures given in 1.8, when measured by resistance during continuous operation at the maximum rating, is not to exceed:

- (a) For dry type transformers, air cooled:
  - insulation of Class A – 50°C
  - insulation of Class E – 60°C
  - insulation of Class B – 70°C
  - insulation of Class F – 90°C
  - insulation of Class H – 110°C
- (b) For liquid filled transformers:
  - 50°C – where air provides cooling of the fluid
  - 65°C – where water provides cooling of the fluid.

9.1.5 When a transformer is connected to a supply system with harmonic distortion, the rating of the transformer is to allow for the increased heating effect of the harmonic loading. Special attention is to be given to transformers connected for the purpose of reducing harmonic distortion.

9.1.6 The inherent regulation of transformers at their rated output is to be such that the total voltage drop to any point in the installation does not exceed that allowed by 1.7.

9.1.7 Transformers, except those for motor starting, are to be double wound.

9.1.8 Liquid fillings for transformers are to be non-toxic and of a type which does not readily support combustion. Liquid filled transformers are to have a pressure relief-device with an alarm and there is to be a suitable means provided to contain any liquid which may escape from the transformer due to the operation of the relief device or damage to the tank.

9.1.9 All transformers are to be capable of withstanding for two seconds, without damage, the thermal and mechanical effects of a short-circuit at the terminals of any winding.

9.1.10 When forced cooling is used, whether air or liquid, there is to be monitoring of the cooling medium and transformer winding temperatures with an alarm should these exceed preset limits. There are to be arrangements so that the load may be reduced to a level commensurate with the cooling available.

9.1.11 Where water cooled heat exchangers are used in transformer cooling circuits, there is to be provision for the detection of water leakage and the system is to be arranged so as to prevent the entry of water into the transformer.

9.1.12 The following tests are to be carried out on all transformers at the manufacturer's works, and a certificate of tests issued by the manufacturer, see also 1.3.2:

- (a) measurement of winding resistances, voltage ratio, impedance voltage, short-circuit impedance, insulation resistance, load loss, no load loss and current;
- (b) dielectric tests;
- (c) temperature rise test on one transformer of each size and type.

### 9.2 Semiconductor equipment

9.2.1 The requirements of 9.2.2 to 9.2.18 apply to semiconductor equipment rated for 5 kW upwards.

9.2.2 Semiconductor equipment is to comply with the requirements of IEC 60146: *Semiconductor converters*, or an acceptable and relevant National Standard amended where necessary for ambient temperature, see 1.8.

9.2.3 Semiconductor static power converter equipment is to be rated for the required duty having regard to peak loads, system transients and overvoltage.

9.2.4 Converter equipment may be air or liquid cooled and is to be so arranged that it cannot remain loaded unless effective cooling is maintained. Alternatively the load may be automatically reduced to a level commensurate with the cooling available.

9.2.5 Liquid cooled converter equipment is to be provided with leakage alarms and there is to be a suitable means provided to contain any liquid which may leak from the system in order to ensure that it does not cause an electrical failure of the equipment. Where the semiconductors and other current carrying parts are in direct contact with the cooling liquid, the liquid is to be monitored for satisfactory resistivity and an alarm initiated at the relevant control station should the resistivity be outside the agreed limits.

9.2.6 Where forced cooling is used there is to be temperature monitoring of the heated cooling medium with an alarm and shutdown when the temperature exceeds a preset value.

9.2.7 Cooling fluids are to be non-toxic and of low flammability.

9.2.8 Converter equipment is to be so arranged that the semiconductor devices, fuses, control and firing circuit boards may be readily removed from the equipment for repair or replacement.

9.2.9 Test and monitoring facilities are to be provided to permit identification of control circuit faults and faulty components.

9.2.10 Protection devices fitted for converter equipment protection are to ensure that, under fault conditions, the protective action of circuit-breakers, fuses or control systems is such that there is no further damage to the converter or the installation.

9.2.11 Converter equipment, including any associated transformers, reactors, capacitors and filters, if provided, is to be so arranged that the harmonic distortion, and voltage spikes, introduced in to the ship's electrical system are within the limits of 1.7.3 or restricted to a lower level necessary to ensure that it causes no malfunction of equipment connected to the electrical installation.

9.2.12 Overvoltage spikes or oscillations caused by commutation or other phenomena, are not to result in the supply voltage waveform deviating from a superimposed equivalent sine wave by more than 10 per cent of the maximum value of the equivalent sine wave.

9.2.13 When converter equipment is operated in parallel, load sharing is to be such that under normal operating conditions overloading of any unit does not occur and the combination of paralleled equipment is stable throughout the operating range.

9.2.14 When converter equipment has parallel circuits there is to be provision to ensure that the load is distributed uniformly between the parallel paths.

9.2.15 Transformers, reactors, capacitors and other circuit devices associated with converter equipment, or associated filters, are to be suitable for the distorted voltage and current waveforms to which they may be subjected and filter circuits are to be provided with facilities to ensure that their capacitors are discharged before the circuits are energized.

9.2.16 Any regenerated power developed during the operation of converter equipment is not to result in disturbances to the supply system voltage and frequency which exceeds the limits of 1.7.

9.2.17 Where control systems form an integral part of semiconductor equipment, they are to be designed and manufactured with regard to the environmental conditions to which they will be exposed in service and their performance is to be demonstrated during the test and trials programme.

9.2.18 Tests at the manufacturer's works of converter equipment and any associated reactors or filters are to include the high voltage test of 20.1, a temperature rise test on one of each size and type of converter equipment, and such other tests as may be necessary to demonstrate the suitability of the equipment for its intended duty. Details of tests are to be submitted for consideration when required, see also 1.3.2.

## 9.3 Uninterruptible power systems

9.3.1 Where uninterruptible power systems (UPS) are required to maintain essential services or provide emergency services, the requirements of this sub-Section apply. This sub-Section is in addition to the requirements of 9.1 to 9.2 and Section 11, as applicable.

9.3.2 UPS units are to be constructed in accordance with IEC 62040: *Uninterruptible power systems (UPS)*, or an acceptable and relevant National or International Standard.

9.3.3 The operation of a UPS is not to depend upon external services.

9.3.4 The type of UPS unit employed, whether off-line, line-interactive or on-line, is to be appropriate to the power supply requirements of the connected load equipment.

9.3.5 An external bypass, that is hardwired and manually operated, is to be provided for UPS to allow isolation of UPS for safety during maintenance and maintain continuity of load power.

9.3.6 UPS units are to be monitored and an audible and visual alarm is to be initiated in the navigating bridge or the engine control room, or an equivalent attended location for:

- power supply failure (voltage and frequency) to the connected load;
- earth fault;
- operation of battery protective device;
- battery discharge; and
- bypass in operation for on-line UPS units.

9.3.7 UPS units required to provide emergency services are to be suitably located for use in an emergency.

9.3.8 UPS units utilising valve-regulated sealed batteries may be located in compartments with standard marine or industrial electrical equipment provided that the arrangements comply with 11.3.5. Ventilation arrangements in accordance with IEC 62040: Uninterruptible power systems (UPS), or an acceptable and relevant National or International Standard, may be considered to satisfy the requirements of 11.5.10.

9.3.9 Output power is to be maintained for the duration required for the connected equipment.

9.3.10 The UPS battery capacity is, at all times, to be capable of supplying the designated loads for the time specified. Where it is proposed that additional circuits are connected to the UPS unit, details verifying that the UPS unit has adequate capacity are to be submitted for consideration, see 1.4.

9.3.11 On restoration of the input power, the rating of the charge unit is to be sufficient to recharge the batteries while maintaining the output supply to the load equipment.

9.3.12 Tests at the manufacturer's works are to include such tests necessary to demonstrate the suitability of a UPS unit for its intended duty and location. This is expected to include as a minimum the following tests:

- a temperature rise test and battery capacity test on one of each size and type of UPS;
- the high voltage test of 20.1;
- a ventilation rate test; and
- functional testing, including operation of alarms.

Details of tests are to be submitted for consideration when required, see also 1.3.2.

9.3.13 Where the supply is to be maintained without a break following a power input failure, this is to be verified after installation by practical testing.

10.1.2 Electric cables for fixed wiring are to be designed, manufactured and tested in accordance with the relevant IEC Standard stated in Table 2.10.1 or an acceptable and relevant National Standard.

Table 2.10.1 Electric cables

Application	IEC Standard	Title
General constructional and testing requirements	60092-350	Low-voltage shipboard power cables. General construction and test requirements
Fixed power and control circuits	60092-353	Single and multicore non-radial field power cables with extruded solid insulation for rated voltages 1 kV and 3 kV
Fixed power circuits	60092-354	Single and three-core power cables with extruded solid insulation for rated voltages 6 kV, 10 kV and 15 kV
Instrumentation, control and communication circuits up to 60 V	60092-375	Shipboard telecommunication cables and radio frequency cables – General instrumentation, control and communication cables
Control circuits up to 250 V	60092-376	Shipboard multicore cables for control circuits
Mineral insulated	60702	Mineral insulated cables with a rated voltage not exceeding 750 V

10.1.3 Provided that adequate flexibility of the finished cable is assured, conductors of nominal cross-section area 2,5 mm<sup>2</sup> and less need not be stranded.

10.1.4 Electric cables for non-fixed wiring applications are to comply with an acceptable and relevant Standard.

10.1.5 For the purpose of this Section, pipes, conduits, trunking or any other system for the additional mechanical protection of cables are hereafter referred to under the generic name 'protective casings'.

10.2 Testing

10.2.1 Routine tests, consisting of at least:

- (a) measurement of electrical resistance of conductors;
- (b) high voltage test, see also Section 20;
- (c) insulation resistance measurement;
- (d) for high voltage cables, partial discharge tests are to be made in accordance with the requirements of the relevant publication or National Standard referred to in 10.1.2 at the manufacturer's works prior to despatch.

Evidence of successful completion of routine tests is to be provided by the manufacturer, see also 1.3.3.

Section 10  
Electric cables and busbar  
trunking systems (busways)

10.1 General

10.1.1 The requirements of 10.1 to 10.15 apply to all electric cables for fixed wiring unless otherwise exempted. The requirements of 10.16 apply to busbar trunking systems (busways) where they are used in place of electric cables.

10.2.2 Particular, special and type tests are to be made, when required, in accordance with the requirements of the relevant publication or National Standard referred to in 10.1.2 and a test report issued by the manufacturer.

### 10.3 Voltage rating

10.3.1 The rated voltage of any electric cable is to be not lower than the nominal voltage of the circuit for which it is used. The maximum sustained voltage of the circuit is not to exceed the maximum voltage for which the cable has been designed.

10.3.2 Electric cables used in unearthed systems are to be suitably rated to withstand the additional stresses imposed on the insulation due to an earth fault.

### 10.4 Operating temperature

10.4.1 The maximum rated conductor temperature of the insulating material for normal operation is to be at least 10°C higher than the maximum ambient temperature liable to be produced in the space where the cable is installed.

10.4.2 The maximum rated conductor temperatures for normal and short-circuit operation, for the insulating materials included within the standards referred to in 10.1.2 is not to exceed the values stated in Table 2.10.2.

**Table 2.10.2 Maximum rated conductor temperature**

Type of insulating compound	Maximum rated conductor temperature, °C	
	Normal operation	Short-circuit
Thermoplastics:		
–Based upon polyvinyl chloride or co-polymer of vinyl chloride and vinyl acetate	60	150
–Based upon polyethylene	60	130
Elastomeric or thermosettings:		
–Based upon ethylene propylene rubber or similar (EPM or EPDM)	85	250
–Based upon chemically crosslinked polyethylene	85	250
–Based upon silicon rubber	95	To be submitted
Mineral:	95	To be submitted

10.4.3 Electric cables constructed of an insulating material not included in Table 2.10.2 are to be rated in accordance with the National Standard chosen in compliance with 10.1.2.

### 10.5 Construction

10.5.1 Electric cables are to be at least of a flame-retardant type. IEC 60332-1-2: *Tests on electric and optical fibre cables under fire conditions – Part 1-2: Test for vertical flame propagation for a single insulated wire or cable – Procedure for 1 kW pre-mixed flame*, will be acceptable.

10.5.2 Exemption from the requirements of 10.5.1 for applications such as radio frequency or digital communication systems, which require the use of particular types of cable, will be subject to special consideration.

10.5.3 Where electric cables are required to be of a 'fire resistant type', they are in addition to be easily distinguishable and comply with the performance requirements of the appropriate part of IEC 60331: *Tests for electric cables under fire conditions – Circuit integrity, when tested with a minimum flame application time of 90 minutes*, as follows:

- IEC 60331-21: *Procedures and requirements – Cables of rated voltage up to and including 0.6/1.0 kV*;
- IEC 60331-23: *Procedures and requirements – Electric data cables*;
- IEC 60331-25: *Procedures and requirements – Optical fibre cables*; or
- IEC 60331-31: *Procedures and requirements – Cables of rated voltage up to and including 0.6/1.0 kV*, where the overall diameter of the cable exceeds 20 mm.

10.5.4 Where electric cables are installed in locations exposed to the weather, in damp and in wet situations, in machinery compartments, refrigerated spaces or exposed to harmful vapours including oil vapour they are to have the conductor insulating materials enclosed in an impervious sheath of material appropriate to the expected ambient conditions.

10.5.5 Electric cables where it is required that their construction includes metallic sheaths, armouring or braids are to be provided with an overall impervious sheath or other means to protect the metallic elements against corrosion.

10.5.6 Where single core electric cables are used in circuits rated in excess of 20 Amps and are armoured the armour is to be of a non-magnetic material.

10.5.7 Electric cables are to be constructed such that they are capable of withstanding the mechanical and thermal effects of the maximum short-circuit current which can flow in any part of the circuit in which they are installed, taking into consideration not only the time/current characteristics of the circuit protective device but also the peak value of the prospective short-circuit current. Where electric cables are to be used in circuits with a maximum short-circuit current in excess of 70 kA, evidence is to be submitted for consideration when required demonstrating that the cable construction can withstand the effects of the short-circuit current.

10.5.8 All high voltage electric cables are to be readily identified by suitable marking.

# Electrical Engineering

## Part 6, Chapter 2

Section 10

### 10.6 Conductor size

10.6.1 The maximum continuous load carried by a cable is not to exceed its continuous current rating. It is to be chosen such that the maximum rated conductor temperature for normal operation for the insulation is not exceeded. In assessing the current rating the correction factors in 10.7 may be applied as required.

10.6.2 The cross-sectional area of the conductors is to be sufficient to ensure that, under short-circuit conditions, the maximum rated conductor temperature for short-circuit operation is not exceeded, taking into consideration the time current characteristics of the circuit protective device and the peak value of the prospective short-circuit current.

10.6.3 The cable current ratings given in Tables 2.10.3 and 2.10.4 are based on the maximum rated conductor temperatures given in Table 2.10.2. When cable sizes are selected on the basis of precise evaluation of current rating based upon experimental and calculated data, details are to be submitted for consideration. Alternative short-circuit temperature limits, other than those given in Table 2.10.4, may be calculated using the method in IEC 60724: *Guide to the short-circuit temperature limits of electric cables* or an acceptable and relevant National Standard.

10.6.4 The cross-sectional area of the conductors is to be sufficient to ensure that at no point in the installation will the voltage variations stated in 1.7 be exceeded when the conductors are carrying the maximum current under their normal conditions of service.

10.6.5 The size of earth conductors is to comply with 1.11.7.

10.6.6 The cross-sectional area of conductors used in circuits supplying cyclic or non-continuous loads is to be sufficient to ensure that the cables maximum rated conductor temperature for normal operation is not exceeded when the conductors are operating under their normal conditions of service, see 10.7.4.

### 10.7 Correction factors for cable current rating

10.7.1 The correction factors of 10.7.2 to 10.7.5 provide a guide for general applications in assessing a current rating. A more precise evaluation based upon experimental and calculated data may be submitted for consideration.

**Table 2.10.3 Electric cable current ratings, normal operation, based on ambient 45°C**

Nominal cross section	Continuous r.m.s current rating, in amperes								
	Thermoplastic, PVC, PE			EP rubber and crosslinked PE			Silicon rubber or mineral		
	Single Core	2-core	3- or 4-core	Single Core	2-core	3- or 4-core	Single Core	2-core	3- or 4-core
0,75	6	5	4	13	11	9	17	14	12
1	8	7	6	16	14	11	20	17	14
1,25	10	8	7	18	15	13	23	19	16
1,5	12	10	8	20	17	14	24	20	17
2	13	11	9	25	21	17	31	26	21
2,5	17	14	12	28	24	20	32	27	22
3,5	21	18	14	35	30	24	39	33	27
4	22	19	15	38	32	27	42	36	29
5,5	27	23	19	46	39	32	52	44	36
6	29	26	20	48	41	34	55	47	39
8	35	30	24	59	50	41	66	56	46
10	40	34	28	67	57	47	75	64	53
14	49	42	34	83	71	58	94	80	66
16	54	46	38	90	77	63	100	85	70
22	66	56	46	110	93	77	124	105	87
25	71	60	50	120	102	84	135	115	95
30	80	68	56	135	115	94	151	128	106
35	87	74	61	145	123	102	165	140	116
38	92	78	64	155	132	108	175	149	122
50	105	89	74	185	153	126	200	175	140
60	123	104	86	205	174	143	233	198	163
70	135	115	95	225	191	158	255	217	179
80	147	125	103	245	208	171	278	236	195
95	165	140	116	275	234	193	310	264	217
100	169	144	118	285	242	199	320	272	224
120	190	162	133	320	272	224	360	306	252
125	194	165	134	325	280	230	368	313	258
150	220	187	154	365	310	256	410	349	287
185	250	213	175	415	353	291	470	400	329
200	260	221	182	440	375	305	494	420	346
240	290	247	203	490	417	343	570	485	400
300	335	285	235	560	476	392	660	560	460

**Table 2.10.4 Electric cable current ratings, r.m.s. short-circuit current**

Nominal cross section	Fault current at 250°C duration			Fault current at 150°C duration			Fault current at 130°C duration		
	1,0 sec. kA	0,5 sec. kA	0,1 sec. kA	1,0 sec. kA	0,5 sec. kA	0,1 sec. kA	1,0 sec. kA	0,5 sec. kA	0,1 sec. kA
1	0,1	0,2	0,5	0,1	0,2	0,4	0,1	0,2	0,3
1,5	0,2	0,3	0,7	0,2	0,3	0,5	0,2	0,3	0,5
2,5	0,4	0,5	1,1	0,3	0,4	0,9	0,3	0,4	0,8
4	0,6	0,8	1,8	0,5	0,7	1,5	0,4	0,6	1,3
6	0,9	1,2	2,8	0,7	1,0	2,2	0,6	0,9	2,0
10	1,5	2,1	4,6	1,2	1,6	3,7	1,0	1,5	3,3
16	2,3	3,3	7,4	1,9	2,6	5,9	1,7	2,4	5,3
25	3,6	5,2	12	2,9	4,1	9,2	2,6	3,7	8,2
35	5,1	7,2	16	4,1	5,8	13	3,6	5,2	12
50	7,3	10	23	5,8	8,2	18	5,2	7,4	16
70	10	14	32	8,2	12	26	7,3	10	23
95	14	20	44	11	16	35	9,9	14	31
120	17	25	55	14	20	44	13	18	40
150	22	31	69	17	25	55	16	22	49
185	27	38	85	22	31	68	19	27	61
240	35	49	110	28	40	89	25	35	79
300	44	62	140	35	50	110	31	44	100

**Table 2.10.5 Correction factors**

Insulation material	Correction factor for ambient air temperature of °C										
	35	40	45	50	55	60	65	70	75	80	85
PVC, Polyethylene	1,29	1,15	1,00	0,82	–	–	–	–	–	–	–
EPR, XLPE	1,12	1,06	1,00	0,94	0,87	0,79	0,71	0,61	0,50	–	–
Mineral, Silicon rubber	1,10	1,05	1,00	0,95	0,89	0,84	0,77	0,71	0,63	0,55	0,45

**10.7.2 Bunching of cables.** Where more than six electric cables, which may be expected to operate simultaneously at their full rated capacity, are laid close together in a cable bunch in such a way that there is an absence of free air circulation around them, a correction factor of 0,85 is to be applied. Signal cables may be exempted from this requirement.

**10.7.3 Ambient temperature.** The current ratings of Table 2.10.3 are based on an ambient temperature of 45°C. For other values of ambient temperature the correction factors shown in Table 2.10.5 are to be applied.

**10.7.4 Short time duty.** When the load is not continuous i.e. operates for periods of half an hour or one hour and the periods of no load are longer than three times the cable's time constant,  $T$  in minutes, the cable's continuous rating may be increased by a duty factor, calculated in accordance with:

$$\text{Duty factor} = \sqrt{\frac{1,12}{1 - e^{-\frac{t_s}{T}}}}$$

When the load is not continuous, is repetitive and has periods of no-load less than three times the cable's time constant, so that the cable has insufficient time to cool down between the applications of load, the cable's continuous rating may be increased by an intermittent factor, calculated in accordance with:

$$\text{Intermittent factor} = \sqrt{\frac{1 - e^{-\frac{t_p}{T}}}{1 - e^{-\frac{t_s}{T}}}}$$

where

$t_p$  = the intermittent period, in minutes, i.e. the total period of load and no-load before the cycle is repeated

$T$  =  $0,245d^{1,35}$  where  $d$  is the overall diameter of the cable, in mm

$t_s$  = the service time of the load current in minutes

**10.7.5 Diversity.** Where cables are used to supply two or more final sub-circuits account may be taken of any diversity factors which may apply, see 5.6.

10.8 Installation of electric cables

10.8.1 Electric cable runs are to be as far as practicable fixed in straight lines and in accessible positions.

10.8.2 The minimum internal radius of bend for the installation of fixed electric cables is to be chosen according to the construction and size of the cable and is not to be less than the values given in Table 2.10.6.

10.8.3 The installation of electric cables across expansion joints in any structure is to be avoided. Where this is not practicable, a loop of electric cable of length sufficient to accommodate the expansion of the joint is to be provided. The internal radius of the loop is to be at least 12 times the external diameter of the cable.

10.8.4 Electric cables for essential and emergency services are to be arranged, so far as is practicable, to avoid galleys, machinery spaces and other enclosed spaces and areas of high fire risk except as is necessary for the service being supplied. Such cables are also, so far as reasonably practicable, to be routed clear of bulkheads to preclude their being rendered unserviceable by heating of the bulkheads that may be caused by a fire in an adjacent space.

10.8.5 Electric cables having insulating materials with different maximum rated conductor temperatures are to be so installed that the maximum rated conductor temperature for normal operation of each cable is not exceeded.

10.8.6 Electric cables having a protective covering which may damage the covering of other cables are not to be bunched with those other cables.

10.8.7 Electric cables are to be as far as practicable installed remote from sources of heat. Where installation of cables near sources of heat cannot be avoided and where there is consequently a risk of damage to the cables by heat, suitable shields, insulation or other precautions are to be installed between the cables and the heat source. The free air circulation around the cables is not to be impaired.

10.8.8 Where electric cables are installed in bunches, provision is to be made to limit the propagation of fire. This requirement is considered satisfied when cables of the bunch have been tested in accordance with the requirements of IEC 60332: *Tests on electric cables under fire conditions, Part 3-22, Test for vertical flame spread of vertically-mounted bunched wires or cables – Category A*, and are installed in the same configuration(s) as are used for the test(s). If the cables are not so installed, information is to be submitted to satisfactorily demonstrate that suitable measures have been taken to ensure that an equivalent limit of fire propagation will be achieved for the configurations to be used. Particular attention is to be given to cables in:

- atria or equivalent spaces; and
  - vertical runs in trunks and other restricted spaces.
- In addition, cables that comply with the requirements of IEC 60332-3-23 are also required to meet the requirements of IEC 60332-1-2.

10.8.9 Electric cables are not to be coated or painted with materials which may adversely affect their sheath or their fire performance.

10.8.10 Where electric cables are installed in refrigerated spaces they are not to be covered with thermal insulation but may be placed directly on the face of the refrigeration chamber, provided that precautions are taken to prevent the electric cables being used as casual means of suspension.

10.8.11 All metal coverings of electric cables are to be earthed in accordance with 1.11.

- 10.8.12 High voltage cables may be installed as follows:
- in the open, (e.g. on carrier plating), when they are to be provided with a continuous metallic sheath or armour which is effectively bonded to earth to reduce danger to personnel. The metallic sheath or armour may be omitted provided that the cable sheathing material has a longitudinal electric resistance high enough to prevent sheath currents which may be hazardous to personnel;
  - contained in earthed metallic protective casings when the cables may be as in (a) or the armour or metal sheath may be omitted. In the latter case care is to be taken to ensure that protective casings are electrically continuous and that short lengths of cable are not left unprotected.

Table 2.10.6 Minimum internal radii of bends in cables for fixed wiring

Cable construction		Overall diameter of cable	Minimum internal radius of bend (times overall diameter of cable)
Insulation	Outer covering		
Thermoplastic and elastomeric 600/1000 V and below	Metal sheathed Armoured and braided	Any	6D
	Other finishes	≤ 25 mm > 25 mm	4D 6D
Mineral	Hard metal sheathed	Any	6D
Thermoplastic and elastomeric above 600/1000 V – single core – multicore	Any	Any	20D
	Any	Any	15D



# Electrical Engineering

## Part 6, Chapter 2

Section 10

10.8.13 High voltage electric cables are not to be run in the open through accommodation spaces.

10.8.14 High voltage electric cables are to be segregated as far as is practicable from electric cables operating at lower voltages.

10.8.15 Electric cables are to be, so far as reasonably practicable, installed remote from sources of mechanical damage. Where necessary the cables are to be protected in accordance with the requirements of 10.9.

10.8.16 Electric cables with the exception of those for portable appliances and those installed in protective casings are to be fixed securely in accordance with the requirements of 10.10.

10.8.17 Where electric cables penetrate bulkheads and decks the requirements of 10.11 are to be complied with.

10.8.18 Where electric cables are installed in protective casings the requirements of 10.12 are to be complied with.

10.8.19 a.c. wiring is to be carried out using multicore cables wherever reasonably practicable. Where it is necessary to install single core electric cables for alternating current circuits in excess of 20 Amps the requirements of 10.13 are to be complied with, see *also* 10.5.6.

### 10.9 Mechanical protection of cables

10.9.1 Electric cables exposed to risk of mechanical damage are to be protected by suitable protective casings unless the protective covering (e.g. armour or sheath) is sufficient to withstand the possible cause of damage.

10.9.2 Electric cables installed in spaces where there is exceptional risk of mechanical damage such as holds, storage spaces, cargo spaces, etc., are to be suitably protected by metallic protective casings, even when armoured, unless the ship's structure affords adequate protection.

10.9.3 Non-metallic protective casings and fixings are to be flame retardant in accordance with the requirements of IEC 60092-101.

10.9.4 Metal protective casings are to be efficiently protected against corrosion, and effectively earthed in accordance with 1.11.

### 10.10 Cable support systems

10.10.1 Electric cables are to be effectively supported and secured, without being damaged, to the ship's structure, either indirectly by a cable support system, or directly by means of clips, saddles or straps to bulkheads etc., see 10.8.4.

10.10.2 Cable support systems, which may be in the form of trays or plates, separate support brackets, hangers or ladder racks, together with their fixings and accessories, are to be robust and are to be of corrosion-resistant material or suitably corrosion inhibited before erection. Where cable support systems are manufactured of plastics materials, evidence of satisfactory type testing in accordance with an acceptable test procedure is to be submitted for consideration. The cable support system is to be effectively secured to the ship's structure, the spacing of the fixings taking account of the probability of vibration and any heavy external forces, e.g. where located in areas subject to impact by sea-water.

10.10.3 The distances between the points at which the cable is supported (e.g. distances between ladder rungs, support brackets, hangers, etc.) are to be chosen according to the construction of cable (i.e. size and rigidity) and the probability of vibration and are to be generally in accordance with those given in Table 2.10.7.

**Table 2.10.7 Maximum spacing of supports or fixings for securing cables**

External diameter of cable		Non-armoured cables	Armoured cables
exceeding	not exceeding		
mm	mm	mm	mm
–	8	200	250
8	13	250	300
13	20	300	350
20	30	350	400
30	–	400	450

10.10.4 Where the cables are laid on top of their support system, the spacings of fixings may be increased beyond those given in Table 2.10.7, but should take account of the probability of movement and vibration and in general is not to exceed 900 mm. This relaxation is not to be applied where cables can be subjected to heavy external forces, e.g. where they are run on, or above, open deck or in areas subject to impact by sea-water.

10.10.5 Where the cable support system or fixings are manufactured from a material other than metal, suitable supplementary metallic fixings or straps spaced at regular distances are to be provided, such that, in the event of a fire or failure, the cable support system and the cables affixed to it are prevented from falling and causing an injury to personnel and/or an obstruction to any escape route. Alternatively, the cables may be routed away from such areas.

10.10.6 Cable support systems manufactured of plastics materials installed on the open deck are to be protected from degradation caused by exposure to solar radiation.

10.10.7 Single core electric cables are to be firmly fixed, using supports of strength adequate to withstand forces corresponding to the values of the peak prospective short-circuit current.

## 10.11 Penetration of bulkheads and decks by cables

*10.11.1* Where electric cables pass through watertight, fire insulated or gastight bulkheads or decks separating dangerous zones or spaces from non-dangerous zones or spaces, the arrangements are to be such as to ensure the integrity of the bulkhead or deck is not impaired. The arrangements chosen are to ensure that the cables are not adversely affected.

*10.11.2* Where cables pass through non-watertight bulkheads or structural steel, the holes are to be bushed with suitable material. If the steel is at least 6 mm thick, adequately rounded edges may be accepted as the equivalent of bushing.

*10.11.3* Electric cables passing through decks are to be protected by deck tubes or ducts.

*10.11.4* Where cables pass through thermal insulation they are to do so at right angles, in tubes sealed at both ends.

## 10.12 Installation of electric cables in protective casings

*10.12.1* Protective casings are to be mechanically continuous across joints and effectively supported and secured to prevent damage to the electric cables.

*10.12.2* When protective casings are secured by means of clips or straps manufactured from a material other than metal the fixings are to be supplemented by suitable metal clips or straps spaced at regular distances each not exceeding 2 m.

*10.12.3* Protective casings are to be suitably smooth on the interior and have their ends shaped or bushed in such a manner as not to damage the cables.

*10.12.4* The internal radius of bends of protective casings are to be not less than that required for the largest cable installed therein, see 10.8.2.

*10.12.5* The space factor (ratio of the sum of the cross sectional areas corresponding to the external diameters of the cables to the internal cross sectional area of the protective casings) is not to exceed 0.4.

*10.12.6* Where necessary, ventilation openings are to be provided at the highest and lowest points of protective casings to permit air circulation and to prevent accumulation of water.

*10.12.7* Expansion joints are to be provided in protective casings where necessary.

*10.12.8* Protective casings containing high voltage electric cables are not to contain other electric cables and are to be clearly identified, defining their function and voltage.

## 10.13 Single-core electric cables for alternating current

*10.13.1* When installed in protective casings, electric cables belonging to the same circuit are to be installed in the same casing, unless the casing is of non-magnetic material.

*10.13.2* Cable clips are to include electric cables of all phases of a circuit unless the clips are of non-magnetic material.

*10.13.3* Single-core cables of the same circuit are to be in contact with one another, as far as possible. In any event the distance between adjacent electric cables is not to be greater than one cable diameter.

*10.13.4* If single-core cables of current rating greater than 250 A are installed near a steel bulkhead, the clearance between the cables and the bulkhead is to be at least 50 mm unless the cables belonging to the same a.c. circuit are installed in trefoil formation.

*10.13.5* Magnetic material is not to be used between single core cables of a group. Where cables pass through steel plates, all the conductors of the same circuit are to pass through a plate or gland, so made that there is no magnetic material between the cables, and the clearance between the cables and the magnetic material is not to be less than 75 mm, unless the cables belonging to the same a.c. circuit are installed in trefoil formation.

*10.13.6* Electric cables are to be installed such that the induced voltages, and any circulating currents, in the sheath or armour are limited to safe values.

## 10.14 Electric cable ends

*10.14.1* Where screw-clamp or spring-clamp type terminations are used in electrical apparatus for external cable connections (see 1.10.6), cable conductors of the solid or stranded type may be inserted directly into the terminals. Where flexible conductors are used, a suitable termination is to be fitted to the cable conductor to prevent 'whiskering' of the strands.

*10.14.2* If compression type conductor terminations are used on the cable ends, they are to be of a size to match the conductor and to be made with a compression type tool with the dies selected to suit the termination and conductor sizes and having a ratchet action to ensure completion of the compression action.

*10.14.3* Soldered sockets may be used in conjunction with non corrosive fluxes provided that the maximum conductor temperature at the joint, under short-circuit conditions, does not exceed 160°C.

*10.14.4* High voltage cables of the radial field type (i.e. having a conducting layer to control the electric field within the insulation) are to have terminations which provide electrical stress control.

10.14.5 Electric cables having hygroscopic insulation (e.g. mineral insulated) are to have their ends sealed against ingress of moisture.

10.14.6 Cable terminations are to be of such a design and dimensions that the maximum current likely to flow through them will not result in degradation of the contacts or damage to insulation as the result of overheating.

10.14.7 The fixing of conductors in terminals at joints and at tapplings is to be capable of withstanding the thermal and mechanical effects of short-circuit currents.

### **10.15 Joints and branch circuits in cable systems**

10.15.1 If a joint is necessary it is to be carried out so that all conductors are adequately secured, insulated and protected from atmospheric action. The flame retardant properties or fire resisting properties of the cable are to be retained, the continuity of metallic sheath, braid or armour is to be maintained and the current carrying capacity of the cable is not to be impaired.

10.15.2 Tapplings (branch circuits) are to be made in suitable boxes of such a design that the conductors remain suitably insulated, protected from atmospheric action and fitted with terminals or busbars of dimensions appropriate to the current rating.

10.15.3 Cables of a fire resistant type (see 10.5.3) are to be installed so that they are continuous throughout their length without any joints or tapplings.

### **10.16 Busbar trunking systems (bustrunks)**

10.16.1 Where busbar trunking systems are used in place of electric cables, they are to comply with the requirements of 10.16.2 to 10.16.6, in addition to the applicable requirements in Section 7.

10.16.2 The busbar trunking, or enclosure system, is to have a minimum ingress protection of IP54, according to IEC60529: *Degrees of protection provided by enclosures* (IP Code).

10.16.3 The internal and external arrangements of the busbar trunking, or enclosure system, are to ensure that the fire and/or watertight integrity of any structure through which it passes is not impaired.

10.16.4 Where the busbar trunking system is employed for circuits on and below the bulkhead deck, arrangements are to be made to ensure that circuits on other decks are not affected in the event of partial flooding under the normal angles of inclination given in 1.9 for essential electrical equipment.

10.16.5 Supports and accessories are to be robust and are to be of corrosion-resistant material or suitably corrosion inhibited before erection. The support system is to effectively secure the busbar trunking system to the ship's structure.

10.16.6 When accessories are fixed to the busbar system by means of clips or straps manufactured from a material other than metal, the fixings are to be supplemented by suitable metal clips or straps, such that, in the event of a fire or failure, the accessories are prevented from falling and causing injury to personnel and/or an obstruction to any escape route. Alternatively, the busbar system may be routed away from such areas.

## **Section 11 Batteries**

### **11.1 General**

11.1.1 The requirements of this Section apply to permanently installed secondary batteries of the vented and valve-regulated sealed type.

11.1.2 A vented battery is one in which the cells have a cover provided with an opening through which the products of electrolysis and evaporation are allowed to escape freely from the cells to the atmosphere.

11.1.3 A valve-regulated sealed battery is one in which the cells are closed but have an arrangement (valve) which allows the escape of gas if the internal pressure exceeds a predetermined value. The electrolyte cannot normally be replaced.

### **11.2 Construction**

11.2.1 Batteries are to be constructed so as to prevent spilling of the electrolyte due to motion and to minimize the emission of electrolyte spray.

### **11.3 Location**

11.3.1 Vented batteries connected to a charging device with a power output of more than 2 kW, calculated from the maximum obtainable charging current and the nominal voltage of the battery, are to be housed in an adequately ventilated compartment assigned to batteries only, or in an adequately ventilated suitable box on open deck.

11.3.2 Vented batteries connected to a charging device with a power output within the range 0,2 kW to 2 kW, calculated from the maximum obtainable charging current and the nominal voltage of the battery, are to be installed in accordance with 11.3.1, or may be installed within a well ventilated machinery or similar space.

11.3.3 Vented batteries connected to a charging device with a power output of less than 0,2 kW, calculated from the maximum obtainable charging current and the nominal voltage of the battery, may be installed in an open position or in a battery box in any suitable space.

11.3.4 Where more than one charging device is installed for any battery or group of batteries in one location, the total power output is to be used to determine the installation requirements of 11.3.1, 11.3.2 or 11.3.3.

11.3.5 Valve-regulated sealed batteries may be located in compartments with standard marine or industrial electrical equipment provided that the ventilation requirements of 11.5.10 and the charging requirements of 11.6.4 and 11.6.5 are complied with. Equipment that may produce arcs, sparks or high temperatures in normal operation is not to be in close proximity to battery vent plugs or pressure relief valve outlets.

11.3.6 Where lead-acid and nickel-cadmium batteries are installed in the same compartment precautions are to be taken, such as the provision of screens, to prevent possible contamination of electrolytes.

11.3.7 Where batteries may be exposed to the risk of mechanical damage or falling objects they are to be suitably protected.

11.3.8 Batteries installed in crew and passenger cabins, together with their associated corridors, are to be of the hermetically sealed type.

11.3.9 A permanent notice prohibiting smoking and the use of naked lights or equipment capable of creating a source of ignition is to be prominently displayed adjacent to the entrances of all compartments containing batteries.

11.3.10 Only electrical equipment necessary for operational reasons and for the provision of lighting is to be installed in compartments provided in compliance with 11.3.1. Such electrical equipment is to be certified for group IIC gases and temperature Class T1 in accordance with IEC 60079: *Electrical apparatus for explosive gas atmospheres*, or an acceptable and relevant National Standard.

## 11.4 Installation

11.4.1 Batteries are to be arranged such that each cell or crate of cells is accessible from the top and at least one side and it is to be ensured that they are suitably secured to move with the ship's motion.

11.4.2 The materials used in the construction of a battery rack or stand are to be resistant to the battery electrolyte or suitably protected by paint or a coating.

11.4.3 Measures are to be taken to minimize the effect of any electrolyte spillage and leakage, for example the use of rubber capping around the top of the cells and the provision of a tray of electrolyte-resistant material below the cells, unless the deck is suitably protected with paint or a coating.

11.4.4 The interiors of all compartments for batteries, including crates, trays, boxes, shelves and other structural parts therein, are to be of an electrolyte-resistant material or suitably protected, for example with paint or a coating.

## 11.5 Ventilation

11.5.1 Battery compartments and boxes are to be ventilated to avoid accumulation of dangerous concentrations of flammable gas. The ventilation openings are to be of a non-closeable type and a permanent notice is to be prominently displayed adjacent to them, stating:

THIS VENTILATOR OPENING IS NOT TO BE CLOSED OR BLOCKED AT ANY TIME – EXPLOSIVE GAS.

11.5.2 Ducted natural ventilation may be employed for battery installations connected to a charging device with a power output of 2 kW or less, provided the exhaust duct can be run directly from the top of the compartment or box to the open air above, with no part of the duct more than 45° from the vertical. A suitable opening is also to be provided below the level of the top of the batteries, so as to ensure a free ventilation air flow. The ventilation duct is to have an area not less than 50 cm<sup>2</sup> for every 1 m<sup>3</sup> of battery compartment or box volume.

11.5.3 Where natural ventilation is impracticable or insufficient, mechanical ventilation is to be provided, with the air inlet located near the floor and the exhaust at the top of the compartment.

11.5.4 Mechanical exhaust ventilation complying with 11.5.9 is to be provided for battery installations connected to a charging device with a total maximum power output of more than 2 kW.

11.5.5 The ventilation system for battery compartments and boxes, other than boxes located on open deck or in spaces to which 11.3.2 and 11.3.3 refer, is to be separate from other ventilation systems. The exhaust ducting is to be led to a location in the open air, where any gases can be safely diluted, away from possible sources of ignition and openings into spaces where gases may accumulate.

11.5.6 Fan motors associated with exhaust ducts from battery compartments are to be placed external to the ducts and the compartments.

11.5.7 Ventilating fans for battery compartments are to be so constructed and be of material such as to minimize risk of sparking in the event of the impeller touching the casing. Non-metallic-impellers are to be of an anti-static material.

11.5.8 Battery boxes are to be provided with sufficient ventilation openings located so as to avoid accumulation of flammable gas whilst preventing the entrance of rain or spray.

11.5.9 The ventilation arrangements for all installations of vented type batteries are to be such that the quantity of air expelled is at least equal to:

$$Q = 110In$$

where

$n$  = number of cells in series

$I$  = maximum current delivered by the charging equipment during gas formation, but not less than 25 per cent of the maximum obtainable charging current in amperes

$Q$  = quantity of air expelled in litres/hr

11.5.10 The ventilation rate for compartments containing valve-regulated sealed batteries may be reduced to 25 per cent of that given in 11.5.9.

### 11.6 Charging facilities

11.6.1 Charging facilities are to be provided for all secondary batteries such that they may be completely charged from the completely discharged state in a reasonable time having regard to the service requirements.

11.6.2 Suitable means, including an ammeter and a voltmeter, are to be provided for controlling and monitoring charging of batteries, and to protect them against discharge into the charging circuits.

11.6.3 For floating circuits or any other conditions where the load is connected to the battery whilst it is on charge, the maximum battery voltage is not to exceed the safe value for any connected apparatus.

11.6.4 Where valve-regulated sealed batteries are installed, the charging facilities are to incorporate independent means such as overvoltage protection to prevent gas evolution in excess of the manufacturer's design quantity.

11.6.5 Boost charge facilities, where provided, are to be arranged such that they are automatically disconnected should the battery compartment ventilation system fail.

### 11.7 Recording of batteries for emergency and essential services

11.7.1 A schedule of batteries fitted for use for essential and emergency services is to be compiled and maintained.

11.7.2 Procedures are to be put in place and documented to ensure that, where batteries are replaced, they are of an equivalent performance type, see also 1.4.3.

11.7.3 When additions or alterations are proposed to the existing batteries for essential and emergency services, the schedule and replacement procedure documentation are to be updated to reflect the proposed installation and submitted in accordance with 1.4.2.

11.7.4 The schedule and replacement procedure documentation are to be made available to the LR Surveyor on request.

## Section 12

### Equipment – Heating, lighting and accessories

#### 12.1 Heating and cooking equipment

12.1.1 The construction of heaters is to give a degree of protection according to IEC 60529: *Degrees of protection provided by enclosures (IP Code)*, or an acceptable and relevant National Standard, suitable for the intended location.

12.1.2 Heating elements are to be suitably guarded.

12.1.3 Heating and cooking equipment is to be installed such that adjacent bulkheads and decks are not subjected to excessive heating.

#### 12.2 Lighting – General

12.2.1 Lampholders are to be constructed of flame retarding non-hygroscopic materials.

12.2.2 Lighting fittings are to be so arranged as to prevent temperature rises which overheat or damage surrounding materials. They must not impair the integrity of fire divisions.

#### 12.3 Incandescent lighting

12.3.1 Tungsten filament lamps and lampholders are to be in accordance with Table 2.12.1.

**Table 2.12.1 Lamps and lampholders**

Designation	Maximum lamp rating		Maximum lampholder current, A
	Voltage, V	Power, W	
Screw cap lamps			
E40	250	3000	16
E27	250	200	4
E14	250	15	2
E10	24	—	2
Bayonet cap lamps			
B22	250	200	4
B15d	250	15	2
B15s	55	15	2
Tubular fluorescent lamps			
G13	250	80	—
G5	250	13	—

12.3.2 Lampholders of type E40 are to be provided with a means of locking the lamp in the lampholder.

#### 12.4 Fluorescent lighting

12.4.1 Fluorescent lamps and lampholders are to be in accordance with Table 2.12.1.

12.4.2 Fittings, reactors, capacitors and other auxiliaries are not to be mounted on surfaces which are subject to high temperatures. If mounted separately they are additionally to be enclosed in an earthed conductive casing.

12.4.3 Where capacitors of 0,5 microfarads and above are installed, means are to be provided to promptly discharge the capacitors on disconnection of the supply.

## 12.5 Discharge lighting

12.5.1 Discharge lamps operating in excess of 250 V are only acceptable as fixed fittings. Warning notices calling attention to the voltage are to be permanently displayed at points of access to the lamps and where otherwise necessary.

## 12.6 Socket outlets and plugs

12.6.1 The temperature rise on the live parts of socket outlet and plugs is not to exceed 30°C. Socket outlets and plugs are to be so constructed that they cannot be readily short-circuited whether the plug is in or out, and so that a pin of the plug cannot be made to earth either pole of the socket outlet.

12.6.2 All socket outlets of current rating in excess of 16 A are to be provided with a switch, and be interlocked such that the plug cannot be inserted or withdrawn when the switch is in the 'on' position.

12.6.3 Where it is necessary to earth the non-current carrying parts of portable or transportable equipment, an effective means of earthing is to be provided at the socket outlet.

12.6.4 On weather decks, galleys, laundries, machinery spaces and all wet situations socket outlets and plugs are to be effectively shielded against rain and spray and are to be provided with means of maintaining this quality after removal of the plug.

## 12.7 Enclosures

12.7.1 Enclosures for the containing and mounting of electrical accessories are to be of metal, effectively protected against corrosion, or of flame retardant insulating materials.

## Section 13

### Electrical equipment for use in explosive gas atmospheres or in the presence of combustible dusts

#### 13.1 General

13.1.1 The installation of electrical equipment in spaces and locations in which flammable mixtures are liable to collect, is to be minimized as far as is consistent with operational necessity and the provision of lighting, monitoring, alarm or control facilities enhancing the overall safety of the ship.

13.1.2 In order to eliminate potential sources of ignition from spaces and locations in which flammable mixtures are liable to collect, in accordance with SOLAS 1974 as amended, Chapter II-1, Regulation 45, such dangerous or hazardous areas are to be identified and electrical equipment within these areas is to be selected and installed in accordance with the requirements of this Section.

#### 13.2 Selection of equipment

13.2.1 When apparatus is to be installed in areas where an explosive gas atmosphere may be present, unless permitted otherwise by 13.2.2, it is to be of a 'safe-type', as listed below, certified or approved by a competent authority for the gases encountered. The construction and type testing is to be in accordance with IEC 60079: *Electrical Equipment for Explosive Gas Atmospheres* or an acceptable and relevant National Standard.

Intrinsically safe	– Ex 'i'
Increased safety	– Ex 'e'
Flameproof	– Ex 'd'
Pressurized enclosure	– Ex 'p'
Powder filled	– Ex 'q'
Encapsulated	– Ex 'm'

13.2.2 Consideration may be given to the use of equipment of the following types:

- equipment such as control panels, protected by purging and pressurization and capable of being verified by inspection as meeting the requirements of IEC 60079-2;
- simple non-energy-storing apparatus having negligible surface temperature rise in normal operation, such as limit switches, strain gauges, etc, incorporated in intrinsically-safe circuits;
- radio aerials having robust construction, meeting the relevant requirements of IEC 60079-15. Additionally, in the case of transmitter aerials, it is to be shown, by detailed study or measurement, or by limiting the peak radiated power and field strength to 1 W and 30 V/m, respectively, that they present negligible risk of inducing incendive sparking in adjacent structures or equipment;
- electrical apparatus with type of protection 'n' or 'N' provided it is in a well ventilated area on open deck and not within 3 m of any flammable gas or vapour outlet.
- electrical apparatus selected in accordance with IEC 60092-502: *Electrical Installations in Ships – Tankers – Special Features*, see 13.9 to 13.11.

# Electrical Engineering

# Part 6, Chapter 2

Section 13

13.2.3 Where apparatus is to be installed in areas where combustible dusts may be present in quantities sufficient to create an explosive atmosphere, it is, when practicable, to be of a type certified or approved by a competent authority for the dusts and additionally any explosive gases encountered.

13.2.4 Electrical equipment for use in combustible dust atmospheres is to be so designed and installed as to minimize the accumulation of dust which may interfere with the safe dissipation of heat from the enclosure.

13.2.5 Where equipment certified for combustible dusts is not available, consideration will be given to the use of apparatus complying as a minimum, with the following requirements provided no explosive gases will be present:

- (a) the enclosure is to be at least dust protected (IP5X) having, when type tested, an ingress of fine dust within the enclosure not exceeding 10 g per m<sup>3</sup> of free air space, and
- (b) the surface temperature of the apparatus, under the most onerous combination of normal operating conditions, but in the absence of a dust layer, is to be at least 10°C below the auto-ignition temperature of the dusts encountered, or
- (c) the equipment is to be certified intrinsically-safe having a temperature classification ensuring compliance with (b), or
- (d) pressurized and operated in accordance with procedures ensuring, prior to its re-energization, the absence of dust within the enclosure following loss of pressurisation and consequent shutdown, and having surface temperature complying with (b), or
- (e) simple apparatus included in intrinsically-safe circuits or radio aerials, complying with 13.2.2(b) or (c) respectively.

## 13.3 Installation of electrical equipment

13.3.1 The method of installation and application of safe-type equipment is to be in accordance with IEC 60079-14, or the national code of practice relevant to the standard to which the equipment has been certified. Any special requirements laid down by the equipment certification documentation are also to be observed. The ambient temperature range for which the apparatus is certified, is to be taken to be minus 20°C to 40°C, unless otherwise stated, and account is to be taken of this when assessing the suitability of the equipment for the auto-ignition temperature of the gases and dusts encountered.

13.3.2 All switches and protective devices from which equipment located in dangerous zones or spaces is supplied are to interrupt all poles or phases and, where practicable are to be located in a non-hazardous zone or space. Such equipment, switches and protective devices are to be suitably labelled for identification purposes.

## 13.4 Dangerous zones and spaces

13.4.1 Dangerous zones or spaces and sources of hazard for ships intended for the carriage in bulk of oil, liquefied gases and other hazardous liquids, and the requirements for ships carrying vehicles with fuel in their tanks, are defined in 13.9 to 13.12. The following principles are to apply in general, and where any specific arrangement does not fall into any of the categories covered by 13.9 to 13.12.

13.4.2 A dangerous zone or space may arise from the presence of any of the following:

- (a) spaces or tanks containing either:
  - (i) flammable liquid having a flashpoint (closed-cup test), not exceeding 60°C;
  - (ii) flammable liquid having a flashpoint exceeding 60°C, heated or raised by ambient conditions to a temperature within 15°C of its flashpoint;
  - (iii) flammable gas.
- (b) piping systems or equipment containing fluid defined by (a) and having flanged joints or glands or other openings through which leakage of fluid may occur under normal operating conditions;
- (c) spaces containing solids, such as coal or grain, liable to release flammable gas and/or combustible dust;
- (d) piping systems or equipment associated with processes (such as battery charging or electrochlorination) generating flammable gas as a by-product and having openings from which the gas may escape under normal operating conditions;
- (e) piping systems or equivalent containing flammable liquids not defined by (a), having flanged joints, glands or other openings through which leakage of fluid in the form of a mist or fine spray may occur under normal operating conditions.

13.4.3 The following zones or spaces are regarded as dangerous:

- (a) the interiors of those spaces, tanks, piping systems and equipment defined by 13.4.2(a), (b) and (c);
- (b) spaces separated by a single bulkhead or deck from a cargo defined by 13.4.2(a);
- (c) enclosed or semi-enclosed spaces containing pipework or equipment defined by 13.4.2(b) and (d);
- (d) enclosed or semi-enclosed spaces with direct opening into a dangerous space or zone;
- (e) zones within a 3 m radius of ventilation inlets or outlets, hatches or doorways or other openings into dangerous spaces, or within 3 m of the ventilation outlets of spaces regarded by 13.6 as open areas and which contain the pipework or equipment defined by 13.4.2(b); where the hazard results from flammable gas or vapour having a density relative to that of air of more than 0.75, the dangerous zone is considered to extend vertically downward to solid deck, or for a distance of 9m, whichever is the lesser;
- (f) zones within a 3 m radius of flanged joints, or glands or other openings defined by 13.4.2(b); in the case of gas or vapour having a relative density of more than 0.75, the dangerous zone is considered to extend vertically downwards as described under (e);
- (g) zones within a 1.5 m radius of the ventilation outlets of spaces regarded as open areas containing items defined under 13.4.2(d):

# Electrical Engineering

# Part 6, Chapter 2

Section 13

- (h) zones within a 1,5 m radius of flanged joints, or glands or other openings defined by 13.4.2(d) and (e);
- (j) zones within a 3 m radius of bunds or barriers intended to contain spillage of liquids defined by 13.4.2(a).

## 13.5 Semi-enclosed spaces

13.5.1 Semi-enclosed spaces are considered to be spaces limited by decks and/or bulkheads in such a manner that the natural conditions of ventilation are sensibly different from those obtained on open deck.

## 13.6 Ventilation

13.6.1 Where an enclosed or semi-enclosed space is provided with mechanical ventilation ensuring at least 12 air changes/hour, and leaving no areas of stagnant air, it may be regarded in consideration of dangerous zones as would otherwise be defined by 13.4.3(c) and (d), as an open area.

13.6.2 Where the rate of ventilation air flow, in relation to the maximum rate of release of flammable substances reasonably to be expected under normal conditions, is sufficient to prevent the concentration of flammable substances approaching their lower explosive limit, consideration may be given to regarding as non-dangerous, the space, ventilation and other openings into it, and the zone around the equipment contained within.

13.6.3 An alarm is to be provided on the navigating bridge, engine control room, and where applicable, cargo control room to indicate any loss of the required ventilation capacity.

## 13.7 Pressurization

13.7.1 A space having access to a dangerous space or zone as defined under 13.4.3(c) to (j) may be regarded as non-dangerous if fulfilling all the following conditions:

- (a) access is by means of an air-lock, having gastight steel doors, the inner of which as a minimum, is self-closing without any hold-back arrangement;
- (b) it is maintained at an overpressure relative to the external hazardous area by ventilation from a non-dangerous area;
- (c) the relative air pressure within the space is continuously monitored and, so arranged, that in the event of loss of overpressure an alarm is given and the electrical supply to all equipment not of a safe-type is automatically disconnected. Where the shutdown of equipment could introduce a hazard, an alarm may be given, in lieu of shutdown, upon loss of overpressure, and a means of disconnection of non-safe-type electrical equipment, capable of being controlled from a manned station, provided in conjunction with an agreed operational procedure; where the means of disconnection is located within the space then it is to be effected by equipment of a safe-type;
- (d) any electrical equipment required to operate upon loss of overpressure, lighting fittings (see 5.7.3) and equipment within the air-lock, is to be of a safe-type;

- (e) means are to be provided to prevent electrical equipment, other than of a safe-type, being energized until the atmosphere within the space is made safe, by air renewal of at least 10 times the capacity of the space.

## 13.8 Cable and cable installation

13.8.1 Electric cables are not to be installed in dangerous zones or spaces, except where specifically permitted by 13.9 to 13.11 or when associated with intrinsically-safe circuits.

13.8.2 In addition to the requirements of Section 10, cables for circuits that are not intrinsically-safe, which are located in dangerous zones or spaces, or which may be exposed to cargo oil, oil vapour or gas, are to be either:

- (a) mineral insulated with copper sheath, or
- (b) armoured or braided for earth detection.

13.8.3 Armouring, braiding and other metal coverings of cables installed in dangerous zones or spaces are to be effectively earthed at least at both ends.

13.8.4 Where there is risk of intermittent contact between armour and exposed metalwork, non-metallic impervious sheath is to be applied over metallic armour of cables.

13.8.5 Cables associated with intrinsically-safe circuits are to be used only for such circuits. They are to be physically separated from cables associated with non-intrinsically-safe circuits, e.g. neither installed in the same protective casing nor secured by the same fixing clip.

## 13.9 Requirements for tankers intended for the carriage in bulk of oil cargoes having a flash point not exceeding 60°C (closed-cup test)

13.9.1 In order to eliminate potential sources of ignition from hazardous areas onboard tankers in accordance with SOLAS 1974 as amended, Chapter II-1, Regulation 45.11, electrical equipment is to be selected and installed in accordance with IEC 60092: *Electrical installations in ships – Part 502: Tankers – Special features*.

## 13.10 Requirements for ships for the carriage of liquefied gases in bulk

13.10.1 See Chapter 10 of the *Rules for Ships for Liquefied Gases*.

## 13.11 Requirements for ships intended for the carriage in bulk of other flammable liquid cargoes

13.11.1 See Chapter 10 of the *Rules for Ships for Liquid Chemicals*.



# Electrical Engineering

# Part 6, Chapter 2

Sections 13 &amp; 14

## 13.12 Special requirements for ships with spaces for carrying vehicles with fuel in their tanks, for their own propulsion

### 13.12.1 Passenger ships with special category spaces above the bulkhead deck for carrying vehicles:

- (a) electrical equipment fitted within a height of 45 cm above the vehicle deck, or any platform on which vehicles are carried, or within the exhaust ventilation trunking for the space, is to be of a safe-type;
- (b) electrical equipment situated elsewhere within the space is to have an enclosure of ingress protection rating of at least IP55, if not of a safe-type, see IEC 60529: *Classification of Degrees of Protection Provided by Enclosures*. Smoke and gas detector heads are exempt from this requirement.

### 13.12.2 Passenger ships with special category spaces below the bulkhead deck for carrying vehicles: electrical equipment fitted within the space and within the exhaust ventilation trunking for the space, is to be of a safe-type.

### 13.12.3 Passenger ships with cargo spaces, other than special category spaces, for carrying vehicles:

- (a) electrical equipment within such a cargo space, or within the exhaust ventilation trunking for the space, is to be of a safe-type;
- (b) all electrical circuits terminating in the cargo space are to be provided with multipole linked isolating switches located outside the cargo hold. Provision is to be made for locking in the off position. This does not apply to safety circuits such as those for fire, smoke or gas detection.

### 13.12.4 Cargo ships with closed ro-ro cargo spaces for carrying vehicles:

- (a) except where exempted by (b) electrical equipment fitted within the space and within the exhaust ventilation trunking for the space is to be of a safe-type;
- (b) where the ventilation system required by SOLAS 1974 as amended, Chapter II-2, Regulation 20.3.1.1.1 is arranged to operate continuously and is sufficient to provide at least ten air changes per hour, whenever vehicles are on board, above a height of 45 cm from the vehicle deck, or any platform on which vehicles are carried, electrical equipment having an enclosure of ingress protection rating of at least IP 55 may be accepted as an alternative to that of a safe-type;
- (c) all electrical circuits terminating in the cargo space are to be provided with multipole linked isolating switches located outside the cargo hold. Provision is to be made for locking in the off position. This does not apply to safety circuits such as those for fire, smoke or gas detection.

## 13.13 Special requirements for ships intended for the carriage of dangerous goods

13.13.1 In order to eliminate potential sources of ignition in enclosed cargo spaces or vehicle spaces in accordance with SOLAS 1974 as amended, Chapter II-2, Regulation 19.3.2, and from associated hazardous areas (see 13.4.2), electrical equipment is to be selected in accordance with 13.13.2 and 13.13.3 and installed in accordance with 13.3 and 13.13.4 to 13.13.7.

13.13.2 Electrical equipment essential for the safety and operation of the ship is to be of a certified safe type selected in accordance with IEC 60092 *Electrical installations in ships – Part 506: Special features – Ships carrying specific dangerous goods and materials hazardous only in bulk*.

13.13.3 In addition to the requirements of IEC 60092-506, pipes such as ventilation and bilge pipes, having ends opening into a hazardous area are to be considered a hazardous area. Enclosed spaces such as pipe tunnels and bilge pump rooms containing such pipes and with equipment and components such as pumps, valves and flanges are to be considered as extended hazardous areas unless protected by overpressure.

13.13.4 Electrical equipment not essential for the safety or operation of the ship and which is not of a certified safe type is to be completely disconnected and protected against unauthorised re-connection. Disconnection is to be made outside the hazardous areas and be effected with isolating links or lockable switches.

13.13.5 Electrical equipment and all cables, including through runs and terminating cables, are to be protected against mechanical damage. Cables are to be either enclosed in screwed heavy gauge steel drawn or seam-welded and galvanized conduit, or protected by electrically continuous metal sheathing or metallic wire armour braid or tape.

13.13.6 Cables joints in cargo spaces are to be avoided where possible. Where joints are unavoidable, they are to be enclosed in metal-clad or impact strength plastic junction boxes of certified safe type (see 13.13.2) or heat-shrink or encapsulated crimp sleeve cable joints.

13.13.7 Cable penetrations of decks and bulkheads are to be sealed against the passage of gas or vapour.

## Section 14 Navigation and manoeuvring systems

### 14.1 Steering gear

14.1.1 The requirements of 14.1.2 to 14.1.7 are to be read in conjunction with those in Pt 5, Ch 19.5.

# Electrical Engineering

# Part 6, Chapter 2

Sections 14 & 15

**14.1.2** Two exclusive circuits, fed from the main source of electrical power and each having adequate capacity to supply all the motors which may be connected to it simultaneously are to be provided for each electric or electrohydraulic steering gear arrangement consisting of one or more electric motors. One of these circuits may pass through the emergency switchboard, *see also* Pt 5, Ch 19,6.

**14.1.3** The main and auxiliary steering gear motors are to be capable of being started from a position on the navigating bridge and also arranged to restart automatically when power is restored after a power failure.

**14.1.4** The motor of an associated auxiliary electric or electrohydraulic power unit may be connected to one of the circuits supplying the main steering gear.

**14.1.5** Only short-circuit protection is to be provided for each main and auxiliary steering gear motor circuit.

**14.1.6** In ships of less than 1600 gross tonnage, if an auxiliary steering gear is not electrically powered or is powered by an electric motor primarily intended for other services, the main steering gear may be fed by one circuit from the main switchboard. Consideration would be given to other protective arrangements other than described in 14.1.5 for such a motor primarily intended for other services.

**14.1.7** Each main and auxiliary steering gear electric control system which is to be operated from the navigating bridge is to be served with electric power by a separate circuit supplied from the associated steering gear power circuit, from a point within the steering gear compartment, or directly from the same section of switchboard busbars, main or emergency, to which the associated steering gear power circuit is connected. Each separate circuit is to be provided with short-circuit protection only.

## 14.2 Thruster systems for steering

**14.2.1** Where azimuth or rotatable thruster units, used as the sole means of steering, are electrically driven the requirements of Pt 5, Ch 20,5.1 are to be complied with.

## 14.3 Thruster systems for dynamic positioning

**14.3.1** For ships having a **DP** notation the requirements of Pt 7, Ch 4 are to be complied with.

## 14.4 Thruster systems for manoeuvring

**14.4.1** Where a thruster unit is fitted solely for the purpose of manoeuvring, and is electrically driven, its starting and operation is not to cause the loss of any essential services.

**14.4.2** In order to ensure that the thruster system is not tripped inadvertently whilst manoeuvring the ship, overload protection in the form of an alarm is to be provided for the electric motor and any associated supply converters, in lieu of tripping.

**14.4.3** The thruster unit electric motor is not to be disconnected as part of a load management switching operation.

## 14.5 Navigation lights

**14.5.1** Navigation lights are to be connected separately to a distribution board reserved for this purpose only and accessible to the officer of the watch. This distribution board is to be connected directly or through transformers to the emergency source of electrical power in compliance with, for passenger ships, 3.2.5(b) and 3.2.7(a)(i) or, for cargo ships, 3.3.5(c) and 3.3.7(a).

**14.5.2** Each navigation light is to be controlled and protected in each insulated pole by a switch and fuse or circuit-breaker mounted on the distribution board.

**14.5.3** Each navigation light is to be provided with an automatic indicator giving audible and/or visual indication of failure of the light. If an audible device alone is fitted, it is to be connected to an independent source of supply, e.g. a battery, with means provided to test this supply. If a visual signal is used connected in series with the navigation light, means are to be provided to prevent extinction of the navigation light due to failure of the signal. The requirements of this paragraph do not apply to tugs, trawlers and similar small vessels.

**14.5.4** Provision is to be made on the navigating bridge for the navigation lights to be transferred to an alternative circuit fed from the main source of electrical power.

**14.5.5** Any statutory requirements of the country of registration are to be complied with and may be accepted as an alternative to the above.

## 14.6 Navigational aids

**14.6.1** Navigational aids as required by SOLAS are to be fed from the emergency source of electrical power, *see also* 3.2.5(c)(ii) and 3.3.5(d)(ii).

**14.6.2** For ships having a notation **NAV 1** navigational aids are to have an alternative supply fed from the main source of electrical power, independent of the emergency switchboard, with automatic changeover facilities.

## Section 15 Electric propulsion

### 15.1 General

**15.1.1** Where the arrangements permit a propulsion motor to be connected to a generating plant having a continuous rating greater than the motor rating, means are to be provided to limit the continuous input to the motor to a value not exceeding the continuous full load torque for which the motor and shafts are approved.

# Electrical Engineering

## Part 6, Chapter 2

Section 15

15.1.2 The ventilation and cooling systems for electrical propulsion equipment are to be provided with monitoring devices arranged to operate an alarm if the temperature of the heated cooling medium exceeds a predetermined safe value.

15.1.3 The embedded temperature detectors required by 8.1.9 are to be arranged to operate an alarm if the temperature exceeds a predetermined safe value.

### 15.2 Power requirements

15.2.1 The propulsion system is to have sufficient power for manoeuvring the ship and for going astern. With the ship travelling at maximum service speed the propulsion equipment is to be capable of stopping and reversing the ship in an agreed time.

15.2.2 The propulsion system is to have adequate torque and power margins for all operating conditions including manoeuvring and rough weather with due regard to propeller and ship characteristics.

15.2.3 The electric power for the propulsion system may be derived from generating sets dedicated to propulsion duty or from a central power generation plant which serves both propulsion and ship service loads.

15.2.4 Where propulsion power is derived from a central, common, power plant the control system is to ensure a safe distribution of power between propulsion and ship services, with tripping of non-essential loads and/or reduction in propulsion power if necessary.

15.2.5 Where a central power generation system is employed the number and rating of generator sets is to be such that with one set out of action the remaining sets are capable of providing all essential and normal ship service loads whilst maintaining an effective level of propulsion power.

15.2.6 Where, in a central power generation system, the electrical power requirements are normally supplied by two or more generating sets operating in parallel, on sudden loss of power from one set, the rating of the remaining set(s) in service is to be sufficient to ensure uninterrupted operation of essential services and an effective level of propulsion power.

### 15.3 Propulsion control

15.3.1 Propulsion control systems are to be stable throughout their normal operating range and arranged to attenuate any effects of cyclic propeller load fluctuations caused by wave action.

15.3.2 Step-less control of propeller speed, and/or pitch, from zero to full power ahead or astern is to be provided.

15.3.3 The control system is to ensure that there is no dangerous overspeeding of propulsion motors upon loss of load.

15.3.4 Interlocks are to be provided in the control system to ensure that ahead and astern circuits are not energized simultaneously.

15.3.5 Any single fault in either the propulsion machine excitation or power distribution systems is not to result in a total loss of propulsion power.

15.3.6 Control stations for the propulsion system are to satisfy the requirements of Pt 6, Ch 1.

15.3.7 Each control station is to be provided with emergency stops for propulsion motors. The emergency stop is to be independent of the normal control system.

15.3.8 The control system is to limit the propulsion power if the power available from the generator(s) is not sufficient to supply the demand level of propulsion power. In the event of a power limitation, there is to be a visual indication at the control stations.

15.3.9 Local controls are to be provided, independent of any remote or automatic system, to permit effective control of the propulsion equipment.

15.3.10 The propulsion control may be in analogue or digital form, which is to be developed using a systematic design procedure incorporating verification and validation methods to ensure successful implementation of the requirements listed above. A quality plan giving evidence of compliance with this requirement is to be submitted when requested.

### 15.4 Protection of propulsion system

15.4.1 Provision is to be made for protection against severe overloads, and electrical faults likely to result in damage to plant.

15.4.2 The main propulsion circuits are to be provided with means for detecting earth faults. Where the fault current flowing is liable to cause damage to the electrical equipment there are to be arrangements for interrupting the current.

15.4.3 For the protection of electrical equipment and cables against overvoltages means are to be provided for limiting the induced voltage when field windings, and other inductive circuits are opened. Protective resistors and devices are to be sized to cater for the likely extreme operating conditions.

15.4.4 Where, on stopping or reversing the propeller, regenerated energy is produced by the propulsion motor this is not to cause a dangerous increase of speed in the prime mover or a dangerous overvoltage condition on the supply system. Where a central power generation system is used then the voltage and frequency fluctuations are not to exceed the limits given in 1.7.

## 15.5 Instruments

15.5.1 The main control station is to be provided with the following instruments:

- (a) a.c. systems:
  - (i) an ammeter for each generator and propulsion motor; voltmeter, wattmeter and frequency meter for each generator and ammeter for each excitation circuit;
  - (ii) a temperature indicator for each generator and propulsion motor, the indicator is to read stator winding and cooling system temperature.
- (b) d.c. systems:
  - a voltmeter and ammeter for each generator and propulsion motor;
  - an ammeter for each excitation circuit.

15.5.2 Each control station is to be provided with instruments to indicate:

- (a) propeller speed;
- (b) direction of rotation for a fixed pitch propeller or pitch position for a controllable pitch propeller; and
- (c) visual indication of power limitation.

## ■ Section 16 Fire safety systems

### 16.1 Fire detection and alarm systems

16.1.1 Fire detection and alarm systems are to be provided with an emergency source of electrical power required by 3.2 or 3.3 and are also to be connected to the main source of electrical power. Separate feeders, reserved solely for this purpose, with automatic changeover facilities located in, or adjacent to, the main fire control panel are to be provided. Failure of any power supply is to operate an audible and visual alarm. See also 1.13 and 1.14.

16.1.2 For machinery spaces the requirements of Ch 1,2.8 are applicable.

16.1.3 The fire detection system within the accommodation spaces is, in addition to the requirements of Ch 1,2.8.4, 2.8.6, 2.8.8 and 2.8.10 to 2.8.14, to comply with 16.1.4 to 16.1.15.

16.1.4 The fire control panel is to be located on the navigating bridge or in a central fire control station and may form part of that panel specified in Ch 1,2.8.2. For passenger ships carrying more than 36 passengers, the fire control panel is to be located in the continuously manned central control station.

16.1.5 Detectors and manually operated call points are to be grouped into sections. The activation of any detector or manually operated call point is to initiate a visual and audible fire signal at the control panel and indicating units. If the signals have not received attention within two minutes an audible alarm is to be automatically sounded throughout the crew accommodation and service spaces, control stations and machinery spaces of Category A. This alarm sounder system need not be an integral part of the detection system.

16.1.6 Indicating units are to denote, as a minimum, the section in which a detector or manually operated call point has operated. At least one unit is to be so located that it is easily accessible to responsible members of the crew. One indicating unit is to be located on the navigating bridge if the control panel is located in the central control station.

16.1.7 Clear information is to be displayed on or adjacent to each indicating unit about the spaces covered and the location of the section.

16.1.8 Where the fire detection system does not include means of remotely identifying each detector individually no section covering more than one deck within accommodation, service spaces and control stations is normally to be permitted except a section which covers an enclosed stairway. The number of enclosed spaces in each section are to be limited to the minimum considered necessary in order to avoid delay in identifying the source of fire. In no case are more than fifty spaces permitted in any section.

16.1.9 In passenger ships, where the fire detection system does not include means of remotely identifying each detector individually a section of detectors is neither to serve spaces on both sides of the ship nor on more than one deck except when permitted by 16.1.14.

16.1.10 A section of fire detectors which covers a control station, a service space or an accommodation space is not to include a machinery space of Category A.

16.1.11 The fire detection system is not to be used for any other purpose, except that closing of fire doors and similar functions may be permitted at the control panel.

16.1.12 A loop circuit of an addressable fire detection system, capable of remotely identifying from either end of the loop each detector served by the circuit, may serve spaces on both sides of the ship and on several decks, but is not to be situated in more than one main vertical or horizontal fire zone, nor is a loop circuit which covers a control station or an accommodation space to include a machinery space of Category A.

16.1.13 A loop circuit of an addressable fire detection system may comprise one or more sections of detectors. Where the loop comprises more than one section, the sections are to be separated by devices which will ensure that if a short-circuit occurs anywhere in the loop, only the affected section of detectors will be isolated from the control panel. No section of detectors is in general to include more than 50 detectors.

16.1.14 A section of detectors of an addressable fire detection system is neither to serve spaces on both sides of the ship nor on more than one deck, except that:

- (a) a section of detectors may serve spaces on more than one deck if those spaces are located in either the fore or aft end of the ship, or they constitute common spaces occupying several decks (i.e. public spaces, enclosed stairways, etc.); or
- (b) in ships of less than 20 m in breadth, a section of detectors may serve spaces on both sides of the ship.

16.1.15 The wiring for each section of detectors in an addressable fire detector system is to be separated as widely as practicable from that of all other sections on the same loop. Where practicable no loop is to pass through a space twice. When this is not practical, such as in large public spaces, the part of the loop which by necessity passes through the space for a second time is to be installed at the maximum possible distance from other parts of the loop.

## **16.2 Automatic sprinkler system**

16.2.1 Any electrically-driven power pump, provided solely for the purpose of continuing automatically the discharge of water from the sprinklers, is to be brought into action automatically by the pressure drop in the system before the standing fresh water charge in the pressure tank is completely exhausted.

16.2.2 For **passenger ships**, electrically-driven sea-water pumps for automatic sprinkler systems are to be served by not less than two circuits reserved solely for this purpose, one fed from the main source of electrical power and one from the emergency source of electrical power. Such feeders are to be connected to an automatic changeover switch situated near the sprinkler pump and the switch is to be normally closed to the feeder from the main source of electrical power. No other switches are permitted in the feeders. The switches on the main and emergency switchboards are to be clearly labelled and normally kept closed.

16.2.3 The automatic alarm and detection system is to be fed by exclusive feeders from two sources of electrical power, one of which is to be an emergency source, with automatic changeover facilities located in, or adjacent to, the main alarm and detection panel.

16.2.4 Feeders for the sea-water pump and the automatic alarm and detection system are to be arranged so as to avoid galleys, machinery spaces and other enclosed spaces of high fire risk, except in so far as it is necessary to reach the appropriate switch boards. The cables are to be of a fire resistant type where they pass through such high risk areas.

## **16.3 Fixed water-based local application fire-fighting systems**

16.3.1 Where fixed water-based local application fire-fighting system pressure sources are reliant on external power they need only be supplied by the main source of electrical power. However, where the system forms a section of the main fixed fire-extinguishing system the power supply arrangements are to be equivalent to those required by 16.2.2.

16.3.2 The fire detection, control and alarm systems are to be provided with an emergency source of electrical power required by 3.2 or 3.3 and are also to be connected to the main source of electrical power. Separate feeders, reserved solely for this purpose, with automatic changeover facilities located in, or adjacent to, the main control panel are to be provided.

16.3.3 Failure of any power supply is to operate an audible and visual alarm. See also 1.13 and 1.14.

16.3.4 Means to activate a system are to be located at easily accessible positions inside and outside the protected space. Arrangements inside the space are to be situated such that they will not be cut off by a fire in the protected areas and are suitable for activation in the event of escape. Proposals to install local activation means outside protected spaces are to be submitted for consideration.

16.3.5 For the electrical safety of electrical and electronic equipment in areas protected by fixed water-based local application fire-fighting systems and adjacent areas where water may extend, the requirements of 16.3.6 to 16.3.8 apply.

16.3.6 Unless essential for safety or operational purposes, electrical and electronic equipment is not to be located within protected areas or adjacent areas. The pump, its electrical motor and the sea valve if any, may be in a protected space provided that they are outside areas where water or spray may extend.

16.3.7 Electrical and electronic equipment located within protected areas and those within adjacent areas exposed to direct spray are to have a degree of protection not less than IP44.

16.3.8 Electrical and electronic equipment within adjacent areas not exposed to direct spray may have a lower degree of protection than IP44 provided evidence of suitability for use in these areas is submitted, including details of the design and equipment layout and arrangements to prevent or restrict the ingress of water mist/spray. Cooling airflow for equipment is to be assured.

## **16.4 Fire pumps**

16.4.1 When the emergency fire pump is electrically-driven, the power is to be supplied by a source other than that supplying the main fire pumps. This source is to be located outside the machinery spaces containing the main fire pumps and their source of power and drive units.

16.4.2 The cables to the emergency fire pump are not to pass through the machinery spaces containing the main fire pumps and their source of power and drive units. The cables are to be of a fire resistant type where they pass through other high fire risk areas.

## 16.5 Refrigerated liquid carbon dioxide systems

16.5.1 Where there are electrically driven refrigeration units for carbon dioxide fire-extinguishing systems, one unit is to be supplied by the main source of electrical power and the other unit from the emergency source of electrical power.

16.5.2 Each electrically driven carbon dioxide refrigerating unit is to be arranged for automatic operation in the event of loss of the alternative unit.

## 16.6 Fire safety stops

16.6.1 In order to limit the fire growth potential in every space of the ship, means for controlling the air supply to the spaces and flammable liquids within the spaces are to be provided.

16.6.2 To control air supply, a means of stopping all forced and induced draught fans, and all ventilation fans serving accommodation spaces, service spaces, control stations and machinery spaces from an easily accessible position outside of the space being served is to be provided. The position is not to be readily cut off in the event of a fire in the spaces served by the fans.

16.6.3 In passenger ships carrying more than 36 passengers, a second means of stopping ventilation fans serving accommodation spaces, service spaces and control stations is to be provided at a position as far apart from the position required by 16.6.2 as is practicable. At both positions, the controls are to be grouped so that all fans can be stopped from either of the two positions.

16.6.4 A second means of stopping ventilation fans serving machinery spaces is to be provided at a position as far apart from the position required by 16.6.2 as is practicable. At both positions the controls are to be grouped so that all fans are operable from either of the two positions. The means for stopping machinery space ventilation fans are to be entirely separate from the means for stopping fans serving all other spaces.

16.6.5 In passenger ships, the means of stopping machinery ventilation fans required by 16.6.2 is to be located at the central control station which is to have safe access from the open deck. The central control station is to be provided with ventilation fan OFF status indications together with a means for restarting the ventilation fans.

16.6.6 To control flammable liquids, a means of stopping all fuel oil, lubricating oil, hydraulic oil, cargo oil and thermal oil pumps, oil purifiers from outside the spaces being served is to be provided. The position is not to be cut off in the event of a fire.

16.6.7 Means of cutting off power to the galley, in the event of a fire, is to be provided outside the galley exits, at positions which will not readily be rendered inaccessible by such a fire.

16.6.8 Following activation of any fire safety stops, a manual reset is to be provided in order to restart the associated equipment.

16.6.9 Fire safety stop systems are to be designed on the fail safe principle or alternatively the power supplies to, and the circuits of, the fire safety stop systems are to be continuously monitored and an alarm initiated in the event of a fault. Cables are to be of a fire-resistant type, see 10.5.3. See also 5.2.1.

## 16.7 Fire doors

16.7.1 The electrical power required for the control, indication and alarm circuits of fire doors is to be provided by an emergency source of electrical power as required by 3.2. In passenger ships carrying more than 36 passengers an alternative supply fed from the main source of electrical power, with automatic changeover facilities, is to be provided at the central control station. Failure of any power supply is to operate an audible and visual alarm, see also 1.13 and 1.14.

16.7.2 The control and indication systems for the fire doors are to be designed on the fail-safe principle with the release system having a manual reset.

## 16.8 Fire dampers

16.8.1 The electrical power required for the control and indication circuits of fire dampers is to be supplied from the emergency source of electrical power.

16.8.2 The control and indication systems for the fire dampers are to be designed on the fail-safe principle with the release system having a manual reset.

## 16.9 Fire-extinguishing media release

16.9.1 Where it is required that alarms be provided to warn of the release of a fire-extinguishing medium, and these are electrically-operated, they are to be provided with an emergency source of electrical power, as required by 3.2 or 3.3, and also connected to the main source of electrical power, with automatic changeover facilities located in, or adjacent to, the fire-extinguishing media release panel, see also 1.13. Failure of any power supply is to operate an audible and visual alarm, see also 1.13 and 1.14.

16.9.2 The opening of the fire-extinguishing media control cabinet door, or panel, for any purpose, other than for the release of the fire-extinguishing media, is not to cause the loss of any essential services (see 1.5.1).

## ■ Section 17

### **Crew and passenger emergency safety systems**

#### **17.1 Emergency lighting**

17.1.1 For the purpose of this Section emergency lighting, transitional emergency lighting and supplementary emergency lighting are hereafter referred to under the generic name 'emergency lighting'.

17.1.2 Emergency lighting provided in compliance with Section 3 is to be arranged so that a fire or other casualty in the spaces containing the emergency source of electrical power, associated transforming equipment and the emergency lighting switchboard does not render the main lighting system inoperative.

17.1.3 The level of illumination provided by the emergency lighting is to be adequate to permit safe evacuation in an emergency, having regard to the possible presence of smoke, see 17.4.

17.1.4 The exit(s) from every main compartment occupied by passengers or crew is to be continuously illuminated by an emergency lighting fitting.

17.1.5 Switches are not to be installed in the final sub-circuits to emergency light fittings unless the light fittings are serving normally unmanned spaces (i.e. storage rooms, cold rooms, etc.), or they are normally required to be extinguished for operational reasons (i.e. for night visibility from the navigating bridge). Where switches are fitted they are to be accessible only to ships crew with provision made to ensure that the emergency lighting is energised when such spaces are manned and/or during emergency conditions.

17.1.6 Where emergency lighting fittings are connected to dimmers, provision is to be made, upon the loss of the main lighting, to automatically restore them to their normal level of illumination.

17.1.7 Fittings are to be specially marked to indicate that they form part of the emergency lighting system.

#### **17.2 General emergency alarm system**

17.2.1 An electrically operated bell or klaxon or other equivalent warning system installed in addition to the ship's whistle or siren, for sounding the general emergency alarm signal is to comply with the *International Life-Saving Appliances (LSA) Code* and with the requirements of this Section, see also 1.13 and 1.14.

17.2.2 The general emergency alarm system is to be provided with an emergency source of electrical power as required by 3.2 or 3.3 and also connected to the main source of electrical power with automatic changeover facilities located in, or adjacent to, the main alarm signal distribution panel. Failure of any power supply is to operate an audible and visual alarm, see also 1.13.

17.2.3 The general emergency alarm distribution system is to be so arranged that a fire or casualty in any one main vertical zone, as defined by SOLAS 1974 as amended Reg II-2/A, 3.32, other than the zone in which the public address control station is located, will not interfere with the distribution in any other such zone.

17.2.4 There are to be segregated cable routes to public rooms, alleyways, stairways, and control stations, so arranged that any single electrical fault, localized fire or casualty will not cause the loss of the facility to sound the general emergency alarm in any public rooms, alleyways, stairways, and control stations, be it at a reduced capacity.

17.2.5 Where the special alarm fitted to summon the crew, operated from the navigation bridge, or fire-control station, forms part of the ship's general alarm system, it is to be capable of being sounded independently of the alarm to the passenger spaces.

17.2.6 The sound pressure levels are to be measured during a practical test and documented, see 20.2.

#### **17.3 Public address system**

17.3.1 Public address systems on passenger ships and public address systems used on cargo ships to sound the general emergency alarm or the fire-alarm, are to comply with the *International Life-Saving Appliances (LSA) Code* and the requirements of this Section.

17.3.2 The public address system is to be provided with an emergency source of electrical power as required by 3.2 or 3.3 and also connected to the main source of electrical power with automatic changeover facilities located adjacent to the public address system. Failure of any power supply is to operate an audible and visual alarm, see also 1.13 and 1.14.

17.3.3 The public address system is to have multiple amplifiers having their power supplies so arranged that a single fault will not cause the loss of the facility to broadcast emergency announcements in public rooms, alleyways, stairways and control stations, albeit at a reduced capacity.

17.3.4 The public address distribution system is to be so arranged that a fire or casualty in any one main vertical zone, as defined by SOLAS 1974 as amended Reg II-2/A, 3.32, other than the zone in which the public address control station is located, will not interfere with the distribution in any other such zone.

17.3.5 There are to be at least two cable routes, sufficiently separated throughout their length, to public rooms, alleyways, stairways and control stations so arranged that any single electrical fault, fire or casualty will not cause the loss of the facility to broadcast emergency announcements in any public rooms, alleyways, stairways and control stations, albeit at a reduced capacity.

17.3.6 Amplifiers are to be continuously rated for the maximum power that they are required to deliver into the system for audio and, where alarms are to be sounded through the public address system, for tone signals.

17.3.7 Loudspeakers are to be continuously rated for their proportionate share of amplifier output and protected against short-circuits.

17.3.8 Amplifiers and loudspeakers are to be selected and arranged to prevent feedback and other interference. There are also to be means to automatically override any volume controls, so as to ensure the specified sound pressure levels are met.

17.3.9 Where the public address system is used for sounding the general emergency alarm and the fire-alarm, the following requirements are to be met in addition to those of 17.2:

- (a) The emergency system is given automatic priority over any other system input.
- (b) More than one device is provided for generating the sound signals for the emergency alarms.

17.3.10 Where more than one alarm is to be sounded through the public address system, they are to have recognizably different characteristics and additionally be arranged, so that any single electrical failure which prevents the sounding of any one alarm will not affect the sounding of the remaining alarms.

17.3.11 The sound pressure levels are to be measured during a practical test using speech and, where applicable, tone signals and documented, see 20.2.

## 17.4 Escape route or low location lighting (LLL)

17.4.1 The escape route or low location lighting (LLL) required by SOLAS 1974 as amended Pt D, Ch II-2, Reg. 13, 3.2.5.1, where satisfied by electric illumination, is to comply with the requirements of this sub-Section.

17.4.2 The LLL system is to be provided with an emergency source of electrical power as required by 3.2 and also be connected to the main source of electrical power, with automatic changeover facilities located adjacent to the control panel, see also 1.14.

17.4.3 The power supply arrangements to the LLL are to be arranged so that a single fault or a fire in any one fire zone or deck does not result in loss of the lighting in any other zone or deck. This requirement may be satisfied by the power supply circuit configuration, use of fire-resistant cables complying with 10.5.3, and/or the provision of suitably located power supply units having integral batteries adequately rated to supply the connected LLL for a minimum period of 60 minutes, see 11.3.8.

17.4.4 The performance and installation of lights and lighting assemblies are to comply with ISO standard 15370: *Ships and marine technology - Low location lighting on passenger ships*.

## Section 18 Ship safety systems

### 18.1 Watertight doors

18.1.1 The electrical power required for power-operated sliding watertight doors is to be separate from any other power circuit and supplied from the emergency switchboard either directly or by a dedicated distribution board situated above the bulkhead deck. The associated control, indication and alarm circuits are to be supplied from the emergency switchboard either directly or by a dedicated distribution board situated above the bulkhead deck and for passenger ships be capable of being automatically supplied by the transitional source of emergency electrical power required by 3.2.6 in the event of failure of either the main or emergency source of electrical power.

18.1.2 For passenger ships, where the sources for opening and closing the watertight doors have electric motors, unless an independent temporary source of stored energy is provided, the electric motors are to be capable of being automatically supplied from the transitional source of emergency electrical power.

18.1.3 A single failure in the power operating or control system of power-operated sliding watertight doors is not to result in a closed door opening or prevent the hand operation of any door.

18.1.4 Availability of the power supply is to be continuously monitored at a point in the electrical circuit adjacent to the door operating equipment. Loss of any such power supply is to activate an audible and visual alarm at the central operating console at the navigating bridge.

18.1.5 Electrical power, control, indication and alarm circuits are to be protected against fault in such a way that a failure in one door circuit will not cause a failure in any other door circuit. Short circuits or other faults in the alarm or indicator circuits of a door are not to result in a loss of power operation of the door. Arrangements are to be such that leakage of water into the electrical equipment located below the bulkhead deck will not cause the door to open.

18.1.6 The enclosures of electrical components necessarily situated below the bulkhead deck are to provide suitable protection against the ingress of water with ratings as defined in IEC 60529: *Degrees of protection provided by enclosures (IP Code)* or an acceptable and relevant National Standard, as follows:

- (a) Electrical motors, associated circuits and control components, protected to IPX7 standard.
- (b) Door position indicators and associated circuit components protected to IPX8 standard, where the water pressure testing of the enclosures is to be based on the pressure that may occur at the location of the component during flooding for a period of 36 hours.
- (c) Door movement warning signals, protected to IPX6 standard.



# Electrical Engineering

# Part 6, Chapter 2

Section 18

18.1.7 Watertight door electrical controls including their electric cables are to be kept as close as is practicable to the bulkhead in which the doors are fitted and so arranged that the likelihood of them being involved in any damage which the ship may sustain is minimized.

18.1.8 An audible alarm, distinct from any other alarm in the area, is to sound whenever the door is closed remotely by power and sound for at least five seconds but no more than ten seconds before the door begins to move and is to continue sounding until the door is completely closed. The audible alarm is to be supplemented by an intermittent visual signal at the door in passenger areas and areas where the noise level exceeds 85 dB(A).

18.1.9 Sliding watertight doors on **cargo ships** are to be capable of being remotely closed from the bridge and are also to be operable locally from each side of the bulkhead. Indicators are to be provided at the control position showing whether the doors are open or closed, and an audible alarm is to be provided at the door closure.

18.1.10 On passenger ships, a central operating console is to be fitted on the navigating bridge and is to be provided with a 'master-mode' switch having:

- (a) a 'local control' mode for normal use which is to allow any door to be locally opened and locally closed after use without automatic closure, and;
- (b) a 'doors closed' mode for emergency use which is to allow any door that is opened to be automatically closed whilst still permitting any doors to be locally opened but with automatic reclosure upon release of the local control mechanism.

18.1.11 On passenger ships, the 'master mode' switch is to be arranged to be normally in the 'local control' mode position; be clearly marked as to its emergency function and be Type Approved in accordance with LR's Procedure for Type Approved Products.

18.1.12 On passenger ships, the central operating console at the navigating bridge is to be provided with a diagram showing the location of each door, with visual indicators to show whether each door is open or closed. A red light is to indicate a door is fully open and a green light, a door fully closed. When the door is closed remotely a red light is to indicate the intermediate position by flashing. The indicating circuit is to be independent of the control circuit for each door.

18.1.13 The arrangements are to be such that it is not possible to remotely open any door from the central operating console.

## 18.2 Stern and side shell doors

18.2.1 A notice is to be displayed at the operating panel stating that the door is to be fully closed, secured and locked preferably before, or immediately the ship leaves the berth and that this operation is to be entered in the ship's log.

18.2.2 Control positions are to be provided with a system of warning indicator lights. The system is to provide positive indication that the door is fully closed, secured and locked. The indication arrangements are to be 'fail-safe' such that in the event of a fault the system cannot incorrectly indicate that the doors are fully closed, secured or locked.

18.2.3 The indication system is to be arranged such that it functions independently of any system for door operation, securing and locking.

18.2.4 The electrical power supply for the indication system is to be independent of any electrical power supply for operating, securing and locking the doors.

18.2.5 The indication system is to be fed from two exclusive circuits, one from the main source of electrical power and one from the emergency source of electrical power with automatic changeover facilities located adjacent to the panel. Loss of either active or standby power supply is to initiate an audible and visual alarm on the navigation bridge.

18.2.6 The indicator panel is to be provided with a lamp test function. It is not to be possible to turn off the indication lights at the panel. Dimming facilities may be provided, but the indications are to remain clearly readable under all operating lighting conditions.

18.2.7 Means are to be provided to prevent unauthorized operation of the doors and associated securing and locking devices.

18.2.8 Detection of door position and securing and locking device status is to be by direct sensing of proximity, contact or equivalent, not inferred from actuator positions. Sensors are to be protected against ice formation, mechanical damage and water ingress to be not less than IPX6 standard as defined in IEC 60529, or an acceptable and relevant National Standard.

18.2.9 Where a strongback or equivalent independent secondary means of securing an inwardly opening door is required, these need not be monitored by the indication system providing their correct positioning can be easily observed from the control position.

18.2.10 Doors with a clear opening area of 12 m<sup>2</sup> or greater are to be provided with closing devices operable from a remote control position. Doors which are located partly or totally below the freeboard deck with a clear opening area greater than 6 m<sup>2</sup> are to be provided with an arrangement for remote control from a position above the freeboard deck. This remote control is to provide centralised control for:

- (a) The closing and opening of the doors.
- (b) Associated securing and locking devices.

18.2.11 The location of the remote control panel is to be such that door operation can be easily observed by the operator or by other suitable means such as closed circuit television. Where remote control is required, television surveillance or other such means may satisfy this requirement.

**18.2.12** The additional requirements of 18.2.13 to 18.2.17 apply to doors in the boundaries of special category spaces or ro-ro cargo spaces through which such spaces may be flooded. For cargo ships, where no part of the door is below the uppermost waterline and the area of the door opening is not greater than 6 m<sup>2</sup>, then the requirements of 18.2.13 to 18.2.17 need not be applied.

**18.2.13** An indicator panel is to be located on the navigating bridge, providing separate visual indications of the position of each door and the status of their associated securing/locking devices.

**18.2.14** The indication system is to be provided with a 'harbour/sea voyage' mode selection function, with means of operation located on or adjacent to the navigating bridge indication panel. The selected mode is to be displayed on all indicator panels. An audible alarm is to be initiated on the navigating bridge if the ship leaves the harbour with any door not fully closed or not fully secured. Where practical, the alarm should be initiated immediately the ship leaves the berth. Audible alarms are to be silenced in the 'harbour' mode. Visual indications are to remain operational in either mode.

**18.2.15** An audible and visual alarm is to be given on the navigation bridge in the event of any fault within the indication system.

**18.2.16** An audible and visual alarm is to be initiated on the navigation bridge and the engine control room, or an equivalent attended position, in the event of leakage through the doors.

**18.2.17** For passenger ships, television surveillance arrangements are to be provided to allow leakage through doors below the freeboard deck to be assessed from the navigation bridge and the engine control room, or equivalent attended position.

## 18.3 Bow and inner doors

**18.3.1** Bow doors and inner doors, giving access to vehicle decks, and subdivision doors are to be provided with an arrangement for remote control, from a position above the freeboard deck, providing centralised control for:

- (a) the closing and opening of the doors, and
- (b) associated securing and locking devices.

**18.3.2** The location of the remote control panel is to be such that door operation can be easily observed by the operator or by other suitable means such as closed circuit television. Where remote control is required, television surveillance or other such means may satisfy this requirement.

**18.3.3** A notice is to be displayed at the control position operating panel stating that the bow and inner doors are to be fully closed, secured and locked immediately before the ship leaves the berth and that this operation is to be entered in the ship's log.

**18.3.4** Means are to be provided to prevent unauthorized operation of the doors and associated securing and locking devices.

**18.3.5** An indicator panel is to be located on the navigating bridge and at each control position, providing separate visual indications of the position of bow and inner doors and the status of their associated securing/locking devices.

**18.3.6** The indication arrangements are to be 'fail-safe' such that in the event of a fault the system cannot incorrectly indicate that the doors are fully closed, secured or locked.

**18.3.7** Indicator panels are to be provided with a lamp test function. It is not to be possible to turn off the indication lights at the panel. Dimming facilities may be provided, but the indications are to remain clearly readable under all operating lighting conditions.

**18.3.8** The indication system is to be provided with a 'harbour/sea voyage' mode selection function, arranged such that an audible alarm is to be initiated on the navigating bridge if the ship leaves the harbour with any door not fully closed or not fully secured. Where practical, the alarm should be initiated immediately the ship leaves the berth. Audible alarms are to be silenced in the 'harbour' mode. Visual indications are to remain operational in either mode.

**18.3.9** An audible and visual alarm is to be given on the navigation bridge in the event of any fault within the indication system.

**18.3.10** The indication system is to be arranged such that it functions independently of any system for door operation.

**18.3.11** The electrical power supply for the indication system is to be independent of any electrical power supply for operating, securing and locking the doors.

**18.3.12** The indication system is to be fed from two exclusive circuits, one from the main source of electrical power and one from the emergency source of electrical power with automatic changeover facilities located adjacent to the panel. Loss of either active or standby power supply is to initiate an audible and visual alarm on the navigation bridge.

**18.3.13** Detection of door position and securing and locking device status is to be by direct sensing of proximity, contact or equivalent, not inferred from actuator positions. Sensors are to be protected against ice formation, mechanical damage and water ingress to be not less than IPX6 standard as defined in IEC 60529, or an acceptable and relevant National Standard.

**18.3.14** An audible and visual alarm is to be initiated on the navigation bridge and the engine control room, or equivalent attended position, in the event of leakage through the inner door.

**18.3.15** Television surveillance arrangements are to be provided that allow the extent of leakage to be readily assessed from the navigation bridge and the engine control room, or equivalent attended position, in the event of leakage through the doors. See also Pt 4, Ch 2,10.2.

# Electrical Engineering

## Part 6, Chapter 2

Sections 18, 19 &amp; 20

18.3.16 The electrical power supply for surveillance lighting is to be independent of any electrical power supply for operating, securing and locking the doors.

### 18.4 Subdivision doors on vehicle decks

18.4.1 Where subdivision doors are provided on passenger ship vehicle decks in accordance with Pt 4, Ch 2,9, the control and monitoring arrangements for these doors are to generally comply with 18.3.

### 18.5 Bilge pumps

18.5.1 Where the bilge pumps for the holds of open-top container ships are electrically driven one pump is to be supplied from the emergency switchboard, the remaining pumps are to be supplied from the main source of electrical power, independent of the emergency switchboard.

## Section 19 Lightning conductors

### 19.1 General

19.1.1 In order to minimise the risks of damage to the ship and its electrical installation due to lightning, ships having non-metallic masts or topmasts are to be fitted with lightning conductors in accordance with the applicable requirements of IEC 60092-401 *Electrical installations in ships*. Part 401: Installation and test of completed installation or an alternative and relevant National Standard.

## Section 20 Testing and trials

### 20.1 Testing

20.1.1 Tests in accordance with 20.1.2 to 20.1.4 are to be satisfactorily carried out on all electrical equipment, complete or in sections, at the manufacturer's premises and a test report issued by the manufacturer.

20.1.2 A high voltage at any frequency between 25 and 100Hz is to be applied between:

- (a) all current carrying parts connected together and earth;
- (b) all current carrying parts of opposite polarity or phase.

For rotating machines the value of test voltage is to be 1000 V plus 2 x rated voltage with a minimum of 2000 V, and for other electrical equipment, it is to be in accordance with Table 2.20.1. Items of equipment included in the assembly for which a test voltage lower than the above is specified may be disconnected during the test and tested separately at the appropriate lower test voltage. The test is to be commenced at a voltage of about one-third the test voltage and is to be increased to full value as rapidly as is consistent with its value being indicated by the measuring instrument. The full test

voltage is then to be maintained for 1 minute, and then reduced to one-third full value before switching off. The assembly is considered to have passed the test if no disruptive discharge occurs.

**Table 2.20.1 Test voltage**

Rated voltage, $U_n$ V	Test voltage a.c. (r.m.s.), V
$U_n \leq 60$	500
$60 < U_n \leq 1000$	$2 \times U_n + 1000$
$1000 < U_n \leq 2500$	6500
$2500 < U_n \leq 3500$	10000
$3500 < U_n \leq 7200$	20000
$7200 < U_n \leq 12000$	28000
$12000 < U_n \leq 15000$	38000

20.1.3 When it is desired to make additional high voltage tests on equipment which has already passed its tests, the voltage of such additional tests is to be 80 per cent of the test voltage the equipment has already passed.

20.1.4 Immediately after the high voltage test, the insulation resistance is to be measured using a direct current insulation tester, between:

- (a) all current carrying parts connected together and earth;
- (b) all current carrying parts of different polarity or phase.

The minimum values of test voltage and insulation resistance are given in Table 2.20.2.

**Table 2.20.2 Test voltage and minimum insulation**

Rated voltage $U_n$ V	Minimum voltage of the tests, V	Minimum insulation resistance, MΩ
$U_n \leq 250$	$2 \times U_n$	1
$250 < U_n \leq 1000$	500	1
$1000 < U_n \leq 7200$	1000	$\frac{U_n}{1000} + 1$
$7200 < U_n \leq 15000$	5000	$\frac{U_n}{1000} + 1$

20.1.5 Tests in accordance with the standard with which the equipment complies may be accepted as an alternative to the above.

## 20.2 Trials

20.2.1 Before a new installation, or any alteration or addition to an existing installation, is put into service the applicable trials in 20.2.2 to 20.2.7 are to be carried out. These trials are in addition to any acceptance tests which may have been carried out at the manufacturer's works and are to be to the Surveyor's satisfaction.

20.2.2 The insulation resistance is to be measured of all circuits and electrical equipment, using a direct current insulation tester, between:

- (a) all current carrying parts connected together and earth and, so far as is reasonably practicable;
  - (b) all current carrying parts of different polarity or phase;
- The minimum values of test voltage and insulation resistance are given in Table 2.20.2. The installation may be subdivided and appliances may be disconnected if initial tests produce results less than these figures.

20.2.3 Tests are to be made to verify the effectiveness of:

- (a) earth continuity conductor;
- (b) the earthing of non-current carrying exposed metal parts of electrical equipment and cables not exempted by 1.11.2;
- (c) bonding for the control of static electricity.

20.2.4 It is to be demonstrated that the Rules have been complied with in respect of:

- (a) satisfactory performance of each generator throughout a run at full rated load;
- (b) temperature of joint, connections, circuit-breakers and fuses;
- (c) the operation of engine governors, synchronizing devices, overspeed trips, reverse-current, reverse-power and over-current trips and other safety devices;
- (d) voltage regulation of every generator when full rated load is suddenly thrown off and when starting the largest motor connected to the system;
- (e) satisfactory parallel operation, and kW and KVA load sharing of all generators capable of being operated in parallel at all loads up to normal working load;
- (f) all essential and other important equipment are to be operated under service conditions, though not necessarily at full load or simultaneously, for a sufficient length of time to demonstrate that they are satisfactory;
- (g) propulsion equipment is to be tested under working conditions and operated in the presence of the Surveyors and to their satisfaction. The equipment is to have sufficient power for going astern to secure proper control of the ship in all normal circumstances. In passenger ships the ability of the machinery to reverse the direction of thrust of the propeller in sufficient time, under normal manoeuvring conditions, and so bring the ship to rest from maximum ahead service speed, is to be demonstrated at the sea trial.

20.2.5 Voltage drop is to be measured, where necessary, to verify that this is not in excess of that specified in 1.7.

20.2.6 It is to be demonstrated by practical tests that the Rules have been complied with in respect of fire, crew and passenger emergency and ship safety systems.

20.2.7 On completion of the general emergency alarm system and the public address system tests, the Surveyor is to be provided with two copies of the test schedule, detailing the measured sound pressure levels. Such schedules are to be signed by the Surveyor and the Builder.

## 20.3 High voltage cables

20.3.1 Before a new high voltage cable installation, or an addition to an existing installation, is put into service a voltage withstand test is to be satisfactorily carried out on each completed cable and its accessories. The test is to be carried out after the insulation resistance test required by 20.2.2 and may use either an a.c. voltage at power frequency or a d.c. voltage.

20.3.2 When an a.c. voltage withstand test is carried out, the voltage is to be not less than the normal operating voltage of the cable and it is to be maintained for a minimum of 24 hours.

20.3.3 When a d.c. voltage withstand test is carried out, the voltage is to be not less than:

- (a)  $1,6 (2,5U_o + 2 \text{ kV})$  for cables of rated voltages ( $U_o$ ) up to and including 3,6 kV, or
- (b)  $4,2U_o$  for higher rated voltages

where  $U_o$  is the rated power frequency voltage between conductor and earth or metallic screen, for which the cable is designed.

The test voltage is to be maintained for a minimum of 15 minutes. After completion of the test the conductors are to be connected to earth for a sufficient period in order to remove any trapped electric charge. An insulation resistance test in accordance with 20.2.2 is then to be repeated.

## 20.4 Hazardous areas

20.4.1 All electric equipment located in hazardous areas is to be examined to ensure that it is of a type permitted by the Rules, has been installed in compliance with its certification, and that the integrity of the protection concept has not been impaired.

20.4.2 Alarms and interlocks associated with pressurized equipment and the ventilation of spaces located in hazardous areas are to be tested for correct operation.

## Section 21 Spare gear

### 21.1 General

21.1.1 It is recommended that adequate spares, together with the tools necessary for maintenance, or repair, be carried. The spares are to be determined by the Owner according to the design and intended service. The maintenance of the spares is the responsibility of the Owner.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

## Section 1

### Sections

- 1 **General requirements**
- 2 **Design criteria**
- 3 **Refrigerating machinery and refrigerant storage compartments**
- 4 **Refrigeration plant, pipes, valves and fittings**
- 5 **Refrigerant detection systems**
- 6 **Electrical installation**
- 7 **Instrumentation, control, alarm, safety and monitoring systems**
- 8 **Personnel safety equipment and systems**
- 9 **Refrigerated cargo spaces**
- 10 **Container ships fitted with refrigerating plant to supply cooled air to insulated containers in holds**
- 11 **Acceptance trials**

## ■ Section 1 General requirements

### 1.1 Application

1.1.1 The requirements of this Chapter apply to the refrigerated cargo installations of refrigerated cargo ships, refrigerated container ships, fish factory ships, fishing vessels, fruit juice carriers, and the reliquefaction/refrigerating plant of liquefied gas carriers and chemical carriers or tankers, where an **RMC** notation is requested.

1.1.2 Ships with refrigerated cargo installations which are approved, installed and tested in accordance with these requirements will be eligible for the applicable class notation specified in Pt 1, Ch 2.

1.1.3 The requirements for the classification of ships for the carriage of liquefied gas are given in Lloyd's Register's (hereinafter referred to as 'LR') *Rules for Ships for Liquefied Gases*. Where reliquefaction or refrigeration equipment is fitted for cargo temperature and pressure control, the equipment is to comply with the requirements of Sections 2 to 11, as applicable.

### 1.2 Plans and particulars

1.2.1 The following plans and particulars, as applicable, and any others which may be specially requested for the **refrigerating plant and systems**, are to be submitted in triplicate for approval, before construction is commenced:

- (a) Schematic plans, including full particulars of piping and instrumentations, for:
  - primary and secondary refrigeration systems;
  - air cooler defrosting arrangements;
  - gas reliquefaction systems; and
  - condenser cooling water systems.
- (b) Detailed dimensioned plans and material specifications for:
  - reciprocating compressor crankshaft and crankcase, where exposed to refrigerant pressure;
  - rotary-type compressor rotors and casing;
  - condensers shell and tube and plate type;
  - evaporators shell and tube and plate type;
  - air coolers;
  - arrangement of air cooling pipe grids and construction method;
  - liquid receivers;
  - oil separators; and
  - any other pressure vessels, see Pt 5, Ch 11,6.1.
- (c) General arrangement of refrigerating machinery compartment in elevation and plan, showing location and arrangement of the plant, ventilation details and location of temperature sensors and vapour detectors.
- (d) Details of automatic controls, alarms and safety systems, see Pt 6, Ch 1,1.
- (e) Details of level indicators.
- (f) Where provision is made for the manufacture and/or storage of inert gas in liquid form, details of the storage vessel insulation arrangements and the reliquefaction equipment and piping system are to be submitted.
- (g) Capacity calculations for pressure relief valves and/or bursting discs, and discharge pipe pressure drop calculations, see 4.15.5 to 4.15.21.
- (h) Programme of tests to be conducted on completion of the installation, see Section 11.

1.2.2 The following plans and particulars, as applicable, and any others which may be specially requested for **refrigerated cargo spaces**, are to be submitted in triplicate for approval, before work is commenced:

- (a) Specification of proposed insulation envelope system, including physical, thermal and fire properties.
- (b) General arrangement of insulated refrigerated spaces in elevation and plan.
  - The plans are to be to a scale adequate for the measurement of the external surfaces and the deck and bulkhead edges.
  - Dimensions and spacing of frames, beams and stiffeners, and details of other steel work intruding into the insulation and within the spaces, are to be shown.
  - Oil fuel and liquid cargo tanks adjacent to or below the refrigerated spaces are to be shown, and whether heating arrangements are provided for such tanks are to be indicated.
  - Ventilating and air conditioning trunks, and ducts passing through refrigerated spaces are to be shown.
  - The plans are to include a diagram showing the position of the spaces in relation to other parts of the ship if this is not otherwise apparent.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 1

- (c) Plans showing:
- the thicknesses and methods of attachment of the insulation and linings on all surfaces including girders, hatch coamings and pillars; and
  - details of prefabricated panels and their fixings, vapour barriers, insulated doors and hatch access, bilge and manhole plugs and their frames.
- (d) Methods of attachment of air cooling grids (if fitted) are to be indicated.
- (e) Size and position of refrigerated space pressure equalizing devices, where fitted, see 9.2.12 and 9.2.13.
- (f) Arrangements of the drainage system, and sounding and air pipes that pass through the refrigerated spaces.
- (g) Arrangements of air ducts and distribution systems within the refrigerated spaces (including method of cooling spaces within hatch coamings), and air cooler spaces showing location of the coolers and their fans and drive motors.
- (h) Details of temperature indicating, and recording and sensing equipment, and arrangement of sensors within the refrigerated spaces.

1.2.3 Single copies of the following plans and particulars are to be submitted:

- LR Data Sheet for refrigerated cargo installations (LR Form 3905).
- Specification of proposed refrigerating system and auxiliary equipment, including the refrigerating capacities of the compressors, condensers, evaporators and air coolers.
- Heat load calculations at all design operating conditions justifying the refrigerating capacity which is to be installed.

### 1.3 Materials

1.3.1 Steel plating used in ship construction is to be of an appropriate grade corresponding to the proposed temperature notation, see Pt 3, Ch 2,2.2.

1.3.2 Materials used in the construction of the refrigerating equipment and associated systems are to be generally manufactured and tested in accordance with the requirements of the Rules for Materials (Part 2).

1.3.3 Where it is proposed to use materials other than those specified in Rules for Materials (Part 2), details of the chemical compositions, heat treatment and mechanical properties are to be submitted for approval. In such cases the values of the mechanical properties used for deriving the allowable stress are to be subject to agreement with LR.

1.3.4 All materials used in refrigerating equipment and systems are to be suitable for use with the selected refrigerants. This includes joints, sealing materials and lubricants. For example, the following materials and refrigerants are not to be combined:

- Copper with ammonia.
- Magnesium with fluorinated hydrocarbons.
- Zinc with ammonia or fluorinated hydrocarbons.

1.3.5 For ammonia systems, the condensers/evaporators are to be manufactured in titanium or a suitable grade of stainless steel.

### 1.4 Equipment to be constructed under survey

1.4.1 All major items of equipment are to be surveyed at the manufacturer's works. The workmanship is to be to the Surveyor's satisfaction and the Surveyor is to be satisfied that the components are suitable for the intended purpose and duty. Examples of such units are:

- Crankshafts, crankcases, rotor shafts and casings for all compressors.
- Condensers.
- Evaporators (secondary refrigerant coolers).
- Air coolers.
- Pressure vessels (e.g. liquid receivers, surge drums, suction separators, intercoolers, oil separators).
- Cooling water pumps for condensers.
- Valves and other components intended for installation in pressure piping systems having a maximum working pressure greater than 7 bar.
- Thermal insulating panels (factory made).

### 1.5 Type approved equipment

1.5.1 Where it is proposed to use components (e.g. compressors, condensers, oil separators) which have valid LR Type Approval or General Approval Certificates, the types and model numbers of the components are to be stated. Plans of components that have been so approved need not be re-submitted.

### 1.6 Notation and temperature conditions

1.6.1 The class notation assigned will state the minimum temperature or a temperature range approved by the Committee for the installation with the maximum sea temperature stated, e.g. '✱ Lloyd's RMC to maintain temperature(s) of minus 29°C to plus 14°C with sea temperature plus 32°C maximum'.

1.6.2 For refrigerated installations aboard container ships with approved refrigerating plant and arrangements to supply refrigerated air through ducting to insulated containers, the class notation assigned will additionally specify the maximum number and characteristics of the containers for which the plant is approved, e.g. 'to supply refrigerated air at temperatures of minus 25°C to plus 14°C to 800 certified insulated containers with an average thermal transmittance per container of 27 W/K with sea temperature plus 32°C maximum'.

1.6.3 For reliquefaction or refrigerating plants aboard liquefied gas carriers, the notation assigned will state the minimum cargo temperature for which the installation is approved, unless otherwise qualified, see LR III.3 of the *Rules for Ships for Liquefied Gases*.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 1 & 2

1.6.4 On application from an Owner, consideration will be given by the Committee to an alternative temperature notation being assigned to that appearing in the *Register Book*.

## 1.7 Novel arrangements and design

1.7.1 Where the proposed construction of the refrigerating plant or refrigerated spaces or chambers is novel in design or involves the use of unusual material, special tests may be required, and a suitable class notation may be assigned when the Committee considers this necessary.

## 1.8 Heat balance tests

1.8.1 A heat balance test will be required as prescribed in Section 11 on a classed installation, or one being considered for reclassification, when extensive repairs or alterations have been carried out, or when the Surveyors consider that an amended temperature condition should be assigned.

## 1.9 Controlled atmosphere (CA) systems

1.9.1 Where it is intended to install a CA system on a vessel intended for classification, the requirements of Pt 7, Ch 1 are to be complied with.

1.9.2 Where a **CA** notation is requested by an Owner, it is a prerequisite that the refrigeration installation be assigned an **RMC** notation.

## 1.10 Spare gear and refrigerant charge

1.10.1 It is recommended that adequate spares, together with the tools necessary for maintenance, or repair, be carried. The spares are to be determined by the Owner according to the design and intended service. The maintenance of the spares is the responsibility of the Owner.

1.10.2 For systems complying with 2.5.6 sufficient carbon dioxide is to be carried on board to allow the refrigeration system to be fully recharged. In addition, adequate reserve supplies of refrigerant are to be carried for maintenance purposes. The replacement refrigerant is to be stored in containers complying with 3.3.5

2.1.2 The properties of steel materials used in refrigerated holds are to be suitable for the proposed notation temperature.

## 2.2 Refrigerants and classes of pipes

2.2.1 These Rules are applicable to the primary refrigerants in Table 3.2.1.

2.2.2 Attention is to be given to any statutory requirements, regarding the use of refrigerants, of the National Authority of the country in which the ship is to be registered.

2.2.3 Within the parameters of pressures, temperatures, toxic nature and flammability, the class of pipe to be used with various refrigerants is shown in Table 3.2.1.

2.2.4 Design conditions as applicable to the classes of pipes are defined in Pt 5, Ch 12, 1.5.

2.2.5 The materials of Class I and Class II piping systems are to be manufactured at a works approved by LR and tested in accordance with the appropriate requirements of Rules for Materials. Particular attention is drawn to Ch 6.4 of the Rules for Materials, where testing requirements for pipes used for low temperature service are given.

2.2.6 The materials of Class III piping system are to be manufactured and tested in accordance with the requirements of acceptable National Specifications. The manufacturer's test certificate will be acceptable and is to be provided for each consignment of materials.

2.2.7 Particulars of refrigerating systems using refrigerants other than those listed will be given special consideration.

## 2.3 Refrigeration units

2.3.1 A refrigerating unit is considered to comprise a compressor, its driving motor and one condenser. Where a secondary refrigerant, such as brine, is employed, the unit is also to include an evaporator (secondary refrigerant cooler) and a brine pump.

2.3.2 Two or more compressors driven by a single motor, or having only one condenser or evaporator (secondary refrigerant cooler) are to be regarded as one unit.

2.3.3 The refrigerating units of a classed cargo installation are to be completely independent of any refrigerating machinery associated with air conditioning plant, or any domestic refrigerated installation, or any process plant, unless full details of any proposal have been submitted and approved.

## Section 2 Design criteria

### 2.1 General

2.1.1 The proposed refrigerating plant, insulation and refrigerants are to be suitable for achieving the designed notation temperature. The refrigerating machinery and all components are to operate satisfactorily under the conditions listed in Table 1.3.1 in Pt 5, Ch 1.

## Refrigerated Cargo Installations

## Part 6, Chapter 3

## Section 2

**Table 3.2.1 Primary refrigerants and their class of pipe**

Refrigerant	Type	Composition	Class I	Class of Pipe Class II	Class III
R-717 (Ammonia)	NH <sub>3</sub>	—	✓	—	—
R-22	HCFC	—	—	✓	—
R-290 (Propane)	HC	—	—	✓	—
R-600a (Isobutane)	HC	—	—	✓	—
R-134a	HFC	—	—	—	✓
R-407C	Blend	R-32, R-125, R-134a	—	✓	—
R-410A	Blend	R-32, R-125	—	✓	—
R-507A	Blend	R-125, R-143a	—	✓	—
R-404A	Blend	R-134a, R-125, R-143a	—	✓	—
R-744 (Carbon Dioxide)	CO <sub>2</sub>	—		See 2.5.6	

## NOTES

1. HCFC – Hydrochlorofluorocarbon.
2. HFC – Hydrofluorocarbon.s
3. HC – Hydrocarbon.
4. In view of increasing world-wide restrictive legislation and phasing out of the refrigerant R-22, it is recommended that this refrigerant should not be used in any new installation.
5. Although ozone depleting and global warming potentials are not included in these Rules for Classification, these effects are important and need to be considered when selecting the refrigerant for a particular application.

**2.4 Refrigeration capacity**

2.4.1 The refrigeration capacity provided is to be sufficient to maintain the temperatures specified in the class notation when operating 24 hours per day with one unit on standby. The plant is to be able to cool down a complete cargo to its carrying temperature within the time specified by the manufacturer. The standby unit may be considered as an operating unit during the cooling down period of a non-precooled cargo. In order to compensate for deterioration of machinery and insulation over the life of the installation, the equipment is to be designed to have at least five per cent excess capacity over that required for maximum design output.

2.4.2 The proposals of both machinery and insulating contractors will be evaluated by LR in determining the theoretical capabilities of the equipment to maintain the duty temperatures. LR will advise the contractors after appraisal of the specification and plans if it is considered that additional refrigeration or insulating effect is required, but the temperature assigned on completion of the capacity heat balance test will be determined from the actual results of the test.

2.4.3 Where the units are not connected in common to all refrigerated chambers, the equipment serving each group of chambers is to comply with 2.4.1.

2.4.4 In the case of installations having a large number of small units arranged to serve individual chambers or groups of chambers, the question of standby capacity will be specially considered.

2.4.5 Where only two refrigerating units are fitted, the working parts are to be interchangeable.

2.4.6 Where a refrigerating plant is provided for sub-cooling the liquid refrigerant of other units, but is not arranged for cooling the cargo chambers independently, it will not be regarded as a unit.

**2.5 Design pressures**

2.5.1 The design pressure of the system is to be regarded as equal to its maximum working pressure.

2.5.2 The maximum working pressure is the maximum permissible pressure within the system (or part system) in operation or at rest. No relief valve is to be set to a pressure higher than the maximum working pressure.

2.5.3 The design pressure of the low pressure side of the system is to be the saturated vapour pressure of the refrigerant at plus 46°C. Due regard is to be taken of defrosting arrangements which may cause a higher pressure to be imposed on the low pressure system.

2.5.4 The minimum design pressure of the high pressure side of the system ( $P_{dh}$ ), is to be  $1,11 \times P_b$ , where  $P_b$  is an allowance for the compressor high pressure cut-out.  $P_b$  is to be at least equal to  $1,11 \times P_a$ , where  $P_a$  is the condenser working pressure, when operating in tropical zones and equates to the saturation pressure at 46°C.



# Refrigerated Cargo Installations

## Part 6, Chapter 3

Sections 2 &amp; 3

2.5.5 Design pressures (bar g) applicable to refrigerants are to be not less than the values given in Table 3.2.2 when condensers are sea-water cooled. The design pressure for other refrigerants is to be agreed with LR.

**Table 3.2.2 Pressure limits**

Refrigerant	Pressure (bar g)	
	High	Low
R-717	21,2	17,2
R-22	20,6	16,7
R-290	18,1	14,7
R-600a	6,4	5,2
R-134a	13,4	10,9
R-470C	23,5	19,0
R-410A	34,5	28,0
R-507A	25,3	20,5
R-404A	24,8	20,1
R-744	See 2.5.6	

2.5.6 Due to the low critical temperature of carbon dioxide it is inappropriate to determine the design pressure in accordance with 2.5.3. The proposed design pressure for a carbon dioxide system is to be stated, taking account of the maximum working pressure and the maximum pressure at rest conditions. Where the maximum pressure at rest condition is maintained by the fitting of a supplementary refrigeration unit, condensing the vapour in a holding vessel, supporting calculation is to be provided to show that this can be undertaken with a local ambient temperature of 45°C. The holding vessel is to be thermally insulated to prevent the operation of the relief devices within a 24 hour period after stopping the supplementary refrigeration unit at an ambient temperature of 45°C and an initial pressure equal to the starting pressure of the refrigeration unit.

2.5.7 Where a carbon dioxide system is designed for hot gas defrosting, due regard is to be given to the possibility of a higher pressure being imposed on the low pressure system. The design pressure for this section of the system shall be 10 per cent above the maximum pressure experienced during defrosting.

### 2.6 Insulation

2.6.1 Properties of materials used for thermal insulation are to be verified against known standards for the following parameters, as applicable, to ensure that they are adequate for the intended service. The following test results are to be made available to LR for approval:

- Closed cell content.
- Density.
- Mechanical properties.
- Thermal expansion.
- Abrasion.
- Cohesion.
- Thermal conductivity.

- Resistance to fire and flame spread.
- Ageing.
- Bonding (adhesive and cohesive strength).

2.6.2 Where the *in situ* foam type of insulation is proposed, full details of the process are to be submitted for approval.

2.6.3 Where applicable, having regard to their location and environmental conditions, insulation materials are to be:

- suitably resistant to fire;
- suitably resistant to the spreading of flame;
- adequately protected against penetration of water vapour; and
- adequately protected against mechanical damage.

## Section 3 Refrigerating machinery and refrigerant storage compartments

### 3.1 General

3.1.1 Refrigerating machinery is to be located in a well ventilated compartment. In general, the arrangements are to be such that all components of the refrigerating machinery can be readily opened up for inspection or replacement. Space is to be provided for the withdrawal and renewal of the tubes in 'shell-and-tube' type evaporators (brine coolers) and condensers. Proposals for alternative arrangements are to be submitted for consideration. See 3.2 for refrigerating machinery using ammonia.

3.1.2 Refrigerating machinery using toxic and/or flammable refrigerants is to be located outside the main machinery space in a separate gastight compartment.

3.1.3 Where the refrigerating machinery is located in a separate gastight compartment, outside the main machinery space, this compartment is to be equipped with effective mechanical ventilation to provide 30 air changes per hour based upon the total volume of the space. The mechanical ventilation is to have two main controls, one of which is to be operable from a place outside the compartment.

3.1.4 Refrigerating machinery using non-toxic and non-flammable refrigerants will not, in general, be required to be located in a separate compartment outside the main machinery space.

3.1.5 Openings for pipes, electrical cables and other fittings in the bulkheads and deck are to be fitted with gastight seals.

3.1.6 Ammonia piping is not to pass through accommodation spaces.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 3

### 3.2 Arrangements for compartments housing machinery using ammonia

3.2.1 Where ammonia refrigerant is used, the refrigerating machinery shall be installed in a dedicated gastight compartment. See also 3.2.9.

3.2.2 The compartment containing ammonia refrigerating machinery and any access ways are to be provided with independent mechanical ventilation capable of:

- removing the heat generated by the equipment installed in the compartment;
- maintaining the atmosphere in the compartment at acceptable vapour threshold levels under normal operating conditions; and
- disposing of ammonia vapour safely and quickly in the event of a major leakage.

3.2.3 The ventilation system is to be of the negative pressure type where abnormal stoppages of the extraction fans activate an audible and visual alarm.

3.2.4 Compartments containing ammonia refrigerating machinery, including process vessels, are to be provided with:

- a negative ventilation system, independent of ventilation systems serving other spaces, having a capacity of not less than 30 air changes per hour based upon the total volume of the space. Other suitable arrangements which ensure an equivalent effectiveness may be considered;
- fresh air inlets, located at a low level in the machinery compartment and arranged so as to provide a supply of fresh air and to minimize the possibility of re-cycling the exhaust air from the outlet;
- exhaust outlets, located at a high level and arranged so as to promote good air distribution throughout the compartment;
- a fixed ammonia detector system with alarms inside and outside the compartment;
- water screens above all access doors, operable manually from outside the compartment in all ambient conditions;
- an independent bilge system;
- where the charge is greater than 50 kg, emergency body shower and eye wash facilities shall be installed locally outside the compartment. The water for the shower is to be thermostatically controlled so as to avoid low temperature shock.

3.2.5 Compartments are to have at least two access doors, opening outwards, one of which is to be an emergency exit giving direct access to the open deck. The doors are to be fitted with an easily operated opening mechanism to facilitate rapid escape in an emergency. In the case of small compartments where more than one door would be impractical, the emergency exit only is to be provided.

3.2.6 At least two sets of self-contained breathing apparatus and protective clothing are to be provided, readily available in the vicinity of the compartment but external to the area of risk. See 8.1.4.

3.2.7 The location of the exhaust duct, from the compartment or area, is to be free from obstruction and be such as not to cause danger. Where practicable, they are to be 10 m, in the horizontal direction from other ventilation intakes and openings to accommodation and other enclosed areas, and at least 2 m above the surrounding deck.

3.2.8 Ventilation fans are not to produce a source of vapour ignition in either the ventilated compartment/area or ventilation system. Ventilation fans and fan ducts, in way of fans only, are to be of non-sparking construction.

3.2.9 In the case of ammonia plants on fishing ships under 55 m overall length, or ammonia plants with a charge of ammonia not greater than 25 kg, the refrigerating machinery may be located in the main machinery space provided it complies with the following requirements:

- The entrance to the machinery space is properly illuminated and marked and has warning signs permanently posted.
- The area where the ammonia machinery is installed is served by a hood with a negative ventilation system, so as not to permit any leakage of ammonia dissipating into other areas.
- A water spray system is provided for the area.
- Coamings, of not less than 150 mm in height, are installed around the ammonia machinery area.
- A fixed ammonia detector system with alarms inside and outside the main machinery space is provided.
- Means are provided for stopping the ammonia compressor prime movers from a position outside the machinery space.
- At least two sets of self-contained breathing apparatus and protective clothing are to be provided readily available in the vicinity of the compartment but external to the area of risk. See 8.1.4.
- Air intakes of other machinery are located away from the ammonia machinery area as far as is practicable.

### 3.3 Gas storage compartments

3.3.1 Portable steel cylinders containing reserve supplies of refrigerant are to be stored in a well ventilated compartment reserved solely for this purpose.

3.3.2 The compartment is to be provided with a mechanical ventilation system providing 10 air changes per hour and is to have at least one door opening outwards giving direct access to open deck.

3.3.3 Bulk storage tanks holding more than 150 kg of replacement carbon dioxide are to be located in a separate compartment. The compartment is to be provided with a mechanical ventilation system having a minimum capacity of 6 air changes per hour. The ventilation system exhaust ducting is to remove air from the base of the compartment. The compartment is to be fitted with a gas tight access door opening outward.

3.3.4 The compartment is to be provided with a vapour detection system.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 3 & 4

3.3.5 The compartment is to be provided with suitable water drainage arrangements not connected with the main machinery spaces.

3.3.6 Steel storage cylinders are to be of an approved type, supplied by the refrigerant manufacturer and are to be filled to a level suitable for an ambient temperature of plus 46°C.

3.3.7 The compartment is to be provided with racks to facilitate secure stowage of the cylinders.

## 3.4 Compartments housing carbon dioxide containing equipment

3.4.1 Self closing gas tight access doors are to be provided between each compartment and the dedicated escape routes. See 5.1.5.

3.4.2 In compartments which are normally occupied and where the volume of ventilation required by 3.1.3 is not desirable, such as production areas on fishing vessels, a negative pressure ventilation system, capable of 10 air changes per hour, is required to be fitted. This ventilation system is to be automatically activated when, in the event of a leak the concentration of carbon dioxide reaches a predetermined level but in no case higher than the threshold limit value of 5,000 ppm.

4.1.6 A pressure relief valve and/or safety disc is to be fitted between each compressor and its gas delivery stop valve in accordance with 4.15.5 and 4.15.6.

4.1.7 Stop valves are to be provided on compressor suctions and discharges.

4.1.8 Suction strainers and lubricating oil filters are to be provided and so arranged that they are easily accessible for cleaning or renewal of the filter elements, without substantial loss of refrigerant or lubricating oil.

4.1.9 The correct direction of rotation is to be permanently indicated.

4.1.10 Where any hermetic or semi-hermetic compressor has the electric motor cooled by the circulating refrigerant, the following arrangements are to be provided:

- Refrigeration circuits are to contain no more than one hermetic or semi-hermetic compressor.
- Every compressor motor is to be fitted with a thermal cut-out device to protect the motor against overheating.
- In each refrigeration circuit containing a hermetic or semi-hermetic compressor, suitable arrangements shall be provided to remove debris and contaminants resulting from a motor failure. See 4.16.1.
- The pressure envelope of any hermetic or semi-hermetic compressor exposed to the refrigerant pressure is to be designed and constructed in accordance with the requirements of Pt 5, Ch 11 and Ch 17 as applicable. Plans are to be submitted for consideration as required by Pt 5, Ch 11,1.6.

## Section 4 Refrigeration plant, pipes, valves and fittings

### 4.1 General requirements for refrigerating compressors

4.1.1 New compressor types or developments of existing types are to be subjected to an agreed programme of type testing to complement the design appraisal and review of documentation.

4.1.2 Where it is proposed to treat the bearing surfaces either by local hardening or by chromium plating, then these processes are to be confined to the bearing area and not extended to the fillets. Particulars of the process are to be submitted.

4.1.3 Where ball or roller bearings are incorporated, they are to have a minimum life expectancy of 25 000 running hours, for the application in question.

4.1.4 A check valve is to be fitted to each compressor discharge.

4.1.5 Where off-loading devices are incorporated, arrangements are to be provided which indicate the extent of the off-loading being effected.

### 4.2 Reciprocating compressors

4.2.1 The specified minimum tensile strength of castings and forgings for crankshafts is to be selected within the following general limits:

- Carbon and carbon-manganese steel castings – 400 to 550 N/mm<sup>2</sup>.
- Carbon and carbon-manganese steel forgings (normalized and tempered) – 400 to 600 N/mm<sup>2</sup>.
- Carbon and carbon-manganese steel forgings (quenched and tempered) – not exceeding 700 N/mm<sup>2</sup>.
- Alloy steel castings – not exceeding 700 N/mm<sup>2</sup>.
- Alloy steel forgings – not exceeding 1000 N/mm<sup>2</sup>.
- Spheroidal or nodular graphite iron castings – 370 to 800 N/mm<sup>2</sup>.
- Grey iron castings – not less than 300 N/mm<sup>2</sup>.

4.2.2 Where it is proposed to use materials outside the ranges specified in 4.2.1, details of the chemical composition, heat treatment and mechanical properties are to be submitted for approval.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 4

4.2.3 Materials for components of reciprocating compressors such as crankshafts, pistons, piston rods, crank cases, etc., are to be produced at a works approved by LR and in general to be tested in accordance with the Rules for Materials (Part 2).

4.2.4 A fully documented fatigue strength analysis is to be submitted indicating a factor of safety of 1,5 at the design loads based on a suitable fatigue strength criteria. Alternatively, the requirements of 4.2.5 to 4.2.9 may be used.

4.2.5 The diameter,  $d$ , of a compressor crankshaft using one of the refrigerants detailed in 2.5, is to be not less than that determined by the following formula, when all cranks are located between two main bearings:

$$d = V_c \left( \frac{D^2 p Z}{78,5} \left( \frac{S}{16} + \frac{ab}{a+b} \right) \right)^{1/3} \text{ mm}$$

where

- $a$  = distance between inner edge of one main bearing and the centreline of the crankpin nearest the centre of the span, in mm
- $b$  = distance from the centreline of the same crankpin to the inner edge of the adjacent main bearing, in mm
- $a + b$  = span between inner edges of main bearings, in mm
- $d_p$  = proposed minimum diameter of crankshaft, in mm
- $p$  = design pressure, in bar g, as defined in 2.5
- $D$  = diameter of cylinder, in mm
- $S$  = length of stroke, in mm
- $V_c$  = 1,0 for shafts having one cylinder per crank, or
 

$\left. \begin{array}{l} = 1,05 \text{ for } 90^\circ \\ = 1,18 \text{ for } 60^\circ \\ = 1,25 \text{ for } 45^\circ \end{array} \right\}$	between adjacent cylinders on the same crankpin
---	---

 for the shaft and cylinder arrangements as detailed in Table 3.4.1

$$Z = \frac{560}{\sigma_u + 160} \text{ for steel}$$

$$Z = \frac{700}{\sigma_u + 260 - 0,059d_p} \text{ for spheroidal or nodular graphite cast iron}$$

$$Z = \frac{700}{\sigma_u + 260 - 0,069d_p} \text{ for grey cast iron}$$

$\sigma_u$  = specified minimum tensile strength of crankshaft material, in N/mm<sup>2</sup>.

**Table 3.4.1 Angle between cylinders**

Number of crankpins	Number of cylinders per crank	Angle between cylinders, in degrees		
1 or 2	2	45	60	90
3	2	45	60	—
4	2	45	60	—
1	3	45	60	90
2	3	45	60	—
3	3	45	—	—
1	4	45	60	—
2	4	45	—	—

4.2.6 Where the shaft is supported additionally by a centre bearing, the diameter is to be evaluated from the half shaft between the inner edges of the centre and outer main bearings. The diameter so found for the half shaft is to be increased by six per cent for the full length shaft diameter.

4.2.7 The dimensions of crankwebs are to be such that  $Bt^2$  is to be not less than given by the following formulae:

0,4 $d^3$ , for the web adjacent to the bearing

0,75 $d^3$ , for intermediate webs

where

$B$  = breadth of web, in mm

$d$  = minimum diameter of crankshaft as required by 4.2.5, in mm

$t$  = axial thickness of web which is to be not less than 0,45 $d$  for the web adjacent to the bearing, or 0,60 $d$  for intermediate webs, in mm.

4.2.8 Fillets at the junction of crankwebs with crankpins or journals are to be machined to a radius not less than 0,05 $d$ . Smaller fillets, but of a radius not less than 0,025 $d$ , may be used provided the diameter of the crankpin or journal is not less than  $cd$ ,

where

$$c = 1,1 - 2 \frac{r}{d} \text{ but to be taken as not less than } 1,0$$

$d$  = minimum diameter of crankshaft as required by 4.2.5, in mm

$r$  = fillet radius, in mm.

4.2.9 Fillets and oil holes are to be rounded to an even contour and smooth finish.

4.2.10 An oil level sight glass is to be fitted to the crankcase.

4.2.11 Compressors with cylinder bores in excess of 50 mm diameter are to be provided with arrangements to relieve high cylinder pressures such as would result from 'hydraulic lock' (i.e. liquid refrigerant in the cylinders). Alternatively the provision of positive means to prevent liquid refrigerant reaching the compressor may be accepted.

4.2.12 The crankcases of trunk piston compressors are to be designed to withstand a pressure equal to the maximum working pressure of the system. The crankcases of compressors of the crosshead type which are substantially isolated from the refrigerant circuit may be designed for lower pressures but are to be provided with relief valves adjusted to lift at a pressure not exceeding the design pressure, and discharging to a safe place.

4.2.13 A crankcase heater, arranged to be energized when the compressor is stopped, is to be provided.

### 4.3 Screw compressors

4.3.1 For screw-type compressors, the materials of the rotors and casings are to be produced, and the manufacture is to be carried out, at a works approved by LR, and in general, they are to be tested in accordance with the Rules for general machinery forgings.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 4

4.3.2 The rotor casing is to be designed for the maximum pressure to which it may be subjected, see 2.5.

4.3.3 Where gearing is fitted to increase the rotor speed and also to locate the rotors, the gearing is to comply with Pt 5, Ch 5. The manufacturer's maximum allowable tolerances for clearances and backlash between mating rotors are to be stated.

### 4.4 Pressure vessels and heat exchangers

4.4.1 The term 'pressure vessel' will normally apply to receivers and heat exchangers, and does not include any of the following:

- Compressors.
- Liquid refrigerant pumps.
- Pipes and their fittings.

The use of plate heat exchangers will be specially considered on submission of plans, and special tests may be required.

4.4.2 Fusion welded steel pressure vessels exposed to the pressure of the refrigerants are to be constructed in accordance with the requirements of Pt 5, Ch 11 and Ch 17. Plans are to be submitted for consideration if required by Pt 5, Ch 11,1.6.

4.4.3 Where ammonia is the refrigerant, the pressure vessels are to be constructed to at least Class 2/1 requirements.

4.4.4 Pressure vessels for the containment of primary refrigerants for use in conventional refrigeration circuits where the pressure/saturation temperature relationship applies are not required to be low temperature impact tested unless the design temperature is lower than minus 40°C.

4.4.5 Pressure vessels are to be thermally insulated to an extent which will minimize condensation of moisture from the surrounding atmosphere. The insulation is to be provided with an efficient vapour barrier and adequately protected from mechanical damage. Prior to applying the insulation, the steel surfaces are to be suitably protected against corrosion.

4.4.6 Each pressure vessel which may contain liquid refrigerant and which is capable of being isolated is to be protected with overpressure relief devices, see 4.15.

### 4.5 Condensers, oil coolers and evaporators

4.5.1 In order to minimize the risk of corrosion, where the refrigerant is ammonia, the material interface between the primary refrigerant and cooling water or secondary refrigerant is to be of a suitable grade of stainless steel. Carbon-manganese steel with a suitable inhibitor would also be acceptable.

4.5.2 Space is to be provided for the withdrawal and replacement of condenser and evaporator tubes, see 3.1.1.

4.5.3 Where ammonia is used as the refrigerant, the refrigerating plant is to comply with the following additional requirements:

- (a) Automatic air purgers are to be provided, with their discharges being led through water before venting to atmosphere.
- (b) The cooling water returns from sea-water cooled condensers are not to be led into the main machinery spaces.
- (c) Fresh water condenser cooling systems are to be provided with pH meters to activate audible and visual alarms in the event of an ammonia leak.

### 4.6 Liquid receivers

4.6.1 Primary refrigerating systems are to be provided with liquid receivers with sufficient capacity to hold the complete refrigerant charge to prevent emission of the refrigerant to the atmosphere during servicing or repairs.

4.6.2 Alternatively, in systems using a secondary refrigerant, with a number of units, smaller receivers may be used provided the system includes a common storage receiver with sufficient capacity to hold at least the primary refrigerant charge from two units. The common receiver is to be provided with the necessary crossover connections to facilitate transfer of refrigerant to and from each unit in the system.

### 4.7 Oil separators

4.7.1 Oil separators are to be provided at compressor discharges and are to be fitted with a control arrangement to enable the separated oil to be returned to the compressor crankcase. Wire gauze used in separators is to be sufficiently robust and well supported.

### 4.8 Air coolers and cooling grids

4.8.1 Refrigerated spaces may be cooled by air coolers or cooling grids on the ceiling, bulkheads and sides. In order to minimize the dehydration of the cargo and the frosting of the air coolers or cooling grids, the installation is to be designed to maintain the required notation temperatures with a minimum of difference between the refrigerant and space temperatures.

4.8.2 Individual spaces are to have a minimum of two independent air coolers, each comprising one or more fans and one or more refrigerant circuits in a single casing and with isolating valves. Alternatively, multiple circuits each with their own fan(s), in a single cooler casing may each be regarded as a separate cooler, provided stop valves are fitted so that each circuit may be isolated.

4.8.3 For refrigerated spaces having a net volume of 300 m<sup>3</sup> or less, a single cooler with one circuit will be accepted.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Section 4

4.8.4 The refrigeration capacity of the air cooler arrangement is to be such that the notation temperature conditions can be maintained with any one independent cooler or circuit out of action. The capacities of the fans are also to be such that they can maintain the required air flow rates (see also 9.4) and uniform air temperature throughout the refrigerated spaces, when part or fully loaded with cargo, with any one cooler or fan out of action.

4.8.5 Air cooler fan motors are to be suitably enclosed to withstand the effects of moisture.

4.8.6 Means are to be provided for effectively defrosting air coolers. Air coolers are to be provided with trays of suitable depth arranged to collect all condensate. The trays are to be provided with drains at their lowest points to enable the condensate to be drained away when the refrigerated spaces are in service. Provision is to be made for the prevention of freezing of the condensate.

4.8.7 Air coolers are to be located such that when the refrigerated spaces are loaded with cargo, adequate space is provided for the inspection, servicing and renewal of controls, valves, fans and fan motors.

4.8.8 The cooling grids in each refrigerated space are to be arranged in not less than two sections, and each section is to be fitted with valves so that it can be shut off. The notation temperature conditions are to be capable of being maintained with any one section isolated. For spaces having a net volume of 300 m<sup>3</sup> or less, a single section will be acceptable.

4.8.9 Steel air cooler circuits and cooling grids are to be suitably protected against external corrosion.

## 4.9 Refrigerant pumps

4.9.1 Pumped primary and/or secondary refrigerant systems are to have a minimum of two pumps. Each pump is to be capable of operating on all cargo chambers and maintaining full duty with any one pump out of operation.

4.9.2 Primary and, where appropriate, secondary refrigerant pumps are to be provided with pressure relief valves, see 4.15.13.

## 4.10 Condenser cooling water pumps

4.10.1 At least two separate condenser cooling water pumps are to be installed. One of the pumps may be considered as a standby pump and may be used for other purposes, provided that it is of adequate capacity and its use on other services does not interfere with the supply of cooling water to the condensers.

4.10.2 Not less than two sea inlets are to be provided supplying sea-water to the pumps for condenser cooling. It is recommended that one of the sea inlets be provided on the port side and the other on the starboard side. The sea inlets are to be fitted in accordance with Pt 5, Ch 13,2.6.

4.10.3 The cooling water pumps and sea inlets are to be suitably valved and cross-connected with each condenser.

4.10.4 Suitable spring-loaded safety valves are to be provided in each cooling water circuit, see 4.15.13.

## 4.11 Piping systems

4.11.1 All piping, valves and fittings are to be suitable for the maximum pressure to which the system can be subjected and are to comply with the requirements of Pt 5, Ch 12.

4.11.2 Pipework for ammonia (R-717) is to comply with Class I requirements.

4.11.3 In addition to visual examination of pipe welds, non-destructive examination of pipe welds is to be carried out in accordance with the requirements of Pt 5, Ch 17,10.2, to the satisfaction of the Surveyors.

4.11.4 All steel pipework on the low temperature part of the system is to be protected against external corrosion. Protective coatings are to be removed from pipe surfaces to a distance of not less than 50 mm either side of the joint weld preparations prior to welding. On completion of welding and testing a protective coating is to be applied.

4.11.5 Where brine is the secondary refrigerant, piping and tanks should not be galvanized on the brine side. If any parts of the brine system have been galvanized, the brine cooling and return tanks are to be provided with a ventilating pipe or pipes led to the atmosphere in a location where no damage will arise from the gas discharged. The ventilation pipes are to be fitted with wire gauze diaphragms which can be readily renewed.

4.11.6 Copper piping is to be manufactured in accordance with Pt 5, Ch 12,3 except in the case of small air coolers having finned pipes of sizes not greater than 19 mm outside diameter, and which have been fabricated under workshop conditions. The finned pipes may have a minimum wall thickness of 0,5 mm when used with R-22 and R-134a refrigerants.

4.11.7 Where the use of plastics pipe is proposed in a secondary refrigerant system (e.g. brine), it is to be in accordance with Pt 5, Ch 12,5.

4.11.8 Pipelines are to have ample provision for expansion and contraction in service conditions. In general, expansion bends are to be used for this purpose. However, the use of metallic expansion bellows will be accepted provided test data is produced showing satisfactory strength and fatigue properties under the appropriate conditions.

4.11.9 All pipelines are to be fully supported and secured so as to prevent vibration. Flexible hoses may be used, where necessary, to prevent transmission of vibration provided the documentation in 4.11.8 is provided. Flexible hoses are to be of a type which has been approved by LR, see Pt 5, Ch 12,6.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

## Section 4

4.11.10 Pipework, which may contain low temperature refrigerant, except within secondary refrigerant cooler rooms, is to be thermally insulated to an extent which will minimize condensation of moisture. Insulation in pre-formed sections is recommended. If *in situ* foamed insulation is employed, pre-production testing on site is to be carried out to the satisfaction of the Surveyor, using a 'mock-up' representative of the system to be employed.

4.11.11 All pipe insulation is to be provided with an efficient vapour barrier, care being taken to ensure that it is not interrupted in way of supports, valves, etc. Also adequate protection of insulation surfaces from mechanical damage is to be provided.

4.11.12 Where refrigerating piping is embedded in the cargo chamber insulation, the locations of the pipe joints are to be marked on the outside of the insulation lining.

### 4.12 Joints

4.12.1 Butt welded pipe joints are to be employed as far as practicable. Socket welded pipe joints are acceptable up to 25 mm diameter. Flanged or other joints are to be kept to a minimum and, in general, are to be restricted to connections with items of machinery or components which may have to be removed for maintenance purposes. Connections to valves are normally to be welded unless they are of a type, or in a position, which precludes *in situ* maintenance.

4.12.2 Pipe connections to fittings (e.g. gauge lines, level controls) which are likely to be subjected to heavy corrosion, are to be of heavy gauge construction, or be made from suitable corrosion resistant materials.

### 4.13 Liquid level indicators

4.13.1 Where liquid level indicators of the 'see-through' variety are used they are to be of the flat plate type incorporating glass (or equivalent material) of heat resistant grade.

4.13.2 All level indicators are to be provided with automatic shut-off devices and isolating valves. Plate-type sight glasses which form an integral part of the component in which they are mounted (e.g. compressor crankcases, pressure vessels) are exempt from this requirement.

4.13.3 All level indicators are to be suitable for the system maximum working pressure and tested accordingly.

### 4.14 Automatic expansion valves

4.14.1 Refrigerating systems with automatic expansion valves are also to be provided with efficient hand expansion valves and the arrangement is to be such that the automatic expansion valves can be by-passed and isolated.

4.14.2 As an alternative, duplicate automatic expansion valves may be fitted, each valve to be capable of the required duty and operable with the other out of action.

### 4.15 Overpressure protection devices

4.15.1 Refrigeration systems are to be provided with relief devices, but it is important to avoid circumstances which would bring about an inadvertent discharge of refrigerant to the atmosphere. The system is to be so designed that pressure due to fire conditions will be safely relieved.

4.15.2 Pressure relief devices are to be mounted in such a way that it is not possible to isolate them from the part of the system which they are protecting except that, where duplicated, a changeover valve may be fitted which will allow either device to be isolated for maintenance purposes without it being possible to shut off the other device at the same time.

4.15.3 Relief discharge is to be led to a safe place above deck away from personnel accesses and air intakes. Discharge piping should be designed to preclude ingress of water, dirt or debris which may cause the equipment to malfunction.

4.15.4 For ammonia systems, discharge from relief valves is to be led through water before venting to the atmosphere. Vapour detectors are to be provided in the discharge pipes to activate audible and visual alarms in the event of a leakage of ammonia.

4.15.5 A pressure relief valve and/or bursting disc is to be fitted between each positive displacement compressor and its gas delivery stop valve, the discharge being led to the suction side of the compressor. The flow capacity of the valve or disc is to exceed the full load compressor capacity on the particular refrigerant at the maximum potential suction pressure. For these internal relief valves, servo-operated valves will be accepted. Where the motive power for the compressor does not exceed 10 kW, the pressure relief valve and/or bursting disc may be omitted.

4.15.6 Compressors protected by bursting discs are to be provided with automatic shutdown in the event of high discharge temperatures.

4.15.7 Each compressor is to be provided with automatic shutdown in the event of high discharge pressure. For refrigeration systems where the maximum working pressure is less than or equal to 40 bar g the automatic shutdown is to operate at a pressure in excess of normal operating pressure but no greater than 0,9 of the maximum working pressure. For refrigeration systems where the maximum working pressure is greater than 40 bar g the automatic shutdown is to operate at a pressure in excess of normal operating pressure but no greater than 0,95 of the maximum working pressure.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

### Section 4

4.15.8 Each pressure vessel which may contain liquid refrigerant and which is capable of being isolated by means of stop or automatic control or check valves is to be protected by two pressure relief valves or two bursting discs, or one of each, controlled by a changeover device.

4.15.9 Pressure vessels which are interconnected by pipework without valves, so that they cannot be isolated from each other, may be regarded as a single pressure vessel for this purpose, provided that the interconnecting pipework does not prevent effective venting of any vessel.

4.15.10 Omission of one of the specified relief devices and the changeover device, as required by 4.15.8, will be allowed where:

- vessels are of less than 300 litres internal gross volume; or
- vessels discharge into the low pressure side by means of a relief valve.; or
- vessels operating using only cargo gas and, which can be independently isolated and gas freed during normal cargo operations provided that a shelf spare is carried.

4.15.11 Sections of systems and components which could become full of liquid between closed valves are to be provided with pressure relief devices relieving to a suitable point in the refrigerant circuit.

4.15.12 Refrigerant pumps are to be provided with pressure relief valves on the discharge side, which may relieve to the suction side, or to another suitable location.

4.15.13 Suitable spring-loaded safety valves are to be provided on the cooling liquid side of condensers and the brine side of evaporators where the pressure from any pump or expansion of the liquid in the circuit could exceed the design pressure of the system or any component forming part of the cooling system.

4.15.14 Relief valves are to be adjusted and bursting discs so selected that they relieve at a pressure not greater than the design pressure of the system, as defined in 2.5.

4.15.15 When satisfactorily adjusted, relief valves are to be protected against tampering or interference by a wire with a lead seal or similar arrangement.

4.15.16 Valves which are arranged to discharge to the low pressure side of the system are to be substantially independent of back pressure and are to be of a type which has been approved by LR.

4.15.17 The minimum required discharge capacity related to air of the pressure relief device for each pressure vessel is to be determined as follows:

$$C = D L f$$

where

- $C$  = minimum required discharge capacity related to air of each relief device, in kg/s
- $D$  = outside diameter of the vessel, in metres
- $L$  = length of the vessel, in metres

$f$  = factor which is dependent on the refrigerant:

R-717 (Ammonia)	0,041
R-22, R-134a, R-407C	0,131
R290 (Propane), R-600a (Isobutane)	0,082
R-410A, R-404A, R-507A	0,203
R-744 (Carbon dioxide)	
(when used on the low side of a cascade system)	0,082

4.15.18 The rated discharge capacity of the pressure relief valves expressed in kg/s of air may also be determined in accordance with an appropriate recognised National or International Standard such as *ISO 5149 Mechanical Refrigeration Systems used for Cooling and Heating – Safety Requirements*.

4.15.19 The rated discharge capacity of a bursting disc discharging to atmosphere under critical flow conditions is to be determined by the following formula:

$$d = 857,5 \sqrt{\frac{C}{P}} \text{ mm}$$

where

- $d$  = minimum diameter of free aperture of bursting disc, in mm
- $C$  = minimum required air equivalent discharge capacity, in kg/s, see 4.15.17
- $P$  = 1,1 x maximum working pressure, see 2.5.

4.15.20 The bore of the discharge pipe shall be at least the same bore as the relieving device outlet. The size of a common discharge line serving two or more pressure relieving devices which may discharge simultaneously shall be based on the sum of their outlet areas. Where discharge lines are long or where the outlets of two or more pressure relieving devices are connected into a common line, the discharge piping shall be sized such that the back pressure at full relief rate does not exceed 10 per cent of the relief valve set pressure.

4.15.21 Due account is to be taken of the reaction force on a relief valve or on discharge piping during discharge and adequate support provided.

4.15.22 As carbon dioxide can form a solid powder at atmospheric pressure, there is a possibility that relief devices will choke if vented directly to atmosphere. The method used to guard against the formation of powder is to be submitted for consideration.

4.15.23 In carbon dioxide systems, overpressure protection is to be fitted to pipelines or components which can be isolated in a liquid full condition. Pressure relief devices are to be arranged such as to vent vapour at all times.

4.15.24 In cascade systems where carbon dioxide is used in combination with ammonia, the effects of carbon dioxide leaking into the ammonia side are to be considered. It may be desirable to design the ammonia system to either withstand the design pressure on the carbon dioxide side or have relief arrangements to safely deal with the additional vapour produced if a leak occurs.



# Refrigerated Cargo Installations

## Part 6, Chapter 3

### Section 4

#### 4.16 Filters, driers and moisture indicators

4.16.1 Suitable filters are to be provided in the refrigerant gas lines to compressors and in the liquid lines to refrigerant flow controls. Wire gauze used in filters is to be sufficiently robust and well-supported. A filter may be combined with the oil separator required by 4.7.1. Stop valves are to be provided to allow for servicing of filters. After first commissioning of the system, the filters should be examined to confirm that elements remain intact and not collapsed.

4.16.2 Refrigerant filters, driers and moisture indicators are to be fitted in halocarbon refrigerant systems, and the arrangement is to be such that filters and driers can be bypassed, isolated and opened up without interrupting plant operations.

#### 4.17 Purging devices

4.17.1 Where the operating pressure of the low pressure system may be below atmospheric, a purging device is to be provided, the discharge from which is to be led to a safe place above deck.

#### 4.18 Piping in way of refrigerated spaces

4.18.1 All sounding pipes, whether for compartments or tanks, which pass through refrigerated spaces or the insulation thereof, in which the temperatures contemplated are 0°C or below, are to be not less than 65 mm bore. The pipework is to be in accordance with the requirements of Pt 5, Ch 12 and Pt 5, Ch 13,2.9.

4.18.2 Sounding pipes to oil compartments are not to terminate within refrigerated spaces or in their air cooler spaces, nor are these pipes to terminate in enclosed spaces from which access is provided to refrigerated spaces or their air cooler spaces.

4.18.3 All pipes, including scupper pipes, air pipes and sounding pipes that pass through refrigerated spaces are to be insulated.

4.18.4 Where the pipes referred to in 4.18.3 pass through chambers intended for temperatures of 0°C or below, they are also to be insulated from the steel structure, except in positions where the temperature of the structure is mainly controlled by the external temperature and will normally be above freezing point. Pipes passing through a deck plate within the ship side insulation, where the deck is fully insulated below and has an insulation ribband on top, are to be attached to the deck plating. In the case of pipes adjacent to the shell plating, metallic contact between the pipes and the shell plating or frames is to be avoided so far as practicable.

4.18.5 The air refreshing pipes to and from refrigerated spaces need not, however, be insulated from the steelwork.

#### 4.19 Drainage from refrigerated spaces

4.19.1 Provision is to be made for the continuous drainage of the inside of all refrigerated spaces and cooler trays. The pipework is to be in accordance with the requirements of Pt 5, Ch 12 and Pt 5, Ch 13,3.2.

4.19.2 All drain pipes from the refrigerated spaces and cooler trays are to be fitted with liquid sealed traps, which are to be of adequate depth and readily accessible for cleaning and refilling with brine. The pipes from lower spaces situated on the tank tops are also to be fitted with bilge non-return valves.

4.19.3 Where drains from separate refrigerated spaces join a common main, the branch pipes are each to be provided with a liquid sealed trap.

4.19.4 Sluices, scuppers or drain pipes which would permit drainage from compartments outside the refrigerated spaces into the bilges of the latter, are not to be fitted.

4.19.5 Screwed plugs or other means for blanking off scuppers, draining chambers and cooler trays are not to be fitted. If, however, it is specially desired to provide means for temporarily closing these scuppers, they may be fitted with shut-off valves.

#### 4.20 Corrosion protection of metal fixtures

4.20.1 All steel bolts, nuts, hangers, brackets and fixtures which support or secure cooling appliances, piping insulation, meat rails, linings and prefabricated insulated panels, etc., are to be suitably protected against corrosion.

#### 4.21 Pressure testing at manufacturers' works

4.21.1 Components intended for use with a primary refrigerant are to be subject to strength and leak pressure tests as detailed in Table 3.4.2.

**Table 3.4.2 Test pressure**

Component	Test pressure, bar g	
	Strength test	Leakage test
1. Pressure vessels	See Pt 5, Ch 11	1,0p
2. Compressor cylinders/ crankcase/casing	1,5p	1,0p
3. Valves and fittings	2,0p	1,0p
4. Pressure piping, fabricated headers, air coolers, etc.	1,5p	1,0p
NOTE p is the design pressure as defined in 2.5.		

4.21.2 Component strength pressure tests are to be hydraulic or where suitable safety measures are taken, may be pneumatic. The latter is to be carried out with a suitable dry inert gas.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 4, 5 &amp; 6

4.21.3 Component leakage pressure tests are to be carried out only after completion of satisfactory strength pressure tests. Pneumatic pressure is to be applied using a suitable dry inert gas.

4.21.4 Components for use with a secondary refrigerant or cooling water are to be hydraulically tested to 1,5 times the design pressure, but in no case less than 3,5 bar g.

## 4.22 Pressure test after installation on board ship

4.22.1 For primary refrigerant piping welded in place, strength pressure tests of the welds are to be carried out at a test pressure of 1,5*p*. This will normally take the form of a pneumatic test since hydraulic testing media such as water are not acceptable due to their incompatibility with the primary refrigerants and the difficulty of removing all traces from a completed system.

4.22.2 Pneumatic pressure tests are to be carried out using a suitable inert gas. All pneumatic tests are potentially dangerous and due precautions are to be observed.

4.22.3 Where pneumatic tests are prohibited by relevant authorities, the tests required by 4.22.2 may be omitted provided non-destructive tests by ultrasonic or radiographic methods are carried out with satisfactory results on the entire circumference of all butt welds not tested in accordance with 4.11.3. Where ultrasonic tests have been carried out, the manufacturer is to provide the Surveyor with a signed statement confirming that ultrasonic examination has been carried out by an approved operator and that there were no indications of defects which could be expected to have a prejudicial effect on the service performance of the piping.

4.22.4 After completion of the test required by 4.22.1, 4.22.2 or 4.22.3, a leak pressure test is to be carried out using a suitable inert gas at a pressure equal to the design pressure, in the presence of the Surveyor.

4.22.5 Secondary refrigerant piping welded in place is to be hydraulically tested to 1,5 times the design pressure, but in no case less than 3,5 bar g.

5.1.3 Detection equipment is to be so designed that it may be readily tested and calibrated, and failure of the equipment is to initiate an alarm.

5.1.4 The location of the detectors is to be determined relative to the layouts of the individual compartments and machinery spaces and are to be indicated on the plan submission.

5.1.5 For carbon dioxide systems, spaces such as machinery rooms, storage compartments, production areas on fishing vessels and valve stations, where leakage may occur, are to be fitted with detectors. Welded pipelines passing through passageways or access ducts are not considered possible leakage areas.

5.1.6 Audible and visual alarms are to be activated, located both inside and outside the affected space. The alarms are to be readily identifiable and be visible and audible in all locations within the space housing the refrigeration equipment.

## 5.2 Ammonia vapour detection and alarm equipment

5.2.1 A fixed detector system for ammonia is to comply with the requirements contained in 5.1.2.

5.2.2 The location of the detectors is to be determined relative to the layouts of the individual spaces and are to be indicated on the plan submission required by 1.2.

5.2.3 Ammonia vapour detectors are to be provided in the refrigeration machinery compartment, associated access ways, the exhaust ducts, the ammonia store room and the discharge pipes from pressure relief valves.

5.2.4 Sufficient detectors are to be provided to monitor the total areas of the above spaces.

5.2.5 For vapour detection in relief valve discharge pipes, see 4.15.4.

5.2.6 Details of the refrigerant detector set points and operational philosophy are to be submitted for consideration.

## Section 5

### Refrigerant detection systems

#### 5.1 General

5.1.1 A fixed refrigerant detection system is to be provided in the refrigerating machinery compartment or space, the discharge pipes from pressure relief valves, ventilation outlet ducts, and the cargo chambers, where appropriate.

5.1.2 The alarm system is to comply with the requirements of Chapter 1 and, as a minimum requirement, the system is to activate at a low-level concentration to give warning of refrigerant leaks, and a high-level concentration corresponding to the refrigerant's safe occupational level.

## Section 6

### Electrical installation

#### 6.1 General

6.1.1 Where the refrigerating machinery is to be electrically driven, the requirements of Ch 2,2 are to be complied with, as applicable.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 6 & 7

6.1.2 The generating capacity available for the refrigerated installation is to be sufficient to supply power to the installation during cooling down of a complete cargo to, and maintenance of, the notation temperature conditions in all refrigerated spaces at the Rule maximum ambient and sea-water temperatures.

6.1.3 Electrical equipment is not to be installed in spaces in which ammonia refrigerant is used or stored unless it is essential for operational purposes. Where electrical equipment is installed in such spaces the requirements of 6.2 are to be complied with.

## 6.2 Electrical equipment for use in explosive gas atmospheres

6.2.1 Lighting fittings are to be of a certified safe-type and be arranged on at least two independent final branch circuits. Switches and protective devices are to interrupt all lines or phases and are to be located outside the space.

6.2.2 Where electric motors driving ventilation fans are located within the spaces, within ventilation ducts, or within three metres of ventilation openings, they are to be of a certified safe-type.

6.2.3 Monitoring control and alarm systems which are required to operate under conditions of ammonia leakage are to be of a certified safe-type.

6.2.4 Electrical equipment which is not of a certified safe-type is to de-energize automatically if the ammonia concentration within the space exceeds 1,0 per cent by volume.

## Section 7 Instrumentation, control, alarm, safety and monitoring systems

### 7.1 Instrumentation

7.1.1 All compressors are to be provided with the following instrumentation and automatic shutdowns:

- Indication of suction pressure (saturated temperature), including intermediate stage, when applicable.
- Indication of discharge pressure (saturated temperature), including intermediate stage, when applicable.
- Indication of lubricating oil pressure.
- Indication of cumulative running hours (screw compressors).
- Automatic shutdown in the event of low lubricating oil pressure.
- Automatic shutdown in the event of high discharge pressure, see also 4.15.7.
- Automatic shutdown in the event of low suction pressure.

7.1.2 The automatic safety equipment is to be designed to fail safe and the arrangements are to be such that the compressors can be operated manually with the equipment out of action, in accordance with the relevant requirements of Chapter 1.

7.1.3 For installations greater than 25 kW the following instrumentation, additional to that required by 7.1.1, is to be provided:

- Indication of lubricating oil temperature.
- Indication of cooling water outlet temperature.
- Indication of cumulative running hours (reciprocating compressors).
- Indication of suction and discharge temperatures.

### 7.2 Control, alarm and safety systems

7.2.1 Where the refrigerating system is fitted with automatic or remote controls, so that under normal operating conditions it does not require any manual intervention by the operators, it is to be provided with the alarms required by 7.2.2 and 7.2.3 in accordance with the relevant requirements of Chapter 1.

7.2.2 Alarms are to be initiated in the event of the following compressor fault conditions:

- High discharge pressure.
- Low suction pressure.
- Low oil pressure.
- High discharge temperature.
- High oil temperature.
- Motor shutdown.

7.2.3 Alarms are also to be initiated in the event of the following fault conditions:

- Failure of condenser cooling water pumps.
- High condenser cooling water outlet temperature.
- Failure of air cooler fans.
- High and low refrigerated air delivery temperatures.
- High secondary refrigerant temperatures.
- Failure of secondary refrigerant pump.
- Failure of air refreshing fans.
- Low level in secondary refrigerant header tank.

### 7.3 Temperature monitoring and recording

7.3.1 Temperature sensors are to be of a type which has been approved by LR. The number of sensors and their locations are to be such as to give a true measurement of the temperatures within the refrigerated spaces and of the cooler delivery and return air temperatures.

7.3.2 At least one automatic recorder is to be provided for the remote monitoring and continuous recording of air temperatures within the refrigerated spaces, and delivery and return air temperatures of individual air coolers. Where only one recorder is installed, at least one sensor in each refrigerated space or in its air distribution system is to be connected to a separate remote temperature indicating instrument.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 7 & 8

7.3.3 Where the equipment controlling the temperature of the air delivered from the air coolers is equipped with a temperature indicator, this indicator will be given consideration as a standby instrument.

7.3.4 In the case of freezer fishing vessels, where the catch is frozen on board and stored in a refrigerated space, thermometer(s) hung within each space(s) will be accepted as the standby temperature indicator, provided the space is accessible at all times.

7.3.5 Automatic temperature recorders and temperature indicators are to be of a type which has been approved by LR and, where appropriate, are to be in accordance with the requirements of Pt 6, Ch 1. Approval will be granted on the basis of compliance with 7.3.6 and 7.3.7, together with satisfactory environmental testing in accordance with the requirements of LR's Type Approval System. This is to include low temperature testing at the class notation minimum temperatures for any components which may be installed in environments subject to temperatures below ambient.

7.3.6 All temperature instrumentation is to be accurate to within  $\pm 0,15^{\circ}\text{C}$  of the true temperature in the range minus  $3^{\circ}\text{C}$  to plus  $15^{\circ}\text{C}$ , and to  $\pm 0,3^{\circ}\text{C}$  in other parts of the range and is to register to 0,1 of a degree Celsius.

7.3.7 Where the installation is intended for the carriage of frozen cargo only, the readings need only be accurate to within  $\pm 0,5^{\circ}\text{C}$  of the true temperature, throughout the range.

7.3.8 A spirit-in-glass thermometer is to be carried on board for checking purposes, which is to be calibrated to a recognized National Standard.

7.3.9 Thermometer tubes with their flanges and covers are to be insulated from the deck plating, and on weather decks they are to be so arranged that water will not run down the tubes when temperatures are being taken.

7.3.10 The inside diameter of thermometer tubes is to be not less than 50 mm, and the tubes are not to be in contact with cold decks.

7.3.11 Where thermometer tubes pass through compartments other than those which they serve, they are to be efficiently insulated.

8.1.2 Access ways to the refrigerated space are to be designed to facilitate escape in emergencies, and the removal of stretcher-borne personnel.

8.1.3 Access ways and air cooler spaces are to be provided with an independent lighting system in accordance with the requirements of Ch 2,5.7.2 and Ch 2,5.7.4, with the means of locking the switches in the 'on' position.

8.1.4 Where ammonia is used in refrigerating systems, the following items of safety equipment are to be provided as a minimum, and positioned in accessible protected storage (e.g. locked glass fronted cabinets) located outside the machinery compartment:

- Two sets of ammonia protective clothing (including helmet, boots and gloves).
- Two portable battery powered hand lamps (to be of certified safe-type).
- Two sets of self-contained breathing apparatus (compressed air).
- Two full face mask respirators.
- Two fire-resistant life-lines.
- Two firemen's axes.
- Two heavy duty adjustable spanners.
- Two wheel wrenches.
- Irrigation facilities or eye wash bottles containing an eye wash solution, distilled water or non-carbonated mineral water.
- Hand or foot-operated douches providing a copious supply of clean water, located outside the compartment's doors. See 3.2.4.

## 8.2 Personnel warning systems

8.2.1 A system to monitor the well-being of crew members entering refrigerated spaces is to be provided.

8.2.2 The system is to be such that at a predetermined time, after initiation, the crew member(s) receives warning that the Surveyors must indicate their well-being by accepting the warning.

8.2.3 The system is to be designed and arranged such that only an authorized person has access for enabling and disabling it and setting the appropriate intervals, and such that it cannot be operated in an unauthorized manner.

8.2.4 It is to be possible to acknowledge the warning by means of illuminated switches situated near the access doors or hatches of each refrigerated space or chambers within the space.

8.2.5 In the event that the crew member(s) fail(s) to respond and accept the warning within an agreed specified time, the system is to immediately initiate an alarm on the bridge and in the engineers' accommodation. Manual initiation of the alarm system from the refrigerated spaces is to be possible at any time.

8.2.6 The system is to comply with the relevant requirements of Chapter 1.

## Section 8

## Personnel safety equipment and systems

### 8.1 Personnel safety equipment

8.1.1 Access doors and hatches to the refrigerated spaces and air cooler spaces are to be provided with an external locking arrangement.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 9

### ■ Section 9 Refrigerated cargo spaces

#### 9.1 Airtightness of refrigerated spaces

9.1.1 The envelopes of individual refrigerated spaces, enclosing each temperature zone, are to be sufficiently airtight to prevent infiltration of water vapour and cross-contaminating odours. Each envelope is to be hose-tested for tightness before the insulation is installed. Alternative proposals to test with gas or air under pressure will be considered.

9.1.2 Hatch closing appliances, access doors, side loading doors, bilge and manhole plugs forming part of an insulated envelope are to be made airtight and, where exposed to ambient conditions, are to be provided with a double seal.

9.1.3 Ventilators, ducts or pipes passing through refrigerated spaces to other compartments are to be made airtight and efficiently insulated. Particular attention is to be given to insulation linings forming surfaces of air ducts. Ventilators to refrigerated spaces, if fitted, are to be provided with airtight closing appliances.

9.1.4 Refrigeration pipes passing through bulkheads or decks of refrigerated chambers or spaces are not to be in direct contact with the steelwork. The temperature of the ship's steelwork close to low temperature refrigeration piping must not be lower than that acceptable for the steel grade, see also Pt 3, Ch 2.2.2. The airtightness of the bulkheads and decks is to be maintained and, where the pipes pass through watertight decks and bulkheads, the fittings and packing of the glands are to be both fire resisting and watertight.

#### 9.2 Insulation systems

9.2.1 Steelwork and fittings are to be clean and dry, and suitably coated to prevent corrosion, before insulation is applied.

9.2.2 *In situ* insulation and insulating panels are to be of a type that has been approved by LR and accordingly, whenever practicable, be selected from the *List of Type Approved Products* published by LR. A copy of the *Procedure for LR Type Approval System* will be supplied on application. Prefabricated panels, with an organic foam core and metal or similar cladding both sides, are also to be manufactured under survey at a works approved by LR. Organic foam materials are to be certified as self-extinguishing. All materials are to be free from odour likely to cause taint.

9.2.3 The thickness of insulation over all surfaces and the manner in which it is supported are to be in accordance with the approved specification and plan.

9.2.4 The insulation is to be efficiently packed and, where it is of slab form, the joints are to be butted closely together and staggered. Where it is intended to use a foamed *in situ* type of insulation, full details of the process are to be submitted for approval before the work commences and pre-production testing on site is to be carried out to the satisfaction of the Surveyor, using a 'mock-up' representative of the system to be employed. Prefabricated panels are to be of a design such that, when erected, continuity of the insulation envelope is maintained without any gaps. Gaps between panels or insulation slabs are to be filled with insulating material to the satisfaction of the Surveyor.

9.2.5 The inner surfaces of insulation envelopes are to be clad with a suitable lining, such as marine grade aluminium or plywood, or equivalent material which is:

- impermeable;
- able to withstand wear and tear and the flexing of the ship's structure without fracture at the notation temperatures;
- non-corrosive, non-rotting; and
- free from odour likely to cause taint.

Where prefabricated panels are employed the outer surfaces are also to be clad with a suitable lining.

9.2.6 Insulation linings are to be constructed and fitted so that they are airtight and provide an effective vapour barrier. The means of joining prefabricated panels are to have sufficient mechanical strength to maintain a vapour barrier on the inner and outer faces. All joints, including corner, deck, deckhead and tank top intersections are to be sealed with a suitable flexible, water vapour resistant sealant or gasket. Special care is necessary where air ducts are embedded in the insulation, and where refrigeration pipes, air refreshing ducts, fan supports, fixtures, etc., protrude through the linings.

9.2.7 Hatch covers and plugs, access doors, manhole plugs, bilge limbers and plugs forming part of the insulated envelope are to be constructed of, or covered with, a suitable lining material.

9.2.8 Insulation linings and air screens, together with supports, are to be strong enough to withstand the loads imposed by either refrigerated or general cargo.

9.2.9 Successive coatings impervious to oil are to be applied before insulating the exposed plating of tank tops and bulkheads protecting tanks containing oil. The total thickness of the required coating will depend on the construction of the tank, the composition of the coating used and the method of application.

9.2.10 If the cargo to be loaded on the tank top insulation could cause damage to the lining, then additional protection is to be provided in way of the hatch and 0,6 m beyond. The protection may be of either a permanent or temporary nature.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 9 &amp; 10

9.2.11 Where the insulation is to support fork lift trucks, the strength of the lining and its supports is to be demonstrated. A sample of the insulation, approximately 4 m x 4 m, is to be prepared and tested by a fully loaded fork lift truck with a gross weight of 6,5 tons on one axle with a wheel pitch of 1450 mm, having single wheeled pneumatic tyres. The truck is to be driven and manoeuvred over the sample to the satisfaction of the Surveyors.

9.2.12 Prefabricated panel systems are to be fitted with suitable pressure equalizing devices to prevent damage which may be caused by under or over pressure resulting from the defrosting of coolers, rapid changes in pressure on the inner and outer faces of the panels or rapid cooling of the chamber.

9.2.13 The pressure equalizing devices are to be so designed as to allow the passage of air in either direction, but remain effectively closed until the pressure differential reaches a value of 10 mm water column. Heating is to be provided to protect the mechanism from freezing.

## 9.3 Access plugs and panels

9.3.1 Insulated plugs are to be provided in the insulation where required for easy access to the bilges, bilge suction strum boxes, cooler and chamber drains and tank manhole lids. Removable panels are to be provided for access to tank air and sounding pipes and drains.

9.3.2 Tank top insulation in way of manholes and bilge hats is to be provided with a liquid-tight steel coaming to prevent seepage into the insulation.

9.3.3 Manholes are not permitted in the bulkheads of fuel oil tanks which form part of the cargo space envelope.

## 9.4 Air circulation and distribution

9.4.1 When frozen cargo is carried, provision is to be made for the adequate circulation of air between the frozen cargo and all the insulation lining surfaces.

9.4.2 When cooled cargo is carried, of a type which may generate heat or emit gas, provision is to be made for the adequate circulation of air through all the stow.

9.4.3 There is to be adequate air flow between cargo and cooling grids, where fitted.

9.4.4 The air distribution arrangements are to be such that the required circulation rate and uniform distribution can be achieved when the space is part or fully loaded with cargo. The arrangement is also to be capable of maintaining uniform air temperature throughout the space with any one fan, or air cooler, or cooling grid circuit out of action, see 4.8.

## 9.5 Air refreshing arrangements

9.5.1 Where spaces are intended for the carriage of refrigerated cargoes requiring controlled ventilation, means are to be provided for air refreshing. The positions of the air inlets are to be carefully selected to minimize the possibility of contaminated air entering the spaces. Chambers or spaces are to be provided with separate inlet and discharge vents. Each vent is to have a positive airtight valve capable of closing onto a seat. It is recommended that a distance of at least 3 m is maintained between inlet and exhaust vents.

## 9.6 Heating arrangements for fruit cargoes

9.6.1 Where the class notation includes the symbol ‡ for the carriage of fruit cargoes, facilities for heating the refrigerated spaces are to be provided to maintain the carrying temperatures when the temperatures outside the spaces are lower.



## Section 10

# Container ships fitted with refrigerating plant to supply cooled air to insulated containers in holds

## 10.1 General

10.1.1 Classed installations designed to supply refrigerated air to insulated 'porthole' containers in holds aboard container ships are to comply with the requirements of Sections 1 to 9 and 11, so far as they are applicable, and the special requirements of this Section.

10.1.2 The classed refrigerating installation is to include the refrigerating machinery, air coolers, supply and return air ducting, and the flexible couplings between containers and the duct system. Where the arrangements are such that cell air conditioning is essential to the carriage of the containers, the air conditioning equipment and (if fitted) the insulation of the hold, deckheads, sides and tank tops are to be included in the classification.

## 10.2 Additional information and plans

10.2.1 In addition to those requirements detailed in Section 1 which are also applicable to refrigerated container ships, the following information is to be submitted before the work commences:

- Details of air coolers.
- Details of the design of ducting proposed, including joints, connections, insulation, vapour sealing and linings.
- Details of cell air conditioning arrangements and components.
- Details of couplings between ducting and containers, including operating arrangements.

# Refrigerated Cargo Installations

# Part 6, Chapter 3

Sections 10 & 11

## 10.3 Air coolers

10.3.1 Air ducts supplying more than ten standard 20 ft containers or five standard 40 ft containers are to have a single air cooler with multiple circuits or two independent coolers. The individual circuits or coolers are to be provided with stop valves so that each circuit or cooler may be readily isolated.

10.3.2 The refrigeration capacity of the air cooler arrangement is to be such that the temperature conditions can be maintained with any one circuit or independent cooler out of action.

10.3.3 For air ducts supplying ten standard 20 ft containers or five standard 40 ft containers or less, a single cooler with one circuit will be acceptable.

## 10.4 Air duct systems

10.4.1 The air ducts, together with all branches and couplings, supplying refrigerated air to insulated containers in holds, are to be made airtight. For design purposes, however, an air leakage rate of 0,5 per cent of total volume flow at the design pressure for each duct is to be taken.

10.4.2 Where air ducting is insulated on the internal surfaces, provision is to be made to prevent retention of odour which may taint subsequent cargo.

10.4.3 Couplings are to be of a type that has been approved by LR. Prototypes are to be tested under all operating conditions, witnessed by the Surveyors, to demonstrate that they extend, retract and separate satisfactorily from a 'container end wall' at the minimum temperature condition. When operated by means of air pressure they are to be supplied with air sufficiently dry to avoid ice formation. The air supply lines are to be strength pressure tested to 1,5 x design pressure.

## 10.5 Duct air leakage and distribution tests

10.5.1 Air leakage tests on at least 10 per cent of ducting, selected at random, are to be carried out to the satisfaction of the Surveyors before the insulation is applied. The Surveyors may require further testing to demonstrate airtightness of ducting. The air leakage from each duct will depend on several factors and, while complete airtightness should be the objective, the air leakage rate for design purposes is not to exceed 0,5 per cent of total volume flow at the design pressure of 250 Pa.

10.5.2 In the case of prefabricated ducts, the prototype is to be subjected to air distribution, heat leakage and air leakage tests. Each production duct is to be tested for air leakage and is not to exceed the prototype test results by more than five per cent. Additionally, one duct in 50 or part thereof is to be tested for heat leakage and the results are not to exceed the prototype test results by more than 10 per cent.

10.5.3 In all cases when prefabricated sections are assembled on board, the tests as detailed in 10.5.2, are to be carried out aboard the ship.

10.5.4 On application from the Owner, the air leakage tests on air ducts installed aboard the ship, as detailed in 10.5.1 to 10.5.3, may be omitted provided that:

- the installation is designed with at least 20 per cent surplus refrigerating capacity, or
- assignment of a temperature notation for the installation be deferred until verified by a thermal balance test to the Surveyor's satisfaction.

10.5.5 All ducts are to be tested for air distribution to the containers, at the manufacturer's works, by measuring the flow of air from the supply couplings while the fan is operated at full speed against the designed pressure. The air flow at each coupling is to meet the specified figure within  $\pm 5$  per cent.

10.5.6 Systems comprising rigid prefabricated ducts complete with coolers and fans are to be tested for air distribution at the place of manufacture. The remaining tests are to be carried out aboard the ship.

## 10.6 Cell air conditioning arrangements

10.6.1 The cell air conditioning equipment and ducting, and/or insulation of the holds, deckheads, sides and tank tops, is to be such as to maintain a uniform temperature throughout the cell and to ensure the ship's steelwork is maintained above the minimum temperature acceptable for the steel grade, see also Pt 3, Ch 2,2.2.

## Section 11 Acceptance trials

### 11.1 Tests after completion

11.1.1 On completion of construction, the acceptance tests prescribed in 11.3.1 are to be carried out to verify the correct functioning of the installation and its ability to maintain the lowest notation temperature conditions required for the assignment of the intended class notation. The proposed test schedules, which should include methods of testing and test facilities provided, are to be submitted for approval before these acceptance tests are started.

### 11.2 Thermographic survey

11.2.1 The insulated envelope of refrigerated cargo ships and, where applicable, fish factory ships, fishing vessels, fruit juice carriers and container ships is to be scanned using a thermal imaging camera. The main purpose of carrying out the infra-red scan is to verify the efficiency of the insulation system.

# Refrigerated Cargo Installations

## Part 6, Chapter 3

Section 11

11.2.2 During the course of, or prior to, the acceptance trials all inner insulated surfaces, including tank tops, bulkheads, 'tween decks, insulated hatches, coamings and weather decks are to be subject to an infra-red scan.

11.2.3 Where internal obstructions preclude an internal scan, it is to be carried out externally.

11.2.4 The scan is to be conducted with the 'tween deck and main holds in total darkness and with air coolers/cooling grids isolated and all heat sources disconnected. The temperature difference, cargo hold to ambient air or sea-water temperature, is to be 15 K or more.

11.2.5 Any deficiencies or abnormalities revealed are to be investigated and repaired to the extent considered necessary by the Surveyor.

### 11.3 Acceptance tests

11.3.1 The acceptance tests (see also 11.3.2 and 11.3.3) are to comprise the following:

- (a) Verification of control, alarm, safety and refrigerant detection systems.
- (b) Test simulating failure of selected components such as compressors, fans and pumps, to verify correct functioning of alarm and systems in service.
- (c) Verification of accuracy, calibration and functioning of temperature control, monitoring and recording instrumentation.
- (d) Verification of air cooler fan outputs running at maximum speed, and air circulation rates and distribution arrangements in individual refrigerated spaces or chambers. The latter is to be undertaken firstly with all coolers in operation and secondly with any one cooler or fan out of action.
- (e) Verification of air refreshing and heating arrangements.
- (f) Verification of personnel safety devices and warning systems in refrigerated spaces.
- (g) Refrigeration and thermal balance tests to demonstrate the capability of the combined refrigerating plant and insulation envelope to maintain the lowest notation temperature to be assigned.
- (h) Refrigeration tests for refrigerated container ships carrying 'porthole' type insulated containers. If the prescribed thermal balance tests cannot be carried out due to the number of insulated containers available in the shipyard being inadequate, then, alternatively, the following separate tests will be accepted:
  - (i) Compressor capacity test.
  - (ii) Duct heat leakage test on at least 20 per cent of the insulated ducting selected at random.
  - (iii) Cell heat leakage test.
- (j) Thermographic scan to be carried out as required by 11.2.

11.3.2 Where a number of identical installations are constructed for the same Owner and by the same shipyard, the refrigeration and thermal balance tests required in 11.3.1(g), need only be carried out on two of the series, provided the results are satisfactory.

11.3.3 Where the cells of 'porthole' type insulated containers are not insulated, a heat leakage test will be required on the first ship of the series only.

### 11.4 Sea trials

11.4.1 Where the class notation includes the symbol ‡ for the carriage of fruit, or the symbol ‡ is to be assigned to a fishing vessel the following records are to be kept during the first loaded voyage:

(a) **Refrigerated cargo or container ships:**

Refrigerating machinery logs and temperature records for the refrigerated cargo spaces or containers, demonstrating the installation's capability to cool down the full cargo of fruit and maintain the notation temperature conditions.

(b) **Fishing vessels:**

Refrigerating machinery and freezing equipment logs and temperature records for the refrigerated cargo spaces, demonstrating the installation's capability to freeze the catch and maintain the notation temperature conditions.

### 11.5 Reporting of tests

11.5.1 On completion of the tests prescribed in 11.1, two copies of the test schedule for the refrigerated cargo installation, giving details of all recorded data and thermal heat balance results, signed by the Surveyor and Builder are to be provided. One copy is to be placed on board the ship and the other submitted to LR.

11.5.2 At the end of the first loaded voyage a copy of the logs and temperature records requested in 11.4.1(a) and (b), as applicable, signed by the ship's Chief Engineer, are to be submitted to LR.



# Fire Protection, Detection and Extinction Requirements

# Part 6, Chapter 4

Sections 1 & 2

## Section

### 1 General

### 2 Fire detection, protection and extinction

## ■ Section 1 General

### 1.1 Application

1.1.1 Cargo ships of 500 gross tons or more, all passenger ships and gas and chemical tankers on international voyages, where provision is made within International Conventions are to be provided with the fire safety measures required by the *International Convention for the Safety of Life at Sea*, 1974, as amended (SOLAS 74). Fishing vessels of 45 m freeboard length and over are to be provided with the fire safety measures required by the Torremolinos Protocol of 1993 relating to the *Torremolinos International Convention for the Safety of Fishing Vessels*, 1977 (Torremolinos Protocol).

1.1.2 Cargo ships of 500 gross tons or more, all passenger ships, and gas and chemical tankers, employed on national voyages are to comply with the fire safety measures prescribed and approved by the Government of the flag state.

1.1.3 It is the responsibility of the Government of the flag state to give effect to the fire protection, detection and extinction requirements of 1.1.1 and 1.1.2. However Lloyd's Register (hereinafter referred to as 'LR') will undertake to do this in cases where:

- (a) contracting Governments have authorized LR to apply the requirements of SOLAS 74 or the Torremolinos Protocol and issue the appropriate certification on their behalf; or
  - (b) the Government of the flag state is not a signatory to SOLAS 74 or the Torremolinos Protocol; or
  - (c) the ship or fishing vessel is to be classed for restricted or special service in national waters for which the Government of the flag state has no national requirements. In such cases, LR will apply the fire safety measures required by SOLAS 74 or the Torremolinos Protocol, as appropriate.
- However, due consideration will be given to arrangements deemed to provide an equivalent level of fire safety, taking due cognizance of the circumstances of the restricted or special service.

1.1.4 Section 2 of this Chapter, which is within the spirit of the International Convention and Protocol requirements for ships of Convention size, is applicable to cargo ships of less than 500 gross tons (where not covered by International Conventions), fishing vessels of 12 m registered length and over but less than 45 m freeboard length, and ships not fitted with propelling machinery.

1.1.5 Consideration will be given to the acceptance of fire safety measures prescribed and approved by the Government of the flag state in lieu of 1.1.4.

1.1.6 Special consideration, consistent with the fire hazard involved, will be given to construction or arrangement features not covered by this Chapter.

1.1.7 Cargo ships of less than 500 gross tons intended for the carriage of dangerous goods are to comply with SOLAS 1974 as amended II-2/G.19.

## ■ Section 2 Fire detection, protection and extinction

### 2.1 General provisions

2.1.1 The provisions of these requirements, are intended to apply to new and, as far as reasonable and practicable, or as found necessary by the relevant Administration, to existing cargo ships of less than 500 GT.

2.1.2 It should be remembered that the *International Codes for the Construction and Equipment of Ships carrying Dangerous Chemicals in Bulk and Liquefied Gases in Bulk* are applicable to such ships regardless of size including those of less than 500 GT.

### 2.2 Definitions

2.2.1 The terms, used in these requirements are as defined in SOLAS 1974 (as amended).

2.2.2 The term Gross Tonnage (GT) is as defined in IMO Resolutions A.493 (XII), calculated in accordance with the 1969 Tonnage Convention and the interim scheme applicable to ships with keels laid up to 18 July 1994 in accordance with IMO Resolution A.494 (XII).

#### 2.2.3 Service area definitions

- (a) 'Unrestricted service' means a ship engaged on international voyages.
- (b) 'Restricted service' is broken down into two broad categories: (a) ships operating coastal or specified operating areas (b) ships operating within protected or extended protected waters.

- (i) **Specified coastal service.** Service along a coast, the geographical limits of which are to be defined and for a distance out to sea generally not exceeding 20 nautical miles, unless some other distance is specified for 'coastal service' by the Administration with which the ship is registered, or by the Administration of the coast off which it is operating. A typical example might be 'Indonesian coastal service'.

**Specified operating or service areas** may be service between two or more ports or other geographical features, or service within a defined geographical area such as 'Red Sea Service', 'Piraeus to Thessaloniki and Islands within the Aegean Sea'.

- (ii) **Protected water service.** Service in sheltered water adjacent to sand banks, reefs, breakwaters to other coastal features, and in sheltered water between islands.

**Extended protected water service.** Service in protected waters and also short distances (generally less than 15 nautical miles) beyond protected waters in 'reasonable weather'.

## 2.3 Surveys and maintenance

2.3.1 The hull, machinery and all equipment required for safety aspects of every ship should be constructed and installed so as to be capable of being regularly maintained to ensure that they are at all times, in all respects, satisfactory for the ship's intended service.

2.3.2 A competent authority should arrange for appropriate surveys of the required equipment relating to fire safety aspects during construction and, at regular intervals after completion, generally as prescribed within Chapter I of SOLAS 1974 (as amended). Such surveys should be carried out by the Society classing the ship or the Flag State.

2.3.3 The condition of the structural fire protection and fire safety related equipment shall be maintained to conform with the provisions of the requirements to ensure that the ship in these respects, will remain fit to proceed to sea without danger to the ship or persons on board. The hull structure and machinery do not form part of these requirements but should be similarly surveyed and maintained.

## 2.4 Requirements

2.4.1 Table 4.2.1 details the various minimum fire protection, detection and extinction arrangements that are required depending on the vessel's intended service area.

**Fire Protection, Detection and Extinction Requirements****Part 6, Chapter 4**

Section 2

**Table 4.2.1 General fire detection, protection and extinction requirements**

Fire-fighting	Unrestricted	Restricted	Protected
1. FIRE PUMPS Ships greater than 150 GT Independently driven power pumps Power pumps Hand pumps Ships less than 150 GT Independently driven power pumps Power pumps Hand pumps	  1 1 —  — 1 1 1	  1 1 —  — 1 1 1	  1 — 1  — 1 —
2. FIRE HYDRANTS Sufficient number and so located that at least one powerful water jet can reach any normally accessible part of ship	X	X	X
3. FIRE HOSES (Length >15 m) With couplings and nozzles	≥ 3	≥ 3	≥ 2
4. FIRE NOZZLES Dual purpose (spray/jet) with 12 mm jet and integral shut-off Jet may be reduced to 10 mm and shut-off omitted for hand pump hoses	X	X	X
5. PORTABLE FIRE EXTINGUISHERS Accommodation and service spaces Boiler rooms, etc. Machinery spaces (one extinguisher per 375 kw of internal combustion engine power) Cargo pump rooms (capacity 9 l. fluid or equivalent)	≥ 3 ≥ 2  ≥ 2 ≤ 6 ≥ 2	≥ 3 ≥ 2  ≥ 2 ≤ 6 ≥ 2	≥ 2 ≥ 2  ≥ 2 ≤ 6 ≥ 2
6. NON-PORTABLE FIRE EXTINGUISHERS IN MACHINERY SPACES Ships greater than 150 GT Ships greater than 350 GT (capacity 45 l. fluid or equivalent)	1 —	1 —	— 1
7. FIXED FIRE EXTINGUISHING SYSTEMS SHIPS GREATER THAN 350 GT Category A machinery spaces Cargo pump rooms	 X X	 X X	 — —
8. CARGO TANK PROTECTION Mobile foam appliances	X	X	X
9. FIREMAN'S OUTFIT Ships greater than 150 GT complete outfit Ships less than 150 GT complete outfit Fireman's axe	≥ 2  ≥ 1 —	≥ 2  ≥ 1 —	≥ 2  — 1
10. MEANS OF ESCAPE Accommodation and service spaces Machinery spaces Cargo pump rooms	2 ≥ 1 1	2 ≥ 1 1	2 ≥ 1 1
11. STRUCTURAL FIRE PROTECTION WHEEL HOUSE AND MACHINERY SPACES Separation from adjacent spaces of negligible fire risk Separation from other adjacent spaces Escape routes	A-0 A-60 B-0	A-0 A-30 B-0	A-0 A-0 B-0





© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset

# RULES AND REGULATIONS FOR THE CLASSIFICATION OF SHIPS

OTHER SHIP TYPES AND SYSTEMS

JULY 2007

PART 7

Lloyd's Register is an exempt charity under the UK Charities Act 1993

Lloyd's Register, its affiliates and subsidiaries and their respective officers, employees or agents are, individually and collectively, referred to in this clause as the 'Lloyd's Register Group'. The Lloyd's Register Group assumes no responsibility and shall not be liable to any person for any loss, damage or expense caused by reliance on the information or advice in this document or howsoever provided, unless that person has signed a contract with the relevant Lloyd's Register Group entity for the provision of this information or advice and in that case any responsibility or liability is exclusively on the terms and conditions set out in that contract.



---

PART	1	REGULATIONS
PART	2	RULES FOR THE MANUFACTURE, TESTING AND CERTIFICATION OF MATERIALS
PART	3	SHIP STRUCTURES (GENERAL)
PART	4	SHIP STRUCTURES (SHIP TYPES)
PART	5	MAIN AND AUXILIARY MACHINERY
PART	6	CONTROL, ELECTRICAL, REFRIGERATION AND FIRE
<b>PART</b>	<b>7</b>	<b>OTHER SHIP TYPES AND SYSTEMS</b>
	<b>Chapter 1</b>	<b>Controlled Atmosphere Systems</b>
	<b>2</b>	<b>Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products</b>
	<b>3</b>	<b>Fire-fighting Ships</b>
	<b>4</b>	<b>Dynamic Positioning Systems</b>
	<b>5</b>	<b>Ships Equipped for Oil Recovery Operations</b>
	<b>6</b>	<b>Arrangements for Offshore Loading</b>
	<b>7</b>	<b>Burning of Coal in Ships' Boilers</b>
	<b>8</b>	<b>Positional Mooring and Thruster-Assisted Positional Mooring Systems</b>
	<b>9</b>	<b>Navigational Arrangements for Periodic One Man Watch</b>
	<b>10</b>	<b>Carriage of Refrigerated Containers</b>
	<b>11</b>	<b>Arrangements and Equipment for Environmental Protection</b>
	<b>12</b>	<b>Integrated Fire Protection (IFP) Systems</b>
	<b>13</b>	<b>Arrangements and Equipment for Bulk Carrier Safety</b>
	<b>14</b>	<b>Passenger and Crew Accommodation Comfort</b>

© Lloyd's Register, 2007. All rights reserved.

Except as permitted under current legislation no part of this work may be photocopied, stored in a retrieval system, published, performed in public, adapted, broadcast, transmitted, recorded or reproduced in any form or by any means, without the prior permission of the copyright owner. Enquiries should be addressed to Lloyd's Register, 71 Fenchurch Street, London, EC3M 4BS.



---

<b>CHAPTER</b>	<b>1</b>	<b>CONTROLLED ATMOSPHERE SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Novel arrangements and design
	1.3	Definitions
<b>Section</b>	<b>2</b>	<b>Plans and documentation</b>
	2.1	Plans of CA zones and adjacent spaces
	2.2	Gas supply system
	2.3	Humidifiers
	2.4	Control equipment
	2.5	Electrical
	2.6	Testing
<b>Section</b>	<b>3</b>	<b>CA zones and adjacent spaces</b>
	3.1	Air-tightness of CA zones
	3.2	CA zone protection
	3.3	Gas freeing of CA zones
	3.4	Ventilation of adjacent spaces
<b>Section</b>	<b>4</b>	<b>Gas systems</b>
	4.1	General
	4.2	Location
	4.3	Gas supply
	4.4	Gas supply compartment ventilation and alarm
<b>Section</b>	<b>5</b>	<b>Relative humidity (RH)</b>
	5.1	Humidification
<b>Section</b>	<b>6</b>	<b>Electrical installation</b>
	6.1	General
<b>Section</b>	<b>7</b>	<b>Control instrumentation and alarms</b>
	7.1	General
	7.2	Gas systems
	7.3	Gas analysers and sampling
	7.4	Gas sensors
<b>Section</b>	<b>8</b>	<b>Safety requirements</b>
	8.1	Personnel safety
<b>Section</b>	<b>9</b>	<b>Inspection and testing on completion</b>
	9.1	General
	9.2	Gas supply and sampling systems
	9.3	Air-tightness of CA zones
	9.4	Gas system performance
	9.5	Gas freeing
	9.6	Safety, alarms and instrumentation
<b>CHAPTER</b>	<b>2</b>	<b>SHIPS WITH INSTALLED PROCESS PLANT FOR CHEMICALS, LIQUEFIED GASES AND RELATED PRODUCTS</b>
<b>Section</b>	<b>1</b>	<b>Introduction</b>
	1.1	Scope
	1.2	General
	1.3	Classification of ship
	1.4	Certification of process plant
<b>Section</b>	<b>2</b>	<b>Class notations</b>
	2.1	Ship notations
	2.2	Additional notations
	2.3	Special mooring and linking arrangements

---

<b>Section</b>	<b>3</b>	<b>Plans and particulars</b>
	3.1	General
	3.2	Hull construction
	3.3	Process plant
	3.4	Mechanical equipment associated with the process plant
	3.5	Boilers and other pressure vessels associated with the process plant
	3.6	Pumping and piping systems associated with the process plant
	3.7	Electrical equipment for the process plant
	3.8	Control equipment for the process plant
	3.9	Fire protection, detection and extinction
<b>Section</b>	<b>4</b>	<b>Materials</b>
	4.1	General
<b>Section</b>	<b>5</b>	<b>Process plant characteristics</b>
	5.1	Design
	5.2	Separation from ship machinery
<b>Section</b>	<b>6</b>	<b>Hull construction</b>
	6.1	General
	6.2	Location of accommodation, service and control spaces
	6.3	Integrity of gastightness between compartments
	6.4	Cofferdams
	6.5	Access and openings to spaces
	6.6	Longitudinal strength
	6.7	Plant support structure
	6.8	Loading due to wave-induced motions
	6.9	Additional loads
	6.10	Allowable stresses in support structure
	6.11	Integrity of weather deck
	6.12	Equipment
	6.13	Gangways and freeing arrangements
<b>Section</b>	<b>7</b>	<b>Mechanical equipment for the process plant</b>
	7.1	General
	7.2	Safety precautions
	7.3	Inspection and installation
<b>Section</b>	<b>8</b>	<b>Boilers and other pressure vessels for the process plant</b>
	8.1	General
	8.2	Construction and installation
	8.3	Safety devices
<b>Section</b>	<b>9</b>	<b>Pumping and piping systems for the process plant</b>
	9.1	General
	9.2	Process plant piping systems
	9.3	Lubricating oil and oil fuel piping
	9.4	Gas fuel supply systems
	9.5	Air and sounding pipes
	9.6	Bilge and effluent arrangements
<b>Section</b>	<b>10</b>	<b>Firing arrangements of steam boilers, fired pressure vessels, heaters, reformers, etc.</b>
	10.1	General
	10.2	Design and construction
<b>Section</b>	<b>11</b>	<b>Electrical equipment for the process plant</b>
	11.1	Design of installation
	11.2	Equipment suitability for environment
	11.3	Hazardous zones
	11.4	Certified safe-type equipment
	11.5	Survey and testing

---

<b>Section</b>	<b>12</b>	<b>Control engineering for the process plant</b>
	12.1	Design of installation
	12.2	Equipment
	12.3	Survey and testing
<b>Section</b>	<b>13</b>	<b>Plant blow-down systems</b>
	13.1	General
<b>Section</b>	<b>14</b>	<b>Plant flare gas systems</b>
	14.1	General
<b>Section</b>	<b>15</b>	<b>Supply and discharge arrangements for feedstock and product</b>
	15.1	General
	15.2	Emergency procedures
<b>Section</b>	<b>16</b>	<b>Ventilation of the process plant and other spaces associated with the process plant operation</b>
	16.1	General
	16.2	Design and construction
	16.3	Air inlets and discharges
	16.4	Installation and inspection
<b>Section</b>	<b>17</b>	<b>Gas detection</b>
	17.1	General
	17.2	Design and construction
	17.3	Installation
<b>Section</b>	<b>18</b>	<b>Fire protection, detection and extinction</b>
	18.1	General
	18.2	Design arrangements
<b>CHAPTER</b>	<b>3</b>	<b>FIRE-FIGHTING SHIPS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Classification and class notations
	1.3	Surveys
	1.4	Submission of plans
	1.5	Definitions
<b>Section</b>	<b>2</b>	<b>Construction</b>
	2.1	Hull
	2.2	Sea suction
	2.3	Stability
	2.4	Manoeuvrability
	2.5	Bunkering
<b>Section</b>	<b>3</b>	<b>Fire-extinguishing</b>
	3.1	Water monitors
	3.2	Pumps
	3.3	Hose stations
	3.4	Fireman's outfits
	3.5	Recharging of equipment
<b>Section</b>	<b>4</b>	<b>Fire protection</b>
	4.1	General
	4.2	Water spray systems
<b>Section</b>	<b>5</b>	<b>Lighting</b>
	5.1	General

## CHAPTER 4 DYNAMIC POSITIONING SYSTEMS

### Section 1 General

- 1.1 Application
- 1.2 Classification notations
- 1.3 Information and plans required to be submitted

### Section 2 Class notation DP(CM)

- 2.1 General
- 2.2 Thrust units
- 2.3 Electrical systems
- 2.4 Control stations
- 2.5 Control system

### Section 3 Class notation DP(AM)

- 3.1 Requirements

### Section 4 Class notation DP(AA)

- 4.1 Requirements

### Section 5 Class notation DP(AAA)

- 5.1 Requirements

### Section 6 Performance Capability Rating (PCR)

- 6.1 Requirements

### Section 7 Testing

- 7.1 General

## CHAPTER 5 SHIPS EQUIPPED FOR OIL RECOVERY OPERATIONS

### Section 1 General

- 1.1 Application
- 1.2 Classification and class notations
- 1.3 Surveys
- 1.4 Plans and supporting documentation

### Section 2 Oil recovery

- 2.1 General
- 2.2 Equipment and principal deck arrangement

### Section 3 Ship structure

- 3.1 Structural arrangement
- 3.2 Scantlings

### Section 4 Machinery arrangements

- 4.1 Piping arrangements
- 4.2 Pump room for recovered oil
- 4.3 Ventilation of machinery spaces
- 4.4 Exhaust systems
- 4.5 Miscellaneous

### Section 5 Electrical equipment

- 5.1 General
- 5.2 Systems of supply and distribution
- 5.3 Hazardous zones and spaces
- 5.4 Ventilation
- 5.5 Pressurization
- 5.6 Selection of electrical equipment for installation in hazardous areas

---

<b>Section</b>	<b>6</b>	<b>Fire protection and extinction</b>
	6.1	Structural fire protection
	6.2	Fire-extinguishing arrangements
	6.3	Fireman's outfits
<b>Section</b>	<b>7</b>	<b>Operating Manual</b>
	7.1	General
<b>CHAPTER</b>	<b>6</b>	<b>ARRANGEMENTS FOR OFFSHORE LOADING</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Class notations
	1.3	Surveys
	1.4	Submission of plans and documentation
<b>Section</b>	<b>2</b>	<b>Arrangements</b>
	2.1	Mooring arrangements
	2.2	Materials for mooring fittings
	2.3	Strength of mooring fittings
	2.4	Enclosed spaces adjacent to manifold connection
<b>Section</b>	<b>3</b>	<b>Positioning, monitoring and control arrangements</b>
	3.1	General
	3.2	Control station
	3.3	Instrumentation
	3.4	Emergency disconnect arrangements for pipeline and mooring
	3.5	Communication
<b>Section</b>	<b>4</b>	<b>Fire protection, detection and extinction</b>
	4.1	General
<b>Section</b>	<b>5</b>	<b>Piping systems</b>
	5.1	Materials
	5.2	Piping system design
	5.3	Piping system testing and non-destructive examination
<b>Section</b>	<b>6</b>	<b>Trials and testing</b>
	6.1	General
<b>CHAPTER</b>	<b>7</b>	<b>BURNING OF COAL IN SHIPS' BOILERS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Submission of plans
	1.3	Surveys
	1.4	Additional bilge drainage
<b>Section</b>	<b>2</b>	<b>Coal storage, handling, ash collection and disposal arrangements</b>
	2.1	Coal storage
	2.2	Coal handling
	2.3	Ash collection and disposal arrangements
<b>Section</b>	<b>3</b>	<b>Coal burning equipment</b>
	3.1	Operating conditions
	3.2	Forced and induced draught air fans
	3.3	Fuel characteristics and specification
	3.4	Alternative means of firing

---

<b>Section</b>	<b>4</b>	<b>Ship structure</b>
	4.1	General
	4.2	Coal bunker hatchways
	4.3	Coal bunker bulkheads
	4.4	Longitudinal strength
	4.5	Ventilation
<b>Section</b>	<b>5</b>	<b>Electrical equipment</b>
	5.1	General
	5.2	Arrangements in coal bunkers
<b>Section</b>	<b>6</b>	<b>Control engineering systems</b>
	6.1	General
<b>Section</b>	<b>7</b>	<b>Fire protection and extinction</b>
	7.1	Fire protection
	7.2	Fire-extinction
<b>CHAPTER</b>	<b>8</b>	<b>POSITIONAL MOORING AND THRUSTER-ASSISTED POSITIONAL MOORING SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Classification notations
	1.3	Surveys
	1.4	Definitions
	1.5	Plans and data submission
<b>Section</b>	<b>2</b>	<b>Environmental criteria – Forces and motions</b>
	2.1	Limiting environmental criteria
	2.2	Design environmental criteria
	2.3	Environmental forces
<b>Section</b>	<b>3</b>	<b>Moorings system – Design and analysis</b>
	3.1	General
	3.2	Design cases and factors of safety
<b>Section</b>	<b>4</b>	<b>Moorings equipment</b>
	4.1	Anchors
	4.2	Fairleads
	4.3	Stoppers
	4.4	Anchor lines
<b>Section</b>	<b>5</b>	<b>Anchor winches and windlasses</b>
	5.1	General
	5.2	Materials
	5.3	Brakes
	5.4	Stoppers
	5.5	Winch/Windlass performance
	5.6	Strength
	5.7	Testing
	5.8	Type approval
<b>Section</b>	<b>6</b>	<b>Electrical and control equipment</b>
	6.1	General
	6.2	Control stations
	6.3	Alarms
	6.4	Controls
<b>Section</b>	<b>7</b>	<b>Thruster-assisted positional mooring</b>
	7.1	General
	7.2	Control systems



---

<b>Section</b>	<b>8</b>	<b>Thruster-assisted mooring – Classification notation requirements</b>
	8.1	Notation <b>T1</b>
	8.2	Notation <b>T2</b>
	8.3	Notation <b>T3</b>
<b>Section</b>	<b>9</b>	<b>Trials</b>
	9.1	General
<b>CHAPTER</b>	<b>9</b>	<b>NAVIGATIONAL ARRANGEMENTS FOR PERIODIC ONE MAN WATCH</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Information and plans required to be submitted
	1.3	Definitions
<b>Section</b>	<b>2</b>	<b>Physical conditions</b>
	2.1	Bridge and wheelhouse arrangement
	2.2	Environment
	2.3	Lighting
	2.4	Windows
	2.5	Fields of vision
<b>Section</b>	<b>3</b>	<b>Workstations</b>
	3.1	Navigation workstation
	3.2	Voyage planning workstation
<b>Section</b>	<b>4</b>	<b>Systems</b>
	4.1	Alarm and warning systems
	4.2	Watch safety system
	4.3	Communications
	4.4	Power supplies
<b>Section</b>	<b>5</b>	<b>Integrated Bridge Navigation System – IBS notation</b>
	5.1	General
	5.2	General requirements
	5.3	Equipment
	5.4	Operator interface
	5.5	Alarm management
	5.6	Power supplies
<b>Section</b>	<b>6</b>	<b>Trials</b>
	6.1	General
<b>CHAPTER</b>	<b>10</b>	<b>CARRIAGE OF REFRIGERATED CONTAINERS</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	General
	1.2	Novel arrangement and designs
	1.3	Definitions
<b>Section</b>	<b>2</b>	<b>Plans and documentation</b>
	2.1	General
<b>Section</b>	<b>3</b>	<b>Ventilation and hold temperature</b>
	3.1	Ventilation system
	3.2	Heat balance
	3.3	Fan redundancy
	3.4	Hull structures

---

<b>Section</b>	<b>4</b>	<b>Electrical, including container plug-in sockets</b>
	4.1	General
	4.2	Plug-in socket outlet supply transformers
	4.3	Container plug-in socket outlets
	4.4	Generated power for plug-in socket outlets
<b>Section</b>	<b>5</b>	<b>Instrumentation, control and alarm systems</b>
	5.1	General
	5.2	Hold space temperature monitoring
	5.3	Container refrigeration system alarms
<b>Section</b>	<b>6</b>	<b>Hold access and maintenance access arrangements</b>
	6.1	Hold pressure/vacuum
	6.2	Hold access arrangements
	6.3	Maintenance access arrangements
<b>Section</b>	<b>7</b>	<b>Water cooler refrigeration units</b>
	7.1	Cooling water system
<b>Section</b>	<b>8</b>	<b>Deck-stowed refrigerated containers</b>
	8.1	General
<b>Section</b>	<b>9</b>	<b>Inspection and testing on completion</b>
	9.1	General
	9.2	Acceptance tests
	9.3	Testing of cooling water system
<b>Section</b>	<b>10</b>	<b>Spare gear</b>
	10.1	General
<b>CHAPTER</b>	<b>11</b>	<b>ARRANGEMENTS AND EQUIPMENT FOR ENVIRONMENTAL PROTECTION</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Application
	1.2	EP class notation
	1.3	Information to be submitted
	1.4	Alterations and additions
	1.5	In-service records
<b>Section</b>	<b>2</b>	<b>Environmental Protection (EP) class notation</b>
	2.1	General
	2.2	Oxides of nitrogen (NO <sub>x</sub> )
	2.3	Oxides of sulphur (SO <sub>x</sub> )
	2.4	Refrigeration systems
	2.5	Fire-fighting systems
	2.6	Oil pollution prevention
	2.7	Garbage handling and disposal
	2.8	Sewage treatment
	2.9	Hull anti-fouling systems
	2.10	Ballast water
<b>Section</b>	<b>3</b>	<b>Supplementary characters</b>
	3.1	Hull anti-fouling systems – A character
	3.2	Ballast water management – B character
	3.3	Grey water – G character
	3.4	Oxides of nitrogen (NO <sub>x</sub> ) – N character
	3.5	Oily bilge water – O character
	3.6	Protected oil tanks – P character
	3.7	Refrigeration systems – R character
	3.8	Oxides of sulphur (SO <sub>x</sub> ) – S character
	3.9	Vapour emission control systems – Vc and Vp characters

<b>Section</b>	<b>4</b>	<b>Survey requirements</b>
	4.1	Initial Survey and Audit
	4.2	Periodical Surveys and Audits
	4.3	Change of company
<b>CHAPTER</b>	<b>12</b>	<b>INTEGRATED FIRE PROTECTION (IFP) SYSTEMS</b>
<b>Section</b>	<b>1</b>	<b>General</b>
	1.1	Application
	1.2	Submission of plans and information
	1.3	Definitions
<b>Section</b>	<b>2</b>	<b>Centralized fire-control station</b>
	2.1	General
	2.2	Communication
<b>Section</b>	<b>3</b>	<b>Control and monitoring of active fire protection and fixed fire-extinguishing systems</b>
	3.1	General
	3.2	Fixed fire detection and fire-alarm systems
	3.3	Fixed water-based fire-extinguishing systems, including local application systems
	3.4	Fixed gas fire-extinguishing systems
	3.5	Dry extinguishing powder fire-extinguishing systems
	3.6	Protected space openings and ventilation systems
	3.7	Oil storage, transfer and pumping arrangements in machinery spaces
<b>Section</b>	<b>4</b>	<b>Integration of other systems</b>
	4.1	General
<b>Section</b>	<b>5</b>	<b>Testing, trials and maintenance</b>
	5.1	General
	5.2	Modifications
<b>CHAPTER</b>	<b>13</b>	<b>ARRANGEMENTS AND EQUIPMENT FOR BULK CARRIER SAFETY</b>
<b>Section</b>	<b>1</b>	<b>Water ingress detection arrangements</b>
	1.1	General requirements
<b>Section</b>	<b>2</b>	<b>Drainage and pumping arrangements</b>
	2.1	General requirements
	2.2	Dewatering capability
<b>CHAPTER</b>	<b>14</b>	<b>PASSENGER AND CREW ACCOMMODATION COMFORT</b>
<b>Section</b>	<b>1</b>	<b>General requirements</b>
	1.1	Scope
	1.2	Definitions
	1.3	Class notations
	1.4	Certificate of Compliance
<b>Section</b>	<b>2</b>	<b>Noise</b>
	2.1	Assessment criteria
	2.2	Passenger accommodation and public spaces
	2.3	Crew accommodation and work areas
	2.4	Maximum noise levels
	2.5	Impact insulation
	2.6	Transient noise
<b>Section</b>	<b>3</b>	<b>Vibration</b>
	3.1	Assessment criteria
	3.2	Passenger accommodation and public spaces
	3.3	Crew accommodation and work spaces

# Contents

# Part 7

---

<b>Section</b>	<b>4</b>	<b>Testing</b>
	4.1	Measurement procedures
	4.2	Test conditions
	4.3	Noise measurements
	4.4	Noise measurement locations
	4.5	Vibration measurements
	4.6	Vibration measurement locations
	4.7	Approved technical organisation
<b>Section</b>	<b>5</b>	<b>Noise and vibration survey reporting</b>
	5.1	General
	5.2	Noise
	5.3	Vibration
<b>Section</b>	<b>6</b>	<b>Non-periodical survey requirements</b>
	6.1	Class notation assignment
	6.2	Maintenance of class notation through-life and following modifications
<b>Section</b>	<b>7</b>	<b>Referenced standards</b>
	7.1	Noise
	7.2	Vibration

# Controlled Atmosphere Systems

# Part 7, Chapter 1

Sections 1 & 2

## Section

- 1 **General requirements**
- 2 **Plans and documentation**
- 3 **CA zones and adjacent spaces**
- 4 **Gas systems**
- 5 **Relative humidity (RH)**
- 6 **Electrical installation**
- 7 **Control instrumentation and alarms**
- 8 **Safety requirements**
- 9 **Inspection and testing on completion**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 The requirements of this Chapter apply to refrigerated cargo ships where a Controlled Atmosphere (CA) notation is requested.

1.1.2 The requirements are additional to the classification requirements for refrigerated cargo installations contained in Pt 6, Ch 3.

1.1.3 Ships provided with CA systems which are approved, installed and tested in accordance with the following requirements will be eligible for the applicable class notation specified in Pt 1, Ch 2,2.5.2.

1.1.4 An example of a typical class notation on a refrigeration installation classed with Lloyd's Register (hereinafter referred to as 'LR'), fitted with a CA system built under Special Survey, would be:

✱ **Lloyd's RMC** to maintain a temperature  $-29^{\circ}\text{C}$  to  $+14^{\circ}\text{C}$  with sea temperature  $35^{\circ}\text{C}$  maximum.

✱ **CA (1–12% O<sub>2</sub>, 0–25% CO<sub>2</sub>) RH**

### 1.2 Novel arrangements and design

1.2.1 Where the proposed construction of the CA system, or CA zones, is novel in design, or involves the use of unusual materials or equivalent arrangements to those specified in the following sections, special tests may be required, and a suitable descriptive note may be assigned.

### 1.3 Definitions

1.3.1 **CA zone** means one or more cargo chambers enclosed in an air-tight envelope.

1.3.2 **Gas** means a suitable gaseous mixture to retard the metabolic process of fresh products.

1.3.3 **Gas system** means a system which controls the levels of oxygen and/or carbon dioxide.

1.3.4 **Adjacent space** means an enclosed space adjoining a CA zone separated by watertight bulkheads or decks penetrated by pipes, cables, ducts, doors, 'tween deck, etc.

## ■ Section 2 Plans and documentation

### 2.1 Plans of CA zones and adjacent spaces

2.1.1 The following plans and particulars of the CA zones and adjacent spaces are to be submitted in triplicate for approval before construction is commenced:

- (a) Capacity plan.
- (b) Location and installation of CA equipment.
- (c) Arrangement of CA zones in elevation and plan view.
- (d) Access arrangement.
- (e) Arrangement and use of spaces adjacent to CA zones.
- (f) Details of securing weather deck and 'tween deck hatch lids.
- (g) Details of securing gratings in way of hatch lids.
- (h) Details of weather deck and access hatch seals.
- (j) Door seals, scuppers, pipes, cables and ducts penetrating the decks, bulkheads, etc., together with proposed design conditions in the CA zones.
- (k) Specified leakage rate and proposals for its measurement.
- (l) Location of sampling points for CA gas and/or sensors in the CA zones and adjacent spaces.
- (m) Details of the gas supply piping system.
- (n) Details of gas freeing arrangements, including fans, valves, ducts and any interlocks.
- (o) Details of pressure/vacuum valves for protecting devices in CA zones, location of outlets from P/V valves and capacity calculations.
- (p) Details of security locks provided on entry to the hatch and manhole covers, and doors leading to CA zones and adjacent spaces.
- (q) Arrangements of ventilation systems for the gas generator compartment and other adjacent spaces adjoining CA zones.

# Controlled Atmosphere Systems

# Part 7, Chapter 1

Sections 2 & 3

## 2.2 Gas supply system

2.2.1 The following plans and particulars of the gas supply system, etc., are to be submitted in triplicate for approval, before construction is commenced:

- (a) Schematic arrangements of the proposed gas supply systems and, where applicable, details of compressors, pressure vessels, membranes, storage tanks, gas cylinders, control and relief valves and safety arrangements, including pressure set points of alarm and safety devices.
- (b) Capacities of gas supply systems at different oxygen and carbon dioxide levels, if applicable.

## 2.3 Humidifiers

2.3.1 Where applicable, the following plans and particulars of the humidification system, etc., are to be submitted in triplicate for approval, before construction is commenced:

- (a) Specification and capacity of the system.
- (b) Principles of operation and control of relative humidities under different operating conditions.
- (c) Details of proposed equipment, nozzles, pads, heaters, pumps, steam generator, compressors, water tanks, etc.
- (d) Layouts of the equipment and the positioning of sensors and controls.

## 2.4 Control equipment

2.4.1 The following plans and details of the control, alarm and safety systems for CA zones, gas supply compartment and other adjacent spaces, are to be submitted in triplicate before construction is commenced:

- (a) Line diagrams of all control circuits.
- (b) List of monitored, control and alarm points.
- (c) Details of computer systems, if fitted.
- (d) Location of control panels and consoles.
- (e) Controls of all valves and dampers fitted to CA zones.
- (f) Details of oxygen and carbon dioxide analysers and arrangements for calibration.
- (g) Relative humidity (RH) sensors and details of calibration.
- (h) Details of alarm system, including location of central control panel and audible and visual warning devices.

## 2.5 Electrical

2.5.1 In addition to the applicable requirements of Pt 6, Ch 2, 1.2, the following information and plans specific to the installed CA system are to be submitted in triplicate for approval, before construction is commenced:

- (a) Main power supply arrangement to the CA system.
- (b) Single-line diagram of the CA system which is to include rating of electrical machines, insulation type, size and current loading of cables and make, type and rating of protective devices.
- (c) A schedule of normal operating loads of CA system, estimated for the different operating conditions expected.

## 2.6 Testing

2.6.1 Details of the testing programme are to be submitted, including instrumentation to be used with range and calibration.

## Section 3 CA zones and adjacent spaces

### 3.1 Air-tightness of CA zones

3.1.1 The CA zones are to be made air-tight in accordance with the requirements in 9.3. Particular attention is to be paid to sealing of hatches, plugs and access doors in each CA zone. Double seals are to be fitted to each opening.

3.1.2 Openings for pipes, ducts, cables, sensors, sampling lines and other fittings passing through the decks and bulkheads are to be suitably sealed and made air-tight.

3.1.3 The liquid sealed traps from bilges and drains from the cooler trays are to be deep enough to withstand, when filled with liquid which will not evaporate or freeze, the design pressure in each CA zone when taking account of the ship's motion.

3.1.4 Air refreshing inlets and outlets are to be provided with isolating arrangements.

### 3.2 CA zone protection

3.2.1 Means are to be provided to protect CA zones against the effect of overpressure or vacuum.

3.2.2 At least two P/V valves are to be fitted in each CA zone. They are to be set for the design conditions of the CA zone.

3.2.3 Consideration will be given to the use of a single valve in combination with other suitable means of overpressure or vacuum protection.

3.2.4 The proposed P/V valves for each zone are to be of adequate size to release any excess pressure and to relieve the vacuum at maximum cooling rate.

3.2.5 P/V valve discharges are to be located at least 2 m above deck and 10 m away from any ventilation inlets. Discharge piping is to be arranged to preclude ingress of water, dirt or debris which may cause the equipment to malfunction.

3.2.6 Pressure sensors are to be installed in locations necessary to monitor pressure of all CA zones. Pressure sensors are to be installed away from fans, air inlets and outlets.

# Controlled Atmosphere Systems

# Part 7, Chapter 1

Sections 3 & 4

## 3.3 Gas freeing of CA zones

3.3.1 The arrangements for gas freeing of CA zones are to be capable of purging all parts of the zone to ensure a safe atmosphere.

3.3.2 Cargo air cooling fans and the air refreshing arrangements may be used for gas freeing operations.

3.3.3 Gas freeing outlets are to be led to a safe place in the atmosphere 2 m above the deck, away from accommodation spaces and intakes of the fans for accommodation.

## 3.4 Ventilation of adjacent spaces

3.4.1 Deckhouses and other adjacent spaces which require to be entered regularly are to be fitted with a positive pressure type mechanical ventilation system with a capacity of at least 10 air changes per hour capable of being controlled from outside these spaces.

3.4.2 Adjacent spaces not normally entered are to be provided with a mechanical ventilation system which can be permanent or portable to gas free the space prior to entry.

3.4.3 Ventilation inlets are to be arranged so as to minimize recycling any gas and are to be at least 10 m in the horizontal direction away from the ventilation outlets.

## Section 4 Gas systems

### 4.1 General

4.1.1 Means are to be provided to achieve and maintain the required oxygen and/or carbon dioxide levels in the CA zones. This may be accomplished by the use of stored gas, portable or fixed gas generating equipment or other equivalent arrangements. The arrangements are to be such that a single failure will not cause a complete loss of gas supply to the CA zones.

4.1.2 The gas system is to have sufficient capacity to make good any gas loss from the CA zones and to maintain a positive pressure in all CA zones.

4.1.3 The gas system is also to be able to:

- Deliver gas at 125 per cent of the specified flow rate with two compressors operating.
- Maintain the specified gas levels in all CA zones when operating 24 hours per day with one unit on stand-by.

4.1.4 Air intakes are to be located to ensure that contaminated air is not drawn into the compressors.

4.1.5 Where it is intended to supply gas by means of stored gas bottles, the arrangements are to be such that depleted bottles may be readily and safely disconnected and charged bottles readily connected.

## 4.2 Location

4.2.1 Fixed gas generating equipment, gas bottles or portable gas generators are to be located in a compartment reserved solely for their use. Such compartments are to be separated by a gastight bulkhead and/or deck from accommodation, service and control station spaces. Access to such compartments is to be only from the open deck.

4.2.2 Gas piping systems are not to be led through accommodation, service and machinery spaces or control stations.

## 4.3 Gas supply

4.3.1 The gas systems are to be designed so that the pressure which they can exert on any CA zone will not exceed the design pressure of the zone.

4.3.2 During initial operation, arrangements are to be made to vent the gas outlets from each generator to the atmosphere. All vents from gas generators are to be led to a safe location on the open deck.

4.3.3 Where gas generators use positive displacement compressors, a pressure relief device is to be provided to prevent excess pressure being developed on the discharge side of the compressor.

4.3.4 Suitable arrangements are to be provided to enable the supply main to be connected to an external supply.

4.3.5 Where it is intended that gas systems are to be operated unattended, the required CA zone environment is to be automatically controlled.

4.3.6 Means of controlling inadvertent release of nitrogen into CA zones, such as locked valves, are to be provided.

## 4.4 Gas supply compartment ventilation and alarm

4.4.1 The gas supply compartment is to be fitted with a mechanical extraction ventilation system providing a rate of at least 20 air changes per hour based on the total empty volume of the compartment.

4.4.2 Ventilation ducts from the gas generator/supply compartment are not to be led through accommodation, service and machinery spaces or control stations.

4.4.3 The air outlet duct is to be led to a safe place on the open deck.

4.4.4 The gas supply compartment is to be provided with a low oxygen alarm system.

# Controlled Atmosphere Systems

# Part 7, Chapter 1

Sections 5, 6 & 7

## Section 5 Relative humidity (RH)

### 5.1 Humidification

5.1.1 Where a humidification system is fitted, the following requirements are to be complied with:

- (a) The supply of fresh water for humidification is to be such as to minimize the risk of corrosion and contamination of the cargo.
- (b) To prevent damage or blockage in the humidification system caused by water freezing, the air, steam or water pipelines in the cargo chambers are to be installed to facilitate ease of drainage and are to be provided with suitable heating arrangements.

## Section 6 Electrical installation

### 6.1 General

6.1.1 In addition to the requirements of Pt 6, Ch 2, the following requirements are to be complied with:

- (a) The electrical power for the CA plant is to be provided from a separate feeder circuit from the main switch-board.
- (b) Under sea-going conditions, the number and rating of service generators are to be sufficient to supply the cargo refrigeration machinery and CA equipment in addition to the ship's essential services, when any one generating set is out of action.

## Section 7 Control instrumentation and alarms

### 7.1 General

7.1.1 An alarm system for monitoring the atmosphere in CA zones is to be installed which may be integral with the machinery space alarm system as required by Pt 6, Ch 1,2.3.

7.1.2 Where alarms are displayed as group alarms in the main machinery space alarm system, provision is to be made to identify individual alarms at the refrigerated cargo control station.

7.1.3 The pressure in each CA zone is to be monitored and an alarm initiated when the pressure is too high or too low.

7.1.4 Where the **RH** notation is to be assigned, humidity sensors are to be installed in each of the CA zones and are to initiate an alarm when the relative humidity (RH) falls below or exceeds the predetermined set values.

7.1.5 Gas sensors or analysers are to be provided to monitor gas content in CA zones, see 7.3 and 7.4.

7.1.6 Gas analysers and sensors are to be calibrated automatically once in every 24 hours. An alarm is to be initiated if accuracy is outside tolerance limits.

7.1.7 Direct readout of the gas quality within any CA zone is to be available to the operating staff on demand.

7.1.8 At least one automatic recorder is to be provided for the remote monitoring and recording of O<sub>2</sub> and CO<sub>2</sub> levels in each CA zone.

7.1.9 Alarms are to be initiated in the event of O<sub>2</sub> or CO<sub>2</sub> levels in each CA zone falling below or exceeding the predetermined set values.

### 7.2 Gas systems

7.2.1 Where air compressors are to be used for gas production, alarms are to be initiated for the following conditions:

- High lubricating oil temperature.
- High differential pressure across the filters.
- Electric supply failure.

The compressors are to shutdown automatically in the event of:

- High discharge air temperature.
- High discharge air pressure.
- Low lubricating oil pressure.
- High pressure in CA zone.

7.2.2 Instrumentation is to be fitted for indicating continuously:

- (a) Gas pressure.
- (b) Gas temperature.
- (c) Gas content.
- (d) Gas flow.

### 7.3 Gas analysers and sampling

7.3.1 Where analysers are fitted, at least two analysers for oxygen and carbon dioxide having a tolerance of  $\pm 0,1$  per cent by volume are to be provided to determine the content of the circulated gas within the CA zones.

7.3.2 Two separate sampling points are to be located in each CA zone and one sampling point in each of the adjacent spaces. The arrangements are to be such as to prevent water condensing and freezing in the sampling lines under normal operating conditions. Filters are to be provided at the inlet to sampling point lines.

7.3.3 Arrangements of the gas sampling points are to be such as to facilitate representative sampling of the gas in the space.

7.3.4 Where gas is extracted from the CA zones via a sampling tube to analysers outside the space, the sample gas is to be discharged safely to the open deck.



# Controlled Atmosphere Systems

# Part 7, Chapter 1

Sections 7, 8 & 9

7.3.5 Provision is to be made for gas sampling by means of portable equipment as required by 9.6.3.

7.3.6 The sampling frequency is to be at least once per hour.

## 7.4 Gas sensors

7.4.1 Where sensors are fitted, at least two sensors for each of O<sub>2</sub> and CO<sub>2</sub>, having a tolerance of ±0,1 per cent are to be installed in each CA zone to monitor gas levels.

7.4.2 Gas sensors may be used for indication and alarm.

## Section 8 Safety requirements

### 8.1 Personnel safety

8.1.1 CA zones are to be clearly labelled with 'Caution' and 'Danger' signs to alert personnel.

8.1.2 Entry hatch and manhole covers, doors leading to the CA zones and adjacent spaces are to be fitted with acceptable security-type locks and alarms activated when covers and doors are opened. The alarms are to be placed in a manned location.

8.1.3 All doors and access hatches to CA zones which may be under pressure are to open outwards and are to be fitted with secondary catches to prevent injury or damage during opening.

8.1.4 At least two portable oxygen sensors are to be provided to sample the oxygen level in all CA zones and adjacent spaces.

8.1.5 A means of communication is to be provided between CA zones and an attended location on deck.

8.1.6 Medical first aid equipment, including at least one set of oxygen resuscitation equipment, is to be provided on board.

## Section 9 Inspection and testing on completion

### 9.1 General

9.1.1 CA system trials are to be witnessed on board by the LR Surveyor, before the system is put into service and before a certificate is issued. These trials are in addition to any tests which may have been carried out at the manufacturer's works.

9.1.2 An Operating and Safety Manual for the guidance of the ship's staff is to be provided, covering the following topics:

- (a) Principal information on the use of CA.
- (b) Complete description of the CA installation on board.
- (c) Hazards of low oxygen atmospheres and consequential effects on human life.
- (d) Countermeasures when exposed to low oxygen atmospheres.
- (e) Instructions for operation, maintenance and calibration of all gas detectors.
- (f) Instructions for use of portable oxygen analysers with alarm for personal protection.
- (g) Prohibition of entry to spaces under CA.
- (h) Loading instructions prior to injection of gas.
- (i) Procedure for checking security of CA zones, doors and access hatches prior to injection of gas.
- (k) Gas freeing procedure for all CA zones.
- (l) Procedure for checking atmosphere of CA zones before entry.

### 9.2 Gas supply and sampling systems

9.2.1 The gas supply main and branches are to be pressure and leak tested. The test pressures are to be 1,5 and 1,0 times the design pressure respectively.

9.2.2 All gas sampling lines are to be leak tested using a vacuum or overpressure method.

### 9.3 Air-tightness of CA zones

9.3.1 Air-tightness of each CA zone is to be tested and the results entered on the certificate. The measured leakage rate of each zone is to be compared with the specified value.

9.3.2 Either a constant pressure method or a pressure decay method is to be used to determine the degree of air-tightness.

9.3.3 If the constant pressure method is used, the test is to be carried out at the design pressure of the CA zones.

9.3.4 If the pressure decay method is used, the time for the pressure to drop from 350 Pa to 150 Pa is to be measured and the leakage is to be calculated using the following formula:

$$A.L. = \frac{7,095 \times V}{t}$$

where

A.L. = air leakage, in m<sup>3</sup>/h

V = volume of zone, in m<sup>3</sup>

t = time, in seconds

7,095 = constant for 200 Pa pressure decay.

During this test, adjacent zones are to be kept at atmospheric pressure.

# Controlled Atmosphere Systems

## Part 7, Chapter 1

Section 9

### 9.4 Gas system performance

9.4.1 Capability of the gas system to supply the gas at the specified flow rate and condition is to be verified by tests.

9.4.2 If the notation conditions cannot be verified during testing, assignment of the notation is to be deferred until log book entries confirm the achievement of the specified conditions in every CA zone during a loaded passage.

### 9.5 Gas freeing

9.5.1 The gas freeing arrangements are to be tested to demonstrate that they are effective.

### 9.6 Safety, alarms and instrumentation

9.6.1 The control, alarm and safety systems are to be tested to demonstrate overall satisfactory performance of the control engineering installation. Testing is also to take account of the electrical power supply arrangements, see *also* Pt 6, Ch 1,2,3.

9.6.2 Locking arrangements of all CA zones and adjacent spaces where gas may accumulate, provision of warning notices at all entrances to such spaces, communication arrangements and operation of alarms, controls, etc., are to be examined.

9.6.3 The provision of portable gas detectors and personnel oxygen monitors are to be verified by the LR Surveyor. Suitable calibrated instruments for measuring the levels of O<sub>2</sub>, CO<sub>2</sub> and humidity, gas pressure and gas flow to the CA zones, are to be provided for testing. Their accuracy is to be verified.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Section 1

### Section

- 1 **Introduction**
- 2 **Class notations**
- 3 **Plans and particulars**
- 4 **Materials**
- 5 **Process plant characteristics**
- 6 **Hull construction**
- 7 **Mechanical equipment for the process plant**
- 8 **Boilers and other pressure vessels for the process plant**
- 9 **Pumping and piping systems for the process plant**
- 10 **Firing arrangements of steam boilers, fired pressure vessels, heaters, reformers, etc.**
- 11 **Electrical equipment for the process plant**
- 12 **Control engineering for the process plant**
- 13 **Plant blow-down systems**
- 14 **Plant flare gas systems**
- 15 **Supply and discharge arrangements for feedstock and product**
- 16 **Ventilation of the process plant and other spaces associated with the process plant operation**
- 17 **Gas detection**
- 18 **Fire protection, detection and extinction**

- 2 Ships which can navigate at sea, but whose plants are intended to be operated only while the ships are in harbour or similarly protected waters.
- 3 Specialized ships, including pontoons, barges and similar structures which are designed as sea transportation vehicles to carry non-operative process plants, but which are specially constructed to be fully supported by the sea bed when the plants are operative.

1.1.2 Each category in 1.1.1 may include provision for the storage of the products used in the process or processes concerned.

### 1.2 General

1.2.1 The Rules are framed on the understanding that ships will not be operated in environmental conditions more severe than those agreed for the design basis and approval, without the prior agreement of Lloyd's Register (hereinafter referred to as 'LR').

1.2.2 Except as indicated in this Chapter, the hull, propulsion machinery, auxiliary machinery, equipment for essential services of the ship, electrical installations and control engineering systems are to comply with the relevant Sections of Parts 3, 4, 5 and 6, the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk* and the *Rules for Ships for Liquefied Gases*, where applicable. Hulls made of reinforced or prestressed concrete will be specially considered.

1.2.3 The additional hull structural requirements for Category 3 ships to enable them to be satisfactorily grounded on prepared foundations will be specially considered. Full details of the intended foundations and the local conditions at the site are to be submitted for use in assessing the hull structural capability, etc.

1.2.4 Where the process plant is intended to operate in close proximity to bulk storage of feedstocks and/or products, further consideration may be necessary in addition to that contained in this Chapter, particularly with regard to the provision of effective separation, methods of storage, loading and discharging arrangements.

1.2.5 For ships of all categories in 1.1.1 except Category 1A, provision is to be made for purging, gas freeing, inerting or otherwise rendering safe the plant and process storage facilities before the ship proceeds to sea or changes location. The provisions to be adopted, if any, when a ship of Category 1A enters harbour will be specially considered.

1.2.6 In addition to the requirements for periodical surveys, a general examination of the ship, machinery and process plant is to be carried out by LR's Surveyors before and after a ship, of any category other than 1A, changes location. Every precaution is to be taken to ensure safety during such examination.

1.2.7 Requirements additional to those of this Chapter may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the process plant is intended to operate.

## Section 1 Introduction

### 1.1 Scope

1.1.1 This Chapter is intended for the classification of self-propelled or non-self-propelled ships with specialized structures which have plant installed on board for the processing of chemicals, liquefied gases and related products, and which fall into one of the following environmental categories:

- 1A Ships which have plants operable while navigating at sea.
- 1B Ships which have plants operable at sea, but only while the ship is attached to an offshore mooring facility.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 1 & 2

### 1.3 Classification of ship

1.3.1 A ship built in accordance with the requirements of this Chapter, or in accordance with requirements equivalent thereto, will be assigned an appropriate class in the *Register Book*, as indicated in Section 2, and will continue to be classed so long as it is found, upon examination at the prescribed surveys, to be maintained in a safe and efficient condition, *see also* 1.4.6.

1.3.2 For each category described in 1.1.1, classification covers the hull, containment systems for stored products, propulsion machinery, auxiliary machinery used for essential services, and equipment necessary to maintain a suitable environment within which the plant may safely operate.

1.3.3 In general, classification will not be extended to the process plant itself, and the classification requirements do not relate to the specialized machinery, equipment and associated piping, etc., which is solely concerned with the production operations, except where the design and/or arrangements of such equipment and piping may affect the safety of the vessel.

1.3.4 When the reliquefaction plant is installed, and the plant and equipment are in accordance with the requirements of the *Rules for Ships for Liquefied Gases*, consideration will be given to classing the plant in accordance with Pt 1, Ch 2.2.5.

### 1.4 Certification of process plant

1.4.1 Process plant will be required to be certified by LR, and a note to the effect that this has been carried out will be appended to the class notation in the *Register Book*.

1.4.2 The certificate will include a brief description of the process plant, indicating the chemical(s) processed and the end products.

1.4.3 The certificate of the plant will cease to be valid if a significant alteration is made to the plant or the arrangements on board without the written approval of LR. This provision does not exclude the direct replacement of any item by a substitute part which has been approved and tested by LR.

1.4.4 The process plant will be required to be surveyed by LR's Surveyors at intervals to be prescribed by the Committee, dependent on the process involved.

1.4.5 The class notation for the ship will, in general, state that the process plant is not classed but certificated by LR and periodically surveyed by LR's Surveyors.

1.4.6 The maintenance of the class of the ship while the plant is in operation will be dependent upon a valid certificate and the plant being found, upon examination at the prescribed surveys, to be maintained in a safe and efficient condition.

1.4.7 The plant certificate is not to be taken as a recommendation for, or an approval of, the process or processes.

### Section 2

#### Class notations

#### 2.1 Ship notations

2.1.1 Ships of Category 1A, which have chemical process plants designed to operate while the ship is navigating at sea, will be eligible to be classed '100A1 Chemical Process Factory', *see also* 1.4.5.

2.1.2 Ships of Category 1B, which have chemical plants designed for operation at sea while the ship is specially moored, anchored or otherwise linked to the shore, sea bed or other stationary vessel or structure, will be eligible to be classed '100A1(T) moored (oil, ammonia, etc.) processing (tanker, barge, etc.) for service at . . .', *see also* 1.4.5.

2.1.3 Ships of Category 2, which have chemical plants installed and designed for operation while the ship is in harbour, will be eligible to be classed '100A(T) chemical process plant installed – for operation only when moored in harbour', *see also* 1.4.5.

2.1.4 Specialized ships of Category 3 which have chemical plants designed to operate only while the ship is fully supported on the sea bed, will be eligible to be classed 'A chemical process plant pontoon/platform – to be operated only when grounded on prepared foundations at...', *see also* 1.4.5.

#### 2.2 Additional notations

2.2.1 A special chemical cargoes notation may be assigned to ships where raw materials or products are stored or retained on board in bulk.

2.2.2 The Committee may append details of process, product storage, safety or other particulars to the notation as it considers necessary.

2.2.3 Ships of Category 1B or 2 which have process plants installed solely for the purposes of the physical liquefaction of impure feedstock gases at low temperatures and the storage of the purified liquefied gases (where the chemical treatment of the impurities is an incidental process) will be assigned additional notations to those stated in 2.1.2 or 2.1.3, such as 'for liquefaction and storage of methane, etc., in independent tanks Type B, etc. – maximum pressure – minimum temperature'.

#### 2.3 Special mooring and linking arrangements

2.3.1 Where the process plant is operable only when the ship is specially moored, anchored or otherwise linked to the shore, sea bed or other stationary vessel, and the equipment and/or other linking arrangements and components have been approved by the Committee as suitable and sufficient for the intended service, an equipment character, T, will be assigned in addition, or as an alternative, to the equipment character, 1, as appropriate.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 2 &amp; 3

2.3.2 For the purpose of the Rules, the word 'linked' is to be taken to include spuds, retractable legs, floating or submerged pipelines connecting directly to the ship, ship to shore electrical connections, etc., which restrain the ship in its operating position, or which require such restraint to be applied and the failure of which could hazard the ship.

### Section 3 Plans and particulars

#### 3.1 General

3.1.1 Before the work is commenced, plans in triplicate, together with the relevant information as detailed in this Section, are to be submitted for consideration. Any subsequent modifications are subject to approval before being put into operation.

3.1.2 Any alterations to basic design, construction, materials, manufacturing procedure, equipment, fittings or arrangements of the process are to be re-submitted for approval.

3.1.3 For Category 1 ships, the plant is to be capable of sustaining an emergency condition at full operating temperatures and pressures with the hull statically listed to an angle of  $22\frac{1}{2}^\circ$  and statically trimmed to an angle of  $10^\circ$  beyond the maximum normal operating trim. These angles may be modified by the Committee in particular cases as it considers necessary. The stress calculations for the plant and the supporting structure are to take account of this condition. Wind loads need not be considered to be acting during this emergency condition.

3.1.4 For Category 2 ships, the plant is to be capable of sustaining an emergency condition at full operating temperatures and pressures with the hull statically listed to an angle of  $15^\circ$  and statically trimmed to an angle of  $5^\circ$  beyond the maximum normal operating trim. These angles may be modified by the Committee in particular cases as it considers necessary. The stress calculations for the plant and the supporting structure are to take account of this condition. Wind loads need not be considered to be acting during this emergency condition.

#### 3.2 Hull construction

3.2.1 For all categories of ship, the plans and information detailed in 3.2.2 to 3.2.6 are to be submitted, in addition to those required by Pt 3, Ch 1.5, Chapter IV of the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk* or Chapter IV of the *Rules for Ships for Liquefied Gases*, as applicable.

3.2.2 Plans showing the general arrangement of the ship are to be submitted, giving the location of the following:

- Hatches and other openings to enclosed plant spaces and adjacent cofferdams.
- Doors, hatches, ventilation and other openings to crew accommodation, stations essential for operation at sea, control stations, store rooms and workshops.

- Coated tanks or tanks constructed of special material.
- Additional structure associated with the plant above the deck.
- Proposed grouping of areas within the plant for segregation purposes.

3.2.3 Plans for mooring, anchoring and linking, as applicable, together with relevant wind and sea data are to be submitted for information.

3.2.4 Plans outlining the containment arrangements in the event of an accident, together with all relevant information, are to be submitted.

3.2.5 Particulars of the marine environment and safety arrangements associated with the process plant are to be submitted, including:

- Arrangements for preventing the ingress of water into the ship or structure where the process plant and equipment protrude through the weather deck.
- Proposed emergency flooding procedures and their control.

3.2.6 Particulars of the proposed storage arrangements of hazardous and/or toxic substances, feedstocks and products in bulk, on the ship or structure, are to be submitted.

#### 3.3 Process plant

3.3.1 A description of the expected method of operation of the process plant and a diagram showing the process flow are to be submitted.

3.3.2 General arrangement plans of the process plant showing the hazardous and safe zones and spaces are to be submitted, indicating the following:

- Spaces where toxic gases or vapours may accumulate.
- Spaces where flammable gases or vapours may accumulate.
- Areas maintained at an over-pressure to prevent the ingress of such gases or vapours.

3.3.3 Details of the flammability, toxicity, corrosivity and reactivity of the substances entering, being processed and leaving, or stored in, each compartment, together with details of any exothermic and hazardous reactions particularly with regard to sea-water and other materials normally found in the marine environment, are to be submitted.

3.3.4 Plans of the layout of the process plant indicating the hatches and other openings to enclosed plant spaces and cofferdams are to be submitted.

3.3.5 Details and arrangements of the blow-down systems, including quantities of materials and the capacity and working pressure of the containers installed for the reception of the materials to be blown down, are to be submitted.

3.3.6 Proposals for de-watering blow-down tanks in which hot oils and/or chemicals are discharged are to be submitted.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Section 3

3.3.7 Proposals for the purging, gas freeing, inerting or otherwise rendering safe of the process plant and storage facilities are to be submitted.

3.3.8 Particulars of the arrangements for protecting the process plant systems and vessels against temperature, over-pressure and vacuum are to be submitted.

3.3.9 Proposals for the disposal of hazardous or toxic gases and liquid effluents during normal plant operation, including any proposed flare systems, are to be submitted.

3.3.10 Particulars of the proposals for isolating the ship or structure from the shore installation and/or lightering ships or vessels, where applicable, and from the supply of fuel to boilers, etc., in the process plant and the return flow of chemicals or process effluent, are to be submitted, including:

- Feedstock supply and product discharge, with details of the arrangements showing the location of shut-off valves and of the control and indicating stations.
- The process plant parameters and analysis of transient conditions under which emergency shutdown will be initiated and the time estimated to obtain a safe environment.
- The proposed emergency procedures for controlled shutdown of the process plant, i.e. depressurizing, inerting, etc., and the arrangements for the continued operation of the essential services necessary to allow for such controlled shutdown under the emergency conditions of 3.1.3 or 3.1.4, as applicable.

3.3.11 Plans for the ventilation of process plant compartments are to be submitted, together with the following information:

- Location of hazardous and safe zones and spaces.
- Location of all possible sources of ignition.
- Location of air inlets and outlets.
- Number of complete air changes per hour.
- Estimated maximum and minimum ambient temperatures for the regions in which the plant is to operate.
- Expected heat loss of the process plant to the compartment environment.

3.3.12 Particulars of any dust or gas explosion hazard in the enclosed compartments of the process plant are to be submitted.

3.3.13 Proposals for the decontamination of the process plant compartments are to be submitted.

3.3.14 Proposals for the detection of vapour or gas and of oxygen deficiency in the process plant compartments are to be submitted.

### 3.4 Mechanical equipment associated with the process plant

3.4.1 A list of mechanical equipment associated with the process plant, with the exception of any boilers and other pressure vessels, to be installed in the ship or structure is to be submitted.

3.4.2 Details of safety and relief devices and their discharge arrangements are to be submitted.

3.4.3 When required, in order to facilitate inspection, plans showing the materials of construction, working pressures and temperatures, maximum power and revolutions per minute, as applicable, are to be submitted before the work is commenced.

3.4.4 Calculations of the torsional vibration characteristics of the shafting systems, where applicable, are to be submitted in accordance with the requirements of Pt 5, Ch 8.

### 3.5 Boilers and other pressure vessels associated with the process plant

3.5.1 Plans of the boilers and other pressure vessels, including the proposals for the support of the vessels, are to be submitted.

3.5.2 Details of the safety and relief devices and their discharge arrangements are to be submitted.

3.5.3 Stress calculations are to be submitted, taking into account the ship linear and angular accelerations, roll and pitch amplitudes, ship flexure and wind loads appropriate to any condition which may normally arise at sea. Where applicable, calculations for the emergency condition in 3.1.3 or 3.1.4 are to be submitted. Due consideration is to be given to the effects of thermal expansion and contraction on the support points of the vessels.

3.5.4 Outline plans of all types of fired equipment, ventilation arrangements with projected casing temperatures, uptake arrangements, gas and/or oil fuel burning arrangements and controls are to be submitted.

### 3.6 Pumping and piping systems associated with the process plant

3.6.1 Plans of the process plant piping systems, showing the materials of construction, scantlings, support and expansion arrangements, together with the calculations, are to be submitted for consideration.

3.6.2 The following diagrammatic plans for systems associated with the process plant are to be submitted, in addition to those required by Pt 5, Ch 13 and Ch 15 or Chapter V of the *Rules for Ships for Liquefied Gases*, as applicable:

- The Shipbuilder's plan of the general pumping arrangements, including air and sounding pipes and any cross flooding pipes and fittings.
- Pumping arrangements at the fore and aft ends, drainage of cofferdams and process spaces.
- Bilge, ballast and oil fuel pumping arrangements in the process plant machinery space, including the capacities of the pumps on bilge service.
- Arrangement of oil fuel pipes and fittings at settling and service tanks.
- Arrangement of gas and/or oil fuel piping in connection with gas and/or oil burning arrangements.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 3, 4 &amp; 5

- Oil fuel overflow systems, where fitted.
- Arrangement of boiler feed system.
- Arrangement of compressed air systems for the process plant.
- Arrangements of lubricating oil and cooling water systems, oil fuel settling, service and other oil tanks not forming part of the ship's structure.

3.6.3 Plans showing the arrangement and dimensions of main steam pipes, with details of flanges, bolts and weld attachments and particulars of the materials of the pipes, flanges, bolts and welding consumables, are to be submitted for consideration.

3.6.4 Details of the safety and relief devices and their discharge arrangements are to be submitted.

### 3.7 Electrical equipment for the process plant

3.7.1 Details of the electrical system(s) are to be submitted, including the following:

- A statement quoting the standard or Code of Practice in accordance with which the installation has been designed.
- A statement quoting the standard of design and/or manufacture of electrical equipment, e.g. BS, NEMA, VDE, etc.,
- A schedule of the normal operational loads on the system, estimated for the different operating conditions expected.
- Expected range of ambient temperature.

3.7.2 The following line diagram plans and particulars are to be submitted:

- General arrangement plan of the process plant showing the location of the major items of electrical equipment.
- Line diagram of the installation(s) indicating the rating of the various items of rotating machinery, converters, transformers and protective devices, together with the types and sizes of cables and the makes and types of protective devices.
- Arrangement plans and circuit diagrams of the switchboards.
- Calculations of short-circuit currents at the main switchboards, sub-switchboards and the secondary side of transformers.
- General arrangement plan of the process plant showing the location of electrical equipment in hazardous zones, together with the Code of Practice on which they are based.
- A schedule of safe-type electrical equipment located in hazardous zones, giving details of the type of equipment employed, the certifying authority and the certificate number.

3.7.3 Written confirmation and Works' Test Certificates that all items of electrical equipment comply with the relevant standard or Code of Practice are to be supplied.

### 3.8 Control equipment for the process plant

3.8.1 Details of the control system(s) are to be submitted, together with the following line diagrams and particulars:

- Line diagrams of any control system(s) fitted.
- General arrangement plan of the process plant showing the locations of items of control equipment and the locations of hazardous zones.
- Schedule of the parameters which are monitored and controlled, including alarms and shutdown devices.

### 3.9 Fire protection, detection and extinction

3.9.1 Plans of fire protection, detection and extinction arrangements, together with details of the fire and explosion hazards involved, are to be submitted.

## Section 4 Materials

### 4.1 General

4.1.1 The materials used in the construction are to be manufactured and tested in accordance with the requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials) and of Chapter 6 of the *Rules for Ships for Liquefied Gases*, as applicable. Materials for which provision is not made in those requirements may be accepted, provided that they comply with an approved specification and such tests as may be considered necessary.

4.1.2 Materials of construction are to be suitable for the intended service, having regard to the substances, process and temperatures involved. For materials unsuitable for use with certain chemicals, and for the protection of materials, see Chapter 6 of the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*.

4.1.3 Details of the materials proposed for all types of construction are to be submitted for approval.

## Section 5 Process plant characteristics

### 5.1 Design

5.1.1 The design and arrangements are to comply with the requirements of this Chapter and with relevant statutory regulations of the National Authority of the country in which the ship or structure is registered and/or in which it is to operate.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 5 & 6

5.1.2 The process plant is to be designed for normal operation in accordance with recognized and agreed codes suitably modified to take into account the ship-borne environment in all its aspects. Except for emergency conditions, as detailed in 3.1.3 or 3.1.4, the total stress in any component of the plant is not to exceed the code value at the temperature concerned, unless expressly agreed otherwise by LR, whether the plant is operative or non-operative, when subjected to any possible combination of the following loads:

- (a) Static and dynamic loads due to wave-induced ship motions.
- (b) Loads resulting from hull flexural effects at the plant support points.
- (c) Direct wind loads.
- (d) Normal process weights and pressures.
- (e) Thermal loads.

5.1.3 For the emergency conditions in 3.1.3 or 3.1.4, the stress levels are to be agreed with LR.

### 5.2 Separation from ship machinery

5.2.1 Where, during operation, process plant spaces contain or are likely to contain hazardous and/or toxic substances, they are to be kept separate and distinct from the main propulsion and auxiliary machinery and essential ship services, and also the power generating machinery for the process plant.

5.2.2 Notwithstanding the requirements of 5.2.1, this does not exclude the use of the ship's main, auxiliary and/or essential services, for process plant operation in suitable cases. Where, for reason of hazard, essential ship services have to be duplicated within the process plant space, they are to comply with the requirements of Section 9 and Parts 5 and 6, as applicable.

## Section 6 Hull construction

### 6.1 General

6.1.1 The hull structure is to comply with the relevant requirements of Parts 3 and 4, except as stated otherwise in this Section. The containment of liquefied gas products is to comply with Chapter 4 of the *Rules for Ships for Liquefied Gases*.

6.1.2 All chemical product and effluent tank structures and their location relative to the ship's hull are to comply with the *Rules for Ships for Liquefied Gases*, or with the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*, as applicable. Where necessary, the probable temperature variations during operations and the thermal stress considerations are to be stated.

6.1.3 Materials for the hull structures subjected to low temperature are to comply with Pt 3, Ch 2.2.2 relating to refrigerated spaces and adjacent structures, or with Chapter 6 of the *Rules for Ships for Liquefied Gases*, as applicable.

6.1.4 Subdivision and damage stability are not covered by these Rules. However, attention must be given to any relevant statutory regulations of the National Authority of the country in which the ship is to be registered or in which the plant is to be operated.

### 6.2 Location of accommodation, service and control spaces

6.2.1 All accommodation and other compartments not directly essential to the operation of the plant are to be arranged well clear of plant spaces, and feedstock and product tanks.

6.2.2 Service and control stations essential to the operation of the plant must be made 'gas-safe' in accordance with internationally accepted codes and standards, and should, wherever possible, be so located that access thereto is from a defined safe space. If such location is not possible, the station is to be specially ventilated.

### 6.3 Integrity of gastightness between compartments

6.3.1 Where integrity of gastightness is required between compartments containing the plant, this is to be maintained in way of pipe tunnels or duct keels where these traverse such compartments.

### 6.4 Cofferdams

6.4.1 Cofferdams are to be sited as required by the *Rules for Ships for Liquefied Gases*, or by the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*, as applicable, segregating any spaces in which raw materials or products are stored or retained in bulk.

6.4.2 Cofferdams are to be arranged around independent tanks containing chemical products or effluents where these are separate from the ship structure, but permanently connected thereto. Such cofferdams are to be mechanically ventilated using portable or permanent systems as required by Chapter 12 of the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*, and are to be of sufficient size to allow effective inspection of all the tank and ship structure in way.

### 6.5 Access and openings to spaces

6.5.1 Access openings, windows, side scuttles and ventilation openings to accommodation, service and control stations essential for the operation of the ship, and similar safe spaces are to be located and arranged, as required by the *Rules for Ships for Liquefied Gases*, or by the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*, as applicable.



# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Section 6

6.5.2 Arrangements are to be made to provide easy access to, or escape from, plant working spaces. In general, ladders are not to be arranged vertically, and intermediate platforms are to be fitted at vertical intervals of about 6 m. Ladders and platforms are to have guard rails and permanent provision made for attaching hoists for use in emergencies. The arrangements for the emergency hoists are to allow a clear, unobstructed lift to the outside deck.

6.5.3 Two separate means of access from the open deck are generally to be provided to the cofferdams required by 6.4.1.

### 6.6 Longitudinal strength

6.6.1 Longitudinal strength calculations are to be made in accordance with Pt 3, Ch 4 for the following conditions, and the Loading Manual required by Pt 3, Ch 4,8 is to include this information:

(a) **Sea-going conditions:**

These conditions are to take account of the weights and disposition of all ballast, plant items including any working fluids, other substances, spare gear, etc., and any special support bracing where thermal effects are considered, which will be on board during any sea-going condition of the plant appropriate to the category of ship.

(b) **Harbour condition:**

This condition is to take account of the weights and disposition of all ballast and plant items, including all working and other substances (in all intended stowage dispositions) and spare gear which will be on board during operation of the plant in harbour.

### 6.7 Plant support structure

6.7.1 Decks and other structure supporting the plant are, in general, to comply with the requirements of Part 3. Such structure can, however, be considered on the basis of an agreed uniformly distributed loading in association with local loads at plant support points, provided that adequate transverse strength of the ship is maintained.

6.7.2 Where the nature and dispositions of heavy plant items are such that forces on the ship and support structure due to ship motions are significant (whether underway with or without working fluids, or moored with working fluids), calculations of the loading and the structural response are to be submitted. In this respect, the guidance formulae for accelerations as given in the *Rules for Ships for Liquefied Gases* can be used where appropriate. Details of the mass distribution and support points of the plant items are to be submitted in all cases.

6.7.3 Where model tests or reliable direct calculation procedures are used to estimate wave-induced responses and which may indicate accelerations and motion amplitudes differing from those arising from the application of the Rules, such values will be taken into account in the approval of support structure.

6.7.4 If the vessel is intended for limited service at sea (e.g. a 'once only' voyage from port of build to service location), a reduction in the Rule accelerations and motion amplitudes may be permitted. In order to apply such a reduction, details of the intended service limitation should be submitted.

### 6.8 Loading due to wave-induced motions

6.8.1 In cases where the mass distribution of large columnar plant items is such that the centre of action of the dynamic force differs significantly from the centre of gravity of the item, due account of this is to be taken in the calculation of the forces and moments at the support positions.

### 6.9 Additional loads

6.9.1 The structure supporting the plant is also to be capable of withstanding forces arising from the following:

- (a) Wind loads (in all conditions of service and all categories of ships).
- (b) The angle of static heel arising from the emergency condition referred to in 3.1.3 or 3.1.4, as applicable.
- (c) For a Category 1A ship, a collision force acting on the tank corresponding to one-half of the weight of the item with or without working fluids, as appropriate, to the approved sea-going conditions from forward and one-quarter of the weight of the item from aft.
- (d) For all other categories of ship, a collision force from any horizontal direction of one-fifth of the weight of the item.

6.9.2 Wind loading, which is to be applied to the plant items and supporting structure protruding above the weather deck, should be considered to act simultaneously with wave-induced loading. Loadings 6.9.1(b), (c) and (d) need not be combined with wind loads or wave-induced loads.

### 6.10 Allowable stresses in support structure

6.10.1 The following stress levels are applicable in conjunction with the loading on the support structure:

- (a) Support members above or below the weather deck which are not subject to main hull girder loading:

direct stress:

$$\sigma_a + \sigma_b = 0,6\sigma_y$$

shear stress:

$$\tau = 0,6\tau_y \text{ or } 0,35\sigma_y \text{ whichever is the smaller combined stress:}$$

$$\sigma_c = 0,75\sigma_y = \sqrt{(\sigma_a + \sigma_b)^2 + 3\tau^2}$$

where

$\sigma_a + \sigma_b$  = the algebraic sum of the axial and bending stresses at the point under consideration

$\sigma_y$  = specified minimum tensile yield stress or 0,2 per cent proof stress at room temperature

$\tau_y$  = shear yield stress

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 6 & 7

- (b) Support members directly connected to hull structure and subject to transference of loading therefrom:
  - the maximum allowable direct, shear and combined stresses as defined in (a), but with member local loading increased by a factor of 1,30, or
  - when the stresses in such structure are determined using methods which satisfactorily take into account any ship deflection and load transference in way of supports, no load factor need be applied.
- (c) Primary members forming an integral ship structural and plant support system:
  - in general, the allowable stresses in such a system will be especially considered on the basis of the degree of refinement employed in the load prediction, structural response and stress analysis methods. Structural response calculations should include the interaction effects of the hull and plant item.

**6.10.2** In general, all seatings, platform decks, girders and pillars supporting plant items are to be arranged to align with the main hull structure, which is to be suitably reinforced, where necessary, to carry the appropriate loads. Attention should be paid to the capability of the support structure to withstand buckling.

### 6.11 Integrity of weather deck

**6.11.1** The integrity of the weather deck is to be maintained. Where items of plant equipment penetrate the weather deck and are intended to constitute the structural barrier to prevent the ingress of water to spaces below the freeboard deck, their structural strength is to be equivalent to the Rule requirements for this purpose. Otherwise, such items are to be enclosed in superstructures or deckhouses fully complying with the Rules. Full details are to be submitted for approval.

### 6.12 Equipment

**6.12.1** Anchors and chain cables for ships navigating at sea are to comply with the requirements of Pt 3, Ch 13,7. Special consideration will be given to the equipment required for ships of Categories 1B and 2.

### 6.13 Gangways and freeing arrangements

**6.13.1** Gangways are to be sufficient to provide proper access to all areas necessary for ship safety while the ship is operational and while it is at sea, and are to be to the Surveyor's satisfaction.

**6.13.2** Freeing ports are to be fitted in accordance with the requirements of Pt 3, Ch 8,5.3.

## Section 7

### Mechanical equipment for the process plant

#### 7.1 General

**7.1.1** The requirements of this Section are applicable to all types of mechanical equipment associated with the process plant, with the exception of boilers and other pressure vessels.

**7.1.2** The mechanical plant and equipment are to be designed and constructed in accordance with the relevant Sections of Part 5 and Pt 6, Ch 3, as applicable, and/or with agreed codes and specifications, suitably modified where necessary to suit shipboard conditions. The design is to be capable of accommodating the forces and moments stated in 6.7, 6.8 and 6.9, as applicable, generated at the support points.

#### 7.2 Safety precautions

**7.2.1** Oil engines, air compressors and associated air starting piping, concerned with supplying services not essential to the safety of the vessel or structure, are to comply with the requirements of Pt 5, Ch 2, where applicable.

**7.2.2** Air intakes for internal combustion engines are to be led from a safe space. Where internal combustion engines, other than gas turbines, are used in association with plant processing flammable substances, the air intakes are to be fitted with an automatic device to prevent overspeeding in the event of accidental ingestion of flammable gases and/or vapours.

**7.2.3** Exhaust pipes from internal combustion engines are to be led well clear of hazardous areas and, where such engines are used in association with plant processing flammable substances, are to be fitted with efficient spark arresters.

**7.2.4** In general, air compressors are not to be installed in hazardous areas. Where this is not practicable, alternative arrangements may be accepted, provided that the air inlets are trunked or ducted from a safe space and that such trunking/ducting is fitted with gas detectors arranged to give audible and visible alarms and to shutdown the compressor in the event of flammable and/or toxic gas or vapour entering the air inlets.

**7.2.5** The gas detectors are to be capable of continuously sampling the air supply and are to be so arranged as to prevent cross-communication between hazardous and safe spaces, such as control rooms, etc.

#### 7.3 Inspection and installation

**7.3.1** The scope of the inspection to be carried out at the manufacturers' works by the Surveyors is to be agreed before the work is commenced.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 7, 8 & 9

7.3.2 The mechanical plant and equipment are to be installed to the Surveyor's satisfaction. Proposals to site internal combustion engines in hazardous areas will be the subject of special consideration.

### ■ Section 8 Boilers and other pressure vessels for the process plant

#### 8.1 General

8.1.1 The requirements of this Section are applicable to fired and unfired pressure vessels associated with the process plant.

8.1.2 The pressure vessels are to be made in accordance with the requirements of the relevant Sections of Pt 5, Ch 10 or Ch 11, as applicable, or with agreed codes and specifications normally used for similar plant in land installations suitably modified and/or adapted for the marine environment. The design is to be capable of accommodating the forces and moments stated in 6.7, 6.8 and 6.9, as applicable, generated at the support points.

8.1.3 Stress calculations are to take account of the emergency conditions in 3.1.3 or 3.1.4, as applicable, in addition to the normal operational loadings. Due consideration is to be given to the effects of thermal expansion and contraction on the support points of the vessels.

#### 8.2 Construction and installation

8.2.1 The pressure vessels are to be constructed, installed and tested to the Surveyor's satisfaction.

8.2.2 Suitable access is to be provided to the vessels for inspection, including checks on the operation of mountings, fittings, controls and pressure relief devices.

#### 8.3 Safety devices

8.3.1 Where necessary, a test rig is to be supplied to enable the pressure setting of the safety and relief devices to be checked.

8.3.2 Where required, an additional pressure relieving device, with sufficient capacity (a) to prevent pressure vessels becoming liquid-full during fire engulfment and/or (b) to discharge vapours generated under fire exposure, is to be fitted in accordance with the relevant *Rules for Ships for Liquefied Gases*.

8.3.3 The arrangement of safety and relief discharges is to be such that there is no possibility of hazardous reaction between the substances involved.

8.3.4 Where provision is made for the isolation of safety relief devices from vessels and/or systems for maintenance purposes, not less than two such safety devices are to be fitted.

8.3.5 The isolating or blocking valves are to be so arranged that at least one safety relief device will remain in communication with the vessel or system under all conditions.

### ■ Section 9 Pumping and piping systems for the process plant

#### 9.1 General

9.1.1 Arrangements are to be made in the process plant spaces, in order that substances which are flammable, toxic or are likely to present a hazard due to reaction when mixed are kept separate.

#### 9.2 Process plant piping systems

9.2.1 Process plant piping systems are to be designed and constructed in accordance with agreed codes and specifications normally used for similar plants in land installations, suitably modified and/or adapted where necessary to suit the marine environment.

9.2.2 Sections of piping which may contain hazardous liquids or gases and which can be isolated are to be suitably protected, see 8.3.2.

#### 9.3 Lubricating oil and oil fuel piping

9.3.1 Lubricating oil and oil fuel pipes, fittings, associated equipment, oil fuel burning arrangements and their materials of construction are to comply with the requirements of Pt 5, Ch 14, where applicable.

#### 9.4 Gas fuel supply systems

9.4.1 The gas fuel supply systems are to comply with the requirements of the relevant Sections of the *Rules for Ships for Liquefied Gases*, where applicable.

9.4.2 Provision to shut off the gas is to be made in the gas firing supply lines immediately before the lines enter the compartment in which the equipment is installed. The shut-off arrangements are to be of the double block and vent type, and are to be operable at the equipment or the equipment control position and at a position in a safe area remote from the equipment.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 9 & 10

### 9.5 Air and sounding pipes

9.5.1 Details of air and sounding pipes to tanks containing chemical products are to be submitted for approval.

### 9.6 Bilge and effluent arrangements

9.6.1 The arrangements for the storage on board ship, and the disposal of bilge and effluent from the process plant spaces, are to be submitted for consideration, and due recognition is to be given to the requirements of the appropriate National Authority.

9.6.2 Bilge and effluent pumping and piping systems in the process plant spaces are to be constructed of material suitable for the substances processed or produced or any combination of the substances which might result from accidental admixture.

9.6.3 Arrangements are to be provided for the control of the bilge and effluent pumping and piping system installed in the process plant spaces from within these spaces and also from a position outside the spaces.

9.6.4 The bilge and effluent pumping and piping systems handling hazardous materials should, wherever possible, be installed in the space associated with the particular hazard. Spaces containing pumps and piping systems that take their suction from a hazardous space may also be considered as hazardous spaces where a pipeline is not of an all-welded construction without flanges, valve glands and bolted connections, etc., and the pumps are not totally enclosed.

9.6.5 Where, during operation, process plant spaces contain or are likely to contain hazardous and/or toxic substances, they are to be kept separate and distinct from the ship's main bilge pumping and piping system. This does not, however, preclude the use of the ship's main bilge system when the process plant is shutdown, gas freed or otherwise made safe.

9.6.6 Pumping and piping systems for the ship services and process plant are to be constructed and installed to the Surveyor's satisfaction.

## Section 10 Firing arrangements of steam boilers, fired pressure vessels, heaters, reformers, etc.

### 10.1 General

10.1.1 The requirements of this Section are applicable to all types of fired equipment associated with the process plant. The equipment is to be constructed, installed and tested to the Surveyor's satisfaction.

### 10.2 Design and construction

10.2.1 Details of the design and construction of the fuel gas burning equipment for steam boilers, oil and gas heater furnaces, reformers, etc., are to be in accordance with the *Rules for Ships for Liquefied Gases*, or with agreed codes and specifications normally used for similar plants in land installations, suitably modified and/or adapted for the marine environment. Ignition of the burners is to be by means of permanently installed igniters, or properly located and interlocked pilot burners and main burners arranged for sequential ignition.

10.2.2 Gas or gas/air mixtures having relative densities compared with that of air at the same temperature greater than one are not to be used as fuels for fired pressure vessels situated below deck. Proposals to burn such mixtures above deck will be specially considered in each case.

10.2.3 Proposals for the furnace purging arrangements prior to ignition of the burners are to be submitted. Such arrangements are to ensure that any accidental leakage of product liquid or gas into the furnace, from a liquid or gas heating element, or from the accidental ingestion of flammable gases and/or vapours, does not result in hazardous conditions.

10.2.4 Compartments containing fired pressure vessels, heaters, reformers, etc., for heating or processing hazardous substances are to be so arranged that the compartment in which the fired equipment is installed is maintained at a higher pressure than the combustion chamber of the equipment. For this purpose, induced draught fans or a closed stokehold system of forced draught may be employed. Alternatively, the fired equipment may be enclosed in a pressurized air casing.

10.2.5 The fired equipment is to be suitably lagged. The clearance spaces between the fired equipment and any tanks containing oil are to be not less than 760 mm. The compartments in which the fired equipment is installed are to be provided with an efficient ventilating system.

10.2.6 Smoke box and header box doors of fired equipment are to be well-fitting and shielded, and the uptake joints made gastight. Where it is proposed to install dampers in the uptake gas passages of fired equipment, the details are to be submitted. Dampers are to be provided with a suitable device whereby they may be securely locked in the fully open position.

10.2.7 Each item of fired equipment is to have a separate uptake to the top of the stack casing. Where it is proposed to install process fired equipment with separately fixed furnaces converging into a convection section common to two or more furnaces and/or a secondary radiant section at the confluence of the fired furnace uptake to the convection section, the proposed arrangements, together with the details of the furnace purging and combustion controls, are to be submitted.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 11 to 14

### ■ Section 11 Electrical equipment for the process plant

#### 11.1 Design of installation

11.1.1 Installations are to be designed in accordance with Pt 6, Ch 2, or with a recognized National or International Standard or Code of Practice.

11.1.2 Attention must be given to any relevant statutory regulations of the National Authority of the country in which the ship is to be registered or in which the process plant is to be operated.

#### 11.2 Equipment suitability for environment

11.2.1 Electrical equipment is to be constructed so that it is suitable for use in the environmental conditions envisaged, e.g. in areas of high ambient temperature, derating may be necessary.

#### 11.3 Hazardous zones

11.3.1 Where flammable gases and vapours are involved, the defining of hazardous zones is to be in accordance with a National or International Standard or Code of Practice.

#### 11.4 Certified safe-type equipment

11.4.1 Where safe-type equipment is permitted in hazardous zones, e.g.:

- Intrinsically-safe (symbol i),
- Flameproof (symbol d),
- Increased safety (symbol e),
- Pressurized enclosure (symbol p),

such equipment is to be certified for the gases and vapours involved. The construction and type testing are to be in accordance with IEC 60079: *Electrical Apparatus for Explosive Gas Atmospheres*, or an equivalent National Standard.

#### 11.5 Survey and testing

11.5.1 All electrical equipment is to be installed and tested to the Surveyor's satisfaction.

### ■ Section 12 Control engineering for the process plant

#### 12.1 Design of installation

12.1.1 Normal good engineering practice and standards are to be employed in any control system(s) fitted.

12.1.2 Due to the wide variety of types of process plant, it is not possible to lay down precise details of control scheme(s), since any control scheme is affected by the nature of, and the operating procedures of, the process plant. A description of the expected method of operation of the process plant is to be submitted.

#### 12.2 Equipment

12.2.1 Control equipment is to be compatible with the materials involved in the plant process.

12.2.2 Where flammable gases or vapours are involved, control equipment located in hazardous zones is to be of certified safe-type.

#### 12.3 Survey and testing

12.3.1 Control system(s) are to be installed and tested to the Surveyor's satisfaction.

### ■ Section 13 Plant blow-down systems

#### 13.1 General

13.1.1 Where a liquid blow-down system is provided in the process plant, the design and installation are to make adequate provision for the effects of back pressure in the system and vapour flash off when the pressures of liquids in the blow-down system are reduced.

13.1.2 Substances which will react with each other are to be provided with separate systems.

### ■ Section 14 Plant flare gas systems

#### 14.1 General

14.1.1 Details of any flare gas stack system and proposals for installation on board the ships, including safety arrangements, are to be submitted for consideration.

14.1.2 The protection zone around the nozzle of the flare gas stack is dependent upon the limiting radiation intensity under all conditions and, also, whether suitable radiation screens are provided. The flare gas stack is to be located so that the nozzle is situated not less than the radius of the protection zone or 50 m, whichever is the greater, from equipment and manned stations, etc.

14.1.3 The arrangements are to ensure that combustion of the flare gas is complete and safe at all times.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 15 & 16

### ■ Section 15 Supply and discharge arrangements for feedstock and product

#### 15.1 General

15.1.1 Arrangements are to be made to isolate the ship from the supply of feedstock for processing, the supply of oil fuel or gas to boilers, heaters, etc., and the return flow of product, chemicals or process effluent, blow-down or flare gas, etc.

15.1.2 The arrangements are to provide for valves installed at the shore connection, where applicable, and on board ship which are to be operable from shut-off control and indicating stations on the ship, on the shore, and at the valves.

#### 15.2 Emergency procedures

15.2.1 Detailed instructions of the emergency shutdown and evacuation procedure are to be posted in a prominent position at the ship and shore control stations, where applicable.

### ■ Section 16 Ventilation of the process plant and other spaces associated with the process plant operation

#### 16.1 General

16.1.1 An efficient means of ventilation is to be provided for all enclosed compartments associated with the operation of the process plant.

16.1.2 The capacity of the ventilation systems is to comply with the requirements of Pt 5, Ch 15,1.7 or the *Rules for Ships for Liquefied Gases*, or Chapter 12 of the *Rules for Ships for the Carriage of Liquid Chemicals in Bulk*, where applicable, or to an acceptable Code of Practice suitably modified and/or adapted where necessary to suit the marine environment. It is to be related to the hazard and/or environmental consideration of manned spaces during normal operation, and take into account additional requirements which may be necessary during start-up procedures.

#### 16.2 Design and construction

16.2.1 Hazardous compartments where flammable and/or toxic substances are being processed or produced are to be arranged for underpressure ventilation, except as stated in 10.2.4.

16.2.2 Safe compartments, including control rooms, are to be arranged for overpressure ventilation.

16.2.3 The number and capacity of fans are to be such that the minimum ventilation capacity required in each compartment is maintained at all times, with one unit out of service. If internal combustion engines are proposed, their fuel supply is to be kept separate from any other system. Electric motors are to be supplied by two alternative circuits, each of which is capable of supplying all the motors which are normally connected to that circuit and which are operated simultaneously.

16.2.4 The mechanical ventilation system is to be capable of being controlled from a position outside the compartment being ventilated.

16.2.5 Reduction of ventilation capacity below the required level should be indicated in the compartment and also in the control room by an audible and visible alarm.

16.2.6 The parts of the rotating body and of the casing of each fan situated in a hazardous space are to be made of recognized spark-proof materials. If non-metallic materials are used, they are to have anti-static properties.

16.2.7 Ventilation trunking or ducting is to be suitably coated or painted, or made from material suitable for the substances processed or produced, or any combination of the substances which might result from accidental admixture.

#### 16.3 Air inlets and discharges

16.3.1 The air inlets for the ventilation systems are to be located in a designated safe area.

16.3.2 The air inlets and discharges of the ventilation system are to be so situated that recirculation of the vented vapours does not occur.

16.3.3 The discharges from ventilation systems which may contain vapours that present a hazard due to reaction with each other are to be effectively segregated.

16.3.4 The discharges from ventilation systems which may contain hazardous vapours are to be located not less than 10 m from the nearest air intake or opening to accommodation, service and control station spaces or other safe spaces, and from all possible sources of ignition.

16.3.5 Air intakes and openings into the accommodation spaces and all service and control station spaces are to be fitted with closing devices. For toxic gases, these devices are to be operable from inside the space.

16.3.6 Where it is impracticable to locate a plant service or control station so that any access thereto is from a safe space, the service or control station is to be maintained at an overpressure of not less than 5 mm water gauge above the surrounding spaces. Details of the arrangements to ensure that this pressure differential is maintained are to be submitted.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Sections 16, 17 &amp; 18

16.3.7 Airlocks for intercompartmental access doors and emergency escape trunks are to have separate ventilation systems so arranged that an overpressure of 5 mm water gauge is maintained above the adjacent compartments. Details of the arrangements to ensure that this pressure differential is maintained are to be submitted.

### 16.4 Installation and inspection

16.4.1 The ventilation systems are to be installed to the Surveyor's satisfaction.

16.4.2 The Surveyors are to be satisfied that the ventilation system is capable of maintaining a safe environment during process plant operation. This may require monitoring over an extended period to prove its effectiveness.

## Section 17 Gas detection

### 17.1 General

17.1.1 An efficient gas detection system, suitable for the gases and/or vapours being processed or produced, and for the measurement of oxygen levels in the process plant compartments, is to be provided. Gas detector systems are also to comply with the requirements of Section 17 or of Chapter 13 of the *Rules for Ships for Liquefied Gases*, where applicable.

### 17.2 Design and construction

17.2.1 The equipment is to consist of a permanently fixed installation and at least two sets of portable equipment suitable for the process or products involved.

17.2.2 The position and number of fixed sampling points should be determined with due regard to the density of the gases and/or vapours of the substances processed or produced, and the dilution resulting from compartment ventilation. In each case, a sufficient number of sampling points are to be provided to give efficient selective sequential sampling to maintain a safe environment.

17.2.3 Unmanned or closed compartments, such as cofferdams, etc., associated with plant processing or producing flammable or toxic substances, are to have permanently installed sampling points suitable for use with portable detection equipment to be used before entry of the spaces by personnel and thereafter continuously while occupied by them.

17.2.4 Arrangements of the sampling point pipe runs are to be such that there is no possibility of hazardous gases and/or vapours entering a safe space. Common sampling lines to the detection equipment are not to be fitted.

17.2.5 The permanently installed gas detection system is to give audible and visible alarm, both in the control station and within the compartment, during hazardous conditions.

17.2.6 Except where continuous sampling is required (i.e. as in 7.2.5), the gas detection equipment should be capable of sampling and analysing from each sampling point at agreed intervals, which are in no case to exceed 30 minutes.

17.2.7 The gas detection equipment is to be designed so that it may be readily and regularly tested and calibrated. Suitable equipment and span gas is to be provided for this purpose. In addition, regular checking procedures with portable equipment are to be provided, particularly for closed or unmanned spaces during process plant operation.

17.2.8 Where equipment for detecting the specific flammable, toxic or asphyxiate substances which may be present in process plant spaces cannot be provided, full details are to be submitted, including personnel protection requirements and arrangements for decontaminating such spaces if necessary.

### 17.3 Installation

17.3.1 The gas detection system is to be installed to the Surveyor's satisfaction.

## Section 18 Fire protection, detection and extinction

### 18.1 General

18.1.1 The requirements of SOLAS Chapter II-2 and the *Rules for Ships for Liquefied Gases* are to be complied with, so far as they are applicable. Additional protection, consistent with the fire hazard involved, may be required for process plant control stations, and accommodation spaces. For the position of accommodation spaces relative to the process plant, see 6.2.

18.1.2 Where the design of the process plant is such that it may be operated only while the vessel or floating structure is specially moored, anchored or otherwise linked close to the shore, consideration will be given to a shore-based fire-fighting facility, taking account of the particular hazards involved.

### 18.2 Design arrangements

18.2.1 Arrangements are to be made in enclosed process plant spaces to prevent contact of dangerously interreactive substances and of flammable materials with sources of ignition. In general, compartments containing process plant are not to exceed 40 m in length, and the boundary bulkheads are to be 'A' Class divisions.

# Ships with Installed Process Plant for Chemicals, Liquefied Gases and Related Products

## Part 7, Chapter 2

Section 18

18.2.2 Where, during operation, process plant spaces or adjacent hazardous zones contain or are likely to contain flammable and/or explosive mixtures, special consideration is to be given to the exclusion of all possible sources of ignition.

18.2.3 All heated surfaces, e.g. exhaust pipes, boiler uptakes and steam pipes, are to be effectively lagged or cooled, so that the maximum temperature, °C, of the surfaces is, in general, not to exceed 70 per cent of the auto-ignition temperature, °C, of any substances which may be present in the compartment. In no case is the difference in these temperatures to be less than 50°C.

18.2.4 Compartments where a fire hazard exists and which are not continuously manned are to be provided with an approved fire detection system which shall give visible and audible warning of the location of the fire in the control station and, for plant operating at sea (Category 1A), at the navigating bridge control position.

18.2.5 The fire main is to be so arranged, and hoses and nozzles provided, that any part of the compartments or structure associated with the process plant can be reached with two powerful jets of water, one of which shall be produced by a single length of hose. The hoses are to be provided with dual-purpose nozzles capable of producing a jet or a spray. Special consideration will be given to an exemption from this requirement in respect of compartments where the use of water would in itself constitute a hazard.

18.2.6 Each compartment where the fire hazard so demands is to be provided with an approved fixed fire-extinguishing system capable of extinguishing fires involving the materials present. Operation of such a system at its required output is not to prevent the simultaneous use of the required jets of water from the fire main. Where carbon dioxide systems and Halon systems are fitted, due consideration should be given to the danger of static electricity.

18.2.7 An adequate number of portable fire extinguishers are to be provided in each compartment where a fire hazard exists. The number of such extinguishers will be decided in relation to the nature of the hazard and the layout of the compartment, but shall not be less than two, one of which is to be positioned near the entrance. The extinguishing medium is to be considered in relation to the nature of the hazard involved.

18.2.8 Means are to be provided for stopping all fans and, where practicable, closing all openings which might admit air to the compartment. Such means should be capable of being operated from a position outside the compartment and not likely to be rendered inaccessible by a fire in the compartment.

18.2.9 Means are to be provided for stopping the supply of combustible materials to the compartment in the event of fire.

18.2.10 The provision of additional fireman's outfits, each complying with the requirements of SOLAS Reg. II-2/A, 17, and the necessity for protective clothing, will be specially considered in relation to the layout of the process plant and the hazards involved.



# Fire-fighting Ships

# Part 7, Chapter 3

Section 1

## Section

- 1 **General**
- 2 **Construction**
- 3 **Fire-extinguishing**
- 4 **Fire protection**
- 5 **Lighting**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to ships intended for fire-fighting operations and are additional to those applicable in other Parts.

1.1.2 A ship provided with fire protection and fire-fighting equipment in accordance with these Rules will be eligible for an appropriate class notation which will be recorded in the *Register Book*.

1.1.3 Requirements additional to these Rules may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the fire-fighting ship is intended to operate.

### 1.2 Classification and class notations

1.2.1 The class notations which may be assigned are:

- 'Fire-fighting ship 1 (total monitor discharge capacity in brackets)',
- 'Fire-fighting ship 2 (total monitor discharge capacity in brackets)',
- 'Fire-fighting ship 3 (total monitor discharge capacity in brackets)',
- 'Fire-fighting ship 1 (total monitor discharge capacity in brackets) with water spray',
- 'Fire-fighting ship 2 (total monitor discharge capacity in brackets) with water spray',
- 'Fire-fighting ship 3 (total monitor discharge capacity in brackets) with water spray'.

1.2.2 The notation **Fire-fighting ship 1**, **Fire-fighting ship 2** or **Fire-fighting ship 3** signifies that a ship complies with these Rules and is provided with the appropriate fire-fighting equipment described in Table 3.1.1, with the total discharge capacity of monitors in m<sup>3</sup>/h shown in brackets.

1.2.3 The addition of the words 'with water spray' to the notations referred to in 1.2.1 signifies that a ship is provided with a water spray system, which will provide an effective cooling spray of water over the vertical surfaces of the ship to enable it to approach a burning installation for fire-fighting purposes. The requirements for such a system are set out in 4.2.

**Table 3.1.1 Fire-fighting equipment**

Equipment	Fire-fighting ship		
	1	2	3
Minimum total pump capacity, m <sup>3</sup> /h	2400	7200	10 000
Minimum number of water monitors	2	3	4
Minimum discharge rate per monitor, m <sup>3</sup> /h	1200	1800	1800
Minimum height of trajectory of jets of monitors above sea level, metres	45	70	70
Minimum range of monitor jets, m	120	150	150
Minimum fuel capacity for monitors, hours	24	96	96
Number of hose connections each side of ship	4	8	8
Number of fireman's outfits	4	8	8

### 1.3 Surveys

1.3.1 The arrangements and equipment referred to in this Chapter are to be examined and tested under working conditions on completion of the installation and, subsequently, annually.

### 1.4 Submission of plans

1.4.1 The following plans and information are to be submitted:

- A general arrangement showing the disposition of all fire-fighting equipment required by this Chapter.
- Details of major items of fire-fighting equipment, such as pumps and monitors, including their capacity, range and trajectory of delivery.
- A general arrangement plan showing the disposition of fire divisions and their class.
- Detailed plans of the fire divisions and, where applicable, copies of the certificates of approval for the insulating materials proposed.
- A plan of the construction of the fire doors.
- Plans showing the layout and capacity of the water spray system.
- A plan of the seating arrangements for the water monitors.
- Particulars of the means of keeping the ship in position during fire-fighting operations.
- A plan showing the fire pumps, the fire water main, the hydrants, hoses and hose nozzles and the monitors, together with particulars of their delivery capability.
- Details of the fireman's outfits provided.
- Plans of any other fire-fighting systems provided.

# Fire-fighting Ships

# Part 7, Chapter 3

Sections 1, 2 & 3

## 1.5 Definitions

1.5.1 'A-60 standard' means a fire-resisting construction of steel or other equivalent material, which is suitably stiffened and so constructed as to be capable of preventing the passage of smoke and flame for the complete period of the one-hour standard fire test. It is to be insulated with approved non-combustible materials, so that the average temperature on the unexposed side will not rise by more than 139°C above the original temperature, nor will the temperature at any one point, including any joint, rise more than 180°C above the original temperature within 60 minutes.

1.5.2 'Steel or other equivalent material'. In this context, 'equivalent material' means any material which, by itself or due to insulation provided, has structural and integrity properties equivalent to steel at the end of the applicable standard fire test exposure period (e.g. aluminium with appropriate insulation).

1.5.3 'The standard fire test' is one in which specimens of the relevant bulkheads or decks, having a surface area of approximately 4,65 m<sup>2</sup> and a height of 2,44 m, resembling as closely as possible the intended construction and including, where appropriate, at least one joint, are exposed in a test furnace to heat on a time-temperature relationship, approximately as follows:

- At the end of the first 5 minutes, 538°C.
- At the end of the first 10 minutes, 704°C.
- At the end of the first 30 minutes, 843°C.
- At the end of the first 60 minutes, 927°C.

1.5.4 A 'non-combustible material' means a material which neither burns nor gives off flammable vapours in sufficient quantity for self-ignition when heated to approximately 750°C. Any other material is a 'combustible material'.

## Section 2 Construction

### 2.1 Hull

2.1.1 The structure of the ship is to be strengthened as necessary to withstand the forces imposed by the fire-extinguishing systems when operating at their maximum capacity.

### 2.2 Sea suction

2.2.1 The sea suction of the fire pumps are to be arranged as low as practicable in the ship's structure to avoid icing or the ingress of oil from the surface of the sea.

2.2.2 All sea inlet valves are to be provided with a low pressure steam or compressed air connection for clearing purposes.

## 2.3 Stability

2.3.1 Each ship is to comply with the draught and stability requirements of the National Authority and is to have on board sufficient stability data to enable the ship to be properly loaded and handled. This data is to take full account of the effect of the monitors when they are operating at their maximum output in all possible directions of use.

## 2.4 Manoeuvrability

2.4.1 Arrangements are to be provided to enable the ship to maintain position, so that the monitors may be effectively deployed.

## 2.5 Bunkering

2.5.1 The Owner should ensure that any fuel which may be required while the ship is operating on station can be safely received on board.

## Section 3 Fire-extinguishing

### 3.1 Water monitors

3.1.1 The minimum number of monitors, their discharge rate, their range and their height of trajectory above sea level are to comply with the requirements of Table 3.1.1.

3.1.2 The monitors are to be so arranged that the required direction, range and height of trajectory can be achieved separately, with the required number of monitors operating simultaneously.

3.1.3 The monitors are to be capable of adequate adjustment in the vertical and horizontal direction and are to be so positioned that the jets will be unimpeded within the required range of operation.

3.1.4 Means are to be provided for preventing the monitor jets from impinging on the ship's structure and equipment.

3.1.5 The monitors are to be capable of being activated and manoeuvred by remote control from a protected position providing a good view of the monitors and the operating area of the water jets.

3.1.6 The monitors are to be of robust construction and their seating arrangements are to be of adequate strength for all modes of operation, particular attention being paid to shock loading when all the monitors are activated simultaneously.

# Fire-fighting Ships

## Part 7, Chapter 3

Sections 3 &amp; 4

3.1.7 For the class notations **Fire-fighting ship 2** and **Fire-fighting ship 3**, an arrangement with one less monitor than required in Table 3.1.1 may be considered as an equivalent solution. In such cases the total pump capacity is to be as required in Table 3.1.1. The minimum range of monitor jets and minimum height of trajectory of jets of monitors above sea level are to be 180 m and 110 m, respectively.

### 3.2 Pumps

3.2.1 The pumps and their piping system which are intended for serving the monitors are not to be available for services other than fire-extinguishing and water spraying. They are to be provided with independent sea inlets.

3.2.2 Where the pumps are used for fixed water spray systems, the piping is to be independent of that supplying the monitors. The water spray systems are to be adequately protected against overpressure.

3.2.3 The minimum total pump capacities required are shown in Table 3.1.1.

3.2.4 For assignment of the notations **Fire-fighting ship 2** or **Fire-fighting ship 3**, there are to be at least two pumps serving the monitors and they should be of approximately equal capacity. For assignment of the notation **Fire-fighting ship 1**, one pump only need be provided.

### 3.3 Hose stations

3.3.1 Hose stations are to be provided on each side of the ship in accordance with Table 3.1.1.

3.3.2 Each hose station is to be provided with a hydrant, a hose and a nozzle capable of producing a jet or a spray and simultaneously a jet and a spray. The hoses are to be 15 m in length and not less than 38 mm nor more than 65 mm in diameter. Where hose stations are connected to the monitor supply lines, provision is to be made to reduce the water pressure at the hydrants to an amount at which each fire hose nozzle can be safely handled by one man. The water pressure shall be sufficient to produce a water jet throw of at least 12 m.

### 3.4 Fireman's outfits

3.4.1 The number of fireman's outfits provided, in addition to those provided in accordance with Pt 6, Ch 4,12 or SOLAS Reg. II-2/A, 17 as applicable, is to be in accordance with Table 3.1.1. They are to be stored in a safe position which is readily accessible from the open deck.

3.4.2 The composition of a fireman's outfit is to be as follows:

- Protective clothing of material to protect the skin from heat radiating from the fire and from burns and scalding by steam. The outer surface is to be water-resistant.
- Boots and gloves of rubber or other electrically non-conducting material.
- A rigid helmet providing effective protection against impact.
- An electric safety lamp (hand lantern) of an approved type with a minimum operating period of three hours.
- An axe having an insulated handle.
- A self-contained breathing apparatus, which is to be capable of functioning for a period of at least 30 minutes and having a capacity of at least 1200 litres of free air. Spare, fully charged air bottles are to be provided at the rate of at least one set per required apparatus.
- For each breathing apparatus, a fireproof lifeline of sufficient length and strength is to be provided capable of being attached by means of a snaphook to the harness of the apparatus or to a separate belt, in order to prevent the breathing apparatus becoming detached when the life-line is operated.

### 3.5 Recharging of equipment

3.5.1 A suitable air compressor for recharging the bottles used in the breathing apparatus of the fireman's outfits is to be provided. It is to be capable of recharging the bottles of the breathing apparatus required to be carried, in accordance with Table 3.1.1, in a time not exceeding 30 minutes.

## Section 4 Fire protection

### 4.1 General

4.1.1 In ships which are not provided with a water spray system as described in 4.2 all windows and port lights are to be provided with efficient deadlights or external steel shutters, except in the wheelhouse.

### 4.2 Water spray systems

4.2.1 Ships which are intended to operate in close proximity to a large fire will require protection from the heat radiated from the fire. Such protection may be afforded by a system which provides a water spray over the surface of the ship, or by a combination of insulation and a water spray system.

4.2.2 The water spray system is to be a fixed system which is capable of delivering a spray of water over all the exposed external vertical surfaces of the hull in the lightest sea-going condition, including the superstructures and deck-houses and over the monitor position. The water spray system will also be required to cover the areas of deck which form the crowns of machinery spaces and other spaces containing combustible materials.

# Fire-fighting Ships

## Part 7, Chapter 3

Sections 4 & 5

4.2.3 The system is to have a capacity of 10 litres/min per m<sup>2</sup> of the protected area of uninsulated steel and 5 litres/min per m<sup>2</sup> of the protected area which is insulated internally to A-60 standard.

4.2.4 The system is to be divided into sections, so that it will be possible to close down sections covering surfaces which are not exposed to radiant heat.

4.2.5 The nozzles are to be arranged to give an even distribution of water spray over the protected area.

4.2.6 The pumping capacity is to be sufficient to supply simultaneously at the required pressure the sections which serve the maximum area which may be exposed to radiant heat from a fire. If the main fire pumps are used for this purpose, they are to be capable of operating this system and the monitors and hose stations simultaneously at the required pressures, see also 3.2.2.

4.2.7 Deck scuppers and freeing ports are to be of sufficient area to ensure efficient drainage of water from decks and horizontal surfaces in all conditions when the water spray system is in operation.

## ■ Section 5 Lighting

### 5.1 General

5.1.1 Two searchlights should be provided for illuminating the burning structure and facilitate the effective deployment of the water monitors at night.

5.1.2 The searchlights are to be capable of providing at a range of 250 m in clear atmospheric conditions a level of illumination of 50 lux within an area of not less than 11 m diameter. They are to be capable of being adjusted in the horizontal and vertical directions.

# Dynamic Positioning Systems

# Part 7, Chapter 4

Section 1

## Section

- 1 **General**
- 2 **Class notation DP(CM)**
- 3 **Class notation DP(AM)**
- 4 **Class notation DP(AA)**
- 5 **Class notation DP(AAA)**
- 6 **Performance Capability Rating (PCR)**
- 7 **Testing**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to ships with installed dynamic positioning systems and are additional to those applicable in other Parts of these Rules.

1.1.2 A ship provided with a dynamic positioning system in accordance with these Rules will be eligible for an appropriate class notation which will be recorded in the *Register Book*.

1.1.3 Requirements, additional to these Rules, may be imposed by the National Administration with whom the ship is registered and/or by the administration within whose territorial jurisdiction it is intended to operate. Where national legislative requirements exist, compliance with such regulations shall also be necessary.

1.1.4 For the purpose of these Rules, dynamic positioning means the provision of a hydrodynamic system with automatic and/or manual control capable of maintaining the heading and position of the ship during operation within specified limits and environmental conditions.

1.1.5 For the purpose of these Rules, the area of operation is the specified allowable position deviation from a set point, see 1.3.2.

1.1.6 Special consideration will be given where the dynamic positioning system is used primarily for purposes other than position keeping, e.g. track following. A descriptive note may be entered in column 6 of the *Register Book* to this effect.

### 1.2 Classification notations

1.2.1 Ships complying with the requirements of this Chapter will be eligible for one of the following class notations, as defined in Pt 1, Ch 2:

- DP(CM)** See Section 2.
- DP(AM)** See Section 3.
- DP(AA)** See Section 4.
- DP(AAA)** See Section 5.

1.2.2 The notations given in 1.2.1 may be supplemented with a Performance Capability Rating (PCR). This rating indicates the calculated percentage of time that a ship is capable of maintaining heading and position under a standard set of environmental conditions (North Sea), see Section 6.

1.2.3 Additional descriptive notes may be entered in column 6 of the *Register Book* indicating the type of position reference system, control system, etc.

1.2.4 Where a **DP** notation is not requested, dynamic positioning systems are to be installed in accordance with the requirements of Section 2 as far as is practicable.

### 1.3 Information and plans required to be submitted

1.3.1 The information and plans specified in 1.3.2 to 1.3.7 are to be submitted in triplicate. The Operation Manuals specified in 1.3.8 are to be submitted in a single set.

1.3.2 Details of the limits of the area of operation and heading deviations, together with proposals for redundancy and segregation provided in the machinery, electrical installations and control systems, are to be submitted. These proposals are to take account of the possible loss of performance capability should a component fail or in the event of fire or flooding, see *also* 1.3.6 and Sections 4 and 5.

1.3.3 Where a common power source is utilised for thrusters, details of the total maximum load required for dynamic positioning are to be submitted.

1.3.4 Plans of the following, together with particulars of ratings in accordance with the relevant Parts of the Rules, are to be submitted for:

- (a) Prime movers, gearing, shafting, propellers and thrust units.
- (b) Machinery piping systems.
- (c) Electrical installations.
- (d) Pressure vessels for use with dynamic positioning system.

1.3.5 Plans of control, alarm and safety systems, including the following, are to be submitted:

- (a) Functional block diagrams of the control system(s).
- (b) Functional block diagrams of the position reference systems and the environmental sensors.
- (c) Details of the electrical supply to the control system(s), the position reference system(s) and the environmental sensors.

# Dynamic Positioning Systems

# Part 7, Chapter 4

Sections 1 & 2

- (d) Details of the monitoring functions of the controllers, sensors and reference system, together with a description of the monitoring functions.
- (e) List of equipment with identification of the manufacturer, type and model.
- (f) Details of the control stations, e.g. control panels and consoles, including the location of the control stations.
- (g) Test schedules (for both works testing and sea trials) that are to include the methods of testing and the test facilities provided.

1.3.6 For assignment of a **DP(AA)** or **DP(AAA)** notation, a Failure Mode and Effect Analysis (FMEA) is to be submitted, demonstrating that adequate segregation and redundancy of the machinery, the electrical installation and the control systems have been achieved in order to maintain position in the event of equipment failure (see Section 4); or fire or flooding, see Section 5. The FMEA is to take a formal and structured approach and is to be performed in accordance with an acceptable and relevant national or international standard, e.g. IEC 60812.

1.3.7 Where the **DP** notation is to be supplemented with a Performance Capability Rating (PCR) (see 1.2.2), the following information is to be submitted for assignment of a PCR:

- (a) Lines plan.
- (b) General arrangement.
- (c) Details of thruster arrangement.
- (d) Thruster powers and thrusts.

1.3.8 Operation Manuals, including details of the dynamic positioning system operation, installation of equipment, maintenance and fault finding procedures, together with a section on the procedure to be adopted in emergency, are to be submitted. A copy of the manual is to be placed and retained on board the ship.

## ■ Section 2 Class notation DP(CM)

### 2.1 General

2.1.1 For assignment of **DP(CM)** notation, the requirements of 2.1.2 and 2.2 to 2.4 are to be complied with.

2.1.2 Control engineering systems, electrical and piping installations and machinery items are to be designed, constructed, installed and tested in accordance with the relevant requirements of Parts 5 and 6.

### 2.2 Thrust units

2.2.1 Thruster installations are to be designed, constructed, installed and tested in accordance with the requirements of Pt 5, Ch 20, as applicable.

2.2.2 Thruster installations are to be designed to minimize potential interference with other thrusters, sensors, hull or other surfaces, which could be encountered in the service for which the ship is intended.

2.2.3 Thruster intakes are to be located at sufficient depth to reduce the possibility of ingesting floating debris and vortex formation.

2.2.4 The response and repeatability of thrusters to changes in propeller pitch or propeller speed/direction of rotation are to be suitable for maintaining the area of operation and heading within specified limits.

### 2.3 Electrical systems

2.3.1 This Section applies to the electrical generation and distribution system associated with the Dynamic Positioning System, whether this generating system is dedicated to the DP system or forms a central generating arrangement for all loads on the ship.

2.3.2 The electrical installation is to be designed, constructed and installed, in accordance with the requirements of Pt 6, Ch 2, together with the requirements of 2.3.3 to 2.3.12.

2.3.3 Where thruster units are electrically driven, the relevant requirements, including surveys, of Pt 6, Ch 2, 15 are to be complied with.

2.3.4 Essential services are those defined in Pt 6, Ch 2, 1.5, as applicable, together with thruster auxiliaries, computers, generator and thruster control equipment, reference systems, environmental sensors and electrically driven thruster units.

2.3.5 The number and rating of generator sets, transformers and converter equipment are to be sufficient to ensure the operation of essential services, even when one generating set, transformer or converter equipment is out of action.

2.3.6 For electrically driven thruster systems, the generator rating is to be determined by the maximum dynamic positioning load, together with the maximum ancillary load.

2.3.7 There are to be arrangements to prevent overloading of the running generator(s). The tripping of non-essential loads and the temporary reduction in the load demands of electrically driven thrusters may form part of these arrangements.

2.3.8 An alarm is to be initiated when the total electrical load exceeds a preset percentage of the running generator(s) capacity. This alarm is to be adjustable between 50 and 100 per cent of the running capacity and is to be set with regard to the number of generators in service and the effect of the loss of any one generator.

2.3.9 On loss of power due to the failure of the operating generator(s), there is to be provision for the automatic starting and connection to the switchboard of a standby set and the automatic sequential restarting of essential services.

2.3.10 Any loads that require an uninterrupted electrical power supply are to be provided with uninterruptible power systems (UPS) having a capacity for a minimum of 30 minutes' operation following loss of the main supply.

# Dynamic Positioning Systems

# Part 7, Chapter 4

Sections 2 & 3

2.3.11 An indication of the absorbed power and the available on-line generating capacity is to be provided at the main dynamic positioning control station.

2.3.12 Essential services are to be served by individual feeders. Services that are duplicated are to be supplied from opposite sides of the main switchboard busbar circuit-breaker and their cables are to be separated throughout their length as widely as practical and without the use of common feeders, transformers, converters, protective devices or control panels and circuits.

## 2.4 Control stations

2.4.1 Control stations from which the dynamic positioning system may be operated are to be designed in accordance with sound ergonomic principles, and are to be provided with sufficient instrumentation to provide effective control and indicate that the systems are functioning correctly. Colour schemes and screen layouts are to be selected such that necessary information is readily available and clearly displayed. See also Pt 6, Ch 1,2.10 for general ergonomic requirements.

2.4.2 Control station(s) are to be located such that the operator has a good view of the ship's exterior limits and surrounding area.

2.4.3 Indication of the following is to be provided at each station from which it is possible to control the dynamic positioning system:

- (a) The heading and location of the ship relative to the desired reference point or course.
- (b) Vectorial thrust output, individual and total.
- (c) Operational status of position reference systems and environmental sensors.
- (d) Environmental conditions, e.g. wind speed and direction.
- (e) Availability status of standby thruster units.

2.4.4 At least one position reference system, heading reference sensor and wind sensor are to be provided to ensure that the specified area of operation and heading can be effectively maintained.

2.4.5 Position reference systems are to incorporate measurement techniques suitable for the service conditions for which the ship is intended.

2.4.6 Where necessary for the correct functioning of a position reference system, a vertical reference sensor is to be provided to correct for the pitch and roll of the ship. There are to be at least as many vertical reference units as there are associated position reference systems.

2.4.7 Alarms, in accordance with the requirements of Pt 6, Ch 1,2.3, are to be provided for the following fault conditions as applicable:

- (a) When the ship deviates from the area of operation.
- (b) When the heading exceeds the allowable deviation.
- (c) Position reference system fault (for each reference system).
- (d) Heading reference sensor fault.
- (e) Vertical reference sensor fault.

- (f) Wind sensor fault.
- (g) Taut wire excursion limit.
- (h) Automatic changeover to a standby position reference system or environmental sensor.

## 2.5 Control system

2.5.1 A centralized remote manual control system is to be provided such that changes in the vectorial thrust output may be readily effected by a single operator action.

2.5.2 Suitable processing and comparative techniques are to be provided to validate the control system inputs from position and other sensors. Abnormal signal errors revealed by the validity checks are to operate alarms.

2.5.3 The control system for dynamic positioning operation is to be stable throughout its operational range and is to meet the specified performance and accuracy criteria.

2.5.4 Automatic controls are to be provided to maintain the heading of the ship within specified limits.

2.5.5 The allowable deviation from the desired heading is to be adjustable, but should not exceed the specified limits, see 1.1.4. Arrangements are to be provided to fix and identify the set point for the desired heading.

2.5.6 Alarms, in accordance with the requirements of Pt 6, Ch 1,2.3, are to be provided for the following fault conditions:

- (a) Control computer system fault.
- (b) Automatic changeover to a standby control computer system, as applicable, see 4.1.7.

## Section 3 Class notation DP(AM)

### 3.1 Requirements

3.1.1 For assignment of **DP(AM)** notation, the applicable requirements of Section 2, together with 3.1.2 to 3.1.7, are to be complied with.

3.1.2 An automatic and a manual control system are to be provided and arranged to operate independently, so that failure in one system will not render the other system inoperative. Arrangements for manual control are to satisfy the requirements of Section 2 when the automatic system is inoperative.

3.1.3 At least two position reference systems suitable for the intended service conditions and incorporating different measurement techniques, are to be provided and arranged, so that a failure in one system will not render the other system inoperative. Special consideration will be given where the use of different techniques would not be practicable during DP operations.

# Dynamic Positioning Systems

# Part 7, Chapter 4

Sections 3, 4 & 5

3.1.4 At least two heading reference sensors and two wind sensors are to be provided and arranged, so that a failure of one sensor will not render the other sensor(s) inoperative.

3.1.5 In the event of a single failure of a position reference, heading reference, or wind sensor, the control systems are to continue operating on signals from the remaining sensors without manual intervention.

3.1.6 The area of operation is to be adjustable, but is not to exceed the specified limits based on a percentage of water depth, or as applicable, a defined absolute or relative surface movement. Arrangements are to be provided to fix and identify the set point for the area of operation.

3.1.7 In the event of failure of any single thruster, the ship is to be capable of maintaining its area of operation and desired heading in the environmental conditions in which the DP system is intended to operate.

## ■ Section 4 Class notation DP(AA)

### 4.1 Requirements

4.1.1 For assignment of **DP(AA)** notation, the applicable requirements of Sections 2 and 3, together with 4.1.2 to 4.1.9 are to be complied with.

4.1.2 Power, control and thruster systems and other systems necessary for the correct functioning of the DP system are to be provided and configured such that a fault in any active component or system will not result in a loss of position. This is to be verified by means of a FMEA (see 1.3.6). Such components may include, but are not restricted to, the following:

- Prime movers (e.g. auxiliary engines).
- Generators and their excitation equipment.
- Gearing.
- Pumps.
- Fans.
- Switchgear.
- Thrusters.
- Valves (where power actuated).

4.1.3 Cables, pipes and other components essential for correct functioning of the DP system are to be located and protected, where necessary, such that the risk of fire or mechanical damage is minimized.

4.1.4 The generation and distribution arrangements are to be such that no single fault will result in the loss of more than 50 per cent of the generating capacity or of any duplicated essential services. However, when electrically driven thrusters are employed, a reduction in position keeping capability may be accepted, but this is not to result in a loss of position in the environmental conditions in which the DP system is intended to operate.

4.1.5 For electrically driven thruster systems, provision is to be made for the automatic starting, synchronizing and load sharing of a non-running generator before the load reaches the alarm level required by 2.3.8.

4.1.6 Two automatic control systems are to be provided and arranged to operate independently, so that failure in one system will not render the other system inoperative.

4.1.7 Control systems are to be arranged such that, in the event of failure of the working control system, the standby system takes control automatically without manual intervention and without any adverse effect of the ship's station keeping performance.

4.1.8 At least three position reference systems incorporating at least two different measurement techniques are to be provided and arranged so that a failure in one system will not render the other systems inoperative.

4.1.9 At least three heading reference sensors are to be provided and arranged so that a failure of one sensor will not render the other sensors inoperative.

## ■ Section 5 Class notation DP(AAA)

### 5.1 Requirements

5.1.1 For assignment of **DP(AAA)** notation, the applicable requirements of Sections 2, 3 and 4, together with 5.1.2 to 5.1.12 are to be complied with.

5.1.2 The DP system is to be arranged such that failure of any component or system necessary for the continuing correct functioning of the DP system, or the loss of any one compartment as a result of fire or flooding, will not result in a loss of position. This is to be verified by means of a FMEA. See 1.3.6.

5.1.3 Thruster units are to be installed in separate machinery compartments, separated by a watertight A-60 class division.

5.1.4 Generating sets, switchboards and associated equipment are to be located in at least two compartments separated by an A-60 class division, so that at least half of the equipment will be available following a fire or similar fault in one of the compartments. If the equipment is located below the operational waterline, the division is also to be watertight. There is to be provision to connect the switchboard sections together by means of circuit-breakers.

5.1.5 Duplicated cables and pipes for services essential for the correct functioning of the DP system are not to be routed through the same compartments. If this is not practicable, then they are to be carried in A-60 protected ducts. The termination arrangements are also to take due account of the degree of protection. Alternative arrangements will be considered.



# Dynamic Positioning Systems

# Part 7, Chapter 4

Sections 5, 6 & 7

5.1.6 An additional/emergency automatic control unit is to be provided at an emergency control station, in a compartment separate from that for the main control station, and is to be arranged to operate independently from the working and standby control units required by 4.1.7.

5.1.7 Arrangements are to be provided such that, in the event of a failure of the working and standby control units, a smooth transfer of control to the emergency control unit may be effected from the emergency control station by manual means.

5.1.8 Arrangements are to be provided at the emergency control station so that changes in the resultant vectorial thrust output may be readily effected by a single operator action.

5.1.9 The control/indication unit of one of the position reference systems required by 4.1.8 is to be located at the emergency control station. A repeater control/indication unit from this system is to be located at the main control station.

5.1.10 One of the heading reference sensors required by 4.1.9 is to be located at the emergency control station.

5.1.11 One wind sensor is to directly supply the additional/emergency control unit.

5.1.12 The additional/emergency control unit is to be supplied from its own independent UPS, see 2.3.10.

## Section 6 Performance Capability Rating (PCR)

### 6.1 Requirements

6.1.1 Where the **DP** notation is to be supplemented with a Performance Capability Rating (PCR) (see 1.2.2), the calculation will be carried out using the information specified in 1.3.7.

6.1.2 Two rating numerals are calculated:

- The first numeral represents the percentage of time that the ship can remain on station when subjected to a set of standard environmental conditions (North Sea fully developed) with all thrusters operating.
- The second numeral represents the percentage of time that the ship can remain on station when subjected to a set of standard environmental conditions (North Sea fully developed) with the most effective thruster being inoperative.

A typical rating might be (95), (70).

6.1.3 In calculating the PCR, the following parameters are considered:

- Thruster force vectors.
- Thruster/thruster, thruster/hull and thruster/current interactions.
- Sea current loads on the ship.
- Wind force on the ship.
- Wave drift force on the ship.

6.1.4 Where the ship has been subject to alteration or addition, which may affect the performance characteristics of the DP system, the PCR is to be recalculated.

## Section 7 Testing

### 7.1 General

7.1.1 Control units are to be surveyed at the manufacturer's works and are to be tested in accordance with the approved test schedule to the Surveyor's satisfaction, see 1.3.5(g).

7.1.2 Before a new installation (or any existing installation, which has been subject to alteration or addition which may affect the performance characteristics of the system) is put into service, sea trials are to be carried out to the approved schedule and to the Surveyor's satisfaction, see 1.3.5(g).

7.1.3 The suitability of the dynamic positioning system is to be demonstrated during sea trials, observing the following:

- Response of the system to simulated failures of major items of control and mechanical equipment, including loss of electrical power, verifying the findings of the FMEA where required.
- Response of the system under a set of predetermined manoeuvres for changing:
  - Location of area of operation.
  - Heading of the ship.
- Continuous operation of the system over a period of four to six hours.

7.1.4 Two copies of the dynamic positioning system sea trial test schedules, as required by 1.3.5(g), each signed by the Surveyor and Builder, are to be provided on completion of the survey. One copy is to be placed and retained on board the ship and the other submitted to Lloyd's Register (hereinafter referred to as 'LR').

7.1.5 Records and data regarding the performance capability of the dynamic positioning system are to be maintained on board the ship and are to be made available at the time of the Annual Survey, see Pt 1, Ch 3,2.2.15.



# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Sections 1 & 2

## Section

- 1 **General**
- 2 **Oil recovery**
- 3 **Ship structure**
- 4 **Machinery arrangements**
- 5 **Electrical equipment**
- 6 **Fire protection and extinction**
- 7 **Operating Manual**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to ships equipped for the recovery of oil floating on the sea and are additional to other applicable Parts of the Rules.

1.1.2 For ships of less than 500 gross tons, also fishing vessels of 12 m length and over, but less than 45 m length, and ships not fitted with propelling machinery, the arrangements for fire protection and extinction are to comply with Section 6. Consideration will be given to the acceptance of the fire safety measures for oil recovery ships prescribed and approved by the Government of the Flag State.

1.1.3 For ships of 500 gross tons and over, also fishing vessels of 45 m length and over, it is the responsibility of the Government of the Flag State to give effect to the fire safety measures, see Pt 6, Ch 4, 1.1. Where the Government of the Flag State has no National Requirements for oil recovery ships, Lloyd's Register (hereinafter referred to as 'LR') will apply the fire safety measures required by Section 6 for classification purposes.

1.1.4 Requirements additional to these Rules may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the ship is intended to operate.

### 1.2 Classification and class notations

1.2.1 A ship primarily intended for oil recovery operations and complying with the requirements of this Chapter will be eligible for the class notation **Oil Recovery Ship** which will be recorded in the *Register Book*.

1.2.2 A ship not primarily intended for oil recovery operations, which has structural arrangements in accordance with 3.1.7, and which complies with the relevant requirements of this Chapter, will be eligible for the class notation **Occasional Oil Recovery Duties** which will be recorded in the *Register Book*.

### 1.3 Surveys

1.3.1 The arrangements and equipment referred to in this Chapter are to be examined and tested on completion of the installation and, subsequently, annually.

### 1.4 Plans and supporting documentation

1.4.1 In addition to the supporting documentation required for classification as specified in other Parts of the Rules, details relevant to oil recovery operations are to be submitted.

1.4.2 Plans covering the following items are to be submitted for approval:

- Structural support in way of equipment.
- Structural arrangement of recovered oil tanks including access.
- Piping system arrangements for recovered oil including venting.
- Power supply, electrical protection and cabling for oil recovery equipment.
- Hazardous areas and spaces.
- Electrical equipment located in hazardous areas and spaces.
- Structural fire protection and extinguishing equipment.

1.4.3 The following supporting documents are to be submitted:

- General arrangement of recovery equipment, including portable items, handling facilities, access, ventilation details, arrangement of other openings to hazardous spaces and adjacent compartments, machinery exhaust outlet positions.
- Gas detection equipment specification.
- Operating Manual.

1.4.4 The following supporting calculations are to be submitted:

- Deck equipment support structure loadings.
- Schedule of loads on the electrical system for oil recovery operations.

## ■ Section 2 Oil recovery

### 2.1 General

2.1.1 The ship is to be capable of performing the following functions at a safe distance from the source of oil spill:

- (a) Separation of the oil film from the surface of the sea.
- (b) Handling, storage and transportation of the recovered oil.

# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Sections 2, 3 & 4

## 2.2 Equipment and principal deck arrangement

2.2.1 The arrangements for collection, handling and transfer of recovered oil are to be such that the probability of oil spill on deck and overflow is minimized and the operation is to be performed as far away from the accommodation spaces as practicable. These arrangements are to include hand rails and gratings or other non-slip surfaces to ensure suitable working conditions.

2.2.2 Means are to be provided to keep deck spills away from the accommodation and service areas. This may be accomplished by provision of a permanent continuous coaming not less than 150 mm high.

2.2.3 At least two portable instruments are to be available on board for gas detection.

2.2.4 For engines used in oil recovery operations, see 4.4.

2.2.5 Masts and derricks, etc., are to comply with the appropriate sections of Chapters 2 and 3 of LR's *Code for Lifting Appliances in a Marine Environment*.

## ■ Section 3 Ship structure

### 3.1 Structural arrangement

3.1.1 The position of bulkheads is to comply with the requirements of Pt 3, Ch 3,4.

3.1.2 Any tanks not utilized during oil recovery operations are to be arranged so that recovered oil cannot be transferred to them inadvertently.

3.1.3 In tanks intended for recovered oil, internal obstructions are to be avoided to prevent the entrapment of foreign objects usually present in recovered oil. Adequate drainage openings are to be provided to ensure free flow of residues to assist in cleaning and gas freeing on completion of recovery operations.

3.1.4 Tanks used for the storage of recovered oil are to be located outside the accommodation and machinery spaces.

3.1.5 Except where permitted by 3.1.6 and 3.1.7, tanks intended for the storage of recovered oil are to be separated from accommodation and machinery spaces by cofferdams. Cofferdams are to be at least one frame spacing in length (600 mm minimum) and are to cover the whole area of the boundary under consideration.

3.1.6 A pump room, oil fuel bunker, water ballast tank or other closed space where oil recovery handling equipment is stored will be accepted in lieu of a cofferdam.

3.1.7 On ships to which 1.2.2 applies, cofferdams may be impractical to arrange. In these cases, tanks arranged adjacent to machinery spaces may be accepted for storage of recovered oil. Acceptance will be conditional upon the tank boundary bulkheads being readily accessible for inspection. The bulkheads are to be carried continuously through joining structure to the top of the tank, where full penetration welding is to be carried out. Such tanks will require to be pressure tested at every Periodical Survey, see Table 1.8.2 in Pt 3, Ch 1, as applicable to oil tankers. Special consideration will be given to arrangements incorporating double bottom tanks in these locations.

3.1.8 All openings to tanks for recovered oil are to be located on the open deck. This includes sounding pipes, vent pipes, and hatches for the deployment of portable pumps and hoses. Suitable access hatches, not less than 600 mm x 600 mm, are to be similarly arranged to facilitate tank cleaning and gas freeing. Dual access hatches, as widely separated as practicable, are to be provided for tanks of a cellular nature.

3.1.9 Removable manhole covers are to be avoided where practicable, except for access from open deck or void spaces to ballast or fresh water tanks.

3.1.10 Where there is a risk of significant sloshing induced loads, additional strength calculations may be required, see Pt 3, Ch 3,5.4.

3.1.11 Where recovered oil temperatures are to be increased significantly above 65°C during transit voyages, attention is drawn to Pt 4, Ch 9,12 regarding thermal stress considerations.

### 3.2 Scantlings

3.2.1 The scantlings will receive individual consideration on the basis of Pt 4, Ch 9 and Ch 10, as applicable.

## ■ Section 4 Machinery arrangements

### 4.1 Piping arrangements

4.1.1 Piping arrangements for the recovered oil system are to be located outside machinery spaces and are to have no connections to such spaces.

4.1.2 When the ship is in oil recovery mode, means are to be provided to isolate the oil recovery system from any other system to which it may be connected.

4.1.3 Ventilation outlets from the recovered oil tanks are to have a minimum height of 2,4 m above deck and be fitted with flame screens. Temporary pipe sections may be used for this purpose. Outlets are to be located not less than 5 m measured horizontally from the nearest air intakes and openings to accommodation and enclosed spaces containing a source of ignition and from deck machinery and equipment which may constitute an ignition hazard.

# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Sections 4 & 5

4.1.4 Each recovered oil tank is to be fitted with suitable means of ascertaining the liquid level in the tank. Sounding pipes or other approved devices are acceptable for this purpose.

## 4.2 Pump room for recovered oil

4.2.1 Pump rooms are to be fitted with a permanent ventilation system of the mechanical extraction type.

4.2.2 The ventilation system is to be capable of being operated from outside the compartment being ventilated and a notice is to be fixed near the entrance stating that no person is to enter the space until the ventilation system has been in operation for a specified period, sufficient to achieve at least five air changes based on the gross volume of the space.

4.2.3 The ventilation system is to be capable of at least six air changes per hour, based on the gross volume of the space.

4.2.4 Protection screens of not more than 13 mm square mesh are to be fitted outside openings of ventilation ducts, and ventilation intakes are to be so arranged as to minimize the possibility of recycling hazardous vapours from any ventilation discharge opening. Vent exhausts are to be arranged to discharge upwards.

4.2.5 The vent exhausts from pump rooms are to discharge at least 3 m above deck, and from the nearest air intakes or openings to accommodation and enclosed working spaces, and from possible sources of ignition.

4.2.6 Ventilation fans to be constructed in accordance with Pt 5, Ch 15,1.8.

4.2.7 Pump rooms are to have no direct communication with machinery spaces.

4.2.8 Bilge drainage of the pump room is to be effected by pumps or bilge ejector suction. For ships of less than 500 gross tons, the pump room bilge may be drained by a hand pump having a 50 mm bore suction.

## 4.3 Ventilation of machinery spaces

4.3.1 Where machinery spaces adjacent to recovered oil tanks are permitted by 3.1.7, the ventilation arrangements are to comply with 5.4.1(a) and (b).

## 4.4 Exhaust systems

4.4.1 The exhaust lines of diesel engines, boilers and equipment containing sources of ignition and the vents of diesel engine crank cases are to be led to a position outside any hazardous area as defined in 5.3. In addition, suitable spark arrestors are to be fitted.

## 4.5 Miscellaneous

4.5.1 Low sea suction are to be provided to supply water for the machinery and all fire pumps.

4.5.2 Means are to be provided to enable heating coils in recovered oil tanks and adjacent tanks to be blanked off during recovery operations.

4.5.3 The heating medium supply and return lines are not to penetrate the recovered oil tank plating, other than at the top of the tank, and the main supply lines are to run above the weather deck.

4.5.4 If required to facilitate discharge operations, steam returns are to be led to an observation tank which is to be in a well-ventilated and well-lighted part of the machinery space remote from the boilers.

## Section 5 Electrical equipment

### 5.1 General

5.1.1 The electrical installation is to comply with the relevant requirements of Pt 6, Ch 2, with the specific exceptions of 13.1, 13.2, 13.4, 13.6, 13.7 and 13.9, which are replaced by 5.3 to 5.6 of this Chapter.

### 5.2 Systems of supply and distribution

5.2.1 Only the systems of generation and distribution, listed under Pt 6, Ch 2,5.1.2, are acceptable.

### 5.3 Hazardous zones and spaces

5.3.1 The following zones or spaces are regarded as hazardous during and on completion of oil recovery operations, until proven gas-safe:

- (a) The interiors of tanks intended for the storage of recovered oil.
- (b) The interiors of piping systems intended for the handling of recovered oil.
- (c) Spaces separated by a single bulkhead, deck or other tank boundary, from the interior of a tank intended for recovered oil, or having a bulkhead immediately above or below and in line with a bulkhead of a tank intended for recovered oil, unless protected by a diagonal plate in accordance with Pt 4, Ch 9,1.2.7 or the arrangements comply with the requirements of 3.1.7.
- (d) Spaces housing piping systems or other equipment containing or contaminated with recovered oil and having flanged joints or glands or other openings from which leakage of fluid may occur under normal operating conditions.
- (e) Zones on open deck within a 3 metre radius of the ventilation outlets, or inspection hatches permitted to be opened under normal operating conditions, of tanks intended for recovered oil.

# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Section 5

- (f) Zones on open deck within a 1,5 m radius of any sampling or sounding point of a tank intended for recovered oil.
- (g) Zones on open deck within a 1,5 m radius of any flanged joints, glands or other parts of any equipment containing or contaminated with recovered oil from which leakage may occur under normal operating conditions.
- (h) Zones on open deck within the confines of, and extending 1,5 m beyond, any bund or barrier intended to contain a spillage of recovered oil, up to a height of 1,5 m.
- (j) Zones on open deck within a 1,5 m radius of any opening into a space described by (c) or (d).
- (k) Zones on open deck over all tanks intended for recovered oil, where the tops of the tanks are exposed to the weather, to the full width of the ship plus 3 m fore and aft of the forwardmost and aftmost tank bulkhead, up to a height of 0,45 m above the deck or to the height of any bulwarks.
- (l) Zones on open deck extending 1,5 m beyond those defined by 5.3.1(e) to (j).
- (m) Any enclosed or semi-enclosed space having a direct opening into a hazardous zone or space identified above, unless the space is protected by pressurization in accordance with 5.5.1 or 5.5.2, or the opening is a ventilation outlet arranged in compliance with 5.4.2.

## 5.4 Ventilation

5.4.1 The extent of any hazardous zone within an enclosed or semi-enclosed space may be limited to that defined for an equivalent situation on open deck, provided that the ventilation arrangements fulfil all the following conditions:

- (a) Mechanical ventilation is provided, with the air intake and outlet located outside any hazardous area defined by 5.3.1, ensuring at least 12 air changes per hour, and leaving no region of stagnant air.
- (b) Ventilation air flow is continuously monitored and so arranged that, in the event of failure of ventilation, an alarm is given at an attended station.

5.4.2 An enclosed or semi-enclosed space having a ventilation outlet situated in a hazardous zone, as defined under 5.3.1(k) or (l), may be regarded as non-hazardous if fulfilling all the following conditions:

- (a) The space has mechanical ventilation with the air intake located outside any hazardous area defined by 5.3.1.
- (b) The ventilation outlet is equipped with a self-closing flap or other suitable means of closure operating automatically on loss of ventilation airflow.
- (c) The space contains no equipment of a type described in 5.3.1(d), or vent from or opening into any hazardous space or zone defined by 5.3.1, other than the ventilation outlet under consideration.
- (d) The space is separated by at least two gastight bulkheads from the interior of any tank intended for recovered oil.

## 5.5 Pressurization

5.5.1 A space having access to a hazardous space or zone, as defined under 5.3.1(c) to (j), may be regarded as non-hazardous if it fulfils all of the following conditions:

- (a) Access is by means of an air-lock, having gastight doors, the inner of which, as a minimum, is self-closing without any hold-back arrangement.
- (b) It is maintained at an over-pressure of at least 50 Pa relative to the external hazardous area by ventilation from a non-dangerous area.
- (c) The relative air pressure within the space is continuously monitored and so arranged that, in the event of loss of over-pressure, an alarm is given at an attended station.
- (d) It contains no piping system or equipment of a type described in 5.3.1(d), and no vent from or opening into any hazardous space or zone defined by 5.3.1, other than the access under consideration.
- (e) It is separated by at least two gastight bulkheads from the interior of any tank intended for recovered oil.

5.5.2 A space having access to a hazardous zone, as defined under 5.3.1(k) or (l), may be regarded as non-hazardous if it fulfils all of the following conditions:

- (a) Access is by means of a gastight self-closing door without any hold back arrangement.
- (b) It is maintained at an overpressure in accordance with 5.5.1(b).
- (c) The air pressure within the space is monitored in accordance with 5.5.1(c).
- (d) It contains no piping system or equipment of a type described in 5.3.1(d), and no vent from or opening into any hazardous space or zone defined by 5.3.1, other than the access under consideration.
- (e) It is separated from the interior of any tank intended for recovered oil in accordance with 5.5.1(e).

5.5.3 A space having access to a hazardous space or zone, as defined under 5.3.1(c) to (j), and fulfilling the conditions given under 5.5.2(a) to (e) may be regarded, for the purposes of selection of electrical equipment, as equivalent to an open-deck hazardous area, such as defined under 5.3.1(k).

## 5.6 Selection of electrical equipment for installation in hazardous areas

5.6.1 The installation of electrical equipment in hazardous areas is to be minimized as far as is consistent with operational necessity and the provision of lighting, monitoring, alarm or control facilities enhancing the overall safety of the ship.

5.6.2 When electrical equipment is to be installed in hazardous areas, unless permitted otherwise by 5.6.3 or 5.6.4, it is to be of a 'safe type', as listed below, certified or approved by a competent authority for Group IIA, temperature class T3. The construction and type testing is to be in accordance with IEC 60079: *Electrical Equipment for Explosive Gas Atmospheres*, or an acceptable and relevant National Standard.

- Intrinsically safe Ex 'i'
- Increased safety Ex 'e'

# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Section 5

- Flameproof Ex 'd'
- Pressurized enclosure Ex 'p'
- Powder filled Ex 'q'
- Encapsulated Ex 'm'

5.6.3 Consideration may additionally be given to the use of equipment of the following types:

- (a) Equipment such as control panels, protected by purging and pressurization and capable of being verified by inspection as meeting the requirements of IEC 60079-2.
- (b) Simple non-energy-storing apparatus having negligible surface temperature rise in normal operation, such as limit switches, strain gauges, etc., incorporated in intrinsically-safe circuits.
- (c) Submersible pumps, having at least two independent methods of shutting down automatically in the event of low liquid level.
- (d) Radio aerials having robust construction, meeting the relevant requirements of IEC 60079-15. Additionally, in the case of transmitter aerials, it is to be shown, by detailed study or measurement, or by limiting the peak radiated power and field strength to 1 W and 30 V/m, respectively, that they present negligible risk of inducing incendive sparking in adjacent structures or equipment.
- (e) Electrical apparatus having a special type of protection (Ex's'), certified or approved by a competent authority.
- (f) Electrical apparatus having the type of protection Ex'n' (or Ex'N'), that, in normal operation, is not capable of igniting a surrounding explosive gas atmosphere, and in which a fault capable of causing ignition is not likely to occur.

5.6.4 Equipment not meeting the requirements of 5.6.5 to 5.6.14 may be installed in hazardous zones or spaces, or locations rendered non-hazardous by ventilation or pressurization, if not required to be energized during oil recovery operations, and not essential for the safety of the ship or crew. Such equipment is to be controlled by multi-pole switches or circuit breakers situated outside any hazardous area. Provision is to be made for the complete isolation of these circuits and locking the means of control in the off position.

5.6.5 In tanks and piping systems defined by 5.3.1(a) and (b), only the following electrical equipment will be permitted:

- (a) Intrinsically-safe apparatus of category 'ia'.
- (b) Simple apparatus, as defined under 5.6.3(b), incorporated in an intrinsically-safe circuit of category 'ia'.
- (c) Submersible pumps, as defined under 5.6.3(c).
- (d) Ex's' apparatus, certified for use in Zone 0, as defined by IEC 60079-10.
- (e) Cable required for the operation of the equipment installed.

5.6.6 In spaces adjacent to tanks, as defined by 5.3.1(c), with no mechanical ventilation, only the following electrical equipment will be permitted:

- (a) That described in 5.6.5(a), (b), (d) and (e).
- (b) Ex'd' lighting fittings.
- (c) Ex'p' lighting fittings of either the air-driven type, or pressurized from an external source of protective gas and arranged to be de-energized automatically on loss of pressurization.

- (d) Gas detector heads having sinter-type flametrap protection, included within an intrinsically-safe circuit, all of which is to be certified as a system.
- (e) Ex'd' alarm sounders, without internal sparking contacts.
- (f) Cables for impressed current cathodic protection systems (for external hull protection only) installed in heavy gauge steel pipes with gastight joints up to the upper deck; the arrangements are to comply with Pt 3, Ch 2,3.5.3.
- (g) Through runs of cables, installed in heavy gauge steel pipes with gastight joints.

The electrical equipment described in (b), (c) and (e) will be permitted only where personnel are required to have access to the space during oil recovery operations.

5.6.7 In spaces adjacent to tanks, as defined by 5.3.1(c) having mechanical ventilation, and in spaces and zones containing piping systems, equipment, etc., or close to vents, flanges, etc., and other zones as defined by 5.3.1(d) to (j), only the following electrical equipment will be permitted:

- (a) That described in 5.6.6.
- (b) Intrinsically-safe apparatus of category 'ib'.
- (c) Simple apparatus, as defined under 5.6.3(b), incorporated in an intrinsically-safe circuit of category 'ib'.
- (d) Other apparatus certified as Ex'e', Ex'd', Ex'q', Ex'm' or Ex's'.
- (e) Pressurized equipment, certified Ex'p', or as described in 5.6.3(a), arranged to be de-energized automatically on loss of pressurization.
- (f) Through runs of cable in spaces and zones described in 5.3.1(d) to (j) only.

5.6.8 In zones defined by 5.3.1(k) and (l), only the following electrical equipment will be permitted:

- (a) That described in 5.6.7.
- (b) Pressurized equipment, certified Ex'p', or as described in 5.6.3(b), arranged to give an audible and visual alarm at a manned station in the event of loss of pressurization.
- (c) Equipment as described in 5.6.3(d) and (f).

5.6.9 Electrical installations in enclosed or semi-enclosed spaces, as described in 5.3.1(m), are to comply with the requirements for the space or zone into which the opening leads, unless ventilated in accordance with 5.4.1 or 5.4.2.

5.6.10 Electrical installations in enclosed or semi-enclosed spaces, ventilated as described in 5.4.1, are to comply with the requirements for hazardous zones, as described in 5.3.1(e) to (l), within the radii or distances from adjacent sources of hazard or sources within the space specified by these paragraphs. Equipment within a radius of 3 m from any ventilation outlet of such a space is to be of a type described in 5.6.8. Equipment not of a type described in 5.6.7 is to be provided with a means of disconnection capable of being controlled from an attended station in the event of ventilation failure. Where the means of disconnection is located within the space, then it is to be of a 'safe type'.

5.6.11 Electrical installations in machinery spaces adjacent to recovered oil tanks, where permitted by 3.1.7, are to comply with the requirements of 5.6.10, and the additional requirement that equipment within 0,45 m of the tank bulk-head or the bottom of the space is to be of a type described in 5.6.8.

# Ships Equipped for Oil Recovery Operations

# Part 7, Chapter 5

Sections 5, 6 & 7

5.6.12 In pressurized spaces defined by 5.5.1, electrical equipment not of a type described in 5.6.8 is to be automatically disconnected in the event of loss of overpressure. Other equipment is to be provided with a means of disconnection capable of being controlled from an attended station in the event of loss of overpressure. Where the means of disconnection is located within the space, it is to be of a 'safe type'. Emergency lighting, pressure monitoring equipment and any alarm sounders or lights are to be of types described in 5.6.6.

5.6.13 In pressurized spaces defined by 5.5.2, any equipment not of a type described in 5.6.8 is to be provided with a means of disconnection capable of being controlled from an attended station in the event of loss of overpressure.

5.6.14 In pressurized spaces defined by 5.5.3, only electrical equipment as described in 5.6.8 may be permitted. Any equipment that is not of a type described in 5.6.7 is to be provided with a means of disconnection capable of being controlled from an attended station in the event of loss of overpressure. Emergency lighting, pressure monitoring equipment and any alarm sounders or lights are to be of types described in 5.6.6.

## Section 6 Fire protection and extinction

### 6.1 Structural fire protection

6.1.1 Exterior boundaries of superstructures and deck-houses enclosing accommodation and service spaces, including any overhanging decks which support such accommodation and service spaces, are to be insulated to 'A-60' standard for all parts which face deck areas where there are arrangements for collection, handling and transfer of recovered oil and for a distance 3 m aft or forward thereof.

6.1.2 Windows and side scuttles in the exterior boundaries, referred to in 6.1.1, are to be provided with permanently installed inside covers of steel. Aluminium alloy components are not to be used in the construction of the windows and side scuttles.

6.1.3 As an alternative to compliance with 6.1.1 and 6.1.2, a fixed water spraying system may be accepted. The system is to be capable of delivering water at a rate of 10 litres/m<sup>2</sup>/min. on all boundaries, windows and side scuttles, that would otherwise be required to comply with 6.1.1 and 6.1.2.

### 6.2 Fire-extinguishing arrangements

6.2.1 Deck areas, where there are arrangements for the collection, handling and transfer of recovered oil, are to be provided with the following fire-extinguishing equipment:

- (a) Two dry powder fire-extinguishers, each at least 50 kg capacity.
- (b) At least one portable low expansion foam applicator.

6.2.2 The fire-extinguishers are to be located near the working deck identified in 6.2.1 and are to be fitted with discharge hoses.

6.2.3 The foam installation is to be capable of applying foam to any part of the working deck. The capacity of any applicator is to be not less than 400 litres/min. of foam solution and the applicator throw in still air conditions is to be not less than 15 m. Sufficient foam concentrate is to be provided for at least 0,4 litres/m<sup>2</sup> of the working deck area with a minimum quantity of 200 litres.

### 6.3 Fireman's outfits

6.3.1 At least two fireman's outfits, additional to those required by Pt 6, Ch 4, 12 or SOLAS Reg II-2/A, 17.3 as applicable, are to be provided.

## Section 7 Operating Manual

### 7.1 General

7.1.1 Information regarding the safe use of the ship with respect to the oil recovery and subsequent operations is to be prepared.

7.1.2 The Operating Manual is, in general, to contain information regarding procedures for:

- (a) establishing and maintaining a safe atmosphere in any space(s) liable to become hazardous during oil recovery and subsequent operations;
- (b) isolation, where necessary, of electrical equipment in zones or spaces considered hazardous during oil recovery and subsequent operations, and in spaces described in 7.1.2(a) prior to carrying out, or on failure of, the measures required to establish and maintain a safe atmosphere;
- (c) fire-fighting;
- (d) gas measurements;
- (e) recovery and storage of oil;
- (f) ballasting;
- (g) transfer of recovered oil;
- (h) tank cleaning;
- (j) gas freeing; and
- (k) contacts in the event of an emergency.



# Arrangements for Offshore Loading

# Part 7, Chapter 6

Section 1

## Section

- 1 **General**
- 2 **Arrangements**
- 3 **Positioning, monitoring and control arrangements**
- 4 **Fire protection, detection and extinction**
- 5 **Piping systems**
- 6 **Trials and testing**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to tankers equipped with bow/stern loading arrangements to facilitate the transfer of cargo oil from offshore loading terminals, such as loading platforms, loading buoys, FPSOs and FSUs, and are additional to those applicable in other Parts of the Rules. These requirements also apply to submerged turret loading systems where applicable.

1.1.2 Requirements additional to these Rules may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction the ship is intended to operate.

1.1.3 The materials used are to be suitable for the intended service conditions.

### 1.2 Class notations

1.2.1 Ships complying with the requirements of this Chapter will be eligible to have one of the following special features notations included in the class notation:

- (a) Ships fitted with a bow loading system, **BLS**.
- (b) Ships fitted with a stern loading system, **SLS**.
- (c) Ships fitted with submerged turret loading systems, **TLS**.

### 1.3 Surveys

1.3.1 The survey of these items is to be arranged to coincide with hull and machinery surveys, see Pt 1, Ch 3.

### 1.4 Submission of plans and documentation

1.4.1 In addition to the plans and information required by other relevant Sections of the Rules, the plans and information detailed below are to be submitted:

- (a) **Bow/stern loading:**  
Detail drawing(s) showing:
  - Cargo loading equipment.
  - Manifold position and pipeline connections.
  - Mooring equipment layout, including design loads and supporting structure.
  - Fire safety arrangements.
  - Control station(s).

- (b) **Systems and arrangements:**  
**General arrangement.** Plans showing the general arrangement of all areas where the piping systems are located, together with ventilation arrangements and details of openings for any enclosed spaces at the fore and/or aft part of the ship.

**Diagrammatic arrangement.** Plans indicating all piping systems arrangements associated with loading systems between cargo tank area and manifold. The plans are to include details of means of isolation, manifold arrangement, means of draining, inerting, cleaning and gas freeing of the cargo piping. Also details of manifold drip tray arrangements with means of drainage, together with any stripping line arrangements, are to be submitted. If the ship is to be installed with a vapour emission control system, plans showing details of piping arrangements are also to be submitted.

**Piping system specification.** Piping design information which includes the materials specifications, design pressure, maximum allowable transfer rate, corrosion allowance, and design ambient weather conditions. Also the design forces and moments for which the presentation manifold, together with the terminal flange and associated supporting arrangements, have been designed are to be submitted.

**Operating Manuals.** Operating Manuals are to be submitted for approval and provided on board. The Manuals are to include the following information:

- Particulars of piping arrangements and control systems.
- Operating criteria.
- Procedures for connecting/disconnecting the cargo hose, isolation arrangements, inerting, cleaning, gas freeing of the pipe line and drainage of the drip tray.
- Procedures to be followed during cargo handling operations. These are to include guidance on procedures to be followed in the event of sudden closure of the terminal valve.
- Detailed communication sequence concerning pre-mooring, mooring, pre-loading, loading and tanker departure phases.

Where the ship is fitted with dynamic positioning and/or a positional mooring system(s), the information required by Ch 4, 1.3.7 and Ch 8, 1.5.6 is also to be submitted as applicable.

- (c) **Submerged turret loading:**  
Detail drawing(s) showing:
  - Arrangement of turret room, including receiving structure, locking mechanism and traction winch equipment with associated supporting structure and design loadings.
  - Turret hatch and operating equipment, including hydraulic power pack and control systems, and cargo loading equipment.
  - Turret room fire safety arrangements.

# Arrangements for Offshore Loading

# Part 7, Chapter 6

Sections 1, 2 & 3

- Turret room electrical installations.
- Piping arrangements for all systems associated with the turret loading.

## Section 2 Arrangements

### 2.1 Mooring arrangements

2.1.1 The ship is to be provided with sufficient mooring arrangements, which may be combined with the ship's manoeuvring system, to ensure adequate alignment and security during bow, stern or submerged turret loading operations.

2.1.2 The mooring/positioning system is to be arranged to prevent mooring forces being transmitted to the loading line connector.

2.1.3 Suitable single point mooring arrangements are indicated in Pt 3, Ch 13,8.

2.1.4 Particular attention is to be given to operational requirements and conditions in the design and mounting of securing devices and fittings. Seatings for equipment are to be designed to avoid the formation of pockets or recesses which may lead to excessive corrosion in service.

### 2.2 Materials for mooring fittings

2.2.1 Where mooring fittings are used as part of a positional mooring system, they are to comply with the requirements of Chapter 8.

### 2.3 Strength of mooring fittings

2.3.1 The strength of the mooring arrangements associated with the bow/stern loading system is to be considered on the basis of Pt 3, Ch 13,8, and Chapter 8 as applicable.

### 2.4 Enclosed spaces adjacent to manifold connection

2.4.1 In addition to the arrangements required by Section 4, the following are to be complied with:

- Spaces where an explosive gas atmosphere may be present are to be suitably ventilated prior to entry.
- Spaces required to be entered during normal operations are to be provided with permanent ventilation arrangements capable of being operated from outside the compartment.

2.4.2 The ventilation arrangements are to provide a minimum of eight air changes per hour, see Pt 6, Ch 2,13.

## Section 3 Positioning, monitoring and control arrangements

### 3.1 General

3.1.1 The requirements of this Section are additional to those given in Pt 6, Ch 1, and Chapter 4 and Chapter 8.

3.1.2 If the ship is fitted with a dynamic positioning system, it is at least to comply with the DP(AM) requirements, see Chapter 4.

### 3.2 Control station

3.2.1 A control station for offshore loading may be arranged within the bow area or on the navigation bridge. All operations concerning positioning of the ship and monitoring of mooring and loading parameters are to be capable of being performed from this station.

### 3.3 Instrumentation

3.3.1 Bow/stern mooring instrumentation is to monitor:

- Mooring line traction.
- Chain stopper.
- Data logger system for recording of mooring and load parameters.

3.3.2 The mooring system is to be provided with a tension meter capable of continuously indicating the tension during the bow loading operation. Consideration may be given to waiving this requirement for ships fitted with a dynamic positioning system.

3.3.3 Bow/stern/submerged turret loading instrumentation is to be provided as follows:

- Indicator for loading connector coupling position.
- Cargo valve position indicators.
- Cargo tank level indicators and high level alarm.
- A system for automatic transfer of signals from the control and safety system, to enable personnel on the offshore terminal to effect control of cargo transfer pump(s) and closing of valve(s) on the terminal.

### 3.4 Emergency disconnect arrangements for pipeline and mooring

3.4.1 In addition to any automatic disconnection systems, a manually operated backup emergency disconnection system is to be provided. This system is to make possible individual operation of the chain stopper and coupling by-pass locks located in the bow control station.

3.4.2 Where an emergency quick-release system is fitted for the mooring system, an equivalent arrangement is to be provided to release the cargo loading hose outboard of the ship.

# Arrangements for Offshore Loading

# Part 7, Chapter 6

Sections 3, 4 & 5

## 3.5 Communication

3.5.1 Main and emergency means of communication are to be provided between the bow control station and the offshore loading terminal. The communication equipment is to be intrinsically-safe.

3.5.2 Continuous communication is to be maintained between the control station and the offshore terminal at all times.

## Section 4 Fire protection, detection and extinction

### 4.1 General

4.1.1 The fire protection and extinction arrangements are to comply with the requirements of the *International Convention for the Safety of Life at Sea, 1974*, as amended, or as required by the National Authority.

4.1.2 When Lloyd's Register (hereinafter referred to as 'LR') is authorized to act on behalf of the National Authority in giving effect to the fire safety measures on non-convention tankers or the application of SOLAS for convention ships, LR will also apply the *Guidelines for bow and stern loading and unloading arrangements on oil tankers* as given in IMO MSC/Circ.474, dated 19 June 1987.

4.1.3 Tankers of less than 500 gross tons will be specially considered.

## Section 5 Piping systems

### 5.1 Materials

5.1.1 All materials used in the piping systems are to be suitable for use with the intended cargoes and ambient weather conditions, and are to comply with the relevant requirements of Pt 5, Ch 12 and the applicable requirements of the *Rules for the Manufacture, Testing and Certification of Materials* (Part 2).

### 5.2 Piping system design

5.2.1 All piping, valves and fittings are to be suitable for the design operating and environmental conditions.

5.2.2 The piping is to comply with the requirements for manufacture, testing and certification of Class II piping systems.

5.2.3 The pipelines and associated piping systems and equipment forward and/or aft of the cargo area are to have only full penetration butt welded joints, except at the loading station where valve connections may be flanged. The pipes are not to pass through enclosed spaces and are to be, as far as possible, self-draining.

5.2.4 Means of mechanical isolation are to be provided in the cargo area, where any pipes used for cargo handling are branched off from the cargo system. Such isolation is to be as near as possible to the boundary of the aftmost, in the case of stern loading, or forwardmost, in the case of bow loading, cargo tank bulkhead and within the cargo area.

5.2.5 A manually operated shut-off terminal valve is to be provided at the manifold. In addition, a blank flange, or equivalent arrangement, is to be provided at the bow and/or stern pipe line end connection.

5.2.6 The terminal pipe, valves and other fittings to which the cargo hose is directly connected are to be of steel or other approved ductile material. They are to be of robust construction, adequately supported and suitable for the stated design conditions. Attention is drawn to the *Recommendations for Oil Tanker Manifolds and Associated Equipment*, published by OCIMF.

5.2.7 Means of emptying, cleaning, inerting and gas-freeing the pipe lines used for cargo handling are to be provided. The venting arrangements are to be located in the cargo deck area. Isolation similar to that described in 5.2.4 is also to be provided.

5.2.8 A drip tray of adequate size, together with means of drainage, are to be provided at the manifold. Suitable spray shields are to be fitted in way of the terminal manifolds where leakage may occur at valves and pipe joints.

5.2.9 Zones on open deck within 3 m of loading manifolds or pipe joints, and within 3 m of the spillage drip tray, are to be regarded as dangerous with regard to machinery or other equipment which could constitute a possible source of ignition, see also Pt 6, Ch 2, 13.4 and 13.9.

5.2.10 Air vent pipes to the tanks and enclosed spaces, and mechanical ventilation outlets are to be located as far as possible, but in no case less than 3 m, from the terminal manifold or the nearest barrier of the spillage drip tray, whichever is closer.

### 5.3 Piping system testing and non-destructive examination

5.3.1 Testing and non-destructive examination of the piping system is to comply with the relevant requirements for Class II piping.

### ■ Section 6 Trials and testing

#### 6.1 General

6.1.1 The arrangements and equipment referred to in this Chapter are to be examined and tested on completion of the installation, including calibration of coupling equipment.

6.1.2 Examination and testing is to include witnessing of the initial hook-up trials and the implementation of operational procedures for the range of actions covered by the Operating Manual.

---

# Burning of Coal in Ships' Boilers

# Part 7, Chapter 7

Sections 1 & 2

## Section

- 1 **General**
- 2 **Coal storage, handling, ash collection and disposal arrangements**
- 3 **Coal burning equipment**
- 4 **Ship structure**
- 5 **Electrical equipment**
- 6 **Control engineering systems**
- 7 **Fire protection and extinction**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to ships using coal as a primary source of heat for the generation of steam for main and essential auxiliary services.

1.1.2 The relevant requirements of the Rules and those of the National Authority with whom the ship is registered, together with any special requirements of the Administration within whose territorial jurisdiction the ship is intended to operate, are to be complied with. Attention is drawn to the statutory requirements concerning intact and damaged stability of the ship.

1.1.3 For the purpose of these requirements, it is assumed that no manual handling of coal for the transportation from bunkers to boiler, or for actual firing of the boiler, will be employed. The emphasis has been placed on the presumption that the boiler firing will be by some form of moving grate. Special consideration will be given to other forms of firing, such as pulverized fuel, slurries of coal-oil-water mixtures or fluidized bed firing, if submitted.

1.1.4 For single main boiler installation, see Pt 5, Ch 3,5.3.

### 1.2 Submission of plans

1.2.1 The plans and information required by 1.2.2 to 1.2.4 are to be submitted in triplicate for consideration.

1.2.2 General arrangement plans and specification of the storing, handling and burning equipment and ash handling plant.

1.2.3 Structural plans showing details and arrangements in way of coal bunkers, and support arrangements for coal handling and ash disposal plans.

1.2.4 A general arrangement plan showing details of construction, fire protection and extinction for coal bunkers and coal handling systems, supplemented as necessary, by detailed plans and calculations for fire-extinguishing, explosion suppression, temperature monitoring and carbon monoxide detection systems.

### 1.3 Surveys

1.3.1 Coal bunkering, coal handling, burning and ash disposal plants are to be built, installed, and tested under operating conditions to the Surveyors' satisfaction and subsequently at each Boiler Survey. Fire-extinguishing, explosion suppression, temperature monitoring and carbon monoxide detection systems are to be installed and tested to the Surveyors' satisfaction and subsequently examined annually as required by Pt 1, Ch 3,2.2.

### 1.4 Additional bilge drainage

1.4.1 It should be noted that, under the provision of SOLAS 1974, additional bilge drainage is required for passenger ships burning coal, as detailed in 1.4.2 and 1.4.3.

1.4.2 In passenger ships there shall be provided in the boiler room, in addition to the other suctions required by the Rules, a flexible suction hose of suitable diameter and sufficient length capable of being connected to the suction side of an independent power pump.

1.4.3 In passenger ships where there is no watertight bulkhead between the engine and the boiler spaces, a direct discharge overboard or, alternatively, a by-pass shall be fitted from any circulating pump discharge used for emergency bilge pumping duties.

## ■ Section 2 Coal storage, handling, ash collection and disposal arrangements

### 2.1 Coal storage

2.1.1 The arrangements for coal bunkers, including hatchways, ventilation, monitoring and their design characteristics regarding intact and damaged stability are to comply with the requirements detailed in Sections 4 and 7, as applicable.

2.1.2 Coal is to be stored in not less than two bunkers. Vessels on restricted routes having a voyage time less than the capacity of the daily service hoppers, or where the boiler has the alternative means of firing, or where alternative means of propulsion are fitted, may be provided with only one bunker.

# Burning of Coal in Ships' Boilers

# Part 7, Chapter 7

Sections 2 & 3

2.1.3 The clearance spaces between the boilers, other heated surfaces and the coal bunkers are to be adequate for the free circulation of air necessary to avoid transmission of heat to the coal.

2.1.4 A daily service storage hopper is to be provided for each coal-fired boiler.

2.1.5 Coal bunkers and daily service storage hoppers are to be designed to avoid dead spots and areas where coal can accumulate and impede the normal flow or can provide the conditions to promote spontaneous combustion.

2.1.6 Bunker and daily service storage hopper outlet gravity-fed discharges are to be provided with shut-off devices. Stopping the transfer device will be acceptable in lieu where a bunker delivers to transfer arrangements and stopping the transfer device effectively prevents flow from the bunker, see 2.2.4.

2.1.7 Shut-off devices on the coal bunker and daily service storage hopper outlets are to be capable of being operated locally and also from an accessible position outside the compartment in which they are situated.

2.1.8 The arrangements for loading coal into bunkers or during transfer into daily service storage hoppers should, in general, avoid the tendency of the coal to segregate. For this purpose, multiple loading points should be used if necessary.

## 2.2 Coal handling

2.2.1 Each daily service storage hopper is to be provided with a separate system for transferring coal from the bunker(s). In the case of a single boiler installation, more than one transfer system from the bunker(s) to the daily service storage hopper are to be provided, unless alternative means of firing the boiler is available.

2.2.2 Adequate access facilities are to be provided in the coal feeder systems to permit maintenance and removal of blockages.

2.2.3 Where coal screens or crushers are necessary for the efficient operation of the coal burning equipment, they are to be provided in each boiler coal feed arrangement.

2.2.4 The coal handling plant is to be capable of being stopped locally and from an accessible position outside the compartment in which it is situated, see 2.1.6.

2.2.5 The use of milling systems for the production of pulverized fuel will be specially considered.

## 2.3 Ash collection and disposal arrangements

2.3.1 Each coal fired boiler is to be provided with a bottom ash and fly ash collecting and disposal arrangement.

2.3.2 Where both bottom ash and fly ash collecting and disposal arrangements are operated by either pneumatic or water systems, then these may be made common.

2.3.3 Two independent means of supplying the operating medium for ash collection and disposal systems are to be provided.

2.3.4 Heated ash storage and transfer systems are to be efficiently lagged to minimize risk of fire and to prevent damage by heat.

2.3.5 Where wet ash water transfer systems are used, consideration is to be given to the effects of corrosion and erosion on the collection, transfer and storage equipment.

2.3.6 Ash transfer systems employing water separation arrangements are to be such that water will drain naturally back to the de-watering bins or into a collection tank. Such drainage facilities should not, in general, be led directly to bilge wells.

2.3.7 Where a dry ash collection system is proposed, the arrangement of conveyors, pipes and chutes should avoid condensation due to excessive cooling to prevent solidification of the ash.

2.3.8 Adequate ash storage capacity, with access facilities to permit maintenance and removal of blockages, is to be provided for systems using boilers which have no alternative means of firing. Certain National Authorities or local Administrations prohibit the direct discharge of ash overboard.

## Section 3 Coal burning equipment

### 3.1 Operating conditions

3.1.1 The design and arrangements for coal burning equipment are to be such that it can be manually controlled from a suitable position local to the boiler fronts.

3.1.2 Burning arrangements for solid fuel firing:

- (a) The arrangements should permit a sufficient level of control of coal feed to the grates or bed to avoid uneven firing conditions likely to cause damage to the grate or bed, due to excessive heat or coal build-up, under all operating conditions.
- (b) In addition to the adequate supplies of air for efficient combustion, sufficient capacity and means of control of the combustion air supply below the grates or beds are to be provided to ensure cooling of the grate or bed under all conditions of coal or alternative means of firing.
- (c) When the coal bed is not fully incandescent, i.e. during low steaming conditions when coal-fired beds are banked or reduced in output, sufficient purging sequences to sweep the furnace volumes are to be provided before any alternative means of firing is attempted.

3.1.3 Where it is proposed to provide means of firing the boiler simultaneously on coal and oil, details of the arrangements for furnace purging and ignition of oil burners are to be submitted and will be the subject of special consideration.

# Burning of Coal in Ships' Boilers

## Part 7, Chapter 7

Sections 3 &amp; 4

### 3.2 Forced and induced draught air fans

3.2.1 In boilers fitted with forced and induced draught fans, suitable bias is to be maintained to avoid gas leakage into the boiler room.

3.2.2 In the event of induced draught fan failure, the forced draught fan should be arranged to stop automatically. Alternative arrangements which will permit the forced draught fan to be controlled to reduce the supply of air may be considered.

### 3.3 Fuel characteristics and specification

3.3.1 In general, the coal burning equipment is to be designed to utilize the various grades of coal likely to be encountered.

### 3.4 Alternative means of firing

3.4.1 Where it is proposed to use an alternative means of firing, such as oil or coal/oil slurry mixtures, the arrangements are to be in accordance with the requirements for oil burning, see Pt 5, Ch 14.

3.4.2 Particular attention is drawn to the requirements concerning arrangements for securely locking up-take dampers in the fully open position when burning oil fuel.

3.4.3 Where it is proposed to use oil fuel burners for lighting up coal fires, details are to be submitted of the pre-purging sequences of the boiler before lighting-up burners are introduced into the furnace.

3.4.4 Where it is proposed to employ lighting-up burners using diesel oil or similar marine distillate fuels, they are to be provided with their own combustion air supply.

3.4.5 Where it is proposed to use steam purging or steam atomizing oil burners with coal-fired boilers, particular attention is to be given to furnace purging arrangements. Details of the purging sequences are to be submitted.

3.4.6 The arrangements for purging the oil burners are to be such that the minimum practicable volume of oil will be introduced into the boiler furnace.

4.1.2 Other than as permitted in 4.3.2, separation between coal bunkers and adjacent spaces is to be gastight. In oil or chemical tankers, coal bunkers are to be separated from cargo tanks by means of cofferdams.

4.1.3 Boiler room access doors are to comply with Pt 3, Ch 11,6.4, as applicable.

4.1.4 Coaling ports on the side shell are to comply with parts of Pt 3, Ch 11,8 as applicable.

4.1.5 No side scuttles are to be fitted in spaces appropriated exclusively for the carriage of coal.

4.1.6 All openings from coal bunkers are to be located clear of the defined hazardous area for the particular ship type.

### 4.2 Coal bunker hatchways

4.2.1 Coal bunker hatchways are to be provided with gasketed steel covers and coamings, complying with Pt 3, Ch 11, as applicable.

4.2.2 Coal bunker hatchways are to be located clear of the defined hazardous area for the particular ship type.

### 4.3 Coal bunker bulkheads

4.3.1 The scantlings of main coal bunker boundary bulkheads which are counted towards the number of bulkheads required by Pt 3, Ch 3,4, or which form the boundary of deep tanks, are to satisfy the requirements of Pt 4, Ch 1,9. Other boundaries are to satisfy the requirements of Pt 4, Ch 1,9, but the load head may be taken to the top of the bunker. The scantlings of cofferdam bulkheads not forming the boundaries of a cargo tank in oil or chemical tankers are to satisfy the requirements of Pt 4, Ch 9,7. In all cases when flooding is envisaged as a means of fire-extinction, the moduli of stiffening members on bunker bulkhead boundaries are to be increased by 25 per cent.

4.3.2 Where the coal bunker is situated immediately forward of the engine room, the aft coal bunker bulkhead may be non-watertight. The scantlings for this bulkhead are to be as required for watertight bulkheads (Pt 4, Ch 1,9) but the load head may be taken to the top of the tank. With this arrangement, the forward end of the coal bunker may, if appropriate, be regarded as the engine room forward bulkhead.

4.3.3 The thickness of the plating in way of the bulkhead knuckles in the region of the hoppers and the plating of the hopper apexes is to be increased by 1,5 mm over that derived from 4.3.1 and 4.3.2. However, the minimum thickness of the lowest strake in the coal hopper is to be not less than 9 mm. Where solid stainless steel is employed, the plate thickness may be reduced by 10 per cent or 1 mm, whichever is the lesser.

## ■ Section 4 Ship structure

### 4.1 General

4.1.1 The requirements of this Section are additional to those given in other parts of these Rules and in separate Rules for specific ship types.

# Burning of Coal in Ships' Boilers

## Part 7, Chapter 7

Sections 4, 5 & 6

4.3.4 Non-watertight coal bunker bulkhead scantlings are to be as required by Table 1.4.8 in Pt 4, Ch 1, but the thickness of the lowest strake is to be not less than 9 mm.

4.3.5 The scantlings of the boundaries of compartments intended for the storage of ash in liquid or slurry form will be specially considered.

4.3.6 Watertight doors may be fitted in watertight bulkheads between permanent and reserve bunkers, and may be of the sliding, hinged or equivalent type. They are to be accessible at all times, see also Pt 3, Ch 11,9.

4.3.7 Arrangements are to be made by means of screens or otherwise to prevent the coal from interfering with the closing of watertight doors.

### 4.4 Longitudinal strength

4.4.1 For the purpose of longitudinal strength, the requirements for the relevant ship types are to be applied.

4.4.2 The calculation of still-water shear forces and bending moments are to cover both departure and arrival conditions, and any special mid-voyage conditions caused by variation in coal bunkering and ballast distribution. Details of typical coal stowage rates are to be submitted, as well as trim and stability data for these conditions.

4.4.3 Where local reduction of double bottom depth is proposed to accommodate coal handling equipment, the strength of the double bottom and scarfing arrangements will require special consideration. Adequate scarfing of longitudinal material in way of double bottom and hopper tanks should be arranged.

### 4.5 Ventilation

4.5.1 Ventilators serving coal bunkers or boiler rooms are to comply with Pt 3, Ch 12,2 as applicable. In addition, the atmosphere in the bunkers is to be sampled by means of fixed or portable monitors as follows:

- (a) prior to entering the space – for oxygen deficiency,
- (b) prior to opening the hatchways – for accumulation of flammable gases.

4.5.2 Ventilator exits from main coal bunkers and coal processing spaces are to discharge clear of the defined hazardous area for the particular ship type and not less than 3 m from the nearest intake or opening to accommodation and enclosed working spaces, and from possible source of ignition.

## Section 5 Electrical equipment

### 5.1 General

5.1.1 All electrical equipment should be situated in positions where it is not exposed to concentration of coal dust. Where this is not practicable, the enclosure of the equipment should be designed and installed such that:

- (a) Dust cannot enter the interior of the enclosure. An ingress protection rating of at least I.P. 55 in accordance with IEC 60529, if not of a safe-type, is considered to be acceptable.
- (b) Dust will not collect on the surface of the enclosure to such an extent that proper cooling is prevented, thus causing a dangerous rise in temperature.
- (c) The maximum surface temperature of the enclosure is not capable of igniting the dust, and should be limited to 165°C for equipment not subjected to overloading and 120°C for equipment such as motors, that may be overloaded.

### 5.2 Arrangements in coal bunkers

5.2.1 Electrical equipment located within the coal bunkers is to be of a safe-type certified for Group II A atmospheres and temperatures Class T1 in accordance with IEC 60079, *Electrical Apparatus for Explosive Atmospheres*, or an equivalent National Standard.

5.2.2 The switches and protective devices for such equipment are to interrupt all lines or phases and are to be located outside the coal bunker spaces. Provision is to be made for the complete isolation of these circuits and locking the means of control in the off position.

## Section 6 Control engineering systems

### 6.1 General

6.1.1 The requirements of Pt 6, Ch 1 are applicable. The additional requirements for boilers which are coal grate-fired and under normal operation are remotely controlled or are automatic in operation, are given in Table 7.6.1.

6.1.2 In general, ships complying with the relevant requirements of Pt 6, Ch 1,4 or Ch 1,5 will be eligible for the notations **UMS** (unattended machinery space) or **CCS** (centralized control station) respectively.



# Burning of Coal in Ships' Boilers

## Part 7, Chapter 7

Sections 6 &amp; 7

**Table 7.6.1 Coal burning: Alarms and safeguards**

Item	Alarm	Note
Drum water level	Low	Combustion air; coal spreaders and/or any alternative fuel supply to be shut-off automatically
Daily service hopper level	High/Low	—
Coal feed plant	Failure	—
Primary combustion air system	Failure	Coal spreaders to be stopped automatically
Secondary combustion air system	Failure	—
Coal supply controller (if separate from spreader)	Failure	Per controller
Spreader drive	Failure/ Overload	Per drive. See also primary combustion air system failure
Grate drive	Failure/ Overload	Per drive
Localized overheating of the grate	Excessive	—
Induced draught fan	Failure	Coal spreaders to be stopped automatically, see also 3.2.2
Ash disposal system	Failure	—
<b>NOTE</b> Interlocks are to be provided to prevent the burning of oil fuel, unless dampers in the gas passages of uptakes have been securely locked in the fully-open position, see also 3.4.2.		

7.1.2 The spaces above the coal in the coal bunkers and coal processing spaces are to be adequately ventilated to prevent the accumulation of flammable gases. The ventilators are to be provided with means of closure which are readily accessible at all times. Where mechanical ventilation is provided, means are to be provided for stopping the fans from a position which will be readily accessible at all times.

### 7.2 Fire-extinction

7.2.1 A fixed fire-extinguishing system should be provided in the coal bunkers. This system should discharge CO<sub>2</sub>, but alternative arrangements such as water flooding will be considered, see also 4.3.

7.2.2 Where, due to operating conditions, it is considered likely that coal dust in significant quantities will be present in the coal crushing and conveying system, an explosion suppression system is to be provided in the coal crushing and conveying system. Activation of the explosion suppression system is to operate an audible and visual alarm.

7.2.3 A fixed fire-extinguishing system should be provided in the ready-use coal hopper and this should be extended to the boiler room, if there is any danger of the spread of fire to that space. The system should depend on CO<sub>2</sub>, but alternative extinguishing media will be considered. Where it can be shown that the residence time, of the coal in the hopper, is of sufficiently short duration that a fire in the hopper is unlikely to be sustained, consideration will be given to dispensing with this requirement.

## Section 7 Fire protection and extinction

### 7.1 Fire protection

7.1.1 In general, the coal bunkers are to be separated from adjacent spaces by 'AO' divisions, but where such spaces are intended to contain highly flammable substances, such as the cargo tanks of an oil tanker, they are to be separated from the coal bunkers by a cofferdam or equivalent space.



# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Section 1

### Section

- 1 **General**
- 2 **Environmental criteria – Forces and motions**
- 3 **Mooring system – Design and analysis**
- 4 **Mooring equipment**
- 5 **Anchor winches and windlasses**
- 6 **Electrical and control equipment**
- 7 **Thruster-assisted positional mooring**
- 8 **Thruster-assisted mooring – Classification notation requirements**
- 9 **Trials**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to Lloyd's Register (hereinafter referred to as 'LR') classed ships with positional mooring systems or thruster-assisted positional mooring systems and are additional to those applicable in other Parts of the Rules. The Rules are not intended to apply to vessels which have station-keeping capabilities, but which are not required to remain on station in adverse weather conditions. This normally precludes the Rules being applicable to small ships.

1.1.2 Compliance with this Chapter is not mandatory, but ships provided with a positional mooring system or thruster-assisted positional mooring system which do comply will be eligible for an appropriate class notation which will be recorded in the *Register Book* at the specific request of an Owner.

1.1.3 The mooring system will be considered for classification with LR on the basis of operating constraints and procedures specified by the Owner and recorded in the Operations Manual.

1.1.4 Requirements additional to these Rules may be imposed by the National Authority with whom the ship is registered and/or by the administration within whose territorial jurisdiction it is intended to operate.

### 1.2 Classification notations

1.2.1 Ships provided with a positional mooring system which complies with the requirements of this Chapter will be eligible to have included in the class notation one of the following special features notations:

- (a) For ships fitted with a positional mooring system:  
**PM** (Positional mooring system), or  
**PMC** (Positional mooring system for mooring in close proximity to other ships or installations. This notation will apply in particular to any ship operating in conjunction with a fixed installation, e.g. crane barge, accommodation unit, maintenance vessel, etc.)
- (b) For ships fitted with a thruster-assisted positional mooring system:  
**PM**  $\textcircled{T_1}$  [or  $\textcircled{T_2}$  or  $\textcircled{T_3}$ ]  
or  
**PMC**  $\textcircled{T_1}$  [or  $\textcircled{T_2}$  or  $\textcircled{T_3}$ ]  
The numeral in the circled supplementary notation,  $\textcircled{T_1}$ , etc., defines the thruster allowance which may be permitted in the design of the positional mooring system, and is determined by the capacity/redundancy of the thrust/machinery installation, see Table 8.3.2.

1.2.2 Additional descriptive notes may be given and entered in column 6 of the *Register Book* indicating the type of positional mooring system, reference system, control system, limiting environmental criteria, etc.

### 1.3 Surveys

1.3.1 The positional mooring and thruster-assisted positional mooring systems and their associated equipment are to be examined and tested during construction and under working conditions on completion of the installation. The Periodical Survey of these items is to be arranged to coincide with Hull and Machinery Surveys as required by other Parts of these Rules.

### 1.4 Definitions

1.4.1 Positional mooring is a method of station keeping by means of multiple anchor lines laid out in catenary array. Each positional mooring system is to consist of the following:

- (a) Anchors or anchor piles.
- (b) Anchor lines.
- (c) Anchor line fittings (shackles, connecting links, wire rope terminations, quick release devices, etc.).
- (d) Fairleads.
- (e) Winches or windlasses.
- (f) Chain or wire rope stoppers.

Where applicable, the structural or mechanical connection of these items to the ship is also considered to be part of the positional mooring system.

1.4.2 'Thruster-assisted Mooring' is the use of thrusters and main propulsion, if so designed, to supplement the ship's anchoring system.

### 1.5 Plans and data submission

1.5.1 The information and plans specified in 1.5.2 to 1.5.5 are to be submitted in triplicate. One copy of the Operations Manual referred to in 1.5.6 is to be forwarded for information.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 1 & 2

1.5.2 Plans and data dealing with positional mooring arrangements and the associated equipment are to be submitted, including the following:

- (a) Mooring arrangements with details of mooring patterns, anchor lines and fittings, etc.
- (b) Mooring equipment with details of anchors, fairleads and cable stoppers.
- (c) Winches or windlasses with details of gearing shafting, brake systems, ratchet and pawl, drum/cable lifter and frame.

1.5.3 For thruster-assisted positional mooring systems, plans of the following, together with particulars of ratings, in accordance with the relevant Parts of these Rules are to be submitted for the following:

- (a) Prime movers, gearing, shafting, propellers and thrust units, see also Pt 5, Ch 8.
- (b) Machinery piping systems.
- (c) Electrical installations.

In addition, details of proposals for the redundancy provided in machinery, electrical installations and control systems are to be submitted. These proposals are to take account of the possible loss of performance capability should a component fail. Where a common power source is utilized for thrusters, details of the total maximum load required for thruster-assist are to be submitted.

1.5.4 Plans of control, alarm and safety systems, including the following, are to be submitted:

- (a) Functional block diagrams of the control system(s).
- (b) Functional block diagrams of the position reference systems and the environmental sensors.
- (c) Details of the electrical supply to the control system(s), the position reference system(s) and the environmental sensors.
- (d) Details of the monitoring functions of the controllers, sensors and reference system, together with a description of the monitoring functions.
- (e) List of equipment with identification of the manufacturer, type and model.
- (f) Details of the overall alarm system linking the centralized control station, subsidiary control stations, relevant machinery spaces and operating areas.
- (g) Details of the control stations, e.g. control panels and consoles, including the location of the control stations.
- (h) Test schedules which are to include the methods of testing and the test facilities provided.

1.5.5 The following supporting plans, data, calculations or documents are to be submitted:

- (a) General arrangement showing plan views, side elevations and sections of the ship.
- (b) Design criteria showing operating and survival environment, water depth range and required station keeping limits.
- (c) Environmental forces on ship showing wind, current and wave drift. These forces are to be verified by direct calculation, model test reports, or full-scale data, etc.
- (d) Ship motions showing first order wave motions, surge, sway and yaw. Tank test data or equivalent to be provided.
- (e) Mooring analysis, including computer printout where relevant.

- (f) Strength calculations for anchors, fairleads, winches/windlasses, cable stoppers and special fittings.
- (g) Thruster arrangements for thruster-assist systems, including powers, thrusts and interactions between thrusters, thruster and hull, thruster and current.

1.5.6 An Operations Manual for the system is to be placed on board the ship. This Manual is to contain all necessary information and instructions regarding positional mooring and, where relevant, thruster-assisted positional mooring. It would normally also contain descriptions of the following:

- Mooring systems.
- Laying the mooring system.
- Anchor pre-loading.
- Pre-tensioning anchor lines.
- Tension adjustment.
- Winch performance.
- Winch operation.
- Procedure in event of failure or emergency.
- Procedure for operating thrusters.
- Fault-finding procedures for thruster-assist system.

### Section 2

## Environmental criteria – Forces and motions

### 2.1 Limiting environmental criteria

2.1.1 Limiting criteria in the form of maximum operating and survival environmental conditions are to be specified by the Owner or Designer.

2.1.2 The limiting criteria are to be defined in terms of wind and current speeds, wave heights and periods, and water depth range.

2.1.3 As water depth will have a large influence on a ship's mooring capability, the limiting environmental criteria may be varied according to water depth.

2.1.4 **Maximum operating conditions** will be those in which the ship is able to carry out its primary operational activities, while anchor line tensions remain within designated operating limits. See 3.2 for required factors of safety in operating conditions.

2.1.5 **Survival conditions** are to be based on an average recurrence period of not less than 50 years. The mooring system is to be such that maximum line tensions will be limited in these conditions to designated survival levels. See 3.2 for required factors of safety.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 2 & 3

### 2.2 Design environmental criteria

**2.2.1 Wind.** The design wind speed for wind force determination can normally be taken as the one-hour mean value referenced to 10 m above sea level. Account is to be taken of the variation of wind speed with height above sea level. The wind velocity gradient can be calculated from the following:

$$V_H = V_{10} \left( \frac{H}{10} \right)^{0,125}$$

where

$V_H$  = wind velocity at  $H$  height above sea level

$V_{10}$  = 1 hour mean wind speed referenced to 10 m above sea level.

**2.2.2 Current.** The design current speed is to be taken as the sum of wind-induced and tidal current velocities. For calculation purposes, tidal current velocity can be assumed constant over water depth, and wind-induced current velocity can be taken to reduce linearly from its maximum value at the surface to zero at 50 m below sea level.

**2.2.3 Wave.** The significant wave height and period range is to be defined for each relevant design case.

### 2.3 Environmental forces

**2.3.1** In determining environmental forces, it is to be assumed that the defined limiting environment of wind, waves and current will act concurrently. For fixed azimuth mooring systems, these forces are considered to act in the same direction.

**2.3.2** Environmental loading on the ship (and the corresponding catenary system motions analysis to determine anchor loads and line tensions, etc.) will require to be investigated for a sufficient number of directions to establish the critical cases.

**2.3.3** It is generally to be assumed that the maximum specified environmental conditions can come from any direction relative to the ship's heading. However, in cases where a ship is to be restricted to specific defined locations, consideration will be given to the acceptance of an environmental rosette (allowing the ship to be headed in the most favourable direction with respect to mooring loads).

**2.3.4** Where quasi-static methods of analysis are adopted (see 3.1.2), at least the wind, current, and mean wave drift forces acting on the ship in the various relevant design conditions are to be calculated or determined. In addition, any significant yawing moments induced by these effects are to be taken into account when carrying out the mooring system motions analysis.

**2.3.5** Environmental forces and moments can be determined by suitable methods of direct calculation or by model testing. In either case, account must be taken of all significant load generating structural elements or equipment. In the case of wind force and moment determination, all deck structures, fittings, cranes, towers, superstructures, etc., are to be considered, and for current force, account is to be taken of thrusters, nozzles, propellers, etc.

**2.3.6** First order wave motions – the oscillatory motions of the ship – are to be determined. Surge and sway are the most relevant motions in terms of quasi-static mooring analysis, see 3.1.2 and Fig. 8.3.1.

**2.3.7** The first order wave motions of the ship are to be determined from appropriate wave spectra, either by use of tank testing or by suitable direct calculation methods.

**2.3.8** Account is to be taken of the effects of shallow water on the ship's first order wave motions.

## Section 3 Mooring system – Design and analysis

### 3.1 General

**3.1.1** The positional mooring system is to be designed to meet the specified limiting environmental criteria (see 2.1), and any associated operational constraints (restricted offset of ship, etc.) as contained in the Operations Manual.

**3.1.2** This Section in general, and the anchor line factors of safety in particular, relate principally to the quasi-static approach to mooring analysis. This method of analysis takes wind, current and wave drift forces to be steady effects which will displace the moored ship from its original equilibrium position to a new mean position where the mooring system will have developed sufficient restoring force to 'balance' the steady applied force. Wave-induced oscillatory vessel motions take place about this new mean position. In quasi-static analysis, maximum anchor line tensions are taken to occur at the extremity of vessel offset, see also Fig. 8.3.1.

**3.1.3** Consideration will be given to the adoption of alternative methods of design for the mooring system, including the use of part-dynamic or full-dynamic analysis techniques. In such cases, factors of safety, etc., will be specially considered.

**3.1.4** For ships which intend to utilize thruster assistance, as an aid to position-keeping or as a means of reducing anchor line tensions, the extent of thruster allowance which is permitted in calculations is given in Table 8.3.2.

**3.1.5** Anchor line length is to be sufficient to avoid uplift forces occurring at the anchors in the worst damaged survival condition.

**3.1.6** Account is to be taken in the mooring analysis of the elastic stretch of anchor lines.


### 3.2 Design cases and factors of safety

**3.2.1** The design cases which require to be considered, and the associated minimum anchor line factors of safety are given in Table 8.3.1.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Section 3



# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 3 & 4

**Table 8.3.1 Minimum anchor line factors of safety**

Design case	Description	Factor of safety	
		Class notation	
		PM, PM $\text{\textcircled{T1}}$ etc.	PMC, PMC $\text{\textcircled{T1}}$ etc.
1	Operating – Intact The ship in an operating mode with its mooring system intact, subject to specified operating constraints (limiting environment and permissible offset of the ship).	2,7	3,0
2	Survival – Intact The ship in survival mode with mooring system intact, subject to maximum (survival) environmental conditions.	1,8	2,0
3	Operating – Damaged As Case 1, but with loss of restraint of any one anchor line, see <i>also</i> Note 3.	1,8	2,0
4	Survival – Damaged As Case 2, but with loss of restraint of any one anchor line.	1,25	2,0/1,4 (See Note 5)

**NOTES**

- In the context of this Chapter, Cases 1 and 2 ('Intact' Cases) refer to the mooring system with all anchor lines intact. Cases 3 and 4 ('Damaged' Cases) refer to the mooring system with the loss of any one anchor line.
- Anchor line factor of safety =  $\frac{\text{Minimum rated break strength}}{\text{Maximum line tension}}$
- The factors of safety given in Table 8.3.1 are to be based on maximum line tensions resulting from steady force offset of the ship, plus maximum first order wave motion. In Design Cases 3 and 4, the factors relate to the ship in its post-damage settled position, following the loss of restraint from an anchor line, (i.e. neglecting transient effects, but see Note 4).
- In addition to the 'static' considerations in Design Cases 3 and 4 (see Note 3), account is also to be taken of transient vessel motions following anchor or line failure. The motion path taken by the vessel in moving to a new static equilibrium position is to be determined for each line breakage case to ensure that:
  - The ship maintains adequate clearance from any adjacent installation (applicable where **PMC** or **PMC  $\text{\textcircled{T1}}$**  etc. notation is to be assigned). A minimum dimensional clearance of 10 m will normally be required.
  - The ship remains within its required operational excursion limits.
  - Successive line failures will not occur. In calculating factors of safety, the maximum anchor line tensions in this case are to be those resulting from the extreme point of transient motion, with the ship subject to steady force and significant wave motion.
- The factor of safety of 2,0 applies to critical lines maintaining separation between the moored ship and an adjacent installation.

**Table 8.3.2 Thruster allowance**

Case	Thruster allowance		
	$\text{\textcircled{T1}}$	$\text{\textcircled{T2}}$	$\text{\textcircled{T3}}$
Operating (Intact)	None	70% of all thrusters, less one	All thrusters, less one
Survival (Intact)	70% of all thrusters	All thrusters	All thrusters
Operating (Damaged)	None	70% of all thrusters, less one	All thrusters, less one
Survival (Damaged)	70% of all thrusters	All thrusters	All thrusters

**NOTES**

- The conditions for assignment of supplementary notations  $\text{\textcircled{T1}}$ ,  $\text{\textcircled{T2}}$  and  $\text{\textcircled{T3}}$  are defined in Section 8.
- Where all thrusters are permitted, the net effect of all thrusters can be included in calculations.
- Where all thrusters except one are permitted, the net effect of all thrusters, less the single most effective one, can be included in calculations.

## Section 4 Mooring equipment

### 4.1 Anchors

**4.1.1** Anchors for positional mooring are to be sufficient in number and holding power, and are to have adequate structural strength, for the intended service. It is the Owners'/ Operators' responsibility to ensure adequate anchor holding power for each location or holding ground.

**4.1.2** The anchors are to be of an approved type. Supporting calculations to verify the structural strength of the anchor under proof test loading are to be submitted.

**4.1.3** The anchors are to be manufactured in accordance with the requirements of Chapter 10 of the *Rules for the Manufacture, Testing and Certification of Materials* (hereinafter referred to as the Rules for Materials (Part 2)).

**4.1.4** The anchors are to be proof tested in the manner laid down in Chapter 10 of the Rules for Materials (Part 2). The level of proof test loading for positional mooring anchors is to be the greater of the following:

- 50 per cent of the minimum rated break strength of the intended anchor line; or
- the value given in Table 10.1.1 in Chapter 10 of the Rules for Materials (Part 2).


# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Section 4

### 4.2 Fairleads

4.2.1 Fairleads are to be designed to permit free movement of the anchor line in all mooring configurations. Fig. 8.4.1 shows the minimum operating range of the fairlead to be considered in conjunction with the design load.



4.2.2 Fairleads and their supporting structures are to be designed for a load equivalent to the rated minimum break strength of the anchor line.

4.2.3 Maximum allowable stresses for the design criteria given in 4.2.1 and 4.2.2 are to be based on the following factors of safety:

Shear	1,89	} Factors relate to tensile yield stress
Tension, compression or bending	1,25	
Combined	1,11	

$$(\text{combined stress} = \sqrt{\sigma_X^2 + \sigma_Y^2 - \sigma_X \sigma_Y + 3\tau^2})$$

Where  $\sigma_X$  and  $\sigma_Y$  are the combined axial and bending stresses in the X and Y directions respectively and  $\tau$  is the combined shear stress due to torsion and/or bending in the X-Y plane.

4.2.4 Materials and steel grades are generally to comply with the requirements given in 5.2 for Type P components.

4.2.5 Chain cable fairleads are to have a minimum of five pockets.

4.2.6 Wire rope fairleads are generally to have a minimum diameter of 20 times the wire rope diameter.

### 4.3 Stoppers

4.3.1 Stoppers may require to be provided depending on the winch arrangements, see Section 5.

4.3.2 Where stoppers are fitted, they are to comply with Section 5 in respect to mechanical and strength aspects, and Section 6 for release arrangements.

### 4.4 Anchor lines

4.4.1 Anchor lines are generally to be of stud link chain cable, steel wire rope or a combination of both. Special consideration will be given to proposals for the use of alternative materials.

4.4.2 Stud link chain cable is to be either of unified grade (U2 or U3) meeting the requirements of Chapter 10 of the Rules for Materials (Part 2), or an approved special grade.

4.4.3 Wire rope for anchor lines is to have a suitable construction for its purpose (6 x 37 construction with independent wire rope core is generally acceptable).

4.4.4 Steel wire ropes are generally to comply with Ch 10,5 of the Rules for Materials (Part 2), or with an equivalent recognized National or International Standard.

4.4.5 Wire rope terminal fittings are to comply with an acceptable code or standard. The strength of terminations, connecting fittings, shackles or links is not to be less than that of the anchor line.



# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Section 5

### Section 5 Anchor winches and windlasses

#### 5.1 General

5.1.1 Machinery items are to be constructed, installed and tested in accordance with the relevant requirements of Part 5. For electrical and control equipment, see Section 6.

#### 5.2 Materials

5.2.1 Materials are generally to comply with the requirements of Pt 5, Ch 1,2.2.

5.2.2 Components have been categorized in this Section as Type P (Primary) and Type S (Secondary) for material selection purposes:

- (a) **Type P:** Components where failure would result in the loss of a primary function of the winch or windlass, e.g.:
- Winch drum.
  - Windlass cable lifter.
  - Reduction gears.
  - Shafts.
  - Brakes.
  - Pawl stoppers.
  - Bedplates.

#### NOTE

Consideration will be given to designating any of the above components as Type S (see below), provided adequate redundancy of operation exists.

- (b) **Type S:** Secondary, stressed items, not categorized as Type P, and where failure would not result in the loss of a primary winch function.

5.2.3 Steel materials for Type P or Type S components are generally to comply with the following Chapters and Sections of the Rules for Materials (Part 2):

- (a) Plates and bars: Chapter 3, Sections 1 and 2, 3 or 6, as appropriate.  
(b) Castings: Chapter 4, Sections 1 and 7.  
(c) Forgings: Chapter 5, Sections 1 and 8.

Consideration will be given to the acceptance of suitable equivalent National Standards.

5.2.4 Material grades are to be selected to provide the necessary notch toughness. See Table 8.5.1 for suitable Grades.

5.2.5 The requirements of 5.2.3 and 5.2.4 apply where the minimum design air temperature is within the range 0°C to minus 15°C. Requirements for design temperatures outside this range will be subject to special consideration.

**Table 8.5.1 Material grades**

Component type	Thickness (mm)	Grade					
		Plate		Castings		Forgings	
		AW (see Note 1)	PWHT (see Note 2)	AW	PWHT	AW	PWHT
P	$t \leq 25$	D, DH32, DH36	AH, B	C-Mn	C-Mn	LT20	LT0
	$25 < t \leq 50$	E, EH32, EH36	DH32, DH36	C-Mn	C-Mn	LT40	LT20
	$50 < t \leq 60$	E, EH32, EH36	E, EH32, EH36* (See Note 5)	C-Mn	C-Mn	LT40	LT40 (See Note 5)
	$60 < t \leq 80$	LT60 (See Note 3)	E, EH32, EH36	2 <sup>1</sup> / <sub>4</sub> Ni (See Note 3)	C-Mn	LT60 (See Note 3)	LT40
	$80 \leq t \leq 100$	LT60	LT60 (See Note 3)	2 <sup>1</sup> / <sub>4</sub> Ni	2 <sup>1</sup> / <sub>4</sub> Ni (See Note 3)	LT60	LT60 (See Note 3)
	$100 < t \leq 130$	(See Note 4)	LT60	3 <sup>1</sup> / <sub>2</sub> Ni	2 <sup>1</sup> / <sub>4</sub> Ni	(See Note 4)	LT60
	$130 < t \leq 160$	1 <sup>1</sup> / <sub>2</sub> Ni	(See Note 4)	(See Note 7)	(See Note 7)	1 <sup>1</sup> / <sub>2</sub> Ni	(See Note 4)
S	$t \leq 60$	DH32, EH36	Not normally applied (See Note 6)				
	$60 < t \leq 80$	E, EH32, EH36* (See Note 5)					
	$80 < t \leq 100$	E, EH32, EH36					
	$100 < t \leq 130$	LT60 (See Note 3)					
	$130 < t \leq 160$	LT60					

NOTES  
1. AW. Without post-weld heat treatment.  
2. PWHT. With post-weld heat treatment or not welded.  
3. Impact test temperature may be raised to -50°C.  
4. Use either 1/2 Ni or 1 1/2 Ni with impact test at -70°C.  
5. Impact test temperature may be raised to -30°C.  
6. If PWHT is used, grades will be specially considered.  
7. To be specially considered.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Section 5

5.2.6 For components such as gears, shafts and boltings made from rolled or forged bar materials not subject to welding, the material composition and heat treatment, etc. may be submitted for approval as an alternative to the requirements of Table 8.5.1.

5.2.7 Non-ductile materials are not to be used for torque transmitting items or for those elements subject to tensile/bending stresses.

5.2.8 Spheroid graphite iron castings are to comply with Ch 7,3 of the Rules for Materials (Part 2), Grades 370/17 or 400/12, or to an equivalent National Standard.

5.2.9 The use of grey iron castings will be subject to special consideration. Where approved, they are to comply with the requirements of Ch 7,2 of the Rules for Materials (Part 2). This material is not to be used for gear components.

5.2.10 Brake lining materials are to be compatible with operating environmental conditions.

### 5.3 Brakes

5.3.1 Each anchor winch or windlass is required to have one primary braking system and one secondary braking system. The two systems are to operate independently.

5.3.2 The braking action of the motor unit may be used for secondary braking purposes where the design is suitable.

5.3.3 A residual braking force of at least 50 per cent of the maximum braking force required by 5.5.1 is to be immediately available and automatically applied in the event of a power failure.

### 5.4 Stoppers

5.4.1 If the winch motor is to be used as a secondary brake, then a stopper is to be provided to take the anchor line load during maintenance of the primary brake.

5.4.2 The stopper may be one of two different types – a pawl stopper fitted at the cable lifter/drum shaft, or a stopper acting directly on the anchor line.

5.4.3 Where the stopper acts directly on the cable, its design is to be such that the cable will not be damaged by the stopper at a load equivalent to the rated breaking strength of the cable.

5.4.4 See also 6.2.1 and 6.2.2 for stopper control station requirements, and 6.4.5 for emergency release of stoppers.

### 5.5 Winch/Windlass performance

5.5.1 The primary brake is required to hold a static load equal to the minimum break strength of the anchor line (at the intended outer working layer of wire rope on storage drum winches). The static load capacity of the primary brake can be reduced to 80 per cent of that value when a stopper capable of holding 100 per cent of the breaking strength of the line is fitted.

5.5.2 The secondary brake is required to hold a static load equal to 50 per cent of the minimum breaking strength of the anchor line.

5.5.3 The anchor winch or windlass is to have adequate dynamic braking capability. The two brake systems in joint operation are to be capable of fully controlling, without overheating, the anchor lines during:

- (a) all anchor handling operations;
- (b) adjustment of anchor line tensions. (This is particularly relevant where the mooring system has been designed and sized, on the basis of active adjustment of anchor lines in extreme conditions, to minimize line tensions).

5.5.4 See also 6.2 for control of winches, windlasses, stoppers and pawls, and 6.4 for brake fail safe requirements and standby power for operation of brakes and release of stoppers in the event of a failure of normal power supply.

5.5.5 The pulling force of the winches or windlasses is to be sufficient to carry out anchor pre-loading on location, to the necessary level. A minimum low-speed pull equal to 40 per cent of the anchor line breaking strength is recommended.

### 5.6 Strength

5.6.1 Design load cases for the winch or windlass assembly and the stopper when fitted are given in Table 8.5.2. The associated maximum allowable stresses are to be based on the factors of safety given in Table 8.5.3.

**Table 8.5.2 Design load cases**

Load case	Condition	Anchor line load percentage of break strength
1	Winch braked	100% (See Note)
2	Stopper engaged	100%
3	Winch pulling	40% or specified duty pull if greater
<p>NOTE</p> <p>Where stopper is fitted, anchor line load in Case 1 can be taken as brake slipping load, but is not to be less than 80 per cent break strength.</p>		

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 5 &amp; 6

**Table 8.5.3 Safety factors for design load cases**

Stress	Load case	
	1 & 2	3
	Factor of safety	
Shear	1,89	2,5
Tension, compression, bending	1,25	1,67
Combined	1,11	1,43
NOTES 1. Factors of safety relate to tensile yield stress. 2. Combined stress = $\sqrt{\sigma_X^2 + \sigma_Y^2 - \sigma_X\sigma_Y + 3\tau^2}$  Where $\sigma_X$ and $\sigma_Y$ are the combined axial and bending stresses in the X and Y directions respectively and $\tau$ is the combined shear stress due to torsion and/or bending in the X-Y plane.		

### 5.7 Testing

5.7.1 Works tests are to be carried out in the presence of the Surveyor, on at least one of the winch or windlass units out of the total outfit for the vessel. The tests to be carried out are given in Table 8.5.4. Alternatively, where a prototype winch has been suitably tested, consideration will be given to the acceptance of these results.

**Table 8.5.4 Works test**

Test	Test load
Static brake – Primary	100% Anchor line break strength (or 80% where stopper fitted. See 5.5.1)
Static brake – Secondary	50% Anchor line break strength
Stopper (where fitted)	100% Anchor line break strength
Motor stall test	Specified stall load

5.7.2 The residual braking capability (see 5.5.4) is to be verified.

5.7.3 Each winch or windlass is to be tested on board the vessel, in the presence of the Surveyor, to demonstrate that all main aspects, including dynamic brakes, function satisfactorily. The proposed test programme is to be submitted.

### 5.8 Type approval

5.8.1 Winches or windlasses may be type approved in accordance with LR's Type Approval Scheme. Where this type approval is obtained, the requirements of 5.7.1 may not be applicable.

## Section 6

### Electrical and control equipment

#### 6.1 General

6.1.1 The electrical installation is to be designed, constructed and installed in accordance with the relevant requirements of Pt 6, Ch 2.

6.1.2 Control, alarm and safety systems are to be designed, constructed and installed, in accordance with the relevant requirements of Pt 6, Ch 1, together with the requirements of 6.2 to 6.4.

#### 6.2 Control stations

6.2.1 The operation of winches, windlasses and associated brakes, chainstoppers and pawls is to be controlled locally from weather-protected control stations which provide good visibility of the equipment and associated anchor handling operations.

6.2.2 A central control station, which may be located on the bridge or a separate manned control room, is to be provided from which brakes, chainstoppers and pawls can be remotely released.

6.2.3 For each anchor winch, the respective local control station is to be provided with a means of indicating the following:

- Line tension.
- Length of line paid out.
- Line speed.

6.2.4 The indication required by 6.2.3(a) and (b) is to be repeated to the central control station and, in addition, a means of indicating the following is to be provided at this position:

- Mooring patterns and anchor line catenaries.
- Status of winch operation.
- Position and heading, *see also* 6.4.6.
- Gangway angle and extension, when applicable.
- Riser angle, when applicable.
- Wind speed and direction, *see also* 6.4.9.

6.2.5 Means of voice communication are to be provided between the central control station, each local control station and anchor handling vessels, when applicable.

#### 6.3 Alarms

6.3.1 Alarms are to be provided at the local and central control stations for the following fault conditions:

- Excessive line tension.
- Loss of line tension.
- Excessive gangway angle and extension, when applicable.
- Excessive riser angle, when applicable.

6.3.2 Alarms are to be provided adjacent to the winches and windlasses to warn personnel prior to and during any remote operation.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 6, 7 & 8

6.3.3 Alarms are to be provided at the central control station for the following fault conditions:

- (a) When the ship deviates from its predetermined area of operation.
- (b) When the ship deviates from its predetermined heading limits.

These alarms are to be adjustable, but should not exceed specified limits. Arrangements are to be provided to fix and identify their set points.

### 6.4 Controls

6.4.1 Adequate controls are to be provided at the local control station for satisfactory operation of the winch(es).

6.4.2 The braking system is to be arranged so that the brakes, when applied, are not released in the event of a failure of the normal power supply.

6.4.3 Standby power is to be provided to enable winch brakes to be released within 15 seconds in an emergency. The release arrangements are to be operable locally at each winch and from the central control position, and are to be such that the entire anchor line can be lowered in a controlled manner.

6.4.4 The standby power is to be such that, during lowering of the anchor line, it is possible to apply the brakes once and then release them again in a controlled manner.

6.4.5 Standby power is to be provided, so that any anchor line stoppers or pawl mechanisms may be released from either the local or central control stations up to a line tension equal to the minimum rated break strength of the anchor line. These mechanisms are to be capable of release at the maximum angles of heel and trim under the damage stability and flooding conditions for which the ship is designed.

6.4.6 At least one position reference system and one gyrocompass or equivalent is to be provided, when applicable, to ensure the specified area of operation and heading deviation can be effectively monitored.

6.4.7 Position reference systems are to incorporate suitable position measurement techniques which may be by means of acoustic devices, radio, radar, taut wire, riser angle, gangway extension and angle or other acceptable means depending on the service conditions for which the ship is intended.

6.4.8 A vertical reference sensor is to be provided, if applicable, to measure the pitch and roll of the ship.

6.4.9 Means are to be provided to ascertain the wind speed and direction acting on the ship.

### Section 7

### Thruster-assisted positional mooring

#### 7.1 General

7.1.1 When the positional mooring system is supplemented by thrusters, the requirements of Pt 7, Ch 4, are to be generally complied with in respect of the machinery, electrical and control engineering arrangements. In applying these requirements, the arrangements for the notations **DP(CM)**, **DP(AM)** and **DP(AA)** may be regarded as equivalent to those for supplementary notations **T1**, **T2** and **T3** respectively, unless otherwise stated in this Chapter.

#### 7.2 Control systems

7.2.1 Suitable processing and comparative techniques are to be provided at the central control station to validate the control system inputs, thereby ensuring optimum performance of the thruster-assisted mooring system.

7.2.2 Abnormal signal errors revealed by the validity checks required by 7.2.1 are to initiate alarms.

7.2.3 The control system is to be stable throughout its operational range and is to meet the specified performance and accuracy criteria.

7.2.4 An alarm is to be provided for a control computer system fault.

7.2.5 Sufficient instrumentation is to be fitted at the central control station to ensure effective control and indicate that the system is functioning correctly, *see also* 6.2.

7.2.6 The deviation from the desired heading and/or position is to be adjustable, but should not exceed the specified limits. Arrangements are to be provided to fix and identify the set points for the desired heading and/or position.

### Section 8

### Thruster-assisted mooring – Classification notation requirements

#### 8.1 Notation **T1**

8.1.1 For assignment of notation **T1**, the applicable requirements of Sections 6 and 7, together with 8.1.2, are to be complied with.

# Positional Mooring and Thruster-Assisted Positional Mooring Systems

## Part 7, Chapter 8

Sections 8 &amp; 9

8.1.2 Centralized automated manual control of the thrusters is to be provided to supplement the position mooring system. The manual control system is to provide output signals to the thrusters, via the manual controller, to change the speed, pitch and azimuth angle, as applicable, thereby optimizing line tension, as indicated at the central control station, see 6.2.4.

### 8.2 Notation (T2)

8.2.1 For assignment of notation (T2), the applicable requirements of Sections 6 and 7, together with 8.2.2 to 8.2.5, are to be complied with.

8.2.2 Automatic and manual control systems are to be provided to supplement the positional mooring systems and arranged to operate independently, so that failure in one system will not render the other system inoperative. *See also* 8.1.2 for manual control.

8.2.3 The automatic control system is to utilize automatic input(s) from the position reference system, the environmental sensors and line tensions, and automatically provide output signals to the thrusters to change the speed, pitch and azimuth angle, as applicable, thereby optimizing line tension.

8.2.4 In the event of line failure or failure of the most effective thruster, the ship is to be capable of maintaining its predetermined area of operation and desired heading in the environmental conditions for which the ship is designed and/or classed.

8.2.5 Control, alarm and safety systems are to incorporate a computer-based consequence analysis, which may be continuous or at predetermined intervals, and is to analyse the consequence of predetermined failures to verify that the anchor line tensions and position/heading deviations remain within acceptable limits. In the event of a possible hazardous condition, arising as a result of the consequence analysis, an alarm is to be initiated at the central control station.

### 8.3 Notation (T3)

8.3.1 For assignment of notation (T3), the applicable requirements of Sections 6 and 7, together with 8.2.3 to 8.2.5 and 8.3.2 to 8.3.5, are to be complied with.

8.3.2 Two automatic control systems are to be provided and arranged to operate independently, so that failure in one system will not render the other system inoperative.

8.3.3 In the event of failure of the working system, the standby automatic control system is to be arranged to changeover automatically without manual intervention and without any adverse effect on the ship's station keeping capability. The automatic changeover is to initiate an alarm.

8.3.4 At least two position reference systems, as defined by 6.4.7, are to be provided.

8.3.5 At least two of each of the environmental sensors, as required by 6.4.8 and 6.4.9, are to be provided.

## Section 9 Trials

### 9.1 General

9.1.1 Before a new installation (or any alteration or addition to an existing installation) is put into service, trials are to be carried out. These trials are in addition to any acceptance tests which may have been carried out at the manufacturers' works and are to be based on the approved test schedules list as required by 1.5.4(h).

9.1.2 The suitability of the positional mooring and/or thruster-assisted positional mooring system is to be demonstrated during sea trials, observing the following:

- (a) Response of the system to simulated failures of major items of control and mechanical equipment, including loss of electrical power.
- (b) Response of the system under a set of predetermined manoeuvres for changing:
  - (i) Location of area of operation.
  - (ii) Heading of the ship.
- (c) Automatic thruster control and line tension optimization.
- (d) Monitoring and consequence analyses.
- (e) Simulation of line breakage and damping.
- (f) Continuous operation of the thruster-assisted positional mooring system over a period of four to six hours.

9.1.3 Two copies of the test schedules, as required by 1.5.4(h), signed by the Surveyor and Builder, are to be provided on completion of the survey. One copy is to be placed on board the ship and the other submitted to LR.



# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 1

### Section

- 1 **General requirements**
- 2 **Physical conditions**
- 3 **Workstations**
- 4 **Systems**
- 5 **Integrated Bridge Navigation System – IBS notation**
- 6 **Trials**

## ■ Section 1 General requirements

### 1.1 General

1.1.1 The requirements of this Chapter apply to ships where an optional class notation for optimizing environment on the bridge for navigational tasks including periodic operation of the ship under the supervision of a single watchkeeper on the bridge is requested, and are additional to those applicable in other Parts of the Rules.

1.1.2 The requirements of this Chapter are based on the understanding that the *International Regulations for Preventing Collisions at Sea* and all other relevant Regulations relating to Radio Communications and Safety of Navigation required by Chapters IV and V respectively of SOLAS are complied with.

1.1.3 Requirements additional to those in this Chapter may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction it is intended to operate.

1.1.4 The requirements of this Chapter are framed on the understanding that contingency plans for emergencies are specified and the conditions under which one man watch is permitted are clearly defined in an operations manual which is acceptable to the Administration with which the ship is registered.

1.1.5 In general, ships complying with the requirements of this Chapter will be eligible for the notation **NAV1**.

1.1.6 Section 5 of this Chapter states additional requirements which apply where the navigational functions are integrated. In general, ships complying with the requirements of Section 5 will be eligible for the notation **IBS**, see Pt 1, Ch 2.2.4.

### 1.2 Information and plans required to be submitted

1.2.1 The following information and plans are to be submitted in triplicate:

- Details of the intended area of operation of the ship.
- List of navigational equipment detailing manufacturer, and model and National Authority approval (where applicable).
- Functional block diagrams and descriptions of the navigational equipment, internal communications systems and watch safety system indicating their relationship to each other.
- Details of the electrical power supplies to the navigational equipment, internal communications systems, watch safety system, and clear view arrangements.
- A general arrangement of the ship showing the fields of vision from the bridge.
- A general arrangement of the bridge and wheelhouse showing the positions of consoles, panels, handrails, seating, windows and clear view arrangements.
- A profile view of the wheelhouse detailing the inclination of windows, heights of upper and lower edges of windows, and dimensions of consoles.
- Detailed arrangements of consoles and panels showing the layout of equipment.
- Test schedules which should include methods of testing and test facilities provided.
- A schedule of the electrical and electronic equipment referred to in 2.2.10 giving details of:
  - equipment description;
  - manufacturer;
  - type and/or model; and
  - Evidence of electromagnetic compatibility.

### 1.3 Definitions

1.3.1 The following definitions are applicable to these Rules:

- (a) **Workstation:**  
A position at which one or several tasks, constituting a particular activity, is carried out.
- (b) **Navigation workstation:**  
A workstation at which the navigator may carry out all tasks relevant for deciding, executing and maintaining course and speed in relation to waters and traffic. The instrumentation and controls at the navigation workstation should allow the navigator to:
  - analyse the traffic situation;
  - monitor position, course, track, speed, time, propeller revolutions and pitch, rudder angle, depth of water, rate of turn, and wind speed and direction;
  - alter course and speed;
  - effect internal and external communications;
  - give and receive sound signals;
  - control navigational lights;
  - monitor and acknowledge navigational alarms;
  - confirm his well-being and watch-keeping awareness; and
  - record navigational data.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Sections 1 & 2

- (c) **Main steering position:**  
That part of the navigation workstation where those controls and instrumentation relevant to controlling the ship's course are located.
- (d) **Conning position:**  
A place on the bridge which is used by navigators when commanding, manoeuvring and controlling a ship.
- (e) **Voyage planning workstation:**  
A workstation at which the navigator may carry out the following tasks without affecting the actual navigation of the vessel:
  - examine and update charts and other relevant documentation;
  - plan a voyage as a series of waypoints, courses, speeds and turns;
  - calculate an estimated time of arrival at various points on the voyage; and
  - determine and plot the ship's position.

- (b) Between the internal entrance to the bridge and the route in (a) a clear passage of at least 700 mm in width is to be provided.
- (c) Between adjacent workstations, a clear passage of at least 700 mm is to be provided.
- (d) Between the bridge front bulkhead or any consoles and installations placed against the front bulkhead, to any consoles or installations placed away from the bridge front, a clear passage of at least 800 mm is to be provided.

Space necessary for operating at a workstation is to be considered as part of the workstation and is not to be part of the passageway.

2.1.7 The clear height between the wheelhouse deck surface covering and the underside of the deckhead is to be at least 2250 mm. The lower edge of deckhead mounted equipment is to be at least 2100 mm in open areas, passage-ways and at standing workstations.

2.1.8 Toilet facilities are to be provided on or adjacent to the bridge.

### Section 2

### Physical conditions

#### 2.1 Bridge and wheelhouse arrangement

2.1.1 The bridge configuration, arrangement of consoles and equipment location are to be such as to enable the officer of the watch to perform navigational tasks and other functions allocated to the bridge, as well as maintain an effective lookout. The following tasks are to be supported:

- navigation and manoeuvring;
- monitoring;
- manual steering;
- docking;
- planning;
- safety;
- communications; and
- conning.

2.1.2 Equipment and associated displays and indicators are to be sited at clearly defined workstations.

2.1.3 Consoles, including the chart table, are to be positioned, so that the instrumentation they contain is mounted in such a manner as to face a person looking forward. As far as practicable, operating surfaces are to be normal to the operator's line of sight.

2.1.4 From other workstations within the wheelhouse it is to be possible to monitor the navigation workstation and to maintain an effective lookout.

2.1.5 The main access to the bridge is to be by means of an internal stairway. Secondary external access is also to be provided.

2.1.6 Clear passage of at least 700 mm width is to be available to allow movement around the bridge with a minimum of inconvenience. Particular attention is to be paid to the following routes which are to be as direct as possible:

- (a) From bridge wing to bridge wing, a clear passage of at least 1200 mm in width.

#### 2.2 Environment

2.2.1 The bridge is to be free of physical hazards to personnel. There are to be no sharp edges or protuberances and wheelhouse, bridge wing and upper bridge decks are to be free of trip hazards and have non-slip surfaces whether wet or dry.

2.2.2 Sufficient hand-rails or equivalent are to be fitted inside the wheelhouse and around workstations to enable personnel to move or stand safely in bad weather. Protection of stairway openings is to be given special consideration.

2.2.3 Provision for seating is to be made in the wheelhouse. Means for securing the seating are to be provided having regard to storm conditions.

2.2.4 Glare and reflections from surfaces are to be minimized. In this respect, walls, ceilings, consoles, chart tables and other major fittings are to be provided with a suitable low reflective finish. Arrangements are to be provided to prevent the obscuration of information presented on visual display units and instruments which are fitted with transparent covers.

2.2.5 Entrance doors to the wheelhouse are to be securable from the inside, and operable with one hand. Bridge wing doors are not to be self-closing, and are to be provided with means to hold them open.

2.2.6 An adequate air conditioning or mechanical ventilation system, together with sufficient heating according to climatic conditions, is to be provided in order to maintain the temperature of the wheelhouse within the range of 14°C to 30°C and the humidity within the range 20 per cent to 60 per cent. The discharge of hot or cold air is not to be directed towards bridge personnel. Control of this system is to be provided in the wheelhouse.



# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 2

2.2.7 The noise level on the bridge is not to interfere with verbal communication, mask audible alarms, or be uncomfortable to bridge personnel. In this respect, the ambient noise level in the wheelhouse in good weather is not to exceed 65 dB(A).

2.2.8 A sound reception system or alternative means is to allow external sound signals to be heard and their direction determined within the wheelhouse.

2.2.9 Permanently installed electrical and electronic equipment is to be installed so that electromagnetic interference does not affect the proper function of the navigational systems and equipment. Installation of the equipment in accordance with the guidelines and recommendations included in IEC 60533: *Electrical and electronic installations in ships – Electromagnetic compatibility*, or an acceptable equivalent standard, would generally be considered to meet the requirement.

2.2.10 Permanently installed electrical and electronic equipment, on the bridge and in the vicinity of the bridge, that is not subject to the approval required by 3.1.13, is to have undergone electromagnetic compatibility testing that demonstrates the equipment satisfies the conducted and radiated emission requirements of:

- IEC 60533: *Electrical and electronic installations in ships – Electromagnetic compatibility*; or
- IEC 60945: *Maritime navigation and radio communication equipment and systems – General requirements – Methods of testing and required test results*.

Testing in accordance with other appropriate standards is subject to consideration and details are to be submitted.

2.2.11 To demonstrate compliance with 2.2.10, a schedule of applicable equipment is to be compiled, see 1.2.1. Where it is proposed to add to or modify the equipment referred to in 2.2.10 the schedule is to be maintained accordingly, see also 6.1.1. A copy of the schedule documentation is to be placed on board the vessel and a copy is to be made available to the LR Surveyor on request.

2.2.12 Passive electromagnetic equipment, considered not liable to cause or be susceptible to electromagnetic disturbances, may be provided with an exemption statement in place of evidence of electromagnetic compatibility for the purposes of 2.2.11. Examples of passive electromagnetic equipment include cables, purely resistive loads and batteries.

### 2.3 Lighting

2.3.1 The level of lighting is to enable bridge personnel to perform all bridge tasks, including maintenance and chart and office work, by day and night. Controls, indicators, instruments, keyboards, etc., on the bridge are to be capable of being seen in the dark, either by means of internal lighting within the equipment or the wheelhouse lighting system. A satisfactory level of flexibility within the lighting system is to be available to enable the bridge personnel to adjust the lighting in brightness and direction as required in different areas of the bridge and by the needs of individual instruments and controls.

2.3.2 All illumination and lighting of instruments, keyboards and controls are to be adjustable down to zero, except the lighting of alarm indicators and the controls of dimmers which are to remain readable.

2.3.3 Two separate circuits are to be provided for wheelhouse lighting, such that failure of any one of the circuits does not leave the space in darkness, see Pt 6, Ch 2,5.7.

2.3.4 Emergency lighting is to be provided for the wheelhouse, stairways and exits, see Pt 6, Ch 2,3.

2.3.5 Lighting used in areas and at items of equipment requiring illumination, whilst the ship is navigating, is to be such that night vision is not impaired, e.g. red lighting. Such lighting is to be arranged, so that it cannot be mistaken for a navigation light by another ship, and to prevent glare and stray image reflections.

2.3.6 In order to avoid possible confusion in colour discrimination, red lighting is not to be fitted over chart tables.

2.3.7 To avoid unnecessary light sources in the front area of the bridge, only instruments necessary for the safe navigation and manoeuvring of the ship are to be located in this area.

2.3.8 Means are to be provided to prevent the sudden flooding of light onto the bridge from alleyways, accommodation areas and the chart table area.

2.3.9 Deck and superstructure lights which may impair safe navigation are to be controlled from the bridge.

2.3.10 Each navigation light is to be provided with an audible and visual alarm to indicate failure of the light, see Pt 6, Ch 2,14.5.

2.3.11 Means are to be provided to test alarm and indicator lamps.

### 2.4 Windows

2.4.1 All wheelhouse windows are to be constructed of shatterproof toughened glass having a strength commensurate with the degree of exposure of the bridge to storm conditions and complying with a recognized National or International Standard, e.g. ISO 3254 *Shipbuilding and marine structures – Toughened safety glass for rectangular windows*.

2.4.2 Windows are to be as wide as possible and divisions between them are to be kept to a minimum. No division is to be positioned immediately forward of any workstation or on the ship's centreline.

2.4.3 To reduce reflections from internal lighting, etc., the bridge windows are to be inclined from the vertical plane top out, at an angle of not less than 10° and not more than 25°. Alternative arrangements will be specially considered.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 2

2.4.4 The height of the lower edge of the front windows is to allow a forward view over the bow for a person at the navigation workstation and is not to obstruct any of the required fields of vision, see 2.5. In this respect, the height of the lower edge of the front windows above the deck is to be kept as low as possible and, as far as practicable, is not to be more than 1000 mm above the deck surface.

2.4.5 The upper edge of the front windows is to allow a forward view of the horizon for a person with an eyeheight of 1800 mm at the conning position when the ship is pitching in heavy seas and, as far as practicable, is not to be less than 2000 mm above the deck surface.

2.4.6 Clear views through the windows in front of the conning position, navigation workstation, and, where applicable, bridge wings are to be provided at all times regardless of weather conditions. At least two windows are to provide such a view.

2.4.7 To ensure a clear view in bright sunshine, sunscreens with minimum colour distortion are to be provided. Such screens are to be readily removable and not permanently installed. Polarized and tinted windows are not to be fitted.

2.4.8 Heavy duty wipers, preferably provided with an interval function and a fresh water wash, are to be fitted.

2.4.9 Efficient cleaning, de-icing and de-misting systems are to be fitted.

2.4.10 Suitable safe external access arrangements fitted under the bridge windows are to be provided to enable cleaning in the event of failure of the above systems.


### 2.5 Fields of vision

2.5.1 It is to be possible to observe all objects necessary for navigation, including other traffic and navigation marks, in any direction from inside the wheelhouse. In this respect, there is to be a field of view around the ship of 360° obtained by an observer moving within the confines of the wheelhouse.

2.5.2 The view of the sea surface from the conning position and the navigation workstation is not to be obscured by more than two ship lengths, or 500 m, whichever is less, forward of the bow to 10° on either side, irrespective of the ship's draught, trim and deck cargo, see Fig. 9.2.1.


2.5.3 Blind sectors caused by cargo, cargo gear and other obstructions outside of the wheelhouse forward of the beam obstructing the view of the sea surface as seen from the conning position and the navigation workstation are not to exceed 10° each. The total arc of blind sectors is not to exceed 20° and the clear sector between blind sectors shall be at least 5°. However, in the view described in the preceding paragraph, each individual blind sector is not to exceed 5°.

2.5.4 The horizontal field of vision from the conning position and the navigation workstation is to extend over an arc from more than 22,5° abaft the beam on one side, through forward, to more than 22,5° abaft the beam on the other side, see Fig. 9.2.2.



2.5.5 From the main steering position, the field of vision is to extend over an arc from dead ahead to at least 60° on each side, see Fig. 9.2.3.




2.5.6 From each bridge wing, the field of vision is to extend over an arc from at least 45° on the opposite bow through dead ahead and then aft to 180° from dead ahead, see Fig. 9.2.4.



# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Sections 2 & 3



2.5.7 There is to be a line of sight from the port wing to the starboard wing through the wheelhouse.

2.5.8 The ship's side is to be visible from the bridge wing.

2.5.9 From workstations for functions other than navigation, the field of vision is to enable an effective lookout to be maintained and, in this respect, is to extend at least over an arc from 90° on the port bow, through forward, to 22,5° abaft the beam on the starboard side, see Fig. 9.2.5.

2.5.10 The height of consoles is not to interfere with the fields of vision defined above and is not to exceed 1350 mm.

### Section 3 Workstations

#### 3.1 Navigation workstation

3.1.1 A workstation for navigation is to be arranged to enable efficient operation by one person under normal operating conditions. The workstation area is to be sufficient to allow at least two operators to use the equipment simultaneously. The arrangement of instruments and controls is to allow the use of all instruments and controls necessary for navigating and manoeuvring in any normal working position.

3.1.2 An adequate conning position is to be provided close to the forward centre window. If the view in the centreline is obstructed by large masts, cranes, etc., two additional conning positions giving a clear view ahead are to be provided, one on the port side and one on the starboard side of the centreline, no more than 5 m apart. In addition to the conning position, a second position with a view of the area immediately in front of the bridge superstructure is to be provided close to a forward window or, alternatively, the conning position is to be wide enough to accommodate two persons.

3.1.3 The main steering position is to be located on the ship's centreline, unless the view ahead is obstructed by large masts, cranes, etc. In this case, the steering position is to be located a distance to starboard of the centreline sufficient to obtain a clear view ahead and special steering references for use by day and night are to be provided, e.g. sighting marks forward.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 3

3.1.4 The following facilities are to be provided at the navigation workstation:

- Radar and radar plotting facilities, see 3.1.5.
- Position-fixing system displays, see 3.1.6.
- Echo sounder display.
- Speed and distance indications, see 3.1.11 and 3.1.12.
- Gyrocompass displays, see 3.1.7.
- Magnetic compass display.
- Wind speed and direction indication.
- Steering controls and indication, see Pt 5, Ch 19.5.
- Rate of turn indication.
- Course/track controls and indications, see 3.1.8 to 3.1.10.
- Main propulsion and thruster controls and indication, see Pt 6, Ch 1, 2.6 and 3.10.
- Watch safety system acknowledge.
- Watch safety system manual initiation.
- Internal communications system.
- VHF radiotelephone.
- Time indication.
- Window clear view controls.
- Navigation lights controls.
- Whistle control.
- Morse light keys.
- Wheelhouse/equipment lighting controls.
- Automatic ship identification system (AIS) information.
- Sound reception system where fitted, see 2.2.8.

3.1.5 Two functionally independent radars or alternative means are to be provided to determine and display the range and bearing of radar transponders and other surface craft, obstructions, buoys, shorelines and navigational marks. One of the radars is to operate in the X-band (9 GHz) and the other is to operate in the S-band (3 GHz). Both radars are to include automatic plotting aids to determine collision risks, and at least one radar is to be equipped with an automatic radar plotting aid (ARPA), capable of tracking at least 20 targets, while the other is to be either ARPA or an automatic tracking aid (ATA).

3.1.6 At least two different automatic position-fixing systems giving a continuous display of latitude and longitude are to be provided. One of these is to be GPS or equivalent. The other is to be Loran C or equivalent, depending on the area of operation.

3.1.7 A gyrocompass or alternative means for determining, displaying and transmitting the ship's heading by shipborne, nonmagnetic means, is to be provided and is to be clearly readable by the helmsman at the main steering position. The heading information is to be used directly by the radars, radar plotting aids and automatic identification system, see 3.1.5 and 3.1.13. The gyrocompass is to be provided with a gyrocompass heading repeater located at the emergency steering position in the steering gear compartment and a gyrocompass bearing repeater allowing bearings to be taken over 360°.

3.1.8 An autopilot, track control system or alternative means of automatically maintaining the ship's heading or a straight track is to be provided. At any time, it is to be possible to immediately restore manual control.

3.1.9 Heading monitoring is to be provided to monitor the actual heading information by independent heading sources. An off-course warning is to be given if the actual heading of the ship deviates from the track course beyond a pre-set value. The pre-set off-course warning limit is to be large enough to prevent unnecessary alarms.

3.1.10 Where automatic track following is provided, sufficient warning is to be given of the approach of a waypoint, so that, in the event of no acknowledgement from the officer of the watch, there is adequate time for the backup navigator to reach the bridge and accept the change of course.

3.1.11 A speed log or alternative means of indicating the ship's speed and distance through water is to be provided. The speed through water measurement is to be used directly by the ARPA as an aid to collision avoidance.

3.1.12 A speed log or alternative means of indicating the ship's speed and distance over ground is to be provided. Speed over ground is to be indicated in both the fore-aft and athwartships directions.

3.1.13 Navigational systems and equipment are to be of a type approved by the national administration and in conformity with appropriate performance standards not inferior to those adopted by IMO from time to time. Documentary evidence to this effect is to be submitted. See SOLAS 1974 as amended, Ch V, Reg. 18.

3.1.14 Where alternative means of fulfilling the navigational requirements are permitted, the means are to be approved by the national administration and in conformity with appropriate performance standards.

### 3.2 Voyage planning workstation

3.2.1 A voyage planning workstation is to be provided at which the following facilities are available:

- Chart table with instruments.
- Position-fixing systems.
- Time indication.

3.2.2 Time indication at the voyage planning workstation is to be derived from the same system as used at the navigation workstation.

3.2.3 The chart table is to be large enough to accommodate all chart sizes normally used internationally for maritime traffic and is to have facilities for illuminating the chart, see also 2.3.8.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 4

### Section 4 Systems

#### 4.1 Alarm and warning systems

4.1.1 Alarms associated with navigation equipment are to be both audible and visual and are to be centralized for efficient identification. Repeater displays may be fitted on the bridge wings and at other appropriate positions on the bridge where necessary.

4.1.2 The following alarms are to be provided:

- Closest point of approach.
- Shallow depth.
- Waypoint approaching (where automatic track following is provided).
- Off-course.
- Off-track (where automatic track following is provided).
- Steering alarms, see Table 19.5.1 in Pt 5, Ch 19 or Table 20.4.1 in Pt 5, Ch 20, as applicable.
- Navigation light failure.
- Gyrocompass failure.
- Watch safety system failure.
- Failure of any power supply to the distribution panels referred to in 4.4.1.

4.1.3 Audible signals are to be designed not to startle operators. Suitable types are shown in Table 9.4.1.

**Table 9.4.1 Suitable audible signals**

Type	Typical characteristics	Considerations
Buzzer	Low intensity and frequencies	Good alerting in quiet environment without startling
Bell	Moderate intensity and frequencies	Penetrates low frequency noise well, abrupt onset has a high alert value
Chime	Moderate intensity and frequencies	Good in quiet environment, non-startling
Tone	Moderate intensity and limited frequency range	Convenient for intercom transmission, high alert value if intermittent

#### 4.2 Watch safety system

4.2.1 A watch safety system satisfying the requirements of the IMO performance standards for a bridge navigational watch alarm system (BNWAS) and approved by the national administration is to be provided to monitor the well-being and awareness of the watchkeeper. The system is not to cause undue interference with the performance of bridge functions.

4.2.2 The watch safety system is to automatically become operational whenever the ships heading or track control system is activated.

4.2.3 The system is to be such that, at a predetermined time, the watchkeeper receives warning that he must indicate his well-being by accepting the warning.

4.2.4 The time interval between warnings is to be adjustable up to a maximum of 12 minutes.

4.2.5 It is to be possible to acknowledge the warning at the navigation workstation and at other appropriate locations on the bridge where an effective look-out may be kept. Acknowledgement of any alarm is automatically to reset the time interval between warnings. Manual adjustment of controls may also be used for this purpose.

4.2.6 Visual warning indications are to be visible, and audible warning indications are to be audible, from all operational positions on the bridge where the watchkeeper may reasonably be expected to be stationed. The colour of visual indicators is not to impair night vision.

4.2.7 In the event that the watchkeeper fails to respond and accept the warning or if any alarm has not been acknowledged on the bridge, within a period of 30 seconds, the system is to immediately initiate a watch alarm to warn the Master and the appointed backup navigator through a fixed installation.

4.2.8 In the event that the watch alarm is not acknowledged, the system is to initiate the watch alarm at the locations of further crew members capable of taking corrective actions following a time delay sufficient to allow the Master or backup navigator to reach the bridge. The time interval is to be adjustable between 90 seconds up to a maximum of 3 minutes. In ships, other than passenger ships, the watch alarm to warn the further crew members may be initiated at the same time as the watch alarm to warn the Master and backup navigator.

4.2.9 The watch alarms which sound in the locations of the Master, officers and further crew members capable of taking corrective action should be easily identifiable by its sound and should indicate urgency. The volume of this alarm should be sufficient for it to be heard throughout the locations above and to wake sleeping persons.

4.2.10 Manual initiation of the watch alarm from the bridge is to be possible at any time.

4.2.11 The system is to be designed and arranged such that only the ship's Master has access for enabling and disabling it and setting the appropriate intervals, so as to prevent accidental or unauthorized operation, e.g. removing the fuses or keeping the acknowledgement button permanently depressed either accidentally or deliberately.

4.2.12 The fixed installation is to be connected to the Master's and navigating officers' cabins, offices, mess and public rooms.

4.2.13 Acknowledgement of the watch alarm is only to be possible on the bridge.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Sections 4 & 5

4.2.14 If, depending upon the shipboard work organization, the backup navigator may attend locations not connected to the alarm transfer system, a wireless portable device is to be provided enabling both the transfer of alarms and two-way speech communication with the bridge. An audible warning from the portable device is to be provided in the event of loss of the wireless link with the bridge. Alternative arrangements will be considered.

4.2.15 Failure of the watch alarm system is to activate an audible and visual alarm at the centralized alarm system.

### 4.3 Communications

4.3.1 A telephone system is to be provided to enable two-way speech communication between the wheelhouse and at least the following locations:

- machinery control station space, see Pt 6, Ch 1,2.6.8;
- emergency steering position in the steering gear compartment;
- Master's and Navigating Officers' cabins, offices, mess and public rooms.

4.3.2 The bridge is to have priority over the system.

4.3.3 A list of extension numbers is to be clearly displayed adjacent to each telephone.

### 4.4 Power supplies

4.4.1 Local distribution panels are to be provided for all items of electrically operated navigational equipment, the telephone system, the watch safety system and the clear view systems. These panels are to be supplied by two exclusive circuits, one fed from the main source of electrical power and one fed from an emergency source of electrical power. Each item of equipment is to be individually connected to its distribution panel. The power supplies to the distribution panels are to be arranged with automatic changeover facilities between the two sources, see also Pt 6, Ch 2,14.6. Failure of any power supply to the distribution panels is to initiate an audible and visual alarm. This alarm should be included in the ship's alarm system, as required by Pt 6, Ch 1,4.2, where applicable.

4.4.2 The watch safety system and the telephone system are to remain operational during blackout conditions.

4.4.3 Following a loss of power which has lasted for 45 seconds or less, all navigation functions are to be readily re-instated. In this respect, all navigational equipment is to recover within five minutes, with minimum operator intervention, by virtue of the emergency source and, where necessary, an uninterruptible power source.

### Section 5

## Integrated Bridge Navigation System – IBS notation

### 5.1 General

5.1.1 Where it is proposed that the bridge navigation functions are so arranged as to form an integrated bridge system, the requirements of 5.2 to 5.6 are to be complied with.

### 5.2 General requirements

5.2.1 For assignment of the notation **IBS**, the layout of the bridge and the equipment on the bridge are to satisfy the requirements for assignment of the notation **NAV1** (Sections 1 to 4). Where the layout of the bridge and the equipment located on the bridge satisfy the requirements of a relevant international or national ergonomic or human centred design standard or an acceptable equivalent, compliance with the requirements of Sections 1 to 4 may be relaxed.

5.2.2 The design features for computer hardware, local area networks and software required by Pt 6, Ch 1,2.10, 2.11, 2.12 and 2.13 respectively are to be complied with. Alarms associated with hardware and data communication are to be incorporated in the centralized alarm system required by 4.1.

5.2.3 Failure of a part of the integrated bridge navigation system is not to affect other parts except for those that directly depend upon the information from the defective part. Following such a failure, it is to be possible to operate each other part of the system separately.

### 5.3 Equipment

5.3.1 Two independent gyrocompasses are to be available to provide heading information to the system. The heading signal from each gyrocompass is to be continuously available for display and for providing input to all relevant items of navigational equipment.

5.3.2 Only one gyrocompass is to be used by the integrated bridge system at any time for main display and control purposes. The navigating officer is to be able to switch between compasses at any time. The non-selected compass is to be used automatically as the independent heading source for the off-course warning required by 3.1.9.

5.3.3 It is to be possible to compare readings from each gyrocompass via the navigation workstation displays.

5.3.4 Automatic comparison between the gyrocompasses is to be provided and an alarm given if the difference between heading signals exceeds a pre-set value.

5.3.5 The capability to receive and utilize differential GPS corrections (or an equivalent) is to be included in the integrated bridge system.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Section 5

5.3.6 As a minimum, the following information is to be displayed at the navigation workstation via visual display units:

- Steering mode.
- Gyro heading.
- Course to steer.
- Rate of turn.
- Rate of turn order.
- Speed and distance (from log and from GPS).
- Speed order.
- Waypoint bearing, distance and ETA.
- Water depth and alarm setpoint.
- Position fix from each available system.
- Main propulsion and thruster indication, see Pt 6, Ch 1,2.6 and Pt 6, Ch 1,3.10.
- Steering indication, see Pt 5, Ch 19,5.
- Wind speed and direction.
- Time, see 3.2.2.

5.3.7 Additional information such as machinery monitoring, fire detection, cargo control, etc., may also be provided via additional pages on the visual display units.

5.3.8 The centralized alarm system and the watch safety system required by 4.1 and 4.2 respectively are to be incorporated as functions of the integrated bridge system and are to be presented to the navigating officer via the conning display.

5.3.9 A route planning capability is to be provided by the integrated bridge system. This is to allow a voyage to be pre-planned as a series of waypoints and turn radii. It is to be possible to edit a voyage plan at any time without affecting route control and monitoring.

5.3.10 An automatic track following capability is to be provided in conjunction with the pre-planned route. The position fix used by the system is to be based at least upon GPS or equivalent, and is to be cross-checked by dead-reckoning, based upon speed over ground provided by the ship's log. In areas where differential corrections are available, it is to be possible to utilize these in the track following system.

5.3.11 In the event of failure of the track following capability, the current heading or rate of turn is to be maintained until manually altered by the navigating officer. The quality of position fix input to the system is to be monitored, see also 3.1.10 and 4.1.2.

5.3.12 The integrated bridge system is to incorporate an electronic chart display, which combines simultaneously a high resolution colour representation of a nautical chart with a continuously updated record of own ship's position, pre-planned track, and radar targets in the vicinity. The entire tactical situation is to be displayed for the navigating officer in such a way that any risk from approaching, overtaking or crossing vessels may be assessed. Factors affecting the vessel's freedom to manoeuvre, such as water depths, channel boundaries, separation zones and other traffic are to be shown on the display.

5.3.13 The following alarms are to be provided and included in the centralized alarm system specified by 4.1.1:

- Off-track.
- Waypoint approaching, see 3.1.10.
- Position fix inaccurate/lost.
- Loss of heading input.
- Loss of log input.
- Equipment or sub-system failure.
- Gyro mis-match.

5.3.14 Manual adjustment of any of the facilities of the integrated bridge system is to reset automatically the watch safety interval timer.

### 5.4 Operator interface

5.4.1 Integrated display and control functions are to adopt a consistent man-machine interface philosophy and strategy. Particular consideration is to be paid to symbols, colours, controls, and information priorities.

5.4.2 The size, colour and density of text and graphic information displayed on a visual display unit is to be such that it may be read easily from the normal operator position under all operational lighting conditions.

5.4.3 Means are to be provided for the manual adjustment of the brightness of each visual display unit.

5.4.4 All information is to be presented on a background of high contrast, emitting as little light as possible by night.

5.4.5 Paged displays are to be presented in a way which allows the operator to find quickly the information needed. An overview page is to be easily available to remind the operator of the paging system.

5.4.6 Pages are to have a standardized format. Particular types of information and functional areas should be presented in a consistent manner, e.g. in the same position on different pages.

5.4.7 Each page is to have a unique identifying label on the screen.

5.4.8 Keyboards are to be divided logically into areas enabling rapid access to a desired function. Alphanumeric, paging and specific system keys are to be grouped separately and grouping is to be identical at all operator interfaces.

5.4.9 Soft keys may be used for display control and operation of systems non-critical to the safe operation of the vessel, otherwise dedicated controls are to be used.

5.4.10 Functions requested by the operator are to be acknowledged and confirmed by the system on completion.

5.4.11 Default values, where applicable, are to be indicated by the system when requesting operator input.

5.4.12 If an input error is detected by the system, it is to allow the operator to correct the error immediately.

# Navigational Arrangements for Periodic One Man Watch

## Part 7, Chapter 9

Sections 5 & 6

5.4.13 The system is to require confirmation from the operator for critical actions, e.g. they should not rely on single keystrokes.

5.4.14 Input error messages are to guide the correct responses, e.g.:

- |            |  |
|------------|--|
| <b>use</b> | Invalid entry: re-enter set point between 0 and 10 |
| <b>not</b> | Invalid entry.                                     |

5.4.15 All functions of the integrated bridge system are to remain available in the event of a single failure of an operator interface. This is to be achieved through redundancy in the integrated bridge system interfaces.

### 5.5 Alarm management

5.5.1 All alarms provided on the bridge are to be included in the centralized alarm system required by 4.1.1.

5.5.2 In general, the alarm system is to be in accordance with Pt 6, Ch 1,2,3.

5.5.3 Alarm management on priority and functional levels is to be provided within the integrated bridge system, including distribution and recording of alarms, as required. Priorities are to be as follows:

- (a) **Emergency alarms** – alarms which indicate that immediate danger to human life, or to the ship and its machinery exists and that immediate action must be taken.
- (b) **Distress, urgency and safety alarms** – alarms which indicate that a caller is in distress or has an urgent message to transmit.
- (c) **Primary alarms** – alarms which indicate a condition that requires prompt attention to prevent an emergency condition.
- (d) **Secondary alarms** – all other alarms.

5.5.4 Appropriate alarm management on general and functional levels is to be provided. This includes prioritization, distribution and recording of alarms as required.

5.5.5 Within each priority, alarms are to be arranged in groups, in order to reduce the quantity of information presented to the operator. More detailed information on the group alarm is to be readily available from the integrated bridge system on request.

5.5.6 The following alarms are not to be grouped:

- Emergency alarms.
- Alarms associated with faults requiring speed or power reduction or the automatic shutdown of propulsion machinery.
- Steering gear alarms.

5.5.7 Alarms are to be displayed in order of priority. Within the priorities, alarms are to be displayed in the order in which they occur. The visual display units are to provide immediate display of new alarm information, regardless of the information display page currently selected. This may be achieved by provision of a dedicated alarm monitor, a dedicated area of screen for alarms or other suitable means.

5.5.8 Unacknowledged alarms are to be distinguished by either flashing text or a flashing marker adjacent to the text, and not merely by a change of colour. Acknowledged alarms are to be distinguished by either steady illuminated text or a steady illuminated marker adjacent to the text.

### 5.6 Power supplies

5.6.1 All equipment forming part of the integrated bridge navigation system is to be regarded as navigational equipment and, as such, is to have power supplies in accordance with 4.4.

## Section 6 Trials

### 6.1 General

6.1.1 Before a new installation (or any alteration or addition to an existing installation) is put into service, tests are to be carried out to ensure satisfactory operation of the navigational equipment. These tests are in addition to any acceptance tests which may have been carried out at the manufacturers' works and are based on the approved test schedule as required by 1.2.1.

6.1.2 Two copies of the test schedule, signed by the Surveyor and Builder, are to be provided on completion of the survey. One copy is to be placed on board the ship and the other submitted to Lloyd's Register.



# Carriage of Refrigerated Containers

# Part 7, Chapter 10

Section 1

## Section

- 1 **General requirements**
- 2 **Plans and documentation**
- 3 **Ventilation and hold temperature**
- 4 **Electrical, including container plug-in sockets**
- 5 **Instrumentation, control and alarm systems**
- 6 **Hold access and maintenance access arrangements**
- 7 **Water cooler refrigeration units**
- 8 **Deck-stowed refrigerated containers**
- 9 **Inspection and testing on completion**
- 10 **Spare gear**

1.1.6 An example of a typical class notation for a reefer ship classed with LR, fitted with electrical plug-in points for deck stowed refrigerated containers, would be:

✱ **CRC -/110** to maintain 110 deck-stowed refrigerated containers operating at their design condition with a 24 hour average external ambient air temperature of 35°C.

1.1.7 In addition to any class notation, an appropriate descriptive notation may be assigned to provide additional information about the ship's ability to carry refrigerated containers.

1.1.8 An example of a typical descriptive notation, which may be assigned in addition to the class notation, would be:

**crc 2,800 kW** provided with a power generating capacity of 2,800 kW dedicated to supplying the container plug-in points.

**crc 60%/40%** stowage ratio of 60% deep frozen and 40% chilled cargoes

1.1.9 These Rules do not cover any requirements for alarm and monitoring systems that may be fitted to container refrigeration units.

## ■ Section 1 General requirements

### 1.1 General

1.1.1 The requirements of this Chapter apply to ships where the class notation **CRC** 'carriage of refrigerated containers' is requested.

1.1.2 This notation may be applied to any ship which has the ability to carry refrigerated containers. The requirements of this Chapter cover refrigerated containers stowed on deck as well as in a hold space. A descriptive notation may be assigned in addition to the **CRC** notation giving details of electrical power and type of cargo.

1.1.3 The requirements are additional to the classification requirements for ships contained in other applicable parts of the Rules.

1.1.4 Ships which comply with the requirements of this Chapter will be eligible for the applicable class notation specified in Pt 1, Ch 2.2.5.

1.1.5 An example of a typical class notation for a container ship classed with LR, fitted with a ventilation system built under Special Survey and fitted with electrical plug-in points for deck stowed refrigerated containers, would be:

✱ **CRC 230/140** to maintain 230 hold-stowed and 140 deck-stowed refrigerated containers operating at their design condition with a 24 hour average external ambient air temperature of 35°C.

### 1.2 Novel arrangement and designs

1.2.1 Where the proposed ventilation arrangement is novel in design, or the ventilation system involves the use of an arrangement different from that specified in the following sections, special tests may be required and a suitable descriptive note may be assigned.

1.2.2 The carriage of refrigerated containers in the hold spaces of ships other than dedicated container ships will be given special consideration. The **CRC** and descriptive notations will be assigned provided that the ventilation system is approved, installed and tested in accordance with the requirements of this Chapter.

1.2.3 Where a dedicated fresh water circulation system is installed to supply cooling water to containers fitted with an optional water cooled condenser, the fresh water system will also need to comply with the relevant sections of Pt 5, Ch 12 of the Rules.

### 1.3 Definitions

1.3.1 **Balanced ventilation system** means a ventilation system consisting of a combination of forced draught and induced or natural draught, to produce a pressure condition in the hold space approximately equal to atmospheric pressure.

1.3.2 **Blackout** means that the main and auxiliary machinery installations, including the main power supply, are out of operation but the services for bringing them into operation (e.g. compressed air, starting current from batteries etc.) are available.

# Carriage of Refrigerated Containers

# Part 7, Chapter 10

Sections 1 & 2

**1.3.3 Container cell** means the position of an individual container. This is usually within a set of vertical cell guides and is normally enclosed by transverse stringers located above and below the container.

**1.3.4 Container electrical power supply** means the generated power supply which is dedicated to supplying the total number of refrigerated containers and the hold ventilation system fan motors.

**1.3.5 Container plug-in point** means an electrical socket located at each applicable container location on deck and each cell location below deck being in accordance with Annex L of ISO 1496-2 : 1996.

**1.3.6 Design conditions** means the lowest design internal container temperature and the design maximum hold space temperature.

**1.3.7 Hold space** means an enclosed space containing refrigerated containers. The containers are usually restrained within cell guides. For hatch coverless ships, hold space means the space below the hatch coamings.

**1.3.8 Independent ventilation system** means a ventilation system that is in no way connected to another ventilation system and there is no provision available to allow connection to another ventilation system.

**1.3.9 Refrigerated container** means a standard container with a self-contained refrigeration system, located within the outer dimensions of the container, which can be driven by electrical power fed from an external power supply. The refrigeration system may be either a 'clip-on' or an integral type of cooling unit.

**1.3.10 Stack factor** means the ratio of the actual heat flowing into the containers forming the stack, to the heat which would flow into the same containers if all their surfaces were completely exposed to the hold temperature.

**1.3.11 Standard container** means a forty-foot equivalent unit (FEU) standard production container constructed in compliance with LR's *Container Certification Scheme*, or another recognized Container Certification Scheme in accordance with ISO 1492/2 requirements. The container may be of the normal or 'high-cube' type.

**1.3.12 Stowage ratio** means the proportion of deep-frozen cargo in relation to banana or chilled cargoes. Unless specifically stated, the stowage ratio will be deemed to be 50 per cent deep-frozen and 50 per cent chilled cargo.

**1.3.13 Ventilation system** means a forced ventilation arrangement using mechanical fans to supply and/or extract air from the hold space.

## Section 2

## Plans and documentation

### 2.1 General

**2.1.1** The following plans and information regarding the hold ventilation systems and the electrical supplies to container plug-in points are to be submitted in triplicate for appraisal before construction is commenced:

(a) **Plans of ventilation arrangements:**

- Location and installation details of each hold space ventilation system showing duct arrangement and sizes.
- Details of all mechanical ventilation fans including locations, number, duty at design conditions and power consumption.
- Details of air inlets including number, type, size and locations.
- Details of air outlets including number, type, size and locations.
- Details and locations of dampers and flaps, if applicable.

(b) **Plans of hold spaces:**

- Refrigerated container stowage plans, including sectional elevation and plan views.
- Design pressure or vacuum in each hold space.
- Details of hatch cover sealing arrangements.
- Personnel access arrangements.
- Details and locations of hold temperature measurement sensors.
- Details of any pressure/vacuum safety valves if applicable.

(c) **Ventilation throughput:**

- Specified air throughput rate and proposed method of measurement.
- Design temperature rise in the hold space and corresponding diurnal external ambient air temperature and relative humidity.
- Schematic arrangement of the ventilation system showing proposed air volume and velocity at junctions.

(d) **Plans of deck-stowed containers:**

- Refrigerated container stowage plans, including sectional elevation and plan views.
- Details of access arrangements for maintenance and monitoring of refrigeration units fitted to deck-stowed containers.

(e) **Hull structure:**

- Details of associated openings through the hull structure are to be submitted.

(f) **Electrical.** In addition to the applicable requirements of Pt 6, Ch 2, 1.2, the following information and plans specific to the container plug-in points and ventilation system are to be submitted:

- Power supply arrangements to the deck stowed refrigerated containers.
- Power supply arrangements to the hold space stowed refrigerated containers.
- Power supply arrangements to the ventilation system.
- Single-line diagram of the ventilation system. This is to include rating of motors, insulation type, size and current loading of cables and make, type and rating of protective devices.

# Carriage of Refrigerated Containers

## Part 7, Chapter 10

Sections 2 &amp; 3

- A schedule of normal operating loads of the ventilation system estimated for the design conditions expected.
- (g) **Control equipment.** In addition to the applicable requirements of Pt 6, Ch 1, 1.2, the following information and plans specific to the ventilation system are to be submitted:
  - Line diagram of control circuits.
  - List of monitored, control and alarm points.
  - Locations of control panels and consoles.
  - Details of alarm system, including location of control panel and audible and visual warning devices.
- (h) **Testing:**
  - Details of the testing and commissioning programme, including instrumentation to be used, are to be submitted.

### Section 3 Ventilation and hold temperature

#### 3.1 Ventilation system

3.1.1 Means are to be provided to maintain the hold space at an acceptable temperature. This can be achieved by either; the direct removal of the waste heat from the refrigerant equipment of each container, or by the dissipation of the waste heat using large quantities of external ambient air. In each case the system is to be arranged in such a way as to minimize its effect on the hold space temperature. This may be accomplished by the use of a ventilation system of a mechanical supply and/or extract type.

3.1.2 The selection of a maximum allowable hold temperature is to be agreed between the designer and Operator/Owner. Whilst the recommendations given in these Rules do not stipulate a maximum allowable hold temperature, generally it should not exceed 45°C dry bulb. Guidance should be sought from container manufacturers on the maximum allowable ambient air temperature. When determining the maximum allowable hold temperature, the maximum number of refrigerated containers within the hold space, operating at their design condition, is to be taken into consideration.

3.1.3 The ventilation system is to have sufficient capacity to remove or dissipate the heat from each designated refrigerated container cell and maintain the hold temperature at or below the maximum allowable hold temperature.

3.1.4 The volume of air to be supplied or exhausted from a hold space per refrigerated container is at the discretion of the ventilation system designer. For guidance purposes, an indication of the amount of air required for a standard FEU having an air cooled condenser operating at the example notation as stated in 1.1.5 is as follows:

Simple supply only system	90 m <sup>3</sup> /min
Supply and exhaust duct system	75 m <sup>3</sup> /min
Sealed exhaust system	37 m <sup>3</sup> /min

3.1.5 The design of the hold space is to be compatible with the type of ventilation system proposed. For example, for supply and ducted exhaust systems, the semi enclosure of each stringer level may be beneficial. For a simple supply only system the provision of multiple gratings in each stringer level would benefit the free circulation and removal of warm air.

3.1.6 Only container cells served by the ventilation system are to be used for the transportation of refrigerated containers.

3.1.7 The design heat rejection for each container cell and the total hold space heat rejection, including any heat imparted from the ventilation system fans, if applicable, are to be stated. Guidance on heat rejection values which may be used is given below.

3.1.8 The minimum quantity of air supplied or extracted for each container cell and for each hold space is dependent on the type of system proposed and to be stated.

3.1.9 The ventilation system designer is to stipulate the maximum allowable back pressure occurring within the hold space. Due regard needs to be given to this value when selecting the ventilation fans and their ability to operate efficiently against the proposed maximum back pressure. The lower the back pressure, the more efficient the system and, hence, the lower the electrical power requirement to drive the fan motors for a given air throughput.

3.1.10 For supply air systems, the air outlet at each container location is to be such as to provide a flow of air towards the container's integral refrigeration system. Consideration should be given to the use of movable spigot outlets or ducting to allow both standard and high-cube containers to be stowed in any location.

3.1.11 The positions of supply air inlets and exhaust air outlets are to be such as to reduce the possibility of short-cycling. An adequate distance is to be maintained between inlet and outlet vents on the open deck.

3.1.12 The effect of warm exhaust air on deck-stowed refrigerated containers is to be taken into consideration. Similarly, the effect of warm exhaust air from deck-stowed refrigerated containers on the inlet air to the hold is to be considered.

3.1.13 Arrangements are to be provided to permit a rapid shutdown and effective closure of the ventilation system in each hold space in case of fire.

3.1.14 Ventilation ducts which penetrate the deck and/or hatch coaming, including dampers and/or closures, are to be made of steel and their arrangement is to be to the satisfaction of the relevant Administration. The use of non-metallic flexible ducts, local to each container location, will be acceptable provided the material demonstrates suitable low flame spread characteristics.

# Carriage of Refrigerated Containers

# Part 7, Chapter 10

Sections 3 & 4

## 3.2 Heat balance

3.2.1 The amount of heat absorbed from the hold space by each container, which is used to determine the design air change rate, is to be stated.

3.2.2 The heat gain or loss from all adjacent spaces, such as fuel oil tanks, ballast tanks, engine room, etc., is to be stated.

3.2.3 The heat rejection from the refrigeration unit of a standard TEU or FEU container when working at low temperature (minus 18°C), chill temperature (2°C) and banana carriage temperature (13°C), used to determine the design air change rate, is to be stated. The following FEU values may be used for guidance purposes:

Frozen cargo (minus 18°C/38°C)	7,0 kW
Chill cargo (2°C/38°C)	10,0 kW
Banana cargo (13°C/38°C)	13,0 kW

3.2.4 The above heat rejection values are for the container during normal operation after the cooling down period of a non-precooled cargo.

3.2.5 The stowage ratio, for the carriage of containers at different internal temperatures, which is used to determine the design air change rate, is to be stated.

3.2.6 When an extraction ventilation system is proposed, a stack factor of 0,9 may be used in the heat balance calculations. If a ventilation system using supply air only is proposed, then no stack factor can be allowed.

## 3.3 Fan redundancy

3.3.1 A single supply or exhaust fan is not to be used for multiple container stack locations.

3.3.2 Individual container cells may be fed by a system having a single mechanical fan or fans to supply and/or extract air.

3.3.3 Installed standby fans are not required. However, a minimum of one replacement fan, or fan blade assembly and motor, of each size is to be carried onboard. Fans are to be arranged to enable each to be replaced whilst the remaining systems remain in operation.

## 3.4 Hull structures

3.4.1 Special consideration will be given to installations using hull spaces for air distribution, rather than dedicated ductwork.

3.4.2 Consideration is to be given to measures to prevent ingress of water into air inlets and exhaust outlets, where applicable.

## Section 4 Electrical, including container plug-in sockets

### 4.1 General

4.1.1 In addition to the requirements of Pt 6, Ch 2, the following are to be complied with:

- (a) Electrical power for the ventilation system is to be provided by one or more separate feeder circuit(s) from the main switchboard.
- (b) Under sea-going conditions, the number and rating of service generators are to be sufficient to supply all container plug-in socket outlets and the hold space ventilation system in addition to the ship's essential services, when any one generating set is out of action.

4.1.2 The choice between a low (440 V) or high (6,600 V) distribution system serving the container plug-in point is considered a purely commercial decision. Consideration needs to be given to the fault level of the generating equipment selected and the total generating capacity of the ship. Independent of the system voltage, only the dedicated plug-in socket outlet kW value will be stated in the notation.

4.1.3 Where a distribution system exceeding 1000 V a.c. is employed, the plug-in socket outlets for each hold space may be fed from a local transformer and the following are to be complied with:

- (a) Transformers are to be fed from individual circuits divided between different sections of the main switchboard.
- (b) The electrical power for the ventilation system may be fed locally from each transformer.

4.1.4 Container plug-in socket outlets are to comply with the requirements of Pt 6, Ch 2, 12.6.

### 4.2 Plug-in socket outlet supply transformers

4.2.1 A standby transformer serving the container plug-in socket outlets is to be provided. However, if the CRC notation is not assigned, then there is no specific requirement covering the installation of a standby power supply.

4.2.2 If a standby transformer is to be provided, then the exact requirements are open to interpretation and consideration should be given to the contents of IACS Unified Interpretation SC 83 with regard to the equipment provided.

### 4.3 Container plug-in socket outlets

4.3.1 The distribution and sub-circuit cabling for the container plug-in socket outlets is to be rated at the full load capacity (maximum rated capacity).

4.3.2 Groups of container plug-in socket outlets may be fed from a number of independent sub circuits.

# Carriage of Refrigerated Containers

## Part 7, Chapter 10

Sections 4, 5 &amp; 6

4.3.3 Sub circuits are to be able to be individually switched, thus allowing a sequential start up after a prolonged (12 hours) blackout. A suitable procedure is to be proposed and approved that takes into consideration the requirements of 4.4 in addition to the requirements of Pt 6, Ch 2.

### 4.4 Generated power for plug-in socket outlets

4.4.1 When determining the dedicated generating power for the plug-in socket outlets, the electrical power drawn by the refrigeration unit of a standard TEU and FEU refrigerated container when working at both low temperature (minus 18°C) and chill temperature (2°C), is to be stated.

4.4.2 The following values for various cargoes operating at normal design conditions may be used for guidance purposes:

4.4.3 Twenty foot equivalent unit (TEU):	
Frozen cargo (minus 18°C/38°C)	5,5 kW
Chill cargo (2°C/38°C)	7,5 kW
Banana cargo (13°C/38°C)	see 4.4.5

4.4.4 Forty foot equivalent unit (FEU) including high-cube containers:

Frozen cargo (minus 18°C/38°C)	8,5 kW
Chill cargo (2°C/38°C)	11,0 kW
Banana cargo (13°C/38°C)	see 4.4.5

4.4.5 If the Owner, charterer or operator has operational data indicating that, for the ship's specific trade (for example banana only cargoes), the power provision for the refrigerated containers requirements exceeds those stated above, then these higher values should be substituted and submitted for consideration.

4.4.6 The above values are for the container during normal operation after the cooling-down period of a non-pre-cooled cargo.

4.4.7 An overall diversity factor may be applied to the container's total power requirement. Consideration is to be given to Pt 6, Ch 2, 5.6. This diversity factor is to be applied to all refrigerated container cell locations. For guidance purposes, the diversity factor is not generally to be less than 0,75.

## Section 5 Instrumentation, control and alarm systems

### 5.1 General

5.1.1 The alarm system is to indicate failure of each independent ventilation system in each hold space. If a balanced ventilation system is proposed, indication of failure for each individual part is to be given. The alarm system may be integral with the machinery space alarm system or, if fitted, the refrigerated container monitoring system.

5.1.2 Alarms are to be initiated in a manned location. Where alarms are displayed as group alarms in the main machinery space alarm system, provision is to be made to identify individual alarms at a separate control panel.

5.1.3 Alarms are to give both an audible and visual warning.

### 5.2 Hold space temperature monitoring

5.2.1 A minimum of two temperature sensors are to be provided in each hold space carrying refrigerated containers. The sensors are to be positioned to give an indication of the mean air temperature occurring in the hold space used for the carriage of refrigerated containers. Sensors are to be positioned so as not to be directly affected by warm air from the condensers.

5.2.2 The hold temperature is to be continually monitored. Temperatures are to be recorded, either automatically or manually as a hold temperature log. If temperatures are to be logged manually, then the mean temperature in each hold space is to be recorded.

5.2.3 If the mean hold space temperature rises above the design maximum, then an alarm is to be initiated.

### 5.3 Container refrigeration system alarms

5.3.1 These Rules do not cover any requirements for alarm and monitoring systems fitted to containers. It is acceptable to utilise the container power supply cables to transmit signals to a suitable receiver or data logger.

## Section 6 Hold access and maintenance access arrangements

### 6.1 Hold pressure/vacuum

6.1.1 The maximum permitted pressure or vacuum that may occur in the hold space is to be stated. It is proposed that a value, in accordance with the contents of Pt 3, Ch 1, 8.3.4, may be considered as a maximum value. An overpressure of 0,15 bar may be used for guidance purposes. If the ventilation system is capable of producing a positive pressure or vacuum in excess of the design allowable figure, then means are to be provided to protect the hold space against the effect of over pressure or vacuum. If axial supply fans are proposed, even if aerofoil fan blades are fitted, it is unlikely that the fans will be able to produce a pressure above 0,025 bar (250 mm water gauge).

6.1.2 If required, consideration is to be given to the use of a pressure or vacuum relief device or other arrangement set to operate below the maximum allowable hold pressure or vacuum.

# Carriage of Refrigerated Containers

# Part 7, Chapter 10

Sections 6, 7 & 8

6.1.3 The proposed pressure or vacuum relief device for each hold space is to be of adequate size.

## 6.2 Hold access arrangements

6.2.1 Suitable means are to be provided to allow personnel safe access to each hold space when the ventilation system is in operation. Consideration is to be given to the possible over pressure or partial vacuum that may occur in the hold space. The use of an airlock arrangement may need to be considered.

## 6.3 Maintenance access arrangements

6.3.1 Free access to each applicable container cell and hold space is to be provided to allow replacement of refrigeration equipment in the event of failure or malfunction.

6.3.2 Adequate access is to be provided to allow plugging in, data recording or retrieval and general maintenance of all deck- and hold-stowed refrigerated containers. Suitable means are to be provided to allow the removal of the compressor and electric motor from each refrigerated container.

6.3.3 Suitable safe access is to be provided to each tier of deck-stowed refrigerated containers to allow electrical connection, monitoring and maintenance. The use of fixed platforms, such as lashing bridges, should be proposed where possible.

## Section 7 Water cooler refrigeration units

### 7.1 Cooling water system

7.1.1 A minimum of two independently operated circulation pumps are to be installed. One of the pumps may be used for other services, such as a general service pump.

7.1.2 The capacity of each pump should be sufficient to supply each container at the required flow rate with an excess capacity of at least 10 per cent. This required flow rate should be obtained from the container manufacturer.

7.1.3 The fresh water system is to provide sufficient flow and even distribution to each container location. This is to be achieved using all possible combinations of fresh water pumps and dedicated refrigerated container cells.

7.1.4 The temperature of the cooling water is to be maintained in accordance with the container manufacturer's recommendations.

7.1.5 Flexible hoses are to be utilized for connecting the water supply and return pipes. The connectors on the ends of the flexible hoses are to be of a type that self-closes on disconnection. Adequate valves are to be provided to allow isolation of each cargo hold sub-circuit in the event of a leak or pipe fracture.

7.1.6 A minimum of two fresh-water to sea-water heat exchangers are to be provided. Each is to be rated at 100 per cent of the required cooling duty at the notation conditions. The second heat exchanger may be a standby or part of a common central system such as that used for main engine cooling duties. The heat exchangers are to be supplied by a minimum of two separate sea-water pumps.

7.1.7 If metal pipes are used, the contents of Pt 5, Ch 12,9.8 are to be given due consideration.

## Section 8 Deck-stowed refrigerated containers

### 8.1 General

8.1.1 Consideration is to be given to the effect of the warm air discharged from the condenser of each deck-stowed refrigerated container. When refrigerated containers are stowed on only two tiers high, it is considered that the warm air from each condenser is dissipated without any undue effect on adjacent containers.

8.1.2 If containers are to be carried three or more tiers high, then consideration is to be given to limiting the effect of short-cycling warm discharge air within the central section of the stack. The proposed method or methods for dealing with this effect are to be stated. Possible options would include reserving the central cells of each stack for non-refrigerated containers, to reduce the block effect or providing fans and ductwork to supply ambient temperature air to the bottom of each vertical stack. Trials of any proposed system are to be undertaken.

8.1.3 Any adverse effect that the warm air discharged from the hold space ventilation system has on the deck stowed refrigerated containers is to be minimised. Similarly, the warm air discharged from the deck stowed refrigerated containers is to be shielded from entering the hold space ventilating system.

# Carriage of Refrigerated Containers

## Part 7, Chapter 10

Section 9

### ■ Section 9 Inspection and testing on completion

#### 9.1 General

9.1.1 On completion of construction and all appropriate safety checks, the acceptance tests prescribed in 9.2 are to be carried out. Their purpose is to verify the correct functioning of the installation and its ability to maintain the air throughput required for the assignment of the intended class notation.

9.1.2 The proposed test schedules, including methods of testing and details of the test equipment to be provided are to be submitted to LR before the tests commence. The proposed test methods are to be appropriate for the design of the system installed and are to include such acceptance criteria as:

- (a) Volume of air to be supplied and/or exhausted at each container cell location.
- (b) Maximum allowable deviation from this air volume.
- (c) Maximum allowable pressure within the hold space when the system is under normal operating conditions.

9.1.3 Trials of the air distribution system within the hold spaces are to be witnessed by LR surveyors before the ship is put into service and prior to the **CRC** notation certificate being issued. These trials are to be in addition to any tests which may have been carried out whilst commissioning the system.

#### 9.2 Acceptance tests

9.2.1 The acceptance tests (see also 9.2.2 and 9.2.3) are to comprise the following:

- (a) Control and alarm systems are to be tested to demonstrate that they operate correctly, see also Pt 6, Ch 1,2.3.
- (b) The accuracy, calibration and functioning of all instrumentation is to be verified.
- (c) For supply air systems: Verification of each supply fan's output when running at maximum speed. Verification of the air discharge rate and operation of any distribution arrangements at each individual container cell location. During the test, all supply fans serving the hold space are to be operated simultaneously, thus replicating normal operating conditions. If a common or multiple supply fan distribution system is fitted, then the arrangements are to be verified; firstly, with all supply fans in operation and, secondly, with any one fan out of action.
- (d) For exhaust air systems: Verification of each exhaust fan's output when running at maximum speed. The volume of air being extracted from each individual container cell location is to be verified with each exhaust fan running at maximum speed. All exhaust fans serving the same hold space are to be operated simultaneously thus replicating normal operating conditions.

- (e) For combined supply and exhaust air systems: Verification of each supply and exhaust fan's output when both are running at maximum speed. The volume of air being supplied and extracted from each individual container cell location is to be verified. All fans serving the same hold space are to be operated simultaneously thus replicating normal operating conditions.
- (f) If the supply and/or exhaust ductwork is prefabricated and installed in one piece testing at the manufacturer's works may be accepted provided the following are considered:
  - Any change in the supply and/or exhaust fan(s) output due to differences in electricity supply.
  - Any de-rating of the fan throughput due to a back pressure or partial vacuum occurring within the hold space during normal operating conditions.
  - Verification of the test results is to be undertaken in a single hold space.
- (g) Where the air volume required to meet the class notation cannot be verified during testing for practical reasons, assignment of the notation is to be deferred until it is demonstrated that the system is able to achieve the specified air throughput within each hold space during a loaded passage.

9.2.2 Where a number of identical fan and ductwork installations are constructed and fitted within each hold space, the acceptance trials required in 9.2.1 need only be carried out in two separate hold spaces, provided that the results are satisfactory.

9.2.3 Where the same system is installed on a number of identical sister ships for the same Owner and by the same shipyard, the testing in accordance with 9.2.1 will only be required on the first ship of the series, provided that the results are satisfactory.

9.2.4 The effect of exhausting warm hold space ventilation air on the operation of the integral air-cooled condensers of deck stowed containers is to be established under normal operational conditions. The discharge from hold space discharges is to be suitably modified if necessary.

#### 9.3 Testing of cooling water system

9.3.1 Cooling water piping that is welded *in situ* is to be hydraulically strength tested at 1,5 times the design pressure, but in no case less than 3,5 bar g.

9.3.2 A distribution test is to be carried out to ensure that even fresh water distribution to each container as well as sufficient flow is achieved. As the fresh water system may be somewhat complicated, this test should be carried out with care, using all possible combinations of fresh water pumps installed.

9.3.3 If required, the distribution test can be carried out without containers, utilizing flexible hoses for connecting the water supply and return pipes together. The return valves should be partly closed or flexible pipe may be crimped to represent the condenser pressure drop. Water flow meters are to be installed at the highest and the lowest container levels to verify equal water flow.

9.3.4 The capacity of each pump should be measured by a flow meter with an accuracy of  $\pm 3$  per cent. Alternatively, this capacity could be obtained from the manufacturer's curves if the static pressure difference across a pump under test conditions is measured.

9.3.5 Sea-water pumps and heat exchangers are normally subjected to a functional test only.

## ■ Section 10 Spare gear

### 10.1 General

10.1.1 Adequate spares, together with the tools necessary for maintenance or repair of the ventilation systems are to be carried. The spares are to be determined by the Owner according to the design and intended service.

10.1.2 A minimum of one replacement fan, or complete fan impeller and motor assembly for each size fitted is to be carried onboard.

10.1.3 The maintenance of the spares is the responsibility of the Owner.



# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Section 1

## Section

## 1 General requirements

## 2 Environmental Protection (EP) class notation

## 3 Supplementary characters

## 4 Survey requirements

### Section 1 General requirements

## 1.1 Application

1.1.1 This Chapter contains requirements for the control of operational pollution.

1.1.2 Compliance with this Chapter is optional. A ship meeting the requirements of this Chapter will be eligible for the **EP** class notation, which will be recorded in the *Register Book*.

1.1.3 Where a ship is classed with another IACS Member and all the requirements of this Chapter are met, a Statement of Compliance will be issued. At the specific request of the Owner, the descriptive note (**EP**) may be recorded in the *Register Book*.

1.1.4 Additional requirements may be imposed by the National Authority with which the ship is registered and/or by the Administration within whose territorial jurisdiction it is intended to operate. Where such additional requirements are relevant to the ship, compliance with such Regulations is the responsibility of the Owner. If specifically requested, Lloyd's Register (hereinafter referred to as 'LR') may provide suitable certification or statement of compliance.

1.1.5 LR is to be advised of any matter that relates to the environmental performance of the ship that would affect the assignment of the **EP** class notation.

## 1.2 EP class notation

1.2.1 Section 2 states the minimum requirements to be met for assignment of the **EP** notation.

1.2.2 Section 3 contains additional requirements. Ships complying with these requirements will be eligible for one or more of the following associated supplementary characters, as applicable:

- A** Anti-fouling coatings.
- B** Ballast water management.
- G** Grey water.
- N** Oxides of nitrogen (NO<sub>x</sub>) exhaust emissions.
- P** Protected oil tanks.
- R** Refrigeration systems.
- S** Oxides of sulphur (SO<sub>x</sub>) exhaust emissions.

- V** Vapour emission control systems (tankers only).
- O** Oily bilge water.

## 1.3 Information to be submitted

1.3.1 The following are to be submitted:

- (a) One copy of all plans and information listed in 1.3.4.
- (b) Two copies of the Operational Procedures listed in 1.3.3.
- (c) One copy of every Certificate listed in 1.3.2.

1.3.2 Certificates:

- (a) MARPOL certificates, as applicable.
- (b) Safety Management Certificate (SMC) and Document of Compliance (DOC) in accordance with the International Safety Management Code (ISM Code).
- (c) Interim Engine International Air Pollution Prevention (EIAPP) Certificate or statement of compliance with the NO<sub>x</sub> emission requirements of MARPOL Annex VI.
- (d) Incinerator certificate or statement of compliance with the requirements of MARPOL Annex VI, Regulation 16.
- (e) Vapour emission control system certificate or statement of compliance with the requirements of USCG 46 CFR 39 or the IMO Standards for Vapour Emission Control Systems (MSC Circular 585) (supplementary character **V** only).
- (f) Sewage system and, where fitted, sewage treatment system statement of compliance with the requirements of USCG 33 CFR 159 and/or MARPOL 73/78 Annex IV.

1.3.3 Operational procedures:

- (a) NO<sub>x</sub> emission control, as applicable.
- (b) Oil fuel management for the control of SO<sub>x</sub> emissions.
- (c) Refrigerant management.
- (d) Oil pollution prevention measures.
- (e) Garbage management.
- (f) Sewage treatment and discharge control.
- (g) Precautionary measures to minimize the transfer of non-native organisms in ballast water.
- (h) Ballast water management, as applicable.

1.3.4 Information and plans:

- (a) SERS registration number or statement of membership of alternative scheme from IACS Member service provider.
- (b) Details of engine type, rated power and intended use for all installed engines.
- (c) Details of NO<sub>x</sub> control arrangements, as applicable.
- (d) Arrangements of permanently installed refrigeration systems (including those used for cargo temperature control, air conditioning, domestic store rooms and chiller units).
- (e) Capacity of refrigeration system.
- (f) Details of intended refrigerant(s).
- (g) Details of fire-extinguishing media to be used in fixed fire-fighting systems and portable extinguishers.
- (h) Bilge holding, waste oil and sludge tank capacities and piping arrangements.
- (i) Arrangements of non-cargo oil loading and discharge connections together with associated drip trays and drainage systems.
- (k) Oil fuel storage, settling and service tank high level alarms/overflow systems.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Sections 1 & 2

- (l) Cargo and ballast tank arrangements (tankers only).
- (m) Cargo and ballast piping system plans, including cargo tank overfill prevention arrangements (tankers only).
- (n) Arrangements of tanker cargo manifolds together with associated drip trays and drainage systems.
- (o) Details of sewage treatment and handling systems.
- (p) Capacity of sewage holding and/or treatment system.
- (q) Maximum numbers of crew and passengers.
- (r) Details of incinerator arrangements, as applicable, associated piping systems, control and monitoring equipment.
- (s) Hull coating system and leaching rate.
- (t) Ballast water treatment arrangements, as applicable (for supplementary **B** character only).
- (u) Arrangements for protected oil tanks (for supplementary **P** character only).
- (v) Details of grey water treatment plant and effluent quality (for supplementary **G** character only).
- (w) Details of self-contained vapour recovery systems, where fitted (for supplementary **V** character only).
- (x) Any information relating to the environmental performance of the ship, which may influence the assignment of the **EP** notation.

### 1.4 Alterations and additions

1.4.1 When an alteration or addition to the approved arrangements and procedures is proposed, appropriate details are to be submitted for approval.

### 1.5 In-service records

1.5.1 Records demonstrating the effective implementation of the operational procedures specified in 1.3.3, as applicable, are to be maintained.

1.5.2 These records are to be kept on board for a minimum period of three years, in a readily accessible form, and are to be available for inspection by LR Surveyors, as required.

## Section 2 Environmental Protection (EP) class notation

### 2.1 General

2.1.1 It is a prerequisite for assignment of the **EP** notation that the ship:

- (a) complies with all adopted Annexes of MARPOL, whether ratified or not, relevant to the ship;
- (b) has a valid Safety Management Certificate (SMC), in accordance with the ISM Code issued by the Flag State Administration with which the ship is registered or a duly authorized organisation complying with Resolution A.739(18) and authorized by the National Authority with which the ship is registered; and

- (c) is enrolled in LR's Ship Emergency Response Service (SERS) or the equivalent scheme of another IACS Member.

2.1.2 Where a ship, by virtue of its gross tonnage, is not required by the MARPOL Convention to have MARPOL Certification, the following are to be maintained:

- (a) An Oil Record Book in accordance with MARPOL Annex I.
- (b) A garbage management plan and record book in accordance with MARPOL Annex V.

2.1.3 Where a ship, by virtue of its gross tonnage is not required to have a SMC, it is exempt from this requirement.

2.1.4 High speed craft, as defined in LR's *Rules and Regulations for the Classification of Special Service Craft*, will be the subject of special consideration.

### 2.2 Oxides of nitrogen (NO<sub>x</sub>)

2.2.1 These requirements apply to all installed diesel engines with an individual output power greater than 130 kW, other than those used solely for emergency purposes. There are no specific requirements relating to NO<sub>x</sub> emissions from boilers, incinerators or gas turbine installations.

2.2.2 All engines falling within the scope of MARPOL Annex VI, Regulation 13 are to comply with its provisions and be certified accordingly. Certification is to be issued by a Flag State Administration or a duly authorized organisation, complying with IMO Resolutions A739(18) and A789(19).

2.2.3 Engines over 130 kW, other than those used solely for emergency purposes, not falling under the requirements of MARPOL Annex VI, Regulation 13, are also to comply with the applicable emission values detailed in paragraph 3(a) of that Regulation. The test procedure and measurement method are to be in accordance with either the Simplified Measurement Method or Direct Measurement and Monitoring Method as detailed in Chapter 6 of the NO<sub>x</sub> Technical Code.

2.2.4 Where the NO<sub>x</sub> emission limits specified in MARPOL Annex VI, Regulation 13 are exceeded, an emission reduction plan is to be developed and agreed with LR.

2.2.5 Equipment and systems used to control NO<sub>x</sub> emission levels are to:

- (a) be arranged so that failure will not prevent continued safe operation of the engine;
- (b) be operated in accordance with manufacturer's instructions;
- (c) be designed, constructed and installed to ensure structure integrity and freedom from significant vibration;
- (d) be designed to include adequate hatches for inspection and maintenance purposes; and
- (e) be instrumented to record operation. Records of operation and the degree of control are to be maintained.

Alternative control arrangements will be given special consideration.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Section 2

2.2.6 Procedures covering the use and maintenance of the equipment and systems specified in 2.2.5 are to be established and effectively implemented. Records are to be maintained which demonstrate the operation of the equipment and systems and the resultant level of NO<sub>x</sub> emissions to the atmosphere.

### 2.3 Oxides of sulphur (SO<sub>x</sub>)

2.3.1 Emission of SO<sub>x</sub> is to be controlled by limiting the sulphur content of oil fuels used on board.

2.3.2 The maximum sulphur content of oil fuel to be used on board will be dependent upon area of operation and bunkering ports. The maximum permissible fuel sulphur content will not exceed 3,5 per cent.

2.3.3 Where the grade of fuel normally used cannot be obtained with the appropriate fuel sulphur level, then a better grade of fuel meeting this requirement will need to be purchased.

2.3.4 An oil fuel management system is to detail the maximum sulphur content to be specified when ordering oil fuels and the means adopted to verify that the sulphur content of oil fuels supplied meets that requirement. This management system is to include the practices to be adopted to ensure that appropriate low sulphur oil fuels are used when the ship is within IMO designated 'SO<sub>x</sub> Emission Control Areas', as applicable.

2.3.5 Where testing to determine the sulphur content of fuel received on board is to be carried out, a representative sample is to be drawn at the time of delivery from the ship's bunker manifold using the manual or automatic sampling methods defined in ISO 3170 or 3171, or their national respective equivalents. Fuel sulphur content is to be subsequently determined using the laboratory test method ISO 8754 or an equivalent National Standard based on ISO 8754.

### 2.4 Refrigeration systems

2.4.1 These requirements apply to refrigeration and air conditioning installations on all ships. This includes refrigeration installations on conventional refrigerated cargo ships, container ships carrying produce in containers cooled by ducted air, and gas carriers fitted with reliquefaction plants. These requirements do not apply to the domestic stand-alone refrigerators used in galleys, pantries, bars and crew accommodation.

2.4.2 The use of chlorofluorocarbons (CFC) in refrigeration or air conditioning installations is prohibited.

2.4.3 Systems are to be arranged with suitable means of isolation so that maintenance, servicing or repair work may be undertaken without releasing the refrigerant charge into the atmosphere. Unavoidable minimal releases are acceptable when using recovery units.

2.4.4 For the purposes of refrigerant recovery, the compressors are to be capable of evacuating a system charge into a liquid receiver. Additionally, recovery units are to be provided to evacuate a system either into the existing liquid receiver or into cylinders dedicated for this purpose. The number of cylinders is to be sufficient to contain the complete charge between points of isolation in the system.

2.4.5 Where different refrigerants are in use they are not to be mixed during evacuation of systems.

2.4.6 Refrigerant leakage is to be minimised by leak prevention and periodic leak detection procedures. The annual refrigerant leakage rate for each system shall be less than 10 per cent of its total charge.

2.4.7 A leak detection system appropriate to the applicable refrigerant is to be provided to monitor continuously the spaces into which the refrigerant could leak. An alarm is to be given in a permanently manned location when the concentration of refrigerant in the space exceeds a predetermined limit (25 ppm for ammonia; 300 ppm for halogenated fluorocarbons). Remedial measures to repair the leakage are to be implemented as soon as practicable after an alarm is activated.

2.4.8 Procedures detailing the means to be adopted to control the loss, leakage, venting and disposal of refrigerants are to be established and implemented effectively.

2.4.9 Refrigerant inventory and log book records are to be maintained covering:

- (a) Refrigerant added to each system.
- (b) Refrigerant leaks, including remedial actions.
- (c) Refrigerant recovered and where stored.
- (d) Refrigerant disposal.

### 2.5 Fire-fighting systems

2.5.1 The use of halon or halo-carbons as the fire-extinguishing medium in fixed fire-fighting systems or extinguishers is not permitted.

### 2.6 Oil pollution prevention

2.6.1 All ships are to comply with the requirements of 2.6.2 to 2.6.11. In addition, tankers are to comply with the requirements of 2.6.12 to 2.6.18.

2.6.2 Drainage from machinery space bilges may be discharged to sea in accordance with the requirements of MARPOL 73/78, Annex I.

2.6.3 The oil-in-water content of the water discharged is to be less than 15 ppm. Oily bilge water is to be discharged through approved oil filtering equipment and a 15 ppm alarm combined with a device for automatically stopping any discharge to sea when the oil content in the discharge exceeds 15 ppm. Full records of all discharges are to be kept.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Section 2

2.6.4 Oil fuel, lubricating oil and other oil loading or discharge connections on deck are to be fitted with drip trays. Drip trays are to be fitted with closed drainage systems.

2.6.5 Oil fuel storage, settling and service tanks are to be fitted with high level alarms and/or acceptable overflow systems.

2.6.6 Leakages and waste oil from machinery and equipment are to be collected in a dedicated waste oil tank prior to disposal ashore or incineration. This waste oil tank is to be separate from the sludge tank specified in MARPOL Annex I, Regulation 2. The volume of the waste oil tank is to be of sufficient capacity to hold a complete lubricating oil charge from the largest engine used for propulsion or electrical generating purposes.

2.6.7 For those ships which only operate on distillate fuel, the waste oil and sludge tanks may be combined to form a single tank. Where such a combined tank is fitted, the total capacity is to be equal to or greater than the aggregated total of the required individual tank capacities.

2.6.8 The bilge holding tank, the waste oil tank and the sludge tank are to be arranged to facilitate the periodic removal of accumulated sediments and other material.

2.6.9 Discharge piping systems to deck from the bilge holding tank, and the waste oil tank, are to be separate from the oil fuel loading and transfer systems. The bilge holding tank and waste oil tank piping systems are to be terminated with the standard discharge connections specified in MARPOL Annex I, Regulation 13. The sludge tank may be discharged through the same piping system as the waste oil tank.

2.6.10 Means are to be provided for the collection and recovery of any oil spilled on decks.

2.6.11 Procedures covering the handling of all oils and oily wastes are to be established and implemented effectively. As a minimum, these are to cover:

- (a) loading, storage and transfer of oil fuels, lubricants, hydraulic oil, thermal heating oil and drummed oil products;
- (b) storage, transfer, discharge and disposal of oily mixtures contained in the ship's sludge, bilge holding and waste oil tanks and machinery space bilges; and
- (c) recovery of any oil spilled on decks.

2.6.12 The constructional requirements of MARPOL Annex I, Regulations 19 and 20 as applicable, are to apply to all oil tankers greater than 600 tonnes deadweight.

2.6.13 Cargo tanks are to be fitted with high level alarms and/or acceptable overflow systems.

2.6.14 The cargo tanks are to be fitted with arrangements to prevent the possible outflow of oil under overfilling conditions.

2.6.15 Cargo tank ballasting arrangements and segregated ballast systems are to be connected to separate and distinct sea chests.

2.6.16 A screw-down non-return valve is to be provided to isolate the cargo piping system from the sea connections.

2.6.17 Cargo manifold connections are to be fitted with drip trays with closed drainage systems.

2.6.18 Cargo manifold terminal pieces are to be designed, where practicable, in accordance with the relevant Oil Companies International Marine Forum (OCIMF) Recommendations for oil tanker manifolds and associated equipment.

## 2.7 Garbage handling and disposal

2.7.1 Procedures covering garbage management are to be established and effectively implemented. As a minimum, these procedures are to include:

- (a) identification of the sources of garbage;
- (b) means of minimising garbage production;
- (c) procedures for the safe and hygienic collection, segregation, storing, processing and disposal of garbage, including the use of the equipment (compactors, comminuters, incinerators or other devices) on board. These procedures are to cover all garbage generated during the normal operation of the ship. The disposal of the following materials is to be specifically covered:
  - Cargo residues.
  - Cargo associated wastes.
  - Waste oil.
  - Paint and painting materials.
  - Medical wastes.
  - Large metal objects such as oil drums and machinery components.
  - Ropes: metal, synthetic or natural fibre.
  - Rust/scale debris.
  - Ballast tank sediments.
  - Equipment containing refrigerants.

2.7.2 Where fitted, incinerators are to be designed and constructed in accordance with the requirements of IMO Resolution MEPC 76(40). A certificate of compliance issued by LR, another IACS Member or the relevant Flag State Administration is to be provided.

2.7.3 Where incineration is to be carried out, procedures are to be developed and implemented covering:

- (a) operation in accordance with the requirements of MARPOL Annex VI, Regulation 16; and
- (b) prevention of incineration within areas where incineration is prohibited by the Coastal State Administration.

## 2.8 Sewage treatment

2.8.1 The capacity of the sewage treatment system, where fitted, is to be sufficient for the maximum number of persons on board. Where 'black water' only is treated, the minimum capacity is to be 115 litres/person/day for a conventional flushing system or 15 litres/person/day for a vacuum system. Where both 'black water' and 'grey water' are treated, an additional allowance of 135 litres/person/day is to be made.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Sections 2 & 3

2.8.2 Procedures for the operation of a sewage treatment system, including the certification of performance, are to be established and effectively implemented. Records are to be maintained of maintenance, repair, remedial work and disinfectant closing rates.

2.8.3 The manufacturer's restriction on materials, which may be disposed of through the sewage treatment system, are to be clearly displayed at each input point.

2.8.4 The disinfectant dosing points of the sewage treatment system are to be readily accessible. Ready access is also to be provided for the taking of samples.

2.8.5 As an alternative to treatment, sewage may be retained onboard. The sewage holding tank is to be of adequate capacity taking into account the operation of the ship, the number of persons on board and other relevant factors. The tank is to be fitted with a visual contents gauge and a high level alarm.

2.8.6 Records are to be maintained detailing discharges from the holding tank. These should include:

- (a) the date, location and quantity of sewage discharged from the holding tank either ashore or at sea;
- (b) distance from land and ship's speed, when sewage is discharged to sea.

2.8.7 Ventilation pipes from the sewage system are to be independent of other vent systems.

### 2.9 Hull anti-fouling systems

2.9.1 Prior to 1 January 2003, the application of anti-fouling systems containing tributyltin (TBT) is acceptable provided that the leaching rate does not exceed  $4 \mu\text{g}/\text{cm}^2/\text{day}$ , as determined by ASTM Method 5108-90.

2.9.2 From 1 January 2003, the application of anti-fouling systems containing TBT is prohibited. Ships to which TBT-based anti-fouling systems have been applied prior to this date will be accepted until 1 January 2008, provided the TBT leaching rate does not exceed  $4 \mu\text{g}/\text{cm}^2/\text{day}$ , as determined by ASTM Method 5108-90.

### 2.10 Ballast water

2.10.1 All ships carrying ballast water are to implement precautionary measures to minimize the translocation of non-native organisms in their ballast water unless it can be demonstrated that the risk of translocation of non-native organisms in their ballast water and sediments is minimal.

2.10.2 As a minimum, precautionary measures to minimize the translocation of non-native organisms are to include:

- (a) minimizing the uptake of aquatic organisms, pathogens and sediments during ballasting, by limiting (or minimizing) ballasting in situations where the numbers of aquatic organisms are likely to be increased locally. For example:

- in darkness, when bottom-dwelling organisms may rise up the water column;
  - in very shallow water;
  - where propellers may stir up sediment;
  - in areas specified by the Port State for avoidance or restriction of ballasting;
- (b) monitoring of sediment build up and, where practical, routine cleaning of ballast tanks to remove sediments;
  - (c) planning uptake and discharge of ballast water such that where ballast needs to be taken on and discharged in the same port, discharge of ballast loaded in another port is to be avoided, where practicable.

## Section 3 Supplementary characters

### 3.1 Hull anti-fouling systems – A character

3.1.1 For assignment of the **A** character, the anti-fouling system applied to the ship's hull is to be non-biocidal.

### 3.2 Ballast water management – B character

3.2.1 Where ballast water management is undertaken, for assignment of the **B** character, a ballast water management plan approved by the Administration with which the ship is registered, is to be in place and implemented effectively.

3.2.2 The ballast water management plan is to be developed in accordance with IMO Resolution MEPC 127(53) and take note of the safety considerations in IMO Resolution MEPC 124(53).

3.2.3 For new ships, the guidance within IMO Resolutions MEPC 149(55) and MEPC 150(55) is to be taken account of, as far as is practicable.

### 3.3 Grey water – G character

3.3.1 Where plant for the treatment of grey water is installed and utilized effectively, the **G** character will be assigned, subject to the plant effluent meeting the standards specified in 3.3.2 or 3.3.3, as applicable.

3.3.2 Where it is not intended that the effluent is recycled or re-used for any purpose, the effluent of the grey water treatment plant is to meet the following standards:

- (a) Faecal coliforms: Content is not to exceed 250/100 ml M.P.N. (most probable number) as determined by a multiple tube fermentation analysis or an equivalent procedure.
- (b) Suspended solids:
  - Where the equipment is tested onshore, the geometric mean of the total suspended solids content of the samples of effluent taken during the test period is not to exceed 50 mg/l.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Section 3

- Where the equipment is tested onboard the ship, the geometric mean of the total suspended solids content of the samples of effluent taken during the test period is not to exceed the suspended solids content of the ambient water used onboard plus 100 mg/l.
- (c) Biochemical Oxygen Demand (BOD<sub>5</sub>):
- The geometric mean of a 5-day Biochemical Oxygen Demand is not to exceed 50 mg/l.
  - When testing onboard the ship, if insufficient time is available for obtaining a number of samples over a period of days, a BOD<sub>5</sub> not exceeding 100 mg/l on a single sample will be accepted providing that suspended solids are within the value stated above.

3.3.3 Where it is intended that the effluent of the grey water treatment plant is to be re-used or recycled for any purpose, the effluent is to meet the potable water quality standards of the Flag or Port State Administration, as appropriate.

### 3.4 Oxides of nitrogen (NO<sub>x</sub>) – N character

3.4.1 For assignment of the **N** character, the total weighted value of NO<sub>x</sub> emissions from all installed diesel engines defined within 2.2.1 is not to exceed 80 per cent of the total weighted NO<sub>x</sub> emission limits specified in MARPOL Annex VI, Regulation 13.

3.4.2 The total weighted emission value for the ship (*WV*) is to be calculated as follows:

$$WV_{\text{ship}} = \frac{WAEV_{\text{cert}}}{WAEV_{\text{IMO}}}$$

where

$$WAEV_{\text{cert}} = \frac{\sum_{n=1}^n (\text{NO}_{x[\text{cert}]}.P)}{\sum_{n=1}^n (P)}$$

$$WAEV_{\text{IMO}} = \frac{\sum_{n=1}^n (\text{NO}_{x[\text{IMO}]} \cdot P)}{\sum_{n=1}^n (P)}$$

*n* = the number of individual engines on board the ship

*P* = the rated power, in kW, of each individual installed engine

NO<sub>x[cert]</sub> = the certified NO<sub>x</sub> emission value, in g/kWh, for each individual engine

NO<sub>x[IMO]</sub> = the NO<sub>x</sub> emission limit value, in g/kWh, of each individual engine as specified in Regulation 13 of Annex VI to MARPOL.

3.4.3 The N character will be assigned when:

$$\frac{WAEV_{\text{cert}}}{WAEV_{\text{IMO}}} \leq 0,8$$

3.4.4 The test procedure and measurement method are to be in accordance with either the Simplified Measurement Method or Direct Measurement and Monitoring Method given in Chapter 6 of the IMO NO<sub>x</sub> Technical Code.

3.4.5 Systems and equipment used to control the NO<sub>x</sub> emissions are to comply with the requirements specified in 2.2.5.

3.4.6 In the case where the individual engines are 'family' or 'group' engines, as defined in the NO<sub>x</sub> Technical Code, the certified emission value may be based on that of the parent engine.

### 3.5 Oily bilge water – O character

3.5.1 For assignment of the **O** character, all drainage from machinery space bilges is to be discharged ashore, except under exceptional circumstances.

3.5.2 Alternatively, discharge to sea is permitted where it can be demonstrated that the oil-in-water content of the water discharged is less than 5 ppm.

3.5.3 Full records of all discharges are to be kept.

### 3.6 Protected oil tanks – P character

3.6.1 For assignment of the **P** character, oil fuel and lubricating oil tanks are to be located in a protected location away from the ship's side or bottom shell plating.

3.6.2 The location of tanks is to be in accordance with the requirements relating to oil fuel tank protection given in IMO Resolution MEPC.141(54).

3.6.3 The requirements apply to oil fuel and lubricating oil tanks. Main engine lubricating oil drain tanks are excluded.

3.6.4 Arrangements providing equivalent protection will be given special consideration.

3.6.5 Suction wells may protrude below oil fuel tanks provided they are as small as possible and the distance between the tank bottom and the ship's bottom shell plating is not reduced by more than 50 per cent.

### 3.7 Refrigeration systems – R character

3.7.1 For assignment of the **R** character, in addition to compliance with the requirements of 2.4, all refrigerants used onboard are to have an Ozone Depleting Potential (ODP) rating of zero and a Global Warming Potential (GWP) of less than 1950, based on a 100-year time horizon.

### 3.8 Oxides of sulphur (SO<sub>x</sub>) – S character

3.8.1 For assignment of the **S** character, all gas oil used onboard is to have a sulphur content of less than 0,20 per cent m/m. All heavy fuel oil is to have a sulphur content of less than 1,5 per cent m/m.

3.8.2 The sampling, fuel sulphur analysis methods and verification requirements stipulated in 2.3.4 and 2.3.5 are to be complied with.

# Arrangements and Equipment for Environmental Protection

## Part 7, Chapter 11

Section 3 &amp; 4

### 3.9 Vapour emission control systems – Vc and Vp characters

3.9.1 Tankers carrying crude oil, petroleum products or chemicals having a flash point not exceeding 60°C (closed-cup test) will be assigned the **Vc** or **Vp** character provided the provisions of either 3.9.2 or 3.9.3 are complied with.

3.9.2 For assignment of the **Vc** character, a vapour emission control system is to be fitted. The system is to be designed and constructed in accordance with the requirements of USCG 46, CFR 39 or the IMO Standards for Vapour Emission Control Systems (MSC Circular 585). A certificate or statement of compliance issued by LR or a competent authority recognized by LR is to be provided. As an alternative, a self-contained vapour recovery system, which is of a type approved by LR and which achieves equivalent performance to the systems above, may be fitted.

3.9.3 For assignment of the **Vp** character, a self-contained system capable of preventing vapour emission formation during loading is to be fitted. This vapour emission prevention system is to be of a type approved by LR and is to reduce vapour emission formation by at least 75 per cent (v/v) as compared to an equivalent ship to which no vapour emissions prevention system has been fitted.

## Section 4 Survey requirements

### 4.1 Initial Survey and Audit

4.1.1 Following satisfactory review of the plans and other information submitted (see 1.3), an EP Initial Survey is to be undertaken for ships under construction or in service.

4.1.2 At the EP Initial Survey, the Surveyor is to be satisfied that the requirements of these Rules, including those relating to any requested supplementary characters, are complied with. The Surveyor is to verify that the hull and machinery arrangements are in accordance with the approved documentation. The installed equipment, together with associated control and alarm systems, is to be demonstrated under working conditions.

4.1.3 Following the successful completion of the Initial Survey, the EP notation may be assigned to a ship. The EP notation will be valid, in the first instance, for a period not exceeding 12 months. During this period, an audit of the procedures as required by these Rules is to be undertaken. This audit is to be performed after the procedures have been fully implemented, subjected to internal audit and have generated at least 3 months of records under in-service conditions.

4.1.4 Audits are to confirm by direct observation, examination of internal audit reports and scrutiny of records that each of the procedures have been implemented effectively over the preceding period. It is also to be verified that:

- (a) the required resources and equipment have been provided; and
- (b) the ship's staff are aware of their duties and responsibilities, and can perform the assigned tasks.

### 4.2 Periodical Surveys and Audits

4.2.1 EP Annual Surveys and Audits are to be held on all ships to which the EP notation applies within three months of each anniversary of assignment of the full **EP** notation.

4.2.2 At the EP Annual Survey and Audit, the Surveyor is to be satisfied that the arrangements and equipment comply with these Rules and operating procedures have been implemented effectively. As far as possible, the installed equipment, together with associated control and alarm systems, are to be demonstrated under working conditions. Additionally:

- (a) where changes to arrangements or equipment fitted to meet the requirements of these Rules have been made, it is to be verified that these changes are in accordance with approved documentation; and
- (b) records for the preceding 12 months are to be reviewed.

4.2.3 EP Audits are to be undertaken in accordance with the requirements given in 4.1.4.

### 4.3 Change of company

4.3.1 Where the company (as defined in the ISM Code) changes, the **EP** notation will be suspended.

4.3.2 The new company may adopt the previously approved procedures as required by these Rules or may compile new procedures which would need to be submitted for approval.

4.3.3 Following implementation of the approved procedures, an audit, in accordance with the requirements in 4.1.3 and 4.1.4, is to be undertaken.

4.3.4 The **EP** notation will be re-assigned following successful completion of the audit provided that the ship has a valid Safety Management Certificate (SMC) and the general requirements given in 2.1.1 are complied with.





# Integrated Fire Protection (IFP) Systems

## Part 7, Chapter 12

Sections 1 &amp; 2

### Section

- 1 **General**
- 2 **Centralized fire-control station**
- 3 **Control and monitoring of active fire protection and fixed fire-extinguishing systems**
- 4 **Integration of other systems**
- 5 **Testing, trials and maintenance**

## ■ Section 1 General

### 1.1 Application

1.1.1 The requirements of this Chapter apply to ships where an optional class notation is requested for the control and monitoring of all active fire protection and fixed fire-extinguishing systems from a centralized fire-control station, implemented by means of an Integrated Fire Protection system. The requirements are additional to those applicable in other Parts of the Rules.

1.1.2 Ships provided with arrangements complying with the requirements of this Chapter will be eligible for the class notation **IFP** – Integrated Fire Protection.

1.1.3 Requirements additional to these Rules may be imposed by the National Authority with whom the ship is registered and/or by the Administration within whose territorial jurisdiction it is intended to operate.

1.1.4 It is the responsibility of the National Authority to give effect to the fire safety and other ship, passenger and crew safety measures required by the *International Convention for the Safety of Life at Sea*, 1974, as amended (SOLAS).

1.1.5 Special consideration will be given where control and monitoring arrangements prescribed and approved by the National Authority give rise to deviation from the requirements of these Rules.

### 1.2 Submission of plans and information

1.2.1 The following plans and information are to be submitted:

- A plan showing the location and physical arrangement of the centralized fire-control station.
- A list of systems and equipment that are to be controlled and monitored from the centralized fire-control station, see 1.2.2.
- Details of controls, alarms, instrumentation and monitoring including line diagrams of control circuits, descriptions of operation and programmable electronic systems details required by Pt 6, Ch 1,1.2.5.
- Details of the power supply arrangements.

- Remote stopping arrangements for independently driven oil pumps and remote oil valve closing arrangements.
- Test schedules including methods of testing and required test results.
- Failure Mode and Effects Analysis (FMEA) report, including worksheets.

1.2.2 Plans for the control and monitoring arrangements of active fire protection, fire-fighting and other integrated systems are to be submitted, including as applicable:

- Fixed fire detection and fire-alarm systems.
- Fire-pumps and fire main systems.
- Fixed water-based fire-extinguishing systems
- Fixed gas fire-extinguishing systems.
- Dry extinguishing powder systems.
- Protected space openings and ventilation systems, including related crew and passenger emergency systems, see Pt 6, Ch 2,17.

### 1.3 Definitions

1.3.1 The definitions given in Pt 6, Ch 4,2 are relevant with regard to the requirements of this Chapter.

## ■ Section 2 Centralized fire-control station

### 2.1 General

2.1.1 A centralized fire control station is to be located on the navigating bridge or in some other suitable compartment that is readily accessible from the accommodation spaces and is provided with two escape routes from the compartment, one of which is to lead directly to an open deck.

2.1.2 A copy of the fire-control plan is to be permanently displayed at the centralized fire-control station.

2.1.3 An Integrated Fire Protection system is to be located at the centralized control station, see Section 3. The system is to enable efficient control and indication of all essential parameters necessary for the safe and effective operation of the active fire protection and fixed fire-extinguishing systems, including the operational status of running and standby machinery.

### 2.2 Communication

2.2.1 At the centralized fire-control station, fixed means of two-way speech communication is to be provided to all the accommodation and service spaces and other control stations, including the main machinery control station and bridge, if applicable. This means of communication is to be independent of the main source of electrical power.

# Integrated Fire Protection (IFP) Systems

# Part 7, Chapter 12

Sections 2 & 3

2.2.2 In addition to the communication required by 2.2.1, a public address system is to be provided that is clearly audible throughout the accommodation and service spaces and other control stations, including the main machinery control station and navigating bridge, if applicable. The public address system is to be operable from the centralized fire-control station and comply with Pt 6, Ch 2,17.3.

2.2.3 Each required breathing apparatus is to incorporate effective means of communication to enable individual fire fighters to communicate easily with each other and the centralized fire-control station during fire-fighting operations.

## Section 3 Control and monitoring of active fire protection and fixed fire-extinguishing systems

### 3.1 General

3.1.1 The Integrated Fire Protection system is to comply with relevant requirements of the Rules, in particular:

- Pt 6, Ch 1,2 in respect of control, alarm and programmable electronic systems;
- Pt 6, Ch 2, 3 in respect of power supply arrangements;
- Pt 6, Ch 2,16 in respect of fire safety systems;
- Pt 6, Ch 2,17 and 18 in respect of crew, passenger and ship safety systems (where applicable, see Section 4).

3.1.2 The Integrated Fire Protection system is to provide a consistent and common user interface to control and monitoring functions by means of multi-function displays and controls. Functions are to be logically grouped to minimise operator workload with means provided to ensure ease of navigation, e.g. hot-keys to emergency functions, overview pages, etc.

3.1.3 The number of user interfaces is to be sufficient to ensure that the operator can simultaneously display all information necessary to enable safe and effective control and monitoring, with due regard to any functions required to be continuously available.

3.1.4 Means are to be provided to override any safety functions automatically initiated by the Integrated Fire Protection system.

3.1.5 A Failure Mode and Effects Analysis (see Pt 6, Ch 1,2.13.5) is to be carried out, which is to demonstrate that:

- (a) failure of any part of the Integrated Fire Protection system will not result in a loss or degradation of centralized control and monitoring functions for more than one active fire protection or fixed fire-extinguishing system,
- (b) failure of any active fire protection or fixed fire-extinguishing system will not result in the loss or degradation of another system as a result of their interconnection through the Integrated Fire Protection system, and

- (c) any such failures are evident at the centralized fire-control station, by means of audible and visual alarms.

NOTE:

The FMEA is to be carried out to the level of identifiable hardware and software component parts providing defined functions, e.g. display unit, network interface card, etc. and is to consider the effects of:

- (i) random failures of hardware components, and,
- (ii) common mode failures of hardware and software components, unless these components have been certified for use in safety applications, see Pt 6, Ch 1,2.

3.1.6 The Integrated Fire Protection system is to be provided with two independent sources of power, one of which is to be the emergency source, with automatic changeover and audible and visual alarm in the event of any power supply failure.

3.1.7 Where the automatic changeover between supplies may affect operation of the Integrated Fire Protection system, a local transitional source of power of not less than thirty minutes capacity is to be provided. The transitional source is to be arranged such that a fault will not affect the supply of main and emergency power to the system, or the changeover arrangement between them. See also 4.1.3.

3.1.8 Control and monitoring functions for active fire protection and fixed fire-extinguishing systems are to be provided by the Integrated Fire Protection system in accordance with 3.2 to 3.7.

### 3.2 Fixed fire detection and fire-alarm systems

3.2.1 The Integrated Fire Protection system is to provide means to indicate the status of each detector head and manual call point and their location in relation to the spaces and fire zones served.

3.2.2 Audible and visual indication is to be provided automatically and immediately in the event of a detector or manual call point being operated.

3.2.3 Information is to be available detailing the location of each section in relation to the spaces and fire zones served.

3.2.4 System faults resulting in the loss or degradation of fire detection and fire-alarm functions are to be automatically indicated by audible and visual alarms at the centralized fire control station, which are to be clearly distinguishable from those required by 3.2.2.

### 3.3 Fixed water-based fire-extinguishing systems, including local application systems

3.3.1 Alarms and monitoring arrangements are indicated in Table 12.3.1.

## Integrated Fire Protection (IFP) Systems

## Part 7, Chapter 12

Section 3

**Table 12.3.1 Alarms and monitoring arrangements for fixed water based systems**

Item	Alarm	Indication	Note
Fire pumps	—	Running/stopped	—
Fire pumps electric power supply	Failure	—	—
System water pressure	Low	Pressure	—
Sea valves serving fire pumps	—	Open/closed	—
System isolating valves	—	Open/closed	—
Distribution control valves	—	Open/closed	—
Activation of system	Warning	Section activated	Not more than one minute after activation
Lubricating oil inlet temperature for diesel-driven pumps	High	—	—
Pump engine lubricating oil pressure	Low	—	—
Pump engine coolant temperature	High	—	For >220 kW
Pump engine coolant pressure or flow	Low	—	—
Pump engine service oil fuel tank level	Low	—	—
Pump engine overspeed	High	—	See Pt 5, Ch 2,5
Pump engine starting air pressure	Low	Pressure	—
Pump engine electrical starting battery charge level	Low	—	—

3.3.2 Controls are to be provided for the following:

- The starting and stopping of all fire pumps.
- The opening and closing of all sea valves serving the fire pumps.
- The opening and closing of all system(s) isolating valves and distribution control valves for water and foam solution.
- The effective operation of foam monitors. Where a clear view of foam monitor nozzles is not available from the centralized fire-control station, television surveillance or other suitable means for observing the monitors may be accepted.

### 3.4 Fixed gas fire-extinguishing systems

3.4.1 Alarms and monitoring arrangements are indicated in Table 12.3.2.

3.4.2 Controls are to be provided for the release of the extinguishing media and the opening and closing of the distribution control valves for conveying the media into selected protected spaces. These controls are to be protected against misuse.

**Table 12.3.2 Alarms and monitoring arrangements for fixed gas fire-extinguishing systems**

Item	Alarm	Indication	Note
Operation of medium release	Warning	Instructions relating to the operation of the system having regard to the safety of personnel	An audible warning is to be given automatically of the release of the medium into any space in which personnel normally work or have access and is to operate for a suitable period before the medium is released
Distribution control valves	—	Open/closed	—
Electric power for medium release	Failure	—	—
Hydraulic or pneumatic pressure for medium release	Low	—	—
Discharge manifold pressure	High	Pressure	—

3.4.3 Means are to be provided to stop all ventilation fans serving the selected protected space before the extinguishing medium is released, see also 3.6.

3.4.4 The requirements of 3.4.2 and 3.4.3 need not be applied to systems protecting cargo spaces except where a limit is placed on the duration of the discharge.

### 3.5 Dry extinguishing powder fire-extinguishing systems

3.5.1 Alarms and monitoring arrangements are indicated in Table 12.3.3.

**Table 12.3.3 Alarms and monitoring arrangements for dry extinguishing powder fire-extinguishing systems**

Item	Alarm	Indication	Note
Dry extinguishing powder container pressure	—	System energised	—
Monitor flow control valve(s)	—	Open/closed	—

# Integrated Fire Protection (IFP) Systems

## Part 7, Chapter 12

Sections 3, 4 &amp; 5

3.5.2 Controls are to be provided for the following:

- Energising the system in readiness for discharge.
- The opening and closing of monitor flow control valve(s).
- The effective operation of the monitor nozzle(s), where applicable. Where the monitor nozzle(s) is required to be aimed remotely, and a clear view of the monitor(s) is not available from the centralized fire-control station, television surveillance or other suitable means for observing the monitor nozzle(s) may be accepted.

### 3.6 Protected space openings and ventilation systems

3.6.1 Alarms and monitoring arrangements are indicated in Table 12.3.4.

**Table 12.3.4 Alarms and monitoring arrangements for protected space openings and ventilation systems**

Item	Alarm	Indication	Note
Ventilation fans	—	Running/stopped	—
Forced and included draught fans	—	Running/stopped	—
Inlets and outlets in ventilation systems	—	Open/closed	—
Miscellaneous openings	—	Open/closed	See 3.6.2(c), (e) and (f)
Loss of ventilating capacity in Ro-Ro cargo spaces	Warning	—	—
Operation of remote release devices for self-closing doors	—	Hold-back arrangements released	—

3.6.2 Controls are to be provided for the following:

- The start and stop of all ventilation fans.
- The start and stop of all forced and induced draught fans.
- The opening and closing of openings into spaces protected by fixed gas fire-extinguishing systems.
- The opening and closing of all main inlets and outlets of ventilation systems, including fire dampers.
- The opening and closing of machinery space skylights and openings in funnels.
- Remote release devices for self-closing doors provided with hold-back arrangements.
- Manual operation of escape route or low location lighting, see Pt 6, Ch 2, 17.4.

### 3.7 Oil storage, transfer and pumping arrangements in machinery spaces

3.7.1 Alarms and monitoring arrangements are indicated in Table 12.3.5.

**Table 12.3.5 Alarms and monitoring arrangements for oil storage, transfer and pumping systems**

Item	Alarm	Indication	Note
Deep tank valves	—	Open/closed	—
Oil pumps	—	Running/stopped	See 3.7.2(b)
High pressure fuel delivery lines	Failure	—	See Pt 6, Ch 1, 3.1.5

3.7.2 Controls are to be provided for the following:

- The closure of valves on all pipes that, if damaged, could allow oil to escape from storage, settling or daily service tanks situated above the double bottom.
- The stopping of oil fuel transfer pumps, oil fuel unit pumps lubricating oil pumps, piston cooling pumps, hydraulic oil pumps and other similar types of pumps.

## Section 4 Integration of other systems

### 4.1 General

4.1.1 The Integrated Fire Protection system is to provide functions required for fire protection purposes only, excepting where permitted below.

4.1.2 Other ship, passenger or crew safety systems, see Pt 6, Ch 2, 17 and 18, may be integrated such that control and monitoring functions are accessed via the common user interface, subject to 1.1.4. Any such arrangements are to be in accordance with the general requirements of 3.1, and comply with any Rules applicable to these systems.

4.1.3 Where watertight door control and indication functions are included, the power supply arrangements are to be in accordance with Pt 6, Ch 2, 3.2.7 or 3.3.7 as applicable. In this case, the requirement of 3.1.7 will be waived.

4.1.4 The **IP** (Integrated Propulsion, see Pt 5, Ch 18), **ICC** (Integrated Computer Control, see Pt 6, Ch 1, 6) or **IBS** (Integrated Bridge Navigational System, see Pt 7, Ch 9, 5) class notations may be applicable to ships where other control and monitoring functions are implemented by an integrated system.

## Section 5 Testing, trials and maintenance

### 5.1 General

5.1.1 The Integrated Fire Protection system is to be examined and tested at the manufacturer's works in accordance with the approved test schedule, see 1.2.1.

5.1.2 The factory acceptance test is to demonstrate that:

- (a) the system is correct with regard to its specification (i.e. verification tests);
- (b) as far as applicable, the system fulfils the requirements of these Rules (i.e. validation tests).

Where sample testing of hardware or software modules is proposed, records of prior verification testing are to be made available to the attending Surveyor.

5.1.3 The arrangements are to be subject to examination and functional testing on completion of the installation. These validation tests are to be based on the approved test schedule and are to demonstrate that the requirements of these Rules have been satisfied. In addition, details of commissioning tests for verification purposes are to be made available to the attending Surveyor.

5.1.4 The arrangements are to be examined and a sample of functions tested at Annual and Special Surveys.

## **5.2 Modifications**

5.2.1 Where any modification of the Integrated Fire Protection system is to be carried out, details are to be submitted to Lloyd's Register for consideration. A suitable testing program is to be submitted for consideration, demonstrating that the system will continue to provide required functions.

5.2.2 All modifications are to be carried out in accordance with a traceable change control procedure. Software versions and relevant documentation are to be updated.

---



# Arrangements and Equipment for Bulk Carrier Safety

## Part 7, Chapter 13

Sections 1 &amp; 2

### Section

- 1 **Water ingress detection arrangements**
- 2 **Drainage and pumping arrangements**

### ■ Section 1 Water ingress detection arrangements

#### 1.1 General requirements

1.1.1 Equipment for detecting the ingress of water is to be fitted in accordance with the requirements of SOLAS 1974 as amended, Chapter XII, Regulation 12.

1.1.2 Bulk carriers are to be fitted with water level detectors:

- (a) In each cargo hold, giving audible and visual alarms, one when the water level above the inner bottom in any hold reaches a height of 0,5 m and another at a height not less than 15 per cent of the depth of the cargo hold but not more than 2 m. The water level detectors are to be fitted in the aft end of the cargo holds. For cargo holds which are used for water ballast, an alarm overriding device may be installed. The visual alarms are to clearly discriminate between the two different water levels detected in each hold;
- (b) in any ballast tank forward of the collision bulkhead required by Pt 3, Ch 3,4, giving an audible and visual alarm when the liquid in the tank reaches a level not exceeding 10 per cent of the tank capacity. An alarm overriding device may be installed to be activated when the tank is in use; and
- (c) in any dry or void space other than a chain cable locker, any part of which extends forward of the foremost cargo hold, giving an audible and visual alarm at a water level of 0,1 m above the deck. Such alarms need not be provided in enclosed spaces the volume of which does not exceed 0,1 per cent of the ship's maximum displacement volume.

1.1.3 The audible and visual alarms specified in 1.1.2 are to be located on the navigation bridge.

### ■ Section 2 Drainage and pumping arrangements

#### 2.1 General requirements

2.1.1 Arrangements for drainage and pumping are to be in accordance with the requirements of SOLAS 1974 as amended, Chapter XII, Regulation 13.

2.1.2 On bulk carriers, the means for draining and pumping ballast tanks forward of the collision bulkhead and bilges of dry spaces any part of which extends forward of the foremost cargo hold are to be capable of being brought into operation from a readily accessible enclosed space, the location of which is accessible from the navigation bridge or propulsion machinery control position without traversing exposed freeboard or superstructure decks. Where pipes serving such tanks or bilges pierce the collision bulkhead, valve operation by means of remotely operated actuators may be accepted, as an alternative to the valve control specified in Pt 5, Ch 13,3.5.6, provided that the location of such valve controls complies with this requirement.

#### 2.2 Dewatering capability

2.2.1 The dewatering system for ballast tanks located forward of the collision bulkhead, and for bilges of dry spaces any part of which extends forward of the foremost cargo hold, is to be designed to remove water from the forward spaces at a rate of not less than  $320A \text{ m}^3/\text{h}$ , where  $A$  is the cross-sectional area in  $\text{m}^2$  of the largest air pipe or ventilator pipe connected from the exposed deck to a closed forward space that is required to be dewatered by these arrangements.





## Section

- 1 **General requirements**
- 2 **Noise**
- 3 **Vibration**
- 4 **Testing**
- 5 **Noise and vibration survey reporting**
- 6 **Non periodical survey requirements**
- 7 **Referenced standards**

## ■ Section 1 General requirements

### 1.1 Scope

1.1.1 These Rules set down the criteria for the assessment of the noise and vibration on ships and are applied in addition to the other relevant requirements of the *Rules and Regulations for the Classification of Ships* (hereinafter referred to as the Rules for Ships).

1.1.2 Compliance with these Rules is optional.

1.1.3 These Rules provide for two alternatives:

- (a) **Class Notations** which indicate that the ship has been assessed and complies with noise and vibration criteria in these Rules and that a periodic survey regime has been established for the lifetime of the ship.
- (b) **Certificate of Compliance** which provides evidence that the ship has been assessed and found to comply with the noise and vibration criteria in these Rules.

1.1.4 These Rules recognize existing National and International Standards and specify levels of noise and vibration currently achievable using good engineering practice. Compliance with these requirements will be assessed by review of procedures, inspection and measurement of the relevant parameters and pre-survey reviews. Inspections and measurements are to be conducted, witnessed or assessed by LR's Surveyors unless otherwise agreed by Lloyd's Register (hereinafter referred to as LR).

1.1.5 Accommodation comfort is a function of ship type and layout. These Rules address two types of ship:

- (a) Passenger (e.g. cruise ships, ro-ro ferries).
- (b) Cargo (e.g. container ships, tankers).

1.1.6 These Rules include levels of noise and vibration which should be verified by measurements following completion of the ship. It is recommended that the Builders undertake calculations of noise and vibration characteristics so that any potential problem areas can be identified and control measures implemented.

1.1.7 The sound pressure levels for audible alarms and public address systems fitted in accordance with other sections of the Rules are to satisfy IMO Resolution A.830(19) Code on Alarms and Indicators.

### 1.2 Definitions

1.2.1 **Passenger spaces** are defined as all areas intended for passenger use, and include the following:

- (a) Passenger cabins.
- (b) Public spaces (e.g. restaurants, hospital, lounges, reading and games rooms, gymnasiums, corridors, shops).
- (c) Open deck recreation areas.

1.2.2 **Crew spaces** are defined as all areas intended for crew use only, and include the following:

- (a) Accommodation spaces (e.g. cabins, offices, mess rooms, recreation rooms).
- (b) Work spaces.
- (c) Navigation spaces.

1.2.3 **Noise level** is defined as the A-weighted sound pressure level measured in accordance with ISO 2923.

1.2.4 **Vibration level** is defined by the application of either of the two versions of the ISO 6954 standard:

- (a) Where ISO 6954:1984 is applied, the vibration level is defined as the single amplitude peak value of deck structure vibration during a period of steady state vibration, representative of maximum repetitive behaviour, in mm/s, over the frequency range 5 to 100 Hz. For frequencies below 5 Hz, the requirements for vibration levels follow constant acceleration curves corresponding to the acceleration at 5 Hz.
- (b) Where ISO 6954:2000 is applied, the vibration level is defined as the overall frequency weighted r.m.s. value of vibration during a period of steady-state operation over the frequency range 1 to 80 Hz.

In general, ISO 6954-2000 is the preferred standard to be applied, however ISO 6954-1984 may be applied where there are practical difficulties in application of ISO 6954-2000 and this has been agreed between the Owner and Builder.

### 1.3 Class notations

1.3.1 The class notations described in 1.3.2 to 1.3.6 provide standards for noise and vibration levels in different spaces at the time of delivery and during the ships life if substantial changes to the machinery installation or interior arrangements are made.

1.3.2 The **PAC** (Passenger Accommodation Comfort), **CAC** (Crew Accommodation Comfort) and **PCAC** (Passenger and Crew Accommodation Comfort) notations are optional and are primarily intended to apply to passenger ships. If requested, however, any ship can be assessed for compliance, using these requirements as the basis for the assessment and a LR Certificate of Compliance issued (see 1.1.3(b) and 1.4).

# Passenger and Crew Accommodation Comfort

## Part 7, Chapter 14

Sections 1 &amp; 2

1.3.3 The **PAC** notation indicates that the passenger accommodation meets the acceptance criteria whilst the **CAC** notation indicates that the crew accommodation and work areas meet the acceptance criteria. The **PCAC** notation indicates that the passenger and crew spaces both meet the acceptance criteria.

1.3.4 For ships which achieve the noise and vibration comfort standards specified in these Rules, the notation **PAC**, **CAC** or **PCAC** will be assigned.

1.3.5 Following the **PAC** or **CAC** notation, numerals **1**, **2** or **3** will indicate the acceptance criteria to which the noise and vibration levels have been assessed. In the case of the **PCAC** notation, two numerals will be assigned. The first will indicate the acceptance criteria for passenger accommodation, whilst the second will indicate the crew comfort criteria.

1.3.6 For particular vessels, impact insulation and transient noise in accordance with 2.5 and 2.6 together with any additional or more stringent noise and vibration criteria may be assessed within the scope of the notations where agreed between the Owner, Builder and LR.

### 1.4 Certificate of Compliance

1.4.1 A Certificate of Compliance records that a ship has been designed and constructed to satisfy the noise and vibration criteria contained in these Rules. This is to be confirmed by measurements and reporting in accordance with Sections 4 and 5.

1.4.2 A Certificate of Compliance is optional and if requested, any ship can be assessed for compliance using the Rule requirements as basis for assessment.

1.4.3 Where noise and vibration levels are at variance with those prescribed by these Rules, these will be added to the certificate for information purposes.

1.4.4 A Certificate of Compliance will be issued after the initial survey required by Section 6.

## Section 2 Noise

### 2.1 Assessment criteria

2.1.1 Where a space is occupied by both passengers and crew, the more stringent of the relevant requirements apply unless agreed between the Builder and Owner and advised to LR.

### 2.2 Passenger accommodation and public spaces

2.2.1 Under test conditions specified in 4.2, the applicable noise levels specified in Table 14.2.1 should not generally be exceeded. See 2.2.3.

**Table 14.2.1 Passenger ships – Maximum noise levels in dB(A)**

Location		Acceptance Numeral		
		1	2	3
Passenger cabins:	Standard	49	52	55
	Superior	45	47	50
Public spaces:	Excluding shops	55	58	62
	Shops	60	62	65
Medical centre:		50	55	60
Theatre/auditorium		50	55	60
Open deck recreation areas (excluding swimming pools and similar)		67	72	72
Swimming pools and similar		70	75	75

#### NOTES

1. The levels may be exceeded by 5dB(A) within 3 m of a ventilation inlet/outlet or machinery intake/uptake on open decks.
2. The levels may be exceeded by 3dB(A) in accommodation above the propellers for three decks above the mooring deck.
3. The levels for open deck recreation areas refer to ship generated noise only. On open deck spaces the noise generated from the effects of wind and waves can be considered separately to limits agreed between the Builder and Owner and advised to LR for the trial conditions.

2.2.2 For cabins bordering discotheques and similar entertainment areas, the deck and bulkhead sound insulation is to be sufficient to ensure that the maximum cabin noise levels are not exceeded even when high external noise levels prevail.

2.2.3 Acceptance of noise levels greater than those specified in Table 14.2.1 may be considered where agreed between the Owner and Builder. Not more than 20 per cent of the passenger cabins, 30 per cent of the public spaces and 20 per cent of the crew cabins should exceed the relevant noise criteria by more than 3 dB(A).

2.2.4 Acoustic insulation of bulkheads and decks between passenger spaces is to be generally in accordance with the values of the weighted apparent sound reduction index  $R_w$  as given in Table 14.2.2, calculated using ISO 717/1. See also 2.2.6.

# Passenger and Crew Accommodation Comfort

# Part 7, Chapter 14

Section 2

2.2.5 For the purpose of selecting acoustic sound insulation, the following sound noise levels may be used with the agreement of the Owner and Builder:

- (a) Cabins – 80 dB(A).
- (b) Dining Rooms – 85 dB(A).
- (c) Corridors – 90 dB(A).
- (d) Discotheques, Theatres, Entertainment Areas – 105 dB(A).

2.2.6 Acceptance of bulkhead and deck acoustic insulation values less than those specified in Table 14.2.2 may be considered where agreed between the Owner and Builder. Not more than 20 per cent of the interfaces tested should have airborne sound insulation indices,  $R_w$ , more than 3 dB(A) lower than the minimum specified values.

**Table 14.2.2 Minimum air-borne sound insulation indices,  $R_w$**

Location		Acceptance Numeral		
		1	2	3
Passenger cabins:	Standard	40	38	37
	Superior	45	42	40
Cabin to corridor:	Standard	38	36	34
	Superior	42	40	37
Cabin to stairway:	Standard	47	45	43
	Superior	50	47	45
Cabin to public space (excluding corridors/stairwells and discotheques):	Standard	52	48	48
	Superior	55	50	50
Discotheques to cabins		60	60	60
Discotheques to stairwells and public spaces		52	52	52
Cabin to machinery rooms and engine casing		55	53	50

## 2.3 Crew accommodation and work areas

2.3.1 Under the applicable test conditions specified in 4.2, the noise levels specified in Tables 14.2.3 and 14.2.4 are not to be exceeded.

2.3.2 Crew space insulation is to comply with the requirements of IMO Resolution A.468(XII).

**Table 14.2.3 Crew accommodation – Maximum noise levels in dB(A)**

Location	Acceptance Numeral		
	1	2	3
Sleeping cabins, hospitals	52	55	60
Day cabins	55	60	60
Office conference rooms	55	60	65
Mess rooms, lounges, reception areas:			
	Within accommodation	57	60
	On open decks	67	72
Alleyways, changing rooms, bathrooms, lockers	70	75	75
NOTE The levels may be exceeded by 5 dB(A) within 3 m of a ventilation inlet/outlet or machinery intake/uptake on open decks.			

**Table 14.2.4 Crew work areas – maximum noise levels in dB(A)**

Location	dB(A) level
Machinery space (continuously manned) e.g. stores	90
Machinery space (not continuously manned) e.g. pump, refrigeration, thrusters or fan rooms	110
Workshops	85
Machinery control rooms	75
Wheelhouse	65
Bridge wing, additional limits:	
• 250 Hz band	68
• 500 Hz band	63
Radio room	60
Galley and pantries:	
• Equipment not working	75
• Individual items at 1 metre	85
Normally unoccupied spaces (e.g. holds, decks)	90
Ship's whistle, on bridge or forecastle	110

## 2.4 Maximum noise levels

2.4.1 Where the measured noise level exceeds the specified criterion by 3 dB(A), or contains subjectively annoying low frequency or tonal components, the noise rating (NR) number is to be established in accordance with the graph shown in Fig. 14.2.1. This is achieved by plotting the linear octave band levels on the graph; the NR number is that NR curve to which the highest plotted octave band level is anywhere tangent. The specified criterion may be considered satisfied if the NR number does not exceed the specified A-weighted value minus 5 dB(A).

2.4.2 Guidance on maximum acceptable sound pressure levels and noise exposure limits for crew spaces is given in IMO Resolution A.468(XII).

## 2.5 Impact insulation

2.5.1 Where agreed between the Owner, Builder and LR, enhanced criteria for noise levels recognising the effects of impact sound pressures may be applied in accordance with 2.5.2 to 2.5.5.

2.5.2 For passenger and crew cabins located below or adjacent to dance floors, stages, aerobics and gymnasium areas, jogging tracks or other areas where impact noise is generated, the normalised impact sound pressure level measured within the cabins is not to exceed 45 dB.

2.5.3 For public rooms under dance floors, stages, aerobics and gymnasium areas, jogging tracks or other areas where impact noise is generated, the normalised impact sound pressure level within the space is not to exceed 55 dB.

2.5.4 For passenger cabins, the normalised impact sound pressure level,  $L_{n,w}$ , calculated using ISO 717/2, is to be generally in accordance with the values stated in Table 14.2.5. See also 2.5.5.

**Table 14.2.5 Passenger cabins normalized impact maximum sound pressure level  $L_{n,w}$**

Location	dB
Below decks covered with carpet and soft materials	50
Below decks covered in hard materials (such as wood, marble or similar)	60
Below dance floors, theatre or sports rooms	47

2.5.5 Acceptance of normalised impact sound pressure levels greater than those specified in Table 14.2.5 may be considered for assignment of the applicable class notation where agreed between the Owner, Builder and LR. No more than 20 per cent of the passenger cabins tested should exceed the levels specified by more than 3 dB.

## 2.6 Transient noise

2.6.1 Where agreed between the Owner, Builder and LR, enhanced criteria for transient noise levels may be applied in accordance with 2.6.2.

2.6.2 The maximum sound pressure level ( $L_{max}$ ) emanating from any machinery or system caused by a single event that produces a noise 'spike' compared to the reference condition sound level (such as vacuum systems or valve operations) is not to cause an increase in noise in comparison with the reference condition as below:

- (a) Passenger cabins and public areas: +2 dB(A)
- (b) Officer cabins: +2 dB(A)
- (c) Crew cabins and public areas: +3 dB(A)

A tolerance of +1 dB(A) may be applied to 5 per cent of cabins and public areas in each fire zone on each deck. This criterion is generally applicable to the specified maximum noise levels for the space concerned.




Fig. 14.2.1 Noise rating curves

■

Section 3

Vibration

3.1

Assessment criteria

- 3.1.1
- Where a space is occupied by both passengers and crew, the more stringent of the relevant requirements apply unless agreed between the Builder and Owner and this agreement advised to LR.
- 3.1.2
- The limits apply to vertical, fore and aft and athwartship vibrations which are to be assessed separately.
- 3.1.3
- Under test conditions specified in 4.2, the applicable vibration levels specified in Tables 14.3.1 and 14.3.2 should not be exceeded.

Table 14.3.1

Passenger ship – Maximum vibration levels

Standard	ISO 6954:1984			ISO 6954:2000		
Units:	Peak velocity (5–100 Hz)			Peak velocity (5–80 Hz) velocity mm/s rms		
	Acceptance Numeral					
Location	1	2	3	1	2	3
Passenger cabin Luxury	1,5	2,0	2,5	1,5	1,8	2,1
Passenger cabin Standard	1,5	2,5	4,0	1,8	2,1	2,4
Public spaces	1,5	2,5	4,0	2,0	2,5	3,0
Open recreation decks	2,5	3,5	5,0	2,5	3,0	3,5
NOTE The vibration level may be exceeded by 0,3 mm/s in the ship's aft body directly above the propellers.						

Table 14.3.2

Crew spaces – Maximum vibration levels

Standard:	ISO 6954:1984	ISO 6954:2000
Units:	Peak velocity (5–100 Hz)	Frequency weighted (1–80 Hz) velocity mm/s rms
Location		
Accommodation and navigation spaces	5,0	3,5
Work spaces	6,0	5,0

- 3.1.4
- Acceptance of vibration levels greater than those specified in Tables 14.3.1 and 14.3.2 may be considered for assignment of the applicable class notation where agreed between the Owner, Builder and LR.
- 3.1.5
- The vibration levels for ISO 6954:1984 are stated as peak vibration velocity amplitude. If root mean square levels are measured, each frequency component may be converted to peak vibration velocity amplitude by application of a 1.41 multiplication factor where the ISO 6954:1984 is used for assessment against Tables 14.3.1 and 14.3.2. An approximation of maximum repetitive values may be obtained for direct comparison with the graph in ISO 6954-1984 by further application of the 1,8 conversion factor as stated in the 'Interim guidelines' note of the standard.

3.2

Passenger accommodation and public spaces

- 3.2.1
- Passenger spaces are to comply with the overall vibration levels specified in Tables 14.3.1 and 14.3.2.
- 3.2.2
- No more than 20 per cent of all passenger spaces/areas and public spaces should exceed the relevant vibration criteria specified in Tables 14.3.1 and 14.3.2 by more than 0,3 mm/s whether using ISO 6954:2000 or ISO 6954:1984.

3.3

Crew accommodation and work spaces

- 3.3.1
- Crew spaces are to comply with the overall vibration levels specified in Table 14.3.2.

■

Section 4

Testing

4.1

Measurement procedures

- 4.1.1
- These requirements take precedence where quoted standards may differ.
- 4.1.2
- The trial measurements may be undertaken by an approved technical organisation as defined in 4.7 or by LR. In the former case, the measurements are to be witnessed by a LR Surveyor.
- 4.1.3
- Subject to agreement by LR and the Owner/Operator, the measurements may be undertaken by the Builder. In this case, the measurements are to be witnessed by a LR Surveyor.

4.2

Test conditions

- 4.2.1
- Test conditions for the surveys are to be in accordance with those detailed in ISO 2923 and ISO 6954:1984 or ISO 6954:2000 as applicable.

4.2.2 The intended operating and loading conditions of the ship during assessment surveys are to be submitted to LR for agreement, prior to commencement of surveys.

4.2.3 Surveys are to be conducted when the ship is fully outfitted and all systems contributing to noise and vibration levels are operational.

**NOTE**

All systems operational are to include those systems that may operate simultaneously with others during normal ship operation.

4.2.4 The test conditions required for the vibration and noise measurements are to be in accordance with the following conditions:

- (a) For passenger ships, prior to measurement surveys being carried out, the ship operating condition where the worst conditions are experienced between 0 and 85 per cent maximum continuous rating of the propulsion machinery is to be determined. To establish this condition, four measurement positions are to be defined with the agreement of LR and measurements taken of the parameters of interest at ship speeds corresponding to percentages of the maximum continuous rating of the propulsion machinery increasing up to 40 per cent MCR in 10 per cent intervals and from 40 per cent in 5 per cent intervals up to the 85 per cent maximum continuous rating of the propulsion machinery. If the 85 per cent maximum continuous rating condition is found to be the worst condition, then this will form the trial operating conditions. However, if a lower speed condition is found to be worse than the 85 per cent maximum continuous rating condition then both that condition and the 85 per cent maximum continuous rating condition will form the trial operating conditions. Where unavoidable any barred range within the values required for the trial operating condition may be excluded on agreement between Owner and Builder subject to approval by LR.
- (b) The power absorbed by the propeller(s) is to be that defined in 4.2.4(a). Alternatively, by special agreement, some lesser power could be accepted if it can be demonstrated by the Owner that this would correspond to a more representative normal service condition.
- (c) Auxiliary machinery essential for the ship's operating conditions together with HVAC systems are to be running at their normal rated capacity during the noise and vibration trials. Combinations of auxiliary machinery operation may be necessary. In addition, the following equipment is to be running if appropriate: stabilizers, waste treatment equipment, swimming pool and jacuzzi equipment.
- (d) For sea-going ships, measurements are to be taken with the ship proceeding ahead, at a constant speed and course, in a depth of water not less than five times the draught of the ship. For other ships, an appropriate water depth is to be agreed with LR prior to the trials.
- (e) Trials are to be conducted in sea conditions not greater than sea state 3 on the WMO sea state code. In addition, noise measurements should not be taken when the wind force exceeds 4 on the Beaufort scale.
- (f) The ship is to be at a displacement and trim representative of an operating condition.

- (g) Rudder angle variations are to be limited to  $\pm 2^\circ$  of the midship position and rudder movements are to be kept to a minimum throughout the measurement periods.
- (h) In addition, for ships which are designed to spend a considerable period of time in harbour, the noise and vibration, are to be measured for this condition, with the auxiliary machinery and HVAC systems running at their normal rated capacity.
- (j) For passenger ships, intermittently run equipment such as transverse propulsion units are to be operated at 60 per cent of their rated power for additional measurements in surrounding ship areas.

4.2.5 Prior to survey, a test programme is to be submitted for approval by LR. This programme is to contain details of the following:

- (a) Measurement locations indicated on a general arrangement of the ship.
- (b) The ship's loading condition during survey.
- (c) The machinery operating condition, including HVAC system, during survey.
- (d) Noise and vibration measuring equipment.

## 4.3 Noise measurements

4.3.1 Noise measurements are to be conducted in accordance with ISO 2923 and IMO Resolution A.468(XII). Measurements of noise levels are to be carried out using precision grade sound level meters conforming to IEC 60651, Type 1 or 2. Subject to demonstration, equivalent standards are acceptable.

4.3.2 Where the measured noise level exceeds the relevant criterion by 3 dB(A), or contains subjectively annoying low frequency noise or obvious tonal components, octave band readings are to be taken, with centre frequencies from 31,5 Hz to 8 kHz.

4.3.3 When outfitting is complete, and all soft furnishings are in place, sound insulation indices for passenger spaces are to be determined in accordance with ISO 140. Cabin to cabin indices are to be determined from a minimum of three locations within the passenger accommodation, the number of test locations being agreed with LR.

4.3.4 If required, impact sound measurements are to be carried out in accordance with ISO 140/7 and presented in accordance with ISO 717/2. See 4.4.4.

## 4.4 Noise measurement locations

4.4.1 Measurement locations are to be chosen so that the assessment represents the overall noise environment on board the ship. In addition to the requirements of IMO Resolution A.468(XII) for crew spaces, all public spaces and at least 50 per cent of passenger cabins in the after third of the ship, and 25 per cent elsewhere, are to be surveyed. Distribution of the measurement locations is to be agreed by LR.

4.4.2 During measurement trials, recognized noise sources are to be operated at their normal level of noise output (e.g. machinery at design rating).

4.4.3 In larger sized spaces, where noise levels may vary considerably, such as restaurants, lounges, atria and open deck recreation areas, measurements are to be taken at locations not greater than 7 m apart.

4.4.4 The number of and locations for impact noise measurements are to be agreed between the Builder, Owner and LR. The measurements are to be carried out when the ship is in harbour. The number and location of measurements are to take account of all different combinations of construction, areas of application, types of cabin and spaces below.

## 4.5 Vibration measurements

4.5.1 Vibration measurements are to be conducted in accordance with ISO 6954:1984 or ISO 6954:2000.

4.5.2 Measurements are to be made with instrumentation meeting the requirements of ISO 8041.

4.5.3 Vibration levels are to be given in terms of the velocity measurement appropriate to the version of the standard being used and should be measured over a period of not less than one minute.

## 4.6 Vibration measurement locations

4.6.1 Measurement locations are to be chosen so that the assessment represents the overall vibration environment onboard the ship. To minimize survey times, readings may be taken at the locations previously defined for the noise assessment part of the survey.

4.6.2 In cabins, vibration readings are to be taken in the centre of the floor area. The measurements are to indicate the vibration of the deck structure. In large spaces, such as restaurants, sufficient measurements are required to define the vibration profile.

4.6.3 Where deck coverings make transducer attachment impracticable, use of a small steel plate having a mass of at least 1 kg, with spikes as appropriate, is permissible.

4.6.4 At all locations, vibrations in the vertical direction are to be assessed. Sufficient measurements in the athwartships and fore and aft directions are to be taken to define global deck vibrations.

## 4.7 Approved technical organisation

4.7.1 An approved technical organisation for the purposes of these Rules is one that is acceptable to the Owner and LR with proven capability in noise and vibration measurement and satisfies all the criteria set out below:

- (a) Have instrumentation whose calibration, both before and after the measurements, can be traced back to National Standards and, hence, back to International Standards.
- (b) Have analysis procedures capable of data reduction to the requirements and standards set out in these Rules.
- (c) Be able to provide a written report in English with contents as defined by Section 5.

## Section 5 Noise and vibration survey reporting

### 5.1 General

5.1.1 Prior to survey, a noise and vibration measurement plan is to be agreed by the Owner, Builder and LR.

5.1.2 The survey report is to comprise the data and analysis for both noise and vibration and is to be submitted to LR for consideration.

5.1.3 The survey report is to be prepared by the organisation undertaking the trial measurements, which may be an approved technical organisation or LR.

5.1.4 The survey report is to be submitted to LR's London Office (MCS/TID) for evaluation and confirmation that the results are in accordance with the noise and vibration levels specified in these Rules and/or agreed between the Owner and Builder. The assignment of a Class Notation or the issue of a Statement of Compliance will be subject to confirmation by LR MCS/TID.

### 5.2 Noise

5.2.1 The reporting of results is to comply with ISO 2923, and is to include:

- (a) Measurement locations indicated on a general arrangement plan including, where possible, the measured dB(A) level.
- (b) Tabulated dB(A) noise levels, together with octave band analysis for positions where the level exceeds the specified criterion by 3 dB(A), or where subjectively annoying low frequency or tonal components were present. The Noise Rating number is also to be given where octave band analyses have been conducted.
- (c) Ship and machinery details.



- (d) Trial details:
- Loading condition.
  - Machinery operating condition.
  - Speed.
  - Average water depth under keel.
  - Weather conditions.
  - Sea state.
- (e) Details of measuring and analysis equipment (e.g. manufacturer, type and serial numbers), including frequency analysis parameters (e.g. resolution, averaging time, window function).
- (f) Copies of the relevant instrument calibration certificates, together with the results of field calibration checks

## 5.3 Vibration

5.3.1 The report is to contain the following information:

- (a) Measurement positions indicated on a general arrangement plan.
- (b) Where ISO 6964:2000 is used, the frequency-weighted overall r.m.s. vibration levels tabulated for all measurement locations calculated using the weighting functions and methodology stated in the standard.
- (c) Where ISO 6954:1984 is used, the maximum peak vibration levels and their corresponding frequencies taken from the frequency spectra, tabulated for all measurement locations.
- (d) Ship and machinery details.
- (e) Trial details:
- Loading condition.
  - Machinery operating condition.
  - Speed.
  - Average water depth under keel.
  - Weather conditions.
  - Sea state.
- (f) Frequency analysis parameters (e.g. resolution, averaging time and window function), if the analysis is done in the frequency domain.
- (g) Copies of the relevant instrument calibration certificates, together with the results of field calibration.

## ■ Section 6 Non-periodical survey requirements

### 6.1 Class notation assignment

6.1.1 Where the assignment of a Class Notation or a Statement of Compliance is requested, an Initial Survey is to comprise sea trial or initial in-service testing, reporting and assessment against the criteria set out in these Rules.

6.1.2 The sea trial or initial in-service testing requirements are set out in Section 4, and are to be reported in accordance with Section 5 and evaluated against the requirements of Sections 2 and 3.

### 6.2 Maintenance of class notation through-life and following modifications

6.2.1 Where an Owner has requested assignment of a Class Notation, arrangements are to be agreed between LR and the Owner to record observations/complaints of excessive noise and vibration that have been such as to disturb the comfort of passengers and crew. The records of the observations are to be made available to the attending LR Surveyor at each Annual Survey.

6.2.2 Where the observations indicate that the noise and/or vibration levels may exceed the criteria relating to the Class Notation requirements and those measured at the Initial Survey, a measurement programme is to be agreed between the Owner and LR and measurements taken in accordance with these Rules.

6.2.3 A Renewal Survey may be required following modifications, alterations or repairs including replacement of major machinery items. It is the responsibility of the Owner to advise LR of such modifications.

## ■ Section 7 Referenced standards

### 7.1 Noise

7.1.1 The following National and International Standards for noise are referred to in these Rules:

- ISO 2923, *Acoustics – Measurement of noise on board vessels*.
- ISO 717/1, *Acoustics – Rating of sound insulation in buildings and of building elements; Part 1: Airborne sound insulation*.
- ISO 717/2, *Acoustics – Rating of sound insulation in buildings and of building elements; Part 2: Impact sound insulation*.
- IMO Resolution A.468(XII), *Code on noise levels on board ships*.
- IEC Publication 651, *Sound level meters*.
- ISO 140/4, *Acoustics – Measurement of sound insulation in buildings and of building elements; Part 4: Field measurements of airborne sound insulation between rooms*.
- ISO 140/7, *Acoustics – Measurement of sound insulation in buildings and of building elements; Part 7: Field measurements of impact sound insulation of floors*.

## 7.2 Vibration

7.2.1 The following National and International Standards for vibration are referred to in these Rules:

- ISO 6954:1984, *Mechanical vibration and shock – Guidelines for the overall evaluation of vibration in merchant ships.*
- ISO 6954:2000, *Mechanical vibration and shock – Guidelines for the measurement, reporting and evaluation of vibration with regard to habitability on passenger and merchant ships.*
- ISO 8041, *Human response to vibration. Measuring instrumentation.*



© Lloyd's Register, 2007  
Published by Lloyd's Register  
*Registered office*  
71 Fenchurch Street, London, EC3M 4BS  
United Kingdom

Printed by Butler and Tanner,  
Frome, Somerset